

LINUX COMPLETE

Command Reference

Compiled by J. Purcell

Red Hat Software, Inc.



201 West 103rd Street
Indianapolis, Indiana 46290

For more information on the Linux operating system and
Red Hat Software, Inc., check <http://www.redhat.com>.

COPYRIGHT © 1997 BY RED HAT SOFTWARE, INC.

FIRST EDITION

All rights reserved. No part of this book shall be reproduced, stored in a retrieval system, or transmitted by any means, electronic, mechanical, photocopying, recording, or otherwise, without written permission from the publisher. No patent liability is assumed with respect to the use of the information contained herein. Although every precaution has been taken in the preparation of this book, the publisher and author assume no responsibility for errors or omissions. Neither is any liability assumed for damages resulting from the use of the information contained herein. For information, address Sams Publishing, 201 W. 103rd St., Indianapolis, IN 46290.

International Standard Book Number: 0-672-31104-6

Library of Congress Catalog Card Number: 97-66202

2000 99 98 97 4 3 2 1

Interpretation of the printing code: the rightmost double-digit number is the year of the book's printing; the rightmost single-digit, the number of the book's printing. For example, a printing code of 97-1 shows that the first printing of the book occurred in 1997.

Composed in AGaramond and MCPdigital by Macmillan Computer Publishing

Printed in the United States of America

TRADEMARKS

All terms mentioned in this book that are known to be trademarks or service marks have been appropriately capitalized. Sams Publishing cannot attest to the accuracy of this information. Use of a term in this book should not be regarded as affecting the validity of any trademark or service mark.

President	<i>Richard K. Swadley</i>
Publisher and Director of Acquisitions	<i>Jordan Gold</i>
Director of Product Development	<i>Dean Miller</i>
Managing Editor	<i>Kitty Wilson Jarrett</i>
Indexing Manager	<i>Johnna L. VanHoose</i>
Director of Marketing	<i>Kelli S. Spencer</i>
Associate Product Marketing Manager	<i>Jennifer Pock</i>
Marketing Coordinator	<i>Linda Beckwith</i>

Acquisitions Editor

Grace M. Buechlein

Development Editor

Brian Proffitt

Software Development Specialist

Jack Belbot

Production Editor

Kitty Wilson Jarrett

Kate Shoup Welsh

Copy Editors

Kimberly K. Hannel

Carolyn Linn

Kristine Simmons

Indexer

Christine L. Nelsen

Technical Reviewer

Bill Ball

Editorial Coordinators

Mandie Rowell

Katie Wise

Technical Edit Coordinator

Lynette Quinn

Editorial Assistants

Carol Ackerman

Andi Richter

Rhonda Tinch-Mize

Karen Williams

Cover Designer

Karen Ruggles

Book Designer

Ann Jones

Copy Writer

David Reichwein

Production Team Supervisor

Beth Lewis

Production Team

Erin Danielson, Bryan Flores,

DiMonique Ford, Julie Geeting,

Kay Hoskin, Christy M. Lemasters,

Tony McDonald, Darlena Murray,

Julie Searls, Sossity Smith

Overview

Part I	
User Commands	2
Part II	
System Calls	738
Part III	
Library Functions	892
Part IV	
Special Files	1064
Part V	
File Formats	1104
Part VI	
Games	1210
Part VII	
Miscellaneous	1214
Part VIII	
Administration and Privileged Commands	1258
Part IX	
Kernel Reference Guide	1424
Index	

Part I User Commands

Introduction	2
addftinfo	2
afmtodit	2
ansi2knr	4
anytopnm	4
appres	5
ar	5
arch	8
GNU as	8
asciitopgm	10
atktopbm	10
bash	11
bdfthpcf	47
beforelight	47
biff	48
bioradtopgm	48
bitmap, bmtoa, atobm	49
bmptoppm	57
brushtopbm	57
cal	58
cat	58
chattr	59
chfn	60
chgrp	61
chkdupexe	61
chmod	61
chown	62
chsh	63
ci	64
cidentd	69
cksum	70
clear	70
cmuwmtopbm	71
co	71
col	76
colcrt	77
colrm	77
column	78
comm	78

convdate	79
cp	80
cccp, cpp	81
crontab	84
csplit	85
ctags	87
cu	88
cut	90
cvs	91
date	106
dd	108
depmod, modprobe	109
df	112
dig	113
dnsquery	117
domainname	119
dsplit	119
du	120
editres	121
elvis, ex, vi, view, input	126
elvprsv	128
elvrec	129
emacs	130
emacscool	134
etags	135
expand	137
find	137
fitstopnm	142
fmt	143
fold	143
free	144
fsinfo	145
fsfonts	145
fstobdf	146
fstopgm	147
ftp	147
fuser	154
g++	155
g3topbm	160
gawk	161

gcal	173
gcc, g++	174
gemtopbm	201
geqn	202
getlist	206
getopt	207
giftopnm	208
gindexbib	209
glookbib	210
gnroff	210
gouldtoppm	211
gpic	211
gprof	216
grefer	217
grep, egrep, fgrep	224
grephistory	226
grodvi	227
groff	228
grog	230
grops	230
grotty	235
gsoelim	236
gtbl	236
gtroff	237
gzip, gunzip, zcatgzip, gunzip, zcat	248
gzexe	252
head	253
hexdump	254
hipstopgm	256
host	257
hostid	258
hostname	259
hpcdtoppm v0.3	260
httpd	261
icontopbm	262
ident	262
ilbmtoppm	263
imake	264
imgtoppm	267
inews	267
info	269
innconfval	270
insmod	271
install	272
installit	273

ispell, buildhash, munchlist, findaffix, tryaffix, icombine, ijoin	274
join	282
kill	283
killall	284
ksyms	284
last	285
lbxproxy	286
ld	287
lispmtopgm	292
lkbib	292
ln	293
lnDIR	294
locate	295
logger	295
login	296
look	297
lpq	298
lpr	299
lprm	301
lpTest	302
ls, dir, vdir	303
lsattr	304
lsmod	305
lynx	306
macptopbm	309
make	310
makedepend	312
makestrs	314
mattrib	315
mbadblocks	316
mcd	316
mcookie	317
mcopy	317
md5sum	318
mdel	318
mdelTree	319
mdir	319
merge	320
mesg	321
mformat	321
mgrtopbm	322
mkdir	323
mkdirhier	323
mkfifo	323
mkmanifest	324

mknod	325
mlabel	325
mmd	326
mmount	326
mmove	327
more	327
mrd	329
mread	329
mren	329
mtest	330
mttools	330
mtvtppm	333
mttype	333
mv	334
mwrite	335
namei	335
newaliases	336
newgrp	336
nl	337
nlmconv	338
nm	339
nntpget	340
objcopy	341
objdump	342
oclock	344
od	345
passwd	346
paste	347
pbmclean	348
pbmfilters	348
pbmlife	352
pbmmake	353
pbmmask	353
pbmyscale	354
pbmreduce	355
pbmtext	355
pbmto10x	356
pbmto4425	357
pbmtoascii	357
pbmtoatk	358
pbmtobg	358
pbmtocmuwm	358
pbmtoepsi	359
pbmtoepson	359
pbmtog3	360

pbmtogem	360
pbmtogo	360
pbmtoicon	361
pbmtolj	361
pbmtoln03	362
pbmtolps	362
pbmtomacp	363
pbmtomgr	363
pbmtopgm	364
pbmtopi3	364
pbmtopk	364
pbmtoplot	365
pbmtoptx	366
pbmtox10bm	366
pbmtoxbm	367
pgmtoybm	367
pbmtozinc	367
pbmupc	368
pcxtopppm	368
pfbtops	369
pgmbentley	369
pgmcrater	370
pgmedge	371
pgmenhance	371
pgmhist	372
pgmkernel	372
pgmnoise	373
pgmnorm	373
pgmoil	374
pgmramp	374
pgmtexture	375
pgmtofs	376
pgmtolispm	376
pgmtopbm	377
pgmtopppm	378
pi1topppm	378
pi3topbm	379
picttopppm	379
pjtopppm	381
pktopbm	381
pnmalias	381
pnmarith	382
pnmcat	383
pnmcomp	383
pnmconvol	384

pnmcrop	385
pnmcut	385
pnmdepth	385
pnmenlarge	386
pnmfile	386
pnmflip	387
pnmgamma	387
pnmhistmap	388
pnmindex	388
pnminvert	389
pnmmargin	389
pnmnlfilt	390
pnmnoraw	391
pnpad	392
pnpaste	392
pnmrotate	393
pnm-scale	393
pnmshar	394
pnm-smooth	395
pnm-tile	395
pnm-todiff	396
pnm-tofits	396
pnm-tops	397
pnm-torast	398
pnm-tosgi	398
pnm-tosir	399
pnm-totiff	399
pnm-toxwd	400
ppm3d	400
ppm-brighten	401
ppm-change	401
ppm-dim	402
ppm-dist	402
ppm-dither	403
ppm-flash	404
ppm-forge	404
ppm-hist	408
ppm-make	408
ppm-mix	408
ppm-norm	409
ppm-ntsc	409
ppm-pat	410
ppm-quant	411
ppm-quantall	412
ppm-qvga	412

ppmrelief	413
ppmshift	413
ppmspread	414
ppmtoacad	414
ppmtobmp	416
ppmtogif	416
ppmtoicr	417
ppmtoilbm	418
ppmtomap	419
ppmtomitsu	420
ppmtopcx	421
ppmtopgm	421
ppmtopi1	422
ppmtopict	422
ppmtopj	423
ppmtopjxl	424
ppmtopuzz	424
ppmtorgb3	425
ppmtosixel	425
ppmtotga	426
ppmtouil	427
ppmtoxpm	427
ppmtoyuv	428
ppmtoyuvsplit	428
pr	429
ps	430
psbb	433
psidtopgm	433
pstopnm	434
pstree	435
psupdate	436
qrttoppm	436
quota	437
ranlib	437
rasttopnm	438
rawtopgm	439
rawtoppm	439
rcp	440
rcs	441
rcsclean	443
rcsdiff	445
rcsfreeze	446
rcsintro	447
rcsmerge	449
rdist	451

reconfig	454
ref	455
reset	456
resize	456
rev	457
rgb3toppm	457
rlog	458
rlogin	460
rm	461
rmdir	462
rmmod	462
rnews	463
rpcgen	464
rsh	466
rstart	467
rstartd	468
rup	472
rusers	472
rwall	473
rwho	474
script	474
sed	475
sessreg	480
setterm	482
sgitopnm	483
shar	484
shlock	487
showrgb	488
shrinkfile	488
sirtopnm	488
size	489
sldtoppm	490
smpoxy	491
sort	492
spctoppm	494
split	494
spotopgm	495
sputoppm	495
sq	496
startx	496
strings	498
strip	499
subst	500
sum	501
SuperProbe	501

tac	503
tail	504
talk	505
tcal	506
telnet	507
tfmtodit	513
tftp	514
tgatoppm	515
tifftopnm	515
tin, rtin, cdtin, tind	516
tload	533
top	533
touch	536
tr	536
tset, reset	539
tsort	542
twm	542
txt2gcal	558
ul	558
unexpand	559
uniq	560
unshar	560
updatedb	561
uptime	562
userlist	563
uucp	563
uuencode	565
uustat	566
uux	569
uuxqt	572
w	573
wall	574
wc	574
whereis	575
write	576
x11perf	577
x11perfcomp	585
xargs	586
xauth	587
xbmtopbm	592
xcmsdb	592
xclock	593
xclipboard	595
xconsole	597
xcutsel	598

xdm	599
xdpyinfo	614
Xf86_Accel	614
XF86_Mono	624
XF86_SVGA	627
XF86_VGA16	631
xf86config	633
xfd	633
XFree86	636
xfs	641
xhost	643
xieperf	645
ximtoppm	654
xinetd	655
xinit	664
xkill	666
xlogo	667
xlsatoms	668
xslclients	669
xlsfonts	670
xmag	671
xmkmf	672
xmodmap	672
xon	676
xpmtoppm	677
xprop	677
xrdb	681
xrefresh	684
Xserver	685
xset	690
xsetroot	693
xsm	694
xsmclient	698
xstdcmap	699
xterm	700
Xvfb	717
xvidtune	719
xvminitoppm	720
xwd	721
xwdtopnm	722
xwininfo	722
xwud	725
ybmtopbm	726
ytalk	727
yuvplittoppm	730

yuvtoppm	731
zcmp, zdiff	731
zeisstopnm	732
zforce	732
zgrep	733
zmore	733
znew	734
 Part II System Calls	
intro	738
exit	739
accept	740
access	741
acct	742
adjtimex	742
alarm	744
bdflush	744
bind	745
brk, sbrk	746
cacheflush	746
chdir, fchdir	747
chmod, fchmod	748
chown, fchown	749
chroot	750
clone	751
close	752
connect	752
dup, dup2	753
execve	754
fcntl	755
fdatasync	756
flock	757
fork, vfork	758
fsync	758
getdents	759
getdomainname, setdomainname	760
getdtablesize	760
getgid, getegid	761
getgroups, setgroups	761
gethostid, sethostid	762
gethostname, sethostname	763
getitimer, setitimer	763
getpagesize	765
getpeername	765
getpid, getppid	766
getpriority, setpriority	766

getrlimit, getrusage, setrlimit	767
getsid	768
getsockname	769
getsockopt, setsockopt	769
gettimeofday, settimeofday	772
getuid, geteuid	773
idle	774
ioctl	774
ioperm	788
iopl	788
ipc	789
kill	790
killpg	790
link	791
listen	792
llseek	793
lseek	793
mkdir	794
mknod	795
mlock	796
mlockall	797
mmap, munmap	799
modify_ldt	800
get_kernel_syms, create_module, init_module, delete_module	800
mount, umount	802
mprotect	804
mremap	805
msgctl	806
msgget	807
msgop	808
msync	811
munlock	811
munlockall	812
nanosleep	813
nice	814
oldfstat, oldlstat, oldstat, oldolduname, olduname	814
open, creat	815
outb, outw, outl, outsb, outsw, outsl	816
pause	817
personality	817
phys	818
pipe	818
profil	819
ptrace	820
quotactl	821

read	822
readdir	823
readlink	823
ready, writev	824
reboot	825
recv, recvfrom, recvmsg	826
rename	828
rmdir	829
sched_get_priority_max, sched_get_priority_min	830
sched_rr_get_interval	831
sched_setparam, sched_getparam	832
sched_setscheduler, sched_getscheduler	833
sched_yield	835
select, FD_CLR, FD_ISSET, FD_SET, FD_ZERO	835
semctl	837
semget	839
semop	840
send, sendto, sendmsg	842
setfsgid	843
setfsuid	844
setgid	845
setpgid, getpgid, setpgrp, getpgrp	845
setregid, setegid	846
setreuid, seteuid	847
setsid	848
setuid	848
setup	849
shmctl	849
shmget	851
shmop	853
shutdown	855
sigaction, sigprocmask, sigpending, sigsuspend	855
signal	857
sigblock, siggetmask, sigsetmask, sigmask	858
sigpause	858
sigreturn	859
sigvec	860
socket	860
socketcall	862
socketpair	862
stat, fstat, lstat	863
statfs, fstatfs	865
stime	866
swapon, swapoff	866
symlink	867

sync	869
sysctl	869
sysfs	871
sysinfo	871
syslog	872
termios, tcgetattr, tcsetattr, tcsendbreak, tcdrain, tcflush, tcflow, cfgetospeed, cfgetispeed, cfsetispeed, cfsetospeed, tcgetpgrp, tcsetpgrp	874
time	878
times	878
truncate, ftruncate	879
umask	880
uname	880
none	881
afs_syscall, break, gtty, lock, mpx, prof, quotactl, stty, ustat	881
unlink	882
uselib	883
ustat	883
utime, utimes	884
vhangup	885
vm86	885
wait, waitpid	886
wait3, wait4	888
write	889
Part III Library Functions	
Intro	892
abort	892
abs	892
acos	893
acosh	893
alloca	894
asin	894
asinh	895
assert	895
atan	896
atan2	896
atanh	897
atexit	897
atof	898
atoi	898
atol	899
bcmp	899
bcopy	900
bsearch	900
bcmp, bcopy, bzero, memccpy, memchr, memcmp, memcpy, memfrob, memmem, memmove, memset	901

htonl, htons, ntohl, ntohs	901
bzero	902
catgets	902
catopen, catclose	903
ceil	904
clientlib	904
clock	905
closedir	905
confstr	906
copysign	907
cos	907
cosh	908
crypt	908
ctermid	909
asctime, ctime, gmtime, localtime, mktime	909
difftime	911
div	911
drand48, erand48, lrand48, nrand48, mrand48, jrand48, srand48, seed48, lcong48	912
drem	913
ecvt, fcvt	913
erf, erfc	914
execl, execlp, execlx, exect, execv, execvp	914
errno	916
exit	917
exp, log, log10, pow	917
expm1, log1p	918
fabs	919
fclose	919
clearerr, feof, ferror, fileno	919
fflush, fpurge	920
ffs	921
fgetgrent	921
fgetpwent	922
floor	923
fmod	923
fnmatch	924
fopen, fdopen, freopen	924
fpathconf, pathconf	925
fread, fwrite	926
frexp	927
fgetpos, fseek, fsetpos, ftell, rewind	927
ftime	928
ftok	929
ftw	930

gcvt	930
getcwd, get_current_dir_name, getwd	931
getdirentries	931
getenv	932
getgrent, setgrent, endgrent	932
getgrnam, getgrgid	933
getlogin, cuserid	934
getmntent, setmntent, addmntent, endmntent, hasmntopt	935
getnetent, getnetbyaddr, getnetbyname, setnetent, endnetent	936
getopt	937
getpass	940
getprotoent, getprotobyname, getprotobynumber, setprotoent, endprotoent	941
getpw	942
getpwent, setpwent, endpwent	943
getpwnam, getpwuid	944
fgetc, fgets,getc, getchar, gets, ungetc	944
getservent, getservbyname, getservbyport, setservent, endservent	945
getusershell, setusershell, endusershell	946
getutent, getutid, getutline, pututline, setutent, endutent, utmpname	947
getw, putw	948
glob, globfree	949
hosts_access, hosts_ctl	950
hcreate, hdestroy, hsearch	951
hypot	953
index, rindex	953
inet_aton, inet_addr, inet_network, inet_ntoa, inet_makeaddr, inet_lnaof, inet_netof	953
infnan	954
initgroups	955
inndcomm	956
insque, remque	957
isalnum, isalpha, isascii, isblank, iscntrl, isdigit, isgraph, islower, isprint, ispunct, isspace, isupper, isxdigit	957
isatty	958
isinf, isnan, finite	959
j0, j1, jn, y0, y1, yn	959
killpg	960
labs	960
ldexp	961
ldiv	961
lgamma	962
libinn	962
libpbm	966
libpgm	969
libpnm	970

libppm	973
localeconv	974
longjmp	975
lfind, lsearch	975
calloc, malloc, free, realloc	976
mblen	977
mbstowcs	977
mbtowc	978
memccpy	978
memchr	979
memcmp	979
memcpy	980
memfrob	980
memmem	981
memmove	981
memset	982
mkfifo	982
mkstemp	983
mktemp	983
modf	984
asctime, ctime, difftime, gmtime, localtime, mktime	984
tzset	986
on_exit	988
opendir	989
parsedate	989
perror	990
popen, pclose	991
printf, fprintf, sprintf, snprintf, vprintf, vfprintf, vsprintf, vsnprintf	992
psignal	996
putenv	996
putpwent	997
fputc, fputs, putc, putchar, puts	997
qio	998
qsort	1000
raise	1000
rand, srand	1001
random, srandom, initstate, setstate	1001
readdir	1002
readv, writev	1003
realpath	1004
Re_comp, re_exec	1005
regcomp, regexec, regerror, regfree	1005
remove	1007
res_query, res_search, res_mkquery, res_send, res_init, dn_comp, dn_expand	1008

rewinddir	1011
rint	1011
rquota	1012
scandir, alphasort	1012
scanf, fscanf, sscanf, vscanf, vsscanf, vfscanf	1013
seekdir	1015
setbuf, setbuffer, setlinebuf, setvbuf	1016
setenv	1017
setjmp	1018
setlocale	1018
siginterrupt	1019
sigemptyset, sigfillset, sigaddset, sigdelset, sigismember	1019
sin	1020
sinh	1021
sleep	1021
snprintf, vsnprintf	1022
sqrt	1023
stdarg	1023
stdio	1025
stpcpy	1027
strcasecmp, strncasecmp	1028
strcat, strncat	1028
strchr, strchr	1029
strcmp, strncmp	1029
strcoll	1030
strcpy, strncpy	1030
strdup	1031
strerror	1032
strfry	1032
strftime	1032
strcasecmp, strcat, strchr, strcmp, strcoll, strcpy, strcspn, strdup, strfry, strlen, strncat, strncmp, strncpy, strncasecmp, strpbrk, strchr, strsep, strspn, strstr, strtok, strxfrm, index, rindex	1034
strlen	1035
strpbrk	1035
strptime	1036
strsep	1037
strsignal	1038
strspn, strcspn	1038
strstr	1039
strtod	1039
strtok	1040
strtol	1041
strtoul	1041
strxfrm	1042

swab	1043
sysconf	1043
closelog, openlog, syslog	1045
system	1047
tan	1047
tanh	1048
telldir	1048
tempnam	1049
termios, tcgetattr, tcsetattr, tcsendbreak, tcdrain, tcflush, tcflow, cfmakeraw, cfgetospeed, cfgetispeed, cfsetispeed, cfsetospeed, tcgetpgrp, tcsetpgrp	1049
tmpfile	1053
tmpnam	1054
toascii	1055
toupper, tolower	1055
tsearch, tfind, tdelete, twalk	1056
ttyname	1058
tzset	1058
none	1060
usleep	1061
wcstombs	1061
wctomb	1061
 Part IV Special Files	
charsets	1064
console	1066
console_codes	1067
console_ioctl	1074
fd	1080
hd	1083
ispell	1084
lp	1090
mem, kmem, port	1091
mouse	1092
null, zero	1094
ram	1094
sd	1095
st	1096
tty	1100
ttys	1101
vcs, vcsa	1101
 Part V File Formats	
intro	1104
active, active.times	1104
adduser.conf	1105
aliases	1106

cfingerd	1106
cfingerd.conf	1109
cfingerd <i>text rules</i>	1115
control.ctl	1115
cvs	1116
DEVINFO	1120
environ	1121
expire.ctl	1121
exports	1123
filesystems	1125
fstab	1126
groff_font	1127
groff_out	1129
group	1131
history	1131
hosts.nntp, hosts.nntp.nolimit	1132
hosts_access	1133
hosts_options	1137
inittab	1139
inn.conf	1141
innwatch.ctl	1142
ipc	1144
issue	1146
lilo.conf	1147
MAKEDEV.cfg	1151
moderators	1151
/etc/modules	1152
motd	1152
mtools	1152
newsfeeds	1158
newslog	1163
nfs	1165
nnrp.access	1167
nnrpsend.ctl	1168
nologin	1168
overview.fmt	1168
passwd	1169
passwd.nntp	1170
pbm	1170
pgm	1171
pnm	1173
ppm	1173
/proc	1174
protocols	1180
rcsfile	1181

	resolver	1183
	securetty	1184
	services	1184
	shells	1186
	syslog.conf	1186
	termcap	1188
	ttytype	1197
	tzfile	1197
	utmp, wtmp	1198
	uuencode	1200
	XF86Config	1201
Part	VI Games	
	intro	1210
	banner	1210
	ddate	1210
Part	VII Miscellaneous	
	intro	1214
	ascii	1214
	bootparam	1216
	groff_me	1225
	groff_mm	1227
	groff_ms	1234
	hier	1236
	hostname	1238
	iso_8859_1	1239
	locale	1243
	mailaddr	1244
	man	1246
	signal	1248
	suffixes	1249
	tr2tex	1252
	Unicode	1253
	UTF-8	1255
Part	VIII Administration and Privileged Commands	
	intro	1258
	adduser, addgroup	1258
	agetty	1259
	archive	1262
	arp	1263
	badblocks	1264
	buffchan	1264
	cfdisk	1265
	chat	1269

chroot	1273
clock	1273
comsat	1274
crond	1275
ctlinnd	1276
ctrlaltdel	1279
cvsbug	1279
cvtbatch	1281
cytune	1282
debugfs	1284
dip	1285
dmesg	1288
dumpe2fs	1289
e2fsck	1289
edquota	1291
expire	1292
expireover	1293
fastrm	1294
fdformat	1295
fdisk	1296
filechan	1297
fsck	1298
fsck.minix	1300
ftpd	1301
ifconfig	1304
inetd	1305
init, telinit	1307
innd, inndstart	1309
innxmit	1312
ipcrm	1313
ipcs	1314
kbdrate	1314
klogd	1315
lpc	1317
lpd	1318
MAKEDEV	1320
MAKEDEV	1321
mke2fs	1324
mkfs	1325
mkfs	1326
mklost+found	1327
mkswap	1327
mount, umount	1328
moundd	1332
named-xfer	1333

named	1334
named.reload	1338
named.restart	1338
ndc	1338
netstat	1339
makeactive, makehistory, newsrequeue	1342
news.daily	1344
newslog	1346
nfsd	1347
nnrpd	1347
nntpsend	1349
nslookup	1350
overchan	1353
pac	1354
pcnfsd	1355
plipconfig	1357
ping	1358
portmap	1358
powerd	1359
pppd	1360
pppstats	1369
prunehistory	1370
quotacheck	1371
quotaon, quotaoff	1372
rarp	1373
rdev	1373
renice	1375
repquota	1376
rexecd	1376
rlogind	1377
route	1379
routed	1380
rpc.rusersd	1382
rpc.rwalld	1383
rpcinfo	1383
rquotad, rpc.rquotad	1384
rshd	1385
rwhod	1386
sendmail	1387
setfdprm	1391
setserial	1391
setsid	1395
showmount	1396
shutdown	1396
simpleinit	1397

slattach	1399
sliplogin	1399
swapon, swapoff	1401
sync	1401
sysklogd	1402
syslogd	1404
talkd	1405
telnetd	1406
tftpd	1407
timed	1407
timedc	1408
traceroute	1409
tune2fs	1412
tunelp	1413
update_state	1414
uucico	1415
vmstat	1417
vipw	1418
zdump	1419
zic	1419
 Part IX Kernel Reference Guide	
add_timer, del_timer, init_timer	1424
adjust_clock	1424
ctrl_alt_del	1425
file_table	1425
file_table_init	1427
filesystems	1427
get_empty_filp	1428
grow_files	1428
in_group_p	1429
insert_file_free	1429
kernel_mktime	1430
proc_sel	1430
put_file_last	1431
remove_file_free	1431

Tell Us What You Think!

As a reader, you are the most important critic of and commentator on our books. We value your opinion and want to know what we're doing right, what we could do better, what areas you'd like to see us publish in, and any other words of wisdom you're willing to pass our way. You can help us make strong books that meet your needs and give you the computer guidance you require.

Do you have access to the World Wide Web? Then check out our site at <http://www.mcp.com>.

NOTE

If you have a technical question about this book, call the technical support line at 317-581-3833 or e-mail support@mcp.com.

As the team leader of the group that created this book, I welcome your comments. You can fax, e-mail, or write me directly to let me know what you did or didn't like about this book—as well as what we can do to make our books stronger. Here's the information:

Fax: 317-581-4669
E-mail: opsys_mgr@sams.mcp.com
Mail: Dean Miller
Comments Department
Sams Publishing
201 W. 103rd Street
Indianapolis, IN 46290

Copyright

exit(2), access(2), alarm(2), close(2), dup(2), fcntl(2), link(2), mkdir(2), mknod(2), open(2), read(2), rename(2), rmdir(2), symlink(2), write(2) copyright © 1992 Drew Eckhardt; 1993 Michael Haardt, Ian Jackson.

unlink(2), remove(3) copyright © 1992 Drew Eckhardt; 1993 Ian Jackson.

chdir(2), chmod(2), chown(2), chroot(2), clone(2), execve(2), fork(2), getrlimit(2), gettimeofday(2), kill(2), nice(2), pause(2), pipe(2), reboot(2), setup(2), stime(2), swapon(2), sync(2), time(2), times(2), umask(2), uname(2), uselib(2), utime(2) copyright © 1992 Drew Eckhardt (drew@cs.colorado.edu), March 28, 1992.

mprotect(2) copyright © 1995 Michael Shields (shields@tembel.org).

select(2) copyright © 1992 Drew Eckhardt, copyright © 1995 Michael Shields.

acct(2), brk(2), intro(2), ioperm(2), phys(2), ptrace(2), setsid(2), termios(2), ascii(7), crypt(3), environ(5), ftime(3), ftw(3), group(5), hd(4), intro(1), intro(3), intro(4), intro(5), intro(6), intro(7), intro(8), isatty(3), issue(5), longjmp(3), mem(4), motd(5), nologin(5), null(4), passwd(5), ram(4), securetty(5), setjmp(3), shells(5), termcap(7), tty(4), ttys(4), ttytype(5), utmp(5), lp(4), perror(3) copyright © 1993, 1994, 1995 Michael Haardt.

bind(2), connect(2), flock(2), fsync(2), getdomainname(2), getdtablesize(2), getgid(2), getgroups(2), gethostid(2), gethostname(2), getpagesize(2), getpid(2), getuid(2), idle(2), iopl(2), profil(2), recv(2), sigvec(2), undocumented(2), vhangup(2), vm86(2), acos(3), getdirent-tries(3), ctrlaltdel(8), dmesg(8), fdformat(8), fdisk(8), fsck.minix(8), ipcrm(8), ipcs(8), sync(8), sd(4), clear(1), clock(8), domainname(1), mkfs.minix(8), mkswap(8), passwd(1), rdev(8), reset(1), setfdprm(8), setserial(8), shutdown(8), kbdrate(8), update state(8), chkdupexe(1), cytune(8) copyright 1992, 1993, 1994, 1995 Rickard E. Faith (faith@cs.unc.edu).

getdents(2), llseek(2), readdir(2), syslog(2), console.4 copyright 1994, 1995 Andries Brouwer (aeb@cwi.nl).

mount(2) copyright 1993 Rickard E. Faith (faith@cs.unc.edu), copyright 1994 Andries E. Brouwer (aeb@cwi.nl).

adjtimex(2), bdflush(2), ipc(2), modify ldt(2), obsolete(2), socketcall(2), unimplemented(2) copyright © 1995 Michael Chastain (mec@shell.portal.com).

accept(2), getpeername(2), listen(2), lseek(2), getpriority(2), getsockname(2), getsockopt(2), ioctl(2), killpg(2), mmap(2), readlink(2), send(2), setpgid(2), setregid(2), setreuid(2), shut-down(2), sigblock(2), sigpause(2), socket(2), socketpair(2), statfs(2), truncate(2), alloca(3), fclose(3), ferror(3), fflush(3), fread(3), fseek(3), getpass(3), mailaddr(7), popen(3), printf(3), scanf(3), setbuf(3), stdarg(3), stdio(3), banner(6), cal(1), col(1), colcrt(1), colrm(1), column(1), fstab(5), getoptprog(1), logger(1), look(1), lpc(8), lpd(8), lpq(1), lpr(1), lprm(1), lpctest(1), mesg(1), mount(8), pac(8), ping(8), syslog.conf(5), syslogd(8), tsort(8), vipw(1), write(1), vi(1), rev(1), biff(1), tset(1), w(1), aliases(5), ftp(1), ftpd(8), inetd(8), newaliases(1), rcp(1), resolver(5), rexecd(8), rlogin(1), routed(8), rpc.rusersd(8), rpc.rwalld(8), rsh(1), rshd(8), rup(1), rusers(1), rwall(1), rwho(1), rwhod(8), sendmail(8), sliplogin(8), talk(1), talkd(8), telnet(1), telnetd(8), tftp(1), tftpd(8), timed(8), timedc(8), traceroute(8) copyright © 1980, 1983, 1985, 1989, 1990, 1991, 1992 The Regents of the University of California. All rights reserved.

getitimer(2) copyright 1993 by Darren Senn (sinster@scintilla.santa-clara.ca.us).

modules(2), ksyms(1), insmod(1), lsmod(1), rmmod(1) copyright © 1994, 1995 Bjorn Ekwall (bjorn@blox.se).

msgctl(2), msgget(2), msgop(2), semctl(2), semget(2), semop(2), ftok(3), ipc(5) copyright 1993 Giorgio Ciucci (giorgio@crcc.it).

setgid(2), setuid(2), realpath(3) copyright © 1994, Graeme W. Willford.

shmctl(2), shmget(2), shmop(2) copyright © 1993 Luigi P. Bai (lpb@softint.com) July 28, 1993.

sigaction(2), signal(2), sigsetops(3) copyright © 1994 Mike Battersby (mike@starbug.apana.org.au).

stat(2) copyright © 1992 Drew Eckhardt (drew@cs.colorado.edu), March 28, 1992. Parts copyright © 1995 Nicolai Langfeldt (janl@ifi.uio.no), January 1, 1995.

sysinfo(2), adjustclock(9), ctrl-alt-del(9), filesystems(9), file table(9), file table init(9), get empty filp(9), grow files(9), in group p(9), insert file free(9), kernel mktime(9), proc sel(9), put file last(9), remove file free(9) copyright © 1993 by Dan Miner (dminer@nyx.cs.du.edu).

wait(2), wait4(2), confstr(3), ctermid(3), fnmatch(3), fpathconf(3), getcwd(3), getopt(3), gets(3), isalpha(3), malloc(3), signal(7), sleep(3), suffixes(7), sysconf(3), system(3), hier(7), assert(3), glob(3), killpg(3), locale(7), localeconv(3), puts(3), raise(3), readv(3), setlocale(3) copyright © 1993 by Thomas Koenig (ig25@rz.uni-karlsruhe.de).

abort(3), abs(3), acos(3), asin(3), asinh(3), atan(3), atan2(3), atanh(3), atexit(3), atof(3), atoi(3), atol(3), bcmp(3), bcopy(3), bstring(3), byteorder(3), bzero(3), ceil(3), closedir(3), confstr(3), copysign(3), cos(3), cosh(3), ctime(3), difftime(3), div(3), drand48(3), drem(3), ecvt(3), erf(3), exec(3), exit(3), exp(3), fabs(3), ffs(3), fgetgrent(3), fgetpwent(3), fmod(3), fopen(3), frexp(3), gcvt(3), getenv(3), getgrent(3), getgrnam(3), gethostbyname(3), getmntent(3), getnetent(3), getprotoent(3), getpw(3), getpwent(3), getpwnam(3), getservernt(3), getusershell(3), hypot(3), index(3), inet(3), infnan(3), initgroups(3), isinf(3), j0(3), labs(3), ldexp(3), ldiv(3), lgamma(3), mblen(3), mbstowcs(3), mbtowc(3), memccpy(3), memchr(3), memcmp(3), memcpy(3), memfrob(3), memmem(3), memmove(3), memset(3), mkstemp(3), mktemp(3), modf(3), on exit(3), opendir(3), psignal(3), putenv(3), putpwent(3), qsort(3), rand(3), random(3), readdir(3), resolver(3), rewinddir(3), rint(3), scandir(3), seekdir(3), setenv(3), siginterrupt(3), sin(3), sinh(3), sqrt(3), strcmp(3), strcat(3), strchr(3), strcmp(3), strcoll(3), strcpy(3), strdup(3), strerror(3), strfry(3), strptime(3), string(3), strlen(3), strpbrk(3), strptime(3), strsep(3), strsignal(3), strspn(3), strstr(3), strtod(3), strtok(3), strtol(3), strtoul(3), strxfrm(3), swab(3), tan(3), tanh(3), telldir(3), tempnam(3), tmpfile(3), tmpnam(3), toupper(3), tzset(3), usleep(3), wctombs(3), wctomb(3) copyright 1993 David Metcalfe (david@prism.demon.co.uk).

add timer(9), console ioctl(4), ttyname(3), vcs(4) copyright © 1995 Jim Van Zandt (jrv@evanzandt.mv.com).

catgets(3), catopen(3), hostid(1) copyright 1993 Mitchum DSouza (m.dsouza@mrc-applied-psychology.cambridge.ac.uk).

fd(4) copyright © 1993 Michael Haardt (michael@cantor.informatik.rwth-aachen.de) and 1994, 1995 Alain Knaff (Alain.Knaff@imag.fr).

getutent(3) copyright 1995 Mark D. Roth (roth@uiuc.edu).

hsearch(3) copyright 1993 Ulrich Drepper (drepper@karlsruhe.gmd.de).

iso88591(7), proc(5), sed(1) copyright 1993[nd]1995 Daniel Quinlan (quinlan@yggdrasil.com).

st(4) copyright 1995 Robert K. Nichols (Robert.K.Nichols@att.com).

agetty(8) copyright © by W.Z. Venema (wietse@wzv.win.tue.nl), Peter Orbaek (poe@daimi.aau.dk).

cfdisk(8) copyright 1994 Kevin E. Martin (martin@cs.unc.edu).

chfn(1), chsh.1 copyright © 1994 by Salvatore Valente (svalente@athena.mit.edu).

crond(8), crontab(1) copyright 1994 Matthew Dillon (dillon@apollo.west.oic.com).

kill(1) copyright 1994 Salvatore Valente (svalente@mit.edu), copyright 1992 Rickard E. Faith (faith@cs.unc.edu).

klogd(8), syslogd(8) copyright 1994 Greg Wettstein, Enjellic Systems Development.

setterm(1) copyright 1990 Gordon Irlam (gordoni@cs.ua.oz.au). Copyright 1992 Rickard E. Faith (faith@cs.unc.edu).

tunelp(8), ps(1), psupdate(8) copyright © 1992 Michael K. Johnson (johnsonm@nigel.vnet.net).

xinetd(1) copyright © 1992 by Panagiotis Tsirigotis.

bash(1) copyright 1995 Chet Ramey (chet@ins.cwru.edu).

adduser(8) copyright 1995 by Ted Hajek, 1994 by Ian Murdock.

e2fsck(8) copyright 1993, 1994 by Theodore Ts'o.

free(1), tload(1) copyright © 1993 Matt Welsh (mdw@sunsite.unc.edu).

top(1) copyright 1992 Robert J. Nation.

vmstat(8) copyright © 1994 Henry Ware (al172@yfn.ysu.edu).

bdftopcf(1x), beforelight(1x), bitmap(1x), editres(1x), fsinfo(1x), flsfonts(1x),fstobdf(1x), iceauth(1x), imake(1x), lbxproxy(1x), lndir(1x), makedepend(1x), makestrs(1x), mkdirhier(1x), mkfontdir(1x), oclock(1x), resize(1x), sessreg(1x), showrgb(1x), smproxy(1x), startx(1x), x11perf(1x), x11perfcomp(1x), xauth(1x), xclipboard(1x), xclock(1x), xcmsdb(1x), xcon-sole(1x), xcutsel(1x), xdm(1x), xdpinfo(1x), xf86config(1x), xfd(1x), xfs(1x), xhost(1x), xinit(1x), xkill(1x), xlogo(1x), xlsatoms(1x), xlsclients(1x), xlsfonts(1x), xmag(1x), xmkmf(1x), xmodmap(1x), xon(1x), xprop(1x), xrdp(1x), xrefresh(1x), xset(1x), xsetroot(1x), xsm(1x), xsmclient(1x), xstdcmap(1x), xterm(1x), xwd(1x), xwininfo(1x), xwud(1x) copyright © 1993, 1994 X Consortium.

portmap(8) copyright © 1987 Sun Microsystems, copyright © 1990, 1991 The Regents of the University of California.

rpcgen.new(1) copyright © 1988, 1990 Sun Microsystems, Inc.

rstart(1x), rstartd(1x) copyright © 1993 Quarterdeck Office Systems.

showmount(8) copyright 1993 Rick Sladkey (jrs@world.std.com).

twm(1x) copyright © 1993, 1994 X Consortium. Portions copyright 1988 Evans & Sutherland Computer Corporation. Portions copyright 1989 Hewlett-Packard Company.

xieperf.1x copyright 1993, 1994 by AGE Logic, Inc.

Many thanks to all these contributors for providing excellent-quality man pages and also to the Free Software Foundation for providing the rest.

Part I:

User Commands

Introduction

This section introduces and describes user commands.

AUTHORS

Look at the header of the manual page for the author(s) and copyright conditions. Note that these can be different from page to page.

addftinfo

`addftinfo`—Add information to `troff` font files for use with `groff`

SYNOPSIS

```
addftinfo [ -paramvalue... ] res unitwidth font
```

DESCRIPTION

`addftinfo` reads a `troff` font file and adds some additional font-metric information that is used by the `groff` system. The font file with the information added is written on the standard output. The information added is guessed using some parametric information about the font and assumptions about the traditional `troff` names for characters. The main information added is the heights and depths of characters. The `res` and `unitwidth` arguments should be the same as the corresponding parameters in the `DESC` file; `font` is the name of the file describing the font; if `font` ends with `I`, the font will be assumed to be italic.

OPTIONS

Each of the `r` options changes one of the parameters that is used to derive the heights and depths. Like the existing quantities in the font file, each value is in inches/`res` for a font whose point size is `unitwidth`. `param` must be one of the following:

<code>x-height</code>	The height of lowercase letters without ascenders such as <code>x</code>
<code>fig-height</code>	The height of figures (digits)
<code>asc-height</code>	The height of characters with ascenders, such as <code>b</code> , <code>d</code> , or <code>l</code>
<code>body-height</code>	The height of characters such as parentheses
<code>cap-height</code>	The height of uppercase letters such as <code>A</code>
<code>comma-depth</code>	The depth of a comma
<code>desc-depth</code>	The depth of characters with descenders, such as <code>p</code> , <code>q</code> , or <code>y</code>
<code>body-depth</code>	The depth of characters such as parentheses

`addftinfo` makes no attempt to use the specified parameters to guess the unspecified parameters. If a parameter is not specified, the default will be used. The defaults are chosen to have the reasonable values for a Times font.

SEE ALSO

`font(5)` `groff_font(5)`, `groff(1)`, `groff_char(7)`

Groff Version 1.09, 6 August 1992

afmtodit

`afmtodit`—Create font files for use with `groff` `-Tps`

SYNOPSIS

```
afmtodit [ -ns ][-ddesc_file ][-eenc_file ][-in ][-an ] afm_file map_file font
```

DESCRIPTION

afmtodit creates a font file for use with groff and grops. afmtodit is written in Perl; you must have Perl version 3 installed in order to run afmtodit. *afm_file* is the AFM (Adobe Font Metric) file for the font. *map_file* is a file that says which groff character names map onto each PostScript character name; this file should contain a sequence of lines of the form:

```
ps_char groff_char
```

where *ps_char* is the PostScript name of the character and *groff_char* is the groff name of the character (as used in the groff font file.) The same *ps_char* can occur multiple times in the file; each *groff_char* must occur, at most, once. *font* is the groff name of the font. If a PostScript character is in the encoding to be used for the font but is not mentioned in *map_file*, then afmtodit will put it in the groff font file as an unnamed character, which can be accessed by the `\N` escape sequence in *troff*. The *groff_font* file will be output to a file called *font*.

If there is a downloadable font file for the font, it may be listed in the file `/usr/lib/groff/font/devps/download`; see `grops(1)`.

If the `-i` option is used, afmtodit will automatically generate an italic correction, a left italic correction, and a subscript correction for each character (the significance of these parameters is explained in *groff_font(5)*); these parameters may be specified for individual characters by adding to the *afm_file* lines of the form:

```
italicCorrectionps charn
leftItalicCorrectionps charn
subscriptCorrectionps charn
```

where *ps_char* is the PostScript name of the character, and *n* is the desired value of the corresponding parameter in thousandths of an em. These parameters are normally needed only for italic (or oblique) fonts.

OPTIONS

- `-n` Don't output a ligatures command for this font. Use this with constant-width fonts.
- `-s` The font is special. The effect of this option is to add the special command to the font file.
- `-ddesc_file` The device description file is *desc_file* rather than the default `DESC`.
- `-eenc_file` The PostScript font should be reencoded to use the encoding described in *enc_file*. The format of *enc_file* is described in *grops(1)*.
- `-an` Use *n* as the slant parameter in the font file; this is used by groff in the positioning of accents. By default, afmtodit uses the negative of the *ItalicAngle* specified in the *afm_file*; with true italic fonts, it is sometimes desirable to use a slant that is less than this. If you find that characters from an italic font have accents placed too far to the right over them, then use the `-a` option to give the font a smaller slant.
- `-in` Generate an italic correction for each character so that the character's width plus the character's italic correction is equal to *n* thousandths of an em plus the amount by which the right edge of the character's bounding is to the right of the character's origin. If this would result in a negative italic correction, use a zero italic correction instead.

Also generate a subscript correction equal to the product of the tangent of the slant of the font and four-fifths of the x-height of the font. If this would result in a subscript correction greater than the italic correction, use a subscript correction equal to the italic correction instead.

Also generate a left italic correction for each character equal to *n* thousandths of an em plus the amount by which the left edge of the character's bounding box is to the left of the character's origin. The left italic correction may be negative.

This option is normally needed only with italic (or oblique) fonts. The font files distributed with groff were created using an option of `-i50` for italic fonts.

FILES

<code>/usr/lib/groff/font/devps/DESC</code>	Device description file
<code>/usr/lib/groff/font/devps/F</code>	Font description file for font <i>F</i>
<code>/usr/lib/groff/font/devps/download</code>	List of downloadable fonts

```
/usr/lib/groff/font/devps/text.enc
/usr/lib/groff/font/devps/generate/textmap
```

Encoding used for text fonts
Standard mapping

SEE ALSO

groff(1), grops(1), groff_font(5), perl(1)

Groff Version 1.09, 14 February 1994

ansi2knr

ansi2knr—Convert ANSI C to Kernighan & Ritchie C

SYNOPSIS

```
ansi2knr input_file output_file
```

DESCRIPTION

If no `output_file` is supplied, output goes to `stdout`. There are no error messages.

`ansi2knr` recognizes functions by seeing a nonkeyword identifier at the left margin, followed by a left parenthesis, with a right parenthesis as the last character on the line. It will recognize a multiline header if the last character on each line but the last is a left parenthesis or comma. These algorithms ignore whitespace and comments, except that the function name must be the first thing on the line.

The following constructs will confuse it:

- Any other construct that starts at the left margin and follows the above syntax (such as a macro or function call)
- Macros that tinker with the syntax of the function header

31 December 1990

anytopnm

anytopnm—Attempt to convert an unknown type of image file to a portable anymap

SYNOPSIS

```
anytopnm file
```

DESCRIPTION

`anytopnm` uses the `file` program, possibly augmented by the magic numbers file included with `PBMPLUS`, to try to figure out what type of image file it is. If that fails (very few image formats have magic numbers), looks at the filename extension. If that fails, punt.

The type of the output file depends on the input file.

SEE ALSO

pnmfile(1), pnm(5), file(1)

BUGS

It's a script. Scripts are not portable to non-UNIX environments.

AUTHOR

Copyright © 1991 by Jef Poskanzer

27 July 1990

appres

appres—List X application resource database

SYNOPSIS

```
appres [[class [instance]] [-1] [toolkitoptions]
```

DESCRIPTION

The `appres` program prints the resources seen by an application (or subhierarchy of an application) with the specified class and instance names. It can be used to determine which resources a particular program will load. For example,

```
% appres XTerm
```

will list the resources that any `xterm` program will load. If no application class is specified, the class `-AppResTest-` is used.

To match a particular instance name, specify an instance name explicitly after the class name, or use the normal `x` toolkit option. For example,

```
% appres XTerm myxterm
```

or

```
% appres XTerm -name myxterm
```

To list resources that match a subhierarchy of an application, specify hierarchical class and instance names. The number of class and instance components must be equal, and the instance name should not be specified with a toolkit option. For example,

```
% appres Xman.TopLevelShell.Form xman.topBox.form
```

will list the resources of widgets of `xman topBox` hierarchy. To list just the resources matching a specific level in the hierarchy, use the `-1` option. For example,

```
% appres XTerm.VT100 xterm.vt100 -1
```

will list the resources matching the `xterm vt100` widget.

SEE ALSO

`x(1)`, `xrdb(1)`, `listres(1)`

AUTHOR

Jim Fulton (MIT X Consortium)

X Version 11 Release 6

ar

ar—Create, modify, and extract from archives

SYNOPSIS

```
ar [ - ] dmpqrtx[abcilosuvV] [ membername ] archive files ...
```

DESCRIPTION

The GNU `ar` program creates, modifies, and extracts from archives. An archive is a single file holding a collection of other files in a structure that makes it possible to retrieve the original individual files (called members of the archive).

The original files' contents, mode (permissions), timestamp, owner, and group are preserved in the archive, and may be reconstituted on extraction.

GNU `ar` can maintain archives whose members have names of any length; however, depending on how `ar` is configured on your system, a limit on member-name length may be imposed (for compatibility with archive formats maintained with other tools). If it exists, the limit is often 15 characters (typical of formats related to `a.out`) or 16 characters (typical of formats related to `coff`).

`ar` is considered a binary utility because archives of this sort are most often used as libraries holding commonly needed subroutines.

`ar` will create an index to the symbols defined in relocatable object modules in the archive when you specify the modifier `s`. Once created, this index is updated in the archive whenever `ar` makes a change to its contents (save for the `q` update operation). An archive with such an index speeds up linking to the library, and allows routines in the library to call each other without regard to their placement in the archive.

You may use `nm -s` or `nm --print-arnmap` to list this index table. If an archive lacks the table, another form of `ar` called `ranlib` can be used to add just the table.

`ar` insists on at least two arguments to execute: one keyletter specifying the operation (optionally accompanied by other keyletters specifying modifiers), and the archive name to act on.

Most operations can also accept further files arguments, specifying particular files to operate on.

OPTIONS

GNU `ar` allows you to mix the operation code `p` and modifier flags `mod` in any order, within the first command-line argument.

If you wish, you may begin the first command-line argument with a dash.

The `p` keyletter specifies what operation to execute; it may be any of the following, but you must specify only one of them:

- `d` Delete modules from the archive. Specify the names of modules to be deleted as files; the archive is untouched if you specify no files to delete.
If you specify the `v` modifier, `ar` will list each module as it is deleted.
- `m` Use this operation to move members in an archive.
The ordering of members in an archive can make a difference in how programs are linked using the library if a symbol is defined in more than one member.
If no modifiers are used with `m`, any members you name in the files arguments are moved to the end of the archive; you can use the `a`, `b`, or `i` modifiers to move them to a specified place instead.
- `p` Print the specified members of the archive to the standard output file. If the `v` modifier is specified, show the membername before copying its contents to standard output.
If you specify no files, all the files in the archive are printed.
- `q` Quick append; add files to the end of archive without checking for replacement.
The modifiers `a`, `b`, and `i` do not affect this operation; new members are always placed at the end of the archive.
The modifier `v` makes `ar` list each file as it is appended.
Since the point of this operation is speed, the archive's symbol table index is not updated, even if it already existed; you can use `ar s` or `ranlib` explicitly to update the symbol table index.
- `r` Insert files into archive (with replacement). This operation differs from `q` in that any previously existing members are deleted if their names match those being added.
If one of the files named in files doesn't exist, `ar` displays an error message and leaves undisturbed any existing members of the archive matching that name.
By default, new members are added at the end of the file, but you may use one of the modifiers `a`, `b`, or `i` to request placement relative to some existing member.
The modifier `v` used with this operation elicits a line of output for each file inserted, along with one of the letters `a` or `r` to indicate whether the file was appended (no old member deleted) or replaced.

- t** Display a table listing the contents of archive, or those of the files listed in files that are present in the archive. Normally, only the membername is shown; if you also want to see the modes (permissions), timestamp, owner, group, and size, you can request that by also specifying the **v** modifier. If you do not specify any files, all files in the archive are listed. If there is more than one file with the same name (say, `file`) in an archive (say, `b.a`), `ar t b.a file` will list only the first instance; to see them all, you must ask for a complete listing—in our example, `ar t b.a`.
- x** Extract members (named files) from the archive. You can use the **v** modifier with this operation to request that `ar` list each name as it extracts it. If you do not specify any files, all files in the archive are extracted.
- A number of modifiers (**mod**) may immediately follow the **p** keyletter, to specify variations on an operation's behavior, as follows:
- a** Add new files after an existing member of the archive. If you use the modifier **a**, the name of an existing archive member must be present as the membername argument, before the archive specification.
- b** Add new files before an existing member of the archive. If you use the modifier **b**, the name of an existing archive member must be present as the membername argument, before the archive specification (same as **i**).
- c** Create the archive. The specified archive is always created if it didn't exist when you request an update. But a warning is issued unless you specify in advance that you expect to create it by using this modifier.
- i** Insert new files before an existing member of the archive. If you use the modifier **i**, the name of an existing archive member must be present as the membername argument, before the archive specification. (same as **b**).
- l** This modifier is accepted but not used.
- o** Preserve the original dates of members when extracting them. If you do not specify this modifier, files extracted from the archive will be stamped with the time of extraction.
- s** Write an object-file index into the archive, or update an existing one, even if no other change is made to the archive. You may use this modifier flag either with any operation, or alone. Running `ar s` on an archive is equivalent to running `ranlib` on it.
- u** Normally, `ar r...` inserts all files listed into the archive. If you would like to insert only those of the files you list that are newer than existing members of the same names, use this modifier. The **u** modifier is allowed only for the operation **r** (replace). In particular, the combination **qu** is not allowed, since checking the timestamps would lose any speed advantage from the operation **q**.
- v** This modifier requests the verbose version of an operation. Many operations display additional information, such as filenames processed, when the modifier **v** is appended.
- v** This modifier shows the version number of `ar`.

SEE ALSO

`binutils` entry in `info`; *The GNU Binary Utilities*, Roland H. Pesch (October 1991); `nm(1)`, `anlib(1)`

COPYING

Copyright © 1991 Free Software Foundation, Inc. Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies. Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

arch

arch—Print architecture

SYNOPSIS

arch

DESCRIPTION

arch displays machine architecture type.

SEE ALSO

uname(1), uname(2)

Debian GNU/Linux, 15 January 1994

GNU as

GNU as—The portable GNU assembler

SYNOPSIS

```
as [ -a | -al | -as ] [-D ] [-f ] [-I path ] [-K ] [-L ] [-o objfile ] [-R ] [-v ] [-w ] [--\| \
files ...]
```

i960-only options:

```
[ -ACA | -ACA A | -ACB | -ACC | -AKA | -AKB | -AKC | -AMC ] [-b ] [-no-relax ]
```

m680x0-only options:

```
[ -l ] [-mc68000 | -mc68010 | -mc68020]
```

DESCRIPTION

GNU as is really a family of assemblers. If you use (or have used) the GNU assembler on one architecture, you should find a fairly similar environment when you use it on another architecture. Each version has much in common with the others, including object file formats, most assembler directives (often called pseudo-ops) and assembler syntax.

For information on the syntax and pseudo-ops used by GNU as, see as entry in *info* (or the manual *Using as: The GNU Assembler*).

as is primarily intended to assemble the output of the GNU C compiler gcc for use by the linker ld. Nevertheless, we've tried to make as assemble correctly everything that the native assembler would. This doesn't mean as always uses the same syntax as another assembler for the same architecture; for example, we know of several incompatible versions of 680x0 assembly language syntax.

Each time you run as, it assembles exactly one source program. The source program is made up of one or more files. (The standard input is also a file.)

If as is given no filenames, it attempts to read one input file from the as standard input, which is normally your terminal. You may have to type Ctrl-D to tell as there is no more program to assemble. Use -- if you need to explicitly name the standard input file in your command line.

as may write warnings and error messages to the standard error file (usually your terminal). This should not happen when as is run automatically by a compiler. Warnings report an assumption made so that as could keep assembling a flawed program; errors report a grave problem that stops the assembly.

OPTIONS

<code>-a -a1 -as</code>	Turn on assembly listings; <code>-a1</code> , listing only, <code>-as</code> , symbols only, <code>-a</code> , everything.
<code>-D</code>	This option is accepted only for script compatibility with calls to other assemblers; it has no effect on <code>as</code> .
<code>-f</code>	“Fast”—skip preprocessing (assume source is compiler output).
<code>-I\path</code>	Add path to the search list for <code>.include</code> directives.
<code>-K</code>	Issue warnings when difference tables altered for long displacements.
<code>-L</code>	Keep (in symbol table) local symbols, starting with <code>L</code> .
<code>-o\obj file</code>	Name the object-file output from <code>as</code> .
<code>-R</code>	Fold data section into text section.
<code>-v</code>	Announce <code>as</code> version.
<code>-W</code>	Suppress warning messages.
<code>--\files...</code>	Source files to assemble, or standard input (<code>--</code>).
<code>-Avar</code>	(When configured for Intel 960.) Specify which variant of the 960 architecture is the target.
<code>-b</code>	(When configured for Intel 960.) Add code to collect statistics about branches taken.
<code>-no-relax</code>	(When configured for Intel 960.) Do not alter compare-and-branch instructions for long displacements; error if necessary.
<code>-l</code>	(When configured for Motorola 68000.) Shorten references to undefined symbols to one word instead of two.
<code>-mc68000 -mc68010 -mc68020</code>	(When configured for Motorola 68000.) Specify which processor in the 68000 family is the target (default <code>68020</code>).

Options may be in any order, and may be before, after, or between filenames. The order of filenames is significant.

The double hyphens command (`--`) by itself names the standard input file explicitly, as one of the files for `as` to assemble.

Except for `--`, any command line argument that begins with a hyphen (`-`) is an option. Each option changes the behavior of `as`. No option changes the way another option works. An option is a hyphen followed by one or more letters; the case of the letter is important. All options are optional.

The `-o` option expects exactly one filename to follow. The filename may either immediately follow the option's letter (compatible with older assemblers) or it may be the next command argument (GNU standard).

These two command lines are equivalent:

```
as -o my-object-file.o mumble.s
```

```
as -omy-object-file.o mumble.s
```

SEE ALSO

as entry in `info`; *Using as: The GNU Assembler*; `gcc(1)`, `ld(1)`.

COPYING

Copyright © 1991, 1992 Free Software Foundation, Inc. Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies. Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

asciitopgm

asciitopgm—Convert ASCII graphics into a portable graymap

SYNOPSIS

```
asciitopgm [-d divisor] height width [asciifile]
```

DESCRIPTION

Reads ASCII data as input. Produces a portable graymap with pixel values that are an approximation of the brightness of the ASCII characters, assuming black-on-white printing. In other words, a capital *M* is very dark, a period is very light, and a space is white. Input lines that are fewer than `width` characters are automatically padded with spaces.

The divisor argument is a floating-point number by which the output pixels are divided; the default value is 1.0. This can be used to adjust the brightness of the graymap; for example, if the image is too dim, reduce the divisor.

In keeping with (I believe) FORTRAN line-printer conventions, input lines beginning with a + (plus) character are assumed to overstrike the previous line, allowing a larger range of gray values.

This tool contradicts the message in the `pbmtoascii` manual: “Note that there is no `asciitopbm` tool—this transformation is one-way.”

BUGS

The table of ASCII-to-gray values is subject to interpretation, and, of course, depends on the typeface intended for the input.

SEE ALSO

`pbmtoascii(1)`, `pgm(5)`

AUTHOR

Wilson H. Bent, Jr. (whb@usc.edu)

26 December 1994

atktopbm

atktopbm—Convert Andrew Toolkit raster object to portable bitmap

SYNOPSIS

```
atktopbm [atkfile]
```

DESCRIPTION

`atktopbm` reads an Andrew Toolkit raster object as input and produces a portable bitmap as output.

SEE ALSO

`pbmtoatk(1)`, `pbm(5)`

AUTHOR

Copyright © 1991 by Bill Janssen

26 September 1991

bash

bash—GNU Bourne–again shell

SYNOPSIS

bash [options] [file]

DESCRIPTION

bash is an sh-compatible command language interpreter that executes commands read from the standard input or from a file. bash also incorporates useful features from the Korn and C shells (ksh and csh).

bash is ultimately intended to be a conformant implementation of the IEEE POSIX Shell and Tools specification (IEEE Working Group 10032).

OPTIONS

In addition to the single-character shell options documented in the description of the set built-in command, bash interprets the following flags when it is invoked:

-c string	If the -c flag is present, then commands are read from string. If there are arguments after the string, they are assigned to the positional parameters, starting with \$0.
-i	If the -i flag is present, the shell is interactive.
-s	If the -s flag is present, or if no arguments remain after option processing, then commands are read from the standard input. This option allows the positional parameters to be set when invoking an interactive shell.
-	A single - signals the end of options and disables further option processing. Any arguments after the - are treated as filenames and arguments. An argument of -- is equivalent to an argument of -.

bash also interprets a number of multicharacter options. To be recognized, these options must appear on the command line before the single-character options.

-norc	Do not read and execute the personal initialization file ~/.bashrc if the shell is interactive. This option is on by default if the shell is invoked as sh.
-noprofile	Do not read either the system-wide startup file /etc/profile or any of the personal initialization files ~/.bash_profile, ~/.bash_login, or ~/.profile. By default, bash normally reads these files when it is invoked as a login shell. (See the “Invocation” section, later in this manual page.)
-rcfile file	Execute commands from file instead of the standard personal initialization file ~/.bashrc, if the shell is interactive. (See “Invocation.”)
-version	Show the version number of this instance of bash when starting.
-quiet	Do not be verbose when starting up (do not show the shell version or any other information). This is the default.
-login	Make bash act as if it had been invoked as a login shell.
-nobraceexpansion	Do not perform curly brace expansion. (See “Brace Expansion,” later in this manual page.)
-nolineediting	Do not use the GNU readline library to read command lines if interactive.
-posix	Change the behavior of bash where the default operation differs from the POSIX 1003.2 standard to match the standard.

ARGUMENTS

If arguments remain after option processing, and neither the -c nor the -s option has been supplied, the first argument is assumed to be the name of a file containing shell commands. If bash is invoked in this fashion, is set to the name of the file, and the positional parameters are set to the remaining arguments. bash reads and executes commands from this file, then exits. bash’s exit status is the exit status of the last command executed in the script.

DEFINITIONS

blank	A space or tab.
word	A sequence of characters considered as a single unit by the shell. Also known as a token.
name	A word consisting only of alphanumeric characters and underscores and beginning with an alphabetic character or an underscore. Also referred to as an identifier.
meta character	A character that, when unquoted, separates words. One of the following: , &, :, (,), <, >, space, tab
control operator	A token that performs a control function. It is one of the following symbols: , &, &&, :, ::, (,), , <newline>

RESERVED WORDS

Reserved words are words that have a special meaning to the shell. The following words are recognized as reserved when unquoted and either the first word of a simple command (see “Shell Grammar,” next) or the third word of a case or for command:

```
! case do done elif else esac fi for function if in select then until while { }
```

SHELL GRAMMAR

SIMPLE COMMANDS

A *simple command* is a sequence of optional variable assignments followed by words and redirections separated by blank and terminated by a control operator. The first word specifies the command to be executed. The remaining words are passed as arguments to the invoked command.

The return value of a simple command is its exit status, or 128+n if the command is terminated by signal n.

PIPELINES

A *pipeline* is a sequence of one or more commands separated by the character |. The format for a pipeline is

```
[!]command [ | command2 ... ]
```

The standard output of command is connected to the standard input of command2. This connection is performed before any redirections specified by the command. (See the “Redirection” section, later in this manual page.)

If the reserved word ! precedes a pipeline, the exit status of that pipeline is the logical NOT of the exit status of the last command. Otherwise, the status of the pipeline is the exit status of the last command. The shell waits for all commands in the pipeline to terminate before returning a value.

Each command in a pipeline is executed as a separate process (that is, in a subshell).

LISTS

A *list* is a sequence of one or more pipelines separated by one of these operators: ;, &, &&, or ||, and terminated by one of these: ;, &, or <newline>.

Of these list operators, && and || have equal precedence, followed by ; and &, which have equal precedence.

If a command is terminated by the control operator &, the shell executes the command in the background in a subshell. The shell does not wait for the command to finish, and the return status is 0. Commands separated by a ; are executed sequentially; the shell waits for each command to terminate in turn. The return status is the exit status of the last command executed.

The control operators && and || denote AND lists and OR lists, respectively. An AND list has the form:

```
command && command2
```

command2 is executed if, and only if, command returns an exit status of Zero.

An `OR` list has the form

```
command command2
```

`command2` is executed if, and only if, `command` returns a non-zero exit status. The return status of `AND` and `OR` lists is the exit status of the last command executed in the list.

COMPOUND COMMANDS

A *compound command* is one of the following:

```
(list)
```

`list` is executed in a subshell. Variable assignments and built-in commands that affect the shell's environment do not remain in effect after the command completes. The return status is the exit status of `list`.

```
{ list; }
```

`list` is simply executed in the current shell environment. This is known as a group command. The return status is the exit status of `list`.

```
for name [ in word;] do list ; done
```

The list of words following `in` is expanded, generating a list of items. The variable `name` is set to each element of this list in turn, and `list` is executed each time. If the `in` word is omitted, the `for` command executes `list` once for each positional parameter that is set. (See “Parameters,” later in this manual page.)

```
select name [ in word;] do list ; done
```

The list of words following `in` is expanded, generating a list of items. The set of expanded words is printed on the standard error, each preceded by a number. If the `in` word is omitted, the positional parameters are printed. (See “Parameters.”) The PS3 prompt is then displayed and a line read from the standard input. If the line consists of the number corresponding to one of the displayed words, then the value of `name` is set to that word. If the line is empty, the words and prompt are displayed again. If EOF is read, the command completes. Any other value read causes `name` to be set to null. The line read is saved in the variable `REPLY`. The list is executed after each selection until a `break` or `return` command is executed. The exit status of `select` is the exit status of the last command executed in `list`, or zero if no commands were executed.

```
case word in [ pattern [ | pattern ]
```

A `case` command first expands `word`, and tries to match it against each `pattern` in turn, using the same matching rules as for pathname expansion. (See “Pathname Expansion,” later in this manual page.) When a match is found, the corresponding list is executed. After the first match, no subsequent matches are attempted. The exit status is zero if no patterns are matches. Otherwise, it is the exit status of the last command executed in `list`.

```
if list then list [ elif list then list ] ... [ else list ] fi
```

The `if` list is executed. If its exit status is zero, the `then` list is executed. Otherwise, each `elif` list is executed in turn, and if its exit status is zero, the corresponding `then` list is executed and the command completes. Otherwise, the `else` list is executed, if present. The exit status is the exit status of the last command executed, or zero if no condition tested `True`.

```
while list do list done
```

```
until list do list done
```

The `while` command continuously executes the `do` list as long as the last command in `list` returns an exit status of zero. The `until` command is identical to the `while` command, except that the test is negated; the `do` list is executed as long as the last command in `list` returns a non-zero exit status. The exit status of the `while` and `until` commands is the exit status of the last `do` list command executed, or zero if none was executed.

```
[ function ] name () { list; }
```

This defines a function named *name*. The body of the function is the list of commands between `{` and `}`. This list is executed whenever *name* is specified as the name of a simple command. The exit status of a function is the exit status of the last command executed in the body. (See “Functions,” later in this manual page.)

COMMENTS

In a noninteractive shell, or an interactive shell in which the `-o interactive-comments` option to the `set` builtin is enabled, a word beginning with `#` causes that word and all remaining characters on that line to be ignored. An interactive shell without the `-o interactive-comments` option enabled does not allow comments.

QUOTING

Quoting is used to remove the special meaning of certain characters or words to the shell. Quoting can be used to disable special treatment for special characters, to prevent reserved words from being recognized as such, and to prevent parameter expansion.

Each of the meta characters listed earlier under “Definitions” has special meaning to the shell and must be quoted if it is to represent itself. There are three quoting mechanisms: the escape character, single quotes, and double quotes.

A nonquoted backslash (`\`) is the escape character. It preserves the literal value of the next character that follows, with the exception of `<newline>`. If a `\<newline>` pair appears, and the backslash is not quoted, the `\<newline>` is treated as a line continuation; that is, it is effectively ignored.

Enclosing characters in single quotes preserves the literal value of each character within the quotes. A single quote may not occur between single quotes, even when preceded by a backslash.

Enclosing characters in double quotes preserves the literal value of all characters within the quotes, with the exception of `$`, `'`, and `\`. The characters `$` and `'` retain their special meaning within double quotes. The backslash retains its special meaning only when followed by one of the following characters: `$`, `'`, `"`, `\`, or `<newline>`. A double quote may be quoted within double quotes by preceding it with a backslash.

The special parameters `*` and `@` have special meaning when in double quotes. (See “Parameters,” next.)

PARAMETERS

A *parameter* is an entity that stores values, somewhat like a variable in a conventional programming language. It can be a name, a number, or one of the special characters listed under “Special Parameters,” following. For the shell’s purposes, a variable is a parameter denoted by a name.

A parameter is set if it has been assigned a value. The null string is a valid value. Once a variable is set, it may be unset only by using the `unset` built-in command. (See “Shell Built-in Commands,” later in this manual page.)

A variable may be assigned to by a statement of the form:

```
name=[value]
```

If `value` is not given, the variable is assigned the null string. All values undergo tilde expansion, parameter and variable expansion, command substitution, arithmetic expansion, and quote removal. If the variable has its `-i` attribute set (see `declare` in “Shell Built-in Commands”) then `value` is subject to arithmetic expansion even if the `${...}` syntax does not appear. Word splitting is not performed, with the exception of `"$@"`, as explained under “Special Parameters.” Pathname expansion is not performed.

POSITIONAL PARAMETERS

A *positional parameter* is a parameter denoted by one or more digits, other than the single digit 0. Positional parameters are assigned from the shell’s arguments when it is invoked, and may be reassigned using the `set` built-in command. Positional parameters may not be assigned to with assignment statements. The positional parameters are temporarily replaced when a shell function is executed. (See “Functions,” later in this manual page.)

When a positional parameter consisting of more than a single digit is expanded, it must be enclosed in braces. (See “Expansion,” later in this manual page.)

SPECIAL PARAMETERS

The shell treats several parameters specially. These parameters may only be referenced; assignment to them is not allowed.

*	Expands to the positional parameters, starting from one. When the expansion occurs within double quotes, it expands to a single word with the value of each parameter separated by the first character of the IFS special variable. That is, "\$*" is equivalent to "\$1c\$2c...", where c is the first character of the value of the IFS variable. If IFS is null or unset, the parameters are separated by spaces.
@	Expands to the positional parameters, starting from one. When the expansion occurs within double quotes, each parameter expands as a separate word. That is, "\$@" is equivalent to "\$1"\$2" When there are no positional parameters, "\$@" and \$@ expand to nothing (in other words, they are removed).
#	Expands to the number of positional parameters in decimal.
?	Expands to the status of the most recently executed foreground pipeline.
-	Expands to the current option flags as specified upon invocation, by the set built-in command, or those set by the shell itself (such as the -i flag).
\$	Expands to the process ID of the shell. In a () subshell, it expands to the process ID of the current shell, not the subshell.
!	Expands to the process ID of the most recently executed background (asynchronous) command.
0	Expands to the name of the shell or shell script. This is set at shell initialization. If bash is invoked with a file of commands, is set to the name of that file. If bash is started with the -c option, then is set to the first argument after the string to be executed, if one is present. Otherwise, it is set to the pathname used to invoke bash, as given by argument zero.
_	Expands to the last argument to the previous command, after expansion. Also set to the full pathname of each command executed and placed in the environment exported to that command.

SHELL VARIABLES

The following variables are set by the shell:

PPID	The process ID of the shell's parent.
PWD	The current working directory as set by the cd command.
OLDPWD	The previous working directory as set by the cd command.
REPLY	Set to the line of input read by the read built-in command when no arguments are supplied.
UID	Expands to the user ID of the current user, initialized at shell startup.
EUID	Expands to the effective user ID of the current user, initialized at shell startup.
BASH	Expands to the full pathname used to invoke this instance of bash.
BASH_VERSION	Expands to the version number of this instance of bash.
SHLVL	Incremented by one each time an instance of bash is started.
RANDOM	Each time this parameter is referenced, a random integer is generated. The sequence of random numbers may be initialized by assigning a value to RANDOM. If RANDOM is unset, it loses its special properties, even if it is subsequently reset.
SECONDS	Each time this parameter is referenced, the number of seconds since shell invocation is returned. If a value is assigned to SECONDS, the value returned upon subsequent references is the number of seconds since the assignment plus the value assigned. If SECONDS is unset, it loses its special properties, even if it is subsequently reset.
LINENO	Each time this parameter is referenced, the shell substitutes a decimal number representing the current sequential line number (starting with 1) within a script or function. When not in a script or function, the value substituted is not guaranteed to be meaningful. When in a function, the value is not the number of the source line that the command appears on (that information has been lost by the time the function is executed), but is an approximation of the number of simple commands executed in the current function. If LINENO is unset, it loses its special properties, even if it is subsequently reset.

HISTCMD	The history number, or index in the history list, of the current command. If HISTCMD is unset, it loses its special properties, even if it is subsequently reset.
OPTARG	The value of the last option argument processed by the getopts built-in command. (See “Shell Built-in Commands,” later in this manual page).
OPTIND	The index of the next argument to be processed by the getopts built-in command. (See “Shell Built-in Commands.”)
HOSTTYPE	Automatically set to a string that uniquely describes the type of machine on which bash is executing. The default is system-dependent.
OSTYPE	Automatically set to a string that describes the operating system on which bash is executing. The default is system-dependent.

The following variables are used by the shell. In some cases, bash assigns a default value to a variable; these cases are noted in the following list:

IFS	The internal field separator that is used for word splitting after expansion and to split lines into words with the read built-in command. The default value is <space><tab><newline>.
PATH	The search path for commands. It is a colon-separated list of directories in which the shell looks for commands. (See “Command Execution,” later in this manual page). The default path is system-dependent, and is set by the administrator who installs bash. A common value is /usr/gnu/bin:/usr/local/bin:/usr/ucb/bin:/usr/bin:.
HOME	The home directory of the current user; the default argument for the cd built-in command.
CDPATH	The search path for the cd command. This is a colon-separated list of directories in which the shell looks for destination directories specified by the cd command. A sample value is .:~/usr.
ENV	If this parameter is set when bash is executing a shell script, its value is interpreted as a filename containing commands to initialize the shell, as in .bashrc. The value of ENV is subjected to parameter expansion, command substitution, and arithmetic expansion before being interpreted as a pathname. PATH is not used to search for the resultant pathname.
MAIL	If this parameter is set to a filename and the MAILPATH variable is not set, bash informs the user of the arrival of mail in the specified file.
MAILCHECK	Specifies how often (in seconds) bash checks for mail. The default is 60 seconds. When it is time to check for mail, the shell does so before prompting. If this variable is unset, the shell disables mail checking.
MAILPATH	A colon-separated list of pathnames to be checked for mail. The message to be printed may be specified by separating the pathname from the message with a question mark (?). \$_ stands for the name of the current mailfile. Example: MAILPATH\ =' /usr/spool/mail/bfox?' "You have mail":~/shell-mail?"\$_has mail!"
	bash supplies a default value for this variable, but the location of the user mail files that it uses is system-dependent (for example, /usr/spool/mail/\$USER).
MAIL_WARNING	If set, and a file that bash is checking for mail has been accessed since the last time it was checked, the message “The mail in mail-file has been read” is printed.
PS1	The value of this parameter is expanded (see “Prompting,” later in this manual page) and used as the primary prompt string. The default value is bash\$.
PS2	The value of this parameter is expanded and used as the secondary prompt string. The default is >.

PS3	The value of this parameter is used as the prompt for the <code>select</code> command. (See “Shell Grammar,” earlier in this manual page.)
PS4	The value of this parameter is expanded and the value is printed before each command <code>bash</code> displays during an execution trace. The first character of <code>PS4</code> is replicated multiple times, as necessary, to indicate multiple levels of indirection. The default is <code>+</code> .
HISTSIZE	The number of commands to remember in the command history, (See “History,” later in this manual page.) The default value is <code>500</code> .
HISTFILE	The name of the file in which command history is saved. (See “History.”) The default value is <code>~/.bash_history</code> . If unset, the command history is not saved when an interactive shell exits.
HISTFILESIZE	The maximum number of lines contained in the history file. When this variable is assigned a value, the history file is truncated, if necessary, to contain no more than that number of lines. The default value is <code>500</code> .
OPTERR	If set to the value <code>1</code> , <code>bash</code> displays error messages generated by the <code>getopts</code> built-in command. (See “Shell Built-in Commands.”) <code>OPTERR</code> is initialized to <code>1</code> each time the shell is invoked or a shell script is executed.
PROMPT_COMMAND	If set, the value is executed as a command prior to issuing each primary prompt.
IGNOREEOF	Controls the action of the shell on receipt of an EOF character as the sole input. If set, the value is the number of consecutive EOF characters typed as the first characters on an input line before <code>bash</code> exits. If the variable exists but does not have a numeric value, or has no value, the default value is <code>10</code> . If it does not exist, EOF signifies the end of input to the shell. This is only in effect for interactive shells.
TMOUT	If set to a value greater than zero, the value is interpreted as the number of seconds to wait for input after issuing the primary prompt. <code>bash</code> terminates after waiting for that number of seconds if input does not arrive.
FCEDIT	The default editor for the <code>fc</code> built-in command.
FIGNORE	A colon-separated list of suffixes to ignore when performing filename completion. (See “Readline,” later in this manual page.) A filename whose suffix matches one of the entries in <code>FIGNORE</code> is excluded from the list of matched filenames. A sample value is <code>.o:~</code> .
INPUTRC	The filename for the <code>readline</code> startup file, overriding the default of <code>~/.inputrc</code> . (See “Readline.”)
notify	If set, <code>bash</code> reports terminated background jobs immediately, rather than waiting until before printing the next primary prompt. (See also the <code>-b</code> option to the <code>set</code> built-in command.)
history_control HISTCONTROL	If set to a value of <code>ignorespace</code> , lines that begin with a space character are not entered on the history list. If set to a value of <code>ignoredups</code> , lines matching the last history line are not entered. A value of <code>ignoreboth</code> combines the two options. If unset, or if set to any other value than the preceding, all lines read by the parser are saved on the history list.
command_oriented_history	If set, <code>bash</code> attempts to save all lines of a multiple-line command in the same history entry. This allows easy reediting of multiline commands.
glob_dot_filenames	If set, <code>bash</code> includes filenames beginning with a period (<code>.</code>) in the results of pathname expansion.
allow-null_glob_expansion	If set, <code>bash</code> allows pathname patterns which match no files (see “Pathname Expansion”) to expand to a null string, rather than themselves.
histchars	The two or three characters that control history expansion and tokenization. (See “History Expansion,” later in this manual page.) The first character is the history expansion character; that is, the character that signals the start of a history expansion,

	normally <code>!</code> . The second character is the quick substitution character, which is used as shorthand for rerunning the previous command entered, substituting one string for another in the command. The default is <code>^</code> . The optional third character is the character that signifies that the remainder of the line is a comment, when found as the first character of a word, normally <code>#</code> . The history comment character causes history substitution to be skipped for the remaining words on the line. It does not necessarily cause the shell parser to treat the rest of the line as a comment.
<code>nolinks</code>	If set, the shell does not follow symbolic links when executing commands that change the current working directory. It uses the physical directory structure instead. By default, <code>bash</code> follows the logical chain of directories when performing commands that change the current directory, such as <code>cd</code> . See also the description of the <code>-P</code> option to the <code>set</code> builtin (“Shell Built-in Commands”).
<code>hostname_completion_file</code> <code>HOSTFILE</code>	Contains the name of a file in the same format as <code>/etc/hosts</code> that should be read when the shell needs to complete a hostname. The file may be changed interactively; the next time hostname completion is attempted <code>bash</code> adds the contents of the new file to the already existing database.
<code>noclobber</code>	If set, <code>bash</code> does not overwrite an existing file with the <code>></code> , <code>>&</code> , and <code><></code> redirection operators. This variable may be overridden when creating output files by using the redirection operator <code>> </code> instead of <code>></code> . (See also the <code>-c</code> option to the <code>set</code> built-in command.)
<code>auto_resume</code>	This variable controls how the shell interacts with the user and job control. If this variable is set, single word simple commands without redirections are treated as candidates for resumption of an existing stopped job. There is no ambiguity allowed; if there is more than one job beginning with the string typed, the job most recently accessed is selected. The name of a stopped job, in this context, is the command line used to start it. If set to the value <code>exact</code> , the string supplied must match the name of a stopped job exactly; if set to <code>substring</code> , the string supplied needs to match a substring of the name of a stopped job. The <code>substring</code> value provides functionality analogous to the <code>%?</code> job ID. (See “Job Control,” later in this manual page.) If set to any other value, the supplied string must be a prefix of a stopped job’s name; this provides functionality analogous to the <code>%</code> job id.
<code>no_exit_on_failed_exec</code>	If this variable exists, a noninteractive shell will not exit if it cannot execute the file specified in the <code>exec</code> built-in command. An interactive shell does not exit if <code>exec</code> fails.
<code>cdable_vars</code>	If this is set, an argument to the <code>cd</code> built-in command that is not a directory is assumed to be the name of a variable whose value is the directory to change to.

EXPANSION

Expansion is performed on the command line after it has been split into words. There are seven kinds of expansion performed: brace expansion, tilde expansion, parameter and variable expansion, command substitution, arithmetic expansion, word splitting, and pathname expansion.

The order of expansions is as follows: brace expansion, tilde expansion, parameter, variable, command, and arithmetic substitution (done in a left-to-right fashion), word splitting, and pathname expansion.

On systems that can support it, there is an additional expansion available: process substitution.

Only brace expansion, word splitting, and pathname expansion can change the number of words of the expansion; other expansions expand a single word to a single word. The single exception to this is the expansion of ``${}`, as explained earlier. (See “Parameters.”)

BRACE EXPANSION

Brace expansion is a mechanism by which arbitrary strings may be generated. This mechanism is similar to pathname expansion, but the filenames generated need not exist. Patterns to be brace expanded take the form of an optional preamble, followed by a series of comma-separated strings between a pair of braces, followed by an optional postamble. The preamble is prepended to each string contained within the braces, and the postamble is then appended to each resulting string, expanding left to right.

Brace expansions may be nested. The results of each expanded string are not sorted; left to right order is preserved. For example, `a{d,c,b}e` expands into `ade ace abe`.

Brace expansion is performed before any other expansions, and any characters special to other expansions are preserved in the result. It is strictly textual. `bash` does not apply any syntactic interpretation to the context of the expansion or the text between the braces.

A correctly formed brace expansion must contain unquoted opening and closing braces, and at least one unquoted comma. Any incorrectly formed brace expansion is left unchanged.

This construct is typically used as shorthand when the common prefix of the strings to be generated is longer than in the preceding example, such as

```
mkdir /usr/local/src/bash/{old,new,dist,bugs}
```

or

```
chown root /usr/{ucb/{ex,edit},lib/{ex.?.*,how_ex}}
```

Brace expansion introduces a slight incompatibility with traditional versions of `sh`, the Bourne shell. `sh` does not treat opening or closing braces specially when they appear as part of a word, and preserves them in the output. `bash` removes braces from words as a consequence of brace expansion. For example, a word entered to `sh` as `file{1,2}` appears identically in the output. The same word is output as `file1 file2` after expansion by `bash`. If strict compatibility with `sh` is desired, start `bash` with the `-nbraceexpansion` flag (see “Options,” earlier in this manual page) or disable brace expansion with the `+o braceexpand` option to the `set` command. (See “Shell Built-in Commands.”)

TILDE EXPANSION

If a word begins with a tilde character (`~`), all of the characters preceding the first slash (or all characters, if there is no slash) are treated as a possible login name. If this login name is the null string, the tilde is replaced with the value of the parameter `HOME`. If `HOME` is unset, the home directory of the user executing the shell is substituted instead.

If a `+` follows the tilde, the value of `PWD` replaces the tilde and `+`. If a `-` follows, the value of `OLDPWD` is substituted. If the value following the tilde is a valid login name, the tilde and login name are replaced with the home directory associated with that name. If the name is invalid, or the tilde expansion fails, the word is unchanged.

Each variable assignment is checked for unquoted instances of tildes following a `:` or `=`. In these cases, tilde substitution is also performed. Consequently, one may use pathnames with tildes in assignments to `PATH`, `MAILPATH`, and `CDPATH`, and the shell assigns the expanded value.

PARAMETER EXPANSION

The `$` character introduces parameter expansion, command substitution, or arithmetic expansion. The parameter name or symbol to be expanded may be enclosed in braces, which are optional but serve to protect the variable to be expanded from characters immediately following it which could be interpreted as part of the name.

`${parameter}` The value of `parameter` is substituted. The braces are required when `parameter` is a positional parameter with more than one digit, or when `parameter` is followed by a character that is not to be interpreted as part of its name.

In each of the following cases, `word` is subject to tilde expansion, parameter expansion, command substitution, and arithmetic expansion. `bash` tests for a parameter that is unset or null; omitting the colon results in a test only for a parameter that is unset.

<code>\${parameter:-word}</code>	Use default values. If <code>parameter</code> is unset or null, the expansion of <code>word</code> is substituted. Otherwise, the value of <code>parameter</code> is substituted.
<code>\${parameter:=word}</code>	Assign default values. If <code>parameter</code> is unset or null, the expansion of <code>word</code> is assigned to <code>parameter</code> . The value of <code>parameter</code> is then substituted. Positional parameters and special parameters may not be assigned to in this way.
<code>\${parameter:?word}</code>	Display Error if null or unset. If <code>parameter</code> is null or unset, the expansion of <code>word</code> (or a message to that effect if <code>word</code> is not present) is written to the standard error and the shell, if it is not interactive, exits. Otherwise, the value of <code>parameter</code> is substituted.
<code>\${parameter:+word}</code>	Use Alternate Value. If <code>parameter</code> is null or unset, nothing is substituted; otherwise, the expansion of <code>word</code> is substituted.
<code>\${#parameter}</code>	The length in characters of the value of <code>parameter</code> is substituted. If <code>parameter</code> is <code>*</code> or <code>@</code> , the length substituted is the length of <code>*</code> expanded within double quotes.
<code>\${parameter#word}</code> <code>\${parameter##word}</code>	The <code>word</code> is expanded to produce a pattern just as in pathname expansion. If the pattern matches the beginning of the value of <code>parameter</code> , then the expansion is the value of <code>parameter</code> with the shortest matching pattern deleted (the <code>#</code> case) or the longest matching pattern deleted (the <code>##</code> case).
<code>\${parameter%word}</code> <code>\${parameter%%word}</code>	The <code>word</code> is expanded to produce a pattern just as in pathname expansion. If the pattern matches a trailing portion of the value of <code>parameter</code> , then the expansion is the value of <code>parameter</code> with the shortest matching pattern deleted (the <code>%</code> case) or the longest matching pattern deleted (the <code>%%</code> case).

COMMAND SUBSTITUTION

Command substitution allows the output of a command to replace the command name.

There are two forms:

`$(command )`

or

`'command'`

performs the expansion by executing `command` and replacing the command substitution with the standard output of the command, with any trailing newlines deleted.

When the old-style backquote form of substitution is used, backslash retains its literal meaning except when followed by `$`, `'`, or `\`. When using the `$(command)` form, all characters between the parentheses make up the command; none are treated specially.

Command substitutions may be nested. To nest when using the old form, escape the inner backquotes with backslashes.

If the substitution appears within double quotes, word splitting and pathname expansion are not performed on the results.

ARITHMETIC EXPANSION

Arithmetic expansion allows the evaluation of an arithmetic expression and the substitution of the result. There are two formats for arithmetic expansion:

`${expression}`
`$((expression))`

The expression is treated as if it were within double quotes, but a double quote inside the braces or parentheses is not treated specially. All tokens in the expression undergo parameter expansion, command substitution, and quote removal. Arithmetic substitutions may be nested.

The evaluation is performed according to the rules listed under “Arithmetic Evaluation,” later in this section. If `expression` is invalid, bash prints a message indicating failure and no substitution occurs.

PROCESS SUBSTITUTION

Process substitution is supported on systems that support named pipes (FIFOs) or the `/dev/fd` method of naming open files. It takes the form of `<(list)` or `>(list)`. The process list is run with its input or output connected to a FIFO or some file in /

`dev/fd`. The name of this file is passed as an argument to the current command as the result of the expansion. If the `>(list)` form is used, writing to the file will provide input for `list`. If the `<(list)` form is used, the file passed as an argument should be read to obtain the output of `list`.

On systems that support it, process substitution is performed simultaneously with parameter and variable expansion, command substitution, and arithmetic expansion.

WORD SPLITTING

The shell scans the results of parameter expansion, command substitution, and arithmetic expansion that did not occur within double quotes for word splitting.

The shell treats each character of `IFS` as a delimiter, and splits the results of the other expansions into words on these characters. If the value of `IFS` is exactly `<space><tab><newline>`, the default, then any sequence of `IFS` characters serves to delimit words. If `IFS` has a value other than the default, then sequences of the whitespace characters `space` and `tab` are ignored at the beginning and end of the word, as long as the whitespace character is in the value of `IFS` (an `IFS` whitespace character). Any character in `IFS` that is not `IFS` whitespace, along with any adjacent `IFS` whitespace characters, delimits a field. A sequence of `IFS` whitespace characters is also treated as a delimiter. If the value of `IFS` is null, no word splitting occurs. `IFS` cannot be unset.

Explicit null arguments (`" "` or `' '`) are retained. Implicit null arguments, resulting from the expansion of parameters that have no values, are removed.

Note that if no expansion occurs, no splitting is performed.

PATHNAME EXPANSION

After word splitting, unless the `-f` option has been set, `bash` scans each word for the characters `*`, `?`, and `[`. If one of these characters appears, then the word is regarded as a pattern and replaced with an alphabetically sorted list of pathnames matching the pattern. If no matching pathnames are found, and the shell variable `allow_null_glob_expansion` is unset, the word is left unchanged. If the variable is set, and no matches are found, the word is removed. When a pattern is used for pathname generation, the character `(.)` at the start of a name or immediately following a slash must be matched explicitly, unless the shell variable `glob_dot_filenames` is set. The slash character must always be matched explicitly. In other cases, the `(.)` character is not treated specially.

The special pattern characters have the following meanings:

- `*` Matches any string, including the null string.
- `?` Matches any single character.
- `[...]` Matches any one of the enclosed characters. A pair of characters separated by a minus sign denotes a range; any character lexically between those two characters, inclusive, is matched. If the first character following the `[` is a `!` or a `^`, then any character not enclosed is matched. A `-` or `]` may be matched by including it as the first or last character in the set.

QUOTE REMOVAL

After the preceding expansions, all unquoted occurrences of the characters `\`, `'`, and `"` are removed.

REDIRECTION

Before a command is executed, its input and output may be redirected using a special notation interpreted by the shell. Redirection may also be used to open and close files for the current shell execution environment. The following redirection operators may precede or appear anywhere within a simple command or may follow a command. Redirections are processed in the order they appear, from left to right.

In the following descriptions, if the file descriptor number is omitted, and the first character of the redirection operator is `<`, the redirection refers to the standard input (file descriptor `0`). If the first character of the redirection operator is `>`, the redirection refers to the standard output (file descriptor `1`).

The word that follows the redirection operator in the following descriptions is subjected to brace expansion, tilde expansion, parameter expansion, command substitution, arithmetic expansion, quote removal, and pathname expansion. If it expands to more than one word, `bash` reports an error.

Note that the order of redirections is significant. For example, the command:

```
ls > dirlist 2>&1
```

directs both standard output and standard error to the file `dirlist`, while the command

```
ls 2>&1 > dirlist
```

directs only the standard output to file `dirlist`, because the standard error was duplicated as standard output before the standard output was redirected to `dirlist`.

REDIRECTING INPUT

Redirection of input causes the file whose name results from the expansion of word to be opened for reading on file descriptor `n`, or the standard input (file descriptor `0`) if `n` is not specified.

The general format for redirecting input is

```
[n]<word
```

REDIRECTING OUTPUT

Redirection of output causes the file whose name results from the expansion of word to be opened for writing on file descriptor `n`, or the standard output (file descriptor `1`) if `n` is not specified. If the file does not exist, it is created; if it does exist it is truncated to zero size.

The general format for redirecting output is

```
[n]>word
```

If the redirection operator is `>|`, then the value of the `-c` option to the `set` built-in command is not tested, and file creation is attempted. (See also the description of `noclobber` under “Shell Variables,” earlier in this manual page.)

APPENDING REDIRECTED OUTPUT

Redirection of output in this fashion causes the file whose name results from the expansion of word to be opened for appending on file descriptor `n`, or the standard output (file descriptor `1`) if `n` is not specified. If the file does not exist, it is created.

The general format for appending output is

```
[n]>>word
```

REDIRECTING STANDARD OUTPUT AND STANDARD ERROR

`bash` allows both the standard output (file descriptor `1`) and the standard error output (file descriptor `2`) to be redirected to the file whose name is the expansion of word with this construct.

There are two formats for redirecting standard output and standard error:

```
&>word
```

and

```
>&word
```

Of the two forms, the first is preferred. This is semantically equivalent to

```
>word 2>&1
```

HERE-DOCUMENTS

This type of redirection instructs the shell to read input from the current source until a line containing only word (with no trailing blanks) is seen. All of the lines read up to that point are then used as the standard input for a command.

The format of here-documents is as follows:

```
<<[-]word here-document delimiter
```

No parameter expansion, command substitution, pathname expansion, or arithmetic expansion is performed on `word`. If any characters in `word` are quoted, the `delimiter` is the result of quote removal on `word`, and the lines in the here-document are not expanded. Otherwise, all lines of the here-document are subjected to parameter expansion, command substitution, and arithmetic expansion. In the latter case, the pair `\<newline>` is ignored, and `\` must be used to quote the characters `\`, `$`, and `'`.

If the redirection operator is `<<-`, then all leading tab characters are stripped from input lines and the line containing delimiter. This allows here-documents within shell scripts to be indented in a natural fashion.

DUPLICATING FILE DESCRIPTORS

The redirection operator:

```
[n]<&word
```

is used to duplicate input file descriptors. If `word` expands to one or more digits, the file descriptor denoted by `n` is made to be a copy of that file descriptor. If `word` evaluates to `-`, file descriptor `n` is closed. If `n` is not specified, the standard input (file descriptor `0`) is used.

The operator:

```
[n]>&word
```

is used similarly to duplicate output file descriptors. If `n` is not specified, the standard output (file descriptor `1`) is used. As a special case, if `n` is omitted, and `word` does not expand to one or more digits, the standard output and standard error are redirected as described previously.

OPENING FILE DESCRIPTORS FOR READING AND WRITING

The redirection operator:

```
[n]<>word
```

causes the file whose name is the expansion of `word` to be opened for both reading and writing on file descriptor `n`, or as the standard input and standard output if `n` is not specified. If the file does not exist, it is created.

FUNCTIONS

A shell function, defined as described above under “Shell Grammar,” stores a series of commands for later execution. Functions are executed in the context of the current shell; no new process is created to interpret them (contrast this with the execution of a shell script). When a function is executed, the arguments to the function become the positional parameters during its execution. The special parameter `#` is updated to reflect the change. Positional parameter `0` is unchanged.

Variables local to the function may be declared with the `local` built-in command. Ordinarily, variables and their values are shared between the function and its caller.

If the built-in command `return` is executed in a function, the function completes and execution resumes with the next command after the function call. When a function completes, the values of the positional parameters and the special parameter `#` are restored to the values they had prior to function execution.

Function names may be listed with the `-f` option to the `declare` or `typeset` built-in commands. Functions may be exported so that subshells automatically have them defined with the `-f` option to the `export` builtin.

Functions may be recursive. No limit is imposed on the number of recursive calls.

ALIASES

The shell maintains a list of aliases that may be set and unset with the `alias` and `unalias` built-in commands. (See “Shell Built-in Commands.”) The first word of each command, if unquoted, is checked to see if it has an alias. If so, that word is replaced by the text of the alias. The alias name and the replacement text may contain any valid shell input, including the meta characters listed above, with the exception that the alias name may not contain `=`. The first word of the replacement text

is tested for aliases, but a word that is identical to an alias being expanded is not expanded a second time. This means that one may alias `ls` to `ls -F`, for instance, and `bash` does not try to recursively expand the replacement text. If the last character of the alias value is a blank, then the next command word following the alias is also checked for alias expansion.

Aliases are created and listed with the `alias` command, and removed with the `unalias` command.

There is no mechanism for using arguments in the replacement text, as in `csh`. If arguments are needed, a shell function should be used.

Aliases are not expanded when the shell is not interactive.

The rules concerning the definition and use of aliases are somewhat confusing. `bash` always reads at least one complete line of input before executing any of the commands on that line. Aliases are expanded when a command is read, not when it is executed. Therefore, an alias definition appearing on the same line as another command does not take effect until the next line of input is read. This means that the commands following the alias definition on that line are not affected by the new alias. This behavior is also an issue when functions are executed. Aliases are expanded when the function definition is read, not when the function is executed, because a function definition is itself a compound command. As a consequence, aliases defined in a function are not available until after that function is executed. To be safe, always put alias definitions on a separate line, and do not use alias in compound commands.

Note that for almost every purpose, aliases are superseded by shell functions.

JOB CONTROL

Job control refers to the ability to selectively stop (suspend) the execution of processes and continue (resume) their execution at a later point. A user typically employs this facility via an interactive interface supplied jointly by the system's terminal driver and `bash`.

The shell associates a job with each pipeline. It keeps a table of currently executing jobs, which may be listed with the `jobs` command. When `bash` starts a job asynchronously (in the background), it prints a line that looks like this:

```
[1] 25647
```

indicating that this job is job number 1 and that the process ID of the last process in the pipeline associated with this job is 25647. All of the processes in a single pipeline are members of the same job. `bash` uses the job abstraction as the basis for job control.

To facilitate the implementation of the user interface to job control, the system maintains the notion of a current terminal process group ID. Members of this process group (processes whose process group ID is equal to the current terminal process group ID) receive keyboard-generated signals such as `SIGINT`. These processes are said to be in the foreground. Background processes are those whose process group ID differs from the terminal's; such processes are immune to keyboard-generated signals. Only foreground processes are allowed to read from or write to the terminal. Background processes that attempt to read from (write to) the terminal are sent a `SIGTTIN` (`SIGTTOU`) signal by the terminal driver, which, unless caught, suspends the process.

If the operating system on which `bash` is running supports job control, `bash` allows you to use it. Typing the suspend character (typically `^Z`, `Control-Z`) while a process is running causes that process to be stopped and returns you to `bash`. Typing the delayed suspend character (typically `^Y`, `Control-Y`) causes the process to be stopped when it attempts to read input from the terminal, and control to be returned to `bash`. You may then manipulate the state of this job, using the `bg` command to continue it in the background, the `fg` command to continue it in the foreground, or the `kill` command to kill it. A `Ctrl+Z` takes effect immediately, and has the additional side effect of causing pending output and typeahead to be discarded.

There are a number of ways to refer to a job in the shell. The character `%` introduces a job name. Job number `n` may be referred to as `%n`. A job may also be referred to using a prefix of the name used to start it, or using a substring that appears in its command line. For example, `%ce` refers to a stopped `ce` job. If a prefix matches more than one job, `bash` reports an error. Using `%?ce`, on the other hand, refers to any job containing the string `ce` in its command line. If the substring matches more than one job, `bash` reports an error. The symbols `%` and `%+` refer to the shell's notion of the current job, which is the last job

stopped while it was in the foreground. The previous job may be referenced using `%-.` In output pertaining to jobs (for example, the output of the `jobs` command), the current job is always flagged with a `+`, and the previous job with a `-`.

Simply naming a job can be used to bring it into the foreground: `%1` is a synonym for `fg %1`, bringing job 1 from the background into the foreground. Similarly, `%1 &` resumes job 1 in the background, equivalent to `bg %1`.

The shell learns immediately whenever a job changes state. Normally, `bash` waits until it is about to print a prompt before reporting changes in a job's status so as to not interrupt any other output. If the `-b` option to the `set` built-in command is set, `bash` reports such changes immediately. (See also the description of the `notify` variable in “Shell Variables,” earlier in this manual page.)

If you attempt to exit `bash` while jobs are stopped, the shell prints a message warning you. You may then use the `jobs` command to inspect their status. If you do this, or try to exit again immediately, you are not warned again, and the stopped jobs are terminated.

SIGNALS

When `bash` is interactive, it ignores `SIGTERM` (so that `kill 0` does not kill an interactive shell), and `SIGINT` is caught and handled (so that the `wait` built-in is interruptible). In all cases, `bash` ignores `SIGQUIT`. If job control is in effect, `bash` ignores `SIGTTIN`, `SIGTTOU`, and `SIGTSTP`.

Synchronous jobs started by `bash` have signals set to the values inherited by the shell from its parent. When job control is not in effect, background jobs (jobs started with `&`) ignore `SIGINT` and `SIGQUIT`. Commands run as a result of command substitution ignore the keyboard-generated job control signals `SIGTTIN`, `SIGTTOU`, and `SIGTSTP`.

COMMAND EXECUTION

After a command has been split into words, if it results in a simple command and an optional list of arguments, the following actions are taken.

If the command name contains no slashes, the shell attempts to locate it. If there exists a shell function by that name, that function is invoked as described earlier in “Functions.” If the name does not match a function, the shell searches for it in the list of shell builtins. If a match is found, that builtin is invoked.

If the name is neither a shell function nor a builtin, and contains no slashes, `bash` searches each element of the `PATH` for a directory containing an executable file by that name. If the search is unsuccessful, the shell prints an error message and returns a nonzero exit status.

If the search is successful, or if the command name contains one or more slashes, the shell executes the named program. Argument `0` is set to the name given, and the remaining arguments to the command are set to the arguments given, if any.

If this execution fails because the file is not in executable format, and the file is not a directory, it is assumed to be a shell script, a file containing shell commands. A subshell is spawned to execute it. This subshell reinitializes itself, so that the effect is as if a new shell had been invoked to handle the script, with the exception that the locations of commands remembered by the parent (see `hash` under “Shell Built-in Commands”) are retained by the child.

If the program is a file beginning with `#!`, the remainder of the first line specifies an interpreter for the program. The shell executes the specified interpreter on operating systems that do not handle this executable format themselves. The arguments to the interpreter consist of a single optional argument following the interpreter name on the first line of the program, followed by the name of the program, followed by the command arguments, if any.

ENVIRONMENT

When a program is invoked, it is given an array of strings called the environment. This is a list of name/value pairs, of the form `name=value`.

The shell allows you to manipulate the environment in several ways. On invocation, the shell scans its own environment and creates a parameter for each name found, automatically marking it for export to child processes. Executed commands inherit the environment. The export and declare `-x` commands allow parameters and functions to be added to and deleted from the environment. If the value of a parameter in the environment is modified, the new value becomes part of the environment,

replacing the old. The environment inherited by any executed command consists of the shell's initial environment, whose values may be modified in the shell, less any pairs removed by the `unset` command, plus any additions via the `export` and `declare -x` commands.

The environment for any simple command or function may be augmented temporarily by prefixing it with parameter assignments, as described earlier in “Parameters.” These assignment statements affect only the environment seen by that command.

If the `-k` flag is set (see the `set` built-in command), then all parameter assignments are placed in the environment for a command, not just those that precede the command name.

When `bash` invokes an external command, the variable is set to the full path name of the command and passed to that command in its environment.

EXIT STATUS

For the purposes of the shell, a command which exits with a zero exit status has succeeded. An exit status of zero indicates success. A non-zero exit status indicates failure. When a command terminates on a fatal signal, `bash` uses the value of `128+signal` as the exit status.

If a command is not found, the child process created to execute it returns a status of 127. If a command is found but is not executable, the return status is 126.

`bash` itself returns the exit status of the last command executed, unless a syntax error occurs, in which case it exits with a non-zero value. (See also the `exit` built-in command.)

PROMPTING

When executing interactively, `bash` displays the primary prompt `PS1` when it is ready to read a command, and the secondary prompt `PS2` when it needs more input to complete a command. `bash` allows these prompt strings to be customized by inserting a number of backslash-escaped special characters that are decoded as follows:

<code>\t</code>	The current time in <code>HH:MM:SS</code> format
<code>\d</code>	The date in “Weekday Month Date” format (for example, “Tue May 26”)
<code>\n</code>	Newline
<code>\s</code>	The name of the shell, the basename of <code>\$0</code> (the portion following the final slash)
<code>\w</code>	The current working directory
<code>\W</code>	The basename of the current working directory
<code>\u</code>	The username of the current user
<code>\h</code>	The hostname
<code>\#</code>	The command number of this command
<code>!\</code>	The history number of this command
<code>\\$</code>	If the effective UID is 0, a #, otherwise a \$
<code>\nnn</code>	The character corresponding to the octal number <code>nnn</code>
<code>\\</code>	A backslash
<code>\[</code>	Begin a sequence of nonprinting characters, which could be used to embed a terminal control sequence into the prompt
<code>\]</code>	End a sequence of nonprinting characters

The command number and the history number are usually different: the history number of a command is its position in the history list, which may include commands restored from the history file (see “History,” later in this manual page), while the command number is the position in the sequence of commands executed during the current shell session. After the string is decoded, it is expanded via parameter expansion, command substitution, arithmetic expansion, and word splitting.

READLINE

This is the library that handles reading input when using an interactive shell, unless the `-noediting` option is given. By default, the line editing commands are similar to those of `emacs`. A `vi`-style line editing interface is also available.

In this section, the `emacs`-style notation is used to denote keystrokes. Control keys are denoted by `C-key`; for example, `C-n` means `Ctrl-N`. Similarly, meta keys are denoted by `M-key`, so `M-x` means `Meta-x`. (On keyboards without a meta key, `M-x` means `Esc-X`; that is, press the Escape key, then the `X` key. This makes `ESC` the meta prefix. The combination `M-C-x` means `Esc-Control-x`, or press the Escape key then hold the Control key while pressing the `X` key.)

The default key-bindings may be changed with a `/.inputrc` file. The value of the shell variable `INPUTRC`, if set, is used instead of `/.inputrc`. Other programs that use this library may add their own commands and bindings.

For example, placing

```
M-Control-u: universal-argument
```

or

```
C-Meta-u: universal-argument
```

into the `/.inputrc` would make `M-C-u` execute the `readline` command `universal-argument`. The following symbolic character names are recognized: `RUBOUT`, `DEL`, `ESC`, `LFD`, `NEWLINE`, `RET`, `RETURN`, `SPC`, `SPACE`, and `TAB`. In addition to command names, `readline` allows keys to be bound to a string that is inserted when the key is pressed (a macro).

`Readline` is customized by putting commands in an initialization file. The name of this file is taken from the value of the `INPUTRC` variable. If that variable is unset, the default is `/.inputrc`. When a program that uses the `readline` library starts up, the `init` file is read, and the key bindings and variables are set. There are only a few basic constructs allowed in the `readline` `init` file. Blank lines are ignored. Lines beginning with a `#` are comments. Lines beginning with a `$` indicate conditional constructs. Other lines denote key bindings and variable settings.

The syntax for controlling key bindings in the `/.inputrc` file is simple. All that is required is the name of the command or the text of a macro and a key sequence to which it should be bound. The name may be specified in one of two ways: as a symbolic key name, possibly with `Meta-` or `Control-` prefixes, or as a key sequence. When using the form `keyname: function-name` or `macro`, `keyname` is the name of a key spelled out in English. For example,

```
Control-u: universal-argument
Meta-Rubout: backward-kill-word
Control-o: ">&output"
```

In the preceding example, `C-u` is bound to the function `universal-argument`, `M-DEL` is bound to the function `backward-kill-word`, and `C-o` is bound to run the macro expressed on the righthand side (that is, to insert the text `>&output` into the line).

In the second form, "`keyseq`": `function-name` or `macro`, `keyseq` differs from `keyname` in that strings denoting an entire key sequence may be specified by placing the sequence within double quotes. Some GNU `emacs`-style key escapes can be used, as in the following example:

```
"\C-u": universal-argument
"\C-x\C-r": re-read-init-file
"\e[11~": "Function Key 1"
```

In this example, `C-u` is again bound to the function `universal-argument`. `C-x C-r` is bound to the function `re-read-init-file`, and `ESC[11~` is bound to insert the text `Function Key 1`. The full set of escape sequences is

<code>\C-</code>	Control prefix
<code>\M-</code>	Meta prefix
<code>\e</code>	An escape character
<code>\\</code>	Backslash
<code>\"</code>	Literal "
<code>\'</code>	Literal '

When entering the text of a macro, single or double quotes should be used to indicate a macro definition. Unquoted text is assumed to be a function name. Backslash will quote any character in the macro text, including " and '.

bash allows the current readline key bindings to be displayed or modified with the `bind` built-in command. The editing mode may be switched during interactive use by using the `-o` option to the `set` built-in command. (See “Shell Built-in Commands.”)

Readline has variables that can be used to further customize its behavior. A variable may be set in the `inputrc` file with a statement of the form:

```
set variable-name value
```

Except where noted, readline variables can take the values `on` or `off`. The variables and their default values are as follows:

<code>horizontal-scroll-mode</code> (Off)	When set to <code>on</code> , makes readline use a single line for display, scrolling the input horizontally on a single screen line when it becomes longer than the screen width rather than wrapping to a new line.
<code>editing-mode</code> (emacs)	Controls whether readline begins with a set of key bindings similar to <code>emacs</code> or <code>vi</code> . <code>editing-mode</code> can be set to either <code>emacs</code> or <code>vi</code> .
<code>mark-modified-lines</code> (Off)	If set to <code>on</code> , history lines that have been modified are displayed with a preceding asterisk (*).
<code>bell-style</code> (audible)	Controls what happens when readline wants to ring the terminal bell. If set to <code>none</code> , readline never rings the bell. If set to <code>visible</code> , readline uses a visible bell if one is available. If set to <code>audible</code> , readline attempts to ring the terminal's bell.
<code>comment-begin</code> ("#")	The string that is inserted in <code>vi</code> mode when the <code>vi-comment</code> command is executed.
<code>meta-flag</code> (Off)	If set to <code>on</code> , readline will enable eight-bit input (that is, it will not strip the high bit from the characters it reads), regardless of what the terminal claims it can support.
<code>convert-meta</code> (On)	If set to <code>on</code> , readline will convert characters with the eighth bit set to an ASCII key sequence by stripping the eighth bit and prepending an escape character (in effect, using escape as the meta prefix).
<code>output-meta</code> (Off)	If set to <code>on</code> , readline will display characters with the eighth bit set directly rather than as a meta-prefixed escape sequence.
<code>completion-query-items</code> (100)	This determines when the user is queried about viewing the number of possible completions generated by the <code>possible-completions</code> command. It may be set to any integer value greater than or equal to zero. If the number of possible completions is greater than or equal to the value of this variable, the user is asked whether or not he wishes to view them; otherwise, they are simply listed on the terminal.
<code>keymap</code> (emacs)	Set the current readline keymap. The set of legal keymap names is <code>emacs</code> , <code>emacs-standard</code> , <code>emacs-meta</code> , <code>emacs-ctlx</code> , <code>vi</code> , <code>vi-move</code> , <code>vi-command</code> , and <code>vi-insert</code> . <code>vi</code> is equivalent to <code>vi-command</code> ; <code>emacs</code> is equivalent to <code>emacs-standard</code> . The default value is <code>emacs</code> ; the value of <code>editing-mode</code> also affects the default keymap.
<code>show-all-if-ambiguous</code> (Off)	This alters the default behavior of the completion functions. If set to <code>on</code> , words which have more than one possible completion cause the matches to be listed immediately instead of ringing the bell.
<code>expand-tilde</code> (Off)	If set to <code>on</code> , tilde expansion is performed when readline attempts word completion.

Readline implements a facility similar in spirit to the conditional compilation features of the C preprocessor that allows key bindings and variable settings to be performed as the result of tests. There are three parser directives used.

`$if` The `$if` construct allows bindings to be made based on the editing mode, the terminal being used, or the application using readline. The text of the test extends to the end of the line; no characters are required to isolate it.

mode	The <code>mode=</code> form of the <code>\$if</code> directive is used to test whether <code>readline</code> is in <code>emacs</code> or <code>vi</code> mode. This may be used in conjunction with the <code>set keymap</code> command, for instance, to set bindings in the <code>emacs-standard</code> and <code>emacs-ctlx</code> keymaps only if <code>readline</code> is starting out in <code>emacs</code> mode.
term	The <code>term=</code> form may be used to include terminal-specific key bindings, perhaps to bind the key sequences output by the terminal's function keys. The word on the right side of the <code>=</code> is tested against the full name of the terminal and the portion of the terminal name before the first <code>-</code> . This allows <code>sun</code> to match both <code>sun</code> and <code>sun-cmd</code> , for instance.
application	The <code>application</code> construct is used to include application-specific settings. Each program using the <code>readline</code> library sets the application name, and an initialization file can test for a particular value. This could be used to bind key sequences to functions useful for a specific program. For instance, the following command adds a key sequence that quotes the current or previous word in <code>bash</code> : <pre>\$if Bash # Quote the current or previous word "\C-xq": "\eb\` \ef\" \$endif</pre>
<code>\$endif</code>	This command, as shown in the preceding example, terminates an <code>\$if</code> command.
<code>\$else</code>	Commands in this branch of the <code>\$if</code> directive are executed if the test fails.

`readline` commands may be given numeric arguments, which normally act as a repeat count. Sometimes, however, it is the sign of the argument that is significant. Passing a negative argument to a command that acts in the forward direction (such as `kill-line`) causes that command to act in a backward direction. Commands whose behavior with arguments deviates from this are noted.

When a command is described as killing text, the text deleted is saved for possible future retrieval (yanking). The killed text is saved in a `kill-ring`. Consecutive kills cause the text to be accumulated into one unit, which can be yanked all at once. Commands that do not kill text separate the chunks of text on the `kill-ring`.

The following is a list of the names of the commands and the default key sequences to which they are bound.

Commands for Moving

<code>beginning-of-line (C-a)</code>	Move to the start of the current line.
<code>end-of-line (C-e)</code>	Move to the end of the line.
<code>forward-char (C-f)</code>	Move forward a character.
<code>backward-char (C-b)</code>	Move back a character.
<code>forward-word (M-f)</code>	Move forward to the end of the next word. Words are composed of alphanumeric characters (letters and digits).
<code>backward-word (M-b)</code>	Move back to the start of this, or the previous, word. Words are composed of alphanumeric characters (letters and digits).
<code>clear-screen (C-l)</code>	Clear the screen leaving the current line at the top of the screen. With an argument, refresh the current line without clearing the screen.
<code>redraw-current-line</code>	Refresh the current line. By default, this is unbound.

Commands for Manipulating the History

<code>accept-line</code> (Newline, Return)	Accept the line regardless of where the cursor is. If this line is non-empty, add it to the history list according to the state of the <code>HIST-CONTROL</code> variable. If the line is a modified history line, then restore the history line to its original state.
<code>previous-history</code> (C-p)	Fetch the previous command from the history list, moving back in the list.
<code>next-history</code> (C-n)	Fetch the next command from the history list, moving forward in the list.
<code>beginning-of-history</code> (M-<)	Move to the first line in the history.
<code>end-of-history</code> (M->)	Move to the end of the input history, that is, the line currently being entered.
<code>reverse-search-history</code> (C-r)	Search backward starting at the current line and moving “up” through the history as necessary. This is an incremental search.
<code>forward-search-history</code> (C-s)	Search forward starting at the current line and moving “down” through the history as necessary. This is an incremental search.
<code>non-incremental-reverse-search-history</code> (M-p)	Search backward through the history, starting at the current line using a non-incremental search for a string supplied by the user.
<code>non-incremental-forward-search-history</code> (M-n)	Search forward through the history using a nonincremental search for a string supplied by the user.
<code>history-search-forward</code>	Search forward through the history for the string of characters between the start of the current line and the current point. This is a nonincremental search. By default, this command is unbound.
<code>history-search-backward</code>	Search backward through the history for the string of characters between the start of the current line and the current point. This is a nonincremental search. By default, this command is unbound.
<code>yank-nth-arg</code> (M-C-y)	Insert the first argument to the previous command (usually the second word on the previous line) at point (the current cursor position). With an argument <i>n</i> , insert the <i>n</i> th word from the previous command (the words in the previous command begin with word 0). A negative argument inserts the <i>n</i> th word from the end of the previous command.
<code>yank-last-arg</code> (M-., M-_)	Insert the last argument to the previous command (the last word on the previous line). With an argument, behave exactly like <code>@codefyank-nth-argg</code> .
<code>shell-expand-line</code> (M-C-e)	Expand the line the way the shell does when it reads it. This performs alias and history expansion as well as all of the shell word expansions. See “History Expansion,” later in this manual page, for a description of history expansion.
<code>history-expand-line</code> (M-^)	Perform history expansion on the current line. See “History Expansion.”
<code>insert-last-argument</code> (M-., M-_)	A synonym for <code>yank-last-arg</code> .
<code>operate-and-get-next</code> (C-o)	Accept the current line for execution and fetch the next line relative to the current line from the history for editing. Any argument is ignored.

Commands for Changing Text

<code>delete-char</code> (C-d)	Delete the character under the cursor. If point is at the beginning of the line, there are no characters in the line, and the last character typed was not C-d, then return EOF.
<code>backward-delete-char</code> (Rubout)	Delete the character behind the cursor. When given a numeric argument, save the deleted text on the kill-ring.
<code>quoted-insert</code> (C-q, C-v)	Add the next character that you type to the line verbatim. This is how to insert characters like C-q, for example.
<code>tab-insert</code> (C-v Tab)	Insert a tab character.
<code>self-insert</code> (a, b, A, 1, !, ...)	Insert the character typed.

transpose-chars (C-t)	Drag the character before point forward over the character at point. Point moves forward as well. If point is at the end of the line, then transpose the two characters before point. Negative arguments don't work.
transpose-words (M-t)	Drag the word behind the cursor past the word in front of the cursor, moving the cursor over that word as well.
upcase-word (M-u)	Uppercase the current (or following) word. With a negative argument, do the previous word, but do not move point.
downcase-word (M-l)	Lowercase the current (or following) word. With a negative argument, do the previous word, but do not move point.
capitalize-word (M-c)	Capitalize the current (or following) word. With a negative argument, do the previous word, but do not move point.

Killing and Yanking

kill-line (C-k)	Kill the text from the current cursor position to the end of the line.
backward-kill-line (C-x C-Rubout)	Kill backward to the beginning of the line.
UNIX-line-discard (C-u)	Kill backward from point to the beginning of the line.
kill-whole-line	Kill all characters on the current line, no matter where the cursor is. By default, this is unbound.
kill-word (M-d)	Kill from the cursor to the end of the current word, or if between words, to the end of the next word. Word boundaries are the same as those used by <code>forward-word</code> .
backward-kill-word (M-Rubout)	Kill the word behind the cursor. Word boundaries are the same as those used by <code>backward-word</code> .
UNIX-word-rubout (C-w)	Kill the word behind the cursor, using whitespace as a word boundary. The word boundaries are different from <code>backward-kill-word</code> .
delete-horizontal-space	Delete all spaces and tabs around point. By default, this is unbound.
yank (C-y)	Yank the top of the kill ring into the buffer at the cursor.
yank-pop (M-y)	Rotate the kill-ring, and yank the new top. Only works following yank or yank-pop.

Numeric Arguments

digit-argument (M-0, M-1, ..., M-))	Add this digit to the argument already accumulating, or start a new argument. <code>M-</code> starts a negative argument.
universal-argument	Each time this is executed, the argument count is multiplied by four. The argument count is initially one, so executing this function the first time makes the argument count four. By default, this is not bound to a key.

Completing

complete (TAB)	Attempt to perform completion on the text before point. Bash attempts completion treating the text as a variable (if the text begins with \$), username (if the text begins with ~), hostname (if the text begins with @), or command (including aliases and functions) in turn. If none of these produces a match, filename completion is attempted.
possible-completions (M-?)	List the possible completions of the text before point.
insert-completions	Insert all completions of the text before point that would have been generated by possible-completions. By default, this is not bound to a key.
complete-filename (M-/)	Attempt filename completion on the text before point.

Completing

<code>possible-filename-completions (C-x /)</code>	List the possible completions of the text before point, treating it as a filename.
<code>complete-username (M-~)</code>	Attempt completion on the text before point, treating it as a username.
<code>possible-username-completions (C-x ~)</code>	List the possible completions of the text before point, treating it as a username.
<code>complete-variable (M-\$)</code>	Attempt completion on the text before point, treating it as a shell variable.
<code>possible-variable-completions (C-x \$)</code>	List the possible completions of the text before point, treating it as a shell variable.
<code>complete-hostname (M-@)</code>	Attempt completion on the text before point, treating it as a hostname.
<code>possible-hostname-completions (C-x @)</code>	List the possible completions of the text before point, treating it as a hostname.
<code>complete-command (M-!)</code>	Attempt completion on the text before point, treating it as a command name. Command completion attempts to match the text against aliases, reserved words, shell functions, builtins, and finally executable filenames, in that order.
<code>possible-command-completions (C-x !)</code>	List the possible completions of the text before point, treating it as a command name.
<code>dynamic-complete-history (M-TAB)</code>	Attempt completion on the text before point, comparing the text against lines from the history list for possible completion matches.
<code>complete-into-braces (M-{)</code>	Perform filename completion and return the list of possible completions enclosed within braces so the list is available to the shell. (See “Brace Expansion,” earlier in this manual page.)

Keyboard Macros

<code>start-kbd-macro (C-x (</code>	Begin saving the characters typed into the current keyboard macro.
<code>end-kbd-macro (C-x)</code>	Stop saving the characters typed into the current keyboard macro and save the definition.
<code>call-last-kbd-macro (C-x e)</code>	Re-execute the last keyboard macro defined, by making the characters in the macro appear as if typed at the keyboard.

Miscellaneous

<code>re-read-init-file (C-x C-r)</code>	Read in the contents of your init file, and incorporate any bindings or variable assignments found there.
<code>abort (C-g)</code>	Abort the current editing command and ring the terminal’s bell (subject to the setting of <code>bell-style</code>).
<code>do-uppercase-version (M-a, M-b, ...)</code>	Run the command that is bound to the corresponding uppercase character.
<code>prefix-meta (ESC)</code>	Metafy the next character typed. <code>ESC-f</code> is equivalent to <code>Meta-f</code> .
<code>undo (C-_, C-x C-u)</code>	Incremental undo, separately remembered for each line.
<code>revert-line (M-r)</code>	Undo all changes made to this line. This is like typing the undo command enough times to return the line to its initial state.
<code>tilde-expand (M-~)</code>	Perform tilde expansion on the current word.
<code>dump-functions</code>	Print all of the functions and their key bindings to the <code>readline</code> output stream. If a numeric argument is supplied, the output is formatted in such a way that it can be made part of an inputrc file.
<code>display-shell-version (C-x C-v)</code>	Display version information about the current instance of bash.
<code>emacs-editing-mode (C-e)</code>	When in <code>vi</code> editing mode, this causes a switch to <code>emacs</code> editing mode.

HISTORY

When interactive, the shell provides access to the command history, the list of commands previously typed. The text of the last `HISTSIZE` commands (default 500) is saved in a history list. The shell stores each command in the history list prior to

parameter and variable expansion (see “Expansion,” earlier in this manual page) but after history expansion is performed, subject to the values of the shell variables `command_oriented_history` and `HISTCONTROL`. On startup, the history is initialized from the file named by the variable `HISTFILE` (default `~/.bash_history`). `HISTFILE` is truncated, if necessary, to contain no more than `HISTFILESIZE` lines. The built-in command `fc` (see Shell Built-in Commands, later in this manual page) may be used to list or edit and re-execute a portion of the history list. The history builtin can be used to display the history list and manipulate the history file. When using the command-line editing, search commands are available in each editing mode that provide access to the history list. When an interactive shell exits, the last `HISTSIZE` lines are copied from the history list to `HISTFILE`. If `HISTFILE` is unset, or if the history file is unwritable, the history is not saved.

HISTORY EXPANSION

The shell supports a history expansion feature that is similar to the history expansion in `csh`. This section describes what syntax features are available. This feature is enabled by default for interactive shells, and can be disabled using the `H` option to the `set` built-in command. (See “Shell Built-in Commands,” later in this manual page.) Noninteractive shells do not perform history expansion.

History expansion is performed immediately after a complete line is read, before the shell breaks it into words. It takes place in two parts. The first is to determine which line from the previous history to use during substitution. The second is to select portions of that line for inclusion into the current one. The line selected from the previous history is the event, and the portions of that line that are acted upon are words. The line is broken into words in the same fashion as when reading input, so that several meta character-separated words surrounded by quotes are considered as one word. Only the backslash (`\`) and single quotes can quote the history escape character, which is `!` by default.

The shell allows control of the various characters used by the history expansion mechanism. (See the description of `histchars` under “Shell Variables,” earlier in this manual page.)

EVENT DESIGNATORS

An event designator is a reference to a command line entry in the history list.

<code>!</code>	Start a history substitution, except when followed by a blank, newline, <code>=</code> , or <code>(</code> .
<code>!!</code>	Refer to the previous command. This is a synonym for <code>!-1</code> .
<code>!n</code>	Refer to command line <code>n</code> .
<code>!-n</code>	Refer to the current command line minus <code>n</code> .
<code>!string</code>	Refer to the most recent command starting with <code>string</code> .
<code>!?string[?]</code>	Refer to the most recent command containing <code>string</code> .
<code>^string1^string2^</code>	Quick substitution. Repeat the last command, replacing <code>string1</code> with <code>string2</code> . Equivalent to <code>!!:s/string1/string2/</code> . (See “Modifiers,” later in this manual page.)
<code>!#</code>	The entire command line typed so far.

WORD DESIGNATORS

A colon (`:`) separates the event specification from the word designator. It can be omitted if the word designator begins with a `^`, `$`, `*`, or `%`. Words are numbered from the beginning of the line, with the first word being denoted by a `0` (zero).

<code>0</code> (zero)	The zeroth word. For the shell, this is the command word.
<code>n</code>	The n th word.
<code>^</code>	The first argument. That is, word 1.
<code>\$</code>	The last argument.
<code>%</code>	The word matched by the most recent <code>?string?</code> search.
<code>x-y</code>	A range of words; <code>-y</code> abbreviates <code>0-y</code> .
<code>*</code>	All of the words but the zeroth. This is a synonym for <code>1-\$</code> . It is not an error to use <code>*</code> if there is just one word in the event; the empty string is returned in that case.
<code>x*</code>	Abbreviates <code>x-\$</code> .
<code>x-</code>	Abbreviates <code>x-\$</code> like <code>x*</code> , but omits the last word.

MODIFIERS

After the optional word designator, you can add a sequence of one or more of the following modifiers, each preceded by a :

<code>h</code>	Remove a trailing pathname component, leaving only the head.
<code>r</code>	Remove a trailing suffix of the form <code>.xxx</code> , leaving the basename.
<code>e</code>	Remove all but the trailing suffix.
<code>t</code>	Remove all leading pathname components, leaving the tail.
<code>p</code>	Print the new command but do not execute it.
<code>q</code>	Quote the substituted words, escaping further substitutions.
<code>x</code>	Quote the substituted words as with <code>q</code> , but break into words at blanks and newlines.
<code>s/old/new/</code>	Substitute <code>new</code> for the first occurrence of <code>old</code> in the event line. Any delimiter can be used in place of <code>/</code> . The final delimiter is optional if it is the last character of the event line. The delimiter may be quoted in <code>old</code> and <code>new</code> with a single backslash. If <code>&</code> appears in <code>new</code> , it is replaced by <code>old</code> . A single backslash will quote the <code>&</code> .
<code>&</code>	Repeat the previous substitution.
<code>g</code>	Cause changes to be applied over the entire event line. This is used in conjunction with <code>:s</code> (for example, <code>:gs/old/new/</code>) or <code>:&</code> . If used with <code>:s</code> , any delimiter can be used in place of <code>/</code> , and the final delimiter is optional if it is the last character of the event line.

ARITHMETIC EVALUATION

The shell allows arithmetic expressions to be evaluated, under certain circumstances. (See the `let` built-in command and “Arithmetic Expansion.”) Evaluation is done in long integers with no check for overflow, though division by 0 is trapped and flagged as an error. The following list of operators is grouped into levels of equal-precedence operators. The levels are listed in order of decreasing precedence.

<code>- +</code>	Unary minus and plus
<code>! ~</code>	Logical and bitwise negation
<code>* / %</code>	Multiplication, division, remainder
<code>+ -</code>	Addition, subtraction
<code><< >></code>	Left and right bitwise shifts
<code><= >= <></code>	Comparison
<code>== !=</code>	Equality and inequality
<code>&</code>	Bitwise AND
<code>^</code>	Bitwise exclusive OR
<code> </code>	Bitwise OR
<code>&&</code>	Logical AND
<code> </code>	Logical OR
<code>= *= /= %= += -= <<= >>= ^= =</code>	Assignment

Shell variables are allowed as operands; parameter expansion is performed before the expression is evaluated. The value of a parameter is coerced to a long integer within an expression. A shell variable need not have its integer attribute turned on to be used in an expression.

Constants with a leading `0` are interpreted as octal numbers. A leading `0x` or `0X` denotes hexadecimal. Otherwise, numbers take the form `[base#]n`, where `base` is a decimal number between 2 and 36 representing the arithmetic base, and `n` is a number in that base. If `base` is omitted, then base 10 is used.

Operators are evaluated in order of precedence. Subexpressions in parentheses are evaluated first and may override the precedence rules.

SHELL BUILT-IN COMMANDS

```
: [arguments]

. filename [arguments]
source filename [arguments]
```

No effect; the command does nothing beyond expanding arguments and performing any specified redirections. A zero exit code is returned.

Read and execute commands from `filename` in the current shell environment and return the exit status of the last command executed from `filename`. If `filename` does not contain a slash, pathnames in `PATH` are used to find the directory containing `filename`. The file searched for in `PATH` need not be executable. The current directory is searched if no file is found in `PATH`. If any arguments are supplied, they become the positional parameters when `file` is executed. Otherwise, the positional parameters are unchanged. The return status is the status of the last command exited within the script (0 if no commands are executed), and False if `filename` is not found.

```
alias [name[=value] ...]
```

`alias` with no arguments prints the list of aliases in the form `name=value` on standard output. When arguments are supplied, an alias is defined for each name whose value is given. A trailing space in value causes the next word to be checked for alias substitution when the alias is expanded. For each name in the argument list for which no value is supplied, the name and value of the alias is printed. `alias` returns True unless a name is given for which no alias has been defined.

```
bg [jobspec]
```

Place `jobspec` in the background, as if it had been started with `&`. If `jobspec` is not present, the shell's notion of the current job is used. `bg jobspec` returns 0 unless run when job control is disabled or, when run with job control enabled, if `jobspec` was not found or started without job control.

```
bind [-m keymap][-lvd][-q name]
bind [-m keymap] -f filename
bind [-m keymap]
keyseq: function-name
```

Display current readline key and function bindings, or bind a key sequence to a readline function or macro. The binding syntax accepted is identical to that of `.inputrc`, but each binding must be passed as a separate argument; for example, `"\C-x\C-r": re-read-init-file`. Options, if supplied, have the following meanings:

<code>-m keymap</code>	Use <code>keymap</code> as the keymap to be affected by the subsequent bindings. Acceptable keymap names are <code>emacs</code> , <code>emacs-standard</code> , <code>emacs-meta</code> , <code>emacs-ctlx</code> , <code>vi</code> , <code>vi-move</code> , <code>vi-command</code> , and <code>vi-insert</code> . <code>vi</code> is equivalent to <code>vi-command</code> ; <code>emacs</code> is equivalent to <code>emacs-standard</code> .
<code>-l</code>	List the names of all readline functions.
<code>-v</code>	List current function names and bindings.
<code>-d</code>	Dump function names and bindings in such a way that they can be reread.
<code>-f filename</code>	Read key bindings from <code>filename</code> .
<code>-q function</code>	Query about which keys invoke the named function.

The return value is 0 unless an unrecognized option is given or an error occurred.

```
break [n]
```

Exit from within a `for`, `while`, or `until` loop. If `n` is specified, `break n` levels. `n` must be 1. If `n` is greater than the number of enclosing loops, all enclosing loops are exited. The return value is 0 unless the shell is not executing a loop when `break` is executed.

```
builtin shell-builtin [arguments]
```

Execute the specified shell builtin, passing it arguments, and return its exit status. This is useful when you wish to define a function whose name is the same as a shell builtin, but need the functionality of the builtin within the function itself. The `cd` builtin is commonly redefined this way. The return status is False if `shell-builtin` is not a shell builtin command.

```
cd [dir]
```

Change the current directory to `dir`. The variable `HOME` is the default `dir`. The variable `CDPATH` defines the search path for the directory containing `dir`. Alternative directory names are separated by a colon (:). A null directory name in `CDPATH` is the same as the current directory, that is, `(.)`. If `dir` begins with a slash (/), then `CDPATH` is

`command [-pVv] command [arg ...]`

not used. An argument of `-` is equivalent to `$OLDPWD`. The return value is `True` if the directory was successfully changed; `False` otherwise.

Run `command` with `args` suppressing the normal shell function lookup. Only built-in commands or commands found in the `PATH` are executed. If the `-p` option is given, the search for `command` is performed using a default value for `PATH` that is guaranteed to find all of the standard utilities. If either the `-v` or `-V` option is supplied, a description of `command` is printed. The `-v` option causes a single word indicating the command or pathname used to invoke `command` to be printed; the `-V` option produces a more verbose description. An argument of `--` disables option checking for the rest of the arguments. If the `-v` or `-V` option is supplied, the exit status is `0` if `command` was found, and `1` if not. If neither option is supplied and an error occurred or `command` cannot be found, the exit status is `127`. Otherwise, the exit status of the `command` builtin is the exit status of `command`.

`continue [n]`

Resume the next iteration of the enclosing `for`, `while`, or `until` loop. If `n` is specified, resume at the `n`th enclosing loop. `n` must be `1`. If `n` is greater than the number of enclosing loops, the last enclosing loop (the top-level loop) is resumed. The return value is `0` unless the shell is not executing a loop when `continue` is executed.

`declare [-frxi][name[=value]]`

`typeset [-frxi][name[=value]]`

Declare variables and/or give them attributes. If no names are given, then display the values of variables instead. The options can be used to restrict output to variables with the specified attribute.

- `-f` Use function names only.
- `-r` Make names read-only. These names cannot then be assigned values by subsequent assignment statements.
- `-x` Mark names for export to subsequent commands via the environment.
- `-i` The variable is treated as an integer; arithmetic evaluation (see “Arithmetic Evaluation”) is performed when the variable is assigned a value.

Using `+` instead of `-` turns off the attribute instead. When used in a function, makes names local, as with the `local` command. The return value is `0` unless an illegal option is encountered, an attempt is made to define a function using `"-f foo=bar"`, one of the names is not a legal shell variable name, an attempt is made to turn off read-only status for a read-only variable, or an attempt is made to display a nonexistent function with `-f`.

`dirs [-l][+/-n]`

Display the list of currently remembered directories. Directories are added to the list with the `pushd` command; the `popd` command moves back up through the list.

- `+n` Displays the `n`th entry counting from the left of the list shown by `dirs` when invoked without options, starting with zero.
- `-n` Displays the `n`th entry counting from the right of the list shown by `dirs` when invoked without options, starting with zero.
- `-l` Produces a longer listing; the default listing format uses a tilde to denote the home directory.

The return value is `0` unless an illegal option is supplied or `n` indexes beyond the end of the directory stack.

`echo [-neE][arg ...]`

Output the `args`, separated by spaces. The return status is always `0`. If `-n` is specified, the trailing newline is suppressed. If the `-e` option is given, interpretation of the following backslash-escaped characters is enabled. The `-E` option disables the interpretation of these escape characters, even on systems where they are interpreted by default.

<code>\a</code>	Alert (bell)
<code>\b</code>	Backspace
<code>\c</code>	Suppress trailing newline
<code>\f</code>	Form feed
<code>\n</code>	Newline
<code>\r</code>	Carriage return
<code>\t</code>	Horizontal tab
<code>\v</code>	Vertical tab
<code>\\</code>	Backslash
<code>\nnn</code>	The character whose ASCII code is <i>nnn</i> (octal)

<code>enable [-n][-all][name ...]</code>	Enable and disable builtin shell commands. This allows the execution of a disk command that has the same name as a shell builtin without specifying a full pathname. If <code>-n</code> is used, each name is disabled; otherwise, names are enabled. For example, to use the test binary found via the PATH instead of the shell builtin version, type <code>enable -n test</code> . If no arguments are given, a list of all enabled shell builtins is printed. If only <code>-n</code> is supplied, a list of all disabled builtins is printed. If only <code>-all</code> is supplied, the list printed includes all builtins, with an indication of whether or not each is enabled. <code>enable</code> accepts <code>-a</code> as a synonym for <code>-all</code> . The return value is 0 unless a name is not a shell builtin.
<code>eval [arg ...]</code>	The args are read and concatenated together into a single command. This command is then read and executed by the shell, and its exit status is returned as the value of the <code>eval</code> command. If there are no args, or only null arguments, <code>eval</code> returns True.
<code>exec [[-] command [arguments]]</code>	If <code>command</code> is specified, it replaces the shell. No new process is created. The arguments become the arguments to <code>command</code> . If the first argument is <code>-</code> , the shell places a dash in the zeroth arg passed to <code>command</code> . This is what login does. If the file cannot be executed for some reason, a noninteractive shell exits, unless the shell variable <code>no_exit_on_failed_exec</code> exists, in which case it returns failure. An interactive shell returns failure if the file cannot be executed. If <code>command</code> is not specified, any redirections take effect in the current shell, and the return status is 0.
<code>exit [n]</code>	Cause the shell to exit with a status of <i>n</i> . If <i>n</i> is omitted, the exit status is that of the last command executed. A trap on <code>exit</code> is executed before the shell terminates.
<code>export [-nf][name[=word]] ...</code> <code>export -p</code>	The supplied names are marked for automatic export to the environment of subsequently executed commands. If the <code>-f</code> option is given, the names refer to functions. If no names are given, or if the <code>-p</code> option is supplied, a list of all names that are exported in this shell is printed. The <code>-n</code> option causes the export property to be removed from the named variables. An argument of <code>-</code> disables option checking for the rest of the arguments. <code>export</code> returns an exit status of 0 unless an illegal option is encountered, one of the names is not a legal shell variable name, or <code>-f</code> is supplied with a name that is not a function.
<code>fc [-e ename][--nlr][first][last]</code> <code>fc -s [pat=rep][cmd]</code>	Fix command. In the first form, a range of commands from <i>first</i> to <i>last</i> is selected from the history list. <i>first</i> and <i>last</i> may be specified as a string (to locate the last command beginning with that string) or as a number (an index into the history list, where a negative number is used as an offset from the current command number). If <i>last</i> is not specified, it is set to the current command for listing (so that <code>fc -1 -10</code> prints the last 10 commands) and to <i>first</i> otherwise. If <i>first</i> is not specified, it is set to the previous command for editing and <code>-16</code> for listing. The <code>-n</code> flag suppresses the command numbers when listing. The <code>-r</code> flag reverses the order of the commands. If the <code>-1</code> flag is given, the commands are listed on standard output. Otherwise, the editor given by <i>ename</i> is invoked on a file containing those commands. If <i>ename</i> is not given, the value of the FCEDIT variable is used, and the

value of `EDITOR` if `FCEDIT` is not set. If neither variable is set, `vi` is used. When editing is complete, the edited commands are echoed and executed.

In the second form, `command` is reexecuted after each instance of `pat` is replaced by `rep`. A useful alias to use with this is `r=fc -s`, so that typing `r cc` runs the last command beginning with `cc` and typing `r` reexecutes the last command.

If the first form is used, the return value is `0` unless an illegal option is encountered or `first` or `last` specify history lines out of range. If the `-e` option is supplied, the return value is the value of the last command executed or failure if an error occurs with the temporary file of commands. If the second form is used, the return status is that of the command reexecuted, unless `cmd` does not specify a valid history line, in which case `fc` returns failure.

`fg [jobspec]`

Place `jobspec` in the foreground, and make it the current job. If `jobspec` is not present, the shell's notion of the current job is used. The return value is that of the command placed into the foreground, or failure if run when job control is disabled or, when run with job control enabled, if `jobspec` does not specify a valid job or `jobspec` specifies a job that was started without job control.

`getopts optstring name [args]`

`getopts` is used by shell procedures to parse positional parameters. `optstring` contains the option letters to be recognized; if a letter is followed by a colon, the option is expected to have an argument, which should be separated from it by whitespace. Each time it is invoked, `getopts` places the next option in the shell variable `name`, initializing `name` if it does not exist, and the index of the next argument to be processed into the variable `OPTARG`. `OPTARG` is initialized to `1` each time the shell or a shell script is invoked. When an option requires an argument, `getopts` places that argument into the variable `OPTARG`. The shell does not reset `OPTARG` automatically; it must be manually reset between multiple calls to `getopts` within the same shell invocation if a new set of parameters is to be used.

`getopts` can report errors in two ways. If the first character of `optstring` is a colon, silent error reporting is used. In normal operation, diagnostic messages are printed when illegal options or missing option arguments are encountered. If the variable `OPTERR` is set to `0`, no error message will be displayed, even if the first character of `optstring` is not a colon.

If an illegal option is seen, `getopts` places a question mark (?) into `name` and, if not silent, prints an error message and unsets `OPTARG`. If `getopts` is silent, the option character found is placed in `OP-TARG` and no diagnostic message is printed.

If a required argument is not found, and `getopts` is not silent, a question mark (?) is placed in `name`, `OPTARG` is unset, and a diagnostic message is printed. If `getopts` is silent, then a colon (:) is placed in `name` and `OPTARG` is set to the option character found.

`getopts` normally parses the positional parameters, but if more arguments are given in `args`, `getopts` parses those instead. `getopts` returns `True` if an option, specified or unspecified, is found. It returns `False` if the end of options is encountered or an error occurs.

`hash [-r][name]`

For each `name`, the full pathname of the command is determined and remembered. The `-r` option causes the shell to forget all remembered locations. If no arguments are given, information about remembered commands is printed. An argument of `-` disables option checking for the rest of the arguments. The return status is `True` unless a name is not found or an illegal option is supplied.

`help [pattern]`

Display helpful information about built-in commands. If `pattern` is specified, `help` gives detailed help on all commands matching `pattern`; otherwise, a list of the builtins is printed. The return status is `0` unless no command matches `pattern`.

```
history [n]
history -rwan [filename]
```

With no options, display the command history list with line numbers. Lines listed with a * have been modified. An argument of *n* lists only the *last n* lines. If a *nooption* argument is supplied, it is used as the name of the history file; if not, the value of HISTFILE is used. Options, if supplied, have the following meanings:

- a Append the “new” history lines (history lines entered since the beginning of the current bash session) to the history file.
- n Read the history lines not already read from the history file into the current history list. These are lines appended to the history file since the beginning of the current bash session.
- r Read the contents of the history file and use them as the current history.
- w- Write the current history to the history file, overwriting the history file’s contents.

The return value is 0 unless an illegal option is encountered or an error occurs while reading or writing the history file.

```
jobs [-lnp][jobspec ... ]
jobs -x command [ args ... ]
```

The first form lists the active jobs. The -l option lists process IDs in addition to the normal information; the -p option lists only the process ID of the job’s process group leader. The -n option displays only jobs that have changed status since last notified. If *jobspec* is given, output is restricted to information about that job. The return status is 0 unless an illegal option is encountered or an illegal *jobspec* is supplied.

If the -x option is supplied, *jobs* replaces any *jobspec* found in *command* or *args* with the corresponding process group ID, and executes *command*, passing it *args*, returning its exit status.

```
kill [-s sigspec | -sigspec]
[pid | jobspec] ...
kill -l [signal]
```

Send the signal named by *sigspec* to the processes named by *pid* or *jobspec*. *sigspec* is either a signal name such as SIGKILL or a signal number. If *sigspec* is a signal name, the name is not case sensitive and may be given with or without the SIG prefix. If *sigspec* is not present, then SIGTERM is assumed. An argument of -l lists the signal names. If any arguments are supplied when -l is given, the names of the specified signals are listed, and the return status is 0. An argument of — disables option checking for the rest of the arguments. *kill* returns True if at least one signal was successfully sent, or False if an error occurs or an illegal option is encountered.

```
let arg [arg ...]
```

Each *arg* is an arithmetic expression to be evaluated. (See “Arithmetic Evaluation.”) If the last *arg* evaluates to 0, *let* returns 1; 0 is returned otherwise.

```
local [name[=value] ...]
```

For each argument, create a local variable named *name*, and assign it *value*. When *local* is used within a function, it causes the variable name to have a visible scope restricted to that function and its children. With no operands, *local* writes a list of local variables to the standard output. It is an error to use *local* when not within a function. The return status is 0 unless *local* is used outside a function, or an illegal name is supplied.

```
logout
```

Exit a login shell.

```
popd [+/-n]
```

Removes entries from the directory stack. With no arguments, removes the top directory from the stack, and performs a *cd* to the new top directory.

- +n Removes the *n*th entry counting from the left of the list shown by *dirs*, starting with zero. For example, *popd +0* removes the first directory, *popd +1* the second.
- n Removes the *n*th entry counting from the right of the list shown by *dirs*, starting with zero. For example, *popd -0* removes the last directory, *popd -1* the next to last.

`pushd [dir] pushd +/-n`

If the `popd` command is successful, a `dirs` is performed as well, and the return status is 0. `popd` returns `False` if an illegal option is encountered, the directory stack is empty, a nonexistent directory stack entry is specified, or the directory change fails.

Adds a directory to the top of the directory stack, or rotates the stack, making the new top of the stack the current working directory. With no arguments, exchanges the top two directories and returns 0, unless the directory stack is empty.

- `+n` Rotates the stack so that the *n*th directory (counting from the left of the list shown by `dirs`) is at the top.
- `-n` Rotates the stack so that the *n*th directory (counting from the right) is at the top.
- `dir` Adds *dir* to the directory stack at the top, making it the new current working directory.

If the `pushd` command is successful, a `dirs` is performed as well. If the first form is used, `pushd` returns 0 unless the `cd` to *dir* fails. With the second form, `pushd` returns 0 unless the directory stack is empty, a nonexistent directory stack element is specified, or the directory change to the specified new current directory fails.

`pwd`

Print the absolute pathname of the current working directory. The path printed contains no symbolic links if the `-P` option to the `set` builtin command is set. (See also the description of `noLinks` under “Shell Variables,” earlier in this manual page.) The return status is 0 unless an error occurs while reading the pathname of the current directory.

`read [-r][name ...]`

One line is read from the standard input, and the first word is assigned to the first name, the second word to the second name, and so on, with leftover words assigned to the last name. Only the characters in `IFS` are recognized as word delimiters. If no names are supplied, the line read is assigned to the variable `REPLY`. The return code is zero, unless end-of-file is encountered. If the `-r` option is given, a backslash-newline pair is not ignored, and the backslash is considered to be part of the line.

`readonly [-f][name ...]`

`readonly -p`

The given names are marked `readonly` and the values of these names may not be changed by subsequent assignment. If the `-f` option is supplied, the functions corresponding to the names are so marked. If no arguments are given, or if the `-p` option is supplied, a list of all `readonly` names is printed. An argument of `-` disables option checking for the rest of the arguments. The return status is 0 unless an illegal option is encountered, one of the names is not a legal shell variable name, or `-f` is supplied with a name that is not a function.

`return [n]`

Causes a function to exit with the return value specified by *n*. If *n* is omitted, the return status is that of the last command executed in the function body. If used outside a function, but during execution of a script by the `.` (source) command, it causes the shell to stop executing that script and return either *n* or the exit status of the last command executed within the script as the exit status of the script. If used outside a function and not during execution of a script by `( . )`, the return status is `False`.

`set [--abefhkmnptuvxldCHP]`

`[-o option][arg ...]`

- `-a` Automatically mark variables that are modified or created for export to the environment of subsequent commands.
- `-b` Cause the status of terminated background jobs to be reported immediately, rather than before the next primary prompt. (Also see `notify` under “Shell Variables.”)
- `-e` Exit immediately if a simple command (see “Shell Grammar,” earlier in this manual page) exits with a non-zero status. The shell does not exit if the command that fails is part of an `until`

or while loop, part of an if statement, part of a && or || list, or if the command's return value is being inverted via !.

- f Disable pathname expansion.
- h Locate and remember function commands as functions are defined. Function commands are normally looked up when the function is executed.
- k All keyword arguments are placed in the environment for a command, not just those that precede the command name.
- m Monitor mode. Job control is enabled. This flag is on by default for interactive shells on systems that support it. (See “Job Control,” earlier in this manual page.) Background processes run in a separate process group and a line containing their exit status is printed upon their completion.
- n Read commands but do not execute them. This may be used to check a shell script for syntax errors. This is ignored for interactive shells.
- o option-name The option-name can be one of the following:
 - allexport—Same as -a.
 - braceexpand—The shell performs brace expansion. (See “Brace Expansion,” earlier in this manual page.) This is on by default.
 - emacs—Use an emacs-style command line editing interface. This is enabled by default when the shell is interactive, unless the shell is started with the -noediting option.
 - errexit—Same as -e.
 - histexpand—Same as -H.
 - ignoreeof—The effect is as if the shell command 'IGNOREEOF=10' had been executed. (See “Shell Variables.”)
 - interactive-comments—Allow a word beginning with # to cause that word and all remaining characters on that line to be ignored in an interactive shell. (See “Comments,” earlier in this manual page.)
 - monitor—Same as -m.
 - noclobber—Same as -C.
 - noexec—Same as -n.
 - noglob—Same as -f.
 - nohash—Same as -d.
 - notify—Same as -b.
 - nounset—Same as -u.
 - physical—Same as -P.
 - posix—Change the behavior of bash where the default operation differs from the POSIX 1003.2 standard to match the standard.
 - privileged—Same as -p.
 - verbose—Same as -v.
 - vi—Use a vi-style command line editing interface.
 - xtrace—Same as -x.

If no option-name is supplied, the values of the current options are printed.

- p Turn on privileged mode. In this mode, the `$ENV` file is not processed, and shell functions are not inherited from the environment. This is enabled automatically on startup if the effective user (group) ID is not equal to the real user (group) ID. Turning this option off causes the effective user and group IDs to be set to the real user and group IDs.
 - t Exit after reading and executing one command.
 - u Treat unset variables as an error when performing parameter expansion. If expansion is attempted on an unset variable, the shell prints an error message, and, if not interactive, exits with a non-zero status.
 - v Print shell input lines as they are read.
 - x After expanding each simple command, bash displays the expanded value of `PS4`, followed by the command and its expanded arguments.
 - l Save and restore the binding of `name` in a `for name [in word]` command. (See “Shell Grammar,” earlier in this manual page.)
 - d Disable the hashing of commands that are looked up for execution. Normally, commands are remembered in a hash table, and once found, do not have to be looked up again.
 - C The effect is as if the shell command `noclobber=` had been executed. (See “Shell Variables.”)
 - H Enable `!` style history substitution. This flag is on by default when the shell is interactive.
 - P If set, do not follow symbolic links when performing commands such as `cd` that change the current directory. The physical directory is used instead.
 - If no arguments follow this flag, then the positional parameters are unset. Otherwise, the positional parameters are set to the args, even if some of them begin with a `-`.
 - Signal the end of options, cause all remaining args to be assigned to the positional parameters. The `-x` and `-v` options are turned off. If there are no args, the positional parameters remain unchanged.
- The flags are off by default unless otherwise noted. Using `+` rather than `-` causes these flags to be turned off. The flags can also be specified as options to an invocation of the shell. The current set of flags may be found in `$-`. After the option arguments are processed, the remaining `n` args are treated as values for the positional parameters and are assigned, in order, to `$1`, `$2`, ... `$n`. If no options or args are supplied, all shell variables are printed. The return status is always `True` unless an illegal option is encountered.

`shift [n]`

The positional parameters from `n+1` ... are renamed to Parameters represented by the numbers `$#` down to `$#-n+1` are unset. If `n` is `0`, no parameters are changed. If `n` is not given, it is assumed to be `1`. `n` must be a non-negative number less than or equal to `$#`. If `n` is greater than `$#`, the positional parameters are not changed. The return status is greater than `0` if `n` is greater than or less than `0`; otherwise `0`.

`suspend [-f]`

Suspend the execution of this shell until it receives a `SIG-CONT` signal. The `-f` option says not to complain if this is a `login` shell; just suspend anyway. The return status is

test expr[expr]

0 unless the shell is a login shell and -f is not supplied, or if job control is not enabled.

Return a status of 0 (True) or 1 (False) depending on the evaluation of the conditional expression *expr*. Expressions may be unary or binary. Unary expressions are often used to examine the status of a file. There are string operators and numeric comparison operators as well. Each operator and operand must be a separate argument. If file is of the form */dev/fd/n*, then file descriptor *n* is checked.

- b *file*—True if *file* exists and is block special.
- c *file*—True if *file* exists and is character special.
- d *file*—True if *file* exists and is a directory.
- e *file*—True if *file* exists.
- f *file*—True if *file* exists and is a regular file.
- g *file*—True if *file* exists and is set-group-id.
- k *file*—True if *file* has its “sticky” bit set.
- L *file*—True if *file* exists and is a symbolic link.
- p *file*—True if *file* exists and is a named pipe.
- r *file*—True if *file* exists and is readable.
- s *file*—True if *file* exists and has a size greater than zero.
- S *file*—True if *file* exists and is a socket.
- t *fd*—True if *fd* is opened on a terminal.
- u *file*—True if *file* exists and its set-user-id bit is set.
- w *file*—True if *file* exists and is writable.
- x *file*—True if *file* exists and is executable.
- O *file*—True if *file* exists and is owned by the effective user ID.
- G *file*—True if *file* exists and is owned by the effective group ID.
- file1* -nt *file2*—True if *file1* is newer (according to modification date) than *file2*.
- file1* -ot *file2*—True if *file1* is older than *file2*.
- file1* -ef *file*—True if *file1* and *file2* have the same device and inode numbers.
- z *string*—True if the length of *string* is zero.
- n *string*—True if the length of *string* is non-zero.
- string1* = *string2*—True if the strings are equal.
- string1* != *string2*—True if the strings are not equal.
- ! *expr*—True if *expr* is False.
- expr1* -a *expr2*—True if both *expr1* AND *expr2* are True.
- expr1* -o *expr2*—True if either *expr1* OR *expr2* is True.
- arg1* OP *arg2* OP is one of -eq, -ne, -lt, -le, -gt, or -ge. These arithmetic binary operators return True if *arg1* is equal, not-equal, less-than, less-than-or-equal, greater-than, or greater-than-or-equal than *arg2*, respectively. *Arg1* and *arg2* may be positive integers, negative integers, or the special expression -1 *string*, which evaluates to the length of *string*.

times

Print the accumulated user and system times for the shell and for processes run from the shell. The return status is 0.

trap [-1][arg][sigspec]

The command *arg* is to be read and executed when the shell receives signal(s) *sigspec*. If *arg* is absent or -, all specified signals are reset to their original values (the

```
type [-all][-type | -path]
name [name ...]
```

```
ulimit [-SHacdfmstpnv [limit]]
```

values they had upon entrance to the shell). If *arg* is the null string, this signal is ignored by the shell and by the commands it invokes. *sigspec* is either a signal name defined in `<signal.h>`, or a signal number. If *sigspec* is `EXIT (0)`, the command *arg* is executed on exit from the shell. With no arguments, *trap* prints the list of commands associated with each signal number. The `-1` option causes the shell to print a list of signal names and their corresponding numbers. An argument of `-` disables option checking for the rest of the arguments. Signals ignored upon entry to the shell cannot be trapped or reset. Trapped signals are reset to their original values in a child process when it is created. The return status is `False` if either the trap name or number is invalid; otherwise, *trap* returns `True`.

With no options, indicate how each name would be interpreted if used as a command name. If the `-type` flag is used, *type* prints a phrase that is one of alias, keyword, function, builtin, or file if *name* is an alias, shell reserved word, function, builtin, or disk file, respectively. If the name is not found, then nothing is printed, and an exit status of `False` is returned. If the `-path` flag is used, *type* either returns the name of the disk file that would be executed if *name* were specified as a command name, or nothing if `-type` would not return file. If a command is hashed, `-path` prints the hashed value, not necessarily the file that appears first in `PATH`. If the `-all` flag is used, *type* prints all of the places that contain an executable named *name*. This includes aliases and functions, if and only if the `-path` flag is not also used. The table of hashed commands is not consulted when using `-all`. *type* accepts `-a`, `-t`, and `-p` in place of `-all`, `-type`, and `-path`, respectively. An argument of `-` disables option checking for the rest of the arguments. *type* returns `True` if any of the arguments are found, `False` if none are found.

ulimit provides control over the resources available to the shell and to processes started by it, on systems that allow such control. The value of *limit* can be a number in the unit specified for the resource, or the value `unlimited`. The `H` and `S` options specify that the hard or soft limit is set for the given resource. A hard limit cannot be increased once it is set; a soft limit may be increased up to the value of the hard limit. If neither `H` nor `S` is specified, the command applies to the soft limit. If *limit* is omitted, the current value of the soft limit of the resource is printed, unless the `H` option is given. When more than one resource is specified, the *limit* name and unit is printed before the value. Other options are interpreted as follows:

<code>-a</code>	All current limits are reported.
<code>-c</code>	The maximum size of core files created.
<code>-d</code>	The maximum size of a process's data segment.
<code>-f</code>	The maximum size of files created by the shell.
<code>-m</code>	The maximum resident set size.
<code>-s</code>	The maximum stack size.
<code>-t</code>	The maximum amount of cpu time in seconds.
<code>-p</code>	The pipe size in 512-byte blocks. (This may not be set.)
<code>-n</code>	The maximum number of open file descriptors. (Most systems do not allow this value to be set, only displayed.)
<code>-u</code>	The maximum number of processes available to a single user.
<code>-v</code>	The maximum amount of virtual memory available to the shell.

An argument of `-` disables option checking for the rest of the arguments. If *limit* is given, it is the new value of the specified resource (the `-a` option is display only). If no option is given, then `-f` is assumed. Values are in 1024-byte increments, except for `-t`, which is in seconds; `-p`, which is in units of 512-byte blocks; and `-n` and `-u`,

	which are unscaled values. The return status is 0 unless an illegal option is encountered, a non-numeric argument other than unlimited is supplied as <code>limit</code> , or an error occurs while setting a new limit.
<code>umask [-S][mode]</code>	The user file-creation mask is set to <code>mode</code> . If <code>mode</code> begins with a digit, it is interpreted as an octal number; otherwise, it is interpreted as a symbolic mode mask similar to that accepted by <code>chmod(1)</code> . If <code>mode</code> is omitted, or if the <code>-s</code> option is supplied, the current value of the mask is printed. The <code>-s</code> option causes the mask to be printed in symbolic form; the default output is an octal number. An argument of <code>—</code> disables option checking for the rest of the arguments. The return status is 0 if the mode was successfully changed or if no <code>mode</code> argument was supplied, and False otherwise.
<code>unalias [-a][name ...]</code>	Remove names from the list of defined aliases. If <code>-a</code> is supplied, all alias definitions are removed. The return value is True unless a supplied name is not a defined alias.
<code>unset [-fv][name ...]</code>	For each name, remove the corresponding variable or, given the <code>-f</code> option, function. An argument of <code>—</code> disables option checking for the rest of the arguments. Note that <code>PATH</code> , <code>IFS</code> , <code>PPID</code> , <code>PS1</code> , <code>PS2</code> , <code>UID</code> , and <code>EUID</code> cannot be unset. If any of <code>RANDOM</code> , <code>SECONDS</code> , <code>LINENO</code> , or <code>HISTCMD</code> are unset, they lose their special properties, even if they are subsequently reset. The exit status is True unless a name does not exist or is non-unsettable.
<code>wait [n]</code>	Wait for the specified process and return its termination status. <code>n</code> may be a process ID or a job specification; if a job spec is given, all processes in that job's pipeline are waited for. If <code>n</code> is not given, all currently active child processes are waited for, and the return status is zero. If <code>n</code> specifies a nonexistent process or job, the return status is 127. Otherwise, the return status is the exit status of the last process or job waited for.

INVOCATION

A *login shell* is one whose first character of argument zero is a `-`, or one started with the `-login` flag.

An *interactive shell* is one whose standard input and output are both connected to terminals (as determined by `isatty(3)`), or one started with the `-i` option. `PS1` is set and includes `i` if bash is interactive, allowing a shell script or a startup file to test this state.

Login shells:

On login (subject to the `-noprofile` option):

if `/etc/profile` exists, source it.

if `~/.bash_profile` exists, source it,

else if `~/.bash_login` exists, source it,

else if `~/.profile` exists, source it.

On exit:

if `~/.bash_logout` exists, source it.

Non-login interactive shells:

On startup (subject to the `-norc` and `-rcfile` options):

if `~/.bashrc` exists, source it.

Non-interactive shells:

On startup:

if the environment variable `ENV` is non-null, expand

it and source the file it names, as if the command

if ["\$ENV"]; then . \$ENV; fi

had been executed, but do not use `PATH` to search

for the pathname. When not started in Posix mode, bash

looks for `BASH_ENV` before `ENV`.

If Bash is invoked as `sh`, it tries to mimic the behavior of `sh` as closely as possible. For a login shell, it attempts to source only `/etc/profile` and `~/.profile`, in that order. The `-noprofile` option may still be used to disable this behavior. A shell invoked as `sh` does not attempt to source any other startup files.

When `bash` is started in `posix` mode, as with the `-posix` command line option, it follows the POSIX standard for startup files. In this mode, the `ENV` variable is expanded and that file sourced; no other startup files are read.

SEE ALSO

Bash Features, Brian Fox and Chet Ramey

The Gnu Readline Library, Brian Fox and Chet Ramey

The Gnu History Library, Brian Fox and Chet Ramey

A System V Compatible Implementation of 4.2BSD Job Control, David Lennert

Portable Operating System Interface (POSIX) Part 2: Shell and Utilities, IEEE

`sh(1)`, `ksh(1)`, `csh(1)`, `emacs(1)`, `vi(1)` `readline(3)`

FILES

<code>/bin/bash</code>	The <code>bash</code> executable
<code>/etc/profile</code>	The systemwide initialization file, executed for login shells
<code>./bash_profile</code>	The personal initialization file, executed for login shells
<code>./bashrc</code>	The individual per-interactive-shell startup file
<code>./inputrc</code>	Individual <code>readline</code> initialization file

AUTHORS

Brian Fox (Free Software Foundation; primary author; bfox@ai.MIT.Edu), Chet Ramey (Case Western Reserve University; chet@ins.CWRU.Edu)

COPYRIGHT

Copyright © 1989, 1991 by the Free Software Foundation, Inc.

BUG REPORTS

If you find a bug in `bash`, you should report it. But first, you should make sure that it really is a bug, and that it appears in the latest version of `bash` that you have.

Once you have determined that a bug actually exists, mail a bug report to bash-maintainers@prep.ai.MIT.Edu. If you have a fix, you are welcome to mail that as well! Suggestions and “philosophical” bug reports may be mailed to bug-bash@prep.ai.MIT.Edu or posted to the Usenet newsgroup `gnu.bash.bug`.

ALL bug reports should include the following:

- The version number of `bash`
- The hardware and operating system
- The compiler used to compile
- A description of the bug behavior
- A short script or “recipe” that exercises the bug

Comments and bug reports concerning this manual page should be directed to chet@ins.cwru.edu.

BUGS

It’s too big and too slow.

There are some subtle differences between `bash` and traditional versions of `sh`, mostly because of the POSIX specification.

Aliases are confusing in some uses.

bdftopcf

bdftopcf—Convert X font from Bitmap Distribution Format to Portable Compiled Format

SYNOPSIS

```
bdftopcf [ -pn ][-un ][-m ][-l ][-M ][-L ][-t ][-i ][-o outputfile ] fontfile.bdf
```

DESCRIPTION

bdftopcf is a font compiler for the X server and font server. Fonts in Portable Compiled Format can be read by any architecture, although the file is structured to allow one particular architecture to read them directly without reformatting. This allows fast reading on the appropriate machine, but the files are still portable (but read more slowly) on other machines.

OPTIONS

-pn	Sets the font glyph padding. Each glyph in the font will have each scanline padded in to a multiple of <i>n</i> bytes, where <i>n</i> is 1, 2, 4, or 8.
-un	Sets the font scanline unit. When the font bit order is different from the font byte order, the scanline unit <i>n</i> describes what unit of data (in bytes) are to be swapped; the unit <i>i</i> can be 1, 2, or 4 bytes.
-m	Sets the font bit order to MSB (most significant bit) first. Bits for each glyph will be placed in this order; that is, the leftmost bit on the screen will be in the highest valued bit in each unit.
-l	Sets the font bit order to LSB (least significant bit) first. The leftmost bit on the screen will be in the lowest valued bit in each unit.
-M	Sets the font byte order to MSB first. All multibyte data in the file (metrics, bitmaps, and everything else) will be written most significant byte first.
-L	Sets the font byte order to LSB first. All multibyte data in the file (metrics, bitmaps, and everything else) will be written least significant byte first.
-t	When this option is specified, bdftopcf will convert fonts into terminal fonts when possible. A <i>terminal font</i> has each glyph image padded to the same size; the X server can usually render these types of fonts more quickly.
-i	This option inhibits the normal computation of ink metrics. When a font has glyph images that do not fill the bitmap image (that is, the “on” pixels don’t extend to the edges of the metrics), bdftopcf computes the actual ink metrics and places them in the PCF file; the -t option inhibits this behavior.
-o output-file-name	By default bdftopcf writes the PCF file to standard output; this option gives the name of a file to be used instead.

SEE ALSO

x(1)

AUTHOR

Keith Packard, MIT X Consortium

X Version 11 Release 6

beforelight

beforelight—Screen saver

SYNOPSIS

```
beforelight [ -toolkitoption ... ]
```

DESCRIPTION

The `beforelight` program is a sample implementation of a screen saver for X servers supporting the MIT-SCREEN-SAVER extension.

AUTHORS

Keith Packard (MIT X Consortium)

X Version 11 Release 6

biff

`biff`—Be notified if mail arrives and who it is from

SYNOPSIS

`biff [ny]`

DESCRIPTION

`biff` informs the system whether you want to be notified when mail arrives during the current terminal session.

Options supported by `biff`:

<code>n</code>	Disables notification
<code>y</code>	Enables notification

When mail notification is enabled, the header and first few lines of the message will be printed on your screen whenever mail arrives. A

`biff y`

`command` is often included in the file `.login` or `.profile` to be executed at each login.

`Biff` operates asynchronously. For synchronous notification use the `MAIL` variable of `sh(1)` or the `mail` variable of `csh(1)`.

SEE ALSO

`csh(1)`, `mail(1)`, `sh(1)`, `comsat(8)`

HISTORY

The `biff` command appeared in BSD 4.0.

BSD 4, 14 March 1991

bioradtopgm

`bioradtopgm`—Convert a Biorad confocal file into a portable graymap

SYNOPSIS

`bioradtopgm [-image#][imagedata]`

DESCRIPTION

Reads a Biorad confocal file as input. Produces a portable graymap as output. If the resulting image is upside down, run it through `pnmflip -tb`.

OPTIONS

`-image#` A Biorad image file may contain more than one image. With this flag, you can specify which image to extract (only one at a time). The first image in the file has number zero. If no image number is supplied, only information about the image size and the number of images in the input is printed out. No output is produced.

BUGS

A Biorad image may be in word format. If PbmPlus is not compiled with the BIGGRAYS flag, word files cannot be converted. See the makefile.

SEE ALSO

`pgm(5)`, `pnmflip(1)`

AUTHORS

Copyright © 1993 by Oliver Treppe

28 June 1993

bitmap, bmtoa, atobm

bitmap, bmtoa, atobm—Bitmap editor and converter utilities for the X Window System

SYNOPSIS

`bitmap [ -options ... ][filename ][basename ]`

`bmtoa [ -chars ... ][filename ]`

`atobm [ -chars cc ][-name variable ][-xhot number ][-yhot number ][filename ]`

DESCRIPTION

The `bitmap` program is a rudimentary tool for creating or editing rectangular images made up of 1s and 0s. Bitmaps are used in `x` for defining clipping regions, cursor shapes, icon shapes, and tile and stipple patterns.

The `bmtoa` and `atobm` filters convert bitmap files (`FILE FORMAT`) to and from ASCII strings. They are most commonly used to quickly print out bitmaps and to generate versions for including in text.

COMMAND-LINE OPTIONS

Bitmap supports the standard X Toolkit command-line arguments; see `x(1)`. The following additional arguments are supported as well:

<code>-size WIDTHxHEIGHT</code>	Specifies size of the grid in squares.
<code>-sw dimension</code>	Specifies the width of squares in pixels.
<code>-sh dimension</code>	Specifies the height of squares in pixels.
<code>-gt dimension</code>	Grid tolerance. If the square dimensions fall below the specified value, grid will be automatically turned off.
<code>-grid, +grid</code>	Turns on or off the grid lines.
<code>-axes, +axes</code>	Turns on or off the major axes.
<code>-dashed, +dashed</code>	Turns on or off dashing for the frame and grid lines.
<code>-stippled, +stippled</code>	Turns on or off stippling of highlighted squares.

<code>-proportional, +proportional</code>	Turns proportional mode on or off. If proportional mode is on, square width is equal to square height. If proportional mode is off, bitmap will use the smaller square dimension, if they were initially different.
<code>-dashes filename</code>	Specifies the bitmap to be used as a stipple for dashing.
<code>-stipple filename</code>	Specifies the bitmap to be used as a stipple for highlighting.
<code>-hl color</code>	Specifies the color used for highlighting.
<code>-fr color</code>	Specifies the color used for the frame and grid lines.
<code>filename</code>	Specifies the bitmap to be initially loaded into the program. If the file does not exist, bitmap will assume it is a new file.
<code>basename</code>	Specifies the basename to be used in the C code output file. If it is different than the basename in the working file, bitmap will change it when saving the file.
bmtoa accepts the following option:	
<code>-chars cc</code>	This option specifies the pair of characters to use in the string version of the bitmap. The first character is used for 0 bits and the second character is used for 1 bits. The default is to use dashes (-) for 0s and number signs (#) for 1s.
atobm accepts the following options:	
<code>-chars cc</code>	This option specifies the pair of characters to use when converting string bitmaps into arrays of numbers. The first character represents a 0 bit and the second character represents a 1 bit. The default is to use dashes (-) for 0s and number signs (#) for 1s.
<code>-name variable</code>	This option specifies the variable name to be used when writing out the bitmap file. The default is to use the basename of the filename command-line argument or leave it blank if the standard input is read.
<code>-xhot number</code>	This option specifies the X coordinate of the hot spot. Only positive values are allowed. By default, no hot spot information is included.
<code>-yhot number</code>	This option specifies the Y coordinate of the hot spot. Only positive values are allowed. By default, no hot spot information is included.

USAGE

bitmap displays grid in which each square represents a single bit in the picture being edited. Actual size of the bitmap image, as it would appear normally and inverted, can be obtained by pressing Meta-I. You are free to move the image pop-up out of the way to continue editing. Pressing the left mouse button in the pop-up window or Meta-I again will remove the real size bitmap image.

If the bitmap is to be used for defining a cursor, one of the squares in the images may be designated as the hot spot. This determines where the cursor is actually pointing. For cursors with sharp tips (such as arrows or fingers), this is usually at the end of the tip; for symmetric cursors (such as crosses or bulls-eyes), this is usually at the center.

Bitmaps are stored as small C code fragments suitable for including in applications. They provide an array of bits as well as symbolic constants giving the width, height, and hot spot (if specified) that may be used in creating cursors, icons, and tiles.

EDITING

To edit a bitmap image, simply click on one of the buttons with drawing commands (Point, Curve, Line, Rectangle, and so on) and move the pointer into the bitmap grid window. Press one of the buttons on your mouse and the appropriate action will take place. You can either set, clear, or invert the grid squares. Setting a grid square corresponds to setting a bit in the bitmap image to 1. Clearing a grid square corresponds to setting a bit in the bitmap image to 0. Inverting a grid square corresponds to changing a bit in the bitmap image from 0 to 1 or 1 to 0, depending what its previous state was. The default behavior of mouse buttons is as follows:

```
MouseButton1 Set
MouseButton2 Invert
MouseButton3 Clear
MouseButton4 Clear
MouseButton5 Clear
```

This default behavior can be changed by setting the button function resources. Here is an example:

```
bitmap*button1Function: Set
bitmap*button2Function: Clear
bitmap*button3Function: Invert
etc.
```

The button function applies to all drawing commands, including copying, moving and pasting, flood filling, and setting the hot spot.

DRAWING COMMANDS

Here is the list of drawing commands accessible through the buttons at the left side of the application's window. Some commands can be aborted by pressing A inside the bitmap window, allowing the user to select different guiding points where applicable.

Clear	This command clears all bits in the bitmap image. The grid squares will be set to the background color. Pressing C inside the bitmap window has the same effect.
Set	This command sets all bits in the bitmap image. The grid squares will be set to the foreground color. Pressing S inside the bitmap window has the same effect.
Invert	This command inverts all bits in the bitmap image. The grid squares will be inverted appropriately. Pressing I inside the bitmap window has the same effect.
Mark	This command is used to mark an area of the grid by dragging out a rectangular shape in the highlighting color. After the area is marked, it can be operated on by a number of commands (see Up, Down, Left, Right, Rotate, Flip, Cut, and so on). Only one marked area can be present at any time. If you attempt to mark another area, the old mark will vanish. The same effect can be achieved by pressing Shift-MouseButton1 and dragging out a rectangle in the grid window. Pressing Shift-MouseButton2 will mark the entire grid area.
Unmark	This command will cause the marked area to vanish. The same effect can be achieved by pressing Shift-MouseButton3.
Copy	This command is used to copy an area of the grid from one location to another. If there is no marked grid area displayed, Copy behaves just like Mark. Once there is a marked grid area displayed in the highlighting color, this command has two alternative behaviors. If you click a mouse button inside the marked area, you will be able to drag the rectangle that represents the marked area to the desired location. After you release the mouse button, the area will be copied. If you click outside the marked area, Copy will assume that you wish to mark a different region of the bitmap image, thus it will behave like Mark again.
Move	This command is used to move an area of the grid from one location to another. Its behavior resembles the behavior of Copy command, except that the marked area will be moved instead of copied.
Flip Horizontally	This command will flip the bitmap image with respect to the horizontal axes. If a marked area of the grid is highlighted, it will operate only inside the marked area. Pressing H inside the bitmap window has the same effect.
Up	This command moves the bitmap image one pixel up. If a marked area of the grid is highlighted, it will operate only inside the marked area. Pressing UpArrow inside the bitmap window has the same effect.

Flip Vertically	This command will flip the bitmap image with respect to the vertical axes. If a marked area of the grid is highlighted, it will operate only inside the marked area. Pressing V inside the bitmap window has the same effect.
Left	This command moves the bitmap image one pixel to the left. If a marked area of the grid is highlighted, it will operate only inside the marked area. Pressing LeftArrow inside the bitmap window has the same effect.
Fold	This command will fold the bitmap image so that the opposite corners become adjacent. This is useful when creating bitmap images for tiling. Pressing F inside the bitmap window has the same effect.
Right	This command moves the bitmap image one pixel to the right. If a marked area of the grid is highlighted, it will operate only inside the marked area. Pressing the right arrow inside the bitmap window has the same effect.
Rotate Left	This command rotates the bitmap image 90 degrees to the left (counter clockwise.) If a marked area of the grid is highlighted, it will operate only inside the marked area. Pressing L inside the bitmap window has the same effect.
Down	This command moves the bitmap image one pixel down. If a marked area of the grid is highlighted, it will operate only inside the marked area. Pressing the down arrow inside the bitmap window has the same effect.
Rotate Right	This command rotates the bitmap image 90 degrees to the right (clockwise.) If a marked area of the grid is highlighted, it will operate only inside the marked area. Pressing R inside the bitmap window has the same effect.
Point	This command will change the grid squares underneath the mouse pointer if a mouse button is being pressed down. If you drag the mouse button continuously, the line may not be continuous, depending on the speed of your system and frequency of mouse motion events.
Curve	This command will change the grid squares underneath the mouse pointer if a mouse button is being pressed down. If you drag the mouse button continuously, it will make sure that the line is continuous. If your system is slow or bitmap receives very few mouse motion events, it might behave quite strangely.
Line	This command will change the grid squares in a line between two squares. Once you press a mouse button in the grid window, bitmap will highlight the line from the square where the mouse button was initially pressed to the square where the mouse pointer is located. By releasing the mouse button, you will cause the change to take effect, and the highlighted line will disappear.
Rectangle	This command will change the grid squares in a rectangle between two squares. Once you press a mouse button in the grid window, bitmap will highlight the rectangle from the square where the mouse button was initially pressed to the square where the mouse pointer is located. By releasing the mouse button you will cause the change to take effect, and the highlighted rectangle will disappear.
Filled Rectangle	This command is identical to Rectangle, except at the end the rectangle will be filled rather than outlined.
Circle	This command will change the grid squares in a circle between two squares. Once you press a mouse button in the grid window, bitmap will highlight the circle from the square where the mouse button was initially pressed to the square where the mouse pointer is located. By releasing the mouse button you will cause the change to take effect, and the highlighted circle will disappear.
Filled Circle	This command is identical to Circle, except at the end the circle will be filled rather than outlined.
Flood Fill	This command will flood fill the connected area underneath the mouse pointer when you click on the desired square. Diagonally adjacent squares are not considered to be connected.

Set Hot Spot	This command designates one square in the grid as the hot spot if this bitmap image is to be used for defining a cursor. Pressing a mouse button in the desired square will cause a diamond shape to be displayed.
Clear Hot Spot	This command removes any designated hot spot from the bitmap image.
Undo	This command will undo the last executed command. It has depth one, that is, pressing Undo after Undo will undo itself.

FILE MENU

The File menu commands can be accessed by pressing the File button and selecting the appropriate menu entry, or by pressing the Ctrl key with another key. These commands deal with files and global bitmap parameters, such as size, basename, filename, and so forth.

New	This command will clear the editing area and prompt for the name of the new file to be edited. It will not load in the new file.
Load	This command is used to load a new bitmap file into the bitmap editor. If the current image has not been saved, user will be asked whether to save or ignore the changes. The editor can edit only one file at a time. If you need interactive editing, run a number of editors and use the cut and paste mechanism as described later in this section. (See “Cut and Paste.”)
Insert	This command is used to insert a bitmap file into the image being currently edited. After being prompted for the filename, click inside the grid window and drag the outlined rectangle to the location where you want to insert the new file.
Save	This command will save the bitmap image. It will not prompt for the filename unless it is said to be <none>. If you leave the filename undesignated or –, the output will be piped to stdout.
Save As	This command will save the bitmap image after prompting for a new filename. It should be used if you want to change the filename.
Resize	This command is used to resize the editing area to the new number of pixels. The size should be entered in the width,height format. The information in the image being edited will not be lost unless the new size is smaller than the current image size. The editor was not designed to edit huge files.
Rescale	This command is used to rescale the editing area to the new width and height. The size should be entered in the width,height format. It will not do antialiasing and information will be lost if you rescale to the smaller sizes. Feel free to add your own algorithms for better rescaling.
Filename	This command is used to change the filename without changing the basename nor saving the file. If you specify – for a filename, the output will be piped to stdout.
Basename	This command is used to change the basename, if a different one from the specified filename is desired.
Quit	This command will terminate the bitmap application. If the file was not saved, user will be prompted and asked whether to save the image or not. Quit is preferred over killing the process.

EDIT MENU

The Edit menu commands can be accessed by pressing the Edit button and selecting the appropriate menu entry, or by pressing Meta key with another key. These commands deal with editing facilities such as grid, axes, zooming, cut and paste, and so on.

Image	This command will display the image being edited and its inverse in its actual size in a separate window. The window can be moved away to continue with editing. Pressing the left mouse button in the image window will cause it to disappear from the screen.

Grid	This command controls the grid in the editing area. If the grid spacing is below the value specified by <code>gridTolerance</code> resource (8 by default), the grid will be automatically turned off. It can be enforced by explicitly activating this command.
Dashed	This command controls the stipple for drawing the grid lines. The stipple specified by <code>dashes</code> resource can be turned on or off by activating this command.
Axes	This command controls the highlighting of the main axes of the image being edited. The actual lines are not part of the image. They are provided to aid user when constructing symmetrical images, or whenever having the main axes highlighted helps your editing.
Stippled	This command controls the stippling of the highlighted areas of the bitmap image. The stipple specified by <code>stipple</code> resource can be turned on or off by activating this command.
Proportional	This command controls the proportional mode. If the proportional mode is on, width and height of all image squares are forced to be equal, regardless of the proportions of the bitmap window.
Zoom	This command controls the zoom mode. If there is a marked area of the image already displayed, bitmap will automatically zoom into it. Otherwise, the user will have to highlight an area to be edited in the zoom mode and bitmap will automatically switch into it. You can use all the editing commands and other utilities in the zoom mode. When you zoom out, undo command will undo the whole zoom session.
Cut	This command cuts the contents of the highlighted image area into the internal cut and paste buffer.
Copy	This command copies the contents of the highlighted image area into the internal cut and paste buffer.
Paste	This command will check if there are any other bitmap applications with a highlighted image area, or if there is something in the internal cut and paste buffer and copy it to the image. To place the copied image, click in the editing window and drag the outlined image to the position where you want to place it, and then release the button.

CUT AND PASTE

Bitmap supports two cut and paste mechanisms; the internal cut and paste and the global X selection cut and paste. The internal cut and paste is used when executing copy and move drawing commands and also cut and copy commands from the Edit menu. The global X selection cut and paste is used whenever there is a highlighted area of a bitmap image displayed anywhere on the screen. To copy a part of image from another bitmap editor, simply highlight the desired area by using the Mark command or pressing the shift key and dragging the area with the left mouse button. When the selected area becomes highlighted, any other applications (such as xterm) that use primary selection will discard their selection values and unhighlight the appropriate information. Now, use the Paste command from the Edit menu or control mouse button to copy the selected part of image into another (or the same) bitmap application. If you attempt to do this without a visible highlighted image area, the bitmap will fall back to the internal cut and paste buffer and paste whatever was stored there at the moment.

WIDGETS

Following is the widget structure of the bitmap application. The widget class name is given first, followed by the widget instance name. All widgets except the bitmap widget are from the standard Athena widget set.

```
Bitmap bitmap
TransientShell image
Box box
Label normalImage
Label invertedImage
TransientShell input
```

Dialog dialog
 Command okay
 Command cancel
 TransientShell error
 Dialog dialog
 Command abort
 Command retry
 TransientShell qsave
 Dialog dialog
 Command yes
 Command no
 Command cancel
 Paned parent
 Form formy
 MenuButton fileButton
 SimpleMenu fileMenu
 SmeBSB new
 SmeBSB load
 SmeBSB insert
 SmeBSB save
 SmeBSB saveAs
 SmeBSB resize
 SmeBSB rescale
 SmeBSB filename
 SmeBSB basename
 SmeLine line
 SmeBSB quit
 MenuButton editButton
 SimpleMenu editMenu
 SmeBSB image
 SmeBSB grid
 SmeBSB dashed
 SmeBSB axes
 SmeBSB stippled
 SmeBSB proportional
 SmeBSB zoom
 SmeLine line
 SmeBSB cut
 SmeBSB copy
 SmeBSB paste
 Label status
 Pane pane
 Bitmap bitmap
 Form form
 Command clear
 Command set
 Command invert
 Toggle mark
 Command unmark
 Toggle copy
 Toggle move
 Command flipHoriz
 Command up
 Command flipVert
 Command left
 Command fold
 Command right
 Command rotateLeft
 Command down
 Command rotateRight

```

Toggle point
Toggle curve
Toggle line
Toggle rectangle
Toggle filledRectangle
Toggle circle
Toggle filledCircle
Toggle floodFill
Toggle setHotSpot
Command clearHotSpot
Command undo

```

COLORS

If you would like bitmap to be viewable in color, include the following in the `#ifdef COLOR` section of the file you read with `xrdb`:

```
*customization: -color
```

This will cause bitmap to pick up the colors in the app-defaults color customization file:

```
<XRoot>/lib/X11/app-defaults/Bitmap-color
```

where `<XRoot>` refers to the root of the X11 install tree.

BITMAP WIDGET

Bitmap widget is a standalone widget for editing raster images. It is not designed to edit large images, although it may be used in that purpose as well. It can be freely incorporated with other applications and used as a standard editing tool. The following are the resources provided by the bitmap widget:

Header file	Bitmap.h
Class	bitmapWidgetClass
Class Name	Bitmap
Superclass	Bitmap

All the Simple Widget resources plus...

<i>Name</i>	<i>Class</i>	<i>Type</i>	<i>Default Value</i>
foreground	Foreground	Pixel	XtDefaultForeground
highlight	Highlight	Pixel	XtDefaultForeground
framing	Framing	Pixel	XtDefaultForeground
gridTolerance	GridTolerance	Dimension	8
size	Size	String	32x32
dashed	Dashed	Boolean	True
grid	Grid	Boolean	True
stippled	Stippled	Boolean	True
proportional	Proportional	Boolean	True
axes	Axes	Boolean	False
squareWidth	SquareWidth	Dimension	16
squareHeight	SquareHeight	Dimension	16
margin	Margin	Dimension	16
xHot	XHot	Position	NotSet (−1)
yHot	YHot	Position	NotSet (−1)
button1Function	Button1Function	DrawingFunction	Set

<i>Name</i>	<i>Class</i>	<i>Type</i>	<i>Default Value</i>
button2Function	Button2Function	DrawingFunction	Invert
button3Function	Button3Function	DrawingFunction	Clear
button4Function	Button4Function	DrawingFunction	Invert
button5Function	Button5Function	DrawingFunction	Invert
filename	Filename	String	None (“”)
basename	Basename	String	None (“”)

AUTHOR

Davor Matic (MIT X Consortium)

X Version 11 Release 6

bmptoppm

bmptoppm—Convert a BMP file into a portable pixmap

SYNOPSIS

bmptoppm [bmpfile]

DESCRIPTION

bmptoppm reads a Microsoft Windows or OS/2 BMP file as input and produces a portable pixmap as output.

SEE ALSO

ppmtobmp(1), ppm(5)

AUTHOR

Copyright © 1992 by David W. Sanderson

26 October 1992

brushtopbm

brushtopbm—Convert a doodle brush file into a portable bitmap

SYNOPSIS

brushtopbm [brushfile]

DESCRIPTION

brushtopbm reads a Xerox doodle brush file as input and produces a portable bitmap as output.

Note that there is currently no pbmtobrush tool.

SEE ALSO

pbm(5)

AUTHOR

Copyright © 1988 by Jef Poskanzer

28 August 1988

cal

cal—Displays a calendar

SYNOPSIS

```
cal [-jy] [month [year]]
```

DESCRIPTION

cal displays a simple calendar. If arguments are not specified, the current month is displayed. The options are as follows:

- j Display Julian dates (days one-based, numbered from January 1)
- y Display a calendar for the current year

A single parameter specifies the year (1–9999) to be displayed; note the year must be fully specified:

```
cal 89
```

will not display a calendar for 1989. Two parameters denote the month (1–12) and year. If no parameters are specified, the current month's calendar is displayed.

A year starts on Jan 1.

The Gregorian Reformation is assumed to have occurred in 1752 on the 3rd of September. By this time, most countries had recognized the reformation (although a few did not recognize it until the early 1900s.) Ten days following that date were eliminated by the reformation, so the calendar for that month is a bit unusual.

HISTORY

A **cal** command appeared in version 6 AT&T UNIX

6 June 1993

cat

cat—Concatenate files and print on the standard output

SYNOPSIS

```
cat [-benstuvAET] [—number] [—number-nonblank] [—squeeze-blank]
```

```
[-show-nonprinting] [-show-ends] [-show-tabs] [-show-all]
```

```
[-help] [-version] [file...]
```

DESCRIPTION

This manual page documents the GNU version of **cat**. **cat** writes the contents of each given file, or the standard input if none are given or when a file named **-** is given, to the standard output.

OPTIONS

- b, —number-nonblank Number all nonblank output lines, starting with 1.
- e Equivalent to -vE.
- n, —number Number all output lines, starting with 1.
- s, —squeeze-blank Replace multiple adjacent blank lines with a single blank line.
- t Equivalent to -vT.
- u Ignored; for UNIX compatibility.

<code>-v, --show-nonprinting</code>	Display control characters except for LFD and TAB using ^ notation and precede characters that have the high bit set with M-.
<code>-A, --show-all</code>	Equivalent to <code>-vET</code> .
<code>-E, --show-ends</code>	Display a \$ after the end of each line.
<code>-T, --show-tabs</code>	Display tab characters as ^I.
<code>--help</code>	Print a usage message and exit with a nonzero status.
<code>--version</code>	Print version information on standard output then exit.

GNU Text Utilities

chattr

chattr—Change file attributes on a Linux second extended file system

SYNOPSIS

```
chattr [ -RV ][-v version] [ mode ] files...
```

DESCRIPTION

chattr changes the files attributes on an second extended file system. The format of a symbolic mode is `+-=[sacdisu]`.

The operator `+` causes the selected attributes to be added to the existing attributes of the files; `-` causes them to be removed; and `=` causes them to be the only attributes that the files have. The letters `sacdisu` select the new attributes for the files: synchronous updates (`s`), append only (`a`), compressed (`χ`), immutable(`i`), nodump (`d`), securedeletion (`s`), and undeletable (`u`).

OPTIONS

<code>-R</code>	Recursively change attributes of directories and their contents.
<code>-V</code>	Verbosely describe changed attributes.
<code>-v version</code>	Set the file's version.

ATTRIBUTES

A file with the `a` attribute set can only be open in append mode for writing.

A file with the `c` attribute set is automatically compressed on the disk by the kernel. A read from this file returns uncompressed data. A write to this file compresses data before storing them on the disk.

A file with the `d` attribute set is not candidate for backup when the `dump(8)` program is run.

A file with the `i` attribute cannot be modified: it cannot be deleted or renamed, no link can be created to this file and no data can be written to the file. Only the superuser can set or clear this attribute.

When a file with the `s` attribute set is deleted, its blocks are zeroed and written back to the disk.

When a file with the `u` attribute set is modified, the changes are written synchronously on the disk; this is equivalent to the `syn` mount option applied to a subset of the files.

When a file with the `u` attribute set is deleted, its contents is saved. This allows the user to ask for its undeletion.

AUTHOR

chattr has been written by Remy Card, <card@masi.ibp.fr>, the developer and maintainer of the `ext2 fs`.

BUGS AND LIMITATIONS

As of `ext2 fs 0.5a`, the `c` and `u` attributes are not honored by the kernel code.

These attributes will be implemented in a future `ext2 fs` version.

AVAILABILITY

chattr is available for anonymous ftp from ftp.ibp.fr and tsx-11.mit.edu in /pub/linux/packages/ext2fs.

SEE ALSO

lsattr(1)

Version 0.5b, November 1994

chfn

chfn—Change your finger information

SYNOPSIS

```
chfn [ -f full-name ][-o office][-p office-phone ] [ -h home-phone ] [ -u ] [ -v ]
[username ]
```

DESCRIPTION

chfn is used to change your finger information. This information is stored in the /etc/passwd file, and is displayed by the finger program. The Linux finger command will display four pieces of information that can be changed by chfn: your real name, your work room and phone, and your home phone.

COMMAND LINE

Any of the four pieces of information can be specified on the command line. If no information is given on the command line, chfn enters interactive mode.

INTERACTIVE MODE

In interactive mode, chfn will prompt for each field. At a prompt, you can enter the new information, or just press return to leave the field unchanged. Enter the keyword none to make the field blank.

OPTIONS

-f, --full-name	Specify your real name.
-o, --office	Specify your office room number.
-p, --office-phone	Specify your office phone number.
-h, --home-phone	Specify your home phone number.
-u, --help	Print a usage message and exit.
-v, --version	Print version information and exit.

SEE ALSO

finger(1), passwd(5)

AUTHOR

Salvatore Valente (<svalente@mit.edu>)

chfn, October 13 1994

chgrp

chgrp—Change the group ownership of files

SYNOPSIS

```
chgrp [-Rcfv] [--recursive] [--changes] [--silent] [--quiet] [--verbose] [--help]
      [--version] group file...
```

DESCRIPTION

This manual page documents the GNU version of chgrp. chgrp changes the group ownership of each given file to the named group, which can be either a group name or a numeric group ID.

OPTIONS

-c, --changes	Verbosely describe only files whose ownership actually changes.
-f, --silent, --quiet	Do not print error messages about files whose ownership cannot be changed.
-v, --verbose	Verbosely describe ownership changes.
-R, --recursive	Recursively change ownership of directories and their contents.
--help	Print a usage message on standard output and exit successfully.
--version	Print version information on standard output, then exit successfully.

GNU File Utilities

chkdupexe

chkdupexe—Find duplicate executables

SYNOPSIS

```
chkdupexe
```

DESCRIPTION

chkdupexe will scan many standard directories that hold executable, and report duplicates.

AUTHOR

Nicolai Langfeldt

BUGS

Requires GNU 1s(1).

Search paths that point to the same directory will cause many bogus duplicates to be found. You might want to edit the script to eliminate some paths that are equivalent on your machine.

11 March 1995

chmod

chmod—Change the access permissions of files

SYNOPSIS

```
chmod [-Rcfv] [--recursive] [--changes] [--silent] [--quiet] [--verbose] [--help]
      [--version] mode file...
```

DESCRIPTION

This manual page documents the GNU version of `chmod`. `chmod` changes the permissions of each given file according to mode, which can be either a symbolic representation of changes to make, or an octal number representing the bit pattern for the new permissions.

The format of a symbolic mode is `[ugoa...][[+-=][rwxXstugo...]]...[,...]`. Multiple symbolic operations can be given, separated by commas.

A combination of the letters `ugoa` controls which users' access to the file will be changed: the user who owns it (`u`), other users in the file's group (`g`), other users not in the file's group (`o`), or all users (`a`). If none of these are given, the effect is as if `a` were given, but bits that are set in the umask are not affected.

The operator `+` causes the permissions selected to be added to the existing permissions of each file; `-` causes them to be removed; and `=` causes them to be the only permissions that the file has.

The letters `rwxXstugo` select the new permissions for the affected users: read (`r`), write (`w`), execute (or access for directories) (`x`), execute only if the file is a directory or already has execute permission for some user (`X`), set user or group ID on execution (`s`), save program text on swap device (`t`), the permissions that the user who owns the file currently has for it (`u`), the permissions that other users in the file's group have for it (`g`), and the permissions that other users not in the file's group have for it (`o`).

A numeric mode is from one to four octal digits (0–7), derived by adding up the bits with values 4, 2, and 1. Any omitted digits are assumed to be leading zeros. The first digit selects the set user ID (4) and set group ID (2) and save text image (1) attributes. The second digit selects permissions for the user who owns the file: read (4), write (2), and execute (1); the third selects permissions for other users in the file's group, with the same values; and the fourth for other users not in the file's group, with the same values.

`chmod` never changes the permissions of symbolic links; the `chmod` system call cannot change their permissions. This is not a problem since the permissions of symbolic links are never used. However, for each symbolic link listed on the command line, `chmod` changes the permissions of the pointed-to file. In contrast, `chmod` ignores symbolic links encountered during recursive directory traversals.

OPTIONS

<code>-c</code> , <code>--changes</code>	Verbosely describe only files whose permissions actually change.
<code>-f</code> , <code>--silent</code> , <code>--quiet</code>	Do not print error messages about files whose permissions cannot be changed.
<code>-v</code> , <code>--verbose</code>	Verbosely describe changed permissions.
<code>-R</code> , <code>--recursive</code>	Recursively change permissions of directories and their contents.
<code>--help</code>	Print a usage message on standard output and exit successfully.
<code>--version</code>	Print version information on standard output, then exit successfully.

GNU File Utilities

chown

`chown`—Change the user and group ownership of files

SYNOPSIS

```
chown [-Rcfv] [-recursive] [-changes] [-help] [-version] [-silent] [-quiet]
      [-verbose] [user][:.] [group] file...
```

DESCRIPTION

This manual page documents the GNU version of `chown`. `chown` changes the user and/or group ownership of each given file, according to its first nonoption argument, which is interpreted as follows. If only a username (or numeric user ID) is given, that user is made the owner of each given file, and the files' group is not changed. If the username is followed by a colon or dot and a group name (or numeric group ID), with no spaces between them, the group ownership of the files is changed as well. If a colon or dot but no group name follows the username, that user is made the owner of the files and the group of the files is changed to that user's login group. If the colon or dot and group are given, but the username is omitted, only the group of the files is changed; in this case, `chown` performs the same function as `chgrp`.

OPTIONS

<code>-c</code> , <code>--changes</code>	Verbosely describe only files whose ownership actually changes.
<code>-f</code> , <code>--silent</code> , <code>--quiet</code>	Do not print error messages about files whose ownership cannot be changed.
<code>-v</code> , <code>--verbose</code>	Verbosely describe ownership changes.
<code>-R</code> , <code>--recursive</code>	Recursively change ownership of directories and their contents.
<code>-help</code>	Print a usage message on standard output and exit successfully.
<code>--version</code>	Print version information on standard output then exit successfully.

GNU File Utilities

chsh

chsh—Change your login shell

SYNOPSIS

```
chsh [ -s shell ] [ -l ] [ -u ] [ -v ] [ username ]
```

DESCRIPTION

`chsh` is used to change your login shell. If a shell is not given on the command line, `chsh` prompts for one.

VALID SHELLS

`chsh` will accept the full pathname of any executable file on the system. However, it will issue a warning if the shell is not listed in the `/etc/shells` file.

OPTIONS

<code>-s</code> , <code>--shell</code>	Specify your login shell.
<code>-l</code> , <code>--list-shells</code>	Print the list of shells listed in <code>/etc/shells</code> and exit.
<code>-u</code> , <code>--help</code>	Print a usage message and exit.
<code>-v</code> , <code>--version</code>	Print version information and exit.

SEE ALSO

`login(1)`, `passwd(5)`, `shells(5)`

AUTHOR

Salvatore Valente (<svalente@mit.edu>)

chsh, 13 October 1994

ci

ci—Check in RCS revisions

SYNOPSIS

```
ci [options] file ...
```

DESCRIPTION

ci stores new revisions into RCS files. Each pathname matching an RCS suffix is taken to be an RCS file. All others are assumed to be working files containing new revisions. ci deposits the contents of each working file into the corresponding RCS file. If only a working file is given, ci tries to find the corresponding RCS file in an RCS subdirectory and then in the working file's directory. (For more details, see "File Naming," later in this manual page.)

For ci to work, the caller's login must be on the access list, unless the access list is empty or the caller is the superuser or the owner of the file. To append a new revision to an existing branch, the tip revision on that branch must be locked by the caller. Otherwise, only a new branch can be created. This restriction is not enforced for the owner of the file if non-strict locking is used; see rcs(1). A lock held by someone else can be broken with the rcs command.

Unless the -f option is given, ci checks whether the revision to be deposited differs from the preceding one. If not, instead of creating a new revision ci reverts to the preceding one. To revert, ordinary ci removes the working file and any lock; ci -l keeps and ci -u removes any lock, and then they both generate a new working file much as if co -l or co -u had been applied to the preceding revision. When reverting, any -n and -s options apply to the preceding revision.

For each revision deposited, ci prompts for a log message. The log message should summarize the change and must be terminated by end-of-file or by a line containing . by itself. If several files are checked in, ci asks whether to reuse the previous log message. If the standard input is not a terminal, ci suppresses the prompt and uses the same log message for all files. (See also -m.)

If the RCS file does not exist, ci creates it and deposits the contents of the working file as the initial revision (default number: 1.1). The access list is initialized to empty. Instead of the log message, ci requests descriptive text (See -t.)

The number rev of the deposited revision can be given by any of the options -f, -i, -I, -j, -k, -l, -M, -q, -r, or -u. rev can be symbolic, numeric, or mixed. Symbolic names in rev must already be defined; see the -n and -N options for assigning names during checkin. If rev is \$, ci determines the revision number from keyword values in the working file.

If rev begins with a period, then the default branch (normally the trunk) is prepended to it. If rev is a branch number followed by a period, then the latest revision on that branch is used.

If rev is a revision number, it must be higher than the latest one on the branch to which rev belongs, or must start a new branch.

If rev is a branch rather than a revision number, the new revision is appended to that branch. The level number is obtained by incrementing the tip revision number of that branch. If rev indicates a nonexistent branch, that branch is created with the initial revision numbered rev.1.

If rev is omitted, ci tries to derive the new revision number from the caller's last lock. If the caller has locked the tip revision of a branch, the new revision is appended to that branch. The new revision number is obtained by incrementing the tip revision number. If the caller locked a nontip revision, a new branch is started at that revision by incrementing the highest branch number at that revision. The default initial branch and level numbers are 1.

If rev is omitted and the caller has no lock, but owns the file and locking is not set to strict, then the revision is appended to the default branch. (Normally the trunk; see the -b option of rcs(1).)

Exception: On the trunk, revisions can be appended to the end, but not inserted.

OPTIONS

<code>-r rev</code>	Check in revision <i>rev</i> .
<code>-r</code>	The bare <code>-r</code> option (without any revision) has an unusual meaning in <i>ci</i> . With other RCS commands, a bare <code>-r</code> option specifies the most recent revision on the default branch, but with <i>ci</i> , a bare <code>-r</code> option reestablishes the default behavior of releasing a lock and removing the working file, and is used to override any default <code>-l</code> or <code>-u</code> options established by shell aliases or scripts.
<code>-l[rev]</code>	Works like <code>-r</code> , except it performs an additional <code>co -l</code> for the deposited revision. Thus, the deposited revision is immediately checked out again and locked. This is useful for saving a revision although one wants to continue editing it after the checkin.
<code>-u[rev]</code>	Works like <code>-l</code> , except that the deposited revision is not locked. This lets one read the working file immediately after checkin.
The <code>-l</code> , bare <code>-r</code> , and <code>-u</code> options are mutually exclusive and silently override each other. For example, <code>ci -u -r</code> is equivalent to <code>ci -r</code> because bare <code>-r</code> overrides <code>-u</code> .	
<code>-f[rev]</code>	Forces a deposit; the new revision is deposited even it is not different from the preceding one.
<code>-k[rev]</code>	Searches the working file for keyword values to determine its revision number, creation date, state, and author—see <code>co(1)</code> —and assigns these values to the deposited revision, rather than computing them locally. It also generates a default login message noting the login of the caller and the actual checkin date. This option is useful for software distribution. A revision that is sent to several sites should be checked in with the <code>-k</code> option at these sites to preserve the original number, date, author, and state. The extracted keyword values and the default log message can be overridden with the options <code>-d</code> , <code>-m</code> , <code>-s</code> , <code>-w</code> , and any option that carries a revision number.
<code>-q[rev]</code>	Quiet mode; diagnostic output is not printed. A revision that is not different from the preceding one is not deposited, unless <code>-f</code> is given.
<code>-i[rev]</code>	Initial checkin; report an error if the RCS file already exists. This avoids race conditions in certain applications.
<code>-j[rev]</code>	Just check in and do not initialize; report an error if the RCS file does not already exist.
<code>-I[rev]</code>	Interactive mode; the user is prompted and questioned even if the standard input is not a terminal.
<code>-d[date]</code>	Uses <i>date</i> for the checkin date and time. The date is specified in free format as explained in <code>co(1)</code> . This is useful for lying about the checkin date, and for <code>-k</code> if no date is available. If <i>date</i> is empty, the working file's time of last modification is used.
<code>-M[rev]</code>	Set the modification time on any new working file to be the date of the retrieved revision. For example, <code>ci -d -M -u f</code> does not alter <i>f</i> 's modification time, even if <i>f</i> 's contents change due to keyword substitution. Use this option with care; it can confuse <code>make(1)</code> .
<code>-mmsg</code>	Uses the string <i>msg</i> as the log message for all revisions checked in. By convention, log messages that start with <code>#</code> are comments and are ignored by programs like GNU <i>emacs</i> 's <i>vc</i> package. Also, log messages that start with <i>clumpname</i> (followed by whitespace) are meant to be clumped together if possible, even if they are associated with different files; the <i>clumpname</i> label is used only for clumping, and is not considered to be part of the log message itself.
<code>-nname</code>	Assigns the symbolic name to the number of the checked-in revision. <i>ci</i> prints an error message if that name is already assigned to another number.
<code>-Nname</code>	Same as <code>-n</code> , except that it overrides a previous assignment of name.
<code>-ssstate</code>	Sets the state of the checked-in revision to the identifier state. The default state is <i>Exp</i> .
<code>-t file</code>	Writes descriptive text from the contents of the named file into the RCS file, deleting the existing text. The file cannot begin with <code>-</code> .
<code>-t-string</code>	Write descriptive text from the string into the RCS file, deleting the existing text.

The `-t` option, in both its forms, has effect only during an initial checkin; it is silently ignored otherwise.

During the initial checkin, if `-t` is not given, *ci* obtains the text from standard input, terminated by end-of-file or by a line containing a dot (`.`) by itself. The user is prompted for the text if interaction is possible; see `-I`.

For backwards compatibility with older versions of RCS, a bare `-t` option is ignored.

<code>-T</code>	Set the RCS file's modification time to the new revision's time if the former precedes the latter and there is a new revision; preserve the RCS file's modification time otherwise. If you have locked a revision, <code>ci</code> usually updates the RCS file's modification time to the current time, because the lock is stored in the RCS file and removing the lock requires changing the RCS file. This can create an RCS file newer than the working file in one of two ways: first, <code>ci -M</code> can create a working file with a date before the current time; second, when reverting to the previous revision the RCS file can change while the working file remains unchanged. These two cases can cause excessive recompilation caused by a <code>make(1)</code> dependency of the working file on the RCS file. The <code>-T</code> option inhibits this recompilation by lying about the RCS file's date. Use this option with care; it can suppress recompilation even when a checkin of one working file should affect another working file associated with the same RCS file. For example, suppose the RCS file's time is 01:00, the (changed) working file's time is 02:00, some other copy of the working file has a time of 03:00, and the current time is 04:00. Then <code>ci -d -T</code> sets the RCS file's time to 02:00 instead of the usual 04:00; this causes <code>make(1)</code> to think (incorrectly) that the other copy is newer than the RCS file.
<code>-wlogin</code>	Uses <code>login</code> for the author field of the deposited revision. Useful for lying about the author, and for <code>-k</code> if no author is available.
<code>-V</code>	Print RCS's version number.
<code>-Vn</code>	Emulate RCS version <i>n</i> . See <code>co(1)</code> for details.
<code>-xsuffixes</code>	Specifies the suffixes for RCS files. A nonempty suffix matches any pathname ending in the suffix. An empty suffix matches any pathname of the form <code>RCS/path</code> or <code>path1/RCS/path2</code> . The <code>-x</code> option can specify a list of suffixes separated by <code>/</code> . For example, <code>-x,v/</code> specifies two suffixes: <code>,v</code> and the empty suffix. If two or more suffixes are specified, they are tried in order when looking for an RCS file; the first one that works is used for that file. If no RCS file is found but an RCS file can be created, the suffixes are tried in order to determine the new RCS file's name. The default for suffixes is installation-dependent; normally it is <code>,v/</code> for hosts like UNIX that permit commas in filenames, and is empty (that is, just the empty suffix) for other hosts.
<code>-zzone</code>	Specifies the date output format in keyword substitution, and specifies the default time zone for date in the <code>-ddate</code> option. The zone should be empty, a numeric UTC offset, or the special string <code>LT</code> for local time. The default is an empty zone, which uses the traditional RCS format of UTC without any time-zone indication and with slashes separating the parts of the date; otherwise, times are output in ISO 8601 format with time zone indication. For example, if local time is January 11, 1990, 8 p.m. Pacific Standard Time, eight hours west of UTC, then the time is output as follows:

Option	Time Output
<code>-z</code>	1990/01/12 04:00:00 (default)
<code>-zLT</code>	1990-01-11 20:00:00-08
<code>-z+05:30</code>	1990-01-12 09:30:00+05:30

The `-z` option does not affect dates stored in RCS files, which are always UTC.

FILE NAMING

Pairs of RCS files and working files can be specified in three ways. (See also "Examples," next.)

- Both the RCS file and the working file are given. The RCS pathname is of the form `path1/workfileX` and the working pathname is of the form `path2/workfile` where `path1/` and `path2/` are (possibly different or empty) paths, `workfile` is a filename, and `X` is an RCS suffix. If `X` is empty, `path1/` must start with `RCS/` or must contain `/RCS/`.
- Only the RCS file is given. Then the working file is created in the current directory and its name is derived from the name of the RCS file by removing `path1/` and the suffix `X`.

3. Only the working file is given. Then `ci` considers each RCS suffix `X` in turn, looking for an RCS file of the form `path2/RCS/workfileX` or (if the former is not found and `X` is nonempty) `path2/workfileX`.

If the RCS file is specified without a path in one of the first two preceding scenarios, `ci` looks for the RCS file first in the directory `./RCS` and then in the current directory.

`ci` reports an error if an attempt to open an RCS file fails for an unusual reason, even if the RCS file's pathname is just one of several possibilities. For example, to suppress use of RCS commands in a directory `d`, create a regular file named `d/RCS` so that casual attempts to use RCS commands in `d` fail because `d/RCS` is not a directory.

EXAMPLES

Suppose `,v` is an RCS suffix and the current directory contains a subdirectory `RCS` with an RCS file `io.c,v`. Then each of the following commands checks in a copy of `io.c` into `RCS/io.c,v` as the latest revision, removing `io.c`:

```
ci io.c; ci RCS/io.c,v; ci io.c,v;
ci io.c RCS/io.c,v; ci io.c io.c,v;
ci RCS/io.c,v io.c; ci io.c,v io.c;
```

Suppose instead that the empty suffix is an RCS suffix and the current directory contains a subdirectory `RCS` with an RCS file `io.c`. Then each of the following commands checks in a new revision:

```
ci io.c; ci RCS/io.c;
ci io.c RCS/io.c;
ci RCS/io.c io.c;
```

FILE MODES

An RCS file created by `ci` inherits the read and execute permissions from the working file. If the RCS file exists already, `ci` preserves its read and execute permissions. `ci` always turns off all write permissions of RCS files.

FILES

Temporary files are created in the directory containing the working file, and also in the temporary directory. (See `TMPDIR` under "Environment.") A semaphore file or files are created in the directory containing the RCS file. With a nonempty suffix, the semaphore names begin with the first character of the suffix; therefore, do not specify a suffix whose first character could be that of a working filename. With an empty suffix, the semaphore names end with an underscore (`_`), so working filenames should not end in `_`. `ci` never changes an RCS or working file. Normally, `ci` unlinks the file and creates a new one; but instead of breaking a chain of one or more symbolic links to an RCS file, it unlinks the destination file instead. Therefore, `ci` breaks any hard or symbolic links to any working file it changes; and hard links to RCS files are ineffective, but symbolic links to RCS files are preserved.

The effective user must be able to search and write the directory containing the RCS file. Normally, the real user must be able to read the RCS and working files and to search and write the directory containing the working file; however, some older hosts cannot easily switch between real and effective users, so on these hosts the effective user is used for all accesses. The effective user is the same as the real user unless your copies of `ci` and `co` have `setuid` privileges. These privileges yield extra security if the effective user owns all RCS files and directories, and if only the effective user can write RCS directories.

Users can control access to RCS files by setting the permissions of the directory containing the files; only users with write access to the directory can use RCS commands to change its RCS files. For example, in hosts that allow a user to belong to several groups, one can make a group's RCS directories writable to that group only. This approach suffices for informal projects, but it means that any group member can arbitrarily change the group's RCS files, and can even remove them entirely. Hence, more formal projects sometimes distinguish between an RCS administrator, who can change the RCS files at will, and other project members, who can check in new revisions but cannot otherwise change the RCS files.

setuid USE

To prevent anybody but their RCS administrator from deleting revisions, a set of users can employ `setuid` privileges as follows:

- Check that the host supports RCS `setuid` use. Consult a trustworthy expert if there are any doubts. It is best if the `setuid` system calls works as described in POSIX 1003.1a Draft 5, because RCS can switch back and forth easily between real and effective users, even if the real user is `root`. If not, the second best is if the `setuid` system call supports saved `setuid` (the `{_POSIX_SAVED_IDS}` behavior of POSIX 1003.1-1990); this fails only if the real or effective user is `root`. If RCS detects any failure in `setuid`, it quits immediately.
- Choose a user A to serve as RCS administrator for the set of users. Only A can invoke the `rcs` command on the users' RCS files. A should not be `root` or any other user with special powers. Mutually suspicious sets of users should use different administrators.
- Choose a pathname B to be a directory of files to be executed by the users.
- Have A set up B to contain copies of `ci` and `co` that are `setuid` to A by copying the commands from their standard installation directory D as follows:

```
mkdir B cp D/c[io] B chmod go-w,u+s B/c[io]
```
- Have each user prepend B to his/her path as follows:

```
PATH=B:$PATH; export PATH # ordinary shell
set path=(B $path) # C shell
```
- Have A create each RCS directory R with write access only to A as follows:

```
mkdir R chmod go-w R
```
- If you want to let only certain users read the RCS files, put the users into a group G, and have A further protect the RCS directory as follows:

```
chgrp G Rchmod g-w,o-rwx R
```
- Have A copy old RCS files (if any) into R, to ensure that A owns them.
- An RCS file's access list limits who can check in and lock revisions. The default access list is empty, which grants checkin access to anyone who can read the RCS file. If you want limit checkin access, have A invoke `rcs -a` on the file; see `rcs(1)`. In particular, `rcs -e -aA` limits access to just A.
- Have A initialize any new RCS files with `rcs -i` before initial checkin, adding the `-a` option if you want to limit checkin access.
- Give `setuid` privileges only to `ci`, `co`, and `rcsclean`; do not give them to `rcs` or to any other command.
- Do not use other `setuid` commands to invoke RCS commands; `setuid` is trickier than you think!

ENVIRONMENT

<code>RCSINIT</code>	Options prepended to the argument list, separated by spaces. A backslash escapes spaces within an option. The <code>RCSINIT</code> options are prepended to the argument lists of most RCS commands. Useful <code>RCSINIT</code> options include <code>-q</code> , <code>-v</code> , <code>-x</code> , and <code>-z</code> .
<code>TMPDIR</code>	Name of the temporary directory. If not set, the environment variables <code>TMP</code> and <code>TEMPs0</code> are inspected instead and the first value found is taken; if none of them are set, a host-dependent default is used, typically <code>/tmp</code> .

DIAGNOSTICS

For each revision, `ci` prints the RCS file, the working file, and the number of both the deposited and the preceding revision. The exit status is zero if and only if all operations were successful.

IDENTIFICATION

Author: Walter F. Tichy.

Manual page revision: 5.17; Release date 16 June 1995

Copyright © 1982, 1988, 1989 Walter F. Tichy

Copyright © 1990, 1991, 1992, 1993, 1994, 1995 Paul Eggert

SEE ALSO

co(1), emacs(1), ident(1), make(1), rcs(1), rcsclean(1), rcsdiff(1), rcsintro(1), rcsmerge(1), rlog(1), setuid(2), rcsfile(5)

Walter F. Tichy, “RCS—A System for Version Control,” *Software Practice & Experience* 15, 7 (July 1985), 637–654.

GNU, 16 June 1995

cidentd

cidentd—identd server

SYNOPSIS

```
cidentd [-usqvnah] [-f file] [-l file] [-t seconds]
```

DESCRIPTION

cidentd gives authentication information.

cidentd is an RFC 1314- and 931-compliant identd daemon. It accepts connections on a port (113 default) and answers queries for port owner of a connection. command;

cidentd normally terminates when the remote command does. The options are as follows:

-u Turns on the use of the .authlie file in the user's home directory to give the requesting system whatever information the user provides. This file is overridden by the -a option and the system file the format is as follows:

mynameis	name-to-be-given	# give this userid
hideme		# hide user id
host-ip	name-to-be-given	# userid for them
host-ip	no-info	# hide you to them

host-ip can be an ip in dot notation or a name. The file is set so that whatever comes last is what they get.

-s Closes the connection after a single query.

-q Quits the daemon after 1 connection (default in 1.0b).

-v Turns on verbose logging to the syslogs.

-n Makes cident act like the old school identd with nothing special.

-a Enables the /etc/cident.users file for options, which overrides the user files if -u is specified. The format is as follows:

username	name-to-send	# send this for username
username		# must send there username
all	name-to-send	# send for every query
all	no-info	# send nothing every query
host-ip	name-to-send	# send to that host
host-ip	no-info	# send nothing to them

host-ip can be an ip in dot notation or a name. The file is set so that whatever comes last is what they get.

-h Displays the help list to the screen you might not want to do this from some terminal types.

-f Sets the file to find the ports and ids of connections. Use this to specify a file other than /proc/net/tcp.

-l Used to specify a file other than /etc/cident.users must be used with the -a option unless you like redundancy.

-t Sets the time out of a connection in seconds. This does not work in this version to cidentd.

If no arguments are specified, the program just runs as normal, almost like the `-n`.
`cidentd -t 30 -a` sets timer to 30 seconds and tells it to look at `.authlie` files.

FILES

`/etc/cidentd.users`
`$(HOME)/.authlie`

SEE ALSO

`identd(1)`

BUGS

None that I know of.

Linux/FreeBSD, May 1996

cksum

`cksum`—Checksum and count the bytes in a file

SYNOPSIS

`cksum [-help] [--version] [file...]`

DESCRIPTION

This manual page documents the GNU version of `cksum`. `cksum` computes a cyclic redundancy check (CRC) for each named file, or the standard input if none are given or when a file named `-` is given. It prints the CRC for each file along with the number of bytes in the file, and the filename unless no arguments were given.

`cksum` is typically used to make sure that files transferred by unreliable means (such as netnews) have not been corrupted. This is accomplished by comparing the `cksum` output for the received files with the `cksum` output for the original files. The CRC algorithm is specified by the POSIX.2 standard. It is not compatible with the BSD or System V `sum` programs; it is more robust.

Available options are

<code>-help</code>	Print a usage message and exit with a nonzero status.
<code>--version</code>	Print version information on standard output then exit.

GNU Text Utilities

clear

`clear`—Clear terminal screen

SYNOPSIS

`clear`

DESCRIPTION

`clear` calls `tput(1)` with the `clear` argument. This causes `tput` to attempt to clear the screen, checking the data in `/etc/termcap` (for the GNU or BSD `tput`) or in the `terminfo` database (for the `ncurses` `tput`) and sending the appropriate sequence to the terminal. This command can be redirected to clear the screen of some other terminal.

SEE ALSO

reset(1), stty(1), tput(1)

AUTHOR

Rik Faith (faith@cs.unc.edu)

Linux 0.99, 10 October 1993

cmuwmtopbm

cmuwmtopbm—Convert a CMU window manager bitmap into a portable bitmap

SYNOPSIS

cmuwmtopbm [cmuwmfile]

DESCRIPTION

Reads a CMU window manager bitmap as input. Produces a portable bitmap as output.

SEE ALSO

pbmto cmuwm(1), pbm(5)

AUTHOR

Copyright © 1989 by Jef Poskanzer

15 April 1989

CO

co—Check out RCS revisions

SYNOPSIS

co [options] file ...

DESCRIPTION

co retrieves a revision from each RCS file and stores it into the corresponding working file.

Pathnames matching an RCS suffix denote RCS files; all others denote working files. Names are paired as explained in ci(1).

Revisions of an RCS file can be checked out locked or unlocked. Locking a revision prevents overlapping updates. A revision checked out for reading or processing (for example, compiling) need not be locked. A revision checked out for editing and later checkin must normally be locked. Checkout with locking fails if the revision to be checked out is currently locked by another user. (A lock can be broken with rcs(1).) Checkout with locking also requires the caller to be on the access list of the RCS file, unless he is the owner of the file or the superuser, or the access list is empty. Checkout without locking is not subject to access list restrictions, and is not affected by the presence of locks.

A revision is selected by options for revision or branch number, checkin date/time, author, or state. When the selection options are applied in combination, co retrieves the latest revision that satisfies all of them. If none of the selection options is specified, co retrieves the latest revision on the default branch, normally the trunk; see the -b option of rcs(1). A revision or branch number can be attached to any of the options -f, -I, -l, -M, -p, -q, -r, or -u. The options -d (date), -s (state), and -w (author) retrieve from a single branch, the selected branch (which is specified by -f or -u), or the default branch.

A co command applied to an RCS file with no revisions creates a zero-length working file. co always performs keyword substitution.

OPTIONS

<code>-r[rev]</code>	Retrieves the latest revision whose number is less than or equal to <code>rev</code> . If <code>rev</code> indicates a branch rather than a revision, the latest revision on that branch is retrieved. If <code>rev</code> is omitted, the latest revision on the default branch is retrieved; see the <code>-b</code> option of <code>rcs(1)</code> . If <code>rev</code> is <code>\$</code> , <code>co</code> determines the revision number from keyword values in the working file. Otherwise, a revision is composed of one or more numeric or symbolic fields separated by periods. If <code>rev</code> begins with a period, then the default branch (normally the trunk) is prepended to it. If <code>rev</code> is a branch number followed by a period, then the latest revision on that branch is used. The numeric equivalent of a symbolic field is specified with the <code>-n</code> option of the commands <code>ci(1)</code> and <code>rcs(1)</code> .
<code>-l[rev]</code>	Same as <code>-r</code> , except that it also locks the retrieved revision for the caller.
<code>-u[rev]</code>	Same as <code>-r</code> , except that it unlocks the retrieved revision if it was locked by the caller. If <code>rev</code> is omitted, <code>-u</code> retrieves the revision locked by the caller, if there is one; otherwise, it retrieves the latest revision on the default branch.
<code>-f[rev]</code>	Forces the overwriting of the working file; useful in connection with <code>-q</code> . (See also “File Modes,” later in this manual page.)
<code>-kkv</code>	Generate keyword strings using the default form, for example, <code>\$Revision: 5.13 \$</code> for the <code>Revision</code> keyword. A locker's name is inserted in the value of the <code>Header</code> , <code>Id</code> , and <code>Locker</code> keyword strings only as a file is being locked, that is, by <code>ci -l</code> and <code>co -l</code> . This is the default.
<code>-kkv1</code>	Like <code>-kkv</code> , except that a locker's name is always inserted if the given revision is currently locked.
<code>-kk</code>	Generate only keyword names in keyword strings; omit their values. (See “Keyword Substitution,” later in this manual page.) For example, for the <code>Revision</code> keyword, generate the string <code>\$Revision\$</code> instead of <code>\$Revision: 5.13 \$</code> . This option is useful to ignore differences due to keyword substitution when comparing different revisions of a file. Log messages are inserted after <code>\$Log\$</code> keywords even if <code>-kk</code> is specified, since this tends to be more useful when merging changes.
<code>-ko</code>	Generate the old keyword string, present in the working file just before it was checked in. For example, for the <code>Revision</code> keyword, generate the string <code>\$Revision: 1.1 \$</code> instead of <code>\$Revision: 5.13 \$</code> if that is how the string appeared when the file was checked in. This can be useful for file formats that cannot tolerate any changes to substrings that happen to take the form of keyword strings.
<code>-kb</code>	Generate a binary image of the old keyword string. This acts like <code>-ko</code> , except it performs all working file input and output in binary mode. This makes little difference on POSIX and UNIX hosts, but on DOS-like hosts one should use <code>rcs -i -kb</code> to initialize an RCS file normally refuses to merge files when <code>-kb</code> is in effect.
<code>-kv</code>	Generate only keyword values for keyword strings. For example, for the <code>Revision</code> keyword, generate the string <code>5.13</code> instead of <code>\$Revision: 5.13 \$</code> . This can help generate files in programming languages where it is hard to strip keyword delimiters like <code>\$Revision: \$</code> from a string. However, further keyword substitution cannot be performed once the keyword names are removed, so this option should be used with care. Because of this danger of losing keywords, this option cannot be combined with <code>-l</code> , and the owner write permission of the working file is turned off; to edit the file later, check it out again without <code>-kv</code> .
<code>-p[rev]</code>	Prints the retrieved revision on the standard output rather than storing it in the working file. This option is useful when <code>co</code> is part of a pipe.
<code>-q[rev]</code>	Quiet mode; diagnostics are not printed.
<code>-I[rev]</code>	Interactive mode; the user is prompted and questioned even if the standard input is not a terminal.
<code>-ddate</code>	Retrieves the latest revision on the selected branch whose checkin date/time is less than or equal to date. The date and time can be given in free format. The time zone <code>LT</code> stands for local time; other common time zone names are understood. For example, the following dates are equivalent if local time is January 11, 1990, 8 p.m. Pacific Standard Time, eight hours west of Coordinated Universal Time (UTC):

8:00 PM lt

4:00 AM, Jan. 12, 1990

Default is UTC

1990-01-12 04:00:00+00	ISO 8601 (UTC)
1990-01-11 20:00:00-08	ISO 8601 (local time)
1990/01/12 04:00:00	Traditional RCS format
Thu Jan 11 20:00:00 1990 LT	Output of <code>ctime(3)</code> + LT
Thu Jan 11 20:00:00 PST 1990	Output of <code>date(1)</code>
Fri Jan 12 04:00:00 GMT 1990	
Thu, 11 Jan 1990 20:00:00 -0800	Internet RFC 822
12-January-1990, 04:00 WET	

Most fields in the date and time can be defaulted. The default time zone is normally UTC, but this can be overridden by the `-z` option. The other defaults are determined in the order year, month, day, hour, minute, and second (most to least significant). At least one of these fields must be provided. For omitted fields that are of higher significance than the highest provided field, the time zone's current values are assumed. For all other omitted fields, the lowest possible values are assumed. For example, without `-z`, the date 20, 10:30 defaults to 10:30:00 UTC of the 20th of the UTC time zone's current month and year. The date/time must be quoted if it contains spaces.

<code>-M[rev]</code>	Sets the modification time on the new working file to be the date of the retrieved revision. Use this option with care; it can confuse <code>make(1)</code> .
<code>-ssstate</code>	Retrieves the latest revision on the selected branch whose state is set to state.
<code>-T</code>	Preserves the modification time on the RCS file even if the RCS file changes because a lock is added or removed. This option can suppress extensive recompilation caused by a <code>make(1)</code> dependency of some other copy of the working file on the RCS file. Use this option with care; it can suppress recompilation even when it is needed, in other words, when the change of lock would mean a change to keyword strings in the other working file.
<code>-w[login]</code>	Retrieves the latest revision on the selected branch that was checked in by the user with login name <code>login</code> . If the argument <code>login</code> is omitted, the caller's login is assumed.
<code>-jjoinlist</code>	Generates a new revision which is the join of the revisions on <code>joinlist</code>. This option is largely made obsolete by <code>rcsmerge(1)</code>, but is retained for backwards compatibility. The <code>joinlist</code> is a comma-separated list of pairs of the form <code>rev2:rev3</code>, where <code>rev2</code> and <code>rev3</code> are (symbolic or numeric) revision numbers. For the initial such pair, <code>rev1</code> denotes the revision selected by the options <code>-f</code>, <code>-w</code>. For all other pairs, <code>rev1</code> denotes the revision generated by the previous pair. (Thus, the output of one join becomes the input to the next.) For each pair, <code>co</code> joins revisions <code>rev1</code> and <code>rev3</code> with respect to <code>rev2</code>. This means that all changes that transform <code>rev2</code> into <code>rev1</code> are applied to a copy of <code>rev3</code>. This is particularly useful if <code>rev1</code> and <code>rev3</code> are the ends of two branches that have <code>rev2</code> as a common ancestor. If <code>rev1 < rev2 < rev3</code> on the same branch, joining generates a new revision which is like <code>rev3</code>, but with all changes that lead from <code>rev1</code> to <code>rev2</code> undone. If changes from <code>rev2</code> to <code>rev1</code> overlap with changes from <code>rev2</code> to <code>rev3</code>, <code>co</code> reports overlaps as described in <code>merge(1)</code>. For the initial pair, <code>rev2</code> can be omitted. The default is the common ancestor. If any of the arguments indicate branches, the latest revisions on those branches are assumed. The options <code>-l</code> and <code>-u</code> lock or unlock <code>rev1</code>.
<code>-V</code>	Prints RCS's version number.
<code>-Vn</code>	Emulates RCS version <code>n</code> , where <code>n</code> can be 3, 4, or 5. This can be useful when interchanging RCS files with others who are running older versions of RCS. To see which version of RCS your correspondents are running, have them invoke <code>rcs -v</code> ; this works with newer versions of RCS. If it doesn't work, have them invoke <code>rlog</code> on an RCS file; if none of the first few lines of output contain the string <code>branch:</code> , it is version 3; if the dates' years have just two digits, it is version 4; otherwise, it is version 5. An RCS file generated while emulating version 3 loses its default branch. An RCS revision generated while emulating version 4 or earlier has a timestamp that is off by up to 13 hours. A revision extracted while emulating version 4 or earlier contains abbreviated dates of the form <code>yy/mm/dd</code> and can also contain different whitespace and line prefixes in the substitution for <code>\$Log\$</code> .

- `-xsuffixes` Uses suffixes to characterize RCS files. See `ci(1)` for details.
- `-zzzone` Specifies the date output format in keyword substitution, and specifies the default time zone for date in the `-ddate` option. The `zone` should be empty, a numeric UTC offset, or the special string `LT` for local time. The default is an empty zone, which uses the traditional RCS format of UTC without any time zone indication and with slashes separating the parts of the date; otherwise, times are output in ISO 8601 format with time zone indication. For example, if local time is January 11, 1990, 8 p.m. Pacific Standard Time, eight hours west of UTC, then the time is output as follows:

Option	Time Output
<code>-z</code>	1990/01/12 04:00:00 (default)
<code>-zLT</code>	1990-01-11 20:00:00-08
<code>-z+05:30</code>	1990-01-12 09:30:00+05:30

The `-z` option does not affect dates stored in RCS files, which are always UTC.

KEYWORD SUBSTITUTION

Strings of the form `$ keyword $` and `$ keyword : ... $` embedded in the text are replaced with strings of the form `$ keyword : value $`, where `keyword` and `value` are pairs in the following list. Keywords can be embedded in literal strings or comments to identify a revision.

Initially, the user enters strings of the form `$keyword$`. On checkout, `co` replaces these strings with strings of the form `$keyword : value$`. If a revision containing strings of the latter form is checked back in, the `value` fields will be replaced during the next checkout. Thus, the keyword values are automatically updated on checkout. This automatic substitution can be modified by the `-k` options.

Keywords and their corresponding values:

<code>\$Author\$</code>	The login name of the user who checked in the revision.
<code>\$Date\$</code>	The date and time the revision was checked in. With <code>-zzzone</code> , a numeric time zone offset is appended; otherwise, the date is UTC.
<code>\$Header\$</code>	A standard header containing the full pathname of the RCS file, the revision number, the date and time, the author, the state, and the locker (if locked). With <code>-zzzone</code> , a numeric time zone offset is appended to the date; otherwise, the date is UTC.
<code>\$Id\$</code>	Same as <code>\$Header\$</code> , except that the RCS filename is without a path.
<code>\$Locker\$</code>	The login name of the user who locked the revision (empty if not locked).
<code>\$Log\$</code>	The log message supplied during checkin, preceded by a header containing the RCS filename, the revision number, the author, and the date and time. With <code>-zzzone</code> a numeric time zone offset is appended; otherwise, the date is UTC. Existing log messages are not replaced. Instead, the new log message is inserted after <code>\$Log: ... \$</code> . This is useful for accumulating a complete change log in a source file.

Each inserted line is prefixed by the string that prefixes the `$Log$` line. For example, if the `$Log$` line is `// $Log: tan.cc $`, RCS prefixes each line of the log with `//`. This is useful for languages with comments that go to the end of the line. The convention for other languages is to use a `*` prefix inside a multiline comment. For example, the initial log comment of a C program conventionally is of the following form:

```
/*
 * $Log$
 */
```

For backwards compatibility with older versions of RCS, if the log prefix is `/*` or `(*` surrounded by optional whitespace, inserted log lines contain a space instead of `/` or `(`; however, this usage is obsolescent and should not be relied on.

<code>\$Name\$</code>	The symbolic name used to check out the revision, if any. For example, <code>co -r Joe</code> generates <code>\$Name: Joe \$</code> . Plain <code>co</code> generates just <code>\$Name: \$</code> .

<code>\$RCSfile\$</code>	The name of the RCS file without a path.
<code>\$Revision\$</code>	The revision number assigned to the revision.
<code>\$Source\$</code>	The full pathname of the RCS file.
<code>\$State\$</code>	The state assigned to the revision with the <code>-s</code> option of <code>rcs(1)</code> or <code>ci(1)</code> .

The following characters in keyword values are represented by escape sequences to keep keyword strings well-formed.

Character	Escape Sequence
tab	<code>\t</code>
newline	<code>\n</code>
space	<code>\040</code>
\$	<code>\044</code>
\	<code>\\</code>

FILE MODES

The working file inherits the read and execute permissions from the RCS file. In addition, the owner write permission is turned on, unless `-kv` is set or the file is checked out unlocked and locking is set to strict; see `rcs(1)`.

If a file with the name of the working file exists already and has write permission, `co` aborts the checkout, asking beforehand if possible. If the existing working file is not writable or `-f` is given, the working file is deleted without asking.

FILES

`co` accesses files much as `ci(1)` does, except that it does not need to read the working file unless a revision number of `$` is specified.

ENVIRONMENT

`RCSINIT` Options prepended to the argument list, separated by spaces. See `ci(1)` for details.

DIAGNOSTICS

The RCS pathname, the working pathname, and the revision number retrieved are written to the diagnostic output. The exit status is zero if and only if all operations were successful.

IDENTIFICATION

Author: Walter F. Tichy.

Manual Page Revision: 5.13; Release Date: 1995/06/01.

Copyright © 1982, 1988, 1989 Walter F. Tichy.

Copyright © 1990, 1991, 1992, 1993, 1994, 1995 Paul Eggert.

SEE ALSO

`rcsintro(1)`, `ci(1)`, `ctime(3)`, `date(1)`, `ident(1)`, `make(1)`, `rcs(1)`, `rcsclean(1)`, `rcsdiff(1)`, `rc-smerge(1)`, `rlog(1)`, `rcsfile(5)`

Walter F. Tichy, "RCS—A System for Version Control," *Software Practice & Experience* 15, 7 (July 1985), 637-654.

LIMITS

Links to the RCS and working files are not preserved.

There is no way to selectively suppress the expansion of keywords, except by writing them differently. In `nröff` and `troff`, this is done by embedding the null-character `\&` into the keyword.

col

`col`—Filter reverse line feeds from input

SYNOPSIS

`col [-bf $x$ ] [-l num]`

DESCRIPTION

`col` filters out reverse (and half-reverse) line feeds so the output is in the correct order with only forward and half-forward line feeds, and replaces whitespace characters with tabs where possible. This can be useful in processing the output of `nroff(1)` and `tbl(1)`. `col` reads from standard input and writes to standard output.

The options are as follows:

- b Do not output any backspaces, printing only the last character written to each column position.
- f Forward half-line feeds are permitted (*fine* mode). Normally characters printed on a half-line boundary are printed on the following line.
- x Output multiple spaces instead of tabs.
- l num Buffer at least *num* lines in memory. By default, 128 lines are buffered.

The control sequences for carriage motion that `col` understands and their decimal values are listed in the following table:

<i>Control Sequence</i>	<i>Decimal Value</i>
Esc+7	Reverse line feed (escape then 7)
Esc+8	Half-reverse line feed (escape then 8)
Esc+9	Half-forward line feed (escape then 9)
Backspace	Moves back one column (8); ignored in the first column
Carriage return	(13)
Newline	Forward line feed (10); also does carriage return
Shift in	Shift to normal character set (15)
Shift out	Shift to alternate character set (14)
Space	Moves forward one column (32)
Tab	Moves forward to next tab stop (9)
Vertical tab	Reverse line feed (11)

All unrecognized control characters and escape sequences are discarded.

`col` keeps track of the character set as characters are read and makes sure the character set is correct when they are output.

If the input attempts to back up to the last flushed line, `col` will display a warning message.

SEE ALSO

`expand(1)`, `nroff(1)`, `tbl(1)`

HISTORY

A `col` command appeared in version 6 AT&T UNIX.

17 June 1991

colcrt

colcrt—Filter nroff output for CRT previewing

SYNOPSIS

```
colcrt [-] [-2] [file ...]
```

DESCRIPTION

colcrt provides virtual half-line and reverse-line feed sequences for terminals without such capability, and on which overstriking is destructive. Half-line characters and underlining (changed to dashing -) are placed on new lines in between the normal output lines.

Available options:

- Suppress all underlining. This option is especially useful for previewing all boxed tables from tbl(1).
- 2 Causes all half-lines to be printed, effectively double spacing the output. Normally, a minimal space output format is used which will suppress empty lines. The program never suppresses two consecutive empty lines, however. The -2 option is useful for sending output to the line printer when the output contains superscripts and subscripts that would otherwise be invisible.

EXAMPLES

A typical use of colcrt would be

```
tbl exum2.n | nroff -ms | colcrt - | more
```

SEE ALSO

nroff(1), troff(1), col(1), more(1), ul(1)

BUGS

Should fold underlines onto blanks even with the - option so that a true underline character would show.

Can't back up more than 102 lines.

General overstriking is lost; as a special case | overstruck with ' ' or underline becomes +. Lines are trimmed to 132 characters.

Some provision should be made for processing superscripts and subscripts in documents that are already double-spaced.

HISTORY

The colcrt command appeared in BSD 3.0.

BSD 3, 30 June 1993

colrm

colrm—Remove columns from a file

SYNOPSIS

```
colrm [startcol [endcol]]
```

DESCRIPTION

colrm removes selected columns from a file. Input is taken from standard input. Output is sent to standard output.

If called with one parameter, the columns of each line will be removed starting with the specified column. If called with two parameters, the columns from the first column to the last column will be removed.

Column numbering starts with column 1.

SEE ALSO

`awk(1)`, `column(1)`, `expand(1)`, `paste(1)`

HISTORY

The `colrm` command appeared in BSD 3.0.

BSD 3, 14 March 1991

column

`column`—Columnate lists

SYNOPSIS

`column [-tx] [-ccolumns] [-ssep] [...file]`

DESCRIPTION

The `column` utility formats its input into multiple columns. Rows are filled before columns. Input is taken from file operands, or, by default, from the standard input. Empty lines are ignored.

The options are as follows:

- `-c` Output is formatted for a display columns wide.
- `-s` Specify a set of characters to be used to delimit columns for the `-t` option.
- `-t` Determine the number of columns the input contains and create a table. Columns are delimited with whitespace, by default, or with the characters supplied using the `-s` option. Useful for pretty-printing displays.
- `-x` Fill columns before filling rows.

Column exits 0 on success, >0 if an error occurred.

ENVIRONMENT

The environment variable `COLUMNS` is used to determine the size of the screen if no other information is available.

EXAMPLES

```
(printf "PERM LINKS OWNER SIZE MONTH DAY HH:MM/YEAR NAME"; ls -l j sed 1d) j column -t
```

SEE ALSO

`colrm(1)`, `ls(1)`, `paste(1)`, `sort(1)`

HISTORY

The `column` command appeared in BSD 4.3 Reno.

6 June 1993

comm

`comm`—Compare two sorted files line by line

SYNOPSIS

`comm [-123] [--help] [--version] file1 file2`

DESCRIPTION

This manual page documents the GNU version of `comm`. `comm` prints lines that are common, and lines that are unique, to two input files. The two files must be sorted before `comm` can be used. The filename `-` means the standard input.

With no options, `comm` produces three column output. Column one contains lines unique to `file1`, column two contains lines unique to `file2`, and column three contains lines common to both files.

OPTIONS

The options `-1`, `-2`, and `-3` suppress printing of the corresponding columns.

- `-help` Print a usage message and exit with a nonzero status.
- `-version` Print version information on standard output then exit.

GNU Text Utilities

convdate

`convdate`—Convert time/date strings and numbers

SYNOPSIS

```
convdate [ -c ][-n ][-s ] arg...
```

DESCRIPTION

`convdate` translates the date/time strings specified as arguments on its command line, outputting the results one to a line.

If the `-s` flag is used, then each argument is taken as a date string to be parsed by `parse-date(3)` and is output as a string formatted by `ctime(3)`. This is the default.

If the `-n` flag is used, then each argument is converted the same way but is output as a time `t`; see `time(2)`.

If the `-c` flag is used, then each argument is taken to be a time `t` and is output in `ctime` format.

Here's an example:

```
% convdate 'feb 10 10am'
Sun Feb 10 10:00:00 1991

% convdate 12pm 5/4/90
Fri Dec 13 00:00:00 1991
Fri May 4 00:00:00 1990

% convdate -n 'feb 10 10am' '12pm 5/4/90'
666198000
641880000
% convdate -c 666198000
Sun Feb 10 10:00:00 1991
```

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net).

SEE ALSO

`parsedate(3)`

cp

cp—Copy files

SYNOPSIS

```
cp [options] source dest
cp [options] source... directory
```

Options:

```
[ -abdfilprsuvxPR ] [ -S backup-suffix ] [ -V fnumbered,existing,simpleg ] [ -backup ]
[ -no-dereference ] [ -force ] [ -interactive ] [ -one-file-system ] [ -preserve ]
[ -recursive ] [ -update ] [ -verbose ] [ -suffix=backup-suffix ]
[ -version-control=fnumbered,existing,simpleg ] [ -archive ] [ -parents ] [ -link ]
[ -symbolic-link ] [ -help ] [ -version ]
```

DESCRIPTION

This manual page documents the GNU version of `cp`. If the last argument names an existing directory, `cp` copies each other given file into a file with the same name in that directory. Otherwise, if only two files are given, it copies the first onto the second. It is an error if the last argument is not a directory and more than two files are given. By default, it does not copy directories.

OPTIONS

<code>-a, --archive</code>	Preserve as much as possible of the structure and attributes of the original files in the copy. The same as <code>-dpR</code> .
<code>-b, --backup</code>	Make backups of files that are about to be overwritten or removed.
<code>-d, --no-dereference</code>	Copy symbolic links as symbolic links rather than copying the files that they point to, and preserve hard link relationships between source files in the copies.
<code>-f, --force</code>	Remove existing destination files.
<code>-i, --interactive</code>	Prompt whether to overwrite existing regular destination files.
<code>-l, --link</code>	Make hard links instead of copies of nondirectories.
<code>-P, --parents</code>	Form the name of each destination file by appending to the target directory a slash and the specified name of the source file. The last argument given to <code>cp</code> must be the name of an existing directory. For example, the command <code>cp --parents a/b/c existing_dir</code> copies the file <code>a/b/c</code> to <code>existing_dir/a/b/c</code> , creating any missing intermediate directories.
<code>-p, --preserve</code>	Preserve the original files' owner, group, permissions, and timestamps.
<code>-r</code>	Copy directories recursively, copying all nondirectories as if they were regular files.
<code>-s, --symbolic-link</code>	Make symbolic links instead of copies of nondirectories. All source filenames must be absolute (starting with <code>/</code>) unless the destination files are in the current directory. This option produces an error message on systems that do not support symbolic links.
<code>-u, --update</code>	Do not copy a nondirectory that has an existing destination with the same or newer modification time.
<code>-v, --verbose</code>	Print the name of each file before copying it.
<code>-x, --one-file-system</code>	Skip subdirectories that are on different filesystems from the one that the copy started on.
<code>-R, --recursive</code>	Copy directories recursively.
<code>--help</code>	Print a usage message on standard output and exit successfully.
<code>--version</code>	Print version information on standard output then exit successfully.
<code>-S, --suffix backup-suffix</code>	The suffix used for making simple backup files can be set with the <code>SIMPLE_BACKUP_SUFFIX</code> environment variable, which can be overridden by this option. If neither of those is given, the default is <code>~</code> , as it is in <code>emacs</code> .

`-V, --version-control`
`{numbered,existing,simple}`

The type of backups made can be set with the `VERSION_CONTROL` environment variable, which can be overridden by this option. If `VERSION_CONTROL` is not set and this option is not given, the default backup type is `existing`. The value of the `VERSION_CONTROL` environment variable and the argument to this option are like the GNU `emacs version-control` variable; they also recognize synonyms that are more descriptive. The valid values are (unique abbreviations are accepted) the following:

<code>t</code> or <code>numbered</code>	Always make numbered backups
<code>nil</code> or <code>existing</code>	Make numbered backups of files that already have them, simple backups of the others
<code>never</code> or <code>simple</code>	Always make simple backups

cccp, cpp

`cccp, cpp`—The GNU C-compatible compiler preprocessor

SYNOPSIS

```
cccp [-$][-A predicate [( value )]] [-C ][-D name [= definition ]]  

      [-dD][-dM][-I\ directory ][-H ][-I- ][-imacros file ][-  

      include file ][-idirafter dir ][-iprefix prefix ][-iwithprefix dir ]  

      [ -lang-c ][-lang-c++ ][-lang-objc ][-lang-objc++ ][-lint ][-  

      M[-MG ]][ -MM[-MG ]][ -MD file ][-MMD file ][-nostdinc ]  

      [ -nostdinc++ ][-P ][-pedantic ][-pedantic-errors ][-traditional ]  

      [ -trigraphs ][-U name ][-undef ][-Wtrigraphs ][-Wcomment ]  

      [ -Wall ][-Wtraditional ]  

      [ infile ]- ][ outfile ]- ]
```

DESCRIPTION

The C preprocessor is a macro processor that is used automatically by the C compiler to transform your program before actual compilation. It is called a macro processor because it allows you to define macros, which are brief abbreviations for longer constructs.

The C preprocessor provides four separate facilities that you can use as you see fit:

- Inclusion of header files. These are files of declarations that can be substituted into your program.
- Macro expansion. You can define macros, which are abbreviations for arbitrary fragments of C code, and then the C preprocessor will replace the macros with their definitions throughout the program.
- Conditional compilation. Using special preprocessing directives, you can include or exclude parts of the program according to various conditions.
- Line control. If you use a program to combine or rearrange source files into an intermediate file which is then compiled, you can use line control to inform the compiler of where each source line originally came from.

C preprocessors vary in some details. For a full explanation of the GNU C preprocessor, see the `info` file `cpp.info`, or the manual *The C Preprocessor*. Both of these are built from the same documentation source file, `cpp.texinfo`. The GNU C preprocessor provides a superset of the features of ANSI Standard C.

ANSI Standard C requires the rejection of many harmless constructs commonly used by today's C programs. Such incompatibility would be inconvenient for users, so the GNU C preprocessor is configured to accept these constructs by default. Strictly speaking, to get ANSI Standard C, you must use the options `-trigraphs`, `-undef`, and `-pedantic`, but in practice the consequences of having strict ANSI Standard C make it undesirable to do this.

When you use the C preprocessor, you will usually not have to invoke it explicitly: the C compiler will do so automatically. However, the preprocessor is sometimes useful individually.

When you call the preprocessor individually, either name (`cpp` or `cccp`) will do; they are completely synonymous.

The C preprocessor expects two filenames as arguments, `infile` and `outfile`. The preprocessor reads `infile` together with any other files it specifies with `#include`. All the output generated by the combined input files is written in `outfile`. Either `infile` or `outfile` may be `-`, which as `infile` means to read from standard input and as `outfile` means to write to standard output. Also, if `outfile` or both filenames are omitted, the standard output and standard input are used for the omitted filenames.

OPTIONS

Here is a table of command options accepted by the C preprocessor. These options can also be given when compiling a C program; they are passed along automatically to the preprocessor when it is invoked by the compiler.

<code>-P</code>	Inhibit generation of <code>#</code> lines with line-number information in the output from the preprocessor. This might be useful when running the preprocessor on something that is not C code and will be sent to a program which might be confused by the <code>#</code> lines.
<code>-C</code>	Do not discard comments: pass them through to the output file. Comments appearing in arguments of a macro call will be copied to the output before the expansion of the macro call.
<code>-traditional</code>	Try to imitate the behavior of old-fashioned C, as opposed to ANSI C.
<code>-trigraphs</code>	Process ANSI standard trigraph sequences. These are three-character sequences, all starting with <code>??</code> , that are defined by ANSI C to stand for single characters. For example, <code>??/</code> stands for <code>\</code> , so <code>??/n</code> is a character constant for a newline. Strictly speaking, the GNU C preprocessor does not support all programs in ANSI Standard C unless <code>-trigraphs</code> is used, but if you ever notice the difference, it will be with relief. You don't want to know any more about trigraphs.
<code>-pedantic</code>	Issue warnings required by the ANSI C standard in certain cases such as when text other than a comment follows <code>#else</code> or <code>#endif</code> .
<code>-pedantic-errors</code>	Like <code>-pedantic</code> , except that errors are produced rather than warnings.
<code>-Wtrigraphs</code>	Warn if any trigraphs are encountered (assuming they are enabled).
<code>-Wcomment</code>	Warn whenever a comment-start sequence <code>/*</code> appears in a comment. (Both forms have the same effect.)
<code>-Wcomments</code>	
<code>-Wall</code>	Requests both <code>-Wtrigraphs</code> and <code>-Wcomment</code> (but not <code>-Wtraditional</code>).
<code>-Wtraditional</code>	Warn about certain constructs that behave differently in traditional and ANSI C.
<code>-I directory</code>	Add the directory <code>directory</code> to the end of the list of directories to be searched for header files. This can be used to override a system header file, substituting your own version, since these directories are searched before the system header file directories. If you use more than one <code>-I</code> option, the directories are scanned in left-to-right order; the standard system directories come after.
<code>-I-</code>	Any directories specified with <code>-I</code> options before the <code>-I-</code> option are searched only for the case of <code>#include "file"</code> ; they are not searched for <code>#include <file></code> . If additional directories are specified with <code>-I</code> options after the <code>-I-</code> , these directories are searched for all <code>#include</code> directives. In addition, the <code>-I-</code> option inhibits the use of the current directory as the first search directory for <code>#include "file"</code> . Therefore, the current directory is searched only if it is requested explicitly with <code>-I</code> followed by a period (<code>.</code>). Specifying both <code>-I-</code> and <code>-I.</code> allows you to control precisely which directories are searched before the current one and which are searched after.
<code>-nostdinc</code>	Do not search the standard system directories for header files. Only the directories you have specified with <code>-I</code> options (and the current directory, if appropriate) are searched.
<code>-nostdinc++</code>	Do not search for header files in the C++-specific standard directories, but do still search the other standard directories. (This option is used when building <code>libg++</code> .)
<code>-D name</code>	Predefine <code>name</code> as a macro, with definition <code>1</code> .
<code>-D name=definition</code>	Predefine <code>name</code> as a macro, with definition <code>definition</code> . There are no restrictions on the contents of <code>definition</code> , but if you are invoking the preprocessor from a shell or shell-like program, you may need to use the shell's quoting syntax to protect characters such as spaces that have a meaning in the shell syntax. If you use more than one <code>-D</code> for the same name, the rightmost definition takes effect.

-U name	Do not predefine name. If both -U and -D are specified for one name, the -U beats the -D and the name is not predefined.
-undef	Do not predefine any nonstandard macros.
-A name(value)	Assert (in the same way as the #assert directive) the predicate name with tokenlist value . Remember to escape or quote the parentheses on shell command lines. You can use -A- to disable all predefined assertions; it also undefines all predefined macros.
-dM	Instead of outputting the result of preprocessing, output a list of #define directives for all the macros defined during the execution of the preprocessor, including predefined macros. This gives you a way of finding out what is predefined in your version of the preprocessor; assuming you have no file foo.h, the command touch foo.h; cpp -dM foo.h will show the values of any predefined macros.
-dD	Like -dM except in two respects: it does not include the predefined macros, and it outputs both the #define directives and the result of preprocessing. Both kinds of output go to the standard output file.
-M[-MG]	Instead of outputting the result of preprocessing, output a rule suitable for make describing the dependencies of the main source file. The preprocessor outputs one make rule containing the object filename for that source file, a colon, and the names of all the included files. If there are many included files then the rule is split into several lines using \\ (newline). -MG says to treat missing header files as generated files and assume they live in the same directory as the source file. It must be specified in addition to -M. This feature is used in automatic updating of makefiles.
-MM[-MG]	Like -M but mention only the files included with #include " file ". System header files included with #include < file > are omitted.
-MDfile	Like -M but the dependency information is written to file. This is in addition to compiling the file as specified. -MD does not inhibit ordinary compilation the way -M does. When invoking gcc, do not specify the file argument. gcc will create filenames made by replacing .c with .d at the end of the input filenames. In Mach, you can use the utility md to merge multiple files into a single dependency file suitable for using with the make command.
-MMDfile	Like -M except mention only user header files, not system header files.
-H	Print the name of each header file used, in addition to other normal activities.
-imacros file	Process file as input, discarding the resulting output, before processing the regular input file. Because the output generated from file is discarded, the only effect of -imacros file is to make the macros defined in file available for use in the main input. The preprocessor evaluates any -D and -U options on the command line before processing -imacros file.
-include file	Process file as input, and include all the resulting output, before processing the regular input file.
-idirafter dir	Add the directory dir to the second include path. The directories on the second include path are searched when a header file is not found in any of the directories in the main include path (the one that -I adds to).
-iprefix prefix	Specify prefix as the prefix for subsequent -iwithprefix options.
-iwithprefix dir	Add a directory to the second include path. The directory's name is made by concatenating prefix and dir, where prefix was specified previously with -iprefix.
-lang-c	Specify the source language. -lang-c++ makes the preprocessor handle C++ comment syntax, and includes extra default include directories for C++, and -lang-objc enables the Objective C #import directive. -lang-c explicitly turns off both of these extensions, and -lang-objc++ enables both. These options are generated by the compiler driver gcc, but not passed from the gcc command line.
-lang-c++	
-lang-objc	
-lang-objc++	
-lint	Look for commands to the program checker lint embedded in comments, and emit them preceded by #pragma lint. For example, the comment /* NOTREACHED */ becomes #pragma lint NOTREACHED. This option is available only when you call cpp directly; gcc will not pass it from its command line.

`-$` Forbid the use of `$` in identifiers. This is required for ANSI conformance. `gcc` automatically supplies this option to the preprocessor if you specify `-ansi`, but `gcc` doesn't recognize the `-$` option itself; to use it without the other effects of `-ansi`, you must call the preprocessor directly.

SEE ALSO

`cpp` entry in *info*; *The C Preprocessor*, Richard M. Stallman.

`gcc(1)`; `gcc` entry in *info*; *Using and Porting GNU CC* (for version 2.0), Richard M. Stallman.

COPYING

Copyright © 1991, 1992, 1993 Free Software Foundation, Inc. Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

GNU Tools, 30 April 1993

crontab

`crontab`—Manipulate per-user crontabs (Dillon's Cron)

SYNOPSIS

<code>crontab file [-u user]</code>	Replace crontab from file
<code>crontab - [-u user]</code>	Replace crontab from stdin
<code>crontab -l [user]</code>	List crontab for user
<code>crontab -e [user]</code>	Edit crontab for user
<code>crontab -d [user]</code>	Delete crontab for user
<code>crontab -c dir</code>	Specify crontab directory

DESCRIPTION

`crontab` manipulates the `crontab` for a particular user. Only the superuser may specify a different user and/or `crontab` directory. Generally, the `-e` option is used to edit your `crontab`. `crontab` will use `/usr/bin/vi` or the editor specified by your `VISUAL` environment variable to edit the `crontab`.

Unlike other `crond/crontabs`, this `crontab` does not try to do everything under the sun. Frankly, a shell script is much more able to manipulate the environment than `cron`, and I see no particular reason to use the user's shell (from his password entry) to run `cron` commands when this requires special casing of nonuser `crontabs`, such as those for UUCP. When a `crontab` command is run, this `crontab` runs it with `/bin/sh` and sets up only three environment variables: `USER`, `HOME`, and `SHELL`.

`crond` automatically detects changes in the time. Reverse-indexed time changes less than an hour old will NOT rerun `crontab` commands already issued in the recovered period. Forward-indexed changes less than an hour into the future will issue missed commands exactly once. Changes greater than an hour into the past or future cause `crond` to resynchronize and not issue missed commands. No attempt will be made to issue commands lost due to a reboot, and commands are not reissued if the previously issued command is still running. For example, if you have a `crontab` command `sleep 70` that you wish to run once a minute, `cron` will only be able to issue the command once every two minutes. If you do not like this feature, you can run your commands in the background with an `&`.

The crontab format is roughly similar to that used by *vixiecron*, but without complex features. Individual fields may contain a time, a time range, a time range with a skip factor, a symbolic range for the day of week and month in year, and additional subranges delimited with commas. Blank lines in the crontab or lines that begin with a hash (#) are ignored. If you specify both a day in the month and a day of week, the result is effectively *or*; the crontab entry will be run on the specified day of week and on the specified day in the month.

```
# MIN HOUR DAY MONTH DAYOFWEEK COMMAND
# at 6:10 a.m. every day
10 6 ***date

# every two hours at the top of the hour
0 */2 ***date

# every two hours from 11p.m. to 7a.m., and at 8a.m.
0 23-7/2,8 ***date

# at 11:00 a.m. on the 4th and on every mon, tue, wed
0 11 4 * mon-wed date

# 4:00 a.m. on january 1st
0 4 1 jan *date

# once an hour, all output appended to log file
0 4 1 jan *date>>/var/log/messages 2>&1
```

The command portion of the line is run with `/bin/sh -c <command>`, and may therefore contain any valid Bourne shell command. A common practice is to run your command with `exec` to keep the process table uncluttered. It is also common to redirect output to a log file. If you do not, and the command generates output on `stdout` or `stderr`, the result will be mailed to the user in question. If you use this mechanism for special users, such as *UUCP*, you may want to create an alias for the user to direct the mail to someone else, such as *root* or *postmaster*.

Internally, this *cron* uses a quick indexing system to reduce CPU overhead when looking for commands to execute. Several hundred crontabs with several thousand entries can be handled without using noticeable CPU resources.

BUGS

Ought to be able to have several crontab files for any given user, as an organizational tool.

AUTHOR

Matthew Dillon (dillon@apollo.west.oic.com)

1 May 1994

csplit

csplit—Split a file into sections determined by context lines

SYNOPSIS

```
csplit [-sqkz] [-f prefix] [-b suffix] [-n digits] [--prefix=prefix]
[--suffix=format=suffix] [--digits=digits] [--quiet] [--silent]
[--keep-files] [--elide-empty-files] [--help] [--version]
file pattern...
```

DESCRIPTION

This manual page documents the GNU version of *csplit*. *csplit* creates zero or more output files containing sections of the given input file, or the standard input if the name `-` is given. By default, *csplit* prints the number of bytes written to each output file after it has been created.

The contents of the output files are determined by the pattern arguments. An error occurs if a pattern argument refers to a nonexistent line of the input file, such as if no remaining line matches a given regular expression. After all the given patterns have been matched, any remaining output is copied into one last output file. The types of pattern arguments are

<code>line</code>	Create an output file containing the current line up to (but not including) line <code>line</code> (a positive integer) of the input file. If followed by a repeat count, also create an output file containing the next <code>line</code> lines of the input file once for each repeat.
<code>/regex/[offset]</code>	Create an output file containing the current line up to (but not including) the next line of the input file that contains a match for <code>regex</code> . The optional offset is a + or - followed by a positive integer. If it is given, the input up to the matching line plus or minus offset is put into the output file, and the line after that begins the next section of input.
<code>%regex%[offset]</code>	Like the previous type, except that it does not create an output file, so that section of the input file is effectively ignored.
<code>{repeat-count}</code>	Repeat the previous pattern <code>repeat-count</code> (a positive integer) additional times. An asterisk may be given in place of the (integer) repeat count, in which case the preceding pattern is repeated as many times as necessary until the input is exhausted.

The output filenames consist of a prefix followed by a suffix. By default, the suffix is merely an ascending linear sequence of two-digit decimal numbers starting with 00 and ranging up to 99; however, this default may be overridden by either the `-digits` option or by the `-suffix-format` option. (See “Options,” next.) In any case, concatenating the output files in sorted order by filename produces the original input file, in order. The default output filename prefix is `xx`.

By default, if `csplit` encounters an error or receives a hangup, interrupt, quit, or terminate signal, it removes any output files that it has created so far before it exits.

OPTIONS

<code>-f, --prefix=prefix</code>	Use <code>prefix</code> as the output filename prefix string.
<code>-b, --suffix-format=suffix</code>	Use <code>suffix</code> as the output filename suffix string. When this option is specified, the suffix string must include exactly one <code>printf(3)</code> style conversion specification (such as <code>%d</code> , possibly including format specification flags, a field width, a precision specifications, or all of these kinds of modifiers). The conversion specification must be suitable for converting a binary integer argument to readable form. Thus, only <code>d</code> , <code>i</code> , <code>u</code> , <code>o</code> , <code>x</code> , and <code>X</code> format specifiers are allowed. The entire suffix string is given (with the current output file number) to <code>sprintf(3)</code> to form the filename suffixes for each of the individual output files in turn. Note that when this option is used, the <code>-digits</code> option is ignored.
<code>-n, --digits=digits</code>	Use output filenames containing numbers that are <code>digits</code> digits long instead of the default 2.
<code>-k, --keep-files</code>	Do not remove output files when errors are encountered.
<code>-z, --elide-empty-files</code>	Suppress the generation of zero-length output files. (In cases where the section delimiters of the input file are supposed to mark the first lines of each of the sections, the first output file will generally be a zero-length file unless you use this option.) Note that the output file sequence numbers will always run consecutively, starting from 0, even in cases where zero-length output sections are suppressed due to the use of this option.
<code>-s, -q, --silent, --quiet</code>	Do not print counts of output file sizes.
<code>--help</code>	Print a usage message and exit with a nonzero status.
<code>--version</code>	Print version information on standard output, then exit.

ctags

ctags—Generates tags and (optionally) refs files

SYNOPSIS

```
ctags [-BSstvrAT] filenames...
```

DESCRIPTION

ctags generates the tags and refs files from a group of C source files. The tags file is used by the elvis :tag command, control-J command, and -t option. The refs file is sometimes used by the ref(1) program.

Each C source file is scanned for #define statements and global function definitions. The name of the macro or function becomes the name of a tag. For each tag, a line is added to the tags file that contains the following:

- The name of the tag
- A tab character
- The name of the file containing the tag
- A tab character
- A way to find the particular line within the file

The filenames list will typically be the names of all C source files in the current directory, like this:

```
$ ctags -stv *.*[ch]
```

OPTIONS

- B Normally, ctags encloses regular expressions in slashes (/regexp/), which causes elvis to search from the top of the file. The -B flag causes ctags to enclose the regular expressions in question marks (?regexp?) so elvis will search backward from the bottom of the file. This rarely matters.
- t Include typedefs. A tag will be generated for each user-defined type. Also tags will be generated for struct and enum names. Types are considered to be global if they are defined in a header file, and static if they are defined in a C source file.
- v Include variable declarations. A tag will be generated for each variable, except for those that are declared inside the body of a function.
- s Include static tags. ctags will normally put global tags in the tags file, and silently ignore the static tags. This flag causes both global and static tags to be added. The name of a static tag is generated by prefixing the name of the declared item with the name of the file where it is defined, with a colon in between. For example, static foo(){} in bar.c results in a tag named bar.c:foo.
- S Include static tags, but make them look like global tags. Most tags-aware programs don't like the filename:tagname tags produced by the -s flag, so -S was added as an alternative. If elvis and ref are the only programs that read the tags file, then you don't need -S; otherwise, you do.
- r This causes ctags to generate both tags and refs. Without -r, it would only generate tags.
- a Append to tags, and maybe refs. Normally, ctags overwrites these files each time it is invoked. This flag is useful when you have too many files in the current directory for you to list them on a single command line; it allows you to split the arguments among several invocations.
- T This flag isn't available on all systems. UNIX has it, but most others don't. The -T flag prevents ctags from generating a tags file. This is useful when you want to generate a refs without changing tags.

FILES

- tags A cross-reference that lists each tag name, the name of the source file that contains it, and a way to locate a particular line in the source file.
- refs The refs file contains the definitions for each tag in the tags file, and very little else. This file can be useful, for example, when licensing restrictions prevent you from making the source code to the standard C library readable by everybody, but you still want everybody to know what arguments the library functions need.

BUGS

ctags is sensitive to indenting and line breaks. Consequently, it might not discover all of the tags in a file that is formatted in an unusual way.

SEE ALSO

elvis(1), refs(1)

AUTHOR

Steve Kirkendall (kirkenda@cs.pdx.edu)

CU

cu—Call up another system

SYNOPSIS

```
cu [ options ] [ system | phone | "dir" ]
```

DESCRIPTION

The `cu` command is used to call up another system and act as a dial in terminal. It can also do simple file transfers with no error checking.

`cu` takes a single argument, besides the options. If the argument is the string `dir`, `cu` will make a direct connection to the port. This may only be used by users with write access to the port, as it permits reprogramming the modem.

Otherwise, if the argument begins with a digit, it is taken to be a phone number to call. Otherwise, it is taken to be the name of a system to call. The `-z` or `—system` option may be used to name a system beginning with a digit, and the `-c` or `—phone` option may be used to name a phone number that does not begin with a digit.

`cu` locates a port to use in the UUCP configuration files. If a simple system name is given, it will select a port appropriate for that system. The `-p`, `—port`, `-l`, `—line`, `-s`, and `—speed` options may be used to control the port selection.

When a connection is made to the remote system, `cu` forks into two processes. One reads from the port and writes to the terminal, while the other reads from the terminal and writes to the port.

`cu` provides several commands that may be used during the conversation. The commands all begin with an escape character, initially `~` (tilde). The escape character is only recognized at the beginning of a line. To send an escape character to the remote system at the start of a line, it must be entered twice. All commands are either a single character or a word beginning with `%` (percent sign).

`cu` recognizes the following commands:

<code>~.</code>	Terminate the conversation.
<code>~! command</code>	Run <code>command</code> in a shell. If <code>command</code> is empty, starts up a shell.
<code>~\$ command</code>	Run <code>command</code> , sending the standard output to the remote system.
<code>~ command</code>	Run <code>command</code> , taking the standard input from the remote system.
<code>~+ command</code>	Run <code>command</code> , taking the standard input from the remote system and sending the standard output to the remote system.
<code>~#, ~%break</code>	Send a break signal, if possible.
<code>~c directory, ~%cd directory</code>	Change the local directory.
<code>~> file</code>	Send a file to the remote system. This just dumps the file over the communication line. It is assumed that the remote system is expecting it.
<code>~<</code>	Receive a file from the remote system. This prompts for the local filename and for the remote command to execute to begin the file transfer. It continues accepting data until the contents of the <code>eofread</code> variable are seen.

<code>^p from to, ^%put from to</code>	Send a file to a remote UNIX system. This runs the appropriate commands on the remote system.
<code>^t from to, ^%take from to</code>	Retrieve a file from a remote UNIX system. This runs the appropriate commands on the remote system.
<code>^s variable value</code>	Set a cu variable to the given value. If value is not given, the variable is set to <code>True</code> .
<code>^! variable</code>	Set a cu variable to <code>False</code> .
<code>^z</code>	Suspend the cu session. This is only supported on some systems. On systems for which <code>^z</code> may be used to suspend a job, <code>^^z</code> will also suspend the session.
<code>^%nostop</code>	Turn off XON/XOFF handling.
<code>^%stop</code>	Turn on XON/XOFF handling.
<code>^v</code>	List all the variables and their values.
<code>^?</code>	List all commands.
	cu also supports several variables. They may be listed with the <code>^v</code> command, and set with the <code>^s</code> or <code>^!</code> commands.
escape	The escape character. Initially <code>^</code> (tilde).
delay	If this variable is <code>True</code> , cu will delay for a second after recognizing the escape character before printing the name of the local system. The default is <code>True</code> .
eol	The list of characters which are considered to finish a line. The escape character is only recognized after one of these is seen. The default is carriage return, <code>^U</code> , <code>^C</code> , <code>^O</code> , <code>^D</code> , <code>^S</code> , <code>^Q</code> , <code>^R</code> .
binary	Whether to transfer binary data when sending a file. If this is <code>False</code> , then newlines in the file being sent are converted to carriage returns. The default is <code>False</code> .
binary-prefix	A string used before sending a binary character in a file transfer, if the binary variable is <code>True</code> . The default is <code>^Z</code> .
echo-check	Whether to check file transfers by examining what the remote system echoes back. This probably doesn't work very well. The default is <code>False</code> .
echonl	The character to look for after sending each line in a file. The default is carriage return.
timeout	The timeout to use, in seconds, when looking for a character, either when doing echo checking or when looking for the echonl character. The default is 30.
kill	The character to use to delete a line if the echo check fails. The default is <code>^U</code> .
resend	The number of times to resend a line if the echo check continues to fail. The default is 10.
eofwrite	The string to write after sending a file with the <code>^></code> command. The default is <code>^D</code> .
eofread	The string to look for when receiving a file with the <code>^<</code> command. The default is <code>\$</code> , which is intended to be a typical shell prompt.
verbose	Whether to print accumulated information during a file transfer. The default is <code>True</code> .

OPTIONS

The following options may be given to cu:

<code>-e, --parity=even</code>	Use even parity.
<code>-o, --parity=odd</code>	Use odd parity.
<code>--parity=none</code>	Use no parity. No parity is also used if both <code>-e</code> and <code>-o</code> are given.
<code>-h, --halfduplex</code>	Echo characters locally (half-duplex mode).
<code>-z system, --system system</code>	The system to call.
<code>-c phone-number, --phone phone-number</code>	The phone number to call.
<code>-p port, --port port</code>	Name the port to use.
<code>-a port</code>	Equivalent to <code>--port port</code> .
<code>-l line, --line line</code>	Name the line to use by giving a device name. This may be used to dial out on ports that are not listed in the UUCP configuration files. Write access to the device is required.

`-s speed, --speed speed`

`-#`

`-n, --prompt`

`-d`

`-x type, --debug type`

`-I file, --config file`

`-v, --version`

`--help`

The speed (baud rate) to use.

Where `#` is a number, equivalent to `--speed #`.

Prompt for the phone number to use.

Enter debugging mode. Equivalent to `--debug all`.

Turn on particular debugging types. The following types are recognized: `abnormal`, `chat`, `handshake`, `uucpproto`, `proto`, `port`, `config`, `spooldir`, `execute`, `incoming`, `outgoing`. Only `abnormal`, `chat`, `handshake`, `port`, `config`, `incoming` and `outgoing` are meaningful for `cu`. Multiple types may be given, separated by commas, and the `--debug` option may appear multiple times. A number may also be given, which will turn on that many types from the foregoing list; for example, `--debug 2` is equivalent to `--debug abnormal,chat`. `--debug all` may be used to turn on all debugging options.

Set configuration file to use. This option may not be available, depending upon how `cu` was compiled.

Report version information and exit.

Print a help message and exit.

BUGS

This program does not work very well.

FILES

The filename may be changed at compilation time, so this is only an approximation. Configuration file:

`/usr/lib/uucp/config`

AUTHOR

Ian Lance Taylor (ian@airs.com)

Taylor UUCP 1.05

cut

`cut`—Remove sections from each line of files

SYNOPSIS

`cut {-b byte-list, --bytes=byte-list} [-n] [--help] [--version] [file...]`

`cut {-c character-list, --characters=character-list} [--help] [--version] [file...]`

`cut {-f field-list, --fields=field-list} [-d delim] [-s] [--delimiter=delim] [--only-delimited] [--help] [--version] [file...]`

DESCRIPTION

This manual page documents the GNU version of `cut`. `cut` prints sections of each line of each input file, or the standard input if no files are given. A filename of `-` means standard input. The sections to be printed are selected by the options.

OPTIONS

The `byte-list`, `character-list`, and `field-list` options are one or more numbers or ranges (two numbers separated by a dash) separated by commas. The first byte, character, and field are numbered 1. Incomplete ranges may be given: `-m` means 1-`m`; `n-` means `n` through end of line or last field.

<code>-b, --bytes byte-list</code>	Print only the bytes in positions listed in <code>byte-list</code> . Tabs and backspaces are treated like any other character; they take up one byte.
<code>-c, --characters character-list</code>	Print only characters in positions listed in <code>character-list</code> . The same as <code>-b</code> for now, but internationalization will change that. Tabs and backspaces are treated like any other character; they take up one character.
<code>-f, --fields field-list</code>	Print only the fields listed in <code>field-list</code> . Fields are separated by TAB by default.
<code>-d, --delimiter delim</code>	For <code>-f</code> , fields are separated by the first character in <code>delim</code> instead of by TAB.
<code>-n</code>	Do not split multibyte characters (<code>no-op</code> for now).
<code>-s, --only-delimited</code>	For <code>-f</code> , do not print lines that do not contain the field separator character.
<code>--help</code>	Print a usage message and exit with a nonzero status.
<code>--version</code>	Print version information on standard output then exit.

GNU Text Utilities

CVS

cvs—Concurrent Versions System

SYNOPSIS

```
cvs [ cvs_options ] cvs-command [ command_options ][command_args ]
```

DESCRIPTION

cvs is a front end to the rcs(1) revision control system, which extends the notion of revision control from a collection of files in a single directory to a hierarchical collection of directories consisting of revision controlled files. These directories and files can be combined together to form a software release. cvs provides the functions necessary to manage these software releases and to control the concurrent editing of source files among multiple software developers.

cvs keeps a single copy of the master sources. This copy is called the source *repository*; it contains all the information to permit extracting previous software releases at any time based on either a symbolic revision tag, or a date in the past.

ESSENTIAL COMMANDS

cvs provides a rich variety of commands (`cvs_command` in the Synopsis), each of which often has a wealth of options, to satisfy the many needs of source management in distributed environments. However, you don't have to master every detail to do useful work with cvs; in fact, five commands are sufficient to use (and contribute to) the source repository.

<code>cvs checkout modules...</code>	A necessary preliminary for most cvs work: creates your private copy of the source for modules (named collections of source; you can also use a path relative to the source repository here). You can work with this copy without interfering with others' work. At least one subdirectory level is always created.
<code>cvs update</code>	Execute this command from within your private source directory when you wish to update your copies of source files from changes that other developers have made to the source in the repository.
<code>cvs add file...</code>	Use this command to enroll new files in cvs records of your working directory. The files will be added to the repository the next time you run <code>cvs commit</code> . Note: You should use the <code>cvs import</code> command to bootstrap new sources into the source repository. <code>cvs add</code> is only used for new files to an already checked-out module.
<code>cvs remove file...</code>	Use this command (after erasing any files listed) to declare that you wish to eliminate files from the repository. The removal does not affect others until you run <code>cvs commit</code> .
<code>cvs commit file...</code>	Use this command when you wish to “publish” your changes to other developers, by incorporating them in the source repository.

OPTIONS

The `cvs` command line can include `cvs_options`, which apply to the overall `cvs` program; a `cvs_command`, which specifies a particular action on the source repository; and `command_options` and `command_arguments` to fully specify what the `cvs_command` will do.

WARNING

You must be careful of precisely where you place options relative to the `cvs_command`. The same option can mean different things depending on whether it is in the `cvs_options` position (to the left of a `cvs` command) or in the `command_options` position (to the right of a `cvs` command).

There are only two situations where you may omit `cvs_command`: `cvs -H` or `cvs -help` elicits a list of available commands, and `cvs -v` or `cvs -version` displays version information on `cvs` itself.

CVS OPTIONS

As of release 1.6, `cvs` supports GNU style long options as well as short options. Only a few long options are currently supported; these are listed in brackets after the short options whose functions they duplicate.

Use these options to control the overall `cvs` program:

<code>-H [-help]</code>	Display usage information about the specified <code>cvs</code> command (but do not actually execute the command). If you don't specify a command name, <code>cvs -H</code> displays a summary of all the commands available.
<code>-Q</code>	Causes the command to be really quiet; the command will generate output only for serious problems.
<code>-q</code>	Causes the command to be somewhat quiet; informational messages, such as reports of recursion through subdirectories, are suppressed.
<code>-b bindir</code>	Use <code>bindir</code> as the directory where RCS programs are located. Overrides the setting of the <code>RCSBIN</code> environment variable. This value should be specified as an absolute pathname.
<code>-d CVS_root_directory</code>	Use <code>CVS_root_directory</code> as the root directory pathname of the master RCS source repository. Overrides the setting of the <code>CVS-ROOT</code> environment variable. This value should be specified as an absolute pathname.
<code>-e editor</code>	Use <code>editor</code> to enter revision log information. Overrides the setting of the <code>CVSEditor</code> and the <code>EDITOR</code> environment variables.
<code>-f</code>	Do not read the <code>cvs</code> startup file (<code>~/.cvsrc</code>).
<code>-l</code>	Do not log the <code>cvs_command</code> in the command history (but execute it anyway). See the description of the <code>history</code> command for information on command history.
<code>-n</code>	Do not change any files. Attempt to execute the <code>cvs_command</code> , but only to issue reports; do not remove, update, or merge any existing files, or create any new files.
<code>-t</code>	Trace program execution; display messages showing the steps of <code>cvs</code> activity. Particularly useful with <code>-n</code> to explore the potential impact of an unfamiliar command.
<code>-r</code>	Makes new working files read-only. Same effect as if the <code>CVS-READ</code> environment variable is set.
<code>-v [-version]</code>	Displays version and copyright information for <code>cvs</code> .
<code>-w</code>	Makes new working files read-write (default). Overrides the setting of the <code>CVSREAD</code> environment variable.
<code>-z compression-level</code>	When transferring files across the network use <code>gzip</code> with compression level <code>compression-level</code> to compress and decompress data as it is transferred. Requires the presence of the GNU <code>gzip</code> program in the current search path at both ends of the link.

USAGE

Except when requesting general help with `cvs -H`, you must specify a `cvs_command` to `cvs` to select a specific release control function to perform. Each `cvs` command accepts its own collection of options and arguments. However, many options are available across several commands. You can display a usage summary for each command by specifying the `-H` option with the command.

CVS STARTUP FILE

Normally, when `cvs` starts up, it reads the `.cvsrc` file from the home directory of the user reading it. This startup procedure can be turned off with the `-f` flag.

The `.cvsrc` file lists `cvs` commands with a list of arguments, one command per line. For example, the following line in

```
.cvsrc:
diff -c
```

will mean that the `cvs diff` command will always be passed the `-c` option in addition to any other options that are specified in the command line (in this case, it will have the effect of producing context sensitive diffs for all executions of `cvs diff`).

CVS COMMAND SUMMARY

Here are brief descriptions of all the `cvs` commands:

<code>add</code>	Add a new file or directory to the repository, pending a <code>cvs commit</code> on the same file. Can only be done from within sources created by a previous <code>cvs checkout</code> invocation. Use <code>cvs import</code> to place whole new hierarchies of sources under <code>cvs</code> control. (Does not directly affect repository; changes working directory.)
<code>admin</code>	Execute RCS control functions on the source repository. (Changes repository directly; uses working directory without changing it.)
<code>checkout</code>	Make a working directory of source files for editing. (Creates or changes working directory.)
<code>commit</code>	Apply to the source repository changes, additions, and deletions from your working directory. (Changes repository.)
<code>diff</code>	Show differences between files in working directory and source repository, or between two revisions in source repository. (Does not change either repository or working directory.)
<code>export</code>	Prepare copies of a set of source files for shipment off site. Differs from <code>cvs checkout</code> in that no <code>cvs</code> administrative directories are created (and therefore <code>cvs commit</code> cannot be executed from a directory prepared with <code>cvs export</code>), and a symbolic tag must be specified. (Does not change repository; creates directory similar to working directories).
<code>history</code>	Show reports on <code>cvs</code> commands that you or others have executed on a particular file or directory in the source repository. (Does not change repository or working directory.) History logs are kept only if enabled by creation of the <code>\$CVSROOT/CVSROOT/history</code> file; see <code>cvs(5)</code> .
<code>import</code>	Incorporate a set of updates from off-site into the source repository, as a “vendor branch.” (Changes repository.)
<code>log</code>	Display RCS log information. (Does not change repository or working directory.)
<code>rdiff</code>	Prepare a collection of <code>diffs</code> as a patch file between two releases in the repository. (Does not change repository or working directory.)
<code>release</code>	Cancel a <code>cvs checkout</code> , abandoning any changes. (Can delete working directory; no effect on repository.)
<code>remove</code>	Remove files from the source repository, pending a <code>cvs commit</code> on the same files. (Does not directly affect repository; changes working directory.)
<code>rtag</code>	Explicitly specify a symbolic tag for particular revisions of files in the source repository. See also <code>cvs tag</code> . (Changes repository directly; does not require or affect working directory.)
<code>status</code>	Show current status of files: latest version, version in working directory, whether working version has been edited and, optionally, symbolic tags in the RCS file. (Does not change repository or working directory.)

tag	Specify a symbolic tag for files in the repository. By default, tags the revisions that were last synchronized with your working directory. (Changes repository directly; uses working directory without changing it.)
update	Bring your working directory up to date with changes from the repository. Merges are performed automatically when possible; a warning is issued if manual resolution is required for conflicting changes. (Changes working directory; does not change repository.)

COMMON COMMAND OPTIONS

This section describes the `command_options` that are available across several `cvs` commands. Not all commands support all of these options; each option is only supported for commands where it makes sense. However, when a command has one of these options you can count on the same meaning for the option as in other commands. (Other command options, which are listed with the individual commands, may have different meanings from one `cvs` command to another.)

WARNING

The `history` command is an exception; it supports many options that conflict even with these standard options.

-D date	Use the most recent revision no later than <code>date_spec</code> (a single argument, date description specifying a date in the past). A wide variety of date formats are supported by the underlying RCS facilities, similar to those described in <code>co(1)</code>, but not exactly the same. The <code>date_spec</code> is interpreted as being in the local time zone, unless a specific time zone is specified. The specification is “sticky” when you use it to make a private copy of a source file; that is, when you get a working file using <code>-D</code>, <code>cvs</code> records the date you specified, so that further updates in the same directory will use the same date (unless you explicitly override it; see the description of the <code>update</code> command). <code>-D</code> is available with the <code>checkout</code>, <code>diff</code>, <code>history</code>, <code>export</code>, <code>rdiff</code>, <code>rtag</code>, and <code>update</code> commands. Examples of valid date specifications include the following: 1 month ago 2 hours ago 400000 seconds ago - last year - last Monday - yesterday - a fortnight ago 3/31/92 10:00:07 PST - January 23, 1987 10:05pm 22:00 GMT
-f	When you specify a particular date or tag to <code>cvs</code> commands, they normally ignore files that do not contain the tag (or did not exist on the date) that you specified. Use the <code>-f</code> option if you want files retrieved even when there is no match for the tag or date. (The most recent version is used in this situation.) <code>-f</code> is available with these commands: <code>checkout</code> , <code>export</code> , <code>rdiff</code> , <code>rtag</code> , and <code>update</code> .
-H	Help; describe the options available for this command. This is the only option supported for all <code>cvs</code> commands.
-k kflag	Alter the default RCS processing of keywords; all the <code>-k</code> options described in <code>co(1)</code> are available. The <code>-k</code> option is available with the <code>add</code>, <code>checkout</code>, <code>diff</code>, <code>export</code>, <code>rdiff</code>, and <code>update</code> commands. Your <code>kflag</code> specification is “sticky” when you use it to create a private copy of a source file; that is, when you use this option with the <code>checkout</code> or <code>update</code> commands, <code>cvs</code> associates your selected <code>kflag</code> with the file, and continues to use it with future <code>update</code> commands on the same file until you specify otherwise. Some of the more useful <code>kflags</code> are <code>-ko</code> and <code>-kb</code> (for binary files, only compatible with RCS version 5.7 or later), and <code>-kv</code>, which is useful for an <code>export</code> where you wish to retain keyword information after an import at some other site.

- l Local; run only in current working directory, rather than recurring through subdirectories. Available with the following commands: `checkout`, `commit`, `diff`, `export`, `remove`, `rdiff`, `rtag`, `status`, `tag`, and `update`.

WARNING

This is not the same as the overall `cvs -l` option, which you can specify to the left of a `cvs` command.

- n Do not run any `checkout/commit/tag/update` program. (A program can be specified to run on each of these activities, in the modules database; this option bypasses it.) Available with the `checkout`, `commit`, `export`, and `rtag` commands.

WARNING

This is not the same as the overall `cvs -n` option, which you can specify to the left of a `cvs` command.

- P Prune (remove) directories that are empty after being updated, on `checkout`, or `update`. Normally, an empty directory (one that is void of revision-controlled files) is left alone. Specifying `-P` will cause these directories to be silently removed from your checked-out sources. This does not remove the directory from the repository, only from your checked out copy. Note that this option is implied by the `-r` or `-d` options of `checkout` and `export`.
- p Pipe the files retrieved from the repository to standard output, rather than writing them in the current directory. Available with the `checkout` and `update` commands.
- r tag Use the revision specified by the `tag` argument instead of the default `head` revision. As well as arbitrary tags defined with the `tag` or `rtag` command, two special tags are always available: `HEAD` refers to the most recent version available in the repository, and `BASE` refers to the revision you last checked out into the current working directory. The `tag` specification is “sticky” when you use this option with `cvs checkout` or `cvs update` to make your own copy of a file: `cvs` remembers the tag and continues to use it on future `update` commands, until you specify otherwise. `tag` can be either a symbolic or numeric tag, in RCS fashion. Specifying the `-q` global option along with the `-r` command option is often useful, to suppress the warning messages when the RCS file does not contain the specified tag. `-r` is available with the `checkout`, `commit`, `diff`, `history`, `export`, `rdiff`, `rtag`, and `update` commands.

WARNING

This is not the same as the overall `cvs -r` option, which you can specify to the left of a `cvs` command.

cvs COMMANDS

Here (finally) are details on all the `cvs` commands and the options each accepts. The summary lines at the top of each command’s description highlight three kinds of things:

Command Options and Arguments	Special options are described in detail; common command options may appear only in the summary line.
Working Directory, or Repository?	Some <code>cvs</code> commands require a working directory to operate; some require a repository. Also, some commands change the repository, some change the working directory, and some change nothing.
Synonyms	Many commands have synonyms, which you may find easier to remember (or type) than the principal name.

- `add [-k kflag][-m 'message'] files...`
 Requires: Repository, working directory
 Changes: Working directory
 Synonym: `new`

Use the `add` command to create a new file or directory in the RCS source repository. The files or directories specified with `add` must already exist in the current directory (which must have been created with the `checkout` command). To add a whole new directory hierarchy to the source repository (for example, files received from a third-party vendor), use the `cvs import` command instead.

If the argument to `cvs add` refers to an immediate subdirectory, the directory is created at the correct place in the RCS source repository, and the necessary `cvs` administration files are created in your working directory. If the directory already exists in the source repository, `cvs add` still creates the administration files in your version of the directory. This allows you to use `cvs add` to add a particular directory to your private sources even if someone else created that directory after your checkout of the sources. You can do the following:

```
example% mkdir new_directory
example% cvs add new_directory
example% cvs update new_directory
```

An alternate approach using `cvs update` might be:

```
example% cvs update -d new_directory
```

(To add any available new directories to your working directory, it's probably simpler to use `cvs checkout` or `cvs update -d`.)

The added files are not placed in the RCS source repository until you use `cvs commit` to make the change permanent. Doing a `cvs add` on a file that was removed with the `cvs remove` command will resurrect the file, if no `cvs commit` command intervened.

You will have the opportunity to specify a logging message, as usual, when you use `cvs commit` to make the new file permanent. If you'd like to have another logging message associated with just creation of the file (for example, to describe the file's purpose), you can specify it with the `-m message` option to the `add` command.

The `-k kflag` option specifies the default way that this file will be checked out. The `kflag` argument is stored in the RCS file and can be changed with `cvs admin`. Specifying `-ko` is useful for checking in binaries that shouldn't have the RCS `id` strings expanded.

- `admin [rcs-options] files...`
 Requires: Repository, working directory
 Changes: Repository
 Synonym: `rcs`

This is the `cvs` interface to assorted administrative RCS facilities, documented in `rcs(1)`. `cvs admin` simply passes all its options and arguments to the `rcs` command; it does no filtering or other processing. This command does work recursively, however, so extreme care should be used.

- `checkout [options] modules...`
 Requires: Repository
 Changes: Working directory
 Synonyms: `co`, `get`

Make a working directory containing copies of the source files specified by `modules`. You must execute `cvs checkout` before using most of the other `cvs` commands, since most of them operate on your working directory.

`modules` are either symbolic names [themselves defined as the module `modules` in the source repository; see `cvs(5)`] for some collection of source directories and files, or paths to directories or files in the repository.

Depending on the modules you specify, `checkout` may recursively create directories and populate them with the appropriate source files. You can then edit these source files at any time (regardless of whether other software developers are editing their

own copies of the sources); update them to include new changes applied by others to the source repository; or commit your work as a permanent change to the RCS repository.

Note that `checkout` is used to create directories. The top-level directory created is always added to the directory where `checkout` is invoked, and usually has the same name as the specified module. In the case of a module alias, the created subdirectory may have a different name, but you can be sure that it will be a subdirectory, and that `checkout` will show the relative path leading to each file as it is extracted into your private work area (unless you specify the `-q` global option).

Running `cvs checkout` on a directory that was already built by a prior `checkout` is also permitted, and has the same effect as specifying the `-d` option to the `update` command described later.

The options permitted with `cvs checkout` include the standard command options `-P`, `-f`, `-k kflag`, `-l`, `-n`, `-p`, `-r tag`, and `-D date`. In addition to those, you can use several special command options with `checkout`, as detailed in the following paragraphs.

Use the `-A` option to reset any sticky tags, dates, or `-k` options. (If you get a working file using one of the `-r`, `-D`, or `-k` options, `cvs` remembers the corresponding tag, date, or `kflag` and continues using it on future updates; use the `-A` option to make `cvs` forget these specifications, and retrieve the head version of the file).

The `-j` branch option merges the changes made between the resulting revision and the revision that it is based on (for example, if the tag refers to a branch, `cvs` will merge all changes made in that branch into your working file).

With two `-j` options, `cvs` will merge in the changes between the two respective revisions. This can be used to “remove” a certain delta from your working file.

In addition, each `-j` option can contain an optional date specification which, when used with branches, can limit the chosen revision to one within a specific date. An optional date is specified by adding a colon (`:`) to the tag. An example might be what `cvs import` tells you to do when you have just imported sources that have conflicts with local changes:

```
example% cvs checkout -jTAG:yesterday -jTAG module
```

Use the `-N` option with `-d dir` to avoid shortening module paths in your working directory. (Normally, `cvs` shortens paths as much as possible when you specify an explicit target directory.)

Use the `-c` option to copy the module file, sorted, to the standard output, instead of creating or modifying any files or directories in your working directory.

Use the `-d dir` option to create a directory called `dir` for the working files, instead of using the module name. Unless you also use `-N`, the paths created under `dir` will be as short as possible.

Use the `-s` option to display per-module status information stored with the `-s` option within the modules file.

```
■ commit [-lnR][-m 'log_message' | -f file][-r revision][files...]
```

Requires: Working directory, repository

Changes: Repository

Synonym: `ci`

Use `cvs commit` when you want to incorporate changes from your working source files into the general source repository.

If you don't specify particular files to commit, all of the files in your working current directory are examined. `commit` is careful to change in the repository only those files that you have really changed. By default (or if you explicitly specify the `-r` option), files in subdirectories are also examined and committed if they have changed; you can use the `-l` option to limit `commit` to the current directory only. Sometimes you may want to force a file to be committed even though it is unchanged; this is achieved with the `-f` flag, which also has the effect of disabling recursion (you can turn it back on with `-R`, of course).

`commit` verifies that the selected files are up-to-date with the current revisions in the source repository; it will notify you, and exit without committing, if any of the specified files must be made current first with `cvs update`. `commit` does not call the `update` command for you, but rather leaves that for you to do when the time is right.

When all is well, an editor is invoked to allow you to enter a log message that will be written to one or more logging programs and placed in the RCS source repository file. You can instead specify the log message on the command line with

the `-m` option, thus suppressing the editor invocation, or use the `-F` option to specify that the argument file contains the log message.

The `-r` option can be used to commit to a particular symbolic or numeric revision within the RCS file. For example, to bring all your files up to the RCS revision 3.0 (including those that haven't changed), you might use

```
example% cvs commit -r3.0
```

cvs will only allow you to commit to a revision that is on the main trunk (a revision with a single dot). However, you can also commit to a branch revision (one that has an even number of dots) with the `-r` option. To create a branch revision, one typically use the `-b` option of the `rtag` or `tag` commands. Then, either `checkout` or `update` can be used to base your sources on the newly created branch. From that point on, all `commit` changes made within these working sources will be automatically added to a branch revision, thereby not perturbing mainline development in any way. For example, if you had to create a patch to the 1.2 version of the product, even though the 2.0 version is already under development, you might use this:

```
example% cvs rtag -b -rFCS1_2 FCS1_2 Patch product_module
example% cvs checkout -rFCS1_2_Patch product module
example% cd product module
[[ hack away ]]
example% cvs commit
```

Say you have been working on some extremely experimental software, based on whatever revision you happened to checkout last week. If others in your group would like to work on this software with you, but without disturbing mainline development, you could commit your change to a new branch. Others can then check out your experimental stuff and utilize the full benefit of cvs conflict resolution. The scenario might look like this:

```
example% cvs tag -b EXPR1
example% cvs update -rEXPR1
[[ hack away ]]
example% cvs commit
```

Others would simply do `cvs checkout -rEXPR1 whatever_module` to work with you on the experimental change.

```
■ diff [-k1][rcsdiff_options][[-r rev1 | -D date1][[-r rev2 | -D date2]] [files...]
```

Requires: Working directory, repository

Changes: Nothing

You can compare your working files with revisions in the source repository, with the `cvs diff` command. If you don't specify a particular revision, your files are compared with the revisions they were based on. You can also use the standard `cvs` command option `-r` to specify a particular revision to compare your files with. Finally, if you use `-r` twice, you can see differences between two revisions in the repository. You can also specify `-D` options to `diff` against a revision in the past. The `-r` and `-D` options can be mixed together with at most two options ever specified.

See `rcsdiff(1)` for a list of other accepted options.

If you don't specify any files, `diff` will display differences for all those files in the current directory (and its subdirectories, unless you use the standard option `-1`) that differ from the corresponding revision in the source repository (that is, files that you have changed), or that differ from the revision specified.

```
■ export [-f lNnQq] -r rev | -D date [-d dir][[-k kflag] module...]
```

Requires: Repository

Changes: Current directory

This command is a variant of `cvs checkout`; use it when you want a copy of the source for `module` without the `cvs` administrative directories. For example, you might use `cvs export` to prepare source for shipment off-site. This command requires that you specify a date or tag (with `-D` or `-r`), so that you can count on reproducing the source you ship to others.

The only nonstandard options are `-d dir` (write the source into directory `dir`) and `-N` (don't shorten module paths). These have the same meanings as the same options in `cvs checkout`.

The `-kv` option is useful when `export` is used. This causes any RCS keywords to be expanded such that an import done at some other site will not lose the keyword revision information. Other `kflag` options may be used with `cvs export` and are described in `co(1)`.

- `history [-report][-flags][-options args][files...]`
 Requires: The file `$CVSROOT/CVSROOT/history`
 Changes: Nothing

`cvs` keeps a history file that tracks each use of the `checkout`, `commit`, `rtag`, `update`, and `release` commands. You can use `cvs history` to display this information in various formats.

WARNING

`cvs history` uses `-f`, `-l`, `-n`, and `-p` in ways that conflict with the descriptions in “Common Command Options,” earlier in this manual page.

Several options (shown as `[-report]` in the preceding bulleted code line) control what kind of report is generated:

- `-c` Report on each time `commit` was used (that is, each time the repository was modified).
- `-m module` Report on a particular module. (You can meaningfully use `-m` more than once on the command line.)
- `-o` Report on checked-out modules.
- `-T` Report on all tags.
- `-x type` Extract a particular set of record types `x` from the `cvs history`. The types are indicated by single letters, which you may specify in combination. Certain commands have a single record type: `check-out` (type `O`), `release` (type `F`), and `rtag` (type `T`). One of four record types may result from an `update`: `w`, when the working copy of a file is deleted during update (because it was gone from the repository); `u`, when a working file was copied from the repository; `g`, when a merge was necessary and it succeeded; and `c`, when a merge was necessary but collisions were detected (requiring manual merging). Finally, one of three record types results from `commit`: `M`, when a file was modified; `A`, when a file is first added; and `R`, when a file is removed.
- `-e` Everything (all record types); equivalent to specifying `-xMACFROGWNUT`.
- `-z zone` Use time zone `zone` when outputting history records. The zone name `LT` stands for local time; numeric offsets stand for hours and minutes ahead of UTC. For example, `+0530` stands for 5 hours and 30 minutes ahead of (that is, east of) UTC.

The options shown as `-flags` constrain the report without requiring option arguments:

- `-a` Show data for all users. (The default is to show data only for the user executing `cvs history`.)
- `-l` Show last modification only.
- `-w` Show only the records for modifications done from the same working directory where `cvs history` is executing.

The options shown as `-options args` constrain the report based on an argument:

- `-b str` Show data back to a record containing the string `str` in either the module name, the filename, or the repository path.
- `-D date` Show data since `date`.
- `-p repository` Show data for a particular source repository (you can specify several `-p` options on the same command line).
- `-r rev` Show records referring to revisions since the revision or tag named `rev` appears in individual RCS files. Each RCS file is searched for the revision or tag.
- `-t tag` Show records since tag `tag` was last added to the history file. This differs from the `-r` flag in that it reads only the history file, not the RCS files, and is much faster.
- `-u name` Show records for username.

- `import [-options] repository vendortag releasetag ...`
 Requires: Repository, source distribution directory
 Changes: Repository

Use `cvcs import` to incorporate an entire source distribution from an outside source (for example, a source vendor) into your source repository directory. You can use this command both for initial creation of a repository, and for wholesale updates to the module from the outside source.

The `repository` argument gives a directory name (or a path to a directory) under the CVS root directory for repositories; if the directory did not exist, `import` creates it.

When you use `import` for updates to source that has been modified in your source repository (since a prior `import`), it will notify you of any files that conflict in the two branches of development; use `cvcs checkout -j` to reconcile the differences, as `import` instructs you to do.

By default, certain filenames are ignored during `cvcs import`: names associated with CVS administration, or with other common source control systems; common names for patch files, object files, archive files, and editor backup files; and other names that are usually artifacts of assorted utilities. Currently, the default list of ignored files includes files matching these names:

```
RCSLOG RCS SCCS
CVS* cvslog.*
tags TAGS
.make.state .nse_depinfo
~ #* .*#* ,
.old *.bak *.BAK *.orig *.rej .del-*
.a *.o *.so *.Z *.elc *.ln core
```

The outside source is saved in a first-level RCS branch, by default `1.1.1`. Updates are leaves of this branch; for example, files from the first imported collection of source will be revision `1.1.1.1`, then files from the first imported update will be revision `1.1.1.2`, and so on.

At least three arguments are required. `repository` is needed to identify the collection of source. `vendortag` is a tag for the entire branch (for example, for `1.1.1`). You must also specify at least one `releasetag` to identify the files at the leaves created each time you execute `cvcs import`.

One of the standard `cvcs` command options is available: `-m message`. If you do not specify a logging message with `-m`, your editor is invoked (as with `commit`) to allow you to enter one.

There are three additional special options.

Use `-d` to specify that each file's time of last modification should be used for the checkin date and time.

Use `-b branch` to specify a first-level branch other than `1.1.1`.

Use `-I name` to specify filenames that should be ignored during import. You can use this option repeatedly. To avoid ignoring any files at all (even those ignored by default), specify `-I !`.

- `log [-l] rlog-options [files...]`
 Requires: Repository, working directory
 Changes: Nothing
 Synonym: `rlog`

Display log information for `files`. `cvcs log` calls the RCS utility `rlog`; all the options described in `rlog(1)` are available. Among the more useful `rlog` options are `-h` to display only the header (including tag definitions, but omitting most of the full log); `-r` to select logs on particular revisions or ranges of revisions; and `-d` to select particular dates or date ranges. See `rlog(1)` for full explanations. This command is recursive by default, unless the `-l` option is specified.

■ `rdiff [-flags][-V vn][-r t1|-D d [-r t2|-D d2]] modules...`

Requires: Repository
Changes: Nothing
Synonym: patch

Builds a Larry Wall format `patch(1)` file between two releases that can be fed directly into the `patch` program to bring an old release up-to-date with the new release. (This is one of the few `cvs` commands that operates directly from the repository and doesn't require a prior checkout.) The `diff` output is sent to the standard output device. You can specify (using the standard `-r` and `-D` options) any combination of one or two revisions or dates. If only one revision or date is specified, the `patch` file reflects differences between that revision or date and the current head revisions in the RCS file.

Note that if the software release affected is contained in more than one directory, then it may be necessary to specify the `-p` option to the `patch` command when patching the old sources, so that `patch` is able to find the files that are located in other directories.

If you use the option `-V vn`, RCS keywords are expanded according to the rules current in RCS version `vn` (the expansion format changed with RCS version 5).

The standard option `flags -f` and `-l` are available with this command. There are also several special options `flags`.

If you use the `-s` option, no `patch` output is produced. Instead, a summary of the changed or added files between the two releases is sent to the standard output device. This is useful for finding out, for example, which files have changed between two dates or revisions.

If you use the `-t` option, a `diff` of the top two revisions is sent to the standard output device. This is most useful for seeing what the last change to a file was.

If you use the `-u` option, the `patch` output uses the newer `unidiff` format for context `diffs`.

You can use `-c` to explicitly specify the `diff -c` form of context `diffs` (which is the default), if you like.

■ `release [-dQq] modules...`

Requires: Working directory
Changes: Working directory, history log

This command is meant to safely cancel the effect of `cvs checkout`. Since `cvs` doesn't lock files, it isn't strictly necessary to use this command. You can always simply delete your working directory, if you like; but you risk losing changes you may have forgotten, and you leave no trace in the `cvs history` file that you've abandoned your checkout.

Use `cvs release` to avoid these problems. This command checks that no uncommitted changes are present; that you are executing it from immediately above, or inside, a `cvs` working directory; and that the repository recorded for your files is the same as the repository defined in the module database.

If all these conditions are true, `cvs release` leaves a record of its execution (attesting to your intentionally abandoning your checkout) in the `cvs history` log.

You can use the `-d` flag to request that your working copies of the source files be deleted if the `release` succeeds.

■ `remove [-lR][files...]`

Requires: Working directory
Changes: Working directory
Synonyms: `rm`, `delete`

Use this command to declare that you wish to remove files from the source repository. Like most `cvs` commands, `cvs remove` works on files in your working directory, not directly on the repository. As a safeguard, it also requires that you first erase the specified files from your working directory.

The files are not actually removed until you apply your changes to the repository with `commit`; at that point, the corresponding RCS files in the source repository are moved into the `Attic` directory (also within the source repository).

This command is recursive by default, scheduling all physically removed files that it finds for removal by the next commit. Use the `-l` option to avoid this recursion, or just specify that actual files that you wish remove to consider.

- `rtag [-f alnRQq][{-b}][{-d}][{-r tag | -D date}] symbolic_tag modules...`
- Requires: Repository
- Changes: Repository
- Synonym: `rfreeze`

You can use this command to assign symbolic tags to particular, explicitly specified source versions in the repository. `cvs rtag` works directly on the repository contents (and requires no prior checkout). Use `cvs tag` instead, to base the selection of versions to tag on the contents of your working directory.

In general, tags (often the symbolic names of software distributions) should not be removed, but the `-d` option is available as a means to remove completely obsolete symbolic names if necessary (as might be the case for an Alpha release, say).

`cvs rtag` will not move a tag that already exists. With the `-F` option, however, `cvs rtag` will relocate any instance of `symbolic_tag` that already exists on that file to the new repository versions. Without the `-F` option, attempting to use `cvs rtag` to apply a tag that already exists on that file will produce an error message.

The `-b` option makes the tag a *branch* tag, allowing concurrent, isolated development. This is most useful for creating a patch to a previously released software distribution.

You can use the standard `-r` and `-D` options to tag only those files that already contain a certain tag. This method would be used to rename a tag; tag only the files identified by the old tag, then delete the old tag, leaving the new tag on exactly the same files as the old tag.

`rtag` executes recursively by default, tagging all subdirectories of modules you specify in the argument. You can restrict its operation to top-level directories with the standard `-l` option; or you can explicitly request recursion with `-R`.

The modules database can specify a program to execute whenever a tag is specified; a typical use is to send electronic mail to a group of interested parties. If you want to bypass that program, use the standard `-n` option.

Use the `-a` option to have `rtag` look in the Attic for removed files that contain the specified tag. The tag is removed from these files, which makes it convenient to reuse a symbolic tag as development continues (and files get removed from the upcoming distribution).

- `status [-lRqQ][{-v}][files ...]`
- Requires: Working directory, repository
- Changes: Nothing

Display a brief report on the current status of files with respect to the source repository, including any sticky tags, dates, or `-k` options. (Sticky options will restrict how `cvs update` operates until you reset them; see the description of `cvs update -A...`

You can also use this command to anticipate the potential impact of a `cvs update` on your working source directory. If you do not specify any files explicitly, reports are shown for all files that `cvs` has placed in your working directory. You can limit the scope of this search to the current directory itself (not its subdirectories) with the standard `-l` option flag; or you can explicitly request recursive status reports with the `-R` option.

The `-v` option causes the symbolic tags for the RCS file to be displayed as well.

- `tag [-lQqR][{-F}][{-b}][{-d}][{-r tag | -D date}][{-f} symbolic_tag [files ...]`
- Requires: Working directory, repository
- Changes: Repository
- Synonym: `freeze`

Use this command to assign symbolic tags to the nearest repository versions to your working sources. The tags are applied immediately to the repository, as with `rtag`. One use for tags is to record a “snapshot” of the current sources when the software freeze date of a project arrives. As bugs are fixed after the freeze date, only those changed sources that are to be part of the release need be retagged.

The symbolic tags are meant to permanently record which revisions of which files were used in creating a software distribution. The `checkout`, `export`, and `update` commands allow you to extract an exact copy of a tagged release at any time in the future, regardless of whether files have been changed, added, or removed since the release was tagged.

You can use the standard `-r` and `-D` options to tag only those files that already contain a certain tag. This method would be used to rename a tag: tag only the files identified by the old tag, then delete the old tag, leaving the new tag on exactly the same files as the old tag.

Specifying the `-f` flag in addition to the `-r` or `-D` flags will tag those files named on the command line even if they do not contain the old tag or did not exist on the specified date.

By default (without a `-r` or `-D` flag), the versions to be tagged are supplied implicitly by the `cvs` records of your working files' history rather than applied explicitly.

If you use `cvs tag -d symbolic tag...`, the symbolic tag you specify is deleted instead of being added.

WARNING

Be very certain of your ground before you delete a tag; doing this effectively discards some historical information, which may later turn out to have been valuable.

`cvs tag` will not move a tag that already exists. With the `-F` option, however, `cvs tag` will relocate any instance of symbolic tag that already exists on that file to the new repository versions. Without the `-F` option, attempting to use `cvs tag` to apply a tag that already exists on that file will produce an error message.

The `-b` option makes the tag a branch tag, allowing concurrent, isolated development. This is most useful for creating a patch to a previously released software distribution.

Normally, `tag` executes recursively through subdirectories; you can prevent this by using the standard `-l` option, or specify the recursion explicitly by using `-R`.

■ `update [-Adf lPpQqR][-d][-r tag][-D date] files...`

Requires: Repository, working directory

Changes: Working directory

After you've run `checkout` to create your private copy of source from the common repository, other developers will continue changing the central source. From time to time, when it is convenient in your development process, you can use the `update` command from within your working directory to reconcile your work with any revisions applied to the source repository since your last `checkout` or `update`.

`update` keeps you informed of its progress by printing a line for each file, prefaced with one of the characters `U`, `A`, `R`, `M`, `C`, or `?` to indicate the status of the file:

<code>U</code> file	The file was brought up-to-date with respect to the repository. This is done for any file that exists in the repository but not in your source, and for files that you haven't changed but are not the most recent versions available in the repository.
<code>A</code> file	The file has been added to your private copy of the sources, and will be added to the RCS source repository when you run <code>cvs commit</code> on the file. This is a reminder to you that the file needs to be committed.
<code>R</code> file	The file has been removed from your private copy of the sources, and will be removed from the RCS source repository when you run <code>cvs commit</code> on the file. This is a reminder to you that the file needs to be committed.
<code>M</code> file	The file is modified in your working directory. <code>M</code> can indicate one of two states for a file you're working on: either there were no modifications to the same file in the repository, so that your file remains as you last saw it; or there were modifications in the repository as well as in your copy, but they were merged successfully, without conflict, in your working directory.

C file A conflict was detected while trying to merge your changes to *file* with changes from the source repository. *file* (the copy in your working directory) is now the output of the `rcsmerge(1)` command on the two versions; an unmodified copy of your file is also in your working directory, with the name `.#file.version`, where *version* is the RCS revision that your modified file started from. (Note that some systems automatically purge files that begin with `.#` if they have not been accessed for a few days. If you intend to keep a copy of your original file, it is a very good idea to rename it.)

? file *file* is in your working directory, but does not correspond to anything in the source repository, and is not in the list of files for `cvs` to ignore; see the description of the `-I` option.

Use the `-A` option to reset any sticky tags, dates, or `-k` options. (If you get a working copy of a file by using one of the `-r`, `-D`, or `-k` options, `cvs` remembers the corresponding tag, date, or `kflag` and continues using it on future updates; use the `-A` option to make `cvs` forget these specifications, and retrieve the head version of the file).

The `-jbranch` option merges the changes made between the resulting revision and the revision that it is based on. (For example, if the tag refers to a branch, `cvs` will merge all changes made in that branch into your working file.)

With two `-j` options, `cvs` will merge in the changes between the two respective revisions. This can be used to “remove” a certain delta from your working file. For example, if the file `foo.c` is based on revision 1.6 and I want to remove the changes made between 1.3 and 1.5, I might do this:

```
example% cvs update -j1.5 -j1.3 foo.c # note the order...
```

In addition, each `-j` option can contain an optional date specification which, when used with branches, can limit the chosen revision to one within a specific date. An optional date is specified by adding a colon (`:`) to the tag:

```
-jSymbolic Tag:Date Specifier
```

Use the `-d` option to create any directories that exist in the repository if they’re missing from the working directory. (Normally, `update` acts only on directories and files that were already enrolled in your working directory.) This is useful for updating directories that were created in the repository since the initial checkout; but it has an unfortunate side effect. If you deliberately avoided certain directories in the repository when you created your working directory (either through use of a module name or by listing explicitly the files and directories you wanted on the command line), then updating with `-d` will create those directories, which may not be what you want.

Use `-I name` to ignore files whose names match *name* (in your working directory) during the update. You can specify `-I` more than once on the command line to specify several files to ignore. By default, `update` ignores files whose names match any of the following:

```
RCSLOG RCS SCCS
CVS* cvslog.*
tags TAGS
.make.state .nse_depinfo
~ #* .#* ,
.old *.bak *.BAK *.orig *.rej .del-*
.a *.o *.so *.Z *.elc *.ln core
```

Use `-I!` to avoid ignoring any files at all.

The standard `cvs` command options `-f`, `-k`, `-l`, `-P`, `-p`, and `-r` are also available with `update`.

FILES

For more detailed information on `cvs` supporting files, see `cvs(5)`.

Files in home directories:

.cvsrc The `cvs` initialization file. Lines in this file can be used to specify default options for each `cvs` command. For example, the line `diff -c` will ensure that `cvs diff` is always passed the `-c` option in addition to any other options passed on the command line.

.cvswrappers Specifies wrappers to be used in addition to those specified in the `CVSROOT/cvswrappers` file in the repository.

Files in working directories:

CVS	A directory of cvs administrative files. Do not delete.
CVS/Entries	List and status of files in your working directory.
CVS/Entries.Backup	A backup of CVS/Entries.
CVS/Entries.Static	Flag: do not add more entries on cvs update.
CVS/Root	Pathname to the repository (CVSRROOT) location at the time of checkout. This file is used instead of the CVSRROOT environment variable if the environment variable is not set. A warning message will be issued when the contents of this file and the CVSRROOT environment variable differ. The file may be overridden by the presence of the CVS_IGNORE_REMOTE_ROOT environment variable.
CVS/Repository	Pathname to the corresponding directory in the source repository.
CVS/Tag	Contains the per-directory sticky tag or date information. This file is created/updated when you specify -r or -D to the checkout or update commands, and no files are specified.
CVS/Checkin.prog	Name of program to run on cvs commit.
CVS/Update.prog	Name of program to run on cvs update.

Files in source repositories:

\$CVSRROOT/CVSRROOT	Directory of global administrative files for repository.
CVSRROOT/commitinfo,v	Records programs for filtering cvs commit requests.
CVSRROOT/cvswrappers,v	Records cvs wrapper commands to be used when checking files into and out of the repository. Wrappers allow the file or directory to be processed on the way in and out of cvs. The intended uses are many; one possible use would be to reformat a C file before the file is checked in, so all of the code in the repository looks the same.
CVSRROOT/editinfo,v	Records programs for editing/validating cvs commit log entries.
CVSRROOT/history	Log file of cvs transactions.
CVSRROOT/loginfo,v	Records programs for piping cvs commit log entries.
CVSRROOT/modules,v	Definitions for modules in this repository.
CVSRROOT/rcsinfo,v	Records pathnames to templates used during a cvs commit operation.
CVSRROOT/taginfo,v	Records programs for validating/logging cvs tag and cvs rtag operations.
MODULE/Attic	Directory for removed source files.
#cvs.lock	A lock directory created by cvs when doing sensitive changes to the RCS source repository.
#cvs.tfl.pid	Temporary lock file for repository.
#cvs.rfl.pid	A read lock.
#cvs.wfl.pid	A write lock.

ENVIRONMENT VARIABLES

CVSRROOT	Should contain the full pathname to the root of the cvs source repository (where the RCS files are kept). This information must be available to cvs for most commands to execute; if CVSRROOT is not set, or if you wish to override it for one invocation, you can supply it on the command line: <code>cvs -d cvsroot cvs command...</code> You may not need to set CVSRROOT if your cvs binary has the right path compiled in; use <code>cvs -v</code> to display all compiled-in paths.
CVSREAD	If this is set, checkout and update will try hard to make the files in your working directory read-only. When this is not set, the default behavior is to permit modification of your working files.
RCSBIN	Specifies the full pathname where to find RCS programs, such as <code>co(1)</code> and <code>ci(1)</code> . If not set, a compiled-in value is used; see the display from <code>cvs -v</code> .
CVSEDITOR	Specifies the program to use for recording log messages during commit. If not set, the EDITOR environment variable is used instead. If EDITOR is not set either, the default is <code>/usr/ucb/vi</code> .
CVS_IGNORE_REMOTE_ROOT	If this variable is set, then cvs will ignore all references to remote repositories in the CVS/Root file.

<code>CVS_RSH</code>	<code>cvs</code> uses the contents of this variable to determine the name of the remote shell command to use when starting a <code>cvs</code> server. If this variable is not set then <code>rsh</code> is used.
<code>CVS_SERVER</code>	<code>cvs</code> uses the contents of this variable to determine the name of the <code>cvs</code> server command. If this variable is not set then <code>cvs</code> is used.
<code>CVSWRAPPERS</code>	This variable is used by the <code>cvswrappers</code> script to determine the name of the wrapper file, in addition to the wrappers defaults contained in the repository (<code>CVSROOT/cvswrappers</code>) and the user's home directory (<code>~/cvswrappers</code>).

AUTHORS

Dick Grune	Original author of the <code>cvs</code> shell script version posted to <code>comp.sources.unix</code> in the volume 6 release of December, 1986. Credited with much of the <code>cvs</code> conflict resolution algorithms.
Brian Berliner	Coder and designer of the <code>cvs</code> program itself in April, 1989, based on the original work done by Dick.
Jeff Polk	Helped Brian with the design of the <code>cvs</code> module and vendor branch support and author of the <code>checkin(1)</code> shell script (the ancestor of <code>cvs import</code>).

SEE ALSO

`ci(1)`, `co(1)`, `cvs(5)`, `cvsbug(8)`, `diff(1)`, `grep(1)`, `patch(1)`, `rcs(1)`, `rcsdiff(1)`, `rcsmerge(1)`, `rlogbug(8)`

13 March 1996

date

`date`—Show and set date and time

SYNOPSIS

```
date [ -u ][-c ][-n ][-d dsttype ] [ -t minutes-west ] [ -a [+!-]sss.fff ][+format ][
[yyyy]mmddhhmm[yy][.ss]]
```

DESCRIPTION

Date without arguments writes the date and time to the standard output in the form:

```
Wed Mar 8 14:54:40 EST 1989
```

with `EST` replaced by the local time zone's abbreviation (or by the abbreviation for the time zone specified in the `TZ` environment variable if set). The exact output format depends on the locale.

If a command-line argument starts with a plus sign (+), the rest of the argument is used as a format that controls what appears in the output. In the format, when a percent sign (%) appears, it and the character after it are not output, but rather identify part of the date or time to be output in a particular way (or identify a special character to output):

Argument	Sample output	Explanation
%a	Wed	Abbreviated weekday name*
%A	Wednesday	Full weekday name*
%b	Mar	Abbreviated month name*
%B	March	Full month name*
%c	Wed Mar 08 14:54:40 1989	Date and time*
%C	19	Century
%d	08	Day of month (always two digits)
%D	03/08/89	Month/day/year (eight characters)

<i>Argument</i>	<i>Sample output</i>	<i>Explanation</i>
%e	8	Day of month (leading zero blanked)
%h	Mar	Abbreviated month name*
%H	14	24-hour-clock hour (two digits)
%I	02	12-hour-clock hour (two digits)
%j	067	Julian day number (three digits)
%k	2	12-hour-clock hour (leading zero blanked)
%l	14	24-hour-clock hour (leading zero blanked)
%m	03	Month number (two digits)
%M	54	Minute (two digits)
%n	nn	Newline character
%p	PM	AM/PM designation
%r	02:54:40 PM	Hour:minute:second AM/PM designation
%R	14:54	Hour:minute
%S	40	Second (two digits)
%t	nt	Tab character
%T	14:54:40	Hour:minute:second
%U	10	Sunday-based week number (two digits)
%w	3	Day number (one digit, Sunday is 0)
%W	10	Monday-based week number (two digits)
%x	03/08/89	Date*
%X	14:54:40	Time*
%y	89	Last two digits of year
%Y	1989	Year in full
%Z	EST	Time zone abbreviation
#+	Wed Mar 8 14:54:40 EST 1989	Default output format*

* The exact output depends on the locale.

If a character other than one of those shown in the preceding table appears after a percent sign in the format, that following character is output. All other characters in the format are copied unchanged to the output; a newline character is always added at the end of the output.

In Sunday-based week numbering, the first Sunday of the year begins week 1; days preceding it are part of week 0. In Monday-based week numbering, the first Monday of the year begins week 1.

To set the date, use a command-line argument with one of the following forms:

1454	24-hour-clock hours (first two digits) and minutes
081454	Month day (first two digits), hours, and minutes
03081454	Month (two digits, January is 01), month day, hours, minutes
8903081454	Year, month, month day, hours, minutes
0308145489	Month, month day, hours, minutes, year (on System V-compatible systems)
030814541989	Month, month day, hours, minutes, four-digit year
198903081454	Four-digit year, month, month day, hours, minutes

If the century, year, month, or month day is not given, the current value is used. Any of the preceding forms may be followed by a period and two digits that give the seconds part of the new time; if no seconds are given, zero is assumed.

These options are available:

<code>-u</code> or <code>-c</code>	Use GMT when setting and showing the date and time.
<code>-n</code>	Do not notify other networked systems of the time change.
<code>-d dsttype</code>	Set the kernel-stored Daylight Saving Time type to the given value. (The kernel-stored DST type is used mostly by “old” binaries.)
<code>-t minutes-west</code>	Set the kernel-stored “minutes west of GMT” value to the one given on the command line. (The kernel-stored DST type is used mostly by “old” binaries.)
<code>-a adjustment</code>	Change the time forward (or backward) by the number of seconds (and fractions thereof) specified in the adjustment argument. Either the seconds part or the fractions part of the argument (but not both) may be omitted. On BSD-based systems, the adjustment is made by changing the rate at which time advances; on System-V-based systems, the adjustment is made by changing the time.

FILES

<code>/usr/lib/locale/L/LC_TIME</code>	Description of time locale <code>L</code>
<code>/usr/local/etc/zoneinfo</code>	Time zone information directory
<code>/usr/local/etc/zoneinfo/localtime</code>	Local time zone file
<code>/usr/local/etc/zoneinfo/posixrules</code>	Used with POSIX-style TZs
<code>/usr/local/etc/zoneinfo/GMT</code>	For UTC leap seconds

If `/usr/local/etc/zoneinfo/GMT` is absent, UTC leap seconds are loaded from `/usr/local/etc/zoneinfo/posixrules`.

dd

`dd`—Convert a file while copying it (data dumper)

SYNOPSIS

```
dd [-help] [--version] [if=file] [of=file] [ibs=bytes] [obs=bytes] [bs=bytes]
[obs=bytes] [skip=blocks] [seek=blocks] [count=blocks] [conv={ascii,
ebcdic, ibm, block, unblock, lcase, ucase, swab, noerror, notrunc, sync}]
```

DESCRIPTION

This manual page documents the GNU version of `dd`. `dd` copies a file (from the standard input to the standard output, by default) with a user-selectable blocksize, while optionally performing conversions on it.

OPTIONS

Numbers can be followed by a multiplier:

`b=512`, `c=1`, `k=1024`, `w=2`, `xm=number m`

These options are available:

<code>--help</code>	Print a usage message on standard output and exit successfully.
<code>--version</code>	Print version information on standard output then exit successfully.
<code>if=file</code>	Read from file instead of the standard input.
<code>of=file</code>	Write to file instead of the standard output. Unless <code>conv=notrunc</code> is given, truncate file to the size specified by <code>seek=</code> (0 bytes if <code>seek=</code> is not given).
<code>ibs=bytes</code>	Read bytes bytes at a time.
<code>obs=bytes</code>	Write bytes bytes at a time.
<code>bs=bytes</code>	Read and write bytes bytes at a time. Override <code>ibs</code> and <code>obs</code> .

cbs=bytes	Convert bytes bytes at a time.
skip=blocks	Skip blocks ibs-sized blocks at start of input.
seek=blocks	Skip blocks obs-sized blocks at start of output.
count=blocks	Copy only blocks ibs-sized input blocks.
conv=conversion[,conversion...]	Convert the file as specified by the conversion arguments.
Conversions:	
ascii	Convert EBCDIC to ASCII.
ebcdic	Convert ASCII to EBCDIC.
ibm	Convert ASCII to alternate EBCDIC.
block	Pad newline-terminated records to size of cbs, replacing newline with trailing spaces.
unblock	Replace trailing spaces in cbs-sized block with newline.
lcase	Change uppercase characters to lowercase.
ucase	Change lowercase characters to uppercase.
swab	Swap every pair of input bytes. Unlike the UNIX dd, this works when an odd number of bytes are read. If the input file contains an odd number of bytes, the last byte is simply copied (since there is nothing to swap it with).
noerror	Continue after read errors.
notrunc	Do not truncate the output file.
sync	Pad every input block to size of ibs with trailing NULLs.

GNU File Utilities

depmod, modprobe

depmod, modprobe—Handle loadable modules automatically

SYNOPSIS

```
depmod [-a]
depmod module1.o module2.o ...

modprobe module.o [symbol=value ...]
modprobe -t tag pattern
modprobe -a -t tag pattern modprobe -l [ -t tag ] pattern
modprobe -r module
modprobe -c
```

DESCRIPTION

These utilities are intended to make a Linux modular kernel manageable for all users, administrators, and distribution maintainers.

depmod creates a makefile-like dependency file, based on the symbols it finds in the set of modules mentioned on the command line (or in a default place). This dependency file can later be used by modprobe to automatically load the relevant module(s).

modprobe is used to load a set of modules—either a single module, a stack of dependent modules, or all modules that are marked with a specified tag.

modprobe will automatically load all base modules needed in a module stack, as described by the dependency file modules.dep. If the loading of one of these modules fails, the whole current stack of modules will be unloaded (by rmmod) automatically.

modprobe has two ways of loading modules. One way (the probe mode) will try to load a module out of a list (defined by pattern). It stops loading as soon as one module load successfully. This can be used to autoload one Ethernet driver out of a list, for example. The other way is to load all modules from a list. This can be used to load some modules at boot time.

With the option `-r`, `modprobe` will automatically unload a stack of modules, similar to the way `rmmod -r` does.

Option `-l` combined with option `-t` lists all available modules of a certain type. An enhanced `mount` command could use the command:

```
modprobe -l -t fs
```

to get the list of all file system drivers available and on request load the proper one. So, the `mount` command could become more generic as well. (The `kernel` solves this without changing the `mount` utility.)

Option `-c` will print all configuration (default + configuration file).

The normal use of `depmod` is to include the line `/sbin/depmod -a` in one of the `rc-files` in `/etc/rc.d`, so that the correct module dependencies will be available immediately after booting the system.

Option `-d` puts `depmod` in debug mode. It outputs all commands it is issuing.

Option `-e` outputs the list of unresolved symbol for each module. Normally, `depmod` only outputs the list of unloadable modules.

Option `-v` outputs the list of all processed modules.

Modules may be located at different place in the filesystem, but there will always be some need to override this, especially for module developers. We expect some official standard will emerge, defined by the FSSTND. Until that time, you might as well use this suggested directory structure.

CONFIGURATION

The behavior of `depmod` and `modprobe` can be adjusted by the (optional) configuration file `/etc/conf.modules`.

The configuration file consists of a set of lines. All empty lines, and all text on a line after a `#`, will be ignored. Lines may be continued by ending the line with a `\`. The remaining lines should all conform to one of the following formats:

```
keep
parameter=value
options module symbol=value ...
alias module real_name
pre-install module command ...
install module command ...
post-install module command ...
pre-remove module command ...
remove module command ...
post-remove module command ...
parameter=value options module symbol=value ... alias module real_name
```

All values in the parameter lines will be processed by a shell, which means that shell tricks like wildcards and commands enclosed in backquotes can be used:

```
path[misc]=/lib/modules/1.1.57/misc
path[net]=/lib/modules/'uname -r'/net
```

Parameters may be repeated multiple times.

These are the legal parameters:

<code>depfile=DEPFILE_PATH</code>	This is the path to the dependency file that will be created by <code>depmod</code> and used by <code>modprobe</code> .
<code>path=SOME_PATH</code>	The path parameter specifies a directory to search for the modules.
<code>path[tag]=SOME_PATH</code>	The path parameter can carry an optional tag. This tells us a little more about the purpose of the modules in this directory and allows some automated operations by <code>modprobe</code> . The tag is appended to the path keyword enclosed in square brackets. If the tag is missing, the tag <code>misc</code> is assumed. One very useful tag is <code>boot</code> , which can be used to mark all modules that should be loaded at boot time.

If the configuration file `/etc/conf.modules` is missing, or if any parameter is not overridden, the following defaults are assumed:

```

depfile=/lib/modules/'uname -r'/modules.dep
path[boot]=/lib/modules/boot

path[fs]=/lib/modules/'uname -r'/fs
path[misc]=/lib/modules/'uname -r'/misc
path[net]=/lib/modules/'uname -r'/net
path[scsi]=/lib/modules/'uname -r'/scsi

path[fs]=/lib/modules/default/fs
path[misc]=/lib/modules/default/misc
path[net]=/lib/modules/default/net
path[scsi]=/lib/modules/default/scsi

path[fs]=/lib/modules/fs
path[misc]=/lib/modules/misc
path[net]=/lib/modules/net
path[scsi]=/lib/modules/scsi

```

All option lines specify the default options that are needed for a module, as in

```
modprobe de620 bnc=1
```

These options will be overridden by any options given on the `modprobe` command line.

The alias lines can be used to give alias names to modules. A line in `/etc/conf.modules` that looks like this:

```
alias iso9660 isofs
```

makes it possible to write `modprobe iso9660`, although there is no such module available.

STRATEGY

The idea is that `modprobe` will look first at the directory containing modules compiled for the current release of the kernel. If the module is not found there, `modprobe` will look in the directory containing modules for a default release.

When you install a new Linux, the modules should be moved to a directory related to the release (and version) of the kernel you are installing. Then you should do a symlink from this directory to the default directory.

Each time you compile a new kernel, the command `make modules_install` will create a new directory, but won't change the default.

When you get a module unrelated to the kernel distribution, you should place it in one of the version-independent directories under `/lib/modules`.

This is the default strategy, which can be overridden in `/etc/conf.modules`.

EXAMPLES

<code>modprobe -t net</code>	Load one of the modules that are stored in the directory tagged <code>net</code> . Each module is tried until one succeeds. (Default: <code>/lib/modules/net</code>).
<code>modprobe -a -t boot</code>	All modules that are stored in the directory tagged <code>boot</code> will be loaded. (Default: <code>/lib/modules/boot</code>).
<code>modprobe slip.o</code>	This will attempt to load the module <code>slhc.o</code> if it was not previously loaded, since the <code>slip</code> module needs the functionality in the <code>slhc</code> module. This dependency will be described in the file <code>modules.dep</code> that was created automatically by <code>depmod</code> .
<code>modprobe -r slip.o</code>	Will unload <code>slip.o</code> . It will also unload <code>slhc.o</code> automatically, unless it is used by some other module as well (such as <code>ppp.o</code>).

FILES

```

/etc/conf.modules
/lib/modules/*/modules.dep
/lib/modules/*

```

SEE ALSO

lsmod(1), kernelld(8), ksyms(1), modules(2)

REQUIRED UTILITIES

insmod(1), nm(1) rmmod(1)

NOTES

The pattern supplied to `modprobe` will often be escaped to ensure that it is evaluated in the proper context.

AUTHOR

Jacques Gelinas (jack@solucorp.qc.ca), Bjorn Ekwall (bj0rn@blox.se)

BUGS

Naah...

Linux, 14 May 1995

df

df—Summarize free disk space

SYNOPSIS

```
df [-aikPv] [-t fstype] [-x fstype] [--all] [--inodes] [--type=fstype]
  [--exclude-type=fstype] [--kilobytes] [--portability] [--print-type]
  [--help] [--version] [filename...]
```

DESCRIPTION

This manual page documents the GNU version of **df**. **df** displays the amount of disk space available on the filesystem containing each filename argument. If no filename is given, the space available on all currently mounted filesystems is shown. Disk space is shown in 1K blocks by default, unless the environment variable `POSIXLY_CORRECT` is set, in which case 512-byte blocks are used.

If an argument is the absolute filename of a disk device node containing a mounted filesystem, **df** shows the space available on that filesystem rather than on the filesystem containing the device node (which is always the root filesystem). This version of **df** cannot show the space available on unmounted filesystems, because on most kinds of systems doing so requires very nonportable, intimate knowledge of filesystem structures.

OPTIONS

-a, --all	Include in the listing filesystems that have 0 blocks, which are omitted by default. Such filesystems are typically special-purpose pseudo-filesystems, such as automounter entries. On some systems, filesystems of type <code>ignore</code> or <code>auto</code> are also omitted by default and included in the listing by this option.
-i, --inodes	List inode usage information instead of block usage. An inode (short for “index node”) is a special kind of disk block that contains information about a file, such as its owner, permissions, timestamps, and location on the disk.
-k, --kilobytes	Print sizes in 1K blocks instead of 512-byte blocks. This overrides the environment variable <code>POSIXLY_CORRECT</code> .
-P, --portability	Use the <code>POSIX</code> output format. This is like the default format except that the information about each filesystem is always printed on exactly one line; a mount device is never put on a line by itself. This means that if the mount device name is more than 20 characters long (as for some network mounts), the columns are misaligned.

<code>-T, --print-type</code>	Print a type string for each filesystem. Any such printed filesystem type name may be used as an argument to either of the <code>--type=</code> or <code>--exclude-type=</code> options.
<code>-t, --type=fstype</code>	Limit the listing to filesystems of type <code>fstype</code> . Multiple filesystem types can be shown by giving multiple <code>-t</code> options. By default, all filesystem types are listed.
<code>-x, --exclude-type=fstype</code>	Limit the listing to filesystems not of type <code>fstype</code> . Multiple filesystem types can be eliminated by giving multiple <code>-x</code> options. By default, all filesystem types are listed.
<code>-v</code>	Ignored; for compatibility with System V versions of <code>df</code> .
<code>--help</code>	Print a usage message on standard output and exit successfully.
<code>--version</code>	Print version information on standard output then exit successfully.

GNU File Utilities

dig

dig—Send domain name query packets to name servers

SYNOPSIS

```
dig [@server] domain [<query-type>][<query-class>][+<query-option>][-<dig-option>]
[%comment]
```

DESCRIPTION

dig (domain information groper) is a flexible command-line tool that can be used to gather information from the Domain Name System servers. dig has two modes: simple interactive mode that makes a single query, and batch that executes a query for each in a list of several query lines. All query options are accessible from the command line.

The usual simple use of dig takes the form:

```
dig @server domain query-type query-class
```

where

`server` May be either a domain name or a dot-notation Internet address. If this optional field is omitted, dig will attempt to use the default name server for your machine.

NOTE

If a domain name is specified, this will be resolved using the domain name system resolver (BIND). If your system does not support DNS, you may have to specify a dot-notation address. Alternatively, if there is a server at your disposal somewhere, all that is required is that `/etc/resolv.conf` be present and indicate where the default name servers reside, so that server itself can be resolved. See `resolver(5)` for information on `/etc/resolv.conf`.

WARNING

Changing `/etc/resolv.conf` will affect the standard resolver library and potentially several programs that use it.) As an option, the user may set the environment variable `LOCALRES` to name a file which is to be used instead of `/etc/resolv.conf` (`LOCALRES` is specific to the dig resolver and not referenced by the standard resolver). If the `LOCALRES` variable is not set or the file is not readable, then `/etc/resolv.conf` will be used.

`domain` The domain name for which you are requesting information. See “Options” [-x] for a convenient way to specify inverse address query.

`query-type` The type of information (DNS query type) that you are requesting. If omitted, the default is a (`T_A` = address). The following types are recognized:

Type	Example	Description
a	T_A	Network address
any	T_ANY	All/any information about specified domain
mx	T_MX	Mail exchanger for the domain
ns	T_NS	Name servers
soa	T_SOA	Zone of authority record
hinfo	T_HINFO	Host information
axfr	T_AXFR	Zone transfer (must ask an authoritative server)
txt	T_TXT	Arbitrary number of strings

(See RFC 1035 for the complete list.)

`query-class` The network class requested in the query. If omitted, the default is in (`C_IN` = Internet). The following classes are recognized:

in	C_IN	Internet class domain
any	C_ANY	All/any class information

(See RFC 1035 for the complete list.)

NOTE

any can be used to specify a class and/or a type of query. dig will parse the first occurrence of any to mean `query-type = T_ANY`.

To specify `query-class = C_ANY` you must either specify any twice, or set `query-class` using `-c` option. (See “Other Options,” next.)

OTHER OPTIONS

`%ignored-comment` % is used to include an argument that is simply not parsed. This may be useful if running dig in batch mode. Instead of resolving every @server-domain-name in a list of queries, you can avoid the overhead of doing so, and still have the domain name on the command line as a reference. Example:

```
dig @128.9.0.32 %venera.isi.edu mx isis.edu
```

`-<dig option>` - is used to specify an option that affects the operation of dig. The following options are currently available (although not guaranteed to be useful):

<code>-x dot-notation-address</code>	Convenient form to specify inverse address mapping. Instead of <code>dig 32.0.9.128.in-addr.arpa</code> one can simply use <code>dig -x 128.9.0.32</code>
<code>-f file</code>	File for dig batch mode. The file contains a list of query specifications (dig command lines) which are to be executed successively. Lines beginning with ;, #, or \n are ignored. Other options may still appear on the command line, and will be in effect for each batch query.
<code>-T time</code>	Time in seconds between start of successive queries when running in batch mode. Can be used to keep two or more batch dig commands running roughly in sync. Default is zero.

<code>-p port</code>	Port number. Query a name server listening to a nonstandard port number. Default is 53.
<code>-P[ping-string]</code>	After query returns, execute a <code>ping(8)</code> command for response time comparison. This rather unelegantly makes a call to the shell. The last three lines of statistics is printed for the command: <code>ping -s server_name 56 3</code> If the optional <code>ping string</code> is present, it replaces <code>ping -s</code> in the shell command.
<code>-t query-type</code>	Specify type of query. May specify either an integer value to be included in the type field or use the abbreviated mnemonic as discussed earlier (<code>mx = T_MX</code>).
<code>-c query-class</code>	Specify class of query. May specify either an integer value to be included in the class field or use the abbreviated mnemonic as discussed earlier (<code>in = C_IN</code>).
<code>-envsav</code>	This flag specifies that the <code>dig</code> environment (defaults, print options, and so on), after all of the arguments are parsed, should be saved to a file to become the default environment. Useful if you do not like the standard set of defaults and do not desire to include a large number of options each time <code>dig</code> is used. The environment consists of resolver state variable flags, timeout, and retries as well as the flags detailing <code>dig</code> output (see below). If the shell environment variable <code>LOCALDEF</code> is set to the name of a file, this is where the default <code>dig</code> environment is saved. If not, the file <code>DIG.env</code> is created in the current working directory.

NOTE

`LOCALDEF` is specific to the `dig` resolver, and will not affect operation of the standard resolver library.

	Each time <code>dig</code> is executed, it looks for <code>./DIG.env</code> or the file specified by the shell environment variable <code>LOCALDEF</code> . If such file exists and is readable, then the environment is restored from this file before any arguments are parsed.
<code>-envset</code>	This flag only affects batch query runs. When <code>-envset</code> is specified on a line in a <code>dig</code> batch file, the <code>dig</code> environment after the arguments are parsed, becomes the default environment for the duration of the batch file, or until the next line which specifies <code>-envset</code> .
<code>-[no]stick</code>	This flag only affects batch query runs. It specifies that the <code>dig</code> environment (as read initially or set by <code>-envset</code> switch) is to be restored before each query (line) in a <code>dig</code> batch file. The default <code>-nostick</code> means that the <code>dig</code> environment does not stick, hence options specified on a single line in a <code>dig</code> batch file will remain in effect for subsequent lines (that is, they are not restored to the sticky default).
<code>+<query option></code>	<code>+</code> is used to specify an option to be changed in the query packet or to change <code>dig</code> output specifics. Many of these are the same parameters accepted by <code>nslookup(8)</code>. If an option requires a parameter, the form is as follows: <code>+keyword[=value]</code> Most keywords can be abbreviated. Parsing of the <code>+</code> options is very simplistic—a value must not be separated from its keyword by whitespace. The following keywords are currently available:

Keyword Abbreviation	Meaning (Default)
<code>[no]debug (deb)</code>	Turn on/off debugging mode <code>[deb]</code>
<code>[no]d2</code>	Turn on/off extra debugging mode <code>[nod2]</code>
<code>[no]recurse (rec)</code>	Use/don't use recursive lookup <code>[rec]</code>
<code>retry=# (ret)</code>	Set number of retries to # <code>[4]</code>

continues

<i>Keyword Abbreviation</i>	<i>Meaning (Default)</i>
time=# (ti)	Set timeout length to # seconds [4]
[no]ko	Keep open option (implies vc) [noko]
[no]vc	Use/don't use virtual circuit [novc]
[no]defname (def)	Use/don't use default domain name [def]
[no]search (sea)	Use/don't use domain search list [sea]
domain=NAME (do)	Set default domain name to NAME
[no]ignore (i)	Ignore/don't ignore trunc. errors [noi]
[no]primary (pr)	Use/don't use primary server [nopr]
[no]aaonly (aa)	Authoritative query only flag [noaa]
[no]sort (sor)	Sort resource records [nosor]
[no]cmd	Echo parsed arguments [cmd]
[no]stats (st)	Print query statistics [st]
[no]Header (H)	Print basic header [H]
[no]header (he)	Print header flags [he]
[no]ttlid (tt)	Print TTLs [tt]
[no]cl	Print class info [nocl]
[no]qr	Print outgoing query [noqr]
[no]reply (rep)	Print reply [rep]
[no]ques (qu)	Print question section [qu]
[no]answer (an)	Print answer section [an]
[no]author (au)	Print authoritative section [au]
[no]addit (ad)	Print additional section [ad]
pfdef	Set to default print flags
pfmin	Set to minimal default print flags
pfset=#	Set print flags to # (# can be hex/octal/decimal)
pfand=#	Bitwise and print flags with #
pfor=#	Bitwise or print flags with #

The `retry` and `time` options affect the retransmission strategy used by resolver library when sending datagram queries. The algorithm is as follows:

```

August 30, 1990
for i = 0 to retry - 1
  for j = 1 to num_servers
    send_query
  wait((time * (2**i)) / num_servers)
end
end

```

Note that `dig` always uses a value of 1 for `num_servers`.

DETAILS

`dig` once required a slightly modified version of the BIND resolver (3) library. BIND's resolver has (as of BIND 4.9) been augmented to work properly with `dig`. Essentially, `dig` is a straightforward (albeit not pretty) effort of parsing arguments and setting appropriate parameters. `dig` uses resolver routines `res_init()`, `res_mkquery()`, `res_send()` as well as accessing `_res` structure.

FILES

`/etc/resolv.conf`

Initial domain name and name server addresses

ENVIRONMENT

LOCALRES file to use in place of `/etc/resolv.conf`

LOCALDEF default environment file

AUTHOR

Steve Hotz (hotz@isi.edu)

ACKNOWLEDGMENTS

`dig` uses functions from `nslookup(8)` authored by Andrew Cherenon.

BUGS

`dig` has a serious case of “creeping featurism,” the result of considering several potential uses during its development. It would probably benefit from a rigorous diet. Similarly, the print flags and granularity of the items they specify make evident their rather ad hoc genesis.

`dig` does not consistently exit nicely (with appropriate status) when a problem occurs somewhere in the resolver (Most of the common exit cases are handled.) This is particularly annoying when running in batch mode. If it exits abnormally (and is not caught), the entire batch aborts; when such an event is trapped, `dig` simply continues with the next query.

SEE ALSO

`named(8)`, `resolver(3)`, `resolver(5)`, `nslookup(8)`

30 August 1990

dnsquery

dnsquery — Query domain name servers using resolver

SYNOPSIS

```
dnsquery [-n nameserver] [-t type] [-c class] [-r retry] [-p retry period]
[-d] [-s] [-v] host
```

DESCRIPTION

The `dnsquery` program is a general interface to nameservers via BIND resolver library calls. The program supports queries to the nameserver with an opcode of `QUERY`. This program is intended to be a replacement or supplement to programs like `nstest`, `nsquery`, and `nslookup`. All arguments except for `host` and `ns` are treated without case-sensitivity.

OPTIONS

- `-n` The nameserver to be used in the query. Nameservers can appear as either Internet addresses of the form `w.x.y.z` or can appear as domain names. (default: as specified in `/etc/resolv.conf`)
- `-t` The type of resource record of interest. Types include:

A	Address
NS	Nameserver
CNAME	Canonical name
PTR	Domain name pointer
SOA	Start of authority

WKS	Well-known service
HINFO	Host information
MINFO	Mailbox information
MX	Mail exchange
RP	Responsible person
MG	Mail group member
AFSDB	DCE or AFS server
ANY	Wildcard

NOTE

Any case may be used (the default is *ANY*).

-c The class of resource records of interest. Classes include the following:

IN	Internet
HS	Hesiod
CHAOS	Chaos
ANY	Wildcard

NOTE

Any case may be used (the default is *IN*).

-r The number of times to retry if the nameserver is not responding. (default: 4)
-p Period to wait before timing out. (default: `RES_TIMEOUT`) options field. (default: any answer)
-d Turn on debugging. This sets the `RES_DEBUG` bit of the resolver's options field. (default: no debugging)
-s Use a stream rather than a packet. This uses a TCP stream connection with the nameserver rather than a UDP datagram. This sets the `RES_USEVC` bit of the resolver's options field. (default: `UDP`)
-v Synonym for the `s` flag.
host The name of the host (or domain) of interest.

FILES

<code>/etc/resolv.conf</code>	To get the default <code>ns</code> and search lists.
<code><arpa/nameser.h></code>	List of usable <code>RR</code> types and classes
<code><resolv.h></code>	List of resolver flags

SEE ALSO

`nslookup(8)`, `nstest(1)`, `nsquery(1)`, `named(8)`, `resolver(5)`

DIAGNOSTICS

If the resolver fails to answer the query and debugging has not been turned on, `dnsquery` will simply print a message like this:

```
Query failed (rc = 1) : Unknown host
```

The value of the return code is supplied by `h_errno`.

BUGS

Queries of a class other than `IN` can have interesting results since ordinarily a nameserver only has a list of root nameservers for class `IN` resource records.

Query uses a call to `inet_addr()` to determine if the argument for the `-n` option is a valid Internet address. Unfortunately, `inet_addr()` seems to cause a segmentation fault with some (bad) addresses (for example, 1.2.3.4.5).

AUTHOR

Bryan Beecher

10 March 1990

domainname

`domainname`—Set or print domain of current host

SYNOPSIS

```
domainname [ name ]
```

DESCRIPTION

`domainname` prints the domain name of the current host, from the `getdomainname(3)` library call. If an argument is present and the effective UID is 0, `domainname` changes the name of the host, with the `setdomainname(2)` system call. This is usually done at boot time in the `/etc/rc.local` script.

FILES

`/etc/rc.local`

SEE ALSO

`getdomainname(3)`, `setdomainname(2)`, `uname(1)`, `uname(2)`

AUTHOR

Lars Wirzenius by substituting in `hostname.c`

Linux 0.98, 26 December 1992

dsplit

`dsplit`—Split a large file into pieces

SYNOPSIS

```
dsplit [ -size nnn ][input_file [ output_base ]]
```

DESCRIPTION

`dsplit` splits binary files into smaller chunks so that they may be placed on floppy disks.

OPTIONS

<code>-size nnn</code>	Specifies the size of each output file, in bytes. The default is 1457000, which is enough to fill a 1.44MB floppy disk.
<code>input_file</code>	Specifies the name of the file to split up. A <code>-</code> indicates standard input. The default is standard input.

`output_base` Specifies the name of the output files to be written. `dsplit` will append `000`, `001`, ..., to the `output_base`. The default is `dsplit`.

AUTHOR'S NOTES

Submitted by: David Arnstein (arnstein@netcom.com)

Posting number: Volume 40, Issue 51

Archive name: `dsplit/part01`

Environment: MS-DOS, UNIX

Here is a portable binary file splitting program. It reads a binary file and splits it into pieces. I use this program to put large binary files on floppy disks. For this reason, the default size of the output files is 1,457,000 bytes, which just about fills up a 1.44MB floppy disk.

Unlike other binary split programs I have seen, `dsplit` does not `malloc` a huge block of memory. `dsplit` is suitable for use under MS-DOS and other primitive operating systems.

(The program came from `gatekeeper.dec.com:/pub/usenet/comp.sources.misc/volume40/dsplit`).

Linux 1.1, 5 July 1994

du

`du`—Summarize disk usage

SYNOPSIS

```
du [-abcklsxDLS] [-all] [-total] [-count-links] [-summarize] [-bytes]
[-kilobytes] [-one-file-system] [-separate-dirs] [-dereference]
[-dereference-args] [-help] [--version] [filename...]
```

DESCRIPTION

This manual page documents the GNU version of `du`. `du` displays the amount of disk space used by each argument and for each subdirectory of directory arguments. The space is measured in 1K blocks by default, unless the environment variable `POSIXLY_CORRECT` is set, in which case 512-byte blocks are used.

OPTIONS

<code>-a</code> , <code>--all</code>	Display counts for all files, not just directories.
<code>-b</code> , <code>--bytes</code>	Print sizes in bytes.
<code>-c</code> , <code>--total</code>	Write a grand total of all of the arguments after all arguments have been processed. This can be used to find out the disk usage of a directory, with some files excluded.
<code>-k</code> , <code>--kilobytes</code>	Print sizes in kilobytes. This overrides the environment variable <code>POSIXLY_CORRECT</code> .
<code>-l</code> , <code>--count-links</code>	Count the size of all files, even if they have appeared already in another hard link.
<code>-s</code> , <code>--summarize</code>	Display only a total for each argument.
<code>-x</code> , <code>--one-file-system</code>	Skip directories that are on different filesystems from the one that the argument being processed is on.
<code>-D</code> , <code>--dereference-args</code>	Dereference symbolic links that are command-line arguments. Does not affect other symbolic links. This is helpful for finding out the disk usage of directories like <code>/usr/tmp</code> where they are symbolic links.
<code>-L</code> , <code>--dereference</code>	Dereference symbolic links (show the disk space used by the file or directory that the link points to instead of the space used by the link).
<code>-S</code> , <code>--separate-dirs</code>	Count the size of each directory separately, not including the sizes of subdirectories.
<code>--help</code>	Print a usage message on standard output and exit successfully.
<code>--version</code>	Print version information on standard output, then exit successfully.

BUGS

On BSD systems, `du` reports sizes that are half the correct values for files that are NFS-mounted from HP-UX systems. On HP-UX systems, it reports sizes that are twice the correct values for files that are NFS-mounted from BSD systems. This is due to a flaw in HP-UX; it also affects the HP-UX `du` program.

GNU File Utilities

editres

editres—A dynamic resource editor for X Toolkit applications

SYNTAX

```
editres [ -toolkitoption ... ]
```

OPTIONS

`editres` accepts all of the standard X Toolkit command-line options (see `x(1)`). The order of the command-line options is not important.

DESCRIPTION

`editres` is a tool that allows users and application developers to view the full widget hierarchy of any X Toolkit application that speaks the `editres` protocol. In addition, `editres` will help the user construct resource specifications, allow the user to apply the resource to the application and view the results dynamically. Once the user is happy with a resource specification, `editres` will append the resource string to the user's X Resources file.

USING editres

`editres` provides a window consisting of the following four areas:

Menu Bar	A set of pop-up menus that allow you full access to <code>editres</code> 's features.
Panner	The panner provides a more intuitive way to scroll the application tree display.
Message Area	Displays information to the user about the action that <code>editres</code> expects.
Application Widget Tree	This area is used to display the selected application's widget tree.

To begin an `editres` session, select the Get Widget Tree menu item from the Command menu. This will change the pointer cursor to crosshair. You should now select the application you wish look at by clicking on any of its windows. If this application understands the `editres` protocol, `editres` will display the application's widget tree in its tree window. If the application does not understand the `editres` protocol, `editres` will inform you of this fact in the message area after a few seconds delay.

After you have a widget tree, you may select any of the other menu options. The effect of each of these is described in "Commands," next.

COMMANDS

Get Widget Tree	Allows the user to click on any application that speaks the <code>editres</code> protocol and receive its widget tree.
Refresh Current Widget Tree	<code>editres</code> only knows about the widgets that exist at the present time. Many applications create and destroy widgets on the fly. Selecting this menu item will cause <code>editres</code> to ask the application to resend its widget tree, thus updating its information to the new state of the application. For example, <code>xman</code> only creates the widgets for its topbox when it starts up. None of the widgets for the manual page window are created until the user actually clicks on the Manual Page button. If you retrieved <code>xman</code>'s widget tree before the manual page is active, you may wish to refresh the widget tree after the manual page has been displayed. This will allow you to also edit the manual page's resources.

Dump Widget Tree to a File	When documenting applications it is often useful to be able to dump the entire application widget tree to an ASCII file. This file can then be included in the manual page. When this menu item is selected, a pop-up dialog is activated. Type the name of the file in this dialog, and either select Okay, or type a carriage-return. <code>editres</code> will dump the widget tree to this file. To cancel the file dialog, select the Cancel button.
Show Resource Box	This command will pop up a resource box for the current application. This resource box (described in detail later in this section) will allow the user to see exactly which resources can be set for the widget that is currently selected in the widget tree display. Only one widget may be currently selected; if greater or fewer are selected, <code>editres</code> will refuse to pop up the resource box and put an error message in the Message Area.
Set Resource	This command will pop up a simple dialog box for setting an arbitrary resource on all selected widgets. You must type in the resource name, as well as the value. You can use the Tab key to switch between the resource name field and the resource value field.
Quit	Exits <code>editres</code> .

TREE COMMANDS

The Tree menu contains several commands that enable operations to be performed on the widget tree.

Select Widget in Client	This menu item allows you to select any widget in the application; <code>editres</code> will then highlight the corresponding element the widget tree display. After this menu item is selected, the pointer cursor will again turn to a crosshair, and you must click any pointer button in the widget you wish to have displayed. Since some widgets are fully obscured by their children, it is not possible to get to every widget this way, but this mechanism does give very useful feedback between the elements in the widget tree and those in the actual application.
Select All, Unselect All, Invert All	These functions allow the user to select, unselect, or invert all widgets in the widget tree.
Select Children, Select Parents	These functions select the immediate parent or children of each of the currently selected widgets.
Select Descendants, Select Ancestors	These functions select all parents or children of each of the currently selected widgets. This is a recursive search.
Show Widget Names, Show Class Names, Show Widget Windows	When the tree widget is initially displayed, the labels of each widget in the tree correspond to the widget names. These functions will cause the label of all widgets in the tree to be changed to show the class name, IDs, or window associated with each widget in the application. The widget IDs, and windows are shown as hex numbers. In addition, there are keyboard accelerators for each of the Tree operations. If the input focus is over an individual widget in the tree, then that operation will only affect that widget. If the input focus is in the Tree background, it will have exactly the same effect as the corresponding menu item. The translation entries shown may be applied to any widget in the application. If that widget is a child of the Tree widget, then it will only affect that widget; otherwise, it will have the same effect as the commands in the Tree menu.
Flash Active Widgets	This command is the inverse of the Select Widget in Client command; it will show the user each widget that is currently selected in the widget tree by flashing the corresponding widget in the application <code>numFlashes</code> (three by default) times in the <code>flash-Color</code> .

Key	Option	Translation Entry
space	Unselect	Select(nothing)
w	Select	Select(widget)
s	Select	Select(all)
i	Invert	Select(invert)

Key	Option	Translation Entry
c	Select	Children Select(children)
d	Select Descendants	Select(descendants)
p	Select Parent	Select(parent)
a	Select Ancestors	Select(ancestors)
N	Show Widget Names	Relabel(name)
C	Show Class Names	Relabel(class)
I	Show Widget IDs	Relabel(id)
W	Show Widget Windows	Relabel(window)
T	Toggle Widget/Class Name	Relabel(toggle)

Clicking button 1 on a widget adds it to the set of selected widgets. Clicking button 2 on a widget deselects all other widgets and then selects just that widget. Clicking button 3 on a widget toggles its label between the widget's instance name the widget's class name.

USING THE RESOURCE BOX

The resource box contains five different areas. Each of the areas, as they appear on the screen from top to bottom, are discussed in the following list:

The Resource Line

This area at the top of the resource box shows the current resource name exactly as it would appear if you were to save it to a file or apply it.

The Widget Names and Classes

This area enables you to select exactly which widgets this resource will apply to. The area contains four lines; the first contains the name of the selected widget and all its ancestors, and the more restrictive dot (.) separator. The second line contains less specific class names of each widget, as well as the less restrictive star (*) separator. The third line contains a set of special buttons called Any Widget that will generalize this level to match any widget. The last line contains a set of special buttons called Any Widget Chain that will turn the single level into something that matches zero or more levels.

The initial state of this area is the most restrictive, using the resource names and the dot separator. By selecting the other buttons in this area, you can ease the restrictions to allow more and more widgets to match the specification. The extreme case is to select all the Any Widget Chain buttons, which will match every widget in the application. As you select different buttons, the tree display will update to show you exactly which widgets will be affected by the current resource specification.

Normal and Constraint Resources

The next area allows you to select the name of the normal or constraint resources you wish to set. Some widgets may not have constraint resources, so that area will not appear.

Resource Value

This next area allows you to enter the resource value. This value should be entered exactly as you would type a line into your resource file. Thus, it should contain no unescaped newlines. There are a few special character sequences for this file:

\n -	This will be replaced with a newline.
\### -	Where # is any octal digit. This will be replaced with a single byte that contains this sequence interpreted as an octal number. For example, a value containing a NULL byte can be stored by specifying \000.
\<new-line>-	This will compress to nothing.
\\ -	This will compress to a single backslash.

Command Area

This area contains several command buttons, described in the following list:

The Set Save File button allows the user to modify file that the resources will be saved to. This button will bring up a dialog box that will ask you for a filename; after the filename has been entered, either hit carriage-return or click on the Okay button. To pop down the dialog box without changing the save file, click the Cancel button.

The Save button will append the resource line already described to the end of the current save file. If no save file has been set, the Set Save File dialog box will be popped up to prompt the user for a filename.

The Apply button attempts to perform a `xtSetValues` call on all widgets that match the resource line described earlier. The value specified is applied directly to all matching widgets. This behavior is an attempt to give a dynamic feel to the resource editor. Since this feature allows users to put an application in states it may not be willing to handle, a hook has been provided to allow specific applications to block these `SetValues` requests. (See “Blocking editres Requests,” following).

Unfortunately, due to design constraints imposed on the widgets by the X Toolkit and the Resource Manager, trying to coerce an inherently static system into dynamic behavior can cause strange results. There is no guarantee that the results of an apply will be the same as what will happen when you save the value and restart the application. This functionality is provided to try to give you a rough feel for what your changes will accomplish, and the results obtained should be considered suspect at best. Having said that, this is one of the neatest features of `editres`, and I strongly suggest that you play with it, and see what it can do.

The Save and Apply button combines the Save and Apply actions described earlier into one button.

The Popdown Resource Box button will remove the resource box from the display.

BLOCKING editres REQUESTS

The `editres` protocol has been built into the Athena Widget set. This allows all applications that are linked against `xaw` to be able to speak to the resource editor. Although this provides great flexibility, and is a useful tool, it can quite easily be abused. It is therefore possible for any `xaw` application to specify a value for the `editresBlock` resource to keep `editres` from divulging information about its internals, or to disable the `SetValues` part of the protocol.

`editresBlock` (Class `EditresBlock`) specifies which type of blocking this application wishes to impose on the `editres` protocol.

The accepted values are as follows:

<code>all</code>	Block all requests.
<code>setValues</code>	Block all <code>SetValues</code> requests. As this is the only <code>editres</code> request that actually modifies the application, this is in effect stating that the application is read-only.
<code>none</code>	Allow all <code>editres</code> requests.

Remember that these resources are set on any `xaw` application, not `editres`. They allow individual applications to keep all or some of the requests `editres` makes from ever succeeding. Of course, `editres` is also an `xaw` application, so it may also be viewed and modified by `editres` (rather recursive, I know); these commands can be blocked by setting the `editresBlock` resource on `editres` itself.

RESOURCES

For `editres`, the available application resources are as follows:

`numFlashes` (Class `NumFlashes`) specifies the number of times the widgets in the application will be flashed when the Show Active Widgets command is invoked.

flashTime (Class FlashTime) specifies the mount of time between the flashes described in the preceding entry.

flashColor (Class flashColor) specifies the color used to flash application widgets. A bright color should be used that will immediately draw your attention to the area being flashed, such as red or yellow.

saveResourcesFile (Class SaveResourcesFile) is the file the resource line will be append to when the Save button activated in the resource box.

WIDGETS

In order to specify resources, it is useful to know the hierarchy of the widgets that compose editres. In the following notation, indentation indicates hierarchical structure. The widget class name is given first, followed by the widget instance name.

```

Editres editres
  Paned paned
    Box box
      MenuButton commands
        SimpleMenu menu
        SmeBSB sendTree
        SmeBSB refreshTree
        SmeBSB dumpTreeToFile
        SmeLine line SmeBSB getResourceList
        SmeLine line
        SmeBSB quit
      MenuButton treeCommands
        SimpleMenu menu
        SmeBSB showClientWidget
        SmeBSB selectAll
        SmeBSB unselectAll
        SmeBSB invertAll
        SmeLine line
        SmeBSB selectChildren
        SmeBSB selectParent
        SmeBSB selectDescendants
        SmeBSB selectAncestors
        SmeLine line
        SmeBSB showWidgetNames
        SmeBSB showClassNames
        SmeBSB showWidgetIDs
        SmeBSB showWidgetWindows
        SmeLine line
        SmeBSB flashActiveWidgets
    Paned hPane
      Panner panner
      Label userMessage
      Grip grip
    Porthole porthole
      Tree tree
        Toggle <name of widget in application>
        .
        .
        .
        TransientShell resourceBox
        Paned pane
        Label resourceLabel
        Form namesAndClasses
        Toggle dot
        Toggle star
        Toggle any
        Toggle name

```

```

Toggle class
.
.
.
Label namesLabel
List namesList
Label constraintLabel
List constraintList
Form valueForm
Label valueLabel
Text valueText
Box commandBox
Command setFile
Command save
Command apply
Command saveAndApply
Command cancel
Grip grip

Grip grip

```

ENVIRONMENT

DISPLAY To get the default host and display number

XENVIRONMENT To get the name of a resource file that overrides the global resources stored in the `RESOURCE_MANAGER` property.

FILES

`<XRoot>/lib/X11/app-defaults/Editres` specifies required resources.

SEE ALSO

`x(1)`, `xrdb(1)`, Athena Widget Set

RESTRICTIONS

This is a prototype. There are lots of nifty features I would love to add, but I hope this will give you some ideas about what a resource editor can do.

AUTHOR

Chris D. Peterson (formerly MIT X Consortium)
X Version 11 Release 6

elvis, ex, vi, view, input

`elvis`, `ex`, `vi`, `view`, `input`—The editor

SYNOPSIS

```
elvis [flags][+cmd][files...]
```

DESCRIPTION

`elvis` is a text editor that emulates `vi/ex`.

On systems which pass the program name as an argument, such as UNIX and Minix, you may also install `elvis` under the names `ex`, `vi`, `view`, and `input`. These extra names would normally be links to `elvis`; see the `ln` shell command.

When `elvis` is invoked as `vi`, it behaves exactly as though it was invoked as `elvis`. However, if you invoke `elvis` as `view`, then the `readonly` option is set as though you had given it the `-R` flag. If you invoke `elvis` as `ex`, then `elvis` will start up in the colon command mode instead of the `visual` command mode, as though you had given it the `-e` flag. If you invoke `elvis` as `input` or `edit`, then `elvis` will start up in input mode, as though the `-i` flag was given.

OPTIONS

<code>-r</code>	To the real <code>vi</code> , this flag means that a previous edit should be recovered. <code>elvis</code> , though, has a separate program, called <code>elvrec(1)</code> , for recovering files. When you invoke <code>elvis</code> with <code>-r</code> , <code>elvis</code> will tell you to run <code>elvrec</code> .
<code>-R</code>	This sets the <code>readonly</code> option, so you won't accidentally overwrite a file.
<code>-s</code>	This sets the <code>safer</code> option, which disables many potentially harmful commands. It has not been rigorously proven to be absolutely secure, however.
<code>-t tag</code>	This causes <code>elvis</code> to start editing at the given tag.
<code>-m [file]</code>	<code>elvis</code> will search through <code>file</code> for something that looks like an error message from a compiler. It will then begin editing the source file that caused the error, with the cursor sitting on the line where the error was detected. If you don't explicitly name a file, then <code>errlist</code> is assumed.
<code>-e</code>	<code>elvis</code> will start up in colon command mode.
<code>-v</code>	<code>elvis</code> will start up in visual command mode.
<code>-i</code>	<code>elvis</code> will start up in input mode.
<code>-w winsize</code>	Sets the <code>window</code> option's value to <code>winsize</code> .
<code>+command</code> or <code>-c command</code>	If you use the <code>+command</code> parameter, then after the first file is loaded, <code>command</code> is executed as an EX command. A typical example would be <code>elvis +237 foo</code> , which would cause <code>elvis</code> to start editing <code>foo</code> and then move directly to line 237. The <code>-c command</code> variant was added for UNIX SysV compatibility.

FILES

<code>/tmp/elv*</code>	During editing, <code>elvis</code> stores text in a temporary file. For UNIX, this file will usually be stored in the <code>/tmp</code> directory, and the first three characters will be <code>elv</code> . For other systems, the temporary files may be stored someplace else; see the version-specific section of the documentation.
<code>tags</code>	This is the database used by the <code>:tags</code> command and the <code>-t</code> option. It is usually created by the <code>ctags(1)</code> program.
<code>.exrc</code> or <code>elvis.rc</code>	On UNIX-like systems, a file called <code>.exrc</code> in your home directory is executed as a series of EX commands. A file by the same name may be executed in the current directory, too. On non-UNIX systems, <code>.exrc</code> is usually an invalid filename; there, the initialization file is called <code>elvis.rc</code> instead.

ENVIRONMENT

<code>TERM</code>	This is the name of your terminal's entry in the <code>termcap</code> or <code>terminfo</code> database. The list of legal values varies from one system to another.
<code>TERMCAP</code>	Optional. If your system uses <code>termcap</code> , and the <code>TERMCAP</code> variable is unset, then <code>elvis</code> will read your terminal's definition from <code>/etc/termcap</code> . If <code>TERMCAP</code> is set to the full pathname of a file (starting with a <code>/</code>) then <code>elvis</code> will look in the named file instead of <code>/etc/termcap</code> . If <code>TERMCAP</code> is set to a value which doesn't start with a <code>/</code> , then its value is assumed to be the full <code>termcap</code> entry for your terminal.
<code>TERMINFO</code>	Optional. If your system uses <code>terminfo</code> , and the <code>TERMINFO</code> variable is unset, then <code>elvis</code> will read your terminal's definition from the database in the <code>/usr/lib/terminfo</code> database. If <code>TERMINFO</code> is set, then its value is used as the database name to use instead of <code>/usr/lib/terminfo</code> .
<code>LINES, COLUMNS</code>	Optional. These variables, if set, will override the screen size values given in the <code>termcap/terminfo</code> for your terminal. On windowing systems such as X, <code>elvis</code> has other ways of determining the screen size, so you should probably leave these variables unset.
<code>EXINIT</code>	Optional. This variable can hold EX commands which will be executed instead of the <code>.exrc</code> file in your home directory.

SHELL	Optional. The <code>SHELL</code> variable sets the default value for the <code>shell</code> option, which determines which shell program is used to perform wildcard expansion in filenames, and also which is used to execute filters or external programs. The default value on UNIX systems is <code>/bin/sh</code> . Note: Under MS-DOS, this variable is called <code>COMSPEC</code> instead of <code>SHELL</code> .
HOME	This variable should be set to the name of your home directory. <code>elvis</code> looks for its initialization file there; if <code>HOME</code> is unset, then the initialization file will not be executed.
TAGPATH	Optional. This variable is used by the <code>ref</code> program, which is invoked by the <code>shift-K</code> , <code>control-J</code> , and <code>:tag</code> commands. See <code>ref</code> for more information.
TMP, TEMP	These optional environment variables are only used in non-UNIX versions of <code>elvis</code> . They allow you to supply a directory name to be used for storing temporary files.

SEE ALSO

`ctags(1)`, `ref(1)`, `elvprsv(1)`, `elvrec(1)`

Elvis—A Clone of Vi/Ex, the complete `elvis` documentation.

BUGS

There is no Lisp support. Certain other features are missing, too.

Auto-indent mode is not quite compatible with the real `vi`. Among other things, `o`d` and `^`d` don't do what you might expect.

Long lines are displayed differently. The real `vi` wraps long lines onto multiple rows of the screen, but `elvis` scrolls sideways.

AUTHOR

Steve Kirkendall (kirkenda@cs.pdx.edu)

Many other people have worked to port `elvis` to various operating systems. To see who deserves credit, run the `:version` command from within `elvis`, or look in the system-specific section of the complete documentation.

elvprsv

`elvprsv`—Preserve the modified version of a file after a crash

SYNOPSIS

```
elvprsv ["-why elvis died"] /tmp/filename...
elvprsv -R /tmp/filename...
```

DESCRIPTION

`elvprsv` preserves your edited text after `elvis` dies. The text can be recovered later, via the `elvprsv` program.

For UNIX-like systems, you should never need to run this program from the command line. It is run automatically when `elvis` is about to die, and it should be run (via `/etc/rc`) when the computer is booted. THAT'S ALL!

For non-UNIX systems such as MS-DOS or VMS, you can either use `elvprsv` the same way as under UNIX systems (by running it from your `AUTOEXEC.BAT` file), or you can run it separately with the `-R` flag to recover the files in one step.

If you're editing a file when `elvis` dies (due to a bug, system crash, power failure, and so on), then `elvprsv` will preserve the most recent version of your text. The preserved text is stored in a special directory; it does not overwrite your text file automatically. (If the preservation directory hasn't been set up correctly, then `elvprsv` will simply send you a mail message describing how to manually run `elvprsv`.)

`elvprsv` will send mail to any user whose work it preserves, if your operating system normally supports mail.

FILES

<code>/tmp/elv*</code>	The temporary file that <code>elvis</code> was using when it died.
<code>/usr/preserve/p*</code>	The text that is preserved by <code>elvprsv</code> .
<code>/usr/preserve/Index</code>	A text file which lists the names of all preserved files, and the names of the <code>/usr/preserve/p*</code> files that contain their preserved text.

BUGS

Due to the permissions on the `/usr/preserve` directory, on UNIX systems `elvprsv` must be run as superuser. This is accomplished by making the `elvprsv` executable be owned by `root` and turning on its “set user id” bit.

If you're editing a nameless buffer when `elvis` dies, then `elvprsv` will pretend that the file was named `foo`.

AUTHOR

Steve Kirkendall (kirkenda@cs.pdx.edu)

elvrec

`elvrec`—Recover the modified version of a file after a crash

SYNOPSIS

```
elvrec [preservedfile [newfile]]
```

DESCRIPTION

If you're editing a file when `elvis` dies, the system crashes, or power fails, the most recent version of your text will be preserved. The preserved text is stored in a special directory; it does not overwrite your text file automatically.

The `elvrec` program locates the preserved version of a given file, and writes it over the top of your text file—or to a new file, if you prefer. The recovered file will have nearly all of your changes.

To see a list of all recoverable files, run `elvrec` with no arguments.

NOTE

If you haven't set up a directory for file preservation, you'll have to manually run the `elvprsv` program instead of `elvrec`.

FILES

<code>/usr/preserve/p*</code>	The text that was preserved when <code>elvis</code> died.
<code>/usr/preserve/Index</code>	A text file that lists the names of all preserved files, and the names of the <code>/usr/preserve/p*</code> files that contain their preserved text.

BUGS

`elvrec` is very picky about filenames. You must tell it to recover the file using exactly the same pathname as when you were editing it. The simplest way to do this is to go into the same directory that you were editing, and invoke `elvrec` with the same filename as `elvis`. If that doesn't work, then try running `elvrec` with no arguments, to see exactly which pathname it is using for the desired file.

Due to the permissions on the `/usr/preserve` directory, on UNIX systems `elvrec` must be run as superuser. This is accomplished by making the `elvrec` executable be owned by `root` and setting its “set user id” bit.

If you're editing a nameless buffer when `elvis` dies, then `elvrec` will pretend that the file was named `foo`.

AUTHOR

Steve Kirkendall (kirkenda@cs.pdx.edu)

emacs

emacs—GNU project emacs

SYNOPSIS

emacs [command-line switches] [files ...]

DESCRIPTION

GNU emacs is a version of emacs, written by the author of the original (PDP-10) emacs, Richard Stallman.

The primary documentation of GNU emacs is in the *GNU Emacs Manual*, which you can read online using `info`, a subsystem of emacs. Please look there for complete and up-to-date documentation. This man page is updated only when someone volunteers to do so; the emacs maintainers' priority goal is to minimize the amount of time this man page takes away from other more useful projects.

The user functionality of GNU emacs encompasses everything other emacs editors do, and it is easily extensible since its editing commands are written in Lisp.

emacs has an extensive interactive help facility, but the facility assumes that you know how to manipulate emacs windows and buffers. `Ctrl+h` (backspace or `Ctrl+h`) enters the Help facility. Help Tutorial (`Ctrl+h t`) requests an interactive tutorial that can teach beginners the fundamentals of emacs in a few minutes. Help Apropos (`Ctrl+h a`) helps you find a command given its functionality, Help Character (`Ctrl+h c`) describes a given character's effect, and Help Function (`Ctrl+h f`) describes a given Lisp function specified by name.

emacs's Undo can undo several steps of modification to your buffers, so it is easy to recover from editing mistakes.

GNU emacs's many special packages handle mail reading (`RMail`) and sending (`Mail`), outline editing (`Outline`), compiling (`Compile`), running subshells within emacs windows (`Shell`), running a Lisp read-eval-print loop (`Lisp-Interaction-Mode`), and automated psychotherapy (`Doctor`).

There is an extensive reference manual, but users of other emacses should have little trouble adapting even without a copy. Users new to emacs will be able to use basic features fairly rapidly by studying the tutorial and using the self-documentation features.

OPTIONS

The following options are of general interest:

<code>file</code>	Edit <code>file</code> .
<code>+number</code>	Go to the line specified by <code>number</code> (do not insert a space between the <code>+</code> sign and the number).
<code>-q</code>	Do not load an init file.
<code>-u user</code>	Load user's init file.
<code>-t file</code>	Use specified file as the terminal instead of using <code>stdin/stdout</code> . This must be the first argument specified in the command line.

The following options are Lisp-oriented (these options are processed in the order encountered):

<code>-f function</code>	Execute the Lisp function <code>function</code> .
<code>-l file</code>	Load the Lisp code in the file <code>file</code> .

The following options are useful when running emacs as a batch editor:

<code>-batch</code>	Edit in batch mode. The editor will send messages to <code>stdout</code> . This option must be the first in the argument list. You must use <code>-l</code> and <code>-f</code> options to specify files to execute and functions to call.
<code>-kill</code>	Exit emacs while in batch mode.

USING emacs WITH X

emacs has been tailored to work well with the X Window System. If you run emacs from under X windows, it will create its own X window to display in. You will probably want to start the editor as a background process so that you can continue using your original window.

emacs can be started with the following X switches:

<code>-rn name</code>	Specifies the program name which should be used when looking up defaults in the user's X resources. This must be the first option specified in the command line.
<code>-name name</code>	Specifies the name that should be assigned to the emacs window.
<code>-r</code>	Display the emacs window in reverse video.
<code>-i</code>	Use the "kitchen sink" bitmap icon when iconifying the emacs window.
<code>-font font, -fn font</code>	Set the emacs window's font to that specified by <code>font</code> . You will find the various X fonts in the <code>/usr/lib/X11/fonts</code> directory. Note that emacs will only accept fixed width fonts. Under the X11 Release 4 font-naming conventions, any font with the value <code>m</code> or <code>c</code> in the eleventh field of the font name is a fixed width font. Furthermore, fonts whose name are of the form <code>width×height</code> are generally fixed width, as is the font fixed. See <code>x1sfonts(1)</code> for more information. When you specify a font, be sure to put a space between the switch and the font name.
<code>-b pixels</code>	Set the emacs window's border width to the number of pixels specified by <code>pixels</code> . Defaults to one pixel on each side of the window.
<code>-ib pixels</code>	Set the window's internal border width to the number of pixels specified by <code>pixels</code> . Defaults to one pixel of padding on each side of the window.
<code>-geometry geometry</code>	Set the emacs window's width, height, and position as specified. The geometry specification is in the standard uformat; see <code>x(1)</code> for more information. The width and height are specified in characters; the default is 80 by 24.
<code>-fg color</code>	On color displays, sets the color of the text. See the file <code>/usr/lib/X11/rgb.txt</code> for a list of valid color names.
<code>-bg color</code>	On color displays, sets the color of the window's background.
<code>-bd color</code>	On color displays, sets the color of the window's border.
<code>-cr color</code>	On color displays, sets the color of the window's text cursor.
<code>-ms color</code>	On color displays, sets the color of the window's mouse cursor.
<code>-d displayname, -display displayname</code>	Create the emacs window on the display specified by <code>displayname</code> . Must be the first option specified in the command line.
<code>-nw</code>	Tells emacs not to use its special interface to x. If you use this switch when invoking emacs from an <code>xterm(1)</code> window, display is done in that window. This must be the first option specified in the command line.

You can set X default values for your emacs windows in your `Xresources` file; see `xrdb(1)`. Use the following format:

emacs.keyword:value

where `value` specifies the default value of `keyword`. emacs lets you set default values for the following keywords:

<code>font</code> (Class Font)	Sets the window's text font.
<code>reverseVideo</code> (Class ReverseVideo)	If <code>reverseVideo</code> 's value is set to on, the window will be displayed in reverse video.
<code>bitmapIcon</code> (Class BitmapIcon)	If <code>bitmapIcon</code> 's value is set to on, the window will iconify into the "kitchen sink."
<code>borderWidth</code> (Class BorderWidth)	Sets the window's border width in pixels.
<code>internalBorder</code> (Class BorderWidth)	Sets the window's internal border width in pixels.
<code>foreground</code> (Class Foreground)	For color displays, sets the window's text color.
<code>background</code> (Class Background)	For color displays, sets the window's background color.
<code>borderColor</code> (Class BorderColor)	For color displays, sets the color of the window's border.

<code>cursorColor</code> (class <code>Foreground</code>)	For color displays, sets the color of the window's text cursor.
<code>pointerColor</code> (class <code>Foreground</code>)	For color displays, sets the color of the window's mouse cursor.
<code>geometry</code> (class <code>Geometry</code>)	Sets the geometry of the <code>emacs</code> window.
<code>title</code> (class <code>Title</code>)	Sets the title of the <code>emacs</code> window.
<code>iconName</code> (class <code>Title</code>)	Sets the icon name for the <code>emacs</code> window icon.

If you try to set color values while using a black-and-white display, the window's characteristics will default as follows: The foreground color will be set to black, the background color will be set to white, the border color will be set to gray, and the text and mouse cursors will be set to black.

USING THE MOUSE

The following lists the mouse button bindings for the `emacs` window under X11.

<i>Mouse Button</i>	<i>Function</i>
left	Set point.
middle	Paste text.
right	Cut text into X cut buffer.
Shift+middle	Cut text into X cut buffer.
Shift+right	Paste text.
Ctrl+middle	Cut text into X cut buffer and kill it.
Ctrl+right	Select this window, then split it into two windows. Same as typing Ctrl+x 2.
Ctrl+Shift+left	X buffer menu; hold the buttons and keys down, wait for menu to appear, select buffer, and release. Move mouse out of menu and release to cancel.
Ctrl+Shift+middle	X help menu; pop up index card menu for <code>emacs</code> help.
Ctrl+Shift+right	Select window with mouse, and delete all other windows. Same as typing Ctrl+x 1.

MANUALS

You can order printed copies of the *GNU Emacs Manual* from the Free Software Foundation, which develops GNU software. See the file `ORDERS` for ordering information.

Your local `emacs` maintainer might also have copies available. As with all software and publications from FSF, everyone is permitted to make and distribute copies of the `emacs` manual. The TeX source to the manual is also included in the `emacs` source distribution.

FILES

<code>/usr/local/info</code>	Files for the <code>info</code> documentation browser (a subsystem of <code>emacs</code>) to refer to. Currently not much of UNIX is documented here, but the complete text of the <code>emacs</code> reference manual is included in a convenient tree structured form.
<code>/usr/local/lib/emacs/\$VERSION/src</code>	C source files and object files.
<code>/usr/local/lib/emacs/\$VERSION/lisp</code>	Lisp source files and compiled files that define most editing commands. Some are preloaded; others are autoloaded from this directory when used.
<code>/usr/local/lib/emacs/\$VERSION/etc</code>	Various programs that are used with GNU <code>emacs</code> , and some files of information.
<code>/usr/local/lib/emacs/\$VERSION/etc/DOC.*</code>	Contains the documentation strings for the Lisp primitives and preloaded Lisp functions of GNU <code>emacs</code> . They are stored here to reduce the size of <code>emacs</code> proper.

<code>/usr/local/lib/emacs/\$VERSION/etc/DIFF</code>	Discusses GNU emacs versus Twenex emacs.
<code>/usr/local/lib/emacs/\$VERSION/etc/CCADIFF</code>	Discusses GNU emacs versus CCA emacs.
<code>/usr/local/lib/emacs/\$VERSION/etc/GOSDIFF</code>	Discusses GNU emacs versus Gosling emacs.
<code>/usr/local/lib/emacs/\$VERSION/etc/SERVICE</code>	Lists people offering various services to assist users of GNU emacs, including education, troubleshooting, porting, and customization. These files also have information useful to anyone wanting to write programs in the emacs Lisp extension language, which has not yet been fully documented.
<code>/usr/local/lib/emacs/lock</code>	Holds lock files that are made for all files being modified in emacs, to prevent simultaneous modification of one file by two users.
<code>/usr/local/lib/emacs/\$VERSION/\$ARCHITECTURE/cpp</code>	The GNU <code>cpp</code> , needed for building emacs on certain versions of UNIX where the standard <code>cpp</code> cannot handle long names for macros.
<code>/usr/lib/X11/rgb.txt</code>	List of valid x color names.

BUGS

There is a mailing list, `bug-gnu-emacs@prep.ai.mit.edu` on the Internet (`ucbvax!prep.ai.mit.edu!bug-gnu-emacs` on UUCPnet), for reporting emacs bugs and fixes. But before reporting something as a bug, please try to be sure that it really is a bug, not a misunderstanding or a deliberate feature. We ask you to read the section “Reporting emacs Bugs” near the end of the reference manual (or info system) for hints on how and when to report bugs. Also, include the version number of the emacs you are running in every bug report that you send in.

Do not expect a personal answer to a bug report. The purpose of reporting bugs is to get them fixed for everyone in the next release, if possible. For personal assistance, look in the `SERVICE` file for a list of people who offer it.

Please do not send anything but bug reports to this mailing list. Send requests to be added to mailing lists to the special list `info-gnu-emacs-request@prep.ai.mit.edu` (or the corresponding UUCP address). For more information about emacs mailing lists, see the file `/usr/local/emacs/etc/MAILINGLISTS`. Bugs tend actually to be fixed if they can be isolated, so it is in your interest to report them in such a way that they can be easily reproduced.

One bug that I know about: Shell will not work with programs running in Raw mode on some UNIX versions.

UNRESTRICTIONS

emacs is free; anyone may redistribute copies of emacs to anyone under the terms stated in the emacs General Public License, a copy of which accompanies each copy of emacs and which also appears in the reference manual.

Copies of emacs may sometimes be received packaged with distributions of UNIX systems, but it is never included in the scope of any license covering those systems. Such inclusion violates the terms on which distribution is permitted. In fact, the primary purpose of the General Public License is to prohibit anyone from attaching any other restrictions to redistribution of emacs.

Richard Stallman encourages you to improve and extend emacs, and urges that you contribute your extensions to the GNU library. Eventually GNU (GNU’s Not UNIX) will be a complete replacement for Berkeley UNIX. Everyone will be free to use, copy, study, and change the GNU system.

SEE ALSO

`x(1)`, `xlsfonts(1)`, `xterm(1)`, `xrdb(1)`

AUTHORS

emacs was written by Richard Stallman and the Free Software Foundation. Joachim Martillo and Robert Krawitz added the X features.

19 April 1994

emacstool

emacstool—Run emacs under Sun windows with function key and mouse support.

SYNOPSIS

```
emacstool [{window_args} {-rc run_command_path} args ... ]
```

TYPICAL USAGE

In `~/suntools` or `~/rootmenu`, include a line like this:

```
"Emacstool" emacstool -WI emacs.icon -f emacstool-init
```

DESCRIPTION

emacstool creates a SunView frame and a tty subwindow within which mouse events and function keys are translated to ASCII sequences that emacs can parse. The translated input events are sent to the process running in the tty subwindow, which is typically GNU emacs. emacstool thereby allows GNU emacs users to make full use of the mouse and function keys. GNU emacs can be loaded with functions to interpret the mouse and function-key events to make a truly fine screen-oriented editor for the Sun Workstation.

NOTE

GNU emacs has a special interface to the X Window System as well. The X Window System has many technical advantages, it is an industry standard, and it is also free software. The Free Software Foundation urges you to try X Windows, and distributes a free copy of X on emacs distribution tapes.

Function keys are translated to a sequence of the form `^X*[a-o][lrt]`. The last character is l, r, or t, corresponding to whether the key is among the Left, Right, or Top function keys. The third character indicates which button of the group was pressed. Thus, the function key in the lower-right corner will transmit the sequence `^X*or`. In addition, the `[lrt]` is affected by the Control, Meta, and Shift keys. Unshifted Ctrl keys will be nonalphabetic: C-l is `[,]`, C-r is `[2]`, C-t is `[4]`.

Mouse buttons are encoded as `^X^@([124] x y)\n`. `^X^@` is the standard GNU emacs mouse event prefix; it is followed by a list indicating the button pressed and the character row and column of the point in the window where the mouse cursor is, and followed by a newline character. In GNU emacs, the `^X^@` dispatches to a mouse event handler which then reads the following list.

OPTIONS

emacstool supports all the standard window arguments, including font and icon specifiers.

By default, emacstool runs the program emacs in the created subwindow. The value of the environment variable EMACSTOOL can be used to override this if your version of emacs is not accessible on your search path by the name emacs. In addition, the run command can be set by the pathname following the last occurrence of the `-rc` flag. This is convenient for using emacstool to run on remote machines.

All other command-line arguments not used by the window system are passed as arguments to the program that runs in the emacstool window.

For example,

```
local% (emacstool -rc rlogin remote -8 &)&
```

will create an emacstool window logged in to a machine named remote. If emacs is run from this window, emacstool will encode mouse and function keys, and send them to rlogin. If emacs is run from this shell on the remote machine, it will see the mouse and function keys properly. However, since the remote host does not have access to the screen, the cursor cannot be changed, menus will not appear, and the selection buffer (STUFF) is limited.

USING WITH GNU emacs

The GNU emacs files `lisp/term/sun.el`, `lisp/sun-mouse.el`, `lisp/sun-fns.el`, and `src/sunfns.c` provide emacs support for the `emacscool` and function keys. `emacscool` will automatically set the `TERM` environment variable to be `sun` and unset the environment variable `TERMCAP`. That is, these variables will not be inherited from the shell that starts `emacscool`. Since the terminal type is `SUN` (that is, the environment variable `TERM` is set to `SUN`), emacs will automatically load the file `lisp/term/sun`. This, in turn, will ensure that `sun-mouse.el` is autoloaded when any mouse events are detected. It is suggested that `sun-mouse` and `sun-fns` be loaded in your `site-init.el` file, so that they will always be loaded when running on a Sun workstation.

In addition, `emacscool` sets the environment variable `IN_EMACSTOOL` = `"t"`. Lisp code in your `~/.emacs` can use `(getenv "IN_EMACSTOOL")` to determine whether to do `emacscool`-specific initialization. `Sun.el` uses this to automatically call `emacscool-init` if `(getenv "IN_EMACSTOOL")` is defined.

The file `src/sunfns.c` defines several useful functions for emacs on the Sun. Among these are procedures to pop up SunView menus, `put` and `get` from the SunView `STUFF` buffer, and a procedure for changing the cursor icon. If you want to define or edit cursor icons, there is a rudimentary mouse-driven icon editor in the file `lisp/sun-cursors.el`. Try invoking `(sc:edit-cursor)`.

BUGS

It takes a few milliseconds to create a menu before it pops up.

ENVIRONMENT VARIABLES

`EMACSTOOL`, `IN_EMACSTOOL`, `TERM`, `TERMCAP`

FILES

`emacs`

SEE ALSO

`emacs(1)`, `.../etc/SUN-SUPPORT`, `.../lisp/term/sun.el`

etags

`etags`—Generate tag file for emacs

`ctags`—Generate tag file for vi

SYNOPSIS

```
etags [ -aCDSVH ] [ -i file ] [ -o tagfile ]
[ --c++ ] [ --no-defines ] [ --ignore-indentation ] [ --help ] [ --version ]
[ --include=file ] [ --output=tagfile ] [ --append ] file ...

ctags [ -aCdSVH ] [ -BtUvwX ] [ -o tagfile ]
[ --c++ ] [ --defines ] [ --ignore-indentation ]
[ --backward-search ] [ --forward-search ] [ --typedefs ] [ --typedefs-and-c++ ]
[ --no-warn ] [ --cxref ] [ --help ] [ --version ]
[ --output=tagfile ] [ --append ] [ --update ] file ...
```

DESCRIPTION

The `etags` program is used to create a tag table file, in a format understood by `emacs(1)`; the `ctags` program is used to create a similar table in a format understood by `vi(1)`. Both forms of the program understand the syntax of C, FORTRAN, Pascal, LaTeX, Scheme, emacs Lisp/Common Lisp, and most assembler-like syntaxes. Both forms read the files specified on the command line, and write a tag table (defaults: `TAGS` for `etags`, `tags` for `ctags`) in the current working directory. The programs recognize the language used in an input file based on its filename and contents; there are no switches for specifying the language.

OPTIONS

Some options make sense only for the vi-style tag files produced by `ctags`; `etags` does not recognize them. The programs accept unambiguous abbreviations for long option names.

<code>-a, --append</code>	Append to existing tag file. (For vi-format tag files, see also <code>--update</code> .)
<code>-B, --backward-search</code>	Tag files written in the format expected by vi contain regular expression search instructions; the <code>-B</code> option writes them using the delimiter <code>?</code> , to search backwards through files. The default is to use the delimiter <code>/</code> to search forwards through files. Only <code>ctags</code> accepts this option.
<code>-C, --c++</code>	Treat files with <code>.c</code> and <code>.h</code> extensions as C++ code, not C code. Files with <code>.C</code> , <code>.H</code> , <code>.cxx</code> , <code>.hxx</code> , or <code>.cc</code> extensions are always assumed to be C++ code.
<code>-d, --defines</code>	Create tag entries for C preprocessor definitions, too. This is the default behavior for <code>etags</code> , so this option is only accepted by <code>ctags</code> .
<code>-D, --no-defines</code>	Do not create tag entries for C preprocessor definitions. This may make the tags file much smaller if many header files are tagged. This is the default behavior for <code>ctags</code> , so this option is only accepted by <code>etags</code> .
<code>-i file, --include=file</code>	Include a note in tag file indicating that, when searching for a tag, one should also consult the tags file <code>file</code> after checking the current file. Only <code>etags</code> accepts this option.
<code>-o tagfile, --output=tagfile</code>	Explicit name of file for tag table; overrides default <code>TAGS</code> or <code>tags</code> . (But ignored with <code>-v</code> or <code>-x</code> .)
<code>-S, --ignore-indentation</code>	Don't rely on indentation as much as we normally do. Currently, this means not to assume that a closing brace in the first column is the final brace of a function or structure definition in C and C++.
<code>-t, --typedefs</code>	Record typedefs in C code as tags. Since this is the default behavior of <code>etags</code> , only <code>ctags</code> accepts this option.
<code>-T, --typedefs-and-c++</code>	Generate tag entries for typedefs, struct, enum, and union tags, and C++ member functions. Since this is the default behavior of <code>etags</code> , only <code>ctags</code> accepts this option.
<code>-u, --update</code>	Update tag entries for files specified on command line, leaving tag entries for other files in place. Currently, this is implemented by deleting the existing entries for the given files and then rewriting the new entries at the end of the tags file. It is often faster to simply rebuild the entire tag file than to use this. Only <code>ctags</code> accepts this option.
<code>-v, --vgrind</code>	Instead of generating a tag file, write index (in <code>vgrind</code> format) to standard output. Only <code>ctags</code> accepts this option.
<code>-w, --no-warn</code>	Suppress warning messages about duplicate entries. The <code>etags</code> program does not check for duplicate entries, so this option is not allowed with it.
<code>-x, --cxref</code>	Instead of generating a tag file, write a cross-reference (in <code>cxref</code> format) to standard output. Only <code>ctags</code> accepts this option.
<code>-H, --help</code>	Print usage information.
<code>-V, --version</code>	Print the current version of the program (same as the version of the emacs <code>etags</code> is shipped with).

SEE ALSO

emacs entry in `info`; *GNU Emacs Manual*, Richard Stallman.

`cxref(1)`, `emacs(1)`, `vgrind(1)`, `vi(1)`.

COPYING

Copyright © 1992 Free Software Foundation, Inc. Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

GNU Tools, 19 April 1994

expand

expand—Convert tabs to spaces

SYNOPSIS

```
expand [-tab1[,tab2[,...]] [-t tab1[,tab2[,...]] [-i] [--tabs=tab1[,tab2[,...]]
[--initial] [--help] [--version] [file...]
```

DESCRIPTION

This manual page documents the GNU version of `expand`. `expand` writes the contents of each given file, or the standard input if none are given or when a file named `-` is given, to the standard output, with tab characters converted to the appropriate number of spaces. By default, `expand` converts all tabs to spaces. It preserves backspace characters in the output; they decrement the column count for tab calculations. The default action is equivalent to `-8` (set tabs every 8 columns).

OPTIONS

<code>-, -t, --tabs tab1[,tab2[,...]]</code>	If only one tab stop is given, set the tabs <code>tab1</code> spaces apart instead of the default 8. Otherwise, set the tabs at columns <code>tab1</code> , <code>tab2</code> , and so forth (numbered from 0) and replace any tabs beyond the tab stops given with single spaces. If the tab-stops are specified with the <code>-t</code> or <code>--tabs</code> option, they can be separated by blanks as well as by commas.
<code>-i, --initial</code>	Only convert initial tabs (those that precede all nonspace or tab characters) on each line to spaces.
<code>--help</code>	Print a usage message and exit with a nonzero status.
<code>--version</code>	Print version information on standard output then exit.

GNU Text Utilities

find

find—Search for files in a directory hierarchy

SYNOPSIS

```
find [path...] [expression]
```

DESCRIPTION

This manual page documents the GNU version of `find`. `find` searches the directory tree rooted at each given filename by evaluating the given expression from left to right, according to the rules of precedence (see “Operators,” later in this manual page), until the outcome is known (the left side is `False` for `AND` operations, `True` for `OR`), at which point `find` moves on to the next filename.

The first argument that begins with `-, (, ), ,,` or `!` is taken to be the beginning of the expression; any arguments before it are paths to search, and any arguments after it are the rest of the expression. If no paths are given, the current directory is used. If no expression is given, the expression `-print` is used.

`find` exits with status `0` if all files are processed successfully, greater than `0` if errors occur.

EXPRESSIONS

The expression is made up of options (which affect overall operation rather than the processing of a specific file, and always return `True`), tests (which return a `True` or `False` value), and actions (which have side effects and return a `True` or `False` value), all separated by operators. `-and` is assumed where the operator is omitted. If the expression contains no actions other than `-prune`, `-print` is performed on all files for which the expression is true.

OPTIONS

All options always return `True`. They always take effect, rather than being processed only when their place in the expression is reached. Therefore, for clarity, it is best to place them at the beginning of the expression.

<code>-daystart</code>	Measure times (for <code>-amin</code> , <code>-atime</code> , <code>-cmin</code> , <code>-ctime</code> , <code>-mmin</code> , and <code>-mtime</code>) from the beginning of today rather than from 24 hours ago.
<code>-depth</code>	Process each directory's contents before the directory itself.
<code>-follow</code>	Dereference symbolic links. Implies <code>-noleaf</code> .
<code>-help</code> , <code>--help</code>	Print a summary of the command-line usage of <code>find</code> and <code>exit</code> .
<code>-maxdepth levels</code>	Descend at most <code>levels</code> (a nonnegative integer) levels of directories below the command-line arguments. <code>-maxdepth 0</code> means only apply the tests and actions to the command-line arguments.
<code>-mindepth levels</code>	Do not apply any tests or actions at levels less than <code>levels</code> (a nonnegative integer). <code>-mindepth 1</code> means process all files except the command-line arguments.
<code>-mount</code>	Don't descend directories on other filesystems. An alternate name for <code>-xdev</code> , for compatibility with some other versions of <code>find</code> .
<code>-noleaf</code>	Do not optimize by assuming that directories contain two fewer subdirectories than their hard link count. This option is needed when searching filesystems that do not follow the UNIX directory-link convention, such as CD-ROM or MS-DOS filesystems or AFS volume mount points. Each directory on a normal UNIX filesystem has at least 2 hard links: its name and its <code>.</code> entry. Additionally, its subdirectories (if any) each have a <code>..</code> entry linked to that directory. When <code>find</code> is examining a directory, after it has statted two fewer subdirectories than the directory's link count, it knows that the rest of the entries in the directory are nondirectories (leaf files in the directory tree). If only the files' names need to be examined, there is no need to stat them; this gives a significant increase in search speed.
<code>-version</code> , <code>--version</code>	Print the <code>find</code> version number and exit.
<code>-xdev</code>	Don't descend directories on other filesystems.

TESTS

Numeric arguments can be specified as

<code>+n</code>	Greater than <code>n</code> .
<code>-n</code>	Less than <code>n</code> .
<code>n</code>	Exactly <code>n</code> .
<code>-amin n</code>	File was last accessed <code>n</code> minutes ago.
<code>-anewer file</code>	File was last accessed more recently than <code>file</code> was modified. <code>-anewer</code> is affected by <code>-follow</code> only if <code>-follow</code> comes before <code>-anewer</code> on the command line.
<code>-atime n</code>	File was last accessed <code>n*24</code> hours ago.
<code>-cmin n</code>	File's status was last changed <code>n</code> minutes ago.
<code>-cnewer file</code>	File's status was last changed more recently than <code>file</code> was modified. <code>-cnewer</code> is affected by <code>-follow</code> only if <code>-follow</code> comes before <code>-cnewer</code> on the command line.
<code>-ctime n</code>	File's status was last changed <code>n*24</code> hours ago.
<code>-empty</code>	File is empty and is either a regular file or a directory.
<code>-false</code>	Always false.

<code>-fstype type</code>	File is on a filesystem of type <i>type</i> . The valid filesystem types vary among different versions of UNIX; an incomplete list of filesystem types that are accepted on some version of UNIX or another is: <code>ufs</code> , <code>4.2</code> , <code>4.3</code> , <code>nfs</code> , <code>tmp</code> , <code>mfs</code> , <code>S51K</code> , <code>S52K</code> . You can use <code>-printf</code> with the <code>%F</code> directive to see the types of your filesystems.
<code>-gid n</code>	File's numeric group ID is <i>n</i> .
<code>-group gname</code>	File belongs to group <i>gname</i> (numeric group ID allowed).
<code>-ilname pattern</code>	Like <code>-lname</code> , but the match is case-insensitive.
<code>-iname pattern</code>	Like <code>-name</code> , but the match is case-insensitive. For example, the patterns <code>fo*</code> and <code>F??</code> match the filenames <code>Foo</code> , <code>F00</code> , <code>foo</code> , <code>f0o</code> , and so on.
<code>-inum n</code>	File has inode number <i>n</i> .
<code>-ipath pattern</code>	Like <code>-path</code> , but the match is case-insensitive.
<code>-iregex pattern</code>	Like <code>-regex</code> , but the match is case-insensitive.
<code>-links n</code>	File has <i>n</i> links.
<code>-lname pattern</code>	File is a symbolic link whose contents match shell pattern <i>pattern</i> . The meta characters do not treat <code>/</code> or <code>.</code> specially.
<code>-mmin n</code>	File's data was last modified <i>n</i> minutes ago.
<code>-mtime n</code>	File's data was last modified <i>n</i> *24 hours ago.
<code>-name pattern</code>	Base of filename (the path with the leading directories removed) matches shell pattern <i>pattern</i> . The meta characters (<code>*</code> , <code>?</code> , and <code>[]</code>) do not match a <code>.</code> at the start of the base name. To ignore a directory and the files under it, use <code>-prune</code> ; see an example in the description of <code>-path</code> .
<code>-newer file</code>	File was modified more recently than <i>file</i> . <code>-newer</code> is affected by <code>-follow</code> only if <code>-follow</code> comes before <code>-newer</code> on the command line.
<code>-nouser</code>	No user corresponds to file's numeric user ID.
<code>-nogroup</code>	No group corresponds to file's numeric group ID.
<code>-path pattern</code>	Filename matches shell pattern <i>pattern</i> . The meta characters do not treat <code>/</code> or <code>.</code> specially; so, for example, <pre>find . -path './src*sc'</pre> will print an entry for a directory called <code>./src/misc</code> (if one exists). To ignore a whole directory tree, use <code>-prune</code> rather than checking every file in the tree. For example, to skip the directory <code>src/emacs</code> and all files and directories under it, and print the names of the other files found, do something like this: <pre>find . -path './src/emacs' -prune -o -print</pre>
<code>-perm mode</code>	File's permission bits are exactly <i>mode</i> (octal or symbolic). Symbolic modes use <code>mode 0</code> as a point of departure.
<code>-perm -mode</code>	All of the permission bits <i>mode</i> are set for the file.
<code>-perm +mode</code>	Any of the permission bits <i>mode</i> are set for the file.
<code>-regex pattern</code>	Filename matches regular expression <i>pattern</i> . This is a match on the whole path, not a search. For example, to match a file named <code>./fubar3</code> , you can use the regular expression <code>.*bar3</code> . or <code>.*b.*3</code> , but not <code>b.*r3</code> .
<code>-size n[bckw]</code>	File uses <i>n</i> units of space. The units are 512-byte blocks by default or if <i>b</i> follows <i>n</i> , bytes if <i>c</i> follows <i>n</i> , kilobytes if <i>k</i> follows <i>n</i> , or 2-byte words if <i>w</i> follows <i>n</i> . The size does not count indirect blocks, but it does count blocks in sparse files that are not actually allocated.
<code>-true</code>	Always true.
<code>-type c</code>	File is of type <i>c</i> . Possible types: <code>b</code> Block (buffered) special <code>c</code> Character (unbuffered) special <code>d</code> Directory <code>p</code> Named pipe (FIFO)

- f Regular file l symbolic link
- s Socket

-uid n File's numeric user ID is n.

-used n File was last accessed n days after its status was last changed.

-user uname File is owned by user uname (numeric user ID allowed).

-xtype c The same as -type unless the file is a symbolic link. For symbolic links: if -follow has not been given, True if the file is a link to a file of type c; if -follow has been given, True if c is l. In other words, for symbolic links, -xtype checks the type of the file that -type does not check.

ACTIONS

-exec command; Execute command; True if 0 status is returned. All following arguments to find are taken to be arguments to the command until an argument consisting of ; is encountered. The string {} is replaced by the current filename being processed everywhere it occurs in the arguments to the command, not just in arguments where it is alone, as in some versions of find. Both of these constructions might need to be escaped (with a \) nor quoted to protect them from expansion by the shell. The command is executed in the starting directory.

-fls file True; like -ls but write to file like -fprint.

-fprint file True; print the full filename into file file. If file does not exist when find is run, it is created; if it does exist, it is truncated. The filenames /dev/stdout and /dev/stderr are handled specially; they refer to the standard output and standard error output, respectively.

-fprint0 file True; like -print0 but write to file like -fprint.

-fprintf file format True; like -printf but write to file like -fprint.

-ok command; Like -exec but ask the user first (on the standard input); if the response does not start with y or Y, do not run the command, and return False.

-print True; print the full filename on the standard output, followed by a newline.

-print0 True; print the full filename on the standard output, followed by a null character. This allows filenames that contain newlines to be correctly interpreted by programs that process the find output.

-printf format True; print format on the standard output, interpreting n escapes and % directives. Field widths and precisions can be specified as with the printf C function. Unlike -print, -printf does not add a newline at the end of the string. The escapes and directives are as follows:

- \a Alarm bell
- \b Backspace
- \c Stop printing from this format immediately and flush the output
- \f Form feed
- \n Newline
- \r Carriage return
- \t Horizontal tab
- \v Vertical tab
- \\ A literal backslash ('\')

A \ character followed by any other character is treated as an ordinary character, so they both are printed:

- %% A literal percent sign.
- %a File's last access time in the format returned by the C ctime function.
- %Ak File's last access time in the format specified by k, which is either @ or a directive for the C strftime function. The possible values for k are listed below; some of them might not be available on all systems, due to differences in strftime between systems.
- @ seconds since Jan. 1, 1970, 00:00 GMT.

Time fields:

H	Hour (00..23)
I	Hour (01..12)
k	Hour (0..23)
l	Hour (1..12)
M	Minute (00..59)
p	Locale's a.m. or p.m.
r	Time, 12-hour (hh:mm:ss [AP]M)
u	Second (00..61)
T	Time, 24-hour (hh:mm:ss)
X	Locale's time representation (H:M:S)
Z	Time zone (for example, EDT), or nothing if no time zone is determinable

Date fields:

a	Locale's abbreviated weekday name (Sun..Sat)
A	Locale's full weekday name, variable length (Sunday..Saturday)
b	Locale's abbreviated month name (Jan..Dec)
B	Locale's full month name, variable length (January.. December)
c	Locale's date and time (Sat Nov 04 12:02:33 EST 1989)
d	Day of month (01..31)
D	Date (mm/dd/yy)
h	Same as b
j	Day of year (001..366)
m	Month (01..12)
U	Week number of year with Sunday as first day of week (00..53)
w	Day of week (0..6)
W	Week number of year with Monday as first day of week (00..53)
x	Locale's date representation (mm/dd/yy)
y	Last two digits of year (00..99)
Y	Year (1970..)

- %b File's size in 512-byte blocks (rounded up).
- %c File's last status change time in the format returned by the C `ctime` function.
- %Ck File's last status change time in the format specified by k, which is the same as for %A.
- %d File's depth in the directory tree; 0 means the file is a command-line argument.
- %f File's name with any leading directories removed (only the last element).
- %F Type of the filesystem the file is on; this value can be used for `-fstype`.
- %g File's group name, or numeric group ID if the group has no name.
- %G File's numeric group ID.
- %h Leading directories of file's name (all but the last element).
- %H Command-line argument under which file was found.
- %i File's inode number (in decimal).
- %k File's size in 1K blocks (rounded up).
- %l Object of symbolic link (empty string if file is not a symbolic link).

<code>%m</code>	File's permission bits (in octal).
<code>%n</code>	Number of hard links to file.
<code>%p</code>	File's name.
<code>%P</code>	File's name with the name of the command-line argument under which it was found removed.
<code>%s</code>	File's size in bytes.
<code>%t</code>	File's last modification time in the format returned by the C <code>ctime</code> function.
<code>%Tk</code>	File's last modification time in the format specified by <code>k</code> , which is the same as for <code>%A</code> .
<code>%u</code>	File's username, or numeric user ID if the user has no name.
<code>%U</code>	File's numeric user ID.
	A <code>%</code> character followed by any other character is discarded (but the other character is printed).
<code>-prune</code>	If <code>-depth</code> is not given, <code>True</code> ; do not descend the current directory. If <code>-depth</code> is given, <code>False</code> ; no effect.
<code>-ls</code>	<code>True</code> ; list current file in <code>ls -dils</code> format on standard output. The block counts are of 1K blocks, unless the environment variable <code>POSIXLY_CORRECT</code> is set, in which case 512- byte blocks are used.

OPERATORS

Listed in order of decreasing precedence:

<code>(expr)</code>	Force precedence.
<code>! expr</code>	<code>True</code> if <code>expr</code> is false.
<code>-not expr</code>	Same as <code>! expr</code> .
<code>expr1 expr2</code>	And (implied); <code>expr2</code> is not evaluated if <code>expr1</code> is false.
<code>expr1 -a expr2</code>	Same as <code>expr1 expr2</code> .
<code>expr1 -and expr2</code>	Same as <code>expr1 expr2</code> .
<code>expr1 -o expr2</code>	Or; <code>expr2</code> is not evaluated if <code>expr1</code> is true.
<code>expr1 -or expr2</code>	Same as <code>expr1 -o expr2</code> .
<code>expr1, expr2</code>	List; both <code>expr1</code> and <code>expr2</code> are always evaluated. The value of <code>expr1</code> is discarded; the value of the list is the value of <code>expr2</code> .

SEE ALSO

`locate(1L)`, `locatedb(5L)`, `updatedb(1L)`, `xargs(1L)` Finding Files (online in `info`, or printed)

GNU File Utilities

fitstopnm

`fitstopnm`—Convert a FITS file into a portable anymap

SYNOPSIS

```
fitstopnm [-image N][-noraw][-scanmax][-printmax][-min f][-max f][FITSfile]
```

DESCRIPTION

Reads a FITS file as input. Produces a portable pixmap if the FITS file consists of 3 image planes (`NAXIS = 3` and `NAXIS3 = 3`), a portable graymap if the FITS file consists of 2 image planes (`NAXIS = 2`), or whenever the `-image` flag is specified. The results may need to be flipped top for bottom; if so, just pipe the output through `pnmflip -tb`.

OPTIONS

The `-image` option is for FITS files with three axes. The assumption is that the third axis is for multiple images, and this option lets you select which one you want.

Flags `-min` and `-max` can be used to override the min and max values as read from the FITS header or the image data if no `DATAMIN` and `DATAMAX` keywords are found. Flag `-scanmax` can be used to force the program to scan the data even when `DATAMIN` and `DATAMAX` are found in the header. If `-printmax` is specified, the program will just print the min and max values and quit. Flag `-noraw` can be used to force the program to produce an ASCII portable anymap.

The program will tell what kind of anymap is writing. All flags can be abbreviated to their shortest unique prefix.

REFERENCES

FITS stands for Flexible Image Transport System. A full description can be found in *Astronomy & Astrophysics Supplement Series 44* (1981), page 363.

SEE ALSO

`pnmtofits(1)`, `pgm(5)`, `pnmf1ip(1)`

AUTHOR

Copyright © 1989 by Jef Poskanzer, with modifications by Daniel Briggs (dbriggs@nrao.edu) and Alberto Accomazzi (alberto@cfa.harvard.edu)

20 September 1989

fmt

`fmt`—Adjust line-length for paragraphs of text

SYNOPSIS

`fmt [-width] [files]...`

DESCRIPTION

`fmt` is a simple text formatter. It inserts or deletes newlines, as necessary, to make all lines in a paragraph be approximately the same width. It preserves indentation and word spacing.

The default line width is 72 characters. You can override this with the `-width` flag. If you don't name any files on the command line, then `fmt` will read from `stdin`.

It is typically used from within `vi` to adjust the line breaks in a single paragraph. To do this, move the cursor to the top of the paragraph, type `!gfmt`, and press Return.

AUTHOR

Steve Kirkendall (kirkenda@cs.pdx.edu)

fold

`fold`—Wrap each input line to fit in specified width

SYNOPSIS

`fold [-bs] [-w width] [-bytes] [-spaces] [--width=width] [--help]
[-version] [file...]`

DESCRIPTION

This manual page documents the GNU version of `fold`. `fold` prints the specified files, or the standard input when no files are given or the filename `-` is encountered, on the standard output. It breaks long lines into multiple shorter lines by inserting a newline at column 80. It counts screen columns, so tab characters usually take more than one column, backspace characters decrease the column count, and carriage return characters set the column count back to zero.

OPTIONS

- `-b, --bytes` Count bytes rather than columns, so that tabs, backspaces, and carriage returns are each counted as taking up one column, just like other characters.
- `-s, --spaces` Break at word boundaries. If the line contains any blanks, the line is broken after the last blank that falls within the maximum line length. If there are no blanks, the line is broken at the maximum line length, as usual.
- `-w, --width width` Use a maximum line length of `width` columns instead of 80.
- `--help` Print a usage message and exit with a nonzero status.
- `--version` Print version information on standard output then exit.

GNU Text Utilities

free

`free`—Display amount of free and used memory in the system

SYNOPSIS

```
free [-b | -k | -m] [-o] [-s delay] [-t]
```

DESCRIPTION

`free` displays the total amount of free and used physical and swap memory in the system, as well as the shared memory and buffers used by the kernel.

OPTIONS

The `-b` switch displays the amount of memory in bytes; the `-k` switch (set by default) displays it in kilobytes; the `-m` switch displays it in megabytes.

The `-t` switch displays a line containing the totals.

The `-o` switch disables the display of a “buffer adjusted” line. Unless specified `free` subtracts/adds buffer memory from/to the used/free memory reports (respectively!).

The `-s` switch activates continuous polling delay seconds apart. You may actually specify any floating point number for delay, `usleep(3)` is used for microsecond resolution delay times.

FILES

`/proc/meminfo` Memory information

SEE ALSO

`ps(1)`, `top(1)`

AUTHORS

Brian Edmonds

Cohesive Systems, 20 March 1993

fsinfo

fsinfo—X font server information utility

SYNOPSIS

```
fsinfo [-server servername]
```

DESCRIPTION

fsinfo is a utility for displaying information about an X font server. It is used to examine the capabilities of a server, the predefined values for various parameters used in communicating between clients and the server, and the font catalogues and alternate servers that are available.

EXAMPLE

The following is a sample produced by fsinfo.

```
name of server: hansen:7100
version number: 1
vendor string: Font Server Prototype
vendor release number: 17
maximum request size: 16384 longwords (65536 bytes)
number of catalogues: 1
all
Number of alternate servers: 2
#0 hansen:7101
#1 hansen:7102
number of extensions: 0
```

ENVIRONMENT

FONTSERVER To get the default fontserver

SEE ALSO

xfs(1), fslsfonts(1)

AUTHOR

Dave Lemke (Network Computing Devices, Inc.)

X Version 11 Release 6

fslsfonts

fslsfonts—List fonts served by X font server

SYNOPSIS

```
fslsfonts [-options ...] [-fn pattern]
```

DESCRIPTION

fslsfonts lists the fonts that match the given pattern. The wildcard character * may be used to match any sequence of characters (including none), and ? to match any single character. If no pattern is given, * is assumed.

The * and ? characters must be quoted to prevent them from being expanded by the shell.

OPTIONS

```
-server host:port              This option specifies the X font server to contact.
-l                              Lists some attributes of the font on one line in addition to its name.
```

<code>-ll</code>	Lists font properties in addition to <code>-l</code> output.
<code>-lll</code>	Supported for compatibility with <code>xlsfonts</code> , but output is the same as for <code>-ll</code> .
<code>-m</code>	This option indicates that long listings should also print the minimum and maximum bounds of each font.
<code>-C</code>	This option indicates that listings should use multiple columns. This is the same as <code>-n 0</code> .
<code>-1</code>	This option indicates that listings should use a single column. This is the same as <code>-n 1</code> .
<code>-w width</code>	This option specifies the width in characters that should be used in figuring out how many columns to print. The default is 79.
<code>-n columns</code>	This option specifies the number of columns to use in displaying the output. The default is 0, which will attempt to fit as many columns of font names into the number of character specified by <code>-w width</code> .
<code>-u</code>	This option indicates that the output should be left unsorted.

SEE ALSO

`xfs(1)`, `showfont(1)`, `xlsfonts(1)`

ENVIRONMENT

`FONTSERVER` To get the default host and port to use

BUGS

Doing `fs1sfonts -l` can tie up your server for a very long time. This is really a bug with single-threaded nonpreemptable servers, not with this program.

AUTHOR

Dave Lemke (Network Computing Devices, Inc.)

X Version 11 Release 6 1

fstobdf

`fstobdf`—Generate BDF font from X font server

SYNOPSIS

```
fstobdf [ -server server ] -fn fontname
```

DESCRIPTION

The `fstobdf` program reads a font from a font server and prints a BDF file on the standard output that may be used to recreate the font. This is useful in testing servers, debugging font metrics, and reproducing lost BDF files.

OPTIONS

<code>-server servername</code>	This option specifies the server from which the font should be read.
<code>-fn fontname</code>	This option specifies the font for which a BDF file should be generated.

ENVIRONMENT

`FONTSERVER` Default server to use

SEE ALSO

`xfs(1)`, `bdftopcf(1)`, `fs1sfonts(1)`

AUTHOR

Olaf Brandt (Network Computing Devices), Dave Lemke (Network Computing Devices), Jim Fulton (MIT X Consortium)
X Version 11 Release 6

fstopgm

fstopgm—Convert a Usenix FaceSaver file into a portable graymap

SYNOPSIS

```
fstopgm [fsfile]
```

DESCRIPTION

Reads a Usenix FaceSaver file as input. Produces a portable graymap as output.

FaceSaver files sometimes have rectangular pixels. Although fstopgm won't rescale them into square pixels for you, it will give you the precise pnmscale command that will do the job. Because of this, reading a FaceSaver image is a two-step process.

First you do

```
fstopgm > /dev/null
```

This will tell you whether you need to use pnmscale. Then use one of the following pipelines:

```
fstopgm | pgmnorm
fstopgm | pnmscale -whatever | pgmnorm
```

To go to PBM, you want something more like one of these:

```
fstopgm | pnmenlarge 3 | pgmnorm | pgmtopbm
fstopgm | pnmenlarge 3 | pnmscale <whatever> | pgmnorm | pgmtopbm
```

You want to enlarge when going to a bitmap because otherwise you lose information; but enlarging by more than 3 does not look good.

FaceSaver is a registered trademark of Metron Computerware Ltd. of Oakland, CA.

SEE ALSO

pgmtops(1), pgm(5), pgmnorm(1), pnmenlarge(1), pnmscale(1), pgmtopbm(1)

AUTHOR

Copyright © 1989 by Jef Poskanzer
6 April 1989

ftp

ftp—ARPAnet file transfer program

SYNOPSIS

```
ftp [-v] [-d] [-i] [-n] [-g] [host]
```

DESCRIPTION

ftp is the user interface to the ARPAnet standard File Transfer Protocol. The program allows a user to transfer files to and from a remote network site.

Options may be specified at the command line, or to the command interpreter.

<code>-v</code>	Verbose option forces <code>ftp</code> to show all responses from the remote server, as well as report on data transfer statistics.
<code>-n</code>	Restrains <code>ftp</code> from attempting auto-login upon initial connection. If auto-login is enabled, <code>ftp</code> will check the (see below) file in the user's home directory for an entry describing an account on the remote machine. If no entry exists, <code>ftp</code> will prompt for the remote machine login name (default is the user identity on the local machine), and, if necessary, prompt for a password and an account with which to login.
<code>-i</code>	Turns off interactive prompting during multiple file transfers.
<code>-d</code>	Enables debugging.
<code>-g</code>	Disables filename globbing.

The client host with which `ftp` is to communicate may be specified on the command line. If this is done, `ftp` will immediately attempt to establish a connection to an FTP server on that host; otherwise, `ftp` will enter its command interpreter and await instructions from the user. When `ftp` is awaiting commands from the user, the prompt

`ftp>`

is provided to the user. The following commands are recognized by `ftp` :

<code>! [command] [args]</code>	Invoke an interactive shell on the local machine. If there are arguments, the first is taken to be a command to execute directly, with the rest of the arguments as its arguments.
<code>\$ macro-name [args]</code>	Execute the macro <code>macro-name</code> that was defined with the <code>macdef</code> command. Arguments are passed to the macro unglobbed.
<code>account [passwd]</code>	Supply a supplemental password required by a remote system for access to resources once a login has been successfully completed. If no argument is included, the user will be prompted for an account password in a nonechoing input mode.
<code>append local-file [remote-file]</code>	Append a local file to a file on the remote machine. If <code>remote-file</code> is left unspecified, the local filename is used in naming the remote file after being altered by any <code>ntrans</code> or <code>nmap</code> setting. File transfer uses the current settings for type, format, mode, and structure.
<code>ascii</code>	Set the file transfer type to network ASCII. This is the default type.
<code>bell</code>	Arrange that a bell be sounded after each file transfer command is completed.
<code>binary</code>	Set the file transfer type to support binary image transfer.
<code>bye</code>	Terminate the FTP session with the remote server and exit <code>ftp</code> . An end of file will also terminate the session and exit.
<code>case</code>	Toggle remote computer filename case mapping during <code>mget</code> commands. When <code>case</code> is on (default is off), remote computer filenames with all letters in upper case are written in the local directory with the letters mapped to lowercase.
<code>cd remote-directory</code>	Change the working directory on the remote machine to <code>remote-directory</code> .
<code>cdup</code>	Change the remote machine working directory to the parent of the current remote machine working directory.
<code>chmod mode file-name</code>	Change the permission modes of the file <code>file-name</code> on the remote system to <code>mode</code> .
<code>close</code>	Terminate the FTP session with the remote server, and return to the command interpreter. Any defined macros are erased.
<code>cr</code>	Toggle carriage return stripping during ASCII type file retrieval. Records are denoted by a carriage return/linefeed sequence during ASCII type file transfer. When <code>cr</code> is on (the default), carriage returns are stripped from this sequence to conform with the UNIX single linefeed record delimiter. Records on non-UNIX remote systems may contain single linefeeds; when an ASCII type transfer is made, these linefeeds may be distinguished from a record delimiter only when <code>cr</code> is off.
<code>delete remote-file</code>	Delete the file <code>remote-file</code> on the remote machine.

<code>debug [debug-value]</code>	Toggle debugging mode. If an optional <code>debug-value</code> is specified, it is used to set the debugging level. When debugging is on, <code>ftp</code> prints each command sent to the remote machine, preceded by the string <code>→</code> .
<code>dir [remote-directory] [local-file]</code>	Print a listing of the directory contents in the directory, <code>remote-directory</code> , and, optionally, placing the output in <code>local-file</code> . If interactive prompting is on, <code>ftp</code> will prompt the user to verify that the last argument is indeed the target local file for receiving <code>dir</code> output. If no directory is specified, the current working directory on the remote machine is used. If no local file is specified, or <code>local-file</code> is <code>-</code> , output comes to the terminal.
<code>disconnect</code>	A synonym for <code>close</code> .
<code>form format</code>	Set the file transfer form to <code>format</code> . The default <code>format</code> is <code>file</code> .
<code>get remote-file [local-file]</code>	Retrieve the <code>remote-file</code> and store it on the local machine. If the local filename is not specified, it is given the same name it has on the remote machine, subject to alteration by the current <code>case</code> , <code>ntrans</code> , and <code>nmap</code> settings. The current settings for type, form, mode, and structure are used while transferring the file.
<code>glob</code>	Toggle filename expansion for <code>mdelete</code> , <code>mget</code> , and <code>mput</code> . If globbing is turned off with <code>glob</code> , the filename arguments are taken literally and not expanded. Globbing for <code>mput</code> is done as in <code>csh</code> 1. For <code>mdelete</code> and <code>mget</code> , each remote filename is expanded separately on the remote machine and the lists are not merged. Expansion of a directory name is likely to be different from expansion of the name of an ordinary file: the exact result depends on the foreign operating system and FTP server, and can be previewed by doing <code>mls remote-files</code> . Note: <code>mget</code> and <code>mput</code> are not meant to transfer entire directory subtrees of files. That can be done by transferring a <code>tar</code> 1 archive of the subtree (in binary mode).
<code>hash</code>	Toggle hash-sign (#) printing for each data block transferred. The size of a data block is 1024 bytes.
<code>help [command]</code>	Print an informative message about the meaning of <code>command</code> . If no argument is given, <code>ftp</code> prints a list of the known commands.
<code>idle [seconds]</code>	Set the inactivity timer on the remote server to <code>seconds</code> seconds. If <code>seconds</code> is omitted, the current inactivity timer is printed.
<code>lcd [directory]</code>	Change the working directory on the local machine. If no directory is specified, the user's home directory is used.
<code>ls [remote-directory] [local-file]</code>	Print a listing of the contents of a directory on the remote machine. The listing includes any system-dependent information that the server chooses to include; for example, most systems will produce output from the command <code>ls</code> 1. (See also <code>nlist</code> .) If <code>remote-directory</code> is left unspecified, the current working directory is used. If interactive prompting is on, <code>ftp</code> will prompt the user to verify that the last argument is indeed the target local file for receiving <code>ls</code> output. If no local file is specified, or if <code>local-file</code> is <code>-</code> , the output is sent to the terminal.
<code>macdef macro-name</code>	Define a macro. Subsequent lines are stored as the macro <code>macro-name</code> ; a null line (consecutive newline characters in a file or carriage returns from the terminal) terminates macro input mode. There is a limit of 16 macros and 4096 total characters in all defined macros. Macros remain defined until a <code>close</code> command is executed. The macro processor interprets <code>\$</code> and <code>\</code> as special characters. A <code>\$</code> followed by a number (or numbers) is replaced by the corresponding argument on the macro invocation command line. A <code>\$</code> followed by an <code>i</code> signals that macro processor that the executing macro is to be looped. On the first pass <code>\$i</code> is replaced by the first argument on the macro invocation command line, on the second pass it is replaced by the second argument, and so on. A <code>\</code> followed by any character is replaced by that character. Use the <code>\to</code> to prevent special treatment of the <code>\$</code> .
<code>mdelete [remote-files]</code>	Delete the <code>remote-files</code> on the remote machine.

<code>mdir remote-files local-file</code>	Like <code>dir</code> , except multiple remote files may be specified. If interactive prompting is on, <code>ftp</code> will prompt the user to verify that the last argument is indeed the target local file for receiving <code>mdir</code> output.
<code>mget remote-files</code>	Expand the <code>remote-files</code> on the remote machine and do a <code>get</code> for each filename thus produced. See <code>glob</code> for details on the filename expansion. Resulting filenames will then be processed according to <code>case</code> , <code>ntrans</code> , and <code>nmap</code> settings. Files are transferred into the local working directory, which can be changed with <code>lcd</code> directory; new local directories can be created with <code>!mkdir</code> directory.
<code>mkdir directory-name</code>	Make a directory on the remote machine.
<code>mls remote-files local-file</code>	Like <code>nlist</code> , except multiple remote files may be specified, and the <code>local-file</code> must be specified. If interactive prompting is on, <code>ftp</code> will prompt the user to verify that the last argument is indeed the target local file for receiving <code>mls</code> output.
<code>mode [mode-name]</code>	Set the file transfer mode to <code>mode-name</code> . The default mode is stream mode.
<code>modtime file-name</code>	Show the last modification time of the file on the remote machine.
<code>mput local-files</code>	Expand wildcards in the list of local files given as arguments and do a <code>put</code> for each file in the resulting list. See <code>glob</code> for details of filename expansion. Resulting filenames will then be processed according to <code>ntrans</code> and <code>nmap</code> settings.
<code>newer file-name</code>	Get the file only if the modification time of the remote file is more recent than the file on the current system. If the file does not exist on the current system, the remote file is considered newer. Otherwise, this command is identical to <code>get</code> .
<code>nlist [remote-directory] [local-file]</code>	Print a list of the files in a directory on the remote machine. If <code>remote-directory</code> is left unspecified, the current working directory is used. If interactive prompting is on, <code>ftp</code> will prompt the user to verify that the last argument is indeed the target local file for receiving <code>nlist</code> output. If no local file is specified, or if <code>local-file</code> is <code>-</code> , the output is sent to the terminal.
<code>nmap [inpattern] outpattern</code>	Set or unset the filename mapping mechanism. If no arguments are specified, the filename mapping mechanism is unset. If arguments are specified, remote filenames are mapped during <code>mput</code> commands and <code>put</code> commands issued without a specified remote target filename. If arguments are specified, local filenames are mapped during <code>mget</code> commands and <code>get</code> commands issued without a specified local target filename. This command is useful when connecting to a non-UNIX remote computer with different file naming conventions or practices. The mapping follows the pattern set by <code>inpattern</code> and <code>outpattern</code> . <code>inpattern</code> is a template for incoming filenames (which may have already been processed according to the <code>ntrans</code> and <code>case</code> settings). Variable templating is accomplished by including the sequences <code>\$1</code> , <code>\$2</code> , ..., <code>\$9</code> in <code>inpattern</code> . Use <code>\</code> to prevent this special treatment of the <code>\$</code> character. All other characters are treated literally, and are used to determine the <code>nmap inpattern</code> variable values. For example, given <code>inpattern \$1.\$2</code> and the remote filename <code>mydata.data</code> , <code>\$1</code> would have the value <code>mydata</code> , and <code>\$2</code> would have the value <code>"data"</code> . The <code>outpattern</code> determines the resulting mapped filename. The sequences <code>\$1</code> , <code>\$2</code> , ..., <code>\$9</code> are replaced by any value resulting from the <code>inpattern</code> template. The sequence <code>\$0</code> is replaced by the original filename. Additionally, the sequence <code>seq1</code> , <code>seq2</code> is replaced by <code>seq1</code> if <code>seq1</code> is not a null string; otherwise, it is replaced by <code>seq2</code> . For example, the command <code>nmap \$1.\$2.\$3 [\$1,\$2].[\$2,file]</code> would yield the output filename <code>myfile.data</code> for input filenames <code>my-file</code> , <code>data</code> and <code>myfile.data.old</code> , <code>myfile.file</code> for the input filename <code>my-file</code> , and <code>myfile.myfile</code> for the input filename <code>.myfile</code> . Spaces may be included in <code>outpattern</code> , as in the example: <code>nmap \$1 sed "s/ *//" > \$1</code> . Use the <code>\</code> character to prevent special treatment of the <code>\$</code> , <code>[</code> , <code>]</code> , and <code>,</code> characters.
<code>ntrans [inchars] [outchars]</code>	Set or unset the filename character translation mechanism. If no arguments are specified, the filename character translation mechanism is unset. If arguments are specified, characters in remote filenames are translated during <code>mput</code> commands and

	put commands issued without a specified remote target filename. If arguments are specified, characters in local filenames are translated during <code>mget</code> commands and <code>get</code> commands issued without a specified local target filename. This command is useful when connecting to a non-UNIX remote computer with different file naming conventions or practices. Characters in a filename matching a character in <code>inchars</code> are replaced with the corresponding character in <code>outchars</code>. If the character's position in <code>inchars</code> is longer than the length of <code>outchars</code>, the character is deleted from the filename.
<code>open host [port]</code>	Establish a connection to the specified host FTP server. An optional port number may be supplied, in which case, <code>ftp</code> will attempt to contact an FTP server at that port. If the <code>auto-login</code> option is on (default), <code>ftp</code> will also attempt to automatically log the user in to the FTP server (see below).
<code>prompt</code>	Toggle interactive prompting. Interactive prompting occurs during multiple file transfers to allow the user to selectively retrieve or store files. If prompting is turned off (default is on), any <code>mget</code> or <code>mput</code> will transfer all files, and any <code>mdelete</code> will delete all files.
<code>proxy ftp-command</code>	Execute an <code>ftp</code> command on a secondary control connection. This command allows simultaneous connection to two remote FTP servers for transferring files between the two servers. The first proxy command should be an <code>open</code>, to establish the secondary control connection. Enter the command "proxy ?" to see other <code>ftp</code> commands executable on the secondary connection. The following commands behave differently when prefaced by <code>proxy</code> :, <code>open</code> will not define new macros during the auto-login process, <code>close</code> will not erase existing macro definitions, <code>get</code> and <code>mget</code> transfer files from the host on the primary control connection to the host on the secondary control connection, and <code>put</code>, <code>mput</code>, and <code>append</code> transfer files from the host on the secondary control connection to the host on the primary control connection. Third-party file transfers depend upon support of the FTP protocol <code>PASV</code> command by the server on the secondary control connection.
<code>put local-file [remote-file]</code>	Store a local file on the remote machine. If <code>remote-file</code> is left unspecified, the local filename is used after processing according to any <code>ntrans</code> or <code>nmap</code> settings in naming the remote file. File transfer uses the current settings for type, format, mode, and structure.
<code>pwd</code>	Print the name of the current working directory on the remote machine.
<code>quit</code>	A synonym for <code>bye</code>.
<code>quote arg1 arg2...</code>	The arguments specified are sent, verbatim, to the remote FTP server.
<code>recv remote-file [local-file]</code>	A synonym for <code>get</code>.
<code>reget remote-file [local-file]</code>	<code>Reget</code> acts like <code>get</code>, except that if <code>local-file</code> exists and is smaller than <code>remote-file</code>, <code>local-file</code> is presumed to be a partially transferred copy of <code>remote-file</code> and the transfer is continued from the apparent point of failure. This command is useful when transferring very large files over networks that are prone to dropping connections.
<code>remotehelp [command-name]</code>	Request help from the remote FTP server. If a <code>command-name</code> is specified, it is supplied to the server as well.
<code>remotestatus [file-name]</code>	With no arguments, show status of remote machine. If <code>file-name</code> is specified, show status of <code>file-name</code> on remote machine.
<code>rename [from] [to]</code>	Rename the file <code>from</code> on the remote machine, to the file <code>to</code>.
<code>reset</code>	Clear reply queue. This command resynchronizes command/reply sequencing with the remote FTP server. Resynchronization may be necessary following a violation of the FTP protocol by the remote server.
<code>restart marker</code>	Restart the immediately following <code>get</code> or <code>put</code> at the indicated marker. On UNIX systems, <code>marker</code> is usually a byte offset into the file.

<code>rmdir directory-name</code>	Delete a directory on the remote machine.
<code>runique</code>	Toggle storing of files on the local system with unique filenames. If a file already exists with a name equal to the target local filename for a <code>get</code> or <code>mget</code> command, a <code>.1</code> is appended to the name. If the resulting name matches another existing file, a <code>.2</code> is appended to the original name. If this process continues up to <code>.99</code> , an error message is printed, and the transfer does not take place. The generated unique filename will be reported. Note that <code>runique</code> will not affect local files generated from a shell command. The default value is <code>off</code> .
<code>send local-file [remote-file]</code>	A synonym for <code>put</code> .
<code>sendport</code>	Toggle the use of <code>PORT</code> commands. By default, <code>ftp</code> will attempt to use a <code>PORT</code> command when establishing a connection for each data transfer. The use of <code>PORT</code> commands can prevent delays when performing multiple file transfers. If the <code>PORT</code> command fails, <code>ftp</code> will use the default data port. When the use of <code>PORT</code> commands is disabled, no attempt will be made to use <code>PORT</code> commands for each data transfer. This is useful for certain FTP implementations which do ignore <code>PORT</code> commands but, incorrectly, indicate they've been accepted.
<code>site arg1 arg2...</code>	The arguments specified are sent, verbatim, to the remote FTP server as a <code>SITE</code> command.
<code>size file-name</code>	Return size of <code>file-name</code> on remote machine.
<code>status</code>	Show the current status of <code>ftp</code> .
<code>struct [struct-name]</code>	Set the file transfer structure to <code>struct-name</code> . By default stream structure is used.
<code>sunique</code>	Toggle storing of files on remote machine under unique filenames. Remote FTP server must support <code>ftp</code> protocol <code>STOU</code> command for successful completion. The remote server will report unique name. Default value is <code>off</code> .
<code>system</code>	Show the type of operating system running on the remote machine.
<code>tenex</code>	Set the file transfer type to that needed to talk to TENEX machines.
<code>trace</code>	Toggle packet tracing.
<code>type [type-name]</code>	Set the file transfer type to <code>type-name</code> . If no type is specified, the current type is printed. The default type is network <code>ASCII</code> .
<code>umask [newmask]</code>	Set the default <code>umask</code> on the remote server to <code>newmask</code> . If <code>newmask</code> is omitted, the current <code>umask</code> is printed.
<code>user user-name [password] [account]</code>	Identify yourself to the remote FTP server. If the password is not specified and the server requires it, <code>ftp</code> will prompt the user for it (after disabling local echo). If an account field is not specified, and the FTP server requires it, the user will be prompted for it. If an account field is specified, an account command will be relayed to the remote server after the login sequence is completed if the remote server did not require it for logging in. Unless <code>ftp</code> is invoked with auto-login disabled, this process is done automatically on initial connection to the FTP server.
<code>verbose</code>	Toggle verbose mode. In verbose mode, all responses from the FTP server are displayed to the user. In addition, if verbose is on, when a file transfer completes, statistics regarding the efficiency of the transfer are reported. By default, verbose is on.
<code>? [command]</code>	A synonym for help.

Command arguments which have embedded spaces may be quoted with quotation marks (").

ABORTING A FILE TRANSFER

To abort a file transfer, use the terminal interrupt key (usually `Ctrl-C`). Sending transfers will be immediately halted. Receiving transfers will be halted by sending an FTP protocol `ABOR` command to the remote server, and discarding any further data received. The speed at which this is accomplished depends upon the remote server's support for `ABOR` processing.

If the remote server does not support the `ABOR` command, an `ftp>` prompt will not appear until the remote server has completed sending the requested file.

The terminal interrupt key sequence will be ignored when `ftp` has completed any local processing and is awaiting a reply from the remote server. A long delay in this mode may result from the `ABOR` processing described earlier in this section, or from unexpected behavior by the remote server, including violations of the FTP protocol. If the delay results from unexpected remote server behavior, the local `ftp` program must be killed by hand.

FILE NAMING CONVENTIONS

Files specified as arguments to `ftp` commands are processed according to the following rules:

If the filename `-` is specified, the `stdin` (for reading) or `stdout` (for writing) is used.

If the first character of the filename is `j`, the remainder of the argument is interpreted as a shell command. `ftp` then forks a shell, using `popen 3` with the argument supplied, and reads (writes) from the `stdout` (`stdin`). If the shell command includes spaces, the argument must be quoted; for example, `ls -lt`. A particularly useful example of this mechanism is: `dir more`.

Failing the preceding checks, if “globbing” is enabled, local filenames are expanded according to the rules used in the `cs` shell; c.f. the `glob` command. If the `ftp` command expects a single local file (for example, `put`), only the first filename generated by the “globbing” operation is used.

For `mget` commands and `get` commands with unspecified local filenames, the local filename is the remote filename, which may be altered by a `case`, `ntrans`, or `nmap` setting. The resulting filename may then be altered if `runique` is on.

For `mput` commands and `put` commands with unspecified remote filenames, the remote filename is the local filename, which may be altered by an `ntrans` or `nmap` setting. The resulting filename may then be altered by the remote server if `sunique` is on.

FILE TRANSFER PARAMETERS

The FTP specification specifies many parameters that may affect a file transfer. The type may be one of ASCII, image (binary), ebcdic, and local byte size (for PDP Ns -10s and PDP Ns -20s mostly). `ftp` supports the ASCII and image types of file transfer, plus local byte size 8 for tenex mode transfers.

`ftp` supports only the default values for the remaining file transfer parameters: `mode`, `form`, and `struct`.

THE .netrc FILE

The file contains login and initialization information used by the auto-login process. It resides in the user's home directory. The following tokens are recognized; they may be separated by spaces, tabs, or newlines:

machine name	Identify a remote machine name. The auto-login process searches the file for a machine token that matches the remote machine specified on the <code>ftp</code> command line or as an open command argument. When a match is made, the subsequent tokens are processed, stopping when the end of file is reached or another machine or a default token is encountered.
default	This is the same as machine name except that <code>default</code> matches any name. There can be only one <code>default</code> token, and it must be after all machine tokens. This is normally used as <code>default login anonymous password user@site</code> , thereby giving the user automatic anonymous <code>ftp</code> login to machines not specified. This can be overridden by using the <code>-n</code> flag to disable auto-login.
login name	Identify a user on the remote machine. If this token is present, the auto-login process will initiate a login using the specified name.
password string	Supply a password. If this token is present, the auto-login process will supply the specified string if the remote server requires a password as part of the login process. Note that if this token is present in the file for any user other than anonymous, <code>ftp</code> will abort the auto-login process if the is readable by anyone besides the user.
account string	Supply an additional account password. If this token is present, the auto-login process will supply the specified string if the remote server requires an additional account password, or the auto-login process will initiate an <code>ACCT</code> command if it does not.

macdef name Define a macro. This token functions like the `ftp macdef` command functions. A macro is defined with the specified name; its contents begin with the next line and continue until a null line (consecutive newline characters) is encountered. If a macro named `init` is defined, it is automatically executed as the last step in the auto-login process.

ENVIRONMENT

`ftp` utilizes the following environment variables:

HOME For default location of a file, if one exists
SHELL For default shell

SEE ALSO

`ftpd(8)`

HISTORY

The `ftp` command appeared in BSD 4.2.

BUGS

Correct execution of many commands depends upon proper behavior by the remote server.

An error in the treatment of carriage returns in the BSD 4.2 ASCII-mode transfer code has been corrected. This correction may result in incorrect transfers of binary files to and from BSD 4.2 servers using the ASCII type. Avoid this problem by using the binary image type.

BSD 4.2, 30 July 1991

fuser

fuser—Identify processes using files

SYNOPSIS

```
fuser [-a|-s][-signal][-kmuv] filename ... [-][-signal][-kmuv] filename ...
fuser [-l]
```

DESCRIPTION

`fuser` displays the PIDs of processes using the specified files or file systems. In the default display mode, each filename is followed by a letter denoting the type of access:

c Current directory.
e Executable being run.
f Open file. `f` is omitted in default display mode.
r Root directory.
m mmap'ed file or shared library.

`fuser` returns a nonzero return code if none of the specified files is accessed or in case of a fatal error. If at least one access has been found, `fuser` returns zero.

OPTIONS

-a Show all files specified on the command line. By default, only files that are accessed by at least one process are shown.
-k Kill processes accessing the file. Unless changed with `-signal`, `SIGKILL` is sent. A `fuser` process never kills itself, but may kill other `fuser` processes.

u	List all known signal names.
-m	<code>filename</code> specifies a file on a mounted file system or a block device that is mounted. All processes accessing files on that file system are listed. If a directory file is specified, it is automatically changed to <code>filename/.</code> to use any file system that might be mounted on that directory.
-s	Silent operation. <code>-a</code> , <code>-u</code> , and <code>-v</code> are ignored in this mode.
-signal	Use the specified signal instead of <code>SIGKILL</code> when killing processes. Signals can be specified either by name (for example, <code>-HUP</code>) or by number (for example, <code>-1</code>).
-u	Append the username of the process owner to each PID.
-v	Verbose mode. Processes are shown in a <code>ps</code> -like style. The fields <code>PID</code> , <code>USER</code> , and <code>COMMAND</code> are similar to <code>ps</code> . <code>ACCESS</code> shows how the process accesses the file.
-	Reset all options and set the signal back to <code>SIGKILL</code> .

FILES

<code>/proc</code>	Location of the <code>proc</code> file system

EXAMPLES

`fuser -km /home` kills all processes accessing the file system `/home` in any way.

In this example:

```
if fuser -s /dev/ttyS1; then ;; else something
fi
```

invokes something if no other process is using `/dev/ttyS1`.

RESTRICTIONS

Processes accessing the same file or filesystem several times in the same way are only shown once.

AUTHOR

Werner Almesberger (<almesber@di.epfl.ch>)

SEE ALSO

`kill(1)`, `killall(1)`, `ps(1)`, `kill(2)`
Linux, 11 October 1994

g++

g++—GNU project C++ Compiler

SYNOPSIS

```
g++ [ option | filename ] . . .
```

DESCRIPTION

The C and C++ compilers are integrated; `g++` is a script to call `gcc` with options to recognize C++. `gcc` processes input files through one or more of four stages: preprocessing, compilation, assembly, and linking. This man page contains full descriptions for only C++ specific aspects of the compiler, though it also contains summaries of some general-purpose options. For a fuller explanation of the compiler, see `gcc(1)`.

C++ source files use one of the suffixes `.c`, `.cc`, `.cxx`, `.cpp`, or `.c++`; preprocessed C++ files use the suffix `.ii`.

OPTIONS

There are many command-line options, including options to control details of optimization, warnings, and code generation, which are common to both `gcc` and `g++`. For full information on all options, see `gcc(1)`.

Options must be separate: `-dr` is quite different from `-d -r`.

Most `-f` and `-W` options have two contrary forms: `-fname` and `-fno-name` (or `-Wname` and `-Wno-name`). Only the nondefault forms are shown here.

<code>-c</code>	Compile or assemble the source files, but do not link. The compiler output is an object file corresponding to each source file.
<code>-Dmacro</code>	Define macro <i>macro</i> with the string <i>1</i> as its definition.
<code>-Dmacro=defn</code>	Define macro <i>macro</i> as <i>defn</i> .
<code>-E</code>	Stop after the preprocessing stage; do not run the compiler proper. The output is preprocessed source code, which is sent to the standard output.
<code>-fall-virtual</code>	Treat all possible member functions as virtual, implicitly. All member functions (except for constructor functions and new or delete member operators) are treated as virtual functions of the class where they appear. This does not mean that all calls to these member functions will be made through the internal table of virtual functions. Under some circumstances, the compiler can determine that a call to a given virtual function can be made directly; in these cases the calls are direct in any case.
<code>-fdollars-in-identifiers</code>	Permit the use of <code>\$</code> in identifiers. Traditional C allowed the character <code>\$</code> to form part of identifiers; by default, GNU C also allows this. However, ANSI C forbids <code>\$</code> in identifiers, and GNU C++ also forbids it by default on most platforms (though on some platforms it's enabled by default for GNU C++ as well).
<code>-felide-constructors</code>	Use this option to instruct the compiler to be smarter about when it can elide constructors. Without this flag, GNU C++ and <code>cfront</code> both generate effectively the same code for <pre>A foo (); A x (foo ()); // x initialized by 'foo ()', no ctor called A y = foo (); // call to 'foo ()' heads to temporary, // y is initialized from the temporary.</pre> Note the difference. With this flag, GNU C++ initializes <code>y</code> directly from the call to <code>foo()</code> without going through a temporary.
<code>-fenum-int-equiv</code>	Normally GNU C++ allows conversion of <code>enum</code> to <code>int</code> , but not the other way around. Use this option if you want GNU C++ to allow conversion of <code>int</code> to <code>enum</code> as well.
<code>-fexternal-templates</code>	Produce smaller code for template declarations, by generating only a single copy of each template function where it is defined. To use this option successfully, you must also mark all files that use templates with either <code>#pragma implementation</code> (the definition) or <code>#pragma interface</code> (declarations). When your code is compiled with <code>-fexternal-templates</code> , all template instantiations are external. You must arrange for all necessary instantiations to appear in the implementation file; you can do this with a <code>typedef</code> that references each instantiation needed. Conversely, when you compile using the default option <code>-fno-external-templates</code> , all template instantiations are explicitly internal.
<code>-fno-gnu-linker</code>	Do not output global initializations (such as C++ constructors and destructors) in the form used by the GNU linker (on systems where the GNU linker is the standard method of handling them). Use this option when you want to use a non-GNU linker, which also requires using the <code>collect2</code> program to make sure the system linker includes constructors and destructors. (<code>collect2</code> is included in the GNU CC distribution.) For systems which must use <code>collect2</code> , the compiler driver <code>gcc</code> is configured to do this automatically.
<code>-fmemoize-lookups-fsave-memorized</code>	These flags are used to get the compiler to compile programs faster using heuristics. They are not on by default since they are only effective about half the time. The other half of the time programs compile more slowly (and take more memory).

The first time the compiler must build a call to a member function (or reference to a data member), it must (1) determine whether the class implements member functions of that name; (2) resolve which member function to call (which involves figuring out what sorts of type conversions need to be made); and (3) check the visibility of the member function to the caller. All of this adds up to slower compilation. Normally, the second time a call is made to that member function (or reference to that data member), it must go through the same lengthy process again. This means that code like this:

```
cout << "This " << p << "has"<< n << " legs.\n";
```

makes six passes through all three steps. By using a software cache, a “hit” significantly reduces this cost. Unfortunately, using the cache introduces another layer of mechanisms which must be implemented, and so incurs its own overhead. -fmemorize-lookups enables the software cache.

Because access privileges (visibility) to members and member functions may differ from one function context to the next, g++ may need to flush the cache. With the -fmemorize-lookups flag, the cache is flushed after every function that is compiled. The -fsave-memorized flag enables the same software cache, but when the compiler determines that the context of the last function compiled would yield the same access privileges of the next function to compile, it preserves the cache. This is most helpful when defining many member functions for the same class: with the exception of member functions which are friends of other classes, each member function has exactly the same access privileges as every other, and the cache need not be flushed.

-fno-default-inline

Do not make member functions inline by default merely because they are defined inside the class scope. Otherwise, when you specify -O, member functions defined inside class scope are compiled inline by default; that is, you don't need to add inline in front of the member function name.

-fno-strict-prototype

Consider the declaration `int foo();`. In C++, this means that the function `foo` takes no arguments. In ANSI C, this is declared `int foo(void);`. With the flag -fno-strict-prototype, declaring functions with no arguments is equivalent to declaring its argument list to be untyped, that is, `int foo();` is equivalent to saying `int foo(...);`. -fnonnull-objects. Normally, GNU C++ makes conservative assumptions about objects reached through references. For example, the compiler must check that `a` is not null in code like the following:

```
obj &a = g ();
a.f (2);
```

Checking that references of this sort have non-null values requires extra code, however, and it is unnecessary for many programs. You can use -fnonnull-objects to omit the checks for null, if your program doesn't require the default checking.

-fhandle-signatures-
fno-handle-signatures
-fthis-is-variable

These options control the recognition of the signature and `sigof` constructs for specifying abstract types. By default, these constructs are not recognized.

The incorporation of user-defined free store management into C++ has made assignment to this an anachronism. Therefore, by default GNU C++ treats the type of this in a member function of class `X` to be `X *const`. In other words, it is illegal to assign to this within a class member function. However, for backwards compatibility, you can invoke the old behavior by using -fthis-is-variable.

-g

Produce debugging information in the operating system's native format (for DBX or SDB or DWARF). GDB also can work with this debugging information. On most systems that use DBX format, -g enables use of extra debugging information that only GDB can use.

Unlike most other C compilers, GNU CC allows you to use -g with -O. The shortcuts taken by optimized code may occasionally produce surprising results: some

variables you declared may not exist at all; flow of control may briefly move where you did not expect it; some statements may not be executed because they compute constant results or their values were already at hand; some statements may execute in different places because they were moved out of loops.

Nevertheless, it proves possible to debug optimized output. This makes it reasonable to use the optimizer for programs that might have bugs.

`-I dir`

Append directory `dir` to the list of directories searched for include files.

`-L dir`

Add directory `dir` to the list of directories to be searched for `-l`.

`-l library`

Use the library named `library` when linking. (C++ programs often require `-lg++` for successful linking.)

`-nostdinc`

Do not search the standard system directories for header files. Only the directories you have specified with `-I` options (and the current directory, if appropriate) are searched.

`-nostdinc++`

Do not search for header files in the standard directories specific to C++, but do still search the other standard directories. (This option is used when building `libg++`.)

`-O`

Optimize. Optimizing compilation takes somewhat more time, and a lot more memory for a large function.

`-o file`

Place output in file `file`.

`-S`

Stop after the stage of compilation proper; do not assemble. The output is an assembler code file for each nonassembler input file specified.

`-traditional`

Attempt to support some aspects of traditional C compilers. Specifically, for both C and C++ programs:

In the preprocessor, comments convert to nothing at all, rather than to a space. This allows traditional token concatenation.

In the preprocessor, macro arguments are recognized within string constants in a macro definition (and their values are stringified, though without additional quote marks, when they appear in such a context). The preprocessor always considers a string constant to end at a newline.

The preprocessor does not predefine the macro `STDC` when you use `-traditional`, but still predefines `GNUC` (since the GNU extensions indicated by `GNUC` are not affected by `-traditional`). If you need to write header files that work differently depending on whether `-traditional` is in use, by testing both of these predefined macros you can distinguish four situations: GNU C, traditional GNU C, other ANSI C compilers, and other old C compilers.

In the preprocessor, comments convert to nothing at all, rather than to a space. This allows traditional token concatenation.

String “constants” are not necessarily constant; they are stored in writable space, and identical looking constants are allocated separately. For C++ programs only (not C), `-traditional` has one additional effect: assignment to this is permitted. This is the same as the effect of `-fthis-is-variable`.

`-Umacro`

Undefine macro `macro`.

`-Wall`

Issue warnings for conditions that pertain to usage that we recommend avoiding and that we believe is easy to avoid, even in conjunction with macros.

`-Wenum-clash`

Warn when converting between different enumeration types.

`-Woverloaded-virtual`

In a derived class, the definitions of virtual functions must match the type signature of a virtual function declared in the base class. Use this option to request warnings when a derived class declares a function that may be an erroneous attempt to define a virtual function; that is, warn when a function with the same name as a virtual function in the base class, but with a type signature that doesn't match any virtual functions from the base class.

-Wtemplate-debugging	When using templates in a C++ program, warn if debugging is not yet fully available.
-w	Inhibit all warning messages.
+eN	Control how virtual function definitions are used, in a fashion compatible with cfront 1.x.

PRAGMAS

Two `#pragma` directives are supported for GNU C++, to permit using the same header file for two purposes: as a definition of interfaces to a given object class, and as the full definition of the contents of that object class.

<code>#pragma interface</code>	Use this directive in header files that define object classes, to save space in most of the object files that use those classes. Normally, local copies of certain information (backup copies of inline member functions, debugging information, and the internal tables that implement virtual functions) must be kept in each object file that includes class definitions. You can use this pragma to avoid such duplication. When a header file containing <code>#pragma interface</code> is included in a compilation, this auxiliary information will not be generated (unless the main input source file itself uses <code>#pragma implementation</code>). Instead, the object files will contain references to be resolved at link time.
<code>#pragma implementation</code> <code>#pragma implementation !objects.h!</code>	Use this pragma in a main input file, when you want full output from included header files to be generated (and made globally visible). The included header file, in turn, should use <code>#pragma interface</code> . Backup copies of inline member functions, debugging information, and the internal tables used to implement virtual functions are all generated in implementation files. If you use <code>#pragma implementation</code> with no argument, it applies to an include file with the same basename as your source file; for example, in <code>allclass.cc</code> , <code>#pragma implementation</code> by itself is equivalent to <code>#pragma implementation "allclass.h"</code> . Use the string argument if you want a single implementation file to include code from multiple header files. There is no way to split up the contents of a single header file into multiple implementation files.

FILES

<code>file.h</code>	C header (preprocessor) file
<code>file.i</code>	Preprocessed C source
<code>file file.C</code>	C++ source file
<code>file.cc</code>	C++ source file
<code>file.cxx</code>	C++ source file
<code>file.s</code>	Assembly language file
<code>file.o</code>	Object file
<code>a.out</code>	Link edited output
<code>TMPPDIR/cc</code>	Temporary files
<code>LIBDIR/cpp</code>	Preprocessor
<code>LIBDIR/cc1plus</code>	Compiler
<code>LIBDIR/collect</code>	Linker front end needed on some machines
<code>LIBDIR/libgcc.a</code>	GCC subroutine library
<code>/lib/crt[01n].o</code>	Start-up routine
<code>LIBDIR/ccrt0</code>	Additional start-up routine for C++
<code>/lib/libc.a</code>	Standard C library; see intro(3)

<code>/usr/include</code>	Standard directory for <code>#include</code> files
<code>LIBDIR/include</code>	Standard gcc directory for <code>#include</code> files
<code>LIBDIR/g++-include</code>	Additional g++ directory for <code>#include</code>

`LIBDIR` is usually `/usr/local/lib/machine/version`.

`TMPDIR` comes from the environment variable `TMPDIR` (default `/usr/tmp` if available, else `/tmp`).

SEE ALSO

`gcc(1)`, `cpp(1)`, `as(1)`, `ld(1)`, `gdb(1)`, `adb(1)`, `dbx(1)`, `sdb(1)`, `gcc`, `cpp`, `as`, `ld`, and `gdb` entries in `info`.

Using and Porting GNU CC (for version 2.0), Richard M. Stallman; *The C Preprocessor*, Richard M. Stallman; *Debugging with GDB: the GNU Source-Level Debugger*, Richard M. Stallman and Roland H. Pesch; *Using as: the GNU Assembler*, Dean Elsner, Jay Fenlason and friends; *gld: the GNU linker*, Steve Chamberlain and Roland Pesch.

BUGS

For instructions on how to report bugs, see the GCC manual.

COPYING

Copyright © 1991, 1992, 1993 Free Software Foundation, Inc. Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

AUTHORS

See the GNU CC Manual for the contributors to GNU CC.

GNU Tools, 30 April 1993

g3topbm

`g3topbm`—Convert a Group 3 fax file into a portable bitmap

SYNOPSIS

```
g3topbm [-kludge] [-reversebits] [-stretch] [g3file]
```

DESCRIPTION

Reads a Group 3 fax file as input. Produces a portable bitmap as output.

OPTIONS

- `-kludge` Tells `g3topbm` to ignore the first few lines of the file; sometimes fax files have some junk at the beginning.
- `-reversebits` Tells `g3topbm` to interpret bits least-significant first, instead of the default most-significant first. Apparently, some fax modems do it one way and others do it the other way. If you get a whole bunch of “bad code word” messages, try using this flag.
- `-stretch` Tells `g3topbm` to stretch the image vertically by duplicating each row. This is for the low-quality transmission mode.

All flags can be abbreviated to their shortest unique prefix.

REFERENCES

The standard for Group 3 fax is defined in CCITT Recommendation T.4.

BUGS

Probably.

SEE ALSO

pbmtog3(1), pbm(5)

AUTHOR

Copyright © 1989 by Paul Haeberli (paul@manray.sgi.com)

2 October 1989

gawk

gawk—Pattern scanning and processing language

SYNOPSIS

```
gawk [ POSIX or GNU style options ] -f program-file [ -- ] file ...
gawk [ POSIX or GNU style options ] [ -- ] program-text file ...
```

DESCRIPTION

gawk is the GNU Project's implementation of the `awk` programming language. It conforms to the definition of the language in the 1003.2 Command Language and Utilities Standard. This version in turn is based on the description in *The AWK Programming Language*, by Aho, Kernighan, and Weinberger, with the additional features defined in the System V Release 4 version of `awk`. gawk also provides some GNU-specific extensions.

The command line consists of options to gawk itself, the `awk` program text (if not supplied via the `-f` or `--file` options), and values to be made available in the `ARGC` and `ARGV` predefined `awk` variables.

OPTIONS

gawk options may be either the traditional one-letter options, or the GNU-style long options. Traditional style options start with a single `-`, while GNU long options start with `--`. GNU-style long options are provided for both GNU-specific features and for mandated features. Other implementations of the `awk` language are likely to only accept the traditional one-letter options.

Following the standard, gawk-specific options are supplied via arguments to the `-w` option. Multiple `-w` options may be supplied, or multiple arguments may be supplied together if they are separated by commas, or enclosed in quotes and separated by whitespace. Case is ignored in arguments to the `-w` option. Each `-w` option has a corresponding GNU-style long option, as detailed below. Arguments to GNU-style long options are either joined with the option by an `=` sign, with no intervening spaces, or they may be provided in the next command-line argument.

gawk accepts the following options:

<code>-F fs</code> , <code>--field-separator=fs</code>	Use <code>fs</code> for the input field separator (the value of the <code>FS</code> -predefined variable).
<code>-v var=val</code> , <code>--assign=var=val</code>	Assign the value <code>val</code> , to the variable <code>var</code> , before execution of the program begins. Such variable values are available to the <code>BEGIN</code> block of an <code>awk</code> program.
<code>-f program-file</code> , <code>--file=program-file</code>	Read the <code>awk</code> program source from the file <code>program-file</code> , instead of from the first command-line argument. Multiple <code>-f</code> (or <code>--file</code>) options may be used.
<code>-mf=NNN</code> , <code>-mr=NNN</code>	Set various memory limits to the value <code>NNN</code> . The <code>f</code> flag sets the maximum number of fields, and the <code>r</code> flag sets the maximum record size. These two flags and the <code>-m</code> option are from the AT&T Bell Labs research version of <code>awk</code> . They are ignored by gawk, since gawk has no predefined limits.

<code>-W compat, --compat</code>	Run in compatibility mode. In compatibility mode, <code>gawk</code> behaves identically to <code>awk</code> ; none of the GNU-specific extensions are recognized. See “GNU Extensions,” later in this manual page, for more information.
<code>-W copyleft, -W copyright, --copyleft, --copyright</code>	Print the short version of the GNU copyright information message on the error output.
<code>-W help, -W usage --help, --usage</code>	Print a relatively short summary of the available options on the error output. Per the GNU Coding Standards, these options cause an immediate, successful exit.
<code>-W lint, --lint</code>	Provide warnings about constructs that are dubious or nonportable to other <code>awk</code> implementations.
<code>-W posix, --posix</code>	This turns on compatibility mode, with the following additional restrictions: \x escape sequences are not recognized. The synonym <code>func</code> for the keyword function is not recognized. The operators <code>**</code> and <code>**=</code> cannot be used in place of <code>^</code> and <code>^=</code> .
<code>-W source=program-text, --source=program-text</code>	Use <code>program-text</code> as <code>awk</code> program source code. This option allows the easy intermixing of library functions (used via the <code>-f</code> and <code>--file</code> options) with source code entered on the command line. It is intended primarily for medium to large <code>awk</code> programs used in shell scripts. The <code>-W source=</code> form of this option uses the rest of the command-line argument for <code>program-text</code> ; no other options to <code>-W</code> will be recognized in the same argument.
<code>-W version, --version</code>	Print version information for this particular copy of <code>gawk</code> on the error output. This is useful mainly for knowing if the current copy of <code>gawk</code> on your system is up-to-date with respect to whatever the Free Software Foundation is distributing. Per the GNU Coding Standards, these options cause an immediate, successful exit.
<code>--</code>	Signal the end of options. This is useful to allow further arguments to the <code>awk</code> program itself to start with a <code>-</code> . This is mainly for consistency with the argument-parsing convention used by most other programs.

In compatibility mode, any other options are flagged as illegal, but are otherwise ignored. In normal operation, as long as program text has been supplied, unknown options are passed on to the `awk` program in the `ARGV` array for processing. This is particularly useful for running `awk` programs via the `#!` executable interpreter mechanism.

awk PROGRAM EXECUTION

An `awk` program consists of a sequence of pattern-action statements and optional function definitions:

```
pattern { action statements }
function name(parameter list) { statements }
```

`gawk` first reads the program source from the `program-file(s)` if specified, from arguments to `-W source=`, or from the first nonoption argument on the command line. The `-f` and `-W source=` options may be used multiple times on the command line. `gawk` will read the program text as if all the `program-files` and command-line source texts had been concatenated together. This is useful for building libraries of `awk` functions, without having to include them in each new `awk` program that uses them. It also provides the ability to mix library functions with command-line programs.

The environment variable `AWKPATH` specifies a search path to use when finding source files named with the `-f` option. If this variable does not exist, the default path is `./usr/lib/awk:/usr/local/lib/awk`.

If a filename given to the `-f` option contains a `/` character, no path search is performed.

`gawk` executes `awk` programs in the following order. First, all variable assignments specified via the `-v` option are performed. Next, `gawk` compiles the program into an internal form. Then, `gawk` executes the code in the `BEGIN` block(s) (if any), and then proceeds to read each file named in the `ARGV` array. If there are no files named on the command line, `gawk` reads the standard input.

If a filename on the command line has the form `var=val`, it is treated as a variable assignment. The variable `var` will be assigned the value `val`. (This happens after any `BEGIN` block(s) have been run.) Command-line variable assignment is most

useful for dynamically assigning values to the variables `awk` uses to control how input is broken into fields and records. It is also useful for controlling state if multiple passes are needed over a single data file.

If the value of a particular element of `ARGV` is empty (""), `gawk` skips over it.

For each line in the input, `gawk` tests to see if it matches any *pattern* in the `awk` program. For each pattern that the line matches, the associated *action* is executed. The patterns are tested in the order they occur in the program.

Finally, after all the input is exhausted, `gawk` executes the code in the `END` block(s) (if any).

VARIABLES AND FIELDS

`awk` variables are dynamic; they come into existence when they are first used. Their values are either floating-point numbers or strings, or both, depending upon how they are used. `awk` also has one-dimensional arrays; arrays with multiple dimensions may be simulated. Several predefined variables are set as a program runs; these will be described as needed and summarized in the “Built-In Variables” subsection.

FIELDS

As each input line is read, `gawk` splits the line into fields, using the value of the `FS` variable as the field separator. If `FS` is a single character, fields are separated by that character. Otherwise, `FS` is expected to be a full regular expression. In the special case that `FS` is a single blank, fields are separated by runs of blanks or tabs. Note that the value of `IGNORECASE` (see the following) will also affect how fields are split when `FS` is a regular expression.

If the `FIELDWIDTHS` variable is set to a space separated list of numbers, each field is expected to have fixed width, and `gawk` will split up the record using the specified widths. The value of `FS` is ignored. Assigning a new value to `FS` overrides the use of `FIELDWIDTHS`, and restores the default behavior.

Each field in the input line may be referenced by its position, `$1`, `$2`, and so on. `$0` is the whole line. The value of a field may be assigned to as well. Fields need not be referenced by constants:

```
n = 5
print $n
```

prints the fifth field in the input line. The variable `NF` is set to the total number of fields in the input line.

References to nonexistent fields (that is, fields after `$NF`) produce the null-string. However, assigning to a nonexistent field (for example, `$(NF+2) = 5`) will increase the value of `NF`, create any intervening fields with the null string as their value, and cause the value of `$0` to be recomputed, with the fields being separated by the value of `OFS`. References to negative-numbered fields cause a fatal error.

BUILT-IN VARIABLES

`awk`’s built-in variables are the following:

<code>ARGC</code>	The number of command-line arguments (does not include options to <code>gawk</code> , or the program source).
<code>ARGIND</code>	The index in <code>ARGV</code> of the current file being processed.
<code>ARGV</code>	Array of command-line arguments. The array is indexed from 0 to <code>ARGC - 1</code> . Dynamically changing the contents of <code>ARGV</code> can control the files used for data.
<code>CONVFMT</code>	The conversion format for numbers, “%.6g”, by default.
<code>ENVIRON</code>	An array containing the values of the current environment. The array is indexed by the environment variables, each element being the value of that variable (for example, <code>ENVIRON["HOME"]</code> might be <code>/u/arnold</code>). Changing this array does not affect the environment seen by programs which <code>gawk</code> spawns via redirection or the <code>system()</code> function. (This may change in a future version of <code>gawk</code> .)
<code>ERRNO</code>	If a system error occurs either doing a redirection for <code>getline</code> , during a read for <code>getline</code> , or during a <code>close()</code> , then <code>ERRNO</code> will contain a string describing the error.
<code>FIELDWIDTHS</code>	A whitespace-separated list of fieldwidths. When set, <code>gawk</code> parses the input into fields of fixed width, instead of using the value of the <code>FS</code> variable as the field separator. The fixed field width facility is still experimental; expect the semantics to change as <code>gawk</code> evolves over time.

FILENAME	The name of the current input file. If no files are specified on the command line, the value of FILENAME is <code>-</code> . However, FILENAME is undefined inside the BEGIN block.
FNR	The input record number in the current input file.
FS	The input field separator, a blank by default.
IGNORECASE	Controls the case-sensitivity of all regular expression operations. If IGNORECASE has a nonzero value, then pattern matching in rules, field splitting with FS, regular expression matching with <code>~</code> and <code>!~</code> , and the <code>gsub()</code> , <code>index()</code> , <code>match()</code> , <code>split()</code> , and <code>sub()</code> predefined functions will all ignore case when doing regular expression operations. Thus, if IGNORECASE is not equal to zero, <code>/aB/</code> matches all of the strings <code>ab</code> , <code>aB</code> , <code>Ab</code> , and <code>AB</code> . As with all awk variables, the initial value of IGNORECASE is zero, so all regular expression operations are normally case-sensitive.
NF	The number of fields in the current input record.
NR	The total number of input records seen so far.
OFMT	The output format for numbers, <code>"%.6g"</code> , by default.
OFS	The output field separator, a blank by default.
ORS	The output record separator, by default a newline.
RS	The input record separator, by default a newline. RS is exceptional in that only the first character of its string value is used for separating records. (This will probably change in a future release of gawk.) If RS is set to the null string, then records are separated by blank lines. When RS is set to the null string, then the newline character always acts as a field separator, in addition to whatever value FS may have.
RSTART	The index of the first character matched by <code>match()</code> ; 0 if no match.
RLENGTH	The length of the string matched by <code>match()</code> ; -1 if no match.
SUBSEP	The character used to separate multiple subscripts in array elements, by default <code>␣</code> .

ARRAYS

Arrays are subscripted with an expression between square brackets. If the expression is an expression list (`expr, expr ...`) then the array subscript is a string consisting of the concatenation of the (string) value of each expression, separated by the value of the SUBSEP variable. This facility is used to simulate multiply dimensioned arrays. For example,

```
i = "A" ; j = "B" ; k = "C"
x[i, j, k] = "hello, world\n"
```

assigns the string `hello, world\n` to the element of the array `x` which is indexed by the string `"A␣B␣C"`. All arrays in awk are associative, that is indexed by string values.

The special operator `in` may be used in an `if` or `while` statement to see if an array has an index consisting of a particular value:

```
if (val in array)
    print array[val]
```

If the array has multiple subscripts, use `(i,j)` in `array`.

The `in` construct may also be used in a `for` loop to iterate over all the elements of an array.

An element may be deleted from an array using the `delete` statement. The `delete` statement may also be used to delete the entire contents of an array.

VARIABLE TYPING AND CONVERSION

Variables and fields may be floating-point numbers, or strings, or both. How the value of a variable is interpreted depends upon its context. If used in a numeric expression, it will be treated as a number; if used as a string, it will be treated as a string.

To force a variable to be treated as a number, add `0` to it; to force it to be treated as a string, concatenate it with the null string.

When a string must be converted to a number, the conversion is accomplished using `atof(3)`. A number is converted to a string by using the value of `CONVFMT` as a format string for `sprintf(3)`, with the numeric value of the variable as the argument. However, even though all numbers in `awk` are floating-point, integral values are *always* converted as integers. Thus, given this:

```
CONVFMT = "%2.2f"
a =12
b =a "
```

the variable `b` has a string value of 12 and not 12.00.

`gawk` performs comparisons as follows: If two variables are numeric, they are compared numerically. If one value is numeric and the other has a string value that is a “numeric string,” then comparisons are also done numerically. Otherwise, the numeric value is converted to a string and a string comparison is performed. Two strings are compared, of course, as strings. According to the standard, even if two strings are numeric strings, a numeric comparison is performed. However, this is clearly incorrect, and `gawk` does not do this.

Uninitialized variables have the numeric value 0 and the string value "" (the null, or empty, string).

PATTERNS AND ACTIONS

`awk` is a line-oriented language. The pattern comes first, and then the action. Action statements are enclosed in and `.BR`. Either the pattern may be missing, or the action may be missing, but, of course, not both. If the pattern is missing, the action will be executed for every single line of input. A missing action is equivalent to

```
{ print }
```

which prints the entire line.

Comments begin with the `#` character, and continue until the end of the line. Blank lines may be used to separate statements. Normally, a statement ends with a newline, however, this is not the case for lines ending in a `,`, `{`, `?`, `:`, `&&`, or `||`. Lines ending in `do` or `else` also have their statements automatically continued on the following line. In other cases, a line can be continued by ending it with a `\`, in which case the newline will be ignored.

Multiple statements may be put on one line by separating them with a semicolon. This applies to both the statements within the action part of a pattern-action pair (the usual case), and to the pattern-action statements themselves.

PATTERNS

`awk` patterns may be one of the following:

```
BEGIN
END
/regular expression/
relational expression
pattern && pattern
pattern jj pattern
pattern ? pattern : pattern
(pattern)
! pattern
pattern1, pattern2
```

`BEGIN` and `END` are two special kinds of patterns that are not tested against the input. The action parts of all `BEGIN` patterns are merged as if all the statements had been written in a single `BEGIN` block. They are executed before any of the input is read. Similarly, all the `END` blocks are merged, and executed when all the input is exhausted (or when an `exit` statement is executed). `BEGIN` and `END` patterns cannot be combined with other patterns in pattern expressions. `BEGIN` and `END` patterns cannot have missing action parts.

For `/regular expression/` patterns, the associated statement is executed for each input line that matches the regular expression. Regular expressions are the same as those in `egrep(1)`, and are summarized as follows:

A relational expression may use any of the operators defined later in the section on actions. These generally test whether certain fields match certain regular expressions.

The `&&`, `||`, and `!` operators are logical AND, logical OR, and logical NOT, respectively, as in C. They do short-circuit evaluation, also as in C, and are used for combining more primitive pattern expressions. As in most languages, parentheses may be used to change the order of evaluation.

The `?:` operator is like the same operator in C. If the first pattern is true, then the pattern used for testing is the second pattern; otherwise, it is the third. Only one of the second and third patterns is evaluated.

The `pattern1, pattern2` form of an expression is called a *range pattern*. It matches all input records starting with a line that matches `pattern1`, and continuing until a record that matches `pattern2`, inclusive. It does not combine with any other sort of pattern expression.

REGULAR EXPRESSIONS

Regular expressions are the extended kind found in `egrep`. They are composed of characters as follows:

<code>c</code>	Matches the non-meta-character <code>c</code> .
<code>\c</code>	Matches the literal character <code>c</code> .
<code>.</code>	Matches any character except newline.
<code>^</code>	Matches the beginning of a line or a string.
<code>\$</code>	Matches the end of a line or a string.
<code>[abc...]</code>	Character class, matches any of the characters <code>abc...</code>
<code>[^abc...]</code>	Negated character class, matches any character except <code>abc...</code> and newline.
<code>r1 r2</code>	Alternation: matches either <code>r1</code> or <code>r2</code> .
<code>r1r2</code>	Concatenation: matches <code>r1</code> , and then <code>r2</code> .
<code>r+</code>	Matches one or more <code>rs</code> .
<code>r*</code>	Matches zero or more <code>rs</code> .
<code>r?</code>	Matches zero or one <code>rs</code> .
<code>(r)</code>	Grouping: matches <code>r</code> .

The escape sequences that are valid in string constants are also legal in regular expressions.

ACTIONS

Action statements are enclosed in braces, `{` and `}`. Action statements consist of the usual assignment, conditional, and looping statements found in most languages. The operators, control statements, and input/output statements available are patterned after those in C.

OPERATORS

The operators in `awk`, in order of increasing precedence, are

<code>=+=--</code>	Assignment. Both absolute assignment (<code>var = value</code>) and operator-assignment (the other forms) are supported.
<code>*= /= %= ^=</code>	
<code>?:</code>	The C conditional expression. This has the form <code>expr1 ? expr2 : expr3</code> . If <code>expr1</code> is true, the value of the expression is <code>expr2</code> ; otherwise, it is <code>expr3</code> . Only one of <code>expr2</code> and <code>expr3</code> is evaluated.
<code> </code>	Logical OR.
<code>&&</code>	Logical AND.
<code>~!</code>	Regular expression match, negated match. NOTE: Do not use a constant regular expression (<code>/foo/</code>) to the left of a <code>~</code> or <code>!~</code> . Only use one on the right side. The expression <code>/foo/ ~ exp</code> has the same meaning as <code>((\$0 ~ /foo/) ~ exp)</code> . This is usually <i>not</i> what was intended.
<code>< > <=>=</code>	The regular relational operators.
<code>blank</code>	String concatenation.
<code>+-</code>	Addition and subtraction.

<code>*/%</code>	Multiplication, division, and modulus.
<code>+ - !</code>	Unary plus, unary minus, and logical negation.
<code>^</code>	Exponentiation (<code>**</code> may also be used, and <code>*=</code> for the assignment operator).
<code>++ --</code>	Increment and decrement, both prefix and postfix.
<code>\$</code>	Field reference.

CONTROL STATEMENTS

The control statements are as follows:

```
if (condition) statement [ else statement ]
while (condition) statement
do statement while (condition)
for (expr1; expr2; expr3) statement
for (var in array) statementbreak
continue
delete array[index]
delete array
exit [ expression ]
{ statements }
```

I/O STATEMENTS

The input/output statements are as follows:

<code>close(filename)</code>	Close file (or pipe, see paragraph following this list).
<code>getline</code>	Set <code>\$0</code> from next input record; set <code>NF</code> , <code>NR</code> , <code>FNR</code> .
<code>getline <file</code>	Set <code>\$0</code> from next record of <code>file</code> ; set <code>NF</code> .
<code>getline var</code>	Set <code>var</code> from next input record; set <code>NF</code> , <code>FNR</code> .
<code>getline var <file</code>	Set <code>var</code> from next record of <code>file</code> .
<code>next</code>	Stop processing the current input record. The next input record is read and processing starts over with the first pattern in the <code>awk</code> program. If the end of the input data is reached, the <code>END</code> block(s), if any, are executed.
<code>next file</code>	Stop processing the current input file. The next input record read comes from the next input file. <code>FILENAME</code> is updated, <code>FNR</code> is reset to 1, and processing starts over with the first pattern in the <code>awk</code> program. If the end of the input data is reached, the <code>END</code> block(s), if any, are executed.
<code>print</code>	Prints the current record.
<code>print expr-list</code>	Prints expressions. Each expression is separated by the value of the <code>OFS</code> variable. The output record is terminated with the value of the <code>ORS</code> variable.
<code>print expr-list >file</code>	Prints expressions on <code>file</code> . Each expression is separated by the value of the <code>OFS</code> variable. The output record is terminated with the value of the <code>ORS</code> variable.
<code>printf fmt, expr-list</code>	Format and print.
<code>printf fmt, expr-list >file</code>	Format and print on <code>file</code> .
<code>system(cmd-line)</code>	Execute the command <code>cmd-line</code> , and return the exit status. (This may not be available on - POSIX systems.)

Other input/output redirections are also allowed. For `print` and `printf`, `>>file` appends output to the `file`, while `|` command writes on a pipe. In a similar fashion, command `|` `getline` pipes into `getline`. The `getline` command will return 0 on end of file, and -1 on an error.

THE printf STATEMENT

The `awk` versions of the `printf` statement and `sprintf()` function accept the following conversion specification formats:

<code>%c</code>	An ASCII character. If the argument used for <code>%c</code> is numeric, it is treated as a character and printed. Otherwise, the argument is assumed to be a string, and the only first character of that string is printed.

<code>%d</code>	A decimal number (the integer part).
<code>%i</code>	Just like <code>%d</code> .
<code>%e</code>	A floating-point number of the form <code>[-]d.dddE[+-]dd</code> .
<code>%f</code>	A floating-point number of the form <code>[-]ddd.ddd</code> .
<code>%g</code>	Use <code>e</code> or <code>f</code> conversion, whichever is shorter, with nonsignificant zeros suppressed.
<code>%o</code>	An unsigned octal number (again, an integer).
<code>%s</code>	A character string.
<code>%x</code>	An unsigned hexadecimal number (an integer).
<code>%X</code>	Like <code>%x</code> , but using <code>ABCDEF</code> instead of <code>abcdef</code> .
<code>%%</code>	A single <code>%</code> character; no argument is converted.

There are optional, additional parameters that may lie between the `%` and the control letter:

<code>-</code>	The expression should be left-justified within its field.
<code>width</code>	The field should be padded to this width. If the number has a leading zero, then the field will be padded with zeros. Otherwise, it is padded with blanks. This applies even to the nonnumeric output formats.
<code>.prec</code>	A number indicating the maximum width of strings or digits to the right of the decimal point.

The dynamic `width` and `prec` capabilities of the C `printf()` routines are supported. A `*` in place of either the `width` or `prec` specifications will cause their values to be taken from the argument list to `printf` or `sprintf()`.

SPECIAL FILENAMES

When doing I/O redirection from either `print` or `printf` into a file, or via `getline` from a file, `gawk` recognizes certain special filenames internally. These filenames allow access to open file descriptors inherited from `gawk`'s parent process (usually the shell). Other special filenames provide access information about the running `gawk` process. The filenames are

<code>/dev/pid</code>	Reading this file returns the process ID of the current process, in decimal, terminated with a newline.
<code>/dev/ppid</code>	Reading this file returns the parent process ID of the current process, in decimal, terminated with a newline.
<code>/dev/pgrp</code>	Reading this file returns the process group ID of the current process, in decimal, terminated with a newline.
<code>/dev/user</code>	Reading this file returns a single record terminated with a newline. The fields are separated with blanks. <code>\$1</code> is the value of the <code>getuid(2)</code> system call, <code>\$2</code> is the value of the <code>geteuid(2)</code> system call, <code>\$3</code> is the value of the <code>getgid(2)</code> system call, and <code>\$4</code> is the value of the <code>getegid(2)</code> system call. If there are any additional fields, they are the group IDs returned by <code>getgroups(2)</code> . Multiple groups may not be supported on all systems.
<code>/dev/stdin</code>	The standard input.
<code>/dev/stdout</code>	The standard output.
<code>/dev/stderr</code>	The standard error output.
<code>/dev/fd/n</code>	The file associated with the open file descriptor <code>n</code> .

These are particularly useful for error messages. For example, you could use

```
print "You blew it!" > "/dev/stderr"
```

whereas you would otherwise have to use

```
print "You blew it!" j "cat 1>&2"
```

These filenames may also be used on the command line to name data files.

NUMERIC FUNCTIONS

`awk` has the following predefined arithmetic functions:

<code>atan2(y, x)</code>	Returns the arctangent of <code>y/x</code> in radians.
<code>cos(expr)</code>	Returns the cosine in radians.

<code>exp(expr)</code>	The exponential function.
<code>int(expr)</code>	Truncates to integer.
<code>log(expr)</code>	The natural logarithm function.
<code>rand()</code>	Returns a random number between 0 and 1.
<code>sin(expr)</code>	Returns the sine in radians.
<code>sqrt(expr)</code>	The square root function.
<code>srand(expr)</code>	Use <i>expr</i> as a new seed for the random number generator. If no <i>expr</i> is provided, the time of day will be used. The return value is the previous seed for the random number generator.

STRING FUNCTIONS

`awk` has the following predefined string functions:

<code>gsub(r, s, t)</code>	For each substring matching the regular expression <i>r</i> in the string <i>t</i> , substitute the string <i>s</i> , and return the number of substitutions. If <i>t</i> is not supplied, use <code>\$0</code> .
<code>index(s, t)</code>	Returns the index of the string <i>t</i> in the string <i>s</i> , or 0 if <i>t</i> is not present.
<code>length(s)</code>	Returns the length of the string <i>s</i> , or the length of <code>\$0</code> if <i>s</i> is not supplied.
<code>match(s, r)</code>	Returns the position in <i>s</i> where the regular expression <i>r</i> occurs, or 0 if <i>r</i> is not present, and sets the values of <code>RSTART</code> and <code>RLLENGTH</code> .
<code>split(s, a, r)</code>	Splits the string <i>s</i> into the array <i>a</i> on the regular expression <i>r</i> , and returns the number of fields. If <i>r</i> is omitted, <code>FS</code> is used instead. The array <i>a</i> is cleared first.
<code>sprintf(fmt, expr-list)</code>	Prints <i>expr-list</i> according to <i>fmt</i> , and returns the resulting string.
<code>sub(r, s, t)</code>	Just like <code>gsub()</code> , but only the first matching substring is replaced.
<code>substr(s, i, n)</code>	Returns the <i>n</i> -character substring of <i>s</i> starting at <i>i</i> . If <i>n</i> is omitted, the rest of <i>s</i> is used.
<code>tolower(str)</code>	Returns a copy of the string <i>str</i> , with all the uppercase characters in <i>str</i> translated to their corresponding lowercase counterparts. Nonalphabetic characters are left unchanged.
<code>toupper(str)</code>	Returns a copy of the string <i>str</i> , with all the lowercase characters in <i>str</i> translated to their corresponding uppercase counterparts. Nonalphabetic characters are left unchanged.

TIME FUNCTIONS

Since one of the primary uses of `awk` programs is processing log files that contain time stamp information, `gawk` provides the following two functions for obtaining time stamps and formatting them.

<code>systemtime()</code>	Returns the current time of day as the number of seconds since the Epoch (Midnight UTC, January 1, 1970 on systems).
<code>strftime(format, timestamp)</code>	Formats <i>timestamp</i> according to the specification in <i>format</i> . The <i>timestamp</i> should be of the same form as returned by <code>systemtime()</code> . If <i>timestamp</i> is missing, the current time of day is used. See the specification for the <code>strftime()</code> function in C for the format conversions that are guaranteed to be available. A public-domain version of <code>strftime(3)</code> and a man page for it are shipped with <code>gawk</code> ; if that version was used to build <code>gawk</code> , then all of the conversions described in that man page are available to <code>gawk</code> .

STRING CONSTANTS

String constants in `awk` are sequences of characters enclosed between double quotes (`"`). Within strings, certain *escape sequences* are recognized, as in C. These are

<code>\\</code>	A literal backslash.
<code>\a</code>	The “alert” character; usually the ASCII BEL character.
<code>\b</code>	Backspace.
<code>\f</code>	Formfeed.
<code>\n</code>	Newline.

<code>\r</code>	Carriage return.
<code>\t</code>	Horizontal tab.
<code>\v</code>	Vertical tab.
<code>\xhex digits</code>	The character represented by the string of hexadecimal digits following the <code>\x</code> . As in C, all following hexadecimal digits are considered part of the escape sequence. (This feature should tell us something about language design by committee.) For example, <code>"\x1B"</code> is the ASCII ESC (escape) character.
<code>\ddd</code>	The character represented by the 1-, 2-, or 3-digit sequence of octal digits. For example, <code>"\033"</code> is the ASCII ESC (escape) character.
<code>\c</code>	The literal character <code>c</code> .

The escape sequences may also be used inside constant regular expressions (for example, `/[\t\f\n\r\v]/` matches whitespace characters).

FUNCTIONS

Functions in `awk` are defined as follows:

```
function name(parameter list) { statements }
```

Functions are executed when called from within the action parts of regular pattern-action statements. Actual parameters supplied in the function call are used to instantiate the formal parameters declared in the function. Arrays are passed by reference, other variables are passed by value.

Functions were not originally part of the `awk` language, so the provision for local variables is rather clumsy: They are declared as extra parameters in the parameter list. The convention is to separate local variables from real parameters by extra spaces in the parameter list. For example

```
function f(p, q, a, b) { # a & b are local
    .... }
/abc/ { ... ; f(1, 2) ; ... }
```

The left parenthesis in a function call is required to immediately follow the function name, without any intervening whitespace. This is to avoid a syntactic ambiguity with the concatenation operator. This restriction does not apply to the built-in functions listed earlier.

Functions may call each other and may be recursive. Function parameters used as local variables are initialized to the null string and the number zero upon function invocation.

The word `func` may be used in place of `function`.

EXAMPLES

Print and sort the login names of all users:

```
BEGIN { FS = ":" }
{ print $1 | "sort" }
```

Count lines in a file:

```
{ nlines++ }
END { print nlines }
```

Precede each line by its number in the file:

```
{ print FNR, $0 }
```

Concatenate and line number (a variation on a theme):

```
{ print NR, $0 }
```

SEE ALSO

`egrep(1)`, `getpid(2)`, `getppid(2)`, `getpgrp(2)`, `getuid(2)`, `geteuid(2)`, `getgid(2)`, `getegid(2)`, `get-groups(2)`

The AWK Programming Language, Alfred V. Aho, Brian W. Kernighan, Peter J. Weinberger, Addison-Wesley, 1988. ISBN 0-201-07981-X.

The GAWK Manual, Edition 0.15, published by the Free Software Foundation, 1993.

POSIX COMPATIBILITY

A primary goal for gawk is compatibility with the standard, as well as with the latest version of `awk`. To this end, gawk incorporates the following user-visible features that are not described in the `awk` book, but are part of `awk` in System V Release 4, and are in the standard.

The `-v` option for assigning variables before program execution starts is new. The book indicates that command-line variable assignment happens when `awk` would otherwise open the argument as a file, which is after the `BEGIN` block is executed. However, in earlier implementations, when such an assignment appeared before any filenames, the assignment would happen *before* the `BEGIN` block was run. Applications came to depend on this “feature.” When `awk` was changed to match its documentation, this option was added to accommodate applications that depended upon the old behavior. (This feature was agreed on by both the AT&T and GNU developers.)

The `-w` option for implementation-specific features is from the standard.

When processing arguments, gawk uses the special option `--` to signal the end of arguments. In compatibility mode, it will warn about, but otherwise ignore, undefined options. In normal operation, such arguments are passed on to the `awk` program for it to process.

The `awk` book does not define the return value of `srand()`. The System V Release 4 version of `awk` (and the standard) has it return the seed it was using, to allow keeping track of random number sequences. Therefore, `srand()` in gawk also returns its current seed.

Other new features are: the use of multiple `-f` options (from MKS `awk`); the `ENVIRON` array; the `\a`, and `\v` escape sequences (done originally in gawk and fed back into AT&T’s version); the `tolower()` and `toupper()` built-in functions (from AT&T); and the C conversion specifications in `printf` (done first in AT&T’s version).

GNU EXTENSIONS

gawk has some extensions to `awk`. They are described in this section. All the extensions described here can be disabled by invoking gawk with the `-W compat` option.

The following features of gawk are not available in `awk`:

The `\x` escape sequence.

The `systeme()` and `strftime()` functions.

The special filenames available for I/O redirection are not recognized.

The `ARGIND` and `ERRNO` variables are not special.

The `IGNORECASE` variable and its side effects.

The `FIELDWIDTHS` variable and fixed width field splitting.

No path search is performed for files named via the `-f` option. Therefore, the `AWKPATH` environment variable is not special.

The use of `next file` to abandon processing of the current input file.

The use of `delete array` to delete the entire contents of an array.

The `awk` book does not define the return value of the `close()` function. gawk’s `close()` returns the value from `fclose(3)`, or `pclose(3)`, when closing a file or pipe, respectively.

When gawk is invoked with the `-W compat` option, if the `fs` argument to the `-F` option is `t`, then `FS` will be set to the `tab` character. Since this is a rather ugly special case, it is not the default behavior. This behavior also does not occur if `-Wposix` has been specified.

HISTORICAL FEATURES

There are two features of historical `awk` implementations that `gawk` supports. First, it is possible to call the `length()` built-in function not only with no argument, but even without parentheses! Thus, this:

```
a = length
```

is the same as either of these:

```
a = length()
a = length($0)
```

This feature is marked as “deprecated” in the standard, and `gawk` will issue a warning about its use if `-W lint` is specified on the command line.

The other feature is the use of either the `continue` or the `break` statements outside the body of a `while`, `for`, or `do` loop. Traditional `awk` implementations have treated such usage as equivalent to the next statement. `gawk` will support this usage if `-W compat` has been specified.

ENVIRONMENT VARIABLES

If `POSIXLY_CORRECT` exists in the environment, then `gawk` behaves exactly as if `--posix` had been specified on the command line. If `--lint` has been specified, `gawk` will issue a warning message to this effect.

BUGS

The `-F` option is not necessary given the command-line variable assignment feature; it remains only for backwards compatibility.

If your system actually has support for `/dev/fd` and the associated `/dev/stdin`, `/dev/stdout`, and `/dev/stderr` files, you may get different output from `gawk` than you would get on a system without those files. When `gawk` interprets these files internally, it synchronizes output to the standard output with output to `/dev/stdout`, while on a system with those files, the output is actually to different open files. Caveat emptor.

VERSION INFORMATION

This man page documents `gawk`, version 2.15.

Starting with the 2.15 version of `gawk`, the `-c`, `-v`, `-C`, `-D`, `-a`, and `-e` options of the 2.11 version are no longer recognized. This fact will not even be documented in the manual page for the next major version.

AUTHORS

The original version of `awk` was designed and implemented by Alfred Aho, Peter Weinberger, and Brian Kernighan of AT&T Bell Labs. Brian Kernighan continues to maintain and enhance it.

Paul Rubin and Jay Fenlason, of the Free Software Foundation, wrote `gawk`, to be compatible with the original version of `awk` distributed in the seventh edition. John Woods contributed a number of bug fixes. David Trueman, with contributions from Arnold Robbins, made `gawk` compatible with the new version of `awk`. Arnold Robbins is the current maintainer.

The initial DOS port was done by Conrad Kwok and Scott Garfinkle. Scott Deifik is the current DOS maintainer. Pat Rankin did the port to VMS, and Michal Jaegermann did the port to the Atari ST. The port to OS/2 was done by Kai Uwe Rommel, with contributions and help from Darrel Hankerson.

BUG REPORTS

If you find a bug in `gawk`, please send electronic mail to

```
bug-gnu-utils@prep.ai.mit.edu,
```

with a copy to `arnold@gnu.ai.mit.edu`. Please include your operating system and its revision, the version of `gawk`, what C compiler you used to compile it, and a test program and data that are as small as possible for reproducing the problem.

Before sending a bug report, please do two things. First, verify that you have the latest version of gawk. Many bugs (usually subtle ones) are fixed at each release, and if yours is out of date, the problem may already have been solved. Second, please read this man page and the reference manual carefully to be sure that what you think is a bug really is, instead of just a quirk in the language.

ACKNOWLEDGMENTS

Brian Kernighan of Bell Labs provided valuable assistance during testing and debugging.

We thank him.

Free Software Foundation, 24 November 1994

gcal

gcal—Displays month/year calendar sheets, eternal holiday lists for Julian and Gregorian years, and fixed date warning lists—all in a variety of ways.

SYNOPSIS

```
gcal [[ Option... ] [%Date ] [@File... ] ] [ Command ]
```

DESCRIPTION

gcal is a program similar the standard calendar programs BSD-`'cal'` and `calendar`.

gcal displays Gregorian calendars, Julian calendars (before September 1752).

If gcal is started without any options or commands, a calendar of the current month is displayed.

If the calendar of a definite year is wanted, the year must be fully specified. For example, `gcal 94` displays a year calendar of the year 94, not of the year 1994.

If two arguments are given in the `command` part, the first argument denotes the month and the second argument denotes the year. In case any illegal commands are given running gcal, the program will use internal defaults.

The Gregorian Reformation is assumed to have occurred in 1752 on the 3rd of September. Ten days following that date were eliminated by the reformation, so the calendar for that month is a bit unusual.

MORE PROGRAM INFORMATION

You get more program information if you start gcal as follows:

```
gcal -h gcal -? gcal -help
resp.,
gcal -hh gcal -?? gcal -long-help[=ARG]j[=?] gcal -usage[=ARG]j[=?]
```

A hypertext file `gcal.info` containing detailed online information should be available, which you can inspect using your GNU Infobrowser.

COPYRIGHT

gcal copyright © 1994, 1995, 1996 by Thomas Esken. This software doesn't claim completeness, correctness, or usability. On principle, I will not be liable for any damages or losses (implicit or explicit), which result from using or handling my software. If you use this software, you agree without any exception to this agreement, which binds you legally.

gcal is free software and distributed under the terms of the GNU General Public License; published by the Free Software Foundation; version 2 or (at your option) any later version.

Any suggestions, improvements, extensions, bug reports, donations, proposals for contract work, and so forth are welcome! If you like this tool, I'd appreciate a postcard from you!

Enjoy it =8^)

AUTHOR

Thomas Esken (esken@uni-muenster.de)

Im Hagenfeld 84

D-48147 Muenster; Germany

Phone : +49 251 232585

SEE ALSO

cal(1), calendar(1)

16 July 1996

gcc, g++

gcc, g++—GNU project C and C++ Compiler (v2.7)

SYNOPSIS

```
gcc [ option j filename ] . . .
g++ [ option j filename ]...
```

WARNING

The information in this man page is an extract from the full documentation of the GNU C compiler and is limited to the meaning of the options.

This man page is not kept up-to-date except when volunteers want to maintain it. If you find a discrepancy between the man page and the software, please check the `info` file, which is the authoritative documentation.

If we find that the things in this man page that are out of date cause significant confusion or complaints, we will stop distributing the man page. The alternative, updating the man page when we update the `info` file, is impossible because the rest of the work of maintaining GNU CC leaves us no time for that. The GNU project regards man pages as obsolete and should not let them take time away from other things.

For complete and current documentation, refer to the `info` file `gcc` or the manual *Using and Porting GNU CC* (for version 2.0). Both are made from the Texinfo source file `gcc.texinfo`.

DESCRIPTION

The C and C++ compilers are integrated. Both process input files through one or more of four stages: preprocessing, compilation, assembly, and linking. Source filename suffixes identify the source language, but which name you use for the compiler governs default assumptions:

```
gcc      Assumes preprocessed (.i) files are C and assumes C-style linking.
g++      Assumes preprocessed (.i) files are C++ and assumes C++-style linking.
```

Suffixes of source filenames indicate the language and kind of processing to be done:

```
.c        C source; preprocess, compile, assemble
.C        C++ source; preprocess, compile, assemble
.cc       C++ source; preprocess, compile, assemble
.cxx      C++ source; preprocess, compile, assemble
.m        Objective-C source; preprocess, compile, assemble
.i        Preprocessed C; compile, assemble
.ii       Preprocessed C++; compile, assemble
.s        Assembler source; assemble
```

`.S` Assembler source; preprocess, assemble
`.h` Preprocessor file; not usually named on command line

Files with other suffixes are passed to the linker. Common cases include

`.o` Object file
`.a` Archive file

Linking is always the last stage unless you use one of the `-c`, `-S`, or `-E` options to avoid it (or unless compilation errors stop the whole process). For the link stage, all `.o` files corresponding to source files, `-l` libraries, unrecognized filenames (including named `.o` object files, and `.a` archives) are passed to the linker in command-line order.

OPTIONS

Options must be separate: `-dr` is quite different from `-d -r`.

Most `-f` and `-W` options have two contrary forms: `-fname` and `-fno-name` (or `-Wname` and `-Wno-name`). Only the nondefault forms are shown here.

Here is a summary of all the options, grouped by type. Explanations are in the following sections.

Overall Options

`-c -S -E -o file -pipe -v -x language`

Language Options

<code>-ansi</code>	<code>-fall-virtual</code>	<code>-fcond-mismatch</code>
<code>-fdollars-in-identifiers</code>	<code>-fenum-int-equiv</code>	<code>-fexternal-templates</code>
<code>-fno-asm</code>	<code>-fno-builtin</code>	<code>-fno-strict-prototype</code>
<code>-fsigned-bitfields</code>	<code>-fsigned-char</code>	<code>-fthis-is-variable</code>
<code>-funsigned-bitfields</code>	<code>-funsigned-char</code>	<code>-fwritable-strings</code>
<code>-traditional</code>	<code>-traditional-cpp</code>	<code>-trigraphs</code>

Warning Options

<code>-fsyntax-only</code>	<code>-pedantic</code>	<code>-pedantic-errors</code>
<code>-w -W -Wall</code>	<code>-Waggregate-return</code>	<code>-Wcast-align</code>
<code>-Wcast-qual</code>	<code>-Wchar-subscript</code>	<code>-Wcomment</code>
<code>-Wconversion</code>	<code>-Wenum-clash</code>	<code>-Werror</code>
<code>-Wformat</code>	<code>-Wid-clash-len</code>	<code>-Wimplicit</code>
<code>-Winline</code>	<code>-Wmissing-prototypes</code>	<code>-Wmissing-declarations</code>
<code>-Wnested-externs</code>	<code>-Wno-import</code>	<code>-Wparentheses</code>
<code>-Wpointer-arith</code>	<code>-Wredundant-decls</code>	<code>-Wreturn-type</code>
<code>-Wshadow</code>	<code>-Wstrict-prototypes</code>	<code>-Wswitch</code>
<code>-Wtemplate-debugging</code>	<code>-Wtraditional</code>	<code>-Wtrigraphs</code>
<code>-Wuninitialized</code>	<code>-Wunused</code>	<code>-Wwrite-strings</code>

Debugging Options

`-a -dletters -fpretend-float -g -glevel -gcoff -gxcoff -gxcoff+ -gdwarf -gdwarf+ -gstabs -gstabs+ -ggdb -p -pg -save-temps -print-file-name=library -print-libgcc-file-name -print-prog-name=program`

Optimization Options

<code>-fcaller-saves</code>	<code>-fcse-follow-jumps</code>	<code>-fcse-skip-blocks</code>
<code>-fdelayed-branch</code>	<code>-felide-constructors</code>	<code>-fexpensive-optimizations</code>
<code>-ffast-math</code>	<code>-ffloat-store</code>	<code>-fforce-addr</code>
<code>-fforce-mem</code>	<code>-finline-functions</code>	<code>-fkeep-inline-functions</code>

-fmemorize-lookups	-fno-default-inline	-fno-defer-pop
-fno-function-cse	-fno-inline	-fno-peephole
-fomit-frame-pointer	-frerun-cse-after-loop	-fschedule-insns
-fschedule-insns2	-fstrength-reduce	-fthread-jumps
-funroll-all-loops	-funroll-loops	-O -O2

Preprocessor Options

-Assertion -C -dD -dM -dN -Dmacro[=defn]-E -H- idirafter dir -include file -imacros file -iprefix file -iwithprefix dir -M -MD -MM -MMD -nostdinc -P -Umacro -undef

Assembler Option

-Wa,option

Linker Options

-llibrary -nostartfiles -nostdlib -static -shared -symbolic -Xlinkeroption -Wl,option -u symbol

Directory Options

-Bprefix -Idir -I- -Ldir

Target Options

-b machine -V version

Configuration-Dependent Options

M680x0 Options

-m68000-m68020 -m68020-40-m68030-m68040-m68881 -mbitfield -mc68000 -mc68020 -mfpa -mnobitfield -mrtld -mshort -msoft-float

VAX Options

-mg -mgnu -munix

SPARC Options

-mepilogue -mfpu -mhard-float -mno-fpu -mno-epilogue -msoft-float -msparclite -mv8 -msupersparc -mcyppress

Convex Options

-margcount -mc1 -mc2 -mnoargcount

AMD29K Options

-m29000-m29050 -mbw -mdw -mkernel-registers -mlarge -mnbw -mnodw -msmall -mstack-check -muser-registers

M88K Options

-m88000 -m88100 -m88110	-mbig-pic
-mcheck-zero-division	-mhandle-large-shift
-midentify-revision	-mno-check-zero-division
-mno-ocs-debug-info	-mno-ocs-frame-position
-mno-optimize-arg-area	-mno-serialize-volatile
-mno-underscores	-mocs-debug-info
-mocs-frame-position	-moptimize-arg-area
-mserialize-volatile	-mshort-data-num
-msvr3 -msvr4	-mtrap-large-shift
-muse-div-instruction	-mversion-03.00
-mwarn-passed-structs	

RS6000 Options

-mfp-in-toc -mno-fop-in-toc

RT Options

-mcall-lib-mul -mfp-arg-in-fpregs -mfp-arg-in-gregs
 -mfull-fp-blocks -mhc-struct-return -min-line-mul
 -mminimum-fp-blocks -mnohc-struct-return

MIPS Options

-mcpu=cpu type -mips2 -mips3 -mint64 -mlong64
 -mlonglong128 -mmips-as -mgas -mrnames
 -mno-rnames -mgpopt -mno-gpopt -mstats
 -mno-stats -mmemcpy -mno-memcpy -mno-mips-tfile
 -mmips-tfile -msoft-float -mhard-float -mabicalls
 -mno-abicalls -mhalf-pic -mno-half-pic -G num -nocpp

i386 Options

-m486 -mno-486 -msoft-float -mno-fp-ret-in-387

HPPA Options

-mpa-risc-1-0 -mpa-risc-1-1 -mkernel -mshared-libs -mno-shared-libs -mlong-calls -mdisable-fpregs -mdisable-indexing -mtrailing-colon

i960 Options

-mcpu.type
 -mnumerics -msoft-float -mleaf-procedures
 -mno-leaf-procedures -mtail-call -mno-tail-call
 -mcomplex-addr -mno-complex-addr -mcode-align
 -mno-code-align -mic-compat -mic2.0-compat
 -mic3.0-compat -masm-compat -mintel-asm
 -mstrict-align -mno-strict-align -mold-align
 -mno-old-align

DEC Alpha Options

-mfp-regs -mno-fp-regs -mno-soft-float -msoft-float

System V Options

-G -Qy -Qn -YP,paths -Ym,dir

Code-Generation Options

-fcall-saved-reg -fcall-used-reg -ffixed-reg -finhibit-size-directive -fnonnull-objects -fno-common -fno-ident
 -fno-gnu-linker -fpcc-struct-return -fpic -fPIC -freg-struct- return -fshared-data -fshort-enums -fshort-double -fvolatile -fvolatile-global -fverbose-asm

OVERALL OPTIONS

- `-x language` Specify explicitly the language for the following input files (rather than choosing a default based on the filename suffix). This option applies to all following input files until the next `-x` option. Possible values of language are `c`, `objective-c`, `c-header`, `c++`, `cpp-output`, `assembler`, and `assembler-with-cpp`.
- `-x none` Turn off any specification of a language, so that subsequent files are handled according to their filename suffixes (as they are if `-x` has not been used at all).

If you want only some of the four stages (preprocess, compile, assemble, link), you can use `-x` (or filename suffixes) to tell `gcc` where to start, and one of the options `-c`, `-S`, or `-E` to say where `gcc` is to stop. Note that some combinations (for example, `-x cpp-output -E`) instruct `gcc` to do nothing at all.

- `-c` Compile or assemble the source files, but do not link. The compiler output is an object file corresponding to each source file.
By default, `gcc` makes the object filename for a source file by replacing the suffix `.c`, `.i`, `.s`, and so on, with `.o`. Use `-o` to select another name.
`gcc` ignores any unrecognized input files (those that do not require compilation or assembly) with the `-c` option.
- `-S` Stop after the stage of compilation proper; do not assemble. The output is an assembler code file for each nonassembler input file specified.
By default, `gcc` makes the assembler filename for a source file by replacing the suffix `.c`, `.i`, and so on, with `.s`. Use `-o` to select another name.
`gcc` ignores any input files that don't require compilation.
- `-E` Stop after the preprocessing stage; do not run the compiler proper. The output is preprocessed source code, which is sent to the standard output.
`gcc` ignores input files that don't require preprocessing.
- `-o file` Place output in file `file`. This applies regardless to whatever sort of output `gcc` is producing, whether it be an executable file, an object file, an assembler file, or preprocessed C code.
Since only one output file can be specified, it does not make sense to use `-o` when compiling more than one input file, unless you are producing an executable file as output.
If you do not specify `-o`, the default is to put an executable file in `a.out`, the object file for `source.suffix` in `source.o`, its assembler file in `source.s`, and all preprocessed C source on standard output.
- `-v` Print (on standard error output) the commands executed to run the stages of compilation. Also print the version number of the compiler driver program and of the preprocessor and the compiler proper.
- `-pipe` Use pipes rather than temporary files for communication between the various stages of compilation. This fails to work on some systems where the assembler cannot read from a pipe; but the GNU assembler has no trouble.

LANGUAGE OPTIONS

The following options control the dialect of C that the compiler accepts:

- `-ansi` Support all ANSI standard C programs.
This turns off certain features of GNU C that are incompatible with ANSI C, such as the `asm`, `inline`, and `typeof` keywords, and predefined macros such as `unix` and `vax` that identify the type of system you are using. It also enables the undesirable and rarely used ANSI trigraph feature, and disallows `$` as part of identifiers. The alternate keywords `__asm__`, `__extension__`, `__inline__`, and `__typeof__` continue to work despite `-ansi`. You would not want to use them in an ANSI C program, of course, but it is useful to put them in header files that might be included in compilations done with `-ansi`. Alternate predefined macros such as `__unix__` and `__vax__` are also available, with or without `-ansi`.
The `-ansi` option does not cause non-ANSI programs to be rejected gratuitously. For that, `-pedantic` is required in addition to `-ansi`.

	The preprocessor predefines a macro <code>__STRICT_ANSI__</code> when you use the <code>-ansi</code> option. Some header files may notice this macro and refrain from declaring certain functions or defining certain macros that the ANSI standard doesn't call for; this is to avoid interfering with any programs that might use these names for other things.
<code>-fno-asm</code>	Do not recognize <code>asm</code> , <code>inline</code> , or <code>typeof</code> as a keyword. These words may then be used as identifiers. You can use <code>__asm__</code> , <code>__inline__</code> , and <code>__typeof__</code> instead. <code>-ansi</code> implies <code>-fno-asm</code> .
<code>-fno-builtin</code>	Don't recognize built-in functions that do not begin with two leading underscores. Currently, the functions affected include <code>_exit</code> , <code>abort</code> , <code>abs</code> , <code>alloca</code> , <code>cos</code> , <code>exit</code> , <code>fabs</code> , <code>labs</code> , <code>memcmp</code> , <code>memcpy</code> , <code>sin</code> , <code>sqrt</code> , <code>strcmp</code> , <code>strcpy</code> , and <code>strlen</code> . The <code>-ansi</code> option prevents <code>alloca</code> and <code>_exit</code> from being built-in functions.
<code>-fno-strict-prototype</code>	Treat a function declaration with no arguments, such as <code>int foo();</code> , as C would treat it—as saying nothing about the number of arguments or their types (C++ only). Normally, such a declaration in C++ means that the function <code>foo</code> takes no arguments.
<code>-trigraphs</code>	Support ANSI C trigraphs. The <code>-ansi</code> option implies <code>-trigraphs</code> .
<code>-traditional</code>	Attempt to support some aspects of traditional C compilers. For details, see the <i>GNU C Manual</i> ; the duplicate list here has been deleted so that we won't get complaints when it is out of date. But one note about C++ programs only (not C). <code>-traditional</code> has one additional effect for C++: assignment to this is permitted. This is the same as the effect of <code>-fthis-is-variable</code> .
<code>-traditional-cpp</code>	Attempt to support some aspects of traditional C preprocessors. This includes the items that specifically mention the preprocessor previously, but none of the other effects of <code>-traditional</code> .
<code>-fdollars-in-identifiers</code>	Permit the use of <code>\$</code> in identifiers (C++ only). You can also use <code>-fno-dollars-in-identifiers</code> to explicitly prohibit use of <code>\$</code> . (GNU C++ allows <code>\$</code> by default on some target systems but not others.)
<code>-fenum-int-equiv</code>	Permit implicit conversion of <code>int</code> to enumeration types (C++ only). Normally GNU C++ allows conversion of <code>enum</code> to <code>int</code> , but not the other way around.
<code>-fexternal-templates</code>	Produce smaller code for template declarations, by generating only a single copy of each template function where it is defined (C++ only). To use this option successfully, you must also mark all files that use templates with either <code>#pragma implementation</code> (the definition) or <code>#pragma interface</code> (declarations). When your code is compiled with <code>-fexternal-templates</code> , all template instantiations are external. You must arrange for all necessary instantiations to appear in the implementation file; you can do this with a <code>typedef</code> that references each instantiation needed. Conversely, when you compile using the default option <code>-fno-external-templates</code> , all template instantiations are explicitly internal.
<code>-fall-virtual</code>	Treat all possible member functions as virtual, implicitly. All member functions (except for constructor functions and <code>new</code> or <code>delete</code> member operators) are treated as virtual functions of the class where they appear. This does not mean that all calls to these member functions will be made through the internal table of virtual functions. Under some circumstances, the compiler can determine that a call to a given virtual function can be made directly; in these cases, the calls are direct in any case.
<code>-fcond-mismatch</code>	Allow conditional expressions with mismatched types in the second and third arguments. The value of such an expression is void.
<code>-fthis-is-variable</code>	Permit assignment to <code>this</code> (C++ only). The incorporation of user-defined free store management into C++ has made assignment to <code>this</code> an anachronism. Therefore, by default it is invalid to assign to <code>this</code> within a class member function. However, for backwards compatibility, you can make it valid with <code>-fthis-is-variable</code> .
<code>-funsigned-char</code>	Let the type <code>char</code> be unsigned, like unsigned <code>char</code> . Each kind of machine has a default for what <code>char</code> should be. It is either like unsigned <code>char</code> by default or like signed <code>char</code> by default.

Ideally, a portable program should always use `signed char` or `unsigned char` when it depends on the signedness of an object. But many programs have been written to use `plain char` and expect it to be signed, or expect it to be unsigned, depending on the machines they were written for. This option, and its inverse, lets you make such a program work with the opposite default.

The type `char` is always a distinct type from each of `signed char` and `unsigned char`, even though its behavior is always just like one of those two.

<code>-fsigned-char</code>	Let the type <code>char</code> be signed, like <code>signed char</code> . Note that this is equivalent to <code>-fno-unsigned-char</code> , which is the negative form of <code>-funsigned-char</code> . Likewise, <code>-fno-signed-char</code> is equivalent to <code>-funsigned-char</code> .
<code>-fsigned-bitfields</code> <code>-funsigned-bitfields</code>	These options control whether a bitfield is signed or unsigned, when declared with no explicit or unsigned qualifier.
<code>-fno-signed-bitfields</code> <code>-fno-unsigned-bitfields</code>	By default, such a bitfield is signed, because this is consistent: The basic integer types such as <code>int</code> signed are signed types. However, when you specify <code>-traditional</code> , bitfields are all unsigned no matter what.
<code>-fwritable-strings</code>	Store string constants in the writable data segment and don't uniquize them. This is for compatibility with old programs which assume they can write into string constants. <code>-traditional</code> also has this effect. Writing into string constants is a very bad idea; constants should be constant.

PREPROCESSOR OPTIONS

These options control the C preprocessor, which is run on each C source file before actual compilation.

If you use the `-E` option, `gcc` does nothing except preprocessing. Some of these options make sense only together with `-E` because they cause the preprocessor output to be unsuitable for actual compilation.

<code>-include file</code>	Process <code>file</code> as input before processing the regular input file. In effect, the contents of <code>file</code> are compiled first. Any <code>-D</code> and <code>-U</code> options on the command line are always processed before <code>-include file</code> , regardless of the order in which they are written. All the <code>-include</code> and <code>-imacros</code> options are processed in the order in which they are written.
<code>-imacros file</code>	Process <code>file</code> as input, discarding the resulting output, before processing the regular input file. Because the output generated from <code>file</code> is discarded, the only effect of <code>-imacros file</code> is to make the macros defined in <code>file</code> available for use in the main input. The preprocessor evaluates any <code>-D</code> and <code>-U</code> options on the command line before processing <code>-imacros file</code> , regardless of the order in which they are written. All the <code>-include</code> and <code>-imacros</code> options are processed in the order in which they are written.
<code>-idirafter dir</code>	Add the directory <code>dir</code> to the second <code>include</code> path. The directories on the second <code>include</code> path are searched when a header file is not found in any of the directories in the main <code>include</code> path (the one that <code>-I</code> adds to).
<code>-iprefix prefix</code>	Specify <code>prefix</code> as the prefix for subsequent <code>-iwithprefix</code> options.
<code>-iwithprefix dir</code>	Add a directory to the second <code>include</code> path. The directory's name is made by concatenating <code>prefix</code> and <code>dir</code> , where <code>prefix</code> was specified previously with <code>-iprefix</code> .
<code>-nostdinc</code>	Do not search the standard system directories for header files. Only the directories you have specified with <code>-I</code> options (and the current directory, if appropriate) are searched. By using both <code>-nostdinc</code> and <code>-I-</code> , you can limit the include file search file to only those directories you specify explicitly.
<code>-nostdinc++</code>	Do not search for header files in the C++-specific standard directories, but do still search the other standard directories. (This option is used when building <code>libg++</code> .)
<code>-undef</code>	Do not predefine any nonstandard macros (including architecture flags).
<code>-E</code>	Run only the C preprocessor. Preprocess all the C source files specified and output the results to standard output or to the specified output file.
<code>-C</code>	Tell the preprocessor not to discard comments. Used with the <code>-E</code> option.

-P	Tell the preprocessor not to generate <code>#line</code> commands. Used with the <code>-E</code> option.
-M [-MG]	Tell the preprocessor to output a rule suitable for <code>make</code> describing the dependencies of each object file. For each source file, the preprocessor outputs one <code>make</code> rule whose target is the object filename for that source file and whose dependencies are all the files that have been included with <code>#include</code> . This rule may be a single line or may be continued with <code>\-newline</code> if it is long. The list of rules is printed on standard output instead of the preprocessed C program. -M implies <code>-E</code> . -MG says to treat missing header files as generated files and assume they live in the same directory as the source file. It must be specified in addition to <code>-M</code> .
-MM [-MG]	Like <code>-M</code> but the output mentions only the user header files included with <code>#include "file"</code> . System header files included with <code>#include <file></code> are omitted.
-MD	Like <code>-M</code> but the dependency information is written to files with names made by replacing <code>.o</code> with <code>.d</code> at the end of the output filenames. This is in addition to compiling the file as specified; <code>-MD</code> does not inhibit ordinary compilation the way <code>-M</code> does. The Mach utility <code>md</code> can be used to merge the <code>.d</code> files into a single dependency file suitable for using with the <code>make</code> command.
-MMD	Like <code>-MD</code> except mention only user header files, not system header files.
-H	Print the name of each header file used, in addition to other normal activities.
-Aquestion(answer)	Assert the answer <code>answer</code> for <code>question</code> , in case it is tested with a preprocessor conditional such as <code>#if question(answer)</code> . <code>-A-</code> disables the standard assertions that normally describe the target machine.
-Aquestion (answer)	Assert the answer <code>answer</code> for <code>question</code> , in case it is tested with a preprocessor conditional such as <code>#if # question (answer)</code> . <code>-A-</code> disables the standard assertions that normally describe the target machine.
-Dmacro	Define macro <code>macro</code> with the string <code>1</code> as its definition.
-Dmacro=defn	Define macro <code>macro</code> as <code>defn</code> . All instances of <code>-D</code> on the command line are processed before any <code>-U</code> options.
-Umacro	Undefine macro <code>macro</code> . <code>-U</code> options are evaluated after all <code>-D</code> options, but before any <code>-include</code> and <code>-imacros</code> options.
-dM	Tell the preprocessor to output only a list of the macro definitions that are in effect at the end of preprocessing. Used with the <code>-E</code> option.
-dD	Tell the preprocessor to pass all macro definitions into the output, in their proper sequence in the rest of the output.
-dN	Like <code>-dD</code> except that the macro arguments and contents are omitted. Only <code>#define name</code> is included in the output.

ASSEMBLER OPTION

-Wa,option	Pass <code>option</code> as an option to the assembler. If <code>option</code> contains commas, it is split into multiple options at the commas.

LINKER OPTIONS

These options come into play when the compiler links object files into an executable output file. They are meaningless if the compiler is not doing a link step.

object-file-name	A filename that does not end in a special recognized suffix is considered to name an object file or library. (Object files are distinguished from libraries by the linker according to the file contents.) If <code>gcc</code> does a link step, these object files are used as input to the linker.
-llibrary	Use the library named <code>library</code> when linking. The linker searches a standard list of directories for the library, which is actually a file named <code>lib library.a</code> . The linker then uses this file as if it had been specified precisely by name.

The directories searched include several standard system directories plus any that you specify with `-L`.

Normally, the files found this way are library files—archive files whose members are object files. The linker handles an archive file by scanning through it for members that define symbols that have so far been referenced but not defined. However, if the linker finds an ordinary object file rather than a library, the object file is linked in the usual fashion. The only difference between using an `-l` option and specifying a filename is that `-l` surrounds `library` with `lib` and `.a` and searches several directories.

<code>-lobjc</code>	You need this special case of the <code>-l</code> option in order to link an Objective C program.
<code>-nostartfiles</code>	Do not use the standard system startup files when linking. The standard libraries are used normally.
<code>-nostdlib</code>	Don't use the standard system libraries and startup files when linking. Only the files you specify will be passed to the linker.
<code>-static</code>	On systems that support dynamic linking, this prevents linking with the shared libraries. On other systems, this option has no effect.
<code>-shared</code>	Produce a shared object which can then be linked with other objects to form an executable. Only a few systems support this option.
<code>-symbolic</code>	Bind references to global symbols when building a shared object. Warn about any unresolved references (unless overridden by the link editor option <code>-Xlinker -z -Xlinker defs</code>). Only a few systems support this option.
<code>-Xlinker option</code>	Pass <code>option</code> as an option to the linker. You can use this to supply system-specific linker options which GNU CC does not know how to recognize. If you want to pass an option that takes an argument, you must use <code>-Xlinker</code> twice: once for the option and once for the argument. For example, to pass <code>-assert definitions</code>, you must write <code>-Xlinker -assert -Xlinker definitions</code>. It does not work to write <code>-Xlinker "-assert definitions"</code>, because this passes the entire string as a single argument, which is not what the linker expects.
<code>-Wl,option</code>	Pass <code>option</code> as an option to the linker. If <code>option</code> contains commas, it is split into multiple options at the commas.
<code>-u symbol</code>	Pretend the symbol <code>symbol</code> is undefined, to force linking of library modules to define it. You can use <code>-u</code> multiple times with different symbols to force loading of additional library modules.

DIRECTORY OPTIONS

These options specify directories to search for header files, for libraries, and for parts of the compiler:

<code>-I dir</code>	Append directory <code>dir</code> to the list of directories searched for include files.
<code>-I-</code>	Any directories you specify with <code>-I</code> options before the <code>-I-</code> option are searched only for the case of <code>#include "file"</code>; they are not searched for <code>#include <file></code>. If additional directories are specified with <code>-I</code> options after the <code>-I-</code>, these directories are searched for all <code>#include</code> directives. (Ordinarily <i>all</i> <code>-I</code> directories are used this way.) In addition, the <code>-I-</code> option inhibits the use of the current directory (where the current input file came from) as the first search directory for <code>#include "file"</code>. There is no way to override this effect of <code>-I-</code>. With <code>-I-</code> you can specify searching the directory that was current when the compiler was invoked. That is not exactly the same as what the preprocessor does by default, but it is often satisfactory. <code>-I-</code> does not inhibit the use of the standard system directories for header files. Thus, <code>-I-</code> and <code>-nostdinc</code> are independent.
<code>-L dir</code>	Add directory <code>dir</code> to the list of directories to be searched for <code>-l</code> .
<code>-Bprefix</code>	This option specifies where to find the executables, libraries, and data files of the compiler itself. The compiler driver program runs one or more of the subprograms <code>cpp</code>, <code>cc1</code> (or, for C++, <code>cc1plus</code>), <code>as</code>, and <code>ld</code>. It tries <code>prefix</code> as a prefix for each program it tries to run, both with and without <code>machine / version /</code>.

For each subprogram to be run, the compiler driver first tries the `-B` prefix, if any. If that name is not found, or if `-B` was not specified, the driver tries two standard prefixes, which are `/usr/lib/gcc/` and `/usr/local/lib/gcc-lib/`. If neither of those results in a filename that is found, the compiler driver searches for the unmodified program name, using the directories specified in your `PATH` environment variable.

The runtime support file `libgcc.a` is also searched for using the `-B` prefix, if needed. If it is not found there, the two standard prefixes (preceding paragraph) are tried, and that is all. The file is left out of the link if it is not found by those means. Most of the time, on most machines, `libgcc.a` is not actually necessary.

You can get a similar result from the environment variable `GCC_EXEC_PREFIX`; if it is defined, its value is used as a prefix in the same way. If both the `-B` option and the `GCC_EXEC_PREFIX` variable are present, the `-B` option is used first and the environment variable value second.

WARNING OPTIONS

Warnings are diagnostic messages that report constructions that are not inherently erroneous but are risky or suggest there may have been an error.

These options control the amount and kinds of warnings produced by GNU CC:

<code>-fsyntax-only</code>	Check the code for syntax errors, but don't emit any output.
<code>-w</code>	Inhibit all warning messages.
<code>-Wno-import</code>	Inhibit warning messages about the use of <code>#import</code> .
<code>-pedantic</code>	Issue all the warnings demanded by strict ANSI standard C; reject all programs that use forbidden extensions. Valid ANSI standard C programs should compile properly with or without this option (though a rare few will require <code>-ansi</code>). However, without this option, certain GNU extensions and traditional C features are supported as well. With this option, they are rejected. There is no reason to use this option; it exists only to satisfy pedants. <code>-pedantic</code> does not cause warning messages for use of the alternate keywords whose names begin and end with <code>'_'</code> . Pedantic warnings are also disabled in the expression that follows <code>extension</code> . However, only system header files should use these escape routes; application programs should avoid them.
<code>-pedantic-errors</code>	Like <code>-pedantic</code> , except that errors are produced rather than warnings.
<code>-W</code>	Print extra warning messages for these events: A nonvolatile automatic variable might be changed by a call to <code>longjmp</code> . These warnings are possible only in optimizing compilation. The compiler sees only the calls to <code>setjmp</code> . It cannot know where <code>longjmp</code> will be called; in fact, a signal handler could call it at any point in the code. As a result, you may get a warning even when there is in fact no problem because <code>longjmp</code> cannot in fact be called at the place which would cause a problem. A function can return either with or without a value. (Falling off the end of the function body is considered returning without a value.) For example, this function would evoke such a warning: <pre>foo (a) { if (a > 0) return a; }</pre> Spurious warnings can occur because GNU CC does not realize that certain functions (including <code>abort</code> and <code>longjmp</code>) will never return. An expression-statement or the left side of a comma expression contains no side effects. To suppress the warning, cast the unused expression to void. For example, an expression such as <code>x[i,j]</code> will cause a warning, but <code>x[(void)i,j]</code> will not. An unsigned value is compared against zero with <code>></code> or <code><=</code> .

<code>-Wimplicit</code>	Warn whenever a function or parameter is implicitly declared.
<code>-Wreturn-type</code>	Warn whenever a function is defined with a <code>return-type</code> that defaults to <code>int</code> . Also warn about any <code>return</code> statement with no <code>return-value</code> in a function whose <code>return-type</code> is not <code>void</code> .
<code>-Wunused</code>	Warn whenever a local variable is unused aside from its declaration, whenever a function is declared static but never defined, and whenever a statement computes a result that is explicitly not used.
<code>-Wswitch</code>	Warn whenever a <code>switch</code> statement has an index of enumerational type and lacks a case for one or more of the named codes of that enumeration. (The presence of a default label prevents this warning.) case labels outside the enumeration range also provoke warnings when this option is used.
<code>-Wcomment</code>	Warn whenever a comment-start sequence <code>/</code> appears in a comment.
<code>-Wtrigraphs</code>	Warn if any trigraphs are encountered (assuming they are enabled).
<code>-Wformat</code>	Check calls to <code>printf</code> and <code>scanf</code> , and so on, to make sure that the arguments supplied have types appropriate to the format string specified.
<code>-Wchar-subscripts</code>	Warn if an array subscript has type <code>char</code> . This is a common cause of error, as programmers often forget that this type is signed on some machines.
<code>-Wuninitialized</code>	An automatic variable is used without first being initialized. These warnings are possible only in optimizing compilation, because they require data flow information that is computed only when optimizing. If you don't specify <code>-O</code>, you simply won't get these warnings. These warnings occur only for variables that are candidates for register allocation. Therefore, they do not occur for a variable that is declared <code>volatile</code>, or whose address is taken, or whose size is other than 1, 2, 4, or 8 bytes. Also, they do not occur for structures, unions, or arrays, even when they are in registers. Note that there may be no warning about a variable that is used only to compute a value that itself is never used, because such computations may be deleted by data flow analysis before the warnings are printed. These warnings are made optional because GNU CC is not smart enough to see all the reasons why the code might be correct despite appearing to have an error. Here is one example of how this can happen:

```

{
  int x;
  switch (y)
  {
    case 1: x = 1;
    break;
    case 2: x = 4;
    break;
    case 3: x = 5;
  }
  foo (x);
}

```

If the value of `y` is always 1, 2, or 3, then `x` is always initialized, but GNU CC doesn't know this. Here is another common case:

```

{
  int save_y;
  if (change_y) save_y=y,y=new_y;
  ...
  if (change_y) y=save_y;
}

```

This has no bug because `save_y` is used only if it is set.

Some spurious warnings can be avoided if you declare as `volatile` all the functions you use that never return.

<code>-Wparentheses</code>	Warn if parentheses are omitted in certain contexts.
<code>-Wtemplate-debugging</code>	When using templates in a C++ program, warn if debugging is not yet fully available (C++ only).
<code>-Wall</code>	All of the preceding <code>-W</code> options combined. These are all the options that pertain to usage that we recommend avoiding and that we believe is easy to avoid, even in conjunction with macros.
The remaining <code>-W...</code> options are not implied by <code>-Wall</code> because they warn about constructions that we consider reasonable to use, on occasion, in clean programs.	
<code>-Wtraditional</code>	Warn about certain constructs that behave differently in traditional and ANSI C: Macro arguments occurring within string constants in the macro body. These would substitute the argument in traditional C, but are part of the constant in ANSI C. A function declared external in one block and then used after the end of the block. A <code>switch</code> statement has an operand of type <code>long</code> .
<code>-Wshadow</code>	Warn whenever a local variable shadows another local variable.
<code>-Wid-clash-len</code>	Warn whenever two distinct identifiers match in the first <code>len</code> characters. This may help you prepare a program that will compile with certain obsolete, brain-damaged compilers.
<code>-Wpointer-arith</code>	Warn about anything that depends on the size of a function type or of <code>void</code> . GNU C assigns these types a size of 1, for convenience in calculations with void pointers and pointers to functions.
<code>-Wcast-qual</code>	Warn whenever a pointer is cast so as to remove a type qualifier from the target type. For example, warn if a <code>const char</code> is cast to an ordinary <code>char</code> .
<code>-Wcast-align</code>	Warn whenever a pointer is cast such that the required alignment of the target is increased. For example, warn if a <code>char</code> is cast to an <code>int</code> on machines where integers can only be accessed at two- or four-byte boundaries.
<code>-Wwrite-strings</code>	Give string constants the type <code>const char[length]</code> so that copying the address of one into a non- <code>const char</code> pointer will get a warning. These warnings will help you find at compile time code that can try to write into a string constant, but only if you have been very careful about using <code>const</code> in declarations and prototypes. Otherwise, it will just be a nuisance; this is why we did not make <code>-Wall</code> request these warnings.
<code>-Wconversion</code>	Warn if a prototype causes a type conversion that is different from what would happen to the same argument in the absence of a prototype. This includes conversions of fixed point to floating and vice versa, and conversions changing the width or signedness of a fixed point argument except when the same as the default promotion.
<code>-Waggregate-return</code>	Warn if any functions that return structures or unions are defined or called. (In languages where you can return an array, this also elicits a warning.)
<code>-Wstrict-prototypes</code>	Warn if a function is declared or defined without specifying the argument types. (An old-style function definition is permitted without a warning if preceded by a declaration which specifies the argument types.)
<code>-Wmissing-prototypes</code>	Warn if a global function is defined without a previous prototype declaration. This warning is issued even if the definition itself provides a prototype. The aim is to detect global functions that fail to be declared in header files.
<code>-Wmissing-declarations</code>	Warn if a global function is defined without a previous declaration. Do so even if the definition itself provides a prototype. Use this option to detect global functions that are not declared in header files.
<code>-Wredundant-decls</code>	Warn if anything is declared more than once in the same scope, even in cases where multiple declaration is valid and changes nothing.
<code>-Wnested-externs</code>	Warn if an extern declaration is encountered within an function.
<code>-Wenum-clash</code>	Warn about conversion between different enumeration types (C++ only).
<code>-Woverloaded-virtual</code>	(C++ only.) In a derived class, the definitions of virtual functions must match the type signature of a virtual function declared in the base class. Use this option to request warnings when a derived class declares a function that may be an erroneous attempt to define a virtual function;

that is, warn when there is a function with the same name as a virtual function in the base class, but with a type signature that doesn't match any virtual functions from the base class.

- Winline Warn if a function cannot be inlined, and either it was declared as inline, or else the `-finline-functions` option was given.
- Werror Treat warnings as errors; abort compilation after any warning.

DEBUGGING OPTIONS

GNU CC has various special options that are used for debugging either your program or gcc:

- g Produce debugging information in the operating system's native format (stabs, COFF, XCOFF, or DWARF). GDB (the GNU debugger) can work with this debugging information.
On most systems that use stabs format, -g enables use of extra debugging information that only GDB can use; this extra information makes debugging work better in GDB but will probably make other debuggers crash or refuse to read the program. If you want to control for certain whether to generate the extra information, use `-gstabs`, `-gstabs+`, `-gxcoff+`, `-gxcoff`, `-gdwarf+`, or `-gdwarf`. Unlike most other C compilers, GNU CC allows you to use -g with -O. The shortcuts taken by optimized code may occasionally produce surprising results: Some variables you declared may not exist at all; flow of control may briefly move where you did not expect it; some statements may not be executed because they compute constant results or their values were already at hand; some statements may execute in different places because they were moved out of loops.
Nevertheless, it proves possible to debug optimized output. This makes it reasonable to use the optimizer for programs that might have bugs.

The following options are useful when GNU CC is generated with the capability for more than one debugging format.

- ggdb Produce debugging information in the native format (if that is supported), including GDB extensions if at all possible.
- gstabs Produce debugging information in stabs format (if that is supported), without GDB extensions. This is the format used by DBX on most BSD systems.
- gstabs+ Produce debugging information in stabs format (if that is supported), using GNU extensions understood only by the GNU debugger (GDB). The use of these extensions is likely to make other debuggers crash or refuse to read the program.
- gcoff Produce debugging information in COFF format (if that is supported). This is the format used by SDB on most System V systems prior to System V Release 4.
- gxcoff Produce debugging information in XCOFF format (if that is supported). This is the format used by the DBX debugger on IBM RS/6000 systems.
- gxcoff+ Produce debugging information in XCOFF format (if that is supported), using GNU extensions understood only by the GNU debugger (GDB). The use of these extensions is likely to make other debuggers crash or refuse to read the program.
- gdwarf Produce debugging information in DWARF format (if that is supported). This is the format used by SDB on most System V Release 4 systems.
- gdwarf+ Produce debugging information in DWARF format (if that is supported), using GNU extensions understood only by the GNU debugger (GDB). The use of these extensions is likely to make other debuggers crash or refuse to read the program.
 - glevel
 - ggdblevel
 - gstabslevel
 - gcofflevel -gxcofflevel
- gdwarflevel Request debugging information and also use `level` to specify how much information. The default level is 2.
Level 1 produces minimal information, enough for making backtraces in parts of the program that you don't plan to debug. This includes descriptions of functions and external variables, but no information about local variables and no line numbers.

	Level 3 includes extra information, such as all the macro definitions present in the program. Some debuggers support macro expansion when you use <code>-g3</code> .
<code>-p</code>	Generate extra code to write profile information suitable for the analysis program <code>prof</code> .
<code>-pg</code>	Generate extra code to write profile information suitable for the analysis program <code>gprof</code> .
<code>-a</code>	Generate extra code to write profile information for basic blocks, which will record the number of times each basic block is executed. This data could be analyzed by a program like <code>tcov</code> . Note, however, that the format of the data is not what <code>tcov</code> expects. Eventually, GNU <code>gprof</code> should be extended to process this data.
<code>-dletters</code>	Says to make debugging dumps during compilation at times specified by <code>letters</code> . This is used for debugging the compiler. The filenames for most of the dumps are made by appending a word to the source filename (for example, <code>foo.c.rtl</code> or <code>foo.c.jump</code>).
<code>-dM</code>	Dump all macro definitions at the end of preprocessing, and write no output.
<code>-dN</code>	Dump all macro names, at the end of preprocessing.
<code>-dD</code>	Dump all macro definitions at the end of preprocessing, in addition to normal output.
<code>-dy</code>	Dump debugging information during parsing, to standard error.
<code>-dr</code>	Dump after RTL generation, to file <code>.rtl</code> .
<code>-dx</code>	Just generate RTL for a function instead of compiling it. Usually used with <code>r</code> .
<code>-dj</code>	Dump after first jump optimization, to file <code>.jump</code> .
<code>-ds</code>	Dump after CSE (including the jump optimization that sometimes follows CSE), to file <code>.cse</code> .
<code>-dL</code>	Dump after loop optimization, to file <code>.loop</code> .
<code>-dt</code>	Dump after the second CSE pass (including the jump optimization that sometimes follows CSE), to file <code>.cse2</code> .
<code>-df</code>	Dump after flow analysis, to file <code>.flow</code> .
<code>-dc</code>	Dump after instruction combination, to file <code>.combine</code> .
<code>-dS</code>	Dump after the first instruction scheduling pass, to file <code>.sched</code> .
<code>-dl</code>	Dump after local register allocation, to file <code>.lreg</code> .
<code>-dg</code>	Dump after global register allocation, to file <code>.greg</code> .
<code>-dR</code>	Dump after the second instruction scheduling pass, to file <code>.sched2</code> .
<code>-dJ</code>	Dump after last jump optimization, to file <code>.jump2</code> .
<code>-dd</code>	Dump after delayed branch scheduling, to file <code>.dbr</code> .
<code>-dk</code>	Dump after conversion from registers to stack, to file <code>.stack</code> .
<code>-da</code>	Produce all the dumps listed previously.
<code>-dm</code>	Print statistics on memory usage, at the end of the run, to standard error.
<code>-dp</code>	Annotate the assembler output with a comment indicating which pattern and alternative was used.
<code>-fpretend-float</code>	When running a cross-compiler, pretend that the target machine uses the same floating-point format as the host machine. This causes incorrect output of the actual floating constants, but the actual instruction sequence will probably be the same as GNU CC would make when running on the target machine.
<code>-save-temps</code>	Store the usual temporary intermediate files permanently; place them in the current directory and name them based on the source file. Thus, compiling <code>foo.c</code> with <code>-c -save-temps</code> would produce files <code>foo.cpp</code> and <code>foo.s</code> , as well as <code>foo.o</code> .
<code>-print-file-name=library</code>	Print the full absolute name of the library file <code>library</code> would be used when linking, and do not do anything else. With this option, GNU CC does not compile or link anything; it just prints the filename.
<code>-print-libgcc-file-name</code>	Same as <code>-print-file-name=libgcc.a</code> .
<code>-print-prog-name=program</code>	Like <code>-print-file-name</code> , but searches for a program such as <code>cpp</code> .

OPTIMIZATION OPTIONS

These options control various sorts of optimizations:

- `-O, -O1` Optimize. Optimizing compilation takes somewhat more time, and a lot more memory for a large function.
Without `-O`, the compiler's goal is to reduce the cost of compilation and to make debugging produce the expected results. Statements are independent: If you stop the program with a breakpoint between statements, you can then assign a new value to any variable or change the program counter to any other statement in the function and get exactly the results you would expect from the source code.
Without `-O`, only variables declared register are allocated in registers. The resulting compiled code is a little worse than produced by PCC without `-O`.
With `-O`, the compiler tries to reduce code size and execution time.
When you specify `-O`, the two options `-fthread-jumps` and `-fdefer-pop` are turned on. On machines that have delay slots, the `-fdelayed-branch` option is turned on. For those machines that can support debugging even without a frame pointer, the `-fomit-frame-pointer` option is turned on. On some machines other flags may also be turned on.
- `-O2` Optimize even more. Nearly all supported optimizations that do not involve a space-speed tradeoff are performed. Loop unrolling and function inlining are not done, for example. As compared to `-O`, this option increases both compilation time and the performance of the generated code.
- `-O3` Optimize yet more. This turns on everything `-O2` does, along with also turning on `-finline-functions`.
- `-O0` Do not optimize.
If you use multiple `-O` options, with or without level numbers, the last such option is the one that is effective.

Options of the form `-f flag` specify machine-independent flags. Most flags have both positive and negative forms; the negative form of `-ffoo` would be `-fno-foo`. The following list shows only one form—the one which is not the default. You can figure out the other form by either removing `no-` or adding it.

- `-ffloat-store` Do not store floating-point variables in registers. This prevents undesirable excess precision on machines such as the 68000 where the floating registers (of the 68881) keep more precision than a double is supposed to have.
For most programs, the excess precision does only good, but a few programs rely on the precise definition of IEEE floating point. Use `-ffloat-store` for such programs.
- `-fmemorize-lookups` Use heuristics to compile faster (C++ only). These heuristics are not enabled by default, since they are only effective for certain input files. Other input files compile more slowly.
The first time the compiler must build a call to a member function (or reference to a data member), it must (1) determine whether the class implements member functions of that name; (2) resolve which member function to call (which involves figuring out what sorts of type conversions need to be made); and (3) check the visibility of the member function to the caller. All of this adds up to slower compilation. Normally, the second time a call is made to that member function (or reference to that data member), it must go through the same lengthy process again. This means that code like this:

```
cout << "This " << p << "has"<< \ << " legs.\n"
```


makes six passes through all three steps. By using a software cache, a hit significantly reduces this cost. Unfortunately, using the cache introduces another layer of mechanisms which must be implemented, and so incurs its own overhead. `-fmemorize-lookups` enables the software cache.
Because access privileges (visibility) to members and member functions may differ from one function context to the next, g++ may need to flush the cache. With the `-fmemorize-lookups` flag, the cache is flushed after every function that is compiled. The `-fsave-memorized` flag

	enables the same software cache, but when the compiler determines that the context of the last function compiled would yield the same access privileges of the next function to compile, it preserves the cache. This is most helpful when defining many member functions for the same class: with the exception of member functions which are friends of other classes, each member function has exactly the same access privileges as every other, and the cache need not be flushed.
<code>-fno-default-inline</code>	Don't make member functions inline by default merely because they are defined inside the class scope (C++ only).
<code>-fno-defer-pop</code>	Always pop the arguments to each function call as soon as that function returns. For machines which must pop arguments after a function call, the compiler normally lets arguments accumulate on the stack for several function calls and pops them all at once.
<code>-fforce-mem</code>	Force memory operands to be copied into registers before doing arithmetic on them. This may produce better code by making all memory references potential common subexpressions. When they are not common subexpressions, instruction combination should eliminate the separate register-load. I am interested in hearing about the difference this makes.
<code>-fforce-addr</code>	Force memory address constants to be copied into registers before doing arithmetic on them. This may produce better code just as <code>-fforce-mem</code> may. I am interested in hearing about the difference this makes.
<code>-fomit-frame-pointer</code>	Don't keep the frame pointer in a register for functions that don't need one. This avoids the instructions to save, set up and restore frame pointers; it also makes an extra register available in many functions. It also makes debugging impossible on most machines. On some machines, such as the VAX, this flag has no effect because the standard calling sequence automatically handles the frame pointer and nothing is saved by pretending it doesn't exist. The machine-description macro <code>FRAME_POINTER_REQUIRED</code> controls whether a target machine supports this flag.
<code>-finline-functions</code>	Integrate all simple functions into their callers. The compiler heuristically decides which functions are simple enough to be worth integrating in this way. If all calls to a given function are integrated, and the function is declared static, then gcc normally does not output the function as assembler code in its own right.
<code>-fcaller-saves</code>	Enable values to be allocated in registers that will be clobbered by function calls, by emitting extra instructions to save and restore the registers around such calls. Such allocation is done only when it seems to result in better code than would otherwise be produced. This option is enabled by default on certain machines, usually those which have no call-preserved registers to use instead.
<code>-fkeep-inline-functions</code>	Even if all calls to a given function are integrated, and the function is declared static, nevertheless output a separate runtime callable version of the function.
<code>-fno-function-cse</code>	Do not put function addresses in registers; make each instruction that calls a constant function contain the function's address explicitly. This option results in less efficient code, but some strange hacks that alter the assembler output may be confused by the optimizations performed when this option is not used.
<code>-fno-peephole</code>	Disable any machine-specific peephole optimizations.
<code>-ffast-math</code>	This option allows gcc to violate some ANSI or IEEE specifications in the interest of optimizing code for speed. For example, it allows the compiler to assume arguments to the <code>sqrt</code> function are nonnegative numbers. This option should never be turned on by any <code>-O</code> option because it can result in incorrect output for programs which depend on an exact implementation of IEEE or ANSI rules/specifications for math functions.

The following options control specific optimizations. The `-O2` option turns on all of these optimizations except `-funroll-loops` and `-funroll-all-loops`.

The `-O` option usually turns on the `-fthread-jumps` and `-fdelayed-branch` options, but specific machines may change the default optimizations.

You can use the following flags in the rare cases when fine-tuning of optimizations to be performed is desired:

<code>-fstrength-reduce</code>	Perform the optimizations of loop strength reduction and elimination of iteration variables.
<code>-fthread-jumps</code>	Perform optimizations where we check to see if a jump branches to a location where another comparison subsumed by the first is found. If so, the first branch is redirected to either the destination of the second branch or a point immediately following it, depending on whether the condition is known to be true or false.
<code>-funroll-loops</code>	Perform the optimization of loop unrolling. This is only done for loops whose number of iterations can be determined at compile time or runtime.
<code>-funroll-all-loops</code>	Perform the optimization of loop unrolling. This is done for all loops. This usually makes programs run more slowly.
<code>-fcse-follow-jumps</code>	In common subexpression elimination, scan through jump instructions when the target of the jump is not reached by any other path. For example, when CSE encounters an <code>if</code> statement with an <code>else</code> clause, CSE will follow the jump when the condition tested is false.
<code>-fcse-skip-blocks</code>	This is similar to <code>-fcse-follow-jumps</code> , but causes CSE to follow jumps which conditionally skip over blocks. When CSE encounters a simple <code>if</code> statement with no <code>else</code> clause, <code>-fcse-skip-blocks</code> causes CSE to follow the jump around the body of the <code>if</code> .
<code>-frerun-cse-after-loop</code>	Rerun common subexpression elimination after loop optimizations has been performed.
<code>-felide-constructors</code>	Elide constructors when this seems plausible (C++ only). With this flag, GNU C++ initializes <code>y</code> directly from the call to <code>foo</code> without going through a temporary in the following code: <pre>A foo (); A y = foo ();</pre> Without this option, GNU C++ first initializes <code>y</code> by calling the appropriate constructor for type <code>A</code>; then assigns the result of <code>foo</code> to a temporary; and, finally, replaces the initial value of <code>y</code> with the temporary. The default behavior (<code>-fno-elide-constructors</code>) is specified by the draft ANSI C++ standard. If your program's constructors have side effects, using <code>-felide-constructors</code> can make your program act differently, since some constructor calls may be omitted.
<code>-fexpensive-optimizations</code>	Perform a number of minor optimizations that are relatively expensive.
<code>-fdelayed-branch</code>	If supported for the target machine, attempt to reorder instructions to exploit instruction slots available after delayed branch instructions.
<code>-fschedule-insns</code>	If supported for the target machine, attempt to reorder instructions to eliminate execution stalls due to required data being unavailable. This helps machines that have slow floating point or memory load instructions by allowing other instructions to be issued until the result of the load or floating point instruction is required.
<code>-fschedule-insns2</code>	Similar to <code>-fschedule-insns</code> , but requests an additional pass of instruction scheduling after register allocation has been done. This is especially useful on machines with a relatively small number of registers and where memory load instructions take more than one cycle.

TARGET OPTIONS

By default, GNU CC compiles code for the same type of machine that you are using.

However, it can also be installed as a cross-compiler, to compile for some other type of machine. In fact, several different configurations of GNU CC, for different target machines, can be installed side by side. Then you specify which one to use with the `-b` option.

In addition, older and newer versions of GNU CC can be installed side by side. One of them (probably the newest) will be the default, but you may sometimes want to use another.

<code>-b machine</code>	The argument <code>machine</code> specifies the target machine for compilation. This is useful when you have installed GNU CC as a cross-compiler. The value to use for <code>machine</code> is the same as was specified as the machine type when configuring GNU CC as a cross-compiler. For example, if a cross-compiler was configured with <code>configure</code>

i386v, meaning to compile for an 80386 running System V, then you would specify `-b i386v` to run that cross compiler.

When you do not specify `-b`, it normally means to compile for the same type of machine that you are using.

`-V version`

The argument `version` specifies which version of GNU CC to run. This is useful when multiple versions are installed. For example, `version` might be `2.0`, meaning to run GNU CC version 2.0.

The default version, when you do not specify `-v`, is controlled by the way GNU CC is installed. Normally, it will be a version that is recommended for general use.

MACHINE-DEPENDENT OPTIONS

Each of the target machine types can have its own special options, starting with `-m`, to choose among various hardware models or configurations—for example, 68010 versus 68020, floating coprocessor or none. A single installed version of the compiler can compile for any model or configuration, according to the options specified.

Some configurations of the compiler also support additional special options, usually for command-line compatibility with other compilers on the same platform.

These are the `-m` options defined for the 68000 series:

<code>-m68000</code>	Generate output for a 68000. This is the default when the compiler is configured for 68000-based systems.
<code>-mc68000</code>	
<code>-m68020</code>	Generate output for a 68020 (rather than a 68000). This is the default when the compiler is configured for 68020-based systems.
<code>-mc68020</code>	
<code>-m68881</code>	Generate output containing 68881 instructions for floating point. This is the default for most 68020-based systems unless <code>-nfp</code> was specified when the compiler was configured.
<code>-m68030</code>	Generate output for a 68030. This is the default when the compiler is configured for 68030-based systems.
<code>-m68040</code>	Generate output for a 68040. This is the default when the compiler is configured for 68040-based systems.
<code>-m68020-40</code>	Generate output for a 68040, without using any of the new instructions. This results in code which can run relatively efficiently on either a 68020/68881 or a 68030 or a 68040.
<code>-mfpa</code>	Generate output containing Sun FPA instructions for floating point.
<code>-msoft-float</code>	Generate output containing library calls for floating point.

WARNING

The requisite libraries are not part of GNU CC. Normally, the facilities of the machine's usual C compiler are used, but this can't be done directly in cross-compilation. You must make your own arrangements to provide suitable library functions for cross-compilation.

<code>-mshort</code>	Consider type <code>int</code> to be 16 bits wide, like <code>short int</code> .
<code>-mnobitfield</code>	Do not use the bit-field instructions. <code>-m68000</code> implies <code>-mnobitfield</code> .
<code>-mbitfield</code>	Do use the bit-field instructions. <code>-m68020</code> implies <code>-mbitfield</code> . This is the default if you use the unmodified sources.
<code>-mrtd</code>	Use a different function-calling convention, in which functions that take a fixed number of arguments return with the <code>rtd</code> instruction, which pops their arguments while returning. This saves one instruction in the caller since there is no need to pop the arguments there. This calling convention is incompatible with the one normally used on UNIX, so you cannot use it if you need to call libraries compiled with the UNIX compiler.

Also, you must provide function prototypes for all functions that take variable numbers of arguments (including `printf`); otherwise, incorrect code will be generated for calls to those functions.

In addition, seriously incorrect code will result if you call a function with too many arguments. (Normally, extra arguments are harmlessly ignored.)

The `rtd` instruction is supported by the 68010 and 68020 processors, but not by the 68000.

These `-m` options are defined for the VAX:

<code>-munix</code>	Do not output certain jump instructions (<code>aob1eq</code> and so on) that the UNIX assembler for the VAX cannot handle across long ranges.
<code>-mgnu</code>	Do output those jump instructions, on the assumption that you will assemble with the GNU assembler.
<code>-mg</code>	Output code for g-format floating-point numbers instead of d-format.

These `-m` switches are supported on the SPARC:

<code>-mfpu</code>	Generate output containing floating-point instructions. This is the default.
<code>-mhard-float</code>	
<code>-mno-fpu</code>	Generate output containing library calls for floating point.
<code>-msoft-float</code>	

WARNING

There is no GNU floating-point library for SPARC. Normally, the facilities of the machine's usual C compiler are used, but this cannot be done directly in cross-compilation. You must make your own arrangements to provide suitable library functions for cross-compilation.

<code>-msoft-float</code>	Changes the calling convention in the output file; therefore, it is only useful if you compile <i>all</i> of a program with this option.
<code>-mno-epilogue</code> <code>-mepilogue</code>	With <code>-mepilogue</code> (the default), the compiler always emits code for function exit at the end of each function. Any function exit in the middle of the function (such as a return statement in C) will generate a jump to the exit code at the end of the function. With <code>-mno-epilogue</code> , the compiler tries to emit exit code inline at every function exit.
<code>-mno-v8</code> <code>-mv8</code> <code>msparclite</code>	These three options select variations on the SPARC architecture. By default (unless specifically configured for the Fujitsu SPARClite), <code>gcc</code> generates code for the v7 variant of the SPARC architecture. <code>-mv8</code> will give you SPARC v8 code. The only difference from v7 code is that the compiler emits the integer multiply and integer divide instructions that exist in SPARC v8 but not in SPARC v7. <code>-msparclite</code> will give you SPARClite code. This adds the integer multiply, integer divide step and scan (<code>ffs</code>) instructions that exist in SPARClite but not in SPARC v7.
<code>-mcyppress</code>	These two options select the processor for which the code is optimized.
<code>-msupersparc</code>	With <code>-mcyppress</code> (the default), the compiler optimizes code for the Cypress CY7C602 chip, as used in the SparcStation and SparcServer 3xx series. This is also appropriate for the older SparcStation 1, 2, IPX, and so on. With <code>-msupersparc</code> the compiler optimizes code for the SuperSparc cpu, as used in the SparcStation 10, 1000, and 2000 series. This flag also enables use of the full SPARC v8 instruction set.

These `-m` options are defined for the Convex:

<code>-mc1</code>	Generate output for a C1. This is the default when the compiler is configured for a C1.
<code>-mc2</code>	Generate output for a C2. This is the default when the compiler is configured for a C2.

<code>-margcount</code>	Generate code which puts an argument count in the word preceding each argument list. Some nonportable Convex and VAX programs need this word. (Debuggers don't, except for functions with variable-length argument lists; this information is in the symbol table.)
<code>-mnoargcount</code>	Omit the argument count word. This is the default if you use the unmodified sources.

These `-m` options are defined for the AMD Am29000:

<code>-mdw</code>	Generate code that assumes the DW bit is set, that is, that byte and half-word operations are directly supported by the hardware. This is the default.
<code>-mnodw</code>	Generate code that assumes the DW bit is not set.
<code>-mbw</code>	Generate code that assumes the system supports byte and halfword write operations. This is the default.
<code>-mnbw</code>	Generate code that assumes the systems does not support byte and halfword write operations. This implies <code>-mnodw</code> .
<code>-msmall</code>	Use a small memory model that assumes that all function addresses are either within a single 256KB segment or at an absolute address of less than 256K. This allows the <code>call</code> instruction to be used instead of a <code>const</code> , <code>consth</code> , <code>calli</code> sequence.
<code>-mlarge</code>	Do not assume that the <code>call</code> instruction can be used; this is the default.
<code>-m29050</code>	Generate code for the Am29050.
<code>-m29000</code>	Generate code for the Am29000. This is the default.
<code>-mkernel-registers</code>	Generate references to registers <code>gr64</code> – <code>gr95</code> instead of <code>gr96</code> – <code>gr127</code> . This option can be used when compiling kernel code that wants a set of global registers disjoint from that used by user-mode code. Note that when this option is used, register names in <code>-f</code> flags must use the normal, user-mode, names.
<code>-muser-registers</code>	Use the normal set of global registers, <code>gr96</code> – <code>gr127</code> . This is the default.
<code>-mstack-check</code>	Insert a call to <code>msp_check</code> after each stack adjustment. This is often used for kernel code.

These `-m` options are defined for Motorola 88K architectures:

<code>-m88000</code>	Generate code that works well on both the m88100 and the m88110.
<code>-m88100</code>	Generate code that works best for the m88100, but that also runs on the m88110.
<code>-m88110</code>	Generate code that works best for the m88110, and may not run on the m88100.
<code>-midentify-revision</code>	Include an <code>ident</code> directive in the assembler output recording the source filename, compiler name and version, timestamp, and compilation flags used.
<code>-mno-underscores</code>	In assembler output, emit symbol names without adding an underscore character at the beginning of each name. The default is to use an underscore as prefix on each name.
<code>-mcheck-zero-division</code> <code>-mno-check-zero-division</code>	Early models of the 88K architecture had problems with division by zero; in particular, many of them didn't trap. Use these options to avoid including (or to include explicitly) additional code to detect division by zero and signal an exception. All gcc configurations for the 88K use <code>-mcheck-zero-division</code> by default.
<code>-mocs-debug-info</code> <code>-mno-ocs-debug-info</code>	Include (or omit) additional debugging information (about registers used in each stack frame) as specified in the 88Open Object Compatibility Standard, OCS. This extra information is not needed by GDB. The default for DG/UX, SVr4, and Delta 88 SVr3.2 is to include this information; other 88K configurations omit this information by default.
<code>-mocs-frame-position</code> <code>-mno-ocs-frame-position</code>	Force (or do not require) register values to be stored in a particular place in stack frames, as specified in OCS. The DG/UX, Delta88 SVr3.2, and BCS configurations use <code>-mocs-frame-position</code> ; other 88K configurations have the default <code>-mno-ocs-frame-position</code> .
<code>-moptimize-arg-area</code> <code>-mno-optimize-arg-area</code>	Control how to store function arguments in stack frames. <code>-moptimize-arg-area</code> saves space, but may break some debuggers (not GDB). <code>-mno-optimize-arg-area</code> conforms better to standards. By default gcc does not optimize the argument area.

<code>-mshort-data-num</code>	Generate smaller data references by making them relative to <code>r0</code> , which allows loading a value using a single instruction (rather than the usual two). You control which data references are affected by specifying <code>num</code> with this option. For example, if you specify <code>-mshort-data-512</code> , then the data references affected are those involving displacements of less than 512 bytes. <code>-mshort-data-num</code> is not effective for <code>num</code> greater than 64K.
<code>-mserialize-volatile</code>	Do, or do not, generate code to guarantee sequential consistency of volatile memory references.
<code>-mno-serialize-volatile</code>	GNU CC always guarantees consistency by default, for the preferred processor submodel. How this is done depends on the submodel. The m88100 processor does not reorder memory references and so always provides sequential consistency. If you use <code>-m88100</code> , GNU CC does not generate any special instructions for sequential consistency. The order of memory references made by the m88110 processor does not always match the order of the instructions requesting those references. In particular, a load instruction may execute before a preceding store instruction. Such reordering violates sequential consistency of volatile memory references, when there are multiple processors. When you use <code>-m88000</code> or <code>-m88110</code> , GNU CC generates special instructions when appropriate, to force execution in the proper order. The extra code generated to guarantee consistency may affect the performance of your application. If you know that you can safely forgo this guarantee, you may use the option <code>-mno-serialize-volatile</code> . If you use the <code>-m88100</code> option but require sequential consistency when running on the m88110 processor, you should use <code>-mserialize-volatile</code> .
<code>-msvr4, -msvr3</code>	Turn on (<code>-msvr4</code>) or off (<code>-msvr3</code>) compiler extensions related to System V release 4 (SVr4). This controls the following: Which variant of the assembler syntax to emit (which you can select independently using <code>-mversion-03.00</code>). <code>-msvr4</code> makes the C preprocessor recognize <code>#pragma weak</code> . <code>-msvr4</code> makes gcc issue additional declaration directives used in SVr4. <code>-msvr3</code> is the default for all m88K configurations except the SVr4 configuration.
<code>-mtrap-large-shift</code>	Include code to detect bit-shifts of more than 31 bits; respectively, trap such shifts or emit code to handle them properly. By default, gcc makes no special provision for large bit shifts.
<code>-mhandle-large-shift</code>	
<code>-muse-div-instruction</code>	Very early models of the 88K architecture didn't have a divide instruction, so gcc avoids that instruction by default. Use this option to specify that it's safe to use the divide instruction.
<code>-mversion-03.00</code>	In the DG/UX configuration, there are two flavors of SVr4. This option modifies <code>-msvr4</code> to select whether the hybrid-COFF or real-ELF flavor is used. All other configurations ignore this option.
<code>-mwarn-passed-structs</code>	Warn when a function passes a struct as an argument or result. Structure-passing conventions have changed during the evolution of the C language, and are often the source of portability problems. By default, gcc issues no such warning.

These options are defined for the IBM RS6000:

<code>-mfp-in-toc</code>	Control whether or not floating-point constants go in the table of contents (TOC), a table of all global variable and function addresses. By default gcc puts floating-point constants there; if the TOC overflows, <code>-mno-fp-in-toc</code> will reduce the size of the TOC, which may avoid the overflow.
<code>-mno-fp-in-toc</code>	

These `-m` options are defined for the IBM RT PC:

<code>-min-line-mul</code>	Use an inline code sequence for integer multiplies. This is the default.
<code>-mcall-lib-mul</code>	Call <code>lmul\$\$</code> for integer multiples.
<code>-mfull-fp-blocks</code>	Generate full-size floating-point data blocks, including the minimum amount of scratch space recommended by IBM. This is the default.

<code>-mminimum-fp-blocks</code>	Do not include extra scratch space in floating-point data blocks. This results in smaller code, but slower execution, since scratch space must be allocated dynamically.
<code>-mfp-arg-in-fpregs</code>	Use a calling sequence incompatible with the IBM calling convention in which floating-point arguments are passed in floating-point registers. Note that <code>varargs.h</code> and <code>stdargs.h</code> will not work with floating-point operands if this option is specified.
<code>-mfp-arg-in-gregs</code>	Use the normal calling convention for floating-point arguments. This is the default.
<code>-mhc-struct-return</code>	Return structures of more than one word in memory, rather than in a register. This provides compatibility with the MetaWare HighC (hc) compiler. Use <code>-fpcc-struct-return</code> for compatibility with the Portable C Compiler (PCC).
<code>-mnohc-struct-return</code>	Return some structures of more than one word in registers, when convenient. This is the default. For compatibility with the IBM-supplied compilers, use either <code>-fpcc-struct-return</code> or <code>-mhc-struct-return</code> .

These `-m` options are defined for the MIPS family of computers:

<code>-mcpu=cpu-type</code>	Assume the defaults for the machine type <code>cpu-type</code> when scheduling instructions. The default <code>cpu-type</code> is <code>default</code> , which picks the longest cycles times for any of the machines, in order that the code run at reasonable rates on all MIPS CPUs. Other choices for <code>cpu-type</code> are <code>r2000</code> , <code>r3000</code> , <code>r4000</code> , and <code>r6000</code> . While picking a specific <code>cpu-type</code> will schedule things appropriately for that particular chip, the compiler will not generate any code that does not meet level 1 of the MIPS ISA (instruction set architecture) without the <code>-mips2</code> or <code>-mips3</code> switches being used.
<code>-mips2</code>	Issue instructions from level 2 of the MIPS ISA (branch likely, square root instructions). The <code>-mcpu=r4000</code> or <code>-mcpu=r6000</code> switch must be used in conjunction with <code>-mips2</code> .
<code>-mips3</code>	Issue instructions from level 3 of the MIPS ISA (64-bit instructions). The <code>-mcpu=r4000</code> switch must be used in conjunction with <code>-mips2</code> .
<code>-mint64</code> , <code>-mlong64</code> <code>-mlonglong128</code>	These options don't work at present.
<code>-mmips-as</code>	Generate code for the MIPS assembler, and invoke <code>mips-tfile</code> to add normal debug information. This is the default for all platforms except for the OSF/1 reference platform, using the OSF/rose object format. If any of the <code>-ggdb</code> , <code>-gstabs</code> , or <code>-gstabs+</code> switches are used, the <code>mips-tfile</code> program will encapsulate the stabs within MIPS ECOFF.
<code>-mgas</code>	Generate code for the GNU assembler. This is the default on the OSF/1 reference platform, using the OSF/rose object format.
<code>-mrnames</code> , <code>-mno-rnames</code>	The <code>-mrnames</code> switch says to output code using the MIPS software names for the registers, instead of the hardware names (for example, <code>a0</code> instead of <code>\$4</code>). The GNU assembler does not support the <code>-mrnames</code> switch, and the MIPS assembler will be instructed to run the MIPS C preprocessor over the source file. The <code>-mno-rnames</code> switch is default.
<code>-mgpopt</code> , <code>-mno-gpopt</code>	The <code>-mgpopt</code> switch says to write all of the data declarations before the instructions in the text section, to all the MIPS assembler to generate one-word memory references instead of using two words for short global or static data items. This is on by default if optimization is selected.
<code>-mstats</code> , <code>-mno-stats</code>	For each nonlinear function processed, the <code>-mstats</code> switch causes the compiler to emit one line to the standard error file to print statistics about the program (number of registers saved, stack size, and so on).
<code>-mmemcpy</code> , <code>-mno-memcpy</code>	The <code>-mmemcpy</code> switch makes all block moves call the appropriate string function (<code>memcpy</code> or <code>bcopy</code>) instead of possibly generating inline code.
<code>-mmips-tfile</code> <code>-mno-mips-tfile</code>	The <code>-mno-mips-tfile</code> switch causes the compiler to not post-process the object file with the <code>mips-tfile</code> program, after the MIPS assembler has generated it to add debug support. If <code>mips-tfile</code> is not run, then no local variables will be available to the debugger. In addition, <code>stage2</code> and <code>stage3</code> objects will have the temporary filenames passed to the assembler embedded in the object file, which means the objects will not compare the same.
<code>-msoft-float</code>	Generate output containing library calls for floating point.

WARNING

The requisite libraries are not part of GNU CC. Normally, the facilities of the machine's usual C compiler are used, but this can't be done directly in cross-compilation. You must make your own arrangements to provide suitable library functions for cross-compilation.

<code>-mhard-float</code>	Generate output containing floating point instructions. This is the default if you use the unmodified sources.
<code>-mfp64</code>	Assume that the FR bit in the status word is on, and that there are 32 64-bit floating-point registers, instead of 32 32-bit floating-point registers. You must also specify the <code>-mcpu=r4000</code> and <code>-mips3</code> switches.
<code>-mfp32</code>	Assume that there are 32 32-bit floating-point registers. This is the default.
<code>-mabicalls</code>	Emit (or do not emit) the <code>.abicalls</code> , <code>.cpload</code> , and <code>.cprestore</code> pseudo operations that some System V.4 ports use for position-independent code.
<code>-mno-abicalls</code>	
<code>-mhalf-pic</code>	The <code>-mhalf-pic</code> switch says to put pointers to extern references into the data section and load them up, rather than put the references in the text section. This option does not work at present.
<code>-mno-half-pic</code>	
<code>-Gnum</code>	Put global and static items less than or equal to <code>num</code> bytes into the small data or bss sections instead of the normal data or bss section. This allows the assembler to emit one-word memory reference instructions based on the global pointer (<code>gp</code> or <code>\$28</code>), instead of the normal two words used. By default, <code>num</code> is 8 when the MIPS assembler is used, and 0 when the GNU assembler is used. The <code>-Gnum</code> switch is also passed to the assembler and linker. All modules should be compiled with the same <code>-Gnum</code> value.
<code>-nocpp</code>	Tell the MIPS assembler to not run its preprocessor over user assembler files (with an <code>.s</code> suffix) when assembling them.

These `-m` options are defined for the Intel 80386 family of computers:

<code>-m486</code> , <code>-mno-486</code>	Control whether or not code is optimized for a 486 instead of a 386. Code generated for a 486 will run on a 386 and vice versa.
<code>-msoft-float</code>	Generate output containing library calls for floating point.

WARNING

The requisite libraries are not part of GNU CC. Normally, the facilities of the machine's usual C compiler are used, but this can't be done directly in cross-compilation. You must make your own arrangements to provide suitable library functions for cross-compilation.

<code>-mno-fp-ret-in-387</code>	On machines where a function returns floating point results in the 80387 register stack, some floating-point opcodes may be emitted even if <code>-msoft-float</code> is used. Do not use the FPU registers for return values of functions. The usual calling convention has functions return values of types float and double in an FPU register, even if there is no FPU. The idea is that the operating system should emulate an FPU. The option <code>-mno-fp-ret-in-387</code> causes such values to be returned in ordinary CPU registers instead.

These `-m` options are defined for the HPPA family of computers:

<code>-mpa-risc-1.0</code>	Generate code for a PA 1.0 processor.
<code>-mpa-risc-1.1</code>	Generate code for a PA 1.1 processor.

<code>-mkernel</code>	Generate code which is suitable for use in kernels. Specifically, avoid <code>add</code> instructions in which one of the arguments is the <code>DP</code> register; generate <code>addl</code> instructions instead. This avoids a rather serious bug in the HP-UX linker.
<code>-mshared-libs</code>	Generate code that can be linked against HP-UX shared libraries. This option is not fully functioning yet, and is not on by default for any PA target. Using this option can cause incorrect code to be generated by the compiler.
<code>-mno-shared-libs</code>	Don't generate code that will be linked against shared libraries. This is the default for all PA targets.
<code>-mlong-calls</code>	Generate code which allows calls to functions greater than 256K away from the caller when the caller and callee are in the same source file. Do not turn this option on unless code refuses to link with branch out of range errors from the linker.
<code>-mdisable-fpregs</code>	Prevent floating-point registers from being used in any manner. This is necessary for compiling kernels that perform lazy context switching of floating-point registers. If you use this option and attempt to perform floating-point operations, the compiler will abort.
<code>-mdisable-indexing</code>	Prevent the compiler from using indexing address modes. This avoids some rather obscure problems when compiling MIG-generated code under MACH.
<code>-mtrailing-colon</code>	Add a colon to the end of label definitions (for ELF assemblers).

These `-m` options are defined for the Intel 80960 family of computers:

<code>-mcpu-type</code>	Assume the defaults for the machine type <code>cpu-type</code> for instruction and addressing-mode availability and alignment. The default <code>cpu-type</code> is <code>kb</code> ; other choices are <code>ka</code> , <code>mc</code> , <code>ca</code> , <code>cf</code> , <code>sa</code> , and <code>sb</code> .
<code>-mnumerics</code>	The <code>-mnumerics</code> option indicates that the processor does support floating-point instructions.
<code>-msoft-float</code>	The <code>-msoft-float</code> option indicates that floating-point support should not be assumed.
<code>-mleaf-procedures</code>	Do (or do not) attempt to alter leaf procedures to be callable with the <code>bal</code> instruction as well as <code>call</code> . This will result in more efficient code for explicit calls when the <code>bal</code> instruction can be substituted by the assembler or linker, but less efficient code in other cases, such as calls via function pointers, or using a linker that doesn't support this optimization.
<code>-mno-leaf-procedures</code>	
<code>-mtail-call</code>	Do (or do not) make additional attempts (beyond those of the machine-independent portions of the compiler) to optimize tail-recursive calls into branches. You may not want to do this because the detection of cases where this is not valid is not totally complete. The default is <code>-mno-tail-call</code> .
<code>-mno-tail-call</code>	
<code>-mcomplex-addr</code>	Assume (or do not assume) that the use of a complex addressing mode is a win on this implementation of the i960. Complex addressing modes may not be worthwhile on the K-series, but they definitely are on the C-series. The default is currently <code>-mcomplex-addr</code> for all processors except the CB and CC.
<code>-mno-complex-addr</code>	
<code>-mcode-align</code>	Align code to 8-byte boundaries for faster fetching (or don't bother). Currently turned on by default for C-series implementations only.
<code>-mno-code-align</code>	
<code>-mic-compat</code>	Enable compatibility with iC960 v2.0 or v3.0.
<code>-mic2.0-compat</code>	
<code>-mic3.0-compat</code>	
<code>-masm-compat</code>	Enable compatibility with the iC960 assembler.
<code>-mintel-asm</code>	
<code>-mstrict-align</code>	Do not permit (do permit) unaligned accesses.
<code>-mno-strict-align</code>	
<code>-mold-align</code>	Enable structure-alignment compatibility with Intel's gcc release version 1.3 (based on gcc 1.37). Currently this is buggy in that <code>#pragma align 1</code> is always assumed as well, and cannot be turned off.

These `-m` options are defined for the DEC Alpha implementations:

<code>-mno-soft-float</code> <code>-msoft-float</code>	Use (do not use) the hardware floating-point instructions for floating-point operations. When <code>-msoft-float</code> is specified, functions in <code>libgcc1.c</code> will be used to perform floating-point operations. Unless they are replaced by routines that emulate the floating-point operations, or compiled in such a way as to call such emulations routines, these routines will issue floating-point operations. If you are compiling for an Alpha without floating-point operations, you must ensure that the library is built so as not to call them. Note that Alpha implementations without floating-point operations are required to have floating-point registers.
<code>-mfp-reg</code> , <code>-mno-fp-regs</code>	Generate code that uses (does not use) the floating-point register set. <code>-mno-fp-regs</code> implies <code>-msoft-float</code> . If the floating-point register set is not used, floating-point operands are passed in integer registers as if they were integers and floating-point results are passed in <code>\$0</code> instead of <code>\$f0</code> . This is a nonstandard calling sequence, so any function with a floating-point argument or return value called by code compiled with <code>-mno-fp-regs</code> must also be compiled with that option. A typical use of this option is building a kernel that does not use, and hence need not save and restore, any floating-point registers.

These additional options are available on System V Release 4 for compatibility with other compilers on those systems:

<code>-G</code>	On SVr4 systems, <code>gcc</code> accepts the option <code>-G</code> (and passes it to the system linker), for compatibility with other compilers. However, we suggest you use <code>-symbolic</code> or <code>-shared</code> as appropriate, instead of supplying linker options on the <code>gcc</code> command line.
<code>-Qy</code>	Identify the versions of each tool used by the compiler, in an <code>.ident</code> assembler directive in the output.
<code>-Qn</code>	Refrain from adding <code>.ident</code> directives to the output file (this is the default).
<code>-YP,dirs</code>	Search the directories <code>dirs</code> , and no others, for libraries specified with <code>-l</code> . You can separate directory entries in <code>dirs</code> from one another with colons.
<code>-Ym,dir</code>	Look in the directory <code>dir</code> to find the M4 preprocessor. The assembler uses this option.

CODE GENERATION OPTIONS

These machine-independent options control the interface conventions used in code generation.

Most of them begin with `-f`. These options have both positive and negative forms; the negative form of `-ffoo` would be `-fno-foo`. In the following table, only one of the forms is listed—the one which is not the default. You can figure out the other form by either removing `no-` or adding it.

<code>-fnonnull-objects</code>	Assume that objects reached through references are not null (C++ only). Normally, GNU C++ makes conservative assumptions about objects reached through references. For example, the compiler must check that <code>a</code> is not null in code like the following: <pre>obj &a = g (); a.f (2);</pre> Checking that references of this sort have nonnull values requires extra code, however, and it is unnecessary for many programs. You can use <code>-fnonnull-objects</code> to omit the checks for null, if your program doesn't require checking.
<code>-fpcc-struct-return</code>	Use the same convention for returning struct and union values that is used by the usual C compiler on your system. This convention is less efficient for small structures, and on many machines it fails to be reentrant; but it has the advantage of allowing intercallability between <code>gcc</code> -compiled code and <code>pcc</code> -compiled code.
<code>-freg-struct-return</code>	Use the convention that struct and union values are returned in registers when possible. This is more efficient for small structures than <code>-fpcc-struct-return</code> . If you specify neither <code>-fpcc-struct-return</code> nor <code>-freg-struct-return</code> , GNU CC defaults to whichever convention is standard for the target. If there is no standard convention, GNU CC defaults to <code>-fpcc-struct-return</code> .

<code>-fshort-enums</code>	Allocate to an <code>enum</code> type only as many bytes as it needs for the declared range of possible values. Specifically, the <code>enum</code> type will be equivalent to the smallest integer type that has enough room.
<code>-fshort-double</code>	Use the same size for <code>double</code> as for <code>float</code> .
<code>-fshared-data</code>	Requests that the data and non-const variables of this compilation be shared data rather than private data. The distinction makes sense only on certain operating systems, where shared data is shared between processes running the same program, while private data exists in one copy per process.
<code>-fno-common</code>	Allocate even uninitialized global variables in the bss section of the object file, rather than generating them as common blocks. This has the effect that if the same variable is declared (without <code>extern</code>) in two different compilations, you will get an error when you link them. The only reason this might be useful is if you want to verify that the program will work on other systems which always work this way.
<code>-fno-ident</code>	Ignore the <code>#ident</code> directive.
<code>-fno-gnu-linker</code>	Do not output global initializations (such as C++ constructors and destructors) in the form used by the GNU linker (on systems where the GNU linker is the standard method of handling them). Use this option when you want to use a non-GNU linker, which also requires using the <code>collect2</code> program to make sure the system linker includes constructors and destructors. (<code>collect2</code> is included in the GNU CC distribution.) For systems that <i>must</i> use <code>collect2</code> , the compiler driver <code>gcc</code> is configured to do this automatically.
<code>-finhibit-size-directive</code>	Don't output a <code>.size</code> assembler directive, or anything else that would cause trouble if the function is split in the middle, and the two halves are placed at locations far apart in memory. This option is used when compiling <code>crtstuff.c</code> ; you should not need to use it for anything else.
<code>-fverbose-asm</code>	Put extra commentary information in the generated assembly code to make it more readable. This option is generally only of use to those who actually need to read the generated assembly code (perhaps while debugging the compiler itself).
<code>-fvolatile</code>	Consider all memory references through pointers to be volatile.
<code>-fvolatile-global</code>	Consider all memory references to <code>extern</code> and global data items to be volatile.
<code>-fpic</code>	If supported for the target machines, generate position-independent code, suitable for use in a shared library.
<code>-fPIC</code>	If supported for the target machine, emit position-independent code, suitable for dynamic linking, even if branches need large displacements.
<code>-ffixed-reg</code>	Treat the register named <code>reg</code> as a fixed register; generated code should never refer to it (except perhaps as a stack pointer, frame pointer, or in some other fixed role). <code>reg</code> must be the name of a register. The register names accepted are machine-specific and are defined in the <code>REGISTER_NAMES</code> macro in the machine description macro file. This flag does not have a negative form, because it specifies a three-way choice.
<code>-fcall-used-reg</code>	Treat the register named <code>reg</code> as an allocable register that is clobbered by function calls. It may be allocated for temporaries or variables that do not live across a call. Functions compiled this way will not save and restore the register <code>reg</code> . Use of this flag for a register that has a fixed pervasive role in the machine's execution model, such as the stack pointer or frame pointer, will produce disastrous results. This flag does not have a negative form, because it specifies a three-way choice.
<code>-fcall-saved-reg</code>	Treat the register named <code>reg</code> as an allocable register saved by functions. It may be allocated even for temporaries or variables that live across a call. Functions compiled this way will save and restore the register <code>reg</code> if they use it. Use of this flag for a register that has a fixed pervasive role in the machine's execution model, such as the stack pointer or frame pointer, will produce disastrous results. A different sort of disaster will result from the use of this flag for a register in which function values may be returned. This flag does not have a negative form, because it specifies a three-way choice.

PRAGMAS

Two `#pragma` directives are supported for GNU C++ to permit using the same header file for two purposes: as a definition of interfaces to a given object class, and as the full definition of the contents of that object class.

<code>#pragma interface</code>	(C++ only.) Use this directive in header files that define object classes, to save space in most of the object files that use those classes. Normally, local copies of certain information (backup copies of inline member functions, debugging information, and the internal tables that implement virtual functions) must be kept in each object file that includes class definitions. You can use this pragma to avoid such duplication. When a header file containing <code>#pragma interface</code> is included in a compilation, this auxiliary information will not be generated (unless the main input source file itself uses <code>#pragma implementation</code>). Instead, the object files will contain references to be resolved at link time.
<code>#pragma implementation</code> <code>#pragma implementation</code> <code>"objects.h"</code>	(C++ only.) Use this pragma in a main input file, when you want full output from included header files to be generated (and made globally visible). The included header file, in turn, should use <code>#pragma interface</code> . Backup copies of inline member functions, debugging information, and the internal tables used to implement virtual functions are all generated in implementation files.

If you use `#pragma implementation` with no argument, it applies to an include file with the same basename as your source file; for example, in `allclass.cc`, `#pragma implementation` by itself is equivalent to `#pragma implementation "allclass.h"`. Use the string argument if you want a single implementation file to include code from multiple header files.

There is no way to split up the contents of a single header file into multiple implementation files.

FILES

<code>file.c</code>	C source file
<code>file.h</code>	C header (preprocessor) file
<code>file.i</code>	Preprocessed C source file
<code>file.C</code>	C++ source file
<code>file.cc</code>	C++ source file
<code>file.cxx</code>	C++ source file
<code>file.m</code>	Objective-C source file
<code>file.s</code>	Assembly language file
<code>file.o</code>	Object file
<code>a.out</code>	Link edited output
<code>TMPDIR/cc</code>	Temporary files
<code>LIBDIR/cpp</code>	Preprocessor
<code>LIBDIR/cc1</code>	Compiler for C
<code>LIBDIR/cc1plus</code>	Compiler for C++
<code>LIBDIR/collect</code>	Linker front end needed on some machines
<code>LIBDIR/libgcc.a</code>	gcc subroutine library
<code>/lib/crt[01n].o</code>	Startup routine
<code>LIBDIR/ccrt0</code>	Additional startup routine for C++
<code>/lib/libc.a</code>	Standard C library; see <code>intro(3)</code>
<code>/usr/include</code>	Standard directory for <code>#include</code> files
<code>LIBDIR/include</code>	Standard gcc directory for <code>#include</code> files
<code>LIBDIR/g++-include</code>	Additional g++ directory for <code>#include</code>

`LIBDIR` is usually `/usr/local/lib/machine/version`.

`TMPDIR` comes from the environment variable `TMPDIR` (default `/usr/tmp` if available; otherwise, `/tmp`).

SEE ALSO

cpp(1), as(1), ld(1), gdb(1), adb(1), dbx(1), sdb(1)

gcc, cpp, as, ld, and gdb entries in info.

Using and Porting GNU CC (for version 2.0), Richard M. Stallman; *The C Preprocessor*, Richard M. Stallman; *Debugging with GDB: the GNU Source-Level Debugger*, Richard M. Stallman and Roland H. Pesch; *Using as: the GNU Assembler*, Dean Elsner, Jay Fenlason & friends; *ld: the GNU Linker*, Steve Chamberlain and Roland Pesch.

BUGS

For instructions on reporting bugs, see the GCC manual.

COPYING

Copyright 1991, 1992, 1993 Free Software Foundation, Inc.

Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the preceding conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

AUTHORS

See the GNU CC manual for the contributors to GNU CC.

GNU Tools, 13 October 1993

gemtopbm

gemtopbm—Convert a GEM IMG file into a portable bitmap

SYNOPSIS

```
gemtopbm [-d] [ gemfile ]
```

DESCRIPTION

Reads a GEM IMG file as input. Reads from stdin if input file is omitted. Produces a portable bitmap as output.

OPTIONS

-d Produce output describing the contents of the IMG file.

BUGS

Does not support files containing more than one plane.

SEE ALSO

pbmtogem(1), pbm(5)

AUTHOR

Copyright© 1988 Diomidis D. Spinellis (dds@cc.ic.ac.uk).

11 July 1992

eqn

eqn—Format equations for troff

SYNOPSIS

```
eqn [ -rvCNR ][-dcc ][-Tname ][-Mdir ][-fF ][-sn ][-pn ][-mn ][files ... ]
```

DESCRIPTION

This manual page describes the GNU version of eqn, which is part of the groff document formatting system. eqn compiles descriptions of equations embedded within troff input files into commands that are understood by troff. Normally, it should be invoked using the -e option of groff. The syntax is quite compatible with UNIX eqn. The output of GNU eqn cannot be processed with UNIX troff; it must be processed with GNU troff. If no files are given on the command line, the standard input will be read. A filename of - will cause the standard input to be read.

eqn searches for the file eqnrc using the path `./usr/lib/groff/tmac:usr/lib/tmac`. If it exists, eqn will process it before the other input files. The -R option prevents this.

GNU eqn does not provide the functionality of neqn: it does not support low-resolution, typewriter-like devices (although it may work adequately for very simple input).

OPTIONS

-C	Recognize .EQ and .EN even when followed by a character other than space or newline.
-N	Don't allow newlines within delimiters. This option allows eqn to recover better from missing closing delimiters.
-v	Print the version number.
-r	Only one size reduction.
-mn	The minimum point-size is n. eqn will not reduce the size of subscripts or superscripts to a smaller size than n.
-Tname	The output is for device name. The only effect of this is to define a macro name with a value of 1. Typically, eqnrc will use this to provide definitions appropriate for the output device. The default output device is ps.
-Mdir	Search dir for eqnrc before the default directories.
-R	Don't load eqnrc.
-fF	This is equivalent to a gfontF command.
-sn	This is equivalent to a gsize command. This option is deprecated. eqn will normally set equations at whatever the current pointsize is when the equation is encountered.
-pn	This says that subscripts and superscripts should be n points smaller than the surrounding text. This option is deprecated. Normally, eqn makes sets subscripts and superscripts at 70 percent of the size of the surrounding text.

USAGE

Only the differences between GNU eqn and UNIX eqn are described here.

Most of the new features of GNU eqn are based on TeX. There are some references to the differences between TeX and GNU eqn as follows; these may safely be ignored if you do not know TeX.

AUTOMATIC SPACING

eqn gives each component of an equation a type, and adjusts the spacing between components using that type. Possible types are

ordinary	An ordinary character such as 1 or x
operator	A large operator such as ;
binary	A binary operator such as +
relation	A relation such as =

opening	An opening bracket such as (
closing	A closing bracket such as)
punctuation	A punctuation character such as ,
inner	A subformula contained within brackets
suppress	Spacing that suppresses automatic spacing adjustment

Components of an equation get a type in one of two ways:

typete	This yields an equation component that contains e but that has type t, where t is one of the types mentioned previously. For example, times is defined as <pre>type "binary" \(\mu</pre> The name of the type doesn't have to be quoted, but quoting protects from macro expansion.
chartypettext	Unquoted groups of characters are split up into individual characters, and the type of each character is looked up; this changes the type that is stored for each character; it says that the characters in text from now on have type t. For example <pre>chartype "punctuation" .,:;</pre> would make the characters .,:; have type punctuation whenever they subsequently appeared in an equation. The type t can also be letter or digit; in these cases, chartype changes the font type of the characters. See the “Fonts” section, later in this manual page.

NEW PRIMITIVES

e1smallovere2	This is similar to over; <code>smallover</code> reduces the size of e1 and e2; it also puts less vertical space between e1 or e2 and the fraction bar. The <code>over</code> primitive corresponds to the <code>\over</code> primitive in display styles; <code>smallover</code> corresponds to <code>\over</code> in nondisplay styles.
vcentere	This vertically centers e about the math axis. The math axis is the vertical position about which characters such as + and - are centered; also it is the vertical position used for the bar of fractions. For example, <code>sum</code> is defined as <pre>{ type "operator" vcenter size +5 \(*S }</pre>
e1accente2	This sets e2 as an accent over e1. e2 is assumed to be at the correct height for a lowercase letter; e2 will be moved down according if e1 is taller or shorter than a lowercase letter. For example, <code>hat</code> is defined as <pre>accent { "~" }</pre> <code>dotdot</code>, <code>dot</code>, <code>tilde</code>, <code>vec</code>, and <code>dyad</code> are also defined using the accent primitive.
e1uaccente2	This sets e2 as an accent under e1. e2 is assumed to be at the correct height for a character without a descender; e2 will be moved down if e1 has a descender. <code>utilde</code> is predefined using <code>uaccent</code> as a tilde accent below the baseline.
splittext	This has the same effect as simply text, but text is not subject to macro expansion because it is quoted; text will be split up and the spacing between individual characters will be adjusted.
nosplittext	This has the same effect as text, but because text is not quoted it will be subject to macro expansion; text will not be split up and the spacing between individual characters will not be adjusted.
eopprime	This is a variant of <code>prime</code> that acts as an operator on e. It produces a different result from <code>prime</code> in a case such as <code>Aopprimesub1</code> : With <code>opprime</code> the 1 will be tucked under the prime as a subscript to the A (as is conventional in mathematical typesetting), whereas with <code>prime</code> the 1 will be a subscript to the prime character. The precedence of <code>opprime</code> is the same as that of <code>bar</code> and <code>under</code> , which is higher than that of everything except <code>accent</code> and <code>uaccent</code> . In unquoted text, a ' that is not the first character will be treated like <code>opprime</code> .
specialtexte	This constructs a new object from e using a <code>gtroff(1)</code> macro named text. When the macro is called, the string <code>os</code> will contain the output for e, and the number registers <code>ow</code> , <code>oh</code> , <code>od</code> , <code>oskern</code> and <code>oskew</code> will contain the width, height, depth, subscript kern, and skew of e. (The <i>subscript kern</i> of an object says how much a subscript on that object should be tucked in; the <i>skew</i> of an object says how far to the right of the center of the object an accent over the object should be placed.) The macro must modify <code>os</code> so that it will output the desired result with its origin at the current point, and increase the current horizontal position by the width of the object. The number registers must also be modified so that they correspond to the result.

For example, suppose you wanted a construct that cancels an expression by drawing a diagonal line through it:

```
.EQ
define cancel 'special Ca'
.EN
.de Ca
.ds 0s \Z'\*(0s'\v'\n(0du'\D'1 \n(0wu -\n(0hu-\n(0du'\v'\n(0hu'
..
```

Then you could cancel an expression U with `cancel e`.

Here's a more complicated construct that draws a box around an expression:

```
.EQ
define box 'special Bx'
.EN
.de Bx
.ds 0s \Z'\h'1n'\*(0s'\
\Z'\v'\n(0du+1n'\D'1 \n(0wu+2n 0'\D'1 0 -\n(0hu-\n(0du-2n'\
\D'1 -\n(0wu-2n 0'\D'1 0 \n(0hu+\n(0du+2n'h'\n(0wu+2n'
.nr 0w +2n
.nr 0d +1n
.nr 0h +1n
..
```

CUSTOMIZATION

The appearance of equations is controlled by a large number of parameters. These can be set using the `set` command.

```
setpn           This sets parameter p to value n; n is an integer. For example
                 set x_height 45
                 says that eqn should assume an x height of 0.45 ems.
```

Possible parameters are as follows. Values are in units of hundredths of an em unless otherwise stated. These descriptions are intended to be expository rather than definitive.

<code>minimum_size</code>	<code>eqn</code> will not set anything at a smaller point size than this. The value is in points.
<code>fat_offset</code>	The <code>fat</code> primitive emboldens an equation by overprinting two copies of the equation horizontally offset by this amount.
<code>over_hang</code>	A fraction bar will be longer by twice this amount than the maximum of the widths of the numerator and denominator; in other words, it will overhang the numerator and denominator by at least this amount.
<code>accent_width</code>	When bar or under is applied to a single character, the line will be this long. Normally, bar or under produces a line whose length is the width of the object to which it applies; in the case of a single character, this tends to produce a line that looks too long.
<code>delimiter_factor</code>	Extensible delimiters produced with the left and right primitives will have a combined height and depth of at least this many thousandths of twice the maximum amount by which the subequation that the delimiters enclose extends away from the axis.
<code>delimiter_shortfall</code>	Extensible delimiters produced with the left and right primitives will have a combined height and depth not less than the difference of twice the maximum amount by which the subequation that the delimiters enclose extends away from the axis and this amount.
<code>null_delimiter_space</code>	This much horizontal space is inserted on each side of a fraction.
<code>script_space</code>	The width of subscripts and superscripts is increased by this amount.
<code>thin_space</code>	This amount of space is automatically inserted after punctuation characters.
<code>medium_space</code>	This amount of space is automatically inserted on either side of binary operators.
<code>thick_space</code>	This amount of space is automatically inserted on either side of relations.

<code>x_height</code>	The height of lowercase letters without ascenders such as <code>x</code> .
<code>axis_height</code>	The height above the baseline of the center of characters such as <code>+</code> and <code>-</code> . It is important that this value be correct for the font you are using.
<code>default_rule_thickness</code>	This should set to the thickness of the <code>\(ru</code> character, or the thickness of horizontal lines produced with the <code>\D</code> escape sequence.
<code>num1</code>	The <code>over</code> command will shift up the numerator by at least this amount.
<code>num2</code>	The <code>smallover</code> command will shift up the numerator by at least this amount.
<code>denom1</code>	The <code>over</code> command will shift down the denominator by at least this amount.
<code>denom2</code>	The <code>smallover</code> command will shift down the denominator by at least this amount.
<code>sup1</code>	Normally superscripts will be shifted up by at least this amount.
<code>sup2</code>	Superscripts within superscripts or upper limits or numerators of <code>smallover</code> fractions will be shifted up by at least this amount. This is usually less than <code>sup1</code> .
<code>sup3</code>	Superscripts within denominators or square roots or subscripts or lower limits will be shifted up by at least this amount. This is usually less than <code>sup2</code> .
<code>sub1</code>	Subscripts will normally be shifted down by at least this amount.
<code>sub2</code>	When there is both a subscript and a superscript, the subscript will be shifted down by at least this amount.
<code>sup_drop</code>	The baseline of a superscript will be no more than this amount below the top of the object on which the superscript is set.
<code>sub_drop</code>	The baseline of a subscript will be at least this much below the bottom of the object on which the subscript is set.
<code>big_op_spacing1</code>	The baseline of an upper limit will be at least this much above the top of the object on which the limit is set.
<code>big_op_spacing2</code>	The baseline of a lower limit will be at least this much below the bottom of the object on which the limit is set.
<code>big_op_spacing3</code>	The bottom of an upper limit will be at least this much above the top of the object on which the limit is set.
<code>big_op_spacing4</code>	The top of a lower limit will be at least this much below the bottom of the object on which the limit is set.
<code>big_op_spacing5</code>	This much vertical space will be added above and below limits.
<code>baseline_sep</code>	The baselines of the rows in a pile or matrix will normally be this far apart. In most cases, this should be equal to the sum of <code>num1</code> and <code>denom1</code> .
<code>shift_down</code>	The midpoint between the top baseline and the bottom baseline in a matrix or pile will be shifted down by this much from the axis. In most cases, this should be equal to <code>axis_height</code> .
<code>column_sep</code>	This much space will be added between columns in a matrix.
<code>matrix_side_sep</code>	This much space will be added at each side of a matrix.
<code>draw_lines</code>	If this is nonzero, lines will be drawn using the <code>\D</code> escape sequence, rather than with the <code>\l</code> escape sequence and the <code>\(ru</code> character.
<code>body_height</code>	The amount by which the height of the equation exceeds this will be added as extra space before the line containing the equation (using <code>\x</code> .) The default value is 85.
<code>body_depth</code>	The amount by which the depth of the equation exceeds this will be added as extra space after the line containing the equation (using <code>\x</code> .) The default value is 35.
<code>nroff</code>	If this is nonzero, then <code>ndefine</code> will behave like <code>define</code> and <code>tdefine</code> will be ignored; otherwise, <code>tdefine</code> will behave like <code>define</code> and <code>ndefine</code> will be ignored. The default value is 0. (This is typically changed to 1 by the <code>eqnrc</code> file for the <code>ascii</code> and <code>latin1</code> devices.)

A more precise description of the role of many of these parameters can be found in Appendix H of *The TeXbook*.

MACROS

Macros can take arguments. In a macro body, $\$n$ where n is between 1 and 9, will be replaced by the n th argument if the macro is called with arguments; if there are fewer than n arguments, it will be replaced by nothing. A word containing a left parenthesis where the part of the word before the left parenthesis has been defined using the `define` command will be recognized as a macro call with arguments; characters following the left parenthesis up to a matching right parenthesis will be treated as comma-separated arguments; commas inside nested parentheses do not terminate an argument.

<code>sdefinenameXanythingX</code>	This is like the <code>define</code> command, but <code>name</code> will not be recognized if called with arguments.
<code>includefile</code>	Include the contents of <code>file</code> . Lines of <code>file</code> beginning with <code>.EQ</code> or <code>.EN</code> will be ignored.
<code>ifdefnameXanythingX</code>	If <code>name</code> has been defined by <code>define</code> (or has been automatically defined because <code>name</code> is the output device), process anything; otherwise ignore anything.
	<code>x</code> can be any character not appearing in anything.

FONTS

`eqn` normally uses at least two fonts to set an equation: an italic font for letters, and a Roman font for everything else. The existing `gfont` command changes the font that is used as the italic font. By default this is `i`. The font that is used as the Roman font can be changed by using the new `grfont` command.

`grfontf` Set the Roman font to `f`.

The italic primitive uses the current italic font set by `gfont`; the Roman primitive uses the current Roman font set by `grfont`. There is also a new `gbfont` command, which changes the font used by the bold primitive. If you only use the Roman, italic, and bold primitives to change fonts within an equation, you can change all the fonts used by your equations just by using `gfont`, `grfont`, and `gbfont` commands.

You can control which characters are treated as letters (and therefore set in italic) by using the `chartype` command described earlier. A type of letter will cause a character to be set in italic type. A type of digit will cause a character to be set in Roman type.

FILES

`/usr/lib/groff/tmac/eqnrc` Initialization file

BUGS

Inline equations will be set at the `pointsize` that is current at the beginning of the input line.

SEE ALSO

`groff(1)`, `gtroff(1)`, `groff_font(5)`, *The TeXbook*

getlist

`getlist`—Get a list from an NNTP server

SYNOPSIS

```
getlist [ -h host ][list [ pattern [ types ]]]
```

DESCRIPTION

The `getlist` program obtains a list from an NNTP server and sends it to standard output.

The list may be one of `active`, `active.times`, `distributions`, or `newsgroups`. These values request the `active(5)`, `active.times`, `/news/lib/distributions`, or `/news/lib/newsgroups` files, respectively.

If the `-h` flag is used, then the program connects to the server on the specified host. The default is to connect to the server specified in the `inn.conf(5)` file.

If the `list` parameter is active, then the `pattern` and `types` parameters may be used to limit the output. When `pattern` is used, only active lines with groups that match according to `wildmat(3)` are printed. When `types` is also given, only active lines that have a fourth field starting with a character found in `types` are printed.

For example, the following command will obtain the one-line descriptions of all newsgroups found on UUNET:

```
getlist -h news.uu.net newsgroups
```

The following line lists all groups where local postings are permitted, moderated, or aliased:

```
getlist active '*' ym=
```

Note that the listing files other than the active file is a common extension to the NNTP protocol and may not be available on all servers.

HISTORY

Written by Landon Curt Noll (<chongo@toad.com>) for InterNetNews.

SEE ALSO

`active(5)`, `nnrpd(8)`, `wildmat(3)`

getopt

getopt—Parse command options

SYNOPSIS

```
set - 'getopt optstring $*'
```

DESCRIPTION

`getopt` is used to break up options in command lines for easy parsing by shell procedures, and to check for legal options. `optstring` is a string of recognized option letters; see `getopt(3)`. If a letter is followed by a colon, the option is expected to have an argument that may or may not be separated from it by whitespace. The special option `--` is used to delimit the end of the options. `getopt` will place `--` in the arguments at the end of the options, or recognize it if used explicitly. The shell arguments (`$1 $2 ...`) are reset so that each option is preceded by a `-` and in its own shell argument; each option argument is also in its own shell argument.

EXAMPLE

The following code fragment shows how one might process the arguments for a command that can take the options `a` and `b`, and the option `o`, which requires an argument:

```
set - 'getopt abo: $*'
if test $? != 0
then
    echo 'Usage: ...'
    exit 2
fi
for i
do
    case "$i"
    in
        -a|-b)
            flag=$i; shift;;
        -o)
            oarg=$2; shift; shift;;
        --)
            shift; break;;
    esac
done
```

This code will accept any of the following as equivalent:

```
cmd -aoarg file file
cmd -a -o arg file file
cmd -oarg -a file file
cmd -a -oarg -- file file
```

SEE ALSO

sh(1), getopt(3)

DIAGNOSTICS

getopt prints an error message on the standard error output when it encounters an option letter not included in optstring.

HISTORY

Written by Henry Spencer, working from a Bell Labs manual page. Behavior believed identical to the Bell version.

BUGS

Whatever getopt(3) has.

Arguments containing whitespace or embedded shell meta characters generally will not survive intact; this looks easy to fix but isn't.

The error message for an invalid option is identified as coming from getopt rather than from the shell procedure containing the invocation of getopt; this, again, is hard to fix.

The precise best way to use the set command to set the arguments without disrupting the value(s) of shell options varies from one shell version to another.

21 June 1993

giftopnm

giftopnm—Convert a GIF file into a portable anymap

SYNOPSIS

```
giftopnm [-verbose][ -comments][ -image N][GIFfile]
```

DESCRIPTION

Reads a GIF file for input, and outputs portable anymap.

OPTIONS

-verbose	Produces verbose output about the GIF file input.
-comments	Only outputs GIF89 comment fields.
-image	Outputs the specified GIF image from the input GIF archive (where <i>N</i> is 1, 2, 20...). Normally, there is only one image per file, so this option is not needed.

All flags can be abbreviated to their shortest unique prefix.

BUGS

This does not correctly handle the Plain Text Extension of the GIF89 standard, since I did not have any example input files containing them.

SEE ALSO

ppmtogif(1), ppm(5)

AUTHOR

Copyright © 1993 by David Koblas (koblas@netcom.com)

29 September 1993

gindxbib

gindxbib—Make inverted index for bibliographic databases

SYNOPSIS

```
gindxbib [-vw] [-c file] [-d dir] [-f file] [-h n] [-i string]
          [-k n] [-l n] [-n n] [-o file] [-t n] [filename ...]
```

DESCRIPTION

gindxbib makes an inverted index for the bibliographic databases in *filename...* for use with *grefer(1)*, *glookbib(1)*, and *1kbib(1)*. The index will be named *filename.i*; the index is written to a temporary file which is then renamed to this. If no filenames are given on the command line because the *-f* option has been used, and no *-o* option is given, the index will be named *Ind.i*.

Bibliographic databases are divided into records by blank lines. Within a record, each fields starts with a % character at the beginning of a line. Fields have a one-letter name that follows the % character.

The values set by the *-c*, *-n*, *-l*, and *-t* options are stored in the index; when the index is searched, keys will be discarded and truncated in a manner appropriate to these options; the original keys will be used for verifying that any record found using the index actually contains the keys. This means that a user of an index need not know whether these options were used in the creation of the index, provided that not all the keys to be searched for would have been discarded during indexing and that the user supplies at least the part of each key that would have remained after being truncated during indexing. The value set by the *-i* option is also stored in the index and will be used in verifying records found using the index.

OPTIONS

<i>-v</i>	Print the version number.
<i>-w</i>	Index whole files. Each file is a separate record.
<i>-c file</i>	Read the list of common words from <i>file</i> instead of <i>/usr/lib/groff/eign</i> .
<i>-ddir</i>	Use <i>dir</i> as the pathname of the current working directory to store in the index, instead of the path printed by <i>pwd(1)</i> . Usually <i>dir</i> will be a symbolic link that points to the directory printed by <i>pwd(1)</i> .
<i>-ffile</i>	Read the files to be indexed from <i>file</i> . If <i>file</i> is <i>-</i> , files will be read from the standard input. The <i>-f</i> option can be given at most once.
<i>-istring</i>	Don't index the contents of fields whose names are in <i>string</i> . Initially, <i>string</i> is <i>xyz</i> .
<i>-hn</i>	Use the first prime greater than or equal to <i>n</i> for the size of the hash table. Larger values of <i>n</i> will usually make searching faster, but will make the index larger and <i>gindxbib</i> use more memory. Initially, <i>n</i> is <i>997</i> .
<i>-kn</i>	Use at most <i>n</i> keys per input record. Initially, <i>n</i> is <i>100</i> .
<i>-ln</i>	Discard keys that are shorter than <i>n</i> . Initially, <i>n</i> is <i>3</i> .
<i>-nn</i>	Discard the <i>n</i> most common words. Initially, <i>n</i> is <i>100</i> .
<i>-obasename</i>	The index should be named <i>basename.i</i> .
<i>-tn</i>	Truncate keys to <i>n</i> . Initially, <i>n</i> is <i>6</i> .

FILES

<code>filename.i</code>	Index
<code>Ind.i</code>	Default index name
<code>/usr/lib/groff/eign</code>	List of common words
<code>indxbibXXXXX</code>	Temporary file

SEE ALSO

`grefer(1)`, `lkbib(1)`, `glookbib(1)`

Groff Version 1.09, 16 April 1993

glookbib

`glookbib`—Search bibliographic databases

SYNOPSIS

```
glookbib [ -v ][-istring ][-tn ] filename ...
```

DESCRIPTION

`glookbib` prints a prompt on the standard error (unless the standard input is not a terminal), reads from the standard input a line containing a set of keywords, searches the bibliographic databases `filename ...` for references containing those keywords, prints any references found on the standard output, and repeats this process until the end of input. For each database `filename` to be searched, if an index `filename.i` created by `gindxbib(1)` exists, then it will be searched instead; each index can cover multiple databases.

OPTIONS

<code>-v</code>	Print the version number.
<code>-istring</code>	When searching files for which no index exists, ignore the contents of fields whose names are in <code>string</code> .
<code>-tn</code>	Only require the first <code>n</code> characters of keys to be given. Initially, <code>n</code> is 6.

FILE

<code>filename.i</code>	Index files

SEE ALSO

`grefer(1)`, `lkbib(1)`, `gindxbib(1)`

gnroff

`gnroff`—Emulate `nroff` command with `groff`

SYNOPSIS

```
gnroff [ -h ][-i ][-mname ][-nnum ][-olist ][-rcn ][-Tname ][file...]
```

DESCRIPTION

The `gnroff` script emulates the `nroff` command using `groff`. The `-T` option with an argument other than `ascii` and `latin1` will be ignored. The `-h` option is equivalent to the `grotty -h` option. The `-i`, `-n`, `-m`, `-o`, and `-r` options have the effect described in `gtroff(1)`. In addition, `gnroff` silently ignores options of `-e`, `-q`, or `-s`.

SEE ALSO

groff(1), gtroff(1), grotty(1)

Groff Version 1.09, 17 May 1993

gouldtoppm

gouldtoppm—Convert Gould scanner file into a portable pixmap

SYNOPSIS

gouldtoppm[gouldfile]

DESCRIPTION

Reads a file produced by the Gould scanner as input. Produces a portable pixmap as output.

SEE ALSO

ppm(5)

AUTHOR

Copyright© 1990 by Stephen Paul Lesniewski

20 May 1990

gpic

gpic—Compile pictures for troff or TeX

SYNOPSIS

gpic [-nvC][filename ...] gpic -t [-cvzC][filename ...]

DESCRIPTION

This manual page describes the GNU version of `pic`, which is part of the `groff` document formatting system. `pic` compiles descriptions of pictures embedded within `troff` or TeX input files into commands that are understood by TeX or `troff`. Each picture starts with a line beginning with `.PS` and ends with a line beginning with `.PE`. Anything outside of `.PS` and `.PE` is passed through without change.

It is the user's responsibility to provide appropriate definitions of the `PS` and `PE` macros. When the macro package being used does not supply such definitions (for example, old versions of `-ms`), appropriate definitions can be obtained with `-mpic`: These will center each picture.

OPTIONS

Options that do not take arguments may be grouped behind a single `-`. The special option `--` can be used to mark the end of the options. A filename of `-` refers to the standard input.

- `-C` Recognize `.PS` and `.PE` even when followed by a character other than space or newline.
- `-n` Don't use the `groff` extensions to the `troff` drawing commands. You should use this if you are using a postprocessor that doesn't support these extensions. The extensions are described in `groff_out(5)`. The `-n` option also causes `pic` not to use zero-length lines to draw dots in `troff` mode.
- `-t` TeX mode.
- `-c` Be more compatible with `tpic`. Implies `-t`. Lines beginning with `n` are not passed through transparently. Lines beginning with `.` are passed through with the initial `.` changed to `\`. A line beginning with `.ps` is given special

treatment: It takes an optional integer argument specifying the line thickness (pen size) in milli-inches; a missing argument restores the previous line thickness; the default line thickness is 8 milli-inches. The line thickness thus specified takes effect only when a nonnegative line thickness has not been specified by use of the thickness attribute or by setting the `linethick` variable.

- v Print the version number.
- z In TeX mode draw dots using zero-length lines.

The following options supported by other versions of `pic` are ignored:

- D Draw all lines using the `\D` escape sequence. `pic` always does this.
- Tdev Generate output for the `troff` device `dev`. This is unnecessary because the `troff` output generated by `pic` is device-independent.

USAGE

This section describes only the differences between GNU `pic` and the original version of `pic`. Many of these differences also apply to newer versions of UNIX `pic`.

mode

`mode` is enabled by the `-t` option. In `mode`, `pic` will define a `vbox` called `ngraph` for each picture. You must yourself print that `vbox` using, for example, the command:

```
\centerline{\box\graph}
```

Actually, since the `vbox` has a height of zero, this will produce slightly more vertical space above the picture than below it, the line

```
\centerline{\raise 1em\box\graph}
```

would avoid this.

You must use a driver that supports the `tpic` specials, version 2.

Lines beginning with `\` are passed through transparently; a `%` is added to the end of the line to avoid unwanted spaces. You can safely use this feature to change fonts or to change the value of `\baselineskip`. Anything else may well produce undesirable results; use at your own risk. Lines beginning with a period are not given any special treatment.

COMMANDS

```
for variable = expr1 to expr2
by [*]expr3 do X body X
[Set variable to expr1
```

```
if expr then X if-true X
[else Y if-false Y]
print arg ...
```

```
command arg ...
```

```
sh X command X
```

```
copy "filename"
```

```
copy ["filename"] thru X body X
[until "word"]
```

```
copy ["filename"] thru macro
[until "word"]
```

While the value of `variable` is less than or equal to `expr2`, do `body` and increment `variable` by `expr3`; if `by` is not given, increment `variable` by 1. If `expr3` is prefixed by `*` then `variable` will instead be multiplied by `expr3`. `X` can be any character not occurring in `body`.

Evaluate `expr`; if it is nonzero, do `if-true`; otherwise, do `if-false`. `u` can be any character not occurring in `if-true`. `Y` can be any character not occurring in `if-false`.

Concatenate the arguments and print as a line on `stderr`. Each `arg` must be an expression, a position, or text. This is useful for debugging.

Concatenate the arguments and pass them through as a line to `troff` or TeX. Each `arg` must be an expression, a position, or text. This has a similar effect to a line beginning with `.` or `\`, but allows the values of variables to be passed through.

Pass `command` to a shell. `X` can be any character not occurring in `command`.

Include `filename` at this point in the file.

This construct does `body` once for each line of `filename`; the line is split into blank-delimited words, and occurrences of `$ i` in `body`, for `i` between 1 and 9, are replaced by the `i`-th word of the line. If `filename` is not given, lines are taken from the current input up to `.PE`. If an `until` clause is specified, lines will be read only until a line the first word of which is `word`; that line will then be discarded. `X` can be any character not occurring in `body`. For example,


```
.PS
copy thru % circle at ($1,$2) % until "END"
1 2
3 4
5 6
END
box
.PE
```

is equivalent to

```
.PS
circle at (1,2)
circle at (3,4)
circle at (5,6)
box
.PE
```

The commands to be performed for each line can also be taken from a macro defined earlier by giving the name of the macro as the argument to `thru`.

`reset variable1, variable2 ...`

Reset predefined variables `variable1`, `variable2` ... to their default values. If no arguments are given, reset all predefined variables to their default values. Note that assigning a value to `scale` also causes all predefined variables that control dimensions to be reset to their default values times the new value of `scale`.

`plot expr ["text"]`

This is a text object which is constructed by using as a format string for text `sprintf` with an argument of `expr`. If `text` is omitted, a format string of `%g` is used. Attributes can be specified in the same way as for a normal text object. Be very careful that you specify an appropriate format string; `pic` does only very limited checking of the string. This is deprecated in favor of `sprintf`.

`variable:=expr`

This is similar to `=` except `variable` must already be defined, and the value of `variable` will be changed only in the innermost block in which it is defined. (By contrast, `=` defines the variable in the current block if it is not already defined there, and then changes the value in the current block.)

Arguments of the form

`XanythingX`

are also allowed to be of the form:

`anything`

In this case, `anything` can contain balanced occurrences of `and` and `.BR`. Strings may contain `x` or imbalanced occurrences of `and` and `.BR`.

EXPRESSIONS

The syntax for expressions has been significantly extended:

```
x^y (exponentiation)
sin(x)
cos(x)
atan2(y,x)
log(x) (base 10)
exp(x) (base 10, ie 10'-.4m'x'.4m')
sqrt(x)
int(x)
rand() (return a random number between 0 and 1)
rand(x) (return a random number between 1 and x; deprecated)
max(e1,e2)
min(e1,e2)
!e
```

```

e1 && e2
e1 || e2
e1 == e2
e1 != e2
e1 >= e2
e1 > e2
e1 <= e2
e1 < e2
"str1"=="str2"
"str1"!="str2"

```

String comparison expressions must be parenthesized in some contexts to avoid ambiguity.

OTHER CHANGES

A bare expression, *expr*, is acceptable as an attribute; it is equivalent to *dir expr*, where *dir* is the current direction. For example

```
line 2i
```

means draw a line 2 inches long in the current direction.

The maximum width and height of the picture are taken from the variables *maxpswid* and *maxpsht*. Initially, these have values 8.5 and 11.

Scientific notation is allowed for numbers. For example

```
x = 5e-2
```

Text attributes can be compounded. For example

```
"foo" above ljust
```

is legal.

There is no limit to the depth to which blocks can be examined. For example

```
[A: [B: [C: box ]]] with .A.B.C.sw at 1,2
circle at last [].A.B.C
```

is acceptable.

Arcs now have compass points determined by the circle of which the arc is a part.

Circles and arcs can be dotted or dashed. In mode, splines can be dotted or dashed.

Boxes can have rounded corners. The *rad* attribute specifies the radius of the quarter-circles at each corner. If no *rad* or *diam* attribute is given, a radius of *boxrad* is used. Initially, *boxrad* has a value of 0. A box with rounded corners can be dotted or dashed.

The *.ps* line can have a second argument specifying a maximum height for the picture. If the width of zero is specified, the width will be ignored in computing the scaling factor for the picture. Note that GNU *pic* will always scale a picture by the same amount vertically as horizontally. This is different from the DWB 2.0 *pic*, which may scale a picture by a different amount vertically than horizontally if a height is specified.

Each text object has an invisible box associated with it. The compass points of a text object are determined by this box. The implicit motion associated with the object is also determined by this box. The dimensions of this box are taken from the width and height attributes; if the width attribute is not supplied, then the width will be taken to be *textwid*; if the height attribute is not supplied, then the height will be taken to be the number of text strings associated with the object times *textht*. Initially *textwid* and *textht* have a value of 0.

In places where a quoted text string can be used, an expression of the form:

```
sprintf(format,arg,...)
```

can also be used; this will produce the arguments formatted according to `format`, which should be a string as described in `printf(3)`, appropriate for the number of arguments supplied, using only the `e`, `f`, `g`, or `%` format characters.

The thickness of the lines used to draw objects is controlled by the `linethick` variable. This gives the thickness of lines in points. A negative value means use the default thickness: in output mode, this means use a thickness of 8 milli-inches; in output mode with the `-c` option, this means use the line thickness specified by `.ps lines`; in `troff` output mode, this means use a thickness proportional to the `point` size. A zero value means draw the thinnest possible line supported by the output device. Initially, it has a value of `-1`. There is also a `thick[ness]` attribute. For example,

```
circle thickness 1.5
```

would draw a circle using a line with a thickness of 1.5 points. The thickness of lines is not affected by the value of the `scale` variable, nor by the width or height given in the `.ps` line.

Boxes (including boxes with rounded corners), circles, and ellipses can be filled by giving then an attribute of `fill[ed]`. This takes an optional argument of an expression with a value between 0 and 1; 0 will fill it with white, 1 with black, values in between with a proportionally gray shade. A value greater than 1 can also be used: this means fill with the shade of gray that is currently being used for text and lines. Normally this will be black, but output devices may provide a mechanism for changing this. Without an argument, then the value of the variable `fillval` will be used. Initially, this has a value of 0.5. The invisible attribute does not affect the filling of objects. Any text associated with a filled object will be added after the object has been filled, so that the text will not be obscured by the filling.

Arrowheads will be drawn as solid triangles if the variable `arrowhead` is nonzero and either mode is enabled or the `-x` option has been given. Initially, `arrowhead` has a value of 1.

The `troff` output of `pic` is device-independent. The `-t` option is therefore redundant. All numbers are taken to be in inches; numbers are never interpreted to be in `troff` machine units.

Objects can have an `aligned` attribute. This will only work when the postprocessor is `grops`. Any text associated with an object having the `aligned` attribute will be rotated about the center of the object so that it is aligned in the direction from the start point to the end point of the object. Note that this attribute will have no effect for objects whose start and end points are coincident.

In places where `nth` is allowed, `expr 'th` is also allowed. Note that `'th` is a single token: no space is allowed between the `'` and the `th`. For example,

```
fori =1 to 4 do{
line from 'i'th box.nw to 'i+1'th box.se
}
```

FILE

`/usr/lib/groff/tmac/tmac.pic` Sample definitions of the PS and PE macros.

SEE ALSO

`gtroff(1)`, `groff_out(5)`, `tex(1)`

TPIC: PIC for AT&T Bell Laboratories, Computing Science Technical Report No. 116, *PIC—A Graphics Language for Typesetting*. (This can be obtained by sending an e-mail message to `netlib@research.att.com` with a body of “send 116 from research/cstr.”)

BUGS

Input characters that are illegal for `groff` (those with ASCII code 0 or between 013 and 037 octal or between 0200 and 0237 octal) are rejected even in mode.

The interpretation of `fillval` is incompatible with the `pic` in 10th edition UNIX, which interprets 0 as black and 1 as white.

gprof

gprof—Display call graph profile data

SYNOPSIS

```
gprof [ -abcsz ] [ -ej-E name ] [-fj-F name ][-k fromname toname ] [ objfile [ gmon.out ] ]
```

DESCRIPTION

gprof produces an execution profile of C, Pascal, or Fortran77 programs. The effect of called routines is incorporated in the profile of each caller. The profile data is taken from the call graph profile file (`gmon.out` default), which is created by programs that are compiled with the `-pg` option of `cc(1)`, `pc(1)`, and `f77(1)`. The `-pg` option also links in versions of the library routines that are compiled for profiling. **gprof** reads the given object file (the default is `a.out`) and establishes the relation between its symbol table and the call graph profile from `gmon.out`. If more than one profile file is specified, the **gprof** output shows the sum of the profile information in the given profile files.

gprof calculates the amount of time spent in each routine. Next, these times are propagated along the edges of the call graph. Cycles are discovered, and calls into a cycle are made to share the time of the cycle. The first listing shows the functions sorted according to the time they represent, including the time of their call graph descendants. Below each function entry is shown its (direct) call graph children, and how their times are propagated to this function. A similar display above the function shows how this function's time and the time of its descendants is propagated to its (direct) call graph parents.

Cycles are also shown, with an entry for the cycle as a whole and a listing of the members of the cycle and their contributions to the time and call counts of the cycle.

Second, a flat profile is given, similar to that provided by `prof(1)`. This listing gives the total execution times, the call counts, the time in milliseconds, the call spent in the routine itself, and the time in milliseconds the call spent in the routine itself, including its descendants.

Finally, an index of the function names is provided.

OPTIONS

The following options are available:

- `-a` Suppresses the printing of statically declared functions. If this option is given, all relevant information about the static function (for example, time samples, calls to other functions, calls from other functions) belongs to the function loaded just before the static function in the `objfile` file.
- `-b` Suppresses the printing of a description of each field in the profile.
- `-c` The static call graph of the program is discovered by a heuristic that examines the text space of the object file. Static-only parents or children are shown with call counts of 0.
- `-e name` Suppresses the printing of the graph profile entry for routine `name` and all its descendants (unless they have other ancestors that aren't suppressed). More than one `-e` option may be given. Only one `name` may be given with each `-e` option.
- `-E name` Suppresses the printing of the graph profile entry for routine `name` (and its descendants) as `-e`, previously and also excludes the time spent in `name` (and its descendants) from the total and percentage time computations. (For example, `-E mcount -E mcleanup` is the default.)
- `-f name` Prints the graph profile entry of only the specified routine `name` and its descendants. More than one `-f` option may be given. Only one `name` may be given with each `-f` option.
- `-F name` Prints the graph profile entry of only the routine `name` and its descendants (as `-f`, previously) and also uses only the times of the printed routines in total time and percentage computations. More than one `-F` option may be given. Only one `name` may be given with each `-F` option. The `-F` option overrides the `-E` option.
- `-k fromname toname` Will delete any arcs from routine `fromname` to routine `toname`. This can be used to break undesired cycles. More than one `-k` option may be given. Only one pair of routine names may be given with each `-k` option.

- s A profile file `gmon.sum` is produced that represents the sum of the profile information in all the specified profile files. This summary profile file may be given to later executions of `gprof` (probably also with an `-s`) to accumulate profile data across several runs of an `objfile` file.
- v Prints the version number for `gprof`, and then exits.
- z Displays routines that have zero usage (as shown by call counts and accumulated time). This is useful with the `-c` option for discovering which routines were never called.

FILES

- `a.out` The name list and text space
- `gmon.out` Dynamic call graph and profile
- `gmon.sum` Summarized dynamic call graph and profile

SEE ALSO

`monitor(3)`, `profil(2)`, `cc(1)`, `prof(1)`

“An Execution Profiler for Modular Programs,” by S. Graham, P. Kessler, M. McKusick; *Software—Practice and Experience*, Vol. 13, pp. 671-685, 1983.

“gprof: A Call Graph Execution Profiler,” by S. Graham, P. Kessler, M. McKusick; *Proceedings of the SIGPLAN '82 Symposium on Compiler Construction*, SIGPLAN Notices, Vol. 17, No 6, pp. 120-126, June 1982.

HISTORY

`gprof` appeared in 4.2 BSD.

BUGS

The granularity of the sampling is shown, but remains statistical at best. We assume that the time for each execution of a function can be expressed by the total time for the function divided by the number of times the function is called. Thus, the time propagated along the call graph arcs to the function's parents is directly proportional to the number of times that arc is traversed.

Parents that are not themselves profiled will have the time of their profiled children propagated to them, but they will appear to be spontaneously invoked in the call graph listing, and will not have their time propagated further. Similarly, signal catchers, even though profiled, will appear to be spontaneous (although for more obscure reasons). Any profiled children of signal catchers should have their times propagated properly, unless the signal catcher was invoked during the execution of the profiling routine, in which case all is lost.

The profiled program must call `exit(2)` or return normally for the profiling information to be saved in the `gmon.out` file.

29 January 1993

grefer

`grefer`—Preprocess bibliographic references for `groff`

SYNOPSIS

```
grefer [-benvCPRS] [-a n] [-c fields] [-f n] [-i fields] [-k field] [-l m,n] [-p filename] [-s fields] [-t n] [-B
field.macro] [filename...]
```

DESCRIPTION

This file documents the GNU version of `refer`, which is part of the `groff` document formatting system. `refer` copies the contents of `filename...` to the standard output, except that lines between `.[` and `.]` are interpreted as citations, and lines between `.R1` and `.R2` are interpreted as commands about how citations are to be processed.

Each citation specifies a reference. The citation can specify a reference that is contained in a bibliographic database by giving a set of keywords that only that reference contains. Alternatively, it can specify a reference by supplying a database record in the citation. A combination of these alternatives is also possible.

For each citation, `refer` can produce a mark in the text. This mark consists of some label that can be separated from the text and from other labels in various ways. For each reference, it also outputs `groff` commands that can be used by a macro package to produce a formatted reference for each citation. The output of `refer` must therefore be processed using a suitable macro package. The `-ms` and `-me` macros are both suitable. The commands to format a citation's reference can be output immediately after the citation, or the references may be accumulated, and the commands output at some later point. If the references are accumulated, then multiple citations of the same reference will produce a single formatted reference.

The interpretation of lines between `.R1` and `.R2` as commands is a new feature of GNU `refer`. Documents making use of this feature can still be processed by UNIX `refer` just by adding the lines:

```
.de R1
.ig R2
..
```

to the beginning of the document. This will cause `troff` to ignore everything between `.R1` and `.R2`. The effect of some commands can also be achieved by options. These options are supported mainly for compatibility with UNIX `refer`. It is usually more convenient to use commands.

`refer` generates `.lf` lines so that filenames and line numbers in messages produced by commands that read `refer` output will be correct; it also interprets lines beginning with `.lf` so that filenames and line numbers in the messages and `.lf` lines that it produces will be accurate even if the input has been preprocessed by a command such as `gsoclim(1)`.

OPTIONS

Most options are equivalent to commands (for a description of these commands, see “Commands,” later in this manual page):

```
-b          no-label-in-text; no-label-in-reference
-e          accumulate
-n          no-default-database
-C          compatible
-P          move-punctuation
-S          label "(A.n!Q) ', ' (D.y!D)"; bracket-label " ( " ) "; "
-an         reverse An
-cfields    capitalize fields
-fn         label %n
-ifields    search-ignore fields
-k          label L%a
-kfield     label field%a
-l          label A.nD.y%a
-lm         label A.n+mD.y%a
-l,n        label A.nD.y-n%a
-lm,n       label A.n+mD.y-n%a
-pfilename  database filename
-sspec      sort spec
-tn         search-truncate n
```

These options are equivalent to the following commands with the addition that the filenames specified on the command line are processed as if they were arguments to the bibliography command instead of in the normal way:

```
-B          Annotate X AP; no-label-in-reference
-Bfield.macro  Annotate field macro; no-label-in-reference
```

The following options have no equivalent commands:

- v Print the version number
- R Don't recognize lines beginning with .R1/.R2

USAGE

BIBLIOGRAPHIC DATABASES

The bibliographic database is a text file consisting of records separated by one or more blank lines. Within each record, fields start with a % at the beginning of a line. Each field has a one-character name that immediately follows the %. It is best to use only uppercase and lowercase letters for the names of fields. The name of the field should be followed by exactly one space, and then by the contents of the field. Empty fields are ignored. The conventional meaning of each field is as follows:

- A The name of an author. If the name contains a title such as Jr. at the end, it should be separated from the last name by a comma. There can be multiple occurrences of the A field. The order is significant. It is a good idea always to supply an A field or a Q field.
- B For an article that is part of a book, the title of the book.
- C The place (city) of publication.
- D The date of publication. The year should be specified in full. If the month is specified, the name rather than the number of the month should be used, but only the first three letters are required. It is a good idea always to supply a D field; if the date is unknown, a value such as *in press* or *unknown* can be used.
- E For an article that is part of a book, the name of an editor of the book. Where the work has editors and no authors, the names of the editors should be given as A fields (*ed*) or (*eds*) should be appended to the last author.
- G U.S. government ordering number.
- I The publisher (issuer).
- J For an article in a journal, the name of the journal.
- K Keywords to be used for searching.
- L Label.
- N Journal issue number.
- O Other information. This is usually printed at the end of the reference.
- P Page number. A range of pages can be specified as *m-n*.
- Q The name of the author, if the author is not a person. This will only be used if there are no A fields. There can only be one Q field.
- R Technical report number.
- S Series name.
- T Title. For an article in a book or journal, this should be the title of the article.
- V Volume number of the journal or book.
- X Annotation.

For all fields except A and E, if there is more than one occurrence of a particular field in a record, only the last such field will be used.

If accent strings are used, they should follow the character to be accented. This means that the `AM` macro must be used with the `-ms` macros. Accent strings should not be quoted: use one `\` rather than two.

CITATIONS

The format of a citation is

```
. [opening-text
flags keywords
fields
] closing-text
```

The `opening-text`, `closing-text`, and `flags` components are optional. Only one of the `keywords` and `fields` components need be specified.

The `keywords` component says to search the bibliographic databases for a reference that contains all the words in `keywords`. It is an error if more than one reference is found.

The `fields` component specifies additional fields to replace or supplement those specified in the reference. When references are being accumulated and the `keywords` component is nonempty, then additional fields should be specified only on the first occasion that a particular reference is cited, and will apply to all citations of that reference.

The `opening-text` and `closing-text` component specifies strings to be used to bracket the label instead of the strings specified in the `bracket-label` command. If either of these components is nonempty, the strings specified in the `bracket-label` command will not be used; this behavior can be altered using the `[` and `]` flags. Note that leading and trailing spaces are significant for these components.

The `flags` component is a list of nonalphanumeric characters, each of which modifies the treatment of this particular citation. UNIX refer will treat these flags as part of the keywords and so will ignore them because they are nonalphanumeric. The following flags are currently recognized:

- # This says to use the label specified by the `short-label` command, instead of that specified by the `label` command. If no short label has been specified, the normal label will be used. Typically, the short label is used with author-date labels and consists of only the date and possibly a disambiguating letter; the `#` is supposed to be suggestive of a numeric type of label.
- [Precede `opening-text` with the first string specified in the `bracket-label` command.
-] Follow `closing-text` with the second string specified in the `bracket-label` command.

One advantage of using the `[` and `]` flags rather than including the brackets in `opening-text` and `closing-text` is that you can change the style of bracket used in the document just by changing the `bracket-label` command. Another advantage is that sorting and merging of citations will not necessarily be inhibited if the flags are used.

If a label is to be inserted into the text, it will be attached to the line preceding the `. [` line. If there is no such line, then an extra line will be inserted before the `. [` line and a warning will be given.

There is no special notation for making a citation to multiple references. Just use a sequence of citations, one for each reference. Don't put anything between the citations. The labels for all the citations will be attached to the line preceding the first citation. The labels may also be sorted or merged. (See the description of the `<>` label expression, and of the `sort-adjacent-labels` and `abbreviate-label-ranges` command.) A label will not be merged if its citation has a nonempty `opening-text` or `closing-text`. However, the labels for a citation using the `]` flag and without any `closing-text` immediately followed by a citation using the `[` flag and without any `opening-text` may be sorted and merged even though the first citation's `opening-text` or the second citation's `closing-text` is nonempty. (If you want to prevent this, just make the first citation's `closing-text \&.`)

COMMANDS

Commands are contained between lines starting with `.R1` and `.R2`. Recognition of these lines can be prevented by the `-R` option. When an `.R1` line is recognized, any accumulated references are flushed out. Neither `.R1` nor `.R2` lines, nor anything between them, is output.

Commands are separated by newlines or semicolons. `#` introduces a comment that extends to the end of the line (but does not conceal the newline). Each command is broken up into words. Words are separated by spaces or tabs. A word that begins with an open quote (") extends to the next close quote (") that is not followed by another open quote ("). If there is no such open quote (") the word extends to the end of the line. Pairs of open quotes (") in a word beginning with collapse to a single open quote ("). Neither `#` nor `;` is recognized inside open quotes ("). A line can be continued by ending it with `\`; this works everywhere except after a `#`.

Each command name that is marked with `*` has an associated negative command `no-name` that undoes the effect of `name`. For example, the `no-sort` command specifies that references should not be sorted. The negative commands take no arguments.

In the following description, each argument must be a single word; *field* is used for a single uppercase or lowercase letter naming a field; *fields* is used for a sequence of such letters; *m* and *n* are used for a nonnegative numbers; *string* is used for an arbitrary string; *filename* is used for the name of a file.

<code>abbreviate*fieldsstring1 string2string3string4</code>	Abbreviate the first names of <i>fields</i> . An initial letter will be separated from another initial letter by <i>string1</i> , from the last name by <i>string2</i> , and from anything else (such as a von or de) by <i>string3</i> . These default to a period followed by a space. In a hyphenated first name, the initial of the first part of the name will be separated from the hyphen by <i>string4</i> ; this defaults to a period. No attempt is made to handle any ambiguities that might result from abbreviation. Names are abbreviated before sorting and before label construction.
<code>abbreviate-label-ranges*string</code>	Three or more adjacent labels that refer to consecutive references will be abbreviated to a label consisting of the first label, followed by <i>string</i> , followed by the last label. This is mainly useful with numeric labels. If <i>string</i> is omitted it defaults to <code>-</code> .
<code>accumulate*</code>	Accumulate references instead of writing out each reference as it is encountered. Accumulated references will be written out whenever a reference of the form: <code>. [\$LIST\$.]</code> is encountered, after all input files have been processed, and whenever an <code>.R1</code> line is recognized.
<code>annotate*fieldstring</code>	<i>field</i> is an annotation; print it at the end of the reference as a paragraph preceded by the line <code>.string</code> If <i>macro</i> is omitted, it will default to <code>AP</code> ; if <i>field</i> is also omitted, it will default to <code>X</code> . Only one <i>field</i> can be an annotation.
<code>articlesstring ... string ...</code>	These are definite or indefinite articles, and should be ignored at the beginning of <i>T</i> fields when sorting. Initially, <i>the</i> , <i>a</i> , and <i>an</i> are recognized as articles.
<code>bibliographyfilename ...</code>	Write out all the references contained in the bibliographic databases <i>filename</i> ...
<code>bracket-labelstring 1string2string3</code>	In the text, bracket each label with <i>string1</i> and <i>string2</i> . An occurrence of <i>string2</i> immediately followed by <i>string1</i> will be turned into <i>string3</i> . The default behavior is <code>bracket-label \"([. \\. \"] \"</code> , “
<code>capitalizefields</code>	Convert <i>fields</i> to caps and small caps.
<code>compatible*</code>	Recognize <code>.R1</code> and <code>.R2</code> even when followed by a character other than space or newline.
<code>databasefilename...</code>	Search the bibliographic databases <i>filename</i> ... For each <i>filename</i> if an index <i>filename.i</i> created by <code>gindexbib(1)</code> exists, then it will be searched instead; each index can cover multiple databases.
<code>date-as-label*string</code>	<i>string</i> is a label expression that specifies a string with which to replace the <i>D</i> field after constructing the label. See “Label Expressions,” later in this manual page, for a description of label expressions. This command is useful if you do not want explicit labels in the reference list, but instead want to handle any necessary disambiguation by qualifying the date in some way. The label used in the text would typically be some combination of the author and date. In most cases, you should also use the <code>no-label-in-reference</code> command. For example, <code>date-as-label D.+yD.y%a*D.-y</code> would attach a disambiguating letter to the year part of the <i>D</i> field in the reference.
<code>default-database*</code>	The default database should be searched. This is the default behavior, so the negative version of this command is more useful. <i>refer</i> determines whether the default database should be searched on the first occasion that it needs to do a search. Thus, a <code>no-default-database</code> command must be given before then, in order to be effective.

`discard*fields`

When the reference is read, `fields` should be discarded; no string definitions for `fields` will be output. Initially, `fields` are `XYZ`.

`et-al*stringmn`

Control use of `et al` in the evaluation of `@` expressions in `label` expressions. If the number of authors needed to make the author sequence unambiguous is `u` and the total number of authors is `t`, then the last `t - u` authors will be replaced by `string`, provided that `t - u` is not less than `m` and `t` is not less than `n`. The default behavior is `et-al " et al" 2 3`.

`includefilename`

Include `filename` and interpret the contents as commands.

`join-authorsstring1`

This says how authors should be joined together. When there are exactly two authors, they will be joined with `string1`. When there are more than two authors, all but the last two will be joined with `string2`, and the last two authors will be joined with `string3`. If `string3` is omitted, it will default to `string1`; if `string2` is also omitted, it will also default to `string1`. For example,

`string2string3`

`join-authors " and " ", " ", and "`

will restore the default method for joining authors.

`label-in-reference*`

When outputting the reference, define the string `[F` to be the reference's label. This is the default behavior; so the negative version of this command is more useful.

`label-in-text*`

For each reference, output a label in the text. The label will be separated from the surrounding text as described in the `bracket-label` command. This is the default behavior; so the negative version of this command is more useful.

`labelstring`

`string` is a label expression describing how to label each reference.

`separate-label-second-parts`

When merging two-part labels, separate the second part of the second label from the first label with `string`. See the description of the `<>` label expression.

`string`

`move-punctuation*`

In the text, move any punctuation at the end of line past the label. It is usually a good idea to give this command unless you are using superscripted numbers as labels.

`reverse*string`

Reverse the fields whose names are in `string`. Each field name can be followed by a number that says how many such fields should be reversed. If no number is given for a field, all such fields will be reversed.

`search-ignore*fields`

While searching for keys in databases for which no index exists, ignore the contents of `fields`. Initially, `fields XYZ` are ignored.

`search-truncate*n`

Only require the first `n` characters of keys to be given. In effect, when searching for a given key, words in the database are truncated to the maximum of `n` and the length of the key. Initially, `n` is 6.

`short-label*string`

`string` is a label expression that specifies an alternative (usually shorter) style of label. This is used when the `#` flag is given in the citation. When using author-date style labels, the identity of the author or authors is sometimes clear from the context, and so it may be desirable to omit the author or authors from the label. The `short-label` command will typically be used to specify a label containing just a date and possibly a disambiguating letter.

`sort*string`

Sort references according to `string`. References will automatically be accumulated. `string` should be a list of field names, each followed by a number, indicating how many fields with the name should be used for sorting. `+` can be used to indicate that all the fields with the name should be used. Also, `.` can be used to indicate the references should be sorted using the (tentative) label. (The "Label Expressions" subsection describes the concept of a tentative label.)

`sort-adjacent-labels*`

Sort labels that are adjacent in the text according to their position in the reference list. This command should usually be given if the `abbreviate-label-ranges` command has been given, or if the label expression contains a `<>` expression. This will have no effect unless references are being accumulated.

LABEL EXPRESSIONS

Label expressions can be evaluated both normally and tentatively. The result of normal evaluation is used for output. The result of tentative evaluation, called the tentative label, is used to gather the information that normal evaluation needs to disambiguate the label. Label expressions specified by the `date-as-label` and `short-label` commands are not evaluated tentatively. Normal and tentative evaluation are the same for all types of expression other than `@`, `*`, and `%` expressions. The following description applies to normal evaluation, except where otherwise specified.

<code>field, field n</code>	The <i>n</i> th part of field. If <i>n</i> is omitted, it defaults to 1.
<code>'string'</code>	The characters in <i>string</i> literally.
<code>@</code>	All the authors joined as specified by the <code>join-authors</code> command. The whole of each author's name will be used. However, if the references are sorted by author (that is the sort specification starts with <code>A+</code>), then authors' last names will be used instead, provided that this does not introduce ambiguity, and also an initial subsequence of the authors may be used instead of all the authors, again provided that this does not introduce ambiguity. The use of only the last name for the <i>i</i> -th author of some reference is considered to be ambiguous if there is some other reference, such that the first <i>i</i> - 1 authors of the references are the same, the <i>i</i> -th authors are not the same, but the <i>i</i> -th authors' last names are the same. A proper initial subsequence of the sequence of authors for some reference is considered to be ambiguous if there is a reference with some other sequence of authors that also has that subsequence as a proper initial subsequence. When an initial subsequence of authors is used, the remaining authors are replaced by the string specified by the <code>et-a1</code> command; this command may also specify additional requirements that must be met before an initial subsequence can be used. <code>@</code> tentatively evaluates to a canonical representation of the authors, such that authors that compare equally for sorting purpose will have the same representation.
<code>%n, %a, %A, %i, %I</code>	The serial number of the reference formatted according to the character following the <code>%</code> . The serial number of a reference is 1 plus the number of earlier references with same tentative label as this reference. These expressions tentatively evaluate to an empty string.
<code>expr*</code>	If there is another reference with the same tentative label as this reference, then <code>expr</code> ; otherwise, an empty string. It tentatively evaluates to an empty string.
<code>expr+n, expr-n</code>	The first (+) or last (-) <i>n</i> uppercase or lowercase letters or digits of <code>expr</code> . troff special characters (such as <code>\ (' a</code>) count as a single letter. Accent strings are retained but do not count toward the total.
<code>expr.l</code>	<code>expr</code> converted to lowercase.
<code>expr.u</code>	<code>expr</code> converted to uppercase.
<code>expr.c</code>	<code>expr</code> converted to caps and small caps.
<code>expr.r</code>	<code>expr</code> reversed so that the last name is first.
<code>expr.a</code>	<code>expr</code> with first names abbreviated. Note that fields specified in the <code>abbreviate</code> command are abbreviated before any labels are evaluated. Thus <code>.a</code> is useful only when you want a field to be abbreviated in a label but not in a reference.
<code>expr.y</code>	The year part of <code>expr</code> .
<code>expr.+y</code>	The part of <code>expr</code> before the year, or the whole of <code>expr</code> if it does not contain a year.
<code>expr.-y</code>	The part of <code>expr</code> after the year, or an empty string if <code>expr</code> does not contain a year.
<code>expr.n</code>	The last name part of <code>expr</code> .
<code>expr1expr2</code>	<code>expr1</code> except that if the last character of <code>expr1</code> is <code>-</code> then it will be replaced by <code>expr2</code> .
<code>expr1 expr2</code>	The concatenation of <code>expr1</code> and <code>expr2</code> .
<code>expr1 expr2</code>	If <code>expr1</code> is nonempty, then <code>expr1</code> ; otherwise, <code>expr2</code> .
<code>expr1&expr2</code>	If <code>expr1</code> is nonempty, then <code>expr2</code> ; otherwise, an empty string.
<code>expr1?expr2:expr3</code>	If <code>expr1</code> is nonempty, then <code>expr2</code> ; otherwise, <code>expr3</code> .
<code><expr></code>	The label is in two parts, which are separated by <code>expr</code> . Two adjacent two-part labels that have the same first part will be merged by appending the second part of the second label onto the first label separated by the string specified in the <code>separate-label-second-parts</code> command (initially, a comma followed by a

space); the resulting label will also be a two-part label with the same first part as before merging, and so additional labels can be merged into it. Note that it is permissible for the first part to be empty; this may be desirable for expressions used in the `short-label` command.

(*expr*) The same as *expr*. Used for grouping.

The preceding expressions are listed in order of precedence (highest first); `&` and `|` have the same precedence.

MACRO INTERFACE

Each reference starts with a call to the macro `] -`. The string `[F` will be defined to be the label for this reference, unless the `no-label-in-reference` command has been given. There then follows a series of string definitions, one for each field: string `[X` corresponds to field `X`. The number register `[P` is set to 1 if the `P` field contains a range of pages. The `[T`, `[A`, and `[O` number registers are set to 1 according as the `T`, `A`, and `O` fields end with one of the characters `.?!`. The `[E` number register will be set to 1 if the `[E` string contains more than one name. The reference is followed by a call to the `]I` macro. The first argument to this macro gives a number representing the type of the reference. If a reference contains a `J` field, it will be classified as type 1; otherwise, if it contains a `B` field, it will be type 3; otherwise, if it contains a `G` or `R` field it will be type 4, otherwise if it contains an `I` field, it will be type 2; otherwise, it will be type 0. The second argument is a symbolic name for the type: `other`, `journal-article`, `book`, `article-in-book`, or `tech-report`. Groups of references that have been accumulated or are produced by the bibliography command are preceded by a call to the `]<` macro and followed by a call to the `]>` macro.

FILES

`/usr/dict/papers/Ind` Default database
`file.i` Index files

SEE ALSO

`gindexbib(1)`, `glookbib(1)`, `lkbib(1)`

BUGS

In label expressions, `<>` expressions are ignored inside `.char` expressions.

Groff Version 1.09

grep, egrep, fgrep

`grep`, `egrep`, `fgrep`—Print lines matching a pattern

SYNOPSIS

```
grep [ -[AB]num ][-[CEFGVBchilnsvw]][-e ] pattern j -ffile ][files... ]
```

DESCRIPTION

`grep` searches the named input *files* (or standard input if no files are named, or the filename `-` is given) for lines containing a match to the given *pattern*. By default, `grep` prints the matching lines.

There are three major variants of `grep`, controlled by the following options:

- `-G` Interpret *pattern* as a basic regular expression (see the list following this one). This is the default.
- `-E` Interpret *pattern* as an extended regular expression.
- `-F` Interpret *pattern* as a list of fixed strings, separated by newlines, any of which is to be matched.

In addition, two variant programs, `egrep` and `fgrep`, are available. `egrep` is similar (but not identical) to `grep -E`, and is compatible with the historical UNIX `egrep`. `Fgrep` is the same as `grep -F`.

All variants of `grep` understand the following options:

-num	Matches will be printed with num lines of leading and trailing context. However, grep will never print any given line more than once.
-A num	Print num lines of trailing context after matching lines.
-B num	Print num lines of leading context before matching lines.
-C	Equivalent to -2.
-V	Print the version number of grep to standard error. This version number should be included in all bug reports.
-b	Print the byte offset within the input file before each line of output.
-c	Suppress normal output; instead print a count of matching lines for each input file. With the -v option, count nonmatching lines.
-e pattern	Use pattern as the pattern; useful to protect patterns beginning with -.
-f file	Obtain the pattern from file.
-h	Suppress the prefixing of filenames on output when multiple files are searched.
-i	Ignore case distinctions in both the pattern and the input files.
-L	Suppress normal output; instead print the name of each input file from which no output would normally have been printed.
-l	Suppress normal output; instead print the name of each input file from which output would normally have been printed.
-n	Prefix each line of output with the line number within its input file.
-q	Quiet; suppress normal output.
-s	Suppress error messages about nonexistent or unreadable files.
-v	Invert the sense of matching, to select nonmatching lines.
-w	Select only those lines containing matches that form whole words. The test is that the matching substring must either be at the beginning of the line, or preceded by a nonword constituent character. Similarly, it must be either at the end of the line or followed by a nonword-constituent character. Word-constituent characters are letters, digits, and the underscore.
-x	Select only those matches that exactly match the whole line.

REGULAR EXPRESSIONS

A regular expression is a pattern that describes a set of strings. Regular expressions are constructed analogously to arithmetic expressions, by using various operators to combine smaller expressions.

grep understands two different versions of regular expression syntax: *basic* and *extended*. In GNU\grep, there is no difference in available functionality using either syntax. In other implementations, basic regular expressions are less powerful. The following description applies to extended regular expressions; differences for basic regular expressions are summarized afterwards.

The fundamental building blocks are the regular expressions that match a single character. Most characters, including all letters and digits, are regular expressions that match themselves. Any meta character with special meaning may be quoted by preceding it with a backslash.

A list of characters enclosed by [and] matches any single character in that list; if the first character of the list is the caret (^) then it matches any character *not* in the list. For example, the regular expression [0123456789] matches any single digit. A range of ASCII characters may be specified by giving the first and last characters, separated by a hyphen. Finally, certain named classes of characters are predefined. Their names are self-explanatory, and they are [:alnum:], [:alpha:], [:cntrl:], [:digit:], [:graph:], [:lower:], [:print:], [:punct:], [:space:], [:upper:], and [:xdigit:]. For example, [[:alnum:]] means [0-9A-Za-z], except the latter form is dependent upon the ASCII character encoding, whereas the former is portable. (Note that the brackets in these class names are part of the symbolic names, and must be included in addition to the brackets delimiting the bracket list.) Most meta characters lose their special meaning inside lists. To include a literal], place it first in the list. Similarly, to include a literal ^, place it anywhere but first. Finally, to include a literal -, place it last.

The period matches any single character. The symbol \w is a synonym for [[:alnum:]] and \W is a synonym for [^[:alnum:]].

The caret and the dollar sign are meta characters that respectively match the empty string at the beginning and end of a line. The symbols `\<` and `\>`, respectively, match the empty string at the beginning and end of a word. The symbol `\b` matches the empty string at the edge of a word, and `\B` matches the empty string provided it's *not* at the edge of a word.

A regular expression matching a single character may be followed by one of several repetition operators:

<code>?</code>	The preceding item is optional and matched at most once.
<code>*</code>	The preceding item will be matched zero or more times.
<code>+</code>	The preceding item will be matched one or more times.
<code>n</code>	The preceding item is matched exactly <i>n</i> times.
<code>n,</code>	The preceding item is matched <i>n</i> or more times.
<code>,m</code>	The preceding item is optional and is matched at most <i>m</i> times.
<code>n,m</code>	The preceding item is matched at least <i>n</i> times, but not more than <i>m</i> times.

Two regular expressions may be concatenated; the resulting regular expression matches any string formed by concatenating two substrings that respectively match the concatenated subexpressions.

Two regular expressions may be joined by the infix operator `|`; the resulting regular expression matches any string matching either subexpression.

Repetition takes precedence over concatenation, which in turn takes precedence over alternation. A whole subexpression may be enclosed in parentheses to override these precedence rules.

The back reference `\n`, where *n* is a single digit, matches the substring previously matched by the *n*th parenthesized subexpression of the regular expression.

In basic regular expressions, the meta characters `!`, `(`, and `)` lose their special meaning; instead use the backslashed versions `\?`, `\+`, `\f`, `\j`, `\(`, and `\)`.

In `egrep`, the meta character `{` loses its special meaning; instead use `\{`.

DIAGNOSTICS

Normally, exit status is `0` if matches were found, and `1` if no matches were found. (The `.B -v` option inverts the sense of the exit status.) Exit status is `2` if there were syntax errors in the pattern, inaccessible input files, or other system errors.

BUGS

E-mail bug reports to bug-gnu-utils@prep.ai.mit.edu. Be sure to include the word `grep` somewhere in the “Subject:” field.

Large repetition counts in the `m, n` construct may cause `grep` to use lots of memory. In addition, certain other obscure regular expressions require exponential time and space, and may cause `grep` to run out of memory.

Back references are very slow, and may require exponential time.

GNU Project, 10 September 1992

grephistory

grephistory—Display filenames from Usenet history file

SYNOPSIS

```
grephistory [ -f filename ] [-e ] [-n ] [-q ] [-l ] [-i ] [-s ] [messageid ]
```

DESCRIPTION

grephistory queries the `dbz(3)` index into the `history(5)` file for an article having a specified Message ID.

If `messageid` cannot be found in the database, the program prints “Not found” and exits with a nonzero status. If `messageid` is in the database, the program prints the pathname and exits successfully. If no pathname exists, the program will print `/dev/`

null and exit successfully. This can happen when an article has been canceled, or if it has been expired but its history is still retained. This is default behavior, which can be obtained by using the `-n` flag.

If the `-q` flag is used, then no message is displayed. The program will still exit with the appropriate exit status. If the `-e` flag is used, then `grephistory` will only print the filename of an existing article.

If the `-l` flag is used, then the entire line from the history file will be displayed.

If the `-i` flag is used, then `grephistory` will read a list of Message-IDs on standard input, one per line. Leading and trailing whitespace is ignored, as are any malformed lines. It will print on standard output those Message-IDs that are not found in the history database. This flag is used in processing `ihave` control messages.

If the `-s` flag is used, then `grephistory` will read a similar list from its standard input. It will print on standard output a list of filenames for each article that is still available. This flag is used in processing `sendme` control messages.

To specify a different value for the history file and database, use the `-f` flag.

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for InterNetNews.

SEE ALSO

`dbz(3)`, `history(5)`

grodvi

`grodvi`—Convert `groff` output to TeX `dvi` format

SYNOPSIS

```
grodvi [ -dv ] [-wn ] [-Fdir ] [files ... ]
```

DESCRIPTION

`grodvi` is a driver for `groff` that produces `dvi` format. Normally, it should be run by `groff-Tdvi`. This will run `gtroff-Tdvi`; it will also input the macros `/usr/lib/groff/tmac/tmac.dvi`; if the input is being preprocessed with `geqn`, it will also input `/usr/lib/groff/font/devdvi/eqnchar`.

The `dvi` file generated by `grodvi` can be printed by any correctly written `dvi` driver. The `troff` drawing primitives are implemented using the `tpic` version 2 specials. If the driver does not support these, the `\D` commands will not produce any output.

There is an additional drawing command available:

<code>\D'Rdhdv'</code>	Draw a rule (solid black rectangle), with one corner at the current position, and the diagonally opposite corner at the current position + (dh,dv). Afterwards, the current position will be at the opposite corner. This produces a rule in the <code>dvi</code> file and so can be printed even with a driver that does not support the <code>tpic</code> specials, unlike the other <code>\D</code> commands.

The `groff` command `\X'anything'` is translated into the same command in the `dvi` file as would be produced by `\special{anything }` in TeX; anything may not contain a newline.

Font files for `grodvi` can be created from `tfm` files using `tfmtodit(1)`. The font description file should contain the following additional commands:

<code>internalname name</code>	The name of the <code>tfm</code> file (without the <code>.tfm</code> extension) is <code>name</code> .
<code>checksum n</code>	The checksum in the <code>tfm</code> file is <code>n</code> .
<code>designsize n</code>	The <code>designsize</code> in the <code>tfm</code> file is <code>n</code> .

These are automatically generated by `tfmtodit`.

In `troff`, the `\N` escape sequence can be used to access characters by their position in the corresponding `tfm` file; all characters in the `tfm` file can be accessed this way.

OPTIONS

- `-d` Do not use `tpic` specials to implement drawing commands. Horizontal and vertical lines will be implemented by rules. Other drawing commands will be ignored.
- `-v` Print the version number.
- `-wn` Set the default line thickness to `n` thousandths of an em.
- `-Fdir` Search directory `dir/devdvi` for font and device description files.

FILES

<code>/usr/lib/groff/font/devdvi/DESC</code>	Device description file
<code>/usr/lib/groff/font/devdvi/ F</code>	Font description file for font <code>F</code>
<code>/usr/lib/groff/tmac/tmac.dvi</code>	Macros for use with <code>grodvi</code>

BUGS

`dvi` files produced by `grodvi` use a different resolution (57,816 units per inch) than those produced by TeX. Incorrectly written drivers that assume the resolution used by TeX, rather than using the resolution specified in the `dvi` file, will not work with `grodvi`.

When using the `-d` option with boxed tables, vertical and horizontal lines can sometimes protrude by one pixel. This is a consequence of the way TeX requires that the heights and widths of rules be rounded.

SEE ALSO

`tfmtodit(1)`, `groff(1)`, `gtroff(1)`, `geqn(1)`, `groff_out(5)`, `groff_font(5)`, `groff_char(7)`

Groff Version 1.09 14

groff

`groff`—Front end for the `groff` document formatting system

SYNOPSIS

```
groff [ -tpeszaivhblCENRVXZ ][-wname ][-Wname ][-mname ][-Fdir ][-Tdev ] [ -ffam ][-Mdir ][-dcs ][-rcn ][-nnum ]
[-olist ][-Parg ][files ... ]
```

DESCRIPTION

`groff` is a front-end to the `groff` document formatting system. Normally, it runs the `gtroff` program and a postprocessor appropriate for the selected device. Available devices are

<code>ps</code>	For PostScript printers and previewers
<code>dvi</code>	For TeX <code>dvi</code> format
<code>x75</code>	For a 75 dpi X11 previewer
<code>x100</code>	For a 100dpi X11 previewer
<code>ascii</code>	For typewriter-like devices
<code>latin1</code>	For typewriter-like devices using the ISO Latin-1 character set.

The postprocessor to be used for a device is specified by the `postpro` command in the device description file. This can be overridden with the `-x` option.

The default device is `ps`. It can optionally preprocess with any of `gpics`, `geqn`, `gtbl`, `grefer`, or `gsaelim`.

Options without an argument can be grouped behind a single `-`. A filename of `-` denotes the standard input.

The `grog` command can be used to guess the correct `groff` command to use to format a file.

OPTIONS

- `-h` Print a help message.
- `-e` Preprocess with `geqn`.
- `-t` Preprocess with `gtbl`.
- `-p` Preprocess with `gpics`.
- `-s` Preprocess with `gsoelim`.
- `-R` Preprocess with `grefer`. No mechanism is provided for passing arguments to `grefer` because most `grefer` options have equivalent commands that can be included in the file. See `grefer(1)` for more details.
- `-v` Make programs run by `groff` print out their version number.
- `-V` Print the pipeline on `stdout` instead of executing it.
- `-z` Suppress output from `gtroff`. Only error messages will be printed.
- `-Z` Do not postprocess the output of `gtroff`. Normally, `groff` will automatically run the appropriate postprocessor.
- `-Parg` Pass `arg` to the postprocessor. Each argument should be passed with a separate `-P` option. Note that `groff` does not prepend `-` to `arg` before passing it to the postprocessor.
- `-l` Send the output to a printer. The command used for this is specified by the `print` command in the device description file.
- `-Larg` Pass `arg` to the spooler. Each argument should be passed with a separate `-L` option. Note that `groff` does not prepend `-` to `arg` before passing it to the postprocessor.
- `-Tdev` Prepare output for device `dev`. The default device is `ps`.
- `-X` Preview with `gxditview` instead of using the usual postprocessor. This is unlikely to produce good results except with `-Tps`.
- `-N` Don't allow newlines with `eqn` delimiters. This is the same as the `-N` option in `geqn`.

The options `-a`, `-b`, `-i`, `-C`, `-E`, `-wname`, `-Wname`, `-mname`, `-olist`, `-dcs`, `-rcn`, `-Fdir`, `-Mdir`, `-ffam`, and `-nnum` are described in `gtroff(1)`.

ENVIRONMENT

<code>GROFF_COMMAND_PREFIX</code>	If this is set <code>X</code> , then <code>groff</code> will run <code>Xtroff</code> instead of <code>gtroff</code> . This also applies to <code>tbl</code> , <code>pic</code> , <code>eqn</code> , <code>refer</code> , and <code>soelim</code> . It does not apply to <code>grops</code> , <code>grodvi</code> , <code>grotty</code> , and <code>gxditview</code> .
<code>GROFF_TMAC_PATH</code>	A colon-separated list of directories in which to search for macro files.
<code>GROFF_TYPESETTER</code>	Default device.
<code>GROFF_FONT_PATH</code>	A colon-separated list of directories in which to search for the <code>devname</code> directory.
<code>PATH</code>	The search path for commands executed by <code>groff</code> .
<code>GROFF_TMPDIR</code>	The directory in which temporary files will be created. If this is not set and <code>TMPDIR</code> is set, temporary files will be created in that directory. Otherwise, temporary files will be created in <code>/tmp</code> . The <code>grops(1)</code> and <code>grefer(1)</code> commands can create temporary files.

FILES

<code>/usr/lib/groff/font/devname/DESC</code>	Device description file for device <i>name</i> .
<code>/usr/lib/groff/font/devname/F</code>	Font file for font <i>F</i> of device <i>name</i> .

AUTHOR

James Clark (jjc@jclark.com)

BUGS

Report bugs to `bug.groff@prep.ai.mit.edu`. Include a complete, self-contained example that will allow the bug to be reproduced, and say which version of `groff` you are using.

COPYRIGHT

Copyright 1989, 1990, 1991, 1992 Free Software Foundation, Inc.

`groff` is free software; you can redistribute it or modify it under the terms of the GNU General Public License as published by the Free Software Foundation; either version 2, or (at your option) any later version.

`groff` is distributed in the hope that it will be useful, but without any warranty; without even the implied warranty of merchantability or fitness for a particular purpose. See the GNU General Public License for more details.

You should have received a copy of the GNU General Public License along with `groff`; see the file `COPYING`. If not, write to the Free Software Foundation, 675 Mass Ave, Cambridge, MA 02139, USA.

AVAILABILITY

The most recent released version of `groff` is always available for anonymous ftp from `prep.ai.mit.edu` (18.71.0.38) in the directory `pub/gnu`.

SEE ALSO

`grog`(1), `gtroff`(1), `gtbl`(1), `gpics`(1), `geqn`(1), `gsoelim`(1), `grefer`(1), `grops`(1), `groddvi`(1), `grotty`(1), `gxditview`(1), `groff_font`(5), `groff_out`(5), `groff_ms`(7), `groff_me`(7), `groff_char`(7)

Groff Version 1.09, 29 October 1992

grog

`grog`—Guess options for `groff` command

SYNOPSIS

```
grog [ -option ... ][files ... ]
```

DESCRIPTION

`grog` reads `files` and guesses which of the `groff`(1) options `-e`, `-man`, `-me`, `-mm`, `-ms`, `-p`, `-s`, and `-t` are required for printing `files`, and prints the `groff` command including those options on the standard output. A filename of `-` is taken to refer to the standard input. If no files are specified, the standard input will be read. Any specified options will be included in the printed command. No space is allowed between options and their arguments. For example,

```
'grog -Tdvi paper.ms'
```

will guess the appropriate command to print `paper.ms` and then run it after adding the `-Tdvi` option.

SEE ALSO

`doctype`(1), `groff`(1), `gtroff`(1), `gtbl`(1), `gpics`(1), `geqn`(1), `gsoelim`(1)

Groff Version 1.09 14

grops

`grops`—PostScript driver for `groff`

SYNOPSIS

```
grops [ -glv ][-bn ][-cn ][-wn ][-Fdir ][files ... ]
```

DESCRIPTION

grops translates the output of GNU troff to PostScript. Normally, grops should be invoked by using the groff command with a -tps option. If no files are given, grops will read the standard input. A filename of - will also cause grops to read the standard input. PostScript output is written to the standard output. When grops is run by groff, options can be passed to grops by using the groff -P option.

OPTIONS

- bn Work around broken spoolers and previewers. Normally grops produces output that conforms the Document Structuring Conventions version 3.0. Unfortunately, some spoolers and previewers can't handle such output. The value of *n* controls what grops does to its output acceptable to such programs. A value of 0 will cause grops not to employ any workarounds. Add 1 if no %%BeginDocumentSetup and %%EndDocumentSetup comments should be generated; this is needed for early versions of TranScript that get confused by anything between the %%EndProlog comment and the first %%Page comment. Add 2 if lines in included files beginning with %! should be stripped out; this is needed for Sun's pageview previewer. Add 4 if %%Page, %%Trailer, and %%EndProlog comments should be stripped out of included files; this is needed for spoolers that don't understand the %%BeginDocument and %%EndDocument comments. Add 8 if the first line of the PostScript output should be %!PS-Adobe-2.0 rather than %!PS-Adobe-3.0; this is needed when using Sun's Newsprint with a printer that requires page reversal. The default value can be specified by a brokenn command in the DESC file. Otherwise, the default value is 0.
- cn Print *n* copies of each page.
- g Guess the page length. This generates PostScript code that guesses the page length. The guess will be correct only if the imageable area is vertically centered on the page. This option allows you to generate documents that can be printed both on letter (8.5×11) paper and on A4 paper without change.
- l Print the document in landscape format.
- Fdir Search the directory *dir*/devname for font and device description files; name is the name of the device, usually ps.
- wn Lines should be drawn using a thickness of *n* thousandths of an em.
- v Print the version number.

USAGE

There are styles called R, I, B, and BI mounted at font positions 1 to 4. The fonts are grouped into families A, BM, C, H, HN, N, P, and T having members in each of these styles:

AR	AvantGarde-Book
AI	AvantGarde-BookOblique
AB	AvantGarde-Demi
ABI	AvantGarde-DemiOblique
BMR	Bookman-Light
BMI	Bookman-LightItalic
BMB	Bookman-Demi
BMBI	Bookman-DemiItalic
CR	Courier
CI	Courier-Oblique
CB	Courier-Bold
CBI	Courier-BoldOblique
HR	Helvetica
HI	Helvetica-Oblique
HB	Helvetica-Bold
HBI	Helvetica-BoldOblique
HNR	Helvetica-Narrow
HNI	Helvetica-Narrow-Oblique

HNB	Helvetica-Narrow-Bold
HNBI	Helvetica-Narrow-BoldOblique
NR	NewCenturySchlbk-Roman
NI	NewCenturySchlbk-Italic
NB	NewCenturySchlbk-Bold
NBI	NewCenturySchlbk-BoldItalic
PR	Palatino-Roman
PI	Palatino-Italic
PB	Palatino-Bold
PBI	Palatino-BoldItalic
TR	Times-Roman
TI	Times-Italic
TB	Times-Bold
TBI	Times-BoldItalic

There is also the following font which is not a member of a family:

ZCMI ZapfChancery-MediumItalic

There are also some special fonts called ss and s. Zapf Dingbats is available as ZD and a reversed version of ZapfDingbats (with symbols pointing in the opposite direction) is available as ZDR; most characters in these fonts are unnamed and must be accessed using \N.

grops understands various X commands produced using the \X escape sequence; grops will only interpret commands that begin with a ps: tag.

`\X'ps:execcode'` This executes the arbitrary PostScript commands in code. The PostScript currentpoint will be set to the position of the \nx command before executing code. The origin will be at the top left corner of the page, and y coordinates will increase down the page. A procedure u will be defined that converts groff units to the coordinate system in effect. For example,

```
\X'ps: exec \nx u 0 rlineto stroke'
```

will draw a horizontal line one inch long. code may make changes to the graphics state, but any changes will persist only to the end of the page. A dictionary containing the definitions specified by def and mdef will be on top of the dictionary stack. If your code adds definitions to this dictionary, you should allocate space for them using \X'ps:mdefn'. Any definitions will persist only until the end of the page. If you use the \Y escape sequence with an argument that names a macro, code can extend over multiple lines. For example,

```
.nr x 1i
.de y
ps: exec
\nx u 0 rlineto
stroke
..
\Yy
```

is another way to draw a horizontal line one inch long.

`\X'ps:filename'` This is the same as the exec command except that the PostScript code is read from file name.

`\X'ps:defcode'` Place a PostScript definition contained in code in the prologue. There should be at most one definition per \X command. Long definitions can be split over several \X commands; all the code arguments are simply joined together separated by newlines. The definitions are placed in a dictionary which is automatically pushed on the dictionary stack when an exec command is executed. If you use the \Y escape sequence with an argument that names a macro, code can extend over multiple lines.

<code>\X'ps:mdefncode'</code>	Like <code>def</code> , except that code may contain up to <code>n</code> definitions. <code>grops</code> needs to know how many definitions code contains so that it can create an appropriately sized PostScript dictionary to contain them.
<code>\X'ps:importfile 11x11yurxurywidth [height]'</code>	Import a PostScript graphic from <code>file</code> . The arguments <code>11x</code> , <code>11y</code> , <code>urx</code> , and <code>ury</code> give the bounding box of the graphic in the default PostScript coordinate system; they should all be integers; <code>11x</code> and <code>11y</code> are the <code>x</code> and <code>y</code> coordinates of the lower-left corner of the graphic; <code>urx</code> and <code>ury</code> are the <code>x</code> and <code>y</code> coordinates of the upper-right corner of the graphic; <code>width</code> and <code>height</code> are integers that give the desired width and height in <code>groff</code> units of the graphic. The graphic will be scaled so that it has this width and height and translated so that the lower-left corner of the graphic is located at the position associated with <code>\x</code> command. If the <code>height</code> argument is omitted, it will be scaled uniformly in the <code>x</code> and <code>y</code> directions so that it has the specified width. Note that the contents of the <code>\x</code> command are not interpreted by <code>troff</code> ; so vertical space for the graphic is not automatically added, and the <code>width</code> and <code>height</code> arguments are not allowed to have attached scaling indicators. If the PostScript file complies with the Adobe Document Structuring Conventions and contains a <code>%%BoundingBox</code> comment, then the bounding box can be automatically extracted from within <code>groff</code> by using the <code>sy</code> request to run the <code>psbb</code> command.

The `-mps` macros (which are automatically loaded when `grops` is run by the `groff` command) include a `PSPIC` macro that allows a picture to be easily imported. This has the format:

```
.PSPIC file [ -L j -R j -I n ][width [ height ]]
```

`file` is the name of the file containing the illustration; `width` and `height` give the desired width and height of the graphic. The `width` and `height` arguments may have scaling indicators attached; the default scaling indicator is `i`. This macro will scale the graphic uniformly in the `x` and `y` directions so that it is no more than `width` wide and `height` high. By default, the graphic will be horizontally centered. The `-L` and `-R` cause the graphic to be left-aligned and right-aligned, respectively. The `-I` option causes the graphic to be indented by `n`.

<code>\X'ps: invis', \X'ps: endinvis'</code>	No output will be generated for text and drawing commands that are bracketed with these <code>\X</code> commands. These commands are intended for use when output from <code>troff</code> will be previewed before being processed with <code>grops</code> ; if the previewer is unable to display certain characters or other constructs, then other substitute characters or constructs can be used for previewing by bracketing them with these <code>\X</code> commands.

For example, `gxditview` is not able to display a proper `\(em` character because the standard X11 fonts do not provide it; this problem can be overcome by executing the following request:

```
.char \(em \X'ps: invis'\
\Z'\v'-.25m'\h'.05m'\D'1 .9m 0'\h'.05m'\
\X'ps: endinvis'\(em
```

In this case, `gxditview` will be unable to display the `\(em` character and will draw the line, whereas `grops` will print the `\(em` character and ignore the line.

The input to `grops` must be in the format output by `gtroff(1)`. This is described in `groff_out(1)`. In addition, the device and font description files for the device used must meet certain requirements. The device and font description files supplied for `ps` device meet all these requirements. `afmtodit(1)` can be used to create font files from AFM files. The resolution must be an integer multiple of 72 times the `sizescale`. The `ps` device uses a resolution of 72000 and a `sizescale` of 1000. The device description file should contain a command:

```
paperlengthn
```

which says that output should be generated that is suitable for printing on a page whose length is `n` machine units. Each font description file must contain a command:

```
internalnamepsname
```

which says that the PostScript name of the font is `psname`. It may also contain a command:

```
encodingenc file
```

which says that the PostScript font should be reencoded using the encoding described in `enc_file`; this file should consist of a sequence of lines of the form:

```
pschar code
```

where `pschar` is the PostScript name of the character, and `code` is its position in the encoding expressed as a decimal integer. The code for each character given in the font file must correspond to the code for the character in encoding file, or to the code in the default encoding for the font if the PostScript font is not to be reencoded. This code can be used with the `\N` escape sequence in `troff` to select the character, even if the character does not have a `groff` name. Every character in the font file must exist in the PostScript font, and the widths given in the font file must match the widths used in the PostScript font. `grops` will assume that a character with a `groff` name of `space` is blank (makes no marks on the page); it can make use of such a character to generate more efficient and compact PostScript output.

`grops` can automatically include the downloadable fonts necessary to print the document. Any downloadable fonts which should, when required, be included by `grops` must be listed in the file `/usr/lib/groff/font/devps/download`; this should consist of lines of the form:

```
font filename
```

where `font` is the PostScript name of the font, and `filename` is the name of the file containing the font; lines beginning with `#` and blank lines are ignored; fields may be separated by tabs or spaces; `filename` will be searched for using the same mechanism that is used for `groff` font metric files. The download file itself will also be searched for using this mechanism.

If the file containing a downloadable font or imported document conforms to the Adobe Document Structuring Conventions, then `grops` will interpret any comments in the files sufficiently to ensure that its own output is conforming. It will also supply any needed font resources that are listed in the download file as well as any needed file resources. It is also able to handle interresource dependencies. For example, suppose that you have a downloadable font called Garamond, and also a downloadable font called Garamond-Outline that depends on Garamond (typically, it would be defined to copy Garamond's font dictionary, and change the `PaintType`), then it is necessary for Garamond to appear before Garamond-Outline in the PostScript document. `grops` will handle this automatically provided that the downloadable font file for Garamond-Outline indicates its dependence on Garamond by means of the Document Structuring Conventions, for example by beginning with the following lines:

```
%!PS-Adobe-3.0 Resource-Font
%%DocumentNeededResources: font Garamond
%%EndComments
%%IncludeResource: font Garamond
```

In this case, both Garamond and Garamond-Outline would need to be listed in the download file. A downloadable font should not include its own name in a `%%DocumentSuppliedResources` comment.

`grops` will not interpret `%%DocumentFonts` comments.

The `%%DocumentNeededResources`, `%%DocumentSuppliedResources`, `%%IncludeResource`, `%%BeginResource`, and `%%EndResource` comments (or possibly the old `%%DocumentNeededFonts`, `%%DocumentSuppliedFonts`, `%%IncludeFont`, `%%BeginFont`, and `%%EndFont` comments) should be used.

FILES

<code>/usr/lib/groff/font/devps/DESC</code>	Device description file
<code>/usr/lib/groff/font/devps/F</code>	Font description file for font <i>F</i>
<code>/usr/lib/groff/font/devps/download</code>	List of downloadable fonts.
<code>/usr/lib/groff/font/devps/text.enc</code>	Encoding used for text fonts
<code>/usr/lib/groff/tmac/tmac.ps</code>	Macros for use with <code>grops</code> ; automatically loaded by <code>troffrc</code>
<code>/usr/lib/groff/tmac/tmac.pspic</code>	Definition of <code>PSPIC</code> macro, automatically loaded by <code>tmac.ps</code>
<code>/usr/lib/groff/tmac/tmac.psold</code>	Macros to disable use of characters not present in older PostScript printers; automatically loaded by <code>tmac.ps</code>
<code>/usr/lib/groff/tmac/tmac.psnew</code>	Macros to undo the effect of <code>tmac.psold</code>
<code>/tmp/gropsXXXXXX</code>	Temporary file

SEE ALSO

afmtodit(1), groff(1), gtroff(1), psbb(1), groff_out(5), groff_font(5), groff_char(7)

Groff Version 1.09, 14 February 1995

grotty

grotty—groff driver for typewriter-like devices

SYNOPSIS

```
grotty [ -hfbuodBUv ][-Fdir ][files ... ]
```

DESCRIPTION

grotty translates the output of GNU troff into a form suitable for typewriter-like devices. Normally, grotty should be invoked by using the groff command with a -Tascii or -Tlatin1 option. If no files are given, grotty will read the standard input. A filename of - will also cause grotty to read the standard input. Output is written to the standard output.

Normally, grotty prints a bold character *c* using the sequence '*c* BACKSPACE *c*' and an italic character *c* by the sequence '*c* BACKSPACE *c*'. These sequences can be displayed on a terminal by piping through u1(1). Pagers such as more(1) or less(1) are also able to display these sequences. Use either -B or -U when piping into less(1); use -b when piping into more(1). There is no need to filter the output through col(1) since grotty never outputs reverse line feeds.

The font description file may contain a command:

```
internalnamen
```

where *n* is a decimal integer. If the 01 bit in *n* is set, then the font will be treated as an italic font; if the 02 bit is set, then it will be treated as a bold font. The code field in the font description field gives the code that will be used to output the character. This code can also be used in the \N escape sequence in troff.

OPTIONS

- Fdir Search the directory *dir*/devname for font and device description files; *name* is the name of the device, usually ascii or latin1.
- h Use horizontal tabs in the output. Tabs are assumed to be set every 8 columns.
- f Use form feeds in the output. A form feed will be output at the end of each page that has no output on its last line.
- b Suppress the use of overstriking for bold characters.
- u Suppress the use of underlining for italic characters.
- B Use only overstriking for bold-italic characters.
- U Use only underlining for bold-italic characters.
- o Suppress overstriking (other than for bold or underlined characters).
- d Ignore all \D commands. Without this, grotty will render \D'1 ...' commands that have at least one zero argument (and so are either horizontal or vertical) using -, !, and + characters.
- v Print the version number.

FILES

/usr/lib/groff/font/devascii/DESC	Device description file for ascii device.
/usr/lib/groff/font/devascii/F	Font description file for font <i>F</i> of ascii device.
/usr/lib/groff/font/devlatin1/DESC	Device description file for latin1 device.
/usr/lib/groff/font/devlatin1/F	Font description file for font <i>F</i> of latin1 device.
/usr/lib/groff/tmac/tmac.tty	Macros for use with grotty.
/usr/lib/groff/tmac/tmac.tty-char	Additional kludgy character definitions for use with grotty.

BUGS

groff is intended only for simple documents.

There is no support for fractional horizontal or vertical motions.

There is no support for \D commands other than horizontal and vertical lines.

Characters above the first line (that is, with a vertical position of 0) cannot be printed.

SEE ALSO

groff(1), gtroff(1), groff_out(5), groff_font(5), groff_char(7), ul(1), more(1), less(1)

Groff Version 1.09, 14 February 1995

gsoelim

gsoelim—Interpret .so requests in groff input

SYNOPSIS

gsoelim [-Cv][files ...]

DESCRIPTION

gsoelim reads files and replaces lines of the form

.sofile

by the contents of file. It is useful if files included with so need to be preprocessed. Normally, gsoelim should be invoked with the -s option of groff.

OPTIONS

-c Recognize .so even when followed by a character other than space or newline
-v Print the version number

SEE ALSO

groff(1)

Groff Version 1.09, 15 September 1992

gtbl

gtbl—Format tables for troff

SYNOPSIS

gtbl [-Cv][files ...]

DESCRIPTION

This manual page describes the GNU version of tbl, which is part of the groff document formatting system. tbl compiles descriptions of tables embedded within troff input files into commands that are understood by troff. Normally, it should be invoked using the -t option of groff. It is highly compatible with UNIX tbl. The output generated by GNU tbl cannot be processed with UNIX troff; it must be processed with GNU troff. If no files are given on the command line, the standard input will be read. A filename of - will cause the standard input to be read.

OPTIONS

- c Recognize .TS and .TE even when followed by a character other than space or newline
- v Print the version number

USAGE

Only the differences between GNU `tbl` and UNIX `tbl` are described here.

Normally, `tbl` attempts to prevent undesirable breaks in the table by using diversions. This can sometimes interact badly with macro packages' own use of diversions, when footnotes, for example, are used. The `nokeep` option tells `tbl` not to try to prevent breaks in this way.

The `decimalpoint` option specifies the character to be recognized as the decimal point character in place of the default period. It takes an argument in parentheses, which must be a single character, as for the `tab` option.

The `f` format modifier can be followed by an arbitrary length font name in parentheses.

There is a `d` format modifier that means that a vertically spanning entry should be aligned at the bottom of its range.

There is no limit on the number of columns in a table, nor any limit on the number of text blocks. All the lines of a table are considered in deciding column widths, not just the first 200. Table continuation (`.T&`) lines are not restricted to the first 200 lines.

Numeric and alphabetic items may appear in the same column.

Numeric and alphabetic items may span horizontally.

`tbl` uses register, string, macro and diversion names beginning with `3`. When using `tbl`, you should avoid using any names beginning with a `3`.

BUGS

You should use `.TSH/.TH` in conjunction with a supporting macro package for *all* multipage boxed tables. If there is no header that you want to appear at the top of each page of the table, place the `.TH` line immediately after the format section. Do not enclose a multipage table within `keep/release` macros, or divert it in any other way.

A text block within a table must be able to fit on one page.

The `bp` request cannot be used to force a page-break in a multipage table. Instead, define `BP` as follows:

```
.de BP
.ie '\n(.z" .bp \\$1
.el \!.BP \\$1
..
```

and use `BP` instead of `bp`.

SEE ALSO

`groff(1)`, `gtroff(1)`

Groff Version 1.09, 1 April 1993

gtroff

gtroff—Format documents

SYNOPSIS

```
gtroff [-abivzCER] [-w name] [-W name] [-d cs] [-f fam] [-m name] [-n num] [-o list] [-r cn] [-T name] [-F dir] [-M dir] [nfiles...n]
```

DESCRIPTION

This manual page describes the GNU version of `troff`, which is part of the `groff` document formatting system. It is highly compatible with UNIX `troff`. Usually, it should be invoked using the `groff` command, which will also run preprocessors and postprocessors in the appropriate order and with the appropriate options.

OPTIONS

<code>-a</code>	Generate an ASCII approximation of the typeset output.
<code>-b</code>	Print a backtrace with each warning or error message. This backtrace should help track down the cause of the error. The line numbers given in the backtrace may not always correct: <code>troff</code> 's idea of line numbers gets confused by <code>as</code> or <code>am</code> requests.
<code>-i</code>	Read the standard input after all the named input files have been processed.
<code>-v</code>	Print the version number.
<code>-wname</code>	Enable warning name. Available warnings are described in the “Warnings” subsection as follows. Multiple <code>-w</code> options are allowed.
<code>-Wname</code>	Inhibit warning name. Multiple <code>-W</code> options are allowed.
<code>-E</code>	Inhibit all error messages.
<code>-z</code>	Suppress formatted output.
<code>-C</code>	Enable compatibility mode.
<code>-dcs, -dname=s</code>	Define <code>c</code> or <code>name</code> to be a string <code>s</code> ; <code>c</code> must be a one-letter name.
<code>-ffam</code>	Use <code>fam</code> as the default font family.
<code>-mname</code>	Read in the file <code>tmac.name</code> . Normally, this will be searched for in <code>/usr/lib/groff/tmac</code> .
<code>-R</code>	Don't load <code>troffrc</code> .
<code>-nnum</code>	Number the first page <code>num</code> .
<code>-olist</code>	Output only pages in <code>list</code> , which is a comma-separated list of page ranges; <code>n</code> means print page <code>n</code> , <code>m-n</code> means print every page between <code>m</code> and <code>n</code> , <code>-n</code> means print every page up to <code>n</code> , <code>n-</code> means print every page from <code>n</code> . <code>Troff</code> will exit after printing the last page in the list.
<code>-rcn, -rname=n</code>	Set number register <code>c</code> or <code>name</code> to <code>n</code> ; <code>c</code> must be a one-character name; <code>n</code> can be any <code>troff</code> numeric expression.
<code>-Tname</code>	Prepare output for device <code>name</code> , rather than the default <code>ps</code> .
<code>-Fdir</code>	Search <code>dir</code> for subdirectories <code>devname</code> (<code>name</code> is the name of the device) for the <code>DESC</code> file and font files before the normal <code>/usr/lib/groff/font</code> .
<code>-Mdir</code>	Search directory <code>dir</code> for macro files before the normal <code>/usr/lib/groff/tmac</code> .

USAGE

Only the features not in UNIX `troff` are described here.

LONG NAMES

The names of number registers, fonts, strings/macros/diversions, special characters can be of any length. In escape sequences, where you can use `{xx}` for a two-character name, you can use `[xxx]` for a name of arbitrary length:

<code>\[xxx]</code>	Print the special character called <code>xxx</code> .
<code>\f[xxx]</code>	Set font <code>xxx</code> .
<code>*[xxx]</code>	Interpolate string <code>xxx</code> .
<code>\n[xxx]</code>	Interpolate number register <code>xxx</code> .

FRACTIONAL POINT SIZES

A scaled point is equal to `1/sizescale` points, where `sizescale` is specified in the `DESC` file (1 by default.) There is a new scale indicator `z` that has the effect of multiplying by `sizescale`. Requests and escape sequences in `troff` interpret arguments that represent a point size as being in units of scaled points, but they evaluate each such argument using a default scale indicator

of `z`. Arguments treated in this way are the argument to the `ps` request, the third argument to the `cs` request, the second and fourth arguments to the `tkf` request, the argument to the `\H` escape sequence, and those variants of the `\s` escape sequence that take a numeric expression as their argument.

For example, suppose `sizescale` is 1,000; then a scaled point will be equivalent to a millipoint; the request `.ps 10.25` is equivalent to `.ps 10.25z`, and so sets the point size to 10,250 scaled points, which is equal to 10.25 points.

The number register `\n(.s` returns the point size in points as decimal fraction. There is also a new number register `\n[.ps]` that returns the point size in scaled points.

It would make no sense to use the `z` scale indicator in a numeric expression whose default scale indicator was neither `u` nor `z`, and so `troff` disallows this. Similarly, it would make no sense to use a scaling indicator other than `z` or `u` in a numeric expression whose default scale indicator was `z`, and so `troff` disallows this as well.

There is also new scale indicator `s` that multiplies by the number of units in a scaled point. So, for example, `\n[.ps]s` is equal to `1m`. Be sure not to confuse the `s` and `z` scale indicators.

NUMERIC EXPRESSIONS

Spaces are permitted in a number expression within parentheses.

`M` indicates a scale of hundredths of an em.

`e1>?e2` The maximum of `e1` and `e2`.

`e1<?e2` The minimum of `e1` and `e2`.

`(c;e)` Evaluate `e` using `c` as the default scaling indicator. If `c` is missing, ignore scaling indicators in the evaluation of `e`.

NEW ESCAPE SEQUENCES

`\A'anything'` This expands to 1 or 0 according to whether `anything` is or is not acceptable as the name of a string, macro, diversion, number register, environment, or font. It will return 0 if `anything` is empty. This is useful if you want to look up user input in some sort of associative table.

`\C'xxx'` Typeset character named `xxx`. Normally it is more convenient to use `\[xxx]`. But `\C` has the advantage that it is compatible with recent versions of UNIX and is available in compatibility mode.

`\E` This is equivalent to an escape character, but it's not interpreted in copy mode. For example, strings to start and end superscripting could be defined like this:

```
.ds { \v'-.3m'\s'\En[.s]*6u/10u'
.ds { \s0\v'-.3m'
```

The use of `\E` ensures that these definitions will work even if `\*f` gets interpreted in copy-mode (for example, by being used in a macro argument).

`\N'n'` Typeset the character with code `n` in the current font. `n` can be any integer. Most devices only have characters with codes between 0 and 255. If the current font does not contain a character with that code, special fonts will *not* be searched. The `\N` escape sequence can be conveniently used on conjunction with the `char` request:

```
.char \[phone] \f(ZDn'37'
```

The code of each character is given in the fourth column in the font description file after the `charset` command. It is possible to include unnamed characters in the font description file by using a name of `—`; the `\N` escape sequence is the only way to use these.

`\R'namen'` This has the same effect as `.nrnamen`

`\s{nn` Set the point size to `nn` points; `nn` must be exactly two digits.

`\s[n], \s'n'` Set the point size to `n` scaled points; `n` is a numeric expression with a default scale indicator of `z`.

`\Vx\V(xx \V[xxx]` Interpolate the contents of the environment variable `xxx`, as returned by `getenv(3)`. `\V` is interpreted in copy-mode.

<code>\Yx\Y(xx \Y[xxx]</code>	This is approximately equivalent to <code>\X'*[xxx]'</code> . However, the contents of the string or macro <code>xxx</code> are not interpreted; also, it is permitted for <code>xxx</code> to have been defined as a macro and thus contain newlines (it is not permitted for the argument to <code>\X</code> to contain newlines). The inclusion of newlines requires an extension to the UNIX troff output format and will confuse drivers that do not know about this extension.
<code>\Z'anything'</code>	Print anything and then restore the horizontal and vertical position; anything may not contain tabs or leaders.
<code>\\$0</code>	The name by which the current macro was invoked. The <code>a1s</code> request can make a macro have more than one name.
<code>\\$*</code>	In a macro, the concatenation of all the arguments separated by spaces.
<code>\\$@</code>	In a macro, the concatenation of all the arguments with each surrounded by double quotes, and separated by spaces.
<code>\\$(nn, \\$[nnn]</code>	In a macro, this gives the <code>n</code> th or <code>nn</code> th argument. Macros can have an unlimited number of arguments.
<code>\?anything\?</code>	When used in a diversion, this will transparently embed anything in the diversion. anything is read in copy mode. When the diversion is reread, anything will be interpreted. anything may not contain newlines; use <code>\!</code> if you want to embed newlines in a diversion. The escape sequence <code>\?</code> is also recognized in copy mode and turned into a single internal code; it is this code that terminates anything. Thus <pre>.nr x 1 .nf .di d \?\\?\\ \\?\\ \\ \\ \\nx\\ \\?\\!\\?\\ .di .nr x 2 .di e .d .di .nr x 3 .di f .e .di .nr x 4 .f</pre> will print 4.
<code>\/</code>	This increases the width of the preceding character so that the spacing between that character and the following character will be correct if the following character is a Roman character. For example, if an italic <i>f</i> is immediately followed by a Roman right parenthesis, then in many fonts the top right portion of the <i>f</i> will overlap the top left of the right parenthesis, producing <i>f)</i> , which is ugly. Inserting <code>\/</code> produces and avoids this problem. It is a good idea to use this escape sequence whenever an italic character is immediately followed by a Roman character without any intervening space.
<code>\,</code>	This modifies the spacing of the following character so that the spacing between that character and the preceding character will correct if the preceding character is a Roman character. For example, inserting <code>\,</code> between the parenthesis and the <i>f</i> changes to (<i>f</i>). It is a good idea to use this escape sequence whenever a Roman character is immediately followed by an italic character without any intervening space.
<code>\)</code>	Like <code>\&</code> except that it behaves like a character declared with the <code>cf1ags</code> request to be transparent for the purposes of end-of-sentence recognition.
<code>\~</code>	This produces an unbreakable space that stretches like a normal interword space when a line is adjusted.
<code>\#</code>	Everything up to and including the next newline is ignored. This is interpreted in copy mode. This is like <code>\%</code> except that <code>\%</code> does not ignore the terminating newline.

NEW REQUESTS

<code>.alnxyy</code>	Create an alias <code>xx</code> for number register object named <code>yy</code> . The new name and the old name will be exactly equivalent. If <code>yy</code> is undefined, a warning of type <code>reg</code> will be generated, and the request will be ignored.
<code>.alsxyy</code>	Create an alias <code>xx</code> for request, string, macro, or diversion object named <code>yy</code> . The new name and the old name will be exactly equivalent (it is similar to a hard rather than a soft link). If <code>yy</code> is undefined, a warning of type <code>mac</code> will be generated, and the request will be ignored. The <code>de</code> , <code>am</code> , <code>di</code> , <code>da</code> , <code>ds</code> , and <code>as</code> requests only create a new object if the name of the macro, diversion, or string diversion is currently undefined or if it is defined to be a request; normally, they modify the value of an existing object.
<code>.asciifyxx</code>	This request only exists in order to make it possible to make certain gross hacks work with GNU troff. It unformats the diversion <code>xx</code> in such a way that ASCII characters that were formatted and diverted into <code>xx</code> will be treated like ordinary input characters when <code>xx</code> is reread. For example, this: <pre>.tr @. .di x @nr\n\1 .br .di .tr @@ .asciify x .x</pre> will set register <code>n</code> to 1.
<code>.backtrace</code>	Print a backtrace of the input stack on <code>stderr</code> .
<code>.break</code>	Break out of a <code>while</code> loop. See also the <code>while</code> and <code>continue</code> requests. Be sure not to confuse this with the <code>br</code> request.
<code>.cflagsnc1c2...</code>	Characters <code>c1</code> , <code>c2</code> , ... have properties determined by <code>n</code> , which is <code>ored</code> from the following.
1	The character ends sentences. (Initially, characters <code>.?!</code> have this property.)
2	Lines can be broken before the character (initially, no characters have this property); a line will not be broken at a character with this property unless the characters on each side both have nonzero hyphenation codes.
4	Lines can be broken after the character (initially, characters <code>-(hy\ (em</code> have this property); a line will not be broken at a character with this property unless the characters on each side both have nonzero hyphenation codes.
8	The character overlaps horizontally (initially, characters <code>\(u1\ (rn\ (ru</code> have this property).
16	The character overlaps vertically (initially, character <code>\(br</code> has this property).
32	An end-of-sentence character followed by any number of characters with this property will be treated as the end of a sentence if followed by a newline or two spaces; in other words, the character is transparent for the purposes of end-of-sentence recognition; this is the same as having a zero space factor in TeX (initially, characters <code>')]*\ (dg\ (rq</code> have this property).
<code>.charcstring</code>	Define character <code>c</code> to be <code>string</code> . Every time character <code>c</code> needs to be printed, <code>string</code> will be processed in a temporary environment and the result will be wrapped up into a single object. Compatibility mode will be turned off and the escape character will be set to <code>\</code> while <code>string</code> is being processed. Any emboldening, constant spacing, or track kerning will be applied to this object rather than to individual characters in <code>string</code> . A character defined by this request can be used just like a normal character provided by the output device. In particular, other characters can be translated to it with the <code>tr</code> request; it can be made the leader character by the <code>lc</code> request; repeated patterns can be drawn with the character by using the <code>\1</code> and <code>\L</code> escape sequences; words containing the character can be hyphenated correctly, if the <code>hcode</code> request is used to give the character a hyphenation code. There is a special antirecursion feature: Use of character within the character's definition will be handled like normal characters not defined with <code>char</code> . A character definition can be removed with the <code>rchar</code> request.

<code>.chopxx</code>	Chop the last character off macro, string, or diversion <code>xx</code> . This is useful for removing the newline from the end of diversions that are to be interpolated as strings.
<code>.closestream</code>	Close the stream named <code>stream</code> ; <code>stream</code> will no longer be an acceptable argument to the <code>write</code> request. See the <code>open</code> request.
<code>.continue</code>	Finish the current iteration of a <code>while</code> loop. See also the <code>while</code> and <code>break</code> requests.
<code>.cpn</code>	If <code>n</code> is nonzero or missing, enable compatibility mode; otherwise, disable it. In compatibility mode, long names are not recognized, and the incompatibilities caused by long names do not arise.
<code>.doxxx</code>	Interpret <code>.xxx</code> with compatibility mode disabled. For example, <code>.do fam T</code> would have the same effect as <code>.fam T</code> except that it would work even if compatibility mode had been enabled. Note that the previous compatibility mode is restored before any files sourced by <code>xxx</code> are interpreted.
<code>.famxx</code>	Set the current font family to <code>xx</code> . The current font family is part of the current environment. See the description of the <code>sty</code> request for more information on font families.
<code>.fspecialfs1s2 ...</code>	When the current font is <code>f</code> , fonts <code>s1</code> , <code>s2</code> , ... will be special; that is, they will be searched for characters not in the current font. Any fonts specified in the <code>special</code> request will be searched after fonts specified in the <code>fspecial</code> request.
<code>.ftrfg</code>	Translate font <code>f</code> to <code>g</code> . Whenever a font named <code>f</code> is referred to in <code>\f</code> escape sequence, or in the <code>ft</code> , <code>ul</code> , <code>bd</code> , <code>cs</code> , <code>tkf</code> , <code>special</code> , <code>fspecial</code> , <code>fp</code> , or <code>sty</code> requests, font <code>g</code> will be used. If <code>g</code> is missing, or equal to <code>f</code> , then font <code>f</code> will not be translated.
<code>.hcodec1code1c2code2...</code>	Set the hyphenation code of character <code>c1</code> to <code>code1</code> and that of <code>c2</code> to <code>code2</code> . A hyphenation code must be a single input character (not a special character) other than a digit or a space. Initially, each lowercase letter has a hyphenation code, which is itself, and each uppercase letter has a hyphenation code which is the lowercase version of itself. See also the <code>hpf</code> request.
<code>.h1a1ang</code>	Set the current hyphenation language to <code>lang</code> . Hyphenation exceptions specified with the <code>hw</code> request and hyphenation patterns specified with the <code>hpf</code> request are both associated with the current hyphenation language. The <code>h1a</code> request is usually invoked by the <code>troffrc</code> file.
<code>.h1mn</code>	Set the maximum number of consecutive hyphenated lines to <code>n</code> . If <code>n</code> is negative, there is no maximum. The default value is <code>-1</code> . This value is associated with the current environment. Only lines output from an environment count towards the maximum associated with that environment. Hyphens resulting from <code>\%</code> are counted; explicit hyphens are not.
<code>.hpffile</code>	Read hyphenation patterns from <code>file</code> ; this will be searched for in the same way that <code>tmac.name</code> is searched for when the <code>-mname</code> option is specified. It should have the same format as the argument to the <code>\patterns</code> primitive in TeX; the letters appearing in this file are interpreted as hyphenation codes. A <code>%</code> character in the patterns file introduces a comment that continues to the end of the line. The set of hyphenation patterns is associated with the current language set by the <code>h1a</code> request. The <code>hpf</code> request is usually invoked by the <code>troffrc</code> file.
<code>.hymn</code>	Set the hyphenation margin to <code>n</code> : when the current adjustment mode is not <code>b</code> , the line will not be hyphenated if the line is no more than <code>n</code> short. The default hyphenation margin is <code>0</code> . The default scaling indicator for this request is <code>m</code> . The hyphenation margin is associated with the current environment. The current hyphenation margin is available in the <code>\n[.hym]</code> register.
<code>.hysn</code>	Set the hyphenation space to <code>n</code> : when the current adjustment mode is <code>b</code> , don't hyphenate the line if the line can be justified by adding no more than <code>n</code> extra space to each word space. The default hyphenation space is <code>0</code> . The default scaling indicator for this request is <code>m</code> . The hyphenation space is associated with the current environment. The current hyphenation space is available in the <code>\n[.hys]</code> register.
<code>.kernn</code>	If <code>n</code> is nonzero or missing, enable pairwise kerning; otherwise, disable it.
<code>.msofile</code>	The same as the <code>so</code> request except that <code>file</code> is searched for in the same way that <code>tmac.name</code> is searched for when the <code>-mname</code> option is specified.
<code>.nroff</code>	Make the <code>n</code> built-in condition true and the <code>t</code> built-in condition false. This can be reversed using the <code>troff</code> request.
<code>.openstreamfilename</code>	Open <code>filename</code> for writing and associate the stream named <code>stream</code> with it. See also the <code>close</code> and <code>write</code> requests.

<code>.openstreamfilename</code>	Like <code>open</code> , but if <code>filename</code> exists, append to it instead of truncating it.
<code>.pnr</code>	Print the names and contents of all currently defined number registers on <code>stderr</code> .
<code>.psocommand</code>	This behaves like the <code>so</code> request except that input comes from the standard output of <code>command</code> .
<code>.ptr</code>	Print the names and positions of all traps (not including input line traps and diversion traps) on <code>stderr</code> . Empty slots in the page trap list are printed as well, because they can affect the priority of subsequently planted traps.
<code>.rcharc1c2...</code>	Remove the definitions of characters <code>c1</code> , <code>c2</code> , ... This undoes the effect of a <code>char</code> request.
<code>.rj, .rjn</code>	Right justify the next <code>n</code> input lines. Without an argument, right justify the next input line. The number of lines to be right justified is available in the <code>\n[.rj]</code> register. This implicitly does <code>.ce0</code> . The <code>ce</code> request implicitly does <code>.rj0</code> .
<code>.rnnxxyy</code>	Rename number register <code>xx</code> to <code>yy</code> .
<code>.shcc</code>	Set the soft hyphen character to <code>c</code> . If <code>c</code> is omitted, the soft hyphen character will be set to the default <code>\(hy</code> . The soft hyphen character is the character that will be inserted when a word is hyphenated at a line break. If the soft hyphen character does not exist in the font of the character immediately preceding a potential break point, then the line will not be broken at that point. Neither definitions (specified with the <code>char</code> request) nor translations (specified with the <code>tr</code> request) are considered when finding the soft hyphen character.
<code>.shiftn</code>	In a macro, shift the arguments by <code>n</code> positions: argument <code>i</code> becomes argument <code>i-n</code> ; arguments <code>1</code> to <code>n</code> will no longer be available. If <code>n</code> is missing, arguments will be shifted by <code>1</code> . Shifting by negative amounts is currently undefined.
<code>.specialsis2...</code>	Fonts <code>s1</code> , <code>s2</code> are special and will be searched for characters not in the current font.
<code>.stynf</code>	Associate style <code>f</code> with font position <code>n</code> . A font position can be associated either with a font or with a style. The current font is the index of a font position and so is also either a font or a style. When it is a style, the font that is actually used is the font the name of which is the concatenation of the name of the current family and the name of the current style. For example, if the current font is <code>1</code> and font position <code>1</code> is associated with style <code>R</code> and the current font family is <code>T</code> , then font <code>TR</code> will be used. If the current font is not a style, then the current family is ignored. When the requests <code>cs</code> , <code>bd</code> , <code>tkf</code> , <code>uf</code> , or <code>fspecial</code> are applied to a style, then they will instead be applied to the member of the current family corresponding to that style. The default family can be set with the <code>-f</code> option. The <code>styles</code> command in the <code>DESC</code> file controls which font positions (if any) are initially associated with styles rather than fonts.
<code>.tkffs1n1s2n2</code>	Enable track kerning for font <code>f</code> . When the current font is <code>f</code> , the width of every character will be increased by an amount between <code>n1</code> and <code>n2</code> ; when the current point size is less than or equal to <code>s1</code> , the width will be increased by <code>n1</code> ; when it is greater than or equal to <code>s2</code> , the width will be increased by <code>n2</code> ; when the point size is greater than or equal to <code>s1</code> and less than or equal to <code>s2</code> , the increase in width is a linear function of the point size.
<code>.trffilename</code>	Transparently output the contents of file <code>filename</code> . Each line is output as it would be were it preceded by <code>\!</code> ; however, the lines are not subject to copy-mode interpretation. If the file does not end with a newline, then a newline will be added. For example, you can define a macro <code>x</code> containing the contents of file <code>f</code> , using <pre>.dix .trff .di</pre> Unlike with the <code>cf</code> request, the file cannot contain characters such as <code>NUL</code> that are not legal <code>troff</code> input characters.
<code>.trnt abcd</code>	This is the same as the <code>tr</code> request except that the translations do not apply to text that is transparently throughput into a diversion with <code>\!</code> . For example, <pre>.tr ab .di x \!.tm a</pre>

	<code>.di</code> <code>.x</code>	will print <code>b</code> ; if <code>trnt</code> is used instead of <code>tr</code> , it will print <code>a</code> .
<code>.troff</code>		Make the <code>n</code> built-in condition false, and the <code>t</code> built-in condition true. This undoes the effect of the <code>nroff</code> request.
<code>.vp tn</code>		Enable vertical position traps if <code>n</code> is nonzero, disable them otherwise. Vertical position traps are traps set by the <code>wh</code> or <code>dt</code> requests. Traps set by the <code>it</code> request are not vertical position traps. The parameter that controls whether vertical position traps are enabled is global. Initially, vertical position traps are enabled.
<code>.warn n</code>		Control warnings. <code>n</code> is the sum of the numbers associated with each warning that is to be enabled; all other warnings will be disabled. The number associated with each warning is listed in the “Warnings” subsection. For example, <code>.warn 0</code> will disable all warnings, and <code>.warn 1</code> will disable all warnings except that about missing characters. If <code>n</code> is not given, all warnings will be enabled.
<code>.while anything</code>		While condition <code>c</code> is true, accept anything as input; <code>c</code> can be any condition acceptable to an <code>if</code> request; anything can comprise multiple lines if the first line starts with <code>\{</code> and the last line ends with <code>\}</code> . See also the <code>break</code> and <code>continue</code> requests.
<code>.writestream anything</code>		Write anything to the stream named <code>stream</code> . <code>stream</code> must previously have been the subject of an open request. anything is read in copy mode; a leading will be stripped.

EXTENDED REQUESTS

<code>.cfilename</code>	When used in a diversion, this will embed in the diversion an object which, when reread, will cause the contents of <code>filename</code> to be transparently copied through to the output. In UNIX <code>troff</code> , the contents of <code>filename</code> are immediately copied through to the output regardless of whether there is a current diversion; this behavior is so anomalous that it must be considered a bug.
<code>.evxx</code>	If <code>xx</code> is not a number, this will switch to a named environment called <code>xx</code> . The environment should be popped with a matching <code>ev</code> request without any arguments, just as for numbered environments. There is no limit on the number of named environments; they will be created the first time that they are referenced.
<code>.fpnf1f2</code>	The <code>fp</code> request has an optional third argument. This argument gives the external name of the font, which is used for finding the font description file. The second argument gives the internal name of the font, which is used to refer to the font in <code>troff</code> after it has been mounted. If there is no third argument, then the internal name will be used as the external name. This feature allows you to use fonts with long names in compatibility mode.
<code>.ssmn</code>	When two arguments are given to the <code>ss</code> request, the second argument gives the sentence space size. If the second argument is not given, the sentence space size will be the same as the word space size. Like the word space size, the sentence space is in units of one twelfth of the <code>spacewidth</code> parameter for the current font. Initially, both the word space size and the sentence space size are 12. The sentence space size is used in two circumstances: If the end of a sentence occurs at the end of a line in fill mode, then both an interword space and a sentence space will be added; if two spaces follow the end of a sentence in the middle of a line, then the second space will be a sentence space. Note that the behavior of UNIX <code>troff</code> will be exactly that exhibited by GNU <code>troff</code> if a second argument is never given to the <code>ss</code> request. In GNU <code>troff</code> , as in UNIX <code>troff</code> , you should always follow a sentence with either a newline or two spaces.
<code>.tan1n2...nnTr1r2...rn</code>	Set tabs at positions <code>n1</code> , <code>n2</code> , ..., <code>nn</code> and then set tabs at <code>nn+r1</code> , <code>nn+r2</code> , ..., <code>nn+rn</code> and then at <code>nn+rn+r1</code> , <code>nn+rn+r2</code> , ..., <code>nn+rn+rn</code> , and so on. For example, <code>.ta T .5i</code> will set tabs every half an inch.

<code>\n[.fam]</code>	The current font family. This is a string-valued register.
<code>\n[.fp]</code>	The number of the next free font position.
<code>\n[.g]</code>	Always 1. Macros should use this to determine whether they are running under GNU troff.
<code>\n[.h1a]</code>	The current hyphenation language as set by the <code>h1a</code> request.
<code>\n[.h1c]</code>	The number of immediately preceding consecutive hyphenated lines.
<code>\n[.h1m]</code>	The maximum allowed number of consecutive hyphenated lines, as set by the <code>h1m</code> request.
<code>\n[.hy]</code>	The current hyphenation flags (as set by the <code>hy</code> request.)
<code>\n[.hym]</code>	The current hyphenation margin (as set by the <code>hym</code> request.)
<code>\n[.hys]</code>	The current hyphenation space (as set by the <code>hys</code> request.)
<code>\n[.in]</code>	The indent that applies to the current output line.
<code>\n[.kern]</code>	1 if pairwise kerning is enabled, 0 otherwise.
<code>\n[.lg]</code>	The current ligature mode (as set by the <code>lg</code> request.)
<code>\n[.ll]</code>	The line length that applies to the current output line.
<code>\n[.lt]</code>	The title length as set by the <code>lt</code> request.
<code>\n[.ne]</code>	The amount of space that was needed in the last <code>ne</code> request that caused a trap to be sprung. Useful in conjunction with the <code>\n[.trunc]</code> register.
<code>\n[.pn]</code>	The number of the next page: either the value set by a <code>pn</code> request, or the number of the current page plus 1.
<code>\n[.ps]</code>	The current pointsize in scaled points.
<code>\n[.psr]</code>	The last requested pointsize in scaled points.
<code>\n[.rj]</code>	The number of lines to be right-justified as set by the <code>rj</code> request.
<code>\n[.sr]</code>	The last requested pointsize in points as a decimal fraction. This is a string-valued register.
<code>\n[.tabs]</code>	A string representation of the current tab settings suitable for use as an argument to the <code>ta</code> request.
<code>\n[.trunc]</code>	The amount of vertical space truncated by the most recently sprung vertical position trap, or, if the trap was sprung by an <code>ne</code> request, minus the amount of vertical motion produced by the <code>ne</code> request. In other words, at the point a trap is sprung, it represents the difference of what the vertical position would have been but for the trap, and what the vertical position actually is. Useful in conjunction with the <code>\n[.ne]</code> register.
<code>\n[.ss]</code>	These give the values of the parameters set by the first and second arguments of the <code>ss</code> request.
<code>\n[.sss]</code>	
<code>\n[.vpt]</code>	1 if vertical position traps are enabled, 0 otherwise.
<code>\n[.warn]</code>	The sum of the numbers associated with each of the currently enabled warnings. The number associated with each warning is listed in the “Warnings” subsection.
<code>\n(.x</code>	The major version number. For example, if the version number is 1.03 then <code>\n(.x</code> will contain 1.
<code>\n(.y</code>	The minor version number. For example, if the version number is 1.03 then <code>\n(.y</code> will contain 03.

The following registers are set by the `\w` escape sequence:

<code>\n[rst]</code>	
<code>\n[rsb]</code>	Like the <code>st</code> and <code>sb</code> registers, but takes account of the heights and depths of characters.
<code>\n[ssc]</code>	The amount of horizontal space (possibly negative) that should be added to the last character before a subscript.
<code>\n[skw]</code>	How far to right of the center of the last character in the <code>\w</code> argument, the center of an accent from a roman font should be placed over that character.

The following read/write number registers are available:

<code>\n[systat]</code>	The return value of the <code>system()</code> function executed by the last <code>sy</code> request.
<code>\n[slimit]</code>	If greater than 0, the maximum number of objects on the input stack. If less than or equal to 0, there is no limit on the number of objects on the input stack. With no limit, recursion can continue until virtual memory is exhausted.

MISCELLANEOUS

Fonts not listed in the `DESC` file are automatically mounted on the next available font position when they are referenced.

If a font is to be mounted explicitly with the `fp` request on an unused font position, it should be mounted on the first unused font position, which can be found in the `\n[.fp]` register; although `troff` does not enforce this strictly, it will not allow a font to be mounted at a position whose number is much greater than that of any currently used position.

Interpolating a string does not hide existing macro arguments. Thus in a macro, a more efficient way of doing

```
.xx\|$@
```

is

```
\*[xx]\|
```

If the font description file contains pairwise kerning information, characters from that font will be kerned. Kerning between two characters can be inhibited by placing a `&` between them.

In a string comparison in a condition, characters that appear at different input levels to the first delimiter character will not be recognized as the second or third delimiters. This applies also to the `t1` request. In a `\w` escape sequence, a character that appears at a different input level to the starting delimiter character will not be recognized as the closing delimiter character. When decoding a macro argument that is delimited by double quotes, a character that appears at a different input level to the starting delimiter character will not be recognized as the closing delimiter character. The implementation of `\$@` ensures that the double quotes surrounding an argument will appear the same input level, which will be different to the input level of the argument itself. In a long escape name `]` will not be recognized as a closing delimiter except when it occurs at the same input level as the opening `]` . In compatibility mode, no attention is paid to the input level.

There are some new types of condition:

<code>.ifrxxx</code>	True if there is a number register named <code>xxx</code> .
<code>.ifdxxx</code>	True if there is a string, macro, diversion, or request named <code>xxx</code> .
<code>.ifcch</code>	True if there is a character <code>ch</code> available; <code>ch</code> is either an ASCII character or a special character <code>\(xx</code> or <code>\[xxx]</code> ; the condition will also be true if <code>ch</code> has been defined by the <code>char</code> request.

WARNINGS

The warnings that can be given by `troff` are divided into the following categories. The name associated with each warning is used by the `-w` and `-W` options; the number is used by the `warn` request, and by the `.warn` register.

<code>char1</code>	Nonexistent characters. This is enabled by default.
<code>number2</code>	Invalid numeric expressions. This is enabled by default.
<code>break4</code>	In fill mode, lines which could not be broken so that their length was less than the line length. This is enabled by default.
<code>delim8</code>	Missing or mismatched closing delimiters.

e116	Use of the e1 request with no matching ie request.
scale32	Meaningless scaling indicators.
range64	Out of range arguments.
syntax128	Dubious syntax in numeric expressions.
di256	Use of di or da without an argument when there is no current diversion.
mac512	Use of undefined strings, macros, and diversions. When an undefined string, macro, or diversion is used, that string is automatically defined as empty. So, in most cases, at most one warning will be given for each name.
reg1024	Use of undefined number registers. When an undefined number register is used, that register is automatically defined to have a value of 0. A definition is automatically made with a value of 0. So, in most cases, at most one warning will be given for use of a particular name.
tab2048	Inappropriate use of a tab character. Either use of a tab character where a number was expected, or use of tab character in an unquoted macro argument.
right-brace4096	Use of \g where a number was expected.
missing8192	Requests that are missing nonoptional arguments.
input16384	Illegal input characters.
escape32768	Unrecognized escape sequences. When an unrecognized escape sequence is encountered, the escape character is ignored.
space65536	Missing space between a request or macro and its argument. This warning will be given when an undefined name longer than two characters is encountered, and the first two characters of the name make a defined name. The request or macro will not be invoked. When this warning is given, no macro is automatically defined. This is enabled by default. This warning will never occur in compatibility mode.
font131072	Nonexistent fonts. This is enabled by default.
ig262144	Illegal escapes in text ignored with the ig request. These are conditions that are errors when they do not occur in ignored text.

There are also names that can be used to refer to groups of warnings:

all	All warnings except di, mac, and reg. It is intended that this covers all warnings that are useful with traditional macro packages.
w	All warnings.

INCOMPATIBILITIES

Long names cause some incompatibilities. UNIX troff will interpret

```
.dsabcd
```

as defining a string ab with contents cd. Normally, GNU troff will interpret this as a call of a macro named dsabcd. Also UNIX troff will interpret *[or \n[as references to a string or number register called [. In GNU troff, however, this will normally be interpreted as the start of a long name. In compatibility mode GNU troff will interpret these things in the traditional way. In compatibility mode, however, long names are not recognized. Compatibility mode can be turned on with the -c command-line option, and turned on or off with the cp request. The number register \n(.c is 1 if compatibility mode is on, 0 otherwise.

GNU troff does not allow the use of the escape sequences in names of strings, macros, diversions, number registers, fonts, or environments; UNIX troff does. The \A escape sequence may be helpful in avoiding use of these escape sequences in names.

Fractional point sizes cause one noteworthy incompatibility. In UNIX troff the ps request ignores scale indicators and so

```
.ps 10u
```

will set the pointsize to 10 points, whereas in GNU troff it will set the pointsize to 10 scaled points.

In GNU `troff` there is a fundamental difference between unformatted, input characters, and formatted, output characters. Everything that affects how an output character will be output is stored with the character; after an output character has been constructed, it is unaffected by any subsequent requests that are executed, including `bd`, `cs`, `tkf`, `tr`, or `fp` requests. Normally output characters are constructed from input characters at the moment immediately before the character is added to the current output line. Macros, diversions, and strings are all, in fact, the same type of object; they contain lists of input characters and output characters in any combination. An output character does not behave like an input character for the purposes of macro processing; it does not inherit any of the special properties that the input character from which it was constructed might have had. For example, this:

```
.di x
\\ \\
.br
.di
.x
```

will print `\\` in GNU `troff`; each pair of input `\s` is turned into one output `\` and the resulting output `\s` are not interpreted as escape characters when they are reread. UNIX `troff` would interpret them as escape characters when they were reread and would end up printing one `\`. The correct way to obtain a printable `\` is to use the `\e` escape sequence: this will always print a single instance of the current escape character, regardless of whether or not it is used in a diversion; it will also work in both GNU `troff` and UNIX `troff`. If you wish for some reason to store in a diversion an escape sequence that will be interpreted when the diversion is reread, you can either use the traditional `\!` transparent output facility, or, if this is unsuitable, the new `\?` escape sequence.

ENVIRONMENT

<code>GROFF_TMAC_PATH</code>	A colon-separated list of directories in which to search for macro files.
<code>GROFF_TYPESETTER</code>	Default device.
<code>GROFF_FONT_PATH</code>	A colon-separated list of directories in which to search for the <code>devname</code> directory. <code>troff</code> will search in directories given in the <code>-F</code> option before these, and in standard directories (<code>:/usr/lib/groff/font</code> , <code>:/usr/lib/font</code> , and <code>:/usr/lib/font</code>) after these.

FILES

<code>/usr/lib/groff/font/devname/DESC</code>	
<code>/usr/lib/groff/tmac/troffrc</code>	Initialization file
<code>/usr/lib/groff/tmac/tmac.name</code>	Macro files
<code>/usr/lib/groff/font/devname/DESC</code>	Device description file for device name
<code>/usr/lib/groff/font/devname/F</code>	Font file for font F of device name

SEE ALSO

`groff(1)` `gtbl(1)` `gpic(1)` `geqn(1)` `grops(1)` `grodvi(1)` `grotty(1)` `groff_font(5)` `groff_out(5)` `groff_char(7)`

Groff Version 1.09, 14 February 1994

gzip, gunzip, zcatgzip, gunzip, zcat

`gzip`, `gunzip`, `zcatgzip`, `gunzip`, `zcat`—Compress or expand files

SYNOPSIS

```
gzip [ -acdfhlLnNrtvV19 ] [-Ssuffix] [ name ... ]
gunzip [ -acfhllLnNrtvV ] [-Ssuffix] [ name ... ]
zcat [ -fhLV ] [name ... ]
```

DESCRIPTION

gzip reduces the size of the named files using Lempel-Ziv coding (LZ77). Whenever possible, each file is replaced by one with the extension `.gz`, while keeping the same ownership modes, access, and modification times. (The default extension is `-gz` for VMS, `z` for MS-DOS, OS/2 FAT, Windows NT FAT and Atari.) If no files are specified, or if a filename is `-`, the standard input is compressed to the standard output. `gzip` will only attempt to compress regular files. In particular, it will ignore symbolic links.

If the compressed filename is too long for its filesystem, `gzip` truncates it. `gzip` attempts to truncate only the parts of the filename longer than three characters. (A part is delimited by dots.) If the name consists of small parts only, the longest parts are truncated. For example, if filenames are limited to 14 characters, `gzip.msdos.exe` is compressed to `gzi.msd.exe.gz`. Names are not truncated on systems that do not have a limit on filename length.

By default, `gzip` keeps the original filename and timestamp in the compressed file. These are used when decompressing the file with the `-n` option. This is useful when the compressed filename was truncated or when the time stamp was not preserved after a file transfer.

Compressed files can be restored to their original form using `gzip -d` or `gunzip` or `zcat`. If the original name saved in the compressed file is not suitable for its filesystem, a new name is constructed from the original one to make it legal.

`gunzip` takes a list of files on its command line and replaces each file whose name ends with `.gz`, `-gz`, `.z`, `-z`, `z`, or `.Z` and which begins with the correct magic number with an uncompressed file without the original extension. `gunzip` also recognizes the special extensions `.tgz` and `.taz` as shorthands for `.tar.gz` and `.tar.Z` respectively. When compressing, `gzip` uses the `.tgz` extension if necessary instead of truncating a file with a `.tar` extension.

`gunzip` can currently decompress files created by `gzip`, `zip`, `compress`, `compress -H`, or `pack`. The detection of the input format is automatic. When using the first two formats, `gunzip` checks a 32-bit CRC. For `pack`, `gunzip` checks the uncompressed length. The standard `compress` format was not designed to allow consistency checks. However, `gunzip` is sometimes able to detect a bad `.Z` file. If you get an error when uncompressing a `.Z` file, do not assume that the `.Z` file is correct simply because the standard `uncompress` does not complain. This generally means that the standard `uncompress` does not check its input, and happily generates garbage output. The SCO `compress -H` format (1zh compression method) does not include a CRC but also allows some consistency checks.

Files created by `zip` can be uncompressed by `gzip` only if they have a single member compressed with the deflation method. This feature is only intended to help conversion of `tar.zip` files to the `tar.gz` format. To extract zip files with several members, use `unzip` instead of `gunzip`.

`zcat` is identical to `gunzip -c`. (On some systems, `zcat` may be installed as `gzcat` to preserve the original link to `compress`.) `zcat` uncompresses either a list of files on the command line or its standard input and writes the uncompressed data on standard output. `zcat` will uncompress files that have the correct magic number whether they have a `.gz` suffix or not.

`gzip` uses the Lempel-Ziv algorithm used in `zip` and `PKZIP`. The amount of compression obtained depends on the size of the input and the distribution of common substrings. Typically, text such as source code or English is reduced by 60 to 70 percent. Compression is generally much better than that achieved by LZW (as used in `compress`), Huffman coding (as used in `pack`), or adaptive Huffman coding (`compact`).

Compression is always performed, even if the compressed file is slightly larger than the original. The worst case expansion is a few bytes for the `gzip` file header, plus 5 bytes every 32KB block, or an expansion ratio of 0.015 percent for large files. Note that the actual number of used disk blocks almost never increases. `gzip` preserves the mode, ownership, and timestamps of files when compressing or decompressing.

OPTIONS

<code>-a -ascii</code>	ASCII text mode: convert end-of-lines using local conventions. This option is supported only on some non-UNIX systems. For MS-DOS, <code>CR LF</code> is converted to <code>LF</code> when compressing, and <code>LF</code> is converted to <code>CR LF</code> when decompressing.
<code>-c -stdout -to-stdout</code>	Write output on standard output; keep original files unchanged. If there are several input files, the output consists of a sequence of independently compressed members. To obtain better compression, concatenate all input files before compressing them.

<code>-d -decompress -uncompress</code>	Decompress.
<code>-f -force</code>	Force compression or decompression even if the file has multiple links or the corresponding file already exists, or if the compressed data is read from or written to a terminal. If the input data is not in a format recognized by <code>gzip</code> , and if the option <code>-stdout</code> is also given, copy the input data without change to the standard output; let <code>zcat</code> behave as <code>cat</code> . If <code>-f</code> is not given, and when not running in the background, <code>gzip</code> prompts to verify whether an existing file should be overwritten.
<code>-h -help</code>	Display a help screen and quit.
<code>-l -list</code>	For each compressed file, list the following fields: compressed size (size of the compressed file), uncompressed size (size of the uncompressed file), ratio (compression ratio—0.0% if unknown), uncompressed name (name of the uncompressed file). The uncompressed size is given as <code>-1</code> for files not in <code>gzip</code> format, such as compressed <code>.z</code> files. To get the uncompressed size for such a file, you can use: <code>zcat file.Z wc -c</code> In combination with the <code>-verbose</code> option, the following fields are also displayed: method (compression method), <code>crc</code> (the 32-bit CRC of the uncompressed data), date & time (timestamp for the uncompressed file). The compression methods currently supported are <code>deflate</code> , <code>compress</code> , <code>lzh</code> (SCO <code>compress -H</code>) and <code>pack</code> . The <code>crc</code> is given as <code>ffffffff</code> for a file not in <code>gzip</code> format. With <code>-name</code> , the uncompressed name, date and time are those stored within the compressed file if present. With <code>-verbose</code> , the size totals and compression ratio for all files is also displayed, unless some sizes are unknown. With <code>-quiet</code> , the title and totals lines are not displayed.
<code>-L -license</code>	Display the <code>gzip</code> license and quit.
<code>-n -no-name</code>	When compressing, do not save the original filename and timestamp by default. (The original name is always saved if the name had to be truncated.) When decompressing, do not restore the original filename if present (remove only the <code>gzip</code> suffix from the compressed filename) and do not restore the original timestamp if present (copy it from the compressed file). This option is the default when decompressing.
<code>-N -name</code>	When compressing, always save the original filename and timestamp; this is the default. When decompressing, restore the original filename and timestamp if present. This option is useful on systems that have a limit on filename length or when the timestamp has been lost after a file transfer.
<code>-q -quiet</code>	Suppress all warnings.
<code>-r -recursive</code>	Travel the directory structure recursively. If any of the filenames specified on the command line are directories, <code>gzip</code> will descend into the directory and compress all the files it finds there (or decompress them in the case of <code>gunzip</code>).
<code>-S .suf -suffix .suf</code>	Use suffix <code>.suf</code> instead of <code>.gz</code> . Any suffix can be given, but suffixes other than <code>.z</code> and <code>.gz</code> should be avoided to avoid confusion when files are transferred to other systems. A null suffix forces <code>gunzip</code> to try decompression on all given files regardless of suffix, as in the following: <code>gunzip -S "" * (*.*) for MS-DOS)</code> Previous versions of <code>gzip</code> used the <code>.z</code> suffix. This was changed to avoid a conflict with <code>pack(1)</code> .
<code>-t -test</code>	Test. Check the compressed file integrity.
<code>-v -verbose</code>	Verbose. Display the name and percentage reduction for each file compressed or decompressed.
<code>-V -version</code>	Version. Display the version number and compilation options, then quit.
<code>-# -fast -best</code>	Regulate the speed of compression using the specified digit <code>#</code> , where <code>-1</code> or <code>--fast</code> indicates the fastest compression method (less compression) and <code>-9</code> or <code>--best</code> indicates the slowest compression method (best compression). The default compression level is <code>-6</code> (that is, biased towards high compression at expense of speed).

ADVANCED USAGE

Multiple compressed files can be concatenated. In this case, gunzip will extract all members at once. For example,

```
gzip -c file1 >foo.gz gzip -c file2>>> foo.gz
```

Then

```
gunzip -c foo
```

is equivalent to

```
cat file1 file2
```

In case of damage to one member of a .gz file, other members can still be recovered (if the damaged member is removed). However, you can get better compression by compressing all members at once.

```
cat file1 file2 | gzip > foo.gz
```

compresses better than

```
gzip -c file1 file2 >foo.gz
```

If you want to recompress concatenated files to get better compression, use

```
gzip -cd old.gz | gzip > new.gz
```

If a compressed file consists of several members, the uncompressed size and CRC reported by the -list option applies to the last member only. If you need the uncompressed size for all members, you can use

```
gzip -cd file.gz | wc -c
```

If you wish to create a single archive file with multiple members so that members can later be extracted independently, use an archiver such as tar or zip. GNU tar supports the -z option to invoke gzip transparently. gzip is designed as a complement to tar, not as a replacement.

ENVIRONMENT

The environment variable GZIP can hold a set of default options for gzip. These options are interpreted first and can be overwritten by explicit command-line parameters. For example,

For sh: GZIP="-8v -name"

Export GZIP for csh: setenv GZIP "-8v -name"

For MS-DOS: set GZIP=-8v -name

On Vax/VMS, the name of the environment variable is GZIP_OPT, to avoid a conflict with the symbol set for invocation of the program.

SEE ALSO

znew(1), zcmp(1), zmore(1), zforce(1), gzexe(1), zip(1), unzip(1), compress(1), pack(1), compact(1)

DIAGNOSTICS

Exit status is normally 0; if an error occurs, exit status is 1. If a warning occurs, exit status is 2.

Usage: gzip [-cdfhLlNrtvV19] [-S suffix] [file ...]

Invalid options were specified on the command line.

file: not in gzip format

The file specified to gunzip has not been compressed.

file: Corrupt input. Use zcat to recover some data.

The compressed file has been damaged. The data up to the point of failure can be recovered using

```
zcat file > recover
```

file: compressed with xx bits, can only handle yy bits

file was compressed (using LZW) by a program that could deal with more bits than the decompress code on this machine. Recompress the file with gzip, which compresses better and uses less memory.

file: already has .gz suffix--no change

The file is assumed to be already compressed. Rename the file and try again.

file already exists; do you wish to overwrite (y or n)?

Respond y if you want the output file to be replaced; n if not.

gunzip: corrupt input

A SIGSEGV violation was detected, which usually means that the input file has been corrupted.

xx.x%

Percentage of the input saved by compression. (Relevant only for `-v` and `-l`.)

- not a regular file or directory: ignored

When the input file is not a regular file or directory, (such as a symbolic link, socket, FIFO, device file), it is left unaltered.

- has xx other links: unchanged

The input file has links; it is left unchanged. See `ln(1)` for more information.

Use the `-f` flag to force compression of files that are multiply linked.

CAVEATS

When writing compressed data to a tape, it is generally necessary to pad the output with zeroes up to a block boundary.

When the data is read and the whole block is passed to gunzip for decompression, gunzip detects that there is extra trailing garbage after the compressed data and emits a warning by default. You have to use the `-quiet` option to suppress the warning. This option can be set in the GZIP environment variable as in the following:

```
for sh: GZIP="-q" tar -xfz -block-compress /dev/rst0 for csh:
(setenv GZIP -q; tar -xfz -block-compr /dev/rst0
```

In the preceding example, gzip is invoked implicitly by the `-z` option of GNU tar. Make sure that the same block size (`-b` option of tar) is used for reading and writing compressed data on tapes. (This example assumes you are using the GNU version of tar.)

BUGS

The `-list` option reports incorrect sizes if they exceed two gigabytes. The `-list` option reports sizes as `-1` and `crc` as `ffffffff` if the compressed file is on a nonseekable media.

In some rare cases, the `-best` option gives worse compression than the default compression level (`-6`). On some highly redundant files, compress compresses better than gzip.

Local

gzexe

gzexe—Compress executable files in place

SYNOPSIS

```
gzexe [ name ... ]
```


DESCRIPTION

The `gzexe` utility enables you to compress executables in place and have them automatically uncompress and execute when you run them (at a penalty in performance). For example if you execute `gzexe /bin/cat`, it will create the following two files:

```
-r-xr-xr-x 1 root bin 9644 Feb 11 11:16 /bin/cat
-r-xr-xr-x 1 bin bin 24576 Nov 23 13:21 /bin/cat^
```

`/bin/cat^` is the original file and `/bin/cat` is the self-uncompressing executable file. You can remove `/bin/cat^` when you are sure that `/bin/cat` works properly.

This utility is most useful on systems with very small disks.

OPTIONS

`-d` Decompress the given executables instead of compressing them

SEE ALSO

`gzip(1)`, `znew(1)`, `zmore(1)`, `zcmp(1)`, `zforce(1)`

CAVEATS

The compressed executable is a shell script. This may create some security holes. In particular, the compressed executable relies on the `PATH` environment variable to find `gzip` and some other utilities (`tail`, `chmod`, `ln`, `sleep`).

BUGS

`gzexe` attempts to retain the original file attributes on the compressed executable, but you may have to fix them manually in some cases, using `chmod` or `chown`.

head

`head`—Output the first part of files

SYNOPSIS

```
head [-c N[bkm]] [-n N] [-qv] [--bytes=N[bkm]] [--lines=N] [--quiet] [--silent]
[--verbose] [--help] [--version] [file...]
```

```
head [-Nbcklmqv] [file...]
```

DESCRIPTION

This manual page documents the GNU version of `head`. `head` prints the first part (10 lines by default) of each given file; it reads from standard input if no files are given or when a filename of `-` is encountered. If more than one file is given, it prints a header consisting of the file's name enclosed in `=>` and `<==` before the output for each file.

OPTIONS

`head` accepts two option formats: the new one, in which numbers are arguments to the option letters; and the old one, in which the number precedes any option letters.

<code>-c N</code> , <code>--bytes N</code>	Print first <code>N</code> bytes. <code>N</code> is a nonzero integer, optionally followed by one of the following characters to specify a different unit.
	<code>b</code> 512-byte blocks.
	<code>k</code> 1-kilobyte blocks.
	<code>m</code> 1-megabyte blocks.
<code>-l</code> , <code>-n N</code> , <code>--lines N</code>	Print first <code>N</code> lines.
<code>-q</code> , <code>--quiet</code> , <code>--silent</code>	Never print filename headers.

<code>-v, --verbose</code>	Always print filename headers.
<code>--help</code>	Print a usage message and exit with a nonzero status.
<code>--version</code>	Print version information on standard output, then exit.

GNU Text Utilities

hexdump

hexdump—ASCII, decimal, hexadecimal, octal dump

SYNOPSIS

```
hexdump [-bcdovx] [-e format_string] [-f format_file] [-n length] [-s skip] [file ...]
```

DESCRIPTION

The `hexdump` utility is a filter that displays the specified files, or the standard input, if no files are specified, in a user-specified format.

The options are as follows:

<code>-b</code>	One-byte octal display. Display the input offset in hexadecimal, followed by sixteen space-separated, three-column, zero-filled bytes of input data, in octal, per line.
<code>-c</code>	One-byte character display. Display the input offset in hexadecimal, followed by sixteen space-separated, three-column, space-filled, characters of input data per line.
<code>-d</code>	Two-byte decimal display. Display the input offset in hexadecimal, followed by eight space-separated, five-column, zero-filled, two-byte units of input data, in unsigned decimal, per line.
<code>-e format_string</code>	Specify a format string to be used for displaying data.
<code>-f format_file</code>	Specify a file that contains one or more newline separated format strings. Empty lines and lines whose first nonblank character is a hash mark (#) are ignored.
<code>-n length</code>	Interpret only length bytes of input.
<code>-o</code>	Two-byte octal display. Display the input offset in hexadecimal, followed by eight space-separated, six-column, zero-filled, two-byte quantities of input data, in octal, per line.
<code>-s offset</code>	Skip <code>offset</code> bytes from the beginning of the input. By default, <code>offset</code> is interpreted as a decimal number. With a leading <code>0x</code> or <code>0X</code> , <code>offset</code> is interpreted as a hexadecimal number; otherwise, with a leading <code>0</code> , <code>offset</code> is interpreted as an octal number. Appending the character <code>b</code> , <code>k</code> , or <code>m</code> to <code>offset</code> causes it to be interpreted as a multiple of 512, 1024, or 1048576, respectively.
<code>-v</code>	The <code>-v</code> option causes <code>hexdump</code> to display all input data. Without the <code>-v</code> option, any number of groups of output lines, which would be identical to the immediately preceding group of output lines (except for the input offsets), are replaced with a line comprised of a single asterisk.
<code>-x</code>	Two-byte hexadecimal display. Display the input offset in hexadecimal, followed by eight, space-separated, four-column, zero-filled, two-byte quantities of input data, in hexadecimal, per line.

For each input file, `hexdump` sequentially copies the input to standard output, transforming the data according to the format strings specified by the `-e` and `-f` options, in the order that they were specified.

FORMATS

A format string contains any number of format units, separated by whitespace. A format unit contains up to three items: an iteration count, a byte count, and a format.

The iteration count is an optional positive integer, which defaults to one. Each format is applied iteration count times.

The byte count is an optional positive integer. If specified, it defines the number of bytes to be interpreted by each iteration of the format.

If an iteration count and/or a byte count is specified, a single slash must be placed after the iteration count and/or before the byte count to disambiguate them. Any whitespace before or after the slash is ignored.

The format is required and must be surrounded by double quote (“ ”) marks. It is interpreted as an `fprintf(3)`-style format string (see `fprintf(3)`) with the following exceptions:

- An asterisk (*) may not be used as a field width or precision.
- A byte count or field precision is required for each `s` conversion character (unlike the `fprintf(3)` default, which prints the entire string if the precision is unspecified).
- The conversion characters `h`, `l`, `n`, `p`, and `q` are not supported.
- The single-character escape sequences described in the C standard are supported:

NUL	<code>\0</code>
Alert character	<code>\a</code>
Backspace	<code>\b</code>
Form-feed	<code>\f</code>
Newline	<code>\n</code>
Carriage return	<code>\r</code>
Tab	<code>\t</code>
Vertical tab	<code>\v</code>

`hexdump` also supports the following additional conversion strings:

- `a[dox]` Display the input offset, cumulative across input files, of the next byte to be displayed. The appended characters `d`, `o`, and `x` specify the display base as decimal, octal, or hexadecimal respectively.
- `A[dox]` Identical to the `a` conversion string except that it is only performed once, when all of the input data has been processed.
- `c` Output characters in the default character set. Nonprinting characters are displayed in three-character, zero-padded octal, except for those representable by standard escape notation (see preceding list), which are displayed as two-character strings.
- `p` Output characters in the default character set. Nonprinting characters are displayed as a single period.
- `u` Output U.S. ASCII characters, with the exception that control characters are displayed using the lowercase names in the following mini-table. Characters greater than `0xff`, hexadecimal, are displayed as hexadecimal strings.

<code>000 nul</code>	<code>001 soh</code>	<code>002 stx</code>	<code>003 etx</code>	<code>004 eot</code>	<code>005 enq</code>
<code>006 ack</code>	<code>007 bel</code>	<code>008 bs</code>	<code>009 ht</code>	<code>00A lf</code>	<code>00B vt</code>
<code>00C ff</code>	<code>00D cr</code>	<code>00E so</code>	<code>00F si</code>	<code>010 dle</code>	<code>011 dc1</code>
<code>012 dc2</code>	<code>013 dc3</code>	<code>014 dc4</code>	<code>015 nak</code>	<code>016 syn</code>	<code>017 etb</code>
<code>018 can</code>	<code>019 em</code>	<code>01A sub</code>	<code>01B esc</code>	<code>01C fs</code>	<code>01D gs</code>
<code>01E rs</code>	<code>01F us</code>	<code>0FF del</code>			

The default and supported byte counts for the conversion characters are as follows:

<code>%c</code> , <code>%p</code> , <code>%u</code> , <code>%C</code>	One-byte counts only.
<code>%d</code> , <code>%i</code> , <code>%o</code> , <code>%u</code> , <code>%X</code> , <code>%x</code>	Four-byte default; one-, two-, and four-byte counts supported.
<code>%E</code> , <code>%e</code> , <code>%f</code> , <code>%G</code> , <code>%g</code>	Eight-byte default, four-byte counts supported.

The amount of data interpreted by each format string is the sum of the data required by each format unit, which is the iteration count times the byte count, or the iteration count times the number of bytes required by the format if the byte count is not specified.

The input is manipulated in *blocks*; a block is defined as the largest amount of data specified by any format string. Format strings interpreting less than an input block's worth of data, whose last format unit both interprets some number of bytes and does not have a specified iteration count, have the iteration count incremented until the entire input block has been processed or there is not enough data remaining in the block to satisfy the format string.

If, either as a result of user specification or `hexdump` modifying the iteration count as described, an iteration count is greater than one, no trailing whitespace characters are output during the last iteration.

It is an error to specify a byte count as well as multiple conversion characters or strings unless all but one of the conversion characters or strings is a `%a` or `%A`. If, as a result of the specification of the `-n` option or end-of-file being reached, input data only partially satisfies a format string, the input block is zero-padded sufficiently to display all available data (that is, any format units overlapping the end of data will display some number of the zero bytes).

Further output by such format strings is replaced by an equivalent number of spaces. An equivalent number of spaces is defined as the number of spaces output by an `%s` conversion character with the same field width and precision as the original conversion character or conversion string but with any `+`, `"`, `"`, `#` conversion flag characters removed, and referencing a `NULL` string.

If no format strings are specified, the default display is equivalent to specifying the `-x` option.

`hexdump` exits `0` on success and `>0` if an error occurred.

EXAMPLES

Display the input in perusal format:

```
"%06.6_ao " 12/1 "%3_u "
"\t\t" "%_p "
"\n"
```

Implement the `-x` option:

```
"%07.7_Ax\n"
"%07.7_ax " 8/2 "%04x " "\n"
```

SEE ALSO

`adb(1)`

18 April 1994

hipstopgm

`hipstopgm`—Convert a HIPS file into a portable graymap

SYNOPSIS

```
hipstopgm [hipsfile]
```

DESCRIPTION

`Hipstopgm` reads a HIPS file as input and produces a portable graymap as output.

If the HIPS file contains more than one frame in sequence, `hipstopgm` will concatenate all the frames vertically.

HIPS is a format developed at the Human Information Processing Laboratory, NYU.

SEE ALSO

`pgm(5)`

AUTHOR

Copyright © 1989 by Jef Poskanzer

24 August 1989

host

host—Look up hostnames using domain server

SYNOPSIS

```
host [-l] [-v] [-w] [-r] [-d] [-t querytype] [-a] host [ server ]
```

DESCRIPTION

host looks for information about Internet hosts. It gets this information from a set of interconnected servers that are spread across the country. By default, it simply converts between hostnames and Internet addresses. However with the -t or -a options, it can be used to find all of the information about this host that is maintained by the domain server.

The arguments can be either hostnames or host numbers. The program first attempts to interpret them as host numbers. If this fails, it will treat them as hostnames. A host number consists of first decimal numbers separated by dots, for example, 128.6.4.194. A hostname consists of names separated by dots, for example, topaz.rutgers.edu. Unless the name ends in a dot, the local domain is automatically tacked on the end. Thus, a Rutgers user can say "host topaz", and it will actually look up topaz.rutgers.edu. If this fails, the name is tried unchanged (in this case, topaz). This same convention is used for mail and other network utilities. The actual suffix to tack on the end is obtained by looking at the results of a hostname call, and using everything starting at the first dot. (Following is a description of how to customize the hostname lookup.)

The first argument is the hostname you want to look up. If this is a number, an *inverse query* is done; that is, the domain system looks in a separate set of databases used to convert numbers to names.

The second argument is optional. It allows you to specify a particular server to query. If you don't specify this argument, the default server (normally the local machine) is used.

If a name is specified, you may see output of three different kinds. Here is an example that shows all of them:

```
% host sun4
sun4.rutgers.edu is a nickname for ATHOS.RUTGERS.EDU
ATHOS.RUTGERS.EDU has address 128.6.5.46
ATHOS.RUTGERS.EDU has address 128.6.4.4
ATHOS.RUTGERS.EDU mail is handled by ARAMIS.RUTGERS.EDU
```

The user has typed the command `host sun4`. The first line indicates that the name `sun4.rutgers.edu` is actually a nickname. The official hostname is `ATHOS.RUTGERS.EDU`. The next two lines show the address. If a system has more than one network interface, there will be a separate address for each. The last line indicates that `ATHOS.RUTGERS.EDU` does not receive its own mail. Mail for it is taken by `ARAMIS.RUTGERS.EDU`. There may be more than one such line, as some systems have more than one other system that will handle mail for them. Technically, every system that can receive mail is supposed to have an entry of this kind. If the system receives its own mail, there should be an entry the mentions the system itself, for example "XXX mail is handled by XXX." However many systems that receive their own mail do not bother to mention that fact. If a system has a "mail is handled by" entry, but no address, this indicates that it is not really part of the Internet, but a system that is on the network will forward mail to it. Systems on Usenet, bitnet, and a number of other networks have entries of this kind.

There are a number of options that can be used before the hostname. Most of these options are meaningful only to the staff who have to maintain the domain database.

The option -w causes host to wait forever for a response. Normally it will time out after around a minute.

The option -v causes printout to be in a verbose format. This is the official domain master file format, which is documented in the man page for `named`. Without this option, output still follows this format in general terms, but some attempt is made to make it more intelligible to normal users. Without -v, a, mx, and cname records are written out as `has address`, `mail is handled by`, and `is a nickname for`, and TTL and class fields are not shown.

The option -r causes recursion to be turned off in the request. This means that the name server will return only data it has in its own database. It will not ask other servers for more information.

The option -d turns on debugging. Network transactions are shown in detail.

The option `-t` allows you to specify a particular type of information to be looked up. The arguments are defined in the man page for `named`. Currently supported types are `a`, `ns`, `md`, `mf`, `cname`, `soa`, `mb`, `mg`, `mr`, `null`, `wks`, `ptr`, `hinfo`, `minfo`, `mx`, `uinfo`, `uid`, `gid`, `unspec`, and the wildcard, which may be written as either `any` or `*`. Types must be given in lowercase. Note that the default is to look first for `a`, and then `mx`, except that if the verbose option is turned on, the default is only `a`.

The option `-a` (for “all”) is equivalent to `-v -t any`.

The option `-l` causes a listing of a complete domain. For example,

```
host -l rutgers.edu
```

will give a listing of all hosts in the `rutgers.edu` domain. The `-t` option is used to filter what information is presented, as you would expect. The default is address information, which also include PTR and NS records. The command `host`:

```
-l -v -t any rutgers.edu
```

will give a complete download of the zone data for `rutgers.edu`, in the official master file format. (However the SOA record is listed twice, for arcane reasons.)

NOTE

`-l` is implemented by doing a complete zone transfer and then filtering out the information you have asked for. This command should be used only if it is absolutely necessary.

CUSTOMIZING HOSTNAME LOOKUP

In general, if the name supplied by the user does not have any dots in it, a default domain is appended to the end. This domain can be defined in `/etc/resolv.conf`, but is normally derived by taking the local hostname after its first dot. The user can override this, and specify a different default domain, using the environment variable `LOCALDOMAIN`. In addition, the user can supply his own abbreviations for hostnames. They should be in a file consisting of one line per abbreviation. Each line contains an abbreviation, a space, and then the full hostname. This file must be pointed to by an environment variable `HOSTALIASES`, which is the name of the file.

SEE ALSO

`named(8)`

BUGS

Unexpected effects can happen when you type a name that is not part of the local domain. Please always keep in mind that the local domain name is tacked onto the end of every name, unless it ends in a dot. Only if this fails is the name used unchanged.

The `-l` option only tries the first name server listed for the domain that you have requested. If this server is dead, you may need to specify a server manually. For example, to get a listing of `foo.edu`, you could try `host -t ns foo.edu` to get a list of all the name servers for `foo.edu`, and then try `host -l foo.edu xxx` for all `xxx` on the list of name servers, until you find one that works.

hostid

`hostid`—Set or print system’s host ID.

SYNTAX

```
hostid [-v] [ decimal-id ]
```

DESCRIPTION

The `hostid` command prints the current host ID number in hexadecimal and both decimal and hexadecimal in parenthesis if the `-v` option is given. This numeric value is expected to be unique across all hosts and is normally set to resemble the host's Internet address.

Only the superuser can set the `hostid` by giving an argument. This value is stored in the file `/etc/hostid` and need only be performed once.

AUTHOR

`hostid` is written by Mitch D'Souza (m.dsouza@mrc-apu.cam.ac.uk).

SEE ALSO

`gethostid(2)`, `sethostid(2)`

hostname

`hostname`—Show or set the system's hostname

`dnsdomainname`--Show the system's domain name

SYNOPSIS

```
hostname [-d][--domain][--filename] [--filefilename] [-f][--fqdn][-h][--help]
[--long][-s][--short][-v][--version][name]
dnsdomainname
```

DESCRIPTION

`hostname` is the program that is used to either set the hostname or display the current host or domain name of the system. This name is used by many of the networking programs to identify the machine.

When called without any arguments, the program displays the current name as set by the `hostname` command. You can change the output format to display always the short or the long hostname (FQDN). When called with arguments, the program will set the value of the `hostname` to the value specified. This usually is done only once, at system startup time, by the `/etc/rc.d/rc.inet1` configuration script.

Note that only the superuser can change the hostname.

If the program was called as `dnsdomainname`, it will show the domain name server (DNS) domain name. You can't change the DNS domain name with `dnsdomainname`. (See the following subsection.)

OPTIONS

<code>-d, --domain</code>	Display the name of the DNS domain. Don't use the <code>com-mand domainname</code> to get the DNS domain name because it will show the NIS domain name and not the DNS domain name.
<code>-F, --file filename</code>	Read the hostname from the specified file. Comments (lines starting with a #) are ignored.
<code>-f, --fqdn, --long</code>	Display the FQDN (fully-qualified domain name). An FQDN consists of a short hostname and the DNS domain name. Unless you are using <code>bind</code> or <code>NIS</code> for host lookups, you can change the FQDN and the DNS domain name (which is part of the FQDN) in the <code>/etc/hosts</code> file.
<code>-h, --help</code>	Print a usage message on standard output and exit successfully.
<code>-s, --short</code>	Display the short hostname.
<code>-v, --version</code>	Print version information on standard output and exit successfully.

FILES

`/etc/hosts`

AUTHOR

Peter Tobias, (tobias@server.et-inf.fho-emden.de)

Linux, 28 July 1994

hpcdtoppm v0.3

hpcdtoppm v0.3—Convert a Photo-CD file into a portable pixmap

SYNOPSIS

```
hpcdtoppm [options] pcd-file [ppm-file]
```

DESCRIPTION

hpcdtoppm reads a Photo-CD image file or overview file, and outputs a portable pixmap. Image files you can find on the Photo-CD in photo_cd/images are named as imgnnnn.pcd, where nnnn is a 4-digit-number. The Overview file is at photo_cd/overview.pcd. If there is no ppm-file given, output will be printed to stdout. hpcdtoppm stands for “Hadmut’s pcdtoppm” to make it distinguishable in case someone else is building the same thing and calling it pcdtoppm.

OPTIONS

- i Give some information from the fileheader to stderr. It works only for image files. (It is not working correctly, just printing some strings.)
- s Apply simple sharpness-operator on the luma channel.
- d Do not show the complete image, but only the decompressed difference. It works only on the 4Base and the 16Base resolution. It does not have any deeper sense, but it was simple to implement and it shows what causes different sizes of image files.
- r Rotate the picture clockwise for portraits.
- l Rotate the picture counter-clockwise for portraits.
- a Try to find out the image orientation. This doesn’t work for overview files yet. It is very experimental and depends on one byte. Please tell me if it doesn’t work.
- x Overskip mode. Works on Base/16, Base/4, Base, and 4Base. In Photo-CD images, the luma channel is stored in full resolution, the two chroma channels are stored in half resolution only and have to be interpolated. In the Overskip mode, the chroma channels of the next higher resolution are taken instead of interpolating. To see the difference, generate one ppm with and one ppm without this flag. Use pnmarith to generate the difference image of these two images. Call ppmhist for this difference or show it with xv (push the HistEq button in the color editor).
- 1 | -Base/16 | -128x192 Extract the Base/16 size picture (size 128×192 pixels). Note that you can only give one size option.
- 2 | -Base/4 | -256x384 Extract the Base/4 size picture.
- 3 | -Base | -512x768 Extract the Base size picture.
- 4 | -4Base | -1024x1536 Extract the 4Base size picture.
- 5 | -16Base | -2048x3072 Extract the 16Base size picture.
- 0 | -Overview | -0 Extract all pictures from an Overview file. A ppm filename must be given. If the given name is foo, the files are named fooNNNN, where NNNN is a 4-digit number. They are stored in Base/16 format, so they are extracted in this format.
- ycc Suppress the ycc to rgb conversion. This is experimental only. You can use this and apply ppmtorgb3 on the file. Then you will get three ppm files, one luma and two chroma files.

BUGS

I still don't have enough information about the Photo-CD to take care of all data structures. The information I have is quite vague and this program was developed by staring at the hexdumps and using the famous trial-and-error-method. :-) If anything doesn't work, please send me a report and perhaps you could try to find out why it doesn't work.

SEE ALSO

ppm(5), ppmquant(1), ppmtopgm(1), ppmhist(1), pnmarith(1), ppmtorgb3(1), xv(1)

AUTHOR

Copyright© 1992 by Hadmut Danisch (danisch@ira.uka.de). Permission to use and distribute this software and its documentation for noncommercial use and without fee is hereby granted, provided that the preceding copyright notice appear in all copies and that both that copyright notice and this permission notice appear in supporting documentation. This software may not be sold in any way. This software is not public domain.

28 November 1992

httpd

httpd—Apache Hypertext Transfer Protocol server

SYNOPSIS

```
httpd [ -vX? ][-d serverroot ][-f config ]
```

DESCRIPTION

httpd is the Apache Hypertext Transfer Protocol (HTTP) server process. The server may be invoked by the Internet daemon inetd(1M) each time a connection to the HTTP service is made, or alternatively it may run as a daemon.

OPTIONS

-d serverroot	Set the initial value for the ServerRoot variable to serverroot. This can be overridden by the ServerRoot command in the configuration file. The default is /usr/local/etc/httpd.
-f config	Execute the commands in the file config on startup. If config does not begin with a /, then it is taken to be a path relative to the ServerRoot. The default is conf/httpd.conf.
-X	Run in single-process mode, for internal debugging purposes only; the daemon does not detach from the terminal or fork any children. Do not use this mode to provide ordinary Web service.
-v	Print the version of httpd, and then exit.
-?	Print a list of the httpd options, and then exit.

FILES

```
/usr/local/etc/httpd/conf/httpd.conf
/usr/local/etc/httpd/conf/srm.conf
/usr/local/etc/httpd/conf/access.conf
/usr/local/etc/httpd/conf/mime.types
/usr/local/etc/httpd/logs/error_log
/usr/local/etc/httpd/logs/access_log
/usr/local/etc/httpd/logs/httpd.pid
```

SEE ALSO

inetd(1m)

Documentation for the Apache HTTP server is available from <http://www.apache.org>.

October 1995

icontopbm

`icontopbm`—Convert a Sun icon into a portable bitmap

SYNOPSIS

```
icontopbm [iconfile]
```

DESCRIPTION

`icontopbm` reads a Sun icon as input and produces a portable bitmap as output.

SEE ALSO

`pbmtoicon(1)`, `pbm(5)`

AUTHOR

Copyright© 1988 by Jef Poskanzer

31 August 1988

ident

`ident`—Identify RCS keyword strings in files

SYNOPSIS

```
ident [ -q ][ -V ][ file ... ]
```

DESCRIPTION

`ident` searches for all instances of the pattern `$ keyword : text $` in the named files or, if no files are named, the standard input.

These patterns are normally inserted automatically by the RCS command `co(1)`, but can also be inserted manually. The option `-q` suppresses the warning given if there are no patterns in a file. The option `-v` prints `ident`'s version number.

`ident` works on text files as well as object files and dumps. For example, if the C program in `f.c` contains

```
#include <stdio.h>
static char const rcsid[] =
"$Id: f.c,v 5.4 1993/11/09 17:40 eggert Exp $";
int main() { return printf("%s\n", rcsid) == EOF; }
```

and `f.c` is compiled into `f.o`, then the command

```
ident f.c f.o
```

will output

```
f.c:
$Id: f.c,v 5.4 1993/11/09 17:40 eggert Exp $
f.o:
$Id: f.c,v 5.4 1993/11/09 17:40 eggert Exp $
```

If a C program defines a string like the `rcsid` but does not use it, `lint(1)` may complain, and some C compilers will optimize away the string. The most reliable solution is to have the program use the `rcsid` string, as shown in the example.

`ident` finds all instances of the `$ keyword : text $` pattern, even if `keyword` is not actually an RCS-supported keyword. This gives you information about nonstandard keywords like `$XConsortium$`.

KEYWORDS

Here is the list of keywords currently maintained by `co(1)`. All times are given in Coordinated Universal Time (UTC, sometimes called GMT by default), but if the files were checked out with `co`'s `-zzone` option, times are given with a numeric time zone indication appended.

<code>\$Author\$</code>	The login name of the user who checked in the revision.
<code>\$Date\$</code>	The date and time the revision was checked in.
<code>\$Header\$</code>	A standard header containing the full pathname of the RCS file, the revision number, the date and time, the author, the state, and the locker (if locked).
<code>\$Id\$</code>	Same as <code>\$Header\$</code> , except that the RCS filename is without a path.
<code>\$Locker\$</code>	The login name of the user who locked the revision (empty if not locked).
<code>\$Log\$</code>	The log message supplied during checkin. For <code>ident</code> 's purposes, this is equivalent to <code>\$RCSfile\$</code> .
<code>\$Name\$</code>	The symbolic name used to check out the revision, if any.
<code>\$RCSfile\$</code>	The name of the RCS file without a path.
<code>\$Revision\$</code>	The revision number assigned to the revision.
<code>\$Source\$</code>	The full pathname of the RCS file.
<code>\$State\$</code>	The state assigned to the revision with the <code>-s</code> option of <code>rcs(1)</code> or <code>ci(1)</code> .

`co(1)` represents the following characters in keyword values by escape sequences to keep keyword strings well formed.

Character	Escape Sequence
Tab	<code>\t</code>
Newline	<code>\n</code>
Space	<code>\040</code>
\$	<code>\044</code>
\	<code>\\</code>

IDENTIFICATION

Author: Walter F. Tichy

Manual Page Revision: 5.4; Release date September 11, 1993.

Copyright© 1982, 1988, 1989 Walter F. Tichy. Copyright© 1990, 1992, 1993 Paul Eggert.

SEE ALSO

`ci(1)`, `co(1)`, `rcs(1)`, `rcsdiff(1)`, `rcsintro(1)`, `rcsmmerge(1)`, `rlog(1)`, `rcsfile(5)`

Walter F. Tichy, *RCS—A System for Version Control, Software—Practice & Experience* 15, 7 (July 1985), 637–654.

GNU, 9 November 1993

ilbmtoppm

`ilbmtoppm`—Convert an ILBM file into a portable pixmap

SYNOPSIS

```
ilbmtoppm [-verbose][ -ignore<chunkID>] [ -isham| -isehb] [ -adjustcolors][ILBMfile]
```

DESCRIPTION

`ilbmtoppm` reads an IFF ILBM file as input and produces a portable pixmap as output. Supported ILBM types are Normal ILBMs with 1–16 planes.

Amiga Extra Halfbrite (EHB)

Amiga HAM with 3–16 planes

24-bit

Multiplatte (normal or HAM) pictures

Colormap (BMHD and CMAP chunk only, nPlanes = 0)

Unofficial direct color; 1–16 planes for each color component.

Chunks used: BMHD, CMAP, CAMG (only HAM and EHB flags used), PCHG, BODY unofficial DCOL chunk to identify direct color ILBM

Chunks ignored: GRAB, DEST, SPRT, CRNG, CCRT, CLUT, DPPV, DRNG, EPSF

Other chunks (ignored but displayed in verbose mode): NAME, AUTH, (d), ANNO, DPI

Unknown chunks are skipped.

OPTIONS

- verbose Give some information about the ILBM file.
- ignore <chunkID> Skip a chunk. <chunkID> is the 4-letter IFF chunk identifier of the chunk to be skipped.
- isham | -isehb Treat the input file as a HAM or Extra Halfbrite picture, even if these flags or not set in the CAMG chunk (or if there is no CAMG chunk).
- adjustcolors If all colors in the CMAP have a value of less than 16, ilbmto ppm assumes a 4-bit colormap and gives a warning. With this option, the colormap is scaled to 8 bits.

BUGS

The multipalette PCHG BigLineChanges and Huffman decompression code are untested.

REFERENCES

Amiga ROM Kernel Reference Manual—Devices (3rd Ed.). Addison Wesley, ISBN 0-201-56775-X.

SEE ALSO

ppm(5), ppmtoilbm(1)

AUTHORS

Copyright© 1989 by Jef Poskanzer.

Modified October 1993 by Ingo Wilken (Ingo.Wilken@informatik.uni-oldenburg.de)

4 October 1993

imake

imake—C preprocessor interface to the make utility

SYNOPSIS

```
imake [ -Ddefine ][-Idir ][-Ttemplate ][-f filename ][-C filename ][-s filename ]
[-e ][-v ]
```

DESCRIPTION

imake is used to generate Makefiles from a template, a set of cpp macro functions, and a per-directory input file called an Imakefile. This allows machine dependencies (such as compiler options, alternate command names, and special make rules) to be kept separate from the descriptions of the various items to be built.

OPTIONS

The following command-line options may be passed to `imake`:

<code>-Ddefine</code>	This option is passed directly to <code>cpp</code> . It is typically used to set directory-specific variables. For example, the X Window System uses this flag to set <code>TOPDIR</code> to the name of the directory containing the top of the core distribution and <code>CURDIR</code> to the name of the current directory, relative to the top.
<code>-Idirectory</code>	This option is passed directly to <code>cpp</code> . It is typically used to indicate the directory in which the <code>imake</code> template and configuration files may be found.
<code>-Ttemplate</code>	This option specifies the name of the master template file (which is usually located in the directory specified with <code>-I</code>) used by <code>cpp</code> . The default is <code>Imake.tmpl</code> .
<code>-f filename</code>	This option specifies the name of the per-directory input file. The default is <code>Imakefile</code> .
<code>-C filename</code>	This option specifies the name of the <code>.c</code> file that is constructed in the current directory. The default is <code>Imakefile.c</code> .
<code>-s filename</code>	This option specifies the name of the <code>make</code> description file to be generated but <code>make</code> should not be invoked. If the filename is a hyphen (<code>-</code>), the output is written to <code>stdout</code> . The default is to generate, but not execute, a <code>Makefile</code> .
<code>-e</code>	This option indicates the <code>imake</code> should execute the generated <code>Makefile</code> . The default is to leave this to the user.
<code>-v</code>	This option indicates that <code>imake</code> should print the <code>cpp</code> command line that it is using to generate the <code>Makefile</code> .

HOW IT WORKS

`Imake` invokes `cpp` with any `-I` or `-D` flags passed on the command line and passes the name of a file containing the following three lines:

```
#define IMAKE_TEMPLATE "Imake.tmpl"
#define INCLUDE_IMAKEFILE <Imakefile>
#include IMAKE_TEMPLATE
```

where `Imake.tmpl` and `Imakefile` may be overridden by the `-T` and `-f` command options, respectively.

The `IMAKE_TEMPLATE` typically reads in a file containing machine-dependent parameters (specified as `cpp` symbols), a site-specific parameters file, a file defining variables, a file containing `cpp` macro functions for generating `make` rules, and finally the `Imakefile` (specified by `INCLUDE_IMAKEFILE`) in the current directory. The `Imakefile` uses the macro functions to indicate what targets should be built; `imake` takes care of generating the appropriate rules.

`Imake` configuration files contain two types of variables, `imake` variables and `make` variables. The `imake` variables are interpreted by `cpp` when `imake` is run. By convention they are mixed case. The `make` variables are written into the `Makefile` for later interpretation by `make`. By convention `make` variables are uppercase.

The rules file (usually named `Imake.rules` in the configuration directory) contains a variety of `cpp` macro functions that are configured according to the current platform. `Imake` replaces any occurrences of the string `@@` with a newline to allow macros that generate more than one line of `make` rules. For example, when called with `program_target(foo, foo1.o foo2.o)`, the macro:

```
#define program_target(program, objlist) @@\
program: objlist @@\
$(CC) -o $@ objlist $(LDFLAGS)
```

will expand to

```
foo: foo1.o foo2.o
$(CC) -o $@ foo1.o foo2.o $(LDFLAGS)
```

`imake` also replaces any occurrences of the word `XCOMM` with the character `#` to permit placing comments in the `Makefile` without causing invalid directive errors from the preprocessor.

Some complex `imake` macros require generated `make` variables local to each invocation of the macro, often because their value depends on parameters passed to the macro. Such variables can be created by using an `imake` variable of the form `XVARdefn`, where `n` is a single digit. A unique `make` variable will be substituted. Later occurrences of the variable `XVARusen` will be replaced by the variable created by the corresponding `XVARdefn`.

On systems whose `cpp` reduces multiple tabs and spaces to a single space, `imake` attempts to put back any necessary tabs (`make` is very picky about the difference between tabs and spaces). For this reason, colons (`:`) in command lines must be preceded by a backslash (`\`).

USE WITH THE X WINDOW SYSTEM

The X Window System uses `imake` extensively, for both full builds within the source tree and external software. As mentioned earlier, two special variables, `TOPDIR` and `CURDIR`, are set to make referencing files using relative pathnames easier. For example, the following command is generated automatically to build the `Makefile` in the directory `lib/X/` (relative to the top of the sources):

```
% ../../config/imake -I../../config \
-DTOPDIR=../../ -DCURDIR=./lib/X
```

When building X programs outside the source tree, a special symbol `UseInstalled` is defined and `TOPDIR` and `CURDIR` are omitted. If the configuration files have been properly installed, the script `xmkmf(1)` may be used.

INPUT FILES

Here is a summary of the files read by `imake` as used by X. The indentation shows which files include which other files.

```
Imake.tmpl generic variables
site.def site-specific, BeforeVendorCF defined
.cf machine-specific
Lib.rules shared library rules
site.def site-specific, AfterVendorCF defined
Imake.rules rules
Project.tmpl X-specific variables
Lib.tmpl shared library variables
Imakefile
Library.tmpl library rules
Server.tmpl server rules
Threads.tmpl multi-threaded rules
```

Note that `site.def` is included twice, once before the `*.cf` file and once after. Although most site customizations should be specified after the `*.cf` file, some, such as the choice of compiler, need to be specified before, because other variable settings may depend on them.

The first time `site.def` is included, the variable `BeforeVendorCF` is defined, and the second time, the variable `AfterVendorCF` is defined. All code in `site.def` should be inside a `#ifdef` for one of these symbols.

FILES

<code>Imakefile.c</code>	Temporary input file for <code>cpp</code>
<code>/tmp/Imf.XXXXXX</code>	Temporary <code>Makefile</code> for <code>-s</code>
<code>/tmp/IIf.XXXXXX</code>	Temporary <code>Imakefile</code> if specified <code>Imakefile</code> uses <code>#</code> comments
<code>/lib/cpp</code>	Default C preprocessor

SEE ALSO

`make(1)`, `xmkmf(1)`

S. I. Feldman, *Make—A Program for Maintaining Computer Programs*.

ENVIRONMENT VARIABLES

The following environment variables may be set; however, their use is not recommended as they introduce dependencies that are not readily apparent when `imake` is run.

IMAKEINCLUDE	If defined, this should be a valid include argument for the C preprocessor. Example: <pre>-I/usr/include/local</pre> Actually, any valid <code>cpp</code> argument will work here.
IMAKECPP	If defined, this should be a valid path to a preprocessor program. Example: <pre>/usr/local/cpp</pre> By default, <code>imake</code> will use <code>/lib/cpp</code>.
IMAKEMAKE	If defined, this should be a valid path to a make program, such as <pre>/usr/local/make</pre> By default, <code>imake</code> will use whatever <code>make</code> program is found using <code>execvp(3)</code>. This variable is only used if the <code>-e</code> option is specified.

AUTHORS

Todd Brunhoff, Tektronix and MIT Project Athena

Jim Fulton, MIT X Consortium

X Version 11 Release 6

imgtoppm

`imgtoppm`—Convert an `Img-whatnot` file into a portable pixmap

SYNOPSIS

```
imgtoppm [imgfile]
```

DESCRIPTION

`imgtoppm` reads an `Img-whatnot` file as input and produces a portable pixmap as output. The `Img-whatnot` toolkit is available for FTP on `venera.isi.edu`, along with numerous images in this format.

SEE ALSO

`ppm(5)`

AUTHOR

Based on a simple conversion program posted to `comp.graphics` by Ed Falk.

Copyright© 1989 by Jef Poskanzer.

5 September 1989

inews

`inews`—Send a Usenet article to the local news server for distribution

SYNOPSIS

```
inews [ -h ][ -D ][ -O ][ -R ][ -S ][ header_flags ][ input ]
```

DESCRIPTION

`Inews` reads a Usenet news article (perhaps with headers) from the named file or standard input if no file is given. It adds some headers and performs some consistency checks. If the article does not meet these checks (for example, too much quoting of old articles, or posting to nonexistent newsgroups), then the article is rejected. If it passes the checks, `inews` sends the article to the local news server as specified in the `inn.conf(5)` file for distribution.

In the standard mode of operation, the input consists of the article headers, a blank line, and the message body. For compatibility with older software, the `-h` flag must be used. If there are no headers in the message, then this flag may be omitted.

Several headers may be specified on the command line, shown in the synopsis above as header flags. Each of these flags takes a single parameter; if the value is more than one word (for example, almost all Subject lines) then quotes must be used to prevent the shell from splitting it into multiple words. The options, and their equivalent headers, are as follows:

a	Approved
c	Control
d	Distribution
e	Expires
f	From
w	Followup-To
n	Newsgroups
r	Reply-To
t	Subject
F	References
o	Organization
x	Path prefix

The Path header is built according to the following rules. If the `-x` flag is used, then its value will be the start of the header. Any other host will see the site in the header, and therefore not offer the article to that site. If the `pathhost` configuration parameter is specified in the `inn.conf(5)` file, then it will be added to the Path. Otherwise, if the server configuration parameter is specified, then the full domain name of the local host will be added to the Path. The Path will always end `not-for-mail`.

The default Organization header will be provided if none is present in the article or if the `-o` flag is not used. To prevent adding the default, use the `-o` flag.

As a debugging aide, if the `-D` flag is used, the consistency checks will be performed, and the article will be sent to the standard output, rather than sent to the server.

For compatibility with C News, `inews` accepts, but ignores, the `-A`, `-V`, and `-W` flags. The C News `-N` flag is treated as the `-D` flag.

If a file named `.signature` exists in the user's home directory, `inews` will try to append it to the end of the article. If the file cannot be read, or if it is too long (for example, more than four lines or one standard I/O buffer), or if some other problem occurs, then the article will not be posted. To suppress this action, use the `-s` flag.

If the `-R` flag is used then `inews` will reject any attempts to post control messages.

If an unapproved posting is made to a moderated newsgroup, `inews` will try to mail the article to the moderator for posting. It uses the `moderators(5)` file to determine the mailing address. If no address is found, it will use the `inn.conf` file to determine a "last-chance" host to try.

If the NNTP server needs to authenticate the client, `inews` will use the `NNTPsendpass-word(3)` routine to authenticate itself. In order to do this, the program will need read access to the `passwd.nntp(5)` file. This is typically done by having the file group-readable and making `inews` run `setgid` to that group.

`Inews` exits with a zero status if the article was successfully posted or mailed, or with a nonzero status if the article could not be delivered.

Since `inews` will spool its input if the server is unavailable, it is usually necessary to run `rnews(1)` with the `-U` flag on a regular basis, usually out of `cron(8)`.

HISTORY

Written by Rich Salz (`rsalz@uunet.uu.net`) for *InterNetNews*.

SEE ALSO

`moderators(5)`, `inn.conf(5)`, `rnews(1)`

info

info—GNU's hypertext system

SYNOPSIS

```
info [ --option-name option-value ] menu-item...
```

DESCRIPTION

The GNU project has a hypertext system called `info` that allows the same source file to be either printed as a paper manual, or viewed using `info`. It is possible to use the `info` program from inside Emacs, or to use the standalone version described here. This manual page gives a brief summary of its capabilities.

OPTIONS

<code>--directory directory-path</code>	Add <code>directory-path</code> to the list of directory paths searched when <code>info</code> needs to find a file. You may issue <code>--directory</code> multiple times. Alternatively, you may specify a value for the environment variable <code>INFOPATH</code> ; if <code>--directory</code> is not given, the value of <code>INFOPATH</code> is used. The value of <code>INFOPATH</code> is a colon-separated list of directory names. If you do not supply either <code>INFOPATH</code> or <code>--directory-path</code> , <code>info</code> uses a default path.
<code>-f filename</code>	Specify a particular <code>info</code> file to visit. By default, <code>info</code> visits the file <code>dir</code> ; if you use this option, <code>info</code> will start with <code>(FILENAME)Top</code> as the first file and node.
<code>-n nodename</code>	Specify a particular node to visit in the initial file that <code>info</code> loads. This is especially useful in conjunction with <code>--file</code> . You may specify <code>--node</code> multiple times.
<code>-o file</code>	Direct output to <code>file</code> instead of starting an interactive <code>info</code> session.
<code>-h</code>	Produce a relatively brief description of the available <code>info</code> options.
<code>--version</code>	Print the version information of <code>info</code> and exit.
<code>menu-item</code>	<code>info</code> treats its remaining arguments as the names of menu items. The first argument is a menu item in the initial node visited, while the second argument is a menu item in the first argument's node. You can easily move to the node of your choice by specifying the menu names that describe the path to that node. For example, <code>info emacs buffers</code> first selects the menu item <code>emacs</code> in the node <code>(dir)Top</code> , and then selects the menu item <code>buffers</code> in the node <code>(emacs)Top</code> .

COMMANDS

In `info`, the following commands are available:

<code>h</code>	Invoke the <code>info</code> tutorial.
<code>?</code>	Get a short summary of <code>info</code> commands.
<code>h</code>	Select the <code>info</code> node from the main directory; this is much more complete than just using <code>?</code> .
<code>Ctrl-g</code>	Abort whatever you are doing.
<code>Ctrl-l</code>	Redraw the screen.

Selecting other nodes:

- `n` Move to the next node of this node.
- `p` Move to the previous node of this node.
- `u` Move to this node's up node.
- `m` Pick a menu item specified by name. Picking a menu item causes another node to be selected. You do not need to type a complete nodename; if you type a few letters and then a space or tab, `info` will try to fill in the rest of the nodename. If you ask for further completion without typing any more characters, you'll be given a list of possibilities; you can also get the list with `?`. If you type a few characters and then hit Enter, `info` will try to do a completion, and if it is ambiguous, use the first possibility.
- `f` Follow a cross reference. You are asked for the name of the reference, using command completion as for `m`.
- `l` Move to the last node you were at.

Moving within a node:

- `Space` Scroll forward a page.
- `DEL` Scroll backward a page.
- `b` Go to the beginning of this node.

Advanced commands:

- `q` Quit `info`.
- `1` Pick first item in node's menu.
- `2 — 5` Pick second to fifth item in node's menu.
- `g` Move to node specified by name. You may include a filename as well, as `(FILENAME)NODENAME`.
- `s` Search through this `info` file for a specified string, and select the node in which the next occurrence is found.
- `M-x print-node` Pipe the contents of the current node through the command in the environment variable `INFO_PRINT_COMMAND`. If the variable does not exist, the node is simply piped to `lpr`.

ENVIRONMENT

- `INFOPATH` A colon-separated list of directories to search for `info` files. Used if `--directory` is not given.
- `INFO_PRINT_COMMAND` The command used for printing.

SEE ALSO

`emacs(1)`

AUTHOR

Brian Fox, Free Software Foundation (bfox@ai.mit.edu)

MANUAL AUTHOR

Robert Lupton (rl1@astro.princeton.edu); updated by Robert J. Chassell (bob@gnu.ai.mit.edu).

7 December 1990

innconfval

`innconfval`—Get an *InterNetNews* configuration parameter

SYNOPSIS

```
innconfval [ -f ][parameter... ]
```

DESCRIPTION

Innconfval prints the values of the parameters specified on the command line. Values are retrieved from the inn.conf(5) file and are described there.

Values are retrieved by using the GetConfigValue routine, or GetFileConfigValue if the -f flag is used. Both are described in libinn(3).

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for *InterNetNews*.

SEE ALSO

libinn(3), inn.conf(5)

insmod

insmod—Install loadable modules (aout and ELF format)

SYNOPSIS

```
insmod [ -fkmsxv ] [ -o internal_name ] object_file [ symbol=value ... ]
```

DESCRIPTION

insmod installs a loadable module in the kernel.

insmod tries to load a module into the kernel, and resolves all symbols from the exported kernel symbols, with version information, if available. The module will get its name by removing the .o extension from the basename of the object file. If the .o extension is omitted, insmod will attempt to locate the module in some common default directories. If the environment contains the variable MODPATH, where all directories are separated with :, insmod will look in these directories for the module, in the specified order.

It is possible to load unversioned modules in a versioned kernel, and all combinations of these.

It is also possible to load ELF modules into an a.out kernel, and all combinations of these.

It is possible to stack modules, that is, let one module use a previously loaded module. All modules that are referenced are updated with this reference. This ensures that a module can't be unloaded if there is another module that refers to it.

It is possible to change integer values in the module when loading it. This makes it possible to tune the module.

The options are as follows:

- f The -f option tries to load the module even if the kernel or symbol versions differs from the version expected by the module. A warning will be issued if the module is locked to a specific kernel version that differs from the current version.
- k This option should really only be used by modprobe, to indicate that the module insertion was requested by kernald. All modules inserted using this option will be subject to autoremoval by the kernald utility if they have been unused for more that a minute. (The usage count is zero and no modules depend on this module.) If the kernel is not kernald-aware, the module will be rejected by the kernel. Just load it without the -k option, and all should be well.
- m The -m option will make insmod output a load map, that will make it easier to debug your modules after a kernel panic, thanks to Derek Atkins (warlord@MIT.EDU).
- o The -o option allows the module to be named to an explicit name instead of having a name derived from the name of the object file. Note that this option can also be placed after the module name, so that the syntax of insmod looks more similar to ld.

<code>symbol=value[,value] ...</code>	The values of all integer or character pointer symbols in the module can be changed at load-time by naming a symbol and giving the new value(s). If the symbol is defined as an array of integers or character pointers, the elements in the array can be initialized by giving the values separated by commas. Specific array entries can be skipped by omitting the value, as in <code>symbol=value1[,value2]</code> . Each integer value can be given as a decimal, octal, or hexadecimal value: 17, 021, or 0x11. If the first character in the given value is nonnumeric, the value is interpreted as a string. The symbol is assumed to be a character pointer, which will be initialized to point to the string. Extra space in the module will be allocated for the string itself. Note the syntax: no spaces are allowed around the = or , signs!
<code>-s</code>	With this option, <code>insmod</code> will produce debugging information and error messages using the <code>syslog</code> facility. (Also used by <code>kerneld</code> , if you have installed it.)
<code>-v</code>	If you want verbose information from the loading, select this option.
<code>-x</code>	The no-export flag, which will inhibit the default <code>insmod</code> behavior—inserting all the module's external symbols into the kernel symbol table. Note that the kernel will still update the references that the module makes to previously loaded modules.

SEE ALSO

`rmmod(1)`, `modprobe(1)`, `depmod(1)`, `lsmod(1)`, `ksyms(1)`, `modules(2)`, `gensyms(8)`

HISTORY

The module support was first conceived by Anonymous (as far as I know). Linux version by Bas Laarhoven (bas@vimec.nl). 0.99.14 version by Jon Tombs (jon@gtex02.us.es). Extended by Bjorn Ekwall (bj0rn@blox.se). ELF help from Eric Youngdale (eric@aib.com).

BUGS

`insmod` relies on the “fact” that symbols, for which one wants to change the value, are defined as integers or character pointers, and that `sizeof(int) == sizeof(char *)`.

Linux, 14 May 1995

install

`install`—Copy files and set their attributes; GNU file installer

SYNOPSIS

```
install [options] [-s] [--strip] source dest
install [options] [-s] [--strip] source... directory
install [options] [-d,--directory] directory...
```

Options:

```
[-c] [-g group] [-m mode] [-o owner] [--group=group] [--mode=mode]
[--owner=owner] [--help] [--version]
```

DESCRIPTION

This manual page documents the GNU version of `install`. `install` copies files and sets their permission modes and, if possible, their owner and group. Used similarly to `cp`; typically used in `Makefiles` to copy programs into their destination directories. It can also be used to create the destination directories and any leading directories, and to set the final directory's modes. It refuses to copy files onto themselves.

OPTIONS

<code>-c</code>	Ignored; for compatibility with old UNIX versions of <code>install</code> .
<code>-d, --directory</code>	Create each given directory and its leading directories, if they do not already exist. Set the owner, group, and mode as given on the command line or to the defaults. Also gives any leading directories that are created those attributes. This is different from the SunOS 4.x <code>install</code> , which gives directories that it creates the default attributes.
<code>-g, --group group</code>	Set the group ownership of the installed file or directory to the group ID of <code>group</code> (default is process's current group). <code>group</code> may also be a numeric group ID.
<code>-m, --mode mode</code>	Set the permission mode for the installed file or directory to <code>mode</code> , which can be either an octal number, or a symbolic mode as in <code>chmod</code> , with <code>0</code> as the point of departure. The default mode is <code>0755</code> .
<code>-o, --owner owner</code>	If run as root, set the ownership of the installed file to the user ID of <code>owner</code> (default is root). <code>owner</code> may also be a numeric user ID.
<code>-s, --strip</code>	Strip the symbol tables from installed programs.
<code>-help</code>	Print a usage message on standard output and exit successfully.
<code>--version</code>	Print version information on standard output and exit successfully.

GNU File Utilities

installit

installit—File/directory installation tool

SYNOPSIS

```
installit [ -o owner ][-g group ][-O owner ][-G group ][-m mode ][-b backup ]
[-s ][-t ] source destination
```

DESCRIPTION

`installit` puts a copy of `source` into the specified `destination`.

If `source` is a period, then `destination` is taken to be the name of a directory that should be created. Otherwise, `source` is taken to name an existing file and `destination` may be either a file or directory; it is interpreted according to the same rules as `cp(1)`.

If `destination` names a preexisting file, it will be removed before the copy is done. To make a backup copy, use the `-b` flag; the existing file will be renamed to have the specified extension. If `source` and `destination` are the same string, or if the two files are identical, then no copying is done, and only the `-o`, `-g`, `-m`, and `-s` flags are processed. In this case, the modification time on the `destination` will be updated using `touch(1)` unless the `-n` (don't touch) flag is used.

After the `destination` has been created, it is possible to set the owner, group, and mode that it should have. This is done by using the `-o`, `-g`, and `-m` flags, respectively. The `-o` and `-G` flags set the owner and group only if `installit` is being run by root, as determined by `whoami(1)`. To strip(1) an installed executable, use the `-s` flag.

Note that `installit` uses no special privileges to copy files from one place to another.

BUGS AND LIMITATIONS

Flags cannot be combined.

The `chown(8)` command must exist in either the `/etc` or `/usr/etc` directory or the user's `PATH`.

The `whoami` command must exist in the `/usr/ucb` directory or the user's `PATH`.

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for *InterNetNews*.

ispell, buildhash, munchlist, findaffix, tryaffix, icombine, ijoin

ispell, buildhash, munchlist, findaffix, tryaffix, icombine, ijoin--Interactive spelling checking

SYNOPSIS

```
ispell [common-flags][-M|-N][-Lcontext] [-V] files
ispell [common-flags] -l
ispell [common-flags][-f file] [-s|-a] -A
ispell [-d file][-w chars] -c
ispell [-d file][-w chars] -e[e]
ispell [-d file] -D
ispell -v[v]

common-flags: [-t][-n][-b][-x][-B][-C][-P][-m][-S][-d file][-p file][-w chars]
[-W n][-T type]

buildhash [-s] dict-file affix-file hash-file
buildhash -s count affix-file munchlist [-l aff-file][-c conv-file]
[-T suffix][-s hash-file] [-D][-v][-w chars][files] findaffix [-p|-s][-f][-c]
[-m min][-M max][-e elim][-t tabchar][-l low][files]

tryaffix [-p|-s] [-c] expanded-file affix[+addition]

icombine [-T type][aff-file]

ijoin [-s|-u] join-options file1 file2
```

DESCRIPTION

`ispell` is fashioned after the `spell` program from ITS (called `ispell` on Twenex systems.) The most common usage is `ispell filename`. In this case, `ispell` will display each word which does not appear in the dictionary at the top of the screen and allow you to change it. If there are “near misses” in the dictionary (words that differ by only a single letter, a missing or extra letter, a pair of transposed letters, or a missing space or hyphen), then they are also displayed on following lines. As well as near misses, `ispell` may display other guesses at ways to make the word from a known root, with each guess preceded by question marks. Finally, the line containing the word and the previous line are printed at the bottom of the screen. If your terminal can display in reverse video, the word itself is highlighted. You have the option of replacing the word completely or choosing one of the suggested words. Commands are single characters as follows (case is ignored):

R	Replace the misspelled word completely.
Space	Accept the word this time only.
A	Accept the word for the rest of this <code>ispell</code> session.
I	Accept the word, capitalized as it is in the file, and update private dictionary.
U	Accept the word, and add an uncapitalized (actually, all lowercase) version to the private dictionary.
0-n	Replace with one of the suggested words.
L	Look up words in system dictionary (controlled by the <code>WORDS</code> compilation option).
X	Write the rest of this file, ignoring misspellings, and start next file.
Q	Exit immediately and leave the file unchanged.
!	Shell escape.

<code>^L</code>	Redraw screen.
<code>^Z</code>	Suspend <code>ispell</code> .
<code>?</code>	Give help screen.

If the `-M` switch is specified, a one-line mini-menu at the bottom of the screen will summarize these options. Conversely, the `-N` switch may be used to suppress the mini-menu. (The mini-menu is displayed by default if `ispell` was compiled with the `MINIMENU` option, but these two switches will always override the default.)

If the `-L` flag is given, the specified number is used as the number of lines of context to be shown at the bottom of the screen. (The default is to calculate the amount of context as a certain percentage of the screen size.) The amount of context is subject to a system-imposed limit.

If the `-v` flag is given, characters that are not in the 7-bit ANSI printable character set will always be displayed in the style of cat `-v`, even if `ispell` thinks that these characters are legal ISO Latin-1 on your system. This is useful when working with older terminals. Without this switch, `ispell` will display 8-bit characters as if they have been defined as string characters for the chosen file type.

Besides the `-l`, `-a`, and `-A` options, Normal mode accepts the following common flags on the command line:

<code>-t</code>	The input file is in TeX or LaTeX format.
<code>-n</code>	The input file is in <code>nroff/troff</code> format.
<code>-b</code>	Create a backup file by appending <code>.bak</code> to the name of the input file.
<code>-x</code>	Don't create a backup file.
<code>-B</code>	Report run-together words with missing blanks as spelling errors.
<code>-C</code>	Consider run-together words as legal compounds.
<code>-P</code>	Don't generate extra root/affix combinations.
<code>-m</code>	Make possible root/affix combinations that aren't in the dictionary.
<code>-S</code>	Sort the list of guesses by probable correctness.
<code>-d file</code>	Specify an alternate dictionary file. For example, use <code>-d deutsch</code> to choose a German dictionary in a German installation.
<code>-p file</code>	Specify an alternate personal dictionary.
<code>-w chars</code>	Specify additional characters that can be part of a word.
<code>-W n</code>	Specify length of words that are always legal.
<code>-T type</code>	Assume a given formatter type for all files.

The `-n` and `-t` options select whether `ispell` runs in `nroff/troff` (`-n`) or TeX/LaTeX (`-t`) input mode. (The default is controlled by the `DEFTXFLAG` installation option.) TeX/LaTeX mode is also automatically selected if an input file has the extension `.tex`, unless overridden by the `-n` switch. In TeX/LaTeX mode, whenever a backslash (`\`) is found, `ispell` skips to the next whitespace or TeX/LaTeX delimiter. Certain commands contain arguments that should not be checked, such as labels and reference keys found in the `\cite` command, because they contain arbitrary, nonword arguments. Spell checking is also suppressed when in math mode. Thus, for example, given

```
\chapter {This is a Ckapter} \cite{SCH86}
```

`ispell` will find “Ckapter” but not “SCH.” The `-t` option does not recognize the TeX comment character `%`, so comments are also spell checked. It also assumes correct LaTeX syntax. Arguments to infrequently used commands and some optional arguments are sometimes checked unnecessarily. The bibliography will not be checked if `ispell` was compiled with `IGNOREBIB` defined. Otherwise, the bibliography will be checked but the reference key will not.

References for the `tib(1)` bibliography system (text between a `[` or `<` and `]` or `>`) will always be ignored in TeX/LaTeX mode.

The `-b` and `-x` options control whether `ispell` leaves a backup (`.bak`) file for each input file.

The `.bak` file contains the precorrected text. If there are file opening/writing errors, the `.bak` file may be left for recovery purposes even with the `-x` option. The default for this option is controlled by the `DEFNOBACKUPFLAG` installation option.

The `-B` and `-C` options control how `ispell` handles run-together words, such as *notthe* for *not the*. If `-B` is specified, such words will be considered errors, and `ispell` will list variations with an inserted blank or hyphen as possible replacements. If `-C` is specified, run-together words will be considered to be legal compounds, so long as both components are in the dictionary, and each component is at least as long as a language-dependent minimum (three characters, by default). This is useful for languages such as German and Norwegian, where many compound words are formed by concatenation. (Note that compounds formed from three or more root words will still be considered errors). The default for this option is language-dependent; in a multilingual installation, the default may vary depending on which dictionary you choose.

The `-P` and `-m` options control when `ispell` automatically generates suggested root/affix combinations for possible addition to your personal dictionary. (These are the entries in the “guess” list that are preceded by question marks.) If `-P` is specified, such guesses are displayed only if `ispell` cannot generate any possibilities that match the current dictionary. If `-m` is specified, such guesses are always displayed. This can be useful if the dictionary has a limited word list, or a word list with few suffixes. However, you should be careful when using this option, as it can generate guesses that produce illegal words. The default for this option is controlled by the dictionary file used.

The `-S` option suppresses `ispell`’s normal behavior of sorting the list of possible replacement words. Some people may prefer this, since it somewhat enhances the probability that the correct word will be low-numbered.

The `-d` option is used to specify an alternate hashed dictionary file, other than the default. If the filename does not contain a `/`, the library directory for the default dictionary file is prefixed; thus, to use a dictionary in the local directory `-d ./xxx.hash` must be used. This is useful to allow dictionaries for alternate languages. Unlike previous versions of `ispell`, a dictionary of `/dev/null` is illegal because the dictionary contains the affix table. If you need an effectively empty dictionary, create a one-entry list with an unlikely string (for example, “qqqq”).

The `-p` option is used to specify an alternate personal dictionary file. If the filename does not begin with `/`, `$HOME` is prefixed. Also, the shell variable `WORDLIST` may be set, which renames the personal dictionary in the same manner. The command line overrides any `WORDLIST` setting. If neither the `-p` switch nor the `WORDLIST` environment variable is given, `ispell` will search for a personal dictionary in both the current directory and `$HOME`, creating one in `$HOME` if none is found. The preferred name is constructed by appending `.ispell` to the base name of the hash file. For example, if you use the English dictionary, your personal dictionary would be named `.ispell_english`. However, if the file `.ispell_words` exists, it will be used as the personal dictionary regardless of the language hash file chosen. This feature is included primarily for backwards compatibility.

If the `-p` option is not specified, `ispell` will look for personal dictionaries in both the current directory and the home directory. If dictionaries exist in both places, they will be merged. When words are added to the personal dictionary, they will be written to the current directory if a dictionary already existed in that place; otherwise, they will be written to the dictionary in the home directory.

The `-w` option may be used to specify characters other than alphabetics that may also appear in words. For instance, `-w "&"` will allow “AT&T” to be picked up. Underscores are useful in many technical documents. There is an admittedly crude provision in this option for 8-bit international characters. Nonprinting characters may be specified in the usual way by inserting a backslash followed by the octal character code, for example, `\014` for a form feed. Alternatively, if `n` appears in the character string, the (up to) three characters following are a decimal code, 0–255, for the character. For example, to include bells and form feeds in your words (an admittedly silly thing to do, but aren’t most pedagogical examples):

```
n007n012
```

Numeric digits other than the three following `n` are simply numeric characters. Use of `n` does not conflict with anything because actual alphabetics have no meaning; alphabetics are already accepted. `ispell` will typically be used with input from a file, meaning that preserving parity for possible 8-bit characters from the input text is okay. If you specify the `-l` option, and actually type text from the terminal, this may create problems if your `stty` settings preserve parity.

The `-w` option may be used to change the length of words that `ispell` always accepts as legal. Normally, `ispell` will accept all one-character words as legal, which is equivalent to specifying `-w 1`. (The default for this switch is actually controlled by the `MINWORD` installation option, so it may vary at your installation.) If you want all words to be checked against the dictionary, regardless of length, you might want to specify `-w 0`. On the other hand, if your document specifies to accept all words of three letters or less, then regardless of the setting of this option, `ispell` will only generate words that are in the dictionary as suggested replacements for words; this prevents the list from becoming too long. Obviously, this option can be very

dangerous, since short misspellings may be missed. If you use this option a lot, you should probably make a last pass without it before you publish your document, to protect yourself against errors.

The `-T` option is used to specify a default formatter type for use in generating string characters. This switch overrides the default type determined from the filename. The `type` argument may be either one of the unique names defined in the language affix file (such as `nroff`) or a file suffix including the dot (for example, `.tex`). If no `-T` option appears and no type can be determined from the filename, the default string character type declared in the language affix file will be used.

The `-l` or `list` option to `ispell` is used to produce a list of misspelled words from the standard input.

The `-a` option is intended to be used from other programs through a pipe. In this mode, `ispell` prints a one-line version identification message, and then begins reading lines of input. For each input line, a single line is written to the standard output for each word checked for spelling on the line. If the word was found in the main dictionary, or your personal dictionary, then the line contains only a `*`. If the word was found through affix removal, then the line contains a `+`, a space, and the root word. If the word was found through compound formation (concatenation of two words, controlled by the `-c` option), then the line contains only a `-`.

If the word is not in the dictionary, but there are near misses, then the line contains an `&`, a space, the misspelled word, a space, the number of near misses, the number of characters between the beginning of the line and the beginning of the misspelled word, a colon, another space, and a list of the near misses separated by commas and spaces. Following the near misses (and identified only by the count of near misses), if the word could be formed by adding (illegal) affixes to a known root, is a list of suggested derivations, again separated by commas and spaces. If there are no near misses at all, the line format is the same, except that the `&` is replaced by `?` (and the near-miss count is always zero). The suggested derivations following the near misses are in the form:

```
[prefix+] root [-prefix] [-suffix] [+suffix]
```

(for example, “re+fry-y+ies” to get “refries”) where each optional `px` and `sfx` is a string. Also, each near miss or guess is capitalized the same as the input word unless such capitalization is illegal; in the latter case each near miss is capitalized correctly according to the dictionary.

Finally, if the word does not appear in the dictionary, and there are no near misses, then the line contains a `#`, a space, the misspelled word, a space, and the character offset from the beginning of the line. Each sentence of text input is terminated with an additional blank line, indicating that `ispell` has completed processing the input line.

These output lines can be summarized as follows:

```
OK:                *
Root:              + <root>
Compound:         -
Miss:              & <original><count><offset>: <miss>, <miss>, ..., <guess>, ...
Guess:            ? <original> 0 <offset>: <guess>, <guess>, ...
None:             # <original> <offset>
```

For example, a dummy dictionary containing the words *fray*, *Frey*, *fry*, and *refried* might produce the following response to the command `echo 'frqy refries' | ispell -a -m -d ./test.hash`:

```
(#) International Ispell Version 3.0.05 (beta), 08/10/91
& frqy 3 0: fray, Frey, fry
& refries 1 5: refried, re+fry-y+ies
```

This mode is also suitable for interactive use when you want to figure out the spelling of a single word.

The `-A` option works just like `-a`, except that if a line begins with the string “&Include File&”, the rest of the line is taken as the name of a file to read for further words. Input returns to the original file when the `include` file is exhausted. Inclusion may be nested up to five deep. The key string may be changed with the environment variable `INCLUDE_STRING` (the ampersands, if any, must be included).

When in the `-a` mode, `ispell` will also accept lines of single words prefixed with any of the following: `*`, `&`, `@`, `+`, `-`, ```, `#`, `!`, `%`, or `^`. A line starting with `*` tells `ispell` to insert the word into the user's dictionary (similar to the `I` command). A line starting with `&` tells `ispell` to insert an all-lowercase version of the word into the user's dictionary (similar to the `U` command). A line starting with `@` causes `ispell` to accept this word in the future (similar to the `A` command). A line starting with `+`, followed immediately by `tex` or `nroff`, will cause `ispell` to parse future input according to the syntax of that formatter. A line consisting solely of a `+` will place `ispell` in TeX/LaTeX mode (similar to the `-t` option) and `-` returns `ispell` to `nroff/troff` mode (but these commands are obsolete). However, string character type is not changed; the ``` command must be used to do this. A line starting with ``` causes `ispell` to set internal parameters (in particular, the default string character type) based on the filename given in the rest of the line. (A file suffix is sufficient, but the period must be included. Instead of a filename or suffix, a unique name, as listed in the language affix file, may be specified.) However, the formatter parsing is not changed; the `+` command must be used to change the formatter. A line prefixed with `#` will cause the personal dictionary to be saved. A line prefixed with `!` will turn on terse mode (explained later in this subsection), and a line prefixed with `%` will return `ispell` to normal (non-terse) mode. Any input following the prefix characters `+`, `-`, `#`, `!`, or `%` is ignored, as is any input following the filename on a ``` line. To allow spell checking of lines beginning with these characters, a line starting with `^` has that character removed before it is passed to the spell checking code. It is recommended that programmatic interfaces prefix every data line with an up arrow to protect themselves against future changes in `ispell`.

To summarize these:

<code>*</code>	Add to personal dictionary
<code>@</code>	Accept word, but leave out of dictionary
<code>#</code>	Save current personal dictionary
<code>`</code>	Set parameters based on filename
<code>+</code>	Enter TeX mode
<code>-</code>	Exit TeX mode
<code>!</code>	Enter terse mode
<code>%</code>	Exit terse mode
<code>^</code>	Spell check rest of line

In terse mode, `ispell` will not print lines beginning with `*`, `+`, or `-`, all of which indicate correct words. This significantly improves running speed when the driving program is going to ignore correct words anyway.

The `-s` option is only valid in conjunction with the `-a` or `-A` options, and only on BSD-derived systems. If specified, `ispell` will stop itself with a `SIGTSTP` signal after each line of input. It will not read more input until it receives a `SIGCONT` signal. This may be useful for handshaking with certain text editors.

The `-f` option is only valid in conjunction with the `-a` or `-A` options. If `-f` is specified, `ispell` will write its results to the given file, rather than to standard output.

The `-v` option causes `ispell` to print its current version identification on the standard output and exit. If the switch is doubled, `ispell` will also print the options that it was compiled with.

The `-c`, `-e[1-4]`, and `-D` options of `ispell` are primarily intended for use by the `munchlist` shell script. The `-c` switch causes a list of words to be read from the standard input. For each word, a list of possible root words and affixes will be written to the standard output. Some of the root words will be illegal and must be filtered from the output by other means; the `munchlist` script does this. As an example, the command

```
echo BOTHER | ispell -c
```

produces

```
BOTHER BOTHE/R BOTH/R
```

The `-e` switch is the reverse of `-c`; it expands affix flags to produce a list of words. For example, the command

```
echo BOTH/R | ispell -e
```

produces

```
BOTH BOTHER
```

An optional expansion level can also be specified. A level of 1 (`-e1`) is the same as `-e` alone. A level of 2 causes the original root/affix combination to be prepended to the line:

```
BOTH/R BOTH BOTHER
```

A level of 3 causes multiple lines to be output, one for each generated word, with the original root/affix combination followed by the word it creates:

```
BOTH/R BOTH
BOTH/R BOTHER
```

A level of 4 causes a floating-point number to be appended to each of the level 3 lines, giving the ratio between the length of the root and the total length of all generated words including the root:

```
BOTH/R BOTH 2.500000
BOTH/R BOTHER 2.500000
```

Finally, the `-D` flag causes the affix tables from the dictionary file to be dumped to standard output.

Unless your system administrator has suppressed the feature to save space, `ispell` is aware of the correct capitalizations of words in the dictionary and in your personal dictionary. As well as recognizing words that must be capitalized (such as *George*) and words that must be all capitals (such as *NASA*), it can also handle words with unusual capitalization (for example, *IT-Corp* or *TeX*). If a word is capitalized incorrectly, the list of possibilities will include all acceptable capitalizations. (More than one capitalization may be acceptable; for example, my dictionary lists both *ITCorp* and *ITcorp*.)

Normally, this feature will not cause you surprises, but there is one circumstance you need to be aware of. If you use `I` to add a word to your dictionary that is at the beginning of a sentence (for example, the first word of this paragraph if *normally* were not in the dictionary), it will be marked as “capitalization required.” A subsequent usage of this word without capitalization will be considered a misspelling by `ispell`, and it will suggest the capitalized version. You must then compare the actual spellings by eye, and then type `I` to add the uncapitalized variant to your personal dictionary. You can avoid this problem by using `U` to add the original word, rather than `I`.

The rules for capitalization are as follows:

1. Any word may appear in all capitals, as in headings.
2. Any word that is in the dictionary in all lowercase form may appear either in lowercase or capitalized (as at the beginning of a sentence).
3. Any word that has unusual capitalization (that is, it contains both cases and there is an uppercase character besides the first) must appear exactly as in the dictionary, except as permitted by rule 1. If the word is acceptable in all lowercase, it must appear thus in a dictionary entry.

buildhash

The `buildhash` program builds hashed dictionary files for later use by `ispell`. The raw word list (with affix flags) is given in `dict-file`, and the affix flags are defined by `affix-file`. The hashed output is written to `hash-file`. The formats of the two input files are described in `ispell(4)`. The `-s` (silent) option suppresses the usual status messages that are written to the standard error device.

munchlist

The `munchlist` shell script is used to reduce the size of dictionary files, primarily personal dictionary files. It is also capable of combining dictionaries from various sources. The given files are read (standard input if no arguments are given), reduced to a minimal set of roots and affixes that will match the same list of words, and written to standard output.

Input for `munchlist` contains of raw words (such as those from your personal dictionary files) or root and affix combinations (probably generated in earlier `munchlist` runs). Each word or root/affix combination must be on a separate line.

The `-D` (debug) option leaves temporary files around under standard names instead of deleting them, so that the script can be debugged. Warning: This option can eat up an enormous amount of temporary file space.

The `-v` (verbose) option causes progress messages to be reported to `stderr` so you won't get nervous that `munchlist` has hung.

If the `-s` (strip) option is specified, words that are in the specified `hash-file` are removed from the word list. This can be useful with personal dictionaries.

The `-l` can be used to specify an alternate `affix-file` for munching dictionaries in languages other than English.

The `-c` option can be used to convert dictionaries that were built with an older affix file, without risk of accidentally introducing unintended affix combinations into the dictionary.

The `-T` option allows dictionaries to be converted to a canonical string-character format. The suffix specified is looked up in the affix file (`-l` switch) to determine the string-character format used for the input file; the output always uses the canonical string-character format. For example, a dictionary collected from TeX source files might be converted to canonical format by specifying `-T tex`.

The `-w` option is passed on to `ispell`.

findaffix

The `findaffix` shell script is an aid to writers of new language descriptions in choosing affixes. The given dictionary files (standard input if none are given) are examined for possible prefixes (`-p` switch) or suffixes (`-s` switch, the default). Each commonly occurring affix is presented along with a count of the number of times it appears and an estimate of the number of bytes that would be saved in a dictionary hash file if it were added to the language table. Only affixes that generate legal roots (found in the original input) are listed.

If the `-c` option is not given, the output lines are in the following format:

```
strip/add/count/bytes
```

where `strip` is the string that should be stripped from a root word before adding the affix, `add` is the affix to be added, `count` is a count of the number of times that this `strip/add` combination appears, and `bytes` is an estimate of the number of bytes that might be saved in the raw dictionary file if this combination is added to the affix file. The field separator in the output will be the tab character specified by the `-t` switch; the default is a slash (/).

If the `-c` (clean output) option is given, the appearance of the output is made visually cleaner (but harder to post process) by changing it to

```
-strip+add<tab>count<tab>bytes
```

where `strip`, `add`, `count`, and `bytes` are as before, and `<tab>` represents the ASCII tab character.

The method used to generate possible affixes will also generate longer affixes which have common headers or trailers. For example, the two words *moth* and *mother* will generate not only the obvious substitution `+er` but also `-h+her` and `-th+ther` (and possibly even longer ones, depending on the value of `min`). To prevent cluttering the output with such affixes, any affix pair that shares a common header (or, for prefixes, trailer) string longer than `elim` characters (default 1) will be suppressed. You may want to set `elim` to a value greater than 1 if your language has string characters; usually, the need for this parameter will become obvious when you examine the output of your `findaffix` run.

Normally, the affixes are sorted according to the estimate of bytes saved. The `-f` switch may be used to cause the affixes to be sorted by frequency of appearance.

To save output file space, affixes which occur fewer than 10 times are eliminated; this limit may be changed with the `-l` switch. The `-m` switch specifies a maximum affix length (default 8). Affixes longer than this will not be reported. (This saves on temporary disk space and makes the script run faster.)

Affixes which generate stems shorter than three characters are suppressed. (A stem is the word after the `strip` string has been removed, and before the `add` string has been added.) This reduces both the running time and the size of the output file. This limit may be changed with the `-m` switch. The minimum stem length should only be set to 1 if you have a lot of free time and disk space (in the range of many days and hundreds of megabytes).

The `findaffix` script requires a nonblank field-separator character for internal use. Normally, this character is a slash (/), but if the slash appears as a character in the input word list, a different character can be specified with the `-t` switch.

`ispell` dictionaries should be expanded before being fed to `findaffix`; in addition, characters that are not in the English alphabet (if any) should be translated to lowercase.

tryaffix

The `tryaffix` shell script is used to estimate the effectiveness of a proposed prefix (`-p` switch) or suffix (`-s` switch, the default) with a given `expanded-file`. Only one affix can be tried with each execution of `tryaffix`, although multiple arguments can be used to describe varying forms of the same affix flag (for example, the `D` flag for English can add either `D` or `ED` depending on whether a trailing *E* is already present). Each word in the expanded dictionary that ends (or begins) with the chosen suffix (or prefix) has that suffix (prefix) removed; the dictionary is then searched for root words that match the stripped word. Normally, all matching roots are written to standard output, but if the `-c` (count) flag is given, only a statistical summary of the results is written. The statistics given are a count of words the affix potentially applies to and an estimate of the number of dictionary bytes that a flag using the affix would save. The estimate will be high if the flag generates words that are currently generated by other affix flags (for example, in English, *bathers* can be generated by either *bath/X* or *bather/S*). The dictionary file, `expanded-file`, must already be expanded (using the `-e` switch of `ispell`) and sorted, and things will usually work best if uppercase has been folded to lower with `tr`.

The affix arguments are things to be stripped from the dictionary file to produce trial roots: for English, `con` (prefix) and `ing` (suffix) are examples. The addition parts of the argument are letters that would have been stripped off the root before adding the affix. For example, in English the affix `ing` normally strips `e` for words ending in that letter (for example, *like* becomes *liking*), so we might run

```
tryaffix ing ing+e
```

to cover both cases.

All of the shell scripts contain documentation as commentary at the beginning; sometimes these comments contain useful information beyond the scope of this manual page.

It is possible to install `ispell` in such a way as to only support ASCII range text if desired.

icombine

The `icombine` program is a helper for `munchlist`. It reads a list of words in dictionary format (roots plus flags) from the standard input, and produces a reduced list of standard output that combines common roots found on adjacent entries. Identical roots that have differing flags will have their flags combined, and roots that have differing capitalizations will be combined in a way that only preserves important capitalization information. The optional `aff-file` specifies a language file that defines the character sets used and the meanings of the various flags. The `-T` switch can be used to select among alternative string character types by giving a dummy suffix that can be found in an `altstringtype` statement.

ijoin

The `ijoin` program is a reimplement of `join(1)`, which handles long lines and 8-bit characters correctly. The `-s` switch specifies that the `sort(1)` program used to prepare the input to `ijoin` uses signed comparisons on 8-bit characters; the `-u` switch specifies that `sort(1)` uses unsigned comparisons. All other options and behaviors of `join(1)` are duplicated as exactly as possible based on the manual page, except that `ijoin` will not handle newline as a field separator. See the `join(1)` manual page for more information.

ENVIRONMENT

DICTIONARY	Default dictionary to use if no <code>-d</code> flag is given
WORDLIST	Personal dictionary filename
INCLUDE_STRING	Code for file inclusion under the <code>-A</code> option
TMPDIR	Directory used for some of <code>munchlist</code> 's temporary files

FILES

!!LIBDIR!!!DEFHASH!!	Hashed dictionary (may be found in some other local directory, depending on the system)
!!LIBDIR!!!DEFLANG!!	Affix-definition file for <code>munchlist</code>
/usr/dict/web2 or /usr/dict/words	For the Lookup function (depending on the <code>WORDS</code> compilation option)
	User's private dictionary
.ispell_hashfile	Directory-specific private dictionary

SEE ALSO

`spell(1)`, `egrep(1)`, `look(1)`, `join(1)`, `sort(1)`, `sq(1L)`, `tib(1L)`, `ispell(4L)`, `english(4L)`

BUGS

It takes several to many seconds for `ispell` to read in the hash table, depending on size.

When all options are enabled, `ispell` may take several seconds to generate all the guesses at corrections for a misspelled word; on slower machines this time is long enough to be annoying.

The hash table is stored as a quarter-megabyte (or larger) array, so a PDP-11 or 286 version does not seem likely.

`IsPELL` should understand more `troff` syntax, and deal more intelligently with contractions.

Although small personal dictionaries are sorted before they are written out, the order of capitalizations of the same word is somewhat random.

When the `-x` flag is specified, `ispell` will unlink any existing BAK file.

There are too many flags, and many of them have non-mnemonic names.

`munchlist` does not deal very gracefully with dictionaries that contain nonword characters. Such characters ought to be deleted from the dictionary with a warning message. `findaffix` and `munchlist` require tremendous amounts of temporary file space for large dictionaries. They do respect the `TMPDIR` environment variable, so this space can be redirected. However, a lot of the temporary space needed is for sorting, so `TMPDIR` is only a partial help on systems with an uncooperative `sort(1)`. (*Cooperative* is defined as accepting the undocumented `-T` switch). At its peak usage, `munchlist` takes 10 to 40 times the original dictionary's size in kilobytes. (The larger ratio is for dictionaries that already have heavy affix use, such as the one distributed with `ispell`). `munchlist` is also very slow; munching a normal-sized dictionary (15KB roots, 45KB expanded words) takes around an hour on a small workstation. (Most of this time is spent in `sort(1)`, and `munchlist` can run much faster on machines that have a more modern sort that makes better use of the memory available to it.) `findaffix` is even worse; the smallest English dictionary cannot be processed with this script in a mere 50KB of free space, and even after specifying switches to reduce the temporary space required, the script will run for more than 24 hours on a small workstation.

AUTHORS

Pace Willisson (`pace@mit-vax`), 1983, based on the PDP-10 assembly version. That version was written by R. E. Gorin in 1971, and later revised by W. E. Matson (1974) and W. B. Ackerman (1978). Collected, revised, and enhanced for the Usenet by Walt Buehring, 1987. Table-driven multilingual version by Geoff Kuenning, 1987–88. Large dictionaries provided by Bob Devine (`vianet!devine`). A complete list of contributors is too large to list here, but is distributed with the `ispell` sources in the file `Contributors`.

VERSION

The version of `ispell` described by this manual page is International Ispell version 3.1.00, October 8, 1993.

join

`join`—Join lines of two files on a common field

SYNOPSIS

```
join [-a 1|2] [-v 1|2] [-e empty-string] [-o field-list...] [-t char]
[-j[1|2] field] [-1 field] [-2 field] file1 file2
join {--help,--version}
```

DESCRIPTION

This manual page documents the GNU version of `join`. `join` prints to the standard output a line for each pair of input lines, one each from `file1` and `file2`, that have identical join fields. Either filename (but not both) can be `-`, meaning the standard

input. `file1` and `file2` should be already sorted in increasing order (not numerically) on the join fields; unless the `-t` option is given, they should be sorted ignoring blanks at the start of the line, as `sort` does when given the `-b` option.

The defaults are the following: The `join` field is the first field in each line; fields in the input are separated by one or more blanks, with leading blanks on the line ignored; fields in the output are separated by a space; each output line consists of the join field, the remaining fields from `file1`, then the remaining fields from `file2`.

OPTIONS

<code>-a file-number</code>	Print a line for each unpairable line in file <code>file-number</code> (either 1 or 2), in addition to the normal output.
<code>-e string</code>	Replace empty output fields (those that are missing in the input) with <code>string</code> .
<code>-1, -j1 field</code>	Join on field <code>field</code> (a positive integer) of file 1.
<code>-2, -j2 field</code>	Join on field <code>field</code> (a positive integer) of file 2.
<code>-j field</code>	Equivalent to <code>-1 field -2 field</code> .
<code>-o field-list...</code>	Construct each output line according to the format in <code>field-list</code> . Each element in <code>field-list</code> consists of a file number (either 1 or 2), a period, and a field number (a positive integer). The elements in the list are separated by commas or blanks. Multiple <code>field-list</code> arguments can be given after a single <code>-o</code> option; the values of all lists given with <code>-o</code> are concatenated together.
<code>-t char</code>	Use character <code>char</code> as the input and output field separator.
<code>-v file-number</code>	Print a line for each unpairable line in file <code>file-number</code> (either 1 or 2), instead of the normal output.

In addition, when GNU `join` is invoked with exactly one argument, the following options are recognized:

<code>--help</code>	Print a usage message on standard output and exit successfully.
<code>--version</code>	Print version information on standard output, then exit successfully.

GNU Text Utilities

kill

`kill`—Terminate a process

SYNOPSIS

```
kill [ -s signal | -p ] [-a]pid ...
kill -l [ signal ]
```

DESCRIPTION

`kill` sends the specified signal to the specified process. If no signal is specified, the `TERM` signal is sent. The `TERM` signal will kill processes that do not catch this signal. For other processes, it may be necessary to use the `KILL(9)` signal because this signal cannot be caught.

Most modern shells have a built-in `kill` function.

OPTIONS

<code>pid ...</code>	Specify the list of processes that <code>kill</code> should signal. Each <code>pid</code> can be a process ID, or a process name.
<code>-s</code>	Specify the signal to send. The signal may be given as a signal name or number.
<code>-p</code>	Specify that <code>kill</code> should only print the process ID (<code>pid</code>) of the named process, and should not send it a signal.
<code>-l</code>	Print a list of signal names. These are found in <code>/usr/include/linux/signal.h</code> .

SEE ALSO

`bash(1)`, `tcsh(1)`, `kill(2)`, `sigvec(2)`

AUTHOR

Taken from BSD 4.4. The ability to translate process names to process ids was added by Salvatore Valente (<svalente@mit.edu>).

Linux Utilities, 14 October 1994

killall

killall—Kill processes by name

SYNOPSIS

```
killall [-iv][-signal] name ...
killall [-l]
```

DESCRIPTION

killall sends a signal to all processes running any of the specified commands. If no signal name is specified, SIGTERM is sent.

Signals can be specified either by name (for example, -HUP) or by number (for example, -1). Signal 0 (check if a process exists) can only be specified by number.

If the command name contains a slash (/), processes executing that particular file will be selected for killing, independent of their name.

killall returns a nonzero return code if no process has been killed for any of the listed commands. If at least one process has been killed for each command, killall returns zero.

A killall process never kills itself (but may kill other killall processes).

OPTIONS

- i Interactively ask for confirmation of killing.
- l List all known signal names.
- v Report if the signal was successfully sent.

FILES

/proc Location of the proc filesystem

KNOWN BUGS

Killing by file only works for executables that are kept open during execution; that is, impure executables can't be killed this way.

AUTHOR

Werner Almesberger (almesber@di.epfl.ch)

SEE ALSO

kill(1), fuser(1), ps(1), kill(2)

Linux, 11 October 1994

ksyms

ksyms—Shows the exported kernel symbols

SYNOPSIS

```
ksyms [-a][-h][-m]
```


DESCRIPTION

ksyms shows information about all exported kernel symbols. The format is
address name [defining module]

The describing header can be turned off with the option `-h`.

Normally, only the symbols defined by the loaded modules are shown, but with the option `-a`, all exported symbols can be seen.

The information can also be seen in `/proc/ksyms`. A shell-script version `ksyms.sh` can be used to get the information from `/proc/ksyms` instead, but this program gets the symbol information directly from the kernel with a system call.

With the option `-m` (stands for memory map), you can also see the starting address and the size of the allocated memory for every loaded module.

SEE ALSO

`insmod(1)`, `modprobe(1)`, `depmod(1)`, `rmmod(1)`, `lsmod(1)`, `modules(2)`

HISTORY

The `ksyms` command was first conceived by Bjorn Ekwall (bjørn@blox.se). The `-m` option was inspired by David Hinds (dhinds@allegro.stanford.edu)

BUGS

`Ksyms` might have some, but they are well hidden....

Linux, 14 May 1995

last

`last`—Indicate last logins by user or terminal

SYNOPSIS

```
last [-number] [-f filename] [-t tty] [-h hostname] [-i address] [-l] [-y] [name...]
```

DESCRIPTION

`Last` looks back in the `wtmp` file, which records all logins and logouts for information about a user, a teletype, or any group of users and teletypes. Arguments specify names of users or teletypes of interest. If multiple arguments are given, the information that applies to any of the arguments is printed. For example `last root console` would list all of `root`'s sessions as well as all sessions on the console terminal. `Last` displays the sessions of the specified users and teletypes, most recent first, indicating the times at which the session began, the duration of the session, and the teletype that the session took place on. If the session is still continuing or was cut short by a reboot, `last` so indicates.

The pseudo-user `reboot` logs in at reboots of the system.

`Last` with no arguments displays a record of all logins and logouts, in reverse order.

If `last` is interrupted, it indicates how far the search has progressed in `wtmp`. If interrupted with a quit signal, `last` indicates how far the search has progressed so far, and the search continues.

OPTIONS

<code>-number</code>	Limit the number of entries displayed to that specified by <code>number</code> .
<code>-f filename</code>	Use <code>filename</code> as the name of the accounting file instead of <code>/var/log/wtmp</code> .
<code>-h hostname</code>	List only logins from <code>hostname</code> .
<code>-i IP address</code>	List only logins from <code>IP address</code> .

- l List IP addresses of remote hosts instead of truncated hostnames.
- t tty List only logins on tty.
- y Also report year of dates.

FILES

`/var/log/wtmp` Login database

20 March 1992

lbxproxy

lbxproxy—LBX proxy server for the X Window system

SYNOPSIS

`lbxproxy [:displaynumber] [option ...]`

NOTE

This manual page is not definitive or “official.” It is derived from information contained in the `README` file in the `lbx` source.

DESCRIPTION

lbxproxy is the Low Bandwidth X pseudo-server. It runs on the remote side of low bandwidth, high-latency connections, such as serial lines and wide area networks. It accepts connections from X clients at the remote end and forwards them to an X server at the local end. The LBX protocol used for the low bandwidth connection includes compression and optimizations designed to make effective use of the bandwidth available. The current version of LBX is not a standard of the X Consortium, and will not be compatible with the final version. The current version should be treated as an “alpha” or “prototype” for people interested in experimenting with it.

OPTIONS

lbxproxy accepts the following options:

- `:displaynumber` lbxproxy runs as the given `displaynumber`, which by default is `0`. A value different from `0` should be used if the host running lbxproxy has a local X display. If multiple lbxproxy servers or other X servers are to run simultaneously on a host, each must have a unique display number. (See the “Display Names” section of the `x(1)` manual page to learn how to specify which display number clients should try to use.)
- `-ac` Disables host-based access control mechanisms. Enables access by any host, and permits any host to modify the access control list. Use with extreme caution. This option exists primarily for running test suites remotely.
- `-display display-number` Sets the name of the X server display that lbxproxy connects to.
- `-help` Prints a usage message.
- `-I` Causes all remaining command-line arguments to be ignored.
- `-to seconds` Sets default connection time-out in seconds.

NETWORK CONNECTIONS

lbxproxy supports client connections via most of the connection types supported by the X servers. (Refer to the `xserver(1)` manual page and hardware-specific X server manual pages for details.) Note that in the current implementation some of the connections types have not been implemented correctly. This mostly applies to System V.

EXAMPLES

To setup lbxproxy, start the X server as usual, and then start the proxy. The lbxproxy is a pseudo-server, so any clients that wish to use it need to adjust their DISPLAY. By default, the proxy will listen on <hostname>:1. This can be changed with the :displaynumber argument.

If the proxy is to be running on a host named sharedhost, connecting to an LBX-capable X server on a desktop machine named mydesktop, you could use the following command to start the proxy (which would be known as display sharedhost:7):

```
mydesktop% rlogin sharedhost
sharedhost% lbxproxy -display mydesktop:0 :7 &
sharedhost% xclient -display sharedhost:7
```

If you are running LBX over a TERM connection between mydesktop and sharedhost, try something like this:

```
mydesktop% trsh
sharedhost% tredir -r 6008 6000
sharedhost% lbxproxy -display sharedhost:8 :7 &
sharedhost% xclient -display sharedhost:7
```

SEE ALSO

General information: x(1)

Server-specific man pages: Xserver(1), Xdec(1), XmacII(1), Xsun(1), Xnest(1), Xvfb(1), XF86_Accel(1), XF86_Mono(1), XF86_SVGA(1), XF86_VGA16(1), XFree86(1)

AUTHORS

The LBX team includes Dave Lemke, Dale Tonogai, Keith Packard, Jim Fulton from NCD, and Chris Kanterjiev from Xerox.

X Version 11 Release 6

ld

ld—The GNU linker

SYNOPSIS

```
ld [ -o.I output ] .I objfile . . . .br .RB ["-A output ] objfile ...
[-A architecture ] [-b\ input-format ] [-Bstatic ] [-c\ commandfile ]
[ -d|-dc|-dp ]
[ -defsym\ symbol = expression ] [-e\ entry ] [-F ] [-F\ format ] [-
format\ input-format ] [-g ] [-G size ] [--help ] [-i ] [-l ar ] [-
L searchdir ] [-M] [-Map mapfile ] [-m emulation ] [-n|-N] [-
noinhibit-exec ] [-oformat\ output-format ] [-R\ filename ] [-relax ]
[ -r|-Ur] [-S ] [-s ] [-sort-common] [-T\ commandfile ] [-Ttext\
textorg ] [-Tdata\ dataorg ] [-Tbss\ bssorg ] [-t ] [-u\ sym ] [-V ] [-
v] [--verbose ] [--version ] [--warn-common] [--warn-once] [-X ]
[ -x ]
```

DESCRIPTION

ld combines a number of object and archive files, relocates their data, and ties up symbol references. Often the last step in building a new compiled program to run is a call to ld.

ld accepts Linker Command Language files to provide explicit and total control over the linking process. This man page does not describe the command language; see the ld entry in info, or the manual *Ld: The GNU Linker*, for full details on the command language and on other aspects of the GNU linker.

This version of `ld` uses the general-purpose BFD libraries to operate on object files. This allows `ld` to read, combine, and write object files in many different formats, for example, COFF or `a.out`. Different formats may be linked together to produce any available kind of object file. You can use `objdump -i` to get a list of formats supported on various architectures; see `objdump(1)`.

Aside from its flexibility, the GNU linker is more helpful than other linkers in providing diagnostic information. Many linkers abandon execution immediately upon encountering an error; whenever possible, `ld` continues executing, allowing you to identify other errors (or, in some cases, to get an output file in spite of the error).

The GNU linker `ld` is meant to cover a broad range of situations, and to be as compatible as possible with other linkers. As a result, you have many choices to control its behavior through the command line, and through environment variables.

OPTIONS

The plethora of command-line options may seem intimidating, but in actual practice few of them are used in any particular context. For instance, a frequent use of `ld` is to link standard UNIX object files on a standard, supported UNIX system. On such a system, this line links a file `hello.o` :

```
$ ld -o output /lib/crt0.o hello.o -lc
```

This tells `ld` to produce a file called `output` as the result of linking the file `/lib/crt0.o` with `hello.o` and the library `libc.a`, which will come from the standard search directories.

The command-line options to `ld` may be specified in any order, and may be repeated at will. For the most part, repeating an option with a different argument will either have no further effect or override prior occurrences (those further to the left on the command line) of an option.

The exceptions—which may meaningfully be used more than once—are `-A`, `-b` (or its synonym `-format`), `-defsym`, `-L`, `-l`, `-R`, and `-u`.

The list of object files to be linked together, shown as `objfile`, may follow, precede, or be mixed in with command-line options, except that an `objfile` argument may not be placed between an option flag and its argument.

Usually the linker is invoked with at least one object file, but other forms of binary input files can also be specified with `-l`, `-R`, and the script command language. If no binary input files at all are specified, the linker does not produce any output, and issues the message `No input files`.

Option arguments must either follow the option letter without intervening whitespace or be given as separate arguments immediately following the option that requires them.

`-Architecture`

In the current release of `ld`, this option is useful only for the Intel 960 family of architectures. In that `ld` configuration, the `architecture` argument is one of the two-letter names identifying members of the 960 family; the option specifies the desired output target and warns of any incompatible instructions in the input files. It also modifies the linker's search strategy for archive libraries to support the use of libraries specific to each particular architecture, by including in the search loop names suffixed with the string identifying the architecture.

For example, if your `ld` command line included `-ACA` as well as `-ltry`, the linker would look (in its built-in search paths, and in any paths you specify with `-L`) for a library with the names

```
try
libtry.a
tryca
libtryca.a
```

The first two possibilities would be considered in any event; the last two are due to the use of `-ACA`.

Future releases of `ld` may support similar functionality for other architecture families.

	You can meaningfully use <code>-A</code> more than once on a command line, if an architecture family allows combination of target architectures; each use will add another pair of name variants to search for when <code>-l</code> specifies a library.
<code>-b input-format</code>	Specify the binary format for input object files that follow this option on the command line. You don't usually need to specify this, as <code>ld</code> is configured to expect as a default input format the most usual format on each machine. <code>input-format</code> is a text string, the name of a particular format supported by the BFD libraries. <code>-format input-format</code> has the same effect, as does the script command <code>TARGET</code>. You may want to use this option if you are linking files with an unusual binary format. You can also use <code>-b</code> to switch formats explicitly (when linking object files of different formats), by including <code>-b input-format</code> before each group of object files in a particular format. The default format is taken from the environment variable <code>GNUTARGET</code>. You can also define the input format from a script, using the command <code>TARGET</code>.
<code>-Bstatic</code>	This flag is accepted for command-line compatibility with the SunOS linker, but has no effect on <code>ld</code>.
<code>-c commandfile</code>	Directs <code>ld</code> to read link commands from the file <code>commandfile</code>. These commands will completely override <code>ld</code>'s default link format (rather than adding to it); <code>commandfile</code> must specify everything necessary to describe the target format. You may also include a script of link commands directly in the command line by bracketing it between <code>{</code> and <code>}</code> characters.
<code>-d, -dc, -dp</code>	These three options are equivalent; multiple forms are supported for compatibility with other linkers. Use any of them to make <code>ld</code> assign space to common symbols even if a relocatable output file is specified (<code>-r</code>). The script command <code>FORCE_COMMON_ALLOCATION</code> has the same effect.
<code>-defsym symbol= expression</code>	Create a global symbol in the output file, containing the absolute address given by <code>expression</code>. You may use this option as many times as necessary to define multiple symbols in the command line. A limited form of arithmetic is supported for the <code>expression</code> in this context; you may give a hexadecimal constant or the name of an existing symbol, or use <code>+</code> and <code>-</code> to add or subtract hexadecimal constants or symbols. If you need more elaborate expressions, consider using the linker command language from a script.
<code>-e entry</code>	Use <code>entry</code> as the explicit symbol for beginning execution of your program, rather than the default entry point.
<code>-F, -Fformat</code>	Some older linkers used this option throughout a compilation toolchain for specifying object-file format for both input and output object files. <code>ld</code>'s mechanisms (the <code>-b</code> or <code>-format</code> options for input files, the <code>TARGET</code> command in linker scripts for output files, the <code>GNUTARGET</code> environment variable) are more flexible, but it accepts (and ignores) the <code>-F</code> option flag for compatibility with scripts written to call the old linker.
<code>-format input-format</code>	Synonym for <code>-b input-format</code>.
<code>-g</code>	Accepted, but ignored; provided for compatibility with other tools.
<code>-G size</code>	Set the maximum size of objects to be optimized using the GP register to <code>size</code> under MIPS ECOFF. Ignored for other object file formats.
<code>--help</code>	Print a summary of the command-line options on the standard output and exit. This option and <code>--version</code> begin with two hyphens instead of one for compatibility with other GNU programs. The other options start with only one hyphen for compatibility with other linkers.
<code>-i</code>	Perform an incremental link (same as option <code>-r</code>).

<code>-lar</code>	Add an archive file <code>ar</code> to the list of files to link. This option may be used any number of times. <code>ld</code> will search its path list for occurrences of <code>lib ar .a</code> for every <code>ar</code> specified.
<code>-Lsearchdir</code>	This command adds path <code>searchdir</code> to the list of paths that <code>ld</code> will search for archive libraries. You may use this option any number of times. The default set of paths searched (without being specified with <code>-L</code>) depends on what emulation mode <code>ld</code> is using, and in some cases also on how it was configured. The paths can also be specified in a link script with the <code>SEARCH_DIR</code> command.
<code>-M</code>	Print (to the standard output file) a link map—diagnostic in-formation about where symbols are mapped by <code>ld</code> , and information on global common storage allocation.
<code>-Map mapfile</code>	Print to the file <code>mapfile</code> a link map—diagnostic information about where symbols are mapped by <code>ld</code> , and information on global common storage allocation.
<code>-m emulation</code>	Emulate the <code>emulation</code> linker. You can list the available emulations with the <code>--verbose</code> option. This option overrides the compiled-in default, which is the system for which you configured <code>ld</code> .
<code>-N</code>	Specifies readable and writable <code>text</code> and <code>data</code> sections. If the output format supports UNIX-style magic numbers, the output is marked as <code>OMAGIC</code> . When you use the <code>-N</code> option, the linker does not page-align the data segment.
<code>-n</code>	Sets the text segment to be read-only, and <code>NMAGIC</code> is written if possible.
<code>-noinhibit-exec</code>	Normally, the linker will not produce an output file if it encounters errors during the link process. With this flag, you can specify that you wish the output file retained even after nonfatal errors.
<code>-o output output</code>	<code>output</code> is a name for the program produced by <code>ld</code> ; if this option is not specified, the name <code>a.out</code> is used by default. The script command <code>OUTPUT</code> can also specify the output filename.
<code>-oformat output-format</code>	Specify the binary format for the output object file. You don't usually need to specify this, as <code>ld</code> is configured to produce as a default output format the most usual format on each machine. <code>output-format</code> is a text string, the name of a particular format supported by the BFD libraries. The script command <code>OUTPUT_FORMAT</code> can also specify the output format, but this option overrides it.
<code>-R filename file</code>	Read symbol names and their addresses from <code>filename</code> , but do not relocate it or include it in the output. This allows your output file to refer symbolically to absolute locations of memory defined in other programs.
<code>-relax</code>	An option with machine-dependent effects. Currently this option is only supported on the H8/300. On some platforms, use this option to perform global optimizations that become possible when the linker resolves addressing in your program, such as relaxing address modes and synthesizing new instructions in the output object file. On platforms where this is not supported, <code>-relax</code> is accepted, but has no effect.
<code>-r</code>	Generates relocatable output, that is, an output file that can in turn serve as input to <code>ld</code> . This is often called <i>partial linking</i> . As a side effect, in environments that support standard UNIX magic numbers, this option also sets the output file's magic number to <code>OMAGIC</code> . If this option is not specified, an absolute file is produced. When linking C++ programs, this option will not resolve references to constructors; <code>-Ur</code> is an alternative. This option does the same as <code>-i</code> .
<code>-S</code>	Omits debugger symbol information (but not all symbols) from the output file.
<code>-s</code>	Omits all symbol information from the output file.
<code>-sort-common</code>	Normally, when <code>ld</code> places the global common symbols in the appropriate output sections, it sorts them by size. First come all the one-byte symbols, then all the two bytes, then all the four bytes, and then everything else. This is to prevent gaps between symbols due to alignment constraints. This option disables that sorting.

<code>-Tbss org, -Tdata org,</code>	Use <code>org</code> as the starting address for—respectively—the bss, data, or the text segment of the output file. <code>textorg</code> must be a hexadecimal integer.
<code>-Ttext org</code>	
<code>-T commandfile, -Tcommandfile</code>	Equivalent to <code>-c commandfile</code> ; supported for compatibility with other tools.
<code>-t</code>	Prints names of input files as <code>ld</code> processes them.
<code>-u sym</code>	Forces <code>sym</code> to be entered in the output file as an undefined symbol. This may, for example, trigger linking of additional modules from standard libraries. <code>-u</code> may be repeated with different option arguments to enter additional undefined symbols.
<code>-Ur</code>	For anything other than C++ programs, this option is equivalent to <code>-r</code> : it generates relocatable output, that is, an output file that can in turn serve as input to <code>ld</code> . When linking C++ programs, <code>-Ur</code> will resolve references to constructors, unlike <code>-r</code> .
<code>--verbose</code>	Display the version number for <code>ld</code> and list the supported emulations. Display which input files can and can not be opened.
<code>-v, -V</code>	Display the version number for <code>ld</code> .
<code>--version</code>	Display the version number for <code>ld</code> and exit.
<code>-warn-common</code>	Warn when a common symbol is combined with another common symbol or with a symbol definition. UNIX linkers allow this somewhat sloppy practice, but linkers on some other operating systems do not. This option allows you to find potential problems from combining global symbols.
<code>-warn-once</code>	Only warn once for each undefined symbol, rather than once per module that refers to it.
<code>-X</code>	If <code>-s</code> or <code>-S</code> is also specified, delete only local symbols beginning with <code>l</code> .
<code>-x</code>	If <code>-s</code> or <code>-S</code> is also specified, delete all local symbols, not just those beginning with <code>l</code> .

ENVIRONMENT

You can change the behavior of `ld` with the environment variable `GNUTARGET`.

`GNUTARGET` determines the input-file object format if you don't use `-b` (or its synonym `-format`). Its value should be one of the BFD names for an input format. If there is no `GNUTARGET` in the environment, `ld` uses the natural format of the host. If `GNUTAR-GET` is set to default, then BFD attempts to discover the input format by examining binary input files; this method often succeeds, but there are potential ambiguities, since there is no method of ensuring that the magic number used to flag object-file formats is unique. However, the configuration procedure for BFD on each system places the conventional format for that system first in the search-list, so ambiguities are resolved in favor of convention.

SEE ALSO

`objdump(1)`; `ld` and `binutils` entries in `info`

Ld: The GNU Linker, Steve Chamberlain and Roland Pesch; *The GNU Binary Utilities*, Roland H. Pesch.

COPYING

Copyright © 1991, 1992 Free Software Foundation, Inc.

Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

Cygnus support, 17 August 1992

lispmtopgm

lispmtopgm—Convert a Lisp Machine bitmap file into PGM format

SYNOPSIS

```
lispmtopgm [lispfile]
```

DESCRIPTION

lispmtopgm reads a Lisp machine bitmap as input and produces a portable graymap as output.

This is the file format written by the `tv:write-bit-array-file` function on TI Explorer and Symbolics Lisp machines.

Multiplane bitmaps on Lisp machines are color; but the `lisp` image file format does not include a colormap, so it must be treated as a graymap instead. This is unfortunate.

SEE ALSO

`pgmtolisp(1)`, `pgm(5)`

BUGS

The `lisp` bitmap file format is a bit quirky; Usually the image in the file has its width rounded up to the next higher multiple of 32, but not always. If the width is not a multiple of 32, we don't deal with it properly, but because of the `lisp` microcode, such arrays are probably not image data anyway.

Also, the `lisp` code for saving bitmaps has a bug, in that if you are writing a bitmap that is not `mod32` across, the file may be up to seven bits too short. They round down instead of up, and we don't handle this bug gracefully.

No color.

AUTHOR

Copyright© 1991 by Jamie Zawinski and Jef Poskanzer.

6 March 1990

lkbib

lkbib—Search bibliographic databases

SYNOPSIS

```
lkbib [ -v ] [-ifields ][-pfilename ][-tn ] key ...
```

DESCRIPTION

lkbib searches bibliographic databases for references that contain the keys `key...` and prints any references found on the standard output. **lkbib** will search any databases given by `-p` options, and then a default database. The default database is taken from the `REFER` environment variable if it is set, otherwise it is

```
/usr/dict/papers/Ind.
```

For each database `filename` to be searched, if an index `filename.i` created by `gindxbib(1)` exists, then it will be searched instead; each index can cover multiple databases.

OPTIONS

<code>-v</code>	Print the version number.
<code>-pfilename</code>	Search <code>filename</code> . Multiple <code>-p</code> options can be used.
<code>-istring</code>	When searching files for which no index exists, ignore the contents of fields whose names are in <code>string</code> .
<code>-tn</code>	Only require the first <code>n</code> characters of keys to be given. Initially <code>n</code> is 6.

ENVIRONMENT

REFER Default database

FILES

/usr/dict/papers/Ind Default database to be used if the REFER environment variable is not set.
filename.i Index files.

SEE ALSO

grefer(1), glookbib(1), gindexbib(1)

Groff Version 1.09, 6 August 1992

ln

ln—Make links between files

SYNOPSIS

```
ln [options] source [dest]
ln [options] source... directory
```

Options:

```
[-bdfinsvF] [-S backup-suffix] [-V {numbered,existing,simple}]
[--version-control={numbered,existing,simple}] [--backup] [--directory]
[--force] [--interactive] [--no-dereference] [--symbolic] [--verbose]
[--suffix=backup-suffix] [--help] [--version]
```

DESCRIPTION

This manual page documents the GNU version of `ln`. If the last argument names an existing directory, `ln` links each other given file into a file with the same name in that directory. If only one file is given, it links that file into the current directory. Otherwise, if only two files are given, it links the first onto the second. It is an error if the last argument is not a directory and more than two files are given. It makes hard links by default. By default, it does not remove existing files.

OPTIONS

<code>-b, --backup</code>	Make backups of files that are about to be removed.
<code>-d, -F, --directory</code>	Allow the superuser to make hard links to directories.
<code>-f, --force</code>	Remove existing destination files.
<code>-i, --interactive</code>	Prompt whether to remove existing destination files.
<code>-n, --no-dereference</code>	When the specified destination is a symbolic link to a directory, attempt to replace the symbolic link rather than dereferencing it to create a link in the directory to which it points. This option is most useful in conjunction with <code>--force</code> .
<code>-s, --symbolic</code>	Make symbolic links instead of hard links. This option produces an error message on systems that do not support symbolic links.
<code>-v, --verbose</code>	Print the name of each file before linking it.
<code>--help</code>	Print a usage message on standard output and exit successfully.
<code>--version</code>	Print version information on standard output then exit successfully.
<code>-S, --suffix backup-suffix</code>	The suffix used for making simple backup files can be set with the <code>SIMPLE_BACKUP_SUFFIX</code> environment variable, which can be overridden by this option. If neither of those is given, the default is <code>~</code> , as it is in Emacs.

`-V, --version-control`
`{numbered,existing,simple}`

The type of backups made can be set with the `VERSION_CONTROL` environment variable, which can be overridden by this option. If `VERSION_CONTROL` is not set and this option is not given, the default backup type is `existing`. The value of the `VERSION_CONTROL` environment variable and the argument to this option are like the GNU Emacs `version-control` variable; they also recognize synonyms that are more descriptive. The valid values (unique abbreviations are accepted) are the following:

<code>t</code> or <code>numbered</code>	Always make numbered backups.
<code>nil</code> or <code>existing</code>	Make numbered backups of files that already have them, simple backups of the others.
<code>never</code> or <code>simple</code>	Always make simple backups.

GNU File Utilities

Indir

Indir—Create a shadow directory of symbolic links to another directory tree

SYNOPSIS

```
Indir fromdir [todir]
```

DESCRIPTION

Indir makes a shadow copy `todir` of a directory tree `fromdir`, except that the shadow is not populated with real files but instead with symbolic links pointing at the real files in the `fromdir` directory tree. This is usually useful for maintaining source code for different machine architectures. You create a shadow directory containing links to the real source which you will have usually NFS mounted from a machine of a different architecture, and then recompile it. The object files will be in the shadow directory, while the source files in the shadow directory are just symlinks to the real files.

This has the advantage that if you update the source, you need not propagate the change to the other architectures by hand because all source in shadow directories are symlinks to the real thing: Just `cd` to the shadow directory and recompile away.

The `todir` argument is optional and defaults to the current directory. The `fromdir` argument may be relative (for example, `../src`) and is relative to `todir` (not the current directory).

Note that `RCS`, `SCCS`, and `CVS.adm` directories are not shadowed.

If you add files, simply run **Indir** again. Deleting files is a more painful problem; the symlinks will just point into never-neverland.

BUGS

`patch` gets upset if it cannot change the files. You should never run `patch` from a shadow directory anyway.

You need to use something like this:

```
find todir -type l -print | xargs rm
```

to clear out all files before you can relink (if `fromdir` moved, for instance). Something like this:

```
find . \! -type d -print
```

will find all files that are not directories.

X Version 11 Release 6

locate

locate—List files in databases that match a pattern

SYNOPSIS

```
locate [-d path] [--database=path] [--version] [--help] pattern...
```

DESCRIPTION

This manual page documents the GNU version of `locate`. For each given pattern, `locate` searches one or more databases of filenames and displays the filenames that contain the pattern. Patterns can contain shell-style meta characters: `*`, `?`, and `[]`. The meta characters do not treat `/` or `.` specially. Therefore, a pattern `foo*bar` can match a filename that contains `foo3/bar`, and a pattern `*duck*` can match a filename that contains `lake/.ducky`. Patterns that contain meta characters should be quoted to protect them from expansion by the shell.

If a pattern is a plain string—it contains no meta characters—`locate` displays all filenames in the database that contain that string anywhere. If a pattern does contain meta characters, `locate` only displays filenames that match the pattern exactly. As a result, patterns that contain meta characters should usually begin with a `*` and will most often end with one as well. The exceptions are patterns that are intended to explicitly match the beginning or end of a filename.

The filename databases contain lists of files that were on the system when the databases were last updated. The system administrator can choose the filename of the default database, the frequency with which the databases are updated, and the directories for which they contain entries; see `updatedb(1L)`.

OPTIONS

<code>-d path, --database=path</code>	Instead of searching the default filename database, search the filename databases in <code>path</code> , which is a colon-separated list of database filenames. You can also use the environment variable <code>LOCATE_PATH</code> to set the list of database files to search. The option overrides the environment variable if both are used. The filename database format changed starting with GNU <code>find</code> and <code>locate</code> version 4.0 to allow machines with different byte orderings to share the databases. This version of <code>locate</code> can automatically recognize and read databases produced for older versions of GNU <code>locate</code> or UNIX versions of <code>locate</code> or <code>find</code> .
<code>--help</code>	Print a summary of the options to <code>locate</code> and exit.
<code>--version</code>	Print the version number of <code>locate</code> and exit.

ENVIRONMENT

`LOCATE_PATH` Colon-separated list of databases to search

SEE ALSO

`find(1L)`, `locatedb(5L)`, `updatedb(1L)`, `xargs(1L)`, *Finding Files* (online in `info`, or printed)

logger

logger—Make entries in the system log

SYNOPSIS

```
logger [-is] [-f file] [-p pri] [-t tag] [message ...]
```

DESCRIPTION

`logger` provides a shell command interface to the `syslog(3)` system log module.

OPTIONS

- `-i` Log the process ID of the logger process with each line.
- `-s` Log the message to standard error, as well as the system log.
- `-f file` Log the specified file.
- `-p pri` Enter the message with the specified priority. The priority may be specified numerically or as a `facility.level` pair. For example, `-p local3.info` logs the message(s) as informational level in the local3 facility. The default is `user.notice`.
- `-t tag` Mark every line in the log with the specified tag.
- `message` Write the message to log; if not specified, and the `-f` flag is not provided, standard input is logged.

The logger utility exits 0 on success, and >0 if an error occurs.

EXAMPLE

```
logger system rebooted:
logger -p local0.notice -t HOSTIDM -f /dev/idmc
```

SEE ALSO

`syslog(3)`, `syslogd(8)`

STANDARDS

The logger command is expected to be compatible with IEEE Std 1003.2 (POSIX).

BSD 4.3, 6 June 1993

login

login—Sign on

SYNOPSIS

```
login [ name ]
login -p
login -h hostname
login -f name
```

DESCRIPTION

`login` is used when signing on to a system. It can also be used to switch from one user to another at any time. (Most modern shells have support for this feature built into them, however.)

If an argument is not given, `login` prompts for the username.

If the user is not root, and if `/etc/nologin` exists, the contents of this file are printed to the screen, and the login is terminated. This is typically used to prevent logins when the system is being taken down.

If the user is root, then the login must be occurring on a tty listed in `/etc/securetty`. Failures will be logged with the `syslog` facility.

After these conditions are checked, the password will be requested and checked (if a password is required for this username). Ten attempts are allowed before `login` dies, but after the first three, the response starts to get very slow. Login failures are reported via the `syslog` facility. This facility is also used to report any successful root logins.

If the file `.hushlogin` exists, then a quiet login is performed (this disables the checking of the checking of mail and the printing of the last login time and message of the day). Otherwise, if `/var/log/lastlog` exists, the last login time is printed (and the current login is recorded).

Random administrative things, such as setting the UID and GID of the `tty`, are performed. The `TERM` environment variable is preserved, if it exists; other environment variables are preserved if the `-p` option is used. Then the `HOME`, `PATH`, `SHELL`, `TERM`, `MAIL`, and `LOGNAME` environment variables are set. `PATH` defaults to `/usr/local/bin:/bin:/usr/bin:.` for normal users, and to `/sbin:/bin:/usr/sbin:/usr/bin` for root. Last, if this is not a quiet login, the message of the day is printed and the file with the user's name in `/usr/spool/mail` will be checked, and a message printed if it has nonzero length.

The user's shell is then started. If no shell is specified for the user in `/etc/passwd`, then `/bin/sh` is used. If there is no directory specified in `/etc/passwd`, then `/` is used. (The home directory is checked for the `.hushlogin` file described earlier.)

OPTIONS

- `-p` Used by `getty(8)` to tell login not to destroy the environment.
- `-f` Used to skip a second login authentication. This specifically does not work for root, and does not appear to work well under Linux.
- `-h` Used by other servers (such as `telnetd(8)`) to pass the name of the remote host to login so that it may be placed in `utmp` and `wtmp`. Only the superuser may use this option.

FILES

```
/var/run/utmp
/var/log/wtmp
/var/log/lastlog
/usr/spool/mail/*
/etc/motd
/etc/passwd
/etc/nologin
/etc/usertty
.hushlogin
```

SEE ALSO

`init(8)`, `getty(8)`, `mail(1)`, `passwd(1)`, `passwd(5)`, `environ(7)`, `shutdown(8)`

BUGS

Linux, unlike other Draconian operating systems, does not check quotas.

The undocumented BSD `-r` option is not supported. This may be required by some `rlogind(8)` programs.

AUTHOR

Derived from BSD login 5.40 (May 9, 1989) by Michael Glad (`glad@daimi.dk`) for HP-UX Ported to Linux 0.12: Peter Orbaek (`poe@daimi.aau.dk`).

Linux 0.99, 1 February 1993

look

`look`—Display lines beginning with a given string

SYNOPSIS

```
look [-dfa] [-t termchar] string [file]
```

DESCRIPTION

The `look` utility displays any lines in `file` that contain `string` as a prefix. As `look` performs a binary search, the lines in `file` must be sorted.

If file is not specified, the file `/usr/dict/words` is used, only alphanumeric characters are compared, and the case of alphabetic characters is ignored.

OPTIONS

- `-d` Dictionary character set and order; that is, only alphanumeric characters are compared.
- `-f` Ignore the case of alphabetic characters.
- `-a` Use the alternate dictionary `/usr/dict/web2`.
- `-t` Specify a string termination character; that is, only the characters in `string` up to and including the first occurrence of `termchar` are compared.

The `look` utility exits 0 if one or more lines were found and displayed, 1 if no lines were found, and >1 if an error occurred.

FILES

- `/usr/dict/words` The dictionary
- `/usr/dict/web2` The alternate dictionary

SEE ALSO

`grep(1)`, `sort(1)`

COMPATIBILITY

The original manual page stated that tabs and blank characters participated in comparisons when the `-d` option was specified. This was incorrect and the current man page matches the historic implementation.

HISTORY

`look` appeared in version 7 AT&T UNIX.

14 June 1993

lpq

`lpq`—Spool queue examination program

SYNOPSIS

```
lpq [-l] [-P printer] [job # ...] [user ...]
```

DESCRIPTION

`lpq` examines the spooling area used by `lpd(8)` for printing files on the line printer, and reports the status of the specified jobs or all jobs associated with a user. `lpq` invoked without any arguments reports on any jobs currently in the queue.

OPTIONS

- `-P` Specify a particular printer; otherwise the default line printer is used (or the value of the `PRINTER` variable in the environment). All other arguments supplied are interpreted as usernames or job numbers to filter out only those jobs of interest.
- `-l` Information about each of the files comprising the job entry is printed. Normally, only as much information as will fit on one line is displayed.

For each job submitted—in other words, each time `lpq(1)` is invoked—`lpq` reports the user's name, current rank in the queue, the names of files comprising the job, the job identifier (a number that may be supplied to `lprm(1)` for removing a specific job), and the total size in bytes. Job ordering is dependent on the algorithm used to scan the spooling directory and is supposed to be FIFO (First in First Out). Filenames comprising a job may be unavailable (when `lpq(1)` is used as a sink in a pipeline) in which case the file is indicated as (standard input).

If `lpq` warns that there is no daemon present (due to some malfunction, for example), the `lpc(8)` command can be used to restart the printer daemon.

ENVIRONMENT

If the following environment variable exists, it is used by `lpq`:

PRINTER Specifies an alternate default printer

FILES

<code>/etc/printcap</code>	To determine printer characteristics
<code>/var/spool/*</code>	The spooling directory, as determined from <code>printcap</code>
<code>/var/spool/*/cf*</code>	Control files specifying jobs
<code>Pa/var/spool/*/lock</code>	The lock file to obtain the currently active job
<code>/usr/share/misc/termcap</code>	For manipulating the screen for repeated display

SEE ALSO

`lpr(1)`, `lprm(1)`, `lpc(8)`, `lpd(8)`

HISTORY

`lpq` appeared in BSD 3.

BUGS

Due to the dynamic nature of the information in the spooling directory, `lpq` may report unreliably. Output formatting is sensitive to the line length of the terminal; this can result in widely spaced columns.

DIAGNOSTICS

Unable to open various files. The lock file is malformed. Garbage files when there is no daemon active, but files in the spooling directory.

BSD 4.2, 9 May 1991

lpr

`lpr`—Offline print

SYNOPSIS

```
lpr [-P printer] [-# num] [-C class] [-J job] [-T title] [-U user]
[-i [numcols]] [-1234 font] [-w num] [-cdfghlnmprstv] [name ...]
```

DESCRIPTION

`lpr` uses a spooling daemon to print the named files when facilities become available. If no names appear, the standard input is assumed.

The following single-letter options are used to notify the line printer spooler that the files are not standard text files. The spooling daemon will use the appropriate filters to print the data accordingly.

<code>-c</code>	The files are assumed to contain data produced by <code>cifplot(1)</code> .
<code>-d</code>	The files are assumed to contain data from TeX (DVI format from Stanford).
<code>-f</code>	Use a filter that interprets the first character of each line as a standard FORTRAN carriage control character.
<code>-g</code>	The files are assumed to contain standard plot data as produced by the plot routines. (See also <code>plot</code> for the filters used by the printer spooler.)

- l Use a filter that allows control characters to be printed and suppresses page breaks.
- n The files are assumed to contain data from `ditroff` (device independent troff).
- p Use `pr(1)` to format the files (equivalent to `print`).
- t The files are assumed to contain data from `troff(1)` (cat phototypesetter commands).
- v The files are assumed to contain a raster image for devices like the Benson Varian.

These options apply to the handling of the print job:

- P Force output to a specific printer. Normally, the default printer is used (site-dependent), or the value of the environment variable `PRINTER` is used.
- h Suppress the printing of the burst page.
- m Send mail upon completion.
- r Remove the file upon completion of spooling or upon completion of printing (with the `-s` option).
- s Use symbolic links. Usually, files are copied to the spool directory. The `-s` option will use `symlink(2)` to link data files rather than trying to copy them so large files can be printed. This means the files should not be modified or removed until they have been printed.

The remaining options apply to copies, the page display, and headers:

- # num The quantity `num` is the number of copies desired of each file named. For example,


```
lpr -#3 foo.c bar.c more.c
```

 would result in three copies of the file `foo.c`, followed by three copies of the file `bar.c`, and so on. On the other hand,


```
cat foo.c bar.c more.c | lpr -#3
```

 will give three copies of the concatenation of the files. Often a site will disable this feature to encourage use of a photocopier instead.
- 1234 font Specifies a font to be mounted on font position `i`. The daemon will construct a `.railmag` file referencing the font pathname.
- C Ar class Job classification to use on the burst page. For example


```
lpr -C EECS foo.c
```

 causes the system name—the name returned by `hostname(1)`—to be replaced on the burst page by `EECS`, and the file `foo.c` to be printed.
- J Ar job Job name to print on the burst page. Normally, the first file's name is used.
- T Ar title Title name for `pr(1)`, instead of the filename.
- U user Username to print on the burst page, also for accounting purposes. This option is only honored if the real user ID is `daemon` (or that specified in the `printcap` file instead of `daemon`), and is intended for those instances where print filters wish to requeue jobs.
- i numcols The output is indented. If the next argument is numeric `numcols`, it is used as the number of blanks to be printed before each line; otherwise, eight characters are printed.
- w Ns Ar num Uses `num` as the page width for `pr(1)`.

ENVIRONMENT

If the following environment variable exists, it is used by `lpr`:

`PRINTER` Specifies an alternate default printer

FILES

<code>etc/passwd</code>	Personal identification.
<code>/etc/printcap</code>	Printer capabilities database.
<code>/usr/sbin/lpd*</code>	Line printer daemons.
<code>/var/spool/output/*</code>	Directories used for spooling.

<code>/var/spool/output/*/cf*</code>	Daemon control files.
<code>/var/spool/output/*/df*</code>	Data files specified in <code>cf</code> files.
<code>/var/spool/output/*/tf*</code>	Temporary copies of <code>cf</code> files.

SEE ALSO

`lpq(1)`, `lprm(1)`, `pr(1)`, `symlink(2)`, `printcap(5)`, `lpc(8)`, `lpd(8)`

HISTORY

The `lpr` command appeared in BSD 3.

DIAGNOSTICS

If you try to spool too large a file, it will be truncated. `lpr` will object to printing binary files. If a user other than root prints a file and spooling is disabled, `lpr` will print a message saying so and will not put jobs in the queue. If a connection to `lpd(1)` on the local machine cannot be made, `lpr` will say that the daemon cannot be started. Diagnostics may be printed in the daemon's log file regarding missing spool files by `lpd(1)`.

BUGS

Fonts for `troff(1)` and TeX reside on the host with the printer. It is currently not possible to use local font libraries.

BSD 4, 24 July 1991

lprm

`lprm`—Remove jobs from the line printer spooling queue

SYNOPSIS

```
lprm [-P printer] [- job # ...] [user ...]
```

DESCRIPTION

`lprm` will remove a job, or jobs, from a printer's spool queue. Since the spooling directory is protected from users, using `lprm` is normally the only method by which a user may remove a job. The owner of a job is determined by the user's login name and hostname on the machine where the `lpr(1)` command was invoked.

Options and arguments:

<code>-P printer</code>	Specify the queue associated with a specific printer; otherwise, the default printer is used.
<code>-</code>	If a single <code>-</code> is given, <code>lprm</code> will remove all jobs that a user owns. If the superuser employs this flag, the spool queue will be emptied entirely.
<code>user</code>	Causes <code>lprm</code> to attempt to remove any jobs queued belonging to that user (or users). This form of invoking <code>lprm</code> is useful only to the superuser.
<code>job #</code>	A user may dequeue an individual job by specifying its job number. This number may be obtained from the <code>lpq(1)</code> program. For example
	<pre>lpq - -l 1st:ken [job#013ucbarpa] (standard input) 100 bytes lprm 13</pre>

If neither arguments nor options are given, `lprm` will delete the currently active job if it is owned by the user who invoked `lprm`.

`lprm` announces the names of any files it removes and is silent if there are no jobs in the queue that match the request list.

`lprm` will kill off an active daemon, if necessary, before removing any spooling files. If a daemon is killed, a new one is automatically restarted upon completion of file removals.

ENVIRONMENT

If the following environment variable exists, it is utilized by `lprm`:

PRINTER If the environment variable `PRINTER` exists, and a printer has not been specified with the `-P` option, the default printer is assumed from `PRINTER`.

FILES

<code>/etc/printcap</code>	Printer characteristics file
<code>/var/spool/*</code>	Spooling directories
<code>/var/spool/*/lock</code>	Lock file used to obtain the pid of the current daemon and the job number of the currently active job

SEE ALSO

`lpr(1)`, `lpq(1)`, `lpd(8)`

DIAGNOSTICS

“Permission denied” if the user tries to remove files other than his own.

BUGS

Because there are race conditions possible in the update of the `lock` file, the currently active job may be incorrectly identified.

HISTORY

The `lprm` command appeared in BSD 3.0.

BSD 4.2, 9 May 1991

lptest

`lptest`—Generate line printer ripple pattern

SYNOPSIS

`lptest [length] [count]`

DESCRIPTION

`lptest` writes the traditional “ripple test” pattern on standard output. In 96 lines, this pattern will print all 96 printable ASCII characters in each position. Although originally created to test printers, it is quite useful for testing terminals, driving terminal ports for debugging purposes, or any other task where a quick supply of random data is needed.

The `length` argument specifies the output line length if the default length of 79 is inappropriate.

The `count` argument specifies the number of output lines to be generated if the default count of 200 is inappropriate. Note that if `count` is to be specified, `length` must also be specified.

HISTORY

`lptest` appeared in BSD 4.3.

BSD 4.3, 9 May 1991

ls, dir, vdir

ls, dir, vdir—List contents of directories

SYNOPSIS

```
ls [-abcdfgiklmnpqrstuxABCFGHJLNQRSUX1] [-w cols] [-T cols] [-I pattern] [--all]
[--escape] [--directory] [--inode] [--kilobytes] [--numeric-uid-gid] [--no-group]
[--hide-control-chars] [--reverse] [--size] [--width=cols] [--tabsize=cols]
[--almost-all] [--ignore-backups] [--classify] [--file-type] [--full-time]
[--ignore=pattern] [--dereference] [--literal] [--quote-name] [--recursive]
[--sort={none, time, size, extension}] [--format={long, verbose, commas,
across, vertical, single-column}] [--time={atime, access, use, ctime, status}]
[--help] [--version] [name...]
```

DESCRIPTION

This manual page documents the GNU version of `ls`. `dir` and `vdir` are versions of `ls` with different default output formats. These programs list each given file or directory name. Directory contents are sorted alphabetically. For `ls`, files are by default listed in columns, sorted vertically, if the standard output is a terminal; otherwise, they are listed one per line. For `dir`, files are by default listed in columns, sorted vertically. For `vdir`, files are by default listed in long format.

OPTIONS

<code>-a, --all</code>	List all files in directories, including all files that start with a period (<code>.</code>).
<code>-b, --escape</code>	Quote nongraphic characters in filenames using alphabetic and octal backslash sequences like those used in C.
<code>-c, --time=ctime,</code> <code>--time=status</code>	Sort directory contents according to the files' status change time instead of the modification time. If the long listing format is being used, print the status change time instead of the modification time.
<code>-d, --directory</code>	List directories like other files, rather than listing their contents.
<code>-f</code>	Do not sort directory contents; list them in whatever order they are stored on the disk. This is the same as enabling <code>-a</code> and <code>-U</code> and disabling <code>-l</code> , <code>-s</code> , and <code>-t</code> .
<code>--full-time</code>	List times in full, rather than using the standard abbreviation heuristics.
<code>-g</code>	Ignored; for UNIX compatibility.
<code>-i, --inode</code>	Print the index number of each file to the left of the filename.
<code>-k, --kilobytes</code>	If file sizes are being listed, print them in kilobytes. This overrides the environment variable <code>POSIXLY_CORRECT</code> .
<code>-l, --format=long,</code> <code>--format=verbose</code>	In addition to the name of each file, print the file type, permissions, number of hard links, owner name, group name, size in bytes, and timestamp (the modification time unless other times are selected). For files with a time that is more than six months old or more than one hour into the future, the timestamp contains the year instead of the time of day.
<code>-m, --format=commas</code>	List files horizontally, with as many as will fit on each line, separated by commas.
<code>-n, --numeric-uid-gid</code>	List the numeric UID and GID instead of the names.
<code>-p</code>	Append a character to each filename indicating the file type.
<code>-q, --hide-control-chars</code>	Print question marks instead of nongraphic characters in filenames.
<code>-r, --reverse</code>	Sort directory contents in reverse order.
<code>-s, --size</code>	Print the size of each file in 1KB blocks to the left of the filename. If the environment variable <code>POSIXLY_CORRECT</code> is set, 512-byte blocks are used instead.
<code>-t, --sort=time</code>	Sort directory contents by timestamp instead of alphabetically, with the newest files listed first.
<code>-u, --time=atime,</code> <code>--time=access, --time=use</code>	Sort directory contents according to the files' last access time instead of the modification time. If the long listing format is being used, print the last access time instead of the modification time.

<code>-x, --format=across,</code> <code>--format=horizontal</code>	List the files in columns, sorted horizontally.
<code>-A, --almost-all</code>	List all files in directories, except for <code>.</code> and <code>..</code> .
<code>-B, --ignore-backups</code>	Do not list files that end with <code>~</code> , unless they are given on the command line.
<code>-C, --format=vertical</code>	List files in columns, sorted vertically.
<code>-F, --classify</code>	Append a character to each filename indicating the file type. For regular files that are executable, append a <code>*</code> . The file type indicators are <code>/</code> for directories, <code>@</code> for symbolic links, <code> </code> for FIFOs, <code>=</code> for sockets, and nothing for regular files.
<code>-G, --no-group</code>	Inhibit display of group information in a long format directory listing.
<code>-L, --dereference</code>	List the files linked to by symbolic links instead of listing the contents of the links.
<code>-N, --literal</code>	Do not quote filenames.
<code>-Q, --quote-name</code>	Enclose filenames in double quotes and quote nongraphic characters as in <code>C</code> .
<code>-R, --recursive</code>	List the contents of all directories recursively.
<code>-S, --sort=size</code>	Sort directory contents by file size instead of alphabetically, with the largest files listed first.
<code>-U, --sort=none</code>	Do not sort directory contents; list them in whatever order they are stored on the disk. This option is not called <code>-f</code> because the UNIX <code>ls -f</code> option also enables <code>-a</code> and disables <code>-l</code> , <code>-s</code> , and <code>-t</code> . It seems useless and ugly to group those unrelated things together in one option. Because this option doesn't do that, it has a different name.
<code>-X, --sort=extension</code>	Sort directory contents alphabetically by file extension (characters after the last period); files with no extension are sorted first.
<code>-l, --format=single-column</code>	List one file per line.
<code>-w, --width cols</code>	Assume the screen is <code>cols</code> columns wide. The default is taken from the terminal driver if possible; otherwise, the environment variable <code>COLUMNS</code> is used if it is set; otherwise, the default is 80.
<code>-T, --tabsize cols</code>	Assume that each tab stop is <code>cols</code> columns wide. The default is 8.
<code>-I, --ignore pattern</code>	Do not list files whose names match the shell pattern <code>pattern</code> unless they are given on the command line. As in the shell, an initial period (<code>.</code>) in a filename does not match a wildcard at the start of <code>pattern</code> .
<code>--help</code>	Print a usage message on standard output and exit successfully.
<code>--version</code>	Print version information on standard output then exit successfully.

BUGS

On BSD systems, the `-s` option reports sizes that are half the correct values for files that are NFS-mounted from HP-UX systems. On HP-UX systems, it reports sizes that are twice the correct values for files that are NFS-mounted from BSD systems. This is due to a flaw in HP-UX; it also affects the HP-UX `ls` program.

GNU File Utilities

lsattr

`lsattr`—List file attributes on a Linux second extended filesystem

SYNOPSIS

```
lsattr [ -Radv ] [ files... ]
```

DESCRIPTION

`lsattr` lists the files attributes on an second extended filesystem.

OPTIONS

- R Recursively list attributes of directories and their contents.
- a List all files in directories, including files that start with period (.).
- d List directories like other files, rather than listing their contents.
- v List the files version.

AUTHOR

lsattr has been written by Remy Card (card@masi.ibp.fr), the developer and maintainer of the ext2 fs.

BUGS

There are none :-).

AVAILABILITY

lsattr is available for anonymous FTP from <ftp.ibp.fr> and <tsx-11.mit.edu> in `/pub/linux/packages/ext2fs`.

SEE ALSO

[chattr\(1\)](#)

Version 0.5b, November 1994

lsmod

lsmod—show the loaded modules

SYNOPSIS

lsmod

DESCRIPTION

lsmod shows information about all loaded modules. The format is

name size [list of referring modules]

size is in 4Kb pages.

This information is a copy of the contents of `/proc/modules`.

SEE ALSO

[insmod\(1\)](#), [modprobe\(1\)](#), [depmod\(1\)](#), [rmmod\(1\)](#), [ksyms\(1\)](#), [modules\(2\)](#)

HISTORY

The module support was first conceived by Anonymous (as far as I know...). Linux version by Bas Laarhoven (bas@vimec.nl), 0.99.14 version by Jon Tombs (jon@gtex02.us.es), extended by Bjorn Ekwall (bjørn@blox.se).

BUGS

lsmod might have some, but they are well hidden....

Linux, 14 May 1995

lynx

lynx—A general-purpose distributed information browser for the World Wide Web

SYNOPSIS

lynx [options] [path or URL]

Use `lynx -help` to display a complete list of current options.

DESCRIPTION

lynx is a fully-featured World Wide Web (WWW) client for users running cursor-addressable, character-cell display devices (for example, vt100 terminals, vt100 emulators running on PCs or Macs, or any other “curses-oriented” display). It will display Hypertext Markup Language (HTML) documents containing links to files residing on the local system, as well as files residing on remote systems running Gopher, HTTP, FTP, WAIS, and NNTP servers. Current versions of lynx run on UNIX and VMS.

lynx can be used to access information on the World Wide Web, or to build information systems intended primarily for local access. For example, lynx has been used to build several Campus Wide Information Systems (CWIS). In addition, lynx can be used to build systems isolated within a single LAN.

OPTIONS

At startup, lynx will load any local file or remote URL specified at the command line. For help with URLs, press `?` or `h` while running lynx. Then follow the link titled “Help on URLs.”

-	If the only argument is -, then lynx expects to receive the arguments from stdin. This is to allow for the potentially very long command line that can be associated with the <code>-get_data</code> or <code>-post_data</code> arguments. (See entries for each later in this list.)
-anonymous	Used to specify the anonymous account.
-ascii	Disable kanji code translation when Japanese mode is on.
-auth=ID:PASSWD	Set authorization ID and password for protected documents at startup.
-book	Use the bookmark page as the startfile. The default or command line startfile is still set for the Main screen command, and will be used if the bookmark page is unavailable or blank.
-buried_news	Toggles scanning of news articles for buried references, and converts them to news links. Not recommended because e-mail addresses enclosed in angle brackets will be converted to false news links, and uuencoded messages can be trashed.
-cache=NUMBER	Set the NUMBER of documents cached in memory. The default is 10.
-case	Enable case-sensitive string searching.
-cfg=FILENAME	Specifies a lynx configuration file other than the default <code>lynx.cfg</code> .
-child	Exit on left-arrow in startfile, and disable save to disk.
-crawl	With <code>-traversal</code> , output each page to a file. With <code>-dump</code> , format output as with <code>-traversal</code> , but to stdout.
-display=DISPLAY	Set the display variable for X rexecd programs.
-dump	Dumps the formatted output of the default document or one specified on the command line to standard out. This can be used in the following way: <code>lynx -dump http://www.w3.org/default.html</code> .
-editor=EDITOR	Enable Edit mode using the specified EDITOR (<code>vi</code> , <code>ed</code> , <code>emacs</code> , and so on).
-emacskeys	Enable Emacs-like key movement.
-enable_scrollback	Toggle compatibility with comm programs' scrollbar keys (may be incompatible with some packages).
-error_file=FILE	Define a file where lynx will report HTTP access codes.
-euc	Set kanji code to EUC when Japanese mode is on.
-fileversions	Include all versions of files in local VMS directory listings.
-force_html	Forces the first document to be interpreted as HTML.

-ftp	Disable FTP access.
-get_data	Send form data from stdin using GET method and dump results.
-head	Send a HEAD request for the mime headers.
-help	Print this lynx command syntax usage message.
-historical	Toggles use of > or -> as a terminator for comments.
-homepage=URL	Set home page separate from start page.
-image_links	Toggles inclusion of links for all images.
-index=URL	Set the default index file to the specified URL.
-jpn	Toggles Japanese character translations on or off.
-link=NUMBER	Starting count for lnk#.dat files produced by -crawl.
-localhost	Disable URLs that point to remote hosts.
-locexec	Enable local program execution from local files only (if lynx was compiled with local execution enabled).
-mime_header	Prints the MIME header of a fetched document along with its source.
-minimal	Toggles minimal versus valid comment parsing.
-nobrowse	Disable directory browsing.
-noexec	Disable local program execution (default).
-nolist	Disable the link list feature in dumps.
-nolog	Disable mailing of error messages to document owners.
-noprint	Disable print functions.
-noredir	Prevents automatic redirection and prints a message with a link to the new URL.
-nostatus	Disable the retrieval status messages.
-number_links	Force numbering of links.
-post_data	Send form data from stdin using POST method and dump results.
-print	Enable print functions (default).
-pseudo_inlines	Toggles pseudo-ALTS for inlines with no ALT string.
-realm	Restricts access to URLs in the starting realm.
-reload	Flushes the cache on a proxy server (only the first document affected).
-restrictions={option}[,option][,option]...	Allows a list of services to be disabled selectively. The following list is printed if no options are specified. all—Restricts all options. bookmark--Disallow changing the location of the bookmark file. bookmark_exec--Disallow execution links via the bookmark file. Change_exec_perms—Disallow changing the execute permission on files (but still allow it for directories) when local file management is enabled. default--Same as command-line option -anonymous. Disables default services for anonymous users. Currently set to all restricted except for the following: inside_telnet, outside_telnet, inside_news, inside_ftp, outside_ftp, inside_rlogin, outside_rlogin, jump, mail, and goto. Defaults are settable within userdefs.h. dired_support—Disallow local file management. disk_save—Disallow saving binary files to disk in the download menu. download--Disallow downloaders in the download menu. editor—Disallow editing. exec--Disable execution scripts. exec_frozen--Disallow the user from changing the local execution option. file_url--Disallow using goto to go to file: URLs. goto—Disable the g (goto) command.

	<code>inside_ftp</code> —Disallow FTPs for people coming from inside your domain. (utmp required for selectivity.)
	<code>inside_news</code> —Disallow Usenet news posting for people coming from inside your domain. (utmp required for selectivity.)
	<code>inside_rlogin</code> —Disallow rlogins for people coming from inside your domain. (utmp required for selectivity.)
	<code>inside_telnet</code> —Disallow Telnets for people coming from inside your domain. (utmp required for selectivity.)
	<code>jump</code> —Disable the <code>j</code> (jump) command.
	<code>mail</code> —Disable mailing feature.
	<code>news_post</code> —Disable Usenet news posting.
	<code>options_save</code> —Disallow saving options in <code>.lynxrc</code> .
	<code>outside_ftp</code> —Disallow FTPs for people coming from outside your domain. (utmp required for selectivity.)
	<code>outside_news</code> —Disallow Usenet news posting for people coming from outside your domain. (utmp required for selectivity.)
	<code>outside_rlogin</code> —Disallow rlogins for people coming from outside your domain. (utmp required for selectivity.)
	<code>outside_telnet</code> —Disallow Telnets for people coming from outside your domain. (utmp required for selectivity.)
	<code>print</code> —Disallow most print options.
	<code>shell</code> —Disallow shell escapes and <code>lynxexec</code> or <code>lynxprog goto</code> 's.
	<code>suspend</code> —Disallow UNIX Ctrl+Z suspends with escape to shell.
	<code>telnet_port</code> —Disallow specifying a port in Telnet <code>goto</code> 's.
<code>-rlogin</code>	Disable recognition of <code>rlogin</code> commands.
<code>-selective</code>	Require <code>.www</code> browsable files to browse directories.
<code>-show_cursor</code>	If enabled, the cursor will not be hidden in the right-hand corner but will instead be positioned at the start of the currently selected link. <code>show_cursor</code> is the default for systems without <code>FANCY_CURSES</code> capabilities, and the default configuration can be changed in <code>userdefs.h</code> .
<code>-sjis</code>	Set kanji code to Shift JIS when Japanese mode is on.
<code>-source</code>	Works the same as <code>dump</code> but outputs HTML source instead of formatted text.
<code>-telnet</code>	Disable recognition of Telnet commands.
<code>-term=TERM</code>	Tell <code>lynx</code> what terminal type to assume it's talking to. (This may be useful for remote execution when, for example, <code>lynx</code> connects to a remote TCP/IP port that starts a script that, in turn, starts another <code>lynx</code> process.)
<code>-trace</code>	Turns on WWW trace mode.
<code>-traversal</code>	Traverse all HTTP links derived from <code>startfile</code> . When used with <code>-crawl</code> , each link that begins with the same string as <code>startfile</code> is output to a file, intended for indexing. See <code>CRAWL.announce</code> for more information.
<code>-underscore</code>	Toggles use of <code>_underline_format</code> in dumps.
<code>-validate</code>	Accept only HTTP URLs (for validation). Complete security restrictions also are implemented.
<code>-version</code>	Print version information.
<code>-vikeys</code>	Enable vi-like key movement.

COMMANDS

- Use Up arrow and Down arrow to scroll through hypertext links.
- Right arrow or Return will follow a highlighted hypertext link.
- Left Arrow will retreat from a link.

- Type `h` or `?` for online help and descriptions of keystroke commands.
- Type `k` for a complete list of the current keystroke command mappings.

NOTES

This is the Lynx 2.5 Release for UN*X/VMS.

If you wish to contribute to the further development of lynx, subscribe to our mailing list. Send e-mail to `majordomo@sig.net` with “subscribe lynx-dev” as the only line in the body of your message.

Send bug reports, comments, and suggestions to `lynx-dev@sig.net` after subscribing.

Unsubscribe by sending e-mail to `majordomo@sig.net` with `unsubscribe lynx-dev` as the only line in the body of your message. Do not send the unsubscribe message to the `lynx-dev` list itself.

ACKNOWLEDGMENTS

lynx has incorporated code from a variety of sources along the way. The earliest versions of lynx included code from Earl Fogel of Computing Services at the University of Saskatchewan, who implemented HYPERREZ in the UN*X environment. HYPERREZ was developed by Niel Larson of Think.com and served as the model for the early versions of lynx. Those versions also incorporated libraries from the UN*X Gopher clients developed at the University of Minnesota, and the later versions of lynx rely on the WWW client library code developed by Tim Berners-Lee and the WWW community. Also a special thanks to Foteos Macrides, who ported much of lynx to VMS and to everyone on the Net who has contributed to lynx’s development either directly (through comments or bug reports) or indirectly (through inspiration and development of other systems).

AUTHORS

Lou Montulli, Garrett Blythe, Craig Lavender, Michael Grobe, Charles Rezac
Academic Computing Services
University of Kansas
Lawrence, Kansas 66047

Foteos Macrides
Worcester Foundation
Shrewsbury, Massachusetts 01545

Local

macptopbm

macptopbm—Convert a MacPaint file into a portable bitmap

SYNOPSIS

```
macptopbm [-extraskip N][macpfile]
```

DESCRIPTION

macptopbm reads a MacPaint file as input and produces a portable bitmap as output.

OPTIONS

<code>-extraskip</code>	This flag is to get around a problem with some methods of transferring files from the Mac world to the UNIX world. Most of these methods leave the Mac files alone, but a few of them add the <code>find-erinfo</code> data onto the front of the UNIX file. This means an extra 128 bytes to skip over when reading the file. The symptom to watch for is that the resulting PBM file looks shifted to one side. If you get this, try <code>-extraskip 128</code> , and if that still doesn’t look right, try another value.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

`picttoppm(1)`, `pbmtomacp(1)`, `pbm(5)`

AUTHOR

Copyright © 1988 by Jef Poskanzer. The MacPaint-reading code is copyright © 1987 by Patrick J. Naughton (naughton@wind.sun.com).

29 March 1989

make

`make`—GNU `make` utility to maintain groups of programs

SYNOPSIS

```
make [ -f makefile ] [ option ] ... target ...
```

WARNING

This man page is an extract of the documentation of GNU `make`. It is updated only occasionally because the GNU project does not use `nroff`. For complete, current documentation, refer to the `info` file `make` or the DVI file `make.dvi`, which are made from the `texinfo` source file `make.texinfo`.

DESCRIPTION

The purpose of the `make` utility is to determine automatically which pieces of a large program need to be recompiled, and issue the commands to recompile them. This manual page describes the GNU implementation of `make`, which was written by Richard Stallman and Roland McGrath. Our examples show C programs because they are most common, but you can use `make` with any programming language whose compiler can be run with a shell command. In fact, `make` is not limited to programs. You can use it to describe any task where some files must be updated automatically from others whenever the others change.

To prepare to use `make`, you must write a file called the `makefile` that describes the relationships among files in your program and states the commands for updating each file. In a program, typically, the executable file is updated from object files, which are in turn made by compiling source files.

Once a suitable `makefile` exists, each time you change some source files, this simple shell command:

```
make
```

suffices to perform all necessary recompilations. The `make` program uses the `makefile` database and the last-modification times of the files to decide which of the files need to be updated. For each of those files, it issues the commands recorded in the database.

`make` executes commands in the `makefile` to update one or more target names, where `name` is typically a program. If no `-f` option is present, `make` will look for the `makefiles` `GNU-makefile`, `makefile`, and `Makefile`, in that order.

Normally you should call your `makefile` either `makefile` or `Makefile`. (We recommend `Makefile` because it appears prominently near the beginning of a directory listing, right near other important files such as `README`.) The first name checked, `GNUmakefile`, is not recommended for most `makefiles`. You should use this name if you have a `makefile` that is specific to GNU `make`, and will not be understood by other versions of `make`. If `makefile` is `-`, the standard input is read.

`make` updates a target if it depends on prerequisite files that have been modified since the target was last modified, or if the target does not exist.

OPTIONS

- `-b, -m` These options are ignored for compatibility with other versions of `make`.
- `-C dir` Change to directory `dir` before reading the makefiles or doing anything else. If multiple `-c` options are specified, each is interpreted relative to the previous one: `-C / -C etc` is equivalent to `-C /etc`. This is typically used with recursive invocations of `make`.
- `-d` Print debugging information in addition to normal processing. The debugging information says which files are being considered for remaking, which file times are being compared and with what results, which files actually need to be remade, which implicit rules are considered and which are applied—everything interesting about how `make` decides what to do.
- `-e` Give variables taken from the environment precedence over variables from makefiles.
- `-f file` Use `file` as a makefile.
- `-i` Ignore all errors in commands executed to remake files.
- `-I dir` Specifies a directory `dir` to search for included makefiles. If several `-I` options are used to specify several directories, the directories are searched in the order specified. Unlike the arguments to other flags of `make`, directories given with `-I` flags may come directly after the flag: `-I dir` is allowed, as well as `-I dir`. This syntax is allowed for compatibility with the C preprocessor's `-I` flag.
- `-j jobs` Specifies the number of jobs (commands) to run simultaneously. If there is more than one `-j` option, the last one is effective. If the `-j` option is given without an argument, `make` will not limit the number of jobs that can run simultaneously.
- `-k` Continue as much as possible after an error. Although the target that failed, and those that depend on it, cannot be remade, the other dependencies of these targets can be processed all the same.
- `-l,`
`-l load` Specifies that no new jobs (commands) should be started if there are other jobs running and the load average is at least `load` (a floating-point number). With no argument, removes a previous load limit.
- `-n` Print the commands that would be executed, but do not execute them.
- `-o file` Do not remake the file `file` even if it is older than its dependencies, and do not remake anything because of changes in `file`. Essentially, the file is treated as very old and its rules are ignored.
- `-p` Print the database (rules and variable values) that results from reading the makefiles; then execute as usual or as otherwise specified. This also prints the version information given by the `-v` switch (see below). To print the database without trying to remake any files, use `make -p -f/dev/null`.
- `-q` Question mode. Do not run any commands or print anything; just return an exit status that is zero if the specified targets are already up-to-date, nonzero otherwise.
- `-r` Eliminate use of the built-in implicit rules. Also clear out the default list of suffixes for suffix rules.
- `-s` Silent operation; do not print the commands as they are executed.
- `-S` Cancel the effect of the `-k` option. This is never necessary except in a recursive `make` where `-k` might be inherited from the top-level `make` via `MAKEFLAGS` or if you set `-k` in `MAKEFLAGS` in your environment.
- `-t` Touch files (mark them up-to-date without really changing them) instead of running their commands. This is used to pretend that the commands were done, in order to fool future invocations of `make`.
- `-v` Print the version of the `make` program plus a copyright, a list of authors, and a notice that there is no warranty. After this information is printed, processing continues normally. To get this information without doing anything else, use `make -v -f/dev/null`.
- `-w` Print a message containing the working directory before and after other processing. This may be useful for tracking down errors from complicated nests of recursive `make` commands.
- `-W file` Pretend that the target file `file` has just been modified. When used with the `-n` flag, this shows you what would happen if you were to modify that file. Without `-n`, it is almost the same as running a `touch` command on the given file before running `make`, except that the modification time is changed only in the imagination of `make`.

SEE ALSO

`/usr/local/doc/gnumake.dvi`

The GNU Make Manual

BUGS

See the chapter “Problems and Bugs” in *The GNU Make Manual*.

AUTHOR

This manual page contributed by Dennis Morse of Stanford University. It has been reworked by Roland McGrath.

GNU, 22 August 1989

makedepend

makedepend—Create dependencies in makefiles

SYNOPSIS

```
makedepend [ -Dname=def ] [-Dname ] [-Iincludedir ] [-Yincludedir ] [-a ]
[-fmakefile ] [-oobjsuffix ] [-pobjprefix ] [-sstring ] [-wwidth ] [-v ] [-m ]
[--otheroptions -- ] sourcefile . . .
```

DESCRIPTION

makedepend reads each `sourcefile` in sequence and parses it like a C-preprocessor, processing all `#include`, `#define`, `#undef`, `#ifdef`, `#ifndef`, `#endif`, `#if` and `#else` directives so that it can correctly tell which `#include` directives would be used in a compilation. Any `#include` directives can reference files having other `#include` directives, and parsing will occur in these files as well.

Every file that a source file includes, directly or indirectly, is what makedepend calls a *dependency*. These dependencies are then written to a makefile in such a way that `make(1)` will know which object files must be recompiled when a dependency has changed.

By default, makedepend places its output in the file named `makefile` if it exists; otherwise, `Makefile`. An alternate makefile may be specified with the `-f` option. It first searches the makefile for the line:

```
# DO NOT DELETE THIS LINE -- make depend depends on it.
```

or one provided with the `-s` option, as a delimiter for the dependency output. If it finds it, it will delete everything following this to the end of the makefile and put the output after this line. If it doesn't find it, the program will append the string to the end of the makefile and place the output following that. For each `sourcefile` appearing on the command line, makedepend puts lines in the makefile of the form:

```
sourcefile.o: dfile . . .
```

where `sourcefile.o` is the name from the command line with its suffix replaced with `.o`, and `dfile` is a dependency discovered in a `#include` directive while parsing `sourcefile` or one of the files it included.

EXAMPLE

Normally, makedepend will be used in a makefile target so that typing makedepend will bring the dependencies up-to-date for the makefile. For example,

```
SRCS = file1.c file2.c . . .
CFLAGS = -O -DHACK -I../foobar -xyz
depend:
makedepend -- $(CFLAGS) -- $(SRCS)
```

OPTIONS

makedepend will ignore any option that it does not understand so that you may use the same arguments that you would for `cc(1)`.

<code>-Dname=def</code> or	Define. This places a definition for <code>name</code> in makedepend's symbol table. Without <code>=def</code> , the symbol becomes defined as 1.
<code>-Dname</code>	

<code>-Iincludedir</code>	Include directory. This option tells <code>makedepend</code> to prepend <code>includedir</code> to its list of directories to search when it encounters a <code>#include</code> directive. By default, <code>makedepend</code> only searches the standard include directories (usually <code>/usr/include</code> and possibly a compiler-dependent directory).
<code>-Yincludedir</code>	Replace all of the standard include directories with the single specified include directory; you can omit the <code>includedir</code> to simply prevent searching the standard include directories.
<code>-a</code>	Append the dependencies to the end of the file instead of replacing them.
<code>-fmakefile</code>	Filename. This allows you to specify an alternate makefile in which <code>makedepend</code> can place its output.
<code>-oobjsuffix</code>	Object file suffix. Some systems may have object files whose suffix is something other than <code>.o</code> . This option allows you to specify another suffix, such as <code>.b</code> with <code>-o.b</code> or <code>:obj</code> with <code>-o:obj</code> and so forth.
<code>-pobjprefix</code>	Object file prefix. The prefix is prepended to the name of the object file. This is usually used to designate a different directory for the object file. The default is the empty string.
<code>-sstring</code>	Starting string delimiter. This option permits you to specify a different string for <code>makedepend</code> to look for in the makefile.
<code>-wwidth</code>	Line width. Normally, <code>makedepend</code> will ensure that every output line that it writes will be no wider than 78 characters for the sake of readability. This option enables you to change this width.
<code>-v</code>	Verbose operation. This option causes <code>makedepend</code> to emit the list of files included by each input file on standard output.
<code>-m</code>	Warn about multiple inclusion. This option causes <code>makedepend</code> to produce a warning if any input file includes another file more than once. In previous versions of <code>makedepend</code> , this was the default behavior; the default has been changed to better match the behavior of the C compiler, which does not consider multiple inclusion to be an error. This option is provided for backwards compatibility, and to aid in debugging problems related to multiple inclusion.
<code>-- options --</code>	If <code>makedepend</code> encounters a double hyphen (<code>--</code>) in the argument list, then any unrecognized argument following it will be silently ignored; a second double hyphen terminates this special treatment. In this way, <code>makedepend</code> can be made to safely ignore esoteric compiler arguments that might normally be found in a <code>CFLAGS</code> make macro. (See the preceding “Example” section.) All options that <code>makedepend</code> recognizes and that appear between the pair of double hyphens are processed normally.

ALGORITHM

The approach used in this program enables it to run an order of magnitude faster than any other dependency generator I have ever seen. Central to this performance are two assumptions: that all files compiled by a single makefile will be compiled with roughly the same `-I` and `-D` options; and that most files in a single directory will include largely the same files.

Given these assumptions, `makedepend` expects to be called once for each makefile, with all source files that are maintained by the makefile appearing on the command line. It parses each source and include file exactly once, maintaining an internal symbol table for each. Thus, the first file on the command line will take an amount of time proportional to the amount of time that a normal C preprocessor takes. But on subsequent files, if it encounters an include file that it has already parsed, it does not parse it again.

For example, imagine you are compiling two files, `file1.c` and `file2.c`; they both include the header file `header.h`, and the file `header.h` in turn includes the files `def1.h` and `def2.h`. When you run the command:

```
makedepend file1.c file2.c
```

`makedepend` will parse `file1.c` and consequently, `header.h` and then `def1.h` and `def2.h`. It then decides that the dependencies for this file are

```
file1.o: header.h def1.h def2.h
```

But when the program parses `file2.c` and discovers that it, too, includes `header.h`, it does not parse the file, but simply adds `header.h`, `def1.h`, and `def2.h` to the list of dependencies for `file2.o`.

SEE ALSO

`cc(1)`, `make(1)`

BUGS

make depend parses, but does not currently evaluate, the SVR4 `#predicate(token-list)` preprocessor expression; such expressions are simply assumed to be true. This may cause the wrong `#include` directives to be evaluated.

Imagine you are parsing two files, say `file1.c` and `file2.c`, and each includes the file `def.h`. The list of files that `def.h` includes might truly be different when `def.h` is included by `file1.c` than when it is included by `file2.c`. But when `make depend` arrives at a list of dependencies for a file, it is cast in concrete.

AUTHOR

Todd Brunhoff, Tektronix, Inc. and MIT Project Athena

X Version 11 Release 6

makestrs

makestrs—Make string table C source and header(s)

SYNOPSIS

```
makestrs [-f source] [-abioptions ...]
```

DESCRIPTION

The `makestrs` command creates string table C source files and headers. If `-f source` is not specified, `makestrs` will read from `stdin`. The C source file is always written to `stdout`. `makestrs` creates one or more C header files as specified in the source file. The following options may be specified: `-sparcabi`, `-intelabi`, `-functionabi`, `-arrayperabi`, and `-defaultabi`.

`-sparcabi` is used on SPARC platforms conforming to the SPARC Compliance Definition, i.e., SVR4/Solaris.

`-intelabi` used on Intel platforms conforming to the System V Application Binary Interface (SVR4).

`-earlyR6abi` may be used in addition to `-intelabi` for situations where the vendor wishes to maintain binary compatibility between X11R6 public-patch 11 (and earlier) and X11R6 public-patch 12 (and later).

`-functionabi` generates a functional application binary interface to the string table. This mechanism imposes a severe performance penalty and it's recommended that you not use it.

`-arrayperabi` results in a separate array for each string. This is the default behavior if `makestrs` was compiled with `-DARRAYPERSTR` (it almost never is).

`-defaultabi` forces the generation of the “normal” string table even if `makestrs` was compiled with `-DARRAYPERSTR`. `makestrs` is almost never compiled with `-DARRAYPERSTR`, so this is the default behavior if no application binary interface (ABI) options are specified.

SYNTAX

The syntax for string-list file is as follows (items in square brackets are optional):

```
#prefix <text>
#feature <text>
#externref <text>
#externdef [<text>]
[#ctempl <text>]
#file <filename>
#table <tablename>
[#htempl] <text>
...
<text>
[#table <tablename>]
<text>
...
```

```
<text>
...
#table <tablename>
...
[#file <filename>
...]
```

You may have one or more `#file` directives. Each `#file` may have one or more `#table` directives.

The `#prefix` directive determines the string that `makestr` will prefix to each definition.

The `#feature` directive determines the string that `makestr` will use for the feature-test macro, for example, `X=STRINGDEFINES`.

The `#externref` directive determines the string that `makestr` will use for the `extern` clause; typically this will be `extern`, but Motif wants it to be `externalref`.

The `#externdef` directive determines the string that `makestr` will use for the declaration; typically, this will be the null string, and Motif will use `externaldef(_xmstrings)`.

The `#ctmpl` directive determines the name of the file used as a template for the C source file that is generated.

Each `#file <filename>` directive will result in a corresponding header file by that name containing the appropriate definitions as specified by command-line options. A single C source file containing the declarations for the definitions in all the headers will be printed to `stdout`.

The `#htmpl` directive determines the name of the file used as a template for the C header file that is generated.

Each `#table <tablename>` directive will be processed in accordance with the ABI. On most platforms, all tables will be catenated into a single table with the name of the first table for that file. To conform to the Intel ABI, separate tables will be generated with the names indicated.

The template files specified by the `#ctmpl` and `#htmpl` directives are processed by copying line for line from the template file to the appropriate output file. The line containing the string `<<<STRING_TABLE_GOES_HERE>>>` is not copied to the output file. The appropriate data is then copied to the output file and then the remainder of the template file is copied to the output file.

BUGS

`makestrs` is not very forgiving of syntax errors. Sometimes you need a trailing space after `#` directives, other times they will mess you up. No warning messages are emitted.

SEE ALSO

SPARC Compliance Definition 2.2, SPARC International Inc., 535 Middlefield Road, Suite 210, Menlo Park, CA 94025

System V Application Binary Interface, Third Edition, ISBN 0-13-100439-5, UNIX Press, PTR Prentice Hall, 113 Sylvan Avenue, Englewood Cliffs, NJ 07632

System V Application Binary Interface, Third Edition, Intel386 Architecture Processor Supplement, ISBN 0-13-104670-5, UNIX Press, PTR Prentice Hall, 113 Sylvan Avenue, Englewood Cliffs, NJ 07632

System V Application Binary Interface, Third Edition, SPARC Architecture Processor Supplement, ISBN 0-13-104696-9, UNIX Press, PTR Prentice Hall, 113 Sylvan Avenue, Englewood Cliffs, NJ 07632

X Version 11 Release 6

mattrib

mattrib—Change MS-DOS file attribute flags

SYNOPSIS

```
mattrib [ -a!+a ] [-h!+h] [-r!+r] [-s!+s] msdosfile [ msdosfiles... ]
```

DESCRIPTION

`attrib` adds attribute flags to an MS-DOS file (with the `+` operator) or removes attribute flags (with the `-` operator).

`attrib` allows the following command-line options:

- `a` Archive bit. Used by some backup programs to indicate a new file.
- `r` Read-only bit. Used to indicate a read-only file. Files with this bit set cannot be erased by `DEL` or modified.
- `s` System bit. Used by MS-DOS to indicate an operating system file.
- `h` Hidden bit. Used to make files hidden from `DIR`.

SEE ALSO

`mtools(1)`

Local

mbadblocks

`mbadblocks`—Scan an MS-DOS floppy and mark its unused bad blocks as bad.

SYNOPSIS

`mbadblocks drive:`

DESCRIPTION

`mbadblocks` scans an MS-DOS floppy for bad blocks. All unused bad blocks are marked as such in the FAT. This is intended to be used right after `mformat`. It is not intended to salvage bad disks.

SEE ALSO

`mtools(1)`

BUGS

This should (but doesn't `:-)` also try to salvage bad blocks that are in use by reading them repeatedly, and then mark them bad.

mcd

`mcd`—Change MS-DOS directory

SYNOPSIS

`mcd [ msdosdirectory ]`

DESCRIPTION

Without arguments, `mcd` will report the current device and working directory. Otherwise, `mcd` changes the current device and current working directory relative to an MS-DOS filesystem.

The environmental variable `MCWD` may be used to locate the file where the device and current working directory information is stored. The default is `$HOME/.mcwd`. Information in this file is ignored if the file is more than six hours old.

MS-DOS subdirectory names are supported with either the `/` or `\` separator. The use of the `\` separator or wildcards will require the directory name to be enclosed in quotes to protect it from the shell.

`mcd` returns 0 on success or 1 on failure.

SEE ALSO

`mdir(1)`

BUGS

Unlike MS-DOS versions of CD, `mc`d can be used to change to another device.

It may be wise to remove old `.mcwd` files at logout.

Local

mcookie

`mcookie`—Generate magic cookies for `xauth`

SYNOPSIS

`mcookie`

DESCRIPTION

`mcookie` generates a 128-bit random hexadecimal number for use with the X authority system. Typical usage:

```
xauth add :0 . 'mcookie'
```

SEE ALSO

`x(1)`, `xauth(1)`

12 February 1995

mcopy

`mcopy`—Copy MS-DOS files to/from UNIX

SYNOPSIS

```
mcopy [ -tnvmo0sSrRA ] sourcefile targetfile
mcopy [ -tnvmo0sSrRA ] sourcefile [ sourcefiles... ] targetdirectory
mcopy [ -tnvm ] MSDOSsourcefile
```

DESCRIPTION

`mcopy` copies the specified file to the named file, or copies multiple files to the named directory. The source and target can be either MS-DOS or UNIX files.

The use of a drive letter designation on the MS-DOS files—a: for example—determines the direction of the transfer. A missing drive designation implies a UNIX file whose path starts in the current directory. If a source drive letter is specified with no attached filename (for example, `mcopy a: .`), all files are copied from that drive.

If only a single, MS-DOS source parameter is provided (for example, `mcopy a:foo.exe`), an implied destination of the current directory (`.`) is assumed.

A filename of `-` means standard input or standard output, depending on its position on the command line.

`mcopy` will allow the following command-line options:

- `t` Text file transfer. `mcopy` will translate incoming carriage return/line feeds to line feeds.
- `n` No warning. `mcopy` will not warn the user when overwriting an existing file.
- `v` Verbose mode.
- `m` Preserve the file modification time.

If the target file already exists, and the `-n` option is not in effect, `mcopy` asks whether to overwrite the file or to rename the new file. (See the `mtools(1)` man page for details.)

SEE ALSO

`mttools(1)`, `mread(1)`, `mwrite(1)`

BUGS

Unlike MS-DOS, the `+` operator (append) from MS-DOS is not supported.

Local

md5sum

`md5sum`—Generate/check MD5 message digests

SYNOPSIS

```
md5sum [-bv][-c [ file ]]
md5sum file ...
```

DESCRIPTION

`md5sum` generates and checks MD5 message digests, as described in RFC-1321. The message digest produced can be thought of as a 128-bit “signature” of the input file. Typically, `md5sum` is used to verify the integrity of files made available for distribution via anonymous FTP (for example, announcements for new versions of `irc(1)` usually contain MD5 signatures). Message digests for a tree of files can be generated with a command similar to the following:

```
find . -type f -print | xargs md5sum
```

The output of this command is suitable as input for the `-c` option.

OPTIONS

<code>-c [file]</code>	Check message digests. Input is taken from <code>stdin</code> or from the specified <code>file</code> . The input should be in the same format as the output generated by <code>md5sum</code> .
<code>-v</code>	Verbose. Print filenames when checking.
<code>-b</code>	Read files in binary mode; otherwise, end-of-file conventions will be ignored.

HISTORY

The `md5sum` program was written by Branko Lankester and may be freely distributed. The original source code is in the MIT PGP 2.6.2 distribution. Those concerned about the integrity of this version should obtain the original sources and compile their own version.

The underlying implementation of Ron Rivest’s MD5 algorithm was written by Colin Plumb and is in the public domain. (Equivalent code is also available from RSA Data Security, Inc.)

SEE ALSO

`sum(1)`, `cksum(1)`, `pgp(1)`

Linux 1.0, 11 February 1995

mdel

`mdel`—Delete an MS-DOS file

SYNOPSIS

```
mdel [ -v ] msdosfile [ msdosfiles... ]
```

DESCRIPTION

`mdel` deletes a file on an MS-DOS filesystem.

`mdel` will allow the following command-line option:

v Verbose mode. Echo the filenames as they are processed.

`mdel` will ask for verification prior to removing a read-only file.

SEE ALSO

`mtools(1)`

Local

mdeltree

`mdeltree`—Remove an MS-DOS directory tree

SYNOPSIS

```
mdeltree [ -v ] msdosdirectory [ msdosdirectories... ]
```

DESCRIPTION

`mdeltree` removes a directory and all the files and subdirectories it contains from an MS-DOS filesystem. `mdeltree` will allow the following command-line option:

v Verbose mode. Displays each file or directory as it is removed.

An error occurs if the directory does not exist.

SEE ALSO

`mtools(1)`, `mrd(1)`

Local

mdir

`mdir`—Display an MS-DOS directory

SYNOPSIS

```
mdir [ -w ] msdosdirectory
mdir [ -w ][-a ] msdosfile [ msdosfiles... ]
```

DESCRIPTION

`mdir` displays the contents of an MS-DOS directory.

`mdir` will allow the following command-line options:

w Wide output. This option will print the filenames across the page without displaying the file size or creation date.

a Also list hidden files.

An error occurs if a component of the path is not a directory.

SEE ALSO

`mtools(1)`

Local

merge

merge—Three-way file merge

SYNOPSIS

```
merge [ options ] file1 file2 file3
```

DESCRIPTION

merge incorporates all changes that lead from `file2` to `file3` into `file1`. The result ordinarily goes into `file1`. merge is useful for combining separate changes to an original. Suppose `file2` is the original, and both `file1` and `file3` are modifications of `file2`. Then merge combines both changes.

A conflict occurs if both `file1` and `file3` have changes in a common segment of lines. If a conflict is found, merge normally outputs a warning and brackets the conflict with <<<<<< and >>>>>> lines. A typical conflict will look like this:

```
<<<<<< file A
lines in file A
=====
lines in file B
>>>>>> file B
```

If there are conflicts, the user should edit the result and delete one of the alternatives.

OPTIONS

- A Output conflicts using the -A style of `diff3(1)`, if supported by `diff3`. This merges all changes leading from `file2` to `file3` into `file1`, and generates the most verbose output.
- E, -e These options specify conflict styles that generate less information than -A. See `diff3(1)` for details. The default is -E. With -e, merge does not warn about conflicts.
- L label This option may be given up to three times, and specifies labels to be used in place of the corresponding filenames in conflict reports. That is, `merge-Lx-L y -Lz a b c` generates output that looks like it came from files `x`, `y`, and `z` instead of from files `a`, `b`, and `c`.
- p Send results to standard output instead of overwriting `file1`.
- q Quiet; do not warn about conflicts.
- v Print RCS's version number.

DIAGNOSTICS

Exit status is 0 for no conflicts, 1 for some conflicts, 2 for trouble.

IDENTIFICATION

Author: Walter F. Tichy.

Manual Page Revision: 5.7; Release Date: 1995/06/01.

Copyright © 1982, 1988, 1989 Walter F. Tichy.

Copyright © 1990, 1991, 1992, 1993, 1994, 1995 Paul Eggert.

SEE ALSO

`diff3(1)`, `diff(1)`, `rcsmerge(1)`, `co(1)`

BUGS

It normally does not make sense to merge binary files as if they were text, but merge tries to do it anyway.

mesg

mesg—Display (do not display) messages from other users

SYNOPSIS

```
mesg [n][y]
```

DESCRIPTION

The `mesg` utility is invoked by a users to control write access others have to the terminal device associated with the standard error output. If write access is allowed, then programs such as `talk(1)` and `write(1)` may display messages on the terminal.

Traditionally, write access is allowed by default. However, as users become more conscious of various security risks, there is a trend to remove write access by default, at least for the primary login shell. To make sure your `ttys` are set the way you want them to be set, `mesg` should be executed in your login scripts.

Options available:

```
n      Disallows messages
y      Permits messages to be displayed
```

If no arguments are given, `mesg` displays the present message status to the standard error output.

The `mesg` utility exits with one of the following values:

```
\0      Messages are allowed.
\1      Messages are not allowed.
1       An error has occurred.
```

FILES

```
/dev/[pt]ty[pq]?
```

SEE ALSO

`biff(1)`, `talk(1)`, `write(1)`, `wall(1)`, `login(1)`, `xterm(1)`

HISTORY

A `mesg` command appeared in version 6 AT&T UNIX.

Linux 1.2, 10 March 1995

mformat

mformat—Add an MS-DOS filesystem to a low-level formatted disk

SYNOPSIS

```
mformat [ -t tracks ] [ -h heads ] [ -s sectors ] [ -l volume label ]
[ -S sizecode ] [ -2 sectors on track 0 ] [ -M software sector size ]
[ -a ][-X ][-C ][-H hidden sectors ] drive:
```

DESCRIPTION

`mformat` adds a minimal MS-DOS filesystem (boot sector, FAT, and root directory) to a disk that has already been formatted by a UNIX low-level format.

The follow options are supported: (The `s`, `2`, `1`, and `M` options may not exist if this copy of `mttools` has been compiled without the `USE_2M` option).

- t The number of tracks (not cylinders).
- h The number of heads (sides).
- s The number of sectors per track. If the `2m` option is given, number of 512-byte sector equivalents on generic tracks (that is, not head 0 track). If the `2m` option is not given, number of physical sectors per track (which may be bigger than 512 bytes).
- l An optional volume label.
- S The sizecode. The size of the sector is $2^{(\text{sizecode} + 7)}$.
- 2 `2m` format. The parameter to this option describes the number of sectors on track 0, head 0. This option is recommended for sectors bigger than normal.
- 1 Don't use a `2m` format, even if the current geometry of the disk is a `2m` geometry.
- M Software sector size. This parameter describes the sector size in bytes used by the MS-DOS filesystem. By default it is the physical sector size.
- a If this option is given, an Atari-style serial number is generated. Ataris store their serial number in the OEM label.
- X Formats the disk as an Xdf disk. Xdf disks are used by OS/2. This format can hold 1756Kb, and is faster than the equivalent `2m` formats. The disk has first to be low-level formatted using the `xdffcopy` utility included in the `fdutils` package.
- c Creates the disk image file to install the MS-DOS filesystem on it. Obviously, this is useless on physical devices such as floppies and hard disk partitions.
- H Number of hidden sectors. This parameter is useful for formatting hard disk partitions, which are not aligned on track boundaries (in other words, first head of first track doesn't belong to the partition, but contains a partition table). In that case the number of hidden sectors is in general the number of sectors per cylinder. This is untested.
- n Serial number.

To format a disk at a density other than the default, you must supply (at least) those command-line parameters that are different from the default.

`Mformat` returns 0 on success or 1 on failure.

SEE ALSO

`mlabel(1)`

BUGS

Requires a low-level format utility from UNIX.

Doesn't detect (or record) bad block information.

Local

mgrtopbm

`mgrtopbm`—Convert an MGR bitmap into a portable bitmap

SYNOPSIS

`mgrtopbm` [`mgrfile`]

DESCRIPTION

`mgrtopbm` reads an MGR bitmap as input and produces a portable bitmap as output.

SEE ALSO

`pbmto mgr(1)`, `pbm(5)`

AUTHOR

Copyright © 1989 by Jef Poskanzer.

24 January 1989

mkdir

mkdir—Make directories

SYNOPSIS

```
mkdir [-p] [-m mode] [--parents] [--mode=mode] [--help] [--version] dir...
```

DESCRIPTION

This manual page documents the GNU version of `mkdir`. `mkdir` creates a directory with each given name. By default, the mode of created directories is 0777 minus the bits set in the umask.

OPTIONS

- `-m, --mode mode` Set the mode of created directories to `mode`, which is symbolic as in `chmod` and uses the default mode as the point of departure.
- `-p, --parents` Ensure that each given directory exists. Create any missing parent directories for each argument. Parent directories default to the umask modified by `u+wx`. Do not consider an argument directory that already exists to be an error.
- `--help` Print a usage message on standard output and exit successfully.
- `--version` Print version information on standard output then exit successfully.

GNU File Utilities

mkdirhier

mkdirhier—Make a directory hierarchy

SYNOPSIS

```
mkdirhier directory ...
```

DESCRIPTION

The `mkdirhier` command creates the specified directories. Unlike `mkdir`, if any of the parent directories of the specified directory do not exist, it creates them as well.

SEE ALSO

`mkdir(1)`

X Version 11 Release 6

mkfifo

mkfifo—Make FIFOs (named pipes)

SYNOPSIS

```
mkfifo [-m mode] [--mode=mode] [--help] [--version] filename...
```

DESCRIPTION

This manual page documents the GNU version of `mkfifo`. `mkfifo` creates a FIFO with each given name. By default, the mode of created FIFOs is 0666 minus the bits set in the `umask`.

OPTIONS

- `-m, --mode mode` Set the mode of created FIFOs to `mode`, which is symbolic as in `chmod` and uses the default mode as the point of departure.
- `--help` Print a usage message on standard output and exit successfully.
- `--version` Print version information on standard output then exit successfully.

GNU File Utilities

mkmanifest

`mkmanifest`—Create a shell script to restore UNIX filenames

SYNOPSIS

```
mkmanifest [ files ]
```

DESCRIPTION

`mkmanifest` creates a shell script that will aid in the restoration of UNIX filenames that got clobbered by the MS-DOS filename restrictions. MS-DOS filenames are restricted to eight-character names, three-character extensions, uppercase only, no device names, and no illegal characters.

The `mkmanifest` program is compatible with the methods used in `pcomm`, `arc`, and `mttools` to change perfectly good UNIX filenames to fit the MS-DOS restrictions.

EXAMPLE

Say you want to copy the following UNIX files to an MS-DOS disk (using the `mcopy` command):

```
very_long_name
2.many.dots
illegal:
good.c
prn.dev
Capital
```

`mcopy` will convert the names to

```
very_lon
2xmany.dot
illegalx
good.c
xprn.dev
capital
```

The command:

```
mkmanifest very_long_name 2.many.dots illegal: good.c prn.dev Capital > manifest
```

would produce the following:

```
mv very_lon very_long_name
mv 2xmany.dot 2.many.dots
mv illegalx illegal:
mv xprn.dev prn.dev
mv capital Capital
```


Notice that `good.c` did not require any conversion, so it did not appear in the output.

Suppose I've copied these files from the disk to another UNIX system, and I now want the files back to their original names. If the file `manifest` (the output captured above) was sent along with those files, it could be used to convert the filenames.

BUGS

The short names generated by `mkmanifest` follow the old convention (from `mttools-2.0.7`) and not the one from Windows 95 and `mttools-3.0`.

SEE ALSO

`arc(1)`, `pcomm(1)`, `mttools(1)`

Local

mknod

`mknod`—Make special files

SYNOPSIS

```
mknod [options] filename {bcu} major minor
mknod [options] filename p
```

Options:

```
[-m mode] [--mode=mode] [--help] [--version]
```

DESCRIPTION

This manual page documents the GNU version of `mknod`. `mknod` creates a FIFO, character special file, or block special file with the given filename. By default, the mode of created files is 0666 minus the bits set in the `umask`.

The argument after `filename` specifies the type of file to make:

`p` for a FIFO

`b` for a block (buffered) special file

`c` or `u` for a character (unbuffered) special file

When making a block or character special file, the major and minor device numbers must be given after the file type.

OPTIONS

```
-m, --mode mode  Set the mode of created files to mode, which is symbolic as in chmod and uses the default mode as the point
                  of departure.
--help           Print a usage message on standard output and exit successfully.
--version        Print version information on standard output then exit successfully.
```

GNU File Utilities

mlabel

`mlabel`—Make an MS-DOS volume label

SYNOPSIS

```
mlabel [ -v ] drive: [ new_label ]
```

DESCRIPTION

`mlabel` displays the current volume label, if present. If `new_label` is not given, and if neither the `c` nor the `s` options are set, it prompts the user for a new volume label. To delete an existing volume label, press return at the prompt.

`mlabel` supports the following command-line option:

- `v` Verbose mode. Display the new volume label if the label supplied is invalid.
- `c` Clears an existing label, without prompting the user.
- `s` Shows the existing label, without prompting the user.

Reasonable care is taken to create a valid MS-DOS volume label. If an invalid label is specified, `mlabel` will change the label (and display the new label if the verbose mode is set).

`Mlabel` returns 0 on success or 1 on failure.

SEE ALSO

`mformat(1)`

Local

mmd

`mmd`—Make an MS-DOS subdirectory

SYNOPSIS

```
mmd [ -vo0sSrRA ] msdosdirectory [ msdosdirectories... ]
```

DESCRIPTION

`mmd` makes a new directory on an MS-DOS filesystem.

`mmd` will allow the following command-line option:

- `v` Verbose mode. Display the new directory name as it is created.

An error occurs if the directory already exists.

SEE ALSO

`mtools(1)`, `mrd(1)`,

Local

mmount

`mmount`—Mount an MS-DOS disk

SYNOPSIS

```
mmount msdosdrive [mountargs]
```

DESCRIPTION

`mmount` reads the boot sector of an MS-DOS disk, configures the drive geometry, and finally mounts it, passing `mountargs` to `mount`. If no `mount` arguments are specified, the name of the device is used. If the disk is write-protected, it is automatically mounted read-only.

SEE ALSO

`mtools(1)`, `mount(8)`

Local

mmove

mmove—Move or rename an existing MS-DOS file or subdirectory

SYNOPSIS

```
mmove [ -voSsrRA ] sourcefile targetfile
mmove [ -voSsrRA ] sourcefile [ sourcefiles... ] targetdirectory
```

DESCRIPTION

mmove moves or renames an existing MS-DOS file or subdirectory.

mmove will allow the following command-line option:

v Verbose mode. Display the new filename if the name supplied is invalid.

Additionally, it allows the clash-handling options described in the man page for `mtools`.

MS-DOS subdirectory names are supported with either the `/` or `\` separator. The use of the `\` separator or wildcards will require the names to be enclosed in quotes to protect them from the shell. Unlike the MS-DOS version of `MOVE`, **mmove** is able to move subdirectories.

SEE ALSO

`mren(1)`, `mtools(1)`

more

more—File perusal filter for crt viewing

SYNOPSIS

```
more [-dlfpcsu] [-num] [+/- pattern] [+ linenum]
```

DESCRIPTION

more is a filter for paging through text one screenful at a time. This version is especially primitive. Users should realize that `less(1)` provides `more(1)` emulation and extensive enhancements.

OPTIONS

Command-line options are described in the following list. Options are also taken from the environment variable `MORE` (make sure to precede them with a hyphen (`-`)) but command-line options will override them.

- num** This option specifies an integer that is the screen size (in lines).
- d** **more** will prompt the user with the message [Press space to continue, 'q' to quit.] and will display [Press 'h' for instructions.] instead of ringing the bell when an illegal key is pressed.
- l** **more** usually treats (form feed) as a special character, and will pause after any line that contains a form feed. The **-l** option will prevent this behavior.
- f** Causes **more** to count logical, rather than screen lines (that is, long lines are not folded).
- p** Do not scroll. Instead, clear the whole screen and then display the text.
- c** Do not scroll. Instead, paint each screen from the top, clearing the remainder of each line as it is displayed.

- s Squeeze multiple blank lines into one.
- u Suppress underlining.
- +/ The +/ option specifies a string that will be searched for before each file is displayed.
- +num Start at line number.

COMMANDS

Interactive commands for `more` are based on `vi(1)`. Some commands may be preceded by a decimal number, called `k` in the following descriptions. In the following descriptions, `^X` means `control-X`.

- h or ? Help: display a summary of these commands. If you forget all the other commands, remember this one.
- SPACE Display next `k` lines of text. Defaults to current screen size.
- z Display next `k` lines of text. Defaults to current screen size. Argument becomes new default.
- RETURN Display next `k` lines of text. Defaults to 1. Argument becomes new default.
- d or ^D Scroll `k` lines. Default is current scroll size, initially 11. Argument becomes new default.
- q or Q INTERRUPT Exit.
- s Skip forward `k` lines of text. Defaults to 1.
- f Skip forward `k` screenfuls of text. Defaults to 1.
- b or ^B Skip backwards `k` screenfuls of text. Defaults to 1.
- ' Go to place where previous search started.
- = Display current line number.
- /pattern Search for `k`th occurrence of regular expression. Defaults to 1.
- n Search for `k`th occurrence of last r.e. Defaults to 1.
- !`<cmd>` or :!`<cmd>` Execute `<cmd>` in a subshell.
- v Start up `/usr/bin/vi` at current line.
- ^L Redraw screen.
- :n Go to `k`th next file. Defaults to 1.
- :p Go to `k`th previous file. Defaults to 1.
- Ic :f Display current filename and line number.
- . Repeat previous command.

ENVIRONMENT

`more` utilizes the following environment variables, if they exist:

- MORE This variable may be set with favored options to `more`.
- SHELL Current shell in use (normally set by the shell at login time).
- TERM Specifies terminal type, used by `more` to get the terminal characteristics necessary to manipulate the screen.

SEE ALSO

`vi(1)`, `less(1)`

AUTHORS

Eric Shienbrood, UC Berkeley. Modified by Geoff Peck, UCB to add underlining, single spacing. Modified by John Foderaro, UCB to add `-c` and `MORE` environment variable.

HISTORY

The `more` command appeared in BSD 3.0. This man page documents `more` version 5.19 (Berkeley 29 June 1988), which is currently in use in the Linux community. Documentation was produced using several other versions of the man page, and extensive inspection of the source code.

mrd

mrd—Remove an MS-DOS subdirectory

SYNOPSIS

```
mrd [ -v ] msdosdirectory [ msdosdirectories... ]
```

DESCRIPTION

mrd removes a directory from an MS-DOS filesystem. mmd will allow the following command-line option:

v Verbose mode. Display the directory name as it is removed.

An error occurs if the directory does not exist or is not empty.

SEE ALSO

mtools(1), mmd(1), mdeltree(1)

Local

mread

mread—Read (copy) an MS-DOS file to UNIX

SYNOPSIS

```
mread [ -tnvmo0sSrRA ] msdosfile unixfile
```

```
mread [ -tnvmo0sSrRA ] msdosfile [ msdosfiles... ] unixdirectory
```

DESCRIPTION

This command is obsolete, and only supplied for backwards compatibility reasons with old scripts. Use mcopy instead.

SEE ALSO

mcopy(1), mtype(1), mtools(1)

mren

mren—Rename or move an existing MS-DOS file or subdirectory

SYNOPSIS

```
mren [ -vo0sSrRA ] sourcefile targetfile
```

```
mmove [ -vo0sSrRA ] sourcefile [ sourcefiles... ] targetdirectory
```

DESCRIPTION

mren renames an existing file on an MS-DOS filesystem.

Mren will allow the following command-line option:

vo0sSrRA Verbose mode. Display the new filename if the name supplied is invalid.

If the first syntax is used (only one *sourcefile*), and if the target name doesn't contain any slashes or colons, the file (or subdirectory) will be renamed in the same directory, instead of being moved to the current *pwd* directory as would be the case with *mmove*. Unlike the MS-DOS version of *REN*, *mren* can be used to rename directories.

BUGS

Unlike the MS-DOS version of `REN`, `mren` can be used to rename directories.

SEE ALSO

`mcd`(1)

Local

mtest

`mtest`—Test the `mtools` configuration files

SYNOPSIS

`mtest`

DESCRIPTION

`mtest` reads the `mtools` configuration files and prints the cumulative configuration to `stdout`. The output can be used as a configuration file itself (although you might want to remove redundant clauses). You may use this program to convert old-style configuration files into new style configuration files.

SEE ALSO

`mtools`(5)

Local

mtools

`mtools`—A collection of tools for manipulating MS-DOS files

SYNOPSIS

The `mtools` are

`mattrib`—Change MS-DOS file attribute flags
`mbadblocks`—Test a floppy disk, and mark the bad blocks in the FAT
`mcd`—Change MS-DOS directory
`mcopy`—Copy MS-DOS files to/from UNIX
`mdel`—Delete an MS-DOS file
`mdir`—Display an MS-DOS directory
`mformat`—Add an MS-DOS filesystem to a low-level formatted floppy disk
`mlabel`—Make an MS-DOS volume label
`mmkd`—Make an MS-DOS subdirectory
`mmount`—Mount an MS-DOS disk
`mrd`—Remove an MS-DOS subdirectory
`mmove`—Move or rename an MS-DOS file or subdirectory
`mren`—Rename an existing MS-DOS file
`mtype`—Display contents of an MS-DOS file
`mtest`—Test and display the configuration

DESCRIPTION

`mttools` is a public domain collection of programs to allow UNIX systems to read, write, and manipulate files on an MS-DOS filesystem (typically a floppy disk). Where reasonable, each program attempts to emulate the MS-DOS equivalent command. However, unnecessary restrictions and oddities of DOS are not emulated. For instance, it is possible to move subdirectories from one subdirectory to another.

MS-DOS filenames are optionally composed of a drive letter followed by a colon, a subdirectory, and a filename. Filenames without a drive letter refer to UNIX files. Subdirectory names can use either the `/` or `\` separator. The use of the `\` separator or wildcards will require the names to be enclosed in quotes to protect them from the shell. (Note: Wildcards in UNIX filenames should not be enclosed in quotes, because here users want the shell to expand them.)

DIFFERENCES WITH MS-DOS

The regular expression “pattern matching” routines follow the UNIX-style rules. For example, `*` matches all MS-DOS files in lieu of `*.*`. The archive, hidden, read-only, and system attribute bits are ignored during pattern matching.

All options use the `-` (minus) flag, not `/` as you’d expect in MS-DOS.

Most `mttools` commands allow multiple filename parameters, which doesn’t follow MS-DOS conventions, but which is more user friendly.

WORKING DIRECTORY

The `pwd` command is used to establish the device and the current working directory (relative to the MS-DOS filesystem); otherwise, the default is assumed to be `A:./`. However, unlike MS-DOS, there is only one working directory, and not one per drive.

VFAT-STYLE LONG FILENAMES

This version of `mttools` supports VFAT-style long filenames. If a UNIX filename is too long to fit in a short DOS name, it is stored as a VFAT long name, and a companion short name is generated. This short name is what you see when you examine the disk with a pre-7.0 version of DOS. The following table shows some examples of short names:

UNIX Name	MS-DOS Name	Reason for the Change
thisisatest	THISISAT	Filename too long
alain.knaff	ALAIN.KNA	Extension too long
prn.txt	XRN.TXT	PRN is a device name
.abc	X.ABC	Null filename
hot+cold	HOTXCOLD	Illegal character

The initial UNIX-style filename (whether long or short) is also called *primary* name, and the derived short name is also called *secondary* name.

Example:

```
mcop /etc/motd a:Reallylongname
```

`mttools` creates a VFAT entry for `Reallylongname`, and uses `REALLYLO` as a short name. `Reallylongname` is the primary name, and `REALLYLO` is the secondary name.

In this example:

```
copy /etc/motd a:motd
```

`motd` fits into the DOS filename limits. `mttools` doesn’t need to derivate another name. `motd` is the primary name, and there is no secondary name.

In a nutshell: The primary name is the long name, if one exists, or the short name if there is no long name.

NAME CLASHES

When writing a file to disk, its long name (primary name) or short name may collide with an already existing file or directory. This may happen for all commands that create new directory entries: `mcop`y, `mmd`, `mren`, `mmove`, `mwrite`, and `mread`.

When a name clash happens, `mttools` asks you what it should do. It offers several choices:

<code>overwrite</code>	Overwrites the existing file. It is not possible to overwrite a directory with a file.
<code>rename</code>	Renames the newly created file. <code>mttools</code> will prompt for the new filename.
<code>autorename</code>	Renames the newly created file. <code>mttools</code> will chose a name by itself, without prompting.
<code>skip</code>	Gives up on this file, and moves on to the next (if any).

To choose an option, type its first letter at the prompt. If you use a lowercase letter, the option applies for this file only; if you use an uppercase letter, the option applies to all files.

You may also choose options (for all files) on the command line when invoking `mttools`:

<code>-o</code>	Overwrites primary names by default
<code>-O</code>	Overwrites secondary names by default
<code>-r</code>	Renames primary name by default
<code>-R</code>	Renames secondary name by default
<code>-a</code>	Autorenames primary name by default
<code>-A</code>	Autorenames secondary name by default
<code>-s</code>	Skips primary name by default
<code>-S</code>	Skips secondary name by default
<code>-m</code>	Asks user what to do with primary name
<code>-M</code>	Asks user what to do with secondary name

By default, the user is prompted if the primary name clashes, and the secondary name is autorenamed.

If a name clash occurs in a UNIX directory, `mttools` only asks whether to overwrite the file or to skip it.

CASE SENSITIVITY OF THE VFAT FILESYSTEM

The VFAT filesystem is able to remember the case of the filenames. However, filenames that differ only in case are not allowed to coexist in the same directory. For example if you store a file called `LongFileName` on a VFAT filesystem, `mdir` will show this file as `LongFileName`, and not as `Longfilename`. However, if you then try to add `Longfilename` to the same directory, it will be refused, because case is ignored for clash checks.

The VFAT filesystem allows the storing of the case of a filename in the attribute byte, if all letters of the filename are the same case, and if all letters of the extension are the same case too. `mttools` uses this information when displaying the files, and also to generate the UNIX when `mcop`y to a UNIX directory. This may have unexpected results when applied to files written using a pre-7.0 version of DOS; indeed, these filenames map to all uppercase. This is different from the behavior of the old version of `mttools`, which used to generate lowercase UNIX filenames.

XDF DISKS (LINUX ONLY)

Xdf is a high-capacity format supported by OS/2. It can hold 1,840KB per disc. That's not very high compared to the best 2m formats, but its main advantage is that it is fast: 600 milliseconds per track. That's faster than the good old 21 sector format, and almost as fast as the standard 18 sector format. In order to access these disks, set the `use_xdf` variable for the drive. See `mttools(5)` for details on how to do this. Fast Xdf access is only available for kernels more recent than 1.1.34.

CAUTION

Attention distributors: If `mttools` is compiled on Linux, on a kernel more recent than 1.3.34, it won't run on an older kernel. However, if it has been compiled on an older kernel, it will still run on a newer kernel, except that Xdf access is

slower. It is recommended that distribution authors only include `mtools` binaries compiled on kernels older than 1.3.34 until 2.0 comes out. When 2.0 is out, `mtools` binaries compiled on newer kernels may (and should) be distributed. `mtools` binaries compiled on kernels older than 1.3.34 won't run on any kernel 2.1 or later.

EXIT CODES

All the `mtools` commands return 0 on success, 1 on utter failure, or 2 on partial failure. All the `mtools` commands perform a few sanity checks before going ahead, to make sure that the disk is indeed an MS-DOS disk (as opposed to, say, an ext2 or minix disk). These checks may reject partially corrupted disks, which might otherwise still be readable. To avoid these checks, set the `MTTOOLS_SKIP_CHECK` environmental variable.

SEE ALSO

`mattrib(1)`, `mbadblocks(1)`, `mcd(1)`, `mdel(1)`, `mformat(1)`, `mmove(1)`, `mrd(1)`, `mren(1)`, `mtype(1)`, `mcopy(1)`, `mdir(1)`, `mlabel(1)`, `mmd(1)`, `mmount(1)`

BUGS

An unfortunate side effect of not guessing the proper device (when multiple disk capacities are supported) is an occasional error message from the device driver. These can be safely ignored.

The fat checking code chokes on 1.72MB disks mformatted with pre-2.0.7 `mtools`. Set the environmental variable `MTTOOLS_FAT_COMPATIBILITY` to bypass the fat checking.

The support for non-Linux OS variants has not been tested for a long time. It may contain bugs, or even not work at all.

Local

mtvtoppm

`mtvtoppm`—Convert output from the MTV or PRT ray tracers into a portable pixmap

SYNOPSIS

`mtvtoppm [mtvfile]`

DESCRIPTION

`mtvtoppm` reads an input file from Mark Van De Wetering's MTV ray tracer and produces a portable pixmap as output.

The PRT ray tracer also produces this format.

SEE ALSO

`ppm(5)`

AUTHOR

Copyright © 1989 by Jef Poskanzer

2 February 1989

mtype

`mtype`—Display contents of an MS-DOS file

SYNOPSIS

`mtype [ -ts ] msdosfile [ msdosfiles... ]`

DESCRIPTION

`mtype` displays the specified MS-DOS file on the screen.

`mtype` will allow the following command-line options:

- `t` Text file viewing. `mtype` will translate incoming carriage return/line feeds to line feeds.
- `s` Strip high bit. `mtype` will strip the high bit from the data.

MS-DOS subdirectory names are supported with either the `/` or `\` separator. The use of the `\` separator or wildcards will require the names to be enclosed in quotes to protect them from the shell.

The `mcd` command may be used to establish the device and the current working directory (relative to MS-DOS); otherwise, the default is `A: /`.

`mtype` returns 0 on success, 1 on utter failure, or 2 on partial failure.

SEE ALSO

`mcd(1)`, `mread(1)`

BUGS

Allows multiple arguments, which does not follow the MS-DOS convention.

Local

mv

`mv`—Rename files

SYNOPSIS

```
mv [options] source dest
mv [options] source... directory
```

Options:

```
[-bfuiuv] [-S backup-suffix] [-V {numbered,existing,simple}] [--backup] [--force]
[--interactive] [--update] [--verbose] [--suffix=backup-suffix]
[--version-control={numbered,existing,simple}] [--help] [--version]
```

DESCRIPTION

This manual page documents the GNU version of `mv`. If the last argument names an existing directory, `mv` moves each other given file into a file with the same name in that directory. Otherwise, if only two files are given, it moves the first onto the second. It is an error if the last argument is not a directory and more than two files are given. It can move only regular files across filesystems. If a destination file is unwritable, the standard input is a tty, and the `-f` or `--force` option is not given, `mv` prompts the user for whether to overwrite the file. If the response does not begin with `y` or `Y`, the file is skipped.

OPTIONS

<code>-b, --backup</code>	Make backups of files that are about to be removed.
<code>-f, --force</code>	Remove existing destination files and never prompt the user.
<code>-i, --interactive</code>	Prompt whether to overwrite each destination file that already exists. If the response does not begin with <code>y</code> or <code>Y</code> , the file is skipped.
<code>-u, --update</code>	Do not move a nondirectory that has an existing destination with the same or newer modification time.
<code>-v, --verbose</code>	Print the name of each file before moving it.
<code>--help</code>	Print a usage message on standard output and exit successfully.
<code>--version</code>	Print version information on standard output, then exit successfully.

`-S, --suffix backup-suffix` The suffix used for making simple backup files can be set with the `SIMPLE_BACKUP_SUFFIX` environment variable, which can be overridden by this option. If neither of those is given, the default is `~`, as it is in Emacs.

`-V, --version-control {numbered,existing,simple}` The type of backups made can be set with the `VERSION_CONTROL` environment variable, which can be overridden by this option. If `VERSION_CONTROL` is not set and this option is not given, the default backup type is `existing`. The value of the `VERSION_CONTROL` environment variable and the argument to this option are like the GNU Emacs `version-control` variable; they also recognize synonyms that are more descriptive.

The valid values are the following (unique abbreviations are accepted):

- `t` or `numbered`--Always make numbered backups.
- `nil` or `existing`--Make numbered backups of files that already have them, simple backups of the others.
- `never` or `simple`—Always make simple backups.

GNU File Utilities

mwwrite

`mwwrite`—Low-level write (copy) a UNIX file to MS-DOS

SYNOPSIS

```
mwwrite [ -tnvmoOsSrRA ] unixfile msdosfile

mwwrite [ -tnvmoOsSrRA ] unixfile [ unixfiles... ] msdosdirectory
```

DESCRIPTION

This command is obsolete and only supplied for backward compatibility reasons with old scripts. Use `mcopy` instead.

SEE ALSO

`mcopy(1)`, `mtools(1)`

Local

namei

`namei`—Follow a pathname until a terminal point is found

SYNOPSIS

```
namei [-mx] pathname [ pathname ... ]
```

DESCRIPTION

`namei` uses its arguments as pathnames to any type of UNIX file (symlinks, files, directories, and so forth). `namei` then follows each pathname until a terminal point is found (a file, directory, char device, and so on). If it finds a symbolic link, the user shows the link, and starts following it, indenting the output to show the context.

This program is useful for finding too many levels of symbolic links problems.

For each line output, `namei` outputs the following characters to identify the file types found:

<code>f</code> :	The pathname the user is currently trying to resolve
<code>d</code>	Directory
<code>l</code>	Symbolic link (both the link and its contents are output)
<code>s</code>	Socket

b	Block device
c	Character device
-	Regular file
?	An error of some kind

`namei` prints an informative message when the maximum number of symbolic links this system can have has been exceeded.

OPTIONS

- x Show mount point directories with a `D` rather than a `d`.
- m Show the mode bits of each file type in the style of `ls(1)`, for example, `rwxr-xr-x`.

AUTHOR

Roger Southwick (rogers@amadeus.wr.tek.com)

BUGS

To be discovered

CAVEATS

`namei` will follow an infinite loop of symbolic links forever. To escape, use `SIGINT` (usually `^C`).

SEE ALSO

`ls(1)`, `stat(1)`

Local

newaliases

`newaliases`—Rebuild the database for the mail aliases file

SYNOPSIS

`newaliases`

DESCRIPTION

`newaliases` rebuilds the random access database for the mail aliases file. It must be run each time it is changed in order for the change to take effect.

SEE ALSO

`aliases(5)`, `sendmail(8)`

HISTORY

The `newaliases` command appeared in BSD 4.0.

BSD 4, 30 July 1991

newgrp

`newgrp`—Log in to a new group

SYNOPSIS

`newgrp [ group ]`

DESCRIPTION

`newgrp` changes the group identification of its caller, analogously to `login(1)`. The same person remains logged in, and the current directory is unchanged, but calculations of access permissions to files are performed with respect to the new group ID.

If no group is specified, the GID is changed to the login GID.

FILES

`/etc/group`
`/etc/passwd`

SEE ALSO

`login(1)`, `group(5)`

Linux 0.99, 9 October 1993

nl

`nl`—Number lines of files

SYNOPSIS

```
nl [-h header-style] [-b body-style] [-f footer-style] [-p] [-d cc]
[-v start-number] [-i increment] [-l lines] [-s line-separator]
[-w line-no-width] [-n {ln,rn,rz}] [--header-numbering=style]
[--body-numbering=style] [--footer-numbering=style]
[--first-page=number] [--page-increment=number] [--no-renumber]
[--join-blank-lines=number] [--number-separator=string]
[--number-width=number] [--number-format={ln,rn,rz}]
[--section-delimiter=cc] [--help] [--version] [file...]
```

DESCRIPTION

This manual page documents the GNU version of `nl`. `nl` copies each given file, or the standard input if none are given or when a file named `-` is given, to the standard output, with line numbers added to some or all of the lines.

`nl` considers its input to be composed of logical pages; by default, the line number is reset to 1 at the top of each logical page. `nl` treats all of the input files as a single document; it does not reset line numbers or logical pages between files.

A logical page consists of three sections: header, body, and footer. Any of the sections can be empty. Each can be numbered in a different style from the others.

The beginnings of the sections of logical pages are indicated in the input file by a line containing nothing except one of the following delimiter strings:

```
\:\:\: start of header
\:\: start of body
\: start of footer
```

The two characters from which these strings are made can be changed with an option (see the next subsection), but the pattern and length of each string cannot be changed.

The section delimiter strings are replaced by an empty line on output. Any text that comes before the first section delimiter string in the input file is considered to be part of a body section, so a file that does not contain any section delimiter strings is considered to consist of a single body section.

OPTIONS

```
-h, --header-numbering=style    See --footer-numbering.
-b, --body-numbering=style      See --footer-numbering.
```

<code>-f, --footer-numbering=style</code>	Select the numbering style for lines in the footer section of each logical page. When a line is not numbered, the current line number is not incremented, but the line number separator character is still prepended to the line. The styles are
<code>a</code>	Number all lines
<code>t</code>	Number only nonempty lines (default for body)
<code>n</code>	Number no lines (default for header and footer)
<code>pregexp</code>	Number only lines that contain a match for <code>regex</code>
<code>-p, --no-renumber</code>	Do not reset the line number at the start of a logical page.
<code>-v, --first-page=number</code>	Set the initial line number on each logical page to <code>number</code> (default 1).
<code>-i, --page-increment=number</code>	Increment line numbers by <code>number</code> (default 1).
<code>-l, --join-blank-lines=number</code>	Consider <code>number</code> (default 1) consecutive empty lines to be one logical line for numbering, and only number the last one. Where fewer than <code>number</code> consecutive empty lines occur, do not number them. An empty line is one that contains no characters, not even spaces or tabs.
<code>-s, --number-separator=string</code>	Separate the line number from the text line in the output with <code>string</code> (default is a tab character).
<code>-w, --number-width=number</code>	Use <code>number</code> characters for line numbers (default 6).
<code>-n, --number-format={ln,rn,rz}</code>	Select the line numbering format:
<code>ln</code>	Left justified, no leading zeros
<code>rn</code>	Right justified, no leading zeros (default)
<code>rz</code>	Right justified, leading zeros
<code>-d, --section-delimiter=cc</code>	Set the two delimiter characters that indicate the beginnings of logical page sections; if only one is given, the second remains <code>:. To enter \, use \\. </code>
<code>--help</code>	Print a usage message and exit with a nonzero status.
<code>--version</code>	Print version information on standard output, then exit.

GNU Text Utilities

n1mconv

n1mconv—Convert object code into an NLM

SYNOPSIS

```
n1mconv[ -Ibfdname|--input-target=bfdname] [ -Obfdname]
--output-target=bfdname ] [ -Theaderfile|--header-file=headerfile ]
[ -V|--version ][--help ] infile outfile
```

DESCRIPTION

n1mconv converts the relocatable object file `infile` into the NetWare Loadable Module (NLM) `outfile`, optionally reading `headerfile` for NLM header information. For instructions on writing the NLM command file language used in header files, see *The NetWare Tool Maker Specification Manual*, available from Novell, Inc. n1mconv currently works with i386 object files in COFF, ELF, or a.out format, and with SPARC object files in ELF or a.out format. n1mconv uses the GNU binary file descriptor library to read `infile`.

OPTIONS

<code>-I bfdname,</code> <code>--input-target=bfdname</code>	Consider the source file's object format to be <code>bfdname</code> , rather than attempting to deduce it.
<code>-O bfdname,</code> <code>--output-target=bfdname</code>	Write the output file using the object format <code>bfdname</code> . n1mconv infers the output format based on the input format, for example, for an i386 input file the output format is <code>n1m32-i386</code> .

-T headerfile,	Reads headerfile for NLM header information. For instructions on writing the NLM command file language used in header files, see <i>The NetWare Tool Maker Specification Manual</i> , available from Novell, Inc.
--header-file=headerfile	
-V, --version	Show the version number of nlmconv and exit.
-h, --help	Show a summary of the options to nlmconv and exit.

SEE ALSO

binutils entry in info; *The GNU Binary Utilities*, Roland H. Pesch (June 1993).

COPYING

Copyright © 1993 Free Software Foundation, Inc. Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

Cygnus support, June 1993

nm

nm—List symbols from object files

SYNOPSIS

```
nm [ -a|--debug-syms ][ -g|--extern-only ][ -B ][ -C|--demangle ]
    [ -D|--dynamic ][ -s|--print-arnmap ][ -o|--print-file-name ]
    [ -n|--numeric-sort ][ -p|--no-sort ][ -r|--reverse-sort ][ --size-sort ]
    [ -u|--undefined-only ][ --help ][ --version ][ -t radix|--radix=radix ]
    [ -P|--portability ] [ -f format|--format=format ][ --target=bfdname ][ objfile ... ]
```

DESCRIPTION

GNU nm lists the symbols from object files *objfile*. If no object files are given as arguments, nm assumes *a.out*.

OPTIONS

The long and short forms of options, shown here as alternatives, are equivalent.

-A, -o	
--print-file-name	Precede each symbol by the name of the input file where it was found, rather than identifying the input file once only before all of its symbols.
-a, --debug-syms	Display debugger-only symbols; normally these are not listed.
-B	The same as --format=bsd (for compatibility with the MIPS nm).
-C, --demangle	Decode (demangle) low-level symbol names into user-level names. Besides removing any initial underscore prepended by the system, this makes C++ function names readable.
-D, --dynamic	Display the dynamic symbols rather than the normal symbols. This is only meaningful for dynamic objects, such as certain types of shared libraries.
-f format	Use the output format <i>format</i> , which can be <i>bsd</i> , <i>sysv</i> , or <i>posix</i> . The default is <i>bsd</i> . Only the first character of <i>format</i> is significant; it can be either uppercase or lowercase.
-g, --extern-only	Display only external symbols.
-n, -v, --numeric-sort	Sort symbols numerically by their addresses, not alphabetically by their names.

<code>-p, --no-sort</code>	Don't bother to sort the symbols in any order; just print them in the order encountered.
<code>-P, --portability</code>	Use the POSIX.2 standard output format instead of the default format. Equivalent to <code>-f posix</code> .
<code>-s, --print-armap</code>	When listing symbols from archive members, include the index, a mapping (stored in the archive by <code>ar</code> or <code>ranlib</code>) of which modules contain definitions for what names.
<code>-r, --reverse-sort</code>	Reverse the sense of the sort (whether numeric or alphabetic); let the last come first.
<code>--size-sort</code>	Sort symbols by size. The size is computed as the difference between the value of the symbol and the value of the symbol with the next higher value. The size of the symbol is printed, rather than the value.
<code>-t radix, --radix=radix</code>	Use <code>radix</code> as the radix for printing the symbol values. It must be <code>d</code> for decimal, <code>o</code> for octal, or <code>x</code> for hexadecimal.
<code>--target=bfdname</code>	Specify an object code format other than your system's default format. See <code>objdump(1)</code> for information on listing available formats.
<code>-u, --undefined-only</code>	Display only undefined symbols (those external to each object file).
<code>-V, --version</code>	Show the version number of <code>nm</code> and exit.
<code>--help</code>	Show a summary of the options to <code>nm</code> and exit.

SEE ALSO

`binutils` entry in `info`; *The GNU Binary Utilities*, Roland H. Pesch (October 1991); `ar(1)`, `objdump(1)`, `ranlib(1)`.

COPYING

Copyright © 1991 Free Software Foundation, Inc. Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

Cygnus support, 5 November 1991

nntpget

`nntpget`—Get Usenet articles from a remote NNTP server

SYNOPSIS

```
nntpget [ -d dist ] [-f file ] [-n newsgroups ] [-t timestring ] [-o ] [-u file ] [-v ] host
```

DESCRIPTION

`nntpget` connects to the NNTP server at the specified `host` and retrieves articles from it. The articles are sent to standard output.

The `-o` flag may be used only if the command is executed on the host where the `innd(8)` server is running. If this flag is used, `nntpget` connects to the specified remote host to retrieve articles. Any article not present in the local history database is then fetched from the remote site and offered to the local server.

If the `-v` flag is used with the `-o` flag, then the Message-ID of each article will be sent to standard output as it is processed.

The list of article Message-IDs is normally read from standard input. If the `-f` flag is used, then a `newnews` command is used to retrieve all articles newer than the modification date of the specified `file`. The `-u` flag is the same except that if the transfer succeeded, the file will be updated with a statistics line, modifying its timestamp so that it can be used in later invocations. If the `-t` flag is used, then the specified `timestring` is used as the time and date parameter to the `newnews` command.

If either the `-t` or `-f` flags are used, then the `-n` flag may be used to specify a newsgroup list and the `-d` flag may be used to specify a distribution list. The default is `*` for all newsgroups, and no distribution list.

BUGS

Truncates articles at 512 lines.

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for *InterNetNews*.

SEE ALSO

innd(8)

objcopy

objcopy—Copy and translate object files

SYNOPSIS

```
objcopy [ -Ibfdname|--target=bfdname ]
[ -Ibfdname|--input-target=bfdname ] [ -Obfdname
--output-target=bfdname ] [ -Rsectionname
--remove-section=sectionname ] [ -S|--strip-all ][-g
--strip-debug ][-x|--discard-all ][-X
--discard-locals][--bbyte|--byte=byte ] [ -iinterleave
--interleave=interleave ] [ -v|--verbose][--V
--version ][--help ] infile [ outfile ]
```

DESCRIPTION

The GNU `objcopy` utility copies the contents of an object file to another. `objcopy` uses the GNU BFD library to read and write the object files. It can write the destination object file in a format different from that of the source object file. The exact behavior of `objcopy` is controlled by command-line options.

`objcopy` creates temporary files to do its translations and deletes them afterward. `objcopy` uses BFD to do all its translation work; it knows about all the formats BFD knows about, and thus is able to recognize most formats without being told explicitly.

`infile` and `outfile` are the source and output files, respectively. If you do not specify `outfile`, `objcopy` creates a temporary file and destructively renames the result with the name of the input file.

OPTIONS

<code>-I bfdname,</code> <code>--input-target=bfdname</code>	Consider the source file's object format to be <code>bfdname</code> , rather than attempting to deduce it.
<code>-O bfdname,</code> <code>--output-target=bfdname</code>	Write the output file using the object format <code>bfdname</code> .
<code>-F bfdname,</code> <code>--target=bfdname</code>	Use <code>bfdname</code> as the object format for both the input and the output file; that is, simply transfer data from source to destination with no translation.
<code>-R sectionname,</code> <code>--remove-section=sectionname</code>	Remove the named section from the file. This option may be given more than once. Note that using this option inappropriately may make the output file unusable.
<code>-S, --strip-all</code>	Do not copy relocation and symbol information from the source file.
<code>-g, --strip-debug</code>	Do not copy debugging symbols from the source file.
<code>-x, --discard-all</code>	Do not copy nonglobal symbols from the source file.
<code>-X, --discard-locals</code>	Do not copy compiler-generated local symbols. (These usually start with <code>_L</code> or <code>._</code>).

<code>-b byte, --byte=byte</code>	Keep only every <code>byte</code> byte of the input file (header data is not affected). <code>byte</code> can be in the range from 0 to the <code>interleave-1</code> . This option is useful for creating files to program ROMs. It is typically used with an <code>srec</code> output target.
<code>-i interleave, --interleave=interleave</code>	Only copy one out of every <code>interleave</code> bytes. The one to copy is selected by the <code>-b</code> or <code>--byte</code> option. The default is 4. The <code>interleave</code> is ignored if neither <code>-b</code> nor <code>--byte</code> is given.
<code>-v, --verbose</code>	Verbose output: list all object files modified. In the case of archives, <code>objcopy -v</code> lists all members of the archive.
<code>-V, --version</code>	Show the version number of <code>objcopy</code> and exit.
<code>--help</code>	Show a summary of the options to <code>objcopy</code> and exit.

SEE ALSO

`binutils` entry in `info`; *The GNU Binary Utilities*, Roland H. Pesch (June 1993).

COPYING

Copyright © 1993 Free Software Foundation, Inc. Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

Cygnus support, June 1993

objdump

`objdump`—Display information from object files.

SYNOPSIS

```
objdump [ -a|--archive-headers ][-b\ bfdname | --target= bfdname ]
[ -d|--disassemble ][-D|--disassemble-all ][-f|--file-headers ]
[ -h|--section-headers | --headers ][-i|--info ][-j\ section
| --section= section ][-l|--line-numbers ][-m\ machine | --
architecture= machine ][-r|--reloc ][-R|--dynamic-reloc ]
[ -s|--full-contents ][--stabs ][-t|--syms ][-T|--dynamic-
syms][--x|--all-headers ][--version ][--help ] objfile ...
```

DESCRIPTION

`objdump` displays information about one or more object files. The options control what particular information to display. This information is mostly useful to programmers who are working on the compilation tools, as opposed to programmers who just want their program to compile and work.

`objfile...` are the object files to be examined. When you specify archives, `objdump` shows information on each of the member object files.

OPTIONS

Where long and short forms of an option are shown together, they are equivalent. At least one option besides `-l` (`--line-numbers`) must be given.

<code>-a, --archive-headers</code>	If any files from <code>objfile</code> are archives, display the archive header information (in a format similar to <code>ls -l</code>). Besides the information you could list with <code>ar tv</code> , <code>objdump -a</code> shows the object file format of each archive member.

<code>-b bfdname,</code> <code>--target=bfdname</code>	Specify the object-code format for the object files to be <code>bfdname</code> . This may not be necessary; <code>objdump</code> can automatically recognize many formats. For example, <code>objdump -b oasys -m vax -h fu.o</code> displays summary information from the section headers (<code>-h</code>) of <code>fu.o</code> , which is explicitly identified (<code>-m</code>) as a Vax object file in the format produced by Oasys compilers. You can list the formats available with the <code>-i</code> option.
<code>-d, --disassemble</code>	Display the assembler mnemonics for the machine instructions from <code>objfile</code> . This option only disassembles those sections that are expected to contain instructions.
<code>-D, --disassemble-all</code>	Like <code>-d</code> , but disassemble the contents of all sections, not just those expected to contain instructions.
<code>-f, --file-headers</code>	Display summary information from the overall header of each file in <code>objfile</code> .
<code>-h, --section-headers,</code> <code>--headers</code>	Display summary information from the section headers of the object file.
<code>--help</code>	Print a summary of the options to <code>objdump</code> and exit.
<code>-i, --info</code>	Display a list showing all architectures and object formats available for specification with <code>-b</code> or <code>-m</code> .
<code>-j name, --section=name</code>	Display information only for section <code>name</code> .
<code>-l, --line-numbers</code>	Label the display (using debugging information) with the filename and source line numbers corresponding to the object code shown. Only useful with <code>-d</code> or <code>-D</code> .
<code>-m machine,</code> <code>--architecture=machine</code>	Specify the object files <code>objfile</code> are for architecture <code>machine</code> . You can list available architectures using the <code>-i</code> option.
<code>-r, --reloc</code>	Print the relocation entries of the file. If used with <code>-d</code> or <code>-D</code> , the relocations are printed interspersed with the disassembly.
<code>-R, --dynamic-reloc</code>	Print the dynamic relocation entries of the file. This is only meaningful for dynamic objects, such as certain types of shared libraries.
<code>-s, --full-contents</code>	Display the full contents of any sections requested.
<code>--stabs</code>	Display the contents of the <code>.stab</code> , <code>.stab.index</code> , and <code>.stab.excl</code> sections from an ELF file. This is only useful on systems (such as Solaris 2.0) in which <code>.stab</code> debugging symbol-table entries are carried in an ELF section. In most other file formats, debugging symbol-table entries are interleaved with linkage symbols, and are visible in the <code>--syms</code> output.
<code>-t, --syms</code>	Symbol table. Print the symbol table entries of the file. This is similar to the information provided by the <code>nm</code> program.
<code>-T, --dynamic-syms</code>	Dynamic symbol table. Print the dynamic symbol table entries of the file. This is only meaningful for dynamic objects, such as certain types of shared libraries. This is similar to the information provided by the <code>nm</code> program when given the <code>-D</code> (<code>--dynamic</code>) option.
<code>--version</code>	Print the version number of <code>objdump</code> and exit.
<code>-x, --all-headers</code>	Display all available header information, including the symbol table and relocation entries. Using <code>-x</code> is equivalent to specifying all of <code>-a -f -h -r -t</code> .

SEE ALSO

`binutils` entry in `info`; *The GNU Binary Utilities*, Roland H. Pesch (October 1991); `nm(1)`.

COPYING

Copyright © 1991 Free Software Foundation, Inc. Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

oclock

oclock—Round X clock

SYNOPSIS

oclock [-option ...]

DESCRIPTION

oclock simply displays the current time on an analog display.

OPTIONS

-fg color	Choose a different color for both hands and the jewel on the clock
-bg color	Choose a different color for the background.
-jewel color	Choose a different color for the jewel on the clock.
-minute color	Choose a different color for the minute hand of the clock.
-hour color	Choose a different color for the hour hand of the clock.
-backing { WhenMapped Always NotUseful }	Select an appropriate level of backing store.
-geometry geometry	Define the initial window geometry; see x(1).
-display display	Specify the display to use; see x(1).
-bd color	Choose a different color for the window border.
-bw width	Choose a different width for the window border. As the Clock widget changes its border around quite a bit, this is most usefully set to zero.
-shape	Cause the clock to use the Shape extension to create an oval window. This is the default unless the shapeWindow resource is set to false.
-noshape	Cause the clock to not reshape itself and ancestors to exactly fit the outline of the clock.
-transparent	Cause the clock to consist only of the jewel, the hands, and the border.

COLORS

If you would like your clock to be viewable in color, include the following in the `#ifdef COLOR` section you read with `xrdb`:

```
*customization: -color
```

This will cause oclock to pick up the colors in the app-defaults color customization file: `<XRoot>/lib/X11/app-defaults/Clock-color`. The default colors are

Clock*Background	Gray
Clock*BorderColor	Light blue
Clock*hour	Yellow
Clock*jewel	Yellow
Clock*minute	Yellow

SEE ALSO

x(1), X Toolkit documentation

AUTHOR

Keith Packard, MIT X Consortium

od

od—Dump files in octal and other formats

SYNOPSIS

```
od [-abcdfhiloxv] [-s[bytes]] [-w[bytes]] [-A radix] [-j bytes] [-N bytes]
[-t type] [--skip-bytes=bytes] [--address-radix=radix] [--read-bytes=bytes]
[--format=type] [--output-duplicates] [--strings[=bytes]] [--width[=bytes]]
[--traditional] [--help] [--version] [file...]
```

DESCRIPTION

This manual page documents the GNU version of `od`. `od` writes to the standard output the contents of the given files, or of the standard input if the name `-` is given. Each line of the output consists of the offset in the input file in the leftmost column of each line, followed by one or more columns of data from the file, in a format controlled by the options. By default, `od` prints the file offsets in octal and the file data as two-byte octal numbers.

OPTIONS

<code>-A, --address-radix=radix</code>	Select the base in which file offsets are printed. <code>radix</code> can be one of the following: <code>d</code> Decimal <code>o</code> Octal <code>x</code> Hexadecimal <code>n</code> None (do not print offsets) The default is octal.
<code>-j, --skip-bytes=bytes</code>	Skip <code>bytes</code> input bytes before formatting and writing. If <code>bytes</code> begins with <code>0x</code> or <code>0X</code> , it is interpreted in hexadecimal; otherwise, if it begins with <code>0</code> , in octal; otherwise, in decimal. Appending <code>b</code> multiplies it by 512, <code>k</code> by 1024, and <code>m</code> by 1048576.
<code>-N, --read-bytes=bytes</code>	Only output up to <code>bytes</code> bytes of each input file. Any prefixes and suffixes on bytes are interpreted as for the <code>-j</code> option.
<code>-t, --format=type</code>	Select the format in which to output the file data. <code>type</code> is a string of one or more of the following type indicator characters. If you include more than one type indicator character in a single <code>type</code> string or use this option more than once, <code>od</code> writes one copy of each output line using each of the data types that you specified, in the order that you specified. <code>a</code> Named character <code>c</code> ASCII character or backslash escape <code>d</code> Signed decimal <code>f</code> Floating point <code>o</code> Octal <code>u</code> Unsigned decimal <code>x</code> Hexadecimal Except for types <code>a</code> and <code>c</code> , you can specify the number of bytes to use in interpreting each number in the given data type by following the type indicator character with a decimal integer. Alternately, you can specify the size of one of the C compiler's built-in data types by following the type indicator character with one of the following characters. For integers (<code>d</code> , <code>o</code> , <code>u</code> , <code>x</code>): <code>c</code> char <code>s</code> short <code>i</code> int <code>l</code> long

	For floating point (f):
	F float
	D double
	L long double
-v, --output-duplicates	Output consecutive lines that are identical. By default, when two or more consecutive output lines would be equal, <code>od</code> outputs only the first line, and puts just an asterisk on the following line to indicate that identical lines have been elided.
-s, --strings[=bytes]	Instead of the normal output, output only string constants in the input, which are a run of at least <code>bytes</code> ASCII graphic (or formatting) characters, terminated by a NUL. If <code>bytes</code> is omitted, it defaults to 3.
-w, --width[=bytes]	The number of input bytes to format per output line. It must be a multiple of the least common multiple of the sizes associated with the specified output types. If <code>bytes</code> is omitted, it defaults to 32. If this option is not given, it defaults to 16.
--help	Print a usage message and exit with a nonzero status.
--version	Print version information on standard output, then exit.

The next several options map the old, pre-POSIX format specification options to the corresponding POSIX format specs. GNU `od` accepts any combination of old- and new-style options. Format specification options accumulate.

-a	Output as named characters. Equivalent to <code>-t a</code> .
-b	Output as octal bytes. Equivalent to <code>-t oC</code> .
-c	Output as ASCII characters or backslash escapes. Equivalent to <code>-t c</code> .
-d	Output as unsigned decimal shorts. Equivalent to <code>-t u2</code> .
-f	Output as floats. Equivalent to <code>-t fF</code> .
-h	Output as hexadecimal shorts. Equivalent to <code>-t x2</code> .
-i	Output as decimal shorts. Equivalent to <code>-t d2</code> .
-l	Output as decimal longs. Equivalent to <code>-t d4</code> .
-o	Output as octal shorts. Equivalent to <code>-t o2</code> .
-x	Output as hexadecimal shorts. Equivalent to <code>-t x2</code> .
--traditional	Recognize the pre-POSIX nooption arguments that some older versions of <code>od</code> accepted. The following syntax:

```
od --traditional [ file ] [[+]offset[.][b]] [[+]label[.][b]]
```

can be used to specify at most one file and optional arguments specifying an offset and a pseudo-start address, `label`. By default, `offset` is interpreted as an octal number specifying how many input bytes to skip before formatting and writing. The optional trailing decimal point forces the interpretation of `offset` as a decimal number. If no decimal is specified and the offset begins with `0x` or `0X`, it is interpreted as a hexadecimal number. If there is a trailing `b`, the number of bytes skipped will be `offset` multiplied by 512. The `label` argument is interpreted just like `offset`, but it specifies an initial pseudo-address. The pseudo addresses are displayed in parentheses following any normal address.

GNU Text Utilities

passwd

passwd—Change password

SYNOPSIS

```
passwd [ name ]
```

DESCRIPTION

`passwd` changes the specified user's password. Only the superuser is allowed to change other users' passwords. If the user is not root, then the old password is prompted for and verified.

A new password is prompted for twice, to avoid typing mistakes. Unless the user is the superuser, the new password must have more than six characters, and must have either both uppercase and lowercase letters, or nonletters. Some passwords that are similar to the user's name are not allowed.

FILES

`/etc/passwd`
`/etc/shells`

SEE ALSO

`chsh(1)`, `chfn(1)`

BUGS

A password consisting of all digits is allowed.

No warnings are printed if the superuser chooses a poor password.

The `-f` and `-s` options are not supported.

AUTHOR

Peter Orbaek (poe@daimi.aau.dk)

Linux 1.0, 22 June 1994

paste

`paste`—Merge lines of files

SYNOPSIS

```
paste [-s] [-d delim-list] [--serial] [--delimiters=delim-list] [--help]
      [--version] [file...]
```

DESCRIPTION

This manual page documents the GNU version of `paste`. `paste` prints lines consisting of sequentially corresponding lines of each given file, separated by tabs, terminated by a newline. If no files are given, the standard input is used. A filename of `-` means standard input.

OPTIONS

<code>-s, --serial</code>	Paste the lines of one file at a time rather than one line from each file.
<code>-d, --delimiters delim-list</code>	Consecutively use the characters in <code>delim-list</code> instead of <code>TAB</code> to separate merged lines. When <code>delim-list</code> is exhausted, start again at its beginning.
<code>--help</code>	Print a usage message and exit with a nonzero status.
<code>--version</code>	Print version information on standard output, then exit.

GNU Text Utilities

pbmclean

pbmclean—Flip isolated pixels in portable bitmap

SYNOPSIS

```
pbmclean [-connect] [pbmfile]
```

DESCRIPTION

pbmclean reads a portable bitmap as input and outputs a portable bitmap with every pixel that has less than connect identical neighbors inverted. pbmclean can be used to clean up “snow” on bitmap images.

SEE ALSO

pbm(5)

AUTHOR

Copyright © 1990 by Angus Duggan. Copyright © 1989 by Jef Poskanzer.

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, provided that the above copyright notice appear in all copies and that both that copyright notice and this permission notice appear in supporting documentation. This software is provided “as is” without express or implied warranty.

pbmfilters

pbmfilters—List of all programs in the PBMPlus package

DESCRIPTION

anytopnm	Attempt to convert an unknown type of image file to a portable anymap
asciitopgm	Convert ASCII graphics into a portable graymap
atktopbm	Convert Andrew Toolkit raster object to a portable bitmap
bioradtopgm	Convert a Biorad confocal file into a portable graymap
bmptoppm	Convert a BMP file into a portable pixmap
brushtopbm	Convert a doodle brush file into a portable bitmap
cmuwmtopbm	Convert a CMU window manager bitmap into a portable bitmap
fitstopnm	Convert a FITS file into a portable anymap
fstopgm	Convert a Usenix FaceSaver file into a portable graymap
g3topbm	Convert a Group 3 fax file into a portable bitmap
gemptopbm	Convert a GEM IMG file into a portable bitmap
giftopnm	Convert a GIF file into a portable anymap
gouldtoppm	Convert Gould scanner file into a portable pixmap
hipstopgm	Convert a HIPS file into a portable graymap
hpcdtoppm	Convert a Photo-CD file into a portable pixmap
icontopbm	Convert a Sun icon into a portable bitmap
ilbmtoppm	Convert an ILBM file into a portable pixmap
imgtoppm	Convert an IMG-whatnot file into a portable pixmap
lispmtopgm	Convert a Lisp machine bitmap file into PGM format
macptopbm	Convert a MacPaint file into a portable bitmap
mgrtopbm	Convert an MGR bitmap into a portable bitmap
mtvtoppm	Convert output from the MTV or PRT ray tracers into a portable pixmap

<code>pbmclean</code>	Flip isolated pixels in portable bitmap
<code>pbm1ife</code>	Apply Conway's Rules of Life to a portable bitmap
<code>pbmmake</code>	Create a blank bitmap of a specified size
<code>pbmmask</code>	Create a mask bitmap from a regular bitmap
<code>pbmyscale</code>	Enlarge a portable bitmap with edge smoothing
<code>pbmreduce</code>	Read a portable bitmap and reduce it N times
<code>pbmtext</code>	Render text into a bitmap
<code>pbmto10x</code>	Convert a portable bitmap into Gemini 10X printer graphics
<code>pbmto4425</code>	Display PBM images on an AT&T 4425 terminal
<code>pbmtoascii</code>	Convert a portable bitmap into ASCII graphics
<code>pbmtoatk</code>	Convert a portable bitmap to Andrew Toolkit raster object
<code>pbmtobg</code>	Convert a portable bitmap into BitGraph graphics
<code>pbmtocmuwm</code>	Convert a portable bitmap into a CMU window manager bitmap
<code>pbmtoepsi</code>	Convert a portable bitmap into an encapsulated PostScript
<code>pbmtoepson</code>	Convert a portable bitmap into Epson printer graphics
<code>pbmto3</code>	Convert a portable bitmap into a Group 3 fax file
<code>pbmto3gem</code>	Convert a portable bitmap into a GEM IMG file
<code>pbmto3go</code>	Convert a portable bitmap into compressed GraphOn graphics
<code>pbmtoicon</code>	Convert a portable bitmap into a Sun icon
<code>pbmto1j</code>	Convert a portable bitmap into HP LaserJet format
<code>pbmto1n03</code>	Convert portable bitmap to DEC LN03+ Sixel output
<code>pbmto1ps</code>	Convert portable bitmap to PostScript
<code>pbmto3macp</code>	Convert a portable bitmap into a MacPaint file
<code>pbmto3mgr</code>	Convert a portable bitmap into an MGR bitmap
<code>pbmto3pgm</code>	Convert a portable bitmap to portable graymap by averaging areas
<code>pbmto3pi3</code>	Convert a portable bitmap into an Atari Degas .pi3 file
<code>pbmto3pk</code>	Convert a portable bitmap into a packed (PK) format font
<code>pbmto3plot</code>	Convert a portable bitmap into a UNIX <code>plot(5)</code> file
<code>pbmto3ptx</code>	Convert a portable bitmap into Printronix printer graphics
<code>pbmto3x10bm</code>	Convert a portable bitmap into an X10 bitmap
<code>pbmto3xbm</code>	Convert a portable bitmap into an X11 bitmap
<code>pbmto3zinc</code>	Convert a portable bitmap into a Zinc bitmap
<code>pbmupc</code>	Create a Universal Product Code bitmap
<code>pcxto3ppm</code>	Convert a PCX file into a portable pixmap
<code>pgmbentley</code>	Bentleyize a portable graymap
<code>p3mcrater</code>	Create cratered terrain by fractal forgery
<code>p3medge</code>	Edge-detect a portable graymap
<code>p3menhance</code>	Edge-enhance a portable graymap
<code>p3mhist</code>	Print a histogram of the values in a portable graymap
<code>p3mkernel</code>	Generate a convolution kernel
<code>p3mnoise</code>	Create a graymap made up of white noise
<code>p3mnorm</code>	Normalize the contrast in a portable graymap
<code>p3moil</code>	Turn a portable graymap into an oil painting
<code>p3mramp</code>	Generate a grayscale ramp
<code>p3mtexture</code>	Calculate textural features on a portable graymap
<code>p3mtofs</code>	Convert a portable graymap to Usenix FaceSaver format

<code>pgmtolisp</code>	Convert a portable graymap into Lisp machine format
<code>pgmtopbm</code>	Convert a portable graymap into a portable bitmap
<code>pgmtoppm</code>	Colorize a portable graymap into a portable pixmap
<code>pgmtoypbm</code>	Convert a portable bitmap into a Bennet Yee “face” file
<code>pi1toppm</code>	Convert an Atari Degas PI1 into a portable pixmap
<code>pi3topbm</code>	Convert an Atari Degas PI3 file into a portable bitmap
<code>picttoppm</code>	Convert a Macintosh PICT file into a portable pixmap
<code>pjtoppm</code>	Convert an HP PaintJet file into a portable pixmap
<code>pktopbm</code>	Convert packed (PK) format font into portable bitmap(s)
<code>pnmalias</code>	Antialias a portable anymap
<code>pnmarith</code>	Perform arithmetic on two portable anymaps
<code>pnmcats</code>	Concatenate portable anymaps
<code>pnmcomp</code>	Composite two portable anymap files together
<code>pnmconvol</code>	General $M \times N$ convolution on a portable anymap
<code>pnmcrop</code>	Crop a portable anymap
<code>pnmcut</code>	Cut a rectangle out of a portable anymap
<code>pnmdepth</code>	Change the <code>maxval</code> in a portable anymap
<code>pnmenlarge</code>	Read a portable anymap and enlarge it N times
<code>pnmfile</code>	Describe a portable anymap
<code>pnmflip</code>	Perform one or more flip operations on a portable anymap
<code>pnmgamma</code>	Perform gamma correction on a portable anymap
<code>pnmhistmap</code>	Draw a histogram for a PGM or PPM file
<code>pnmindex</code>	Build a visual index of a bunch of anymaps
<code>pnminvert</code>	Invert a portable anymap
<code>pnmmargin</code>	Add a border to a portable anymap
<code>pnmnlfilt</code>	Nonlinear filters: smooth, alpha trim mean, optimal
<code>pnmnoraw</code>	Force a portable anymap into plain format
<code>pnmpad</code>	Add borders to portable anymap
<code>pnmpaste</code>	Paste a rectangle into a portable anymap
<code>pnmrotate</code>	Rotate a portable anymap by some angle
<code>pnmscale</code>	Scale a portable anymap
<code>pnmshear</code>	Shear a portable anymap by some angle
<code>pnmsmooth</code>	Smooth out an image
<code>pnmtile</code>	Replicate a portable anymap into a specified size
<code>pnmtoddif</code>	Convert a portable anymap to DDIF format
<code>pnmtofits</code>	Convert a portable anymap into FITS format
<code>pnmtops</code>	Convert portable anymap to PostScript
<code>pnmtorast</code>	Convert a portable pixmap into a Sun raster file
<code>pnmtosgi</code>	Convert a portable anymap to an SGI image file
<code>pnmtosir</code>	Convert a portable anymap into a Solitaire format
<code>pnmtotiff</code>	Convert a portable anymap into a TIFF file
<code>pnmtowxd</code>	Convert a portable anymap into an X11 window dump
<code>ppm3d</code>	Convert two portable pixmap into a red/blue 3D glasses pixmap
<code>ppmbrighten</code>	Change an images Saturation and Value from an HSV map
<code>ppmchange</code>	Change all pixels of one color to another in a portable pixmap
<code>ppmdim</code>	Dim a portable pixmap down to total blackness

ppmdist	Simplistic grayscale assignment for machine generated, color images
ppmdither	Ordered dither for color images
ppmflash	Brighten a picture up to complete white-out
ppmforge	Fractal forgeries of clouds, planets, and starry skies
ppmhist	Print a histogram of a portable pixmap
ppmmake	Create a pixmap of a specified size and color
ppmmix	Blend together two portable pixmaps
ppmnorm	Normalize the contrast in a portable pixmap
ppmntsc	Make a portable pixmap look like it was taken from an American TV show
ppmpat	Make a pretty pixmap
ppmquant	Quantize the colors in a portable pixmap down to a specified number
ppmquantall	Run ppmquant on a bunch of files all at once, so they share a common colormap
ppmqvga	8-plane quantization
ppmrelief	Run a Laplacian relief filter on a portable pixmap
ppmshift	Shift lines of a portable pixmap left or right by a random amount
ppmspread	Displace a portable pixmap's pixels by a random amount
ppmtoacad	Convert portable pixmap to AutoCAD database or slide
ppmtobmp	Convert a portable pixmap into a BMP file
ppmtogif	Convert a portable pixmap into a GIF file
ppmtoicr	Convert a portable pixmap into NCSA ICR format
ppmtoilbm	Convert a portable pixmap into an ILBM file
ppmtomap	Extract all colors from a portable pixmap
ppmtomitsu	Convert a portable pixmap to a Mitsubishi S340-10 file
ppmtopcx	Convert a portable pixmap into a PCX file
ppmtopgm	Convert a portable pixmap into a portable graymap
ppmtopi1	Convert a portable pixmap into an Atari Degas PI1 file
ppmtopict	Convert a portable pixmap into a Macintosh PICT file
ppmtopj	Convert a portable pixmap to an HP PaintJet file
ppmtopjxl	Convert a portable pixmap into an HP PaintJet XL PCL file
ppmtopuzz	Convert a portable pixmap into an X11 "puzzle" file
ppmtorgb3	Separate a portable pixmap into three portable graymaps
ppmtosixel	Convert a portable pixmap into DEC sixel format
ppmtotga	Convert portable pixmap into a TrueVision Targa file
ppmtouil	Convert a portable pixmap into a Motif UIL icon file
ppmtoxpm	Convert a portable pixmap into an X11 pixmap
ppmtoyuv	Convert a portable pixmap into an Abekas YUV file
ppmtoyuvsplit	Convert a portable pixmap into three subsampled raw YUV files
psidtopgm	Convert PostScript "image" data into a portable graymap
pstopnm	Convert a PostScript file into a portable anymap
qrttpgm	Convert output from the QRT ray tracer into a portable pixmap
rasttopnm	Convert a Sun raster file into a portable anymap
rawtopgm	Convert raw grayscale bytes into a portable graymap
rawtoppm	Convert raw RGB bytes into a portable pixmap
rgb3toppm	Combine three portable graymaps into one portable pixmap
sgitopnm	Convert an SGI image file into a portable anymap
sirtopnm	Convert a Solitaire file into a portable anymap

<code>sldtoppm</code>	Convert an AutoCAD slide file into a portable pixmap
<code>spctoppm</code>	Convert an Atari compressed Spectrum file into a portable pixmap
<code>spottopgm</code>	Convert SPOT satellite images to Portable Graymap format
<code>sputoppm</code>	Convert an Atari uncompressed Spectrum file into a portable pixmap
<code>tgatoppm</code>	Convert TrueVision Targa file into a portable pixmap
<code>tifftopnm</code>	Convert a TIFF file into a portable anymap
<code>xbmtopbm</code>	Convert an X11 or X10 bitmap into a portable bitmap
<code>ximtoppm</code>	Convert an XIM file into a portable pixmap
<code>xpmtoppm</code>	Convert an X11 pixmap into a portable pixmap
<code>xvminitoppm</code>	Convert an XV thumbnail picture to PPM
<code>xwdtopnm</code>	Convert an X11 or X10 window dump file into a portable anymap
<code>ybmtopbm</code>	Convert a Bennet Yee “face” file into a portable bitmap
<code>yuvplittoppm</code>	Convert a Y-, U- and V-file into a portable pixmap
<code>yuvtoppm</code>	Convert Abekas YUV bytes into a portable pixmap
<code>zeisstopnm</code>	Convert a Zeiss confocal file into a portable anymap

SEE ALSO

`anytopnm(1)`, `asciitopgm(1)`, `atktopbm(1)`, `bioradtopgm(1)`, `bmtopppm(1)`, `brushtopbm(1)`, `cmuwmtopbm(1)`, `fitstopnm(1)`, `fstopgm(1)`, `g3topbm(1)`, `gemtopbm(1)`, `giftopnm(1)`, `gouldtoppm(1)`, `hipstopgm(1)`, `hpcdtoppm(1)`, `icontopbm(1)`, `ilbmtoppm(1)`, `imgtoppm(1)`, `lispmtopgm(1)`, `macptopbm(1)`, `mgrtopbm(1)`, `mtvtoppm(1)`, `pbmclean(1)`, `pbm1ife(1)`, `pbmmake(1)`, `pbm1mask(1)`, `pbm1pscale(1)`, `pbm1reduce(1)`, `pbm1text(1)`, `pbm1to10x(1)`, `pbm1to4425(1)`, `pbm1toascii(1)`, `pbm1toatk(1)`, `pbm1tobb1nbg(1)`, `pbm1tocmuwm(1)`, `pbm1toepsi(1)`, `pbm1toepson(1)`, `pbm1tog3(1)`, `pbm1togem(1)`, `pbm1togo(1)`, `pbm1toicon(1)`, `pbm1tolj(1)`, `pbm1toln03(1)`, `pbm1tolps(1)`, `pbm1tomacp(1)`, `pbm1tomgr(1)`, `pbm1topgm(1)`, `pbm1topi3(1)`, `pbm1topk(1)`, `pbm1toplot(1)`, `pbm1top1tx(1)`, `pbm1tox10bm(1)`, `pbm1toxbm(1)`, `pbm1toybm(1)`, `pbm1tozinc(1)`, `pbm1upc(1)`, `pcxtopppm(1)`, `pgmbentley(1)`, `pgmcrater(1)`, `pgmedge(1)`, `pgmenhance(1)`, `pgmhist(1)`, `pgmkernel(1)`, `pgmnoise(1)`, `pgmnorm(1)`, `pgmoil(1)`, `pgmramp(1)`, `pgmtexture(1)`, `pgmtofs(1)`, `pgmtolisp(1)`, `pgmtopbm(1)`, `pgmtopppm(1)`, `pi1toppm(1)`, `pi3topbm(1)`, `picttopppm(1)`, `pjtoppm(1)`, `pktopbm(1)`, `pnmalias(1)`, `pnmarith(1)`, `pnmcat(1)`, `pnmcomp(1)`, `pnmconvol(1)`, `pnmcrop(1)`, `pnmcut(1)`, `pnmdepth(1)`, `pnmenlarge(1)`, `pnmfile(1)`, `pnmflip(1)`, `pnmgamma(1)`, `pnmhistmap(1)`, `pnmindex(1)`, `pnminvert(1)`, `pnmmargin(1)`, `pnmnlfilt(1)`, `pnmnoraw(1)`, `pnmpad(1)`, `pnmpaste(1)`, `pnmrotate(1)`, `pnmscale(1)`, `pnmshear(1)`, `pnmsmooth(1)`, `pnmtile(1)`, `pnmtoddiff(1)`, `pnmtofits(1)`, `pnmtops(1)`, `pnmtorast(1)`, `pnmtosgi(1)`, `pnmtosir(1)`, `pnmtotiff(1)`, `pnmtowd(1)`, `ppm3d(1)`, `ppmbrighten(1)`, `ppmchange(1)`, `ppmdim(1)`, `ppmdist(1)`, `ppmdither(1)`, `ppmflash(1)`, `ppmforge(1)`, `ppmhist(1)`, `ppmmake(1)`, `ppmmix(1)`, `ppmnorm(1)`, `ppmntsc(1)`, `ppmpat(1)`, `ppmquant(1)`, `ppmquantall(1)`, `ppmqvga(1)`, `ppmrelief(1)`, `ppmshift(1)`, `ppmspread(1)`, `ppmtoacad(1)`, `ppmtobmp(1)`, `ppmtogif(1)`, `ppmtoicr(1)`, `ppmtoilbm(1)`, `ppmtomap(1)`, `ppmtomitsu(1)`, `ppmtopc1x(1)`, `ppmtopgm(1)`, `ppmtopi1(1)`, `ppmtopict(1)`, `ppmtopj(1)`, `ppmtopjx1(1)`, `ppmtopuzz(1)`, `ppmtorgb3(1)`, `ppmtosixel(1)`, `ppmtotga(1)`, `ppmtouil(1)`, `ppmtoxpm(1)`, `ppmtoyuv(1)`, `ppmtoyuvsplit(1)`, `psidtopgm(1)`, `pstopnm(1)`, `qrttoppm(1)`, `rasttopnm(1)`, `rawtopgm(1)`, `rawtoppm(1)`, `rgb3toppm(1)`, `sgitopnm(1)`, `sirtopnm(1)`, `sldtoppm(1)`, `spctoppm(1)`, `spottopgm(1)`, `sputoppm(1)`, `tgatoppm(1)`, `tifftopnm(1)`, `xbmtopbm(1)`, `ximtoppm(1)`, `xpmtoppm(1)`, `xvminitoppm(1)`, `xwdtopnm(1)`, `nybmtopbm(1)`, `yuvsplitppm(1)`, `yuvtoppm(1)`, `zeisstopnm(1)`

AUTHORS

Many. See the individual manual pages.

pbm1ife

`pbm1ife`—Apply Conway’s Rules of Life to a portable bitmap

SYNOPSIS

```
pbm1ife [pbmfile]
```

DESCRIPTION

`pbm1ife` reads a portable bitmap as input, applies the Rules of Life to it for one generation, and produces a portable bitmap as output.

A white pixel in the image is interpreted as a live beastie, and a black pixel as an empty space.

SEE ALSO

`pbm(5)`

AUTHOR

Copyright © 1988, 1991 by Jef Poskanzer

21 February 1991

pbmmake

`pbmmake`—Create a blank bitmap of a specified size

SYNOPSIS

```
pbmmake [-white|-black|-gray ] width height
```

DESCRIPTION

`pbmmake` produces a portable bitmap of the specified width and height. The color defaults to white.

OPTIONS

In addition to the usual `-white` and `-black`, this program implements `-gray`. This gives a simple 50 percent gray pattern with 1's and 0's alternating.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

`pbm(5)`, `ppmmake(1)`

AUTHOR

Copyright © 1989 by Jef Poskanzer

22 February 1989

pbmmask

`pbmmask`—Create a mask bitmap from a regular bitmap

SYNOPSIS

```
pbmmask [-expand][pbmfile]
```

DESCRIPTION

`pbmmask` reads a portable bitmap as input and creates a corresponding mask bitmap and writes it out.

The color to be interpreted as background is determined automatically. Regardless of which color is background, the mask will be white where the background is white and black where the figure is black.

This lets you do a masked paste like this, for objects with a black background:

```
pbm mask obj > objmask
pnmpaste < dest -and objmask <x><y>|pnmpaste -or obj <x><y>
```

For objects with a white background, you can either invert them or add a step:

```
pbm mask obj > objmask
pnminvert objmask | pnmpaste -and obj 0 0 > blackback
pnmpaste < dest -and objmask <x><y>|pnmpaste -or blackback <x><y>
```

Note that this three-step version works for objects with black backgrounds, too, if you don't care about the wasted time.

You can also use masks with graymaps and pixmaps, using the `pnmarith` tool. For instance:

```
ppmtopgm obj.ppm | pgmtopbm -threshold | pbmask > objmask.pbm
pnmarith -multiply dest.ppm objmask.pbm > t1.ppm
pnminvert objmask.pbm | pnmarith -multiply obj.ppm - > t2.ppm
pnmarith -add t1.ppm t2.ppm
```

An interesting variation on this is to pipe the mask through the `pnmsmooth` script before using it. This makes the boundary between the two images less sharp.

OPTIONS

`-expand` Expands the mask by one pixel out from the image. This is useful if you want a little white border around your image. (A better solution might be to turn the `pbm life` tool into a general cellular automaton tool...)

SEE ALSO

`pnmpaste(1)`, `pnminvert(1)`, `pbm(5)`, `pnmarith(1)`, `pnmsmooth(1)`

AUTHOR

Copyright © 1988 by Jef Poskanzer

8 August 1989

pbmpscale

`pbmpscale`—Enlarge a portable bitmap with edge smoothing

SYNOPSIS

```
pbmpscale N [ pbmfile ]
```

DESCRIPTION

`pbmpscale` reads a portable bitmap as input and outputs a portable bitmap enlarged `N` times. Enlargement is done by pixel replication, with some additional smoothing of corners and edges.

SEE ALSO

`pnmenlarge(1)`, `ppmscale(1)`, `pbm(5)`

AUTHOR

Copyright © 1990 by Angus Duggan. Copyright © 1989 by Jef Poskanzer.

NOTES

`pbmpscale` works best for enlargements of 2. Enlargements greater than 2 should be done by as many enlargements of 2 as possible, followed by an enlargement by the remaining factor.

pbmreduce

pbmreduce—Read a portable bitmap and reduce it N times

SYNOPSIS

```
pbmreduce [-floyd|-fs|-threshold ][-value val] N [pbmfile]
```

DESCRIPTION

pbmreduce reads a portable bitmap as input, reduces it by a factor of N, and produces a portable bitmap as output.

pbmreduce duplicates a lot of the functionality of pgmtopbm; you could do something like `pnmscale 1 pgmtopbm`, but pbmreduce is a lot faster.

pbmreduce can be used to “re-half-tone” an image. Say you have a scanner that only produces black and white, not grayscale, and it does a terrible job of halftoning (most black-and-white scanners fit this description). One way to fix the halftoning is to scan at the highest possible resolution, say 300dpi, and then reduce by a factor of three or so using pbmreduce. You can even correct the brightness of an image, by using the `-value` flag.

OPTIONS

By default, the halftoning after the reduction is done via boustrophedonic Floyd-Steinberg error diffusion; however, the `-threshold` flag can be used to specify simple thresholding. This gives better results when reducing line drawings.

The `-value` flag alters the thresholding value for all quantizations. It should be a real number between 0 and 1. Above 0.5 means darker images; below 0.5 means lighter.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

`pnmenlarge(1)`, `pnmscale(1)`, `pgmtopbm(1)`, `pbm(5)`

AUTHOR

Copyright © 1988 by Jef Poskanzer

2 August 1989

pbmtext

pbmtext—Render text into a bitmap

SYNOPSIS

```
pbmtext [-font fontfile][-builtin fontname][text]
```

DESCRIPTION

pbmtext takes the specified text, either a single line from the command line or multiple lines from standard input, and renders it into a bitmap.

OPTIONS

By default, pbmtext uses a built-in font called bdf (about a 10-point Times Roman font). You can use a fixed-width font by specifying `-builtin fixed`.

You can also specify your own font with the `-font` flag. The `fontfile` is either a BDF file from the X Window System or a PBM file.

If the `fontfile` is a PBM file, it is created in a very specific way. In your window system of choice, display the following text in the desired (fixed-width) font:

```
M ",/^ ['jqy! M
/ !"$%&'()*+ /
< ,-. /01234567 <
> 89:;<=>?@ABC >
@ DEFGHIJKLMNO @
PQRSTUVWXYZ[
{ \]^ 'abcdefg {
} hijklmnopqrs }
~ tuvwxyz{|}~
M ",/^ ['jqy! M
```

Do a screen grab or window dump of that text, using for instance `xwd`, `xgrabsc`, or `screen-dump`. Convert the result into a PBM file. If necessary, use `pnmcut` to remove everything except the text. Finally, run it through `pnmcrop` to make sure the edges are right up against the text. `pbmtext` can figure out the sizes and spacings from that.

SEE ALSO

`pbm(5)`, `pnmcut(1)`, `pnmcrop(1)`

AUTHOR

Copyright© 1993 by Jef Poskanzer and George Phillips

26 October 1993

pbmto10x

`pbmto10x`—Convert a portable bitmap into Gemini 10X printer graphics

SYNOPSIS

```
pbmto10x [-h] [pbmfile]
```

DESCRIPTION

`pbmto10x` reads a portable bitmap as input and produces a file of Gemini 10X printer graphics as output. The 10X's printer codes are alleged to be similar to the Epson codes.

Note that there is no `10xtopbm` tool; this transformation is one-way.

OPTIONS

The resolution is normally 60H by 72V. If the `-h` flag is specified, resolution is 120H by 144V. You may find it useful to rotate landscape images before printing.

SEE ALSO

`pbm(5)`

AUTHOR

Copyright © 1990 by Ken Yap¹

January 1990

pbmto4425

pbmto4425—Display PBM images on an AT&T 4425 terminal

SYNOPSIS

pbmto4425 [pbmfile]

DESCRIPTION

Pbmto4425 displays PBM format images on an AT&T 4425 ASCII terminal using that terminal's mosaic graphics character set. The program should also work with other VT100-like terminals with mosaic graphics character sets such as the C. Itoh CIT-101, but it has not yet been tested on terminals other than the 4425.

Pbmto4425 puts the terminal into 132-column mode to achieve the maximum resolution of the terminal. In this mode the terminal has a resolution of 264 columns by 69 rows. The pixels have an aspect ratio of 1:2.6; therefore, an image should be processed before being displayed in a manner such as this:

```
% pnmscale -xscale 2.6 pnmfile \
| pnmscale -ysize 264 69 \
| ppmtopgm \
| pgmtopbm \
| pbmto4425
```

AUTHOR

Copyright © 1993 by Robert Perlberg

pbmtoascii

pbmtoascii—Convert a portable bitmap into ASCII graphics

SYNOPSIS

pbmtoascii [-1x2|-2x4][pbmfile]

DESCRIPTION

pbmtoascii reads a portable bitmap as input and produces a somewhat crude ASCII graphic as output.

Note that there is no asciitopbm tool; this transformation is one-way.

OPTIONS

The `-1x2` and `-2x4` flags provide two alternate ways for the bits to get mapped to characters. With `1x2`, the default, each character represents a group of 1 bit across by 2 bits down. With `-2x4`, each character represents 2 bits across by 4 bits down. With the `1x2` mode you can see the individual bits, so it's useful for previewing small bitmaps on a nongraphics terminal. The `2x4` mode lets you display larger bitmaps on a standard 80-column display, but it obscures bit-level details. `2x4` mode is also good for displaying graymaps. `pnmscale -width 158 | pgmnorm | pgmtopbm -thresh` should give good results.

SEE ALSO

pbm(5)

AUTHOR

Copyright © 1988, 1992 by Jef Poskanzer

20 March 1992

pbmtoatk

pbmtoatk—Convert portable bitmap to Andrew Toolkit raster object

SYNOPSIS

```
pbmtoatk [pbmfile]
```

DESCRIPTION

pbmtoatk reads a portable bitmap as input and produces an Andrew Toolkit raster object as output.

SEE ALSO

atktopbm(1), pbm(5)

AUTHOR

Copyright © 1991 by Bill Janssen

26 September 1991

pbmtobg

pbmtobg—Convert a portable bitmap into BitGraph graphics

SYNOPSIS

```
pbmtobg [rasterop][x y]< pbmfile
```

DESCRIPTION

pbmtobg reads a portable bitmap as input and produces BBN BitGraph terminal display pixel data (DPD) sequence as output.

The rasterop can be specified on the command line. If this is omitted, 3 (replace) will be used. A position in (x,y) coordinates can also be specified. If both are given, the rasterop comes first. The portable bitmap is always taken from the standard input.

Note that there is no bgtopbm tool.

SEE ALSO

pbm(5)

AUTHOR

Copyright © 1989 by Mike Parker

16 May 1989

pbmtocmuwm

pbmtocmuwm—Convert a portable bitmap into a CMU window manager bitmap

SYNOPSIS

```
pbmtocmuwm [pbmfile]
```

DESCRIPTION

pbmtocmuwm reads a portable bitmap as input and produces a CMU window manager bitmap as output.

SEE ALSO

cmuwmktopbm(1), pbm(5)

AUTHOR

Copyright © 1989 by Jef Poskanzer

15 April 1989

pbmtoepsi

pbmtoepsi—Convert a portable bitmap into an encapsulated PostScript-style preview bitmap

SYNOPSIS

```
pbmtoepsi [-bonly] [pbmfile]
```

DESCRIPTION

pbmtoepsi reads a portable bitmap as input and produces an encapsulated PostScript-style bitmap as output. The output is not a standalone PostScript file; it is only a preview bitmap, which can be included in an encapsulated PostScript file. Note that there is no epsitopbm tool; this transformation is one-way.

This utility is a part of the pstoepsi tool by Doug Crabill (dgc@cs.purdue.edu).

OPTIONS

-bonly Only create a boundary box, don't fill it with the image.

SEE ALSO

pbm(5), pnmtops(1), psidtopgm(1)

AUTHOR

Copyright © 1988 by Jef Poskanzer, modified by Doug Crabill 1992

1992

pbmtoepson

pbmtoepson—Convert a portable bitmap into Epson printer graphics

SYNOPSIS

```
pbmtoepson [pbmfile]
```

DESCRIPTION

pbmtoepson reads a portable bitmap as input and produces a file of Epson printer graphics as output.

Note that there is no epsontopbm tool; this transformation is one-way.

SEE ALSO

pbm(5)

AUTHOR

Copyright © 1991 by John Tiller (tiller@galois.msfc.nasa.gov) and Jef Poskanzer

4 January 1991

pbmtog3

pbmtog3—Convert a portable bitmap into a Group 3 fax file

SYNOPSIS

pbmtog3 [pbmfile]

DESCRIPTION

pbmtog3 reads a portable bitmap as output and produces a Group 3 fax file as input.

REFERENCES

The standard for Group 3 fax is defined in CCITT Recommendation T.4.

BUGS

Probably.

SEE ALSO

g3topbm(1), pbm(5)

AUTHOR

Copyright © 1989 by Paul Haeberli (<paul@manray.sgi.com>)

2 October 1989

pbmtogem

pbmtogem—Convert a portable bitmap into a GEM IMG file

SYNOPSIS

pbmtogem [pbmfile]

DESCRIPTION

pbmtogem reads a portable bitmap as input and produces a compressed GEM IMG file as output.

BUGS

pbmtogem does not support compression of repeated lines.

SEE ALSO

gemtopbm(1), pbm(5)

AUTHORS

Copyright © 1988 by David Beckemeyer and Jef Poskanzer

11 July 1992

pbmtogo

pbmtogo—Convert a portable bitmap into compressed GraphOn graphics

SYNOPSIS

pbmtogo [pbmfile]

DESCRIPTION

`pbmtogo` reads a portable bitmap as input and produces 2D compressed GraphOn graphics as output. Be sure to set up your GraphOn with the following modes: 8 bits/no parity; obeys no XON/XOFF; NULs are accepted. These are all on the Comm menu. Also, remember to turn off tty post processing. Note that there is no `gotopbm` tool.

SEE ALSO

`pbm(5)`

AUTHORS

Copyright © 1988, 1989 by Jef Poskanzer, Michael Haberler, and Bo Thide

24 November 1989

pbmtoicon

`pbmtoicon`—Convert a portable bitmap into a Sun icon

SYNOPSIS

`pbmtoicon [pbmfile]`

DESCRIPTION

`pbmtoicon` reads a portable bitmap as input and produces a Sun icon as output.

SEE ALSO

`icontopbm(1)`, `pbm(5)`

AUTHOR

Copyright © 1988 by Jef Poskanzer

31 August 1988

pbmtolj

`pbmtolj`—Convert a portable bitmap into HP LaserJet format

SYNOPSIS

`pbmtolj [-resolution N][-float][-noreset][pbmfile]`

DESCRIPTION

`pbmtolj` reads a portable bitmap as input and produces HP LaserJet data as output.

Note that there is no `ljtopbm` tool.

OPTIONS

- `-resolution` Specifies the resolution of the output device, in dpi. Typical values are 75, 100, 150, 300. The default is 75.
- `-float` Suppresses positioning information. The default is to write the sequence ESC & 1 0 E to the output file.
- `-noreset` Prevents `pbmtolj` from writing the reset sequences to the beginning and end of the output file.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

`pbm(5)`

AUTHORS

Copyright © 1988 by Jef Poskanzer and Michael Haberler. `-float` and `-noreset` options added by Wim Lewis

29 August 1988

pbmtoln03

`pbmtoln03`—Convert portable bitmap to DEC LN03+ Sixel output

SYNOPSIS

```
pbmtoln03 [-rltbf] pbmfile
```

DESCRIPTION

`pbmtoln03` reads a portable bitmap as input and produces a DEC LN03+ Sixel output file.

OPTIONS

- `-l nn` Use `nn` as value for left margin (default 0).
- `-r nn` Use `nn` as value for right margin (default 2400).
- `-t nn` Use `nn` as value for top margin (default 0).
- `-b nn` Use `nn` as value for bottom margin (default 3400).
- `-f nn` Use `nn` as value for form length (default 3400).

SEE ALSO

`pbm(5)`

AUTHOR

Tim Cook, 26 February 1992

7 May 1993

pbmtolps

`pbmtolps`—Convert a portable bitmap to PostScript

SYNOPSIS

```
pbmtolps [ -dpi n ] [ pbmfile ]
```

DESCRIPTION

`pbmtolps` reads a portable bitmap as input, and outputs PostScript. The output PostScript uses lines instead of the image operator to generate a (device-dependent) picture that will be imaged much faster.

The PostScript path length is constrained to be less than 1000 points so that no limits are overrun on the Apple Laserwriter and (presumably) no other printers.

SEE ALSO

`pgmtops(1)`, `ppmtops(1)`, `pbm(5)`

AUTHOR

George Phillips (<phillips@cs.ubc.ca>)

pbmtomacp

pbmtomacp—Convert a portable bitmap into a MacPaint file

SYNOPSIS

```
pbmtomacp [-l left][-r right][-b bottom][-t top][pbmfile]
```

DESCRIPTION

pbmtomacp reads a portable bitmap as input. If no input file is given, standard input is assumed. Produces a MacPaint file as output.

The generated file is only the data fork of a picture. You will need a program such as `mcvert` to generate a Macbinary or a BinHex file that contains the necessary information to identify the file as a PNTG file to MacOS.

OPTIONS

Left, right, bottom, and top let you define a square into the PBM file, which must be converted. Default is the whole file. If the file is too large for a MacPaint file, the bitmap is cut to fit from (left, top).

BUGS

The source code contains comments in a language other than English.

SEE ALSO

`ppmtopict(1)`, `macptopbm(1)`, `pbm(5)`, `mcvert(1)`

AUTHOR

Copyright © 1988 by Douwe van der Schaaf (...!mcvax!uvapsy!vdschaaf)

31 August 1988

pbmtomgr

pbmtomgr—Convert a portable bitmap into an MGR bitmap

SYNOPSIS

```
pbmtomgr [pbmfile]
```

DESCRIPTION

pbmtomgr reads a portable bitmap as input and produces an MGR bitmap as output.

SEE ALSO

`mgrtopbm(1)`, `pbm(5)`

AUTHOR

Copyright © 1989 by Jef Poskanzer

24 January 1989

pbmtopgm

pbmtopgm—Convert portable bitmap to portable graymap by averaging areas

SYNOPSIS

```
pbmtopgm <width><height> [pbmfile]
```

DESCRIPTION

pbmtopgm reads a portable bitmap as input and outputs a portable graymap created by averaging the number of pixels within a sample area of width by height around each point. pbmtopgm is similar to a special case of ppmconvol. A ppmsmooth step may be needed after pbmtopgm.

pbmtopgm has the effect of antialiasing bitmaps that contain distinct line features.

SEE ALSO

pbm(5)

AUTHOR

Copyright © 1990 by Angus Duggan. Copyright © 1989 by Jef Poskanzer.

NOTES

pbmtopgm works best with odd sample widths and heights.

pbmtopi3

pbmtopi3—Convert a portable bitmap into an Atari Degas PI3 file

SYNOPSIS

```
pbmtopi3 [pbmfile]
```

DESCRIPTION

pbmtopi3 reads a portable bitmap as input and produces an Atari Degas PI3 file as output.

SEE ALSO

pi3topbm(1), pbm(5), ppmtopi1(1), pi1toppm(1)

AUTHOR

Copyright © 1988 by David Beckemeyer (bdt@david) and Jef Poskanzer.

11 March 1990

pbmtopk

pbmtopk—Convert a portable bitmap into a packed (PK) format font

SYNOPSIS

```
pbmtopk pkfile[.pk] tfmfile[.tfm] resolution [-s designsize] [-p num param...]
[-C cod-ingscheme] [-F family] [-f optfile] [-c num] [-W width] [-H height]
[-D depth] [-I ital] [-h horiz] [-v vert] [-x xoff] [-y yoff] [pbmfile]...
```


DESCRIPTION

pbmtpk reads portable bitmaps as input and produces a packed (PK) font file and a TFM (TeX font metric) file as output. The resolution parameter indicates the resolution of the font, in dots per inch. If the filename `-` is used for any of the filenames, the standard input stream (or standard output, where appropriate) will be used.

OPTIONS

- s *designsize* Sets the design size of the font, in TeX's points (72.27 points to the inch). The default design size is 1. The TFM parameters are given as multiples of the design size.
- p *num param...* Sets the first *num* font parameters for the font. The first seven parameters are the slant, interword spacing, interword space stretchability, interword space shrinkability, x-height, quad width, and post-sentence extra space of the font. Math and symbol fonts may have more parameters; see *The TeXbook* for a list of these. Reasonable default values are chosen for parameters that are not specified.
- C *codingscheme* Sets the coding scheme comment in the TFM file.
- F *family* Sets the font family comment in the TFM file.
- f *optfile* Reads the file *optfile*, which should contain a line of the form:
 filename xoff yoff horiz vert width height depth ital
 The PBM files specified by the *filename* parameters are inserted consecutively in the font with the specified attributes. If any of the attributes are omitted, or replaced with `*`, a default value will be calculated from the size of the bitmap. The settings of the `-W`, `-H`, `-D`, `-I`, `-h`, `-v`, `-x`, and `-y` options do not affect characters created in this way. The character number can be changed by including a line starting with `=`, followed by the new number. Lines beginning with `%` or `#` are ignored.
- c *num* Sets the character number of the next bitmap encountered to *num*.
- W *width* Sets the TFM width of the next character to *width* (in design size multiples).
- H *height* Sets the TFM height of the next character to *height* (in design size multiples).
- D *depth* Sets the TFM depth of the next character to *depth* (in design size multiples).
- I *ital* Sets the italic correction of the next character to *ital* (in design size multiples).
- h *horiz* Sets the horizontal escapement of the next character to *horiz* (in pixels).
- v *vert* Sets the vertical escapement of the next character to *vert* (in pixels).
- x *xoff* Sets the horizontal offset of the next character to *xoff* (in pixels).
- y *yoff* Sets the vertical offset of the next character to *yoff* (in pixels, from the top row).

SEE ALSO

pktopbm(1), pbm(5)

AUTHOR

Adapted from Tom Rokicki's pxtopk by Angus Duggan (ajcd@dcs.ed.ac.uk).

6 August 1990

pbmtoplot

pbmtoplot—Convert a portable bitmap into a UNIX plot(5) file

SYNOPSIS

pbmtoplot [*pbmfile*]

DESCRIPTION

pbmtoplot reads a portable bitmap as input and produces a UNIX plot file.

Note that there is no plottopbm tool; this transformation is one way.

SEE ALSO

`pbm(5)`, `plot(5)`

AUTHOR

Copyright © 1990 by Arthur David Olson.

1 September 1990

`pbmtoptx`

`pbmtoptx`—Convert a portable bitmap into Printronix printer graphics

SYNOPSIS

`pbmtoptx [pbmfile]`

DESCRIPTION

`pbmtoptx` reads a portable bitmap as input and produces a file of Printronix printer graphics as output.

Note that there is no `ptxtoptbm` tool; this transformation is one-way.

SEE ALSO

`pbm(5)`

AUTHOR

Copyright© 1988 by Jef Poskanzer

31 August 1988

`pbmtox10bm`

`pbmtox10bm`—Convert a portable bitmap into an X10 bitmap

SYNOPSIS

`pbmtox10bm [pbmfile]`

DESCRIPTION

`pbmtox10bm` reads a portable bitmap as input and produces an X10 bitmap as output. This older format is maintained for compatibility.

Note that there is no `x10bmtoptbm` tool because `xbmtoptbm` can read both X11 and X10 bitmaps.

SEE ALSO

`pbmtoxbm(1)`, `xbmtoptbm(1)`, `pbm(5)`

AUTHOR

Copyright© 1988 by Jef Poskanzer.

31 August 1988

pbmtoxbm

pbmtoxbm—Convert a portable bitmap into an X11 bitmap

SYNOPSIS

```
pbmtoxbm [pbmfile]
```

DESCRIPTION

pbmtoxbm reads a portable bitmap as input and produces an X11 bitmap as output.

SEE ALSO

pbmtox1bm(1), xbmtoxbm(1), pbm(5)

AUTHOR

Copyright © 1988 by Jef Poskanzer.

31 August 1988

pgmtoybm

pgmtoybm—Convert a portable bitmap into a Bennet Yee “face” file

SYNOPSIS

```
pgmtoybm [pbmfile]
```

DESCRIPTION

pgmtoybm reads a portable bitmap as input and produces as output a file acceptable to the `face` and `xbm` programs by Bennet Yee (bsy+@cs.cmu.edu).

SEE ALSO

ybmtoxbm(1), pbm(5), face(1), face(5), xbm(1)

AUTHORS

Copyright © 1991 by Jamie Zawinski and Jef Poskanzer.

6 March 1990

pbmtozinc

pbmtozinc—Convert a portable bitmap into a Zinc bitmap

SYNOPSIS

```
pbmtozinc [pbmfile]
```

DESCRIPTION

pbmtozinc reads a portable bitmap as input and produces a bitmap in the format used by the Zinc Interface Library (ZIL) version 1.0 as output.

SEE ALSO

pbm(5)

AUTHORS

Copyright © 1988 by James Darrell McCauley (jdm5548@diamond.tamu.edu) and Jef Poskanzer.

2 November 1990

pbmupc

pbmupc—Create a Universal Product Code bitmap

SYNOPSIS

```
pbmupc [-s1|-s2] type manufac product
```

DESCRIPTION

pbmupc generates a Universal Product Code symbol. The three arguments are: a one-digit product type, a five-digit manufacturer code, and a five-digit product code. For example, `0 72890 00011` is the code for Heineken.

As presently configured, pbmupc produces a bitmap 230 bits wide and 175 bits high. The size can be altered by changing the defines at the beginning of the program, or by running the output through `pnmenlarge` or `pnmscale`.

OPTIONS

The `-s1` and `-s2` flags select the style of UPC to generate. The default, `-s1`, looks more or less like this:

```
|||||
|||||
|||||
|||||
|||||
|||||
|||||
|||||
|||||
|||||
0||12345||67890||5
```

The other style, `-s2`, puts the product type digit higher up, and doesn't display the checksum digit:

```
|||||
|||||
|||||
0|||||
|||||
|||||
|||||
||12345||67890||
```

SEE ALSO

`pbm(5)`

AUTHOR

Copyright © 1989 by Jef Poskanzer.

14 March 1989

pcxto ppm

pcxto ppm—Convert a PCX file into a portable pixmap

SYNOPSIS

```
pcxto ppm[pcx file]
```

DESCRIPTION

pcxto ppm reads a PCX file as input and produces a portable pixmap as output.

SEE ALSO

ppmtopcx(1), ppm(5)

AUTHOR

Copyright © 1990 by Michael Davidson.

9 April 1990

pfbtops

pfbtops—Translate a PostScript font in PFB format to ASCII

SYNOPSIS

pfbtops [pfb_file]

DESCRIPTION

pfbtops translates a PostScript font in PFB format to ASCII. If `pfb_file` is omitted, the PFB file will be read from the standard input. The ASCII format PostScript font will be written on the standard output. PostScript fonts for MS-DOS are normally supplied in PFB format.

The resulting ASCII format PostScript font can be used with `groff`. It must first be listed in `/usr/lib/groff/font/devps/download`.

SEE ALSO

grops(1)

Groff Version 1.09, 6 August 1992

pgmbentley

pgmbentley—Bentleyize a portable graymap

SYNOPSIS

pgmbentley [pgmfile]

DESCRIPTION

pgmbentley reads a portable graymap as input, performs the Bentley Effect, and writes a portable graymap as output.

The Bentley Effect is described in *Beyond Photography* by Holzmman, Chapter 4, photo 4. It's a vertical smearing based on brightness.

SEE ALSO

pgmoil(1), ppmrelief(1), pgm(5)

AUTHOR

Copyright © 1990 by Wilson Bent (whb@hoh-2.att.com).

11 January 1991

pgmcrater

pgmcrater—Create cratered terrain by fractal forgery

SYNOPSIS

```
pgmcrater [-number n][ -height|-ysize s][ -width|-xsize s][ -gamma g]
```

DESCRIPTION

pgmcrater creates a portable graymap that mimics cratered terrain. The graymap is created by simulating the impact of a given number of craters with random position and size, then rendering the resulting terrain elevations based on a light source shining from one side of the screen. The size distribution of the craters is based on a power law that results in many more small craters than large ones. The number of craters of a given size varies as the reciprocal of the area as described on pages 31 and 32 of *The Science Of Fractal Images*, edited by H.O. Peitgen and D. Saupe (New York: Springer-Verlag, 1988). Cratered bodies in the solar system are observed to obey this relationship. The formula used to obtain crater radii governed by this law from a uniformly distributed pseudorandom sequence was developed by Rudy Rucker.

High resolution images with large numbers of craters often benefit from being piped through `pnmsmooth`. The averaging performed by this process eliminates some of the jagged pixels and lends a mellow “telescopic image” feel to the overall picture.

OPTIONS

`-number n` Causes `n` craters to be generated. If no `-number` specification is given, 50,000 craters will be generated. Don’t expect to see them all! For every large crater, there are many, many more tiny ones that tend simply to erode the landscape. In general, the more craters you specify, the more realistic the result; ideally, you want the entire terrain to have been extensively turned over again and again by cratering. High-resolution images containing five to ten million craters are stunning but take quite a while to create.

`-height height` Sets the height of the generated image to `height` pixels. The default height is 256 pixels.
`-width width` Sets the width of the generated image to `width` pixels. The default width is 256 pixels.
`-xsize width` Sets the width of the generated image to `width` pixels. The default width is 256 pixels.
`-ysize height` Sets the height of the generated image to `height` pixels. The default height is 256 pixels.
`-gamma factor` The specified `factor` is used to gamma correct the graymap in the same manner as performed by `pnmgamma`. The default value is `1.0`, which results in a medium contrast image. Values larger than 1 lighten the image and reduce contrast, while values less than 1 darken the image, increasing contrast.

All flags can be abbreviated to their shortest unique prefix.

BUGS

The `-gamma` option isn’t really necessary because you can achieve the same effect by piping the output from `pgmcrater` through `pnmgamma`. However, `pgmcrater` performs an internal gamma map anyway in the process of rendering the elevation array into a graymap, so there’s no additional overhead in allowing a user-specified gamma.

Real craters have two distinct morphologies. `pgmcrater` simulates only small craters, which are hemispherical in shape (regardless of the incidence angle of the impacting body, as long as the velocity is sufficiently high). Large craters, such as Copernicus and Tycho on the moon, have a “walled plain” shape with a cross-section more like:

```
 /\ \
____/  \____  /\____/  \____
```

Larger craters should really use this profile, including the central peak, and totally obliterate the preexisting terrain.

SEE ALSO

`pgm(5)`, `pnmgamma(1)`, `pnmsmooth(1)`

AUTHOR

John Walker
Autodesk SA Avenue des Champs-Montants 14b
CH-2074 MARIN
Suisse/Schweiz/Svizzera/Svizra/Switzerland

Usenet: kelvin@Autodesk.com
Fax: 038/33 88 15
Voice: 038/33 76 33

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, without any conditions or restrictions. This software is provided “as is” without express or implied warranty.

PLUGWARE! If you like this kind of stuff, you may also enjoy James Gleick’s “Chaos—The Software” for MS-DOS, available for \$59.95 from your local software store or directly from Autodesk, Inc., Attn: Science Series, 2320 Marinship Way, Sausalito, CA 94965, USA. Telephone: 800-688-2344 toll-free or, outside the U.S. (415) 332-2344 Ext 4886. Fax: 415-289-4718. “Chaos—The Software” includes a more comprehensive fractal forgery generator that creates three-dimensional landscapes as well as clouds and planets, plus five more modules that explore other aspects of Chaos. The user guide of more than 200 pages includes an introduction by James Gleick and detailed explanations by Rudy Rucker of the mathematics and algorithms used by each program.

15 October 1991

pgmedge

pgmedge—Edge detect a portable graymap

SYNOPSIS

```
pgmedge [pgmfile]
```

DESCRIPTION

pgmedge reads a portable graymap as input, outlines the edges, and writes a portable graymap as output. Piping the result through `pgmtopbm -threshold` and playing with the threshold value will give a bitmap of the edges.

The edge detection technique used is to take the Pythagorean sum of two Sobel gradient operators at 90 degrees to each other. For more details see *Digital Image Processing* by Gonzalez and Wintz, Chapter 7.

SEE ALSO

pgmenhance(1), pgmtopbm(1), pgm(5), pbm(5)

AUTHOR

Copyright © 1991 by Jef Poskanzer.

4 February 1990

pgmenhance

pgmenhance—Edge enhance a portable graymap

SYNOPSIS

```
pgmenhance [-N][pgmfile]
```

DESCRIPTION

`pgmenhance` reads a portable graymap as input, enhances the edges, and writes a portable graymap as output.

The edge enhancing technique is taken from Philip R. Thompson's `xim` program, which took it from section 6 of *Digital Halftones by Dot Diffusion*, D. E. Knuth, *ACM Transaction on Graphics* Vol. 6, No. 4, October 1987, which in turn got it from two 1976 papers by J. F. Jarvis et. al.

OPTIONS

The optional `-N` flag should be a digit from 1 to 9. 1 is the lowest level of enhancement, 9 is the highest; the default is 9.

SEE ALSO

`pgmedge(1)`, `pgm(5)`, `pbm(5)`

AUTHOR

Copyright © 1989 by Jef Poskanzer.

13 January 1989

pgmhist

`pgmhist`—Print a histogram of the values in a portable graymap

SYNOPSIS

`pgmhist [pgmfile]`

DESCRIPTION

`pgmhist` reads a portable graymap as input and prints a histogram of the gray values.

SEE ALSO

`pgmnorm(1)`, `pgm(5)`, `ppmhist(1)`

AUTHOR

Copyright © 1989 by Jef Poskanzer

28 February 1989

pgmkernel

`pgmkernel`—Generate a convolution kernel

SYNOPSIS

`pgmkernel [ -weight w ] width [ height ]`

DESCRIPTION

`pgmkernel` generates a portable graymap array of size `width` x `height` (or `width` x `width` if `height` is not specified) to be used as a convolution file by `pnmconvol`. The data in the convolution array `K` are computed according to the formula:

$$K(i,j) = \frac{1}{1 + w \sqrt{(i - \text{width}/2)^2 + (j - \text{height}/2)^2}}$$

where *w* is a coefficient specified via the `-weight` flag, and *width* and *height* are the X and Y filter sizes.

The output PGM file is always written out in ASCII format.

OPTIONS

The optional `-weight` flag should be a real number greater than -1. The default value is 6.0.

BUGS

The computation time is proportional to *width* * *height*. This increases rapidly with the increase of the kernel size. A better approach could be to use a FFT in these cases.

SEE ALSO

`pnmconvol(1)`, `pnmsmooth(1)`

AUTHOR

Alberto Accomazzi (alberto@cfa.harvard.edu)

10 December 1992

pgmnoise

`pgmnoise`—Create a graymap made up of white noise

SYNOPSIS

`pgmnoise width height`

DESCRIPTION

`pgmnoise` creates a portable graymap that is made up of random pixels with gray values in the range of 0 to `PGM_MAXMAXVAL` (depends on the compilation, either 255 or 65535). The graymap has a size of *width* * *height* pixels.

SEE ALSO

`pgm(5)`

AUTHOR

Copyright © 1993 by Frank Neumann

16 November 1993

pgmnorm

`pgmnorm`—Normalize the contrast in a portable graymap

SYNOPSIS

`pgmnorm[-bpercent N | -bvalue N][-wpercent N | -wvalue N][pgmfile]`

DESCRIPTION

`pgmnorm` reads a portable graymap as input; normalizes the contrast by forcing the lightest pixels to white, the darkest pixels to black, and linearly rescaling the ones in between; and produces a portable graymap as output.

OPTIONS

By default, the darkest two percent of all pixels are mapped to black, and the lightest one percent are mapped to white. You can override these percentages by using the `-bpercent` and `-wpercent` flags, or you can specify the exact pixel values to be

mapped by using the `-bvalue` and `-wvalue` flags. Appropriate numbers for the flags can be gotten from the `pgmhist` tool. If you just want to enhance the contrast, then choose values at elbows in the histogram; for example, if value 29 represents 3 percent of the image but value 30 represents 20 percent, choose 30 for `bvalue`. If you want to lighten the image, then set `bvalue` to 0 and just fiddle with `wvalue`; similarly, to darken the image, set `wvalue` to `maxval` and play with `bvalue`.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

`pgmhist(1)`, `ppmnorm(1)`, `pgm(5)`

AUTHOR

Partially based on the `fbnorm` filter in Michael Mauldin's "Fuzzy Pixmap" package.

Copyright© 1989 by Jef Poskanzer.

28 February 1989

pgmoil

`pgmoil`—Turn a portable graymap into an oil painting

SYNOPSIS

```
pgmoil [-n N][pgmfile]
```

DESCRIPTION

`pgmoil` reads a portable graymap as input, does an "oil transfer," and writes a portable graymap as output.

The oil transfer is described in *Beyond Photography* by Holzmann, Chapter 4, photo 7. It's a sort of localized smearing.

OPTIONS

The optional `-n` flag controls the size of the area smeared. The default value is 3.

BUGS

Takes a long time to run.

SEE ALSO

`pgmbentley(1)`, `ppmrelief(1)`, `pgm(5)`

AUTHOR

Copyright© 1990 by Wilson Bent (whb@hoh-2.att.com).

11 January 1991

pgmramp

`pgmramp`—Generate a grayscale ramp

SYNOPSIS

```
pgmramp -lr|-tb | -rectangle|-ellipse width height
```

DESCRIPTION

`pgmramp` generates a graymap of the specified size containing a black-to-white ramp. These ramps are useful for multiplying with other images, using the `pnmarith` tool.

OPTIONS

- lr A left to right ramp
- tb A top to bottom ramp
- rectangle A rectangular ramp
- ellipse An elliptical ramp

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

pnmarith(1), pgm(5)

AUTHOR

Copyright © 1989 by Jef Poskanzer.

24 November 1989

pgmttexture

pgmttexture—Calculate textural features on a portable graymap

SYNOPSIS

```
pgmttexture [-d d][pgmfile]
```

DESCRIPTION

pgmttexture reads a portable graymap as input. Calculates textural features based on spatial dependence matrices at 0, 45, 90, and 135 degrees for a distance *d* (default = 1). Textural features include

- (1) Angular Second Moment
- (2) Contrast
- (3) Correlation
- (4) Variance
- (5) Inverse Difference Moment
- (6) Sum Average
- (7) Sum Variance
- (8) Sum Entropy
- (9) Entropy
- (10) Difference Variance
- (11) Difference Entropy
- (12, 13) Information Measures of Correlation
- (14) Maximal Correlation Coefficient

Algorithm taken from “Textural Features for Image Classification,” *IEEE Transactions on Systems, Man, and Cybernetics*, R.M. Haralick, K. Shanmugam, and I. Dinstein, 1973. SMC-3(6):610–621.

BUGS

The program can run incredibly slowly for large images (larger than 64×64) and command-line options are limited. The method for finding the maximal correlation coefficient, which requires finding the second largest eigenvalue of a matrix *Q*, does not always converge.

REFERENCES

IEEE Transactions on Systems, Man, and Cybernetics, SMC-3(6):610–621.

SEE ALSO

`pgm(5)`, `pnmcut(1)`

AUTHOR

Copyright © 1991 by Texas Agricultural Experiment Station, employer-for-hire of James Darrell McCauley.

22 August 1991

pgmtofs

`pgmtofs`—Convert portable graymap to Usenix FaceSaver format

SYNOPSIS

`pgmtofs [pgmfile]`

DESCRIPTION

`pgmtofs` reads a portable graymap as input. Produces Usenix FaceSaver format as output.

FaceSaver is a registered trademark of Metron Computerware Ltd. of Oakland, CA.

SEE ALSO

`fstopgm(1)`, `pgm(5)`

AUTHOR

Copyright© 1991 by Jef Poskanzer.

18 May 1990

pgmtolisp

`pgmtolisp`—Convert a portable graymap into Lisp machine format

SYNOPSIS

`pgmtolisp [pgmfile]`

DESCRIPTION

`pgmtolisp` reads a portable graymap as input and produces a Lisp machine bitmap as output.

This is the file format read by the `tv:read-bit-array-file` function on TI Explorer and Symbolics Lisp machines.

Given a PGM (instead of a PBM), a multiplane image will be output. This is probably not useful unless you have a color Lisp machine.

Multiplane bitmaps on Lisp machines are color; but the `lisp` image file format does not include a colormap, so it must be treated as a graymap instead. This is unfortunate.

SEE ALSO

`lispmtopgm(1)`, `pgm(5)`

BUGS

Output width is always rounded up to the nearest multiple of 32; this might not always be what you want, but it probably is (arrays that are not modulo 32 cannot be passed to the `lisp` `BITBLT` function, and thus cannot easily be displayed on the screen).

No color.

AUTHOR

Copyright © 1991 by Jamie Zawinski and Jef Poskanzer.

6 March 1990

pgmtopbm

pgmtopbm—Convert a portable graymap into a portable bitmap

SYNOPSIS

```
pgmtopbm [-floyd|-fs|-threshold | -hilbert | -dither8|-d8|-cluster3
|-c3|-cluster4|-c4 | -cluster8|-c8][-value val][-clump size][pgmfile]
```

DESCRIPTION

pgmtopbm reads a portable graymap as input and produces a portable bitmap as output.

Note that there is no pbmtopgm converter because any pgm program can read PBM files automagically.

OPTIONS

The default quantization method is boustrophedonic Floyd-Steinberg error diffusion (`-floyd` or `-fs`). Also available are simple thresholding (`-threshold`); Bayer's ordered dither (`-dither8`) with a 16×16 matrix; and three different sizes of 45-degree clustered-dot dither (`-cluster3`, `-cluster4`, `-cluster8`). A space-filling curve halftoning method using the Hilbert curve is also available. (`-hilbert`).

Floyd-Steinberg will almost always give the best looking results; however, looking good is not always what you want. For instance, thresholding can be used in a pipeline with the `pnmconvol` tool, for tasks like edge and peak detection. And clustered-dot dithering gives a newspaper-like look, a useful special effect. The `-value` flag alters the thresholding value for Floyd-Steinberg and simple thresholding. It should be a real number between 0 and 1. Above 0.5 means darker images; below 0.5 means lighter.

The Hilbert curve method is useful for processing images before display on devices that do not render individual pixels distinctly (like laser printers). This dithering method can give better results than the dithering usually done by the laser printers themselves. The `-clump` flag alters the number of pixels in a clump. This is usually an integer between 2 and 100 (default 5). Smaller clump sizes smear the image less and are less grainy, but seem to lose some grayscale linearity. Typically, a PGM image will have to be scaled to fit on a laser printer page (2400 × 3000 pixels for an A4 300dpi page), and then dithered to a PBM image before being converted to a PostScript file. A printing pipeline might look something like this:

```
pnmscale -ysize 2400 3000 image.pgm | pgmtopbm -hil | pnmtops -scale 0.25 image.ps
```

All flags can be abbreviated to their shortest unique prefix.

REFERENCES

The only reference you need for this stuff is *Digital Halftoning* by Robert Ulichney, MIT Press, ISBN 0-262-21009-6.

The Hilbert curve space filling method is taken from “Digital Halftoning with Space Filling Curves” by Luiz Velho, *Computer Graphics* Volume 25, Number 4, proceedings of SIGGRAPH '91, page 81. ISBN 0-89791-436-8

SEE ALSO

`pbmreduce(1)`, `pgm(5)`, `pbm(5)`, `pnmconvol(1)`, `pnmscale(1)`, `pnmtops(1)`

AUTHOR

Copyright © 1989 by Jef Poskanzer.

26 July 1988

pgmtoppm

pgmtoppm—Colorize a portable graymap into a portable pixmap

SYNOPSIS

```
pgmtoppm colorspec [pgmfile]
pgmtoppm colorspec1-colorspec2 [pgmfile]
pgmtoppm -map mapfile [pgmfile]
```

DESCRIPTION

pgmtoppm reads a portable graymap as input, colorizes it by multiplying the gray values by specified color or colors, and produces a portable pixmap as output.

If only one color is specified, black in the PGM file stays black and white in the PGM file turns into the specified color in the PPM file. If two colors (separated by a hyphen) are specified, then black gets mapped to the first color and white gets mapped to the second.

The color can be specified in five ways:

- A name, assuming that a pointer to an X11-style color names file was compiled in.
- An X11-style hexadecimal specifier: `rgb:r/g/b`, where `r`, `g`, and `b` are each 1- to 4-digit hexadecimal numbers.
- An X11-style decimal specifier: `rgbi:r/g/b`, where `r`, `g`, and `b` are floating-point numbers between 0 and 1.
- For backwards compatibility, an old-X11-style hexadecimal number: `#rgb`, `#rrggbb`, `#rrrgggbbb`, or `#rrrrggggbbb`.
- For backwards compatibility, a triplet of numbers separated by commas: `r,g,b`, where `r`, `g`, and `b` are floating-point numbers between 0 and 1. (This style was added before MIT came up with the similar `rgbi` style.)

Also, the `-map` flag lets you specify an entire colormap to be used. The mapfile is just a PPM file; it can be any shape, all that matters is the colors in it and their order. In this case, black gets mapped to the first color in the mapfile, and white gets mapped to the last.

SEE ALSO

`rgb3toppm(1)`, `ppmtopgm(1)`, `ppmtorgb3(1)`, `ppm(5)`, `pgm(5)`

AUTHOR

Copyright© 1991 by Jef Poskanzer.

11 January 1991

pi1toppm

pi1toppm—Convert an Atari Degas PI1 into a portable pixmap

SYNOPSIS

```
pi1toppm [pi1file]
```

DESCRIPTION

pi1toppm reads an Atari Degas PI1 file as input and produces a portable pixmap as output.

SEE ALSO

`ppmtopi1(1)`, `ppm(5)`, `pi3topbm(1)`, `pbmtopi3(1)`

AUTHORS

Copyright© 1991 by Steve Belczyk (seb3@gte.com) and Jef Poskanzer.

19 July 1990

pi3topbm

pi3topbm—Convert an Atari Degas PI3 file into a portable bitmap

SYNOPSIS

```
pi3topbm [pi3file]
```

DESCRIPTION

pi3topbm reads an Atari Degas PI3 file as input. Produces a portable bitmap as output.

SEE ALSO

pbmtopi3(1), pbm(5), pi1toppm(1), ppmtopi1(1)

AUTHORS

Copyright© 1988 by David Beckemeyer (bdt@david) and Diomidis D. Spinellis.

11 March 1990

picttoppm

picttoppm—Convert a Macintosh PICT file into a portable pixmap

SYNOPSIS

```
picttoppm [-verbose][-fullres][-noheader][-quickdraw][-fontdirfile] [pictfile]
```

DESCRIPTION

picttoppm reads a PICT file (version 1 or 2) and outputs a portable pixmap. Useful as the first step in converting a scanned image to something that can be displayed on UNIX.

OPTIONS

- fontdir file Make the list of BDF fonts in file available for use by pict-toppm when drawing text. For the format of the fontdir file, see the “fontdir File Format” subsection.
- fullres Force any images in the PICT file to be output with at least their full resolution. A PICT file may indicate that a contained image is to be scaled down before output. This option forces images to retain their sizes and prevent information loss. Use of this option disables all PICT operations except images.
- noheader Do not skip the 512-byte header that is present on all PICT files. This is useful when you have PICT data that was not stored in the data fork of a PICT file.
- quickdraw Execute only pure quickdraw operations. In particular, turn off the interpretation of special PostScript printer operations.
- verbose Turns on verbose mode, which prints a whole bunch of information that only picttoppm hackers really care about.

BUGS

The PICT file format is a general drawing format. picttoppm does not support all the drawing commands, but it does have full support for any image commands and reasonable support for line, rectangle, polygon, and text drawing. It is useful for converting scanned images and some drawing conversion.

Memory is used very liberally with at least six bytes needed for every pixel. Large bitmap PICT files will likely run your computer out of memory.

fontdir FILE FORMAT

`picttoppm` has a built-in default font and your local installer probably provided adequate extra fonts. You can point `picttoppm` at more fonts that you specify in a font directory file. Each line in the file is either a comment line, which must begin with `#`, or font information. The font information consists of four whitespace separated fields. The first is the font number, the second is the font size in pixels, the third is the font style, and the fourth is the name of a BDF file containing the font. The BDF format is defined by the X Window System and is not described here.

The font number indicates the type face. Here is a list of known font numbers and their faces.

0	Chicago
1	Application font
2	New York
3	Geneva
4	Monaco
5	Venice
6	London
7	Athens
8	San Francisco
9	Toronto
11	Cairo
12	Los Angeles
20	Times Roman
21	Helvetica
22	Courier
23	Symbol
24	Taliesin

The font style indicates a variation on the font. Multiple variations may apply to a font and the font style is the sum of the variation numbers, which are

1	Boldface
2	Italic
4	Underlined
8	Outlined
16	Shadow
32	Condensed
64	Extended

Obviously, the font definitions are strongly related to the Macintosh. More font numbers and information about fonts can be found in Macintosh documentation.

SEE ALSO

Inside Macintosh volumes 1 and 5, `ppmto pict(1)`, `ppm(5)`

AUTHOR

Copyright ©1993 George Phillips.

29 November 1991

pjtoppm

pjtoppm—Convert an HP PaintJet file to a portable pixmap

SYNOPSIS

```
pjtoppm [paintjet]
```

DESCRIPTION

pjtoppm reads an HP PaintJet file as input and converts it into a portable pixmap. This was a quick hack to save some trees, and it only handles a small subset of the paintjet commands. In particular, it will only handle enough commands to convert most raster image files.

REFERENCES

HP PaintJet XL Color Graphics Printer User's Guide

SEE ALSO

ppmtopj(1)

AUTHOR

Copyright© 1991 by Christos Zoulas.

14 July 1991

pktopbm

pktopbm—Convert packed (PK) format font into portable bitmap(s)

SYNOPSIS

```
pktopbm pkfile[.pk] [-c num] pbmfile ...
```

DESCRIPTION

pktopbm reads a packed (PK) font file as input and produces portable bitmaps as output. If the filename “-” is used for any of the filenames, the standard input stream (or standard output where appropriate) will be used.

OPTIONS

-c num Sets the character number of the next bitmap written to num.

SEE ALSO

pbmtopk(1), pbm(5)

AUTHOR

Adapted from Tom Rokicki's pxtopk by Angus Duggan (ajcd@dcs.ed.ac.uk).

6 August 1990

pnmalias

pnmalias—Antialias a portable anymap.

SYNOPSIS

```
pnmalias [-bgcolor color][-fgcolor color][-bonly][-fonly][-balias][-falias]
          [-weight w][pnmfile]
```

DESCRIPTION

`pnmalias` reads a portable anymap as input and applies antialiasing to background and foreground pixels. If the input file is a portable bitmap, the output antialiased image is promoted to a graymap, and a message is printed informing the user of the change in format.

OPTIONS

- `-bgcolor colorb,` Set the background color to `colorb`, and the foreground to color to `colorf`. Pixels with these values will be antialiased. By default, the background color is taken to be black, and foreground color is assumed to be white. The colors can be specified in five ways:
 - A name, assuming that a pointer to an X11-style color names file was compiled in.
 - An X11-style hexadecimal specifier: `rgb:r/g/b`, where `r`, `g`, and `b` are each 1- to 4-digit hexadecimal numbers.
 - An X11-style decimal specifier: `rgbi:r/g/b`, where `r`, `g`, and `b` are floating-point numbers between 0 and 1.
 - For backwards compatibility, an old-X11-style hexadecimal number: `#rgb`, `#rrggbb`, `#rrrrgggbbb`, or `#rrrrggggbbbb`.
 - For backwards compatibility, a triplet of numbers separated by commas: `r,g,b`, where `r`, `g`, and `b` are floating-point numbers between 0 and 1. (This style was added before MIT came up with the similar `rgbi` style.)
- `-fgcolor colorf`

Note that even when dealing with graymaps, background and foreground colors need to be specified in the fashion described in the preceding list. In this case, background and foreground pixel values are taken to be the value of the red component for the given color.

- `-bonly, -fonly` Apply antialiasing only to background (`-bonly`), or foreground (`-fonly`) pixels.
- `-balias, -falias` Apply antialiasing to all pixels surrounding background (`-balias`), or foreground (`-falias`) pixels. By default, antialiasing takes place only among neighboring background and foreground pixels.
- `-weight w` Use `w` as the central weight for the aliasing filter. `w` must be a real number in the range $0 < w < 1$. The lower the value of `w` is, the “blurrier” the output image is. The default is `w = 1/3`.

SEE ALSO

`pbmtext(1)`, `pnmsmooth(1)`, `pnm(5)`

AUTHOR

Copyright© 1992 by Alberto Accomazzi, Smithsonian Astrophysical Observatory.

30 April 1992

pnmarith

`pnmarith`—Perform arithmetic on two portable anymaps

SYNOPSIS

```
pnmarith -add|-subtract|-multiply|-difference pnmfile1 pnmfile2
```

DESCRIPTION

`pnmarith` reads two portable anymaps as input, performs the specified arithmetic operation, and produces a portable anymap as output. The two input anymaps must be the same width and height.

The arithmetic is performed between corresponding pixels in the two anymaps, as if `maxval` was 1.0, black was 0.0, with a linear scale in between. Results that fall outside of [0..1) are truncated.

The operator `-difference` calculates the absolute value of
`pnmarith -subtract pnmfile1 pnm-file2`

In other words, no truncation is done.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

`pbm_mask(1)`, `pnmpaste(1)`, `pnminvert(1)`, `pnm(5)`

AUTHOR

Copyright© 1989, 1991 by Jef Poskanzer. Lightly modified by Marcel Wijkstra (wijkstra@fwi.uva.nl).

26 August 1993

pnmcat

`pnmcat`—Concatenate portable anymaps

SYNOPSIS

```
pnmcat [-white|-black] -leftright|-lr [-jtop|-jbottom] pnmfile pnmfile ...
pnmcat [-white|-black] -topbottom|-tb [-jleft|-jright] pnmfile pnmfile ...
```

DESCRIPTION

`pnmcat` reads portable anymaps as input, concatenates them either left to right or top to bottom, and produces a portable anymap as output.

OPTIONS

If the anymaps are not all the same height (left-right) or width (top-bottom), the smaller ones have to be justified with the largest. By default, they get centered, but you can specify one side or the other with one of the `-j*` flags. So, `-topbottom -jleft` would stack the anymaps on top of each other, flush with the left edge.

The `-white` and `-black` flags specify which color to use to fill in the extra space when doing this justification. If neither is specified, the program makes a guess.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

`pnm(5)`

AUTHOR

Copyright© 1989 by Jef Poskanzer.

12 March 1989

pnmcomp

`pnmcomp`—Composite two portable anymap files together

SYNOPSIS

```
pnmcomp [-invert][-xoffN] [-yoffN] [-alphagmfile] overlay [pnm-input][pnm-output]
```

DESCRIPTION

`pnmcomp` reads in a portable anymap image and puts an overlay upon it, with optional alpha mask. The `-alphapgmfile` allows you to also add an alpha mask file to the compositing process; the range of `max` and `min` can be swapped by using the `-invert` option. The `-xoff` and `-yoff` arguments can be negative, allowing you to shift the overlay off the top corner of the screen.

SEE ALSO

`pnm(5)`

AUTHOR

Copyright© 1992 by David Koblas (koblas@mips.com).

21 February 1989

pnmconvol

`pnmconvol`—General $M \times N$ convolution on a portable anymap

SYNOPSIS

`pnmconvol convolutionfile [pnmfile]`

DESCRIPTION

`pnmconvol` reads two portable anymaps as input, convolves the second using the first, and writes a portable anymap as output.

Convolution means replacing each pixel with a weighted average of the nearby pixels. The weights and the area to average are determined by the convolution matrix. The unsigned numbers in the convolution file are offset by `-maxval/2` to make signed numbers, and then normalized, so the actual values in the convolution file are only relative.

Here is a sample convolution file; it does a simple average of the nine immediate neighbors, resulting in a smoothed image:

```
P2
3 3
18
10 10 10
10 10 10
10 10 10
```

To see how this works, do the offset mentioned in the preceding paragraph: $10 - 18/2$ gives 1. The possible range of values is from 0 to 18, and after the offset that's -9 to 9. The normalization step makes the range -1 to 1, and the values get scaled correspondingly so they become $1/9$ —exactly what you want. The equivalent matrix for 5×5 smoothing would have `maxval` 50 and be filled with 26.

The convolution file will usually be a graymap, so that the same convolution is applied to each color component. However, if you want to use a pixmap and do a different convolution to different colors, you can certainly do that.

SEE ALSO

`pnmsmooth(1)`, `pnm(5)`

AUTHOR

Copyright© 1989, 1991 by Jef Poskanzer.

13 January 1991

pnmcrop

pnmcrop—Crop a portable anymap

SYNOPSIS

```
pnmcrop [-white|-black][ -left][ -right][ -top][ -bottom] [pnmfile]
```

DESCRIPTION

pnmcrop reads a portable anymap as input, removes edges that are the background color, and produces a portable anymap as output.

OPTIONS

By default, it makes a guess as to what the background color is. You can override the default with the `-white` and `-black` flags.

The options `-left`, `-right`, `-top` and `-bottom` restrict cropping to the sides specified. The default is to crop all sides of the image.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

pnmcut(1), pnm(5)

AUTHOR

Copyright © 1989 by Jef Poskanzer.

25 February 1989

pnmcut

pnmcut—Cut a rectangle out of a portable anymap

SYNOPSIS

```
pnmcut x y width height [pnmfile]
```

DESCRIPTION

pnmcut reads a portable anymap as input, extracts the specified rectangle, and produces a portable anymap as output. The `x` and `y` can be negative, in which case they are interpreted relative to the right and bottom of the anymap, respectively.

SEE ALSO

pnm(5)

AUTHOR

Copyright © 1989 by Jef Poskanzer.

21 February 1989

pnmddepth

pnmddepth—Change the maxval in a portable anymap

SYNOPSIS

```
pnmddepth newmaxval [pnmfile]
```

DESCRIPTION

`pnmddepth` reads a portable anymap as input, scales all the pixel values, and writes out the image with the new `maxval`. Scaling the colors down to a smaller `maxval` will result in some loss of information.

Be careful of off-by-one errors when choosing the new `maxval`. For instance, if you want the color values to be five bits wide, use a `maxval` of 31, not 32.

SEE ALSO

`pnm(5)`, `ppmquant(1)`, `ppmdither(1)`

AUTHOR

Copyright © 1989, 1991 by Jef Poskanzer.

12 January 1991

pnmenlarge

`pnmenlarge`—Read a portable anymap and enlarge it `N` times

SYNOPSIS

`pnmenlarge N [pnmfile]`

DESCRIPTION

`pnmenlarge` reads a portable anymap as input, replicates its pixels `N` times, and produces a portable anymap as output.

`pnmenlarge` can only enlarge by integer factors. The slower but more general `pnm-scale` can enlarge or reduce by arbitrary factors, and `pbmreduce` can reduce by integer factors, but only for bitmaps.

If you enlarge by a factor of 3 or more, you should probably add a `pnm-smooth` step; otherwise, you can see the original pixels in the resulting image.

SEE ALSO

`pbmreduce(1)`, `pnm-scale(1)`, `pnm-smooth(1)`, `pnm(5)`

AUTHOR

Copyright © 1989 by Jef Poskanzer.

26 February 1989

pnmfile

`pnmfile`—Describe a portable anymap

SYNOPSIS

`pnmfile [pnmfile] ...`

DESCRIPTION

`pnmfile` reads one or more portable anymaps as input and writes out short descriptions of the image type, size, and so on. This is mostly for use in shell scripts, so the format is not particularly pretty.

SEE ALSO

`pnm(5)`, `file(1)`

AUTHOR

Copyright © 1991 by Jef Poskanzer.

9 January 1991

pnmflip

pnmflip—Perform one or more flip operations on a portable anymap

SYNOPSIS

```
pnmflip [-leftright|-lr][-topbottom|-tb][-transpose|-xy][-rotate90|-r90|-ccw ]
[-rotate270|-r270|-cw ][-rotate180|-r180][pnmfile]
```

DESCRIPTION

pnmflip reads a portable anymap as input, performs one or more flip operations in the order specified, and writes out a portable anymap.

OPTIONS

The flip operations available are left for right (`-leftright` or `-lr`); top for bottom (`-topbottom` or `-tb`); and transposition (`-transpose` or `-xy`). In addition, some canned concatenations are available: `-rotate90` or `-ccw` is equivalent to `-transpose -topbottom`; `-rotate270` or `-cw` is equivalent to `-transpose -leftright`; and `-rotate180` is equivalent to `-leftright -topbottom`.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

pnmrotate(1), pnm(5)

AUTHOR

Copyright© 1989 by Jef Poskanzer.

25 July 1989

pnmgamma

pnmgamma—Perform gamma correction on a portable anymap

SYNOPSIS

```
pnmgamma value [pnmfile]
pnmgamma redvalue greenvalue bluevalue [pnmfile]
```

DESCRIPTION

pnmgamma reads a portable anymap as input, performs gamma correction, and produces a portable anymap as output.

The arguments specify what gamma value(s) to use. A value of 1.0 leaves the image alone, less than 1 darkens it, and greater than 1 lightens it.

SEE ALSO

pnm(5)

AUTHOR

Copyright© 1991 by Bill Davidson and Jef Poskanzer.

12 January 1991

pnmhistmap

pnmhistmap—Draw a histogram for a PGM or PPM file

SYNOPSIS

```
pnmhistmap [-black][-white][-max N][-verbose][pnmfile]
```

DESCRIPTION

pnmhistmap reads a portable anymap as input, although bitmap (PBM) input produces an error message and no image, and produces an image showing a histogram of the color (or gray) values in the input. A graymap (PGM) input produces a bitmap output. A pixmap (PPM) input produces pixmap output with three overlaid histograms: a red one for the red input, a green one for the green input, and a blue one for the blue input. The output is fixed in size: 256 pixels wide by 200 pixels high.

OPTIONS

- black Ignores the count of black pixels when scaling the histogram.
- white Ignores the count of white pixels when scaling the histogram.

The -black and -white options, which can be used separately or together, are useful for images with a large percentage of pixels whose value is zero or 255, which can cause the remaining histogram data to become unreadably small. Note that, for pixmap inputs, these options apply to all colors; if, for example, the input has a large number of bright-red areas, you will probably want to use the -white option.

- max N Force the scaling of the histogram to use *N* as the largest-count value. This is useful for inputs with a large percentage of single-color pixels that are not black or white.
- verbose Report the progress of making the histogram, including the largest-count value used to scale the output.

All flags can be abbreviated to their shortest unique prefix.

BUGS

Assumes `maxval` is always 255. Images with a smaller `maxval` will only use the lower-value side of the histogram. This can be overcome either by piping the input through `pnmdepth 255` or by cutting and scaling the lower-value side of the histogram. Neither is a particularly elegant solution.

Should allow the output size to be specified.

SEE ALSO

`pgmhist(1)`, `ppmhist(1)`, `pgm(5)`, `ppm(5)`

AUTHOR

Wilson H. Bent, Jr. (whb@usc.edu).

25 October 1993

pnmindex

pnmindex—Build a visual index of a bunch of anymaps

SYNOPSIS

```
pnmindex [-size N][-across N][-colors N][-black] pnmfile ...
```

DESCRIPTION

This script makes small versions of a bunch of anymaps, adds labels, and concatenates them together into a collage.

OPTIONS

- size Controls how big each image becomes; the default is 100x100.
- across Controls how many images are in each row; the default is six.
- colors Controls how many colors the final index gets quantized to, if quantization is necessary; the default is 256.
- black Controls the color of the padding between the images; normally it's white and the labels are black lettering on white background, but the -black flag reverses this.

SEE ALSO

pnmscale(1), pnmcat(1), pbmtext(1), ppmquant(1), pnm(5)

BUGS

It's very slow.

It's a csh script. csh scripts are not portable to System V. Scripts in general are not portable to non-UNIX environments.

AUTHOR

Copyright © 1991 by Jef Poskanzer.

9 January 1991

pnminvert

pnminvert—Invert a portable anymap

SYNOPSIS

pnminvert [pnmfile]

DESCRIPTION

pnminvert reads a portable anymap as input, inverts it black for white, and produces a portable anymap as output.

SEE ALSO

pnm(5)

AUTHOR

Copyright © 1989 by Jef Poskanzer.

8 August 1989

pnmmargin

pnmmargin—Add a border to a portable anymap

SYNOPSIS

pnmmargin [-white|-black|-color colorspec] size [pnmfile]

DESCRIPTION

pnmmargin reads a portable anymap as input, adds a border of the specified number of pixels, and produces a portable anymap as output.

OPTIONS

You can specify the border color with the `-white`, `-black`, and `-color` flags. If no color is specified, the program makes a guess.

SEE ALSO

`pnm(5)`

BUGS

It's a script. Scripts are not portable to non-UNIX environments.

AUTHOR

Copyright © 1991 by Jef Poskanzer.

9 January 1991

pnmnlfilt

`pnmnlfilt` - Nonlinear filters: smooth, alpha trim mean, optimal estimation smoothing, edge enhancement.

SYNOPSIS

`pnmnlfilt alpha radius [pnmfile]`

DESCRIPTION

This is something of a Swiss army knife filter. It has three distinct operating modes. In all of the modes, each pixel in the image is examined and processed according to it and its surrounding pixels values. Rather than using the nine pixels in a 3×3 block, seven hexagonal area samples are taken, the size of the hexagons being controlled by the `radius` parameter. A `radius` value of 0.3333 means that the seven hexagons exactly fit into the center pixel (that is, there will be no filtering effect). A `radius` value of 1.0 means that the seven hexagons exactly fit a 3×3 pixel array.

ALPHA-TRIMMED MEAN FILTER (0.0 ≤ alpha ≤ 0.5)

The value of the center pixel will be replaced by the mean of the seven hexagon values, but the seven values are sorted by size and the top and bottom alpha portion of the seven are excluded from the mean. This implies that an alpha value of 0.0 gives the same sort of output as a normal convolution (that is, averaging or smoothing filter), where `radius` will determine the “strength” of the filter. A good value to start from for subtle filtering is `alpha = 0.0`, `radius = 0.55`. For a more blatant effect, try `alpha = 0.0` and `radius = 1.0`.

An alpha value of 0.5 will cause the median value of the seven hexagons to be used to replace the center pixel value. This sort of filter is good for eliminating “pop” or single pixel noise from an image without spreading the noise out or smudging features on the image. Judicious use of the `radius` parameter will fine-tune the filtering. Intermediate values of alpha give effects somewhere between smoothing and “pop” noise reduction. For subtle filtering, try starting with values of `alpha = 0.4`, `radius = 0.6`. For a more blatant effect, try `alpha = 0.5`, `radius = 1.0`.

OPTIMAL ESTIMATION SMOOTHING. (1.0 ≤ alpha ≤ 2.0)

This type of filter applies a smoothing filter adaptively over the image. For each pixel, the variance of the surrounding hexagon values is calculated, and the amount of smoothing is made inversely proportional to it. The idea is that if the variance is small, then it is due to noise in the image, while if the variance is large, it is because of “wanted” image features. As usual, the `radius` parameter controls the effective radius, but it probably advisable to leave the `radius` between 0.8 and 1.0 for the variance calculation to be meaningful. The alpha parameter sets the noise threshold, over which less smoothing will be done. This means that small values of alpha will give the most subtle filtering effect, while large values will tend to smooth all parts of the image. You could start with values like `alpha = 1.2`, `radius = 1.0` and try increasing or decreasing the alpha parameter to get the desired effect. This type of filter is best for filtering out dithering noise in both bitmap and color images.

EDGE ENHANCEMENT. (-0.1 >= alpha >= -0.9)

This is the opposite type of filter to the smoothing filter. It enhances edges. The `alpha` parameter controls the amount of edge enhancement, from subtle (-0.1) to blatant (-0.9). The `radius` parameter controls the effective radius as usual, but useful values are between 0.5 and 0.9. Try starting with values of `alpha` = 0.3, `radius` = 0.8.

COMBINATION USE

The various modes of `pnmnlfilt` can be used one after the other to get the desired result. For instance to turn a monochrome dithered image into a grayscale image, you could try one or two passes of the smoothing filter, followed by a pass of the optimal estimation filter, then some subtle edge enhancement. Note that using edge enhancement is only likely to be useful after one of the nonlinear filters (alpha-trimmed mean or optimal estimation filter), as edge enhancement is the direct opposite of smoothing.

For reducing color quantization noise in images (that is, turning GIF files back into 24-bit files), you could try a pass of the optimal estimation filter (`alpha` 1.2, `radius` 1.0), a pass of the median filter (`alpha` 0.5, `radius` 0.55), and possibly a pass of the edge enhancement filter. Several passes of the optimal estimation filter with declining `alpha` values are more effective than a single pass with a large `alpha` value. As usual, there is a tradeoff between filtering effectiveness and loosing detail. Experimentation is encouraged.

REFERENCES

The alpha-trimmed mean filter is based on the description in *IEEE CG&A*, May 1990, page 23, by Mark E. Lee and Richard A. Redner, and has been enhanced to allow continuous alpha adjustment.

The optimal estimation filter is taken from an article “Converting Dithered Images Back to Grayscale” by Allen Stenger, *Dr. Dobbs's Journal*, November 1992, and this article references “Digital Image Enhancement and Noise Filtering by Use of Local Statistics” by Jong-Sen Lee, *IEEE Transactions on Pattern Analysis and Machine Intelligence*, March 1980.

The edge enhancement details are from `pgmenhance(1)`, which is taken from Philip R. Thompson's `xim` program, which in turn took it from Section 6 of “Digital Halftones by Dot Diffusion” by D. E. Knuth, *ACM Transaction on Graphics* Vol. 6, No. 4, October 1987, which in turn got it from two 1976 papers by J. F. Jarvis et al.

SEE ALSO

`pgmenhance(1)`, `pnmconvol(1)`, `pnm(5)`

BUGS

Integers and tables may overflow if `PPM_MAXMAXVAL` is greater than 255.

AUTHOR

Graeme W. Gill (`graeme@labtam.oz.au`).

5 February 1993

pnmnoraw

`pnmnoraw`—Force a portable anymap into plain format

SYNOPSIS

`pnmnoraw` [`pnmfile`]

DESCRIPTION

`pnmnoraw` reads a portable anymap as input and writes it out in plain (nonraw) format. This is fairly useless if you haven't defined the `PBPLUS_RAWBITS` compile-time option.

SEE ALSO

`pnm(5)`

AUTHOR

Copyright © 1991 by Jef Poskanzer.

8 January 1991

pnmpad

`pnmpad`—Add borders to portable anymap

SYNOPSIS

```
pnmpad [-white|-black] [-l#] [-r#] [-t#] [-b#] [pnmfile]
```

DESCRIPTION

`pnmpad` reads a portable anymap as input and outputs a portable anymap with extra borders of the sizes specified. The color of the borders can be set to black or white (default black).

SEE ALSO

`pbmmake(1)`, `pnmpaste(1)`, `pbm(5)`

AUTHOR

Copyright © 1990 by Angus Duggan. Copyright © 1989 by Jef Poskanzer.

pnmpaste

`pnmpaste`—Paste a rectangle into a portable anymap

SYNOPSIS

```
pnmpaste [-replace|-or|-and |-xor] frompnmfile x y [intopnmfile]
```

DESCRIPTION

`pnmpaste` reads two portable anymaps as input, inserts the first anymap into the second at the specified location, and produces a portable anymap the same size as the second as output. If the second anymap is not specified, it is read from `stdin`. The `x` and `y` can be negative, in which case they are interpreted relative to the right and bottom of the anymap, respectively.

This tool is most useful in combination with `pnmcut`. For instance, if you want to edit a small segment of a large image, and your image editor cannot edit the large image, you can cut out the segment you are interested in, edit it, and then paste it back in.

Another useful companion tool is `pbmmask`.

The optional flag specifies the operation to use when doing the paste. The default is `-replace`. The other logical operations are only allowed if both input images are bitmaps. These operations act as if white is `TRUE` and black is `FALSE`.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

`pnmcut(1)`, `pnminvert(1)`, `pnmarith(1)`, `pnm(5)`, `pbm(5)`, `pbm(5)`

AUTHOR

Copyright © 1989, 1991 by Jef Poskanzer.

21 February 1991

pnmrotate

pnmrotate—Rotate a portable anymap by some angle

SYNOPSIS

```
pnmrotate [-noantialias] angle [pnmfile]
```

DESCRIPTION

pnmrotate reads a portable anymap as input, rotates it by the specified angle, and produces a portable anymap as output. If the input file is in color, the output will be, too; otherwise, it will be grayscale. The angle is in degrees (floating-point), measured counter-clockwise. It can be negative, but it should be between -90 and 90. Also, for rotations greater than 45 degrees you may get better results if you first use `pnmflip` to do a 90-degree rotation and then `pnmrotate` less than 45 degrees back the other direction.

The rotation algorithm is Alan Paeth's three-shear method. Each shear is implemented by looping over the source pixels and distributing fractions to each of the destination pixels. This has an antialiasing effect—it avoids jagged edges and similar artifacts. However, it also means that the original colors or gray levels in the image are modified. If you need to keep precisely the same set of colors, you can use the `-noantialias` flag. This does the shearing by moving pixels without changing their values. If you want antialiasing and don't care about the precise colors, but still need a limited **number** of colors, you can run the result through `ppmquant`.

All flags can be abbreviated to their shortest unique prefix.

REFERENCES

"A Fast Algorithm for General Raster Rotation" by Alan Paeth, *Graphics Interface '86*, pages 77–81.

SEE ALSO

```
pnmshear(1), pnmflip(1), pnm(5), ppmquant(1)
```

AUTHOR

Copyright © 1989, 1991 by Jef Poskanzer.

12 January 1991

pnmscale

pnmscale—Scale a portable anymap

SYNOPSIS

```
pnmscale s [pnmfile]
pnmscale -xsize|-width|-ysize|-height s [pnmfile]
pnmscale -xscale|-yscale s [pnmfile]
pnmscale -xscale|-xsize|-width s -yscale|-ysize|-height s [pnmfile]
pnmscale -ysize x y [pnmfile]
pnmscale -pixels n [pnmfile]
```

DESCRIPTION

`pnmscale` reads a portable anymap as input, scales it by the specified factor or factors, and produces a portable anymap as output. If the input file is in color, the output will be, too; otherwise, it will be grayscale. You can both enlarge (scale factor > 1) and reduce (scale factor < 1).

You can specify one dimension as a pixel size, and the other dimension will be scaled correspondingly.

You can specify one dimension as a scale, and the other dimension will not be scaled.

You can specify different sizes or scales for each axis.

You can use the special `-ysize` flag, which fits the image into the specified size without changing the aspect ratio.

Or, you can use the `-pixels` flag, which fits the image into the specified number of pixels without changing the aspect ratio.

All flags can be abbreviated to their shortest unique prefix.

If you enlarge by a factor of three or more, you should probably add a `pnmsmooth` step; otherwise, you can see the original pixels in the resulting image.

SEE ALSO

`pbmreduce(1)`, `pnmenlarge(1)`, `pnmsmooth(1)`, `pnm(5)`

AUTHOR

Copyright © 1989, 1991 by Jef Poskanzer.

12 January 1991

pnmshear

`pnmshear`—Shear a portable anymap by some angle

SYNOPSIS

```
pnmshear [-noantialias] angle [pnmfile]
```

DESCRIPTION

`pnmshear` reads a portable anymap as input, shears it by the specified angle, and produces a portable anymap as output. If the input file is in color, the output will be too; otherwise, it will be grayscale. The angle is in degrees (floating-point), and measures this:

```
+-----+ +-----+
|      |
|      |
| OLD  || NEW  \
|      ||
| an   \
+-----+ | g1e+-----+
```

If the angle is negative, it shears the other way:

```
+-----+ | -an+-----+
|      |
| g1   /
| OLD  || e/ NEW  /
|      ||
|      /
+-----+ +-----+
```

The angle should not get too close to 90 or -90, or the resulting anymap will be unreasonably wide.

The shearing is implemented by looping over the source pixels and distributing fractions to each of the destination pixels. This has an antialiasing effect—it avoids jagged edges and similar artifacts. However, it also means that the original colors or gray levels in the image are modified. If you need to keep precisely the same set of colors, you can use the `-noantialias` flag.

This does the shearing by moving pixels without changing their values. If you want antialiasing and don't care about the precise colors, but still need a limited **number** of colors, you can run the result through `ppmquant`.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

`pnmrotate(1)`, `pnmflip(1)`, `pnm(5)`, `ppmquant(1)`

AUTHOR

Copyright © 1989, 1991 by Jef Poskanzer.

12 January 1991

pnmsmooth

`pnmsmooth`—Smooth out an image

SYNOPSIS

`pnmsmooth [pnmfile]`

DESCRIPTION

`pnmsmooth` smooths out an image by replacing each pixel with the average of its nine immediate neighbors. It is implemented as a simple script using `pnmconvol`.

SEE ALSO

`pnmconvol(1)`, `pnm(5)`

BUGS

It's a script. Scripts are not portable to non-UNIX environments.

AUTHOR

Copyright © 1989, 1991 by Jef Poskanzer

13 January 1991

pnmtile

`pnmtile`—Replicate a portable anymap into a specified size

SYNOPSIS

`pnmtile width height [pnmfile]`

DESCRIPTION

`pnmtile` reads a portable anymap as input, replicates it until it is the specified size, and produces a portable anymap as output.

SEE ALSO

`pnm(5)`

AUTHOR

Copyright © 1989 by Jef Poskanzer.

13 May 1989

pnmtoddif

pnmtoddif—Convert a portable anymap to DDIF format

SYNTAX

```
pnmtoddif pnmtoddif [-resolution x y] [pnmfile [ddiffile]]
```

OPTIONS

resolution x y	The horizontal and vertical resolution of the output image in dots per inch. Defaults to 78dpi.
pnmfile	The filename for the image file in PNM format. If this argument is omitted, input is read from stdin.
ddiffile	The filename for the image file to be created in DDIF format. If this argument is omitted, the ddiffile is written to standard output. It can only specified if a pnmfile is also specified.

DESCRIPTION

pnmtoddif takes a portable anymap from standard input and converts it into a DDIF image file on standard output or the specified DDIF file.

PBM format (bitmap) data is written as 1-bit DDIF, PGM format data (grayscale) as 8-bit grayscale DDIF, and PPM format data is written as 8,8,8-bit color DDIF. All DDIF image files are written as uncompressed. The data plane organization is interleaved by pixel.

In addition to the number of pixels in the width and height dimension, DDIF images also carry information about the size that the image should have, that is, the physical space that a pixel occupies. PBMPLUS images do not carry this information, hence it has to be externally supplied. The default of 78dpi has the beneficial property of not causing a resize on most Digital Equipment Corporation color monitors.

AUTHOR

Burkhard Neidecker-Lutz
Digital Equipment Corporation, CEC Karlsruhe
neideck@nestvx.enet.dec.com

pnmtofits

pnmtofits—Convert a portable anymap into FITS format

SYNOPSIS

```
pnmtofits [-max f][-min f][pnmfile]
```

DESCRIPTION

pnmtofits reads a portable anymap as input and produces a FITS (Flexible Image Transport System) file as output. The resolution of the output file is either 8 bits/pixel, or 16 bits/pixel, depending on the value of maxval in the input file. If the input file is a portable bitmap or a portable graymap, the output file consists of a single plane image (NAXIS = 2). If instead the input file is a portable pixmap, the output file will consist of a three-plane image (NAXIS = 3, NAXIS3 = 3). A full description of the FITS format can be found in *Astronomy & Astrophysics Supplement Series 44* (1981), page 363.

OPTIONS

Flags -min and -max can be used to set DATAMAX, DATAMIN, BSCALE, and BZERO in the FITS header, but do not cause the data to be rescaled.

SEE ALSO

fitstopnm(1), pgm(5)

AUTHOR

Copyright © 1989 by Wilson H. Bent (whb@hoh-2.att.com), with modifications by Alberto Accomazzi (alberto@cfa.harvard.edu).

5 December 1992

pnmtops

pnmtops—Convert portable anymap to PostScript

SYNOPSIS

```
pnmtops [-scale s][-turn|-noturn][-rle|-runlength][-dpi n][-width n][-height n]
[-center|-nocenter][pnmfile]
```

DESCRIPTION

pnmtops reads a portable anymap as input and produces encapsulated PostScript as output.

If the input file is in color (PPM), a color PostScript file gets written. Some PostScript interpreters can't handle color PostScript. If you have one of these, you will need to run your image through `ppmtopgm` first.

Note that there is no `pstopnm` tool; this transformation is one-way, because a `pstopnm` tool would be a full-fledged PostScript interpreter, which is beyond the scope of this package. However, see the `psidtopgm` tool, which can read grayscale non-run-length PostScript image data. Also, if you're willing to install the fairly large GhostScript package, it comes with a `pstopm script`.

OPTIONS

The `-scale` flag controls the scale of the result. The default scale is 1, which on a 300dpi printer such as the Apple LaserWriter makes the output look about the same size as the input would if it was displayed on a typical 72dpi screen. To get one PNM pixel per 300dpi printer pixel, use `-scale 0.25`.

The `-turn` and `-noturn` flags control whether the image gets turned 90 degrees. Normally, if an image is wider than it is tall, it gets turned automatically to better fit the page. If the `-turn` flag is specified, it will be turned no matter what its shape; and if the `-noturn` flag is specified, it will not be turned no matter what its shape.

The `-rle` or `-runlength` flag specifies run-length compression. This may save time if the host-to-printer link is slow; but normally the printer's processing time dominates, so `-rle` makes things slower.

The `-dpi` flag lets you specify the dots per inch of your output device. The default is 300dpi. In theory PostScript is device-independent and you don't have to worry about this, but in practice its raster rendering can have unsightly bands if the device pixels and the image pixels aren't in sync.

The `-width` and `-height` flags let you specify the size of the page. The default is 8.5 inches by 11 inches.

With the `-nocenter` flag, the output is not centered on the page; it appears in the upper-left corner. This is useful for programs that can include PostScript files, but can't cope with pictures that are not positioned in the upper-left corner. The default is `-center`--the image is centered on the page.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

`pnm(5)`, `psidtopgm(1)`

AUTHOR

Copyright © 1989, 1991 by Jef Poskanzer. Modified November 1993 by Wolfgang Stuerzlinger (wrz1@gup.uni-linz.ac.at).

26 October 1991

pnmtorast

pnmtorast—Convert a portable pixmap into a Sun raster file

SYNOPSIS

```
pnmtorast [-standard|-rle][pnmfile]
```

DESCRIPTION

pnmtorast reads a portable pixmap as input and produces a Sun raster file as output.

Color values in Sun raster files are eight bits wide, so pnmtorast will automatically scale colors to have a `maxval` of 255. An extra `pnmddepth` step is not necessary.

OPTIONS

The `-standard` flag forces the result to be in `RT_STANDARD` form; the `-rle` flag, `RT_BYTE_ENCODED`, which is smaller but, well, less standard. The default is `-rle`.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

`rasttopnm(1)`, `pnm(5)`

AUTHOR

Copyright © 1989, 1991 by Jef Poskanzer.

12 January 1991

pnmtosgi

pnmtosgi—Convert a portable anymap to an SGI image file

SYNOPSIS

```
pnmtosgi [-verbatim|-rle][-imagename Name][pnmfile]
```

DESCRIPTION

pnmtosgi reads a portable anymap as input and produces an SGI image file as output. The SGI image will be two-dimensional (one channel) for PBM and PGM input, and three-dimensional (three channels) for PPM.

OPTIONS

<code>-verbatim</code>	Write an uncompressed file.
<code>-rle</code> (default)	Write a compressed (run-length-encoded) file.
<code>-imagename name</code>	Write the string <code>name</code> into the <code>imagename</code> field of the header. The name string is limited to 79 characters. If no name is given, pnmtosgi writes no <code>name</code> into this field.

BUGS

Probably.

REFERENCES

SGI image file format documentation (draft v0.95) by Paul Haeberli (paul@sgi.com). Available via FTP at [sgi.com:graphics/SGIIMAGESPEC](ftp://sgi.com:graphics/SGIIMAGESPEC).

SEE ALSO

pnm(5), sgitopnm(1)

AUTHOR

Copyright © 1994 by Ingo Wilken (Ingo.Wilken@informatik.uni-oldenburg.de).

29 January 1994

pnmtosir

pnmtosir—Convert a portable anymap into a Solitaire format

SYNOPSIS

pnmtosir [pnmfile]

DESCRIPTION

pnmtosir reads a portable anymap as input and produces a Solitaire image recorder format.

pnmtosir produces an MGI TYPE 17 file for PBM and PGM files. For ppm, it writes an MGI TYPE 11 file.

SEE ALSO

sirtopnm(1), pnm(5)

AUTHOR

Copyright © 1991 by Marvin Landis.

20 March 1991

pnmtotiff

pnmtotiff—Convert a portable anymap into a TIFF file

SYNOPSIS

```
pnmtotiff [-none|-packbits|-lzw|-g3|-g4][-2d][-fill][-predictor n]
          [-msb2lsb|-lsb2msb] [-rowsperstrip n][pnmfile]
```

DESCRIPTION

pnmtotiff reads a portable anymap as input. Produces a TIFF file as output.

OPTIONS

By default, `pnmtotiff` creates a TIFF file with LZW compression. This is your best bet most of the time. However, some TIFF readers can't deal with it. If you want to try another compression scheme or tweak some of the other even more obscure output options, there are a number of flags to play with.

The `-none`, `-packbits`, `-lzw`, `-g3`, and `-g4` options are used to override the default and set the compression scheme used in creating the output file. The CCITT Group 3 and Group 4 compression algorithms can only be used with bilevel data. The `-2d` and `-fill` options are meaningful only with Group 3 compression: `-2d` requests two-dimensional encoding, while `-fill` requests that each encoded scanline be zero-filled to a byte boundary. The `-predictor` option is only meaningful with LZW compression: a predictor value of 2 causes each scanline of the output image to undergo horizontal differencing before it is encoded; a value of 1 forces each scanline to be encoded without differencing. By default, `pnmtotiff` creates a TIFF file with `msb-to-lsb` fill order. The `-msb2lsb` and `-lsb2msb` options are used to override the default and set the fill order used in creating the file. The `-rowsperstrip` option can be used to set the number of rows (scanlines) in each strip of data in the

output file. By default, the output file has the number of rows per strip set to a value that will ensure each strip is no more than eight kilobytes long.

BUGS

This program is not self-contained. To use it you must fetch the TIFF Software package listed in the `OTHER.SYSTEMS` file and configure `PBMPLUS` to use `libtiff`. See `PBM-PLUS`'s Makefile for details on this configuration.

SEE ALSO

`tifftopnm(1)`, `pnm(5)`

AUTHOR

Derived by Jef Poskanzer from `ras2tiff.c`, which is Copyright© 1990 by Sun Microsystems, Inc. Author: Patrick J. Naughton (`naughton@wind.sun.com`).

13 January 1991

pnmtoxwd

`pnmtoxwd`—Convert a portable anymap into an X11 window dump

SYNOPSIS

```
pnmtoxwd [-pseudodepth n][directcolor][pnmfile]
```

DESCRIPTION

`pnmtoxwd` reads a portable anymap as input and produces an X11 window dump as output. This window dump can be displayed using the `xwud` tool.

Normally, `pnmtoxwd` produces a StaticGray dump file for PBM and PGM files. For ppm, it writes a PseudoColor dump file if there are up to 256 colors in the input, and a DirectColor dump file otherwise. The `-directcolor` flag can be used to force a DirectColor dump. The `-pseudodepth` flag can be used to change the depth of PseudoColor dumps from the default of 8 bits/256 colors.

SEE ALSO

`xwdtopnm(1)`, `pnm(5)`, `xwud(1)`

AUTHOR

Copyright© 1989, 1991 by Jef Poskanzer.

24 September 1991

ppm3d

`ppm3d`—Convert two portable pixmap into a red/blue 3D glasses pixmap

SYNOPSIS

```
ppm3d leftppmfile rightppmfile [horizontal_offset]
```

DESCRIPTION

`ppm3d` reads two portable pixmaps as input and produces a portable pixmap as output, with the images overlapping by `horizontal_offset` pixels in blue/red format.

`horizontal_offset` defaults to 30 pixels. Pixmaps *must* be the same size.

SEE ALSO

ppm(5)

AUTHOR

Copyright © 1993 by David K. Drum.

2 November 1993

ppmbrighten

ppmbrighten—Change an image's saturation and value from an HSV map

SYNOPSIS

```
ppmbrighten [-n] [-s <+- saturation>] [-v <+- value>] <ppmfile>
```

DESCRIPTION

ppmbrighten reads a portable pixmap as input, converts the image from RGB space to HSV space, and changes the value by <+- value> as a percentage; the same with the saturation. Use

```
ppmbrighten -v 100
```

to add 100 percent to the value.

The `n` option normalizes the value to exist between 0 and 1 (normalized).

SEE ALSO

pgmnorm(1), ppm(5)

AUTHOR

Copyright© 1990 by Brian Moffet. Copyright© 1989 by Jef Poskanzer.

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, provided that the above copyright notice appear in all copies and that both that copyright notice and this permission notice appear in supporting documentation. This software is provided “as is” without express or implied warranty.

NOTES

This program does not change the number of colors.

20 November 1990

ppmchange

ppmchange—Change all pixels of one color to another in a portable pixmap

SYNOPSIS

```
ppmchange oldcolor newcolor [...] [ppmfile]
```

DESCRIPTION

ppmchange reads a portable pixmap as input and changes all pixels of `oldcolor` to `newcolor`, leaving all others unchanged. Up to 256 colors may be replaced by specifying couples of colors on the command line.

The colors can be specified in five ways:

- A name, assuming that a pointer to an X11-style color names file was compiled in.
- An X11-style hexadecimal specifier: `rgb:r/g/b`, where `r`, `g`, and `b` are each 1- to 4-digit hexadecimal numbers.
- An X11-style decimal specifier: `rgb:r/g/b`, where `r`, `g`, and `b` are floating-point numbers between 0 and 1.
- For backwards compatibility, an old-X11-style hexadecimal number: `#rgb`, `#rrggbb`, `#rrrgggbbb`, or `#rrrrggggbbbb`.
- For backwards compatibility, a triplet of numbers separated by commas: `r,g,b`, where `r`, `g`, and `b` are floating-point numbers between 0 and 1. (This style was added before MIT came up with the similar `rgbi` style.)

SEE ALSO

`pgmtoppm(1)`, `ppm(5)`

AUTHOR

Wilson H. Bent, Jr. (whb@usc.edu), with modifications by Alberto Accomazzi (alberto@cfa.harvard.edu).

3 December 1993

ppmdim

`ppmdim`—Dim a portable pixmap down to total blackness

SYNOPSIS

```
ppmdim dimfactor [ppmfile]
```

DESCRIPTION

`ppmdim` reads a portable pixmap as input and diminishes its brightness by the specified `dimfactor` down to total blackness. The `dimfactor` may be in the range from 0.0 (total blackness, deep night, nada, null, nothing) to 1.0 (original picture's brightness).

As `pnngamma` does not do the brightness correction in the way I wanted it, I wrote this small program.

`ppmdim` is similar to `ppmbrighten`, but not exactly the same.

SEE ALSO

`ppm(5)`, `ppmflash(1)`, `pnngamma(1)`, `ppmbrighten(1)`

AUTHOR

Copyright© 1993 by Frank Neumann.

16 November 1993

ppmdist

`ppmdist`—Simplistic grayscale assignment for machine-generated color images

SYNOPSIS

```
ppmdist [-intensity|-frequency][ppmfile]
```

DESCRIPTION

`ppmdist` reads a portable pixmap as input and performs a simplistic grayscale assignment intended for use with grayscale or bitmap printers.

Often conversion from ppm to pgm will yield an image with contrast too low for good printer output. The program maximizes contrast between the gray levels' output.

A ppm input of n colors is read, and a pgm of n gray levels is written. The gray levels take on the values $0 \dots n-1$, while `maxval` takes on $n-1$.

The mapping from color to stepped grayscale can be performed in order of input pixel intensity, or input pixel frequency (number of repetitions).

OPTIONS

- `-frequency` Sort input colors by the number of times a color appears in the input, before mapping to evenly distributed gray levels of output.
- `-intensity` Sort input colors by their grayscale intensity, before mapping to evenly distributed gray levels of output. This is the default.

BUGS

Helpful only for images with a very small number of colors. Perhaps should have been an option to `ppmtopgm(1)`.

SEE ALSO

`ppmtopgm(1)`, `ppmhist(1)`, `ppm(5)`

AUTHOR

Copyright© 1993 by Dan Stromberg.

22 July 1992

ppmdither

ppmdither—Ordered dither for color images

SYNOPSIS

`ppmdither [-dim dimension] [-red shades] [-green shades] [-blue shades] [ppmfile]`

DESCRIPTION

`ppmdither` reads a portable pixmap as input, and applies dithering to it to reduce the number of colors used down to the specified number of shades for each primary. The default number of shades is `red=5`, `green=9`, `blue=5`, for a total of 225 colors. To convert the image to a binary RGB format suitable for color printers, use `-red 2 -green 2 -blue 2`. The maximum number of colors that can be used is 256 and can be computed as the product of the number of red, green, and blue shades.

OPTIONS

- `-dim dimension` The size of the dithering matrix. Must be a power of 2.
- `-red shades` The number of red shades to be used; minimum of 2.
- `-green shades` The number of green shades to be used; minimum of 2.
- `-blue shades` The number of blue shades to be used; minimum of 2.

SEE ALSO

`pnmdepth(1)`, `ppmquant(1)`, `ppm(5)`

AUTHOR

Copyright© 1991 by Christos Zoulas.

14 July 1991

ppmflash

ppmflash—Brighten a picture up to complete white-out

SYNOPSIS

```
ppmflash flashfactor [ppmfile]
```

DESCRIPTION

ppmflash reads a portable pixmap as input and increases its brightness by the specified `flashfactor` up to a total white-out image. The `flashfactor` may be in the range from 0.0 (original picture's brightness) to 1.0 (full white-out, The Second After).

As `pnmgamma` does not do the brightness correction in the way I wanted it, I wrote this small program.

This program is similar to `ppmbrighten`, but not exactly the same.

SEE ALSO

`ppm(5)`, `ppmdim(1)`, `pnmgamma(1)`, `ppmbrighten(1)`

AUTHOR

Copyright© 1993 by Frank Neumann.

16 November 1993

ppmforge

ppmforge—Fractal forgeries of clouds, planets, and starry skies

SYNOPSIS

```
ppmforge [-clouds] [-night] [-dimension dimen] [-hour hour] [-inclination| -tilt angle]
[-mesh size] [-power factor] [-glaciers level] [-ice level] [-saturation sat]
[-seed seed] [-stars fraction] [-xsize| -width width] [-ysize| -height height]
```

DESCRIPTION

ppmforge generates three kinds of “random fractal forgeries,” the term coined by Richard F. Voss of the IBM Thomas J. Watson Research Center for seemingly realistic pictures of natural objects generated by simple algorithms embodying randomness and fractal self-similarity. The techniques used by ppmforge are essentially those given by Voss, particularly the technique of spectral synthesis explained in more detail by Dietmar Saupe. (The “See Also” subsection provides more detailed information about these men’s work.)

The program generates two varieties of pictures, planets and clouds, which are just different renderings of data generated in an identical manner, illustrating the unity of the fractal structure of these very different objects. A third type of picture, a starry sky, is synthesized directly from pseudorandom numbers.

The generation of planets or clouds begins with the preparation of an array of random data in the frequency domain. The size of this array, the *mesh size*, can be set with the `-mesh` option; the larger the mesh, the more realistic the pictures, but the calculation time and memory requirement increases as the square of the mesh size. The fractal dimension, which you can specify with the `-dimension` option, determines the roughness of the terrain on the planet or the scale of detail in the clouds. As the fractal dimension is increased, more high frequency components are added into the random mesh.

After the mesh is generated, an inverse two-dimensional Fourier transform is performed upon it. This converts the original random frequency domain data into spatial amplitudes. You scale the real components that result from the Fourier transform into numbers from 0 to 1 associated with each point on the mesh. You can further modify this number by applying a *power law scale* to it with the `-power` option. Unity scale leaves the numbers unmodified; a power scale of 0.5 takes the square root

of the numbers in the mesh, while a power scale of 3 replaces the numbers in the mesh with their cubes. Power law scaling is best envisioned by thinking of the data as representing the elevation of terrain; powers less than one yield landscapes with vertical scarps that look like glacial-carved valleys; powers greater than one make fairy-castle spires (which require large mesh sizes and high resolution for best results).

After these calculations, you have an array of the specified size containing numbers that range from 0 to 1. The pixmaps are generated as follows:

- Clouds** A color map is created that ranges from pure blue to white by increasing admixture (desaturation) of blue with white. Numbers less than 0.5 are colored blue, and numbers between 0.5 and 1.0 are colored with corresponding levels of white, with 1.0 being pure white.
- Planet** The mesh is projected onto a sphere. Values less than 0.5 are treated as water and values between 0.5 and 1.0 as land. The water areas are colored based on the water depth; land, based on its elevation. The random depth data are used to create clouds over the oceans. An atmosphere approximately like the Earth's is simulated; its light absorption is calculated to create a blue cast around the limb of the planet. A function that rises from 0 to 1 based on latitude is modulated by the local elevation to generate polar ice caps—high altitude terrain carries glaciers farther from the pole. Based on the position of the star with respect to the observer, the apparent color of each pixel of the planet is calculated by ray-tracing from the star to the planet to the observer and applying a lighting model that sums ambient light and diffuse reflection (for most planets ambient light is zero, as their primary star is the only source of illumination). Additional random data are used to generate stars around the planet.
- Night** A sequence of pseudorandom numbers is used to generate stars with a user-specified density.

Cloud pictures always contain 256 or fewer colors and may be displayed on most color-mapped devices without further processing. Planet pictures often contain tens of thousands of colors that must be compressed with `ppmquant` or `ppmdither` before encoding in a color-mapped format. If the display resolution is high enough, `ppmdither` generally produces better-looking planets. `ppmquant` tends to create discrete color bands, particularly in the oceans, which are unrealistic and distracting. The number of colors in starry sky pictures generated with the `-night` option depends on the value specified for `-saturation`. Small values limit the color temperature distribution of the stars and reduce the number of colors in the image. If the `-saturation` is set to 0, none of the stars will be colored and the resulting image will never contain more than 256 colors. Night sky pictures with many different star colors often look best when color-compressed by `pnmdepth` rather than `ppmquant` or `ppmdither`. Try `newmaxval` settings of 63, 31, or 15 with `pnmdepth` to reduce the number of colors in the picture to 256 or fewer.

OPTIONS

- `-clouds` Generate clouds. A pixmap of fractal clouds is generated. Selecting clouds sets the default for fractal dimension to 2.15 and power scale factor to 0.75.
- `-dimension dimen` Sets the fractal dimension to the specified `dimen`, which may be any floating-point value between 0 and 3. Higher fractal dimensions create more “chaotic” images, which require higher resolution output and a larger FFT mesh size to look good. If no dimension is specified, 2.4 is used when generating planets and 2.15 for clouds.
- `-glaciers level` The floating-point `level` setting controls the extent to which terrain elevation causes ice to appear at lower latitudes. The default value of 0.75 makes the polar caps extend toward the equator across high terrain and forms glaciers in the highest mountains, as on Earth. Higher values make ice sheets that cover more and more of the land surface, simulating planets in the midst of an ice age. Lower values tend to be boring, resulting in unrealistic geometrically precise ice cap boundaries.
- `-hour hour` When generating a planet, `hour` is used as the hour angle at the central meridian. If you specify `-hour 12`, for example, the planet will be fully illuminated, corresponding to high noon at the longitude at the center of the screen. You can specify any floating-point value between 0 and 24 for `hour`, but values which place most of the planet in darkness (0 to 4 and 20 to 24) result in crescents which, while pretty, don't give you many illuminated pixels for the amount of computing that's required. If no `-hour` option is specified, a random hour angle is chosen, biased so that only 25 percent of the images generated will be crescents.

<code>-ice level</code>	Sets the extent of the polar ice caps to the given floating-point <code>level</code> . The default level of 0.4 produces ice caps similar to those of the Earth. Smaller values reduce the amount of ice, while larger <code>-ice</code> settings create more prominent ice caps. Sufficiently large values, such as 100 or more, in conjunction with small settings for <code>-glaciers</code> (try 0.1) create “ice balls” like Europa.
<code>-inclination -tilt angle</code>	The inclination angle of the planet with regard to its primary star is set to <code>angle</code> , which can be any floating-point value from -90 to 90. The inclination angle can be thought of as specifying, in degrees, the “season” the planet is presently experiencing or, more precisely, the latitude at which the star transits the zenith at local noon. If 0, the planet is at equinox; the star is directly overhead at the equator. Positive values represent summer in the northern hemisphere, negative values summer in the southern hemisphere. The Earth’s inclination angle, for example, is about 23.5 at the June solstice, 0 at the equinoxes in March and September, and -23.5 at the December solstice. If no inclination angle is specified, a random value between -21.6 and 21.6 degrees is chosen.
<code>-mesh size</code>	A mesh of <code>size</code> by <code>size</code> will be used for the fast Fourier transform (FFT). Note that memory requirements and computation speed increase as the square of <code>size</code> ; if you double the mesh size, the program will use four times the memory and run four times as long. The default mesh is 256x256, which produces reasonably good looking pictures while using half a megabyte for the 256x256 array of single precision complex numbers required by the FFT. On machines with limited memory capacity, you may have to reduce the mesh size to avoid running out of RAM. Increasing the mesh size produces better looking pictures; the difference becomes particularly noticeable when generating high-resolution images with relatively high fractal dimensions (between 2.2 and 3).
<code>-night</code>	A starry sky is generated. The stars are created by the same algorithm used for the stars that surround planet pictures, but the output consists exclusively of stars.
<code>-power factor</code>	Sets the power factor used to scale elevations synthesized from the FFT to <code>factor</code> , which can be any floating-point number greater than zero. If no factor is specified, a default of 1.2 is used if a planet is being generated, or 0.75 if clouds are selected by the <code>-clouds</code> option. The result of the FFT image synthesis is an array of elevation values between 0 and 1. A nonunity power factor exponentiates each of these elevations to the specified power. For example, a power factor of 2 squares each value, while a power factor of 0.5 replaces each with its square root. (Note that exponentiating values between 0 and 1 yields values that remain within that range.) Power factors less than 1 emphasize large-scale elevation changes at the expense of small variations. Power factors greater than 1 increase the roughness of the terrain and, like high fractal dimensions, may require a larger FFT mesh size or higher screen resolution to look good.
<code>-saturation sat</code>	Controls the degree of color saturation of the stars that surround planet pictures and fill starry skies created with the <code>-night</code> option. The default value of 125 creates stars that resemble the sky as seen by the human eye from Earth’s surface. Stars are dim; only the brightest activate the cones in the human retina, causing color to be perceived. Higher values of <code>sat</code> approximate the appearance of stars from Earth orbit, where better dark adaptation, absence of sky glow, and the concentration of light from a given star onto a smaller area of the retina thanks to the lack of atmospheric turbulence enhances the perception of color. Values greater than 250 create “science fiction” skies that, while pretty, don’t occur in this universe. Thanks to the inverse square law combined with nature’s love of mediocrity, there are many, many dim stars for every bright one. This population relationship is accurately reflected in the skies created by <code>ppmforge</code> . Dim, low mass stars live much longer than bright, massive stars; consequently there are many reddish stars for every blue giant. This relationship is preserved by <code>ppmforge</code> . You can reverse the proportion, simulating the sky as seen in a starburst galaxy, by specifying a negative <code>sat</code> value.

<code>-seed num</code>	Sets the seed for the random number generator to the integer <code>num</code> . The seed used to create each picture is displayed on standard output (unless suppressed with the <code>-quiet</code> option). Pictures generated with the same seed will be identical. If no <code>-seed</code> is specified, a random seed derived from the date and time will be chosen. Specifying an explicit seed allows you to re-render a picture you particularly like at a higher resolution or with different viewing parameters.
<code>-stars fraction</code>	Specifies the percentage of pixels, in tenths of a percent, that will appear as stars, either surrounding a planet or filling the entire frame if <code>-night</code> is specified. The default <code>fraction</code> is 100.
<code>-xsize -width width</code>	Sets the width of the generated image to <code>width</code> pixels. The default width is 256 pixels. Images must be at least as wide as they are high; if a width less than the height is specified, it will be increased to equal the height. If you must have a long, skinny pixmap, make a square one with <code>ppmforge</code> , then use <code>pnmcut</code> to extract a portion of the shape and size you require.
<code>-ysize -height height</code>	Sets the height of the generated image to <code>height</code> pixels. The default height is 256 pixels. If the height specified exceeds the width, the width will be increased to equal the height.

All flags can be abbreviated to their shortest unique prefix.

BUGS

The algorithms require the output pixmap to be at least as wide as it is high, and the width to be an even number of pixels. These constraints are enforced by increasing the size of the requested pixmap if necessary.

You may have to reduce the FFT mesh size on machines with 16-bit integers and segmented pointer architectures.

SEE ALSO

`pnmcut(1)`, `pnmdepth(1)`, `ppmdither(1)`, `ppmquant(1)`, `ppm(5)`

“Random Fractal Forgeries” by Richard F. Voss, in *Fundamental Algorithms for Computer Graphics* by Earnshaw et al. Berlin: Springer-Verlag, 1985.

The Science Of Fractal Images, edited by H. O. Peitgen and D. Saupe. New York: Springer-Verlag, 1988.

AUTHOR

John Walker
Autodesk SA
Avenue des Champs-Montants 14b
CH-2074 MARIN
Suisse/Schweiz/Svizzera/Svizra/Switzerland

Usenet: `kelvin@Autodesk.com`

Fax: 038/33 88 15

Voice: 038/33 76 33

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, without any conditions or restrictions. This software is provided “as is” without express or implied warranty.

PLUGWARE! If you like this kind of stuff, you may also enjoy James Gleick’s “Chaos—The Software” for MS-DOS, available for \$59.95 from your local software store or directly from Autodesk, Inc., Attn: Science Series, 2320 Marinship Way, Sausalito, CA 94965, USA. Telephone: 800-688-2344 toll-free or, outside the U.S. 415-332-2344 Ext 4886. Fax: 415-289-4718. “Chaos—The Software” includes a more comprehensive fractal forgery generator that creates three-dimensional landscapes as well as clouds and planets, plus five more modules that explore other aspects of Chaos. The user guide of more than 200 pages includes an introduction by James Gleick and detailed explanations by Rudy Rucker of the mathematics and algorithms used by each program.

25 October 1991

ppmhist

ppmhist—Print a histogram of a portable pixmap

SYNOPSIS

```
ppmhist [ppmfile]
```

DESCRIPTION

ppmhist reads a portable pixmap as input and generates a histogram of the colors in the pixmap.

SEE ALSO

ppm(5), pgmhist(1)

AUTHOR

Copyright© 1989 by Jef Poskanzer.

3 April 1989

ppmmake

ppmmake—Create a pixmap of a specified size and color

SYNOPSIS

```
ppmmake color width height
```

DESCRIPTION

ppmmake produces a portable pixmap of the specified color, width, and height.

The color can be specified in five ways:

- A name, assuming that a pointer to an X11-style color names file was compiled in.
- An X11-style hexadecimal specifier: `rgb:r/g/b`, where `r`, `g`, and `b` are each 1- to 4-digit hexadecimal numbers.
- An X11-style decimal specifier: `rgbi:r/g/b`, where `r`, `g`, and `b` are floating-point numbers between 0 and 1.
- For backwards compatibility, an old-X11-style hexadecimal number: `#rgb`, `#rrggbb`, `#rrrgggbbb`, or `#rrrrggggbbbb`.
- For backwards compatibility, a triplet of numbers separated by commas: `r,g,b`, where `r`, `g`, and `b` are floating-point numbers between 0 and 1. (This style was added before MIT came up with the similar `rgbi` style.)

SEE ALSO

ppm(5), pbmmake(1)

AUTHOR

Copyright© 1991 by Jef Poskanzer.

24 September 1991

ppmmix

ppmmix—Blend together two portable pixmaps

SYNOPSIS

```
ppmmix fadefactor ppmfile1 ppmfile2
```

DESCRIPTION

`ppmmix` reads two portable pixmaps as input and mixes them together using the specified fade factor. The fade factor may be in the range from 0.0 (only `ppmfile1`'s image data) to 1.0 (only `ppmfile2`'s image data). Anything in between gains a smooth blend between the two images.

The two pixmaps must have the same size.

SEE ALSO

`ppm(5)`

AUTHOR

Copyright© 1993 by Frank Neumann.

16 November 1993

ppmnorm

`ppmnorm`—Normalize the contrast in a portable pixmap

SYNOPSIS

```
ppmnorm[-bpercent N | -bvalue N][-wpercent N | -wvalue N][ppmfile]
```

DESCRIPTION

`ppmnorm` reads a portable pixmap as input; normalizes the contrast by forcing the lightest pixels to white, the darkest pixels to black, and linearly rescaling the ones in between; and produces a portable pixmap as output.

It works by computing the relative gray level of each pixel as with `ppmtopgm`, and uses those values to scale the RGB levels. Note that this is different from using `pgmnorm` on the individual red, green, and blue graymaps (as produced by `ppmtorgb3`) and recombining them.

OPTIONS

By default, the darkest two percent of all pixels are mapped to black, and the lightest one percent are mapped to white. You can override these percentages by using the `-bpercent` and `-wpercent` flags, or you can specify the exact pixel values to be mapped by using the `-bvalue` and `-wvalue` flags. Appropriate numbers for the flags can be gotten from the `ppmhist` tool. If you just want to enhance the contrast, then choose values at elbows in the histogram; for example, if value 29 represents 3 percent of the image but value 30 represents 20 percent, choose 30 for `bvalue`. If you want to lighten the image, then set `bvalue` to 0 and just fiddle with `wvalue`; similarly, to darken the image, set `wvalue` to `maxval` and play with `bvalue`.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

`pgmnorm(1)`, `ppmhist(1)`, `ppm(5)`

AUTHOR

Wilson H. Bent, Jr. (whb@usc.edu), heavily based on the `pgmnorm` filter by Jef Poskanzer.

7 October 1993

ppmntsc

`ppmntsc`—Make a portable pixmap look like it is taken from an American TV show

SYNOPSIS

```
ppmntsc dimfactor [ppmfile]
```

DESCRIPTION

ppmmtsc reads a portable pixmap as input and dims every other row of image data down by the specified dim factor. This factor may be in the range of 0.0 (the alternate lines are totally black) to 1.0 (original image).

This creates an effect similar to what I saw once in the video clip “You Could be Mine” by Guns’n’ Roses. In the scene I’m talking about you can see John Connor on his motorbike, looking up from the water trench (?) he’s standing in. While the camera pulls back, the image becomes “normal” by brightening up the alternate rows of it. I thought this would be an interesting effect to try in MPEG. I did not yet check this out, however. Try for yourself.

SEE ALSO

ppm(5), ppmdim(1)

AUTHOR

Copyright© 1993 by Frank Neumann.

16 November 1993

ppmpat

ppmpat—Make a pretty pixmap

SYNOPSIS

```
ppmpat -gingham2|-g2|-gingham3| -g3|-madras|-tartan| -poles|-squig|-camo|
      -anticamo width height
```

DESCRIPTION

ppmpat produces a portable pixmap of the specified width and height, with a pattern in it.

This program is mainly to demonstrate use of the ppmdraw routines, a simple but powerful drawing library. See the ppmdraw.h include file for more information on using these routines. Still, some of the patterns can be rather pretty. If you have a color workstation, something like `ppmpat -squig 300 300 | "ppmquant 128"` should generate a nice background.

OPTIONS

The different flags specify various different pattern types:

-gingham2	A gingham check pattern. Can be tiled.
-gingham3	A slightly more complicated gingham. Can be tiled.
-madras	A madras plaid. Can be tiled.
-tartan	A tartan plaid. Can be tiled.
-poles	Color gradients centered on randomly placed poles. May need to be run through ppmquant.
-squig	Squiggly tubular pattern. Can be tiled. May need to be run through ppmquant.
-camo	Camouflage pattern. May need to be run through ppmquant.
-anticamo	Anticamouflage pattern; like -camo, but ultra-bright colors. May need to be run through ppmquant.

All flags can be abbreviated to their shortest unique prefix.

REFERENCES

Some of the patterns are from “Designer’s Guide to Color 3” by Jeanne Allen.

SEE ALSO

pnmtile(1), ppmquant(1), ppm(5)

AUTHOR

Copyright© 1989 by Jef Poskanzer.

4 September 1989

ppmquant

ppmquant—Quantize the colors in a portable pixmap down to a specified number

SYNOPSIS

```
ppmquant [-floyd|-fs] ncolors [ppmfile]
ppmquant [-floyd|-fs] -map mapfile [ppmfile]
```

DESCRIPTION

ppmquant reads a portable pixmap as input. It chooses `ncolors` colors to best represent the image, maps the existing colors to the new ones, and writes a portable pixmap as output.

The quantization method is Heckbert's "median cut."

Alternately, you can skip the color-choosing step by specifying your own set of colors with the `-map` flag. The `mapfile` is just a ppm file; it can be any shape, all that matters is the colors in it. For instance, to quantize down to the 8-color IBM TTL color set, you might use the following:

```
P3
8 1
255
0 0 0
255 0 0
0 255 0
0 0 255
255 255 0
255 0 255
0 255 255
255 255 255
```

If you want to quantize one pixmap to use the colors in another one, just use the second one as the mapfile. You don't have to reduce it down to only one pixel of each color, just use it as is.

The `-floyd/-fs` flag enables a Floyd-Steinberg error diffusion step. Floyd-Steinberg gives vastly better results on images where the unmodified quantization has banding or other artifacts, especially when going to a small number of colors such as the preceding IBM set. However, it does take substantially more CPU time, so the default is off.

All flags can be abbreviated to their shortest unique prefix.

REFERENCES

"Color Image Quantization for Frame Buffer Display," by Paul Heckbert, SIGGRAPH '82 Proceedings, page 297.

SEE ALSO

ppmquantall(1), pnmdepth(1), ppmdither(1), ppm(5)

AUTHOR

Copyright© 1989, 1991 by Jef Poskanzer.

12 January 1991

ppmquantall

`ppmquantall`—Run `ppmquant` on a bunch of files all at once, so they share a common colormap

SYNOPSIS

```
ppmquantall ncolors ppmfile ...
```

DESCRIPTION

`ppmquantall` takes a bunch of portable pixmap as input. It chooses `ncolors` colors to best represent all of the images, maps the existing colors to the new ones, and overwrites the input files with the new quantized versions.

Verbose explanation: Say you have a dozen pixmaps that you want to display on the screen all at the same time. Your screen can only display 256 different colors, but the pixmaps have a total of a thousand or so different colors. For a single pixmap, you solve this problem with `ppmquant`; this script solves it for multiple pixmaps. All it does is concatenate them together into one big pixmap, run `ppmquant` on that, and then split it up into little pixmaps again.

(Note that another way to solve this problem is to preselect a set of colors and then use `ppmquant`'s `-map` option to separately quantize each pixmap to that set.)

SEE ALSO

`ppmquant(1)`, `ppm(5)`

BUGS

It's a `csh` script. `csh` scripts are not portable to System V. Scripts in general are not portable to non-UNIX environments.

AUTHOR

Copyright© 1991 by Jef Poskanzer.

27 July 1990

ppmqvga

`ppmqvga`—8-plane quantization

SYNOPSIS

```
ppmqvga [ options ] [ input file ]
```

DESCRIPTION

`ppmqvga` quantizes PPM files to eight planes, with optional Floyd-Steinberg dithering. Input is a PPM file from the file named, or standard input if no file is provided.

OPTIONS

<code>-d dither</code>	Apply Floyd-Steinberg dithering to the data
<code>-q quiet</code>	Produces no progress reporting, and no terminal output unless an error occurs.
<code>-v verbose</code>	Produces additional output describing the number of colors found, and some information on the resulting mapping. May be repeated to generate loads of internal table output, but generally only useful once.

EXAMPLES

```
ppmqvga -d my_image.ppm | pfmtogif >my_image.gif
```

```
tgatoppm zombie.tga | ppmqvga | pfmtotif > zombie.tif
```


SEE ALSO

ppmquant

DIAGNOSTICS

Error messages if problems; various levels of optional progress reporting.

AUTHORS

Original by Lyle Rains (lrains@netcom.com) as ppmq256 and ppmq256fs combined; documented and enhanced by Bill Davidsen (davidsen@crd.ge.com).

COPYRIGHT

Copyright© 1991, 1992 by Bill Davidsen, all rights reserved. The program and documentation may be freely distributed by anyone in source or binary format. Please clearly note any changes.

Local

ppmrelief

ppmrelief—Run a Laplacian relief filter on a portable pixmap

SYNOPSIS

ppmrelief [ppmfile]

DESCRIPTION

ppmrelief reads a portable pixmap as input, does a Laplacian relief filter, and writes a portable pixmap as output.

The Laplacian relief filter is described in *Beyond Photography* by Holzmnn, equation 3.19. It's a sort of edge-detection.

SEE ALSO

pgmbentley(1), pgmoil(1), ppm(5)

AUTHOR

Copyright© 1990 by Wilson Bent (whb@hoh-2.att.com).

11 January 1991

ppmshift

ppmshift—Shift lines of a portable pixmap left or right by a random amount

SYNOPSIS

ppmshift shift [ppmfile]

DESCRIPTION

ppmshift reads a portable pixmap as input and shifts every row of image data to the left or right by a certain amount. The shift parameter determines by how many pixels a row is to be shifted at most.

Another one of those effects I intended to use for MPEG tests. Unfortunately, this program will not help me here—it creates patterns that are too random to be used for animations. Still, it might give interesting results on still images.

EXAMPLE

Check this out: Save your favorite model's picture from something like `alt.binaries.pictures.supermodels` (okay, or from any other picture source), convert it to ppm, and process it like this, assuming the picture is 800×600 pixels:

1. Take the upper half and leave it like it is: `pnmcut 0 0 800 300 cs.ppm >upper.ppm.`
2. Take the lower half, flip it upside down, dim it, and distort it a little: `pnmcut 0 300 800 300 cs.ppm | pnmflip -tb | ppmDIM 0.7 | ppmshift 10 >lower.ppm.`
3. Concatenate the two pieces: `pnmcats -tb upper.ppm lower.ppm >newpic.ppm.`

The resulting picture looks like the image being reflected on a water surface with slight ripples.

SEE ALSO

`ppm(5)`, `pnmcut(1)`, `pnmflip(1)`, `ppmDIM(1)`, `pnmcats(1)`

AUTHOR

Copyright© 1993 by Frank Neumann.

16 November 1993

ppmspread

`ppmspread`—Displace a portable pixmap's pixels by a random amount

SYNOPSIS

`ppmspread amount [ppmfile]`

DESCRIPTION

`ppmspread` reads a portable pixmap as input and moves every pixel around a bit relative to its original position. `amount` determines by how many pixels a pixel is to be moved around at most.

Pictures processed with this filter will seem to be somewhat dissolved or unfocussed (although they appear more coarse than images processed by something like `pnmconvol`).

SEE ALSO

`ppm(5)`, `pnmconvol(1)`

AUTHOR

Copyright© 1993 by Frank Neumann.

16 November 1993

ppmtoacad

`ppmtoacad`—Convert portable pixmap to AutoCAD database or slide

SYNOPSIS

`ppmtoacad [-dxb] [-poly] [-background colour] [-white] [-aspect ratio] [-8] [ppmfile]`

DESCRIPTION

`ppmtoacad` reads a portable pixmap as input. Produces an AutoCAD slide file or binary database import (DXB) file as output. If no `ppmfile` is specified, input is read from standard input.

OPTIONS

-dxb	An AutoCAD binary database import (DXB) file is written. This file is read with the <code>DXBIN</code> command and, once loaded, becomes part of the AutoCAD geometrical database and can be viewed and edited like any other object. Each sequence of identical pixels becomes a separate object in the database; this can result in very large AutoCAD drawing files. However, if you want to trace over a bitmap, it lets you zoom and pan around the bitmap as you wish.
-poly	If the <code>-dxb</code> option is not specified, the output of <code>ppmtoacad</code> is an AutoCAD slide file. Normally, each row of pixels is represented by an AutoCAD line entity. If <code>-poly</code> is selected, the pixels are rendered as filled polygons. If the slide is viewed on a display with higher resolution than the source pixmap, this will cause the pixels to expand instead of appearing as discrete lines against the screen background color. Regrettably, this representation yields slide files that occupy more disc space and take longer to display.
-background color	Most AutoCAD display drivers can be configured to use any available color as the screen background. Some users prefer a black screen background, others white, while splinter groups advocate burnt ochre, tawny puce, and shocking gray. Discarding pixels whose closest AutoCAD color representation is equal to the background color can substantially reduce the size of the AutoCAD database or slide file needed to represent a bitmap. If no <code>-background color</code> is specified, the screen background color is assumed to be black. Any AutoCAD color number may be specified as the screen background; color numbers are assumed to specify the hues defined in the standard AutoCAD 256-color palette.
-white	Because many AutoCAD users choose a white screen background, this option is provided as a short-cut. Specifying <code>-white</code> is identical in effect to <code>-background 7</code> .
-aspect ratio	If the source pixmap had nonsquare pixels, the ratio of the pixel width to pixel height should be specified as <code>ratio</code> . The resulting slide or DXB file will be corrected so that pixels on the AutoCAD screen will be square. For example, to correct an image made for a 320×200 VGA/MCGA screen, specify <code>-aspect 0.8333</code> .
-8	Restricts the colors in the output file to the eight RGB shades.

All flags can be abbreviated to their shortest unique prefix.

BUGS

AutoCAD has a fixed palette of 256 colors, distributed along the hue, lightness, and saturation axes. Pixmapes that contain many nearly identical colors, or colors not closely approximated by AutoCAD's palette, may be poorly rendered.

`ppmtoacad` works best if the system displaying its output supports the full 256 color AutoCAD palette. Monochrome, 8-color, and 16-color configurations will produce less than optimal results.

When creating a DXB file or a slide file with the `-poly` option, `ppmtoacad` finds both vertical and horizontal runs of identical pixels and consolidates them into rectangular regions to reduce the size of the output file. This is effective for images with large areas of constant color, but it's no substitute for true raster to vector conversion. In particular, thin diagonal lines are not optimized at all by this process.

Output files can be huge.

SEE ALSO

AutoCAD Reference Manual: "Slide File Format" and "Binary Drawing Interchange (DXB) Files"; `ppm(5)`

AUTHOR

John Walker
Autodesk SA
Avenue des Champs-Montants 14b
CH-2074 MARIN
Suisse/Schweiz/Svizzera/Svizra/Switzerland

Usenet: kelvin@Autodesk.com
 Fax: 038/33 88 15
 Voice: 038/33 76 33

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, without any conditions or restrictions. This software is provided “as is” without express or implied warranty.

AutoCAD and Autodesk are registered trademarks of Autodesk, Inc.

10 October 1991

ppmtobmp

ppmtobmp—Convert a portable pixmap into a BMP file

SYNOPSIS

```
ppmtobmp [-windows] [-os2] [ppmfile]
```

DESCRIPTION

ppmtobmp reads a portable pixmap as input and produces a Microsoft Windows or OS/2 BMP file as output.

OPTIONS

-windows Tells the program to produce a Microsoft Windows BMP file.
 -os2 Tells the program to produce an OS/2 BMP file. (This is the default.)

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

bmptoppm(1), ppm(5)

AUTHOR

Copyright© 1992 by David W. Sanderson.

26 October 1992

ppmtogif

ppmtogif—Convert a portable pixmap into a GIF file

SYNOPSIS

```
ppmtogif [-interlace] [-sort] [-map mapfile] [-transparent color] [ppmfile]
```

DESCRIPTION

ppmtogif reads a portable pixmap as input and produces a GIF file as output.

OPTIONS

-interlace Tells the program to produce an interlaced GIF file.
 -sort Produces a GIF file with a sorted colormap.
 -map mapfile Uses the colors found in the mapfile to create the colormap in the GIF file, instead of the colors from ppmfile. The mapfile can be any ppm file; all that matters is the colors in it. If the colors in

ppmfile do not match those in mapfile, they are matched to a “best match.” A (much) better result can be obtained by using the following filter in advance:

```
ppmquant -floyd -map mapfile
```

`-transparent color` Mark the given color as transparent in the GIF file. The color is specified as in `ppmmake(1)`. Note that this option outputs a GIF89a format file, which might not be understood by your software.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

`giftoppm(1)`, `ppmquant(1)`, `ppm(5)`

AUTHOR

Based on GIFENCOD by David Rowley (mgardi@watdcsu.waterloo.edu). Lempel-Ziv compression based on compress.

Copyright© 1989 by Jef Poskanzer.

30 June 1993

ppmtoicr

ppmtoicr—Convert a portable pixmap into NCSA ICR format

SYNOPSIS

```
ppmtoicr [-windowname name][ -expand expand][ -display display][ -rle][ ppmfile]
```

DESCRIPTION

ppmtoicr reads a portable pixmap file as input and produces an NCSA Telnet Interactive Color Raster graphic file as output. If ppmfile is not supplied, ppmtoicr will read from standard input.

Interactive Color Raster (ICR) is a protocol for displaying raster graphics on workstation screens. The protocol is implemented in NCSA Telnet for the Macintosh version 2.3. The ICR protocol shares characteristics of the Tektronix graphics terminal emulation protocol. For example, escape sequences are used to control the display.

ppmtoicr will output the appropriate sequences to create a window of the dimensions of the input pixmap, create a colormap of up to 256 colors on the display, then load the picture data into the window.

Note that there is no icrtoppm tool; this transformation is one-way.

OPTIONS

<code>-windowname name</code>	Output will be displayed in name. (Default is to use ppm-file or “untitled” if standard input is read.)
<code>-expand expand</code>	Output will be expanded on display by factor expand. (For example, a value of 2 will cause four pixels to be displayed for every input pixel.)
<code>-display display</code>	Output will be displayed on screen numbered display.
<code>-rle</code>	Use run-length encoded format for display. (This will nearly always result in a quicker display, but may skew the colormap.)

EXAMPLES

This displays a ppm file using the protocol:

```
ppmtoicr ppmfile
```

This will create a window named ppmfile on the display with the correct dimensions for ppmfile, create and download a colormap of up to 256 colors, and download the picture into the window. The same effect may be achieved by the following sequence:

```
ppmtoicr ppmfile > filename
cat filename
```

To display a GIF file using the protocol in a window titled after the input file, zoom the displayed image by a factor of 2, and run-length encode the data:

```
giftoppm giffile | ppmtoicr -w giffile -r -e 2
```

BUGS

The protocol uses frequent `fflush` calls to speed up display. If the output is saved to a file for later display via `cat`, drawing will be much slower. In either case, increasing the `Blocksize` limit on the display will speed up transmission substantially.

SEE ALSO

`ppm(5)`

NCSA Telnet for the Macintosh, University of Illinois at Urbana-Champaign (1989)

AUTHOR

Copyright© 1990 by Kanthan Pillay (svpillay@Princeton.EDU), Princeton University Computing and Information Technology

30 July 1990

ppmtoilbm

`ppmtoilbm`—Convert a portable pixmap into an ILBM file

SYNOPSIS

```
ppmtoilbm [-maxplanes| -mp N][ -fixplanes| -fp N][ -ham6| -ham8][ -dcbits -dcplanesrgb]
[ -normal| -hamif| -hamforce| -24if| -24force| -dcif| -dcforce| -cmaponly] [ -ecs| -aga]
[ -compress| -nocompress][ -cmethod type][ -mappmfile] [ -savemem][ ppmfile]
```

DESCRIPTION

`ppmtoilbm` reads a portable pixmap as input and produces an ILBM file as output. Supported ILBM types are the following:

Normal ILBMs with 1–16 planes

Amiga HAM with 3–16 planes

24-bit

Colormap (BMHD and CMAP chunk only, `nPlanes = 0`)

Unofficial direct color 1–16 planes for each color component

Chunks written: BMHD, CMAP, CAMG (only for HAM), BODY (not for colormap files) unofficial DCOL chunk for direct color ILBM

OPTIONS

Options marked with (*) can be prefixed with `no`, for example, `-nohamif`. All options can be abbreviated to their shortest unique prefix.

<code>-maxplanes -mp n</code>	(default 5, minimum 1, maximum 16) Maximum planes to write in a normal ILBM. If the pixmap does not fit into <code>n</code> planes, <code>ppmtoilbm</code> writes a HAM file (if <code>-hamif</code> is used), a 24-bit file (if <code>-24if</code> is used), a direct color file (if <code>-dcif</code> is used). or aborts with an error.
<code>-fixplanes -fp n</code>	(min 1, max 16) If a normal ILBM is written, it will have exactly <code>n</code> planes.
<code>-hambits -hamplanes n</code>	(default 6, min 3, max 16) Select number of planes for HAM picture. The current Amiga hardware supports 6 and 8 planes, so for now you should only use this values.

<code>-normal (default)</code>	Turns off <code>-hamif/-24if/-dcif</code> , <code>-hamforce/-24force/-dcforce</code> and <code>-cmaponly</code> . Also sets compression type to <code>byterun1</code> .
<code>-hamif (*)</code> , <code>-24if (*)</code> , <code>-dcif (*)</code>	Write a HAM/24-bit/direct color file if the pixmap does not fit into <code>maxplanes</code> planes.
<code>-hamforce (*)</code> , <code>-24force (*)</code> , <code>-dcforce (*)</code>	Write a HAM/24-bit/direct color file.
<code>-dcbits -dcplanes r g b</code>	(default 5, min 1, max 16). Select number of bits for red, green, and blue in a direct color ILBM.
<code>-ecs (default)</code>	Shortcut for: <code>-hamplanes 6 -maxplanes 5</code>
<code>-aga</code>	Shortcut for: <code>-hamplanes 8 -maxplanes 8</code>
<code>-ham6</code>	Shortcut for: <code>-hamplanes 6 -hamforce</code>
<code>-ham8</code>	Shortcut for: <code>-hamplanes 8 -hamforce</code>
<code>-compress (*) (default)</code> , <code>-cmethod none byterun1</code>	Compress the <code>BODY</code> chunk. The default compression method is <code>byterun1</code> . Compression requires building the ILBM image in memory; turning compression off allows stream-writing of the image, but the resulting file will usually be 30 percent to 50 percent larger. Another alternative is the <code>-savemem</code> option; this will keep memory requirements for compression at a minimum, but is very slow.
<code>-map ppmfile</code>	Write a normal ILBM using the colors in <code>ppmfile</code> as the colormap. The colormap file also determines the number of planes; a <code>-maxplanes</code> or <code>-fixplanes</code> option is ignored.
<code>-cmaponly</code>	Write a colormap file: only <code>BMHD</code> and <code>CMAP</code> chunks, no <code>BODY</code> chunk, <code>nPlanes = 0</code> .
<code>-savemem</code>	See the <code>-compress</code> option.

BUGS

HAM pictures will always get a grayscale colormap; a real color selection algorithm might give better results. On the other hand, this allows row-by-row operation on HAM images, and all HAM images of the same depth (number of planes) share a common colormap, which is useful for building HAM animations.

REFERENCES

Amiga ROM Kernel Reference Manual—Devices (Third Edition), Addison Wesley, ISBN 0-201-56775-X

SEE ALSO

`ppm(5)`, `ilbmtoppm(1)`

AUTHORS

Copyright© 1989 by Jef Poskanzer; modified October 1993 by Ingo Wilken (Ingo.Wilken@informatik.uni-oldenburg.de).

31 October 1993

ppmtomap

ppmtomap—Extract all colors from a portable pixmap

SYNOPSIS

```
ppmtomap [-sort][-square][ppmfile]
```

DESCRIPTION

`ppmtomap` reads a portable pixmap as input and produces a portable pixmap as output, representing a colormap of the input file. All `n` different colors found are put in an `NX1` portable pixmap. This colormap file can be used as a mapfile for `ppmquant` or `ppmtogif`.

OPTIONS

- sort Produces a portable pixmap with the colors in some sorted order
- square Produces a (more or less) square output file, instead of putting all colors on the top row

All flags can be abbreviated to their shortest unique prefix.

WARNING

If you want to use the output file as a mapfile for `ppmtogif`, you first have to do a `ppmquant 256` because `ppmtomap` is not limited to 256 colors (but to 65536).

SEE ALSO

`ppmtogif(1)`, `ppmquant(1)`, `ppm(5)`

AUTHOR

Marcel Wijkstra (wijkstra@wi.uva.nl)

Copyright© 1989 by Jef Poskanzer.

11 August 1993

ppmtomitsu

ppmtomitsu—Convert a portable pixmap to a Mitsubishi S340-10 file

SYNOPSIS

```
ppmtomitsu [-sharpness val][-enlarge val][-media string][-copy val]
[-dpi300][-tiny] [ppmfile]
```

DESCRIPTION

ppmtomitsu reads a portable pixmap as input and converts it into a format suitable to be printed by a Mitsubishi S340-10 printer, or any other Mitsubishi color sublimation printer.

The Mitsubishi S340-10 Color Sublimation printer supports 24-bit color. Images of the available sizes take so long to transfer that there is a fast method, employing a lookup table that ppmtomitsu will use if there is a maximum of 256 colors in the pixmap. ppmtomitsu will try to position your image to the center of the paper, and will rotate your image for you if `xsize` is larger than `ysize`. If your image is larger than the media allows, ppmtomitsu will quit with an error message. (We decided that the media were too expensive to have careless users produce misprints.) After data transmission has started, the job can't be stopped in a sane way without resetting the printer. The printer understands putting together images in the printer's memory; ppmtomitsu doesn't utilize this as `pnmcats` and so on provide the same functionality and let you view the result onscreen, too. The S340-10 is the lowest common denominator printer; for higher resolution printers, there's the `dpi300` option. The other printers also support higher values for `enlarge` eg, but I don't think that's essential enough to warrant a change in the program.

- sharpness 1-4 Sharpness designation. Default is to use the current sharpness.
- enlarge 1-3 Enlarge by a factor; default is 1 (no enlarge)
- media A, A4, AS, A4S Designate the media you're using. Default is 1184 x 1350, which will fit on any media. A is 1216 x 1350, A4 is 1184 x 1452, AS is 1216 x 1650, and A4S is 1184 x 1754. A warning: If you specify a different media than the printer currently has, the printer will wait until you put in the correct media or switch it off.
- copy 1-9 The number of copies to produce. Default is 1.
- dpi300 Double the number of allowed pixels for a S3600-30 Printer in S340-10 compatibility mode. (The S3600-30 has 300dpi.)

-tiny

Memory-safing, but always slow. The printer will get the data line-by-line in 24-bit. It's probably a good idea to use this if your machine starts paging a lot without this option.

REFERENCES

Mitsubishi Sublimation Full Color Printer S340-10; Specifications of Parallel Interface LSP-F0232F

SEE ALSO

ppmquant(1), pnmscale(1), ppm(5)

BUGS

We didn't find any—yet. Besides, they're called features anyway :-). If you should find one, please e-mail me at the following address.

AUTHOR

Copyright© 1992, 1993 by S. Petra Zeidler, MPIFR Bonn, Germany (spz@specklec.mpifr-bonn.mpg.de).

29 January 1992

ppmtopcx

ppmtopcx—Convert a portable pixmap into a PCX file

SYNOPSIS

ppmtopcx [ppmfile]

DESCRIPTION

ppmtopcx reads a portable pixmap as input and produces a PCX file as output.

SEE ALSO

pcxtoppm(1), ppm(5)

AUTHOR

Copyright © 1990 by Michael Davidson.

9 April 1990

ppmtopgm

ppmtopgm—Convert a portable pixmap into a portable graymap

SYNOPSIS

ppmtopgm [ppmfile]

DESCRIPTION

ppmtopgm reads a portable pixmap as input and produces a portable graymap as output. The quantization formula used is $.299\ r + .587\ g + .114\ b$.

Note that although there is a `pgmtoppm` program, it is not necessary for simple conversions from `pgm` to `ppm`, because any `ppm` program can read `pgm` (and `pbm`) files automatically. `pgmtoppm` is for colorizing a `pgm` file. Also, see `ppmtorgb3` for a different way of converting color to gray.

QUOTE

*Cold-hearted orb that rules the night
Removes the colors from our sight
Red is gray, and yellow white
But we decide which is right
And which is a quantization error.*

SEE ALSO

`pgmtoppm(1)`, `ppmtorgb3(1)`, `rgb3toppm(1)`, `ppm(5)`, `pgm(5)`

AUTHOR

Copyright© 1989 by Jef Poskanzer.

23 December 1988

ppmtopi1

`ppmtopi1`—Convert a portable pixmap into an Atari Degas PI1 file

SYNOPSIS

`ppmtopi1 [ppmfile]`

DESCRIPTION

`ppmtopi1` reads a portable pixmap as input and produces an Atari Degas PI1 file as output.

SEE ALSO

`pi1toppm(1)`, `ppm(5)`, `pbmtopi3(1)`, `pi3topbm(1)`

AUTHOR

Copyright© 1991 by Steve Belczyk (seb3@gte.com) and Jef Poskanzer.

19 July 1990

ppmtopict

`ppmtopict`—Convert a portable pixmap into a Macintosh PICT file

SYNOPSIS

`ppmtopict [ppmfile]`

DESCRIPTION

`ppmtopict` reads a portable pixmap as input and produces a Macintosh PICT file as output.

The generated file is only the data fork of a picture. You will need a program such as `mcvert` to generate a Macbinary or a BinHex file that contains the necessary information to identify the file as a PICT file to MacOS.

Even though PICT supports 2 and 4 bits per pixel, `ppmtopict` always generates an 8-bits-per-pixel file.

BUGS

The picture size field is only correct if the output is to a file because writing into this field requires seeking backwards on a file. However, the PICT documentation seems to suggest that this field is not critical anyway because it is only the lower 16 bits of the picture size.

SEE ALSO

picttoppm(1), ppm(5), mcvert(1)

AUTHOR

Copyright© 1990 by Ken Yap (ken@cs.rochester.edu).

15 April 1990

ppmtopj

ppmtopj—Convert a portable pixmap to an HP PaintJet file

SYNOPSIS

```
ppmtopj [-gamma val][-xpos val][-ypos val][-back dark|lite][-rle][-center]
[-render none|snap|bw|dither|diffuse|monodither|monodiffuse|clusterdither|
monoclusterdither][ppmfile]
```

DESCRIPTION

ppmtopj reads a portable pixmap as input and converts it into a format suitable to be printed by an HP PaintJet printer.

For best results, the input file should be in 8-color RGB form; that is, it should have only the eight binary combinations of full-on and full-off primaries. You could get this by sending the input file through ppmquant -map with a mapfile such as

```
P3
8 1
255
0 0 0 255 0 0 0 255 0 0 255
255 255 0 255 0 255 0 255 255 255 255 255
```

Or else you could use ppmdither -red 2 -green 2 -blue 2.

OPTIONS

-rle	Run-length encode the image. (This can result in larger images.)
-back	Enhance the foreground by indicating if the background is light or dark compared to the foreground.
-render alg	Use an internal rendering algorithm (default dither).
-gamma int	Gamma correct the image using the integer parameter as a gamma (default 0).
-center	Center the image to an 8.5 by 11 page.
-xpos pos	Move by pos pixels in the x direction.
-ypos pos	Move by pos pixels in the y direction.

REFERENCES

HP PaintJet XL Color Graphics Printer User's Guide

SEE ALSO

pnmddepth(1), ppmquant(1), ppmdither(1), ppm(5)

BUGS

Most of the options have not been tested because of the price of the paper.

AUTHOR

Copyright© 1991 by Christos Zoulas.

13 July 1991

ppmtopjxl

ppmtopjxl—Convert a portable pixmap into an HP PaintJet XL PCL file

SYNOPSIS

```
ppmtopjxl [-nopack] [-gamma <n> ] [-presentation] [-dark] [-diffuse]
[-cluster] [-dither] [-xshift <s> ] [-yshift <s> ] [-xshift <s> ] [-yshift <s> ]
[-xsize|-width|-xscale <s> ] [-ysize|-height|-yscale <s> ] [ppmfile]
```

DESCRIPTION

ppmtopjxl reads a portable pixmap as input and produces a PCL file suitable for printing on an HP PaintJet XL printer as output.

The generated file is not suitable for printing on a normal PrintJet printer. The `-nopack` option generates a file that does not use the normal TIFF 4.0 compression method. This file might be printable on a normal PaintJet printer (not an XL).

The `-gamma` option sets the gamma correction for the image. The useful range for the PaintJet XL is approximately 0.6 to 1.5.

The rendering algorithm used for images can be altered with the `-dither`, `-cluster`, and `-diffuse` options. These options select ordered dithering, clustered ordered dithering, or error diffusion, respectively. The `-dark` option can be used to enhance images with a dark background when they are reduced in size. The `-presentation` option turns on presentation mode, in which two passes are made over the paper to increase ink density. This should be used only for images where quality is critical.

The image can be resized by setting the `-xsize` and `-ysize` options. The parameter to either of these options is interpreted as the number of dots to set the width or height to, but an optional dimension of `pt` (points), `dp` (decipoints), `in` (inches), or `cm` (centimeters) may be appended. If only one dimension is specified, the other will be scaled appropriately.

The options `-width` and `-height` are synonyms of `-xsize` and `-ysize`.

The `-xscale` and `-yscale` options can alternatively be used to scale the image by a simple factor.

The image can be shifted on the page by using the `-xshift` and `-yshift` options. These move the image the specified dimensions right and down.

SEE ALSO

ppm(5)

AUTHOR

Angus Duggan

14 March 1991

ppmtopuzz

ppmtopuzz—Convert a portable pixmap into an X11 puzzle file

SYNOPSIS

```
ppmtopuzz [ppmfile]
```

DESCRIPTION

ppmtopuzz reads a portable pixmap as input and produces an X11 puzzle file as output. A puzzle file is for use with the `puzzle` program included with the X11 distribution; `puzzle`'s `-picture` flag lets you specify an image file.

SEE ALSO

ppm(5), puzzle(1)

AUTHOR

Copyright© 1991 by Jef Poskanzer.

22 August 1990

ppmtorgb3

ppmtorgb3—Separate a portable pixmap into three portable graymaps

SYNOPSIS

ppmtorgb3 [ppmfile]

DESCRIPTION

ppmtorgb3 reads a portable pixmap as input and writes three portable graymaps as output, one each for red, green, and blue.

The output filenames are constructed by taking the input filename, stripping off any extension, and appending .red, .grn, and .blu. For example, separating `lenna.ppm` would result in `lenna.red`, `lenna.grn`, and `lenna.blu`. If the input comes from `stdin`, the names are `noname.red`, `noname.grn`, and `noname.blu`.

SEE ALSO

rgb3toppm(1), ppmtopgm(1), pgmtoppm(1), ppm(5), pgm(5)

AUTHOR

Copyright© 1991 by Jef Poskanzer.

10 January 1991

ppmtosixel

ppmtosixel—Convert a portable pixmap into DEC sixel format

SYNOPSIS

ppmtosixel [-raw] [-margin] [ppmfile]

DESCRIPTION

ppmtosixel reads a portable pixmap as input and produces sixel commands (SIX) as output. The output is formatted for color printing, for example, for a DEC LJ250 color inkjet printer.

If RGB values from the PPM file do not have `maxval=100`, the RGB values are rescaled. A printer control header and a color assignment table begin the SIX file. Image data is written in a compressed format by default. A printer control footer ends the image file.

OPTIONS

- raw If specified, each pixel will be explicitly described in the image file. If `-raw` is not specified, output will default to compressed format in which identical adjacent pixels are replaced by `repeat pixel` commands. A raw file is often an order of magnitude larger than a compressed file and prints much slower.
- margin If `-margin` is not specified, the image will start at the left margin (of the window, paper, or whatever). If `-margin` is specified, a 1.5 inch left margin will offset the image.

PRINTING

Generally, sixel files must reach the printer unfiltered. Use the `lpr -x` option or `cat filename > /dev/tty0?`.

BUGS

Upon rescaling, truncation of the least significant bits of RGB values may result in poor color conversion. If the original PPM `maxval` was greater than 100, rescaling also reduces the image depth. While the actual RGB values from the `ppm` file are more or less retained, the color palette of the LJ250 may not match the colors on your screen. This seems to be a printer limitation.

SEE ALSO

`ppm(5)`

AUTHOR

Copyright© 1991 by Rick Vinci.

26 April 1991

ppmtotga

`ppmtotga`—Convert portable pixmap into a TrueVision Targa file

SYNOPSIS

```
ppmtotga [-mono|-cmap|-rgb][-norle][ppmfile]
```

DESCRIPTION

`ppmtotga` reads a portable pixmap as input and produces a TrueVision Targa file as output.

OPTIONS

- `-mono` Forces Targa file to be of type 8-bit monochrome. Input must be a portable bitmap or a portable graymap.
- `-cmap` Forces Targa file to be of type 24-bit colormapped. Input must be a portable bitmap, a portable graymap, or a portable pixmap containing no more than 256 distinct colors.
- `-rgb` Forces Targa file to be of type 24-bit unmapped color.
- `-norle` Disables run-length encoding, in case you have a Targa reader that can't read run-length encoded files.

All flags can be abbreviated to their shortest unique prefix. If no file type is specified, the most highly constrained compatible type is used, where monochrome is more constrained than colormapped, which is in turn more constrained than unmapped.

BUGS

Does not support all possible Targa file types. Should really be in `pnm`, not `ppm`.

SEE ALSO

`tgatoppm(1)`, `ppm(5)`

AUTHOR

Copyright© 1989, 1991 by Mark Shand and Jef Poskanzer.

28 October 1991

ppmtouil

ppmtouil—Convert a portable pixmap into a Motif UIL icon file

SYNOPSIS

```
ppmtouil [-name uilname][ppmfile]
```

DESCRIPTION

ppmtouil reads a portable pixmap as input and produces a Motif UIL icon file as output.

If the program was compiled with an `rgb` database specified, and an RGB value from the `ppm` input matches an RGB value from the database, then the corresponding color name mnemonic is printed in the UIL's colormap. If no `rgb` database was compiled in, or if the RGB values don't match, then the color will be printed with the `#RGB`, `#RRGGBB`, `#RRRGGBBB`, or `#RRRRGGGGBBBB` hexadecimal format.

OPTIONS

`-name` Allows you to specify the prefix string that is printed in the resulting UIL output. If not specified, it will default to the filename (without extension) of the `ppmfile` argument. If `-name` is not specified and no `ppmfile` is specified (that is, piped input), the prefix string will default to the string "noname".

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

`ppm(5)`

AUTHOR

Converted by Jef Poskanzer from `ppmtoxpm.c`, which is copyright© 1990 by Mark W. Snitily.

31 August 1990

ppmtoxpm

ppmtoxpm—Convert a portable pixmap into an X11 pixmap

SYNOPSIS

```
ppmtoxpm [-name <xpmname>] [-rgb <rgb-textfile>][<ppmfile>]
```

DESCRIPTION

ppmtoxpm reads a portable pixmap as input and produces an X11 pixmap (version 3) as output that can be loaded directly by the XPM library.

The `-name` option allows you to specify the prefix string which is printed in the resulting XPM output. If not specified, it will default to the filename (without extension) of the `ppmfile` argument. If `-name` is not specified and `ppmfile` is not specified (that is, piped input), the prefix string will default to the string "noname".

The `-rgb` option allows you to specify an X11 `rgb` text file for the lookup of color name mnemonics. This RGB text file is typically the `/usr/lib/X11/rgb.txt` of the MIT X11 distribution, but any file using the same format may be used. When specified and an RGB value from the `ppm` input matches an RGB value from the `<rgb-textfile>`, then the corresponding color name mnemonic is printed in the XPM's colormap. If `-rgb` is not specified, or if the RGB values don't match, then the color will be printed with the `#RGB`, `#RRGGBB`, `#RRRGGBBB`, or `#RRRRGGGGBBBB` hexadecimal format.

All flags can be abbreviated to their shortest unique prefix.

For example, to convert the file `dot` (found in `/usr/include/X11/bitmaps`), from `xbm` to `xpm`, you could specify

```
xbmtopbm dot | pmtotpm -name dot
```

or, with an `rgb` text file (in the local directory)

```
xbmtopbm dot | pmtotpm -name dot -rgb rgb.txt
```

BUGS

An option to match the closest (rather than exact) color name mnemonic from the `rgb` text would be a desirable enhancement.

Truncation of the least significant bits of an RGB value may result in nonexact matches when performing color name mnemonic lookups.

SEE ALSO

`ppm(5)`

XPM Manual by Arnaud Le Hors (lehors@mirsa.inria.fr).

AUTHOR

Copyright © 1990 by Mark W. Snitely. This tool was developed for Schlumberger Technologies, ATE Division, and with their permission is being made available to the public with the above copyright notice and permission notice.

Upgraded to XPM2 by Paul Breslaw, MecaSoft SA, Zurich, Switzerland (paul@mecazh.uu.ch); Thu, Nov 8, 16:01:17, 1990.

Upgraded to XPM version 3 by Arnaud le Hors (lehors@mirsa.inria.fr).

9 April 1991

ppmtoyuv

`ppmtoyuv`—Convert a portable pixmap into an Abekas YUV file

SYNOPSIS

```
ppmtoyuv [ppmfile]
```

DESCRIPTION

`ppmtoyuv` reads a portable pixmap as input and produces an Abekas YUV file as output.

SEE ALSO

`yuvtoppm(1)`, `ppm(5)`

AUTHOR

Marc Boucher (<marc@PostImage.COM>), based on Example Conversion Program, *A60/A64 Digital Video Interface Manual*, page 69. Copyright© 1991 by DHD Post Image Inc. Copyright© 1987 by Abekas Video Systems Inc.

25 March 1991

ppmtoyuvsplit

`ppmtoyuvsplit`—Convert a portable pixmap into three subsampled raw YUV files

SYNOPSIS

```
ppmtoyuvsplit basename [ppmfile]
```


DESCRIPTION

`ppmtouyvsplit` reads a portable pixmap as input and produces three raw files—`basename.Y`, `basename.U`, and `basename.V`—as output. These files are the subsampled raw YUV representation of the input pixmap, as required by the Stanford MPEG code. The subsampling is done by arithmetic mean of 4 pixels colors into one. The YUV values are scaled according to CCIR.601, as assumed by MPEG.

SEE ALSO

`mpeg(1)`, `ppm(5)`

AUTHOR

Copyright© 1993 by Andre Beck (AndreBeck@IRS.Inf.TU-Dresden.de). Based on `ppmtouyv.c`.

9 September 1993

pr

`pr`—Convert text files for printing

SYNOPSIS

```
pr [+PAGE] [-COLUMN] [-abcdFmrtv] [-e[in-tab-char[in-tab-width]]] [-h header]
[-i[out-tab-char[out-tab-width]]] [-l page-length] [-n[number-separator[digits]]]
[-o left-margin] [-s[column-separator]] [-w page-width] [--help] [--version] [file...]
```

DESCRIPTION

This manual page documents the GNU version of `pr`. `pr` prints on the standard output a paginated and optionally multicolumn copy of the text files given on the command line, or of the standard input if no files are given or when the filename `-` is encountered. Form feeds in the input cause page breaks in the output.

OPTIONS

<code>PAGE</code>	Begin printing with page <code>PAGE</code> .
<code>-COLUMN</code>	Produce <code>COLUMN</code> -column output and print columns down. The column width is automatically decreased as <code>COLUMN</code> increases; unless you use the <code>-w</code> option to increase the page width as well, this option might cause some columns to be truncated.
<code>-a</code>	Print columns across rather than down.
<code>-b</code>	Balance columns on the last page.
<code>-c</code>	Print control characters using hat notation (for example, <code>^G</code>); print other unprintable characters in octal backslash notation.
<code>-d</code>	Double-space the output.
<code>-e[in-tab-char [in-tab-width]]</code>	Expand tabs to spaces on input. Optional argument <code>in-tab-char</code> is the input tab character, default <code>tab</code> . Optional argument <code>in-tab-width</code> is the input tab character's width, default 8.
<code>-F, -f</code>	Use a form feed instead of newlines to separate output pages.
<code>-h header</code>	Replace the filename in the header with the string <code>header</code> .
<code>--help</code>	Print a usage message and exit with a nonzero status.
<code>-i[out-tab-char [out-tab-width]]</code>	Replace spaces with tabs on output. Optional argument <code>out-tab-char</code> is the output tab character, default <code>tab</code> . Optional argument <code>out-tab-width</code> is the output tab character's width, default 8.
<code>-l page-length</code>	Set the page length to <code>page-length</code> lines. The default is 66. If <code>page-length</code> is less than 10, the headers and footers are omitted, as if the <code>-t</code> option had been given.
<code>-m</code>	Print all files in parallel, one in each column.

<code>-n[number-separator [digits]]</code>	Precede each column with a line number; with parallel files, precede each line with a line number. Optional argument <code>number-separator</code> is the character to print after each number, default tab. Optional argument <code>digits</code> is the number of digits per line number, default 5.
<code>-o left-margin</code>	Offset each line with a margin <code>left-margin</code> spaces wide. The total page width is this offset plus the width set with the <code>-w</code> option.
<code>-r</code>	Do not print a warning message when an argument file cannot be opened. Failure to open a file still makes the exit status nonzero, however.
<code>-s[column-separator]</code>	Separate columns by the single character <code>column-separator</code> , default tab, instead of spaces.
<code>-t</code>	Do not print the 5-line header and the 5-line trailer that are normally on each page, and do not fill out the bottoms of pages (with blank lines or form feeds).
<code>-v</code>	Print unprintable characters in octal backslash notation.
<code>--version</code>	Print version information on standard output then exit.
<code>-w page-width</code>	Set the page width to <code>page-width</code> columns. The default is 72.

GNU Text Utilities

ps

`ps`—Report process status

SYNOPSIS

```
ps [-][lujsvmaxSccewhrnu][ttx][0[+|-]k1[[+|-]k2...]] [pids]
```

There are also two long options:

```
--sortX[+|-]key[, [+|-]key[, ...]]
```

```
--help
```

More long options are on the way...

DESCRIPTION

`ps` gives a snapshot of the current processes. If you want a repetitive update of this status, use `top`. This man page documents the `/proc`-based version of `ps`, or tries to.

COMMAND-LINE OPTIONS

Command-line arguments may optionally be preceded by a `-`, but there is no need for it. There are also some long options in GNU style; see the following subsection for those.

<code>l</code>	Long format.
<code>u</code>	User format: gives username and start time.
<code>j</code>	Jobs format: <code>pgid sid</code> .
<code>s</code>	Signal format.
<code>v</code>	<code>vm</code> format.
<code>m</code>	Displays memory information (combine with <code>p</code> flag to get number of pages).
<code>f</code>	Forest family tree format for command line.
<code>a</code>	Show processes of other users too.
<code>x</code>	Show processes without controlling terminal.
<code>S</code>	Add child cpu time and page faults.
<code>c</code>	Command name from task struct.
<code>e</code>	Show environment after command line and <code>+</code> .

w	Wide output: don't truncate command lines to fit on one line.
h	No header.
r	Running procs only.
n	Numeric output for USER and WCHAN.
txx	Only procs with controlling tty xx; use for xx the same letters as shown in the TT field. The tty name must be given immediately after the option, with no intervening space, for example, ps -tv1.
0[+ -]k1[, [+ -]k2[, ...]]	Order the process listing according to the multilevel sort specified by the sequence of short keys from SORT KEYS, k1, k2, ... Default order specifications exist for each of the various formats of ps. These are overridden by a user-specified ordering. The + is quite optional, merely reiterating the default direction on a key. - reverses direction only on the key it precedes. As with t and pids, the 0 option must be the last option in a single command argument, but specifications in successive arguments are catenated.
pids	List only the specified processes; they are comma-delimited. The list must be given immediately after the last option in a single command-line argument, with no intervening space, for example, ps -j1,4,5. Lists specified in subsequent arguments are catenated, for example, ps -11,23,4 5 6 will list all of the processes 1-6 in long format.

LONG COMMAND-LINE OPTIONS

These options are preceded by a double hyphen.

--sortX[+ -]key[, [+ -]key[, ...]]	Choose a multiletter key from the SORTKEYS section. X may be any convenient separator character. To be GNU-ish, use =. The + is really optional because default direction is increasing numerical or lexicographic order. Example: ps -jax -sort=uid,-ppid,+pid
--help	Get a help message that summarizes the usage and gives a list of supported sort keys. This list may be more up-to-date than this man page.

SORT KEYS

Note that the values used in sorting are the internal values ps uses and *not* the “cooked” values used in some of the output format fields. If someone wants to volunteer to write special comparison functions for the cooked values,...;-)

Short	Long	Description
c	cmd	Simple name of executable
C	cmdline	Full command line
f	flags	Flags as in long format F field
g	pgrp	Process group ID
G	tpgid	Controlling tty process group ID
j	cutime	Cumulative user time
J	cstime	Cumulative system time
k	utime	User time
K	stime	System time
m	min_flt	Number of minor page faults
M	maj_flt	Number of major page faults
n	cmin_flt	Cumulative minor page faults
N	cmaj_flt	Cumulative major page faults
o	session	Session ID
p	pid	Process ID

continues

<i>Short</i>	<i>Long</i>	<i>Description</i>
P	ppid	Parent process ID
r	rss	Resident set size
R	resident	Resident pages
s	size	Memory size in kilobytes
S	share	Amount of shared pages
t	tty	The minor device number of tty
T	start_time	Time process was started
U	uid	User ID number
u	user	Username
v	vsize	Total VM size in bytes
y	priority	Kernel scheduling priority

FIELD DESCRIPTIONS

PRI	This is the counter field in the task struct. It is the time in HZ of the process's possible time slice.
NI	Standard UNIX nice value; a positive value means less cpu time.
SIZE	Virtual image size; size of text+data+stack.
RSS	Resident set size; kilobytes of program in memory.
WCHAN	Name of the kernel function where the process is sleeping, with the sys stripped from the function name. If /boot/psdatabase does not exist, it is just a hex number instead.
STAT	Information about the status of the process. The first field is R for runnable, S for sleeping, D for uninterruptible sleep, T for stopped or traced, or Z for a zombie process. The second field contains W if the process has no resident pages. The third field is N if the process has a positive nice value (NI field).
TT	Controlling tty.
PAGEIN	Number of major page faults (page faults that cause pages to be read from disk, including pages read from the buffer cache).
TRS	Text resident size.
SWAP	Kilobytes (or pages if -p is used) on swap device.
SHARE	Shared memory.

UPDATING

This proc-based ps works by reading the files in the proc filesystem, mounted on /proc. This ps does not need to be suid kmem or have any privileges to run. *Do not give this ps any special permissions.*

You will need to update the /boot/psdatabase file by running /usr/sbin/psupdate to get meaningful information from the WCHAN field. This should be done every time you compile a new kernel.

NOTES

The member used_math of task_struct is not shown, since crt0.s checks to see if math is present. This causes the math flag to be set for all processes, and so it is worthless.

Programs swapped out to disk will be shown without command-line arguments, and unless the c option is given, in parentheses.

%CPU shows the cputime/realtime percentage. It will not add up to 100 percent unless you are lucky. It is time used divided by the time the process has been running.

The SIZE and RSS fields don't count the page tables and the task struct of a proc; this is at least 12k of memory that is always resident. SIZE is the virtual size of the proc (code+data+stack).

BUGS

tty names are hard-coded: virtual consoles are v1, v2,...; serial lines are s0 and s1; pty's are pp0, pp1 ... pq0, pq1, ...

AUTHORS

ps was originally written by Branko Lankester (lankeste@fwi.uva.nl) Michael K. Johnson (johnsonm@sunsite.unc.edu) rewrote it significantly to use the proc filesystem, changing a few things in the process. Michael Shields (mjshield@nyx.cs.du.edu) added the multiple-pids feature. Charles Blake(cblake@ucsd.edu) added multilevel sorting and is the current maintainer of the proc-ps suite.

Cohesive Systems, 27 July 1994

psbb

psbb—Extract bounding box from PostScript document

SYNOPSIS

psbb file

DESCRIPTION

psbb reads file, which should be a PostScript document conforming to the document structuring conventions and looks for a %%BoundingBox comment. If it finds one, it prints a line

llx lly urx ury

on the standard output and exits with zero status. If it doesn't find such a line or if the line is invalid, it prints a message and exits with nonzero status.

SEE ALSO

grops(1)

Groff Version 1.09, 6 August 1992

psidtopgm

psidtopgm—Convert PostScript image data into a portable graymap

SYNOPSIS

psidtopgm width height bits/sample [imagedata]

DESCRIPTION

psidtopgm reads the image data from a PostScript file as input and produces a portable graymap as output.

This is a very simple and limited program, and is here only because so many people have asked for it. To use it you have to manually extract the readhexstring data portion from your PostScript file, and then give the width, height, and bits/sample on the command line. Before you attempt this, you should at least read the description of the image operator in the *PostScript Language Reference Manual*.

It would probably not be too hard to write a script that uses this filter to read a specific variety of PostScript image, but the variation is too great to make a general-purpose reader. Unless, of course, you want to write a full-fledged PostScript interpreter...

SEE ALSO

pnmtops(1), pgm(5)

AUTHOR

Copyright© 1989 by Jef Poskanzer.

2 August 1989

pstopnm

pstopnm—Convert a PostScript file into a portable anymap

SYNOPSIS

```
pstopnm [-forceplain][-help][-llx s][-lly s][-landscape][-portrait][-nocrop]
[-pbm |-pgm |-ppm][-urx s][-ury s][-verbose][-xborder n][-xmax n][-xsize f]
[-yborder f][-ymax n][-ysize n] psfile.ps
```

DESCRIPTION

pstopnm reads a PostScript file as input and produces portable anymap files as output. This program is just a useful shell script that runs GhostScript to render a PostScript into one or more pnm files. pstopnm will create as many files as the number of pages in the PostScript document. If the input file is named `psfile.ps`, the name of the files will be `psfile001.ppm`, `psfile002.ppm`, and so on.

The program maps a rectangular portion of the PostScript document into an image file according to the command-line options. The selected area will always be centered in the output file, and may have borders around it. The image area to be extracted from the PostScript file and rendered into a portable anymap is defined by four numbers, the lower-left corner and the upper-right corner x and y coordinates. These coordinates are usually specified by the `BoundingBox` comment in the PostScript file header, but they can be overridden by the user by specifying one or more of the following flags: `-llx`, `-lly`, `-urx`, and `-ury`. The presence and thickness of a border to be left around the image area is controlled by the use of the flags `-xborder` and `-yborder`. If `BoundingBox` parameters are not found, and image area coordinates are not specified on the command line, default values are used. Unless both output file width and height are specified via the `-xsize` and `-ysize` flags, the program will map the document into the output image by preserving its aspect ratio.

OPTIONS

<code>-forceplain</code>	Forces the output file to be a plain (in other words, not “raw”) portable anymap.
<code>-help</code>	Prints the command syntax.
<code>-llx bx</code>	Selects <code>bx</code> as the lower left corner x coordinate (in inches).
<code>-lly by</code>	Selects <code>by</code> as the lower left corner y coordinate (in inches).
<code>-landscape</code>	Renders the image in landscape mode.
<code>-portrait</code>	Renders the image in portrait mode.
<code>-nocrop</code>	Does not crop the output image dimensions to match the PostScript image area dimensions.
<code>-pbm -pgm -ppm</code>	Selects the format of the output file. By default, all files are rendered as portable pixmaps (ppm format).
<code>-urx tx</code>	Selects <code>tx</code> as the upper-right corner x coordinate (in inches).
<code>-ury ty</code>	Selects <code>ty</code> as the upper-right corner y coordinate (in inches).
<code>-verbose</code>	Prints processing information to <code>stdout</code> .
<code>-xborder frac</code>	Specifies that the border width along the Y axis should be <code>frac</code> times the document width as specified by the bounding box comment in the PostScript file header. The default value is 0.1.
<code>-xmax xs</code>	Specifies that the maximum output image width should have a size less or equal to <code>xs</code> pixels (default: 612).
<code>-xsize xs</code>	Specifies that the output image width must be exactly <code>xs</code> pixels.
<code>-yborder frac</code>	Specifies that the border width along the X axis should be <code>frac</code> times the document width as specified by the bounding box comment in the PostScript file header. The default value is 0.1.
<code>-ymax ys</code>	Specifies that the maximum output image height should have a size less or equal to <code>ys</code> pixels (default: 792).
<code>-ysize ys</code>	Specifies that the output image height must be exactly <code>ys</code> pixels.

BUGS

The program will produce incorrect results with PostScript files that initialize the current transformation matrix. In these cases, page translation and rotation will not have any effect. To render these files, probably the best bet is to use the following flags:

```
pstopnm -xborder 0 -yborder 0 -portrait -nocrop file.ps
```

Additional flags may be needed if the document is supposed to be rendered on a medium different from letter-size paper.

SEE ALSO

gs(l), pstofits(l)

COPYRIGHT

Copyright© 1992 Smithsonian Astrophysical Observatory. PostScript is a trademark of Adobe Systems Inc.

AUTHOR

Alberto Accomazzi, WIPL, Center for Astrophysics

28 December 1992

pstree

pstree—Display a tree of processes

SYNOPSIS

```
pstree [-a][-c][-h][-l][-p][-u][pid|user]
```

DESCRIPTION

pstree shows running processes as a tree. The tree is rooted at either pid or init if pid is omitted. If a username is specified, all process trees rooted at processes owned by that user are shown.

pstree visually merges identical branches by putting them in square brackets and prefixing them with the repetition count; for example,

```
init+-getty
  | -getty
  | -getty
  | -getty
```

becomes

```
init-4*[getty]
```

OPTIONS

- a Show command-line arguments. If the command line of a process is swapped out, that process is shown in parentheses. -a implicitly disables compaction.
- c Disable compaction of identical subtrees. By default, subtrees are compacted whenever possible.
- h Highlight the current process and its ancestors. This is a no-op if the terminal doesn't support highlighting or if neither the current process nor any of its ancestors are in the subtree being shown.
- l Display long lines. By default, lines are truncated to the display width or 132 if output is sent to a non-tty or if the display width is unknown.
- p Show pids. pids are shown as decimal numbers in parentheses after each process name. -p implicitly disables compaction.
- u Show uid transitions. Whenever the uid of a process differs from the uid of its parent, the new uid is shown in parentheses after the process name.

FILES

`/proc` Location of the `proc` filesystem

AUTHOR

Werner Almesberger (`almesber@di.epfl.ch`)

SEE ALSO

`ps(1)`, `top(1)`

Linux, 11 October 1994

psupdate

`psupdate`—Update the `ps` database of kernel offsets

SYNOPSIS

`psupdate` [`system path`]

DESCRIPTION

`psupdate` updates the `/boot/psdatabase` file to correspond to the current kernel image system mapfile, `/usr/src/linux/vmlinux` by default.

OPTIONS

If your system mapfile is not `/usr/src/linux/vmlinux`, you may give the name of an alternate mapfile on the command line.

FILES

`/boot/psdatabase`
`/usr/src/linux/vmlin`

SEE ALSO

`ps(1)`, `top(1)`, `utmp(5)`

AUTHORS

Original code written by Branko Lankaster, horribly munged by Michael K. Johnson in a desperate effort to add `/etc/psdatabase` support to `procps`. Someday, it should be rewritten, and the support in `ps` for alternate namelists added. Anyone want to volunteer to be added to the “Authors” section?

Cohesive Systems, 15 September 1993

qrttoppm

`qrttoppm`—Convert output from the QRT ray tracer into a portable pixmap

SYNOPSIS

`qrttoppm` [`qrtfile`]

DESCRIPTION

`qrttoppm` reads a QRT file as input and produces a portable pixmap as output.

SEE ALSO

ppm(5)

AUTHOR

Copyright© 1989 by Jef Poskanzer.

25 August 1989

quota

quota—Display disk usage and limits

SYNOPSIS

```
quota [ -guv | q ]
quota [ -uv | q ] user
quota [ -gv | q ] group
```

DESCRIPTION

quota displays users' disk usage and limits. By default, only the user quotas are printed.

- g Print group quotas for the group of which the user is a member. The optional -u flag is equivalent to the default.
- v Will display quotas on filesystems where no storage is allocated.
- q Print a more terse message, containing only information on filesystems where usage is over quota.

Specifying both -g and -u displays both the user quotas and the group quotas (for the user).

Only the superuser may use the -u flag and the optional user argument to view the limits of other users. Non-superusers can use the -g flag and optional group argument to view only the limits of groups of which they are members.

The -q flag takes precedence over the -v flag.

quota reports the quotas of all the filesystems listed in /etc/fstab. For filesystems that are NFS-mounted, a call to the rpc.rquotad on the server machine is performed to get the information. If quota exits with a nonzero status, one or more filesystems are over quota.

FILES

quota.user	Located at the filesystem root with user quotas
quota.group	Located at the filesystem root with group quotas
/etc/fstab	To find filesystem names and locations

SEE ALSO

quotactl(2), fstab(5), edquota(8), quotacheck(8), quotaon(8), repquota(8)

8 January 1993

ranlib

ranlib—Generate index to archive

SYNOPSIS

ranlib [-v|-V] archive

DESCRIPTION

`ranlib` generates an index to the contents of an archive and stores it in the archive. The index lists each symbol defined by a member of an archive that is a relocatable object file.

You may use `nm -s` or `nm --print-armap` to list this index.

An archive with such an index speeds up linking to the library, and allows routines in the library to call each other without regard to their placement in the archive.

The GNU `ranlib` program is another form of GNU `ar`; running `ranlib` is completely equivalent to executing `ar -s`.

OPTIONS

`-v` Print the version number of `ranlib` and exit

SEE ALSO

`binutils` entry in *info*; *The GNU Binary Utilities*, Roland H. Pesch (October 1991); `ar(1)`; `nm(1)`.

COPYING

Copyright© 1991 Free Software Foundation, Inc. Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

Cygnus support, 5 November 1991

rasttopnm

`rasttopnm`—Convert a Sun raster file into a portable anymap

SYNOPSIS

`rasttopnm [rastfile]`

DESCRIPTION

`rasttopnm` reads a Sun raster file as input and produces a portable anymap as output. The type of the output file depends on the input file—if it's black and white, a `pbm` file is written; else if it's grayscale, a `pgm` file; else a `ppm` file. The program tells you which type it is writing.

SEE ALSO

`pnmtorast(1)`, `pnm(5)`

AUTHOR

Copyright © 1989, 1991 by Jef Poskanzer.

13 January 1991

rawtopgm

rawtopgm—Convert raw grayscale bytes into a portable graymap

SYNOPSIS

```
rawtopgm [-headerskip N][ -rowskip N][ -tb| -topbottom][width height][imagedata]
```

DESCRIPTION

rawtopgm reads raw grayscale bytes as input and produces a portable graymap as output. The input file is just grayscale bytes. If you don't specify the width and height on the command line, the program will check the size of the image and try to make a quadratic image of it. It is an error to supply a non-quadratic image without specifying width and height. The `maxval` is assumed to be 255.

OPTIONS

- headerskip If the file has a header, you can use this flag to skip over it.
- rowskip If there is padding at the ends of the rows, you can skip it with this flag. Note that rowskip can be a real number. Amazingly, I once had an image with 0.376 bytes of padding per row. This turned out to be due to a file transfer problem, but I was still able to read the image.
- tb -topbottom Flips the image upside down. The first pixel in a pgm file is in the lower-left corner of the image. For conversion from images with the first pixel in the upper-left corner (for example, the Molecular Dynamics and Leica confocal formats), this flips the image right. This is equivalent to `rawtopgm [file] | pnmflip -tb`.

BUGS

If you don't specify the image width and height, the program will try to read the entire image to a memory buffer. If you get a message that states that you are out of memory, try to specify the width and height on the command line. Also, the `-tb` option consumes much memory.

SEE ALSO

`pgm(5)`, `rawtoppm(1)`, `pnmflip(1)`

AUTHORS

Copyright© 1989 by Jef Poskanzer; modified June 1993 by Oliver Treppe (oliver@fysik4.kth.se).

15 June 1993

rawtoppm

rawtoppm—Convert raw RGB bytes into a portable pixmap

SYNOPSIS

```
rawtoppm[-headerskip N][ -rowskip N][ -rgb| -rbg| -grb | -gbr| -brg| -bgr ]
[-interpixel| -interrow] width height [imagedata]
```

DESCRIPTION

rawtoppm reads raw RGB bytes as input and produces a portable pixmap as output. The input file is just RGB bytes. You have to specify the width and height on the command line because the program obviously can't get them from the file. The `maxval` is assumed to be 255. If the resulting image is upside down, run it through `pnmflip -tb`.

OPTIONS

<code>-headerskip</code>	If the file has a header, you can use this flag to skip over it.
<code>-rowskip</code>	If there is padding at the ends of the rows, you can skip it with this flag.
<code>-rgb -rbg -grb -gbr -brg -bgr</code>	These flags let you specify alternate color orders. The default is <code>-rgb</code> .
<code>-interpixel -interrow</code>	These flags let you specify how the colors are interleaved. The default is <code>-interpixel</code> , meaning interleaved by pixel. A byte of red, a byte of green, and a byte of blue, or whatever color order you specified. <code>-interrow</code> means interleaved by row—a row of red, a row of green, a row of blue, assuming standard RGB color order. An <code>-interplane</code> flag—all the red pixels, then all the green, then all the blue—would be an obvious extension, but is not implemented. You could get the same effect by splitting the file into three parts (perhaps using <code>dd</code>), turning each part into a PGM file with <code>rawtopgm</code> , and then combining them with <code>rgb3toppm</code> .

SEE ALSO

`ppm(5)`, `rawtopgm(1)`, `rgb3toppm(1)`, `pnmf1ip(1)`

AUTHOR

Copyright© 1991 by Jef Poskanzer.

6 February 1991

rcp

`rcp`—Remote file copy

SYNOPSIS

```
rcp [-px] [-k realm] file1 file2
rcp [-px] [-r] [-k Ar realm] file ... directory
```

DESCRIPTION

`rcp` copies files between machines. Each file or directory argument is either a remote filename of the form `rname@rhost:path`, or a local filename (containing no `:` characters, or a `/` before any `:` characters).

- `-r` If any of the source files are directories, `rcp` copies each subtree rooted at that name; in this case the destination must be a directory.
- `-p` Causes `rcp` to attempt to preserve (duplicate) in its copies the modification times and modes of the source files, ignoring the `umask`. By default, the mode and owner of `file2` are preserved if it already existed; otherwise, the mode of the source file modified by the `umask 2` on the destination host is used.
- `-k` Requests `rcp` to obtain tickets for the remote host in realm `realm` instead of the remote host's realm as determined by `krb_realmofhost 3`.
- `-x` Turns on DES encryption for all data passed by `rcp`. This may impact response time and CPU utilization, but provides increased security.

If `path` is not a full pathname, it is interpreted relative to the `login` directory of the specified user `ruser` on `rhost`, or your current username if no other remote username is specified. A path on a remote host may be quoted (using `\`, `"`, or `'`) so that the meta characters are interpreted remotely.

`rcp` does not prompt for passwords; it performs remote execution via `rsh(1)`, and requires the same authorization.

`rcp` handles third-party copies, where neither source nor target files are on the current machine.

SEE ALSO

cp(1), ftp(1), rsh(1), rlogin(1)

HISTORY

The rcp command appeared in BSD 4.2 . The version of rcp described here has been reimplemented with Kerberos in BSD 4.3 Reno.

BUGS

Doesn't detect all cases in which the target of a copy might be a file when only a directory should be legal.

Is confused by any output generated by commands in a or file on the remote host.

The destination username and hostname may have to be specified as rhost.rname when the destination machine is running the BSD 4.2 version of rcp.

BSD 4.3r, 27 July 1991

RCS

rcc—Change RCS file attributes

SYNOPSIS

rcc options file ...

DESCRIPTION

rcc creates new RCS files or changes attributes of existing ones. An RCS file contains multiple revisions of text, an access list, a change log, descriptive text, and some control attributes. For rcc to work, the caller's login name must be on the access list—unless the access list is empty, the caller is the owner of the file or the superuser, or the -i option is present.

Pathnames matching an RCS suffix denote RCS files; all others denote working files. Names are paired as explained in ci(1). Revision numbers use the syntax described in ci(1).

OPTIONS

- i Create and initialize a new RCS file, but do not deposit any revision. If the RCS file has no path prefix, try to place it first into the subdirectory ./RCS, and then into the current directory. If the RCS file already exists, print an error message.
- a logins Append the login names appearing in the comma-separated list logins to the access list of the RCS file.
- A oldfile Append the access list of oldfile to the access list of the RCS file.
- e [logins] Erase the login names appearing in the comma-separated list logins from the access list of the RCS file. If logins is omitted, erase the entire access list.
- b [rev] Set the default branch to rev. If rev is omitted, the default branch is reset to the (dynamically) highest branch on the trunk.
- c string Set the comment leader to string. An initial ci, or an rcc -i without -c, guesses the comment leader from the suffix of the working filename.

This option is obsolescent, since RCS normally uses the preceding \$Log\$ line's prefix when inserting log lines during checkout (see co(1)). However, older versions of RCS use the comment leader instead of the \$Log\$ line's prefix, so if you plan to access a file with both old and new versions of RCS, make sure its comment leader matches its \$Log\$ line prefix.

- k subst Set the default keyword substitution to subst. The effect of keyword substitution is described in co(1). Giving an explicit -k option to co, rcsdiff, and rcsmerge overrides this default. Beware rcc -kv, because -kv is incompatible with co -1. Use rcc -kkv to restore the normal default keyword substitution.

- `-l[rev]` Lock the revision with number `rev`. If a branch is given, lock the latest revision on that branch. If `rev` is omitted, lock the latest revision on the default branch. Locking prevents overlapping changes. If someone else already holds the lock, the lock is broken as with `rcs -u`.
- `-u[rev]` Unlock the revision with number `rev`. If a branch is given, unlock the latest revision on that branch. If `rev` is omitted, remove the latest lock held by the caller. Normally, only the locker of a revision can unlock it. Somebody else unlocking a revision breaks the lock. This causes a mail message to be sent to the original locker. The message contains a commentary solicited from the breaker. The commentary is terminated by end-of-file or by a line containing a period by itself.
- `-L` Set locking to `strict`. `strict` locking means that the owner of an RCS file is not exempt from locking for checkin. This option should be used for files that are shared.
- `-U` Set locking to `non-strict`. `non-strict` locking means that the owner of a file need not lock a revision for checkin. This option should *not* be used for files that are shared. Whether default locking is `strict` is determined by your system administrator, but it is normally `strict`.
- `-mrev:msg` Replace revision `rev`'s log message with `msg`.
- `-M` Do not send mail when breaking somebody else's lock. This option is not meant for casual use; it is meant for programs that warn users by other means, and invoke `rcs -u` only as a low-level lock-breaking operation.
- `-nname[:rev]` Associate the symbolic name `name` with the branch or revision `rev`. Delete the symbolic name if both `:` and `rev` are omitted; otherwise, print an error message if `name` is already associated with another number. If `rev` is symbolic, it is expanded before association. A `rev` consisting of a branch number followed by a period stands for the current latest revision in the branch. A `:` with an empty `rev` stands for the current latest revision on the default branch, normally the trunk. For example, `rcs -nname: RCS/*` associates `name` with the current latest revision of all the named RCS files; this contrasts with `rcs -nname:$ RCS/*`, which associates `name` with the revision numbers extracted from keyword strings in the corresponding working files.
- `-Nname[:rev]` Act like `-n`, except override any previous assignment of `name`.
- `-orange` Deletes ("outdates") the revisions given by `range`. A range consisting of a single revision number means that revision. A range consisting of a branch number means the latest revision on that branch. A range of the form `rev1:rev2` means revisions `rev1` to `rev2` on the same branch, `:rev` means from the beginning of the branch containing `rev` up to and including `rev`, and `rev:` means from revision `rev` to the end of the branch containing `rev`. None of the outdated revisions can have branches or locks.
- `-q` Run quietly; do not print diagnostics.
- `-I` Run interactively, even if the standard input is not a terminal.
- `-ssstate[:rev]` Set the state attribute of the revision `rev` to `state`. If `rev` is a branch number, assume the latest revision on that branch. If `rev` is omitted, assume the latest revision on the default branch. Any identifier is acceptable for `state`. A useful set of states is `Exp` (for experimental), `Stab` (for stable), and `Re1` (for released). By default, `ci(1)` sets the state of a revision to `Exp`.
- `-t[file]` Write descriptive text from the contents of the named `file` into the RCS file, deleting the existing text. The `file` pathname cannot begin with `~`. If `file` is omitted, obtain the text from standard input, terminated by end-of-file or by a line containing a period by itself. Prompt for the text if interaction is possible; see `-I`. With `-i`, descriptive text is obtained even if `-t` is not given.
- `-t-string` Write descriptive text from the `string` into the RCS file, deleting the existing text.
- `-T` Preserve the modification time on the RCS file unless a revision is removed. This option can suppress extensive recompilation caused by a `make(1)` dependency of some copy of the working file on the RCS file. Use this option with care; it can suppress recompilation even when it is needed, that is, when a change to the RCS file would mean a change to keyword strings in the working file.
- `-V` Print RCS's version number.
- `-Vn` Emulate RCS version `n`. See `co(1)` for details.
- `-xsuffixes` Use `suffixes` to characterize RCS files. See `ci(1)` for details.
- `-zzone` Use `zone` as the default time zone. This option has no effect; it is present for compatibility with other RCS commands.

At least one explicit option must be given, to ensure compatibility with future planned extensions to the `rcs` command.

COMPATIBILITY

The `-brev` option generates an RCS file that cannot be parsed by RCS version 3 or earlier.

The `-ksbst` options (except `-kkv`) generate an RCS file that cannot be parsed by RCS version 4 or earlier.

Use `rcs -vn` to make an RCS file acceptable to RCS version `n` by discarding information that would confuse version `n`.

RCS version 5.5 and earlier does not support the `-x` option, and requires a `,v` suffix on an RCS pathname.

FILES

`rcs` accesses files much as `ci(1)` does, except that it uses the effective user for all accesses, it does not write the working file or its directory, and it does not even read the working file unless a revision number of `$` is specified.

ENVIRONMENT

`RCSINITf1[: rev]` Options prepended to the argument list, separated by spaces. See `ci(1)` for details.

DIAGNOSTICS

The RCS pathname and the revisions outdated are written to the diagnostic output. The exit status is zero if and only if all operations were successful.

IDENTIFICATION

Author: Walter F. Tichy.

Manual Page Revision: 5.13; Release Date: 1995/06/05.

Copyright 1982, 1988, 1989 Walter F. Tichy.

Copyright 1990, 1991, 1992, 1993, 1994, 1995 Paul Eggert.

SEE ALSO

`rcsintro(1)`, `co(1)`, `ci(1)`, `ident(1)`, `rcsclean(1)`, `rcsdiff(1)`, `rcsmerge(1)`, `rlog(1)`, `rcsfile(5)`

“RCS—A System for Version Control” by Walter F. Tichy, *Software Practice & Experience* 15, 7 (July 1985), pages 637-654.

BUGS

A catastrophe (for example, a system crash) can cause RCS to leave behind a semaphore file that causes later invocations of RCS to claim that the RCS file is in use. To fix this, remove the semaphore file. A semaphore file’s name typically begins with a comma or ends with an underscore.

The separator for revision ranges in the `-o` option used to be `-` instead of `:`, but this leads to confusion when symbolic names contain `-`. For backwards compatibility, `rcs -o` still supports the old `-` separator, but it warns about this obsolete use.

Symbolic names need not refer to existing revisions or branches. For example, the `-o` option does not remove symbolic names for the outdated revisions; you must use `-n` to remove the names.

GNU, 5 June 1995

rcsclean

`rcsclean`—Clean up working files

SYNOPSIS

`rcsclean [options][file ...]`

DESCRIPTION

`rcsclean` removes files that are not being worked on. `rcsclean -u` also unlocks and removes files that are being worked on but have not changed.

For each `file` given, `rcsclean` compares the working file and a revision in the corresponding RCS file. If it finds a difference, it does nothing. Otherwise, it first unlocks the revision if the `-u` option is given, and then removes the working file unless the working file is writable and the revision is locked. It logs its actions by outputting the corresponding `rcs -u` and `rm -f` commands on the standard output.

Files are paired as explained in `ci(1)`. If no `file` is given, all working files in the current directory are cleaned. Pathnames matching an RCS suffix denote RCS files; all others denote working files.

The number of the revision to which the working file is compared may be attached to any of the options `-n`, `-q`, `-r`, or `-u`. If no revision number is specified, then if the `-u` option is given and the caller has one revision locked, `rcsclean` uses that revision; otherwise, `rcsclean` uses the latest revision on the default branch, normally the root.

`rcsclean` is useful for `clean` targets in makefiles. See also `rcsdiff(1)`, which prints out the differences, and `ci(1)`, which normally reverts to the previous revision if a file was not changed.

OPTIONS

<code>-ksubst</code>	Use <code>subst</code> -style keyword substitution when retrieving the revision for comparison. See <code>co(1)</code> for details.
<code>-n[rev]</code>	Do not actually remove any files or unlock any revisions. Using this option will tell you what <code>rcsclean</code> would do without actually doing it.
<code>--q[rev]</code>	Do not log the actions taken on standard output.
<code>--r[rev]</code>	This option has no effect other than specifying the revision for comparison.
<code>-T</code>	Preserve the modification time on the RCS file even if the RCS file changes because a lock is removed. This option can suppress extensive recompilation caused by a <code>make(1)</code> dependency of some other copy of the working file on the RCS file. Use this option with care; it can suppress recompilation even when it is needed, that is, when the lock removal would mean a change to keyword strings in the other working file.
<code>-u[rev]</code>	Unlock the revision if it is locked and no difference is found.
<code>-V</code>	Print RCS's version number.
<code>-Vn</code>	Emulate RCS version <code>n</code> . See <code>co(1)</code> for details.
<code>-xsuffixes</code>	Use <code>suffixes</code> to characterize RCS files. See <code>ci(1)</code> for details.
<code>-zzone</code>	Use <code>zone</code> as the time zone for keyword substitution; see <code>co(1)</code> for details.

EXAMPLES

`rcsclean *.c *.h` removes all working files ending in `.c` or `.h` that were not changed since their checkout.

`rcsclean` removes all working files in the current directory that were not changed since their check-out.

FILES

`rcsclean` accesses files much as `ci(1)` does.

ENVIRONMENT

RCSINIT Options prepended to the argument list, separated by spaces. A backslash escapes spaces within an option. The **RCSINIT** options are prepended to the argument lists of most `rcs` commands. Useful **RCSINIT** options include `-q`, `-V`, `-x`, and `-z`.

DIAGNOSTICS

The exit status is zero if and only if all operations were successful. Missing working files and RCS files are silently ignored.

IDENTIFICATION

Author: Walter F. Tichy.

Manual Page Revision: 1.12; Release Date: 1993/11/03.

Copyright© 1982, 1988, 1989 Walter F. Tichy.

Copyright© 1990, 1991, 1992, 1993 Paul Eggert.

SEE ALSO

`ci(1)`, `co(1)`, `ident(1)`, `rcs(1)`, `rcsdiff(1)`, `rcsintro(1)`, `rcsmerge(1)`, `rlog(1)`, `rcsfile(5)`

“RCS—A System for Version Control” by Walter F. Tichy, *Software Practice & Experience* 15, 7 (July 1985), pages 637-654.

BUGS

At least one file must be given in older UNIX versions that do not provide the needed directory scanning operations.

GNU, 3 November 1993

rcsdiff

rcsdiff—Compare rcs revisions

SYNOPSIS

```
rcsdiff [ -ksubst ][-q ][-rrev1 [ -rrev2 ]][-T ][-V[n]][-xsuffixes ][-zzone ]
[diff options ] file . . .
```

DESCRIPTION

rcsdiff runs `diff(1)` to compare two revisions of each RCS file given.

Pathnames matching an RCS suffix denote RCS files; all others denote working files. Names are paired as explained in `ci(1)`.

The option `-q` suppresses diagnostic output. Zero, one, or two revisions may be specified with `-r`. The option `-ksubst` affects keyword substitution when extracting revisions, as described in `co(1)`; for example, `-kk -r1.1 -r1.2` ignores differences in keyword values when comparing revisions 1.1 and 1.2. To avoid excess output from locker name substitution, `-kkv1` is assumed if at most one revision option is given, no `-k` option is given, `-kkv` is the default keyword substitution, and the working file's mode would be produced by `co -1`. See `co(1)` for details about `-T`, `-V`, `-x`, and `-z`. Otherwise, all options of `diff(1)` that apply to regular files are accepted, with the same meaning as for `diff`.

If both `rev1` and `rev2` are omitted, `rcsdiff` compares the latest revision on the default branch (by default the trunk) with the contents of the corresponding working file. This is useful for determining what you changed since the last checkin.

If `rev1` is given, but `rev2` is omitted, `rcsdiff` compares revision `rev1` of the RCS file with the contents of the corresponding working file.

If both `rev1` and `rev2` are given, `rcsdiff` compares revisions `rev1` and `rev2` of the RCS file.

Both `rev1` and `rev2` may be given numerically or symbolically.

EXAMPLE

The command

```
rcsdiff f.c
```

compares the latest revision on the default branch of the RCS file to the contents of the working file `f.c`.

ENVIRONMENT

RCSINIT Options prepended to the argument list, separated by spaces. See `ci(1)` for details.

DIAGNOSTICS

Exit status is 0 for no differences during any comparison, 1 for some differences, 2 for trouble.

IDENTIFICATION

Author: Walter F. Tichy.

Manual Page Revision: 5.5; Release Date: 1993/11/03.

Copyright© 1982, 1988, 1989 Walter F. Tichy.

Copyright© 1990, 1991, 1992, 1993 Paul Eggert.

SEE ALSO

`ci(1)`, `co(1)`, `diff(1)`, `ident(1)`, `rcs(1)`, `racsintro(1)`, `racsmerge(1)`, `rlog(1)`

“RCS—A System for Version Control” by Walter F. Tichy, *Software Practice & Experience* 15, 7 (July 1985), pages 637–654.

GNU, 3 November 1993

rscsfreeze

`rscsfreeze`—Freeze a configuration of sources checked in under RCS

SYNOPSIS

`rscsfreeze` [*name*]

DESCRIPTION

`rscsfreeze` assigns a symbolic revision number to a set of RCS files that form a valid configuration.

The idea is to run `rscsfreeze` each time a new version is checked in. A unique symbolic name (`c_number`, where *number* is increased each time `rscsfreeze` is run) is then assigned to the most recent revision of each RCS file of the main trunk.

An optional *name* argument to `rscsfreeze` gives a symbolic name to the configuration. The unique identifier is still generated and is listed in the log file, but it will not appear as part of the symbolic revision name in the actual RCS files.

A log message is requested from the user for future reference.

The shell script works only on all RCS files at one time. All changed files must be checked in already. Run `rcsclean(1)` first and see whether any sources remain in the current directory.

FILES

<code>RCS/.rscsfreeze.ver</code>	Version number
<code>RCS/.rscsfreeze.log</code>	Log messages, most recent first

AUTHOR

Stephan V. Bechtolsheim

SEE ALSO

`co(1)`, `racs(1)`, `rcsclean(1)`, `rlog(1)`

BUGS

`rscsfreeze` does not check whether any sources are checked out and modified.

Although both source filenames and RCS filenames are accepted, they are not paired as usual with `racs` commands.

Error checking is rudimentary.

`rcsfreeze` is just an optional example shell script, and should not be taken too seriously. See `cvs` for a more complete solution.

GNU, 3 November 1990

rcsintro

rcsintro—Introduction to `rcs` commands

DESCRIPTION

The Revision Control System (RCS) manages multiple revisions of files. RCS automates the storing, retrieval, logging, identification, and merging of revisions. RCS is useful for text that is revised frequently; for example programs, documentation, graphics, papers, and form letters.

The basic user interface is extremely simple. The novice only needs to learn two commands: `ci(1)` and `co(1)`. `ci`, short for check in, deposits the contents of a file into an archival file called an RCS file. An RCS file contains all revisions of a particular file. `co`, short for check out, retrieves revisions from an RCS file.

FUNCTIONS OF RCS

Store and retrieve multiple revisions of text. RCS saves all old revisions in a space-efficient way. Changes no longer destroy the original because the previous revisions remain accessible. Revisions can be retrieved according to ranges of revision numbers, symbolic names, dates, authors, and states.

Maintain a complete history of changes. RCS logs all changes automatically. Besides the text of each revision, RCS stores the author, the date and time of checkin, and a log message summarizing the change. The logging makes it easy to find out what happened to a module without having to compare source listings or having to track down colleagues.

Resolve access conflicts. When two or more programmers wish to modify the same revision, RCS alerts the programmers and prevents one modification from corrupting the other.

Maintain a tree of revisions. RCS can maintain separate lines of development for each module. It stores a tree structure that represents the ancestral relationships among revisions.

Merge revisions and resolve conflicts. Two separate lines of development of a module can be coalesced by merging. If the revisions to be merged affect the same sections of code, RCS alerts the user about the overlapping changes.

Control releases and configurations. Revisions can be assigned symbolic names and marked as released, stable, experimental, and so on. With these facilities, configurations of modules can be described simply and directly.

Automatically identify each revision with name, revision number, creation time, author, and so on. The identification is like a stamp that can be embedded at an appropriate place in the text of a revision. The identification makes it simple to determine which revisions of which modules make up a given configuration.

Minimize secondary storage. RCS needs little extra space for the revisions (only the differences). If intermediate revisions are deleted, the corresponding deltas are compressed accordingly.

GETTING STARTED WITH RCS

Suppose you have a file `f.c` that you wish to put under control of RCS. If you have not already done so, make an `RCS` directory with the command:

```
mkdir RCS
```

Then invoke the check in command:

```
ci f.c
```

This command creates an RCS file in the `RCS` directory, stores `f.c` into it as revision 1.1, and deletes `f.c`. It also asks you for a description. The description should be a synopsis of the contents of the file. All later check in commands will ask you for a log entry, which should summarize the changes that you made.

Files in the `RCS` directory are called RCS files; the others are called working files. To get back the working file `f.c` in the previous example, use the check out command:

```
co f.c
```

This command extracts the latest revision from the RCS file and writes it into `f.c`. If you want to edit `f.c`, you must lock it as you check it out with the command:

```
co -l f.c
```

You can now edit `f.c`.

Suppose after some editing you want to know what changes that you have made. The command:

```
rcsdiff f.c
```

tells you the difference between the most recently checked-in version and the working file. You can check the file back in by invoking

```
ci f.c
```

This increments the revision number properly.

If `ci` complains with the message:

```
ci error: no lock set by your name
```

then you have tried to check in a file even though you did not lock it when you checked it out. Of course, it is too late now to do the checkout with locking, because another checkout would overwrite your modifications. Instead, invoke

```
rcs -l f.c
```

This command will lock the latest revision for you, unless somebody else got ahead of you already. In that case, you'll have to negotiate with that person.

Locking assures that you, and only you, can check in the next update, and avoids nasty problems if several people work on the same file. Even if a revision is locked, it can still be checked out for reading, compiling, and so on. All that locking prevents is a check-in by anybody but the locker.

If your RCS file is private—if you are the only person who is going to deposit revisions into it—strict locking is not needed and you can turn it off. If strict locking is turned off, the owner of the RCS file need not have a lock for checkin; all others still do. Turning strict locking off and on is done with the commands `rcs -U f.c` and `rcs -L f.c`. If you don't want to clutter your working directory with RCS files, create a subdirectory called `RCS` in your working directory, and move all your RCS files there. `rcs` commands will look first into that directory to find needed files. All the commands discussed here will still work, without any modification. (Actually, pairs of RCS and working files can be specified in three ways: both are given, only the working file is given, or only the RCS file is given. Both RCS and working files may have arbitrary path prefixes; `rcs` commands pair them up intelligently.)

To avoid the deletion of the working file during checkin (in case you want to continue editing or compiling), invoke

```
ci -l f.c or ci -u f.c
```

These commands check in `f.c` as usual, but perform an implicit checkout. The first form also locks the checked in revision, the second one doesn't. Thus, these options save you one checkout operation. The first form is useful if you want to continue editing, the second one if you just want to read the file. Both update the identification markers in your working file. (See the following subsection, "Automatic Identification.")

You can give `ci` the number you want assigned to a checked in revision. Assume all your revisions were numbered 1.1, 1.2, 1.3, etc., and you would like to start release 2. The command:

```
ci -r2 f.c or ci -r2.1 f.c
```

assigns the number 2.1 to the new revision. From then on, `ci` will number the subsequent revisions with 2.2, 2.3, and so on. The corresponding `co` commands:

```
co -r2 f.c
```

and

```
co -r2.1 f.c
```

retrieve the latest revision numbered 2.x and the revision 2.1, respectively. `co` without a revision number selects the latest revision on the trunk, that is, the highest revision with a number consisting of two fields. Numbers with more than two fields are needed for branches. For example, to start a branch at revision 1.3, invoke

```
ci -r1.3.1 f.c
```

This command starts a branch numbered 1 at revision 1.3, and assigns the number 1.3.1.1 to the new revision. For more information about branches, see `rcsfile(5)`.

AUTOMATIC IDENTIFICATION

RCS can put special strings for identification into your source and object code. To obtain such identification, place the marker:

```
$Id$
```

into your text, for instance inside a comment. RCS will replace this marker with a string of the form:

```
$Id: filename revision date time author state $
```

With such a marker on the first page of each module, you can always see with which revision you are working. RCS keeps the markers up-to-date automatically. To propagate the markers into your object code, simply put them into literal character strings. In C, this is done as follows:

```
static char rcsid[] = "$Id$";
```

The command `ident` extracts such markers from any file, even object code and dumps. Thus, `ident` lets you find out which revisions of which modules were used in a given program.

You may also find it useful to put the marker `$Log$` into your text, inside a comment. This marker accumulates the log messages that are requested during checkin. Thus, you can maintain the complete history of your file directly inside it. There are several additional identification markers; see `co(1)` for details.

IDENTIFICATION

Author: Walter F. Tichy.

Manual Page Revision: 5.3; Release Date: 1993/11/03.

Copyright© 1982, 1988, 1989 Walter F. Tichy.

Copyright© 1990, 1991, 1992, 1993 Paul Eggert.

SEE ALSO

`ci(1)`, `co(1)`, `ident(1)`, `rcs(1)`, `rcsdiff(1)`, `rcsintro(1)`, `rcsmerge(1)`, `rlog(1)`

“RCS—A System for Version Control” by Walter F. Tichy, *Software Practice & Experience* 15, 7 (July 1985), pages 637–654.

GNU, 3 November 1993

rcsmerge

rcsmerge—Merge RCS revisions

SYNOPSIS

```
rcsmerge [options] file
```

DESCRIPTION

`rcsmerge` incorporates the changes between two revisions of an RCS file into the corresponding working file.

Pathnames matching an RCS suffix denote RCS files; all others denote working files. Names are paired as explained in `ci(1)`.

At least one revision must be specified with one of the options described in the next subsection, usually `-r`. At most two revisions may be specified. If only one revision is specified, the latest revision on the default branch (normally the highest branch on the trunk) is assumed for the second revision. Revisions may be specified numerically or symbolically.

`rcsmerge` prints a warning if there are overlaps, and delimits the overlapping regions as explained in `merge(1)`. The command is useful for incorporating changes into a checked-out revision.

OPTIONS

- `-A` Output conflicts using the `-A` style of `diff3(1)`, if supported by `diff3`. This merges all changes leading from `file2` to `file3` into `file1`, and generates the most verbose output.
- `-E, -e` These options specify conflict styles that generate less information than `-A`. See `diff3(1)` for details. The default is `-E`. With `-e`, `rcsmerge` does not warn about conflicts.
- `-ksubst` Use `subst`-style keyword substitution. See `co(1)` for details. For example, `-kk -r1.1 -r1.2` ignores differences in keyword values when merging the changes from 1.1 to 1.2. It normally does not make sense to merge binary files as if they were text, so `rcsmerge` refuses to merge files if `-kb` expansion is used.
- `-p[ rev]` Send the result to standard output instead of overwriting the working file.
- `-q[ rev]` Run quietly; do not print diagnostics.
- `-r[ rev]` Merge with respect to revision `rev`. Here an empty `rev` stands for the latest revision on the default branch, normally the head.
- `-T` This option has no effect; it is present for compatibility with other `rcs` commands.
- `-V` Print RCS's version number.
- `-Vn` Emulate RCS version `n`. See `co(1)` for details.
- `-xsuffixes` Use `suffixes` to characterize RCS files. See `ci(1)` for details.
- `-zzone` Use `zone` as the time zone for keyword substitution. See `co(1)` for details.

EXAMPLES

Suppose you have released revision 2.8 of `f.c`. Assume, furthermore, that after you complete an unreleased revision 3.4, you receive updates to release 2.8 from someone else. To combine the updates to 2.8 and your changes between 2.8 and 3.4, put the updates to 2.8 into file `f.c` and execute

```
rcsmerge -p -r2.8 -r3.4 f.c >f.merged.c
```

Then examine `f.merged.c`. Alternatively, if you want to save the updates to 2.8 in the RCS file, check them in as revision 2.8.1.1 and execute `co -j`:

```
ci -r2.8.1.1 f.c
co -r3.4 -j2.8:2.8.1.1 f.c
```

As another example, the following command undoes the changes between revision 2.4 and 2.8 in your currently checked out revision in `f.c`:

```
rcsmerge -r2.8 -r2.4 f.c
```

Note the order of the arguments, and that `f.c` will be overwritten.

ENVIRONMENT

`RCSINIT` Options prepended to the argument list, separated by spaces. See `ci(1)` for details.

DIAGNOSTICS

Exit status is 0 for no overlaps, 1 for some overlaps, 2 for trouble.

IDENTIFICATION

Author: Walter F. Tichy.

Manual Page Revision: 5.6; Release Date: 1995/06/01.

Copyright© 1982, 1988, 1989 Walter F. Tichy.

Copyright© 1990, 1991, 1992, 1993, 1994, 1995 Paul Eggert.

SEE ALSO

`ci(1)`, `co(1)`, `ident(1)`, `merge(1)`, `rcs(1)`, `rcsdiff(1)`, `rcsintro(1)`, `rlog(1)`, `rcsfile(5)`

“RCS—A System for Version Control” by Walter F. Tichy, *Software-Practice & Experience* 15, 7 (July 1985), pages 637–654.

GNU, 1 June 1995

rdist

rdist—Remote file distribution program

SYNOPSIS

```
rdist [-nqbRhivwy] [-f distfile] [-d var=value] [-m host] [name ...]
rdist [-nqbRhivwy] -c name ... [login@host:dest]
```

DESCRIPTION

rdist is a program to maintain identical copies of files over multiple hosts. It preserves the owner, group, mode, and mtime of files if possible and can update programs that are executing. rdist reads commands from `distfile` to direct the updating of files and/or directories.

Options specific to the first SYNOPSIS form:

- If `distfile` is `-`, the standard input is used.
- f `distfile` Use the specified `distfile`.

If either the `-f` or `-` option is not specified, the program looks first for `distfile`, then `Distfile` to use as the input. If no names are specified on the command line, rdist will update all of the files and directories listed in `distfile`. Otherwise, the argument is taken to be the name of a file to be updated or the label of a command to execute. If label and filenames conflict, it is assumed to be a label. These may be used together to update specific files using specific commands.

Options specific to the second SYNOPSIS form:

- c Forces rdist to interpret the remaining arguments as a small `distfile`.
The equivalent `distfile` is as follows:
`name ... -i login@ host install dest ;`

Options common to both forms:

- b Binary comparison. Perform a binary comparison and update files if they differ rather than comparing dates and sizes.
- d `var=value` Define `var` to have `value`. The `-d` option is used to define or override variable definitions in the `distfile`. `value` can be the empty string, one name, or a list of names surrounded by parentheses and separated by tabs and/or spaces.
- h Follow symbolic links. Copy the file that the link points to rather than the link itself.
- i Ignore unresolved links. rdist will normally try to maintain the link structure of files being transferred and warn the user if all the links cannot be found.
- m `host` Limit which machines are to be updated. Multiple `-m` arguments can be given to limit updates to a subset of the hosts listed in the `distfile`.

- n Print the commands without executing them. This option is useful for debugging `distfile`.
- q Quiet mode. Files that are being modified are normally printed on standard output. The `-q` option suppresses this.
- R Remove extraneous files. If a directory is being updated, any files that exist on the remote host that do not exist in the master directory are removed. This is useful for maintaining truly identical copies of directories.
- v Verify that the files are up-to-date on all the hosts. Any files that are out-of-date will be displayed, but no files will be changed nor any mail sent.
- w Whole mode. The whole filename is appended to the destination directory name. Normally, only the last component of a name is used when renaming files. This will preserve the directory structure of the files being copied instead of flattening the directory structure. For example, renaming a list of files such as `dir1/f1 dir2/f2` to `dir3` would create files `dir3/dir1/f1` and `dir3/dir2/f2` instead of `dir3/f1` and `dir3/f2`.
- y Younger mode. Files are normally updated if their mtime and size (see `stat(2)` for more details) disagree. The `-y` option causes `rdist` not to update files that are younger than the master copy. This can be used to prevent newer copies on other hosts from being replaced. A warning message is printed for files that are newer than the master copy.

`distfile` contains a sequence of entries that specify the files to be copied, the destination hosts, and what operations to perform to do the updating. Each entry has one of the following formats:

```
<variable name> '=' <name list>
[label:]<source list> '-'> <destination list><command list>
[label:]<source list> '::' <time_stamp file><command list>
```

The first format is used for defining variables. The second format is used for distributing files to other hosts. The third format is used for making lists of files that have been changed since some given date. The source list specifies a list of files and/or directories on the local host that are to be used as the master copy for distribution. The destination list is the list of hosts to which these files are to be copied. Each file in the source list is added to a list of changes if the file is out-of-date on the host that is being updated (second format), or the file is newer than the timestamp file (third format).

Labels are optional. They are used to identify a command for partial updates.

Newlines, tabs, and blanks are only used as separators and are otherwise ignored. Comments begin with `#` and end with a newline.

Variables to be expanded begin with `$` followed by one character or a name enclosed in curly braces (see the examples at the end).

The source and destination lists have the following format: `<name>` or `'(' <zero or more names separated by white-space> ')'`.

The shell meta characters `[`, `]`, `{`, `}`, `*`, and `?` are recognized and expanded (on the local host only) in the same way as `csh(1)`. They can be escaped with a backslash. The ``` character is also expanded in the same way as `csh(1)` but is expanded separately on the local and destination hosts. When the `-w` option is used with a filename that begins with ```, everything except the home directory is appended to the destination name. Filenames that do not begin with `/` or ``` use the destination user's home directory as the root directory for the rest of the filename.

The command list consists of zero or more commands of the following format:

```
'install' <options> opt_dest_name ';'
'notify' <name list> ';'
'except' <name list> ';'
'except_pat' <pattern list> ';'
'special' <name list> string ';'

```

The `install` command is used to copy out-of-date files and/or directories. Each source file is copied to each host in the destination list. Directories are recursively copied in the same way. `opt_dest_name` is an optional parameter to rename files. If no `install` command appears in the command list or the destination name is not specified, the source filename is used.

Directories in the pathname will be created if they do not exist on the remote host. To help prevent disasters, a nonempty directory on a target host will never be replaced with a regular file or a symbolic link. However, under the `-R` option, a nonempty directory will be removed if the corresponding filename is completely absent on the master host. The options are `-R`, `-h`, `-i`, `-v`, `-w`, `-y`, and `-b` and have the same semantics as options on the command line except they only apply to the files in the source list. The login name used on the destination host is the same as the local host unless the destination name is of the format `login@host`.

The `notify` command is used to mail the list of files updated (and any errors that may have occurred) to the listed names. If no `@` appears in the name, the destination host is appended to the name (for example, `name1@host`, `name2@host`).

The `except` command is used to update all of the files in the source list except for the files listed in `name list`. This is usually used to copy everything in a directory except certain files.

The `except_pat` command is like the `except` command except that `pattern list` is a list of regular expressions (see `ed(1)` for details). If one of the patterns matches some string within a filename, that file will be ignored. Note that because `\` is a quote character, it must be doubled to become part of the regular expression. Variables are expanded in `pattern list`, but not shell file pattern-matching characters. To include a `$`, it must be escaped with `\`.

The `special` command is used to specify `sh(1)` commands that are to be executed on the remote host after the file in `name list` is updated or installed. If the `name list` is omitted, then the shell commands will be executed for every file updated or installed. The shell variable `FILE` is set to the current filename before executing the commands in `string`. `string` starts and ends with double quotes (`"`) and can cross multiple lines in `distfile`. Multiple commands to the shell should be separated by a semicolon. Commands are executed in the user's home directory on the host being updated. The special command can be used to rebuild private databases, and so on after a program has been updated.

The following is a small example:

```
HOSTS = ( matisse root@arpa )

FILES = ( /bin /lib /usr/bin /usr/games
  /usr/include/{*.h,{stand,sys,vax*,pascal,machine}}/*.h
  /usr/lib /usr/man/man? /usr/ucb /usr/local/rdist )

EXLIB = ( Mail.rc aliases aliases.dir aliases.pag crontab dshrc sendmail.cf
  sendmail.fc sendmail.hf sendmail.st uuvc vfont )

${FILES} -> ${HOSTS} install -R ; except /usr/lib/${EXLIB} ; except /usr/games/lib ;
special /usr/lib/sendmail "/usr/lib/sendmail -bz" ;

srcs: /usr/src/bin -> arpa except pat ( \\o\$ /SCCS\$);

IMAGEN = ( ips dviimp catdvi )

imagen: /usr/local/${IMAGEN} -> arpa install /usr/local/lib ; notify ralph ;

${FILES} :: stamp.cory notify root@cory ;
```

FILES

<code>distfile</code>	Input command file
<code>/tmp/rdist*</code>	Temporary file for update lists

SEE ALSO

`sh(1)`, `csh(1)`, `stat(2)`

HISTORY

The `rdist` command appeared in BSD 4.3.

DIAGNOSTICS

A complaint about mismatch of `rdist` version numbers may really stem from some problem with starting your shell; for example, you are in too many groups.

BUGS

Source files must reside on the local host where `rdist` is executed.

There is no easy way to have a special command executed after all files in a directory have been updated.

Variable expansion only works for name lists; there should be a general macro facility.

`rdist` aborts on files that have a negative mtime (before Jan 1, 1970).

There should be a `force` option to allow replacement of nonempty directories by regular files or symlinks. A means of updating file modes and owners of otherwise identical files is also needed.

BSD 4.3, 30 December 1993

reconfig

`reconfig`—Convert old Xconfig to new XF86Config

SYNOPSIS

```
reconfig < Xconfig > XF86Config
```

DESCRIPTION

The `reconfig` program converts the Xconfig file format used in XFree86 versions prior to 3.1 into the XF86Config format currently used. The XF86Config format contains more information than the Xconfig format, so manual editing is required after converting.

SEE ALSO

XFree86(1), XF86Config(4/5), xf86config(1)

AUTHOR

Gertjan Akkerman

BUGS

Comment lines are stripped out when converting.

XFree86 Version 3.1.1

ref

ref—Display a C function header

SYNOPSIS

```
ref [-t] [-x] [-c class]... [-f file]... tag
```

DESCRIPTION

ref quickly locates and displays the header of a function. To do this, ref looks in the tags file for the line that describes the function, and then scans the source file for the function. When it locates the function, it displays an introductory comment (if there is one), the function's declaration, and the declarations of all arguments.

SEARCH METHOD

ref uses a fairly sophisticated tag look-up algorithm. If you supply a filename via -f file, then elvis first scans the tags file for a static tag from that file. This search is limited to the tags file in the current directory.

If you supply a class name via -c class, then elvis searches for a tag from that class. This search is not limited to the current directory; You can supply a list of directories in the environment variable TAGPATH, and ref will search through the tags file in each directory until it finds a tag in the desired class.

If that fails, ref will then try to look up an ordinary global tag. This search checks all of the directories listed in TAGPATH, too. If the tag being sought doesn't contain any colons, and you haven't given a -x flag, then any static tags in a tags file will be treated as global tags.

If you've given the -t flag, then ref will simply output the tag line that it found, and then exit. Without -t, though, ref will search for the tag line. It will try to open the source file, which should be in the same directory as the tags file where the tag was discovered. If the source file doesn't exist, or is unreadable, then ref will try to open a file called refs in that directory. Either way, ref will try to locate the tag, and display whatever it finds.

INTERACTION WITH elvis

ref is used by the elvis shift-K command. If the cursor is located on a word such as *splat*, in the file *foo.c*, then elvis will invoke ref with the command `ref -f foo.c splat`.

If elvis has been compiled with the -DEXTERNAL_TAGS flag, then elvis will use ref to scan the tags files. This is slower than the built-in tag searching, but it allows elvis to access the more sophisticated tag lookup provided by ref. Other than that, external tags should act exactly like internal tags.

OPTIONS

- t Output tag info, instead of the function header.
- f file The tag might be a static function in file. You can use several -f flags to have ref consider static tags from more than one file.
- c class The tag might be a member of class class. You can use several -c flags to have ref consider tags from more than one class.

FILES

- tags List of function names and their locations, generated by ctags
- refs Function headers extracted from source files (optional)

ENVIRONMENT

- TAGPATH List of directories to be searched. The elements in the list are separated by either semicolons (for MS-DOS, Atari TOS, and AmigaDos), or by colons (every other operating system). For each operating system, ref has a built-in default which is probably adequate.

NOTES

You might want to generate a `tags` file for the directory that contains the source code for standard C library on your system. If licensing restrictions prevent you from making the library source readable by everybody, then you can have `ctags` generate a `refs` file, and make `refs` readable by everybody.

If your system doesn't come with the library source code, then perhaps you can produce something workable from the `lint` libraries.

SEE ALSO

`elvis(1)`, `ctags(1)`

AUTHOR

Steve Kirkendall (kirkenda@cs.pdx.edu)

reset

`reset`—Reset the terminal

SYNOPSIS

`clear`

DESCRIPTION

`reset` calls `tput(1)` with the `clear`, `rmacs`, `rmm`, `rmul`, `rs1`, `rs2`, and `rs3` arguments. This causes `tput` to send appropriate reset strings to the terminal based on information in `/etc/termcap` (for the GNU or BSD `tput`) or in the `terminfo` database (for the ncurses `tput`). This sequence seems to be sufficient to reset the Linux VC's when they start printing “funny-looking” characters. For good measure, `stty(1)` is called with the `sane` argument in an attempt to get Cooked mode back.

SEE ALSO

`reset(1)`, `stty(1)`, `tput(1)`

AUTHOR

Rik Faith (faith@cs.unc.edu)

Linux 0.99, 10 October 1993

resize

`resize`—Set `TERMCAP` and terminal settings to current `xterm` window size

SYNOPSIS

```
resize [ -u | -c ][-s [ row col ]]
```

DESCRIPTION

`resize` prints a shell command for setting the `TERM` and `TERMCAP` environment variables to indicate the current size of `xterm` window from which the command is run. For this output to take effect, `resize` must either be evaluated as part of the command line (usually done with a shell alias or function) or else redirected to a file that can then be read in. From the C shell (usually known as `/bin/csh`), the following alias could be defined in the user's `.cshrc`:

```
% alias rs 'set noglob; eval `resize`'
```

After resizing the window, the user would type:

```
%rs
```

Users of versions of the Bourne shell (usually known as `/bin/sh`) that don't have command functions will need to send the output to a temporary file and then read it back in with the `.` command:

```
$ resize > /tmp/out
$ . /tmp/out
```

OPTIONS

The following options may be used with `resize`:

- `-u` This option indicates that Bourne shell commands should be generated even if the user's current shell isn't `/bin/sh`.
- `-c` This option indicates that C shell commands should be generated even if the user's current shell isn't `/bin/csh`.
- `-s [rows columns]` This option indicates that Sun console escape sequences will be used instead of the special `xterm` escape code. If `rows` and `columns` are given, `resize` will ask the `xterm` to resize itself. However, the window manager may choose to disallow the change.

FILES

- `/etc/termcap` For the base `termcap` entry to modify
- `~/.cshrc` User's alias for the command

SEE ALSO

`csh(1)`, `tset(1)`, `xterm(1)`

AUTHORS

Mark Vandevoorde (MIT-Athena), Edward Moy (Berkeley)
 Copyright© 1984, 1985 by XConsortium
 See `X(1)` for a complete copyright notice.

BUGS

The `-u` or `-c` must appear to the left of `-s` if both are specified.

X Version 11 Release 6

rev

`rev`—Reverse lines of a file

SYNOPSIS

```
rev [file]
```

DESCRIPTION

The `rev` utility copies the specified files to the standard output, reversing the order of characters in every line. If no files are specified, the standard input is read.

21 March 1992

rgb3toppm

`rgb3toppm`—Combine three portable graymaps into one portable pixmap

SYNOPSIS

```
rgb3toppmredpgmfile greenpgmfile bluepgmfile
```

DESCRIPTION

`rgb3toppm` reads three portable graymaps as input and combines them and produces one portable pixmap as output.

SEE ALSO

`ppmtorgb3(1)`, `pgmtoppm(1)`, `ppmtopgm(1)`, `ppm(5)`, `pgm(5)`

AUTHOR

Copyright© 1991 by Jef Poskanzer.

15 February 1990

rlog

`rlog`—Print log messages and other information about RCS files

SYNOPSIS

```
rlog [ options ] file ...
```

DESCRIPTION

`rlog` prints information about RCS files.

Pathnames matching an RCS suffix denote RCS files; all others denote working files. Names are paired as explained in `ci(1)`.

`rlog` prints the following information for each RCS file: RCS pathname, working pathname, head (the number of the latest revision on the trunk), default branch, access list, locks, symbolic names, suffix, total number of revisions, number of revisions selected for printing, and descriptive text. This is followed by entries for the selected revisions in reverse chronological order for each branch. For each revision, `rlog` prints revision number, author, date/time, state, number of lines added/deleted (with respect to the previous revision), locker of the revision (if any), and log message. All times are displayed in Coordinated Universal Time (UTC) by default; this can be overridden with `-z`. Without options, `rlog` prints complete information. The options below restrict this output.

- `-L` Ignore RCS files that have no locks set. This is convenient in combination with `-h`, `-l`, and `-R`.
- `-R` Print only the name of the RCS file. This is convenient for translating a working pathname into an RCS pathname.
- `-h` Print only the RCS pathname, working pathname, head, default branch, access list, locks, symbolic names, and suffix.
- `-t` Print the same as `-h`, plus the descriptive text.
- `-N` Do not print the symbolic names.
- `-b` Print information about the revisions on the default branch, normally the highest branch on the trunk.
- `-ddates` Print information about revisions with a checkin date/time in the ranges given by the semicolon-separated list of *dates*. A range of the form *d1*<*d2* or *d2*>*d1* selects the revisions that were deposited between *d1* and *d2* exclusive. A range of the form <*d* or *d*> selects all revisions earlier than *d*. A range of the form *d*< or >*d* selects all revisions dated later than *d*. If < or > is followed by =, then the ranges are inclusive, not exclusive. A range of the form *d* selects the single, latest revision dated *d* or earlier. The date/time strings *d*, *d1*, and *d2* are in the free format explained in `co(1)`. Quoting is normally necessary, especially for < and >. Note that the separator is a semicolon.
- `-l[lockers]` Print information about locked revisions only. In addition, if the comma-separated list *lockers* of login names is given, ignore all locks other than those held by the *lockers*. For example, `rlog -L -R -lwft RCS/*` prints the name of RCS files locked by the user *wft*.

- `-r[revisions]` Print information about revisions given in the comma-separated list *revisions* of revisions and ranges. A range *rev1:rev2* means revisions *rev1* to *rev2* on the same branch, *:rev* means revisions from the beginning of the branch up to and including *rev*, and *rev:* means revisions starting with *rev* to the end of the branch containing *rev*. An argument that is a branch means all revisions on that branch. A range of branches means all revisions on the branches in that range. A branch followed by a *.* means the latest revision in that branch. A bare `-r` with no *revisions* means the latest revision on the default branch, normally the trunk.
- `-ssstates` Print information about revisions whose state attributes match one of the states given in the comma-separated list *states*.
- `-w[logins]` Print information about revisions checked in by users with login names appearing in the comma-separated list *logins*. If *logins* is omitted, the user's login is assumed.
- `-T` This option has no effect; it is present for compatibility with other *r*cs commands.
- `-V` Print the RCS version number.
- `-Vn` Emulate RCS version *n* when generating logs. (See *co*(1) for more details.)
- `-xsuffixes` Use *suffixes* to characterize RCS files. (See *ci*(1) for details.)

rlog prints the intersection of the revisions selected with the options `-d`, `-l`, `-s`, and `-w`, intersected with the union of the revisions selected by `-b` and `-r`.

- `-zzzone` Specifies the date output format, and specifies the default time zone for *date* in the `-ddates` option. The zone should be empty, a numeric UTC offset, or the special string *LT* for local time. The default is an empty zone, which uses the traditional RCS format of UTC without any time zone indication and with slashes separating the parts of the date; otherwise, times are output in ISO 8601 format with time zone indication. For example, if local time is January 11, 1990, 8 p.m. Pacific Standard Time, eight hours west of UTC, then the time is output as follows:

option	time output
-----	-----
<code>-z</code>	1990/01/12 04:00:00 (default)
<code>-zLT</code>	1990-01-11 20:00:00-08
<code>-z+05:30</code>	1990-01-12 09:30:00+05:30

EXAMPLES

Here are four *rlog* commands:

```
rlog -L -R RCS/*
rlog -L -h RCS/*
rlog -L -l RCS/*
rlog RCS/*
```

The first command prints the names of all RCS files in the subdirectory *RCS* that have locks. The second command prints the headers of those files, and the third prints the headers plus the log messages of the locked revisions. The last command prints complete information.

ENVIRONMENT

RCSINIT Options prepended to the argument list, separated by spaces. (See *ci*(1) for details.)

DIAGNOSTICS

The exit status is zero if and only if all operations were successful.

IDENTIFICATION

Author: Walter F. Tichy

Manual Page Revision: 5.9; Release Date: 1995/06/16

Copyright© 1982, 1988, 1989 Walter F. Tichy

Copyright© 1990, 1991, 1992, 1993, 1994, 1995 Paul Eggert

SEE ALSO

`ci(1)`, `co(1)`, `ident(1)`, `rcs(1)`, `rcsdiff(1)`, `rcsintro(1)`, `rcsmerge(1)`, `rcsfile(5)`

“RCS-A System for Version Control” by Walter F. Tichy, *Software-Practice & Experience* 15, 7 (July 1985), pages 637–654.

BUGS

The separator for revision ranges in the `-r` option used to be `-` instead of `:`, but this leads to confusion when symbolic names contain `-`. For backwards compatibility, `rlog -r` still supports the old `-` separator, but it warns about this obsolete use.

GNU, 16 June 1995

rlogin

`rlogin`—Remote login

SYNOPSIS

```
rlogin [-8EKLDx] [-e char] [-k realm] [-l username] host
```

DESCRIPTION

`rlogin` starts a terminal session on a remote host `host`.

`rlogin` first attempts to use the Kerberos authorization mechanism, described in the following subsection. If the remote host does not support Kerberos, the standard Berkeley authorization mechanism is used. The options are as follows:

- 8 The `-8` option allows an eight-bit input data path at all times; otherwise, parity bits are stripped except when the remote side's stop and start characters are other than `^S/^Q`.
- E The `-E` option stops any character from being recognized as an escape character. When used with the `-8` option, this provides a completely transparent connection.
- K The `-K` option turns off all Kerberos authentication.
- L The `-L` option allows the `rlogin` session to be run in `litout` mode. (See `tty(4)` for details).
- d The `-d` option turns on socket debugging (see the `setsockopt(2)` man page) on the TCP sockets used for communication with the remote host.
- e The `-e` option allows user specification of the escape character, which is the tilde (`~`) by default. This specification may be as a literal character, or as an octal value in the form `nnnn`.
- k The `-k` option requests `rlogin` to obtain tickets for the remote host in realm `realm` instead of the remote host's realm as determined by `krb_realmofhost(3)`.
- x The `-x` option turns on DES encryption for all data passed via the `rlogin` session. This may impact response time and CPU utilization, but provides increased security.

A line of the form `<escape char>` disconnects from the remote host. Similarly, the line `<escape char>^Z` will suspend the `rlogin` session, and `<escape char><delayed-suspend char>` suspends the send portion of the `rlogin`, but allows output from the remote system. By default, the tilde (`~`) character is the escape character, and normally control `^Y (^Y)` is the delayed-suspend character.

All echoing takes place at the remote site, so that (except for delays) the `rlogin` is transparent. Flow control via `^S/^Q` and flushing of input and output on interrupts is handled properly.

KERBEROS AUTHENTICATION

Each user may have a private authorization list in the file in his or her home directory. Each line in this file should contain a Kerberos principal name of the form `principal.instance (@realm)`. If the originating user is authenticated to one of the principals named, access is granted to the account. The principal `accountname.(@localrealm)` is granted access if there is no file. Otherwise, a login and password will be prompted for on the remote machine as in `login(1)`. To avoid certain security problems, the file must be owned by the remote user.

If Kerberos authentication fails, a warning message is printed and the standard Berkeley `rlogin` is used instead.

ENVIRONMENT

The following environment variable is utilized by `rlogin`:

TERM Determines the user's terminal type

SEE ALSO

`rsh(1)`, `kerberos(3)`, `krb_sendauth(3)`, `krb_realmofhost(3)`

HISTORY

The `rlogin` command appeared in BSD 4.2.

BUGS

`rlogin` will be replaced by `telnet(1)` in the near future.

More of the environment should be propagated.

BSD 4.2, 27 July 1991

rm

rm—Remove files

SYNOPSIS

```
rm [-dfirvR] [--directory] [--force] [--interactive] [--recursive]
    [--help] [--version] [--verbose] name...
```

DESCRIPTION

This manual page documents the GNU version of `rm`. `rm` removes each specified file. By default, it does not remove directories. If a file is unwritable, the standard input is a `tty`, and the `-f` or `--force` option is not given, `rm` prompts the user for whether to remove the file. If the response does not begin with `y` or `Y`, the file is skipped.

GNU `rm`, like every program that uses the `getopt` function to parse its arguments, lets you use the `--` option to indicate that all following arguments are nonoptions. To remove a file called `-f` in the current directory, you could type either

```
rm -- -f
```

or

```
rm ./-f
```

The UNIX `rm` program's use of a single `-` for this purpose predates the development of the `getopt` standard syntax.

OPTIONS

-d, --directory Remove directories with `unlink` instead of `rmdir`, and don't require a directory to be empty before trying to unlink it. Only works for the superuser. Because unlinking a directory causes any files in the deleted directory to become unreferenced, it is wise to `fsck` the filesystem after doing this.

<code>-f, --force</code>	Ignore nonexistent files and never prompt the user.
<code>-i, --interactive</code>	Prompt whether to remove each file. If the response does not begin with <code>y</code> or <code>Y</code> , the file is skipped.
<code>-r, -R, --recursive</code>	Remove the contents of directories recursively.
<code>-v, --verbose</code>	Print the name of each file before removing it.
<code>--help</code>	Print a usage message on standard output and exit successfully.
<code>--version</code>	Print version information on standard output, then exit successfully.

GNU File Utilities

rmmdir

rmmdir—Remove empty directories

SYNOPSIS

rmmdir [-p] [--parents] [--help] [--version] dir...

DESCRIPTION

This manual page documents the GNU version of **rmmdir**. **rmmdir** removes each given empty directory. If any nonoption argument does not refer to an existing empty directory, it is an error.

OPTIONS

<code>-p, --parents</code>	Remove any parent directories that are explicitly mentioned in an argument, if they become empty after the argument file is removed.
<code>--help</code>	Print a usage message on standard output and exit successfully.
<code>--version</code>	Print version information on standard output, then exit successfully.

GNU File Utilities

rmmod

rmmod—Unload loadable modules

SYNOPSIS

rmmod [-r] module ...

DESCRIPTION

rmmod unloads loadable modules from the kernel.

rmmod tries to unload a set of modules from the kernel, with the restriction that they are not in use and that they are not referred to by other modules.

If more than one module is named on the command line, the modules will be removed in the given order. This supports unloading of stacked modules.

With the option `-r`, a recursive removal of modules will be attempted. This means that if a top module in a stack is named on the command line, all modules that are used by this module will be removed as well, if possible.

SEE ALSO

`insmod(1)`, `lsmod(1)`, `ksyms(1)`, `modules(2)`

HISTORY

The module support was first conceived by Anonymous (as far as I know...). Linux version by Bas Laarhoven (basevimec.nl), 0.99.14 version by Jon Tombs (jon@gtex02.us.es), extended by Bjorn Ekwall (bj0rn@blox.se).

BUGS

rmmod might have some, but they are well hidden.

Linux, 14 May 1995

rnews

rnews—Receive news from a UUCP connection

SYNOPSIS

```
rnews [ -h host ][ -v ][ -U ][ -S master ][ input ]
```

DESCRIPTION

rnews reads messages sent by a downstream uucp newsfeed and sends them to the local InterNetNews server. The message is read from the specified input file, or standard input if no input is named.

If the -s flag is used, then rnews will connect to the specified host. If the flag is not used, it will try to connect to the server by opening a UNIX-domain stream connection. If that fails, it will try to open a TCP connection to the default remote server.

If the server is not available, the message is spooled into a new file created in the /var/spool/rnews directory. The -U flag may be used to send all spooled messages to the server when it becomes available again, and can be invoked regularly by cron(8).

When sent over uucp, Usenet articles are typically joined in a single batch to reduce the uucp overhead. Batches can also be compressed, to reduce the communication time. If a message does not start with a number sign (#) and an exclamation point, then the entire input is taken as a single news article. If it does start with those two characters, then the first line is read and interpreted as a batch command.

If the command is #! rnews nnn, where nnn is a number, then the next nnn bytes (starting with the next line) are read as a news article.

If the command is #! cunbatch, then the rest of input is fed to the compress(1) program with the -d flag to uncompress it, and the output of this pipe is read as input from rnews. This is for historical compatibility—there is no program named cunbatch. A compressed batch will start with a #! cunbatch line, then contain a series of articles separated by #! rnews nnn lines.

If the command is any other word, then rnews will try to execute a program with that name in the directory /news/bin/rnews. The batch will be fed into the program's standard input, and the standard output will be read back as input into rnews.

If rnews detects any problems with an article, such as a missing header or an unintelligible reply from the server, it will save a copy of the article in the /var/spool/rnews/bad directory. If the -v flag is used, it will print a notice of all such errors on the standard error, naming the input file (if known) and printing the first few characters of the input. Errors are always logged through syslog(3).

If the -h flag is given, or failing that, the environment variable UU_MACHINE is set, then rnews will log the Message-ID and host for each article offered to the server via syslog(3). Logging will only be done if the value is not an empty string.

BUGS

rnews cannot process articles that have embedded \0s in them.

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for InterNetNews.

SEE ALSO

innd(8).

rpcgen

rpcgen—An RPC protocol compiler

SYNOPSIS

```
rpcgen infile
rpcgen [-D name[= value]] [-T] [-K secs] infile
rpcgen -c|-h|-l|-m|-t [-o outfile] infile
rpcgen [-I] -s nettype [-o outfile] infile
rpcgen -n netid [-o outfile] infile
```

DESCRIPTION

rpcgen is a tool that generates C code to implement an RPC protocol. The input to rpcgen is a language similar to C known as RPC language (Remote Procedure Call Language). rpcgen is normally used as in the first synopsis where it takes an input file and generates up to four output files. If the *infile* is named *proto.x*, then rpcgen will generate a header file in *proto.h*, *xdr* routines in *proto_xdr.c*, server-side stubs in *proto_svc.c*, and client-side stubs in *proto_clnt.c*.

With the *-T* option, it will also generate the RPC dispatch table in *proto_tbl.i*. With the *-Sc* option, it will also generate sample code that would illustrate how to use the remote procedures on the client side. This code would be created in *proto_client.c*. With the *-Ss* option, it will also generate a sample server code that would illustrate how to write the remote procedures. This code would be created in *proto_server.c*. The server created can be started both by the port monitors (for example, *inetd* or *listen*) or by itself. When it is started by a port monitor, it creates servers only for the transport for which the file descriptor 0 was passed. The name of the transport must be specified by setting up the environmental variable *PM_TRANSPORT*.

When the server generated by rpcgen is executed, it creates server handles for all the transports specified in *NETPATH* environment variable, or if it is unset, it creates server handles for all the visible transports from */etc/netconfig* file. Note: the transports are chosen at runtime and not at compile time. When the server is self-started, it backgrounds itself by default. A special define symbol *RPC_SVC_FG* can be used to run the server process in the foreground. The second synopsis provides special features that allow for the creation of more sophisticated RPC servers. These features include support for user-provided *#defines* and RPC dispatch tables. The entries in the RPC dispatch table contain

- Pointers to the service routine corresponding to that procedure
- A pointer to the input and output arguments
- The size of these routines

A server can use the dispatch table to check authorization and then to execute the service routine; a client library may use it to deal with the details of storage management and *xdr* data conversion. The other three synopses shown in the preceding paragraph are used when one does not want to generate all the output files, but only a particular one. (Some examples of their usage is described in the “Example” subsection.) When rpcgen is executed with the *-s* option, it creates servers for that particular class of transports. When executed with the *-n* option, it creates a server for the transport specified by *netid*. If *infile* is not specified, rpcgen accepts the standard input. The C preprocessor, *cc -E* (see *cc(1)* for details), is run on the input file before it is actually interpreted by rpcgen. For each type of output file, rpcgen defines a special preprocessor symbol for use by the rpcgen programmer, as follows:

RPC_HDR	Defined when compiling into header files
RPC_XDR	Defined when compiling into XDR routines
RPC_SVC	Defined when compiling into server-side stubs
RPC_CLNT	Defined when compiling into client-side stubs
RPC_TBL	Defined when compiling into RPC dispatch tables Any line beginning with % is passed directly into the output file, uninterpreted by rpcgen. For every data type referred to in <code>infile</code> , rpcgen assumes that there exists a routine with the string <code>xdr</code> prepended to the name of the data type. If this routine does not exist in the RPC/XDR library, it must be provided. Providing an undefined data type allows customization of XDR routines. The following options are available:
-a	Generate all the files including sample code for client and server side.
-b	This generates code for the SunOS4.1 style of rpc. It is for backwards compatibility. This is the default.
-5	This generates code for the SysVr4 style of rpc. It is used by the Transport Independent RPC that is in Svr4 systems. By default, rpcgen generates code for SunOS4.1 type of rpc.
-c	Compile into XDR routines.
-C	Generate code in ANSI C. This option also generates code that could be compiled with the C++ compiler. This is the default.
-k	Generate code in K&R C. The default is ANSI C.
-Dname [=value]	Define a symbol name. Equivalent to the <code>#define</code> directive in the source. If no value is given, value is defined as 1. This option may be specified more than once.
-h	Compile into C data-definitions (a header file). <code>-t</code> option can be used in conjunction to produce a header file that supports RPC dispatch tables.
-I	Generate a service that can be started from <code>inetd</code> . The default is to generate a static service that handles transports selected with <code>-s</code> . Using <code>-I</code> allows starting a service by either method.
-K secs	By default, services created using rpcgen wait 120 seconds after servicing a request before exiting. That interval can be changed using the <code>-K</code> flag. To create a server that exits immediately upon servicing a request, <code>-K 0</code> can be used. To create a server that never exits, the appropriate argument is <code>-K -1</code> . When monitoring for a server, some port monitors, such as <code>listen(1M)</code> , always spawn a new process in response to a service request. If it is known that a server will be used with such a monitor, the server should exit immediately on completion. For such servers, rpcgen should be used with <code>-K -1</code> .
-l	Compile into client-side stubs.
-m	Compile into server-side stubs, but do not generate a main routine. This option is useful for doing callback-routines and for users who need to write their own main routine to do initialization.
-n netid	Compile into server-side stubs for the transport specified by <code>netid</code> . There should be an entry for <code>netid</code> in the <code>netconfig</code> database. This option may be specified more than once, so as to compile a server that serves multiple transports.
-N	Use the newstyle of rpcgen. This allows procedures to have multiple arguments. It also uses the style of parameter passing that closely resembles C. So, when passing an argument to a remote procedure, you do not have to pass a pointer to the argument but the argument itself. This behavior is different from the old style of rpcgen-generated code. The new style is not the default case because of backwards compatibility.
-o outfile	Specify the name of the output file. If none is specified, standard output is used (<code>-c</code> , <code>-h</code> , <code>-l</code> , <code>-m</code> , <code>-n</code> , <code>-s</code> , <code>-sc</code> , <code>-ss</code> , and <code>-t</code> modes only).

<code>-s nettype</code>	Compile into server-side stubs for all the transports belonging to the class <code>nettype</code> . The supported classes are <code>netpath</code> , <code>visible</code> , <code>circuit_n</code> , <code>circuit_v</code> , <code>datagram_n</code> , <code>datagram_v</code> , <code>tcp</code> , and <code>udp</code> . See <code>rpc(3N)</code> for the meanings associated with these classes. This option may be specified more than once. Note: The transports are chosen at runtime and not at compile time.
<code>-Sc</code>	Generate sample code to show the use of remote procedure and how to bind to the server before calling the client-side stubs generated by <code>rpcgen</code> .
<code>-Ss</code>	Generate skeleton code for the remote procedures on the server side. You would need to fill in the actual code for the remote procedures.
<code>-t</code>	Compile into RPC dispatch table.
<code>-T</code>	Generate the code to support RPC dispatch tables. The options <code>-c</code> , <code>-h</code> , <code>-l</code> , <code>-m</code> , <code>u</code> , and <code>-t</code> are used exclusively to generate a particular type of file, while the options <code>-D</code> and <code>-T</code> are global and can be used with the other options.

NOTES

The RPC language does not support nesting of structures. As a workaround, structures can be declared at the top level, and their name used inside other structures in order to achieve the same effect. Name clashes can occur when using program definitions because the apparent scoping does not really apply. Most of these can be avoided by giving unique names for programs, versions, procedures, and types. The server code generated with the `-n` option refers to the transport indicated by `netid` and hence is very site-specific.

EXAMPLE

The following example:

```
$ rpcgen -T prot.x
```

generates five files: `prot.h`, `prot_clnt.c`, `prot_svc.c`, `prot_xdr.c`, and `prot_tbl.i`.

This example:

```
$ rpcgen -h prot.x
```

sends the C data-definitions (header file) to the standard output.

To send the test version of the `-DTEST`, server-side stubs for all the transport belonging to the class `datagram_n` to standard output, use

```
$ rpcgen -s datagram_n -DTEST prot.x
```

To create the server-side stubs for the transport indicated by `netid` `tcp`, use

```
$ rpcgen -n tcp -o prot_svc.c prot.x
```

SEE ALSO

`cc(1)`.

rsh

rsh—Remote shell

SYNOPSIS

```
rsh [-k dnx] [-k realm] [-l username] host command
```

DESCRIPTION

rsh executes `command` on `host`.

rsh copies its standard input to the remote command, the standard output of the remote command to its standard output, and the standard error of the remote command to its standard error. Interrupt, quit, and terminate signals are propagated to the remote command; rsh normally terminates when the remote command does. The options are as follows:

- K Turns off all Kerberos authentication.
- d Using `setsockopt(2)`, turns on socket debugging on the TCP sockets used for communication with the remote host.
- k Causes rsh to obtain tickets for the remote host in `realm` instead of the remote host's realm as determined by `krb_realmofhost(3)`.
- l By default, the remote username is the same as the local username. The `-l` option allows the remote name to be specified. Kerberos authentication is used, and authorization is determined as in `rlogin(1)`.
- n The `-n` option redirects input from the special device. (See the “Bugs” section of this manual page.)
- x The `-x` option turns on DES encryption for all data exchange. This may introduce a significant delay in response time.

If no command is specified, you will be logged in on the remote host using `rlogin(1)`.

Shell metacharacters that are not quoted are interpreted on local machine, while quoted metacharacters are interpreted on the remote machine. For example, the command:

```
rsh otherhost cat remotefile >> localfile
```

appends the remote file `remotefile` to the local file `localfile`, while

```
rsh otherhost cat remotefile >> other remotefile
```

appends `remotefile` to `other remotefile`.

FILES

`/etc/hosts`

SEE ALSO

`rlogin(1)`, `kerberos(3)`, `krb sendauth(3)`, `krb_realmofhost(3)`

HISTORY

The `rsh` command appeared in BSD 4.2.

BUGS

If you are using `cs(1)` and put a `rsh` in the background without redirecting its input away from the terminal, it will block even if no reads are posted by the remote command. If no input is desired you should redirect the input of `rsh` to using the `-n` option.

You cannot run an interactive command (`rogue(6)` or `vi(1)`, for example) using `rsh`; use `rlogin(1)` instead.

Stop signals stop the local `rsh` process only; this is arguably wrong, but currently hard to fix for reasons too complicated to explain here.

BSD 4.2, 24 July 1991

rstart

rstart—A sample implementation of a Remote Start client

SYNOPSIS

```
rstart [-c context] [-g] [-l username] [-v] hostname command args ...
```

DESCRIPTION

`rstart` is a simple implementation of a Remote Start client as defined in “A Flexible Remote Execution Protocol Based on `rsh`.” It uses `rsh` as its underlying remote execution mechanism.

OPTIONS

- `-c context` This option specifies the context in which the command is to be run. A `context` specifies a general environment the program is to be run in. The details of this environment are host-specific; the intent is that the client need not know how the environment must be configured. If omitted, the context defaults to `x`. This should be suitable for running `x` programs from the host’s “usual” `x` installation.
- `-g` Interprets command as a *generic* command, as discussed in the protocol document. This is intended to allow common applications to be invoked without knowing what they are called on the remote system. Currently, the only generic commands defined are `Terminal`, `LoadMonitor`, `ListContexts`, and `ListGenericCommands`.
- `-l username` This option is passed to the underlying `rsh`; it requests that the command be run as the specified user.
- `-v` This option requests that `rstart` be verbose in its operation. Without this option, `rstart` discards output from the remote’s `rstart` helper, and directs the `rstart` helper to detach the program from the `rsh` connection used to start it. With this option, responses from the helper are displayed and the resulting program is not detached from the connection.

NOTES

This is a trivial implementation. Far more sophisticated implementations are possible and should be developed.

Error-handling is nonexistent. Without `-v`, error reports from the remote are discarded silently. With `-v`, error reports are displayed.

The `$DISPLAY` environment variable is passed. If it starts with a colon, the local hostname is prepended. The local domain name should be appended to unqualified hostnames, but isn’t.

The `$SESSION_MANAGER` environment variable should be passed, but isn’t.

`x11` authority information is passed for the current display.

ICE authority information should be passed, but isn’t. It isn’t completely clear how `rstart` should select what ICE authority information to pass.

Even without `-v`, the sample `rstart` helper will leave a shell waiting for the program to complete. This causes no real harm and consumes relatively few resources, but if it is undesirable it can be avoided by explicitly specifying the `exec` command to the shell, for example, `0 rstart somehost exec xterm`.

This is obviously dependent on the command interpreter being used on the remote system; the example given will work for the Bourne and C shells.

SEE ALSO

`rstartd(1)`, `rsh(1)`, “A Flexible Remote Execution Protocol Based on `rsh`”

AUTHOR

Jordan Brown, Quarterdeck Office Systems

X Version 11 Release 6

rstartd

`rstartd`—A sample implementation of a Remote Start `rsh` helper

SYNOPSIS

```
rstartd
```

```
rstartd.real [-c configfilename]
```

DESCRIPTION

rstartd is an implementation of a Remote Start “helper” as defined in “A Flexible Remote Execution Protocol Based on rsh.”

This document describes the peculiarities of rstartd and how it is configured.

OPTIONS

-c configfilename This option specifies the global configuration file that rstartd is to read. Normally, rstartd is a shell script that invokes rstartd.real with the **-c** switch, allowing local configuration of the location of the configuration file. If rstartd.real is started without the **-c** option, it reads `<XRoot>/lib/X11/rstart/config`, where `<XRoot>` refers to the root of the X11 install tree.

INSTALLATION

It is critical to successful interoperation of the Remote Start protocol that rstartd be installed in a directory that is in the default search path, so that default rsh requests and the `ilk` will be able to find it.

CONFIGURATION AND OPERATION

rstartd is by design highly configurable. One would like things like configuration file locations to be fixed, so that users and administrators can find them without searching, but reality is that no two vendors will agree on where things should go, and nobody thinks the original location is “right.” Thus, rstartd allows the relocation of all of its files and directories.

rstartd has a hierarchy of configuration files that are executed in order when a request is made. They are global config, per-user (“local”) config, global per-context config, per-user (“local”) per-context config, config from request.

As you might guess from the presence of `config from request`, all of the config files are in the format of an rstart request. rstartd defines a few additional keywords with the `INTERNAL -` prefix for specifying its configuration.

rstartd starts by reading and executing the global config file. This file will normally specify the locations of the other configuration files and any system-wide defaults.

rstartd will then read the user's local config file, default name `$HOME/.rstart`.

rstartd will then start interpreting the request.

Presumably, one of the first lines in the request will be a `CONTEXT` line. The context name is converted to lowercase.

rstartd will read the global config file for that context, default name `<XRoot>/lib/X11/rstart/context/<name>`, if any.

It will then read the user's config file for that context, default name `$HOME/.rstart.context/<name>`, if any.

(If neither of these exists, rstartd aborts with a Failure message.)

rstartd will finish interpreting the request, and execute the program specified. This allows the system administrator and the user a large degree of control over the operation of rstartd. The administrator has final say, because the global config file doesn't need to specify a per-user config file. If it does, however, the user can override anything from the global file, and can even completely replace the global context config files.

The config files have a somewhat more flexible format than requests do; they are allowed to contain blank lines and lines beginning with `#` are comments and ignored. (`#`s in the middle of lines are data, not comment markers.)

Any commands run are provided a few useful pieces of information in environment variables. The exact names are configurable, but the supplied defaults are

<code>\$RSTART_CONTEXT</code>	The name of the context
<code>\$RSTART_GLOBAL_CONTEXTS</code>	The global contexts directory
<code>\$RSTART_LOCAL_CONTEXTS</code>	The local contexts directory
<code>\$RSTART_GLOBAL_COMMANDS</code>	The global generic commands directory
<code>\$RSTART_LOCAL_COMMANDS</code>	The local generic commands directory

`$RSTART_{GLOBAL,LOCAL}_CONTEXTS` should contain one special file, `@List`, which contains a list of the contexts in that directory in the format specified for `ListContexts`. The supplied version of `ListContexts` will cat both the global and local copies of `@List`.

Generic commands are searched for in several places: (defaults)

Per-user per-context directory	<code>\$HOME/.rstart.commands/<context></code>
Global per-context directory	<code><XRoot>/lib/X11/rstart/commands/<context></code>
Per-user all-contexts directory	<code>\$HOME/.rstart.commands</code>
Global all-contexts directory	<code><XRoot>/lib/X11/rstart/commands</code>

(Yes, this means you can't have an all-contexts generic command with the same name as a context. It didn't seem like a big deal.)

Each of these directories should have a file called `@List` that gives the names and descriptions of the commands in that directory in the format specified for `ListGenericCommands`.

CONFIGURATION KEYWORDS

There are several special `rstart` keywords defined for `rstartd` configuration. Unless otherwise specified, there are no defaults; related features are disabled in this case.

`Internal-Registries name...`—Gives a space-separated list of `MISC` registries that this system understands. (Registries other than these are accepted but generate a warning.)

`Internal-Local-Default relative_filename`—Gives the name (`$HOME` relative) of the per-user config file.

`INTERNAL-GLOBAL-CONTEXTS absolute_directory_name`—Gives the name of the system-wide contexts directory.

`INTERNAL-LOCAL-CONTEXTS relative_directory_name`—Gives the name (`$HOME` relative) of the per-user contexts directory.

`INTERNAL-GLOBAL-COMMANDS absolute_directory_name`—Gives the name of the system-wide generic commands directory.

`INTERNAL-LOCAL-COMMANDS relative_directory_name`—Gives the name (`$HOME` relative) of the per-user generic commands directory.

`INTERNAL-VARIABLE-PREFIX prefix`—Gives the prefix for the configuration environment variables `rstartd` passes to its kids.

`INTERNAL-AUTH-PROGRAM authscheme program argv[0] argv[1]...`—Specifies the program to run to set up authentication for the specified authentication scheme. `program argv[0] ...` gives the program to run and its arguments, in the same form as the `EXEC` keyword.

`INTERNAL-AUTH-INPUT authscheme`—Specifies the data to be given to the authorization program as its standard input. Each argument is passed as a single line. `$n`, where `n` is a number, is replaced by the `n`th argument to the `AUTH authscheme arg1 arg2 ...` line.

`INTERNAL-PRINT arbitrary text`—Prints its arguments as a Debug message. Mostly for `rstartd` debugging, but could be used to debug config files.

NOTES

When using the C shell, or any other shell that runs a script every time the shell is started, the script may be run several times. In the worst case, the script may be run three times: By `rsh`, to run `rstartd`; by `rstartd`, to run the specified command; by the command, such as `xterm`.

`rstartd` currently limits lines, both from config files and requests, to `BUFSIZ` bytes.

`DETACH` is implemented by redirecting file descriptors 0, 1, and 2 to `/dev/null` and forking before executing the program.

`CMD` is implemented by invoking `$SHELL` (default `/bin/sh`) with `-c` and the specified command as arguments.

`POSIX-UMASK` is implemented in the obvious way.

The authorization programs are run in the same context as the target program—same environment variables, path, and so on. Long term, this might be a problem.

In the X context, `GENERIC-CMD Terminal` runs `xterm`. In the OpenWindows context, `GENERIC-CMD Terminal` runs `cmdtool`.

In the X context, `GENERIC-CMD LoadMonitor` runs `xload`. In the OpenWindows context, `GENERIC-CMD LoadMonitor` runs `perfmeter`.

`GENERIC-CMD ListContexts` lists the contents of `@List` in both the system-wide and per-user contexts directories. It is available in all contexts.

`GENERIC-CMD ListGenericCommands` lists the contents of `@List` in the system-wide and per-user commands directories, including the per-context subdirectories for the current context. It is available in all contexts.

`CONTEXT None` is not implemented.

`CONTEXT Default` is really dull.

For installation ease, the `contexts` directory in the distribution contains a file `@Aliases`, which lists a context name and aliases for that context. This file is used to make symlinks in the contexts and commands directories.

All `MISC` values are passed unmodified as environment variables.

You can mistreat `rstartd` in any number of ways, resulting in anything from stupid behavior to core dumps. Other than by explicitly running programs, I don't think it can write or delete any files, but there's no guarantee of that. The important thing is that (a) it probably won't do anything REALLY stupid and (b) it runs with the user's permissions, so it can't do anything catastrophic.

`@List` files need not be complete; contexts or commands that are dull or which need not or should not be advertised need not be listed. In particular, per-user `@List` files should not list things that are in the system-wide `@List` files. In the future, perhaps `ListContexts` and `ListGenericCommands` will automatically suppress lines from the system-wide files when there are per-user replacements for those lines.

Error-handling is OK to weak. In particular, no attempt is made to properly report errors on the `exec` itself. (Perversely, `exec` errors could be reliably reported when detaching, but not when passing the `stdin/out` socket to the app.)

If compiled with `-DODT1_DISPLAY_HACK`, `rstartd` will work around a bug in SCO ODT version 1. (1.1?) (The bug is that the x clients are all compiled with a bad library that doesn't know how to look hostnames up using DNS. The fix is to look up a hostname in `$DISPLAY` and substitute an IP address.) This is a trivial example of an incompatibility that `rstart` can hide.

SEE ALSO

`rstart(1)`, `rsh(1)`, "A Flexible Remote Execution Protocol Based on `rsh`"

AUTHOR

Jordan Brown, Quarterdeck Office Systems

rup

rup—Remote status display

SYNOPSIS

```
rup [-dhlt] [host ...]
```

DESCRIPTION

rup displays a summary of the current system status of a particular host or all hosts on the local network. The output shows the current time of day, how long the system has been up, and the load averages. The load average numbers give the number of jobs in the run queue averaged over 1, 5 and 15 minutes.

The following options are available:

- d For each host, report what its local time is. This is useful for checking time synchronization on a network.
- h Sort the display alphabetically by hostname.
- l Sort the display by load average.
- t Sort the display by up time.

The `rpc.rstatd(8)` daemon must be running on the remote host for this command to work. rup uses an RPC protocol defined in `/usr/include/rpcsvc/rstat.x`.

EXAMPLE

```
example% rup otherhost
otherhost up 6 days, 16:45, load average: 0.20, 0.23, 0.18
example%
```

DIAGNOSTICS

rup: RPC: Program not registered—The `rpc.rstatd(8)` daemon has not been started on the remote host.

rup: RPC: Timed out—A communication error occurred. Either the network is excessively congested, or the `rpc.rstatd(8)` daemon has terminated on the remote host.

rup: RPC: Port mapper failure - RPC: Timed out—The remote host is not running the portmapper (see `portmap(8)` man page), and cannot accommodate any RPC-based services. The host may be down.

SEE ALSO

`ruptime(1)`, `portmap(8)`, `rpc.rstatd(8)`

HISTORY

The rup command appeared in SunOS.

BSD 4.3, 7 June 1993

rusers

rusers—Output who is logged in to machines on local network

SYNOPSIS

```
rusers [-al] [host ...]
```

DESCRIPTION

The rusers command produces output similar to `who`, but for the list of hosts or all machines on the local network. For each host responding to the rusers query, the hostname with the names of the users currently logged on is printed on each line.

The `rusers` command will wait for one minute to catch late responders.

The following options are available:

- a Print all machines responding even if no one is currently logged in.
- l Print a long format listing. This includes the username, hostname, tty that the user is logged in to, the date and time the user logged in, the amount of time since the user typed on the keyboard, and the remote host the user logged in from (if applicable).

DIAGNOSTICS

rusers: RPC: Program not registered—The `rpc.rusersd(8)` daemon has not been started on the remote host.

rusers: RPC: Timed out—A communication error occurred. Either the network is excessively congested, or the `rpc.rusersd(8)` daemon has terminated on the remote host.

rusers: RPC: Port mapper failure - RPC: Timed out—The remote host is not running the portmapper (see `portmap(8)` for more information), and cannot accommodate any RPC-based services. The host may be down.

SEE ALSO

`rwho(1)`, `users(1)`, `who(1)`, `portmap(8)`, `rpc.rusersd(8)`

HISTORY

The `rusers` command appeared in SunOS.

BUGS

The sorting options are not implemented.

BSD 4.2, 23 April 1991

rwall

`rwall`—Send a message to users logged on a host

SYNOPSIS

`rwall host`

DESCRIPTION

The `rwall` command sends a message to the users logged in to the specified host. The message to be sent can be typed in and terminated with EOF or it can be in a file.

DIAGNOSTICS

rwall: RPC: Program not registered—The `rpc.rwalld(8)` daemon has not been started on the remote host.

rwall: RPC: Timed out—A communication error occurred. Either the network is excessively congested, or the `rpc.rwalld(8)` daemon has terminated on the remote host.

rwall: RPC: Port mapper failure - RPC: Timed out—The remote host is not running the portmapper, and cannot accommodate any RPC-based services. The host may be down.

SEE ALSO

`wall(1)`, `portmap(8)`, `rpc.rwalld(8)`

HISTORY

The `rwall` command appeared in SunOS.

BSD 4.2, 23 April 1991

rwho

rwho—Output who is logged in on local machines

SYNOPSIS

```
rwho -a
```

DESCRIPTION

The **rwho** command produces output similar to **who**, but for all machines on the local network. If no report has been received from a machine for 11 minutes, then **rwho** assumes the machine is down, and does not report users last known to be logged in to that machine.

If a user hasn't typed to the system for a minute or more, then **rwho** reports this idle time. If a user hasn't typed to the system for an hour or more, then the user will be omitted from the output of **rwho** unless the **-a** flag is given.

FILES

`/var/rwho/whod.*` Information about other machines

SEE ALSO

finger(1), **rup(1)**, **ruptime(1)**, **rusers(1)**, **who(1)**, **rwhod(8)**

HISTORY

The **rwho** command appeared in BSD 4.3.

BUGS

This is unwieldy when the number of machines on the local net is large.

BSD 4.2, 23 April 1991

script

script—Make typescript of terminal session

SYNOPSIS

```
script [-a] [file]
```

DESCRIPTION

script makes a typescript of everything printed on your terminal. It is useful for students who need a hardcopy record of an interactive session as proof of an assignment, as the typescript file can be printed out later with **lpr(1)**.

If the argument file is given, **script** saves all dialogue in file. If no filename is given, the typescript is saved in the file **typescript**.

Option:

-a Append the output to file or typescript, retaining the prior contents

The script ends when the forked shell exits (a **control-D** to exit the Bourne shell, **sh(1)**, and **exit**, **logout**, or **control-d** (if **ignoreeof** is not set) for the C-shell, **csh(1)**).

Certain interactive commands, such as **vi(1)**, create garbage in the typescript file. Script works best with commands that do not manipulate the screen; the results are meant to emulate a hardcopy terminal.

ENVIRONMENT

The following environment variable is utilized by `script`:

SHELL If the variable `SHELL` exists, the shell forked by `script` will be that shell. If `SHELL` is not set, the Bourne shell is assumed. (Most shells set this variable automatically.)

SEE ALSO

`csh(1)` (for the history mechanism)

HISTORY

The `script` command appeared in BSD 3.0.

BUGS

`script` places everything in the `log` file, including linefeeds and backspaces. This is not what the naive user expects.

BSD 4, 27 July 1991

sed

`sed`—Stream-oriented editor

SYNOPSIS

```
sed [ -hnV ][-e script ][-f script-file ][--help ][--quiet ][--silent ]
[ --version ][-expression=script ][-file=script-file ][file ... ]
```

DESCRIPTION

`sed` reads the specified files or the standard input if no files are specified, makes editing changes according to a list of commands, and writes the results to the standard output.

OPTIONS

<code>-h, --help</code>	Print a usage message on standard output and exit successfully.
<code>-n, --quiet, --silent</code>	Suppress the default output. <code>sed</code> only displays lines explicitly specified for output with the <code>p</code> command or the <code>p</code> flag of the <code>s</code> command. The default behavior is to echo each line of input, after edits, to the standard output.
<code>-V, --version</code>	Print the version number on the standard output and exit successfully.
<code>-e script, --expression=script</code>	Append one or more commands specified in the string <code>script</code> to the list of commands. If there is just one <code>-e</code> option and no <code>-f</code> options, the <code>-e</code> flag may be omitted.
<code>-f script-file, --file=script-file</code>	Append the editing commands from <code>script-file</code> to the list of commands.

Multiple `-e` and `-f` commands may be specified. Scripts are added to the list of commands to execute in the order specified, regardless of their origin.

USAGE

OPERATION

`sed` operates as follows:

Each line of input, not including its terminating newline character, is successively copied into a pattern space (a temporary buffer).

All editing commands whose addresses match that pattern space are sequentially applied to the pattern space.

When reaching the end of the command list, the pattern space is written to the standard output (except under `-n`) with an appended newline.

The pattern space is cleared and the process is repeated for each line in the input.

With `sed`, original input files remain unchanged because editing commands only modify a copy of the input.

Some `sed` commands use a hold space to save all or part of the pattern space for later retrieval.

COMMAND SYNTAX

A `sed` script consists of commands with the general form:

```
[address[,address]][!]command[arguments]
```

Typically, there is only one command per line, but commands may also be concatenated on a single line by semicolons.

Whitespace characters may be inserted before the first address and the command portions of the script command.

ADDRESSES

A `sed` command, as indicated, can specify zero, one, or two addresses. An address can be

A line number, represented in decimal. The internal line number count maintained by `sed` is cumulative across input files and is not reset for each input file.

A pattern that is a regular expression, represented by `ncpatternnc`, where `c` is any character except backslash (`\`) or newline. In the address `nxabcnxdex`, the second `x` stands for itself, so the regular expression is `abcxdef`. However, the preferred (and equivalent) method to construct a regular expression is to enclose the pattern in slashes—`/pattern/`. Additionally, `\n` can be used to match any newline in the pattern space, except for the final newline character.

A `$` character that addresses the last line of input.

GNU `sed` also implements a new type of address. The address has form `n~m`, which matches any line where the line number modulo `m` is equal to `n modulo m`. If `m` is `0` or missing, then `1` is used in its place. This feature is not specified by POSIX.

The following rules apply to addressed commands:

A command line with no address selects each input line.

A command line with one address selects any line matching the address. Several commands accept only one address: `=`, `a`, `i`, `r`, and `q`.

A command line with two comma-separated addresses selects the first matching line and all following lines up to and including the line matching the second address. If the second address starts before or is the same line as the first address, then only the first line is selected.

An address followed by `!` selects all lines that do not match the address.

REGULAR EXPRESSIONS

Regular expressions are patterns used in selecting text. For example, the `sed` command

```
/string/p
```

prints all lines containing `string`.

In addition to specifying string literals, regular expressions can represent classes of strings. Strings thus represented are said to be matched by the corresponding regular expression. If it is possible for a regular expression to match several strings in a line, then the leftmost longest match is the one selected.

The following symbols are used in constructing search patterns:

	The null regular expression is equivalent to the last regular expression used.
<code>c</code>	Any character <code>c</code> not listed here—including <code>{</code> , <code>}</code> , <code>,</code> , <code><</code> , <code>></code> , <code>!</code> , and <code>+</code> —matches itself.
<code>\c</code>	Any backslash-escaped character <code>c</code> , except for <code>{</code> , <code>}</code> , <code>,</code> , <code><</code> , <code>></code> , <code>!</code> , and <code>+</code> , matches itself.
<code>'-1n'</code>	Matches any single character except newline.

<code>[char-class]</code>	Matches any single character, other than newline, in <code>char-class</code> . To include a <code>]</code> in <code>char-class</code> , it must be the first character. A range of characters may be specified by separating the end characters of the range with a <code>-</code> , for example, <code>a-z</code> specifies the lowercase characters. The following literal expressions can also be used in <code>char-class</code> to specify sets of characters: <code>[:alnum:]</code> <code>[:cntrl:]</code> <code>[:lower:]</code> <code>[:space:]</code> <code>[:alpha:]</code> <code>[:digit:]</code> <code>[:print:]</code> <code>[:upper:]</code> <code>[:blank:]</code> <code>[:graph:]</code> <code>[:punct:]</code> <code>[:xdigit:]</code> If <code>-</code> appears as the first or last character of <code>char-class</code> , then it matches itself. All other characters in <code>char-class</code> match themselves.
<code>^[^char-class]</code>	Matches any single character, other than newline, not in <code>char-class</code> . <code>char-class</code> is defined as in the preceding entry.
<code>^</code>	If <code>^</code> is the first character of a regular expression, then it anchors the regular expression to the beginning of a line. Otherwise, it matches itself.
<code>\$</code>	If <code>\$</code> is the last character of a regular expression, it anchors the regular expression to the end of a line. Otherwise, it matches itself.
<code>\<, \></code>	Anchors the single-character regular expression or subexpression immediately following it to the beginning (<code>\<</code>) or ending (<code>\></code>) of a word, that is, in ASCII, a maximal string of alphanumeric characters, including the underscore (<code>_</code>).
<code>\(re\)</code>	Defines a (possibly null) subexpression <code>re</code> . Subexpressions may be nested. A subsequent back reference of the form <code>'\n'</code> , where <code>n</code> is a number in the range 1–9, expands to the text matched by the <code>n</code> th subexpression. For example, the regular expression <code>\(a.c\)\1</code> matches the string <code>'abcabc'</code> , but not <code>'abcadc'</code> . Subexpressions are ordered relative to their left delimiter.
<code>*</code>	Matches the single-character regular expression or subexpression immediately preceding it zero or more times. If <code>*</code> is the first character of a regular expression or subexpression, then it matches itself. The <code>*</code> operator sometimes yields unexpected results. For example, the regular expression <code>b*</code> matches the beginning of the string <code>'abbb'</code> (as opposed to the substring <code>'bbb'</code>) because a null match is the only leftmost match.
<code>\+</code>	Matches the single character regular expression or subexpression immediately preceding it one or more times.
<code>\ </code>	Matches the regular expression or subexpression specified before or after it.
<code>\{n,m\}</code> or <code>\{n,\}</code> or <code>\{n\}</code>	Matches the single-character regular expression or subexpression immediately preceding it at least <code>n</code> and at most <code>m</code> times. If <code>m</code> is omitted, then it matches at least <code>n</code> times. If the comma is also omitted, then it matches exactly <code>n</code> times.
<code>(\group\)</code>	Matches the enclosed group of regular expressions.

The following characters only have special meaning when used in replacement patterns:

<code>\</code>	Escape the following character.
<code>\n</code>	Matches the <code>n</code> th pattern previously saved by <code>n('</code> and <code>'n)</code> , where <code>n</code> is a number from 0 to 9. Previously saved patterns are counted from the leftmost position on the line.
<code>&</code>	Prints the entire search pattern when used in a replacement string.

COMMENTS

If the first nonwhite character in a line is a `#`), `sed` treats that line as a comment, and ignores it. If, however, the first such line is of the form:

```
#n
```

`sed` runs as if the `-n` flag were specified.

GROUPING COMMANDS

Braces (`{`, `}`) can be used to nest one address within another or to apply multiple commands to the same address:

```
[address][,address]{
command 1 command 2 ...
}
```

The opening `{` must end a line and the closing `}` must be on a line by itself.

COMMANDS

The maximum number of permissible addresses for each command is indicated in parentheses in the following list.

An argument denoted `text` consists of one or more lines of text. If `text` is longer than one line in length, then any newline characters must be hidden by preceding them with a backslash (`\`).

An argument denoted `read-filename` or `write-filename` must terminate the command line and must be preceded by exactly one space. Each `write-filename` is created before processing begins.

(0)	An empty command is ignored.
(0) <code>#comment</code>	The line is a comment and is ignored by <code>sed</code> . If, however, the first such line in a script is of the form <code>#n</code> , then <code>sed</code> behaves as if the <code>-n</code> flag had been specified.
(0) <code>: label</code>	Affix <code>label</code> to a line in the script for a transfer of control by <code>b</code> or <code>t</code> commands.
(1) <code>=</code>	Write the current line number on the standard output as a line.
(1) <code>a\text</code>	Append <code>text</code> following each line matched by the address on the standard output before reading the next input line.
(2) <code>b label</code>	Unconditionally transfer control to the <code>:</code> command bearing the <code>label</code> . If no <code>label</code> is specified, then branch to the end of the script; no more commands are executed on the current pattern space.
(2) <code>c\text</code>	Change the pattern space by replacing the selected pattern with <code>text</code> . When multiple lines are specified, all lines in the pattern space are replaced with a single copy of <code>text</code> . The end result is that the pattern space is deleted and no further editing commands can be applied to it.
(2) <code>d</code>	Delete the pattern space, preventing the line from being passed to the standard output, and start the next cycle.
(2) <code>D</code>	Delete the initial segment of the pattern space through the first newline and start the next cycle.
(2) <code>g</code>	Replace the contents of the pattern space by the contents of the hold space.
(2) <code>G</code>	Append a newline character followed by the contents of the hold space to the pattern space.
(2) <code>h</code>	Replace the contents of the hold space by the contents of the pattern space.
(2) <code>H</code>	Append a newline character followed by the contents of the pattern space to the hold space.
(1) <code>i\text</code>	Insert <code>text</code> by writing it to the standard output.
(2) <code>l</code>	Write the pattern space to standard output in a visually unambiguous form. Nonprinting characters are displayed as either three-digit octal values, preceded by a <code>\</code> , or as one of the following character constant escape sequences:
	<code>\\</code> Backslash
	<code>\a</code> Alert
	<code>\b</code> Backspace
	<code>\f</code> Form-feed
	<code>\n</code> Newline
	<code>\r</code> Carriage-return
	<code>\t</code> Tab
	<code>\v</code> Vertical tab

	Long lines are folded, with the point of folding indicated by a backslash (\) and a newline character. The end of every line is marked with a \$.
(2) n	Copy the pattern space to the standard output. Replace the pattern space with the next line of input.
(2) N	Append the next line of input to the pattern space with an embedded newline. (The current line number changes.)
(2) p	Print the pattern space to the standard output.
(2) P	Copy the initial segment of the pattern space through the first newline to the standard output.
(1) q	Quit by transferring control to the end of the script and do not start a new cycle. The pattern space is still written to the standard output.
(2) r read-filename	Read the contents of read-filename. Place them on the output before reading the next input line.
(2) s/regularexpression/ replacement/flags	Substitute the replacement string for instances of the regular expression in the pattern space. Any character may be used instead of /. (For a fuller description, see the explanation of replacement patterns in the “Regular Expressions” section of this manual page.) flags is zero or more of: - n Substitute for just the nth occurrence of the regular expression. - g Globally substitute for all nonoverlapping instances of the regular expression rather than just the first one. - p Print the pattern space if a replacement was made.
w write-filename	Append the pattern space to write-filename if a replacement was made.
(2) t label	Branch to the : command bearing the label if any substitutions have been made since the most recent reading of an input line or execution of a t. If label is empty, branch to the end of the script.
(2) w write-filename	Append the pattern space to write-filename.
(2) x	Exchange the contents of the pattern and hold spaces.
(2) y/string1/string2/	Replace all occurrences of characters in string1 with the corresponding character in string2. The lengths of string1 and string2 must be equal. Any character other than ' ' or newline can be used instead of slash to delimit the strings. Within string1 and string2, the delimiter itself can be used as a literal character if it is preceded by a backslash.

DIAGNOSTICS

Command only uses one address—A command that takes one address had two addresses specified.

Command doesn't take any addresses—A command that takes no addresses had an address specified.

Extra characters after command—A command had extra text after the end.

Unexpected End-of-file—The end of a script was reached before it should have been. This usually occurs when a command is started, but not finished.

No previous regular expression—A metacharacter calling for a previous regular expression before any regular expressions were used.

Missing command—An address was not followed by a command.

Unknown command—A command was not one of the ones recognized by sed.

Unexpected ', '—A command had a spurious comma after an address.

Multiple '!'s—More than one ! (exclamation point) was used in a command.

Unexpected g—A g character was given in a command without a preceding f.

Unexpected f—An f character was given in a command without a following g.

} doesn't want any addresses—} should be alone on a line.

`:` doesn't want any addresses—The `:` command should not be preceded by an address.

Unterminated `s` command—The replacement field of the `s` command should be completed with a `/` character.

Multiple `p` options to `s` command —The `p` option was given more than once in an `s` command.

Multiple `g` options to `s` command—The `g` option was given more than once in an `s` command.

Multiple number options to `s` command—More than one number option was given to an `s` command.

Unknown option to `s`—An unknown option was used for the `s` command. Maybe you shouldn't do that.

Strings for `y` command are different lengths—There should be a one-to-one mapping between strings for the `y` command.

Missing `' '` before filename—There was no space between an `r`, `w`, or `s///w` command, and the filename specified for that command.

Hopelessly evil compiled in limit on number of open file. re-compile sed.—An attempt was made to open too many files, no matter how you look at it.

SEE ALSO

`awk(1)`, `ed(1)`, `grep(1)`, `perl(1)`, `regex(3)`

HISTORY

A `sed` command appeared in version 7 AT&T UNIX.

STANDARDS

GNU `sed` is expected to be a superset of the IEEE Std1003.2 (POSIX) specification.

CAVEATS

GNU `sed` uses the POSIX basic regular expression syntax. According to the standard, the meaning of some escape sequences is undefined in this syntax; notably `\|` and `\+`.

As in all GNU programs that use POSIX basic regular expressions, `sed` interprets these escape sequences as metacharacters. So, `x\+` matches one or more occurrences of `x`. `abc\|def` matches either `abc` or `def`.

This syntax may cause problems when running scripts written for other versions of `sed`. Some `sed` programs have been written with the assumption that `\|` and `\+` match the literal characters `|` and `+`. Such scripts must be modified by removing the spurious backslashes if they are to be used with GNU `sed`.

BUGS

It has long been noted that GNU `sed` is much slower than other implementations. The current bottleneck is the way `sed` reads and writes data files. It should read large blocks at a time (or even map files, where that is supported). When possible, it should avoid copying its input from one place in memory to another. Patches to make it do those things are welcome!

Version 2.05, December 1994

sessreg

`sessreg`—Manage `utmp/wtmp` entries for non-init clients

SYNOPSIS

```
sessreg [-w wtmp-file] [-u utmp-file] [-l line-name] [-h host-name]
[-s slot-number] [-x Xservers-file] [-t ttys-file] [-a] [-d] user-name
```

DESCRIPTION

`sessreg` is a simple program for managing `utmp/wtmp` entries for `xdm` sessions.

System V has a better interface to `/etc/utmp` than BSD; it dynamically allocates entries in the file instead of writing them at fixed positions indexed by position in `/etc/ttys`.

To manage BSD-style `utmp` files, `sessreg` has two strategies. In conjunction with `xdm`, the `-x` option counts the number of lines in `/etc/ttys` and then adds to that the number of the line in the `Xservers` file that specifies the display. The display name must be specified as the `line-name` using the `-l` option. This sum is used as the `slot-number` in `/etc/utmp` that this entry will be written at. In the more general case, the `-s` option specifies the `slot-number` directly. If for some strange reason your system uses a file other than `/etc/ttys` to manage `init`, the `-t` option can direct `sessreg` to look elsewhere for a count of terminal sessions.

Conversely, System V managers will never need to use these options (`-x`, `-s`, and `-t`). To make the program easier to document and explain, `sessreg` accepts the BSD-specific flags in the System V environment and ignores them.

BSD also has a `host-name` field in the `utmp` file that doesn't exist in System V. This option is also ignored by the System V version of `sessreg`.

USAGE

In `Xstartup`, place a call like:

```
sessreg -a -l $DISPLAY -x /usr/X11R6/lib/xdm/Xservers $USER
```

and in `Xreset`:

```
sessreg -d -l $DISPLAY -x /usr/X11R6/lib/xdm/Xservers $USER
```

OPTIONS

<code>-w wtmp-file</code>	This specifies an alternate <code>wtmp</code> file, instead of <code>/usr/adm/wtmp</code> for BSD or <code>/etc/wtmp</code> for <code>sysv</code> . The special name <code>none</code> disables writing records to <code>/usr/adm/wtmp</code> .
<code>-u utmp-file</code>	This specifies an alternate <code>utmp</code> file, instead of <code>/etc/utmp</code> . The special name <code>none</code> disables writing records to <code>/etc/utmp</code> .
<code>-l line-name</code>	This describes the <code>line</code> name of the entry. For terminal sessions, this is the final pathname segment of the terminal device filename (for example, <code>ttysd0</code>). For <code>x</code> sessions, it should probably be the local display name given to the users session (for example, <code>:0</code>). If <code>none</code> is specified, the terminal name will be determined with <code>ttyname(3)</code> and stripped of leading components.
<code>-h host-name</code>	This is set for BSD hosts to indicate that the session was initiated from a remote host. In typical <code>xdm</code> usage, this options is not used.
<code>-s slot-number</code>	Each potential session has a unique slot number in BSD systems; most are identified by the position of the <code>line-name</code> in the <code>/etc/ttys</code> file. This option overrides the default position determined with <code>ttys-lot(3)</code> . This option is inappropriate for use with <code>xdm</code> , the <code>-x</code> option is more useful.
<code>-x Xservers-file</code>	As <code>x</code> sessions are one-per-display, and each display is entered in this file, this options sets the <code>slot-number</code> to be the number of lines in the <code>ttys-file</code> plus the index into this file that the <code>line-name</code> is found.
<code>-t ttys-file</code>	This specifies an alternate file that the <code>-x</code> option will use to count the number of terminal sessions on a host.
<code>-a</code>	This session should be added to <code>utmp/wtmp</code> .
<code>-d</code>	This session should be deleted from <code>utmp/wtmp</code> . <code>-a</code> or <code>-d</code> must be specified.

SEE ALSO

`xdm(1)`

AUTHOR

Keith Packard, MIT X Consortium

setterm

setterm—Set terminal attributes

SYNOPSIS

```
setterm [ -term terminal name ]

setterm [ -reset ]

setterm [ -initialize ]

setterm [ -cursor [on|off] ]

setterm [ -keyboard pc|olivetti|dutch|extended ]

setterm [ -repeat [on|off] ]

setterm [ -appcursorkeys [on|off] ]

setterm [ -linewrap [on|off] ]

setterm [ -snow [on|off] ]

setterm [ -softscroll [on|off] ]

setterm [ -defaults ]

setterm [ -foreground black|red|green|yellow|blue|magenta|cyan|white|default ]

setterm [ -background black|red|green|yellow|blue|magenta|cyan|white|default ]

setterm [ -ulcolor black|grey|red|green|yellow|blue|magenta|cyan|white ]

setterm [ -ulcolor bright red|green|yellow|blue|magenta|cyan|white ]

setterm [ -hbcolor black|grey|red|green|yellow|blue|magenta|cyan|white ]

setterm [ -hbcolor bright red|green|yellow|blue|magenta|cyan|white ]

setterm [ -inversescreen [on|off] ]

setterm [ -bold [on|off] ]

setterm [ -half-bright [on|off] ]

setterm [ -blink [on|off] ]

setterm [ -reverse [on|off] ]

setterm [ -underline [on|off] ]

setterm [ -store ]

setterm [ -clear [ all|rest ] ]

setterm [ -tabs [tab1 tab2 tab3 ... ] ] where (tabn = 1-160)

setterm [ -clrtabs [ tab1 tab2 tab3 ... ] where (tabn = 1-160)
```

```

setterm [ -regtabs [ 1-160 ]]

setterm [ -blank [ 0-60 ]]

setterm [ -dump [ 1-NR CONS ]]

setterm [ -append [ 1-NR CONS ]]

setterm [ -file dumpfilename ]

setterm [ -standout [ attr ]]

```

DESCRIPTION

setterm writes to standard output a character string that will invoke the specified terminal capabilities. Where possible, /etc/termcap is consulted to find the string to use. Some options, however, do not correspond to a termcap(5) capability. In this case, if the terminal type is minix-vc or minix-vcam, the string that invokes the specified capabilities on the PC Minix virtual console driver is output. Options that are not implemented by the terminal are ignored.

OPTIONS

Most options are self-explanatory. The less obvious options are as follows:

-term	Can be used to override the TERM environment variable
-reset	Displays the terminal reset string, which typically resets the terminal to its power on state
-initialize	Displays the terminal initialization string, which typically sets the terminal's rendering options, and other attributes to the default values
-default	Sets the terminal's rendering options to the default values
-store	Stores the terminal's current rendering options as the default values

Linux 0.98, 25 December 1992

SEE ALSO

tput(1), stty(1), termcap(5), tty(4)

BUGS

Differences between the Minix and Linux versions are not documented.

AUTHORS

Gordon Irlam (gordoni@cs.ua.oz.au); adaptation to Linux by Peter MacDonald; enhancements by Mika Liljeberg (liljeber@cs.Helsinki.FI)

Linux 0.98, 25 December 1992

sgitopnm

sgitopnm—Convert an SGI image file to a portable anymap

SYNOPSIS

```
sgitopnm [-verbose][SGI file]
```

DESCRIPTION

Reads an SGI image file as input. Produces a PGM image for a two-dimensional (one-channel) input file, and a PPM image for a three-dimensional (three or more channels) input file.

OPTIONS

`-verbose` Give some information about the SGI image file

BUGS

Probably

REFERENCES

SGI Image File Format documentation (draft v0.95) by Paul Haeberli (paul@sgi.com). Available via ftp at `sgi.com:graphics/SGIIMAGESPEC`.

SEE ALSO

`pnm(5)`, `pnmtosgi(1)`

AUTHOR

Copyright© 1994 by Ingo Wilken (Ingo.Wilken@informatik.uni-oldenburg.de).

29 January 1994

shar

`shar`—Create shell archives

SYNOPSIS

```
shar [ options ] file ...
shar -S [ options ]
```

DESCRIPTION

`shar` creates shell archives (or `shar` files) that are in text format and can be mailed. These files may be unpacked later by executing them with `/bin/sh`. The resulting archive is sent to standard out unless the `-o` option is given. A wide range of features provide extensive flexibility in manufacturing shar's and in specifying shar "smartness." Archives may be "vanilla" or comprehensive. This manual page reflects shar version 4.0.

OPTIONS

Options have a one-letter version starting with `-` or a long version starting with `--`. The exceptions are `--help` and `--version`, which do not have short versions. Options can be given in any order. Some options depend on each other: The `-o` option is required if the `-l` or `-L` option is used.

The `-n` option is required if the `-a` option is used.

See `-v` in the following list.

These are the available options:

<code>--version</code>	Print the version number of the program on standard output, then immediately exit.
<code>--help</code>	Print a help summary on standard output, then immediately exit.
<code>-V</code> , <code>--vanilla-operation</code>	Produce vanilla shar's that rely only upon the existence of <code>sed</code> and <code>echo</code> in the unsharing environment. In addition, <code>if</code> test must also be supported if the <code>-x</code> option is used. The <code>-v</code> silently disables options offensive to the network cop (or brown shirt), but does warn you if it is specified with <code>-B</code> , <code>-z</code> , <code>-Z</code> , <code>-p</code> , or <code>-M</code> (any of which does or might require <code>uudecode</code> , <code>gzip</code> or <code>compress</code> in the unsharing environment).

-v, --no-verbose	Verbose OFF. disables the inclusion of comments to be output when the archive is unpacked.
-w, --no-character-count	Do NOT check with wc -c after unpack. The default is to check.
-n name, --archive-name=name	Name of archive to be included in the header of the shar files. (See the -a switch.)
-a, --net-headers	Allows automatic generation of headers: Submitted by: who@where Archive-name: <name>/part## The <name> must be given with the -n switch. If name includes a /, then / part isn't used. Thus -n xyzzy produces the following: xyzzy/part01 xyzzy/part02 -n xyzzy/patch produces the following: xyzzy/patch01 xyzzy/patch02 -n xyzzy/patch01. produces the following: xyzzy/patch01.01 xyzzy/patch01.02 The who@where can be explicitly stated with the -s switch if the default isn't appropriate. who@where is essentially built as 'whoami '@'uname'.
-s who@where, --submitter=who@where	Override automatically determined submitter name.
-x, --no-check-existing	Overwrite existing files without checking. If neither -x nor -X is specified, the unpack will check for and not overwrite existing files when unpacking the archive (unless -c is passed as a parameter to the script when unpacking).
-X, --query-user	Interactively overwrite existing files (Do not use for shar's submitted to the Net.)
-B, --uencode	Treat all files as binary; use uencode prior to packing. This increases the size of the archive. The recipient must have udecode in order to unpack. (Use of uencode is not appreciated by many on the Net.)
-T, --text-files	Treat all files as text (default).
-z, --gzip	Use gzip and uencode on all files prior to packing. The recipient must have udecode and gzip (used with -d) in order to unpack. (Use of uencode and gzip is not appreciated by many on the Net.)
-Z, --compress	Use compress and uencode on all files prior to packing. The recipient must have udecode and compress (used with -d) in order to unpack. (Use of uencode and compress is not appreciated by many on the Net.) Option -c is synonymous to -Z, but is being depreciated.
-m, --no-timestamp	Avoid generating touch commands to restore the file modification dates when unpacking files from the archive.
-p, --intermix-type	Allow positional parameter options. The options -B, -T, -z, and -Z may be embedded, and files to the right of the option will be processed in the specified mode.
-g X, --level-for-gzip=X	When doing compression, use -X as a parameter to gzip. The -g option turns on the -z option by default.
-b X, --bits-per-code=X	When doing compression, use -bX as a parameter to compress. The -B option turns on the -Z option by default.

<code>-M, --mixed-uencode</code>	Mixed mode. Determine if the files are text or binary and archive correctly. Files found to be binary are udecoded prior to packing. (Use of <code>uencode</code> is not appreciated by many on the Net.)
<code>-P, --no-piping</code>	Use temporary files instead of pipes in the <code>shar</code> file.
<code>-C, --cut-mark</code>	Start the <code>shar</code> with a cut line. A line saying <code>Cut here</code> is placed at the start of each output file.
<code>-f, --basename</code>	Restore by filename only, rather than path. This option causes only filenames to be used, which is useful when building a <code>shar</code> from several directories, or another directory. Note that if a directory name is passed to <code>shar</code> , the substructure of that directory will be restored whether <code>-f</code> is specified or not.
<code>-d XXX, --here-delimiter=XXX</code>	Use <code>XXX</code> to delimit the files in the <code>shar</code> instead of <code>SHAR_EOF</code> . This is for those who want to personalize their <code>shar</code> files.
<code>-F, --force-prefix</code>	Forces the <code>prefix</code> character (normally <code>x</code> unless the parameter to the <code>-d</code> option starts with <code>x</code>) to be prepended to every line even if not required. This option may slightly increase the size of the archive, especially if <code>-B</code> or <code>-Z</code> is used.
<code>-o XXX --output-prefix=XXX</code>	Save the archive to files <code>XXX.01</code> through <code>XXX.nn</code> instead of standard out. Must be used when the <code>-1</code> or the <code>-L</code> switches are used.
<code>-l XX --whole-size-limit=XX</code>	Limit the output file size to <code>xxk</code> bytes, but don't split input files.
<code>-L XX --split-size-limit=XX</code>	Limit output file size to <code>xxk</code> bytes and split files if necessary. The archives created with this option must be unpacked in correct order.
<code>-S --stdin-file-list</code>	Read list of files to be packed from the standard input rather than from the command line. Input must be in a form similar to that generated by the <code>find</code> command, one filename per line. This switch is especially useful when the command line will not hold the list of files to be packed. For example: <pre>find . -type f -print sort shar -S -Z -L50 -o /tmp/big</pre> If <code>-p</code> is specified on the command line, then the options <code>-B</code> , <code>-T</code> , <code>-z</code> , and <code>-Z</code> may be included in the standard input (on a line separate from filenames). The maximum number of lines of standard input, filenames, and options may not exceed 1024.

EXAMPLES

```
shar *.c > cprog.shar # all C prog sources
shar -v *.*[ch] > cprog.shar # non-verbose, .c and .h files
shar -B -l28 -oarc.sh *.arc # all binary .arc files, into
# files arc.sh.01 thru arc.sh.NN
shar -f /lcl/src/u*.c > u.sh # use only the filenames
```

WARNINGS

No `chmod` or `touch` is ever generated for directories created when unpacking. Thus, if a directory is given to `shar`, the protection and modification dates of corresponding unpacked directory may not match those of the original.

If a directory is passed to `shar`, it may be scanned more than once. Therefore, one should be careful not to change the directory while `shar` is running.

Be careful that the output file(s) are not included in the inputs or `shar` may loop until the disk fills up. Be particularly careful when a directory is passed to `shar` that the output files are not in that directory (or a subdirectory of that directory).

Use of the `-B`, `-z`, or `-Z`, and especially `-M`, may slow the archive process considerably, depending on the number of files.

Use of `-X` produces `shars` that will cause problems with many `unshar` procedures. Use this feature only for archives to be passed among agreeable parties. Certainly, `-X` is not for shell archives that are to be submitted to Usenet. Usage of `-B`, `-z`, or `-Z` in Net `shars` will cause you to be flamed off the earth. Not using `-m` or not using `-F` may also get you occasional complaints.

SEE ALSO

unshar(1)

DIAGNOSTICS

There are error messages for illegal or incompatible options; for nonregular, missing, or inaccessible files; or for (unlikely) memory allocation failure.

AUTHORS

shar(3) is a derived work based on the efforts of the following: James Gosling at CMU (decvax!microsof!uw-beave!jim), Michael A. Thompson, Dalhousie University, Halifax, N.S., Canada, Bill Davidsen (davidsen@sixhub), Richard H. Gumpertz (rhg@CPS.COM), Colas Nahaboo (colas@avahi.inria.fr), Bill Aten (bill@netagw.com), Dennis Boylan (dennis%nanovx@gatech.edu), Warren Tucker (wht%n4hgfr@gatech.edu), and other anonymous persons. Jan Djfrv (jhd@irfu.se) created the man pages.

27 September 1990

shlock

shlock—Create lock files for use in shell scripts

SYNOPSIS

```
shlock -p pid -f name [ -b ][ -u ][ -c ]
```

DESCRIPTION

shlock tries to create a lock file named name and write the process ID pid into it. If the file already exists, shlock will read the process ID from the file and test to see if the process is currently running. If the process exists, then the file will not be created.

shlock exits with a zero status if it was able to create the lock file, or non-zero if the file refers to the currently active process.

Process IDs are normally read and written in ASCII. If the -b flag is used, then they will be written as a binary int. For compatibility with other systems, the -u flag is accepted as a synonym for -b because binary locks are used by many uucp packages.

The following example shows how shlock would be used within a shell script:

```
LOCK=/news/lib/LOCK.send
trap 'rm -f ${LOCK} ;exit1' 1 2 3 15
if shlock -p $$ -f ${LOCK} ; then
# Do appropriate work
else
echo Locked by 'cat ${LOCK}'
fi
```

If the -c flag is used, then shlock will not create a lock file, but will instead use the file to see if the lock is held by another program. If the lock is valid, the program will exit with a non-zero status; if the lock is not valid (that is, invoking shlock without the flag would have succeeded), then the program will exit with a zero status.

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) after a description of HDB UUCP locking given by Peter Honeyman.

showrgb

showrgb—Uncompile an RGB colorname database

SYNOPSIS

```
showrgb [ database ]
```

DESCRIPTION

The **showrgb** program reads an RGB colorname database compiled for use with the **dbm** database routines and converts it back to source form, printing the result to standard output. The default database is the one that **x** was built with, and may be overridden on the command line. Specify the database name without the **.pag** or **.dir** suffix.

FILES

<XRoot>/lib/X11/rgb Default database

X Version 11 Release 6

shrinkfile

shrinkfile—Shrink a file on a line boundary

SYNOPSIS

```
shrinkfile [ -s size ][-v ] file...
```

DESCRIPTION

The **shrinkfile** program shrinks files to a given size, preserving the data at the end of the file. Truncation is performed on line boundaries, where a line is a series of bytes ending with a newline, **\n**. There is no line length restriction and files may contain any binary data.

Temporary files are created in the **/tmp** directory. The **TMPDIR** environment variable may be used to specify a different directory.

A newline will be added to any nonempty file that does not end with a newline. The maximum file size will not be exceeded by this addition.

By default, files are truncated to zero bytes. The **-s** flag may be used to change the maximum size. Because the program truncates only on line boundaries, the final size may be smaller than the specified maximum. The **size** parameter may end with a **k**, **m**, or **g**, indicating kilobyte (1024), megabyte (1048576) or gigabyte (1073741824) lengths. Uppercase letters are also allowed. The maximum file size is 2147483647 bytes.

If the **-v** flag is used, then **shrinkfile** will print a status line if a file was shrunk.

HISTORY

Written by Landon Curt Noll (chongo@toad.com) and Rich Salz (rsalz@uunet.uu.net) for InterNetNews.

sirtopnm

sirtopnm—Convert a Solitaire file into a portable anymap

SYNOPSIS

```
sirtopnm [sirfile]
```

DESCRIPTION

Reads a Solitaire Image Recorder file as input. Produces a portable anymap as output. The type of the output file depends on the input file; if it's an MGI TYPE 17 file, a pgm file is written. If it's an MGI TYPE 11 file, a ppm file is written. The program tells you which type it is writing.

SEE ALSO

pnmtosir(1), pnm(5)

AUTHOR

Copyright© 1991 by Marvin Landis.

20 March 1991

size

size—List section sizes and total size

SYNOPSIS

```
size [ -A | -B | --format=compatibility ][ --help ]
[ -d | -o | -x | --radix=number ]
[ --target=bfdname ][ -V | --version ] objfile ...
```

DESCRIPTION

The GNU `size` utility lists the section sizes and the total size for each of the object files `objfile` in its argument list. By default, one line of output is generated for each object file or each module in an archive.

OPTIONS

<code>-A, -B, --format compatibility</code>	Using one of these options, you can choose whether the output from GNU <code>size</code> resembles output from System V <code>size</code> (using <code>-A</code> , or <code>--format=sysv</code>), or Berkeley <code>size</code> (using <code>-B</code> or <code>--format=berkeley</code>). The default is the one-line format similar to Berkeley's.
<code>--help</code>	Show a summary of acceptable arguments and options.
<code>-d, -o, -x, --radix number</code>	Using one of these options, you can control whether the size of each section is given in decimal (<code>-d</code> , or <code>--radix 10</code>); octal (<code>-o</code> , or <code>--radix 8</code>); or hexadecimal (<code>-x</code> , or <code>--radix 16</code>). In <code>--radix number</code> , only the three values (8, 10, 16) are supported. The total size is always given in two radices: decimal and hexadecimal for <code>-d</code> or <code>-x</code> output, or octal and hexadecimal if you're using <code>-o</code> .
<code>--target bfdname</code>	You can specify a particular object-code format for <code>objfile</code> as <code>bfdname</code> . This may not be necessary; <code>size</code> can automatically recognize many formats. (See <code>objdump(1)</code> for information on listing available formats.)
<code>-V, --version</code>	Display version number information on <code>size</code> itself.

SEE ALSO

binutils entry in `info`; *The GNU Binary Utilities*, Roland H. Pesch (October 1991); `ar(1)`, `objdump(1)`

COPYING

Copyright© 1991 Free Software Foundation, Inc. Permission is granted to make and distribute verbatim copies of this manual, provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

Cygnus Support, 5 November 1991

sldtoppm

sldtoppm—Convert an AutoCAD slide file into a portable pixmap

SYNOPSIS

```
sldtoppm [-adjust][-dir][-height|-ysize s][-info][-lib|-Lib name][-scale s]
[-verbose][-width|-xsize s][slidefile]
```

DESCRIPTION

sldtoppm reads an AutoCAD slide file and outputs a portable pixmap. If no `slidefile` is specified, input is read from standard input. The `ppmdraw` library is used to convert the vector and polygon information in the slide file to a pixmap; see the file `ppmdraw.h` for details on this package.

OPTIONS

- adjust** If the display on which the slide file was created had nonsquare pixels, when the slide is processed with sldtoppm and the `-adjust` option is not present, the following warning will appear: `Warning - pixels on source screen were non-square.`
Specifying `-adjust` will correct image width to compensate. Specifying the `-adjust` option causes sldtoppm to scale the width of the image so that pixels in the resulting portable pixmap are square (and hence circles appear as true circles, not ellipses). The scaling is performed in the vector domain, before scan-converting the objects. The results are, therefore, superior in appearance to what you'd obtain were you to perform the equivalent scaling with `pnmscale` after the bitmap had been created.
- dir** The input is assumed to be an AutoCAD slide library file. A directory listing each slide in the library is printed on standard error.
- height size** Scales the image in the vector domain so it is `size` pixels in height. If no `-width` or `-xsize` option is specified, the width will be adjusted to preserve the pixel aspect ratio.
- info** Dump the slide file header on standard error, displaying the original screen size and aspect ratio among other information.
- lib name** Extracts the slide with the given `name` from the slide library given as input. The specified name is converted to uppercase.
- Lib name** Extracts the slide with the given `name` from the slide library given as input. The name is used exactly as specified; it is not converted to uppercase.
- scale s** Scales the image by factor `s`, which may be any floating-point value greater than zero. Scaling is done after aspect ratio adjustment, if any. Because scaling is performed in the vector domain, before rasterization, the results look much better than running the output of sldtoppm through `pnmscale`.
- verbose** Dumps the slide file header and lists every vector and polygon in the file on standard error.
- width size** Scales the image in the vector domain, so it is `size` pixels wide. If no `-height` or `-ysize` option is specified, the height will be adjusted to preserve the pixel aspect ratio.
- xsize size** Scales the image in the vector domain so it is `size` pixels wide. If no `-height` or `-ysize` option is specified, the height will be adjusted to preserve the pixel aspect ratio.
- ysize size** Scales the image in the vector domain so it is `size` pixels in height. If no `-width` or `-xsize` option is specified, the width will be adjusted to preserve the pixel aspect ratio.

All flags can be abbreviated to their shortest unique prefix.

BUGS

Only Level 2 slides are converted. Level 1 format has been obsolete since the advent of AutoCAD Release 9 in 1987 and was not portable across machine architectures.

Slide library items with names containing 8-bit (such as ISO) or 16-bit (Kanji, for example) characters may not be found when chosen with the `-lib` option unless `sldtoppm` has been built with character set conversion functions appropriate to the locale. You can always retrieve slides from libraries regardless of the character set by using the `-Lib` option and specifying the precise name of library member. Use the `-dir` option to list the slides in a library if you're unsure of the exact name.

SEE ALSO

AutoCAD Reference Manual: “Slide File Format”; `pnmscale(1)`, `ppm(5)`

AUTHOR

John Walker
Autodesk SA
Avenue des Champs-Montants 14b
CH-2074 MARIN
Suisse/Schweiz/Svizzera/Svizra/Switzerland

Usenet: `kelvin@Autodesk.com`

Fax: 038/33 88 15

Voice: 038/33 76 33

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, without any conditions or restrictions. This software is provided “as is” without express or implied warranty.

AutoCAD and Autodesk are registered trademarks of Autodesk, Inc.

10 October 1991

smproxy

smproxy—Session Manager Proxy

SYNOPSIS

```
smproxy [-clientId id] [-restore saveFile]
```

OPTIONS

`-clientId id` Specifies the session ID used by `smproxy` in the previous session.
`-restore saveFile` Specifies the file used by `smproxy` to save state in the previous session.

DESCRIPTION

`smproxy` allows x applications that do not support X11R6 session management to participate in an X11R6 session.

In order for `smproxy` to act as a proxy for an x application, one of the following must be true:

- The application maps a top-level window containing the `WM_CLIENT_LEADER` property. This property provides a pointer to the client leader window that contains the `WM_CLASS`, `WM_NAME`, `WM_COMMAND`, and `WM_CLIENT_MACHINE` properties.
- or
- The application maps a top-level window that does not contain the `WM_CLIENT_LEADER` property. However, this top-level window contains the `WM_CLASS`, `WM_NAME`, `WM_COMMAND`, and `WM_CLIENT_MACHINE` properties.

An application that supports the `WM_SAVE_YOURSELF` protocol will receive a `WM_SAVE_YOURSELF` client message each time the session manager issues a checkpoint or shutdown. This allows the application to save state. If an application does not support the `WM_SAVE_YOURSELF` protocol, then the proxy will provide enough information to the session manager to restart the application (using `WM_COMMAND`), but no state will be restored.

SEE ALSO

`xsm(1)`

AUTHOR

Ralph Mor, X Consortium

X Version 11 Release 6

sort

sort—Sort lines of text files

SYNOPSIS

```
sort [-cmus] [-t separator] [-o output-file] [-T tmpdir] [-bdfiMnr]
[+POS1 [-POS2]] [-k POS1[,POS2]] [file...]
sort {--help,--version}
```

DESCRIPTION

This manual page documents the GNU version of `sort`. `sort` sorts, merges, or compares all the lines from the given files, or the standard input if no files are given. A filename of `-` means standard input. By default, `sort` writes the results to the standard output.

`sort` has three modes of operation: `sort` (the default), `merge`, and `check for sortedness`. The following options change the operation mode:

- `-c` Check whether the given files are already sorted; if they are not all sorted, print an error message and exit with a status of 1.
- `-m` Merge the given files by sorting them as a group. Each input file should already be individually sorted. It always works to sort instead of merge; merging is provided because it is faster, in the case where it works.

A pair of lines is compared as follows: if any key fields have been specified, `sort` compares each pair of fields, in the order specified on the command line, according to the associated ordering options, until a difference is found or no fields are left.

If any of the global options `Mbdfinr` are given but no key fields are specified, `sort` compares the entire lines according to the global options.

Finally, as a last resort when all keys compare equal (or if no ordering options were specified at all), `sort` compares the lines byte by byte in machine collating sequence. The last resort comparison honors the `-r` global option. The `-s` (stable) option disables this last-resort comparison so that lines in which all fields compare equal are left in their original relative order. If no fields or global options are specified, `-s` has no effect.

GNU `sort` has no limits on input line length or restrictions on bytes allowed within lines. In addition, if the final byte of an input file is not a newline, GNU `sort` silently supplies one.

If the environment variable `TMPDIR` is set, `sort` uses it as the directory in which to put temporary files instead of the default, `/tmp`. The `-T tmpdir` option is another way to select the directory for temporary files; it overrides the environment variable.

The following options affect the ordering of output lines. They may be specified globally or as part of a specific key field. If no key fields are specified, global options apply to comparison of entire lines; otherwise, the global options are inherited by key fields that do not specify any special options of their own.

- b Ignore leading blanks when finding sort keys in each line.
- d Sort in phone directory order; ignore all characters except letters, digits, and blanks when sorting.
- f Fold lowercase characters into the equivalent uppercase characters when sorting so that, for example, b is sorted the same way B is.
- i Ignore characters outside the ASCII range 040–0176 octal (inclusive) when sorting.
- M An initial string, consisting of any amount of whitespace, followed by three letters abbreviating a month name, is folded to uppercase and compared in the order 'JAN' < 'FEB' < ... < 'DEC'. Invalid names compare low to valid names.
- n Compare according to arithmetic value an initial numeric string consisting of optional whitespace, an optional - sign, and zero or more digits, optionally followed by a decimal point and zero or more digits.
- r Reverse the result of comparison, so that lines with greater key values appear earlier in the output instead of later.

Other options are

- o *output-file* Write output to *output-file* instead of to the standard output. If *output-file* is one of the input files, *sort* copies it to a temporary file before sorting and writing the output to *output-file*.
- t *separator* Use character *separator* as the field separator when finding the sort keys in each line. By default, fields are separated by the empty string between a nonwhitespace character and a whitespace character. That is to say, given the input line *foo bar*, *sort* breaks it into fields *foo* and *bar*. The field separator is not considered to be part of either the field preceding or the field following it.
- u For the default case or the -m option, only output the first of a sequence of lines that compare equal. For the -c option, check that no pair of consecutive lines compares equal.
- +POS1 [-POS2] Specify a field within each line to use as a sorting key. The field consists of the portion of the line starting at POS1 and up to (but not including) POS2 (or to the end of the line if POS2 is not given). The fields and character positions are numbered starting with 0.
- k POS1[,POS2] An alternate syntax for specifying sorting keys. The fields and character positions are numbered starting with 1.

A position has the form *f.c*, where *f* is the number of the field to use and *c* is the number of the first character from the beginning of the field (for +pos) or from the end of the previous field (for -pos). The .*c* part of a position may be omitted, in which case it is taken to be the first character in the field. If the -b option has been given, the .*c* part of a field specification is counted from the first nonblank character of the field (for +pos) or from the first nonblank character following the previous field (for -pos).

A +pos or -pos argument may also have any of the option letters *mbdfinr* appended to it, in which case the global ordering options are not used for that particular field. The -b option may be independently attached to either or both of the +pos and -pos parts of a field specification, and if it is inherited from the global options, it will be attached to both. If a -n or -M option is used, thus implying a -b option, the -b option is taken to apply to both the +pos and the -pos parts of a key specification. Keys may span multiple fields.

In addition, when GNU *join* is invoked with exactly one argument, the following options are recognized:

- help Print a usage message on standard output and exit successfully
- version Print version information on standard output, then exit successfully

COMPATIBILITY

Historical (BSD and System V) implementations of *sort* have differed in their interpretation of some options, particularly -b, -f, and -n. GNU *sort* follows the POSIX behavior, which is usually (but not always) like the System V behavior. According to POSIX, -n no longer implies -b. For consistency, -M has been changed in the same way. This may affect the meaning of character positions in field specifications in obscure cases. If this bites you, the fix is to add an explicit -b.

BUGS

The different meaning of field numbers depending on whether -k is used is confusing. It's all POSIX's fault!

spctoppm

spctoppm—Convert an Atari compressed Spectrum file into a portable pixmap

SYNOPSIS

```
spctoppm [spcfile]
```

DESCRIPTION

spctoppm reads an Atari compressed Spectrum file as input and produces a portable pixmap as output.

SEE ALSO

sputoppm(1), ppm(5)

AUTHOR

Copyright© 1991 by Steve Belczyk (seb3@gte.com) and Jef Poskanzer.

19 July 1990

split

split—Split a file into pieces

SYNOPSIS

```
split [-l lines] [-l lines] [-b bytes[bkm]] [-C bytes[bkm]] [--lines=lines]
[--bytes=bytes[bkm]] [--line-bytes=bytes[bkm]] [--help] [--version]
[infile [outfile-prefix]]
```

DESCRIPTION

This manual page documents the GNU version of **split**. **split** creates one or more output files (as many as necessary) containing consecutive sections of the **infile**, or the standard input if none is given or the name **-** is given. By default, **split** puts 1000 lines of the input file, or whatever is left if it is less than that, into each output file.

The output filenames consist of a prefix followed by a group of letters, chosen so that concatenating the output files in sorted order by filename produces the original input file, in order. The default output filename prefix is **x**. If the **outfile-prefix** argument is given, it is used as the output filename prefix instead.

OPTIONS

-l lines , -l lines , --lines=lines	Put lines lines of the input file into each output file.
-b bytes[bkm] , --bytes=bytes[bkm]	Put bytes bytes of the input file into each output file. bytes is a non-zero integer, optionally followed by one of the following characters to specify a different unit:
	b 512-byte blocks
	k 1-kilobyte blocks
	m 1-megabyte blocks
-C bytes[bkm] , --line-bytes=bytes[bkm]	Put into each output file as many complete lines of the input file as is possible without exceeding bytes bytes. If a line that is longer than bytes bytes occurs, put bytes bytes of it into each output file until less than bytes bytes of the line are left, then continue normally. bytes has the same format as for the --bytes option.

--help Print a usage message and exit with a non-zero status.
 --version Print version information on standard output then exit.

GNU Text Utilities

spottopgm

spottopgm—Convert SPOT satellite images to portable graymap format

SYNTAX

spottopgm [-1|2|3] [Firstcol Firstline Lastcol Lastline] inputfile

OPTIONS

-1|2|3 Extract the given color from the SPOT image. The colors are infrared, visible light, and ultra-violet, although I don't know which corresponds to which number. If the image is in color, this will be announced on standard error. The default color is 1.

Firstcol Firstline Lastcol Lastline Extract the specified rectangle from the SPOT image. Most SPOT images are 3,000 lines long and 3,000 or more columns wide. Unfortunately, the SPOT format only gives the width and not the length. The width is printed on standard error. The default rectangle is the width of the input image by 3,000 lines.

DESCRIPTION

spottopgm converts the named inputfile into portable graymap format, defaulting to the first color and the whole SPOT image unless specified by the options.

INSTALLATION

You must edit the source program and either define BIGENDIAN or LITTLEENDIAN, and fix the typedefs for uint32t, uint16t, and uint8t appropriately.

BUGS

Currently, spottopgm doesn't determine the length of the input file; this would involve two passes over the input file. It defaults to 3,000 lines instead.

spottopgm could extract a three-color image (ppm), but I didn't feel like making the program more complicated than it is now. Besides, there is no one-to-one correspondence between red, green, blue, and infra-red, visible, and ultra-violet.

I've had only a limited number of SPOT images to play with, and therefore wouldn't guarantee that this will work on any other images.

AUTHOR

Warren Toomey (wkt@csadfa.cs.adfa.oz.au)

SEE ALSO

The rest of the pbmp1us suite.

sputoppm

sputoppm—Convert an Atari uncompressed Spectrum file into a portable pixmap

SYNOPSIS

```
sputoppm [spufile]
```

DESCRIPTION

sputoppm reads an Atari uncompressed Spectrum file as input and produces a portable pixmap as output.

SEE ALSO

spctoppm(1), ppm(5)

AUTHOR

Copyright© 1991 by Steve Belczyk (seb3@gte.com) and Jef Poskanzer.

19 July 1990

sq

sq—Squeeze a sorted word list

unsq—Unsqueeze a sorted word list

SYNOPSIS

```
sq < infile > outfile
unsq < infile > outfile
```

DESCRIPTION

sq compresses a sorted list of words (a dictionary). For example,

```
sort /usr/dict/words | sq | compress > words.sq.Z
```

will compress dict by about a factor of 4.

unsq uncompresses the output of sq. For example,

```
compress -d < words.sq.Z | unsq | sort -f -o words
```

will uncompress a dictionary compressed with sq. The squeezing is achieved by eliminating common prefixes and replacing them with a single character that encodes the number of characters shared with the preceding word. The prefix size is encoded as a single printable character: 0–9 represent 0–9, A–Z represent 10–35, and a–z represent 36–61.

AUTHOR

Mike Wexler

SEE ALSO

compress(1), sort(1).

Local

startx

startx—Initialize an X session

SYNOPSIS

```
startx [[client] options ..] [-- [server] options ...]
```

DESCRIPTION

NOTE

The `startx` script supplied with the X11 distribution is a sample designed more as a base for customization than as a finished product. Site administrators are urged to customize it for their site—and to update this manual page when they do.

The `startx` script is a front end to `xinit` that provides a somewhat nicer user interface for running a single session of the X Window System. It is typically run with no arguments.

To determine the client to run, `startx` first looks for a file called `.xinitrc` in the user's home directory. If that is not found, it uses the file `xinitrc` in the `xinit` library directory. If command-line client options are given, they override this behavior. To determine the server to run, `startx` first looks for a file called `.xserverrc` in the user's home directory. If that is not found, it uses the file `xserverrc` in the `xinit` library directory. If command-line server options are given, they override this behavior. Users rarely need to provide a `.xserverrc` file. (See the `xinit(1)` manual page for more details on the arguments.)

The `.xinitrc` is typically a shell script that starts many clients according to the user's preference. When this shell script exits, `startx` kills the server and performs any other session shutdown needed. Most of the clients started by `.xinitrc` should be run in the background. The last client should run in the foreground; when it exits, the session will exit. People often choose a session manager, window manager, or `xterm` as the “magic” client.

EXAMPLE

Following is a sample `xinitrc` that starts several applications and leaves the window manager running as the “last” application. Assuming that the window manager has been configured properly, the user then chooses the Exit menu item to shut down X.

```
xrdb -load $HOME/.Xresources
xsetroot -solid gray &
xbiff -geometry -430+5 &
oclock -geometry 75x75-0-0 &
xload -geometry -80-0 &
xterm -geometry +0+60 -ls &
xterm -geometry +0-100 &
xconsole -geometry -0+0 -fn 5x7 &
exec twm
```

ENVIRONMENT VARIABLES

DISPLAY This variable gets set to the name of the display to which clients should connect. Note that this gets set, not read.

FILES

<code>\$(HOME)/.xinitrc</code>	Client to run. Typically a shell script that runs many programs in the background.
<code>\$(HOME)/.xserverrc</code>	Server to run. The default is <code>x</code> .
<code><XRoot>/lib/X11/xinit/xinitrc</code>	Client to run if the user has no <code>.xinitrc</code> file. <code><XRoot></code> refers to the root of the X11 install tree.
<code><XRoot>/lib/X11/xinit/xserverrc</code>	Client to run if the user has no <code>.xserverrc</code> file. This is only needed if the server needs special arguments or is not named. <code><XRoot></code> refers to the root of the X11 install tree.

SEE ALSO

`xinit(1)`

strings

strings—Print the strings of printable characters in files

SYNOPSIS

```
strings [ -a|--all ][-f|--print-file-name][-o ][--help ][-v|--version ]
[ -n min-len |--min-len |--bytes= min-len ][-t o,x,d ]
[ --target=bfdname ] |--radix= o,x,d ] file
```

DESCRIPTION

For each `file` given, GNU `strings` prints the printable character sequences that are at least four characters long (or the number given with the options below) and are followed by a NUL or newline character. By default, it only prints the strings from the initialized data sections of object files; for other types of files, it prints the strings from the whole file.

`strings` is mainly useful for determining the contents of nontext files.

OPTIONS

The long and short forms of options, shown here as alternatives, are equivalent.

<code>-a, --all, -</code>	Do not scan only the initialized data section of object files; scan the whole files.
<code>-f, --print-file-name</code>	Print the name of the file before each string.
<code>--help</code>	Print a summary of the options to <code>strings</code> on the standard output and exit.
<code>-v, --version</code>	Print the version number of <code>strings</code> on the standard output and exit.
<code>-n min-len, --min-len, -bytes=min-len</code>	Print sequences of characters that are at least <code>min-len</code> characters long, instead of the default 4.
<code>-t o,x,d, --radix=o,x,d</code>	Print the offset within the file before each string. The single character argument specifies the radix of the offset—octal, hexadecimal, or decimal.
<code>--target=bfdname</code>	Specify an object code format other than your system's default format. (See <code>objdump(1)</code> , for information on listing available formats.)
<code>-o</code>	Like <code>-t o</code> .

SEE ALSO

`binutils` entry in `info`; *The GNU Binary Utilities*, Roland H. Pesch (October 1991); `ar(1)`, `nm(1)`, `objdump(1)`, `ranlib(1)`.

COPYING

Copyright© 1993 Free Software Foundation, Inc. Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

Cygnus Support, 25 June 1993

strip

strip—Discard symbols from object files.

SYNOPSIS

```
strip [ -Fbfdname|--target=bfdname ] [ -Ibfdname|
--input-target=bfdname ] [ -Obfdname|--output-target=bfdname ]
[ -Rsectionname|--remove-section=sectionname ] [ -s|--strip-all ]
[ -S|-g|--strip-debug ] [ -x|--discard-all ] [ -X|--discard-locals ]
[ -v|--verbose ] [ -V|--version ] [ -V|--help ] objfile ...
```

DESCRIPTION

GNU `strip` discards all symbols from the object files `objfile`. The list of object files may include archives. At least one object file must be given.

`strip` modifies the files named in its argument, rather than writing modified copies under different names.

OPTIONS

<code>-F bfdname, --target=bfdname</code>	Treat the original <code>objfile</code> as a file with the object code format <code>bfdname</code> , and rewrite it in the same format.
<code>--help</code>	Show a summary of the options to <code>strip</code> and exit.
<code>-I bfdnamefdname", --input-target=bfdname</code>	Treat the original <code>objfile</code> as a file with the object code format <code>bfdname</code> .
<code>-O bfdname, --output-target=bfdname</code>	Replace <code>objfile</code> with a file in the output format <code>bfdname</code> .
<code>-R sectionname, --remove-section=sectionname</code>	Remove the named section from the file. This option may be given more than once. Note that using this option inappropriately may make the object file unusable.
<code>-s, --strip-all</code>	Remove all symbols.
<code>-S, -g, --strip-debug</code>	Remove debugging symbols only.
<code>-x, --discard-all</code>	Remove nonglobal symbols.
<code>-X, --discard-locals</code>	Remove compiler-generated local symbols. (These usually start with <code>_</code> or a period.
<code>-v, --verbose</code>	Verbose output: list all object files modified. In the case of archives, <code>strip -v</code> lists all members of the archive.
<code>-V, --version</code>	Show the version number for <code>strip</code> and exit.

SEE ALSO

`binutils` entry in `info`; *The GNU Binary Utilities*, Roland H. Pesch (October 1991)

COPYING

Copyright© 1991 Free Software Foundation, Inc. Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

Cygnus Support, 5 November 1991

subst

subst—Substitute definitions into file(s)

SYNOPSIS

```
subst [ -e editor ] -f substitutions victim ...
```

DESCRIPTION

subst makes substitutions into files, in a way that is suitable for customizing software to local conditions. Each `victim` file is altered according to the contents of the `substitutions` file.

The `substitutions` file contains one line per substitution. A line consists of two fields separated by one or more tabs. The first field is the name of the substitution, the second is the value. Neither should contain the character `#`, and use of text-editor metacharacters like `&` and `\` is also unwise; the name in particular is best restricted to alphanumeric. A line starting with `#` is a comment and is ignored.

In the `victim` files, each line on which a substitution is to be made (a target line) must be preceded by a prototype line. The prototype line should be delimited in such a way that it will be taken as a comment by whatever program processes the file later. The prototype line must contain a prototype of the target line bracketed by `=(< and >())=`; everything else on the prototype line is ignored. `subst` extracts the prototype, changes all instances of substitution names bracketed by `@<` and `>@` to their values, and then replaces the target line with the result.

Substitutions are done using the `sed(1)` editor, which must be found in either the `/bin` or `/usr/bin` directories. To specify a different executable, use the `-e` flag.

EXAMPLE

If the `substitutions` file is

```
FIRST 111
SECOND 222
```

and the `victim` file is

```
x =2;
/* =(<y =@<FIRST>@+@<SECOND>@;>())= */
y =88 +99;
z =5;
```

then `subst -f substitutions victim` changes `victim` to

```
x =2;
/* =(<y =@<FIRST>@+@<SECOND>@;>())= */
y = 111 + 222;
z =5;
```

FILES

```
victimdir/substtmp.new  New version being built
victimdir/substtmp.old  Old version during renaming
```

SEE ALSO

`sed(1)`

DIAGNOSTICS

Complains and halts if it is unable to create its temporary files or if they already exist.

HISTORY

Written at University of Toronto by Henry Spencer.

Rich \$alz added the `-e` flag July, 1991.

BUGS

When creating a file to be substed, it's easy to forget to insert a dummy target line after a prototype line; if you forget, subst ends up deleting whichever line did in fact follow the prototype line.

Local

SUM

sum—Checksum and count the blocks in a file

SYNOPSIS

```
sum [-rs] [--sysv] [--help] [--version] [file...]
```

DESCRIPTION

This manual page documents the GNU version of `sum`. `sum` computes a 16-bit checksum for each named file, or the standard input if none are given or when a file named `-` is given. It prints the checksum for each file along with the number of blocks in the file (rounded up). By default, each corresponding filename is also printed if at least two arguments are specified. With the `--sysv` option, corresponding filenames are printed when there is at least one file argument. By default, the GNU `sum` computes checksums using an algorithm that is compatible with the BSD `sum` and prints file sizes in units of 1K blocks.

OPTIONS

<code>-r</code>	Use the default (BSD-compatible) algorithm. This option is included for compatibility with the System V <code>sum</code> . Unless the <code>-s</code> option was also given, it has no effect.
<code>-s, --sysv</code>	Compute checksums using an algorithm that is compatible with the one the System V <code>sum</code> uses by default and print file sizes in units of 512-byte blocks instead of 1K.
<code>--help</code>	Print a usage message and exit with a non-zero status.
<code>--version</code>	Print version information on standard output, then exit.

GNU Text Utilities

SuperProbe

SuperProbe—Probe for and identify installed video hardware

SYNOPSIS

```
SuperProbe [-verbose] [-no16] [-excl list] [-mask10] [-order list] [-noprobe list] [-bios base]
[-no bios] [-no dac] [-no mem] [-info]
```

DESCRIPTION

`SuperProbe` is a program that will attempt to determine the type of video hardware installed in an EISA/ISA/VLB-bus system by checking for known registers in various combinations at various locations (MicroChannel and PCI machines may not be fully supported; many work with the use of the `-no_bios` option.) This is an error-prone process, especially on UNIX (which usually has a lot more esoteric hardware installed than MS-DOS systems do), so `SuperProbe` may likely need help from the user.

SuperProbe runs on SVR3, SVR4, Linux, 386BSD/FreeBSD/NetBSD, Minix-386, and Mach. It should be trivial to extend it to work on any other UNIX-like operating system, and even non-UNIX operating systems. All of the operating system (OS) dependencies are isolated to a single file for each OS.

At this time, SuperProbe can identify MDA, Hercules, CGA, MCGA, EGA, VGA, and an entire horde of SVGA chipsets. (See the `-info` option under “Options.”) It can also identify several HiColor/True-color RAMDACs in use on SVGA boards, and the amount of video memory installed (for many chipsets). It can identify 8514/A and some derivatives, but not XGA, or PGC (although the author intends to add those capabilities). Nor can it identify other esoteric video hardware (like Targa, TIGA, or Microfield boards).

OPTIONS

<code>-verbose</code>	SuperProbe will be verbose and provide lots of information as it does its work.
<code>-no16</code>	SuperProbe will not attempt to use any ports that require 16-bit I/O address decoding. The original ISA bus only specified that I/O ports be decoded to 10 bits. Therefore, some old cards (including many 8-bit cards) will misdecode references to ports that use the upper 6 bits, and may get into funny states because they think that they are being addressed when they are not. It is recommended that this option be used initially if any 8-bit cards are present in the system.
<code>-excl\list</code>	SuperProbe will not attempt to access any I/O ports on the specified exclusion list. Some video cards use rather nonstandard I/O ports that may conflict with other cards installed in your system. By specifying to SuperProbe, a list of ports already in use, it will know that there cannot be any video cards that use those ports, and hence will not probe them (which could otherwise confuse your hardware). The exclusion list is specified as a comma-separated list of I/O ports or port ranges. A range is specified as <code>low-high</code> , and is inclusive. The ports can be specified in decimal, in octal (numbers begin with <code>0</code>), or hexadecimal (numbers begin with <code>0x</code>).
<code>-mask10</code>	This option is used in combination with <code>-excl</code> . It tells SuperProbe that when comparing an I/O port under test against the exclusion list, the port address should be masked to 10 bits. This is important with older 8-bit cards that only do 10-bit decoding, and for some cheap 16-bit cards as well. This option is simply a less drastic form of the <code>-no16</code> option.
<code>-order\list</code>	This option specifies which chipsets SuperProbe should test, and in which order. The <code>list</code> parameter is a comma-separated list of chipset names. This list overrides the built-in default testing order. To find the list of acceptable names, use the <code>-info</code> option described later in this list. Note that items displayed as “Standard video hardware” are not usable with the <code>-order</code> option.
<code>-noprobe\list</code>	This option specifies which chipsets SuperProbe should not test. The order of testing will either be the default order, or that specified with the <code>-order</code> option. The <code>list</code> parameter is a comma-separated list of chipset names. To find the list of acceptable names, use the <code>-info</code> option. Note that items displayed as “Standard video hardware” are not usable with the <code>-noprobe</code> option.
<code>-bios\base</code>	This option specifies the base address for the graphics-hardware BIOS. By default, SuperProbe will attempt to locate the BIOS base on its own (the normal address is <code>0xc0000</code>). If it fails to correctly locate the BIOS (an error message will be printed if this occurs), the <code>-bios</code> option can be used to specify the base.
<code>-no_bios</code>	Disallow reading of the video BIOS and assume that an EGA or later (VGA, SVGA) board is present as the primary video hardware.
<code>-no_dac</code>	Skip probing for the RAMDAC type when an (S)VGA is identified.
<code>-no_mem</code>	Skip probing for the amount of installed video memory.
<code>-info</code>	SuperProbe will print out a listing of all the video hardware that it knows how to identify.

EXAMPLES

To run SuperProbe in its most basic and automated form, simply enter the following:

```
SuperProbe
```

NOTE

You may want to redirect `stdout` to a file when you run `SuperProbe` (especially if your OS does not support Virtual Terminals on the console).

However, if you have any 8-bit cards installed, you should initially run `SuperProbe` as

```
SuperProbe -verbose -no16
```

(the `-verbose` option is included so you can see what `SuperProbe` is skipping).

Finer granularity can be obtained with an exclusion list, for example,

```
SuperProbe -verbose -exc1 0x200,0x220-0x230,0x250
```

will not test for any device that uses port `0x200`, ports `0x220` through `0x230`, inclusive, or port `0x250`. If you have any 8-bit cards installed, you should add `-mask10` to the list of options.

To restrict the search to Western Digital, Tseng, and Cirrus chipset, run `SuperProbe` as follows:

```
SuperProbe -order WD,Tseng,Cirrus
```

BUGS

Probably a lot at this point. Please report any bugs or incorrect identifications to the author.

It is possible that `SuperProbe` can lock up your machine. Be sure to narrow the search by using the `-no16`, `-exc1`, and `-mask10` options provided to keep `SuperProbe` from conflicting with other installed hardware.

SEE ALSO

The `vgadoc3.zip` documentation package by Finn Thøgersen, available in the MS-DOS archives of many FTP repositories.
Programmer's Guide to the EGA and VGA Cards, Second Edition, by Richard Ferraro.

AUTHOR

David E. Wexelblat (dwex@xfree86.org) with help from David Dawes (dawes@xfree86.org) and the XFree86 development team.

Version 2.2

tac

`tac`—Concatenate and print files in reverse

SYNOPSIS

```
tac [-br] [-s separator] [--before] [--regex] [--separator=separator]
    [--help] [--version] [file...]
```

DESCRIPTION

This manual page documents the GNU version of `tac`. `tac` copies each given file, or the standard input if none are given or when a filename of `-` is encountered, to the standard output with the order of the records reversed. The records are separated by instances of a string, or a newline if none is given. By default, the separator string is attached to the end of the record that it follows in the file.

OPTIONS

<code>-b, --before</code>	The separator is attached to the beginning of the record that it precedes in the file.
<code>-r, --regex</code>	The separator is a regular expression.
<code>-s string, --separator=string</code>	Use <code>string</code> as the record separator.
<code>--help</code>	Print a usage message and exit with a non-zero status.
<code>--version</code>	Print version information on standard output, then exit.

GNU Text Utilities

tail

`tail`—Output the last part of files

SYNOPSIS

```
tail [-c [+]N[bkm]] [-n [+]N] [-fqv] [--bytes=[+]N[bkm]] [--lines=[+]N]
[--follow] [--quiet] [--silent] [--verbose] [--help] [--version] [file...]
```

```
tail [{-,+}Nbcfklmqv] [file...]
```

DESCRIPTION

This manual page documents the GNU version of `tail`. `tail` prints the last part (10 lines by default) of each given file; it reads from standard input if no files are given or when a filename of `-` is encountered. If more than one file is given, it prints a header consisting of the file's name enclosed in `==>` and `<==` before the output for each file.

The GNU `tail` can output any amount of data, unlike the UNIX version, which uses a fixed size buffer. It has no `-r` option (print in reverse). Reversing a file is really a different job from printing the end of a file; the BSD `tail` can only reverse files that are at most as large as its buffer, which is typically 32KB. A reliable and more versatile way to reverse files is the GNU `tac` command.

OPTIONS

`tail` accepts two option formats: the new one, in which numbers are arguments to the option letters, and the old one, in which a `+` or `-` and optional number precede any option letters.

If a number (*N*) starts with a `+`, `tail` begins printing with the *N*th item from the start of each file, instead of from the end.

<code>-c <i>N</i>, --bytes <i>N</i></code>	Tail by <i>N</i> bytes. <i>N</i> is a non-zero integer, optionally followed by one of the following characters to specify a different unit.
<code>b</code>	512-byte blocks
<code>k</code>	1-kilobyte blocks
<code>m</code>	1-megabyte blocks
<code>-f, --follow</code>	Loop forever, trying to read more characters at the end of the file, on the assumption that the file is growing. Ignored if reading from a pipe. If more than one file is given, <code>tail</code> prints a header whenever it gets output from a different file, to indicate which file that output is from.
<code>-l, -n <i>N</i>, --lines <i>N</i></code>	Tail by <i>N</i> lines. <code>-l</code> is only recognized using the old option format.
<code>-q, --quiet, --silent</code>	Never print filename headers.
<code>-v, --verbose</code>	Always print filename headers.
<code>--help</code>	Print a usage message and exit with a non-zero status.
<code>--version</code>	Print version information on standard output then exit.

GNU Text Utilities

talk

talk—Talk to another user

SYNOPSIS

```
talk person [ttyname]
```

DESCRIPTION

talk is a visual communication program that copies lines from your terminal to that of another user.

The following options are available:

person	If you wish to talk to someone on your own machine, then <code>person</code> is just the person's login name. If you wish to talk to a user on another host, then <code>person</code> is of the form <code>user@host</code> .
ttyname	If you wish to talk to a user who is logged in more than once, the <code>ttyname</code> argument may be used to indicate the appropriate terminal name, where <code>ttyname</code> is of the form <code>ttysx</code>

When first called, talk sends the message `Message from TalkDaemon@his_machine...`:

```
talk: connection requested by your_name@your_machine
```

```
talk: respond with: talk your_name@your_machine
```

to the user you wish to talk to. At this point, the recipient of the message should reply by typing

```
talk your_name@your_machine
```

It doesn't matter from which machine the recipient replies, as long as his login name is the same. Once communication is established, the two parties may type simultaneously, with their output appearing in separate windows. Typing `control-L` will cause the screen to be reprinted, while your `erase`, `kill`, and `word kill` characters will behave normally. To exit, just type your interrupt character; talk then moves the cursor to the bottom of the screen and restores the terminal to its previous state.

Permission to talk may be denied or granted by use of the `mesg 1` command. At the outset, talking is allowed. Certain commands, in particular `nroff 1` and `pr 1`, disallow messages in order to prevent messy output.

FILES

<code>/etc/hosts</code>	To find the recipient's machine
<code>/var/run/utmp</code>	To find the recipient's <code>tty</code>

SEE ALSO

`mail(1)`, `mesg(1)`, `who(1)`, `write(1)`

BUGS

The version of `talk 1` released with BSD 4.3 uses a protocol that is incompatible with the protocol used in the version released with BSD 4.2.

HISTORY

The `talk` command appeared in BSD 4.2.

BSD 4.2, 22 April 1991

tcal

tcal—Runs the gcal program with the date of tomorrow's day

SYNOPSIS

```
tcal [ --help | --version ] | [ --shift=[+|-]number ][Argument... ]
```

DESCRIPTION

tcal is a program that runs gcal with a date set one day ahead (equivalent to the --shift=1 option). All given arguments are passed unmodified to the gcal program. If the gcal program shall be called with a date other than tomorrow's date, this desired date can be selected by using the --shift=[+|-]number option, in which [+|-]number is the number of days the desired date is distant from the actual date. The --shift option must be given before all other arguments, which are passed to the gcal program. An exit status of 0 means all processing is successfully done; any other value means an error has occurred.

OPTIONS

--help	Print a usage message listing all available options, then exit successfully.
--version	Print the version number, then exit successfully.
--shift=[+ -]number	Define the displacement in [+ -]number days the desired date is distant from the actual date.

ENVIRONMENT

GCALPROG	The GCALPROG environment variable contains the filename of the executable gcal program, which is used by tcal to call gcal. Takes precedence over the filename gcal, which is burned-in during the compilation step of tcal.

COPYRIGHT

Copyright© 1995, 1996 by Thomas Esken. This software doesn't claim completeness, correctness, or usability. On principle, I will not be liable for any damages or losses (implicit or explicit), which result from using or handling my software. If you use this software, you agree without any exception to this agreement, which binds you *LEGALLY*.

tcal is free software and distributed under the terms of the GNU General Public License; published by the Free Software Foundation; version 2 or (at your option) any later version.

Any suggestions, improvements, extensions, bug reports, donations, proposals for contract work, and so forth are welcome! If you like this tool, I'd appreciate a postcard from you!

Enjoy it =8^)

AUTHOR

Thomas Esken (esken@uni-muenster.de)
 m Hagenfeld 84
 D-48147 Muenster; Germany
 Phone : +49 251 232585

SEE ALSO

gcal(1)

16 July 1996

telnet

telnet—User interface to the Telnet protocol

SYNOPSIS

```
telnet [-d] [-a] [-n tracefile] [-e escapechar] [-l user] host [port]
```

DESCRIPTION

The `telnet` command is used to communicate with another host using the Telnet protocol. If `telnet` is invoked without the host argument, it enters command mode, indicated by its prompt `telnet>`. In this mode, it accepts and executes the commands listed below. If it is invoked with arguments, it performs an open command with those arguments.

OPTIONS

<code>-d</code>	Sets the initial value of the debug toggle to <code>True</code> .
<code>-a</code>	Attempt automatic login. Currently, this sends the username via the <code>USER</code> variable of the <code>ENVIRON</code> option if supported by the remote system. The name used is that of the current user as returned by <code>getlogin</code> 2 if it agrees with the current user ID; otherwise, it is the name associated with the user ID.
<code>-n tracefile</code>	Opens <code>tracefile</code> for recording trace information. See the <code>set tracefile</code> command in the “Commands” section.
<code>-l user</code>	When connecting to the remote system, if the remote system understands the <code>ENVIRON</code> option, then user will be sent to the remote system as the value for the variable <code>USER</code> . This option implies the <code>-a</code> option. This option may also be used with the <code>open</code> command.
<code>-e escape char</code>	Sets the initial <code>telnet</code> escape character to <code>escape char</code> . If <code>escape char</code> is omitted, then there will be no escape character.
<code>host</code>	Indicates the official name, an alias, or the Internet address of a remote host.
<code>port</code>	Indicates a port number (address of an application). If a number is not specified, the default <code>telnet</code> port is used.

Once a connection has been opened, `telnet` will attempt to enable the `TELNETLINEMODE` option. If this fails, then `telnet` will revert to one of two input modes—either character-at-a-time or old line-by-line, depending on what the remote system supports.

When `LINEMODE` is enabled, character processing is done on the local system, under the control of the remote system. When input editing or character echoing is to be disabled, the remote system will relay that information. The remote system will also relay changes to any special characters that happen on the remote system, so that they can take effect on the local system.

In character-at-a-time mode, most text typed is immediately sent to the remote host for processing.

In old line-by-line mode, all text is echoed locally, and (normally) only completed lines are sent to the remote host. The local echo character (initially `^E`) may be used to turn off and on the local echo. (This would mostly be used to enter passwords without the password being echoed.)

If the `LINEMODE` option is enabled, or if the `localchars` toggle is `True` (the default for old line-by-line), the user's `quit`, `intr`, and `flush` characters are trapped locally, and sent as Telnet protocol sequences to the remote side. If `LINEMODE` has ever been enabled, then the user's `susp` and `eof` are also sent as Telnet protocol sequences, and `quit` is sent as a `TELNET ABORT` instead of `BREAK`. There are options (see `toggle autoflush` and `toggle autosynch` in the following list) that cause this action to flush subsequent output terminal (until the remote host acknowledges the `telnet` sequence) and flush previous terminal input (in the case of `quit` and `intr`).

COMMANDS

While connected to a remote host, `telnet` command mode may be entered by typing the `telnet` escape character (initially `^]`). When in command mode, the normal terminal editing conventions are available.

The following `telnet` commands are available. Only enough of each command to uniquely identify it need be typed. (This is also true for arguments to the `mode`, `set`, `toggle`, `unset`, `slc`, `environ`, and `display` commands.)

<code>close</code>	Close a <code>telnet</code> session and return to command mode.
<code>display argument...</code>	Displays all, or some, of the <code>set</code> and <code>toggle</code> values.
<code>mode type</code>	<code>type</code> is one of several options, depending on the state of the <code>telnet</code> session. The remote host is asked for permission to go into the requested mode. If the remote host is capable of entering that mode, the requested mode will be entered. The <code>type</code> options are
<code>character</code>	Disable the <code>TELNET LINEMODE</code> option, or, if the remote side does not understand the <code>LINEMODE</code> option, then enter character at a time mode.
<code>line</code>	Enable the <code>TELNET LINEMODE</code> option, or, if the remote side does not understand the <code>LINEMODE</code> option, then attempt to enter old-line-by-line mode.
<code>isig -isig</code>	Attempt to enable (disable) the <code>TRAPSIG</code> mode of the <code>LINEMODE</code> option. This requires that the <code>LINEMODE</code> option be enabled.
<code>edit -edit</code>	Attempt to enable (disable) the <code>EDIT</code> mode of the <code>LINEMODE</code> option. This requires that the <code>LINEMODE</code> option be enabled.
<code>softtabs</code>	Attempt to enable (disable) the <code>SOFT_TAB</code> mode of the <code>LINEMODE</code> option. This requires that <code>-softtabs</code> the <code>LINEMODE</code> option be enabled.
<code>litecho -litecho</code>	Attempt to enable (disable) the <code>LIT_ECHO</code> mode of the <code>LINEMODE</code> option. This requires that the <code>LINEMODE</code> option be enabled.
<code>?</code>	Prints out help information for the <code>mode</code> command.
<code>open host user] [-port]</code>	Open a connection to the named host. If no port number is specified, <code>telnet</code> will attempt to <code>[-1]</code> contact a Telnet server at the default port. The host specification may be either a hostname (see <code>hosts(5)</code> for more information) or an Internet address specified in the dot notation (see <code>inet(3)</code> for more information). The <code>-1</code> option may be used to specify the username to be passed to the remote system via the <code>ENVIRON</code> option. When connecting to a nonstandard port, <code>telnet</code> omits any automatic initiation of <code>telnet</code> options. When the port number is preceded by a minus sign, the initial option negotiation is done. After establishing a connection, the file in the user's home directory is opened. Lines beginning with a <code>#</code> are comment lines. Blank lines are ignored. Lines that begin without whitespace are the start of a machine entry. The first thing on the line is the name of the machine that is being connected to. The rest of the line, and successive lines that begin with whitespace, are assumed to be <code>telnet</code> commands and are processed as if they had been typed in manually to the <code>telnet</code> command prompt.
<code>quit</code>	Close any open <code>telnet</code> session and exit <code>telnet</code> . An end-of-file (in command mode) will also close a session and exit.
<code>send arguments</code>	Sends one or more special character sequences to the remote host. The following are the arguments that may be specified (more than one argument may be specified at a time):
<code>abort</code>	Sends the <code>TELNET ABORT</code> (Abort Processes) sequence.
<code>ao</code>	Sends the <code>TELNET AO</code> (Abort Output) sequence, which should cause the remote system to flush all output from the remote system to the user's terminal.
<code>ayt</code>	Sends the <code>TELNET AYT</code> (Are You There) sequence, to which the remote system may or may not choose to respond.
<code>brk</code>	Sends the <code>TELNET BRK</code> (Break) sequence, which may have significance to the remote system.

<code>ec</code>	Sends the TELNET EC (Erase Character) sequence, which should cause the remote system to erase the last character entered.
<code>el</code>	Sends the TELNET EL (Erase Line) sequence, which should cause the remote system to erase the line currently being entered.
<code>eof</code>	Sends the TELNET EOF (End-of-File) sequence.
<code>eor</code>	Sends the TELNET EOR (End of Record) sequence.
<code>escape</code>	Sends the current <code>telnet</code> escape character (initially <code>^</code>).
<code>ga</code>	Sends the TELNET GA (Go Ahead) sequence, which likely has no significance to the remote system.
<code>getstatus</code>	If the remote side supports the TELNET STATUS command, <code>getstatus</code> will send the subnegotiation to request that the server send its current option status.
<code>ip</code>	Sends the TELNET IP (Interrupt Process) sequence, which should cause the remote system to abort the currently running process.
<code>nop</code>	Sends the TELNET NOP (no operation) sequence.
<code>susp</code>	Sends the TELNET SUSP (suspend process) sequence.
<code>synch</code>	Sends the TELNET SYNCH sequence. This sequence causes the remote system to discard all previously typed (but not yet read) input. This sequence is sent as TCP urgent data (and may not work if the remote system is a BSD 4.2 system—if it doesn't work, a lowercase <code>r</code> may be echoed on the terminal).
<code>?</code>	Prints out help information for the <code>send</code> command.
<code>set argument value,</code> <code>unset argument value</code>	The <code>set</code> command will set any one of a number of <code>telnet</code> variables to a specific value or to <code>True</code> . The special value <code>off</code> turns off the function associated with the variable; this is equivalent to using the <code>unset</code> command. The <code>unset</code> command will disable or set to <code>False</code> any of the specified functions. The values of variables may be interrogated with the <code>display</code> command. The variables that may be set or unset, but not toggled, are listed here. In addition, any of the variables for the <code>toggle</code> command may be explicitly set or unset using the <code>set</code> and <code>unset</code> commands.
<code>echo</code>	This is the value (initially <code>^E</code>) which, when in line-by-line mode, toggles between doing local echoing of entered characters (for normal processing), and suppressing echoing of entered characters (for entering, say, a password).
<code>eof</code>	If <code>telnet</code> is operating in <code>LINEMODE</code> or old line-by-line mode, entering this character as the first character on a line will cause this character to be sent to the remote system. The initial value of the <code>eof</code> character is taken to be the terminal's <code>eof</code> character.
<code>erase</code>	If <code>telnet</code> is in <code>localchars</code> mode (see <code>toggle localchars</code> , following), and if <code>telnet</code> is operating in character at a time mode, then when this character is typed, a TELNET EC sequence (see <code>send ec</code> , earlier in this man page) is sent to the remote system. The initial value for the <code>erase</code> character is taken to be the terminal's <code>erase</code> character.
<code>escape</code>	This is the <code>telnet</code> escape character (initially <code>^I</code>) which causes entry into <code>telnet</code> command mode (when connected to a remote system).
<code>flushoutput</code>	If <code>telnet</code> is in <code>localchars</code> mode (see <code>toggle localchars</code>) and the <code>flushoutput</code> character is typed, a TELNET AO sequence is sent to the remote host. The initial value for the flush character is taken to be the terminal's flush character.
<code>interrupt</code>	If <code>telnet</code> is in <code>localchars</code> mode (see <code>toggle localchars</code>) and the interrupt character is typed, a TELNET IuP sequence is sent to the remote host. The initial value for the interrupt character is taken to be the terminal's <code>intr</code> character.

	<code>kill</code>	If <code>telnet</code> is in <code>localchars</code> mode (see <code>toggle localchars</code>), and if <code>telnet</code> is operating in character at a time mode, then when this character is typed, a TELNET EL sequence is sent to the remote system. The initial value for the <code>kill</code> character is taken to be the terminal's <code>kill</code> character.
	<code>lnext</code>	If <code>telnet</code> is operating in <code>LINEMODE</code> or old line-by-line mode, then this character is taken to be the terminal's <code>lnext</code> character. The initial value for the <code>lnext</code> character is taken to be the terminal's <code>lnext</code> character.
	<code>quit</code>	If <code>telnet</code> is in <code>localchars</code> mode (see <code>toggle localchars</code>) and the <code>quit</code> character is typed, a TELNET BRK sequence is sent to the remote host. The initial value for the <code>quit</code> character is taken to be the terminal's <code>quit</code> character.
	<code>reprint</code>	If <code>telnet</code> is operating in <code>LINEMODE</code> or old line-by-line mode, then this character is taken to be the terminal's <code>reprint</code> character. The initial value for the <code>reprint</code> character is taken to be the terminal's <code>reprint</code> character.
	<code>start</code>	If the <code>TELNETTOGGLE-FLOW-CONTROL</code> option has been enabled, then this character is taken to be the terminal's <code>start</code> character. The initial value for the <code>start</code> character is taken to be the terminal's <code>start</code> character.
	<code>stop</code>	If the <code>TELNETTOGGLE-FLOW-CONTROL</code> option has been enabled, then this character is taken to be the terminal's <code>stop</code> character. The initial value for the <code>kill</code> character is taken to be the terminal's <code>stop</code> character.
	<code>susp</code>	If <code>telnet</code> is in <code>localchars</code> mode, or <code>LINEMODE</code> is enabled, and the <code>suspend</code> character is typed, a TELNET SUSP sequence is sent to the remote host. The initial value for the <code>suspend</code> character is taken to be the terminal's <code>suspend</code> character.
	<code>tracefile</code>	This is the file to which the output, caused by <code>netdata</code> or option tracing being <code>True</code> , will be written. If it is set to <code>-</code> , then tracing information will be written to standard output (the default).
	<code>worderase</code>	If <code>telnet</code> is operating in <code>LINEMODE</code> or old line-by-line mode, then this character is taken to be the terminal's <code>worderase</code> character. The initial value for the <code>worderase</code> character is taken to be the terminal's <code>worderase</code> character.
	<code>?</code>	Displays the <code>set</code> <code>unset</code> commands.
<code>slc state</code>		The <code>slc</code> command (Set Local Characters) is used to set or change the state of the special characters when the <code>TELNETLINEMODE</code> option has been enabled. Special characters are characters that get mapped to <code>telnet</code> command sequences (like <code>ip</code> or <code>quit</code>) or line-editing characters (like <code>erase</code> and <code>kill</code>). By default, the local special characters are exported. The variables are
	<code>export</code>	Switch to the local defaults for the special characters. The local default characters are those of the local terminal at the time <code>telnet</code> was started.
	<code>import</code>	Switch to the remote defaults for the special characters. The remote default characters are those of the remote system at the time when the <code>telnet</code> connection was established.
	<code>check</code>	Verify the current settings for the current special characters. The remote side is requested to send all the current special character settings, and if there are any discrepancies with the local side, the local side will switch to the remote value.
	<code>?</code>	Prints out help information for the <code>slc</code> command.

environ arguments... The `environ` command is used to manipulate the variables that may be sent through the TELNET `ENVIRON` option. The initial set of variables is taken from the users environment, with only the `DISPLAY` and `PRINTER` variables being exported by default. The `USER` variable is also exported if the `-a` or `-l` options are used.

Valid arguments for the `environ` command are

<code>define variable value</code>	Define the variable <code>variable</code> to have a value of <code>value</code> . Any variables defined by this command are automatically exported. The value may be enclosed in single or double quotes so that tabs and spaces may be included.
<code>undefine variable</code>	Remove <code>variable</code> from the list of environment variables.
<code>export variable</code>	Mark the variable <code>variable</code> to be exported to the remote side.
<code>unexport variable</code>	Mark the variable <code>variable</code> to not be exported unless explicitly asked for by the remote side.
<code>list</code>	List the current set of environment variables. Those marked with a <code>*</code> will be sent automatically; other variables will only be sent if explicitly requested.
<code>?</code>	Prints out help information for the <code>environ</code> command.

toggle arguments... Toggle (between `True` and `False`) various flags that control how `telnet` responds to events. These flags may be set explicitly to `True` or `False` using the `set` and `unset` commands listed earlier. More than one argument may be specified. The state of these flags may be interrogated with the `display` command. Valid arguments are

<code>autoflush</code>	If <code>autoflush</code> and <code>localchars</code> are both <code>True</code> , then when the <code>ao</code> or <code>quit</code> characters are recognized (and transformed into <code>telnet</code> sequences; see <code>set</code> for details), <code>telnet</code> refuses to display any data on the user's terminal until the remote system acknowledges (via a <code>TELNET TIMING MARK</code> option) that it has processed those <code>telnet</code> sequences. The initial value for this toggle is <code>True</code> if the terminal user had not done an <code>"stty noflsh"</code> ; otherwise, <code>False</code> . (See <code>stty(1)</code> for more details.)
<code>autosynch</code>	If <code>autosynch</code> and <code>localchars</code> are both <code>True</code> , then when either the <code>intr</code> or <code>quit</code> character is typed (see <code>set</code> for descriptions of the <code>intr</code> and <code>quit</code> characters), the resulting <code>telnet</code> sequence sent is followed by the <code>TELNET SYNCH</code> sequence. This procedure should cause the remote system to begin throwing away all previously typed input until both of the <code>telnet</code> sequences have been read and acted upon. The initial value of this toggle is <code>False</code> .
<code>binary</code>	Enable or disable the <code>TELNET BINARY</code> option on both input and output.
<code>inbinary</code>	Enable or disable the <code>TELNET BINARY</code> option on input.
<code>outbinary</code>	Enable or disable the <code>TELNET BINARY</code> option on output.
<code>crlf</code>	If this is <code>True</code> , then carriage returns will be sent as <code><CR><LF></code> . If this is <code>False</code> , then carriage returns will be sent as <code><CR><NUL></code> . The initial value for this toggle is <code>False</code> .
<code>crmod</code>	Toggle carriage return mode. When this mode is enabled, most carriage return characters received from the remote host will be mapped into a carriage return followed by a line feed. This mode does not affect those characters typed by the user, only those received from the remote host. This mode is not very useful unless the remote host only sends carriage return, but never line feed. The initial value for this toggle is <code>False</code> .

	<code>debug</code>	Toggles socket level debugging (useful only to the super user). The initial value for this toggle is <code>False</code> .
	<code>localchars</code>	If this is <code>True</code> , then the <code>flush</code> , <code>interrupt</code> , <code>quit</code> , <code>erase</code> , and <code>kill</code> characters (see <code>set</code>) are recognized locally, and transformed into (hopefully) appropriate <code>telnet</code> control sequences (respectively <code>ao</code> , <code>ip</code> , <code>brk</code> , <code>ec</code> , and <code>el</code> ; see <code>send</code>). The initial value for this toggle is <code>True</code> in old line-by-line mode, and <code>False</code> in character at a time mode. When the <code>LINEMODE</code> option is enabled, the value of <code>localchars</code> is ignored, and assumed to always be <code>True</code> . If <code>LINEMODE</code> has ever been enabled, then <code>quit</code> is sent as <code>abort</code> , and <code>eof</code> and <code>suspend</code> are sent as <code>eof</code> and <code>susp</code> ; see <code>send</code> .
	<code>netdata</code>	Toggles the display of all network data (in hexadecimal format). The initial value for this toggle is <code>False</code> .
	<code>options</code>	Toggles the display of some internal <code>telnet</code> protocol processing (having to do with <code>telnet</code> options). The initial value for this toggle is <code>False</code> .
	<code>prettydump</code>	When the <code>netdata</code> toggle is enabled, if <code>prettydump</code> is enabled, the output from the <code>netdata</code> command will be formatted in a more user-readable format. Spaces are put between each character in the output, and the beginning of any <code>telnet</code> escape sequence is preceded by an <code>*</code> to aid in locating them.
	<code>?</code>	Displays the legal toggle commands.
<code>z</code>		Suspend <code>telnet</code> . This command only works when the user is using the <code>csh(1)</code> .
<code>! command</code>		Execute a single command in a subshell on the local system. If <code>command</code> is omitted, then an interactive subshell is invoked.
<code>status</code>		Show the current status of <code>telnet</code> . This includes the peer one is connected to, as well as the current mode.
<code>? command</code>		Get help. With no arguments, <code>telnet</code> prints a help summary. If a command is specified, <code>telnet</code> will print the help information for just that command.

ENVIRONMENT

`telnet` uses at least the `HOME`, `SHELL`, `DISPLAY`, and `TERM` environment variables. Other environment variables may be propagated to the other side via the `TELNET ENVIRON` option.

FILES

`~/.telnetrc` User customized `telnet` startup values

HISTORY

The `telnet` command appeared in BSD 4.2.

NOTES

On some remote systems, `echo` has to be turned off manually when in old line-by-line mode.

In old line-by-line mode or `LINEMODE`, the terminal's `eof` character is only recognized (and sent to the remote system) when it is the first character on a line.

tfmtodit

tfmtodit—Create font files for use with groff -Tdvi

SYNOPSIS

```
tfmtodit [ -sv ][-ggf file ][-kskewchar ] tfm file map file font
```

DESCRIPTION

tfmtodit creates a font file for use with groff -Tdvi. `tfm_file` is the name of the font metric file for the font. `map_file` is a file giving the groff names for characters in the font; this file should consist of a sequence of lines of the form:

```
n c1c2 ...
```

where `n` is a decimal integer giving the position of the character in the font, and `c1`, `c2`, ... are the groff names of the character. If a character has no groff names but exists in the `tfm` file, then it will be put in the groff font file as an unnamed character. `font` is the name of the groff font file. The groff font file is written to `font`.

The `-s` option should be given if the font is special (a font is special if `troff` should search it whenever a character is not found in the current font.) If the font is special, it should be listed in the `fonts` command in the `DESC` file; if it is not special, there is no need to list it because `troff` can automatically mount it when it's first used.

To do a good job of math typesetting, groff requires font metric information not present in the `tfm` file. The reason for this is that has separate math italic fonts whereas groff uses normal italic fonts for math. The additional information required by groff is given by the two arguments to the `math_fit` macro in the Metafont programs for the Computer Modern fonts. In a text font (a font for which `math_fitting` is `False`), Metafont normally ignores these two arguments. Metafont can be made to put this information in the `gf` file by loading the following definition after `cm.base` when creating `cm.base`:

```
def ignore_math_fit(expr left_adjustment,right_adjustment) =
special "adjustment";
numspecial left_adjustment*16/designsize;
numspecial right_adjustment*16/designsize;
enddef;
```

The `gf` file created using this modified `cm.base` should be specified with the `-g` option. The `-g` option should not be given for a font for which `math_fitting` is `true`.

OPTIONS

- `-v` Print the version number.
- `-s` The font is special. The effect of this option is to add the `special` command to the font file.
- `-kn` The skewchar of this font is at position `n`. `n` should be an integer; it may be given in decimal, or with a leading `0` in octal, or with a leading `0x` in hexadecimal. The effect of this option is to ignore any kerns whose second component is the specified character.
- `-ggf_file` `gf_file` is a `gf` file produced by Metafont containing special and `num special` commands giving additional font metric information.

FILES

- `/usr/lib/groff/font/devdvi/DESC` Device description file.
- `/usr/lib/groff/font/devdvi/F` Font description file for font `F`.

SEE ALSO

groff(1), grodvi(1), groff_font(5)

tftp

tftp—Trivial file transfer program

SYNOPSIS

tftp [host]

DESCRIPTION

tftp is the user interface to the Internet TFTP (Trivial File Transfer Protocol), which allows users to transfer files to and from a remote machine. The remote host may be specified on the command line, in which case tftp uses host as the default host for future transfers. (See the connect command in the following section.)

COMMANDS

Once tftp is running, it issues the prompt:

tftp>

and recognizes the following commands:

? command-name ...	Print help information.
ascii	Shorthand for “mode ascii”
binary	Shorthand for “mode binary”
connect host-name port	Set the host (and optionally port) for transfers. Note that the TFTP protocol, unlike the FTP protocol, does not maintain connections between transfers; thus, the connect command does not actually create a connection, but merely remembers what host is to be used for transfers. You do not have to use the connect command; the remote host can be specified as part of the get or put commands.
get filename, get remotename localname, get file1 file2 ... fileN	Get a file or set of files from the specified sources. Source can be in one of two forms: a filename on the remote host, if the host has already been specified; or a string of the form hosts:filename to specify both a host and filename at the same time. If the latter form is used, the last hostname specified becomes the default for future transfers.
mode transfer-mode	Set the mode for transfers; transfer-mode may be ascii or binary. The default is ascii.
put file put localfile remotefile put file1 file2 ... fileN remote-directory	Put a file or set of files to the specified remote file or directory. The destination can be in one of two forms: a filename on the remote host, if the host has already been specified; or a string of the form hosts:filename to specify both a host and filename at the same time. If the latterform is used, the hostname specified becomes the default for future transfers. If the remote-directory form is used, the remote host is assumed to be a UNIX machine.
quit	Exit tftp . An end-of-file also exits.
rexmt retransmission-timeout	Set the per-packet retransmission time-out, in seconds.
status	Show current status.
timeout total-transmission-timeout	Set the total transmission time-out, in seconds.
trace	Toggle packet tracing.
verbose	Toggle verbose mode.

BUGS

Because there is no user-login or validation within the TFTP protocol, the remote site will probably have some sort of file-access restrictions in place. The exact methods are specific to each site and therefore difficult to document here.

HISTORY

The `tftp` command appeared in BSD 4.3.

BSD 4.3, 22 April 1991

tgatoppm

`tgatoppm`—Convert TrueVision Targa file into a portable pixmap

SYNOPSIS

```
tgatoppm [-debug] [tgafile]
```

DESCRIPTION

Reads a TrueVision Targa file as input. Produces a portable pixmap as output.

OPTIONS

`-debug` Causes the header information to be dumped to `stderr`

All flags can be abbreviated to their shortest unique prefix.

BUGS

Should really be in `pnm`, not `ppm`.

SEE ALSO

`ppmtotga(1)`, `ppm(5)`

AUTHOR

Partially based on `tga2rast`, version 1.0, by Ian J. MacPhedran

Copyright© 1989 by Jef Poskanzer.

26 August 1989

tifftopnm

`tifftopnm`—Convert a TIFF file into a portable anymap

SYNOPSIS

```
tifftopnm [-headerdump] tifffile
```

DESCRIPTION

`tifftopnm` reads a TIFF file as input and produces a portable anymap as output. The type of the output file depends on the input file; if it's black and white, a `pbm` file is written; if it's grayscale, a `pgm` file; otherwise, a `ppm` file. The program tells you which type it is writing.

OPTIONS

`-headerdump` Dump TIFF file information to `stderr`. This information may be useful in debugging TIFF file conversion problems.

All flags can be abbreviated to their shortest unique prefix.

SEE ALSO

`pnmtotiff(1)`, `pnm(5)`

BUGS

This program is not self-contained. To use it you must fetch the TIFF Software package listed in the `OTHER.SYSTEMS` file and configure `pbmplus` to use `libtiff`. See the `pbmplus` Makefile for details on this configuration.

AUTHOR

Derived by Jef Poskanzer from `tif2ras.c`, which is copyright© 1990 by Sun Microsystems, Inc. Author Patrick J. Naughton (`naughton@wind.sun.com`).

13 January 1991

tin, rtin, cdtin, tind

`tin`, `rtin`, `cdtin`, `tind`—A Netnews reader

SYNOPSIS

`tin/rtin/cdtin/tind [ options ] [newsgroups ]`

DESCRIPTION

`tin` is a full-screen easy-to-use Netnews reader. It can read news locally (`/usr/spool/news`) or remotely (`rtin` or `tin -r` option) via an NNTP (Network News Transport Protocol) server. `cdtin` can read news locally and news archived on CD-ROM. It will automatically utilize `nov` (news overview)-style index files if available locally or via the `nnntp xover` command.

`tin` has five separate levels of operation: group selection level, `spooldir` selection level, group level, thread level and article level. Use the `h` (`help`) command to view a list of the commands available at a particular level.

On startup, `tin` will show a list of the newsgroups found in `$HOME/.newsrc`. An arrow `->` or highlighted bar will point to the first newsgroup. Move to a group by using the terminal arrow keys (terminal-dependent) or `j` and `k`. Use `PgUp/PgDn` (terminal-dependent) or `Ctrl-U` and `Ctrl-D` to page up/down. Enter a newsgroup by pressing `Return`.

The `Tab` key advances to the next newsgroup with unread articles and enters it.

OPTIONS

- `-c` Create/update index files for every group in `$HOME/.newsrc` or file specified by `-f` option and mark all articles as read.
- `-f file` Use the specified file of subscribed to newsgroups in place of `$HOME/.newsrc`.
- `-h` Help listing all command-line options.
- `-H` Brief introduction to `tin` that is also shown the first time it is started.
- `-I dir` Directory in which to store newsgroup index files. Default is `$HOME/.tin/.index`.
- `-m dir` Mailbox directory to use. Default is `$HOME/Mail`.
- `-M user` Mail unread articles to specified user for later reading. For more information read the “Automatic Mailing and Saving New News” section later in this manual page.
- `-n` Only load groups from the active file that are also subscribed to in the users `.newsrc`. This allows a noticeable speedup when connecting via a slow line.
- `-p program` Print program with options.
- `-q` Quick start without checking for new newsgroups.
- `-P` Purge group index files of articles that no longer exist. Care should be taken when using this command as it starts each and every article in each group that is accessed. On a low-speed connection, this can have an undesirable effect and it also knocks the hell out of your file system.

- r Read news remotely from the default NNTP server specified in the environment variable NNTPSERVER or contained in the file `/etc/nntpserver`.
- R Read news saved by -S option (not yet implemented).
- s dir Save articles to directory. Default is `$HOME/News`.
- S Save unread articles for later reading by -R option. For more information, see “Automatic Mailing and Saving New News.”
- u Create/update index files for every group in `$HOME/.newsrc` or file specified by -f option. This option is disabled if tin retrieves its index files via an NNTP server.
- U Start tin in the background to update index files while reading news in the foreground. This option is disabled if tin retrieves its index files via an NNTP server.
- v Verbose mode for -c, -M, -S, -u, and -Z options.
- w Quick mode to post an article and then exit.
- z Only start tin if there is any new/unread news. If there is news, tin will position cursor at first group with unread news. Useful for putting in login file.
- Z Check if there is any new/unread news and exit with appropriate status. If -v option is specified, the number of unread articles in each group is printed. An exit code 0 indicates no news, 1 that an error occurred, and 2 that new/unread news exists. Useful for writing scripts.

tin can also dynamically change its options by the M menu command. Any changes are written to `$HOME/.tin/tinrc`.

The index daemon version, tind, only supports the -f, -h, -I, and -v options.

INDEX FILES

In order to keep track of threads, tin maintains an index for each newsgroup. There are a number of methods in which index files can be created and updated.

The simplest method is that each user creates/updates his or her own index files that are stored in `$HOME/.tin/.index`. This has the advantage that any user can compile and install tin, but the disadvantage is that each user is going to be creating duplicate files and using precious disk space. A good way to keep index files updated is by doing a tin -u that will update index files in the background while you are reading news in the foreground. You can also update index files via the system batcher cron with the -u option: `30 6 ***/usr/local/bin/tin -u`.

A slightly better method is to set tin setuid news and have all index files created and updated in the news spool directory (that is, `/usr/spool/news/.index`). This has the advantage that there will only be one copy of the index files on each machine on your network, but the disadvantage is that you will have tin running setuid news.

A better method is to install the tind index file updating daemon and have it create and update index files for all groups in your active file at regular intervals in the news spool directory (`/usr/spool/news/.index`). This has the advantage that there will only be one copy of the index files on each machine on your network, and tin must not be setuid news, but the disadvantage is that you will have to have news permissions to install tind and root permissions to install an entry in the cron batcher system to have tind regularly update index files.

The best method is to install the tind index file updating daemon on your NNTP server and have it create and update index files for all groups in your active file at regular intervals in the news spool directory (`/usr/spool/news/.index`). This has the advantage that there will only be one copy of the index files on the NNTP server for the whole of your network, but the disadvantage is that you will have to install my NNTP server patches to allow tin to retrieve index file from your NNTP server and you must install an entry in the cron batcher system to have tind regularly update index files. (This is the method we use on our network of 40 to 50 machines and we have not had any problems.)

Entering a group the first time tends to be slow because the index file must be built from scratch unless the tind update daemon is being used. To alleviate the slowness, start tin to create all index files for the groups you subscribe to with tin -u -v and go for a coffee. Subsequent readings of a group will cause incremental updating of the index file.

If reading news remotely and locally updating index files operation will be somewhat slower because the articles must be retrieved from the NNTP server.

NEWS ADMINISTRATION

Maintaining Netnews on large networks of machines can be a pretty time-consuming job, as I discovered when I was given the job of maintaining our news system and news users.

`tin` is a News User Agent and so most of the users were always asking questions or doing things that could be frowned upon by their departments. To relieve news administrators (and especially me) of this, features have been added to make life easier for them.

When a user starts `tin`, it is possible to inform them of any important changes or information concerning the news system by displaying a message of the day (`motd`) file. The `motd` file should be created in your news lib directory (`/usr/lib/news/motd`) and should have file permissions set to `0644`. The `motd` file will only be displayed if its contents is newer than the last time the user started `tin`. If reading news via NNTP, my `XMOTD` patch will have to have been applied to your NNTP server.

A user starting `tin` for the first time can be automatically subscribed to a list of newsgroups that are deemed appropriate by the news administrator. At our site the subscriptions file has 125 groups (our active file contains more than 400 groups with many only being marginally interesting to most people). The subscriptions file should be created in your news lib directory (`/usr/lib/news/subscriptions`) and should have file permissions set to `0644`. If reading news via NNTP, my `LIST SUBSCRIPTIONS` patch will have to have been applied to your NNTP server.

If my NNTP `XUSER` patch has been applied to your NNTP server, you will be able to log the username and machine to your NNTP logfile for usage statistics.

SCREEN FORMAT

`tin` has five separate levels of operation: group selection level, `spooldir` selection level, group level, thread level, and article level.

At the group selection level, the title displays the number of subscribed groups. The newsgroups are displayed on the left of the screen with the number of unread articles displayed on the same line in the middle of the screen, like this:

```
<Selection Num><Newsgroup><Num of unread articles>
i.e.,
 1  alt.sources                10
 2  comp.sources.misc          3
 3  news.software.readers      12
```

At the group level, the title contains the name of the group, the number of conversation threads, and total number of articles, for example, `alt.sources (7 23)`. If the group has been set up not to thread articles (for example, `alt.sources` is in `$(HOME)/.tin/unthread`), the title will be `alt.sources (U 23)`. There are two possible display formats:

```
<Selection Num><Unread><Responses><Subject><Author>
e.g.,
 1  +   3   Bnews sources?                iain@an1433.uucp
 2    1   This question has                ether@net
```

or

```
<Selection Num><Unread><Responses><Subject (longer)>
e.g.,
 1  +   3   Bnews sources?
 2    1   This question has a longer subject line
```

At the article level, the page header has the following format:

```
<Date posted><Newsgroup>
<Thread 1 of n>
<Article Num><Subject><Num of responses in thread>
```

```

<Author><Organization>
<Article body>
i.e.,
24 Jul 15:20:03 GMT      alt.sources      Thread 1 of 2
Article 452              Bnews sources?   3 responses
iain@anl433.uucp        Organization name

```

COMMON MOVING KEYS

The following table shows the common keys/commands for moving at all five levels within tin:

Beginning of list/article	Home 1 (^R or g at article level)
End of list/article	End \$ (also G at article level)
Page up	PgUp ^U or ^B or b
Page down	PgDn ^D or ^F or <SPACE>
Line up	Up arrow k (not at article level)
Line down	Down arrow j (not at article level)

COMMON EDITING COMMANDS

An emacs-style editing package allows the easy editing of input strings. A history list allows the easy reuse of previously entered strings. The following commands are available when editing a string:

^A, ^E	Move to beginning or end of line, respectively.
^F, ^B	Nondestructive move forward or back one location, respectively.
^D	Delete the character currently under the cursor, or send EOF if no characters are in the buffer.
^H, <DEL>	Delete character left of the cursor.
^K	Delete from cursor to end of line.
^P, ^N	Move through history, previous and next, respectively.
^L, ^R	Redraw the current line.
<CR>	Places line on history list if nonblank, appends newline, and returns to the caller.
<ESC>	Aborts the present editing operation.

NEWSGROUP SELECTION COMMANDS

4	Select group 4.
^K	Delete current group from \$HOME/.newsrc file.
^L	Redraw page.
^R	Reset \$HOME/.newsrc file.
<CR>	Read current group.
<TAB>	View next group with unread news. Will wrap around to the beginning of the group selection list looking for unread groups.
B	Mail a bug report or comment to the author. This is the best way to get bugs fixed and features added/changed.
c	Mark current group as all read with confirmation and go to next group in group selection list.
C	Mark current group as all read and go to next unread group in group selection list.
d	Toggle display to show just the group name or the group name and the group's description.
g	Choose a new group by name. The position of the group within the group list will also be asked for. When 1 is entered, the new group will be the first group in the displayed list; when 8 is entered, the group will be the eighth group in the list; and so on. When \$ is entered, the group will be the last group displayed.

h	Help screen of newsgroup selection commands.
H	Toggle the display of help mini-menu at the bottom of the screen.
I	Toggle inverse video.
l	List and allow selection of the available spool directories. This feature requires a special library to be linked with <code>tin</code> to create <code>cdtin</code> , which can then read news from an active news feed and also from multiple CD-ROMs.
m	Move the current group within the group selection list. When 1 is entered, the group will become the first displayed group in the list; when 8 is entered, the eighth group in the list; and so on. When \$ is entered, the group will be the last group displayed.
M	User-configurable Options menu (for more information, see the “Global Options Menu” section later in this manual page).
q	Quit <code>tin</code> .
Q	Quit <code>tin</code> .
r	Toggle display of all subscribed-to groups and just the subscribed-to groups containing unread articles. Command has no effect if groups were read from the command line when <code>tin</code> was started.
s	Subscribe to current group.
S	Subscribe to groups matching user-specified pattern.
u	Unsubscribe to current group.
U	Unsubscribe to groups matching user-specified pattern.
v	Print <code>tin</code> version information.
w	Post an article to current group.
W	List articles posted by user. The date posted, the newsgroup, and the subject are listed.
y	The first time this command is called, it will yank in all groups from <code>\$LIB-DIR/active</code> that are not in <code>\$HOME/.newsrc</code> . After any groups have been subscribed/unsubscribed to, this command, if pressed again, will reread <code>\$HOME/.newsrc</code> and display only the subscribed groups.
Y	Reread the active file to see if any new news has arrived since starting <code>tin</code> .
z	Mark all articles in the current group as unread.
Z	Undelete previously deleted group by ^K command from <code>\$HOME/.newsrc</code> .
/	Group forward search.
?	Group backward search.

SPOOL DIRECTORY SELECTION COMMANDS

4	Select spool directory 4.
^L	Redraw page.
<CR>	Read news from selected spool directory.
B	Mail a bug report or comment to the author. This is the best way to get bugs fixed and features added/changed.
h	Help screen of spool directory selection commands.
H	Toggle the display of help mini-menu at the bottom of the screen.
I	Toggle inverse video.
q	Return to previous level.
Q	Quit <code>tin</code> .
v	Print <code>tin</code> version information.

GROUP INDEX COMMANDS

4	Select article 4.
^K	Kill current article (for more information, see the “Automatic Kill and Selection” section later in this manual page).
^L	Redraw page.
<CR>	Read current article.
<TAB>	View next unread article or group.
a	Author forward search.
A	Author backward search.
c	Mark all articles as read with confirmation.
C	Mark all articles as read and go to next group with unread news.
d	Toggle display to show just the subject or the subject and author.
g	Choose a new group by name.
h	Help screen of group index commands.
H	Toggle the display of help mini-menu at the bottom of the screen.
I	Toggle inverse video.
K	Mark article/thread as read and advance to next unread article/thread.
l	List the author of each response in current thread and enter thread selection level.
m	Mail current article/thread/auto-selected (hot) articles/articles matching pattern/tagged articles to someone.
M	User-configurable Options menu (for more information see “Global Options Menu” section).
n	Go to next group.
N	Go to next unread article.
o	Output current article/thread/autoselected (hot) articles/articles matching pattern/tagged articles to printer.
p	Go to previous group.
P	Go to previous unread article.
q	Return to previous level.
Q	Quit tin.
s	Save current article/thread/autoselected (hot) articles/articles matching pattern/tagged articles to file/files/mailbox. To save to a mailbox, enter = or =mailbox when asked for filename to save to. To save in <newsgroup name>/<filename> format, enter +filename. Environment variables are allowed within a filename (for example, \$SOURCES/dir/filename).
t	Tag current article/thread for mailing (m)/piping (!)/printing (o)/saving (s)/crossposting (x).
u	Toggle display to show all articles as unthreaded or threaded.
U	Untag all articles that were tagged.
v	Print tin version information.
w	Post an article to current group.
W	List articles posted by user. The date posted, the newsgroup, and the subject are listed.
x	Crosspost already posted current article/thread/autoselected (hot) articles/articles matching pattern/tagged articles to another newsgroup(s). Useful for reposting from global to local newsgroups.
X	Mark all unread articles that have not been selected as read, redo screen to reflect changes, and put index at the first thread to begin reading. Pressing x again will toggle back to the way it was before. See ~ command for clearing the toggle effect.
z	Mark current article as unread.
Z	Mark current thread as unread.

/	Search forward for specified subject.
?	Search backward for specified subject.
-	Show last message.
	Pipe current article/thread/autoselected (hot) articles/articles matching pattern/tagged articles into command.
*	Select current thread for later processing.
*	Toggle selection of current thread. If at least one unread art in thread (but not all unread arts) is selected, then all unread arts become selected.
@	Reverse all selections on all articles.
~	Undo all selections on all articles. It clears the toggle effect of x command. Thus, after first doing an x, you can then do ~ to reset articles. Thus, you can iteratively whittle down uninteresting threads.
+	Perform autoselection on current group.
;	For each thread in current group, if it at least one unread art is selected, all unread arts become selected. This is useful for autoselection on author when the reader wants to see the entire thread.
=	Prompts for a pattern with which to match on. All threads whose subjects match the pattern will be selected. A pattern of * will match all subjects. Entering just <CR> will cause the previous pattern to be used.

THREAD LISTING COMMANDS

4	Select article 4 within thread.
^L	Redraw page.
<CR>	Read current article within thread.
<TAB>	View next unread article within thread.
B	Mail a bug report or comment to the author. This is the best way of getting bugs fixed and features added/changed.
c	Mark thread as read after confirmation and return to previous level.
d	Toggle display to show just the subject or the subject and author.
h	Help screen of thread listing commands.
H	Toggle the display of help mini-menu at the bottom of the screen.
I	Toggle inverse video.
K	Mark thread as read and return to previous level.
q	Return to previous level.
Q	Quit tin.
r	Toggle display to show all articles or only unread articles.
B	Mail a bug report or comment to the author. This is the best way of getting bugs fixed and features added/changed.
t	Tag current article for mailing (m)/piping (!)/printing (o)/saving (s)/crossposting (x).
T	Return to group index level.
v	Print tin version information.
z	Mark current article in thread as unread.
Z	Mark all articles in thread as unread.

ARTICLE VIEWER COMMANDS

0	Read the base article in this thread.
4	Read response 4 in this thread.
^H	Show all of the article's mail header.

^K	Kill current article (for more information, see the “Automatic Kill and Selection” section)
^L	Redraw page.
<CR>	Go to next base article.
<TAB>	Go to next unread article.
a	Author forward search.
A	Author backward search.
c	Mark all articles as read with confirmation and return to group selection level.
C	Mark current group as all read and go to next unread group in group selection list.
d	Toggle rot-13 decoding for this article.
D	Delete current article. It must have been posted by the same user. The cancel message can be seen in the newsgroup control.
f	Post a follow-up to the current article with a copy of the article included.
F	Post a follow-up to the current article.
h	Help screen of article page commands.
H	Toggle the display of help mini-menu at the bottom of the screen.
I	Toggle inverse video.
k	Mark article as read and advance to next unread article.
K	Mark thread as read and advance to next unread thread.
m	Mail current article/thread/autoselected (hot) articles/articles matching pattern/tagged articles to someone.
M	User-configurable Options menu (for more information, see the “Global Options Menu” section later in this manual page).
n	Go to the next article.
N	Go to the next unread article.
o	Output current article/thread/autoselected (hot) articles/articles matching pattern/tagged articles to printer.
o	Output article/thread/tagged articles to printer.
p	Go to the previous article.
P	Go to the previous unread article.
q	Return to previous level.
Q	Quit tin.
r	Reply through mail to the author of the current article with a copy of the article included.
R	Reply through mail to the author of the current article.
s	Save current article/thread/autoselected (hot) articles/articles matching pattern/tagged articles to file/files/mailbox. To save to a mailbox enter = or =mailbox when asked for filename to save to. To save in <newsgroup name>/<filename> format, enter +filename. Environment variables are allowed within a filename (such as \$SOURCES/dir/filename).
t	Return to group selection level.
T	Tag current article for mailing (m)/piping (;)/printing (o)/saving (s)/crossposting (x).
v	Print tin version information.
w	Post an article to current group.
W	List articles posted by user. The date posted, the newsgroup and the subject are listed.
x	Crosspost already posted current article/thread/autoselected (hot) articles/articles matching pattern/tagged articles to another newsgroup(s). Useful for reposting from global to local newsgroups.
z	Mark article as unread.
/	Article forward search.
?	Article backward search

	Pipe current article/thread/autoselected (hot) articles/articles matching pattern/tagged articles into command.
<	Go to the first article in the current thread.
>	Go to the last article in the current thread.
*	Select current thread for later processing.
*	Toggle selection of current article.
@	Reverse article selections.
-	Undo all selections on current thread.

GLOBAL OPTIONS MENU

This menu is accessed by pressing **M** at all levels. It allows the user to customize the behavior of **tin**. The options are saved to the file `$HOME/.tin/tinrc`. Use `<SPACE>` to toggle the required option and `<CR>` to set.

Auto save	Automatically save articles/threads by “Archive-name:” line in article header and post process them if process type is not set to None .
Editor offset	Set ON if the editor used for posting, follow-ups and bug reports has the capability of starting and positioning the cursor at a specified line within a file.
Mark saved read	Allows saved articles/threads to be automatically marked as read.
Confirm Command	Allows certain commands (such as c catchup) that require user confirmation to be executed immediately if set OFF .
Draw arrow	Allows groups/articles to be selected by an arrow <code>-></code> if set ON or by a highlighted bar if set OFF .
Print header	This allows the complete mail header or only the “Subject:” and “From:” fields to be output when printing articles.
Go to 1st unread	This allows the cursor to be placed at the first/last unread article upon entering a newsgroup with unread news.
Scroll full page	If set ON , scrolling of groups/articles will be a full page at a time; otherwise, half a page at a time.
Catch up on quit	If set ON , the user is asked when quitting if all groups read during the current session should be marked read.
Thread articles	If set ON , articles will be threaded in all groups (default); otherwise, articles will be shown unthreaded. Threading or unthreading is possible on a per-group basis by setting the group attribute variable <code>thread_arts</code> to ON/OFF in the file <code>\$HOME/.tin/attributes</code> .
Show only unread	If set ON , show only new/unread articles; otherwise, show all articles.
Show description	If set ON , show a short descriptive text for each displayed newsgroup. The text used is taken from the <code>\$LIBDIR/newsgroups</code> file.
Show Author	If set None , only the “Subject:” line will be displayed. If set Addr , “Subject:” line and the address part of the “From:” line are displayed. If set Name , “Subject:” line and the author’s full name part of the “From:” line are displayed. If set Both , “Subject:” line and all of the “From:” line are displayed.
Process type	This specifies the default type of post processing to perform on saved articles. The following types of processing are allowed: ■ None ■ Unpacking of multipart shell archives ■ Unpacking of multipart uuencoded files ■ Unpacking of multipart uuencoded files, which produce a <code>*.zoo</code> archive whose contents are listed ■ Unpacking of multipart uuencoded files, which produce a <code>*.zoo</code> archive whose contents are extracted ■ Unpacking of multipart uuencoded files, which produce a <code>*.zip</code> archive whose contents are listed

	■ Unpacking of multipart uuencoded files, which produce a *.zip archive whose contents are extracted ■ Unpacking of multipart uuencoded files, which produce an *.lha archive whose contents are listed (AmigaDOS version only) ■ Unpacking of multipart uuencoded files, which produce an *.lha archive whose contents is extracted (AmigaDOS version only)
Sort articles by	This specifies how articles should be sorted. The following sort types are allowed: ■ Don't sort articles (default). ■ Sort articles by "Subject:" field (ascending and descending). ■ Sort articles by "From:" field (ascending and descending). ■ Sort articles by "Date:" field (ascending and descending).
Save directory	The directory where articles/threads are to be saved. Default is \$HOME/News.
Mail directory	The directory where articles/threads are to be saved in mailbox format. This feature is mainly for use with the elm mail program. It allows the user to save articles, threads, or groups simply by giving = as the filename to save to.
Printer	The printer program with options that is to be used to print articles. Default is lpr for BSD machines and lp for SysV machines.

tinrc CONFIGURABLE VARIABLES

The following variables are user-configurable by editing \$HOME/.tin/tinrc directly. It is hoped to eventually provide a menu to allow the setting of the most common variables.

batch_save	If set ON, articles/threads will be saved in batch mode when save -S or mail -M is specified on the command line. Default is OFF.
beginner_level	If set ON, a mini-menu of the most useful commands will be displayed at the bottom of the screen for each level. Default is ON.
display_reading_prompt	The prompt Reading... will be displayed when reading an article from an NNTP server to provide feedback to the user. Default is ON.
force_screen_redraw	Specifies whether a screen redraw should always be done after certain external commands. Default is OFF.
groupname_max_length	Maximum length of the names of newsgroups to be displayed so that more of the newsgroup description can be displayed. Default is 132.
default_sigfile	The path that specifies the signature file to use when posting, following up to, or replying to an article. If the path is a directory, then the signature will be randomly generated from files that are in the specified directory. Default is \$HOME/.Sig.
editor_format	The format string used to create the editor start command with parameters. Default is %E +%N %F (for example, /bin/vi +7 .article).
hot_art_mark	The character used to show that an article/thread is autoselected (hot). Default is *.
quote_chars	The character used in quoting included text to article follow-ups and mail replies. The ' ' character represents a blank character and is replaced with ' ' when read. Default is ': '.
reread_active_file_secs	The news active file is reread at regular intervals to show if any new news has arrived. Default is 300 seconds.
return_art_mark	The character used to show that an article will return. Default is -.
save_to_mmdf_mailbox	Allows articles to be saved to an mmdf-style mailbox instead of mbox format. Default is OFF unless reading news on SCO UNIX, which uses MMDF by default.
show_last_line_prev_page	The last line of the previous page will be displayed as the first line of next page. Default is OFF.

<code>slow_speed_terminal</code>	Strips the blanks from the end of each line, thereby speeding up the display when reading on a slow terminal or via modem. Default is <code>OFF</code> .
<code>tab_after_X_selection</code>	If enabled, will automatically go to the first unread article after having selected all hot articles and threads with the <code>X</code> command at group index level. Default is <code>OFF</code> .
<code>tab_goto_next_unread</code>	If enabled, pressing <code>Tab</code> at the article viewer level will go to the next unread article immediately instead of first paging through the current one. Default is <code>ON</code> .
<code>unread_art_mark</code>	The character used to show that an article has not been read. Default is <code>+</code> .
<code>use_builtin_inews</code>	Allows the built-in NNTP inews to be enabled/disabled. Default is <code>ON</code> (enabled).
<code>use_keypad</code>	Allows the scroll keys on the keypad to be enabled/disabled on supported terminals. Default is <code>OFF</code> .

GROUP ATTRIBUTES

`tin` allows certain attributes to be set on a per-group basis. These group attributes are read from the file `$HOME/.tin/attributes`. A later version will provide a menu interface to set all the attributes. At present, you will have to edit the file with your editor `:-)`. The following group attributes are available:

```
newsgroup=alt.sources
maildir=/usr/iain/Mail/sources
savedir=/usr/iain/News/alt.sources
sigfile=/usr/iain/.funny sig
organization=Wacky Bits Inc.
followup to=alt.sources.d
printer=/usr/local/bin/a2ps -nn | /bin/lpr
auto save=ON
batch save=OFF
delete tmp files=ON
show only unread=OFF
thread arts=ON
show author=1
sort art type=5
post proc type=1
```

Note that the `newsgroup=<groupname>` line has to be specified before the attributes are specified for that group.

All attributes are set to a reasonable default so you only have to specify the attribute that you want to change (for example, `savedir`).

All toggle attributes are set by specifying `ON/OFF`.

The `show_author` attribute is specified by a number from the following range: `0`=none, `1`=username, `2`=network address, `3`=both.

The `sort_art_type` attribute is specified by a number from the following range: `0`=none, `1`=subject descending, `2`=subject ascending, `3`=from descending, `4`=from ascending, `5`=date descending, `6`=date ascending.

The `post_proc_type` attribute is specified by a number from the following range: `0`=none, `1`=unshar, `2`=uudecode, `3`=uudecode & list zoo archive, `4`=uudecode & extract zoo archive, `5`=uudecode & list zip archive, `6`=uudecode & extract zip archive. (If running on AmigaDOS, the zoo options are replaced by their corresponding `1ha` archiver options.)

AUTOMATIC KILL AND SELECTION

When there is a subject or an author that you are either very interested in, or find completely uninteresting, you can easily instruct `tin` to autoselect or autokill articles with specific subjects or from specific authors. These instructions are stored in a `kill` file.

This menu is accessed by pressing `^K` at the group and page levels. It allows the user to kill or select an article that matches the current “Subject:” line, “From:” line, or a string entered by the user. The user-entered string can be applied to the “Subject:” or “From:” lines of an article. The `kill` description can be limited to the current newsgroup or it can apply to all

newsgroups. Once entered, the user can abort the command and not save the `kill` description, edit the `kill` file, or save the `kill` description.

On starting `tin`, the user's `kill` file `$HOME/.tin/kill` is read and on entering a newsgroup any `kill` or `select` descriptions are applied.

Articles that match a `kill` description are marked killed and are not displayed. Articles that match an `autoselect` description are marked with an `*` when displayed.

POSTING ARTICLES

`tin` allows posting of articles, follow-up to already posted articles, and replying direct through mail to the author of an article.

Use the `w` command to post an article to a newsgroup. After entering the post subject, the default editor (such as `vi`) or the editor specified by the `$VISUAL` environment variable will be started and the article can be entered. To crosspost articles, simply add a comma and the name of the newsgroup(s) to the end of the "Newsgroups:" line at the beginning of the article. After saving and exiting the editor, you are asked if you wish to abort posting the article, edit the article again or post the article to the specified newsgroup(s).

Use the `w` command to display a history of the articles you have posted. The date the article was posted, which newsgroups the article was posted to, and the article's subject line are displayed.

Use the `f/F` command to post a follow-up article to an already posted article. The `f` command will copy the text of the original article into the editor. The editing procedure is the same as when posting an article with the `w` command.

Use the `r/R` command to reply direct through mail to the author of an already posted article. The `r` command will copy the text of the original article into the editor. The editing procedure is the same as when posting an article with the `w` command. After saving and exiting the editor, you are asked if you wish to abort sending the article, edit the article again, or send the article to the author.

CUSTOMIZING THE ARTICLE QUOTE STRING

When posting a follow-up to an article or replying direct to the author of an article via e-mail, the text of the article can be quoted. The beginning of the quoted text can contain information about the quoted article (for example, the Name and the Message ID of the article). To allow for different situations, certain information from the article can be used in the quoted string. The following variables are expanded if found in the `tinrc` variables `mail_quote_format=` or `news_quote_format=`:

<code>%A</code>	Address (e-mail)
<code>%D</code>	Date
<code>%F</code>	Full address (<code>%N</code> (<code>%A</code>))
<code>%G</code>	Groupname
<code>%M</code>	Message ID
<code>%N</code>	Name of user

For example,

```
mail_quote_format=On %D in %G you wrote:
news_quote_format=In %M, %F wrote:
```

would expand when used to:

```
On 21 Jul 1992 09:45:51 -0400 in alt.sources you wrote:
In <abcINN123@an1433.uucp>, Iain Lea (iain@erlm.siemens.de) wrote:
```

MAILING, PIPING, PRINTING, REPOSTING, AND SAVING ARTICLES

The command interface to mail (`m`), pipe (`l`), print (`o`), crosspost (`x`) and save (`s`) articles is the same for ease of use.

The initial command will ask you to select which article, thread, hot (autoselected) `regex` pattern, tagged articles you wish to mail, pipe, and so on.

Tagged articles must have already been tagged with the `T` command. All tagged articles can be untagged by the `U` untag command.

If `regex` pattern matching is selected, you are asked to enter a regular expression (for example, to match all article subject lines containing `net News`, you must enter `*net News*`). Any articles that match the entered expression will be mailed, piped, and so on.

To save articles to a mailbox with the name of the current newsgroup (for example, `Alt.sources`) enter `= or =<mailbox name>` when asked for the save filename.

To save articles in `<newsgroup name>/<filename>` format, enter `+<filename>`.

When saving articles, you can specify whether the saved files should be post processed (such as `unshar shell archive`, `uudecode multiple parts`, and so on). A default process type can be set by the `Process type` in the `M Options` menu.

AUTOMATIC MAILING AND SAVING NEW NEWS

`tin` allows new/unread news articles to be mailed (`-M` option)/saved (`-S` option) in batch mode for later reading—useful when going on holiday and you don't want to return and find that `expire` has removed a whole load of unread articles. It's best to run from `crontab` every day while away, after which you will be mailed a report of which articles were mailed/saved from which newsgroups and the total number of articles mailed/saved. Articles are saved in a private news structure under your `<savedit>` directory (default is `$HOME/News`).

Be careful of using this option if you read a lot of groups because you could overflow your filesystem. If you only want to save a few groups, it would be best to back up your full `$HOME/.newsrc` and create a new one that only contains the newsgroups you want to mail/save. Saved news can be read later by `tin -R`.

```
tin -M iain -c -f newsrc.mail      Mail any unread articles in newsgroups specified in file newsrc.mail
tin -S -c -f newsrc.save          Save any unread articles in newsgroups specified in file newsrc.save
tin -R                           Read any articles saved by tin -S
```

SIGNATURES

`tin` will recognize a signature in either `$HOME/.signature` or `$HOME/.Sig`. If `$HOME/.signature` exists, then the signature will be pulled into the editor for mail commands. A signature in `$HOME/.signature` will not be pulled into the editor for posting commands because `inews` will append the signature itself.

A signature in `$HOME/.Sig` will be pulled into the editor for both posting and mailing commands.

The following is an example of a `$HOME/.Sig` file:

```
NAMES Iain Lea iain.lea@erlm.siemens.de
SNAIL Bruecken Strasse 12, 8500 Nuernberg 90, Germany
PHONE +49-911-331963 (home) +49-911-3089-407 (work)
```

`tin` also has the capability to generate random signatures on a per-newsgroup basis if so desired. The way to accomplish this is to specify the default signature or the group attribute `sigfile` as a directory. If, for example, the `sigfile` path is `/usr/iain/.sigs` and `.sigs` is a directory, then `tin` will select a random signature from any file that is in the directory `.sigs` (note: one signature per numbered file). A random signature can also consist of a fixed part signature that can contain your name, address, and so on, followed by the random `sig`. The fixed part of the random `sig` is read from the file `$HOME/.sigfixed`.

ENVIRONMENT VARIABLES

<code>TINRC</code>	Define this variable if you want to specify command-line options that <code>tin</code> should be started with to save typing them each time it is started. The contents of the environment variable are added to the front of the command-line options before it is parsed, therefore allowing an option specified on the command line to override the same option specified in the environment.
<code>TIN_HOMEDIR</code>	Define this variable if you do not want the <code>.tin</code> directory in <code>\$HOME/.tin</code> . For example, if you want all <code>tin</code> 's private files in <code>/tmp/.tin</code> , you would set <code>TINDIR</code> to <code>/tmp</code> .

TIN_INDEXDIR	Define this variable if you do not want the <code>.index</code> directory in <code>\$HOME/.tin/.index</code> . For example, if you want all tin's index files in <code>/tmp/.index</code> , you would set <code>TIN_INDEXDIR</code> to <code>/tmp</code> .
TIN_LIBDIR	Define this variable if you want to override the <code>LIBDIR</code> path that was compiled into the tin binary via the Makefile.
TIN_SPOOLDIR	Define this variable if you want to override the <code>SPOOLDIR</code> path that was compiled into the tin binary via the Makefile.
TIN_NOVROOTDIR	Define this variable if you want to override the <code>NOVROOTDIR</code> path that was compiled into the tin binary via the Makefile.
TIN_ACTIVEFILE	Define this variable if you want to override the <code>LIBDIR/active</code> path that was compiled into the tin binary via the Makefile.
NNTPSERVER	The default NNTP server to remotely read news from. This variable only needs to be set if the <code>-r</code> command-line option is specified and the file <code>/etc/nntpserver</code> does not exist.
DISTRIBUTION	Set the article header field "Distribution:" to the contents of the variable instead of the system default.
ORGANIZATION	Set the article header field "Organization:" to the contents of the variable instead of the system default. This variable has precedence over the file <code>\$HOME/.tin/organization</code> that may also contain an organization string. If you are reading news on an Apollo DomainOS machine, the environment variable <code>NEWSORG</code> has to be used instead of <code>ORGANIZATION</code> .
REPLYTO	Set the article header field "Reply-To:" to the return address specified by the variable. This is useful if the machine is not registered in the UUCP mail maps or if you wish to receive replies at a different machine. This variable has precedence over the file <code>\$HOME/.tin/replyto</code> that may also contain a return address.
ADD_ADDRESS	This can contain an address to append to the return address when replying directly through mail to somebody whose mail address is not directly recognized by the local host. For example say the return address is <code>user@bigvax</code> , but <code>bigvax</code> is not recognized by your host, so therefore the mail will not reach user. But the host <code>littevox</code> is known to recognize your host and <code>bigvax</code> , so if <code>ADDADDRESS</code> is set (for example, <code>setenv ADD_ADDRESS @littevox</code> for <code>csh</code> or <code>set ADD_ADDRESS @littevox</code> and <code>export ADD_ADDRESS</code> for <code>sh</code>), the address <code>user@bigvax@littlevax</code> will be used and the mail will reach <code>user@bigvax</code> . This variable has precedence over the file <code>\$HOME/.tin/add_address</code> that may also contain an address.
BUG_ADDRESS	If the <code>B</code> command bug report mail address is not correct, this variable should be set to the correct mail address. This variable has precedence over the file <code>\$HOME/.tin/bug_address</code> that may also contain a mail address.
MAILER	This variable has precedence over the default mailer that is used in all mailing operations within tin (for example, replying <code>rR</code> , and bug reports <code>B</code>).
VISUAL	This variable has precedence over the default editor (for example, <code>vi</code>) that is used in all editing operations within tin (for example, posting <code>w</code> , replying <code>rR</code> , follow-ups <code>fF</code> , and bug reports <code>B</code>).
AUTOSUBSCRIBE	tin interprets this variable similarly to <code>rn</code> . It contains a list of patterns, separated by commas and possibly prefixed with exclamation points. A new group is checked against the list of patterns; if it matches, tin subscribes the user to the group without further query. An exclamation point negates the meaning of a match on this pattern and can be used to cancel certain matches. For example, setting <code>AUTOSUBSCRIBE=comp.os.unix.*,talk.*,!talk.politics.*</code> will automatically subscribe the user to all newsgroups in the <code>comp.os.unix</code> hierarchy, and all talk groups other than <code>talk.politics</code> groups (which will be queried for as usual).

AUTOUNSUBSCRIBE `tin` interprets this variable similarly to `rn`. It is handled like the `AUTOSUBSCRIBE` variable, but groups matching the list are unsubscribed from without further query. For example, setting `AUTOUNSUBSCRIBE=alt.flame.*,u*,!uk.*` will automatically unsubscribe the user from all new `alt.flame` groups and all groups starting with `u` (university groups) other than `uk` groups (which will be queried for as usual).

TIPS AND TRICKS

`tin` can pretty much be navigated by using the four cursor keys. The left-arrow key goes up a level, the right-arrow key goes down a level, the up-arrow key goes up a line (or page, at article viewer level) and the down-arrow key goes down a line (or page, at article viewer level).

The following newsgroups provide useful information concerning news software:

<code>--news.software.readers</code>	Information about news user agents <code>tin</code> , <code>rn</code> , <code>nn</code> , <code>vn</code> , and so on
<code>--news.software.nntp</code>	Information about NNTP
<code>--news.software.b</code>	Information about news transport agents <code>Bnews</code> , <code>Cnews</code> , and <code>INN</code>
<code>--news.answers</code>	Frequently asked questions (FAQs) about many different themes

Many prompts (for example, `Mark everything as read? (y/n):`) within `tin` offer a default choice that the cursor is positioned on. When you press `<CR>`, the default value is taken.

Many prompts (for example, `Post subject [ ]>`) within `tin` can be aborted by pressing `<ESC>`.

When `tin` is run in an `xterm` window, it will resize itself each time the `xterm` is resized.

`tin` will reread the active file at set intervals to show any newly arrived news.

xterm BUTTONS

If the environment variable `TERM` is set to `xterm`, then button pressing can be used to select groups and articles.

In the Group Selection menu, if the mouse is pointing before the group's listing region, the previous page is selected (just like `b`). If the mouse is pointing after the group's listing region, the next page is selected (just like `space`). If the mouse is pointing at a group, then

Left button	Moves to the group pointed at
Other buttons	Move to and select the group pointed at, just like <code><CR></code>

In the Article menu, if the mouse is pointing before the article listing region, the previous page is selected (just like `b`). If the mouse is pointing after the article listing region, the next page is selected (just like `space`). If the mouse is pointing at an article, then

Left button	Moves to the article pointed at
Center button	Reads next unread article from that pointed at, just like <code><TAB></code>
Right button	Reads article pointed at, just like <code><CR></code>

In the Thread menu, if the mouse is pointing before the article listing region, the previous page is selected (just like `b`). If the mouse is pointing after the article listing region, the next page is selected (just like `space`). If the mouse is pointing at an article, then

Left button	Moves to the article pointed at
Center button	Reads next unread article from that pointed at, just like <code><TAB></code>
Right button	Reads article pointed at, just like <code><CR></code>

In the Spool Selection menu, if the mouse is pointing before the spool listing region, the previous page is selected (just like `b`). If the mouse is pointing after the spool listing region, the next page is selected (just like `space`). If the mouse is pointing at a spool selection, then

Left button Moves to the spool pointed at
 Other buttons Move to and select the spool pointed at, just like <CR>

In other menus and areas, button pressing reverts back to usual cut and paste of xterm, but after one click of any button.

FILES

\$HOME/.newsrc	Subscribed to newsgroups
\$HOME/.newsauth	nntpserver password pairs for NNTP servers that require authorization
\$HOME/.tin/tinrc	Options
\$HOME/.tin/attributes	Contains user-specified group attributes
\$HOME/.tin/.index	Newsgroups index files directory
\$HOME/.tin/.mailidx	Mailgroups index files directory
\$HOME/.tin/.saveidx	Saved newsgroups index files directory
\$HOME/.tin/active.mail	Active file of users mailgroups
\$HOME/.tin/active.save	Active file of users saved newsgroups
\$HOME/.tin/add_address	Address to add to when replying through mail
\$HOME/.tin/bug_address	Address to send bug reports to
\$HOME/.tin/kill	Article kill and autoselection file
\$HOME/.tin/organization	String to replace default organization
\$HOME/.tin/posted	History of articles posted by user
\$HOME/.tin/replyto	Host address to use in "Reply-To:" mail header
\$HOME/.signature	Signature
\$HOME/.Sig	Signature
\$HOME/.sigfixed	Fixed part of a randomly generated signature
/usr/lib/news/motd	News message-of-the-day file
/usr/lib/news/newsgroups	Short description of all newsgroups
/usr/lib/news/subscriptions	List of newsgroups to subscribe first-time user to

BUGS

There are bugs somewhere among the creeping featurism. Any bugs found should be reported by the B (bug report) command.

Coredumps when setting certain toggle options from the Options menu at article viewer level.

Coredumps when killing last article in a thread at article viewer level.

HISTORY

Based on the tass newsreader that was developed by Rich Skrenta and posted to alt.sources in March 1991. tass was itself heavily influenced by NOTES, which was developed at the University of Illinois by Ray Essick and Rob Kolstad in 1982.

v1.0 PL0 (full) was posted in eight parts to alt.sources on 23 Aug 1991. v1.0 PL1 (full) was posted in eight parts to alt.sources on 03 Sep 1991. v1.0 PL2 (full) was posted in nine parts to alt.sources on 24 Sep 1991. v1.0 PL3 (patch) was posted in four parts to alt.sources on 30 Sep 1991. v1.0 PL4 (patch) was posted in two parts to alt.sources on 02 Oct 1991. v1.0 PL5 (patch) was posted in four parts to alt.sources on 17 Oct 1991. v1.0 PL6 (patch) was posted in five parts to alt.sources on 27 Nov 1991. v1.0 PL7 (patch) was posted in two parts to alt.sources on 27 Nov 1991. v1.1 PL0 (full) was posted in eleven parts to alt.sources on 13 Feb 1992. v1.1 PL1 (full) was posted in twelve parts to alt.sources on 24 Mar 1992. v1.1 PL2 (patch) was posted in four parts to alt.sources on 30 Mar 1992. v1.1 PL3 (full) was posted in fifteen parts to alt.sources on 13 May 1992. v1.1 PL4 (full) was posted in fifteen parts to alt.sources on 22 Jun 1992. v1.1 PL5 (patch) was posted in seven parts to alt.sources on 11 Aug 1992. v1.1 PL6 (full) was posted in

fifteen parts to `alt.sources` on 14 Sep 1992. `v1.1 PL7` (patch) was posted in ten parts to `alt.sources` on 15 Nov 1992. `v1.1 PL8` (patch) was posted in six parts to `alt.sources` on 06 Dec 1992. `v1.1 PL9` (patch) was posted in three parts to `alt.sources` on 20 Mar 1993. `v1.2 PL0` (full) was posted in fourteen parts to `alt.sources` on 25 May 1993. `v1.2 PL1` (patch) was posted in eight parts to `alt.sources` on 14 Jul 1993. `v1.2 PL2` (patch) was posted in parts to `alt.sources` in September 1993.

CREDITS

Rich Skrenta	Author of <code>tass v3.2</code> , which this newsreader used as its base
Bill Davidsen	Author of <code>envarg.c</code> environment variable reading routine
Mike Gleason	Author of <code>sigfile.c</code> random signature generation routines
Arnold Robbins	Author of <code>strftime.c</code> date formatting routine
Jim Robinson	Coauthor of <code>kill.c</code> article kill and autoselection routines
Rich Salz	Author of <code>wildmat.c</code> pattern matching and <code>parsedate.y</code> date parsing routines
Dave Taylor	Author of <code>curses.c</code> from the <code>elm</code> mailreader
Chris Thewalt	Author of <code>getline.c</code> emacs-style editing routine
Mark Tomlinson	For porting <code>tin</code> to the AmigaDOS operating system
Andreas Wrede	For porting <code>tin</code> to the OS/2 operating system
Dieter Becker	For generously posting certain releases for me when my net connection was removed by a group of very short-sighted people

I wish to thank the following people for supplying patches:

David Abbott, Earle Ake, Joachim Astel, Anton Aylward, George Baltz, Paul Bauwens, Dieter Becker, Dan Berry, David Binderman, Fokke de Boer, Mark Boucher, Herman ten Brugge, Leila Burrell-Davis, Peter Castro, Robert Claeson, Steven Cogswell, Don Costello, Bryan Curnutt, Ned Danieleley, Chris Davies, John Davis, Tom Dickey, Bryan Dongray, Craig Durland, Kirk Edson, Stefan Elf, Rob Engle, Brent Ermlick, Olle Eriksson, Michael Faurot, Werner Fleck, Callum Gibson, Mike Glendinning, Philippe Goujard, Carl Hage, Paul Halsema, Ed Hanway, Scott Hauck, Per Headland, Daniel Hermans, Jose Herrero, Tom Hite, Torsten Homeyer, Tommy Hsieh, Steve Hunt, Pieter Immelman, Robbin John-son, Nelson Kading, Fritz Kleeman, Dwarven Knight, Karl-Koenig Koenigsson, Martin Kraemer, Kris Kugel, Geoff Lane, Alex Lange, Alain Lasserre, Marty Leisner, Hakan Lennestall, Otto Lind, Richard Lloyd, Clifford Luke, David MacKenzie, Hugh Mahon, Kazushi Marukawa, Owen Medd, Soren Moller, Sergio Morales, Michael Morrell, Klaus Mueller, Udo Munk, James Nugen, Jeb Palmer, Neil Parker, Tom Parry, Jim Patterson, Walter Pelissero, Colin Perkins, Eric Peterson, Tim Pierce, Bill Poitras, Wolfgang Prediger, Ted Richards, Ollivier Robert, Jim Robinson, Stephen Roseman, Clifton Royston, Nicko-lay Saukh, Rich Salz, Gary Sanders, John Sauter, Christopher Sawtell, John Schmitz, Bart Sears, Karl Olav Serrander, Doug Sewell, Philip Shearer, Mark Smith, Steve Spearman, Cliff Stanford, Steve Starck, Jason Steiner, Ed Szynter, Derek Terveer, Julian Thompson, Andry Timonin, Mark Tomlin, Michael Traub, Adri Verhoef, Paul Vickers, Cary Whitney, Greg Woods, Lloyd Wright

I wish to thank the following people for bug reports/comments:

Jack Applin, Klaus Arzig, Scott Babb, Reiner Balling, Preston Bannister, Bill de Beabien, Volker Beyer, Etienne Bido, Roger Binns, Georg Biehler, Jean-Marc Bonnaudet, Eric Bowles, Sean Brady, Ian Brown, Andreas Brosig, Craig Bruce, Brett Carver, Tom Czarnik, Dave Datta, Mat Davis, Karl Denninger, Klaus Dimmler, David Donovan, Peter Dressler, Gerhard Ermer, Hugh Fader, Miguel Farah, Joachim Feld, Paul Fox, Jay Geertsens, Herschel Gelman, Bernhard Gmelch, Jason Haar, Viet Hoang, Andy Jackson, Joe Johnson, Ralph Jud, Cyrill Jung, Kuo-Chein Kai, Tonis Kelder, Hans-Juergen Knopp, Sridhar Komandur, Tom Kovar, Bernhard Kroenung, Murray Laing, Per Lindqvist, Eric Litman, Bob Lukas, Michael Marshall, Kazushi Marukawa, Olaf Mittelstaedt, Phillip Molloy, Phil Molyneux, Toni Metz, Greg Miller, Deeptendu Majumder, Klaus Neuberger, Otto Niesser, Reiner Oelhaf, Alex Pakter, John Palkovic, Dave Pascoe, Wolf Paul, Andrew Phillips, Stefan Rathmann, Jon Robinson, David Ross, Jonas Rwgmyr, Malkani Sanjay, Daemon Schae-fer, Dean Schrimpf, Klammer Schutte, Fredy Schwatz, Dave Schweisguth, Bernd Schwerin, Don Sheythe, Chris Smith, Daniel Smith, Richard Stanton, Ralf Stephan, Hironobu Taka-hashii, Ken Taylor, Tony Travis, Paul Verket, Sven Werner, Dick Wexelblat, Paul Wood, Gregory Woodbury, Norm Yamane, Blair Zajac, Orest Zboroski, Thomas Ziegler

AUTHOR

Iain Lea (iain.lea@er1m.siemens.de)

Version 1.2 PL2

tload

tload—Graphic representation of system load average

SYNOPSIS

```
tload [-s scale] [-d delay] [tty]
```

DESCRIPTION

tload prints a graph of the current system load average to the specified **tty** (or the **tty** of the **tload** process if none is specified).

OPTIONS

The **-s scale** option allows a vertical scale to be specified for the display (in characters between graph ticks); thus, a smaller value represents a larger scale, and vice versa.

The **-d delay** sets the delay between graph updates in seconds.

FILES

/proc/loadavg Load average information

SEE ALSO

ps(1), **top(1)**, **uptime(1)**, **w(1)**

BUGS

The **-d delay** option sets the time argument for an **alarm(2)**; if **-d 0** is specified, the alarm is set to **0**, which will never send the **SIGALRM** and update the display.

AUTHORS

Branko Lankester, David Engel (david@ods.com), and Michael K. Johnson (johnsonm@sunsite.unc.edu)

Cohesive Systems, 20 March 1993

top

top—Display top CPU processes

SYNOPSIS

```
top [-][delay][q][S][s][i]
```

DESCRIPTION

top provides an ongoing look at processor activity in real time. It displays a listing of the most CPU-intensive tasks on the system, and can provide an interactive interface for manipulating processes.

COMMAND-LINE OPTIONS

- d** Specifies the delay between screen updates. You can change this with the **s** interactive command.
- q** This causes **top** to refresh without any delay. If the caller has superuser privileges, **top** runs with the highest possible priority.
- S** Specifies cumulative mode, where each process is listed with the CPU time that it as well as its dead children has spent. This is like the **-s** flag to **ps(1)**. See the discussion of the **S** interactive command later in this manual page.
- s** Tells **top** to run in secure mode. This disables the potentially dangers of the interactive commands. (See “Interactive Commands,” later in this manual page.) A secure **top** is a nifty thing to leave running on a spare terminal.
- i** Start **top**, ignoring any idle or zombie processes. (See the interactive command **i**.)

FIELD DESCRIPTIONS

top displays a variety of information about the processor state. The display is updated every five seconds by default, but you can change that with the **d** command-line option or the **s** interactive command.

uptime	This line displays the time the system has been up, and the three load averages for the system. The load averages are the average number of process ready to run during the last 1, 5, and 15 minutes. This line is just like the output of uptime(1) .
processes	The total number of processes running at the time of the last update. This is also broken down into the number of tasks that are running, sleeping, stopped, or undead.
CPU states	Shows the percentage of CPU time in user mode, system mode, niced tasks, and idle. (Niced tasks are only those whose nice value is negative.) Time spent in niced tasks will also be counted in system and user time, so the total will be more than 100 percent.
Mem	Statistics on memory usage, including total available memory, free memory, used memory, shared memory, and memory used for buffers.
Swap	Statistics on swap space, including total swap space, available swap space, and used swap space. This and Mem are just like the output of free(1) .
PID	The process ID of each task.
USER	The username of the task's owner.
PRI	The priority of the task.
NI	The nice value of the task. Negative nice values are lower priority.
SIZE	The size of the task's code plus data plus stack space, in kilobytes, is shown here.
RSS	The total amount of physical memory used by the task, in kilobytes, is shown here.
SHRD	The amount of shared memory used by the task is shown in this column.
ST	The state of the task is shown here. The state is either S for sleeping, D for uninterruptible sleep, R for running, z for zombies, or T for stopped or traced.
TIME	Total CPU time the task has used since it started. If cumulative mode is on, this also includes the CPU time used by the process's children that have died. You can set cumulative mode with the S command-line option or toggle it with the interactive command S .
%CPU	The task's share of the CPU time since the last screen update, expressed as a percentage of total CPU time.
%MEM	The task's share of the physical memory.
COMMAND	The task's command name, which will be truncated if it is too long to be displayed on one line. Tasks in memory will have a full command line, but swapped-out tasks will only have the name of the program in parentheses, for example, (getty).

INTERACTIVE COMMANDS

Several single-key commands are recognized while **top** is running. Some are disabled if the **s** option has been given on the command line.

<code>^L</code>	Erases and redraws the screen.
<code>h</code> or <code>?</code>	Displays a help screen giving a brief summary of commands, and the status of secure and cumulative modes.
<code>k</code>	Kill a process. You will be prompted for the <code>PID</code> of the task, and the signal to send to it. For a normal kill, send signal 15. For a sure, but rather abrupt, kill, send signal 9. The default signal, as with <code>kill(1)</code> , is 15, <code>SIGTERM</code> . This command is not available in secure mode.
<code>i</code>	Ignore idle and zombie processes. This is a toggle switch.
<code>n</code> or <code>#</code>	Change the number of processes to show. You will be prompted to enter the number. This overrides automatic determination of the number of processes to show, which is based on window size measurement. If 0 is specified, then <code>top</code> will show as many processes as will fit on the screen; this is the default.
<code>q</code>	Quit.
<code>r</code>	Renice a process. You will be prompted for the <code>PID</code> of the task, and the value to nice it to. Entering a positive value will cause a process to be niced to negative values, and lose priority. If root is running <code>top</code> , a negative value can be entered, causing a process to get a higher than normal priority. The default renice value is 10. This command is not available in secure mode.
<code>s</code>	This toggles cumulative mode, the equivalent of <code>ps -s</code> , in other words, that CPU times will include a process's defunct children. For some programs, such as compilers, which work by forking into many separate tasks, normal mode will make them appear less demanding than they actually are. For others, however, such as shells and <code>init</code> , this behavior is correct. In any case, try cumulative mode for an alternative view of CPU use.
<code>s</code>	Change the delay between updates. You will be prompted to enter the delay time, in seconds, between updates. Fractional values are recognized down to microseconds. Entering 0 causes continuous updates. The default value is 5 seconds. Note that low values cause nearly unreadably fast displays, and greatly raise the load. This command is not available in secure mode.

NOTES

This `proc`-based `top` works by reading the files in the `proc` filesystem, mounted on `/proc`. If `/proc` is not mounted, `top` will not work.

`%CPU` shows the `cputime/realtime` percentage in the period of time between updates. For the first update, a short delay is used, and `top` itself dominates the CPU usage. After that, `top` will drop back, and a more reliable estimate of CPU usage is available.

The `SIZE` and `RSS` fields don't count the page tables and the `task_struct` of a process; this is at least 12K of memory that is always resident. `SIZE` is the virtual size of the process (`code+data+stack`).

Keep in mind that a process must die for its time to be recorded on its parent by cumulative mode. Perhaps more useful behavior would be to follow each process upwards, adding time, but that would be more expensive, possibly prohibitively so. In any case, that would make `top`'s behavior incompatible with `ps`.

SEE ALSO

`ps(1)`, `free(1)`, `uptime(1)`, `kill(1)`, `renice(1)`.

BUGS

If the window is less than about 70×7, `top` will not format information correctly.

AUTHOR

`top` was originally written by Roger Binns, based on Branko Lankester's (lankeste@fwl.uva.nl) `ps` program. Robert Nation (nation@rocket.sanders.lockheed.com) rewrote it significantly to use the `proc` filesystem, based on Michael K. Johnson's (johnsonm@sunsite.unc.edu) `proc`-based `ps` program. Many changes were made, including secure and cumulative modes and a general cleanup, by Michael Shields (mjshield@nyx.cs.du.edu).

touch

touch—Change file timestamps

SYNOPSIS

```
touch [-acfm] [-r reference-file] [-t MMDDhhmm[[CC]YY][.ss]] [-d time]
[--time={atime, access, use, mtime, modify}] [--date=time] [--file=reference-file]
[--no-create] [--help] [--version] file...
```

DESCRIPTION

This manual page documents the GNU version of touch. touch changes the access and modification times of each given file to the current time. Files that do not exist are created empty. If the first filename given would be a valid argument to the -t option and no timestamp is given with any of the -d, -r, or -t options and the -- argument is not given, that argument is interpreted as the time for the other files instead of as a filename.

If changing both the access and modification times to the current time, touch can change the timestamps for files that the user running it does not own but has write permission for. Otherwise, the user must own the files.

OPTIONS

-a, <i>--time</i> =atime,	Change the access time only.
<i>--time</i> =access,	
<i>--time</i> =use	
-c, <i>--no-create</i>	Do not create files that do not exist.
-d, <i>--date</i> time	Use time (which can be in various common formats) instead of the current time. It can contain month names, time zones, am and pm, and so on.
-f	Ignored; for compatibility with BSD versions of touch.
-m, <i>--time</i> =mtime,	Change the modification time only.
<i>--time</i> =modify	
-r, <i>--file</i> reference-file	Use the times of reference-file instead of the current time.
-t MMDDhhmm[[CC]YY][.ss]	Use the argument (months, days, hours, minutes, optional century and years, optional seconds) instead of the current time.
<i>--help</i>	Print a usage message on standard output and exit successfully.
<i>--version</i>	Print version information on standard output, then exit successfully.

GNU File Utilities

tr

tr—Translate or delete characters

SYNOPSIS

```
tr [-cst] [--complement] [--squeeze-repeats] [--truncate-set1] string1 string2

tr f-s,--squeeze-repeatsg [-c] [--complement] string1

tr f-d,--deleteg [-c] string1

tr f-d,--deleteg f-s,--squeeze-repeatsg [-c] [--complement] string1 string2
```

GNU tr also accepts the *--help* and *--version* options.

DESCRIPTION

This manual page documents the GNU version of `tr`. `tr` copies the standard input to the standard output, performing one of the following operations:

- Translate and optionally squeeze repeated characters in the result
- Squeeze repeated characters
- Delete characters
- Delete characters, then squeeze repeated characters from the result.

The `string1` and (if given) `string2` arguments define ordered sets of characters, referred to below as `set1` and `set2`. These sets are the characters of the input that `tr` operates on. The `--complement (-c)` option replaces `set1` with its complement (all of the characters that are not in `set1`).

SPECIFYING SETS OF CHARACTERS

The format of the `string1` and `string2` arguments resembles the format of regular expressions; however, they are not regular expressions, only lists of characters. Most characters simply represent themselves in these strings, but the strings can contain the shorthands in the following list, for convenience. Some of them can be used only in `string1` or `string2`, as noted.

Backslash escapes. A backslash followed by a character not listed causes an error message.

<code>\a</code>	Control-G
<code>\b</code>	Control-H
<code>\f</code>	Control-L
<code>\n</code>	Control-J
<code>\r</code>	Control-M
<code>\t</code>	Control-I
<code>\v</code>	Control-K
<code>\ooo</code>	The character with the value given by <code>ooo</code> , which is 1 to 3 octal digits
<code>\n</code>	A backslash

Ranges. The notation `m-n` expands to all of the characters from `m` through `n`, in ascending order. `m` should collate before `n`; if it doesn't, an error results. As an example, `0-9` is the same as `0123456789`. Although GNU `tr` does not support the System V syntax that uses square brackets to enclose ranges, translations specified in that format will still work as long as the brackets in `string1` correspond to identical brackets in `string2`.

Repeated characters. The notation `[c*n]` in `string2` expands to `n` copies of character `c`. Thus, `[y*6]` is the same as `yyyyyy`. The notation `[c*]` in `string2` expands to as many copies of `c` as are needed to make `set2` as long as `set1`. If `n` begins with a `0`, it is interpreted in octal, otherwise in decimal.

Character classes. The notation `[ :class-name: ]` expands to all of the characters in the (predefined) class named `class-name`. The characters expand in no particular order, except for the `upper` and `lower` classes, which expand in ascending order. When the `--delete (-d)` and `--squeeze-repeats (-s)` options are both given, any character class can be used in `string2`. Otherwise, only the character classes `lower` and `upper` are accepted in `string2`, and then only if the corresponding character class (`upper` and `lower`, respectively) is specified in the same relative position in `string1`. Doing this specifies case conversion. The class names are given in the following list; an error results when an invalid class name is given.

<code>alnum</code>	Letters and digits
<code>alpha</code>	Letters
<code>blank</code>	Horizontal whitespace
<code>cntrl</code>	Control characters
<code>digit</code>	Digits
<code>graph</code>	Printable characters, not including space
<code>lower</code>	Lowercase letters

<code>print</code>	Printable characters, including space
<code>punct</code>	Punctuation characters
<code>space</code>	Horizontal or vertical whitespace
<code>upper</code>	Uppercase letters
<code>xdigit</code>	Hexadecimal digits

Equivalence classes. The syntax `[=c=]` expands to all of the characters that are equivalent to `c`, in no particular order.

Equivalence classes are a recent invention intended to support non-English alphabets. But there seems to be no standard way to define them or determine their contents. Therefore, they are not fully implemented in GNU `tr`; each character's equivalence class consists only of that character, which makes this a useless construction currently.

TRANSLATING

`tr` performs translation when `string1` and `string2` are both given and the `--delete (-d)` option is not given. `tr` translates each character of its input that is in `set1` to the corresponding character in `set2`. Characters not in `set1` are passed through unchanged. When a character appears more than once in `set1` and the corresponding characters in `set2` are not all the same, only the final one is used. For example, these two commands are equivalent:

```
tr aaa xyz
```

```
tr a z
```

A common use of `tr` is to convert lowercase characters to uppercase. This can be done in many ways. Here are three of them:

```
tr abcdefghijklmnopqrstuvwxyz ABCDEFGHIJKLMNOPQRSTUVWXYZ
```

```
tr a-z A-Z
```

```
tr '[:lower:]' '[:upper:]'
```

When `tr` is performing translation, `set1` and `set2` should normally have the same length. If `set1` is shorter than `set2`, the extra characters at the end of `set2` are ignored.

On the other hand, making `set1` longer than `set2` is not portable; POSIX.2 says that the result is undefined. In this situation, the BSD `tr` pads `set2` to the length of `set1` by repeating the last character of `set2` as many times as necessary. The System V `tr` truncates `set1` to the length of `set2`.

By default, GNU `tr` handles this case like the BSD `tr` does. When the `--truncate-set1 (-t)` option is given, GNU `tr` handles this case like the System V `tr` instead. This option is ignored for operations other than translation.

Acting like the System V `tr` in this case breaks the relatively common BSD idiom:

```
tr -cs A-Za-z0-9 '\n012'
```

because it converts only zero bytes (the first element in the complement of `set1`), rather than all nonalphanumerics, to newlines.

SQUEEZING REPEATS AND DELETING

When given just the `--delete (-d)` option, `tr` removes any input characters that are in `set1`.

When given just the `--squeeze-repeats (-s)` option, `tr` replaces each input sequence of a repeated character that is in `set1` with a single occurrence of that character.

When given both the `--delete` and the `--squeeze-repeats` options, `tr` first performs any deletions using `set1`, then squeezes repeats from any remaining characters using `set2`.

The `--squeeze-repeats` option may also be used when translating, in which case `tr` first performs translation, then squeezes repeats from any remaining characters using `set2`.

Here are some examples to illustrate various combinations of options.

Remove all zero bytes:

```
tr -d 'n000'
```

Put all words on lines by themselves. This converts all nonalphanumeric characters to newlines, then squeezes each string of repeated newlines into a single newline:

```
tr -cs '[a-zA-Z0-9]' '[nn*]'
```

Convert each sequence of repeated newlines to a single newline:

```
tr -s 'nn'
```

GNU `tr` also accepts the following options in any combination with the others.

- `--help` Print a usage message and exit with a non-zero status.
- `--version` Print version information on standard output, then exit.

WARNING MESSAGES

Setting the environment variable `POSIXLY_CORRECT` turns off several warning and error messages, for strict compliance with POSIX.2. The messages normally occur in the following circumstances:

1. When the `--delete` option is given but `--squeeze-repeats` is not, and `string2` is given, GNU `tr` by default prints a usage message and exits, because `string2` would not be used. The POSIX specification says that `string2` must be ignored in this case. Silently ignoring arguments is a bad idea.
2. When an ambiguous octal escape is given. For example, `n400` is actually `n40` followed by the digit `0`, because the value `400` octal does not fit into a single byte.

Note that GNU `tr` does not provide complete BSD or System V compatibility. For example, there is no option to disable interpretation of the POSIX constructs `[:alpha:]`, `[=c=]`, and `[c*10]`. Also, GNU `tr` does not delete zero bytes automatically, unlike traditional UNIX versions, which provide no way to preserve zero bytes.

GNU Text Utilities

tset, reset

`tset, reset`—Terminal initialization

SYNOPSIS

```
tset [-IQrs] [-t] [-e ch] [-i ch] [-k ch] [-m mapping] [terminal]
```

```
tset -h
```

```
tset -V
```

```
reset [-IQrs] [-t] [-e ch] [-i ch] [-k ch] [-m mapping] [terminal]
```

```
reset -h
```

```
reset -V
```

DESCRIPTION

`tset` initializes terminals. `tset` first determines the type of terminal that you are using. This determination is done as follows, using the first terminal type found:

- The terminal argument specified on the command line
- The value of the `TERM` environmental variable
- The terminal type associated with the standard error output device in the `/etc/ttytype` file
- The default terminal type, unknown

If the terminal type was not specified on the command line, the `-m` option mappings are then applied (see the following section, “Options,” for more information). Then, if the terminal type begins with a question mark (?), the user is prompted for confirmation of the terminal type. An empty response confirms the type, or, another type can be entered to specify a new type. After the terminal type has been determined, the `termcap` entry for the terminal is retrieved. If no `termcap` entry is found for the type, the user is prompted for another terminal type.

After the `termcap` entry is retrieved, the window size, backspace, interrupt, and line kill characters (among many other things) are set and the terminal and tab initialization strings are sent to the standard error output. Finally, if the erase, interrupt, and line kill characters have changed, or are not set to their default values, their values are displayed to the standard error output.

When invoked as `reset`, `tset` sets cooked and echo modes, turns off `cbreak` and raw modes, turns on newline translation and resets any unset special characters to their default values before doing the terminal initialization described above. This is useful after a program dies leaving a terminal in an abnormal state. Note, you may have to type `<LF>reset<LF>` (the line-feed character is normally `control-J`) to get the terminal to work, as carriage-return may no longer work in the abnormal state. Also, the terminal will often not echo the command.

OPTIONS

The options are as follows:

- `-t` The terminal type is displayed to the standard output, and the terminal is not initialized in any way.
- `-e` Set the erase character to `ch`.
- `-I` Do not send the terminal or tab initialization strings to the terminal.
- `-i` Set the interrupt character to `ch`.
- `-k` Set the line kill character to `ch`.
- `-m` Specify a mapping from a port type to a terminal. See the following section, “Setting the Environment,” for more information.
- `-r` Print the terminal type to the standard error output.
- `-s` Print the sequence of shell commands to initialize the environment variables `COLUMNS`, `LINES`, `TERM`, and `TERMCAP` to the standard output.
- `Q` Don’t display any values for the erase, interrupt, and line kill characters.
- `-w` Force setting of display size as defined in `/etc/termcap` file.
- `-h` Print short usage message.
- `-V` Print version number.

The arguments for the `-e`, `-i`, and `-k` options may either be entered as actual characters or by using the hat notation, for example, `control-h` may be specified as `^H` or `^h`.

SETTING THE ENVIRONMENT

It is often desirable to set the terminal type and information about the terminal’s capabilities and display size in the shell’s environment. This is done with the `-s` option; when this option is specified, the commands to enter the information into the shell’s environment are output to the standard output. If the `SHELL` environmental variable ends in `csh`, the output commands are for the `csh(1)`; otherwise, they are for `sh(1)`. Note, the output commands for the `csh` set and unset the shell variable `noglob`. The following line in the `.login` or `.profile` files will initialize the environment correctly:

```
eval `tset -s options ...`
```

TERMINAL TYPE MAPPING

When the terminal is not hardwired into the system (or the current system information is incorrect), the terminal type derived from the `/etc/ttytype` file or the `TERM` environmental variable is often something generic like `network`, `dialup`, or `unknown`. When `tset` is used in a startup script `.profile` for `sh(1)` users or `.login` for `csh(1)` users), it is often desirable to

provide information about the type of terminal used on such ports. The purpose of the `-m` option is to map from some set of conditions to a terminal type; that is, to tell `tset`, “If I’m on this port at a particular speed, guess that I’m on that kind of terminal.”

The argument to the `-m` option consists of an optional port type, an optional operator, an optional baud rate specification, an optional colon (`:`) character, and a terminal type. The port type is a string (delimited by either the operator or the colon character). The operator may be any combination of: `&>`, `&<`, `&@`, and `&!`; `&>` means greater than, `&<` means less than, `&@` means equal to, and `&!` inverts the sense of the test. The baud rate is specified as a number and is compared with the speed of the standard error output (which should be the control terminal). The terminal type is a string.

If the terminal type is not specified on the command line, the `-m` mappings are applied to the terminal type. If the port type and baud rate match the mapping, the terminal type specified in the mapping replaces the current type. If more than one mapping is specified, the first applicable mapping is used.

For example, consider the following:

```
dialup>9600:vt100
```

The port type is `dialup`, the operator is `>`, the baud rate specification is `9600`, and the terminal type is `vt100`. The result of this mapping is to specify that if the terminal type is `dialup`, and the baud rate is greater than `9600` baud, a terminal type of `vt100` will be used.

If no port type is specified, the terminal type will match any port type; for example,

```
-m dialup:vt100 -m :?xterm
```

will cause any dialup port, regardless of baud rate, to match the terminal type:

```
vt100,
```

and any nondialup port type to match the terminal type:

```
?xterm.
```

Note, because of the leading question mark, the user will be queried on a default port as to whether they are actually using an `xterm` terminal.

No whitespace characters are permitted in the `-m` option argument. Also, to avoid problems with metacharacters, it is suggested that the entire `-m` option argument be placed within single quote characters, and that `cs`h users insert a backslash character (`\`) before any exclamation marks (`!`).

ENVIRONMENT

The `tset` command utilizes the `SHELL` and `TERM` environment variables.

`tset` can set `COLUMNS`, `LINES`, `TERM`, and `TERMCAP` environmental variables.

FILES

<code>/etc/ttytype</code>	system	Port name to terminal type mapping database
<code>/etc/termcap</code>		Terminal capability database

SEE ALSO

`csh`(1), `tcsh`(1), `sh`(1), `bash`(1), `stty`(1), `tty`(4), `termcap`(5), `ttytype`(5), `environ`(7)

HISTORY

The `tset` command appeared in BSD 3.0.

COMPATIBILITY

The `-A`, `-E`, `-h`, `-S`, `-u`, and `-v` options have been deleted from the `tset` utility. None of them were documented in 4.3BSD and all are of limited utility at best. The `-a`, `-d`, and `-p` options are similarly not documented or useful, but were retained as they appear to be in widespread use. It is strongly recommended that any usage of these three options be changed to use the `-m` option instead. The `-n` option remains, but has no effect. It is still permissible to specify the `-e`, `-i`, and `-k` options without arguments, although it is strongly recommended that such usage be fixed to explicitly specify the character.

Executing `tset` as `reset` no longer implies the `-q` option. Also, the interaction between the `-` option and the terminal argument in some historic implementations of `tset` has been removed and has been replaced with `-t` option.

Finally, the `tset` implementation has been completely redone as part of the addition to the system of a IEEE Std1003.1-1988 (POSIX) -compliant terminal interface and will no longer compile on systems with older terminal interfaces.

Linux, 12 January 1995

tsort

`tsort`—Topological sort of a directed graph

SYNOPSIS

```
tsort [file]
```

DESCRIPTION

`tsort` takes a list of pairs of node names representing directed arcs in a graph and prints the nodes in topological order on standard output. Input is taken from the named file, or from standard input if no file is given.

Node names in the input are separated by whitespace, and there must be an even number of nodes.

Presence of a node in a graph can be represented by an arc from the node to itself. This is useful when a node is not connected to any other nodes.

If the graph contains a cycle (and therefore cannot be properly sorted), one of the arcs in the cycle is ignored and the sort continues. Cycles are reported on standard error.

SEE ALSO

`ar(1)`

HISTORY

A `tsort` command appeared in AT&T v7. This `tsort` command and manual page are derived from sources contributed to Berkeley by Michael Rendell of Memorial University of Newfoundland.

23 April 1991

twm

`twm`—Tab Window Manager for the X Window System

SYNTAX

```
twm [ -display dpy ][ -s ][ -f initfile ][ -v ]
```

DESCRIPTION

`twm` is a window manager for the X Window System. It provides titlebars, shaped windows, several forms of icon management, user-defined macro functions, click-to-type and pointer-driven keyboard focus, and user-specified key and pointer button bindings.

This program is usually started by the user's session manager or startup script. When used from `xdm(1)` or `xinit(1)` without a session manager, `twm` is frequently executed in the foreground as the last client. When run this way, exiting `twm` causes the session to be terminated (logged out).

By default, application windows are surrounded by a “frame” with a titlebar at the top and a special border around the window. The titlebar contains the window's name, a rectangle that is lit when the window is receiving keyboard input, and function boxes known as *titlebuttons* at the left and right edges of the titlebar.

Pressing pointer Button1 (usually the leftmost button unless it has been changed with `xmodmap`) on a *titlebutton* will invoke the function associated with the button. In the default interface, windows are iconified by clicking (pressing and then immediately releasing) the left *titlebutton* (which looks like a dot). Conversely, windows are deiconified by clicking in the associated icon or entry in the icon manager. (See description of the variable `Show - IconManager` and of the function `f.showiconmgr`.)

Windows are resized by pressing the right *titlebutton* (which resembles a group of nested squares), dragging the pointer over the edge that is to be moved, and releasing the pointer when the outline of the window is the desired size. Similarly, windows are moved by pressing in the title or highlight region, dragging a window outline to the new location, and then releasing when the outline is in the desired position. Just clicking in the title or highlight region raises the window without moving it.

When new windows are created, `twm` will honor any size and location information requested by the user (usually through `-geometry` command-line argument or resources for the individual applications). Otherwise, an outline of the window's default size, its titlebar, and lines dividing the window into a 3×3 grid that track the pointer are displayed. Clicking pointer Button1 will position the window at the current position and give it the default size. Pressing pointer Button2 (usually the middle pointer button) and dragging the outline will give the window its current position but allow the sides to be resized as described above. Clicking pointer Button3 (usually the right pointer button) will give the window its current position but attempt to make it long enough to touch the bottom of the screen.

OPTIONS

`twm` accepts the following command-line options:

- `-display dpy` This option specifies the x server to use.
- `-s` This option indicates that only the default screen (as specified by `-display` or by the `DISPLAY` environment variable) should be managed. By default, `twm` will attempt to manage all screens on the display.
- `-f filename` This option specifies the name of the startup file to use. By default, `twm` will look in the user's home directory for files named `.twmrc.num` (where `num` is a screen number) or `.twmrc`.
- `-v` This option indicates that `twm` should print error messages whenever an unexpected X Error event is received. This can be useful when debugging applications but can be distracting in regular use.

CUSTOMIZATION

Much of `twm`'s appearance and behavior can be controlled by providing a startup file in one of the following locations (searched in order for each screen being managed when `twm` begins):

- `$HOME/.twmrc.screennumber` The `screennumber` is a small positive number (for example, 0, 1, and so on) representing the screen number (for example, the last number in the `DISPLAY` environment variable `host:displaynum.screennum`) that would be used to contact that screen of the display. This is intended for displays with multiple screens of differing visual types.
- `$HOME/.twmrc` This is the usual name for an individual user's startup file.
- `<XRoot>/lib/X11/twm/system.twmrc` If neither of the preceding files are found, `twm` will look in this file for a default configuration. This is often tailored by the site administrator to provide convenient menus or familiar bindings for novice users. `<XRoot>` refers to the root of the X11 install tree.

If no startup files are found, `twm` will use the built-in defaults described. The only resource used by `twm` is `bitmapFilePath` for a colon-separated list of directories to search when looking for bitmap files. For more information, see the Athena Widgets manual and `xrdb(1)`.

`twm` startup files are logically broken up into three types of specifications: `Variables`, `Bindings`, and `Menus`. The `Variables` section must come first and is used to describe the fonts, colors, cursors, border widths, icon and window placement, highlighting, autoraising, layout of titles, warping, and use of the icon manager. The `Bindings` section usually comes second and is used to specify the functions that should be invoked when keyboard and pointer buttons are pressed in windows, icons, titles, and frames. The `Menus` section gives any user-defined menus (containing functions to be invoked or commands to be executed).

Variable names and keywords are case-insensitive. Strings must be surrounded by double quote characters (for example, “blue”) and are case-sensitive. A pound sign (#) outside of a string causes the remainder of the line in which the character appears to be treated as a comment.

VARIABLES

Many of the aspects of `twm`’s user interface are controlled by variables that may be set in the user’s startup file. Some of the options are enabled or disabled simply by the presence of a particular keyword. Other options require keywords, numbers, strings, or lists of all of these.

Lists are surrounded by braces and are usually separated by whitespace or a newline. For example,

```
AutoRaise { "emacs" "XTerm" "Xmh" }
```

or

```
AutoRaise
{
    "emacs"
    "XTerm"
    "Xmh"
}
```

When a variable containing a list of strings representing windows is searched (for example, to determine whether or not to enable autoraize, as shown in the preceding example), a string must be an exact, case-sensitive match to the window’s name (given by the `WM_NAME` window property), resource name, or class name (both given by the `WM_CLASS` window property). The preceding example would enable autoraize on windows named `emacs` as well as any `xterm` (because they are of class `XTerm`) or `xmh` windows (which are of class `xmh`).

String arguments that are interpreted as filenames (see `Pixmap`s, `Cursors`, and `IconDirectory` in the following list of variables) will prepend the user’s directory (specified by the `HOME` environment variable) if the first character is a tilde (~). If, instead, the first character is a colon (:), the name is assumed to refer to one of the internal bitmaps that are used to create the default titlebars symbols: `:xlogo` or `:delete` (both refer to the `x` logo), `:dot` or `:iconify` (both refer to the dot), `:resize` (the nested squares used by the resize button), `:menu` (a page with lines), and `:question` (the question mark used for nonexistent bitmap files).

The following variables may be specified at the top of a `twm` startup file. Lists of Window name prefix strings are indicated by `win-list`. Optional arguments are shown in square brackets:

<code>AutoRaise { win-list }</code>	This variable specifies a list of windows that should automatically be raised whenever the pointer enters the window. This action can be interactively enabled or disabled on individual windows using the function <code>f.auraise</code> .
<code>AutoRelativeResize</code>	This variable indicates that dragging out a window size (either when initially sizing the window with pointer <code>Button2</code> or when resizing it) should not wait until the pointer has crossed the window edges. Instead, moving the pointer automatically causes the nearest edge or edges to move by the same amount. This allows the resizing of windows that extend off the edge of the screen. If the pointer is in the center of the window, or if the resize is begun

	by pressing a <code>titlebutton</code> , <code>twm</code> will still wait for the pointer to cross a window edge (to prevent accidents). This option is particularly useful for people who like the press-drag-release method of sweeping out window sizes.
<code>BorderColor</code> string windows, [{ <code>wincolorlist</code> }]	This variable specifies the default color of the border to be placed around all noniconified and may only be given within a <code>Color</code> , <code>Grayscale</code> , or <code>Monochrome</code> list. The optional <code>wincolorlist</code> specifies a list of window and color name pairs for specifying particular border colors for different types of windows. For example: <pre> BorderColor "gray50" { "XTerm" "red" "xmh" "green" } </pre> The default is black.
<code>BorderTileBackground</code> <code>wincolorlist</code> }	This variable specifies the default background color in the gray pattern used in <code>string</code> [{ unhighlighted borders (only if <code>NoHighlight</code> hasn't been set), and may only be given within a <code>Color</code> , <code>Grayscale</code> , or <code>Monochrome</code> list. The optional <code>wincolorlist</code> allows per-window colors to be specified. The default is white.
<code>BorderTileForeground</code> string [{ <code>wincolorlist</code> }]	This variable specifies the default foreground color in the gray pattern used in unhighlighted borders (only if <code>NoHighlight</code> hasn't been set), and may only be given within a <code>Color</code> , <code>Grayscale</code> , or <code>Monochrome</code> list. The optional <code>wincolorlist</code> allows per-window colors to be specified. The default is black.
<code>BorderWidth</code> pixels	This variable specifies the width in pixels of the border surrounding all client window frames if <code>ClientBorderWidth</code> has not been specified. This value is also used to set the border size of windows created by <code>twm</code> (such as the icon manager). The default is 2.
<code>ButtonIndent</code> pixels	This variable specifies the amount by which <code>titlebuttons</code> should be indented on all sides. Positive values cause the buttons to be smaller than the window text and highlight area so that they stand out. Setting this and the <code>TitleButtonBorderWidth</code> variables to 0 makes <code>titlebuttons</code> as tall and wide as possible. The default is 1.
<code>ClientBorderWidth</code>	This variable indicates that border width of a window's frame should be set to the initial border width of the window, rather than to the value of <code>BorderWidth</code> .
<code>Color</code> { <code>colors-list</code> }	This variable specifies a list of color assignments to be made if the default display is capable of displaying more than simple black and white. The <code>colors-list</code> is made up of the following color variables and their values: <pre> DefaultBackground DefaultForeground MenuBackground MenuForeground MenuTitleBackground MenuTitleForeground MenuShadowColor PointerForeground PointerBackground </pre> The following color variables may also be given a list of window and color name pairs to allow per-window colors to be specified (see <code>BorderColor</code> for details): <pre> BorderColor IconManagerHighlight BorderTileBackground BorderTileForeground TitleBackground </pre>

```
TitleForeground
IconBackground
IconForeground
IconBorderColor
IconManagerBackground
IconManagerForeground
```

For example:

```
Color
{
MenuBackground "gray50"
MenuForeground "blue"
BorderColor "red" { "XTerm" "yellow" }
TitleForeground "yellow"
TitleBackground "blue"
}
```

All of these color variables may also be specified for the `Monochrome` variable, allowing the same initialization file to be used on both color and monochrome displays.

`ConstrainedMoveTime`
`milliseconds`

This variable specifies the length of time between button clicks needed to begin a constrained move operation. Double-clicking within this amount of time when invoking `f.move` will cause the window to be moved only in a horizontal or vertical direction. Setting this value to 0 will disable constrained moves. The default is 400 milliseconds.

`Cursors { cursor-list }`

This variable specifies the glyphs that `twm` should use for various pointer cursors. Each cursor may be defined either from the `cursor` font or from two `bitmap` files. Shapes from the `cursor` font may be specified directly as

```
0 cursorname "string"
```

where `cursorname` is one of the cursor names listed below, and `string` is the name of a glyph as found in the file:

```
<XRoot>/include/X11/cursorfont.h
```

(without the `XC` prefix). If the cursor is to be defined from `bitmap` files, the following syntax is used instead:

```
0 cursorname "image" "mask"
```

The `image` and `mask` strings specify the names of files containing the glyph image and mask in `bitmap(1)` form. The `bitmap` files are located in the same manner as `icon` `bitmap` files. The following example shows the default cursor definitions:

```
Cursors
{
Frame          "top_left_arrow"
Title          "top_left_arrow"
Icon           "top_left_arrow"
IconMgr        "top_left_arrow"
Move           "fleur"
Resize         "fleur"
Menu           "sb_left_arrow"
Button         "hand2"
Wait           "watch"
Select         "dot"
Destroy        "pirate"
}
```

`DecorateTransients`

This variable indicates that transient windows (those containing a `WM_TRANSIENT_FOR` property) should have titlebars. By default, transients are not reparented.

`DefaultBackground string`

This variable specifies the background color to be used for sizing and information windows. The default is white.

DefaultForeground string	This variable specifies the foreground color to be used for sizing and information windows. The default is <code>black</code> .
DontIconifyByUnmapping { win-list }	This variable specifies a list of windows that should not be iconified window (as would be the case if <code>IconifyByUnmapping</code> had been set). This is frequently used to force some windows to be treated as icons while other windows are handled by the icon manager.
DontMoveOff	This variable indicates that windows should not be allowed to be moved off the screen. It can be overridden by the <code>f.forcemove</code> function.
DontSqueezeTitle [{ win-list }]	This variable indicates that titlebars should not be squeezed to their minimum size as described under <code>SqueezeTitle</code> below. If the optional window list is supplied, only those windows will be prevented from being squeezed.
ForceIcons	This variable indicates that icon pixmaps specified in the <code>Icons</code> variable should override any client-supplied pixmaps.
FramePadding pixels	This variable specifies the distance between the titlebar decorations (the button and text) and the window frame. The default is 2 pixels.
Grayscale { colors }	This variable specifies a list of color assignments that should be made if the screen has a <code>Grayscale</code> default visual. See the description of <code>Colors</code> .
IconBackground string [{ win-list }]	This variable specifies the background color of icons, and may only be specified inside of a <code>Color</code> , <code>Grayscale</code> , or <code>Monochrome</code> list. The optional <code>win-list</code> is a list of window names and colors so that per-window colors may be specified. See the <code>Border-Color</code> variable for a complete description of the <code>win-list</code> . The default is <code>white</code> .
IconBorderColor string [{ win-list }]	This variable specifies the color of the border used for icon windows, and may only be specified inside of a <code>Color</code> , <code>Grayscale</code> , or <code>Monochrome</code> list. The optional <code>win-list</code> is a list of window names and colors so that per-window colors may be specified. See the <code>BorderColor</code> variable for a complete description of the <code>win-list</code> . The default is <code>black</code> .
IconBorderWidth pixels	This variable specifies the width in pixels of the border surrounding icon windows. The default is 2.
IconDirectory string	This variable specifies the directory that should be searched if a bitmap file cannot be found in any of the directories in the <code>bitmapFilePath</code> resource.
IconFont string	This variable specifies the font to be used to display icon names within icons. The default is variable.
IconForeground string [{ win-list }]	This variable specifies the foreground color to be used when displaying icons, and may only be specified inside of a <code>Color</code> , <code>Grayscale</code> , or <code>Monochrome</code> list. The optional <code>win-list</code> is a list of window names and colors so that per-window colors may be specified. See the <code>BorderColor</code> variable for a complete description of the <code>win-list</code> . The default is <code>black</code> .
IconifyByUnmapping [{ win-list }]	This variable indicates that windows should be iconified by being unmapped without trying to map any icons. This assumes that the user will remap the window through the icon manager, the <code>f.warpto</code> function, or the <code>TwmWindows</code> menu. If the optional <code>win-list</code> is provided, only those windows will be iconified by simply unmapping. Windows that have both this and the <code>IconManager DontShow</code> options set may not be accessible if no binding to the <code>TwmWindows</code> menu is set in the user's startup file.
IconManagerBackground string [{ win-list }]	This variable specifies the background color to use for icon manager entries, and may only be specified inside of a <code>Color</code> , <code>Grayscale</code> , or <code>Monochrome</code> list. The optional <code>win-list</code> is a list of window names and colors so that per-window colors may be specified. See the <code>BorderColor</code> variable for a complete description of the <code>win-list</code> . The default is <code>white</code> .
IconManagerDontShow [{ win-list }]	This variable indicates that the icon manager should not display any windows. If the optional <code>win-list</code> is given, only those windows will not be displayed. This variable is used to prevent windows that are rarely iconified (such as <code>xclock</code> or <code>xload</code>) from taking up space in the icon manager.

<code>IconManagerFont string</code>	This variable specifies the font to be used when displaying icon manager entries. The default is variable.
<code>IconManagerForeground string [{ win-list }]</code>	This variable specifies the foreground color to be used when displaying icon manager entries, and may be specified only inside of a <code>Color</code> , <code>Grayscale</code> , or <code>Monochrome</code> list. The optional <code>win-list</code> is a list of window names and colors so that per-window colors may be specified. See the <code>BorderColor</code> variable for a complete description of the <code>win-list</code> . The default is <code>black</code> .
<code>IconManagerGeometry string [columns]</code>	This variable specifies the geometry of the icon manager window. The <code>string</code> argument is standard geometry specification that indicates the initial full size of the icon manager. The icon manager window is then broken into <code>columns</code> pieces and scaled according to the number of entries in the icon manager. Extra entries are wrapped to form additional rows. The default number of columns is 1.
<code>IconManagerHighlight string [{ win-list }]</code>	This variable specifies the border color to be used when highlighting the icon manager entry that currently has the focus, and can only be specified inside of a <code>Color</code> , <code>Grayscale</code> , or <code>Monochrome</code> list. The optional <code>win-list</code> is a list of window names and colors so that per-window colors may be specified. See the <code>Border-Color</code> variable for a complete description of the <code>win-list</code> . The default is <code>black</code> .
<code>IconManagers { iconmgr-list }</code>	This variable specifies a list of icon managers to create. Each item in the <code>iconmgr-list</code> has the following format: <pre>0 "win-name" ["iconname"] "geometry" columns</pre> where <code>winname</code> is the name of the windows that should be put into this icon manager, <code>iconname</code> is the name of that icon manager window's icon, <code>geometry</code> is a standard geometry specification, and <code>columns</code> is the number of columns in this icon manager as described in <code>Icon-ManagerGeometry</code>. For example: <pre>IconManagers { "XTerm" "=300x5+800+5" 5 "myhost" "=400x5+100+5" 2 }</pre> Clients whose name or class is <code>XTerm</code> will have an entry created in the <code>XTerm</code> icon manager. Clients whose name was <code>myhost</code> would be put into the <code>myhost</code> icon manager.
<code>IconManagerShow{ win-list }</code>	This variable specifies a list of windows that should appear in the icon manager. When used in conjunction with the <code>IconManagerDontShow</code> variable, only the windows in this list will be shown in the icon manager.
<code>IconRegion geomstring vgrav hgrav gridwidth gridheight</code>	This variable specifies an area on the root window in which icons are placed if no specific icon location is provided by the client. The <code>geomstring</code> is a quoted string containing a standard geometry specification. If more than one <code>IconRegion</code> line is given, icons will be put into the succeeding icon regions when the first is full. The <code>vgrav</code> argument should be either <code>North</code> or <code>South</code> and is used to control whether icons are first filled in from the top or bottom of the icon region. Similarly, the <code>hgrav</code> argument should be either <code>East</code> or <code>West</code> and is used to control whether icons should be filled in from the left or from the right. Icons are laid out within the region in a grid with cells <code>gridwidth</code> pixels wide and <code>gridheight</code> pixels high.
<code>Icons { win-list }</code>	This variable specifies a list of window names and the <code>bitmap</code> filenames that should be used as their icons. For example, <pre>Icons { "XTerm" "xterm.icon" "xfd" "xfd_icon" }</pre>

	Windows that match "xTerm" and would not be iconified by unmapping would try to use the icon bitmap in the file <code>xterm.icon</code>. If <code>ForceIcons</code> is specified, this bitmap will be used even if the client has requested its own icon pixmap.
<code>InterpolateMenuColors</code>	This variable indicates that menu entry colors should be interpolated between entry specified colors. In this example, <pre>Menu "mymenu" { "Title" ("black":"red") f.title "entry1" f.nop "entry2" f.nop "entry3" ("white":"green") f.nop "entry4" f.nop "entry5" ("red":"white") f.nop }</pre> the foreground colors for "entry1" and "entry2" will be interpolated between black and white, and the background colors between red and green. Similarly, the foreground for "entry4" will be halfway between white and red, and the background will be halfway between green and white.
<code>MakeTitle { win-list }</code>	This variable specifies a list of windows on which a title-bar should be placed and is used to request titles on specific windows when <code>NoTitle</code> has been set.
<code>MaxWindowSize string</code>	This variable specifies a geometry in which the width and height give the maximum size for a given window. This is typically used to restrict windows to the size of the screen. The default width is 32767—screen width. The default height is 32767—screen height.
<code>MenuBackground string</code>	This variable specifies the background color used for menus, and can only be specified inside of a <code>Color</code> or <code>Monochrome</code> list. The default is <code>white</code>.
<code>MenuFont string</code>	This variable specifies the font to use when displaying menus. The default is <code>variable</code>.
<code>MenuForeground string</code>	This variable specifies the foreground color used for menus and can only be specified inside of a <code>Color</code>, <code>Grayscale</code>, or <code>Monochrome</code> list. The default is <code>black</code>.
<code>MenuShadowColor string</code>	This variable specifies the color of the shadow behind pull-down menus and can only be specified inside of a <code>Color</code>, <code>Grayscale</code>, or <code>Monochrome</code> list. The default is <code>black</code>.
<code>MenuTitleBackground string</code>	This variable specifies the background color for <code>f.title</code> entries in menus, and can only be specified inside of a <code>Color</code>, <code>Grayscale</code>, or <code>Monochrome</code> list. The default is <code>white</code>.
<code>MenuTitleForeground string</code>	This variable specifies the foreground color for <code>f.title</code> entries in menus and can only be specified inside of a <code>Color</code> or <code>Monochrome</code> list. The default is <code>black</code>.
<code>Monochrome { colors }</code>	This variable specifies a list of color assignments that should be made if the screen has a depth of 1. See the description of <code>Colors</code>.
<code>MoveDelta pixels</code>	This variable specifies the number of pixels the pointer must move before the <code>f.move</code> function starts working. Also see the <code>f.deltastop</code> function. The default is zero pixels.
<code>NoBackingStore</code>	This variable indicates that <code>twm</code>'s menus should not request backing store to minimize repainting of menus. This is typically used with servers that can repaint faster than they can handle backing store.
<code>NoCaseSensitive</code>	This variable indicates that case should be ignored when sorting icon names in an icon manager. This option is typically used with applications that capitalize the first letter of their icon name.
<code>NoDefaults</code>	This variable indicates that <code>twm</code> should not supply the default titlebuttons and bindings. This option should only be used if the startup file contains a completely new set of bindings and definitions.
<code>NoGrabServer</code>	This variable indicates that <code>twm</code> should not grab the server when popping up menus and moving opaque windows.

<code>NoHighlight [{ win-list }]</code>	This variable indicates that borders should not be highlighted to track the location of the pointer. If the optional <code>win-list</code> is given, highlighting will only be disabled for those windows. When the border is highlighted, it will be drawn in the current <code>BorderColor</code> . When the border is not highlighted, it will be stippled with a gray pattern using the current <code>BorderTileForeground</code> and <code>BorderTileBackground</code> colors.
<code>NoIconManagers</code>	This variable indicates that no icon manager should be created.
<code>NoMenuShadows</code>	This variable indicates that menus should not have drop shadows drawn behind them. This is typically used with slower servers because it speeds up menu drawing at the expense of making the menu slightly harder to read.
<code>NoRaiseOnDeiconify</code>	This variable indicates that windows that are deiconified should not be raised.
<code>NoRaiseOnMove</code>	This variable indicates that windows should not be raised when moved. This is typically used to allow windows to slide underneath each other.
<code>NoRaiseOnResize</code>	This variable indicates that windows should not be raised when resized. This is typically used to allow windows to be resized underneath each other.
<code>NoRaiseOnWarp</code>	This variable indicates that windows should not be raised when the pointer is warped into them with the <code>f.warpto</code> function. If this option is set, warping to an occluded window may result in the pointer ending up in the occluding window instead the desired window, which causes unexpected behavior with <code>f.warping</code> .
<code>NoSaveUnders</code>	This variable indicates that menus should not request save-unders to minimize window repainting following menu selection. It is typically used with displays that can repaint faster than they can handle save-unders.
<code>NoStackMode [{ win-list }]</code>	This variable indicates that client window requests to change stacking order should be ignored. If the optional <code>win-list</code> is given, only requests on those windows will be ignored. This is typically used to prevent applications from relentlessly popping themselves to the front of the window stack.
<code>NoTitle [{ win-list }]</code>	This variable indicates that windows should not have title-bars. If the optional <code>win-list</code> is given, only those windows will not have titlebars. <code>MakeTitle</code> may be used with this option to force titlebars to be put on specific windows.
<code>NoTitleFocus</code>	This variable indicates that <code>twm</code> should not set keyboard input focus to each window as it is entered. Normally, <code>twm</code> sets the focus so that focus and key events from the titlebar and icon managers are delivered to the application. If the pointer is moved quickly and <code>twm</code> is slow to respond, input can be directed to the old window instead of the new. This option is typically used to prevent this input lag and to work around bugs in older applications that have problems with focus events.
<code>NoTitleHighlight [{ win-list }]</code>	This variable indicates that the highlight area of the titlebar, which is used to indicate the window that currently has the input focus, should not be displayed. If the optional <code>win-list</code> is given, only those windows will not have highlight areas. This and the <code>SqueezeTitle</code> options can be set to substantially reduce the amount of screen space required by titlebars.
<code>OpaqueMove</code>	This variable indicates that the <code>f.move</code> function should actually move the window instead of just an outline so that the user can immediately see what the window will look like in the new position. This option is typically used on fast displays (particularly if <code>NoGrabServer</code> is set).
<code>Pixmap { pixmaps }</code>	This variable specifies a list of pixmaps that define the appearance of various images. Each entry is a keyword indicating the pixmap to set, followed by a string giving the name of the bitmap file. The following pixmaps may be specified: <code>0 Pixmap { TitleHighlight "gray1" }</code> The default for <code>TitleHighlight</code> is to use an even stipple pattern.
<code>Priority priority</code>	This variable sets <code>twm</code> 's priority. <code>priority</code> should be an unquoted, signed number (for example, 999). This variable has an effect only if the server supports the SYNC extension.
<code>RandomPlacement</code>	This variable indicates that windows with no specified geometry should be placed in a pseudorandom location instead of having the user drag out an outline.

<code>ResizeFont string</code>	This variable specifies the font to be used for in the dimensions window when resizing windows. The default is <code>fixed</code> .
<code>RestartPreviousState</code>	This variable indicates that <code>twm</code> should attempt to use the <code>WM_STATE</code> property on client windows to tell which windows should be iconified and which should be left visible. This is typically used to try to regenerate the state that the screen was in before the previous window manager was shutdown.
<code>SaveColor { colors-list }</code>	This variable indicates a list of color assignments to be stored as pixel values in the root window property <code>_MIT_PRIORITY_COLORS</code>. Clients may elect to preserve these values when installing their own colormaps. Note that use of this mechanism is a way for an application to avoid the “technicolor” problem, whereby useful screen objects such as window borders and titlebars disappear when a program’s custom colors are installed by the window manager. For example: <pre>SaveColor { BorderColor TitleBackground TitleForeground "red" "green" "blue" }</pre> This would place on the root window three pixel values for borders and titlebars, as well as the three color strings, all taken from the default colormap.
<code>ShowIconManager</code>	This variable indicates that the icon manager window should be displayed when <code>twm</code> is started. It can always be brought up using the <code>f.showiconmgr</code> function.
<code>SortIconManager</code>	This variable indicates that entries in the icon manager should be sorted alphabetically rather than by simply appending new windows to the end.
<code>SqueezeTitle</code> <code>[{ squeeze-list }]</code>	This variable indicates that <code>twm</code> should attempt to use the <code>SHAPE</code> extension to make titlebars occupy only as much screen space as they need, rather than extending all the way across the top of the window. The optional <code>squeeze-list</code> may be used to control the location of the squeezed titlebar along the top of the window. It contains entries of the form: <code>0 "name" justification num denom</code> where <code>name</code> is a window name, <code>justification</code> is either <code>left</code>, <code>center</code>, or <code>right</code>, and <code>num</code> and <code>denom</code> are numbers specifying a ratio giving the relative position about which the titlebar is justified. The ratio is measured from left to right if the numerator is positive, and right to left if negative. A denominator of <code>0</code> indicates that the numerator should be measured in pixels. For convenience, the ratio <code>0/0</code> is the same as <code>1/2</code> for center and <code>-1/1</code> for right. For example, <pre>SqueezeTitle { "XTerm" left 0 0 "xterm1" left 1 3 "xterm2" left 2 3 "oclock" center 0 0 "emacs" right 0 0 }</pre> The <code>DontSqueezeTitle</code> list can be used to turn off squeezing on certain titles.
<code>StartIconified</code> <code>[{ win-list }]</code>	This variable indicates that client windows should initially be left as icons until explicitly deiconified by the user. If the optional <code>win-list</code> is given, only those windows will be started iconic. This is useful for programs that do not support an <code>-iconic</code> command-line option or resource.
<code>TitleBackground string</code> <code>[{ win-list }]</code>	This variable specifies the background color used in titlebars, and may only be specified inside of a <code>Color</code> , <code>Grayscale</code> , or <code>Monochrome</code> list. The optional <code>win-list</code> is a list of window names and colors so that per-window colors may be specified. The default is white.
<code>TitleButtonBorderWidth</code> <code>pixels</code>	This variable specifies the width in pixels of the border surrounding titlebuttons. This is typically set to <code>0</code> to allow titlebuttons to take up as much space as possible and to not have a border. The default is <code>1</code> .

<code>TitleFont</code> string	This variable specifies the font to be used for displaying window names in titlebars. The default is <code>variable</code> .
<code>TitleForeground</code> string { { win-list } }	This variable specifies the foreground color used in titlebars, and may only be specified inside of a <code>Color</code> , <code>Grayscale</code> , or <code>Monochrome</code> list. The optional <code>win-list</code> is a list of window names and colors so that per-window colors may be specified. The default is <code>black</code> .
<code>TitlePadding</code> pixels	This variable specifies the distance between the various buttons, text, and highlight areas in the titlebar. The default is 8 pixels.
<code>UnknownIcon</code> string	This variable specifies the filename of a bitmap file to be used as the default icon. This bitmap will be used as the icon of all clients that do not provide an icon bitmap and are not listed in the <code>Icons</code> list.
<code>UsePPosition</code> string	This variable specifies whether or not <code>twm</code> should honor program-requested locations (given by the <code>PPosition</code> flag in the <code>WM_NORMAL_HINTS</code> property) in the absence of a user-specified position. The argument <code>string</code> may have one of three values: <code>off</code> (the default), indicating that <code>twm</code> should ignore the program-supplied position; <code>on</code> , indicating that the position should be used; and <code>non-zero</code> , indicating that the position should used if it is other than <code>(0,0)</code> . The latter option is for working around a bug in older toolkits.
<code>WarpCursor</code> { { win-list } }	This variable indicates that the pointer should be warped into windows when they are deiconified. If the optional <code>win-list</code> is given, the pointer will only be warped when those windows are deiconified.
<code>WindowRing</code> { win-list }	This variable specifies a list of windows along which the <code>f.warping</code> function cycles.
<code>WarpUnmapped</code>	This variable indicates that the <code>f.warpto</code> function should deiconify any iconified windows it encounters. This is typically used to make a key binding that will pop up a particular window (such as <code>xmh</code>) no matter where it is. The default is for <code>f.warpto</code> to ignore iconified windows.
<code>XorValue</code> number	This variable specifies the value to use when drawing window outlines for moving and resizing. This should be set to a value that will result in a variety of distinguishable colors when exclusive <code>OR</code> is used with the contents of the user's typical screen. Setting this variable to 1 often gives nice results if adjacent colors in the default colormap are distinct. By default, <code>twm</code> will attempt to cause temporary lines to appear at the opposite end of the colormap from the graphics.
<code>Zoom</code> [count]	This variable indicates that outlines suggesting movement of a window to and from its iconified state should be displayed whenever a window is iconified or deiconified. The optional <code>count</code> argument specifies the number of outlines to be drawn. The default <code>count</code> is 8.

The following variables must be set after the fonts have been assigned, so it is usually best to put them at the end of the variables or at the beginning of the bindings sections:

<code>DefaultFunction</code> function	This variable specifies the function to be executed when a key or button event is received for which no binding is provided. This is typically bound to <code>f.nop</code> , <code>f.beep</code> , or a menu containing window operations.
<code>WindowFunction</code> function	This variable specifies the function to execute when a window is selected from the <code>TwmWindows</code> menu. If this variable is not set, the window will be deiconified and raised.

BINDINGS

After the desired variables have been set, functions may be attached titlebuttons and key and pointer buttons. Titlebuttons may be added from the left or right side and appear in the titlebar from left to right according to the order in which they are specified. Key and pointer button bindings may be given in any order.

Titlebuttons' specifications must include the name of the pixmap to use in the button box and the function to be invoked when a pointer button is pressed within them:

```
0 LeftTitleButton "bitmapname"=function
```

or

```
0 RightTitleButton "bitmapname"=function
```

The `bitmapname` may refer to one of the built-in bitmaps (which are scaled to match `Title-Font`) by using the appropriate colon-prefixed name described earlier.

Key and pointer button specifications must give the modifiers that must be pressed, over which parts of the screen the pointer must be, and what function is to be invoked. Keys are given as strings containing the appropriate `keysym` name; buttons are given as the keywords `Button1-Button5`: `0 "FP1" = modlist : context : function Button1 = modlist : context : function`

The `modlist` is any combination of the modifier names `shift`, `control`, `lock`, `meta`, `mod1`, `mod2`, `mod3`, `mod4`, or `mod5` (which may be abbreviated as `s`, `c`, `l`, `m`, `m1`, `m2`, `m3`, `m4`, `m5`, respectively) separated by a vertical bar (`|`). Similarly, the `context` is any combination of `window`, `title`, `icon`, `root`, `frame`, `iconmgr`, their first letters (`iconmgr` abbreviation is `m`), or `all`, separated by a vertical bar. The function is any of the `f` keywords described in the following list. For example, the default startup file contains the following bindings:

```
Button1 = : root : f.menu "TwmWindows"
Button1 = m : window | icon : f.function "move-or-lower"
Button2 = m : window | icon : f.iconify
Button3 = m : window | icon : f.function "move-or-raise"
Button1 = : title : f.function "move-or-raise"
Button2 = : title : f.raiselower
Button1 = : icon : f.function "move-or-iconify"
Button2 = : icon : f.iconify
Button1 = : iconmgr : f.iconify
Button2 = : iconmgr : f.iconify
```

A user who wanted to be able to manipulate windows from the keyboard could use the following bindings:

```
"F1" = : all : f.iconify
"F2" = : all : f.raiselower
"F3" = : all : f.warping "next"
"F4" = : all : f.warpto "xmh"
"F5" = : all : f.warpto "emacs"
"F6" = : all : f.colormap "next"
"F7" = : all : f.colormap "default"
"F20" = : all : f.warptoscreen "next"
"Left" = m : all : f.backiconmgr
"Right" = m | s : all : f.forwiconmgr
"Up" = m : all : f.upiconmgr
"Down" = m | s : all : f.downiconmgr
```

`twm` provides many more window manipulation primitives than can be conveniently stored in a titlebar, menu, or set of key bindings. Although a small set of defaults is supplied (unless the `NoDefaults` is specified), most users will want to have their most common operations bound to key and button strokes. To do this, `twm` associates names with each of the primitives and provides user-defined functions for building higher level primitives and menus for interactively selecting among groups of functions.

User-defined functions contain the name by which they are referenced in calls to `f.function` and a list of other functions to execute. For example,

```
Function "move-or-lower" { f.move f.deltastop f.lower }
Function "move-or-raise" { f.move f.deltastop f.raise }
Function "move-or-iconify" { f.move f.deltastop f.iconify }
Function "restore-colormap" { f.colormap "default" f.lower }
```

The function name must be used in `f.function` exactly as it appears in the function specification.

In the following descriptions, if the function is said to operate on the selected window, but is invoked from a root menu, the cursor will be changed to the Select cursor and the next window to receive a button press will be chosen:

<code>! string</code>	This is an abbreviation for <code>f.exec string</code> .
<code>f.autoraise</code>	This function toggles whether or not the selected window is raised whenever entered by the pointer. See the description of the variable <code>AutoRaise</code> .
<code>f.backiconmgr</code>	This function warps the pointer to the previous column in the current icon manager, wrapping back to the previous row if necessary.
<code>f.beep</code>	This function sounds the keyboard bell.
<code>f.bottomzoom</code>	This function is similar to the <code>f.fullzoom</code> function, but resizes the window to fill only the bottom half of the screen.
<code>f.circledown</code>	This function lowers the topmost window that occludes another window.
<code>f.circlepup</code>	This function raises the bottommost window that is occluded by another window.
<code>f.colormap string</code>	This function rotates the colormaps (obtained from the <code>WM_COLORMAP_WINDOWS</code> property on the window) that <code>twm</code> will display when the pointer is in this window. The argument <code>string</code> may have one of the following values: <code>next</code> , <code>prev</code> , and <code>default</code> . It should be noted here that in general, the installed colormap is determined by keyboard focus. A pointer-driven keyboard focus will install a private colormap upon entry of the window owning the colormap. Using the click-to-type model, private colormaps will not be installed until the user clicks on the target window.
<code>f.deiconify</code>	This function deiconifies the selected window. If the window is not an icon, this function does nothing.
<code>f.delete</code>	This function sends the <code>WM_DELETE_WINDOW</code> message to the selected window if the client application has requested it through the <code>WM_PROTOCOLS</code> window property. The application is supposed to respond to the message by removing the indicated window. If the window has not requested <code>WM_DELETE_WINDOW</code> messages, the keyboard bell will be rung, indicating that the user should choose an alternative method. Note this is very different from <code>f.destroy</code> . The intent here is to delete a single window, not necessarily the entire application.
<code>f.deltastop</code>	This function allows a user-defined function to be aborted if the pointer has been moved more than <code>MoveDelta</code> pixels. See the example definition given for Function "move-or-raise" at the beginning of the section.
<code>f.destroy</code>	This function instructs the X server to close the display connection of the client that created the selected window. This should only be used as a last resort for shutting down runaway clients. See also <code>f.delete</code> .
<code>f.downiconmgr</code>	This function warps the pointer to the next row in the current icon manger, wrapping to the beginning of the next column if necessary.
<code>f.exec string</code>	This function passes the argument <code>string</code> to <code>/bin/sh</code> for execution. In multiscreen mode, if <code>string</code> starts a new X client without giving a display argument, the client will appear on the screen from which this function was invoked.
<code>f.focus</code>	This function toggles the keyboard focus of the server to the selected window, changing the focus rule from pointer-driven if necessary. If the selected window already was focused, this function executes an <code>f.unfocus</code> .

<code>f.forcemove</code>	This function is like <code>f.move</code> except that it ignores the <code>DontMoveOff</code> variable.
<code>f.forwiconmgr</code>	This function warps the pointer to the next column in the current icon manager, wrapping to the beginning of the next row if necessary.
<code>f.fullzoom</code>	This function resizes the selected window to the full size of the display or else restores the original size if the window was already zoomed.
<code>f.function string</code>	This function executes the user-defined function whose name is specified by the argument <code>string</code> .
<code>f.hbzoom</code>	This function is a synonym for <code>f.bottomzoom</code> .
<code>f.hideiconmgr</code>	This function unmaps the current icon manager.
<code>f.horizoom</code>	This variable is similar to the <code>f.zoom</code> function except that the selected window is resized to the full width of the display.
<code>f.htzoom</code>	This function is a synonym for <code>f.topzoom</code> .
<code>f.hzoom</code>	This function is a synonym for <code>f.horizoom</code> .
<code>f.iconify</code>	This function iconifies or deiconifies the selected window or icon, respectively.
<code>f.identify</code>	This function displays a summary of the name and geometry of the selected window. If the server supports the <code>SYNC</code> extension, the priority of the client owning the window is also displayed. Clicking the pointer or pressing a key in the window will dismiss it.
<code>f.lefticonmgr</code>	This function is similar to <code>f.backiconmgr</code> except that wrapping does not change rows.
<code>f.leftzoom</code>	This variable is similar to the <code>f.bottomzoom</code> function but causes the selected window to be resized only on the left half of the display.
<code>f.lower</code>	This function lowers the selected window.
<code>f.menu string</code>	This function invokes the menu specified by the argument <code>string</code> . Cascaded menus may be built by nesting calls to <code>f.menu</code> .
<code>f.move</code>	This function drags an outline of the selected window (or the window itself if the <code>OpaqueMove</code> variable is set) until the invoking pointer button is released. Double-clicking within the number of milliseconds given by <code>ConstrainedMoveTime</code> warps the pointer to the center of the window and constrains the move to be either horizontal or vertical, depending on which grid line is crossed. To abort a move, press another button before releasing the first button.
<code>f.nexticonmgr</code>	This function warps the pointer to the next icon manager containing any windows on the current or any succeeding screen.
<code>f.nop</code>	This function does nothing and is typically used with the <code>Default-Function</code> or <code>WindowFunction</code> variables or to introduce blank lines in menus.
<code>f.previceonmgr</code>	This function warps the pointer to the previous icon manager containing any windows on the current or preceding screens.
<code>f.priority string</code>	This function sets the priority of the client owning the selected window to the numeric value of the argument <code>string</code> , which should be a signed integer in double quotes (for example, "999"). This function has an effect only if the server supports the <code>SYNC</code> extension.
<code>f.quit</code>	This function causes <code>twm</code> to restore the window's borders and exit. If <code>twm</code> is the first client invoked from <code>xdm</code> , this will result in a server reset.
<code>f.raise</code>	This function raises the selected window.
<code>f.raiselower</code>	This function raises the selected window to the top of the stacking order if it is occluded by any windows; otherwise, the window is lowered.
<code>f.refresh</code>	This function causes all windows to be refreshed.
<code>f.resize</code>	This function displays an outline of the selected window. Crossing a border (or setting <code>AutoRelativeResize</code>) will cause the outline to begin to rubber band until the invoking button is released. To abort a resize, press another button before releasing the first button.
<code>f.restart</code>	This function kills and restarts <code>twm</code> .
<code>f.righticonmgr</code>	This function is similar to <code>f.nexticonmgr</code> except that wrapping does not change rows.

<code>f.rightzoom</code>	This variable is similar to the <code>f.bottomzoom</code> function except that the selected window is only resized to the right half of the display.
<code>f.saveyourself</code>	This function sends a <code>WM_SAVEYOURSELF</code> message to the selected window if it has requested the message in its <code>WM_PROTOCOLS</code> window property. Clients that accept this message are supposed to checkpoint all states associated with the window and update the <code>WM_COMMAND</code> property as specified in the <code>ICCCM</code> . If the selected window has not been selected for this message, the keyboard bell will be rung.
<code>f.showiconmgr</code>	This function maps the current icon manager.
<code>f.sorticonmgr</code>	This function sorts the entries in the current icon manager alphabetically. See the variable <code>SortIconManager</code> .
<code>f.title</code>	This function provides a centered, unselectable item in a menu definition. It should not be used in any other context.
<code>f.topzoom</code>	This variable is similar to the <code>f.bottomzoom</code> function except that the selected window is only resized to the top half of the display.
<code>f.unfocus</code>	This function resets the focus back to pointer-driven. This should be used when a focused window is no longer desired.
<code>f.upiconmgr</code>	This function warps the pointer to the previous row in the current icon manager, wrapping to the last row in the same column if necessary.
<code>f.vlzoom</code>	This function is a synonym for <code>f.leftzoom</code> .
<code>f.vrzoom</code>	This function is a synonym for <code>f.rightzoom</code> .
<code>f.warp ring string</code>	This function warps the pointer to the next or previous window (as indicated by the argument <code>string</code> , which may be "next" or "prev") specified in the <code>WindowRing</code> variable.
<code>f.warpto string</code>	This function warps the pointer to the window that has a name or class that matches <code>string</code> . If the window is iconified, it will be deiconified if the variable <code>WarpUnmapped</code> is set or else ignored.
<code>f.warptoiconmgr string</code>	This function warps the pointer to the icon manager entry associated with the window containing the pointer in the icon manager specified by the argument <code>string</code> . If <code>string</code> is empty (that is, ""), the current icon manager is chosen.
<code>f.warptoscreen string</code>	This function warps the pointer to the screen specified by the argument <code>string</code> . <code>string</code> may be a number (such as "0" or "1"), the word "next" (indicating the current screen plus 1, skipping over any unmanaged screens), the word "back" (indicating the current screen minus 1, skipping over any unmanaged screens), or the word "prev" (indicating the last screen visited).
<code>f.winrefresh</code>	This function is similar to the <code>f.refresh</code> function except that only the selected window is refreshed.
<code>f.zoom</code>	This function is similar to the <code>f.fullzoom</code> function, except that only the height of the selected window is changed.

MENUS

Functions may be grouped and interactively selected using pop-up (when bound to a pointer button) or pull-down (when associated with a titlebutton) menus. Each menu specification contains the name of the menu as it will be referred to by `f.menu`, optional default foreground and background colors, the list of item names and the functions they should invoke, and optional foreground and background colors for individual items:

```
Menu "menuname" [("deffore":"defback") ] { string1 [("fore1":"backn")] function1 string2
[("fore2":"backn")] function2 ...stringN [("foreN":"backN")] functionN }
```

The `menuname` is case-sensitive. The optional `deffore` and `defback` arguments specify the foreground and background colors used on a color display to highlight menu entries. The `string` portion of each menu entry will be the text that will appear in the menu. The optional `fore` and `back` arguments specify the foreground and background colors of the menu entry when the

pointer is not in the entry. These colors will only be used on a color display. The default is to use the colors specified by the `MenuForeground` and `MenuBackground` variables. The function portion of the menu entry is one of the functions, including any user-defined functions, or additional menus.

There is a special menu named `TwmWindows` that contains the names of all of the client and twm-supplied windows. Selecting an entry will cause the `WindowFunction` to be executed on that window. If `WindowFunction` hasn't been set, the window will be deiconified and raised.

ICONS

twm supports several different ways of manipulating iconified windows. The common pixmap-and-text style may be laid out by hand or automatically arranged as described by the `IconRegion` variable. In addition, a terse grid of icon names, called an icon manager, provides a more efficient use of screen space as well as the ability to navigate among windows from the keyboard.

An icon manager is a window that contains names of selected windows or all windows currently on the display. In addition to the window name, a small button using the default iconify symbol will be displayed to the left of the name when the window is iconified. By default, clicking on an entry in the icon manager performs `f.iconify`. To change the actions taken in the icon manager, use the `iconmgr` context when specifying button and keyboard bindings.

If you move the pointer into the icon manager, the keyboard focus is also directed to the indicated window (setting the focus explicitly or else sending synthetic events `NoTitleFocus` is set). Using the `f.upiconmgr`, `f.downiconmgr`, `f.lefticonmgr`, and `f.righticonmgr` functions, the input focus can be changed between windows directly from the keyboard.

BUGS

The resource manager should have been used instead of all of the window lists.

The `IconRegion` variable should take a list.

Double-clicking very fast to get the constrained move function will sometimes cause the window to move, even though the pointer is not moved.

If `IconifyByUnmapping` is on and windows are listed in `IconManagerDontShow` but not in `DontIconifyByUnmapping`, they may be lost if they are iconified and no bindings to `f.menu "TwmWindows"` or `f.warpto` are setup.

FILES

```
$HOME/.twmrc.<screen number>
$HOME/.twmrc
<XRoot>/lib/X11/twm/system.twmrc
```

ENVIRONMENT VARIABLES

DISPLAY This variable is used to determine which x server to use. It is also set during `f.exec` so that programs come up on the proper screen.

HOME This variable is used as the prefix for files that begin with a tilde and for locating the twm startup file.

SEE ALSO

`x(1)`, `Xserver(1)`, `xdm(1)`, `xrdb(1)`

AUTHORS

Tom LaStrange, Solbourne Computer; Jim Fulton, MIT X Consortium; Steve Pitschke, Stardent Computer; Keith Packard, MIT X Consortium; Dave Payne, Apple Computer.

SEE ALSO

`x(1)`, `Xserver(1)`, `x`

txt2gcal

txt2gcal—Creates a verbatim gcal resource file from a text file

SYNOPSIS

```
txt2gcal [ --help | --version ] [ [ Text-file | - ][Date-part ]
```

DESCRIPTION

txt2gcal is a program that creates a verbatim gcal resource file from a text file. If no `text-file` or `-` argument is given, the program reads and processes all input received from the standard input channel. If no `date-part` argument is given, txt2gcal creates a `0` for the date part. All results are always shown on the standard output channel. An exit status of `0` means all processing is successfully done; any other value means an error has occurred.

OPTIONS

```
--help      Print a usage message listing all available options, then exit successfully.
--version   Print the version number, then exit successfully.
```

COPYRIGHT

Copyright© 1996 Thomas Esken. This software doesn't claim completeness, correctness, or usability. On principle, I will not be liable for any damages or losses (implicit or explicit), which result from using or handling my software. If you use this software, you agree without any exception to this agreement, which binds you legally.

txt2cal is free software and distributed under the terms of the GNU General Public License; published by the Free Software Foundation; version 2 or (at your option) any later version.

Any suggestions, improvements, extensions, bug reports, donations, proposals for contract work, and so forth are welcome. If you like this tool, I'd appreciate a postcard from you!

Enjoy it =8~)

AUTHOR

Thomas Esken (esken@uni-muenster.de)
 m Hagenfeld 84
 D-48147 Muenster; Germany
 Phone : +49 251 232585

SEE ALSO

gcal(1), tcal(1)

16 July 1996

ul

ul—Do underlining

SYNOPSIS

```
ul [-i] [-t terminal] [name ...]
```

DESCRIPTION

ul reads the named files (or standard input if none are given) and translates occurrences of underscores to the sequence that indicates underlining for the terminal in use, as specified by the environment variable `TERM`. The file `/etc/termcap` is read to determine the appropriate sequences for underlining. If the terminal is incapable of underlining but is capable of a standout

mode, then that is used instead. If the terminal can overstrike, or handles underlining automatically, `u1` degenerates to `cat(1)`. If the terminal cannot underline, underlining is ignored.

The following options are available:

- `-i` Underlining is indicated by a separate line containing appropriate dashes `-`; this is useful when you want to look at the underlining which is present in an `nroff` output stream on a CRT terminal.
- `-t terminal` Overrides the terminal type specified in the environment with `terminal`.

ENVIRONMENT

The following environment variable is used

- TERM** Relates a `tty` device with its device capability description; see `termcap(5)`. `TERM` is set at login time, either by the default terminal type specified in `/etc/ttys` or as set during the login process by the user in the login file; see `setenv(1)`.

SEE ALSO

`man(1)`, `nroff(1)`, `colcrt(1)`

BUGS

`nroff` usually outputs a series of backspaces and underlines intermixed with the text to indicate underlining. No attempt is made to optimize the backward motion.

HISTORY

The `u1` command appeared in BSD 3.0.

BSD 4, 6 June 1993

unexpand

`unexpand`—Convert spaces to tabs

SYNOPSIS

```
unexpand [-tab1[,tab2[,...]] [-t tab1[,tab2[,...]]] [-a][--tabs=tab1[,tab2[,...]]]
[--all] [--help] [--version] [file...]
```

DESCRIPTION

This manual page documents the GNU version of `unexpand`. `unexpand` writes the contents of each given file, or the standard input if none are given or when a file named `-` is given, to the standard output, with strings of two or more space or tab characters converted to as many tabs as possible followed by as many spaces as are needed. By default, `unexpand` converts only initial spaces and tabs (those that precede all characters that aren't spaces or tabs) on each line. It preserves backspace characters in the output; they decrement the column count for tab calculations. By default, tabs are set at every 8th column.

OPTIONS

- `-, -t, --tabs tab1[,tab2[,...]]` If only one tab stop is given, set the tabs `tab1` spaces apart instead of the default 8. Otherwise, set the tabs at columns `tab1`, `tab2`, and so on (numbered from 0) and leave spaces and tabs beyond the tab stops given unchanged. If the tab stops are specified with the `-t` or `--tabs` option, they can be separated by blanks as well as by commas. This option implies the `-a` option.
- `-a, --all` Convert all strings of two or more spaces or tabs, not just initial ones, to tabs.
- `--help` Print a usage message and exit with a non-zero status.
- `--version` Print version information on standard output, then exit.

uniq

uniq—Remove duplicate lines from a sorted file

SYNOPSIS

```
uniq [-cdu] [-f skip-fields] [-s skip-chars] [-w check-chars] [-#skip-fields]
[+#skip-chars] [--count] [--repeated] [--unique] [--skip-fields=skip-fields]
[--skip-chars=skip-chars] [--check-chars=check-chars] [--help] [--version]
[infile] [outfile]
```

DESCRIPTION

This manual page documents the GNU version of `uniq`. `uniq` prints the unique lines in a sorted file, discarding all but one of a run of matching lines. It can optionally show only lines that appear exactly once, or lines that appear more than once. `uniq` requires sorted input because it compares only consecutive lines.

If the output file is not specified, `uniq` writes to the standard output. If the input file is not specified, it reads from the standard input.

OPTIONS

<code>-u, --unique</code>	Only print unique lines
<code>-d, --repeated</code>	Only print duplicate lines
<code>-c, --count</code>	Print the number of times each line occurred along with the line
<code>-number, -f,</code> <code>--skip-fields=number</code>	In this option, <code>number</code> is an integer representing the number of fields to skip over before checking for uniqueness. The first <code>number</code> fields, along with any blanks found before <code>number</code> fields is reached, are skipped over and not counted. Fields are defined as a strings of <code>nonspace</code> , <code>nontab</code> characters that are separated from each other by spaces and tabs.
<code>+number, -s,</code> <code>--skip-chars=number</code>	In this option, <code>number</code> is an integer representing the number of characters to skip over before checking for uniqueness. The first <code>number</code> characters, along with any blanks found before <code>number</code> characters is reached, are skipped over and not counted. If you use both the field and character skipping options, fields are skipped over first.
<code>-w,</code> <code>--check-chars=number</code>	Specify the number of characters to compare in the lines, after skipping any specified fields and characters. Normally, the entire remainder of the lines are compared.
<code>--help</code>	Print a usage message and exit with a non-zero status.
<code>--version</code>	Print version information on standard output, then exit.

GNU Text Utilities

unshar

unshar—Unpack a shar file

SYNOPSIS

```
unshar [ -d directory ] [ -c ][-e | -E exit_line ] [ file ... ]
```

DESCRIPTION

`unshar` scans mail messages looking for the start of a shell archive. It then passes the archive through a copy of the shell to unpack it. It will accept multiple files. If no files are given, standard input is used. This manual page reflects `unshar` version 4.0.

OPTIONS

Options have a one-letter version starting with `-` or a long version starting with `--`. The exceptions are `--help` and `--version`, which don't have a short version.

<code>--version</code>	Print the version number of the program on standard output, then immediately exit.
<code>--help</code>	Print a help summary on standard output, then immediately exit.
<code>-d DIRECTORY</code>	Change directory to <code>DIRECTORY</code>
<code>--directory=DIRECTORY</code>	before unpacking any files.
<code>-c --overwrite</code>	Passed as an option to the <code>shar</code> file. Many shell archive scripts (including those produced by <code>shar 3.40</code> and newer) accept a <code>-c</code> argument to indicate that existing files should be overwritten.
<code>-e --exit-0</code>	This option exists mainly for people who collect many shell archives into a single mail folder. With this option, <code>unshar</code> isolates each different shell archive from the others that have been put in the same file, unpacking each in turn, from the beginning of the file towards its end. Its proper operation relies on the fact that many <code>shar</code> files are terminated by an <code>exit 0</code> at the beginning of a line. Option <code>-e</code> is internally equivalent to <code>-E "exit 0"</code> .
<code>-E STRING</code>	This option works like <code>-e</code> , but it allows you to specify the string that separates archives if <code>exit 0</code> isn't appropriate. For example, noticing that most <code>.signatures</code> have a <code>--</code> on a line right before them, one can sometimes use <code>--split-at=--</code> for splitting shell archives that lack the <code>exit 0</code> line at end. The signature will then be skipped altogether with the headers of the following message.
<code>--split-at=STRING</code>	

SEE ALSO

`shar(1)`

DIAGNOSTICS

Any message from the shell may be displayed.

AUTHORS

Michael Mauldin at Carnegie-Mellon University, Guido van Rossum at CWI, Amsterdam (guido@mcvax), Bill Davidsen (davidsen@sixhub.uuxp), Warren Tucker (wht%40gatech.edu)
Richard H. Gumpertz (rhg@CPS.COM), and Colas Nahaboo (colas@avahi.inria.fr). Man pages by Jan Djfrv (jhd@irfu.se).

12 August 1990

updatedb

`updatedb`—Update a filename database

SYNOPSIS

`updatedb [options]`

DESCRIPTION

This manual page documents the GNU version of `updatedb`, which updates filename databases used by GNU `locate`. The filename databases contain lists of files that were in particular directory trees when the databases were last updated. The filename of the default database is determined when `locate` and `updatedb` are configured and installed. The frequency with which the databases and the directories for which they contain entries are updated depends on how often `updatedb` is run,

and with which arguments. In networked environments, it often makes sense to build a database at the root of each filesystem, containing the entries for that filesystem. To prevent thrashing the network, `updatedb` is then run for each filesystem on the filesystem where that filesystem is on a local disk. Users can select which databases locate searches using an environment variable or command-line option; see `locate(1L)`. Databases can not be concatenated together. The filename database format changed starting with GNU `find` and `locate` version 4.0 to allow machines with different byte orderings to share the databases. The new GNU `locate` can read both the old and new database formats. However, old versions of `locate` and `find` produce incorrect results if given a new-format database.

OPTIONS

<code>--localpaths='path1 path2...'</code>	Nonnetwork directories to put in the database. Default is <code>/</code> .
<code>--netpaths='path1 path2...'</code>	Network (NFS, AFS, RFS, and so on) directories to put in the database. Default is none.
<code>--prunepaths='path1 path2...'</code>	Directories to not put in the database, which would otherwise be put there. Default is <code>/tmp /usr/tmp /var/tmp /afs</code> .
<code>--output=dbfile</code>	The database file to build. Default is system-dependent, but typically <code>/usr/local/var/locatedb</code> .
<code>--netuser=user</code>	The user to search network directories as, using <code>su(1)</code> . Default is <code>daemon</code> .
<code>--old-format</code>	Create the database in the old format instead of the new one.
<code>--version</code>	Print the version number of <code>updatedb</code> and exit.
<code>--help</code>	Print a summary of the options to <code>updatedb</code> and exit.

SEE ALSO

`find(1L)`, `locate(1L)`, `locatedb(5L)`, `xargs(1L)` *Finding Files* (online in `info`, or printed)

uptime

`uptime`—Tell how long the system has been running

SYNOPSIS

`uptime`

DESCRIPTION

`uptime` gives a one-line display of the information that follows it: the current time, how long the system has been running, how many users are currently logged on, and the system load averages for the past 1, 5, and 15 minutes.

This is the same information contained in the header line displayed by `w(1)`.

FILES

<code>/var/run/utmp</code>	Information about who is currently logged on
<code>/proc</code>	Process information

AUTHORS

`uptime` was written by Larry Greenfield (`greenfie@gauss.rutgers.edu`) and Michael K. Johnson (`johnsonm@sunsite.unc.edu`).

SEE ALSO

`ps(1)`, `top(1)`, `utmp(5)`, `w(1)`

userlist

userlist—User listing of who's on your system

SYNOPSIS

userlist

DESCRIPTION

This program simply gives you a listing of who is connected to your system. It is used primarily in the sorted listing that utilizes the same method of display for a more uniform output between systems. It also made more sense to do it this way instead of having jumbled up display listings in sorted finger displays. Besides, it made more sense to do this than use finger. :)

This program functions with the same types of things in mind that cfingerd does. If the user has a .nofinger file, his or her username will not be displayed in the user listing.

Example output is shown as

```
Username Real Name Idletime TTY Remote console username I'm real ... 9d 23:59 0
(remote.site.com)
```

where it would display the user's login name, the user's real name, the user's idle time given in the format "dd hh:mm", the TTY, and the remote location (or where the user is telnetting from).

If the username is more than a certain number of characters, the program will not search for their information in the passwd file because it may be too long. Besides, it checks getpwnam, anyway.

CONTACTING

If you like this program, have any suggestions on how it could be modified, or have bug reports, please write to khollis@bitgate.com.

Your continued public domain support is appreciated! Thanks.

SEE ALSO

cfingerd.conf(5), cfingerd(8), finger(1)

Userlist 0.0.1, 26 August 1995

uucp

uucp—UNIX-to-UNIX copy

SYNOPSIS

uucp [options] source-file destination-file

uucp [options] source-file... destination-directory

DESCRIPTION

The uucp command copies files between systems. Each file argument is either a pathname on the local machine or is of the form

system!path

which is interpreted as being on a remote system. In the first form, the contents of the first file are copied to the second. In the second form, each source file is copied into the destination directory.

A file be transferred to or from `system2` via `system1` by using
`system1!system2!path`

Any pathname that does not begin with `/` or `~` will be appended to the current directory (unless the `-W` or `--noexpand` option is used); this resulting path will not necessarily exist on a remote system. A pathname beginning with a simple `~` starts at the `uucp` public directory; a pathname beginning with `~name` starts at the home directory of the named user. The `~` is interpreted on the appropriate system. Note that some shells will interpret a simple `~` to the local home directory before `uucp` sees it; to avoid this, the `~` must be quoted.

Shell metacharacters `? * [ ]` are interpreted on the appropriate system, assuming they are quoted to prevent the shell from interpreting them first.

The copy does not take place immediately, but is queued up for the `uucico(8)` daemon; the daemon is started immediately unless the `-r` or `--nouucico` switch is given. In any case, the next time the remote system is called, the file(s) will be copied.

OPTIONS

The following options may be given to `uucp`.

<code>-c, --nocopy</code>	Do not copy local source files to the spool directory. If they are removed before being processed by the <code>uucico(8)</code> daemon, the copy will fail. The files must be readable by the <code>uucico(8)</code> daemon, and by the invoking user.
<code>-C, --copy</code>	Copy local source files to the spool directory. This is the default.
<code>-d, --directories</code>	Create all necessary directories when doing the copy. This is the default.
<code>-f, --nodirectories</code>	If any necessary directories do not exist for the destination path, abort the copy.
<code>-g grade, --grade grade</code>	Set the grade of the file transfer command. Jobs of a higher grade are executed first. Grades run <code>0 ... 9 A ... Z a ... z</code> from high to low.
<code>-m, --mail</code>	Report completion or failure of the file transfer by <code>mail(1)</code> .
<code>-n user, --notify user</code>	Report completion or failure of the file transfer by <code>mail(1)</code> to the named user on the remote system.
<code>-r, --nouucico</code>	Do not start <code>uucico(8)</code> daemon immediately; merely queue up the file transfer for later execution.
<code>-j, --jobid</code>	Print <code>jobid</code> on standard output. The job may be later canceled by passing the <code>jobid</code> to the <code>-k</code> switch of <code>uustat(1)</code> . It is possible for some complex operations to produce more than one <code>jobid</code> , in which case, each will be printed on a separate line. For example, <code>uucp sys1!~user1/file1 sys2!~user2/file2 ~user3</code> will generate two separate jobs, one for the system <code>sys1</code> and one for the system <code>sys2</code> .
<code>-W, --noexpand</code>	Do not prepend remote relative pathnames with the current directory.
<code>-x type, --debug type</code>	Turn on particular debugging types. The following types are recognized: <code>abnormal</code> , <code>chat</code> , <code>handshake</code> , <code>uucp-proto</code> , <code>proto</code> , <code>port</code> , <code>config</code> , <code>spooldir</code> , <code>execute</code> , <code>incoming</code> , <code>outgoing</code> . Only <code>abnormal</code> , <code>config</code> , <code>spooldir</code> , and <code>execute</code> are meaningful for <code>uucp</code> . Multiple types may be given, separated by commas, and the <code>--debug</code> option may appear multiple times. A number may also be given, which will turn on that many types from the foregoing list; for example, <code>--debug 2</code> is equivalent to <code>--debug abnormal,chat</code> .
<code>-I file, --config file</code>	Set configuration file to use. This option may not be available, depending upon how <code>uucp</code> was compiled.
<code>-v, --version</code>	Report version information and exit.
<code>--help</code>	Print a help message and exit.

FILES

The filenames may be changed at compilation time or by the configuration file, so these are only approximations.

<code>/usr/lib/uucp/config</code>	Configuration file
<code>/usr/spool/uucpuucp</code>	Spool directory
<code>/usr/spool/uucp/Log</code>	uucp log file
<code>/usr/spool/uucppublic</code>	Default uucp public directory

SEE ALSO

`mail(1)`, `uux(1)`, `uustat(1)`, `uucico(8)`

BUGS

Some of the options are dependent on the capabilities of the `uucico(8)` daemon on the remote system.

The `-n` and `-m` switches do not work when transferring a file from one remote system to another.

File modes are not preserved, except for the execute bit. The resulting file is owned by the uucp user.

AUTHOR

Ian Lance Taylor (ian@airs.com)

Taylor UUCP 1.05

uuencode

`uuencode`—Encode a binary file

`uudecode`—Decode a file created by `uuencode`

SYNOPSIS

`uuencode [-m] [ file ] name`

`uudecode [-o outfile] [ file ]...`

DESCRIPTION

`uuencode` and `uudecode` are used to transmit binary files over transmission mediums that do not support other than simple ASCII data.

`uuencode` reads `file` (or by default the standard input) and writes an encoded version to the standard output. The encoding uses only printing ASCII characters and includes the mode of the file and the operand name for use by `uudecode`. If `name` is `/dev/stdout`, the result will be written to standard output. By default, the standard uu encoding format will be used. If the option `-m` is given on the command line, `base64` encoding is used instead.

`uudecode` transforms uuencoded files (or by default, the standard input) into the original form. The resulting file is named `name` (or `outfile` if the `-o` option is given) and will have the mode of the original file except that `setuid` and `execute` bits are not retained. If `outfile` or `name` is `/dev/stdout`, the result will be written to standard output. `uudecode` ignores any leading and trailing lines. The program can automatically decide which of the supported encoding schemes are used.

EXAMPLES

The following example packages up a source tree, compresses it, uuencodes it, and mails it to a user on another system.

When `uudecode` is run on the target system, the file `src_tree.tar.Z` will be created, which may then be uncompressed and extracted into the original tree.

```
tar cf - src_tree | compress | uuencode src_tree.tar.Z | mail sys1!sys2!user
```

SEE ALSO

`compress(1)`, `mail(1)`, `uucp(1)`, `uuencode(5)`

STANDARDS

This implementation is compliant with P1003.2b/D11.

BUGS

If more than one file is given to `uudecode` and the `-o` option is given or more than one name in the encoded files is the same, the result is probably not what is expected.

The encoded form of the file is expanded by 37 percent for uu encoding and by 35 percent for base64 encoding (3 bytes become 4 plus control information).

HISTORY

The `uuencode` command appeared in BSD 4.0.

uustat

`uustat`—uucp status inquiry and control

SYNOPSIS

```
uustat -a
```

```
uustat --all
```

```
uustat [ -eKRiMNQ ][-sS system ] [ -uU user ] [ -cC command ] [ -oy hours ]
[ -B lines ] [ --executions ][--kill-all ][--rejuvenate-all ][--prompt ][--mail ]
[ --notify ][--no-list ][--system system ] [ --not-system system ] [ --user user ]
[ --not-user user ] [ --command command ] [ --not-command command ]
[ --older-than hours ] [ --younger-than hours ] [ --mail-lines lines ]
uustat [ -kr jobid ] [ --kill jobid ] [ --rejuvenate jobid ]
```

```
uustat -q [ -sS system ] [ -oy hours ] [ --system system ] [ --not-system system ]
[ --older-than hours ] [ --younger-than hours ]
```

```
uustat --list [ -sS system ] [ -oy hours ] [ --system system ]
[ --not-system system ] [ --older-than hours ] [ --younger-than hours ]
```

```
uustat -m
```

```
uustat --status
```

```
uustat -p
```

```
uustat --ps
```

DESCRIPTION

The `uustat` command can display various types of status information about the UUCP system. It can also be used to cancel or rejuvenate requests made by `uucp(1)` or `uux(1)`.

By default `uustat` displays all jobs queued up for the invoking user, as if given the `--user` option with the appropriate argument.

If any of the `-a`, `--all`, `-e`, `--executions`, `-s`, `--system`, `-S`, `--not-system`, `-u`, `--user`, `-U`, `--not-user`, `-c`, `--command`, `-C`, `--not-command`, `-o`, `--older-than`, `-y`, `--younger-than` options are given, then all jobs that match the combined specifications are displayed.

The `-k` or `--kill-all` option may be used to kill off a selected group of jobs, such as all jobs more than seven days old.

OPTIONS

The following options may be given to `uustat`.

<code>-a</code> , <code>--all</code>	List all queued file transfer requests.
<code>-e</code> , <code>--executions</code>	List queued execution requests rather than queued file transfer requests. Queued execution requests are processed by <code>uuxqt(8)</code> rather than <code>uucico(8)</code> . Queued execution requests may be waiting for some file to be transferred from a remote system. They are created by an invocation of <code>uux(1)</code> .
<code>-s system</code> , <code>--system system</code>	List all jobs queued up for the named system. These options may be specified multiple times, in which case all jobs for all the systems will be listed. If used with <code>--list</code> , only the systems named will be listed.
<code>-S system</code> , <code>--not-system system</code>	List all jobs queued for systems other than the one named. These options may be specified multiple times, in which case no jobs from any of the specified systems will be listed. If used with <code>--list</code> , only the systems not named will be listed. These options may not be used with <code>-s</code> or <code>--system</code> .
<code>-u user</code> , <code>--user user</code>	List all jobs queued up for the named user. These options may be specified multiple times, in which case all jobs for all the users will be listed.
<code>-U user</code> , <code>--not-user user</code>	List all jobs queued up for users other than the one named. These options may be specified multiple times, in which case no jobs from any of the specified users will be listed. These options may not be used with <code>-u</code> or <code>--user</code> .
<code>-c command</code> , <code>--command command</code>	List all jobs requesting the execution of the named command. If <code>command</code> is <code>ALL</code> this will list all jobs requesting the execution of some command (as opposed to simply requesting a file transfer). These options may be specified multiple times, in which case all jobs requesting any of the commands will be listed.
<code>-C command</code> , <code>--not-command command</code>	List all jobs requesting execution of some command other than the named command, or, if <code>command</code> is <code>ALL</code> , list all jobs that simply request a file transfer (as opposed to requesting the execution of some command). These options may be specified multiple times, in which case, no job requesting one of the specified commands will be listed. These options may not be used with <code>-c</code> or <code>--command</code> .
<code>-o hours</code> , <code>--older-than hours</code>	List all queued jobs older than the given number of hours. If used with <code>--list</code> , only systems whose oldest job is older than the given number of hours will be listed.
<code>-y hours</code> , <code>--younger-than hours</code>	List all queued jobs younger than the given number of hours. If used with <code>--list</code> , only systems whose oldest job is younger than the given number of hours will be listed.
<code>-k jobid</code> , <code>--kill jobid</code>	Kill the named job. The job ID is shown by the default output format, as well as by the <code>-j</code> or <code>--jobid</code> option to <code>uucp(1)</code> or <code>uux(1)</code> . A job may only be killed by the user who created the job, or by the UUCP administrator or the superuser. The <code>-k</code> or <code>--kill</code> options may be used multiple times on the command line to kill several jobs.
<code>-r jobid</code> , <code>--rejuvenate jobid</code>	Rejuvenate the named job. This will mark it as having been invoked at the current time, affecting the output of the <code>-o</code> , <code>--older-than</code> , <code>-y</code> , or <code>--younger-than</code> options and preserving it from any automated cleanup daemon. The job ID is shown by the default output format, as well as by the <code>-j</code> or <code>--jobid</code> options to <code>uucp(1)</code> or <code>uu(1)</code> . A job may only be rejuvenated by the user who created the job, or by the UUCP administrator or the superuser. The <code>-r</code> or <code>--rejuvenate</code> options may be used multiple times on the command line to rejuvenate several jobs.

<code>-q, --list</code>	Display the status of commands, executions, and conversations for all remote systems for which commands or executions are queued. The <code>-s, --system</code> , <code>-S, --not-system</code> , <code>-o, --older-than</code> , <code>-y</code> , and <code>--younger-than</code> options may be used to restrict the systems that are listed. Systems for which no commands or executions are queued will never be listed.
<code>-m, --status</code>	Display the status of conversations for all remote systems.
<code>-p, --ps</code>	Display the status of all processes holding uucp locks on systems or ports.
<code>-i, --prompt</code>	For each listed job, prompt whether to kill the job or not. If the first character of the input line is <code>y</code> or <code>Y</code> , the job will be killed.
<code>-K, --kill-all</code>	Automatically kill each listed job. This can be useful for automatic cleanup scripts, in conjunction with the <code>--mail</code> and <code>--notify</code> options.
<code>-R, --rejuvenate-all</code>	Automatically rejuvenate each listed job. This may not be used with <code>--kill-all</code> .
<code>-M, --mail</code>	For each listed job, send mail to the UUCP administrator. If the job is killed (due to <code>--kill-all</code> or <code>--prompt</code> with an affirmative response), the mail will indicate that. A comment specified by the <code>--comment</code> option may be included. If the job is an execution, the initial portion of its standard input will be included in the mail message; the number of lines to include may be set with the <code>--mail-lines</code> option (the default is 100). If the standard input contains null characters, it is assumed to be a binary file and is not included.
<code>-N, --notify</code>	For each listed job, send mail to the user who requested the job. The mail is identical to that sent by the <code>-M</code> or <code>--mail</code> options.
<code>-W, --comment</code>	Specify a comment to be included in mail sent with the <code>-M</code> , <code>--mail</code> , <code>-N</code> , or <code>--notify</code> options.
<code>-Q, --no-list</code>	Do not actually list the job, but only take any actions indicated by the <code>-i, --prompt</code> , <code>-K, --kill-all</code> , <code>-M, --mail</code> , <code>-N</code> , or <code>--notify</code> options.
<code>-x type, --debug type</code>	Turn on particular debugging types. The following types are recognized: <code>abnormal</code> , <code>chat</code> , <code>handshake</code> , <code>uucp-proto</code> , <code>proto</code> , <code>port</code> , <code>config</code> , <code>spooldir</code> , <code>execute</code> , <code>incoming</code> , <code>outgoing</code> . Only <code>abnormal</code> , <code>config</code> , <code>spooldir</code> , and <code>execute</code> are meaningful for <code>uustat</code> . Multiple types may be given, separated by commas, and the <code>--debug</code> option may appear multiple times. A number may also be given, which will turn on that many types from the foregoing list; for example, <code>--debug 2</code> is equivalent to <code>--debug abnormal,chat</code> .
<code>-I file, --config file</code>	Set configuration file to use. This option may not be available, depending upon how <code>uustat</code> was compiled.
<code>-v, --version</code>	Report version information and exit.
<code>--help</code>	Print a help message and exit.

EXAMPLES

<code>uustat -all</code>	Display status of all jobs. A sample output line is as follows: bugsA027h bugs ian 04-01 13:50 Executing rmail ian@airs.com (sending 1283 bytes) The format is jobid system user queue-date command (size) The <code>jobid</code> may be passed to the <code>--kill</code> or <code>--rejuvenate</code> options. The <code>size</code> indicates how much data is to be transferred to the remote system, and is absent for a file receive request. The <code>--system</code> , <code>--not-system</code> , <code>--user</code> , <code>--not-user</code> , <code>--command</code> , <code>--not-command</code> , <code>--older-than</code> , and <code>--younger-than</code> options may be used to control which jobs are listed.
<code>uustat -executions</code>	Display status of queued up execution requests. A sample output line is as follows: bugs bugs!ian 05-20 12:51 rmail ian The format is system requestor queue-date command The <code>--system</code> , <code>--not-system</code> , <code>--user</code> , <code>--not-user</code> , <code>--command</code> , <code>--not-command</code> , <code>--older-than</code> , and <code>--younger-than</code> options may be used to control which requests are listed.

<code>uustat -list</code>	Display status for all systems with queued-up commands. A sample output line is as follows: <pre>bugs 4C (1 hour) 0X (0 secs) 04-01 14:45 Dial failed</pre> This indicates the system, the number of queued commands, the age of the oldest queued command, the number of queued local executions, the age of the oldest queued execution, the date of the last conversation, and the status of that conversation.
<code>uustat -status</code>	Display conversation status for all remote systems. A sample output line is as follows: <pre>bugs 04-01 15:51 Conversation complete</pre> This indicates the system, the date of the last conversation, and the status of that conversation. If the last conversation failed, <code>uustat</code> will indicate how many attempts have been made to call the system. If the retry period is currently preventing calls to that system, <code>uustat</code> also displays the time when the next call will be permitted.
<code>uustat -ps</code>	Display the status of all processes holding <code>uucp</code> locks. The output format is system-dependent, as <code>uustat</code> simply invokes <code>ps(1)</code> on each process holding a lock. A sample output line is as follows: <pre>uustat -command rmail -older-than 168 -kill-all -no-list -mail -notify - comment "Queued for over 1 week"</pre> This will kill all <code>rmail</code> commands that have been queued up waiting for delivery for over one week (168 hours). For each such command, mail will be sent both to the UUCP administrator and to the user who requested the <code>rmail</code> execution. The mail message sent will include the string given by the <code>--comment</code> option. The <code>--no-list</code> option prevents any of the jobs from being listed on the terminal, so any output from the program will be error messages.

FILES

The filenames may be changed at compilation time or by the configuration file, so these are only approximations.

`/usr/lib/uucp/config` Configuration file
`/usr/spool/uucp` `uucp` spool directory

SEE ALSO

`ps(1)`, `rmail(1)`, `uucp(1)`, `uux(1)`, `uucico(8)`, `uuxqt(8)`

AUTHOR

Ian Lance Taylor (ian@airs.com)

Taylor UUCP 1.05

UUX

`uux`—Remote command execution over `uucp`

SYNOPSIS

`uux [ options ] command`

DESCRIPTION

The `uux` command is used to execute a command on a remote system, or to execute a command on the local system using files from remote systems. The command is not executed immediately; the request is queued until the `uucico(8)` daemon calls the system and executes it. The daemon is started automatically unless one of the `-r` or `--nouucico` options is given.

The actual command execution is done by the `uuxqt(8)` daemon.

File arguments can be gathered from remote systems to the execution system, as can standard input. Standard output may be directed to a file on a remote system.

The command name may be preceded by a system name followed by an exclamation point if it is to be executed on a remote system. An empty system name is taken as the local system.

Each argument that contains an exclamation point is treated as naming a file. The system that the file is on is before the exclamation point, and the pathname on that system follows it. An empty system name is taken as the local system; this must be used to transfer a file to a command being executed on a remote system. If the path is not absolute, it will be appended to the current working directory on the local system; the result may not be meaningful on the remote system. A pathname may begin with `~/`, in which case it is relative to the `uucp` public directory (usually `/usr/spool/uucppublic`) on the appropriate system. A pathname may begin with `name/`, in which case it is relative to the home directory of the named user on the appropriate system.

Standard input and output may be redirected as usual; the pathnames used may contain exclamation points to indicate that they are on remote systems. Note that the redirection characters must be quoted so that they are passed to `uux` rather than interpreted by the shell. Append redirection (`>>`) does not work.

All specified files are gathered together into a single directory before execution of the command begins. This means that each file must have a distinct base name. For example,

```
uux 'sys1!diff sys2!`user1/foo sys3!`user2/foo >!foo.diff'
```

will fail because both files will be copied to `sys1` and stored under the name `foo`.

Arguments may be quoted by parentheses to avoid interpretation of exclamation points. This is useful when executing the `uucp` command on a remote system.

OPTIONS

The following options may be given to `uux`.

<code>-,</code> <code>-p</code> , <code>--stdin</code>	Read standard input and use it as the standard input for the command to be executed.
<code>-c</code> , <code>--nocopy</code>	Do not copy local files to the spool directory. This is the default. If they are removed before being processed by the <code>uucico(8)</code> daemon, the copy will fail. The files must be readable by the <code>uucico(8)</code> daemon, as well as by the invoker of <code>uux</code> .
<code>-C</code> , <code>--copy</code>	Copy local files to the spool directory.
<code>-l</code> , <code>--link</code>	Link local files into the spool directory. If a file can not be linked because it is on a different device, it will be copied unless one of the <code>-c</code> or <code>--nocopy</code> options also appears (in other words, use of <code>--link</code> switches the default from <code>--nocopy</code> to <code>--copy</code>). If the files are changed before being processed by the <code>uucico(8)</code> daemon, the changed versions will be used. The files must be readable by the <code>uucico(8)</code> daemon, as well as by the invoker of <code>uux</code> .
<code>-g grade</code> , <code>--grade grade</code>	Set the grade of the file transfer command. Jobs of a higher grade are executed first. Grades run <code>0 ... 9 A ... Z a ... z</code> from high to low.
<code>-n</code> , <code>--notification=no</code>	Do not send mail about the status of the job, even if it fails.
<code>-z</code> , <code>--notification=error</code>	Send mail about the status of the job if an error occurs. For many <code>uuxqt</code> daemons, including the Taylor <code>uucp uuxqt</code> , this is the default action; for those, <code>--notification=error</code> will have no effect. However, some <code>uuxqt</code> daemons will send mail if the job succeeds unless the <code>--notification=error</code> option is used, and some other <code>uuxqt</code> daemons will not send mail if the job fails unless the <code>--notification=error</code> option is used.
<code>-r</code> , <code>--nouucico</code>	Do not start the <code>uucico(8)</code> daemon immediately; merely queue up the execution request for later processing.

<code>-j, --jobid</code>	Print jobids on standard output. A jobid will be generated for each file copy operation required to perform the operation. These file copies may be canceled by passing the jobid to the <code>--kill</code> switch of <code>uustat(1)</code> , which will make the execution impossible to complete.
<code>-a address,</code> <code>--requestor address</code>	Report job status to the specified e-mail address.
<code>-x type, --debug type</code>	Turn on particular debugging types. The following types are recognized: <code>abnormal</code> , <code>chat</code> , <code>handshake</code> , <code>uucp-proto</code> , <code>proto</code> , <code>port</code> , <code>config</code> , <code>spooldir</code> , <code>execute</code> , <code>incoming</code> , <code>outgoing</code> . Only <code>abnormal</code> , <code>config</code> , <code>spooldir</code> , and <code>execute</code> are meaningful for <code>uux</code> . Multiple types may be given, separated by commas, and the <code>--debug</code> option may appear multiple times. A number may also be given, which will turn on that many types from the foregoing list; for example, <code>--debug 2</code> is equivalent to <code>--debug abnormal,chat</code> .
<code>-I file, --config file</code>	Set configuration file to use. This option may not be available, depending upon how <code>uux</code> was compiled.
<code>-v, --version</code>	Report version information and exit.
<code>--help</code>	Print a help message and exit.

EXAMPLES

`uux -z - sys1!rmail user1`—Execute the command `rmail user1` on the system `sys1`, giving it as standard input whatever is given to `uux` as standard input. If a failure occurs, send a message using `mail(1)`.

`uux 'diff -c sys1!`user1/file1 sys2!`user2/file2 >!file.diff'`—Fetch the two named files from system `sys1` and system `sys2` and execute `diff`, putting the result in `file.diff` in the current directory. The current directory must be writable by the `uuxqt(8)` daemon for this to work.

`uux 'sys1!uucp `user1/file1 (sys2!`user2/file2)'`—Execute `uucp` on the system `sys1` copying `file1` (on system `sys1`) to `sys2`. This illustrates the use of parentheses for quoting.

RESTRICTIONS

The remote system may not permit you to execute certain commands. Many remote systems only permit the execution of `rmail` and `rnews`.

Some of the options are dependent on the capabilities of the `uuxqt(8)` daemon on the remote system.

FILES

The filenames may be changed at compilation time or by the configuration file, so these are only approximations.

<code>/usr/lib/uucp/config</code>	Configuration file
<code>/usr/spool/uucp/uucp</code>	spool directory
<code>/usr/spool/uucp/Log</code>	uucp log file
<code>/usr/spool/uucppublic</code>	Default uucp public directory

SEE ALSO

`mail(1)`, `uustat(1)`, `uucp(1)`, `uucico(8)`, `uuxqt(8)`

BUGS

Files can not be referenced across multiple systems.

Too many jobids are output by `--jobid`, and there is no good way to cancel a local execution requiring remote files.

AUTHOR

Ian Lance Taylor (ian@airs.com)

uuxqt

uuxqt—uucp execution daemon

SYNOPSIS

uuxqt [options]

DESCRIPTION

The `uuxqt` daemon executes commands requested by `uux(1)` from either the local system or from remote systems. It is started automatically by the `uucico(8)` daemon (unless `uucico(8)` is given the `-q` or `--nouuxqt` option).

There is normally no need to run this command because it will be invoked by `uucico(8)`. However, it can be used to provide greater control over the processing of the work queue.

Multiple invocations of `uuxqt` may be run at once, as controlled by the `max-uuxqts` configuration command.

OPTIONS

The following options may be given to `uuxqt`:

<code>-c command, --command command</code>	Only execute requests for the specified command. For example, <code>uuxqt -command rmail</code>
<code>-s system, --system system</code>	Only execute requests originating from the specified system.
<code>-x type, --debug type</code>	Turn on particular debugging types. The following types are recognized: <code>abnormal</code> , <code>chat</code> , <code>handshake</code> , <code>uucp-proto</code> , <code>proto</code> , <code>port</code> , <code>config</code> , <code>spooldir</code> , <code>execute</code> , <code>incoming</code> , <code>outgoing</code> . Only <code>abnormal</code> , <code>config</code> , <code>spooldir</code> and <code>execute</code> are meaningful for <code>uuxqt</code> . Multiple types may be given, separated by commas, and the <code>--debug</code> option may appear multiple times. A number may also be given, which will turn on that many types from the foregoing list; for example, <code>--debug 2</code> is equivalent to <code>--debug abnormal,chat</code> . The debugging output is sent to the debugging file, usually <code>/usr/spool/uucp/Debug</code> , <code>/usr/spool/uucp/DEBUG</code> , or <code>/usr/spool/uucp/.Admin/audit.local</code> .
<code>-I file, --config</code>	Set configuration file to use. This option may not be available, depending upon how <code>uuxqt</code> was compiled.
<code>-v, --version</code>	Report version information and exit.
<code>--help</code>	Print a help message and exit.

FILES

The filenames may be changed at compilation time or by the configuration file, so these are only approximations.

<code>/usr/lib/uucp/config</code>	Configuration file
<code>/usr/spool/uucpuucp</code>	spool directory
<code>/usr/spool/uucp/Log</code>	uucp log file
<code>/usr/spool/uucppublic</code>	Default uucp public directory
<code>/usr/spool/uucp/Debug</code>	Debugging file

SEE ALSO

`uucp(1)`, `uux(1)`, `uucico(8)`

AUTHOR

Ian Lance Taylor (ian@airs.com)

W

w—Present who users are and what they are doing

SYNOPSIS

```
w [-hin] [-user]
```

DESCRIPTION

The `w` utility prints a summary of the current activity on the system, including what each user is doing. The first line displays the current time of day, how long the system has been running, the number of users logged into the system, and the load averages. The load average numbers give the number of jobs in the run queue averaged over 1, 5, and 15 minutes.

The fields output are the user's login name, the name of the terminal the user is on, the host from which the user is logged in, the time the user logged on, the time since the user last typed anything, and the name and arguments of the current process.

The options are as follows:

- h Suppress the heading
- i Output is sorted by idle time
- n Show network addresses as numbers
- w Interpret addresses and attempt to display them symbolically

If a username is specified, the output is restricted to that user.

FILES

`/var/run/utmp` List of users on the system

SEE ALSO

`who(1)`, `finger(1)`, `ps(1)`, `uptime(1)`,

BUGS

The notion of the current process is muddy. The current algorithm is “the highest numbered process on the terminal that is not ignoring interrupts, or, if there is none, the highest numbered process on the terminal.” This fails, for example, in critical sections of programs like the shell and editor, or when faulty programs running in the background fork and fail to ignore interrupts. (In cases where no process can be found, `w` prints a period.)

The CPU time is only an estimate; in particular, if someone leaves a background process running after logging out, the person currently on that terminal is charged with the time.

Background processes are not shown, even though they account for much of the load on the system.

Sometimes processes, typically those in the background, are printed with null or garbaged arguments. In these cases, the name of the command is printed in parentheses.

The `w` utility does not know about the new conventions for detection of background jobs. It will sometimes find a background job instead of the right one.

COMPATIBILITY

The `-f`, `-l`, `-s`, and `-w` flags are no longer supported.

HISTORY

The `w` command appeared in BSD 3.0.

wall

wall—Write a message to users

SYNOPSIS

wall [file]

DESCRIPTION

wall displays the contents of file or, by default, its standard input, on the terminals of all currently logged in users.

Only the superuser can write on the terminals of users who have chosen to deny messages or are using a program that automatically denies messages.

SEE ALSO

mesg(1), talk(1), write(1), shutdown(8)

HISTORY

A wall command appeared in AT&T v7.

Linux 0.99, 8 March 1993

WC

wc—Print the number of bytes, words, and lines in files

SYNOPSIS

wc [-clw] [--bytes] [--chars] [--lines] [--words] [--help] [--version] [file...]

DESCRIPTION

This manual page documents the GNU version of wc. wc counts the number of bytes, whitespace-separated words, and newlines in each given file, or the standard input if none are given or when a file named - is given. It prints one line of counts for each file, and if the file was given as an argument, it prints the filename following the counts. If more than one filename is given, wc prints a final line containing the cumulative counts, with the filename total. The counts are printed in the order lines, words, bytes.

By default, wc prints all three counts. Options can specify that only certain counts be printed. Options do not undo others previously given, so wc --bytes --words prints both the byte counts and the word counts.

OPTIONS

-c, --bytes, --chars	Print only the byte counts.
-w, --words	Print only the word counts.
-l, --lines	Print only the newline counts.
--help	Print a usage message and exit with a non-zero status.
--version	Print version information on standard output, then exit.

GNU Text Utilities

whereis

whereis—Locate the binary, source, and manual page files for a command

SYNOPSIS

```
whereis [ -bmsu ][-BMS directory... -f ] filename ...
```

DESCRIPTION

whereis locates source/binary and manuals sections for specified files. The supplied names are first stripped of leading pathname components and any (single) trailing extension of the form `.ext`, for example, `.c`. Prefixes of `s.` resulting from use of source code control are also dealt with. **whereis** then attempts to locate the desired program in a list of standard Linux places:

```
/bin
/usr/bin
/etc
/usr/etc
/sbin
/usr/sbin
/usr/games
/usr/games/bin
/usr/emacs/etc
/usr/lib/emacs/19.22/etc
/usr/lib/emacs/19.23/etc
/usr/lib/emacs/19.24/etc
/usr/lib/emacs/19.25/etc
/usr/lib/emacs/19.26/etc
/usr/lib/emacs/19.27/etc
/usr/lib/emacs/19.28/etc
/usr/lib/emacs/19.29/etc
/usr/lib/emacs/19.30/etc
/usr/TeX/bin
/usr/tex/bin
/usr/interviews/bin/LINUX
/usr/bin/X11
/usr/X11/bin
/usr/X11R5/bin
/usr/X11R6/bin
/usr/X386/bin
/usr/local/bin
/usr/local/etc
/usr/local/sbin
/usr/local/games
/usr/local/games/bin
/usr/local/emacs/etc
/usr/local/TeX/bin
/usr/local/tex/bin
/usr/local/bin/X11
/usr/contrib
/usr/hosts
/usr/include
/usr/g++-include
```

OPTIONS

- b Search only for binaries.
- m Search only for manual sections.
- s Search only for sources.
- u Search for unusual entries. A file is said to be unusual if it does not have one entry of each requested type. Thus `whereisnn-mnn-unn*` asks for those files in the current directory which have no documentation.
- B Change or otherwise limit the places where `whereis` searches for binaries.
- M Change or otherwise limit the places where `whereis` searches for manual sections.
- S Change or otherwise limit the places where `whereis` searches for sources.
- f Terminate the last directory list and signals the start of filenames; *must* be used when any of the -B, -M, or -S options are used.

EXAMPLE

Find all files in `/usr/bin` that are not documented in `/usr/man/man1` with source in `/usr/src`:

```
example% cd /usr/bin
example% whereis -u -M /usr/man/man1 -S /usr/src -f *
```

FILES

```
/{bin,sbin,etc}
/usr/{lib,bin,old,new,local,games,include,etc,src,man,sbin,
X386, TeX, g++-include}
/usr/local/{X386,TeX,X11,include,lib,man,etc,bin,games,emacs}
```

SEE ALSO

`chdir(2V)`

BUGS

Since `whereis` uses `chdir(2V)` to run faster, pathnames given with the -M, -S, or -B must be full; that is, they must begin with a `/`.

8 May 1994

write

`write`—Send a message to another user

SYNOPSIS

```
write user [ttyname]
```

DESCRIPTION

`write` allows you to communicate with other users by copying lines from your terminal to theirs.

When you run the `write` command, the user you are writing to gets a message of the form:

```
Message from yourname@yourhost on yourtty at hh:mm ...
```

Any further lines you enter will be copied to the specified user's terminal. If the other user wants to reply, he or she must run `write` as well.

When you are done, type an end-of-file or interrupt character. The other user will see the message EOF, indicating that the conversation is over.

You can prevent people (other than the superuser) from writing to you with the `mesg(1)` command. Some commands, for example, `nroff(1)` and `pr(1)`, may disallow writing automatically, so that your output isn't overwritten.

If the user you want to write to is logged in on more than one terminal, you can specify which terminal to write to by specifying the terminal name as the second operand to the `write` command. Alternatively, you can let `write` select one of the terminals—it will pick the one with the shortest idle time. Thus, if the user is logged in at work and also dialed up from home, the message will go to the right place.

The traditional protocol for writing to someone is that the string `-o`, either at the end of a line or on a line by itself, means that it's the other person's turn to talk. The string `oo` means that the person believes the conversation to be over.

SEE ALSO

`mesg(1)`, `talk(1)`, `who(1)`

HISTORY

A `write` command appeared in Version 6 AT&T UNIX.

12 March 1995

x11perf

`x11perf`—X11 server performance test program

SYNTAX

`x11perf [ -option ... ]`

DESCRIPTION

The `x11perf` program runs one or more performance tests and reports how fast an X server can execute the tests.

Many graphics benchmarks assume that the graphics device is used to display the output of a single fancy graphics application, and that the user gets his work done on some other device, like a terminal. Such benchmarks usually measure drawing speed for lines, polygons, text, and so on.

Because workstations are not used as standalone graphics engines, but as super-terminals, `x11perf` measures window management performance as well as traditional graphics performance. `x11perf` includes benchmarks for the time it takes to create and map windows (as when you start up an application); to map a preexisting set of windows onto the screen (as when you deiconify an application or pop up a menu); and to rearrange windows (as when you slosh windows to and fro trying to find the one you want).

`x11perf` also measures graphics performance for operations not normally used in standalone graphics displays, but are nonetheless used frequently by X applications. Such operations include `CopyPlane` (used to map bitmaps into pixels), `scrolling` (used in text windows), and various stipples and tiles (used for CAD and color halftoning, respectively).

`x11perf` should be used to analyze particular strengths and weaknesses of servers, and is most useful to a server writer who wants to analyze and improve a server. `x11perf` is meant to comprehensively exercise just about every X11 operation you can perform; it does not purport to be a representative sample of the operations that X11 applications actually use. Although it can be used as a benchmark, it was written and is intended as a performance testing tool.

As such, `x11perf` does not whittle down measurements to a single `HexStones` or `MeXops` number. We consider such numbers to be uninformative at best and misleading at worst. Some servers that are very fast for certain applications can be very slow for others. No single number or small set of numbers is sufficient to characterize how an X implementation will perform on all applications. However, by knowledge of your favorite application, you may be able to use the numbers `x11perf` reports to predict its performance on a given X implementation.

That said, you might also want to look at `x11perfcomp(1)`, a program to compare the outputs of different `x11perf` runs. You provide a list of files containing results from `x11perf`, and it lays them out in a nice tabular format.

For repeatable results, `x11perf` should be run using a local connection on a freshly started server. The default configuration runs each test five times in order to see if each trial takes approximately the same amount of time. Strange glitches should be examined; if nonrepeatable, you might chalk them up to daemons and network traffic. Each trial is run for five seconds, in order to reduce random time differences. The number of objects processed per second is displayed to three significant digits, but you'll be lucky on most UNIX systems if the numbers are actually consistent to two digits. `x11perf` moves the cursor out of the test window; you should be careful not to bump the mouse and move it back into the window. (A prize to people who correctly explain why!)

Before running a test, `x11perf` determines what the round trip time to the server is, and factors this out of the final timing reported. It ensures that the server has actually performed the work requested by fetching a pixel back from the test window, which means that servers talking to graphics accelerators can't claim that they are done, while in the meantime the accelerator is painting madly.

By default, `x11perf` automatically calibrates the number of repetitions of each test, so that each should take approximately the same length of time to run across servers of widely differing speeds. However, because each test must be run to completion at least once, some slow servers may take a very long time, particularly on the window moving and resizing tests, and on the arc drawing tests.

All timing reports are for the smallest object involved. For example, the line tests use a `PolyLine` request to paint several lines at once, but report how many lines per second the server can paint, not how many `PolyLine` requests per second. Text tests paint a line of characters, but report on the number of characters per second. Some window tests map, unmap, or move a single parent window, but report on how many children windows per second the server can map, unmap, or move.

The current program is mostly the responsibility of Joel McCormack. It is based upon the `x11perf` developed by Phil Karlton, Susan Angebrannt, Chris Kent, Mary Walker, and Todd Newman, who wanted to assess performance differences between various servers. Several tests were added in order to write and tune the PMAX (DECStation 3100) servers. For a general release to the world, `x11perf` was rewritten to ease making comparisons between widely varying machines, to cover most important (and unimportant) x functionality, and to exercise graphics operations in as many different orientations and alignments as possible.

OPTIONS

`x11perf` is solely `Xlib` based, and accepts the following options:

<code>-display host:dpY</code>	Specifies which display to use.
<code>-sync</code>	Runs the tests in synchronous mode. Normally only useful for debugging <code>x11perf</code> .
<code>-pack</code>	Runs rectangle tests so that they pack rectangles right next to each other. This makes it easy to debug server code for stipples and tiles; if the pattern looks ugly, you've got alignment problems.
<code>-repeat <n></code>	Repeats each test <i>n</i> times (by default each test is run <code>five</code> times).
<code>-time <s></code>	Specifies how long in seconds each test should be run (default 5 seconds).
<code>-all</code>	Runs all tests. This may take a while.
<code>-range <test1>[,<test2>]</code>	Runs all the tests starting from the specified name <code>test1</code> until the name <code>test2</code> , tests. The testnames should be one of the options starting from <code>-dot</code> . For example, <code>-range line100</code> will perform the tests from the 100 pixel line test, and go on till the last test; <code>-range line100,dline10</code> will do the tests from <code>line100</code> to <code>dline10</code> .
<code>-labels</code>	Generates just the descriptive labels for each test specified. See <code>x11perfcomp</code> for more details.
<code>-fg color-or-pixel</code>	Specifies the foreground color or pixel value to use.
<code>-bg color-or-pixel</code>	Specifies the background color or pixel value to use.
<code>-clips default</code>	Default number of clip windows.

-ddbg color-or-pixel	Specifies the color or pixel value to use for drawing the odd segments of a DoubleDashed line or arc. This will default to the bg color.
-rop <rop0 rop1 ...>	Use specified raster ops (default is GXcopy). This option only affects graphics benchmarks in which the graphics function is actually used.
-pm <pm0 pm1 ...>	Use specified planemasks (default is ~0). This option only affects graphics benchmarks in which the planemask is actually used.
-depth <depth>	Use a visual with <depth> planes per pixel. (Default is the default visual.)
-vclass <vclass>	Use a visual with of class <vclass>. <vclass> can be StaticGray, GrayScale, StaticColor, PseudoColor, TrueColor, or DirectColor. (Default is the default visual).
-reps <n>	Specify the repetition count. (Default is number that takes approximately five seconds.)
-subs <s0 s1 ...>	Specify the number of sub windows to use in the Window tests. Default is 4, 16, 25, 50, 75, 100, and 200.
-v1.2	Perform only x11perf version 1.2 tests using version 1.2 semantics.
-v1.3	Perform only x11perf version 1.3 tests using version 1.3 semantics.
-su	Set the save_under window attribute to True on all windows created by x11perf. Default is False.
-bs	Set the backing_store window attribute to the given value on all windows created by x11perf. <backing_store_hint> can be WhenMapped or Always. Default is NotUseful.
<backing_store_hint>	
-dot	Dot.
-rect1	1×1 solid-filled rectangle.
-rect10	10×10 solid-filled rectangle.
-rect100	100×100 solid-filled rectangle.
-rect500	500×500 solid-filled rectangle.
-srect1	1×1 transparent stippled rectangle, 8×8 stipple pattern.
-srect10	10×10 transparent stippled rectangle, 8×8 stipple pattern.
-srect100	100×100 transparent stippled rectangle, 8×8 stipple pattern.
-srect500	500×500 transparent stippled rectangle, 8×8 stipple pattern.
-osrect1	1×1 opaque stippled rectangle, 8×8 stipple pattern.
-osrect10	10×10 opaque stippled rectangle, 8×8 stipple pattern.
-osrect100	100×100 opaque stippled rectangle, 8×8 stipple pattern.
-osrect500	500×500 opaque stippled rectangle, 8×8 stipple pattern.
-tilerect1	1×1 tiled rectangle, 4×4 tile pattern.
-tilerect10	10×10 tiled rectangle, 4×4 tile pattern.
-tilerect100	100×100 tiled rectangle, 4×4 tile pattern.
-tilerect500	500×500 tiled rectangle, 4×4 tile pattern.
-oddsrect1	1×1 transparent stippled rectangle, 17×15 stipple pattern.
-oddsrect10	10×10 transparent stippled rectangle, 17×15 stipple pattern.
-oddsrect100	100×100 transparent stippled rectangle, 17×15 stipple pattern.
-oddsrect500	500×500 transparent stippled rectangle, 17×15 stipple pattern.
-oddosrect1	1×1 opaque stippled rectangle, 17×15 stipple pattern.
-oddosrect10	10×10 opaque stippled rectangle, 17×15 stipple pattern.
-oddosrect100	100×100 opaque stippled rectangle, 17×15 stipple pattern.
-oddosrect500	500×500 opaque stippled rectangle, 17×15 stipple pattern.
-oddtilerect1	1×1 tiled rectangle, 17×15 tile pattern.
-oddtilerect10	10×10 tiled rectangle, 17×15 tile pattern.

<code>-oddtilerect100</code>	100×100 tiled rectangle, 17×15 tile pattern.
<code>-oddtilerect500</code>	500×500 tiled rectangle, 17×15 tile pattern.
<code>-bigirect1</code>	1×1 stippled rectangle, 161×145 stipple pattern.
<code>-bigirect10</code>	10×10 stippled rectangle, 161×145 stipple pattern.
<code>-bigirect100</code>	100×100 stippled rectangle, 161×145 stipple pattern.
<code>-bigirect500</code>	500×500 stippled rectangle, 161×145 stipple pattern.
<code>-bigosirect1</code>	1×1 opaque stippled rectangle, 161×145 stipple pattern.
<code>-bigosirect10</code>	10×10 opaque stippled rectangle, 161×145 stipple pattern.
<code>-bigosirect100</code>	100×100 opaque stippled rectangle, 161×145 stipple pattern.
<code>-bigosirect500</code>	500×500 opaque stippled rectangle, 161×145 stipple pattern.
<code>-bigtileirect1</code>	1×1 tiled rectangle, 161×145 tile pattern.
<code>-bigtileirect10</code>	10×10 tiled rectangle, 161×145 tile pattern.
<code>-bigtileirect100</code>	100×100 tiled rectangle, 161×145 tile pattern.
<code>-bigtileirect500</code>	500×500 tiled rectangle, 161×145 tile pattern.
<code>-eschertileirect1</code>	1×1 tiled rectangle, 215×208 tile pattern.
<code>-eschertileirect10</code>	10×10 tiled rectangle, 215×208 tile pattern.
<code>-eschertileirect100</code>	100×100 tiled rectangle, 215×208 tile pattern.
<code>-eschertileirect500</code>	500×500 tiled rectangle, 215×208 tile pattern.
<code>-seg1</code>	1-pixel thin line segment.
<code>-seg10</code>	10-pixel thin line segment.
<code>-seg100</code>	100-pixel thin line segment.
<code>-seg500</code>	500-pixel thin line segment.
<code>-seg100c1</code>	100-pixel thin line segment (1 obscuring rectangle).
<code>-seg100c2</code>	100-pixel thin line segment (2 obscuring rectangles).
<code>-seg100c3</code>	100-pixel thin line segment (3 obscuring rectangles).
<code>-dseg10</code>	10-pixel thin dashed segment (3 on, 2 off).
<code>-dseg100</code>	100-pixel thin dashed segment (3 on, 2 off).
<code>-ddseg100</code>	100-pixel thin double-dashed segment (3 fg, 2 bg).
<code>-hseg10</code>	10-pixel thin horizontal line segment.
<code>-hseg100</code>	100-pixel thin horizontal line segment.
<code>-hseg500</code>	500-pixel thin horizontal line segment.
<code>-vseg10</code>	10-pixel thin vertical line segment.
<code>-vseg100</code>	100-pixel thin vertical line segment.
<code>-vseg500</code>	500-pixel thin vertical line segment.
<code>-whseg10</code>	10-pixel wide horizontal line segment.
<code>-whseg100</code>	100-pixel wide horizontal line segment.
<code>-whseg500</code>	500-pixel wide horizontal line segment.
<code>-wvseg10</code>	10-pixel wide vertical line segment.
<code>-wvseg100</code>	100-pixel wide vertical line segment.
<code>-wvseg500</code>	500-pixel wide vertical line segment.
<code>-line1</code>	1-pixel thin (width 0) line.
<code>-line10</code>	10-pixel thin line.
<code>-line100</code>	100-pixel thin line.
<code>-line500</code>	500-pixel thin line.

<code>-dline10</code>	10-pixel thin dashed line (3 on, 2 off).
<code>-dline100</code>	100-pixel thin dashed line (3 on, 2 off).
<code>-ddline100</code>	100-pixel thin double-dashed line (3 fg, 2 bg).
<code>-wline10</code>	10-pixel line, line width 1.
<code>-wline100</code>	100-pixel line, line width 10.
<code>-wline500</code>	500-pixel line, line width 50.
<code>-wdline100</code>	100-pixel dashed line, line width 10 (30 on, 20 off).
<code>-wddline100</code>	100-pixel double-dashed line, line width 10 (30 fg, 20 bg).
<code>-orect10</code>	10x10 thin rectangle outline.
<code>-orect100</code>	100-pixel thin vertical line segment.
<code>-orect500</code>	500-pixel thin vertical line segment.
<code>-worect10</code>	10x10 wide rectangle outline.
<code>-worect100</code>	100-pixel wide vertical line segment.
<code>-worect500</code>	500-pixel wide vertical line segment.
<code>-circle1</code>	1-pixel diameter thin (line-width 0) circle.
<code>-circle10</code>	10-pixel diameter thin circle.
<code>-circle100</code>	100-pixel diameter thin circle.
<code>-circle500</code>	500-pixel diameter thin circle.
<code>-dcircle100</code>	100-pixel diameter thin dashed circle (3 on, 2 off).
<code>-ddcircle100</code>	100-pixel diameter thin double-dashed circle (3 fg, 2 bg).
<code>-wcircle10</code>	10-pixel diameter circle, line width 1.
<code>-wcircle100</code>	100-pixel diameter circle, line width 10.
<code>-wcircle500</code>	500-pixel diameter circle, line width 50.
<code>-wdcircle100</code>	100-pixel diameter dashed circle, line width 10 (30 on, 20 off).
<code>-wddcircle100</code>	100-pixel diameter double-dashed circle, line width 10 (30 fg, 20 bg).
<code>-pcircle10</code>	10-pixel diameter thin partial circle, orientation and arc angle evenly distributed.
<code>-pcircle100</code>	100-pixel diameter thin partial circle.
<code>-wpcircle10</code>	10-pixel diameter wide partial circle.
<code>-wpcircle100</code>	100-pixel diameter wide partial circle.
<code>-fcircle1</code>	1-pixel diameter filled circle.
<code>-fcircle10</code>	10-pixel diameter filled circle.
<code>-fcircle100</code>	100-pixel diameter filled circle.
<code>-fcircle500</code>	500-pixel diameter filled circle.
<code>-fpcircle10</code>	10-pixel diameter partial-filled circle, chord fill, orientation and arc angle evenly distributed.
<code>-fpcircle100</code>	100-pixel diameter partial-filled circle, chord fill.
<code>-fspcircle10</code>	10-pixel diameter partial-filled circle, pie slice fill, orientation and arc angle evenly distributed.
<code>-fspcircle100</code>	100-pixel diameter partial-filled circle, pie slice fill.
<code>-ellipse10</code>	10-pixel diameter thin (line width 0) ellipse, major and minor axis sizes evenly distributed.
<code>-ellipse100</code>	100-pixel diameter thin ellipse.
<code>-ellipse500</code>	500-pixel diameter thin ellipse.
<code>-dellipse100</code>	100-pixel diameter thin dashed ellipse (3 on, 2 off).
<code>-ddellipse100</code>	100-pixel diameter thin double-dashed ellipse (3 fg, 2 bg).
<code>-wellipse10</code>	10-pixel diameter ellipse, line width 1.

<code>-wellipse100</code>	100-pixel diameter ellipse, line width 10.
<code>-wellipse500</code>	500-pixel diameter ellipse, line width 50.
<code>-wdellipse100</code>	100-pixel diameter dashed ellipse, line width 10 (30 on, 20 off).
<code>-wddellipse100</code>	100-pixel diameter double-dashed ellipse, line width 10 (30 fg, 20 bg).
<code>-pellipse10</code>	10-pixel diameter thin partial ellipse.
<code>-pellipse100</code>	100-pixel diameter thin partial ellipse.
<code>-wpellipse10</code>	10-pixel diameter wide partial ellipse.
<code>-wpellipse100</code>	100-pixel diameter wide partial ellipse.
<code>-fellipse10</code>	10-pixel diameter filled ellipse.
<code>-fellipse100</code>	100-pixel diameter filled ellipse.
<code>-fellipse500</code>	500-pixel diameter filled ellipse.
<code>-fcpellipse10</code>	10-pixel diameter partial-filled ellipse, chord fill.
<code>-fcpellipse100</code>	100-pixel diameter partial-filled ellipse, chord fill.
<code>-fspellipse10</code>	10-pixel diameter partial-filled ellipse, pie slice fill.
<code>-fspellipse100</code>	100-pixel diameter partial-filled ellipse, pie slice fill.
<code>-triangle1</code>	Fill 1-pixel/side triangle.
<code>-triangle10</code>	Fill 10-pixel/side triangle.
<code>-triangle100</code>	Fill 100-pixel/side triangle.
<code>-trap1</code>	Fill 1×1 trapezoid.
<code>-trap10</code>	Fill 10×10 trapezoid.
<code>-trap100</code>	Fill 100×100 trapezoid.
<code>-trap300</code>	Fill 300×300 trapezoid.
<code>-strap1</code>	Fill 1×1 transparent stippled trapezoid, 8×8 stipple pattern.
<code>-strap10</code>	Fill 10×10 transparent stippled trapezoid, 8×8 stipple pattern.
<code>-strap100</code>	Fill 100×100 transparent stippled trapezoid, 8×8 stipple pattern.
<code>-strap300</code>	Fill 300×300 transparent stippled trapezoid, 8×8 stipple pattern.
<code>-ostrap1</code>	Fill 10×10 opaque stippled trapezoid, 8×8 stipple pattern.
<code>-ostrap10</code>	Fill 10×10 opaque stippled trapezoid, 8×8 stipple pattern.
<code>-ostrap100</code>	Fill 100×100 opaque stippled trapezoid, 8×8 stipple pattern.
<code>-ostrap300</code>	Fill 300×300 opaque stippled trapezoid, 8×8 stipple pattern.
<code>-tiletrap1</code>	Fill 10×10 tiled trapezoid, 4×4 tile pattern.
<code>-tiletrap10</code>	Fill 10×10 tiled trapezoid, 4×4 tile pattern.
<code>-tiletrap100</code>	Fill 100×100 tiled trapezoid, 4×4 tile pattern.
<code>-tiletrap300</code>	Fill 300×300 tiled trapezoid, 4×4 tile pattern.
<code>-oddstrap1</code>	Fill 1×1 transparent stippled trapezoid, 17×15 stipple pattern.
<code>-oddstrap10</code>	Fill 10×10 transparent stippled trapezoid, 17×15 stipple pattern.
<code>-oddstrap100</code>	Fill 100×100 transparent stippled trapezoid, 17×15 stipple pattern.
<code>-oddstrap300</code>	Fill 300×300 transparent stippled trapezoid, 17×15 stipple pattern.
<code>-oddstrap1</code>	Fill 10×10 opaque stippled trapezoid, 17×15 stipple pattern.
<code>-oddstrap10</code>	Fill 10×10 opaque stippled trapezoid, 17×15 stipple pattern.
<code>-oddstrap100</code>	Fill 100×100 opaque stippled trapezoid, 17×15 stipple pattern.
<code>-oddstrap300</code>	Fill 300×300 opaque stippled trapezoid, 17×15 stipple pat-tern.
<code>-oddtiletrap1</code>	Fill 10×10 tiled trapezoid, 17×15 tile pattern.
<code>-oddtiletrap10</code>	Fill 10×10 tiled trapezoid, 17×15 tile pattern.

-oddtiletrap100	Fill 100×100 tiled trapezoid, 17×15 tile pattern.
-oddtiletrap300	Fill 300×300 tiled trapezoid, 17×15 tile pattern.
-bigstrap1	Fill 1×1 transparent stippled trapezoid, 161×145 stipple pattern.
-bigstrap10	Fill 10×10 transparent stippled trapezoid, 161×145 stipple pattern.
-bigstrap100	Fill 100×100 transparent stippled trapezoid, 161×145 stipple pattern.
-bigstrap300	Fill 300×300 transparent stippled trapezoid, 161×145 stipple pattern.
-bigostrap1	Fill 10×10 opaque stippled trapezoid, 161×145 stipple pattern.
-bigostrap10	Fill 10×10 opaque stippled trapezoid, 161×145 stipple pattern.
-bigostrap100	Fill 100×100 opaque stippled trapezoid, 161×145 stipple pattern.
-bigostrap300	Fill 300×300 opaque stippled trapezoid, 161×145 stipple pattern.
-bigtiletrap1	Fill 10×10 tiled trapezoid, 161×145 tile pattern.
-bigtiletrap10	Fill 10×10 tiled trapezoid, 161×145 tile pattern.
-bigtiletrap100	Fill 100×100 tiled trapezoid, 161×145 tile pattern.
-bigtiletrap300	Fill 300×300 tiled trapezoid, 161×145 tile pattern.
-eschertiletrap1	Fill 1×1 tiled trapezoid, 216×208 tile pattern.
-eschertiletrap10	Fill 10×10 tiled trapezoid, 216×208 tile pattern.
-eschertiletrap100	Fill 100×100 tiled trapezoid, 216×208 tile pattern.
-eschertiletrap300	Fill 300×300 tiled trapezoid, 216×208 tile pattern.
-complex10	Fill 10-pixel/side complex polygon.
-complex100	Fill 100-pixel/side complex polygon.
-64poly10convex	Fill 10×10 convex 64-gon.
-64poly100convex	Fill 100×100 convex 64-gon.
-64poly10complex	Fill 10×10 complex 64-gon.
-64poly100complex	Fill 100×100 complex 64-gon.
-ftext	Character in 80-char line (6×13).
-f8text	Character in 70-char line (8×13).
-f9text	Character in 60-char line (9×15).
-f14text16	2-byte character in 40-char line (k14).
-tr10text	Character in 80-char line (Times-Roman 10).
-tr24text	Character in 30-char line (Times-Roman 24).
-polytext	Character in 20/40/20 line (6×13, Times-Roman 10, 6×13).
-polytext16	2-byte character in 7/14/7 line (k14, k24).
-fitext	Character in 80-char image line (6×13).
-f8itext	Character in 70-char image line (8×13).
-f9itext	Character in 60-char image line (9×15).
-f14itext16	2-byte character in 40-char image line (k14).
-f24itext16	2-byte character in 23-char image line (k24).
-tr10itext	Character in 80-char image line (Times-Roman 10).
-tr24itext	Character in 30-char image line (Times-Roman 24).
-scroll10	Scroll 10×10 pixels vertically.
-scroll100	Scroll 100×100 pixels vertically.
-scroll500	Scroll 500×500 pixels vertically.

-copywinwin10	Copy 10×10 square from window to window.
-copywinwin100	Copy 100×100 square from window to window.
-copywinwin500	Copy 500×500 square from window to window.
-copypixwin10	Copy 10×10 square from pixmap to window.
-copypixwin100	Copy 100×100 square from pixmap to window.
-copypixwin500	Copy 500×500 square from pixmap to window.
-copywinpix10	Copy 10×10 square from window to pixmap.
-copywinpix100	Copy 100×100 square from window to pixmap.
-copywinpix500	Copy 500×500 square from window to pixmap.
-copypixpix10	Copy 10×10 square from pixmap to pixmap.
-copypixpix100	Copy 100×100 square from pixmap to pixmap.
-copypixpix500	Copy 500×500 square from pixmap to pixmap.
-copyplane10	Copy 10×10 1-bit deep plane.
-copyplane100	Copy 100×100 1-bit deep plane.
-copyplane500	Copy 500×500 1-bit deep plane.
-putimage10	PutImage 10×10 square.
-putimage100	PutImage 100×100 square.
-putimage500	PutImage 500×500 square.
-putimagexy10	PutImage XY format 10×10 square.
-putimagexy100	PutImage XY format 100×100 square.
-putimagexy500	PutImage XY format 500×500 square.
-shmput10	PutImage 10×10 square, MIT-shared memory extension.
-shmput100	PutImage 100×100 square, MIT-shared memory extension.
-shmput500	PutImage 500×500 square, MIT-shared memory extension.
-shmputxy10	PutImage XY format 10×10 square, MIT-shared memory extension.
-shmputxy100	PutImage XY format 100×100 square, MIT-shared memory extension.
-shmputxy500	PutImage XY format 500×500 square, MIT-shared memory extension.
-getimage10	GetImage 10×10 square.
-getimage100	GetImage 100×100 square.
-getimage500	GetImage 500×500 square.
-getimagexy10	GetImage XY format 10×10 square.
-getimagexy100	GetImage XY format 100×100 square.
-getimagexy500	GetImage XY format 500×500 square.
-noop	X protocol NoOperation.
-atom	GetAtomName.
-pointer	QueryPointer.
-prop	GetProperty.
-gc	Change graphics context.
-create	Create child window and map using MapSubwindows.
-ucreate	Create unmapped window.
-map	Map child window via MapWindow on parent.
-unmap	Unmap child window via UnmapWindow on parent.
-destroy	Destroy child window via DestroyWindow parent.
-popup	Hide/expose window via Map/Unmap pop-up window.

-move	Move window.
-umove	Moved unmapped window.
-movetree	Move window via MoveWindow on parent.
-resize	Resize window.
-uresize	Resize unmapped window.
-circulate	Circulate lowest window to top.
-ucirculate	Circulate unmapped window to top.

X DEFAULTS

There are no x defaults used by this program.

SEE ALSO

x(1), xbench(1), x11perfcomp(1)

AUTHORS

Joel McCormack
 Phil Karlton
 Susan Angebrannt
 Chris Kent
 Keith Packard
 Graeme Gill

X Version 11 Release 6

x11perfcomp

x11perfcomp—X11 server performance comparison program

SYNTAX

```
x11perfcomp [-rj -ro ] [ -l label_file ] files
```

DESCRIPTION

The x11perfcomp program merges the output of several x11perf(1) runs into a nice tabular format. It takes the results in each file, fills in any missing test results if necessary, and for each test shows the objects/second rate of each server. If invoked with the -r or -ro options, it shows the relative performance of each server to the first server.

Normally, x11perfcomp uses the first file specified to determine which specific tests it should report on. Some (non-DEC:) servers may fail to perform all tests. In this case, x11perfcomp automatically substitutes in a rate of 0.0 objects/second. Since the first file determines which tests to report on, this file must contain a superset of the tests reported in the other files, else x11perfcomp will fail.

You can provide an explicit list of tests to report on by using the -l switch to specify a file of labels. You can create a label file by using the -label option in x11perf.

OPTIONS

x11perfcomp accepts the following options:

-r	Specifies that the output should also include relative server performance.
-ro	Specifies that the output should include only relative server performance.
-l_label_file	Specifies a label file to use.

X DEFAULTS

There are no `x` defaults used by this program.

SEE ALSO

`x(1)`, `x11perf(1)`

AUTHORS

Mark Moraes wrote the original scripts to compare servers. Joel McCormack just munged them together a bit.

X Version 11 Release 6

xargs

`xargs`—Build and execute command lines from standard input

SYNOPSIS

```
xargs [-0prt看] [-e[eof-str]] [-i[replace-str]] [-l[max-lines]] [-n max-args]
[-s max-chars] [-P max-procs] [--null] [--eof[=eof-str]] [--replace[=replace-str]]
[--max-lines[=max-lines]] [--interactive] [--max-chars=max-chars] [--verbose]
[--exit] [--max-procs=max-procs] [--max-args=max-args] [--no-run-if-empty]
[--version] [--help] [command [initial-arguments]]
```

DESCRIPTION

This manual page documents the GNU version of `xargs`. `xargs` reads arguments from the standard input, delimited by blanks (which can be protected with double or single quotes or a backslash) or newlines, and executes the command (default is `/bin/echo`) one or more times with any `initial-arguments` followed by arguments read from standard input. Blank lines on the standard input are ignored.

`xargs` exits with the following status:

- 0 if it succeeds
- 123 if any invocation of the command exited with status 1-125
- 124 if the command exited with status 255
- 125 if the command is killed by a signal
- 126 if the command cannot be run
- 127 if the command is not found
- 1 if some other error occurred.

OPTIONS

- `--null, -0` Input filenames are terminated by a null character instead of by whitespace, and the quotes and backslash are not special (every character is taken literally). Disables the end-of-file string, which is treated like any other argument. Useful when arguments might contain whitespace, quote marks, or backslashes. The GNU `find -print0` option produces input suitable for this mode.
- `--eof[=eof-str], -e[=eof-str]` Set the end-of-file string to `eof-str`. If the end-of-file string occurs as a line of input, the rest of the input is ignored. If `eof-str` is omitted, there is no end of file string. If this option is not given, the end-of-file string defaults to an underscore.
- `--help` Print a summary of the options to `xargs` and `exit`.
- `--replace[=replace-str], -i[replace-str]` Replace occurrences of `replace-str` in the initial arguments with names read from standard input. Also, unquoted blanks do not terminate arguments. If `replace-str` is omitted, it defaults to `{}` (like for `find -exec`). Implies `-x` and `-l 1`.

<code>--max-lines[=max-lines], -l[max-lines]</code>	Use at most <code>max-lines</code> nonblank input lines per command line; <code>max-lines</code> defaults to 1 if omitted. Trailing blanks cause an input line to be logically continued on the next input line. Implies <code>-x</code> .
<code>--max-args=max-args, -n max-args</code>	Use at most <code>max-args</code> arguments per command line. Fewer than <code>max-args</code> arguments will be used if the size (see the <code>-s</code> option) is exceeded, unless the <code>-x</code> option is given, in which case <code>xargs</code> will exit.
<code>--interactive, -p</code>	Prompt the user about whether to run each command line and read a line from the terminal. Only run the command line if the response starts with <code>y</code> or <code>Y</code> . Implies <code>-t</code> .
<code>--no-run-if-empty, -r</code>	If the standard input does not contain any nonblanks, do not run the command. Normally, the command is run once even if there is no input.
<code>--max-chars=max-chars, -s max-chars</code>	Use at most <code>max-chars</code> characters per command line, including the command and initial arguments and the terminating <code>nulls</code> at the ends of the argument strings. The default is as large as possible, up to 20k characters.
<code>--verbose, -t</code>	Print the command line on the standard error output before executing it.
<code>--version</code>	Print the version number of <code>xargs</code> and exit.
<code>--exit, -x</code>	Exit if the size (see the <code>-s</code> option) is exceeded.
<code>--max-procs=max-procs, -P max-procs</code>	Run up to <code>max-procs</code> processes at a time; the default is 1. If <code>max-procs</code> is 0, <code>xargs</code> will run as many processes as possible at a time. Use the <code>-n</code> option with <code>-P</code> ; otherwise, chances are that only one <code>exec</code> will be done.

SEE ALSO

`find(1L)`, `locate(1L)`, `locatedb(5L)`, `updatedb(1)` *Finding Files* (online in `info`, or printed)

xauth

xauth—x authority file utility

SYNOPSIS

```
xauth [ -f authfile ][-vqib ][command arg ... ]
```

DESCRIPTION

The `xauth` program is used to edit and display the authorization information used in connecting to the x server. This program is usually used to extract authorization records from one machine and merge them in on another (as is the case when using remote logins or granting access to other users). Commands (described below) may be entered interactively, on the `xauth` command line, or in scripts. Note that this program does not contact the x server. Normally `xauth` is not used to create the authority file entry in the first place; `xdm` does that.

OPTIONS

The following options may be used with `xauth`. They may be given individually (for example, `-q -i`) or may combined (for example, `-qi`).

<code>-f authfile</code>	This option specifies the name of the authority file to use. By default, <code>xauth</code> will use the file specified by the <code>XAUTHORITY</code> environment variable or <code>xauthority</code> in the user's home directory.
<code>-q</code>	This option indicates that <code>xauth</code> should operate quietly and not print unsolicited status messages. This is the default if an <code>xauth</code> command is given on the command line or if the standard output is not directed to a terminal.
<code>-v</code>	This option indicates that <code>xauth</code> should operate verbosely and print status messages indicating the results of various operations (such as how many records have been read in or written out). This is the default if <code>xauth</code> is reading commands from its standard input and its standard output is directed to a terminal.

- i This option indicates that `xauth` should ignore any authority file locks. Normally, `xauth` will refuse to read or edit any authority files that have been locked by other programs (usually `xdm` or another `xauth`).
- b This option indicates that `xauth` should attempt to break any authority file locks before proceeding. Use this option only to clean up stale locks.

COMMANDS

The following commands may be used to manipulate authority files:

<code>add displayname protocolname hexkey</code>	An authorization entry for the indicated display using the given protocol and key data is added to the authorization file. The data is specified as an even-lengthed string of hexadecimal digits, each pair representing one octet. The first digit of each pair gives the most significant 4 bits of the octet, and the second digit of the pair gives the least significant 4 bits. For example, a 32-character hexkey would represent a 128-bit value. A protocol name consisting of just a single period is treated as an abbreviation for <code>MIT-MAGIC-COOKIE-1</code> .
<code>[n]extract filename displayname...</code>	Authorization entries for each of the specified displays are written to the indicated file. If the <code>nextract</code> command is used, the entries are written in a numeric format suitable for nonbinary transmission (such as secure electronic mail). The extracted entries can be read back in using the <code>merge</code> and <code>nmerge</code> commands. If the filename consists of just a single dash, the entries will be written to the standard output.
<code>[n]list [displayname...]</code>	Authorization entries for each of the specified displays (or all if no displays are named) are printed on the standard output. If the <code>nlist</code> command is used, entries will be shown in the numeric format used by the <code>nextract</code> command; otherwise, they are shown in a textual format. Key data is always displayed in the hexadecimal format given in the description of the <code>add</code> command.
<code>[n]merge [filename...]</code>	Authorization entries are read from the specified files and are merged into the authorization database, superceding any matching existing entries. If the <code>nmerge</code> command is used, the numeric format given in the description of the <code>extract</code> command is used. If a filename consists of just a single dash, the standard input will be read if it hasn't been read before.
<code>remove displayname... source filename</code>	Authorization entries matching the specified displays are removed from the authority file. The specified file is treated as a script containing <code>xauth</code> commands to execute. Blank lines and lines beginning with a pound sign (#) are ignored. A single hyphen may be used to indicate the standard input, if it hasn't already been read.
<code>info</code>	Information describing the authorization file, whether or not any changes have been made, and from where <code>xauth</code> commands are being read is printed on the standard output.
<code>exit</code>	If any modifications have been made, the authority file is written out (if allowed), and the program exits. An end-of-file is treated as an implicit <code>exit</code> command.
<code>quit</code>	The program exits, ignoring any modifications. This may also be accomplished by pressing the interrupt character.
<code>help [string]</code>	A description of all commands that begin with the given string (or all commands if no string is given) is printed on the standard output.
<code>?</code>	A short list of the valid commands is printed on the standard output.

DISPLAY NAMES

Display names for the `add`, `[n]extract`, `[n]list`, `[n]merge`, and `remove` commands use the same format as the `DISPLAY` environment variable and the common `-display` command-line argument. Display-specific information (such as the screen number) is unnecessary and will be ignored. Same-machine connections (such as local-host sockets, shared memory, and the Internet Protocol hostname `localhost`) are referred to as `hostname/unix:displaynumber` so that local entries for different

machines may be stored in one authority file.

EXAMPLE

The most common use for xauth is to extract the entry for the current display, copy it to another machine, and merge it into the user's authority file on the remote machine:

```
% xauth extract  
- $DISPLAY | rsh otherhost xauth merge -
```

ENVIRONMENT

This xauth program uses the following environment variables:

XAUTHORITY	To get the name of the authority file to use if the <code>-f</code> option isn't used.
HOME	To get the user's home directory if XAUTHORITY isn't defined.

FILES

`$HOME/.Xauthority` is the default authority file if XAUTHORITY isn't defined.

X Version 11 Release 6

`[n]list [displayname...]`

Authorization entries for each of the specified displays (or all if no displays are named) are printed on the standard output. If the `nlist` command is used, entries will be shown in the numeric format used by the `nextract` command; otherwise, they are shown in a textual format. Key data is always displayed in the hexadecimal format given in the description of the `add` command.

`[n]merge [filename...]`

Authorization entries are read from the specified files and are merged into the authorization database, superseding any matching existing entries. If the `nmerge` command is used, the numeric format given in the description of the `extract` command is used. If a filename consists of just a single dash, the standard input will be read if it hasn't been read before.

`remove displayname...`

Authorization entries matching the specified displays are removed from the authority file.

`source filename`

The specified file is treated as a script containing `xauth` commands to execute. Blank lines and lines beginning with a `#` are ignored. A single dash may be used to indicate the standard input, if it hasn't already been read.

`info`

Information describing the authorization file, whether or not any changes have been made, and from where `xauth` commands are being read is printed on the standard output.

`exit`

If any modifications have been made, the authority file is written out (if allowed), and the program exits. An end of file is treated as an implicit `exit` command.

`quit`

The program exits, ignoring any modifications. This may also be accomplished by pressing the interrupt character.

`help [string]`

A description of all commands that begin with the given string (or all commands if no string is given) is printed on the standard output.

`?`

A short list of the valid commands is printed on the standard output.

DISPLAY NAMES

Display names for the `add`, `[n]extract`, `[n]list`, `[n]merge`, and `remove` commands use the same format as the `DISPLAY` environment variable and the common `-display` command-line argument. Display-specific information (such as the screen number) is unnecessary and will be ignored. Same-machine connections (such as local-host sockets, shared memory, and the Internet Protocol `hostnamelocalhost`) are referred to as `hostname/unix:displaynumber` so that local entries for different machines may be stored in one authority file.

EXAMPLE

The most common use for `xauth` is to extract the entry for the current display, copy it to another machine, and merge it into the user's authority file on the remote machine:

```
% xauth extract
- $DISPLAY rsh otherhost xauth merge -
```

ENVIRONMENT

This xauth program uses the following environment variables:

<code>XAUTHORITY</code>	To get the name of the authority file to use if the <code>-f</code> option isn't used
<code>HOME</code>	To get the user's home directory if <code>XAUTHORITY</code> isn't defined

FILES

<code>\$HOME/.Xauthority</code>	Default authority file if <code>XAUTHORITY</code> isn't defined

BUGS

Users that have unsecured networks should take care to use encrypted file transfer mechanisms to copy authorization entries between machines. Similarly, the `MIT-MAGIC-COOKIE-1` protocol is not very useful in unsecured environments. Sites that are interested in additional security may need to use encrypted authorization mechanisms such as Kerberos.

Spaces are currently not allowed in the protocol name. Quoting could be added for the truly perverse.

AUTHOR

Jim Fulton, MIT X Consortium

X Version 11 Release 6

xbmtopbm

`xbmtopbm`—Convert an X11 or X10 bitmap into a portable bitmap

SYNOPSIS

```
xbmtopbm [ bitmapfile ]
```

DESCRIPTION

Reads an X11 or X10 bitmap as input. Produces a portable bitmap as output.

SEE ALSO

`pbmtobm(1)`, `pbmtopbm(1)`, `pbm(5)`

AUTHOR

Copyright (c) 1988 by Jef Poskanzer.

31 August 1988

xcmsdb

`xcmsdb`—Device Color Characterization utility for X Color Management System

SYNOPSIS

```
xcmsdb [ -query ] [ -remove ] [ -format 32j16j8 ] [ filename ]
```

DESCRIPTION

`xcmsdb` is used to load, query, or remove device color characterization data stored in properties on the root window of the screen as specified in section 7, Device Color Characterization, of the ICCCM. Device color characterization data (also called the Device Profile) is an integral part of Xlib's X Color Management System (`xcms`), necessary for proper conversion of color specification between device-independent and device-dependent forms. `xcms` uses 3×3 matrices stored in the `XDCCC_LINEAR_RGB_MATRICES` property to convert color specifications between CIEXYZ and RGB Intensity (`XcmsRGBi`, also referred to as linear RGB). `xcms` then uses display gamma information stored in the `XDCCC_LINEAR_RGB_CORRECTION` property to convert color specifications between `RGBi` and RGB device (`XcmsRGB`, also referred to as device RGB).

Note that `xcms` allows clients to register function sets in addition to its built-in function set for CRT color monitors. Additional function sets may store their device profile information in other properties in function set specific format. This utility is unaware of these nonstandard properties.

The ASCII readable contents of filename (or the standard input if no input file is given) are appropriately transformed for storage in properties, provided the `-query` or `-remove` options are not specified.

OPTIONS

`xcmsdb` program accepts the following options:

`-query`

This option attempts to read the `XDCCC` properties off the screen's root window. If successful, it transforms the data into a more readable format, then sends the data to standard out.

`-remove`

This option attempts to remove the `XDCCC` properties on the screen's root window.

`-format 32j16j8`

Specifies the property format (32, 16, or 8 bits per entry) for the `XDCCC_LINEAR_RGB_CORRECTION` property. Precision of encoded floating-point values increases with the increase in bits per entry. The default is 32 bits per entry.

SEE ALSO

`xprop(1)`, Xlib documentation

ENVIRONMENT

`DISPLAY`

To figure out which display and screen to use

AUTHOR

Chuck Adams, Tektronix, Inc., and Al Tabayoyon, SynChromatics, Inc. (added multivisual support)

X Version 11 Release 6

xclock

`xclock`—Analog/digital clock for X

SYNOPSIS

```
xclock [ -help ][-analog ][-digital ][-chime ][-hd color ][-hl color ]
        [-update seconds ][-padding number ]
```

DESCRIPTION

The `xclock` program displays the time in analog or digital form. The time is continuously updated at a frequency which may be specified by the user.

OPTIONS

`xclock` accepts all of the standard X Toolkit command-line options along with the additional options listed here:

<code>-help</code>	This option indicates that a brief summary of the allowed options should be printed on the standard error.
<code>-analog</code>	This option indicates that a conventional 12-hour clock face with tick marks and hands should be used. This is the default.
<code>-digital</code> or <code>-d</code>	This option indicates that a 24-hour digital clock should be used.
<code>-chime</code>	This option indicates that the clock should chime once on the half hour and twice on the hour.
<code>-hands color</code> (or <code>-hd color</code>)	This option specifies the color of the hands on an analog clock. The default is <code>black</code> .
<code>-highlight color</code> (or <code>-hl color</code>)	This option specifies the color of the edges of the hands on an analog clock, and is only useful on color displays. The default is <code>black</code> .
<code>-update seconds</code>	This option specifies the frequency in seconds at which <code>xclock</code> should update its display. If the clock is obscured and then exposed, it will be updated immediately. A value of 30 seconds or less will enable a second hand on an analog clock. The default is 60 seconds.
<code>-padding number</code>	This option specifies the width in pixels of the padding between the window border and clock text or picture. The default is 10 on a digital clock and 8 on an analog clock.

X DEFAULTS

This program uses the Clock widget. It understands all of the core resource names and classes as well as:

<code>width</code> (class <code>Width</code>)	Specifies the width of the clock. The default for analog clocks is 164 pixels; the default for digital clocks is whatever is needed to hold the clock when displayed in the chosen font.
<code>height</code> (class <code>Height</code>)	Specifies the height of the clock. The default for analog clocks is 164 pixels; the default for digital clocks is whatever is needed to hold the clock when displayed in the chosen font.
<code>update</code> (class <code>Interval</code>)	Specifies the frequency in seconds at which the time should be redisplayed.
<code>foreground</code> (class <code>Foreground</code>)	Specifies the color for the tick marks. The default is depends on whether <code>reverseVideo</code> is specified. If <code>reverseVideo</code> is specified, the default is <code>white</code> ; otherwise, the default is <code>black</code> .
<code>hands</code> (class <code>Foreground</code>)	Specifies the color of the insides of the clock's hands. The default depends on whether <code>reverseVideo</code> is specified. If <code>reverseVideo</code> is specified, the default is <code>white</code> ; otherwise, the default is <code>black</code> .
<code>highlight</code> (class <code>Foreground</code>)	Specifies the color used to highlight the clock's hands. The default depends on whether <code>reverseVideo</code> is specified. If <code>reverseVideo</code> is specified, the default is <code>white</code> ; otherwise, the default is <code>black</code> .
<code>analog</code> (class <code>Boolean</code>)	Specifies whether or not an analog clock should be used instead of a digital one. The default is <code>True</code> .
<code>chime</code> (class <code>Boolean</code>)	Specifies whether or not a bell should be rung on the hour and half hour.

padding (class Margin)

Specifies the amount of internal padding in pixels to be used. The default is 8.

font (class Font)

Specifies the font to be used for the digital clock. Note that variable width fonts currently will not always display correctly.

WIDGETS

In order to specify resources, it is useful to know the hierarchy of the widgets which compose `xclock`. In the following notation, indentation indicates hierarchical structure. The widget class name is given first, followed by the widget instance name:

```
XClock xclock
  Clock clock
```

ENVIRONMENT

DISPLAY

To get the default host and display number

XENVIRONMENT

To get the name of a resource file that overrides the global resources stored in the `RESOURCE_MANAGER` property

FILES

<XRoott/lib/X11/app-defaults/XClock

Specifies required resources

SEE ALSO

`x(1)`, `xrdb(1)`, `time(3C)`

BUGS

`xclock` believes the system clock.

When in digital mode, the string should be centered automatically.

AUTHORS

Tony Della Fera (MIT-Athena, DEC), Dave Mankins (MIT-Athena, BBN), and Ed Moy (UC Berkeley)

X Version 11 Release 6

xclipboard

xclipboard—X clipboard client

SYNOPSIS

```
xclipboard [ -toolkitoption ... ] [ -w ][-nw ]
```

DESCRIPTION

The `xclipboard` program is used to collect and display text selections that are sent to the Clipboard by other clients. It is typically used to save Clipboard selections for later use. It stores each Clipboard selection as a separate string, each of which can be selected. Each time Clipboard is asserted by another application, `xclipboard` transfers the contents of that selection to a new buffer and displays it in the text window. Buffers are never automatically deleted, so you'll want to use the delete button to get rid of useless items.

Since `xclipboard` uses a Text Widget to display the contents of the clipboard, text sent to the Clipboard may be reselected for use in other applications. `xclipboard` also responds to requests for the Clipboard selection from other clients by sending the entire contents of the currently displayed buffer.

An `xclipboard` window has the following buttons across the top:

quit	When this button is pressed, <code>xclipboard</code> exits.
delete	When this button is pressed, the current buffer is deleted and the next one displayed.
new	Creates a new buffer with no contents. Useful in constructing a new Clipboard selection by hand.
save	Displays a File Save dialog box. Pressing the Accept button saves the currently displayed buffer to the file specified in the text field.
next	Displays the next buffer in the list.
previous	Displays the previous buffer.

OPTIONS

The `xclipboard` program accepts all of the standard X Toolkit command-line options as well as the following:

<code>-w</code>	This option indicates that lines of text that are too long to be displayed on one line in the clipboard should wrap around to the following lines.
<code>-nw</code>	This option indicates that long lines of text should not wrap around. This is the default behavior.

WIDGETS

In order to specify resources, it is useful to know the hierarchy of the widgets which compose `xclipboard`. In the following notation, indentation indicates hierarchical structure. The widget class name is given first, followed by the widget instance name.

```
XClipboard xclipboard
  Form form
    Command Quit
    Command delete
    Command new
    Command Save
    Command next
    Command prev
    Label index
    Text text
  TransientShell fileDialogShell
    Dialog fileDialog
    Label label
    Command accept
    Command cancel
    Text value
  TransientShell failDialogShell
    Dialog failDialog
    Label label
    Command continue
```

SENDING/RETRIEVING CLIPBOARD CONTENTS

Text is copied to the Clipboard whenever a client asserts ownership of the Clipboard selection. Text is copied from the Clipboard whenever a client requests the contents of the Clipboard selection. Examples of event bindings that a user may wish to include in a resource configuration file to use the Clipboard are

```
*VT100.Translations: #override \
<Btn3Up>: select-end(CLIPBOARD) \n\
```



```
<Btn2Up>: insert-selection(PRIMARY,CLIPBOARD) \n\
<Btn2Down>: ignore ()
```

SEE ALSO

x(1), xcutsel(1), xterm(1), individual client documentation for how to make a selection and send it to the Clipboard.

ENVIRONMENT

DISPLAY

To get the default host and display number

XENVIRONMENT

To get the name of a resource file that overrides the global resources stored in the RESOURCE_MANAGER property

FILES

<XRoot>/lib/X11/app-defaults/XClipboard

Specifies required resources

AUTHOR

Ralph R. Swick (DEC/MIT Project Athena), Chris D. Peterson (MIT X Consortium), Keith Packard (MIT X Consortium)

X Version 11 Release 6

xconsole

xconsole—Monitor system console messages with X

SYNOPSIS

```
xconsole [-toolkitoption ...] [-file file-name] [-notify] [-stripNonprint] [-daemon] [-verbose]
        [-exitOnFail]
```

DESCRIPTION

The xconsole program displays messages that are usually sent to /dev/console.

OPTIONS

xconsole accepts all of the standard X Toolkit command-line options along with the additional options listed here:

-file file-name

To monitor some other device, use this option to specify the device name. This does not work on regular files as they are always ready to be read from.

-notify, -nonotify

When new data are received from the console and the notify option is set, the icon name of the application has * appended, so that it is evident even when the application is iconified. -notify is the default.

-daemon

This option causes xconsole to place itself in the background, using fork/exit.

-verbose

When set, this option directs xconsole to display an informative message in the first line of the text buffer.

-exitOnFail

When set, this option directs xconsole to exit when it is unable to redirect the console output.

X DEFAULTS

This program uses the Athena Text widget, look in the Athena Widget Set documentation for controlling it.

WIDGETS

In order to specify resources, it is useful to know the hierarchy of the widgets that compose `xconsole`. In the following notation, indentation indicates hierarchical structure. The widget class name is given first, followed by the widget instance name.

```
XConsole xconsole
      XConsole text
```

ENVIRONMENT

`DISPLAY`

To get the default host and display number.

`XENVIRONMENT`

To get the name of a resource file that overrides the global resources stored in the `RESOURCE_MANAGER` property.

FILES

`<XRoot>/lib/X11/app-defaults/XConsole`

Specifies required resources

SEE ALSO

`x(1)`, `xrdb(1)`, Athena Text widget

AUTHOR

Keith Packard (MIT X Consortium)

X Version 11 Release 6

xcutsel

`xcutsel`—Interchange between cut buffer and selection

SYNOPSIS

```
xcutsel [ -toolkitoption ... ] [-selection selection] [-cutbuffer number]
```

DESCRIPTION

The `xcutsel` program is used to copy the current selection into a cut buffer and to make a selection that contains the current contents of the cut buffer. It acts as a bridge between applications that don't support selections and those that do.

By default, `xcutsel` will use the selection named `PRIMARY` and the cut buffer `CUT_BUFFER0`. Either or both of these can be overridden by command-line arguments or by resources.

An `xcutsel` window has the following buttons:

quit

When this button is pressed, `xcutsel` exits. Any selections held by `xcutsel` are automatically released.

copy `PRIMARY` to 0

When this button is pressed, `xcutsel` copies the current selection into the cut buffer.

copy 0 to `PRIMARY`

When this button is pressed, `xcutsel` converts the current contents of the cut buffer into the selection.

The button labels reflect the selection and cut buffer selected by command-line options or through the resource database.

When the copy 0 to `PRIMARY` button is activated, the button will remain inverted as long as `xcutsel` remains the owner of the selection. This serves to remind you which client owns the current selection. Note that the value of the selection remains constant; if the cut buffer is changed, you must again activate the copy button to retrieve the new value when desired.

OPTIONS

`xcutsel` accepts all of the standard X Toolkit command-line options as well as the following:

<code>-selection name</code>	This option specifies the name of the selection to use. The default is <code>PRIMARY</code> . The only supported abbreviations for this option are <code>-select</code> , <code>-sel</code> , and <code>-s</code> , as the standard toolkit option <code>-selectionTimeout</code> has a similar name.
<code>-cutbuffer number</code>	This option specifies the cut buffer to use. The default is <code>cutbuffer 0</code> .

X DEFAULTS

This program accepts all of the standard X Toolkit resource names and classes as well as the following:

<code>selection (class Selection)</code>	This resource specifies the name of the selection to use. The default is <code>PRIMARY</code> .
<code>cutBuffer (class CutBuffer)</code>	This resource specifies the number of the <code>cutbuffer</code> to use. The default is <code>0</code> .

WIDGET NAMES

The following instance names may be used when user configuration of the labels in them is desired:

<code>sel-cut (class Command)</code>	This is the “copy <code>SELECTION</code> to <code>BUFFER</code> ” button.
<code>cut-sel (class Command)</code>	This is the “copy <code>BUFFER</code> to <code>SELECTION</code> ” button.
<code>quit (class Command)</code>	This is the “quit” button.

SEE ALSO

`x(1)`, `xclipboard(1)`, `xterm(1)`, text widget documentation, individual client documentation for how to make a selection.

BUGS

There is no way to change the name of the selection or the number of the cut buffer while the program is running.

AUTHOR

Ralph R. Swick (DEC/MIT Project Athena)

X Version 11 Release 6

xdm

`xdm`—X Display Manager with support for XDMCP, host chooser

SYNOPSIS

```
xdm [ -config configuration_file ][-nodaemon ][-debug debug_level ]
    [-error error_log_file ][-resources resource_file ][-server server_entry ]
    [-session session_program]
```

DESCRIPTION

`xdm` manages a collection of X displays, which may be on the local host or remote servers. The design of `xdm` was guided by the needs of X terminals as well as the X Consortium standard `XDMCP`, the X Display Manager Control Protocol. `xdm` provides services similar to those provided by `init`, `getty`, and `login` on character terminals: prompting for login name and password, authenticating the user, and running a session.

A *session* is defined by the lifetime of a particular process; in the traditional character-based terminal world, it is the user's login shell. In the `xm` context, it is an arbitrary session manager. This is because in a windowing environment, a user's login shell process does not necessarily have any terminal-like interface with which to connect. When a real session manager is not available, a window manager or terminal emulator is typically used as the *session manager*, meaning that termination of this process terminates the user's session.

When the session is terminated, `xm` resets the X server and (optionally) restarts the whole process.

When `xm` receives an Indirect query via XDMCP, it can run a chooser process to perform an XDMCP BroadcastQuery (or an XDMCP Query to specified hosts) on behalf of the display and offer a menu of possible hosts that offer XDMCP display management. This feature is useful with X terminals that do not offer a host menu themselves.

Because `xm` provides the first interface that users will see, it is designed to be simple to use and easy to customize to the needs of a particular site. `xm` has many options, most of which have reasonable defaults. Browse through the various sections of this manual, picking and choosing the things you want to change. Pay particular attention to the "Session Program" subsection, which will describe how to set up the style of session desired.

OVERVIEW

`xm` is highly configurable, and most of its behavior can be controlled by resource files and shell scripts. The names of these files themselves are resources read from the file `xm-config` or the file named by the `-config` option.

`xm` offers display management two different ways. It can manage X servers running on the local machine and specified in `xservers`, and it can manage remote X servers (typically X terminals) using XDMCP (the XDM Control Protocol) as specified in the `xaccess` file.

The resources of the X clients run by `xm` outside the user's session, including `xm`'s own login window, can be affected by setting resources in the `xresources` file.

For X terminals that do not offer a menu of hosts to get display management from, `xm` can collect willing hosts and run the chooser program to offer the user a menu. For X displays attached to a host, this step is typically not used, as the local host does the display management.

After resetting the X server, `xm` runs the `xsetup` script to assist in setting up the screen the user sees along with the `xlogin` widget.

When the user logs in, `xm` runs the `xstartup` script as root.

Then `xm` runs the `xsession` script as the user. This system session file may do some additional startup and typically runs a script in the user's home directory. When the `xsession` script exits, the session is over.

At the end of the session, the `xreset` script is run to clean up, the X server is reset, and the cycle starts over.

The file `/usr/X11R6/lib/X11/xm/xm-errors` will contain error messages from `xm` and anything output to `stderr` by `xsetup`, `xstartup`, `xsession`, or `xreset`. When you have trouble getting `xm` working, check this file to see if `xm` has any clues to the trouble.

OPTIONS

All of these options, except `-config` itself, specify values that can also be specified in the configuration file as resources.

`-config configuration_file`

Names the configuration file, which specifies resources to control the behavior of `xm`. `<XRoot>/lib/X11/xm/xm-config` is the default. See the subsection called "Configuration File."

`-nodaemon`

Specifies `false` as the value for the `DisplayManager.daemonMode` resource. This suppresses the normal daemon behavior, which is for `xm` to close all file descriptors, disassociate itself from the controlling terminal, and put itself in the background when it first starts up.

<code>-debug debug_level</code>	Specifies the numeric value for the <code>DisplayManager.debugLevel</code> resource. A non-zero value causes <code>x_{dm}</code> to print lots of debugging statements to the terminal; it also disables the <code>DisplayManager.daemonMode</code> resource, forcing <code>x_{dm}</code> to run synchronously. To interpret these debugging messages, a copy of the source code for <code>x_{dm}</code> is almost a necessity. No attempt has been made to rationalize or standardize the output.
<code>-error error_log_file</code>	Specifies the value for the <code>DisplayManager.errorLogFile</code> resource. This file contains errors from <code>x_{dm}</code> as well as anything written to <code>stderr</code> by the various scripts and programs run during the progress of the session.
<code>-resources resource_file</code>	Specifies the value for the <code>DisplayManager*resources</code> resource. This file is loaded using <code>xrdb</code> to specify configuration parameters for the authentication widget.
<code>-server server_entry</code>	Specifies the value for the <code>DisplayManager.servers</code> resource. See the subsection “Local Server Specification” for a description of this resource.
<code>-udpPort port_number</code>	Specifies the value for the <code>DisplayManager.requestPort</code> resource. This sets the port number, which <code>x_{dm}</code> will monitor for XDMCP requests. As XDMCP uses the registered well-known UDP port 177, this resource should not be changed except for debugging.
<code>-session session_program</code>	Specifies the value for the <code>DisplayManager*session</code> resource. This indicates the program to run as the session after the user has logged in.
<code>-xrm resource_specification</code>	Allows an arbitrary resource to be specified, as in most X Toolkit applications.

RESOURCES

At many stages the actions of `xdm` can be controlled through the use of its configuration file, which is in the X resource format. Some resources modify the behavior of `xdm` on all displays, while others modify its behavior on a single display. Where actions relate to a specific display, the display name is inserted into the resource name between `Display-Manager` and the final resource name segment.

For local displays, the resource name and class are as read from the `xservers` file.

For remote displays, the resource name is what the network address of the display resolves to. See the `removeDomain` resource. The name must match exactly; `xdm` is not aware of all the network aliases that might reach a given display. If the name resolve fails, the address is used. The resource class is as sent by the display in the XDMCP Manage request.

Because the resource manager uses colons to separate the name of the resource from its value and dots to separate resource name parts, `xdm` substitutes underscores for both dots and colons when generating the resource name. For example, `DisplayManager.expo x org 0.startup` is the name of the resource that defines the startup shell file for the `expo.x.org:0` display.

`DisplayManager.servers`

This resource either specifies a filename full of server entries, one per line (if the value starts with a slash), or a single server entry. See the subsection “Local Server Specification” for the details.

`DisplayManager.requestPort`

This indicates the UDP port number that `xdm` uses to listen for incoming XDMCP requests. Unless you need to debug the system, leave this with its default value of 177.

`DisplayManager.errorLogFile`

Error output is normally directed at the system console. To redirect it, set this resource to a filename. A method to send these messages to `syslog` should be developed for systems that support it; however, the wide variety of interfaces precludes any system-independent implementation. This file also contains any output directed to `stderr` by the `xsetup`, `xstartup`, `xsession`, and `xreset` files, so it will contain descriptions of problems in those scripts as well.

`DisplayManager.debugLevel`

If the integer value of this resource is greater than zero, reams of debugging information will be printed. It also disables daemon mode, which would redirect the information into the bit-bucket, and allows nonroot users to run `xdm`, which would normally not be useful.

`DisplayManager.daemonMode`

Normally, `xdm` attempts to make itself into a daemon process unassociated with any terminal. This is accomplished by forking and leaving the parent process to exit, then closing file descriptors and releasing the controlling terminal. In some environments this is not desired (in particular, when debugging). Setting this resource to `false` will disable this feature.

`DisplayManager.pidFile`

The filename specified will be created to contain an ASCII representation of the process-id of the main `xdm` process. `xdm` also uses file locking on this file to attempt to eliminate multiple daemons running on the same machine, which would cause quite a bit of havoc.

`DisplayManager.lockPidFile`

This is the resource which controls whether `xdm` uses file locking to keep multiple display managers from running amok. On System V, this uses the `lockf` library call, while on BSD it uses `flock`.

`DisplayManager.authDir`

This names a directory in which `xdm` stores authorization files while initializing the session. The default value is `y`.

`DisplayManager.autoRescan`

This Boolean controls whether `xdm` rescans the configuration, servers, access control and authentication keys files after a session terminates and the files have changed. By default it is `true`. You can force `xdm` to reread these files by sending a `SIGHUP` to the main process.

`DisplayManager.removeDomainname`

When computing the display name for XDMCP clients, the name resolver will typically create a fully qualified hostname for the terminal. As this is sometimes confusing, `xdm` will remove the domain name portion of the hostname if it is the same as the domain name of the local host when this variable is set. By default the value is `true`.

`DisplayManager.keyFile`

XDM-AUTHENTICATION-1 style XDMCP authentication requires that a private key be shared between `xdm` and the terminal. This resource specifies the file containing those values. Each entry in the file consists of a display name and the shared key. By default, `xdm` does not include support for XDM-AUTHENTICATION-1, as it requires DES, which is not generally distributable because of United States export restrictions.

<code>DisplayManager.accessFile</code>	To prevent unauthorized XDMCP service and to allow forwarding of XDMCP <code>IndirectQuery</code> requests, this file contains a database of hostnames that are either allowed direct access to this machine, or have a list of hosts to which queries should be forwarded to. The format of this file is described in the subsection “XDMCP Access Control.”
<code>DisplayManager.exportList</code>	A list of additional environment variables, separated by whitespace, to pass on to the <code>Xsetup</code> , <code>Xstartup</code> , <code>Xsession</code> , and <code>Xreset</code> programs.
<code>DisplayManager.randomFile</code>	A file to checksum to generate the seed of authorization keys. This should be a file that changes frequently. The default is <code>/dev/mem</code> .
<code>DisplayManager.greeterLib</code>	On systems that support a dynamically loadable greeter library, the name of the library. Default is <code><XRoot>/lib/X11/xdm/libXdmGreet.so</code> .
<code>DisplayManager.choiceTimeout</code>	Number of seconds to wait for display to respond after user has selected a host from the chooser. If the display sends an XDMCP <code>IndirectQuery</code> within this time, the request is forwarded to the chosen host. Otherwise, it is assumed to be from a new session and the chooser is offered again. Default is 15.
<code>DisplayManager.DISPLAY.resources</code>	This resource specifies the name of the file to be loaded by <code>xrdb</code> as the resource database onto the root window of screen 0 of the display. The <code>Xsetup</code> program, the Login widget, and chooser will use the resources set in this file. This resource database is loaded just before the authentication procedure is started, so it can control the appearance of the login window. See the subsection “Authentication Widget,” which describes the various resources that are appropriate to place in this file. There is no default value for this resource, but <code><XRoot>/lib/X11/xdm/Xresources</code> is the conventional name.
<code>DisplayManager.DISPLAY.chooser</code>	Specifies the program run to offer a host menu for <code>Indirect</code> queries redirected to the special hostname <code>CHOOSE</code> R. <code><XRoot>/lib/X11/xdm/chooser</code> is the default. See the subsections “XDMCP Access Control” and “chooser.”
<code>DisplayManager.DISPLAY.xrdb</code>	Specifies the program used to load the resources. By default, <code>x_{dm}</code> uses <code><XRoot>/bin/xrdb</code> .
<code>DisplayManager.DISPLAY.cpp</code>	This specifies the name of the C preprocessor that is used by <code>xrdb</code> .
<code>DisplayManager.DISPLAY.setup</code>	This specifies a program that is run (as root) before offering the Login window. This may be used to change the appearance of the screen around the Login window or to put up other windows (for example, you may want to run <code>xconsole</code> here). By default, no program is run. The conventional name for a file used here is <code>Xsetup</code> . See the subsection “Setup Program.”
<code>DisplayManager.DISPLAY.startup</code>	This specifies a program that is run (as root) after the authentication process succeeds. By default, no program is run. The conventional name for a file used here is <code>Xstartup</code> . See the subsection “Startup Program.”
<code>DisplayManager.DISPLAY.session</code>	This specifies the session to be executed (not running as root). By default, <code><XRoot>/bin/xterm</code> is run. The conventional name is <code>Xsession</code> . See the subsection “Session Program.”

`DisplayManager.DISPLAY.reset`

`DisplayManager.DISPLAY.openDelay,`
`DisplayManager.DISPLAY.openRepeat,`
`DisplayManager.DISPLAY.openTimeout,`
`DisplayManager.DISPLAY.startAttempts`

`DisplayManager.DISPLAY.pingInterval,`
`DisplayManager.DISPLAY.pingTimeout`

`DisplayManager.DISPLAY.`
`terminateServer`

`DisplayManager.DISPLAY.userPath`

`DisplayManager.DISPLAY.`
`systemPath`

This specifies a program which is run (as root) after the session terminates. Again, by default, no program is run. The conventional name is `Xreset`. See the subsection “Reset Program.”

These numeric resources control the behavior of `xdm` when attempting to open intransigent servers. `openDelay` is the length of the pause (in seconds) between successive attempts, `openRepeat` is the number of attempts to make, `openTimeout` is the amount of time to wait while actually attempting the open (that is, the maximum time spent in the `connect(2)` system call) and `startAttempts` is the number of times this entire process is done before giving up on the server. After `openRepeat` attempts have been made, or if `openTimeout` seconds elapse in any particular attempt, `xdm` terminates and restarts the server, attempting to connect again. This process is repeated `startAttempts` times, at which point the display is declared dead and disabled. Although this behavior may seem arbitrary, it has been empirically developed and works quite well on most systems. The default values are 5 for `openDelay`, 5 for `openRepeat`, 30 for `openTimeout` and 4 for `startAttempts`.

To discover when remote displays disappear, `xdm` occasionally pings them, using an X connection and `XSync` calls. `pingInterval` specifies the time (in minutes) between each ping attempt, `pingTimeout` specifies the maximum amount of time (in minutes) to wait for the terminal to respond to the request. If the terminal does not respond, the session is declared dead and terminated. By default, both are set to 5 minutes. If you frequently use X terminals that can become isolated from the managing host, you might want to increase this value. The only worry is that sessions will continue to exist after the terminal has been accidentally disabled. `xdm` will not ping local displays. Although it would seem harmless, it is unpleasant when the workstation session is terminated as a result of the server hanging for NFS service and not responding to the ping.

This Boolean resource specifies whether the X server should be terminated when a session terminates (instead of resetting it). This option can be used when the server tends to grow without bound over time, in order to limit the amount of time the server is run. The default value is `false`.

`xdm` sets the `PATH` environment variable for the session to this value. It should be a colon separated list of directories; see `sh(1)` for a full description. `:/bin:/usr/bin:/usr/X11R6/bin:/usr/ucb` is a common setting. The default value can be specified at build time in the `X` system configuration file with `DefaultUserPath`.

`Xdm` sets the `PATH` environment variable for the startup and reset scripts to the value of this resource. The default for this resource is specified at build time by the `DefaultSystem-Path` entry in the system configuration file; `/etc:/bin:/usr/bin`

DisplayManager.DISPLAY.
systemShell

DisplayManager.DISPLAY
failsafeClient

DisplayManager.DISPLAY.grabServer,
DisplayManager.DISPLAY.grabTimeout xdm

DisplayManager.DISPLAY.authorize,
DisplayManager.DISPLAY.authName

DisplayManager.DISPLAY.authFile

DisplayManager.DISPLAY.
authComplain

DisplayManager.DISPLAY.
resetSignal

DisplayManager.DISPLAY.
termSignal

: /usr/X11R6/bin:/usr/ucb is a common choice. Note the absence of (.) from this entry. This is a good practice to follow for root; it avoids many common Trojan Horse system penetration schemes.

Xdm sets the SHELL environment variable for the startup and reset scripts to the value of this resource. It is /bin/sh by default.

If the default session fails to execute, xdm will fall back to this program. This program is executed with no arguments, but executes using the same environment variables as the session would have had. (See the subsection “Session Program.”) By default, <XRoot>/bin/xterm is used.

To improve security, this grabs the server and keyboard while reading the login name and password. The grabServer resource specifies if the server should be held for the duration of the name/password reading. When false, the server is ungrabbed after the keyboard grab succeeds; otherwise, the server is grabbed until just before the session begins. The default is false. The grabTimeout resource specifies the maximum time xdm will wait for the grab to succeed. The grab may fail if some other client has the server grabbed, or possibly if the network latencies are very high. This resource has a default value of 3 seconds; you should be cautious when raising it, as a user can be spoofed by a look-alike window on the display. If the grab fails, xdm kills and restarts the server (if possible) and the session.

authorize is a Boolean resource that controls whether xdm generates and uses authorization for the local server connections. If authorization is used, authName is a list of authorization mechanisms to use, separated by whitespace. XDMCP connections dynamically specify which authorization mechanisms are supported, so authName is ignored in this case. When authorize is set for a display and authorization is not available, the user is informed by having a different message displayed in the Login widget. By default, authorize is true. authName is MIT-MAGIC-COOKIE-1, or, if XDM-AUTHORIZATION-1 is available, XDM-AUTHORIZATION-1 MIT-MAGIC-COOKIE-1.

This file is used to communicate the authorization data from xdm to the server, using the -auth server command-line option. It should be kept in a directory that is not world-writable as it could easily be removed, disabling the authorization mechanism in the server.

If set to false, disables the use of the insecureGreeting in the login window. See the subsection “Authentication Widget.” The default is true.

The number of the signal xdm sends to reset the server. See the subsection “Controlling the Server.” The default is 1 (SIGHUP).

The number of the signal xdm sends to terminate the server. See the subsection “Controlling the Server.” The default is 15 (SIGTERM).

```
DisplayManager.DISPLAY.  
resetForAuth
```

```
DisplayManager.DISPLAY.  
userAuthDir
```

The original implementation of authorization in the sample server reread the authorization file at server reset time, instead of when checking the initial connection. As `xdm` generates the authorization information just before connecting to the display, an old server would not get up-to-date authorization information. This resource causes `xdm` to send `SIGHUP` to the server after setting up the file, causing an additional server reset to occur, during which time the new authorization information will be read. The default is `false`, which will work for all MIT servers.

When `xdm` is unable to write to the usual user authorization file (`$HOME/.Xauthority`), it creates a unique filename in this directory and points the environment variable `XAUTHORITY` at the created file. It uses `/tmp` by default.

CONFIGURATION FILE

First, the `xdm` configuration file should be set up. Make a directory (usually `<XRoot>/lib/X11/xdm`, where `<XRoot>` refers to the root of the X11 install tree) to contain all of the relevant files. In the examples that follow, `/usr/X11R6` is used as the value of `<XRoot>`.

Here is a reasonable configuration file, which could be named `xdm-config`:

```
DisplayManager.servers: /usr/X11R6/lib/X11/xdm/Xservers  
DisplayManager.errorLogFile: /usr/X11R6/lib/X11/xdm/xdm-errors  
DisplayManager*resources: /usr/X11R6/lib/X11/xdm/Xresources  
DisplayManager*startup: /usr/X11R6/lib/X11/xdm/Xstartup  
DisplayManager*session: /usr/X11R6/lib/X11/xdm/Xsession  
DisplayManager.pidFile: /usr/X11R6/lib/X11/xdm/xdm-pid  
DisplayManager. 0.authorize: true  
DisplayManager*authorize: false
```

Note that this file mostly contains references to other files. Note also that some of the resources are specified with `*` separating the components. These resources can be made unique for each different display, by replacing the `*` with the display name, but normally this is not very useful. See the “Resources” section for a complete discussion.

XDMCP ACCESS CONTROL

The database file specified by the `DisplayManager.accessFile` provides information which `xdm` uses to control access from displays requesting XDMCP service. This file contains three types of entries: entries that control the response to `Direct` and `Broadcast` queries, entries that control the response to `Indirect` queries, and macro definitions.

The format of the `Direct` entries is simple, either a hostname or a pattern, which is distinguished from a hostname by the inclusion of one or more metacharacters (`*` matches any sequence of 0 or more characters, and `?` matches any single character) which are compared against the hostname of the display device. If the entry is a hostname, all comparisons are done using network addresses, so any name which converts to the correct network address may be used. For patterns, only canonical hostnames are used in the comparison, so ensure that you do not attempt to match aliases. Preceding either a hostname or a pattern with a `!` character causes hosts that match that entry to be excluded.

An `Indirect` entry also contains a hostname or pattern, but follows it with a list of hostnames or macros to which indirect queries should be sent.

A macro definition contains a macro name and a list of hostnames and other macros that the macro expands to. To distinguish macros from hostnames, macro names start with a `%` character. Macros may be nested.

`Indirect` entries may also specify to have `xdm` run `chooser` to offer a menu of hosts to connect to. See the subsection “chooser.”

When checking access for a particular display host, each entry is scanned in turn and the first matching entry determines the response. Direct and Broadcast entries are ignored when scanning for an Indirect entry and vice versa.

Blank lines are ignored, # is treated as a comment delimiter causing the rest of that line to be ignored, and \newline causes the newline to be ignored, allowing indirect host lists to span multiple lines. Here is a sample Xaccess file:

```
#
# Xaccess - XDMCP access control file
#
#
# Direct/Broadcast query entries
#
!xtra.lcs.mit.edu # disallow direct/broadcast service for xtra
bambi.ogi.edu # allow access from this particular display
.lcs.mit.edu # allow access from any display in LCS
#
# Indirect query entries
#
%HOSTS expo.lcs.mit.edu xenon.lcs.mit.edu \
excess.lcs.mit.edu kanga.lcs.mit.edu extract.lcs.mit.edu xenon.lcs.mit.edu #force extract to contact xenon
!xtra.lcs.mit.edu dummy #disallow indirect access
.lcs.mit.edu %HOSTS #all others get to choose
```

chooser

For X terminals that do not offer a host menu for use with Broadcast or Indirect queries, the chooser program can do this for them. In the Xaccess file, specify CHOOSE as the first entry in the Indirect host list. chooser will send a Query request to each of the remaining hostnames in the list and offer a menu of all the hosts that respond.

The list may consist of the word BROADCAST, in which case chooser will send a Broadcast instead, again offering a menu of all hosts that respond. Note that on some operating systems, UDP packets cannot be broadcast, so this feature will not work.

Example Xaccess file using chooser:

```
extract.lcs.mit.edu CHOOSE %HOSTS #offer a menu of these hosts
xtra.lcs.mit.edu CHOOSE BROADCAST #offer a menu of all hosts
```

The program to use for chooser is specified by the DisplayManager.DISPLAY.chooser resource. For more flexibility at this step, the chooser could be a shell script. chooser is the session manager here; it is run instead of a child xdm to manage the display.

Resources for this program can be put into the file named by DisplayManager.DISPLAY.resources.

When the user selects a host, chooser prints the host chosen, which is read by the parent xdm, and exits. xdm closes its connection to the X server, and the server resets and sends another Indirect XDMCP request. xdm remembers the user's choice (for DisplayManager.choiceTimeout seconds) and forwards the request to the chosen host, which starts a session on that display.

LOCAL SERVER SPECIFICATION

The resource DisplayManager.servers gives a server specification or, if the values starts with a slash (/), the name of a file containing server specifications, one per line.

Each specification indicates a display which should constantly be managed and which is not using XDMCP. This method is used typically for local servers only. If the resource or the file named by the resource is empty, xdm will offer XDMCP service only.

Each specification consists of at least three parts: a display name, a display class, a display type, and (for local servers) a command line to start the server. A typical entry for local display number 0 would be

```
:0 Digital-QV local /usr/X11R6/bin/X :0
```

The display types are

Local local display: `xm` must run the server

Foreign remote display: `xm` opens an X connection to a running server

The display name must be something that can be passed in the `-display` option to an X program. This string is used to generate the display-specific resource names, so be careful to match the names (for example, use `:0 Sun-CG3 local /usr/X11R6/bin/X :0` instead of `localhost:0 Sun-CG3 local /usr/X11R6/bin/X :0` if your other resources are specified as `DisplayManager._0.session`). The display class portion is also used in the display-specific resources, as the class of the resource. This is useful if you have a large collection of similar displays (such as a corral of X terminals) and would like to set resources for groups of them. When using XDMCP, the display is required to specify the display class, so the manual for your particular X terminal should document the display class string for your device. If it doesn't, you can run `xm` in debug mode and look at the resource strings that it generates for that device, which will include the class string.

When `xm` starts a session, it sets up authorization data for the server. For local servers, `xm` passes `-auth filename` on the server's command line to point it at its authorization data. For XDMCP servers, `xm` passes the authorization data to the server via the `Accept XDMCP` request.

RESOURCES FILE

The `xresources` file is loaded onto the display as a resource database using `xrdb`. As the authentication widget reads this database before starting up, it usually contains parameters for that widget:

```
xlogin*login.translations: #override\
Ctrl<Key>R: abort-display()\n\
<Key>F1: set-session-argument(failsafe) finish-field()\n\
<Key>Return: set-session-argument() finish-field()
xlogin*borderWidth: 3
xlogin*greeting: CLIENTHOST
#ifdef COLOR
xlogin*greetColor: CadetBlue
xlogin*failColor: red
#endif
```

Please note the translations entry; it specifies a few new translations for the widget that allow users to escape from the default session (and avoid troubles that may occur in it). Note that if `#override` is not specified, the default translations are removed and replaced by the new value, not a very useful result as some of the default translations are quite useful (such as `<Key>: insert-char ()`, which responds to normal typing).

This file may also contain resources for the setup program and chooser.

SETUP PROGRAM

The `Xsetup` file is run after the server is reset, but before the Login window is offered. The file is typically a shell script. It is run as root, so you should be careful about security. This is the place to change the root background or bring up other windows that should appear on the screen along with the Login widget.

In addition to any specified by `DisplayManager.exportList`, the following environment variables are passed:

<code>DISPLAY</code>	The associated display name
<code>PATH</code>	The value of <code>DisplayManager.DISPLAY.systemPath</code>
<code>SHELL</code>	The value of <code>DisplayManager.DISPLAY.systemShell</code>
<code>XAUTHORITY</code>	May be set to an authority file

Note that since `xm` grabs the keyboard, any other windows will not be able to receive keyboard input. They will be able to interact with the mouse, however; beware of potential security holes here. If `DisplayManager.DISPLAY.grabServer` is set, `Xsetup` will not be able to connect to the display at all. Resources for this program can be put into the file named by `DisplayManager.DISPLAY.resources`.

Here is a sample Xsetup script:

```
#!/bin/sh
# Xsetup 0 - setup script for one workstation
xcmsdb </usr/X11R6/lib/monitors/alex.0
xconsole -geometry 480x130-0-0 -notify -verbose -exitOnFail &
```

AUTHENTICATION WIDGET

The authentication widget reads a name/password pair from the keyboard. Nearly every imaginable parameter can be controlled with a resource. Resources for this widget should be put into the file named by `DisplayManager.DISPLAY.resources`. All of these have reasonable default values, so it is not necessary to specify any of them.

```
xlogin.Login.width,
xlogin.Login.height,
xlogin.Login.x,
xlogin.Login.y
xlogin.Login.foreground
xlogin.Login.font
xlogin.Login.greeting

xlogin.Login.unsecureGreeting

xlogin.Login.greetFont
xlogin.Login.greetColor
xlogin.Login.namePrompt

xlogin.Login.passwdPrompt

xlogin.Login.promptFont
xlogin.Login.promptColor
xlogin.Login.fail

xlogin.Login.failFont
xlogin.Login.failColor
xlogin.Login.failTimeout

xlogin.Login.translations
```

The geometry of the Login widget is normally computed automatically. If you wish to position it elsewhere, specify each of these resources.

The color used to display the typed-in username.

The font used to display the typed-in username.

A string which identifies this window. The default is `X Window System`.

When X authorization is requested in the configuration file for this display and none is in use, this greeting replaces the standard greeting. The default is `This is an unsecure session`.

The font used to display the greeting.

The color used to display the greeting.

The string displayed to prompt for a username. `xrdb` strips trailing whitespace from resource values, so to add spaces at the end of the prompt (usually a nice thing), add spaces escaped with backslashes. The default is `Login:`.

The string displayed to prompt for a password. The default is `Password:`.

The font used to display both prompts.

The color used to display both prompts.

A message that is displayed when the authentication fails. The default is `Login incorrect`.

The font used to display the failure message.

The color used to display the failure message.

The number of seconds that the failure message is displayed. The default is `30`.

This specifies the translations used for the login widget. Refer to the X Toolkit documentation for a complete discussion on translations. The default translation table is

```
Ctrl<Key>H      delete-previous-character() \n\
Ctrl<Key>D      delete-character() \n\
Ctrl<Key>B      move-backward-character() \n\
Ctrl<Key>F      move-forward-character() \n\
Ctrl<Key>A      move-to-beginning() \n\
Ctrl<Key>E      move-to-end() \n\
```

The actions that are supported by the widget are

```
delete-previous-character
delete-character
move-backward-character
move-forward-character
move-to-beginning
```

```
move-to-end
erase-to-end-of-line
erase-line
finish-field
```

```
abort-session
abort-display
```

```
restart-session
```

```
insert-char
set-session-argument
allow-all-access
```

```
Ctrl<Key>K      erase-to-end-of-line() \n\
Ctrl<Key>U      erase-line() \n\
Ctrl<Key>X      erase-line() \n\
Ctrl<Key>C      restart-session() \n\
Ctrl<Key>nn     abort-session() \n\
<Key>BackSpace delete-previous-character() \n\
<Key>Delete    delete-previous-character() \n\
<Key>Return    finish-field() \n\
<Key>          insert-char() \
```

Erases the character before the cursor.

Erases the character after the cursor.

Moves the cursor backward.

Moves the cursor forward.

(Apologies about the spelling error.) Moves the cursor to the beginning of the editable text.

Moves the cursor to the end of the editable text.

Erases all text after the cursor.

Erases the entire text.

If the cursor is in the name field, proceeds to the password field; if the cursor is in the password field, checks the current name/password pair. If the name/password pair is valid, xdm starts the session. Otherwise, the failure message is displayed and the user is prompted again.

Terminates and restarts the server.

Terminates the server, disabling it. This action is not accessible in the default configuration. There are various reasons to stop xdm on a system console, such as when shutting the system down, when using xdmshell, to start another type of server, or to generally access the console. Sending xdm a SIGHUP will restart the display. See the subsection “Controlling XDM.”

Resets the X server and starts a new session. This can be used when the resources have been changed and you want to test them or when the screen has been overwritten with system messages.

Inserts the character typed.

Specifies a single word argument that is passed to the session at startup. See the subsection “Session Program.”

Disables access control in the server. This can be used when the .xauthority file cannot be created by xdm. Be very careful using this; it might be better to disconnect the machine from the network before doing this.

STARTUP PROGRAM

The xstartup file is typically a shell script. It is run as root and should be very careful about security. This is the place to put commands that add entries to /etc/utmp (the sessreg program may be useful here), mount users’ home directories from file servers, display the message of the day, or abort the session if logins are not allowed.

In addition to any specified by `DisplayManager.exportList`, the following environment variables are passed:

DISPLAY	The associated display name
HOME	The initial working directory of the user
USER	The username
PATH	The value of <code>DisplayManager.DISPLAY.systemPath</code>
SHELL	The value of <code>DisplayManager.DISPLAY.systemShell</code>
XAUTHORITY	May be set to an authority file

No arguments are passed to the script. `xdm` waits until this script exits before starting the user session. If the exit value of this script is non-zero, `xdm` discontinues the session and starts another authentication cycle.

The sample `xstartup` file shown here prevents login while the file `/etc/nologin` exists. Thus, this is not a complete example, but simply a demonstration of the available functionality.

Here is a sample `xstartup` script:

```
#!/bin/sh
#
# Xstartup
#
# This program is run as root after the user is verified
#
if [ -f /etc/nologin ]; then
    xmessage -file /etc/nologin
    exit 1
fi
sessreg -a -l $DISPLAY -x /usr/X11R6/lib/xdm/Xservers $USER
/usr/X11R6/lib/xdm/GiveConsole
exit 0
```

SESSION PROGRAM

The `xsession` program is the command that is run as the user's session. It is run with the permissions of the authorized user.

In addition to any specified by `DisplayManager.exportList`, the following environment variables are passed:

DISPLAY	The associated display name
HOME	The initial working directory of the user
USER	The username
PATH	The value of <code>DisplayManager.DISPLAY.userPath</code>
SHELL	The user's default shell (from <code>getpwnam</code>)
AUTHORITY	May be set to a nonstandard authority file
KRB5CCNAME	May be set to a Kerberos credentials cache file

At most installations, `xsession` should look in `$HOME` for a file `xsession`, which contains commands that each user would like to use as a session. `xsession` should also implement a system default session if no user-specified session exists. See the subsection "Typical Usage."

An argument may be passed to this program from the authentication widget using the `set-session-argument` action. This can be used to select different styles of session. One good use of this feature is to allow the user to escape from the ordinary session when it fails. This allows users to repair their own `.xsession` if it fails, without requiring administrative intervention. The example following demonstrates this feature.

This example recognizes the special failsafe mode, specified in the translations in the `Xresources` file, to provide an escape from the ordinary session. It also requires that the `.xsession` file be executable so you don't have to guess what shell it wants to use.

```
#!/bin/sh
#
# Xsession
#
# This is the program that is run as the client
# for the display manager.
case $# in
  1)
    case $1 in
      failsafe)
        exec xterm -geometry 80x24-0-0
        ;;
      esac
    esac
  startup=$HOME/.xsession
  resources=$HOME/.Xresources
  if [ -f "$startup" ]; then
    exec "$startup"
  else
    if [ -f "$resources" ]; then
      xrb -load "$resources"
    fi
    twm &
    xman -geometry +10-10 &
    exec xterm -geometry 80x24+10+10 -ls
  fi
```

The user's `.xsession` file might look something like the following example. Don't forget that the file must have execute permission.

```
#!/bin/csh
# no -f in the previous line so .cshrc gets run to set $PATH
twm &
xrb -merge "$HOME/.Xresources"
emacs -geometry +0+50 &
xbiff -geometry -430+5 &
xterm -geometry -0+50 -ls
```

RESET PROGRAM

Symmetrical with `Xstartup`, the `Xreset` script is run after the user session has terminated. Run as root, it should contain commands that undo the effects of commands in `Xstartup`, removing entries from `/etc/utmp` or unmounting directories from file servers. The environment variables that were passed to `Xstartup` are also passed to `Xreset`.

A sample `Xreset` script:

```
#!/bin/sh
#
# Xreset
#
# This program is run as root after the session ends
#
sessreg -d -l $DISPLAY -x /usr/X11R6/lib/xdm/Xservers $USER
/usr/X11R6/lib/xdm/TakeConsole
exit 0
```

CONTROLLING THE SERVER

`xdm` controls local servers using POSIX signals. `SIGHUP` is expected to reset the server, closing all client connections and performing other cleanup duties. `SIGTERM` is expected to terminate the server. If these signals do not perform the expected actions, the resources `DisplayManager.DISPLAY.resetSignal` and `DisplayManager.DISPLAY.termSignal` can specify alternate signals.

To control remote terminals not using XDMCP, x_{dm} searches the window hierarchy on the display and uses the protocol request `killClient` in an attempt to clean up the terminal for the next session. This may not actually kill all of the clients, as only those which have created windows will be noticed. XDMCP provides a more sure mechanism; when x_{dm} closes its initial connection, the session is over and the terminal is required to close all other connections.

CONTROLLING x_{dm}

x_{dm} responds to two signals: `SIGHUP` and `SIGTERM`. When sent a `SIGHUP`, x_{dm} rereads the configuration file, the access control file, and the servers file. For the servers file, it notices if entries have been added or removed. If a new entry has been added, x_{dm} starts a session on the associated display. Entries that have been removed are disabled immediately, meaning that any session in progress will be terminated without notice and no new session will be started.

When sent a `SIGTERM`, x_{dm} terminates all sessions in progress and exits. This can be used when shutting down the system.

x_{dm} attempts to mark its various subprocesses for `ps(1)` by editing the command-line argument list in place. Because x_{dm} can't allocate additional space for this task, it is useful to start x_{dm} with a reasonably long command line (using the full pathname should be enough). Each process which is servicing a display is marked `-display`.

OTHER POSSIBILITIES

You can use x_{dm} to run a single session at a time, using the 4.3 `init` options or other suitable daemon by specifying the server on the command line:

```
xdm -server ":0 SUN-3/60CG4 local /usr/X11R6/bin/X :0"
```

Or you might have a file server and a collection of X terminals. The configuration for this is identical to that of the preceding sample, except the `Xservers` file would look like this:

```
extol:0 VISUAL-19 foreign
exalt:0 NCD-19 foreign
explode:0 NCR-TOWERVIEW3000 foreign
```

This directs x_{dm} to manage sessions on all three of these terminals. See the subsection "Controlling x_{dm}" for a description of using signals to enable and disable these terminals in a manner reminiscent of `init(8)`.

LIMITATIONS

One thing that x_{dm} isn't very good at doing is coexisting with other window systems. To use multiple window systems on the same hardware, you'll probably be more interested in `xinit`.

FILES

<XRoot>/lib/X11/x _{dm} /x _{dm} -config	The default configuration file
\$HOME/.Xauthority	User authorization file where x _{dm} stores keys for clients to read
<XRoot>/lib/X11/x _{dm} /chooser	The default chooser
<XRoot>/bin/X11/xrdb	The default resource database loader
<XRoot>/bin/X11/X	The default server
<XRoot>/bin/X11/xterm	The default session program and failsafe client
<XRoot>/lib/X11/x _{dm} /A<display>-<suffix>	The default place for authorization files
/tmp/K5C<display> Kerberos	Credentials cache

Note: <XRoot> refers to the root of the X11 install tree.

See Also

x(1), xinit(1), xauth(1), xsecurity(1), sessreg(1), Xserver(1)

X Display Manager Control Protocol

AUTHOR

Keith Packard (MIT X Consortium)

X Version 11 Release 6

xdpyinfo

`xdpyinfo`—Display information utility for X

SYNOPSIS

```
xdpyinfo [-display displayname] [-queryExtensions] [-ext extension-name]
```

DESCRIPTION

`xdpyinfo` is a utility for displaying information about an X server. It is used to examine the capabilities of a server, the predefined values for various parameters used in communicating between clients and the server, and the different types of screens and visuals that are available.

By default, numeric information (opcode, base event, base error) about protocol extensions is not displayed. This information can be obtained with the `-queryExtensions` option. Use of this option on servers that dynamically load extensions will likely cause all possible extensions to be loaded, which can be slow and can consume significant server resources.

Detailed information about a particular extension is displayed with the `-ext extensionName` option. If `extensionName` is all, information about all extensions supported by both `xdpy-info` and the server is displayed.

ENVIRONMENT

`DISPLAY`

To get the default host, display number, and screen

SEE ALSO

`X(1)`, `xwininfo(1)`, `xprop(1)`, `xrdb(1)`

AUTHOR

Jim Fulton (MIT X Consortium)

X Version 11 Release 6

Xf86_Accel

`Xf86_Accel`—Accelerated X Window System servers for UNIX on x86 platforms with an S3, Mach8, Mach32, Mach64, P9000, AGX, ET4000/W32, or 8514/A accelerator board

SYNOPSIS

```
XF86_S3 [:displaynumber] [ option ] ...
XF86_Mach8 [:displaynumber] [ option ] ...
XF86_Mach32 [:displaynumber] [ option ] ...
XF86_Mach64 [:displaynumber] [ option ] ...
XF86_P9000 [:displaynumber] [ option ] ...
XF86_AGX [:displaynumber] [ option ] ...
XF86_W32 [:displaynumber] [ option ] ...
XF86_8514 [:displaynumber] [ option ] ...
```

DESCRIPTION

XF86_S3 is an 8-bit PseudoColor, 16-bit TrueColor and 24-bit TrueColor server for S3 graphic accelerator boards. Note, 16-bit and 24-bit operation is not supported on all S3 accelerator boards. Refer to README.S3 for details of which boards are supported at which depths.

XF86_Mach8 is an 8-bit PseudoColor server for ATI Mach8 graphic accelerator boards.

XF86_Mach32 is an 8-bit PseudoColor and 16-bit TrueColor server for ATI Mach32 graphic accelerator boards. Note, 16-bit operation is not supported on all Mach32 accelerator boards.

XF86_Mach64 is an 8-bit PseudoColor, 16-bit TrueColor, and 24-bit TrueColor server for ATI Mach64 graphic accelerator boards. Note, 16-bit and 24-bit operation is not supported for all RAMDACs. Refer to README.Mach64 for details of which RAMDACs are supported at which depths.

XF86_P9000 is an 8-bit PseudoColor, 16-bit TrueColor, and 24-bit TrueColor server for Weitek Power 9000 (P9000) graphic accelerator boards.

XF86_AGX is an 8-bit PseudoColor and 16-bit TrueColor server for AGX/XGA graphic accelerator boards.

XF86_W32 is an 8-bit PseudoColor server for ET4000/W32, ET4000/W32i, and ET4000/W32p graphic accelerator boards.

XF86_8514 is an 8-bit PseudoColor server for 8514/A graphic accelerator boards.

These are derived from the x386 server provided with X11R5, and from the x8514 server developed by Kevin Martin (<martin@cs.unc.edu>).

CONFIGURATIONS

The servers support the following chipsets:

XF86_S3	86C911, 86C924, 86C801, 86C805, 86C805i, 86C928, 86C928- P, 86C732 (Trio32), 86C764 (Trio64), 86C864, 86C868, 86C964, 86C968
XF86_Mach8	ATI Mach8, ATI Mach32
XF86_Mach32	ATI Mach32
XF86_Mach64	ATI Mach64
XF86_P9000	Diamond Viper vLB, Diamond Viper PCI, Orchid P9000, and some clones (Weitek P9000)
XF86_AGX	AGX-010, AGX-014, AGX-015, AGX-016, XGA-1, XGA-2
XF86_W32	ET4000/W32, ET4000/W32i, ET3000/W32p
XF86_8514	IBM 8514/A and true clones

For S3, virtual resolutions up to (approximately) 1,152×800 are supported, using (up to) 1MB of display memory (the S3 uses an internal width of 1,280 except for new revisions of some of the chips, hence 1MB can't support 1,152×900). Physical resolutions up to 1,280×1,024 (1,600×1,280 on some cards) are possible using 2MB or more of display memory. (Virtual resolution is dependent solely on the amount of memory installed, with the maximum virtual width being 2,048, and maximum virtual height is 4,096.)

Similar resolutions are supported on the Mach64. Refer to README.Mach64 for configuration details.

Similar resolutions are supported on the Mach32. For the Mach32, the maximum virtual width is 1,536, and the maximum virtual height is 1,280.

For Mach8, the maximum virtual width is 1,024.

For 8514, the maximum resolution is 1,024×768.

For the AGX chips, maximum resolution depends upon the chip revision and amount of available display memory. Refer to README.agx for configuration details.

For the P9000, the virtual and physical resolutions must be the same. With sufficient memory, resolutions up to 1,280×1,024 are supported.

All the servers that support 24-bit visuals do so using a 32-bit per pixel configuration where 8 bits in every 32 bits is unused. This needs to be taken into account when calculating the maximum virtual display size that can be supported at this depth.

OPTIONS

In addition to the normal server options described in the `xserver(1)` manual page, these servers accept some more command-line switches, as described in the `XFree86(1)` man page.

The Mach64, Mach32, S3, P9000, and AGX servers now support more than 8-bit color. The Mach32 and AGX servers support 16-bit TrueColor and the Mach64, S3, and P9000 servers support 16-and 32-bit TrueColor. The 32-bit TrueColor mode only uses 24 bits per pixel for color information (giving you 16 million colors). These modes may be used by specifying the `-bpp` option as specified in the `XFree86(1)` man page.

SETUP

`XFree86` uses a configuration file called `XF86Config` for its initial setup.

See the `XF86Config(4/5)` man page for general details. Here only the parts specific to the `XF86_S3`, `XF86_Mach8`, `XF86_Mach32`, `XF86_Mach64`, `XF86_P9000`, `XF86_AGX`, `XF86_W32`, and `XF86_8514` servers are explained.

Entries for the `Device` section in the `XF86Config` file include the following:

Chipset "name"	Specifies a chipset so the correct driver can be used. Possible chipsets are
	<code>XF86_S3</code>
	<code>S3_generic</code> : (for a standard IO-driven server)
	<code>Mmio_928</code> : (for a memory-mapped IO-driven server on 86C928, 86C732, 86C764, 86C864, 86C868, 86C964, and 86C968 boards)
	<code>XF86_Mach8</code> , <code>Mach8</code> (to force the Mach8 server to run on Mach32 boards)
	<code>XF86_Mach32</code> , <code>Mach32</code>
	<code>XF86_Mach64</code> , <code>Mach64</code>
	<code>XF86_P9000</code>
	<code>Vipervlb</code> (for the Diamond Viper VLB)
	<code>Viperpci</code> (for the Diamond Viper PCI)
	<code>Orchidp9000</code> (for the Orchid P9000 and many generic P9000-based boards)
	<code>XF86_AGX</code>
	<code>Agx-016</code>
	<code>Agx-015</code>
	<code>Agx-014</code>
	<code>Agx-010</code>
	<code>Xga-2</code>
	<code>Xga-1</code>

NOTE

Only the `agx-016`, `agx-015`, `agx-014`, and `xga-2` have been tested. Refer to the `XGA` and `AGX-010` section of `README.agx` before attempting to use the other chipsets.

XF86 W32

```

Et4000w32
Et4000w32i
Et4000w32i_rev_b
Et4000w32i_rev_c
Et4000w32p_rev_a
Et4000w32p_rev_b
Et4000w32p_rev_c
Et4000w32p_rev_d

```

XF86_8514

```
Ibm8514
```

Clocks clock ...

For boards with nonprogrammable clock chips, the clocks can be specified here (see XF86Config(4/5)). The P9000 server now no longer requires a `Clocks` line. It will now work the same way as other servers with a programmable clock chip (that is, use the clocks as specified in the Modes). Note, clocks over 110 MHz are not recommended or supported by the P9000 server. The Mach64 server also does not require a `Clocks` line because the clocks are normally read directly from the video card's BIOS. For the Mach64 server, the clocks given in the XF86Config file are ignored unless the `no_bios_clocks` option is given (see below).

ClockChip "clockchip-type"

For boards with programmable clock chips (except with the P9000 and AGX servers), the name of the clock chip is given. Possible values for the S3 server include "icd2061a", "ics9161a", "dcs2834", "sc11412", "s3gendac", "s3 sdac", "ti3025", "ti3026", "ics2595", "ics5300", "ics5342", "ch8391", "stg1703", and "ibm_rgb5xx".

Ramdac "ramdac-type"

This specifies the type of RAMDAC used on the board. Only the S3, AGX, and W32 servers use this.

Normal—(S3, AGX) Card does not have one of the other RAMDACs mentioned here. This option is only required for the S3 server if the server incorrectly detects one of those other RAMDACs. The AGX server does not yet auto-detect RAMDACs, this is the default if no RAMDAC is specified.

Generic—(W32) This forces the W32 server to treat the RAMDAC as a generic VGA RAMDAC.

Att20c490—(S3, AGX) Card has an AT&T 20C490 or AT&T 20C491 RAMDAC. When the `dac_8_bit` option is specified, these RAMDACs may be operated in 8-bit per RGB mode. It also allows 16bpp operation with 801/805/928 boards. True AT&T 20C490 RAMDACs should be autodetected by the S3 server. This RAMDAC must be specified explicitly in other cases. Note that 8-bit per RGB mode does not appear to work with the Winbond 82C490 RAMDACs (which SuperProbe identifies as AT&T 20C492). 16bpp works fine with the Winbond 82C490. The Diamond SS2410 RAMDAC is reported to be compatible when operating in 15bpp mode (not 16bpp). The Chrontel 8391 appears to be compatible in all modes.

sc15025—(S3, AGX) Card has a Sierra SC15025 or SC15026 RAMDAC. The S3 server has code to autodetect this RAMDAC.

sc11482—(S3) Card has a Sierra SC11482, SC11483, or SC11484 RAMDAC. The S3 server has code to autodetect this RAMDAC.

sc11485—(S3) Card has a Sierra SC11485, SC11487 or SC11489 RAMDAC. The S3 server will detect these RAMDACs as an **sc11482**, so this option must be specified to take advantage of extra features (they support 16bpp, 15bpp, and 8bpp, while the others only support 15bpp and 8bpp).

Bt485—(S3) Card has a BrookTree Bt485 or Bt9485 RAMDAC. This must be specified if the server fails to detect it.

Att20c505—(S3) Card has an AT&T 20C505 RAMDAC. This must be specified either if the server fails to detect the 20C505, or if the card has a Bt485 RAMDAC and there are problems using clocks higher than 67.5MHz.

Att20c498—(S3) Card has an AT&T 20C498 or 21C498 RAMDAC. This must be specified if the server fails to detect it.

Att22c498—(S3) Card has an AT&T 22C498 RAMDAC. This must be specified if the server fails to detect it.

Ibm_rgb514—(S3) Card has an IBM RGB514 RAMDAC. This must be specified if the server fails to detect it.

Ibm_rgb524—(S3) Card has an IBM RGB524 RAMDAC. This must be specified if the server fails to detect it.

Ibm_rgb525—(S3) Card has an IBM RGB525 RAMDAC. This must be specified if the server fails to detect it.

Ibm_rgb528—(S3) Card has an IBM RGB528 RAMDAC. This must be specified if the server fails to detect it.

Stg1700—(S3) Card has an STG1700 RAMDAC. This must be specified if the server fails to detect it.

Stg1703—(S3) Card has an STG1703 RAMDAC. This must be specified if the server fails to detect it.

S3gendac—(S3) Card has an S3 86C708 GENDAC. This RAMDAC does not support 8-bit per RGB mode (don't specify the **dac_8_bit** option). It allows 16bpp operation with 801/805 boards. There is currently no autodetection for this RAMDAC.

S3_sdac—(S3) Card has an S3 86C716 SDAC RAMDAC. This must be specified if the server fails to detect it.

Ics5300—(S3) Card has an ICS5300 RAMDAC. This must be specified if the server fails to detect it (the server will recognize this as an S3 GENDAC which is OK).

Ics5342—(S3) Card has an ICS5342 RAMDAC. This must be specified if the server fails to detect it (the server will recognize this as an S3 SDAC which is OK).

Ti3020—(S3) Card has a TI ViewPoint Ti3020 RAMDAC. This must be specified if the server fails to detect the Ti3020. Note that pixel multiplexing will be used for this RAMDAC if any mode requires a dot clock higher than 70MHz.

	Ti3025—(S3) Card has a TI ViewPoint Ti3025 RAMDAC. This must be specified if the server fails to detect the Ti3025. Ti3026—(S3) Card has a TI ViewPoint Ti3026 RAMDAC. This must be specified if the server fails to detect the Ti3026. Bt481—(AGX) Card has a BrookTree Bt481 RAMDAC. Bt482—(AGX) Card has a BrookTree Bt482 RAMDAC. Herc_dual_dac—(AGX) Card (Hercules Graphite Pro) has both the 84-pin (Bt485 or AT&T20C505) and 44-pin (Bt481 or Bt482) RAMDACs installed. Herc_small_dac—(AGX) Card (Hercules Graphite Pro) has only the 44-pin (Bt481 or Bt482) RAMDAC installed.
IOBase <i>ioaddress</i>	Specifies the base address for extended IO registers. This is only used by the AGX server, and by the P9000 server for the Viper PCI. For details of how to use it, refer to <code>README.agx</code> and <code>README.P9000</code>.
MemBase <i>memaddress</i>	Specifies the hard-wired part of the linear framebuffer base address. This option is only used by the P9000, S3, Mach64, and Mach32 servers (and only when using a linear framebuffer). For the S3 server, the hard-wired part is the high 10 bits of the 32-bit address (that is, <i>memaddress</i> is masked with <code>0xFFC00000</code>). Note: This should not be required for the 864 and 964 chips where the entire framebuffer address is software-selectable. Also, note that in versions prior to 3.1.1, the S3 server used only the top 6 bits of <i>memaddress</i>, and ORed it with <code>0x3C00000</code>. To get the same behavior, OR <code>0x3C00000</code> with the value given previously. For the Mach32 server, the mask is <code>0xF8000000</code> (except for PCI cards, where the <i>membase</i> setting is ignored). This option must be specified with the P9000 server. With local bus Diamond Vipers the value of <i>memaddress</i> can be either <code>0x80000000</code>, <code>0x20000000</code>, or <code>0xA0000000</code>. The default is <code>0x80000000</code>. Any value should work as long as it does not conflict with another device already at that address. For the Viper PCI, refer to <code>README.P9000</code>. For the Orchid P9000, the base address may be <code>0xC0000000</code>, <code>0xD0000000</code>, or <code>0xE0000000</code>, and must correspond the board's jumper setting. Note: The s3 server will normally probe for this address automatically. Setting this option overrides that probe. This is not normally recommended because the failure of the server's probe usually indicates problems in using the linear framebuffer.

NOTE

The Mach64 server requires the memory aperture. For ISA bus video cards, this means that the aperture must be enabled and the aperture address must be set to a value less than 16MB (which means that, on ISA systems only, to use the Mach64 server you must have 12MB of main memory or less). Normally the Mach64 server will use predefined values for this address, but setting this option will override the predefined address.

The Mach32 server should not require the use of this option under normal circumstances.

COPBase baseaddress

This sets the coprocessor base address for the AGX server. Refer to `README.agx` for details.

Instance instance

This sets the XGA instance number for the AGX server. Refer to `README.agx` for details.

S3MC1k memclk

This allows the video card's memory clock value to be specified. This is only used for 805i, 864 and Trio32/64 cards, and the value should not normally be given here for cards with an S3 Gendac or Trio64. This entry doesn't change the card's memory clock, but it is used to calculate the DRAM timing parameters. For further details refer to `README.S3`.

S3MNAdjust M N

This allows some memory timing parameters to be adjusted for DRAM cards. For further details refer to `README.S3`.

S3RefClk refclk

This allows the PLL reference clock to be specified. This may be required for some cards that use the IBM RGB5xx RAMDACs. The value is in MHz. For further details refer to `README.S3`.

Option flags may be specified in either the Device section or the Display subsection of the `XF86Config` file.

Option "optionstring"

Allows the user to select certain options provided by the drivers. Currently the following strings are recognized:

Nomemaccess—(S3) Disable direct access to video memory. This option is ignored for the 864 and 964 chips.

Noaccel—(AGX, P9000) Disable hardware acceleration for the P9000, and disables the font cache with the AGX.

Vram_128—(AGX, P9000) When memory probe fails, use if you have 128Kx8 VRAMs.

Vram_256—(AGX, P9000) When memory probe fails, use if you don't have 128Kx8 VRAMs.

Nolinear—(S3 and Mach32) Disable use of a linear-mapped framebuffer.

Ti3020_curs—(S3) Enables the Ti3020's internal HW cursor. (Default)

No_ti3020_curs—(S3) Disables the Ti3020's internal HW cursor.

Sw_cursor—(S3, Mach32, Mach64, P9000, AGX) Disable the hardware cursor.

Dac_8_bit—(S3, Mach32, Mach64, AGX) Enables 8-bit per RGB. Currently only supported with the Ti3020/5/6, Bt485, AT&T20C505, AT&T20C490/1, Sierra SC15025/6, AT&T20C498 and STG1700/3, IBM RGB5xx (S3 server), Bt481 and Bt482 (AGX server), ATI68875/TLC34075/Bt885 (Mach32 server), ATI68875, TLC34075, ATI68860, ATI68880, STG1702, and STG1703 (Mach64 server) RAMDACs. This is now set by default in the S3 server when one of the preceding RAMDACs other than the AT&T20C490/1 is used.

Dac_6_bit—(S3) Force 6-bit per RGB in cases where 8-bit mode would automatically be enabled.

Sync_on_green—(S3, P9000) Enables generation of sync on the green signal on cards with Bt485, AT&T20C505, Ti3020/5/6 or IBMRGB5xx RAMDACs. Note: Although these RAMDACs support `sync_on_green`, it won't work on many cards because of the way they are designed.

Power_saver—(S3 and Mach64) This option enables the server to use the power-saving features of VESA DPMS-compatible monitors. The suspend level is currently only supported for the Mach64 and for the 732, 764, 864, 868, 964, 968 S3 chips. Refer to the `XF86Config(4/5)` manual page for details of how to set the time-outs for the different levels of operation. This option is experimental.

intel_gx—(Mach32) Sets the hard-wired offset for the linear framebuffer correctly for the Intel GX Pro cards. This option is equivalent to setting the `membase` to `0x78000000`.

spea_mercury—(S3) Enables pixel multiplex support for SPEA Mercury cards (928 + Bt485 RAMDAC). For these cards, pixel multiplexing is required in order to use dot clocks higher than 67.5 MHz and to access more than 1MB of video memory. Pixel multiplexing is currently supported only for noninterlaced modes, and modes with a physical width no smaller than 1,024.

stb_pegasus—(S3) Enables pixel multiplex support for STB Pegasus cards (928 + Bt485 RAMDAC). For these cards, pixel multiplexing is required in order to use dot clocks higher than 67.5 MHz. Pixel multiplexing is currently supported only for noninterlaced modes, and modes with a physical width no smaller than 1,024.

number_nine—(S3) Enables pixel multiplex support for Number Nine GXe level 10, 11, 12 cards (928 + Bt485 RAMDAC). For these cards, pixel multiplexing is required in order to use dot clocks higher than 85MHz. Pixel multiplexing is currently supported only for noninterlaced modes, and modes with a physical width no smaller than 800. This option is also required for some other Number Nine cards (for example, GXE64 and GXE64pro).

diamond—(S3) This option may be required for some Diamond cards (in particular, the 964/968 VRAM cards).

elsa_w1000pro—(S3) Enables support for the ELSA Winner 1000 PRO. This option is not usually required because the board can be autodetected.

elsa_w1000isa—(S3) Enables support for the ELSA Winner 1000 ISA. This option is not usually required because the board can be autodetected.

elsa_w2000pro—(S3) Enables support for the ELSA Winner 2000 PRO. This option is not usually required because the board can be autodetected.

pci_hack—(S3) Enables a workaround for problems seen with some PCI 928 cards on machines with a buggy SMC UART.

s3_964_bt485_vclk—(S3) Enables a workaround for possible problems on cards using the 964 and Bt485.

genoa, stb, hercules, or number_nine—(S3) These options may be used to select different defaults for the blank delay settings for untested cards with IBM RGB5xx RAMDACs to avoid pixel-wrapping problems.

slow_vram—(S3) Adjusts the VRAM timings for cards using slow VRAM. This is required for some Diamond Stealth 64 VRAM and Hercules Terminator 64 cards.

Fast_vram—(S3) Adjusts the VRAM timings for faster VRAM access. There will be display errors and pixel garbage if your card can't support it.

Slow_dram_refresh—(S3) Adjusts the DRAM refresh for cards with slow DRAM to avoid lines of corrupted pixels when switching modes.

No_block_write—(Mach64) Disables the block write mode on certain types of VRAM Mach64 cards. If noise or shadows appear on the screen, this option should remove them.

Block_write—(Mach64) Enables the block write mode on certain types of VRAM Mach64 cards. Normally the Mach64 server will automatically determine if the card can handle block write mode, but this option will override the probe result.

No_bios_clocks—(Mach64) The Mach64 server normally reads the clocks from the bios. This option overrides the bios clocks and forces the server to use the clocks given in the XF86Config file.

There are also numerous tuning options for the AGX server. Refer to README.agx for details.

Note that XFree86 has some internal capabilities to determine what hardware it is running on. Thus, normally the keywords **chipset**, **clocks**, and **videoram** don't have to be specified. But there may be occasions when this autodetection mechanism fails, (for example, too high a load on the machine when you start the server). For cases like this, one should first run the server on an unloaded machine, look at the results of the autodetection (that are printed out during server startup), and then explicitly specify these parameters in the configuration file. It is recommended that all parameters, especially **clock** values, be specified in the XF86Config file.

FILES

```
<XRoot>/bin/XF86 S3
<XRoot>/bin/XF86 Mach8
<XRoot>/bin/XF86 Mach32
<XRoot>/bin/XF86 Mach64
<XRoot>/bin/XF86 P9000
<XRoot>/bin/XF86 AGX
<XRoot>/bin/XF86 W32
<XRoot>/bin/XF86 8514
/etc/XF86Config
<XRoot>/lib/X11/XF86Config
<XRoot>/lib/X11/doc/README.agx
<XRoot>/lib/X11/doc/README.P9000
<XRoot>/lib/X11/doc/README.S3
<XRoot>/lib/X11/doc/README.W32
```

The 8-, 16-, and 24-bit color X server for S3

The 8-bit color X server for Mach8

The 8- and 16-bit color X server for Mach32

The 8-, 16-, and 24-bit color X server for Mach64

The 8-, 16-, and 24-bit color X server for the P9000

The 8- and 16-bit color X server for AGX and XGA

The 8-bit color X server for ET4000/W32

The 8-bit color X server for IBM 8514 and true compatibles

Server configuration file

Server configuration file (secondary location)

Extra documentation for the AGX server

Extra documentation for the P9000 server

Extra documentation for the S3 server

Extra documentation for the W32 server

Note: <XRoot> refers to the root of the X11 install tree.

SEE ALSO

x(1), Xserver(1), XFree86(1), XF86Config(4/5), xvidthune(1), xdm(1), xf86config(1), xinit(1)

AUTHORS

In addition to the authors of XFree86 the following people contributed major work to this server: Kevin Martin (martin@cs.unc.edu), Jon Tombs (tombs@XFree86.org), Rik Faith (faith@cs.unc.edu). (Did the overall work on the base accelerated servers.)

David Dawes (dawes@XFree86.org), Dirk Hohndel (hohndel@XFree86.org), David Wexelblat (dwex@XFree86.org). (Merged their work into XFree86.)

Jon Tombs (tombs@XFree86.org), David Wexelblat (dwex@XFree86.org), David Dawes (dawes@XFree86.org), Amancio Hasty (hasty@netcom.com), Robin Cutshaw (robin@XFree86.org), Norbert Distler (Norbert.Distler@physik.tu-muenchen.de), Leonard N. Zubkoff (lnz@dandelion.com), Harald Koenig (koenig@tat.physik.uni-tuebingen.de), Bernhard Bender (br@elsa.mhs.compuserve.com), Hans Nasten (nasten@everyware.se). (Development and improvement of the s3-specific code.)

Kevin Martin (martin@cs.unc.edu), Rik Faith (faith@cs.unc.edu), Tiago Gons (tiago@comosjn.hobby.nl), Hans Nasten (nasten@everyware.se), Scott Laird (lair@midway.uchicago.edu). (Development and improvement of the Mach8- and 8514/A-specific code.)

Kevin Martin (martin@cs.unc.edu), Rik Faith (faith@cs.unc.edu), Mike Bernson (mike@msun.mlb.org), Mark Weaver (MarkWeaver@brown.edu), Craig Groeschel (craig@metrolink.com). (Development and improvement of the Mach32-specific code.)

Kevin Martin, (martin@cs.unc.edu). (Development of the Mach64-specific code.)

Erik Nygren (nygren@mit.edu), Harry Langenbacher (harry@brain.jpl.nasa.gov), Chris Mason (clmitch@osfmail.isc.rit.edu), Henrik Harmsen (harmsen@eritel.se). (Development and improvement of the P9000-specific code.)

Henry Worth (henry.worth@amail.amdahl.com). (Development of the AGX specific code.)

Glenn Lai (glenn@cs.utexas.edu). (Development of the ET4000/W32-specific code.)

See also the XFree86(1) manual page.

BUGS

Some S3 cards with bt485 RAMDACs are currently restricted to dot-clocks less than 85MHz.

The P9000 server may still have problems with cards other than the Diamond Viper VLB. There may still be problems with VGA mode restoration, but these should almost never occur. Using physical resolutions different from the virtual resolution is not supported and is not possible with the P9000. Use at dot-clocks greater than 110MHz is not recommended and not supported. Diamond claims that 135MHz is the maximum clock speed, but some of its bt485s are not rated that high. If you do not have a 135MHz bt485 on your Viper, contact Diamond tech support and they will send you an RMA number to replace the board. Acceleration is being added in slowly. At the present, only CopyArea, MoveWindow, and DrawLine are implemented. Other accelerated features are being tested and may be available in the next release. There seems to be a problem with olvwm when used with xdm and VT switching. The cursor will be messed up when you return to a VT if the cursor changed while you were in the VT.

CONTACT INFO

XFree86 source is available from the FTP server ftp.XFree86.Org and mirrors. Send e-mail to XFree86@XFree86.Org for details.

XFree86 Version 3.1.2

XF86_Mono

XF86_Mono—1-bit nonaccelerated X Window System servers for UNIX on x86 platforms

SYNOPSIS

XF86 Mono [:displaynumber] [option] ...

DESCRIPTION

XF86_Mono is a 1-bit StaticGrey server for VGA and Super VGA cards and for some other monochrome cards.

CONFIGURATIONS

The XF86_Mono server supports the following popular Super VGA chipsets in monochrome mode:

ATI	18800, 18800-1, 28800-2, 28800-4, 28800-5, 28800-6, 68800-3, 68800-6, 68800AX, 68800LX, 88800CX, 88800GX
Tseng	ET3000, ET4000, ET4000/W32
Western Digital	PVGA1, WD90C00, WD90C10, WD90C11, WD90C30, WD90C31, WD90C33
Genoa	GVGA
Trident	TVGA8800CS, TVGA8900B, TVGA8900C, TVGA8900CL, TVGA9000
NCR	77C22, 77C22E
Compaq	AVGA
Oak	OTI067, OTI077, OTI087
Cirrus	CLGD5420, CLGD5422, CLGD5424, CLGD5426, CLGD5428, CLGD5429, CLGD5430, CLGD5434, CLGD5436, CLGD6205, CLGD6215, CLGD6225, CLGD6235, CL6410, CL6412, CL6420, CL6440

The XF86_Mono server supports the following monochrome cards and resolutions:

Sigma	L-View, LaserView PLUS (in 1bpp mode): 1,664×1,280
Hyundai	HGC-1280: 1,280[1,472]×1,024
Apollo	Monochrome card (with ID 9) from Apollo workstations: 1,280×1,024
Hercules and compatibles cards	720×348

Additionally, it supports generic VGA cards with a maximum virtual resolution of (approximately) 800×650.

On supported SVGA chipsets, XF86_Mono will use up to 1/4 of display memory, which yields a maximum virtual resolution of (approximately) 1,664×1,260 with 1MB of display memory. XF86_Mono does not support the accelerated functions of the supported chipsets.

OPTIONS

In addition to the normal server options described in the xserver(1) manual page, XF86_Mono accepts some more command-line switches, as described in the XFree86(1) man page.

SETUP

XFree86 uses a configuration file called XF86Config for its initial setup.

See the XF86Config(4/5) man page for general details. Here only the XF86_Mono specific parts are explained.

The Driver entry in Screen section of the XF86Config file should be set to vga2 for VGA and SVGA boards, and mono for non-VGA mono boards. If Screen sections are present for both of these, the server will start in a dual-headed configuration.

Entries for the Device section in the XF86Config file include the following:

chipset "name"	Specifies a chipset so the correct driver can be used. Possible chipsets for VGA2: <table><tr><td>ATI</td><td>Vgawonder</td></tr><tr><td>Tseng</td><td>Et3000, et4000, et4000w32, et4000w32i, et4000w32p</td></tr><tr><td>Western Digital</td><td>Pvga1, wd90c00, wd90c10, wd90c30, wd90c31, wd90c33</td></tr><tr><td>Genoa</td><td>Gvga</td></tr><tr><td>Trident</td><td>Tvga8800cs, tvga8900b, tvga8900c, tvga8900cl, tvga9000</td></tr><tr><td>NCR</td><td>Ncr77c22, ncr77c22e Compaq: cpq avga OAK: oti067, oti077, oti087</td></tr><tr><td>Cirrus</td><td>Clgd5420, clgd5422, clgd5424, clgd5426, clgd5428, clgd5429, clgd5430, clgd5434, clgd5436, clgd6205, clgd6215, clgd6225, clgd6235, cl6410, cl6412, cl6420, cl6440</td></tr><tr><td>Generic VGA</td><td>generic</td></tr></table> Possible chipsets for mono: <table><tr><td>Hyundai</td><td>hgc1280</td></tr><tr><td>Sigma</td><td>sigmalview</td></tr><tr><td>Apollo</td><td>apollo9</td></tr><tr><td>Hercules</td><td>hercules</td></tr></table>	ATI	Vgawonder	Tseng	Et3000, et4000, et4000w32, et4000w32i, et4000w32p	Western Digital	Pvga1, wd90c00, wd90c10, wd90c30, wd90c31, wd90c33	Genoa	Gvga	Trident	Tvga8800cs, tvga8900b, tvga8900c, tvga8900cl, tvga9000	NCR	Ncr77c22, ncr77c22e Compaq: cpq avga OAK: oti067, oti077, oti087	Cirrus	Clgd5420, clgd5422, clgd5424, clgd5426, clgd5428, clgd5429, clgd5430, clgd5434, clgd5436, clgd6205, clgd6215, clgd6225, clgd6235, cl6410, cl6412, cl6420, cl6440	Generic VGA	generic	Hyundai	hgc1280	Sigma	sigmalview	Apollo	apollo9	Hercules	hercules
ATI	Vgawonder																								
Tseng	Et3000, et4000, et4000w32, et4000w32i, et4000w32p																								
Western Digital	Pvga1, wd90c00, wd90c10, wd90c30, wd90c31, wd90c33																								
Genoa	Gvga																								
Trident	Tvga8800cs, tvga8900b, tvga8900c, tvga8900cl, tvga9000																								
NCR	Ncr77c22, ncr77c22e Compaq: cpq avga OAK: oti067, oti077, oti087																								
Cirrus	Clgd5420, clgd5422, clgd5424, clgd5426, clgd5428, clgd5429, clgd5430, clgd5434, clgd5436, clgd6205, clgd6215, clgd6225, clgd6235, cl6410, cl6412, cl6420, cl6440																								
Generic VGA	generic																								
Hyundai	hgc1280																								
Sigma	sigmalview																								
Apollo	apollo9																								
Hercules	hercules																								
MemBase memaddress	Specifies the base address of the video memory. This option is only used for the Sigma LaserViewcards. Valid addresses for these cards are 0xA0000, 0xB0000, 0xC0000, 0xD0000, 0xE0000. The default is 0xE0000.																								
Black red green blue	Sets the black color to the RGB values specified. These values must be given as integers in the range 0–63. The default is 0 0 0. This option is only valid for the vga2 screen type.																								
White red green blue	Sets the white color to the RGB values specified. These values must be given as integers in the range 0–63. The default is 63 63 63. This option is only valid for the vga2 screen type.																								
Option "optionstring"	Allows the user to select certain options provided by the drivers. Currently the following strings are recognized: legend—For Sigma Legend ET4000-based boards. This option enables a special clock-selection algorithm used on Legend boards, and MUST be specified for these boards to function correctly. swap_hibit—For Western Digital/PVGA1 chipsets. Some Western Digital-based boards require the high-order clock-select lead to be inverted. It is not possible for the server to determine this information at run-time. If the 9th clock in the list of clocks detected by the server is less than 30Mhz, this option likely needs to be set.																								

hibit_low, hibit_high—For Tseng ET4000 chipsets. With some ET4000 cards, the server has difficulty getting the state of the high-order clocks select bit right when started from a high-resolution text mode. These options allow the correct initial state of that bit to be specified. To find out what the correct initial state is, start the server from an 80×25 text mode. This option is only needed if the clocks reported by the server when started from a high-resolution text mode differ from those reported when it is started from an 80×25 text mode.

8clocks—For the PVGA1 chipset, the default is 4 clocks. Some cards with this chipset may support 8 clocks. Specifying this option will allow the driver to detect and use the extra clocks.

16clocks—For Trident TVGA8900B and 8900C chipsets. Some newer boards using 8900B and 8900C chipsets actually support 16 clocks rather than the standard 8 clocks. Such boards will have a TCK9002 or TCK9004 chip on them. Specifying this option will allow the driver to detect and use the extra 8 clocks.

Power_saver—This option enables the server to use the power saving features of VESA DPMS-compatible monitors. The suspend level is currently not supported. Refer to the XF86Config(4/5) manual page for details of how to set the timeouts for the different levels of operation. This option is experimental.

secondary—For the hgc1280 and apollo9 chipsets. This option allows the use of these cards jumpered to the secondary I/O memory address. These addresses are

```
hgc1280:  I/O 0x3B0-0x3BF, mem 0xB0000-0xBFFFF (prim.)
          I/O 0x390-0x39F, mem 0xC8000-0xCFFFF (sec.)
apollo9:  I/O 0x3B0-0x3BF, mem 0xFA0000-0xFDFFFF (prim.)
          I/O 0x3D0-0x3DF, mem 0xA0000-0xDFFFF (sec.)
```

XFree86 can detect the HGC-1280 on both primary and secondary address; for the apollo card the primary address is used by default.

Note that XFree86 has some internal capabilities to determine what hardware it is running on. Thus, normally the keywords **chipset**, **clocks**, and **videoram** don't have to be specified. But there may be occasions when this autodetection mechanism fails, (for example, too high a load on the machine when you start the server). For cases like this, one should first run **XF86_Mono** on an unloaded machine, look at the results of the autodetection (that are printed out during server startup) and then explicitly specify these parameters in the configuration file. It is recommended that all parameters, especially **clock** values, be specified in the XF86Config file.

FILES

<XRoot>/bin/XF86 Mono

/etc/XF86Config

<XRoot>/lib/X11/XF86Config

The monochrome X server for VGA, SVGA and other monochrome cards

Server configuration file

Server configuration file

Note: <XRoot refers to the root of the X11 install tree.

SEE ALSO

x(1), Xserver(1), XFree86(1), XF86Config(4/5), xf86config(1), xvidtune(1), xdm(1), xinit(1)

BUGS

There are no known bugs at this time, although we welcome reports e-mailed to the address listed below.

CONTACT INFO

XFree86 source is available from the FTP server <ftp.XFree86.org>.

Send e-mail to XFree86@XFree86.org for details.

AUTHORS

Refer to the XFree86(1) manual page.

XFree86 Version 3.1.2

XF86_SVGA

XF86_SVGA—Nonaccelerated SVGA X Window System servers for UNIX on x86 platforms

SYNOPSIS

XF86_SVGA [:displaynumber] [option] ...

DESCRIPTION

XF86_SVGA is an 8-bit PseudoColor, 16-bit TrueColor and 24-bit TrueColor server for Super VGA cards. It is derived from the x386 server provided with x11R5. Note: 16-bit TrueColor is currently only supported for some Cirrus and ARK chips, and 24-bit TrueColor is only supported for some Cirrus chips.

CONFIGURATIONS

The XF86_SVGA server supports the following popular Super VGA chipsets in 256-color mode. Virtual resolutions up to (approximately) 1152×900 are supported, using (up to) 1MB of display memory. The Western Digital WD90C33 and some of the Cirrus chipsets support up to 2MB of display memory and virtual resolutions of 1,280×1,024 and higher. Some of the Cirrus chipsets also support 16bpp and 32bpp (truecolor) modes on certain configurations. Some of the ARK chipsets support 16bpp modes on certain configurations. Generic VGA cards are also supported at 8bpp 320×200 only.

ATI	18800, 18800-1, 28800-2, 28800-4, 28800-5, 28800-6, 68800-3, 68800-6, 68800AX, 68800LX, 88800CX, 88800GX
Tseng	ET3000, ET4000, ET4000/W32
Western Digital	PVGA1, WD90C00, WD90C10, WD90C11, WD90C24A, WD90C30, WD90C31, WD90C33
Genoa	GVGA
Trident	TVGA8800CS, TVGA8900B, TVGA8900C, TVGA8900CL, TVGA9000
NCR	77C22, 77C22E
Cirrus Logic	CLGD5420, CLGD5422, CLGD5424, CLGD5426, CLGD5428, CLGD5429, CLGD5430, CLGD5434, CLGD5436, CLGD6205, CLGD6215, CLGD6225, CLGD6235, CL6410, CL6412, CL6420, CL6440
ARK	ARK1000PV, ARK1000VL, ARK2000PV
RealTek	RTG3106
Compaq	AVGA
Oak	OTI067, OTI077, OTI087

Avance Logic	AL2101, ALI2301, ALI2302, ALI2308, ALI2401
Chips & Technology	65520, 65530, 65540, 65545
MX	MX68000, MX68010
Video7	HT216-32

Accelerated support is included for most of the Cirrus chipsets, and for the Western Digital WD90C31 and WD90C33 chipsets. Accelerated support for the ET4000/W32 is implemented in a separate server (see XF86_W32(1)). Users of boards based on ATI's Mach8, Mach32, and Mach64 chipsets should refer to the XF86_Mach8(1), XF86_Mach32(1) and XF86_Mach64(1) manual pages, respectively.

OPTIONS

In addition to the normal server options described in the xserver(1) manual page, XF86_SVGA accepts some more command-line switches, as described in the XFree86(1) man page.

SETUP

XFree86 uses a configuration file called XF86Config for its initial setup.
See the XF86Config(4/5) man page for general details. Here only the XF86_SVGA specific parts are explained.
This server requires a Screen section in the XF86Config file with the Driver entry set to svga.
Entries for the Device section in the XF86Config file include

chipset "name"	Specifies a chipset so the correct driver can be used. Possible chipsets are
ATI	vgawonder
Tseng	et3000, et4000, et4000w32, et4000w32i, et4000w32p
Western Digital	pvga1, wd90c00, wd90c10, wd90c24, wd90c30, wd90c31, wd90c33
Genoa	gvga
Trident	tvga8800cs, tvga8900b, tvga8900c, tvga8900cl, tvga9000
NCR	ncr77c22, ncr77c22e
Cirrus Logic	clgd5420, clgd5422, clgd5424, clgd5426, clgd5428, clgd5429, clgd5430, clgd5434, clgd5436, clgd6205, clgd6215, clgd6225, clgd6235, cl6410, cl6412, cl6420, cl6440
RealTek	realtek
ARK	ark1000pv, ark1000v1, ark2000pv
Compaq	cpq_avga
Oak	oti067, oti077, oti087
Avance Logic	al2101, ali2301, ali2302, ali2308, ali2401
Chips & Technology	ct65520, ct65530, ct65540, ct65545
MX	mx
Video7	video7
Generic	generic

Option "optionstring"

Allows the user to select certain options provided by the drivers. Currently the following strings are recognized:

legend—For Sigma Legend ET4000-based boards. This option enables a special clock-selection algorithm used on Legend boards, and **MUST** be specified for these boards to function correctly.

swap_hibit—For Western Digital/PVGA1 chipsets. Some Western Digital-based boards require the high-order clock-select lead to be inverted. It is not possible for the server to determine this information at run-time. If the 9th clock in the list of clocks detected by the server is less than 30Mhz, this option likely needs to be set.

hibit_low, **hibit_high**—For Tseng ET4000 chipsets. With some ET4000 cards, the server has difficulty getting the state of the high-order clocks select bit right when started from a high-resolution text mode. These options allow the correct initial state of that bit to be specified. To find out what the correct initial state is, start the server from an 80×25 text mode. This option is only needed if the clocks reported by the server when started from a high-resolution text mode differ from those reported when it is started from an 80×25 text mode.

8clocks—For the PVGA1 chipset, the default is 4 clocks. Some cards with this chipset may support 8 clocks. Specifying this option will allow the driver to detect and use the extra clocks.

16clocks—For Trident TVGA8900B and 8900C chipsets. Some newer boards using 8900B and 8900C chipsets actually support 16 clocks rather than the standard 8 clocks. Such boards will have a TCK9002 or TCK9004 chip on them. Specifying this option will allow the driver to detect and use the extra 8 clocks.

probe_clocks—For Cirrus chipsets. The Cirrus driver has a fixed set of clocks that are normally used. Specifying this option will force the driver to probe for clocks instead of reporting the built-in defaults. This option is for debugging purposes only.

power_saver—This option enables the server to use the power-saving features of VESA DPMS-compatible monitors. The suspend level is currently not supported. Refer to the XF86Config(4/5) manual page for details of how to set the timeouts for the different levels of operation. This option is experimental.

noaccel—For Cirrus and WD chipsets. This option disables the accelerated features for the clgd5426, clgd5428, wd90c24, wd90c31, and wd90c33 chipsets.

fifo_conservative—For Cirrus chipsets. This option sets the CRT_FIFO threshold to a conservative value for dot clocks above 65MHz. This reduces performance, but may help in eliminating problems with “streaks” on the screen during BitBLT operations.

fifo_aggressive—For Cirrus chipsets. This option sets the CRT_FIFO threshold to an aggressive value for dot clocks above 65MHz. This may increase performance.

`speedup "selection"`

`slow_dram`—For Cirrus chipsets. This option sets the DRAM timings for slow DRAM chips.

`fast_dram`—For ET4000 and Cirrus chipsets. This option sets the DRAM timings for fast DRAM chips.

`no_2mb_bankse1`—For Cirrus chipsets. This option is required for Cirrus cards with 2MB of videoram, which is in the form of 512kx8 DRAMs (4 chips) rather than 256kx4 DRAMs (16 chips).

`no_bitblt`—For Cirrus chipsets. This option disables use of hardware BitBLT.

`linear`—Attempt a linear mapping of the framebuffer into high memory. Currently only supported for some Cirrus configurations.

`med_dram`, `favour_bitblt`, `sw_cursor`, `clgd6225_lcd`, `mmio`—More Cirrus-specific options. Refer to `/usr/X11R6/lib/X11/doc/README.cirrus` for a detailed description of Cirrus options.

Sets the selection of SpeedUps to use. The optional selection string can take the following values:

`none`

`all`

If the selection string is omitted, or if the `speedup` option is omitted, the selection defaults to `all`. Some of the SpeedUps can only be used with the ET4000, WD90C31, and WD90C33 chipsets and others require a virtual resolution with a `xdim` of 1024. SpeedUps that won't work with a given configuration are automatically disabled.

`nospeedup`

Disables the SpeedUp code. This is equivalent to `speedup none`.

`Ramdac ramdac-type`

This specifies the type of RAMDAC used on the board. Only the ARK driver currently uses this. RAMDAC types recognized include

`Att20c490`—AT&T 20C490 or compatible 8-bit RAMDAC.

`Att20c498`—AT&T 20C498 or compatible 16-bit RAMDAC.

`Zoomdac`—RAMDAC used by the Hercules Stingray Pro/V and 64/V.

`stg1700`—STG1700 or compatible RAMDAC.

Note that `XFree86` has some internal capabilities to determine what hardware it is running on. Thus, normally the keywords `chipset`, `clocks`, and `videoram` don't have to be specified. But there may be occasions when this autodetection mechanism fails, (for example, too high a load on the machine when you start the server). For cases like this, you should first run `XF86_SVGA` on an unloaded machine, look at the results of the autodetection (that are printed out during server startup), and then explicitly specify these parameters in the configuration file. It is recommended that all parameters, especially `clock` values, be specified in the `XF86Config` file.

FILES

`<XRoot>/bin/XF86_SVGA`

`/etc/XF86Config`

`<XRoot>/lib/X11/XF86Config`

`<XRoot>/lib/X11/doc/README.ark`

`<XRoot>/lib/X11/doc/README.atl`

The SVGA color X server

Server configuration file

Server configuration file

Extra documentation for the ARK driver

Extra documentation for the ATI `vgawon-der` driver

<XRoot>/lib/X11/doc/README.cirrus
<XRoot>/lib/X11/doc/README.trident
<XRoot>/lib/X11/doc/README.tseng
<XRoot>/lib/X11/doc/README.Oak
<XRoot>/lib/X11/doc/README.Video7
<XRoot>/lib/X11/doc/README.WstDig

Extra documentation for the Cirrus driver
Extra documentation for the Trident driver
Extra documentation for the ET4000 and ET3000 drivers
Extra documentation for the Oak driver
Extra documentation for the Video7 driver
Extra documentation for the WD/PVGA driver

Note: <XRoot> refers to the root of the X11 install tree.

SEE ALSO

X(1), Xserver(1), XFree86(1), XF86Config(4/5), xf86config(1), xvidthune(1), xdm(1), xinit(1)

BUGS

Bug reports are welcome, and should be e-mailed to the address listed below.

CONTACT INFO

XFree86 source is available from the FTP server <ftp.XFree86.org>.

Send e-mail to XFree86@XFree86.org for details.

AUTHORS

Refer to the XFree86(1) manual page.

XFree86 Version 3.1.2

XF86_VGA16

XF86_VGA16—4-bit nonaccelerated X Window System server for UNIX on x86 platforms

SYNOPSIS

XF86_VGA16 [:displaynumber] [option] ...

DESCRIPTION

XF86_VGA16 is a 4-bit color server for VGA cards. The default root visual for this server is StaticColor. It also includes support for the non-VGA monochrome cards described in the XF86_Mono(1) manual page. It may be run in a dual-headed configuration.

CONFIGURATIONS

The XF86_VGA16 server supports the following popular SVGA chipsets in 16-color mode.

ATI	18800, 18800-1, 28800-2, 28800-4, 28800-5, 28800-6, 68800-3, 68800-6, 68800AX, 68800LX, 88800CX, 88800GX
Tseng	ET4000
Trident	TVGA8800CS, TVGA8900B, TVGA8900C, TVGA8900CL, TVGA9000
Cirrus	CL6410, CL6412, CL6420, CL6440
Oak	OTI067, OTI077, OTI087

Additionally, it supports generic VGA cards.

XF86_VGA16 does not support the accelerated functions of the supported chipsets.

OPTIONS

In addition to the normal server options described in the `xserver(1)` manual page, `XF86_VGA16` accepts some more command-line switches, as described in the `XFree86(1)` man page.

SETUP

`XFree86` uses a configuration file called `XF86Config` for its initial setup.

See the `XF86Config(4/5)` man page for general details. Here, only the `XF86_VGA16` specific parts are explained.

The `Driver` entry in the `Screen` section of the `XF86Config` file should be set to `vga16`. To run in dual-headed configuration, there should also be a `Screen` section with the `Driver` entry set to `mono`.

Entries for the `Device` section in the `XF86Config` file include the following:

chipset "name"	Specifies a chipset so the correct driver can be used. Possible chipsets are
	ATI vgawonder
	Tseng et4000, et4000w32, et4000w32i, et4000w32p
	Trident tvga8800cs, tvga8900b, tvga8900c, tvga8900cl, tvga9000
	Cirrus c16410, c16412, c16420, c16440
	Oak oti067, oti077, oti087
	Generic VGA generic
Option "optionstring"	Allows the user to select certain options provided by the drivers. Currently, the following strings are recognized:
	legend—For Sigma Legend ET4000-based boards. This option enables a special clock-selection algorithm used on Legend boards, and MUST be specified for these boards to function correctly.
	hibit_low,hibit_high—For Tseng ET4000 chipsets. With some ET4000 cards, the server has difficulty getting the state of the high-order clocks select bit right when started from a high-resolution text mode. These options allow the correct initial state of that bit to be specified. To find out what the correct initial state is, start the server from an 80×25 text mode. This option is only needed if the clocks reported by the server when started from a high-resolution text mode differ from those reported when it is started from an 80×25 text mode.
	power_saver—This option enables the server to use the power saving features of VESA DPMS-compatible monitors. The suspend level is currently not supported.
	Refer to the <code>XF86Config(4/5)</code> manual page for details of how to set the time-outs for the different levels of operation. This option is experimental.

Note that `XFree86` has some internal capabilities to determine what hardware it is running on. Thus normally the keywords `chipset`, `clocks`, and `videoram` don't have to be specified. But there may be occasions when this autodetection mechanism fails, (for example, too high a load on the machine when you start the server). For cases like this, you should first run `XF86_VGA16` on an unloaded machine, look at the results of the autodetection (that are printed out during server startup), and then explicitly specify these parameters in the configuration file. It is recommended that all parameters, especially `Clock` values, be specified in the `XF86Config` file.

FILES

<XRoot>/bin/XF86_VGA16	The 16-color X server
/etc/XF86Config	Server configuration file
<XRoot>/lib/X11/XF86Config	Server configuration file

Note: <XRoot> refers to the root of the X11 install tree.

SEE ALSO

x(1), Xserver(1), XFree86(1), XF86Config(4/5), XF86 Mono(1), xf86config(1), xvidtune(1), xdm(1), xinit(1)

CONTACT INFO

XFree86 source is available from the FTP server <ftp.XFree86.org>.

Send e-mail to XFree86@XFree86.org for details.

AUTHORS

The primary developer of this server is Gertjan Akkerman (akkerman@utiba.twi.tudelft.nl).

See also the XFree86(1) manual page.

XFree86 Version 3.1.2

xf86config

xf86config—Generate an XF86Config file

SYNOPSIS

xf86config

DESCRIPTION

xf86config is an interactive program for generating an XF86Configfile for use with XFree86 X servers.

FILES

<xroot>/lib/X11/Cards	Video cards database

SEE ALSO

XFree86(1), XF86Config(4/5), reconfig(1)

AUTHOR

Harm Hanemaayer

XFree86 Version 3.1.1

xfd

xfd—Display all the characters in an X font

SYNOPSIS

xfd [-options ...] -fn fontname

DESCRIPTION

The `xfd` utility creates a window containing the name of the font being displayed, a row of command buttons, several lines of text for displaying character metrics, and a grid containing one glyph per cell. The characters are shown in increasing order from left to right, top to bottom. The first character displayed at the top left will be character number 0 unless the `-start` option has been supplied, in which case the character with the number given in the `-start` option will be used.

The characters are displayed in a grid of boxes, each large enough to hold any single character in the font. Each character glyph is drawn using the `PolyText16` request (used by the `Xlib` routine `XDrawString16`). If the `-box` option is given, a rectangle will be drawn around each character, showing where an `ImageText16` request (used by the `Xlib` routine `XDrawImageString16`) would cause background color to be displayed.

The origin of each glyph is normally set so that the character is drawn in the upper left corner of the grid cell. However, if a glyph has a negative left bearing or an unusually large ascent, descent, or right bearing (as is the case with cursor font), some characters may not appear in their own grid cells. The `-center` option may be used to force all glyphs to be centered in their respective cells.

All the characters in the font may not fit in the window at once. To see the next page of glyphs, press the Next button at the top of the window. To see the previous page, press Prev. To exit `xfd`, press Quit.

Individual character metrics (index, width, bearings, ascent, and descent) can be displayed at the top of the window by clicking on the desired character.

The font name displayed at the top of the window is the full name of the font, as determined by the server. See `xlsfonts` for ways to generate lists of fonts, as well as more detailed summaries of their metrics and properties.

OPTIONS

`xfd` accepts all of the standard toolkit command-line options along with the following additional options:

<code>-fn font</code>	This option specifies the font to be displayed. This can also be set with the <code>FontGrid</code> <code>font</code> resource. A font must be specified.
<code>-box</code>	This option indicates that a box should be displayed outlining the area that would be filled with background color by an <code>ImageText</code> request. This can also be set with the <code>FontGrid</code> <code>boxChars</code> resource. The default is <code>False</code> .
<code>-center</code>	This option indicates that each glyph should be centered in its grid. This can also be set with the <code>FontGrid</code> <code>centerChars</code> resource. The default is <code>False</code> .
<code>-start number</code>	This option specifies the glyph index of the upper left corner of the grid. This is used to view characters at arbitrary locations in the font. This can also be set with the <code>FontGrid</code> <code>startChar</code> resource. The default is 0.
<code>-bc color</code>	This option specifies the color to be used if <code>ImageText</code> boxes are drawn. This can also be set with the <code>FontGrid</code> <code>boxColor</code> resource.
<code>-rows numRows</code>	This option specifies the number of rows in the grid. This can also be set with the <code>FontGrid</code> <code>cellRows</code> resource.
<code>-columns numcols</code>	This option specifies the number of columns in the grid. This can also be set with the <code>FontGrid</code> <code>cellColumns</code> resource.

WIDGETS

In order to specify resources, it is useful to know the widgets that compose `xfd`. In the notation below, indentation indicates hierarchical structure. The widget class name is given first, followed by the widget instance name. The application class name is `xfd`.

```

Xfd xfd
    Paned pane
        Label fontname
            Box box
                Command quit
                Command prev
                Command next
            Label select
            Label metrics
            Label range
            Label start
Form form
FontGrid grid

```

FONTGRID RESOURCES

The FontGrid widget is an application-specific widget, and a subclass of the Simple widget in the Athena widget set. The effects and instance names of this widget's resources are given in the “Options” subsection. Capitalize the first letter of the resource instance name to get the corresponding class name.

APPLICATION SPECIFIC RESOURCES

The instance names of the application-specific resources are given in the following list. Capitalize the first letter of the resource instance name to get the corresponding class name. These resources are unlikely to be interesting unless you are localizing x/d for a different language.

selectFormat	Specifies a printf-style format string used to display information about the selected character. The default is character <code>0x%02x%02x (%u,%u) (%#o,%#o)</code>. The arguments that will come after the format string are <code>char.byte1</code>, <code>char.byte2</code>, <code>char.byte1</code>, <code>char.byte2</code>, <code>char.byte1</code>, <code>char.byte2</code>. <code>char.byte1</code> is byte 1 of the selected character. <code>char.byte2</code> is byte 2 of the selected character.
metricsFormat	Specifies a printf-style format string used to display character metrics. The default is width <code>%d</code>; left <code>%d</code>, right <code>%d</code>; ascent <code>%d</code>, descent <code>%d</code> (font <code>%d</code>, <code>%d</code>). The arguments that will come after the format string are the character metrics width, lbearing, rbearing, character ascent, character descent, font ascent, and font descent.
rangeFormat	Specifies a printf-style format string used to display the range of characters currently being displayed. The default is range: <code>0x%02x%02x (%u,%u) thru 0x%02x%02x (%u,%u)</code>. The arguments that will come after the format string are the following fields from the <code>XFontStruct</code> that is returned from opening the font: <code>min_byte1</code>, <code>min_char_or_byte2</code>, <code>min_byte1</code>, <code>min_char_or_byte2</code>, <code>max_byte1</code>, <code>max_char_or_byte2</code>, <code>max_byte1</code>, <code>max_char_or_byte2</code>.
startFormat	Specifies a printf-style format string used to display information about the character at the upper left corner of the font grid. The default is upper left: <code>0x%04x (%d,%d)</code>. The arguments that will come after the format string are the new character, the high byte of the new character, and the low byte of the new character.
nocharFormat	Specifies a printf-style format string to display when the selected character does not exist. The default is no such character <code>0x%02x%02x (%u,%u) (%#o,%#o)</code>. The arguments that will come after the format string are the same as for the select-Format resource.

SEE ALSO

`x(1)`, `xlsfonts(1)`, `xrdb(1)`, `xfontsel(1)`, X Logical Font Description Conventions

BUGS

The program should skip over pages full of nonexistent characters.

AUTHOR

Jim Fulton (MIT X Consortium); previous program of the same name by Mark Lillibridge (MIT Project Athena)

X Version 11 Release 6

XFree86

XFree86—X11R6 for UNIX on x86 platforms

DESCRIPTION

XFree86 is a collection of X servers for UNIX-like OSs on Intel x86 platforms. This work is derived from `x386n1.2`, which was contributed to `x11R5` by Snitily Graphics Consulting Service.

CONFIGURATIONS

XFree86 operates under the following operating systems:

- SVR3.2: SCO 3.2.2, 3.2.4, ISC 3.x, 4.x
- SVR4.0: ESIX, Microport, Dell, UHC, Consensys, MST, ISC, AT&T, NCR
- SVR4.2: Consensys, Univel (UNIXWare)
- Solaris (x86) 2.1, 2.4
- FreeBSD 1.1.5, 2.0, 2.0.5, NetBSD 1.0 (i386 port only)
- BSD/386 version 1.1 and BSD/OS 2.0
- Mach (from CMU)
- Linux
- Amoeba version 5.1
- Minix-386vm version 1.6.25.1
- LynxOS AT versions 2.2.1 and 2.3

NETWORK CONNECTIONS

XFree86 supports connections made using the following reliable byte-streams:

Local

XFree86 supports local connections via Streams pipe via various mechanisms, using the following paths (`n` represents the display number):

`/dev/X/server.n` (SVR3 and SVR4)

`/dev/X/Nserver.n` (SVR4)

`/dev/XnS` and `/dev/XnR` (SCO SVR3)

In SVR4.0.4, if the Advanced Compatibility Package is installed, and in SVR4.2, XFree86 supports local connections from clients for SCO XSight/ODT, and (with modifications to the binary) clients for ISC SVR3.

UNIX Domain

XFree86 uses `/tmp/.X11-unix/Xn` as the filename for the socket, where `n` is the display number.

TCPIP

xFree86 listens on port `htons(6000+n)`, where `n` is the display number.

Amoeba RPC

This is the default communication medium used under native Amoeba. Note that under Amoeba, the server should be started with a `hostname:displaynumber` argument.

ENVIRONMENT VARIABLES

For operating systems that support local connections other than UNIX Domain sockets (SVR3 and SVR4), there is a compiled-in list specifying the order in which local connections should be attempted. This list can be overridden by the `XLOCAL` environment variable described next. If the display name indicates a best-choice connection should be made (for example, `:0.0`), each connection mechanism is tried until a connection succeeds or no more mechanisms are available. Note: For these OSs, the UNIX Domain socket connection is treated differently from the other local connection types. To use it the connection must be made to `unix:0.0`.

The `XLOCAL` environment variable should contain a list of one more of the following:

NAMED

PTS

SCO

ISC

which represent SVR4 Named Streams pipe, Old-style USL Streams pipe, SCO XSight Streams pipe, and ISC Streams pipe, respectively. You can select a single mechanism (for example, `XLOCAL=NAMED`), or an ordered list, for example,

```
XLOCAL="NAMED:PTS:SCO"
```

This variable overrides the compiled-in defaults. For SVR4 it is recommended that `NAMED` be the first preference connection. The default setting is

```
PTS:NAMED:ISC:SCO.
```

To globally override the compiled-in defaults, you should define (and export if using `sh` or `ksh`) `XLOCAL` globally. If you use `startx/xinit`, the definition should be at the top of your `.xinitrc` file. If you use `xdm`, the definitions should be early on in the `<XRoot>/lib/X11/xdm/Xsession` script.

OPTIONS

In addition to the normal server options described in the `xserver(1)` manual page, xFree86 accepts the following command-line switches:

`vtXX`

`xx` specifies the Virtual Terminal device number that xFree86 will use. Without this option, xFree86 will pick the first available Virtual Terminal that it can locate. This option applies only to SVR3, SVR4, Linux, and BSD OSs with the `syscons` or `pcvt` driver.

`-probeonly`

Causes the server to exit after the device probing stage. The `XF86Config` file is still used when this option is given, so information that can be auto detected should be commented out.

`-quiet`

Suppresses most informational messages at startup.

`-bpp n`

Set number of bits per pixel. The default is 8. Legal values are 8, 15, 16, 24, 32. Not all servers support all values.

`-weight nnn`

Sets RGB weighting at 16 bpp. The default is 565. This applies only to those servers that support 16 bpp.

`-gamma value`

Sets the gamma correction. `value` must be between 0.1 and 10. The default is 1.0. This value is applied equally to the R, G, and B values. Not all servers support this.

-rgamma value

-ggamma value

-bgamma value

-showconfig

-verbose

-xf86config file

-keeptty

Sets the red gamma correction. *value* must be between 0.1 and 10. The default is 1.0. Not all servers support this.

Sets the green gamma correction. *value* must be between 0.1 and 10. The default is 1.0. Not all servers support this.

Sets the blue gamma correction. *value* must be between 0.1 and 10. The default is 1.0. Not all servers support this.

Prints out a list of screen drivers configured in the server.

Maximizes information printed at startup (more than the default).

Reads the server configuration from file. This option is only available when the server is run as root (that is, with real-UID 0).

Prevents the server from detaching its initial controlling terminal. This option is only useful when debugging the server.

KEYBOARD

Multiple key presses recognized directly by XFree86 are

Ctrl+Alt+Backspace

Immediately kills the server—no questions asked. (Can be disabled by specifying "DontZap" in the Server-Flags section of the XF86Config file.)

Ctrl+Alt+Keypad-Plus

Changes video mode to next one specified in the configuration file, (increasing video resolution order).

Ctrl+Alt+Keypad-Minus

Changes video mode to previous one specified in the configuration file, (decreasing video resolution order).

Ctrl+Alt+F1...F12

For BSD systems using the syscons driver and Linux, these keystroke combinations are used to switch to Virtual Console 1 through 12.

SETUP

XFree86 uses a configuration file called XF86Config for its initial setup. Refer to the XF86Config(4/5) manual page for more information.

FILES

<XRoot>/bin/XF86 SVGA

<XRoot>/bin/XF86 Mono

<XRoot>/bin/XF86 S3

<XRoot>/bin/XF86 Mach8

<XRoot>/bin/XF86 Mach32

<XRoot>/bin/XF86 Mach64

<XRoot>/bin/XF86 P9000

<XRoot>/bin/XF86 AGX

<XRoot>/bin/XF86 W32

<XRoot>/bin/XF86 8514

/etc/XF86Config

<XRoot>/lib/X11/XF86Config.hostname

<XRoot>/lib/X11/XF86Config

<XRoot>/bin/

The color SVGA X server

The monochrome X server for VGA and other mono cards

The accelerated S3 X server

The accelerated Mach8 X server

The accelerated Mach32 X server

The accelerated Mach64 X server

The accelerated P9000 X server

The accelerated AGX X server

The accelerated ET4000/W32 X server

The accelerated 8514/A X server

Server configuration file

Server configuration file

Server configuration file

Client binaries

```
<XRoot>/include/
<XRoot>/lib/
<XRoot>/lib/X11/fonts/
<XRoot>/lib/X11/rgb.txt
<XRoot>/lib/X11/XErrorDB
<XRoot>/lib/X11/app-defaults/
<XRoot>/man/man?/
/etc/Xn.hosts
```

Header files
Libraries
Fonts
Color names to RGB mapping
Client error message database
Client resource specifications
Manual pages
Initial access control list for display n

Note: <XRoot> refers to the root of the X11 install tree.

SEE ALSO

X(1), Xserver(1), xdm(1), xinit(1), XF86Config(4/5), xf86config(1), XF86 SVGA(1), XF86 VGA16(1), XF86 Mono(1), XF86 Accel(1), xvidtune(1)

AUTHORS

For X11R5, XF86 1.2 was provided by the following:

Thomas Roell (roell@informatik.tu-muenchen.de; server and SVR4 stuff), Mark W. Snitily (mark@sgcs.com sgcs; SVR3 support, X Consortium Sponsor), and many more people out there on the Net who helped with ideas and bug fixes.

XF86 was integrated into X11R6 by the following team:

Stuart Anderson (anderson@metrolink.com), Doug Anson (danson@lgc.com), Gertjan Akkerman (akkerman@dutiba.twi.tudelft.nl), Mike Bernson (mike@msun.mlb.org), Robin Cutshaw (robin@XFree86.org), David Dawes (dawes@XFree86.org), Marc Evans (marc@XFree86.org), Pascal Haible (haible@izfm.uni-stuttgart.de), Matthieu Herrb (Matthieu.Herrb@laas.fr), Dirk Hohndel (hohndel@XFree86.org), David Holland (davidh@use.com), Alan Hourihane (alanh@fairlite.demon.co.uk), Jeffrey Hsu (hsu@soda.berkeley.edu), Glenn Lai (glenn@cs.utexas.edu), Ted Lemon (mellon@ncd.com), Rich Murphey (rich@XFree86.org), Hans Nasten (nasten@everyware.se), Mark Snitily (mark@sgcs.com), Randy Terbush (randyt@cse.unl.edu), Jon Tombs (tombs@XFree86.org), Kees Verstoep (versto@cs.vu.nl), Paul Vixie (paul@vix.com), Mark Weaver (Mark.Weaver@brown.edu), David Wexelblat (dwex@XFree86.org), Philip Wheatley (Philip.Wheatley@ColumbiaSC.NCR.COM), Thomas Wolfram (wolf@prz.tu-berlin.de), and Orest Zborowski (orestz@eskimo.com).

The xFree86 enhancement package was provided by

David Dawes, dawes@XFree86.org

Glenn Lai, glenn@cs.utexas.edu

Jim Tsillas, jtsilla@ccs.neu.edu

David Wexelblat, dwex@XFree86.org

Dirk Hohndel, hohndel@XFree86.org

Amancio Hasty Jr., hasty@netcom.com

Rich Murphey, rich@XFree86.org

Release coordination, administration of FTP repository and mailing lists. Source tree management and integration, accelerated server integration, fixing, and coding.

The SpeedUp code for ET4000-based SVGA cards, and ET4000/W32 accelerated server.

Many server speedups from the fX386 series of enhancements. Integration of the fX386 code into the default server, many driver fixes, and driver documentation, assembly of the VGA card/monitor database, development of the generic video mode listing. Accelerated server integration, fixing, and coding.

Linux-shared libraries and release coordination. Accelerated server integration and fixing. Generic administritivia and documentation.

Porting to 386BSD version 0.1 and XS3 development.

Ported to 386BSD version 0.1 based on the original port by Pace Willison. Support for 386BSD, FreeBSD, and NetBSD.

Robert Baron, robert.baron@ernst.mach.cs.cmu.edu
 Orest Zborowski, orestz@eskimo.com
 Doug Anson, danson@lgc.com
 David Holland, davidh@use.com
 David McCullough, davidm@stallion.oz.au
 Michael Rohleder, michael.rohleder@stadt-frankfurt.de
 Kees Verstoep, versto@cs.vu.nl

Marc Evans, Marc@XFree86.org
 Philip Homburg, philip@cs.vu.nl
 Thomas Mueller, tm@sysstrix.de
 Jon Tombs, tombs@XFree86.org
 Harald Koenig, koenig@tat.physik.uni-tuebingen.de
 Bernhard Bender, br@elsa.mhs.compuserve.com
 Kevin Martin, martin@cs.unc.edu

Rik Faith, faith@cs.unc.edu
 Tiago Gons, tiago@comosjn.hobby.nl
 Hans Nasten, nasten@everyware.se

Mike Bernson, mike@msun.mlb.org
 Mark Weaver, Mark.Weaver@brown.edu
 Craig Groeschel, craig@metrolink.com
 Henry Worth, Henry.Worth@amail.amdahl.com
 Erik Nygren, nygren@mit.edu
 Harry Langenbacher, harry@brain.jpl.nasa.gov
 Chris Mason, mason@mail.csh.rit.edu
 Henrik Harmsen, harmsen@eritel.se
 Simon Cooper, scooper@vizlab.rutgers.edu
 Harm Hanemaayer, hhanemaa@cs.ruu.nl
 Mike Tierney, floyd@eng.umd.edu
 Bill Conn, conn@bnr.ca
 Brad Bosch, brad@lachman.com
 Alan Hourihane, alanh@fairlite.demon.co.uk
 Marc La France, Marc.La-France@ualberta.ca
 Steve Goldman, sgoldman@encore.com Oak
 Jorge Delgado, ernar@edit.upm.es
 Bill Conn, conn@bnr.ca
 Paolo Severini, lendl@dist.dist.unige.it
 Ching-Tai Chiu, cchiu@netcom.com
 Manfred Brands, mb@oceanics.nl
 Randy Hendry, randy@sgi.com
 Frank Dikker, dikker@cs.utwente.nl
 Regis Cridlig, cridlig@dm.ens.fr
 Jon Block, block@frc.com

Ported to Mach.
 Ported to Linux.
 Ported to Solaris x86.
 Ported to Solaris x86.
 Ported to SCO SVR3.
 Ported to ISC SVR3.
 Ported to Amoeba based on Leendert van Doorn's original Amoeba port of X11R5.
 Ported to OSF/1.
 Ported to Minix-386vm.
 Ported to LynxOS.
 S3 server and accelerated server coordination.
 S3 server development.
 S3 server development.
 Overall work on the base accelerated servers (ATI and 8514/A), and Mach64 server.
 Overall work on the base accelerated servers (ATI and 8514/A).
 Mach8 and 8514/A server development.
 Mach8, 8514/A, and S3 server development and BSD/386 support.
 Mach32 server development.
 Mach32 server development.
 Mach32 server development.
 AGX server.
 P9000 server.
 P9000 server.
 P9000 server.
 P9000 server.
 Cirrus accelerated code (based on work by Bill Reynolds).
 Cirrus accelerated code and ARK driver.
 WD accelerated code.
 WD accelerated code.
 WD 90C24A support.
 Trident SVGA driver
 ATI vga wonder SVGA driver
 067/077 SVGA driver.
 Oak SVGA driver, and 087 accelerated code.
 WD accelerated code.
 AL2101 SVGA driver.
 Avance Logic ALI SVGA driver.
 Cirrus 64xx SVGA driver.
 Cirrus 6440 support in the cl64xx SVGA driver.
 MX SVGA driver.
 Chips & Technology driver.
 Chips & Technology driver.

Mike Hollick, hollick@graphics.cis.upenn.edu
 Peter Trattler, peter@sbox.tu-graz.ac.at
 Craig Struble, cstruble@acm.vt.edu
 Gertjan Akkerman, akkerman@utiba.twi.tudelft.nl
 Davor Matic, dmatric@Athena.MIT.EDU
 Pascal Haible, haible@izfm.uni-stuttgart.de

Chips & Technology driver
 RealTek SVGA driver.
 Video7 SVGA driver.
 16-color VGA server, and XF86Config parser.
 Hercules driver.
 Banked monochrome VGA support, Hercules support, and
 mono frame buffer support for dumb monochrome devices.

and many more people out there on the Net who helped with beta-testing this enhancement.

XFree86 source is available from the FTP server ftp.XFree86.org, among others. Send e-mail to XFree86@XFree86.org for details.

XFree86 Version 3.1.2

xfs

xfs—X font server

SYNOPSIS

xfs [-config configuration_file] [-port tcp_port]

DESCRIPTION

xfs is the X Window System font server. It supplies fonts to X Window System display servers.

STARTING THE SERVER

The server is usually run by a system administrator, and started via boot files like `/etc/rc.local`. Users may also wish to start private font servers for specific sets of fonts.

OPTIONS

-config configuration_file

Specifies the configuration file the font server will use.

-ls listen-socket

Specifies a file descriptor that is already set up to be used as the listen socket. This option is only intended to be used by the font server itself when automatically spawning another copy of itself to handle additional connections.

-port tcp_port

Specifies the TCP port number on which the server will listen for connections.

SIGNALS

SIGTERM

This causes the font server to exit cleanly.

SIGUSR1

This signal is used to cause the server to reread its configuration file.

SIGUSR2

This signal is used to cause the server to flush any cached data it may have.

SIGHUP

This signal is used to cause the server to reset, closing all active connections and rereading the configuration file.

CONFIGURATION

The configuration language is a list of keyword and value pairs. Each keyword is followed by an = and then the desired value.

Recognized keywords include the following:

catalogue (list of string)

Ordered list of font path element names. Use of the key-word “catalogue” is very misleading at present; the current implementation only supports a single catalogue (*all*), containing all of the specified fonts.

alternate-servers (list of string)

List of alternate servers for this font server.

client-limit (cardinal)

Number of clients this font server will support before refusing service. This is useful for tuning the load on each individual font server.

clone-self (Boolean)

Whether this font server should attempt to clone itself when it reaches the *client-limit*.

default-point-size
(cardinal)

The default pointsize (in decipoints) for fonts that don't specify. The default is 120.

default-resolutions
(list of resolutions)

Resolutions the server supports by default. This information may be used as a hint for prerendering, and substituted for scaled fonts that do not specify a resolution. A resolution is a comma-separated pair of x and y resolutions in pixels per inch. Multiple resolutions are separated by commas.

error-file (string)

Filename of the error file. All warnings and errors will be logged here.

port (cardinal)

TCP port on which the server will listen for connections.

use-syslog (Boolean)

Whether *syslog(3)* (on supported systems) is to be used for errors.

deferglyphs (string)

Set the mode for delayed fetching and caching of glyphs. Value is *none*, meaning deferred glyphs is disabled, *all*, meaning it is enabled for all fonts, and *16*, meaning it is enabled only for 16-bits fonts.

EXAMPLE

```
#
# sample font server configuration file
#
# allow a max of 10 clients to connect to this font server client-limit = 10
# when a font server reaches its limit, start up a new one clone-self = on
# alternate font servers for clients to use alternate-servers = hansen:7101,hansen:7102
# where to look for fonts
# the first is a set of Speedo outlines, the second is a set of
# misc bitmaps and the last is a set of 100dpi bitmaps
#
catalogue = /usr/X11R6/lib/X11/fonts/speedo,
/usr/X11R6/lib/X11/fonts/misc,
/usr/X11R6/lib/X11/fonts/100dpi/
# in 12 points, decipoints
default-point-size = 120
# 100 x 100 and 75 x 75
default-resolutions = 100,100,75,75
use-syslog = off
```

FONT SERVER NAMES

One of the following forms can be used to name a font server that accepts TCP connections:

```
tcp/hostname:port tcp/hostname:port/cataloguelist
```

The `hostname` specifies the name (or decimal numeric address) of the machine on which the font server is running. The `port` is the decimal TCP port on which the font server is listening for connections. The `cataloguelist` specifies a list of catalogue names, with `+` as a separator.

Examples: `tcp/fs.x.org:7100`, `tcp/18.30.0.212:7101/all`.

One of the following forms can be used to name a font server that accepts DECnet connections:

```
decnet/nodename::font$objname decnet/nodename::font$objname/cataloguelist
```

The `nodename` specifies the name (or decimal numeric address) of the machine on which the font server is running. The `objname` is a normal, case-insensitive DECnet object name. The `cataloguelist` specifies a list of catalogue names, with `+` as a separator.

Examples: `DECnet/SRVNOD::FONT$DEFAULT`, `decnet/44.70::font$special/symbols`.

SEE ALSO

`x(1)`, font server implementation overview

BUGS

Multiple catalogues should be supported.

AUTHORS

Dave Lemke (Network Computing Devices, Inc.), Keith Packard (Massachusetts Institute of Technology)

X Version 11 Release 6

xhost

`xhost`—Server access control program for X

SYNOPSIS

```
xhost [[+-]name ...]
```

DESCRIPTION

The `xhost` program is used to add and delete hostnames or usernames to the list allowed to make connections to the X server. In the case of hosts, this provides a rudimentary form of privacy control and security. It is only sufficient for a workstation (single user) environment, although it does limit the worst abuses. Environments that require more sophisticated measures should implement the user-based mechanism or use the hooks in the protocol for passing other authentication data to the server.

OPTIONS

`xhost` accepts the following command-line options. For security, the options that effect access control may only be run from the “controlling host.” For workstations, this is the same machine as the server. For X terminals, it is the login host.

`-help`

Prints a usage message.

`[+]name`

The given name (the plus sign is optional) is added to the list allowed to connect to the X server. The name can be a hostname or a username.

`-name`

The given name is removed from the list allowed to connect to the server. The name can be a hostname or a username. Existing connections are not broken, but new connection attempts will be denied. Note that the current machine is allowed to be removed; however, further connections (including attempts to add it back) will not be permitted. Resetting the server (thereby breaking all connections) is the only way to allow local connections again.

`+`

Access is granted to everyone, even if they aren't on the list (in other words, access control is turned off).

`-`

Access is restricted to only those on the list (that is, access control is turned on).

`nothing`

If no command-line arguments are given, a message indicating whether or not access control is currently enabled is printed, followed by the list of those allowed to connect. This is the only option that may be used from machines other than the controlling host.

NAMES

A complete name has the syntax `family:name` where the families are as follows:

<code>inet</code>	Internet host
<code>dne</code>	DECnet host
<code>nis</code>	Secure RPC network name
<code>krb</code>	Kerberos V5 principal
<code>local</code>	Contains only one name, the empty string

The family is case insensitive. The format of the name varies with the family.

When Secure RPC is being used, the network-independent netname (for example, `nis:unix.uid@domainname`) can be specified, or a local user can be specified with just the username and a trailing at sign (`@`) (for example, `nis:pat@`).

For backward compatibility with pre-R6 `xhost`, names that contain an at sign are assumed to be in the `nis` family. Otherwise, the `inet` family is assumed.

DIAGNOSTICS

For each name added to the access control list, a line of the form `name being added to access control list` is printed. For each name removed from the access control list, a line of the form `name being removed from access control list` is printed.

FILES

`/etc/X*.hosts`

SEE ALSO

`x(1)`, `Xsecurity(1)`, `Xserver(1)`, `xdm(1)`

ENVIRONMENT

`DISPLAY`

To get the default host and display to use

BUGS

You can't specify a display on the command line because `-display` is a valid command-line argument (indicating that you want to remove the machine named `display` from the access list).

The X server stores network addresses, not hostnames. This is not really a bug. If somehow you change a host's network address while the server is still running, `xhost` must be used to add the new address and/or remove the old address.

AUTHORS

Bob Scheifler (MIT Laboratory for Computer Science) and Jim Gettys (MIT Project Athena/DEC)

X Version 11 Release 6

xieperf

xieperf—XIE server extension test and demo program

SYNTAX

`xieperf [-option ...]`

DESCRIPTION

The `xieperf` program is based upon `R5 x11perf(1)`, and while not entirely comprehensive in its coverage of the XIE protocol (see the “Bugs” subsection), it is intended to be useful in the evaluation of XIE implementations in the areas of protocol adherence and performance. The `xieperf` program includes tests that execute each of the protocol requests and photoflo elements specified by revision 5.0 of the XIE protocol. In addition, `xieperf` provides a set of tests that can be used to validate the detection and transmission of XIE protocol request errors, such as `FloMatch`, `FloValue`, and so forth. Finally, `xieperf` provides a customizable demonstration program for XIE.

A test is made up of three components executed in sequence: an initialization function, a test function, and an end function. The initialization function is responsible for allocating and populating test resources, such as photomaps and LUTs, and for creating a stored photoflo that will be executed by the test function. The test function, in most cases, simply executes the stored photoflo for a specified number of repetitions. The end function, which is called following the test function, is used primarily to destroy any noncacheable server resources used by the test, and to free any memory that was dynamically allocated by the client. Some tests, such as `-modify1`, `-await`, `-abort`, and `-redefine`, perform additional steps within the test function inner loop, as required by the element being tested, or in an attempt to make the test more visually appealing.

Evaluating the performance of individual XIE elements is not as simple as measuring Core X drawing times. The XIE protocol requires elements to be embedded within photoflos in order to be exercised, and the minimum possible photoflo size is two. This implies that it is impossible to measure performance of a single element in isolation—the time it takes to run the flo depends on what other elements exist in the flo. Extrapolating performance of a single element (or technique) in a flo must be done carefully, on a case-by-case basis, because in general, measured element performance depends on input image size, data type, and other factors, all of which can be influenced by upstream flo elements. Note further that the number and type of elements in a flo can be influenced by the visuals available on the display, so even flo-flo comparisons on machines with different visuals must be done with caution.

Many test labels contain an abbreviated pipeline description. For instance, `IP/IL/P/ED` indicates `ImportPhotomap`, `ImportLUT`, `Point`, and `ExportDrawable`. Pipelines ending in `ED` (`ExportDrawable`) often include hidden elements such as `BandExtract`, `ConvertToIndex`, `Dither`, or `Point` to match the flo output to the screen visual. Pipelines ending in `EP` (`ExportPhotomap`) will result in a blank window.

`xieperf` is compatible with `x11perfcomp(1)`, which is used to compare the outputs of different `xieperf` and `x11perf` runs in a nice, tabular format. In `xieperf` you will need to use the `-labels` option (see the “Options” subsection), and provide the resulting labels file to `x11perfcomp(1)` to obtain correct output. See the `x11perfcomp(1)` man pages for more details on this.

OPTIONS

`xieperf` accepts the following options:

`-display host:dpy`
`-images <path>`

`-timeout<s>`

`-sync`
`-script <file>`

`-repeat <n>`

`-time <s>`

`-depth <depth>`

`-GrayScale`
`-PseudoColor`
`-StaticGray`
`-StaticColor`
`-TrueColor`
`-DirectColor`
`-WM_SAFE`

Specifies which display to use.

Normally, `xieperf` references image files located in the directory `images`, which `xieperf` assumes is located in your current directory. If the `images` directory is not in your current directory, or the file has been renamed, use this option to specify its location.

Some tests require the reception of an event such as `FlOtnotify` to continue, and may cause `xieperf` to hang should these events not be received. This option allows the user to specify a time-out value which, if exceeded, will cause `xieperf` to give up waiting for an event, and continue on with the next test in sequence. Should an event time-out, a warning message will be printed to `stderr`. The default time-out value is 60 seconds.

Runs the tests in synchronous mode.

Using this option gives the user the ability to run a subset of the available tests and control the number of times the tests are executed on an individual basis. This is thought to be especially useful for those running `xieperf` for demonstration purposes. Using this option causes `xieperf` to read commands specified in a script file, or from `stdin` if `<file>` is `.`. Tests are specified by newline-terminated input lines of the form `command [-reps n] [-repeat m]`. Characters following and including `#` are treated as comments. See the `-mkscript` option.

Repeats each test `n` times (by default each test is run two times). This option may be used in script files also, in which case the script file `-repeat` overrides the command-line option. Specifies how long in seconds each test should be run (default 5 seconds).

Use a visual with `<depth>` planes per pixel (default is the default visual).

Use a `GrayScale` visual (default is the default visual).

Use a `PseudoColor` visual (default is the default visual).

Use a `StaticGray` visual (default is the default visual).

Use a `StaticColor` visual (default is the default visual).

Use a `TrueColor` visual (default is the default visual).

Use a `DirectColor` visual (default is the default visual).

If `xieperf` must be run in a window manager environment, use this flag to make `xieperf` aware of this. If specified, `xieperf` will create a window, identical to the size of the root window, and all further windows created by `xieperf` will be transient pop-up children of this window. If this flag is omitted, `xieperf` will set the `override_redirect` attribute of all windows to `True` and will also do evil things such as calling `XInstallColormap`. Using this option will cause the window manager to (hopefully) obey window geometry hints specified by `xieperf`.

<code>-showtechs</code>	Display a comprehensive list of techniques, by category, indicating which of the techniques are supported by the xIE server.
<code>-showlabels</code>	Print test label to screen prior to calling any of the test code. This allows the user to know which test is executing in case the test hangs for some reason.
<code>-showevents</code>	Be verbose when running event and error tests. Also, can be used to catch and display information on any signals received during execution of xieperf. Note that this flag is best used in a debugging situation, or to validate that the error events received by xieperf are valid the first time the tests are executed on a new platform.
<code>-events</code>	Run tests that test for event generation.
<code>-errors</code>	Run tests that test for error event generation.
<code>-loCal</code>	Skip test calibration. This may be used when running xieperf in situations where execution timing is not important. Execution times will not be reported by xieperf when this option is enabled. The inner loop repeat count, additionally, is set to a value of 5 (but can be overridden by the <code>-reps</code> option).
<code>-all</code>	Runs all tests. This may take a while, depending on the speed of your machine, and its floating-point capabilities. This option is ignored if a script file is used.
<code>-tests</code>	Generate a list of the available tests for the xieperf program. In x11perf, this list is normally displayed in the usage statement. It was yanked from the usage of xieperf because it was too lengthy.
<code>-mkscript</code>	Generate a script file suitable for use with the script option. If <code>-repeat</code> or <code>-reps</code> are also specified, they will be automatically placed at the end of each command in the script. The script is generated to <code>stderr</code> . See the <code>-script</code> command, above.
<code>-cache <n></code>	Most test flos utilize a photomap resource for a source. A photomap cache of up to <code>n</code> entries is controlled by xieperf to avoid having to constantly reload these images during test initialization. The default cache size is 4. If a value less than the default is specified, the cache size will be set to the default.
<code>-labels</code>	Generates just the descriptive labels for each test specified. Use <code>-all</code> or <code>-range</code> to specify which tests are included. See <code>x11perfcomp(1)</code> for more details.
<code>-DIS</code>	Pretend we are running xieperf while connected to a DIS-only capable implementation of xIE. This will cause xieperf to execute those tests that only use protocol requests found in the DIS subset of xIE, and bypass those which are not DIS-compatible. If xieperf detects a DIS server, it will do this automatically, and this option is ignored. Use <code>-all</code> or <code>-range</code> to specify the initial range of tests.
<code>-range <test1>[,<test2>]</code>	Runs all the tests starting from the specified name <code>test1</code> until the name <code>test2</code> , including both the specified tests. Some tests, like the event and error tests, also require the <code>-errors</code> or <code>-events</code> options to specified. This option is ignored if a script is used.

`-reps <n>`

`-ImportObscuredEvent`
through `-ExportAvailable`

`-BadValue` through
`-FloValueError`

`-ColorList`
`-LUT`
`-Photomap`
`-ROI`
`-Photospace`
`-Photoflo`
`-QueryPhotomap`
`-QueryColorList`
`-QueryTechniquesDefault`
through `-QueryTechniques`
`WhiteAdjust`
`-QueryPhotoflo`
`-PurgeColorList`
`-Abort`

`-Await`

`-importclientlut1`
`-importclientphoto1` through
`-importclientphoto9`

`-importclientroi1`
`-importclientroi2`
`-encodephoto1` through
`-encodephoto14`

Fix the inner loop repetitions to `n`. This indicates how many times the photoflo will be executed each time the test is run. This option is overridden on a per test basis if specified in a script. Typically, `xieperf` determines the ideal number of reps during each test's calibration period.

Test generation of events. Requires `-events` flag.

Test generation of errors. Requires `-errors` flag.

Create and destroy `ColorList` resource test.

Create and destroy `LUT` resource test.

Create and destroy `Photomap` resource test.

Create and destroy `ROI` resource test.

Create and destroy `Photospace` test.

Create and destroy `Photoflo` test.

Query `Photomap` resource test.

Query `ColorList` resource test.

Query techniques as specified by test name.

Query `Photoflo` test.

Purge `ColorList` test.

This test creates a photoflo that is started and blocks for data provided by `PutClientData()`. Instead of sending the data, the test uses `XieAbort()` to stop the photoflo, and then waits for the `PhotofloDone` event to be sent by the server. If the test times out waiting for the event, an error message is sent to `stderr`.

This test creates a flo of the form `ImportClientLUT -> ExportLUT`, and starts the flo executing. `xieperf` then forks, and the child process streams the `LUT` data to the flo using `PutClientData`, while the parent blocks in `XieAwait`. If the flo successfully finishes, `XieAwait` will return and the flo state, after query, will indicate that it has completed. If `XieAwait` does not complete naturally, or after return from `XieAwait` the flo is still active, an error is reported to `stderr`. Note, on a really slow machine, it is possible that `XieAwait` will return before the flo has a chance to finish. In this case, use the `-timeout` option to increase the time-out for this test.

`ImportClientLUT -> ExportLUT` test.

Flos of the form `ImportClient-Photo -> ExportPhotomap` using various decode techniques, for example, `G32D`, `TIFF2`, `UncompressedTriple`.

`ImportClientROI` with 10 rectangles.

`ImportClientROI` with 100 rectangles.

Flos of the form `ImportPhotomap - ExportPhotomap` using various encode techniques, for example `G32D`, `TIFF2`, `UncompressedTriple`. Original encoding is shown in left window; image after encoding is shown in right window.

```
-encodeclientphoto1 through
-encodeclientphoto11
```

```
-exportclientlut1
-exportclientroi1
```

```
-exportclientroi2
-exportclienthistogram1
through
-exportclienthistogram4
-exportclienthistogramroi1
through
-exportclienthistogramroi4
-exportclienthistogramcplane1
through
-exportclienthistogramcplane4
-importlut1
-importphoto1
```

```
-importphoto2
-importroi1
```

```
-importroi2
```

```
-importdrawable1
```

```
-importdrawable2
```

```
-importdrawable3
```

```
-importdrawable4
```

```
-importdrawable5
```

```
-importdrawable6
```

```
-importdrawable7
```

```
-importdrawable8
```

```
-constrain1
```

Two flos, one of the form `ImportPhotomap -> ExportClientPhoto`, and the other of the form `ImportClientPhoto -> ExportPhotomap`, where `ExportClientPhoto` in the first flo uses various encode techniques, for example `G32D`, `TIFF2`, `UncompressedTriple`. The image before encoding is displayed in the left window, while the right window shows the image that was encoded in the first flo and read back in the second flo.

`ExportClientLUT` test. LUT is displayed in a histogram window.

`ExportClientROI` test, 10 ROIs. The ROIs that are sent to the server are represented by the filled rectangles. The ROIs that are received back from the server by the client are drawn as white-bordered, nonfilled rectangles. The resulting output illustrates how the server combined the rectangles sent to it. Same as `exportclientroi1`, except using 100 rectangles.

`ExportClientHistogram` tests using various images. The histogram is displayed in a window that overlaps the image.

Same as the `ExportClientHistogram` test, but using a ROI to identify the area of interest.

Same as the `ExportClientHistogram` test, but using a control plane to identify the area of interest.

Test `ImportLUT` element; LUT size is 256.

`ImportPhotomap -> ExportPhotomap`, with source and destination equal.

`ImportPhotomap -> ExportDrawable`, window destination.

`ImportROI -> ExportROI`, 10 rectangles, source and destination ROIs equal.

`ImportROI -> ExportROI`, 100 rectangles, source and destination ROIs equal.

`ImportDrawable -> ExportDrawable`, source is pixmap, destination is window.

`ImportDrawable -> ExportDrawable`, source and destination are both window.

`ImportDrawable -> ExportDrawable`, destination window obscured by source window.

`ImportDrawable -> ExportDrawable`, source window obscured by destination window.

`ImportDrawablePlane -> ExportDrawablePlane`, pixmap, source = destination.

`ImportDrawablePlane -> ExportDrawablePlane`, window, source = destination.

`ImportDrawablePlane -> ExportDrawablePlane`, window, source obscures destination.

`ImportDrawablePlane -> ExportDrawablePlane`, window, destination obscures source.

`Constrain HardClip` technique test, drawable destination.

```

-constrain2
-constrainphoto1
-constrainphoto2
-convolve1
-convolve2
-convolve3
-convolve4
-convolveroi1
-convolveroi2
-convolvecplane1
-convolvecplane2
-math1 through -mathcplane7

-arithmeticdyadic1 through
-arithmeticdyadic5
-arithmeticmonadic1 through
-arithmeticmonadic9
-arithmeticdyadicroi1
through
arithmeticdyadicroi5
-arithmeticmonadicroi1
through
-arithmeticmonadicroi9
-arithmeticdyadiccplane1
through
-arithmeticdyadiccplane5
-arithmeticmonadiccplane1
through
-arithmeticmonadiccplane9
-arithmeticfloatdyadic1
though
-arithmeticfloatdyadic5
-arithmeticfloatmonadic1
though
-arithmeticfloatmonadic9
-arithmeticcroifloatdyadic1
to
-arithmeticcroifloatdyadic5
-arithmeticcroifloatmonadic1
to
-arithmeticcroifloatmonadic9
-band1

```

Constrain ClipScale technique test, drawable destination.

Constrain HardClip technique test, photomap destination.

Constrain ClipScale technique test, photomap destination.

Boxcar 3×3 convolution test. Smoothing or lowpass filter.

Boxcar 5×5 convolution test. Smoothing or lowpass filter.

LaPlacian 3×3 convolution test. Edge or highpass filter.

LaPlacian 5×5 convolution test. Edge or highpass filter.

LaPlacian 3×3 convolution test, with ROI.

LaPlacian 5×5 convolution test, with ROI.

LaPlacian 3×3 convolution test, with control plane.

LaPlacian 5×5 convolution test, with control plane.

Various tests that exercise the math element, some tests using ROIs and control planes.

Arithmetic element tests, using photomaps as the operands.

Arithmetic element tests, photomap and constant operands.

Arithmetic element tests, using - photomaps as the operands, with ROIs.

Arithmetic element tests, photomap and constant operands, with ROIs.

Arithmetic element tests, using photomaps as the operands, with control planes.

Arithmetic element tests, photomap and constant operands, with control planes.

Arithmetic element tests, using photomaps as the operands, unconstrained.

Arithmetic element tests, photomap and constant operands, unconstrained.

Arithmetic element tests, photomaps as the operands, ROIs, unconstrained.

Arithmetic element tests, photomap and constant operands, ROIs, unconstrained.

BandSelect element test. Image input is triple band. If visual of xieperf window is a color visual, then three Band-Select elements are used to extract the individual bands; they are combined once again using BandCombine, and displayed using ConvertToIndex. If the visual is not color, for example, GrayScale or StaticGray, then the flo simply uses one BandSelect element to extract a single band for display.

-band2	BandCombine test. Input bands are made of three separate single band photomaps. These are combined using a BandCombine element, which is followed by a BandExtract and ExportDrawable. CCIR 601-1 coefficients.
-band3	BandExtract test. Input is a triple band photomap. CCIR 601-1 coefficients. Destination window colormap is gray ramp.
-band4	BandExtract test. Input is a triple band photomap. CCIR 601-1 coefficients. Destination window colormap is RGB BEST MAP standard colormap.
-band5	BandExtract test. Input is a triple band photomap. CCIR 601-1 coefficients. Destination window colormap is RGB_DEFAULT_MAP standard colormap.
-comparedyadic1 through -comparedyadic6	Test various compare operators with dyadic photomap operands.
-comparemonadic1 through -comparemonadic6	Test various compare operators with photomap, constant operands.
-compareroidyadic1 through -compareroidyadic6	Test various compare operators with dyadic photomap operands, using ROIs.
-compareroimonadic1 through compare compareroimonadic6	Test various operators with photomap, constant operands, using ROIs.
-comparecplanedyadic1 through -comparecplanedyadic6	Test various compare operators with dyadic photomap operands, control planes.
-comparecplanemonadic1 through -comparecplanemonadic6	Test various compare operators with photomap, constant operands, control planes.
-matchhistogram1 through -matchhistogram18	MatchHistogram element tests, using various images and histogram matching techniques.
-matchhistogramroi1 through -matchhistogramroi6	A selection of MatchHistogram element tests, with ROIs.
-matchhistogramcplane1 through -matchhistogramcplane6	A selection of MatchHistogram element tests, with control planes.
-unconstrain1	ImportPhotomap, Unconstrain, Constrain(ClipScale), ExportDrawable test.
-pasteup1 through -pasteup2	PasteUp element tests.
-geometry1 through -geometry14	Geometry element tests, including rotations, scales, and mirroring. NearestNeighbor technique.
-geometry15 through -geometry28	Geometry element tests, including rotations, scales, and mirroring. AntiAlias technique.
-geometry29 through -geometry42	Geometry element tests, including rotations, scales, and mirroring. BilinearInterpolation technique.
-geomg31dscale1 through -geometryfaxradio1	Tests to exercise the various FAX decoders and the Geometry element.
-dither1	Dither test, ErrorDiffusion dither technique, ExportDrawable.
-dither2	Dither test, ErrorDiffusion dither technique, ExportDrawablePlane.

<code>-dither3</code>	Dither test, Ordered(4) dither technique, ExportDrawable.
<code>-dither4</code>	Dither test, Ordered(4) dither technique, ExportDrawablePlane.
<code>-dither5</code>	Dither test, Ordered(8) dither technique, ExportDrawable.
<code>-dither6</code>	Dither test, Ordered(8) dither technique, ExportDrawablePlane.
<code>-dither7</code>	Dither test, Default dither technique, ExportDrawable.
<code>-dither8</code>	Dither test, Default dither technique, ExportDrawablePlane.
<code>-logicalmonadic1 through -logicalmonadic16</code>	Logical element, photomap and a constant of 0 as operands, various operators.
<code>-logicaldyadic1 through -logicaldyadic16</code>	Logical element tests, dyadic photomaps as operands, various operators.
<code>-logicalmonadicroi1 through -logicalmonadicroi16</code>	Logical element, photomap and constant of 0 operands, various operators, ROIs.
<code>-logicaldyadicroi1 through -logicaldyadicroi16</code>	Logical element, dyadic photomaps as operands, various operators, ROIs.
<code>-logicalmonadicplane1 through -logicalmonadicplane16</code>	Logical element, photomap and constant of 0 operands, various operators, Control Planes.
<code>-logicaldyadicplane1 through -logicaldyadicplane16</code>	Logical element, dyadic photomaps as operands, various operators, control planes.
<code>-blend1</code>	Blend element test. Monadic source, 0.1 source constant. Alpha constant of 0.5.
<code>-blend2</code>	Blend element test. Dyadic sources. Alpha constant of 0.5.
<code>-blendroi1</code>	Blend test. Monadic source, 0.1 source constant. Alpha constant of 0.5. ROIs.
<code>-blendroi2</code>	Blend element test. Dyadic sources. Alpha constant of 0.5. Uses ROIs.
<code>-blendplane1</code>	Blend test. Monadic source, 0.1 source constant. Alpha constant of 0.5. control plane.
<code>-blendplane2</code>	Blend element test. Dyadic sources. Alpha constant of 0.5. control plane.
<code>-blendalpha1</code>	Blend test. Monadic source, 220 source constant. Alpha plane is a photomap.
<code>-blendalpha2</code>	Blend test. Dyadic sources. Alpha plane is a constant 220.
<code>-blendalpharoi1</code>	Blend test. Monadic source, 220 source constant. Alpha plane photomap. ROIs.
<code>-blendalpharoi2</code>	Blend test. Dyadic sources. Alpha plane is a constant 220. ROIs.
<code>-triplepoint1 through -triplepoint2</code>	Illustrate use of point and standard colormaps for rendering triple band images.
<code>-funnyencode1 through -funnyencode8</code>	These tests are designed to perform limited exercising of XIE's capability of dealing with various encodings of flo source data. The test <code>init</code> function obtains a photomap using <code>ICP -> EP</code> . A series of independent permanent flo pairs, one of the form <code>IP -> EP</code> , and the other of the basic form <code>IP -> ED</code> , are con- structed. The encoding parameters for the <code>ExportPhotomap (EP)</code> element in the first flo are derived from test configuration. The number of flo pairs created is also dependent upon test

-point1 through -point3
 -pointroi1
 -pointcplane1

-pointphoto1
 -pointroiphoto1

-pointcplanephoto1

-redefine

-modify1

-modify2

-modify3

-modify4

-modify5

-rgb1 through -rgb16

-converttoindexpixel

-converttoindexplane

configuration. The tests can be configured so that the test `init` function will constrain the input `photomap` to a specified number of levels, on a per band basis, so that word-sized and quad-sized pixels are passed through the flos. Some tests below take advantage of this. See `tests.c` for test configuration, and hints on how to add similar tests.

Simple Point element tests. Drawable destination.

Simple Point element test that uses ROIs. Drawable destination.

Simple Point element test that uses a control plane. Drawable destination.

Simple Point element test. Photomap destination.

Simple Point element test that uses ROIs. Photomap destination.

Simple Point element test that uses a control plane. Photomap destination.

Two flographs are created that are the same in structure, except for the x and y offsets specified for the `ExportDrawable` flo elements. The test `init` function creates a `photoflo` based upon one of the two flographs. The inner loop of the test function uses `XieRedefinePhotoflo()` to alternate between each of the flographs. Make sure that your inner loop reps are 2 or greater in order to exercise this test fully (see `-reps`).

Test `XieModifyPhotoflo()` by adjusting ROI offsets and size.

Test `XieModifyPhotoflo()` by changing the LUT input to a Point element.

Test `XieModifyPhotoflo()` by changing `ExportDrawable` x and y offsets.

This test creates a rather long flo of arithmetic elements, each of which does nothing more than add 1 to a small image. The test `init` function scales the input `photomap`. The `ExportDrawable` x and y offset is modified randomly during each iteration of the test function inner loop.

This test creates a rather long flo of arithmetic elements, each of which does nothing more than add 1 to a large image. Each rep, the `Geometry` and `ExportDrawable` elements at the end of the flo are modified to crop a small piece of the input into its appropriate place in the larger image.

These tests all basically take an `UncompressedTriple` image as input, send it to `ConvertFromRGB`, which converts the image to some configured colorspace, and then send the converted image on to `ConvertToRGB` prior to display. The original image is displayed in the left-hand window, and the image that has passed through the flo is shown in the right-hand window. The goal of these test is to show that `ConvertFromRGB -> ConvertToRGB` is lossless.

`ConvertToIndex` test, `TripleBand BandByPixel`.

`ConvertToIndex` test, `TripleBand BandByPlane`.

`-convertfromindex`

`-complex`

The test `init` function uses a flo containing `ConvertToIndex` to display an image in the left window. The test function uses this drawable as input to a flo that does `ConvertFromIndex` -> `ConvertToIndex` and sends the resulting image to the right window. The result should be lossless.

A somewhat large flo that uses control planes, LUTs, Point, PasteUp, Logical, Constrain, Dither, Geometry, MatchHistogram, BandCombine, and BandSelect elements. See the Postscript file `complex.ps` for a rendition of the photoflo that is executed.

X DEFAULTS

There are no X defaults used by this program.

SEE ALSO

`x(1)`, `x11perf(1)`, `x11perfcomp(1)`

BUGS

There should be an `IMAGES` environment variable to augment the `-images` option.

Many tests only scratch the surface of possible test cases. Some of the options available for certain flo elements are either inadequately tested, or ignored altogether. There are insufficient tests for bitonal, large pixel, or triple band tests.

Some of the test names are inconsistently cased, for example, `-Abort` and `-dither1`.

Some tests are hopelessly slow when run against machines with slow FPUs.

Bitonal images are, for the most part, displayed using the `ExportDrawable` flo element; however, `ExportDrawablePlane` would be a better choice.

AUTHOR

Syd Logan (AGE Logic, Inc.)

X Version 11 Release 6

ximtoppm

`ximtoppm`—Convert an `XIM` file into a portable pixmap

SYNOPSIS

`ximtoppm [ximfile]`

DESCRIPTION

Reads an `xim` file as input. Produces a portable pixmap as output. The `xim` toolkit is included in the contrib tree of the X.V11R4 release.

SEE ALSO

`ppm(5)`

AUTHOR

Copyright (c) 1991 by Jef Poskanzer.

25 March 1990

xinetd

xinetd—The extended Internet services daemon

SYNOPSIS

xinetd [options]

DESCRIPTION

xinetd performs the same function as inetd: it starts programs that provide Internet services. Instead of having such servers started at system initialization time, and be dormant until a connection request arrives, xinetd is the only daemon process started and it listens on all service ports for the services listed in its configuration file. When a request comes in, xinetd starts the appropriate server. Because of the way it operates, xinetd (as well as inetd) is also referred to as a super-server.

The services listed in xinetd's configuration file can be separated into two groups. Services in the first group are called multithreaded and they require the forking of a new server process for each new connection request. The new server then handles that connection. For such services, xinetd keeps listening for new requests so that it can spawn new servers. On the other hand, the second group includes services for which the service daemon is responsible for handling all new connection requests. Such services are called single-threaded and xinetd will stop handling new requests for them until the server dies. Services in this group are usually datagram based.

So far, the only reason for the existence of a super-server was to conserve system resources by avoiding to fork a lot of processes who might be dormant for most of their lifetime. While fulfilling this function, xinetd takes advantage of the idea of a super-server to provide features such as access control and logging. Furthermore, xinetd is not limited to services listed in /etc/services. Therefore, anybody can use xinetd to start special-purpose servers.

OPTIONS

-d

Enables debug mode. This produces a lot of debugging output, and it makes it possible to use a debugger on xinetd.

-syslog syslog_facility

This option enables syslog logging of xinetd-produced messages using the specified syslog facility. The following facility names are supported: daemon, auth, user, local[0-7] (check syslog.conf(5) for their meanings). This option is ineffective in debug mode because all relevant messages are sent to the terminal.

-filelog logfile

xinetd-produced messages will be placed in the specified file. Messages are always appended to the file. If the file does not exist, it will be created. This option is ineffective in debug mode because all relevant messages are sent to the terminal.

-f config_file

Determines the file that xinetd uses for configuration. The default is /etc/xinetd.conf.

-pid

The process pid is written to standard error. This option is ineffective in debug mode.

-loop rate

This option sets the loop rate beyond which a service is considered in error and is deactivated. The loop rate is specified in terms of the number of servers per second that can be forked for a process. The speed of your machine determines the correct value for this option. The default rate is 10.

-reuse

If this option is used, xinetd will set the socket option SO_REUSEADDR before binding the service socket to an Internet address. This allows binding of the address even if there are programs that use it, which happens when a previous instance of xinetd has started some servers that are still running. This option has no effect on RPC services.

`-limit proc_limit`

This option places a limit on the number of concurrently running processes that can be started by `xinetd`. Its purpose is to prevent process table overflows.

`-logprocs limit`

This option places a limit on the number of concurrently running servers for remote user ID acquisition.

`-shutdownprocs limit`

This option places a limit on the number of concurrently running servers for service shutdown (forked when the `RECORD` option is used).

The `syslog` and `filelog` options are mutually exclusive. If none is specified, the default is `syslog` using the daemon facility. You should not confuse `xinetd` messages with messages related to service logging. The latter are logged only if this is specified via the configuration file.

CONFIGURATION FILE

The configuration file determines the services provided by `xinetd`. Any line whose first nonwhitespace character is a `#` is considered a comment line. Empty lines are ignored.

The file contains entries of the form:

```
service <service_name>
{
<attribute> <assign_op><value><value> ...
...
}
```

The assignment operator, `assign_op`, can be one of `=`, `+=`, `-=`. The majority of attributes support only the simple assignment operator, `=`. Attributes whose value is a set of values support all assignment operators. For such attributes, `+=` means adding a value to the set and `-=` means removing a value from the set. A list of these attributes is given after all the attributes are described.

Each entry defines a service identified by the `service_name`. The following is a list of available attributes:

`id`

This attribute is used to uniquely identify a service. This is useful because there exist services that can use different protocols and need to be described with different entries in the configuration file. By default, the service `id` is the same as the service name.

`type`

Possible values are the following:

<code>RPC</code>	If this is an <code>RPC</code> service
<code>INTERNAL</code>	If this is a service provided by <code>xinetd</code> .
<code>UNLISTED</code>	If this is a service not listed in <code>/etc/services</code> .

`flags`

Possible `flag` values are

<code>REUSE</code>	Set the <code>SO_REUSEADDR</code> flag on the service socket.
<code>INTERCEPT</code>	Intercept packets or accepted connections in order to verify that they are coming from acceptable locations (internal or multithreaded services cannot be intercepted).

<code>NORETRY</code>	Avoid retry attempts in case of fork failure.

`socket type`

Possible values are

<code>stream</code>	Stream-based service
<code>dgram</code>	Datagram-based service
<code>raw</code>	Service that requires direct access to IP
<code>seqpacket</code>	Service that requires reliable sequential datagram transmission

protocol	Determines the protocol that is employed by the service. The protocol must exist in <code>/etc/protocols</code> . If this attribute is not defined, the default protocol employed by the service will be used.
wait	This attribute determines if the service is single-threaded or multithreaded. If its value is yes, the service is single-threaded; this means that <code>xinetd</code> will start the server and then it will stop handling requests for the service until the server dies. If the attribute value is no, the service is multithreaded and <code>xinetd</code> will keep handling new service requests.
user	Determines the uid for the server process. The username must exist in <code>/etc/passwd</code> . This attribute is ineffective if the effective user ID of <code>xinetd</code> is not super-user.
group	Determines the gid for the server process. The group name must exist in <code>/etc/group</code> . If a group is not specified, the group of user will be used (from <code>/etc/passwd</code>). This attribute is ineffective if the effective user ID of <code>xinetd</code> is not super-user.
instances	Determines the number of servers that can be simultaneously active for a service. By default, there is no limit. The value of this attribute can be either a number or UNLIMITED, which means that there is no limit.
server	Determines the program to execute for this service.
server_args	Determines the arguments passed to the server. In contrast to <code>inetd</code> , the server name should not be included in <code>server_args</code> .
only_from	Determines the remote hosts to which the particular service is available. Its value is a list of IP addresses that can be specified in any combination of the following ways: a) A numeric address in the form of <code>%d.%d.%d.%d</code>. If the rightmost components are 0, they are treated as wildcards (for example, <code>128.138.12.0</code> matches all hosts on the <code>128.138.12</code> subnet). <code>0.0.0.0</code> matches all Internet addresses. b) A factorized address in the form of <code>%d.%d.%d.{%d,%d,...}</code>. There is no need for all four components (<code>%d.%d.{%d,%d,...%d}</code> is also OK). However, the factorized part must be at the end of the address. c) A network name (from <code>/etc/networks</code>). d) A hostname. All IP addresses of the specified hostname will be used.
" "	Specifying this attribute without a value makes the service available to nobody.
no_access	Determines the remote hosts to which the particular service is unavailable. Its value can be specified in the same way as the value of the <code>only_from</code> attribute. These two attributes determine the location access control enforced by <code>xinetd</code> . If none of the two is specified for a service, the service is available to anyone. If both are specified for a service, the one that is the better match for the address of the remote host determines if the service is available to that host (for example, if the <code>only_from</code> list contains <code>128.138.209.0</code> and the <code>no_access</code> list contains <code>128.138.209.10</code> , then the host with the address <code>128.138.209.10</code> can not access the service).

access_times	Determines the time intervals when the service is available. An interval has the form <code>hour:min-hour:min</code> (connections will be accepted at the bounds of an interval). Hours can range from 0 to 23 and minutes from 0 to 59.												
log_type	Determines where the service log output is sent. There are two formats: <table><tr><td><code>SYSLOG syslog facility [syslog level]</code></td><td>The log output is sent to syslog at the specified facility. If a level is present, the messages will be recorded at that level instead of <code>LOG_INFO</code> (which is the default level).</td></tr><tr><td><code>FILE file [soft_limit [hard_limit]]</code></td><td>The log output is appended to <code>file</code>, which will be created if it does not exist. Two limits on the size of the log file can be optionally specified. The first limit is a soft one; <code>xinetd</code> will log a message the first time this limit is exceeded (if <code>xinetd</code> logs to syslog, the message will be sent at the <code>LOG_ALERT</code> priority level). The second limit is a hard limit; <code>xinetd</code> will stop logging for the affected service (if the log file is a common log file, then more than one service may be affected) and will log a message about this (if <code>xinetd</code> logs to syslog, the message will be sent at the <code>LOG_ALERT</code> priority level). If a hard limit is not specified, it defaults to the soft limit increased by 1 percent but the extra size must be within the parameters <code>LOG_EXTRA_MIN</code> and <code>LOG_EXTRA_MAX</code> (defined in <code>config.h</code>).</td></tr></table>	<code>SYSLOG syslog facility [syslog level]</code>	The log output is sent to syslog at the specified facility. If a level is present, the messages will be recorded at that level instead of <code>LOG_INFO</code> (which is the default level).	<code>FILE file [soft_limit [hard_limit]]</code>	The log output is appended to <code>file</code> , which will be created if it does not exist. Two limits on the size of the log file can be optionally specified. The first limit is a soft one; <code>xinetd</code> will log a message the first time this limit is exceeded (if <code>xinetd</code> logs to syslog, the message will be sent at the <code>LOG_ALERT</code> priority level). The second limit is a hard limit; <code>xinetd</code> will stop logging for the affected service (if the log file is a common log file, then more than one service may be affected) and will log a message about this (if <code>xinetd</code> logs to syslog, the message will be sent at the <code>LOG_ALERT</code> priority level). If a hard limit is not specified, it defaults to the soft limit increased by 1 percent but the extra size must be within the parameters <code>LOG_EXTRA_MIN</code> and <code>LOG_EXTRA_MAX</code> (defined in <code>config.h</code>).								
<code>SYSLOG syslog facility [syslog level]</code>	The log output is sent to syslog at the specified facility. If a level is present, the messages will be recorded at that level instead of <code>LOG_INFO</code> (which is the default level).												
<code>FILE file [soft_limit [hard_limit]]</code>	The log output is appended to <code>file</code> , which will be created if it does not exist. Two limits on the size of the log file can be optionally specified. The first limit is a soft one; <code>xinetd</code> will log a message the first time this limit is exceeded (if <code>xinetd</code> logs to syslog, the message will be sent at the <code>LOG_ALERT</code> priority level). The second limit is a hard limit; <code>xinetd</code> will stop logging for the affected service (if the log file is a common log file, then more than one service may be affected) and will log a message about this (if <code>xinetd</code> logs to syslog, the message will be sent at the <code>LOG_ALERT</code> priority level). If a hard limit is not specified, it defaults to the soft limit increased by 1 percent but the extra size must be within the parameters <code>LOG_EXTRA_MIN</code> and <code>LOG_EXTRA_MAX</code> (defined in <code>config.h</code>).												
log_on_success	Determines what information is logged when a server is started and when that server exits (the service ID is always included in the log entry). Any combination of the following values may be specified: <table><tr><td><code>PID</code></td><td>Logs the server process ID. (If the service is implemented by <code>xinetd</code> without forking another process, the logged process ID will be 0.)</td></tr><tr><td><code>HOST</code></td><td>Logs the remote host address</td></tr><tr><td><code>TIME</code></td><td>Logs the time when the server was started.</td></tr><tr><td><code>USERID</code></td><td>Logs the user ID of the remote user using the RFC 931 identification protocol. This option is available only for multithreaded stream services.</td></tr><tr><td><code>EXIT</code></td><td>Logs the fact that a server exited along with the exit status or the termination signal (the process ID is also logged if the <code>PID</code> option is used).</td></tr><tr><td><code>DURATION</code></td><td>Logs the duration of a service session.</td></tr></table>	<code>PID</code>	Logs the server process ID. (If the service is implemented by <code>xinetd</code> without forking another process, the logged process ID will be 0.)	<code>HOST</code>	Logs the remote host address	<code>TIME</code>	Logs the time when the server was started.	<code>USERID</code>	Logs the user ID of the remote user using the RFC 931 identification protocol. This option is available only for multithreaded stream services.	<code>EXIT</code>	Logs the fact that a server exited along with the exit status or the termination signal (the process ID is also logged if the <code>PID</code> option is used).	<code>DURATION</code>	Logs the duration of a service session.
<code>PID</code>	Logs the server process ID. (If the service is implemented by <code>xinetd</code> without forking another process, the logged process ID will be 0.)												
<code>HOST</code>	Logs the remote host address												
<code>TIME</code>	Logs the time when the server was started.												
<code>USERID</code>	Logs the user ID of the remote user using the RFC 931 identification protocol. This option is available only for multithreaded stream services.												
<code>EXIT</code>	Logs the fact that a server exited along with the exit status or the termination signal (the process ID is also logged if the <code>PID</code> option is used).												
<code>DURATION</code>	Logs the duration of a service session.												
log_on_failure	Determines what information is logged when a server cannot be started (either because of a lack of resources or because of access control restrictions). The service ID is always included in the log entry along with the reason for failure. Any combination of the following values may be specified: <table><tr><td><code>HOST</code></td><td>Logs the remote host address.</td></tr></table>	<code>HOST</code>	Logs the remote host address.										
<code>HOST</code>	Logs the remote host address.												

	TIME	Logs the time when the server was started.
	USERID	Logs the user ID of the remote user using the RFC 931 identification protocol. This option is available only for multithreaded stream services.
	ATTEMPT	Logs the fact that a failed attempt was made.
	RECORD	Records information from the remote end in case the server could not be started. This allows monitoring of attempts to use the service. For example, the login service logs the local user, remote user, and terminal type. Currently, the services that support this option are <code>login</code> , <code>shell</code> , <code>exec</code> , <code>finger</code> .
<code>rpc_version</code>		Determines the RPC version for an RPC service. The version can be a single number or a range in the form <code>number-number</code> .
<code>env</code>		The value of this attribute is a list of strings of the form <code>name=value</code> . These strings will be added to the environment before starting a server (therefore the server's environment will include <code>xinetd</code> 's environment plus the specified strings).
<code>passenv</code>		The value of this attribute is a list of environment variables from <code>xinetd</code> 's environment that will be passed to the server.
<code>port</code>		Determines the service port. If this attribute is specified for a service listed in <code>/etc/services</code> , it must be equal to the port number listed in that file.

You don't need to specify all of the preceding attributes for each service. The necessary attributes for a service are the following:

<code>socket</code>	<code>type</code>	
<code>user</code>		(non-unlisted services only)
<code>server</code>		(non-internal services only)
<code>wait</code>		
<code>protocol</code>		(RPC and unlisted services only)
<code>rpc_version</code>		(RPC services only)
<code>port</code>		(unlisted services only)

The following attributes support all assignment operators, except as indicated:

<code>only_from</code>	
<code>no_access</code>	
<code>log_on_success</code>	
<code>log_on_failure</code>	
<code>passenv</code>	
<code>env</code>	(does not support the <code>-=</code> operator)

These attributes can also appear more than once in a service entry. The remaining attributes support only the `=` operator and can appear at most once in a service entry.

The configuration file may also contain a single defaults entry that has the form:

```
defaults
{
<attribute> = <value><value> ...
...
}
```

This entry provides default attribute values for service entries that don't specify those attributes. Possible default attributes:

<code>log_type</code>	
<code>log_on_success</code>	(cumulative effect)
<code>log_on_failure</code>	(cumulative effect)
<code>only_from</code>	(cumulative effect)
<code>no_access</code>	(cumulative effect)
<code>passenv</code>	(cumulative effect)
<code>instances</code>	
<code>disabled</code>	(cumulative effect)

Attributes with a cumulative effect can be specified multiple times with the values specified each time accumulating (in other words, = does the same thing as +=). With the exception of `disabled` they all have the same meaning as if they were specified in a service entry. `disabled` determines services that are disabled even if they have entries in the configuration file. This allows for quick reconfiguration by specifying disabled services with the `disabled` attribute instead of commenting them out. The value of this attribute is a list of space-separated service IDs.

INTERNAL SERVICES

`xinetd` provides the following services internally (both stream- and datagram-based): `echo`, `time`, `daytime`, `chargen`, and `discard`. These services are under the same access restrictions as all other services except for the ones that don't require `xinetd` to fork another process for them. Those ones (`time`, `daytime`, and the datagram-based `echo`, `chargen`, and `discard`) have no limitation in the number of instances.

CONTROLLING `xinetd`

`xinetd` performs certain actions when it receives certain signals. The actions associated with the specific signals can be redefined by editing `config.h` and recompiling.

<code>SIGUSR1</code>	Causes a soft reconfiguration, which means that <code>xinetd</code> rereads the configuration file and adjusts accordingly.
<code>SIGUSR2</code>	Causes a hard reconfiguration, which is the same as a soft reconfiguration except that servers for services that are no longer available are terminated. Access control is performed again on running servers by checking the remote location, access times and server instances. If the number of server instances is lowered, some arbitrarily picked servers will be killed to satisfy the limit; this will happen after any servers are terminated because of failing the remote location or access time checks. Also, if the <code>INTERCEPT</code> flag was clear and is set, any running servers for that service will be terminated; the purpose of this is to ensure that after a hard reconfiguration there will be no running servers that can accept packets from addresses that do not meet the access control criteria.
<code>SIGQUIT</code>	Causes program termination.
<code>SIGTERM</code>	Terminates all running servers before terminating <code>xinetd</code> .
<code>SIGHUP</code>	Causes an internal state dump (the default dump file is <code>/tmp/xinetd.dump</code> ; to change the filename, edit <code>config.h</code> and recompile).
<code>SIGIOT</code>	Causes an internal consistency check to verify that the data structures used by the program have not been corrupted. When the check is completed <code>xinetd</code> will generate a message that says if the check was successful or not.

On reconfiguration, the log files are closed and reopened. This allows removal of old log files. Also, the following attributes cannot be changed on reconfiguration: `socket_type`, `wait`, `protocol`, `type`.

xinetd LOG FORMAT

Log entries are lines with the following format:

entry: service-id data

The data depends on the entry. Possible entry types:

START	Generated when a server is started
EXIT	Generated when a server exits
FAIL	Generated when it is not possible to start a server
DATA	Generated when an attempt to start a server fails and the service supports the <code>RECORD</code> log option.
USERID	Generated if the <code>USERID</code> log option is used.

In the following formats, the information enclosed in brackets appears if the appropriate log option is used.

A `START` entry has the format

START: service-id [pid=%d] [from=%d.%d.%d] [time=time]

Time is given as year/month/day@hour:minutes:seconds.

An `EXIT` entry has the format

EXIT: service-id [type=%d] [pid=%d] [duration=%d(sec)]

type can be either status or signal. The number is either the exit status or the signal that caused process termination.

A `FAIL` entry has the format:

FAIL: service-id reason [from=%d.%d.%d] [time=time]

Possible reasons are

fork	A certain number of consecutive fork attempts failed (this number is a configurable parameter).
time	The time check failed.
address	The address check failed.
service_limit	The allowed number of server instances for this service would be exceeded.
process_limit	A limit on the number of forked processes was specified and it would be exceeded.

A `DATA` entry has the format

DATA: service-id data

The data logged depends on the service.

login	remote_user=%s local_user=%s tty=%s
exec	remote_user=%s verify=status command=%s Possible status values:
	ok The password was correct
	failed The password was incorrect
	baduser No such user
	shell remote_user=%s local_user=%s command=%s
	finger received string OR EMPTY-LINE

A USERID entry has the format

USERID: text

The text is the response of the RFC 931 daemon at the remote end excluding the port numbers (which are included in the response). Here's an example:

```
#
# Sample configuration file for xinetd
#
defaults
{
    log_type = FILE /var/log/servicelog
    log_on_success = PID
    log_on_failure = HOST TIME RECORD
    only_from = 128.138.193.0 128.138.204.0 128.138.209.0
    only_from = 128.138.252.1
    instances = 10
    disabled = rstatd
}
#
# Note 1: the protocol attribute is not required
# Note 2: the instances attribute overrides the default
#
service login
{
    socket_type = stream
    protocol = tcp
    wait = no
    user = root
    server = /usr/etc/in.rlogind
    instances = UNLIMITED
}
#
# Note 1: the instances attribute overrides the default
# Note 2: the log on success flags are augmented
#
service shell
{
    socket_type = stream
    wait = no
    user = root
    instances = UNLIMITED
    server = /usr/etc/in.rshd
    log_on_success += HOST TIME RECORD
}
service ftp
{
    socket_type = stream
    wait = no
    user = root
    server = /usr/etc/in.ftpd
    server_args = -l
    instances = 4
    log_on_success += DURATION HOST USERID
    access_times = 2:00-9:00 12:00-24:00
}
#
# This entry and the next one specify internal services. Since this
# is the same service using a different socket type, the id attribute
# is used to uniquely identify each entry
#
```

```

service echo
{
    id = echo-stream
    type = INTERNAL
    socket_type = stream
    user = root
    wait = no
}
service echo
{
    id = echo-dgram
    type = INTERNAL
    socket_type = dgram
    user = root
    wait = no
}
#
# Sample RPC service
#
service rstatd
{
    type = RPC
    socket_type = dgram
    protocol = udp
    server = /usr/etc/rpc.rstatd
    wait = yes
    user = root
    rpc_version = 2-4
    env = LD_LIBRARY_PATH=/etc/securelib
}
#
# Sample unlisted service
#
service unlisted
{
    type = UNLISTED
    socket_type = stream
    protocol = tcp
    wait = no
    server = /home/user/some server
    port = 20020
}

```

FILES

/etc/xinetd.conf
/tmp/xinetd.dump

Default configuration file
Default dump file

SEE ALSO

inetd(8)

Postel J., *Echo Protocol*, RFC 862, May 1983.

Postel J., *Discard Protocol*, RFC 863, May 1983.

Postel J., *Character Generator Protocol*, RFC 864, May 1983.

Postel J., *Daytime Protocol*, RFC 867, May 1983.

Postel J., Harrenstien K., *Time Protocol*, RFC 868, May 1983.

St. Johns M., *Authentication Server*, RFC 931, January 1985.

AUTHOR

Panos Tsirigotis (CS Department, University of Colorado, Boulder)

NOTES

When the attributes `only_from` and `no_access` are not specified for a service (either directly or via defaults), the address check is considered successful (that is, access will not be denied).

If the `USERID` log option is specified and the remote RFC 931 server sends back an `ERROR` reply, access will not be denied.

If the `USERID` log option is specified and the remote host does not run an RFC 931 server, there will be no indication in the log of that fact (other than the missing `USERID` log entry).

BUGS

Supplementary group IDs are not supported.

If the `INTERCEPT` flag is not used, access control on the address of the remote host is not performed when `wait` is `yes` and `socket_type` is `stream`.

If the `INTERCEPT` flag is not used, access control on the address of the remote host for services where `wait` is `yes` and `socket_type` is `dgram` is performed only on the first packet. The server may then accept packets from hosts not in the access control list. This can happen with RPC services.

Unlisted RPC services are not supported; that is, all RPC services must be registered in `/etc/rpc`. Specifying an RPC service by its RPC program number is not (yet) possible.

There is no way to put a `SPACE` in an environment variable.

When `wait` is `yes` and `socket_type` is `stream`, the socket passed to the server can only accept connections.

The `INTERCEPT` flag is not supported for internal services or multithreaded services.

Interception works by forking a process that acts as a filter between the remote host(s) and the local server. This obviously has a performance impact which depends on the volume of information exchanged. It is up to you to make the compromise between security and performance for each service.

PRONUNCIATION

`xinetd` is pronounced “zy-net-d.”

10 May 1992

xinit

`xinit`—X Window System initializer

SYNOPSIS

```
xinit [[client ] options ][-- [ server ][display ] options ]
```

DESCRIPTION

The `xinit` program is used to start the X Window System server and a first client program on systems that cannot start X directly from `/etc/init` or in environments that use multiple window systems. When this first client exits, `xinit` will kill the X server and then terminate.

If no specific client program is given on the command line, `xinit` will look for a file in the user’s home directory called `.xinitrc` to run as a shell script to start up client programs. If no such file exists, `xinit` will use the following as a default:

```
xterm -geometry +1+1 -n login -display :0
```

If no specific server program is given on the command line, `xinit` will look for a file in the user's home directory called `.xserverrc` to run as a shell script to start up the server. If no such file exists, `xinit` will use the following as a default:

```
X :0
```

Note that this assumes that there is a program named `X` in the current search path. However, servers are usually named `Xdisplaytype` where `displaytype` is the type of graphics display that is driven by this server. The site administrator should, therefore, make a link to the appropriate type of server on the machine, or create a shell script that runs `xinit` with the appropriate server.

Note, when using a `.xserverrc` script be sure to mark the real `X` server as `exec`. Failing to do this can make the `X` server slow to start and exit. For example

```
exec Xdisplaytype
```

An important point is that programs which are run by `xinitrc` should be run in the background if they do not exit right away, so that they don't prevent other programs from starting up. However, the last long-lived program started (usually a window manager or terminal emulator) should be left in the foreground so that the script won't exit (which indicates that the user is done and that `xinit` should exit).

An alternate client and/or server may be specified on the command line. The desired client program and its arguments should be given as the first command-line arguments to `xinit`. To specify a particular server command line, append two dashes (`--`) to the `xinit` command line (after any client and arguments) followed by the desired server command.

Both the client program name and the server program name must begin with a slash (/) or a period (.). Otherwise, they are treated as arguments to be appended to their respective startup lines. This makes it possible to add arguments (for example, foreground and background colors) without having to retype the whole command line.

If an explicit server name is not given and the first argument following the double dash (`--`) is a colon followed by a digit, `xinit` will use that number as the display number instead of zero. All remaining arguments are appended to the server command line.

EXAMPLES

Following are several examples of how command-line arguments in `xinit` are used:

This will start up a server named `X` and run the user's `xinitrc`, if it exists, or else start an `xterm`:

```
xinit
```

This is how one could start a specific type of server on an alternate display:

```
xinit -- /usr/X11R6/bin/Xqds :1
```

This will start up a server named `X`, and will append the given arguments to the default `xterm` command (it will ignore `xinitrc`):

```
xinit -geometry =80x65+10+10 -fn 8x13 -j -fg white -bg navy
```

This will use the command `Xsun -l -c` to start the server and will append the arguments `-e widgets` to the default `xterm` command:

```
xinit -e widgets -- ./Xsun -l -c
```

This will start a server named `X` on display `1` with the arguments `-a 2 -t5`:

```
xinit /usr/ucb/rsh fasthost cpupig -display ws:1 -- :1 -a 2 -t 5
```

It will then start a remote shell on the machine `fasthost` in which it will run the command `cpupig`, telling it to display back on the local workstation.

Following is a sample `xinitrc` that starts a clock, starts several terminals, and leaves the window manager running as the "last" application. Assuming that the window manager has been configured properly, the user then chooses the `Exit` menu item to shut down `X`.

```
xrdb -load $HOME/.Xresources
xsetroot -solid gray &
```

```
xclock -g 50x50-0+0 -bw 0 &
xload -g 50x50-50+0 -bw 0 &
xterm -g 80x24+0+0 &
xterm -g 80x24+0-0 &
twm
```

Sites that want to create a common startup environment could simply create a default `xinitrc` that references a site-wide startup file:

```
#!/bin/sh
. /usr/local/lib/site.xinitrc
```

Another approach is to write a script that starts `xinit` with a specific shell script. Such scripts are usually named `x11`, `xstart`, or `startx`, and are a convenient way to provide a simple interface for novice users:

```
#!/bin/sh
xinit /usr/local/lib/site.xinitrc -- /usr/X11R6/bin/X bc
```

ENVIRONMENT VARIABLES

`DISPLAY`

This variable gets set to the name of the display to which clients should connect.

`XINITRC`

This variable specifies an `init` file containing shell commands to start up the initial windows. By default, `xinitrc` in the home directory will be used.

FILES

`.xinitrc`

Default client script

`xterm`

Client to run if `.xinitrc` does not exist

`.xserverrc`

Default server script

`X`

Server to run if `.xserverrc` does not exist

SEE ALSO

`x(1)`, `startx(1)`, `xserver(1)`, `xterm(1)`

AUTHOR

Bob Scheifler (MIT Laboratory for Computer Science)

X Version 11 Release 6

xkill

`xkill`—Kill a client by its X resource

SYNOPSIS

```
xkill [-display displayname] [-id resource] [-button number] [-frame] [-all]
```

DESCRIPTION

`xkill` is a utility for forcing the X server to close connections to clients. This program is very dangerous, but is useful for aborting programs that have displayed undesired windows on a user's screen. If no resource identifier is given with `-id`, `xkill` will display a special cursor as a prompt for the user to select a window to be killed. If a pointer button is pressed over a nonroot window, the server will close its connection to the client that created the window.

OPTIONS

`-display displayname`
`-id resource`

This option specifies the name of the X server to contact.

This option specifies the X identifier for the resource whose creator is to be aborted. If no resource is specified, `xkill` will display a special cursor with which you should select a window to be kill.

`-button number`

This option specifies the number of pointer button that should be used in selecting a window to kill. If the word “any” is specified, any button on the pointer may be used. By default, the first button in the pointer map (which is usually the leftmost button) is used.

`-all`

This option indicates that all clients with top-level windows on the screen should be killed. `xkill` will ask you to select the root window with each of the currently defined buttons to give you several chances to abort. Use of this option is highly discouraged.

`-frame`

This option indicates that `xkill` should ignore the standard conventions for finding top-level client windows (which are typically nested inside a window manager window), and simply believe that you want to kill direct children of the root.

XDEFAULTS

Button

Specifies a specific pointer button number or the word “any” to use when selecting windows.

SEE ALSO

`x(1)`, `xwininfo(1)`, `XKillClient` and `XGetPointerMapping` in the *Xlib Programmers Manual*, `KillClient` in the *X Protocol Specification*

AUTHOR

Jim Fulton (MIT X Consortium) and Dana Chee (Bellcore)

X Version 11 Release 6

xlogo

xlogo—X Window System logo

SYNOPSIS

`xlogo [-toolkitoption ...]`

DESCRIPTION

The `xlogo` program displays the X Window System logo.

OPTIONS

`xlogo` accepts all of the standard X Toolkit command-line options, as well as the following:

`-shape`

This option indicates that the logo window should be shaped rather than rectangular.

RESOURCES

The default width and the default height are each 100 pixels. This program uses the Logo widget in the Athena widget set. It understands all of the Simple widget resource names and classes as well as:

`foreground` (class `Foreground`)

Specifies the color for the logo. The default depends on whether `reverseVideo` is specified. If `reverseVideo` is specified, the default is `XtDefaultForeground`, otherwise the default is `XtDefaultBackground`.

`shapeWindow` (class `ShapeWindow`)

Specifies that the window is shaped to the X logo. The default is `False`.

WIDGETS

In order to specify resources, it is useful to know the hierarchy of the widgets that compose `xlogo`. In the following notation, indentation indicates hierarchical structure. The widget class name is given first, followed by the widget instance name.

```
XLogo xlogo
  Logo xlogo
```

ENVIRONMENT

`DISPLAY`

To get the default host and display number.

`XENVIRONMENT`

To get the name of a resource file that overrides the global resources stored in the `RESOURCE_MANAGER` property.

FILES

`<XRoot>/lib/X11/app-defaults/XLogo` Specifies required resources

SEE ALSO

`x(1)`, `xrdb(1)`

AUTHORS

Ollie Jones of Apollo Computer and Jim Fulton of the MIT X Consortium wrote the logo graphics routine, based on a graphic design by Danny Chong and Ross Chapman of Apollo Computer.

X Version 11 Release 6

xlsatoms

`xlsatoms`—List interned atoms defined on server

SYNOPSIS

```
xlsatoms [-options ...]
```

DESCRIPTION

`xlsatoms` lists the interned atoms. By default, all atoms starting from 1 (the lowest atom value defined by the protocol) are listed until unknown atom is found. If an explicit range is given, `xlsatoms` will try all atoms in the range, regardless of whether or not any are undefined.

OPTIONS

-display dpy
 -format string

 -range [low] - [high]

 -name string

This option specifies the X server to which to connect.

This option specifies a printf-style string used to list each atom <value,name> pair, printed in that order (value is an unsigned long and name is a char *). xlsatoms will supply a newline at the end of each line. The default is %ld\t%s.

This option specifies the range of atom values to check. If low is not given, a value of 1 is assumed. If high is not given, xlsatoms will stop at the first undefined atom at or above low.

This option specifies the name of an atom to list. If the atom does not exist, a message will be printed on the standard error.

SEE ALSO

x(1), Xserver(1), xprop(1)

ENVIRONMENT

DISPLAY

To get the default host and display to use

AUTHOR

Jim Fulton (MIT X Consortium)

X Version 11 Release 6

xlsclients

xlsclients—List client applications running on a display

SYNOPSIS

xlsclients [-display displayname] [-a] [-l] [-m maxcmdlen]

DESCRIPTION

xlsclients is a utility for listing information about the client applications running on a display. It may be used to generate scripts representing a snapshot of the user's current session.

OPTIONS

-display displayname
 -a

 -l

 -m maxcmdlen

This option specifies the X server to contact.

This option indicates that clients on all screens should be listed. By default, only those clients on the default screen are listed.

List in long format, giving the window name, icon name, and class hints in addition to the machine name and command string shown in the default format.

This option specifies the maximum number of characters in a command to print out. The default is 10000.

ENVIRONMENT

DISPLAY

To get the default host, display number, and screen.

SEE ALSO

`x(1)`, `xwininfo(1)`, `xprop(1)`

AUTHOR

Jim Fulton (MIT X Consortium)

X Version 11 Release 6

xlsfonts

`xlsfonts`—Server font list display for X

SYNOPSIS

`xlsfonts [-options ...] [-fn pattern]`

DESCRIPTION

`xlsfonts` lists the fonts that match the given pattern. The wildcard character `*` may be used to match any sequence of characters (including none), and `?` to match any single character. If no pattern is given, `*` is assumed.

The `*` and `?` characters must be quoted to prevent them from being expanded by the shell.

OPTIONS

`-display host:dpy`

This option specifies the X server to contact.

`-l`

Lists some attributes of the font on one line in addition to its name.

`-ll`

Lists font properties in addition to `-l` output.

`-lll`

Lists character metrics in addition to `-ll` output.

`-m`

This option indicates that long listings should also print the minimum and maximum bounds of each font.

`-C`

This option indicates that listings should use multiple columns. This is the same as `-n 0`.

`-1`

This option indicates that listings should use a single column. This is the same as `-n 1`.

`-w width`

This option specifies the width in characters that should be used in figuring out how many columns to print. The default is 79.

`-n columns`

This option specifies the number of columns to use in displaying the output. By default, it will attempt to fit as many columns of font names into the number of character specified by `-w width`.

`-u`

This option indicates that the output should be left unsorted.

`-o`

This option indicates that `xlsfonts` should do an `OpenFont` (and `QueryFont`, if appropriate) rather than a `ListFonts`. This is useful if `ListFonts` or `ListFontsWithInfo` fail to list a known font (as is the case with some scaled font systems).

`-fn pattern`

This option specifies the font name pattern to match.

SEE ALSO

`x(1)`, `Xserver(1)`, `xset(1)`, `xfd(1)`, X Logical Font Description Conventions

ENVIRONMENT

DISPLAY

To get the default host and display to use

BUGS

Doing `xlsfonts -l` can tie up your server for a very long time. This is really a bug with single-threaded nonpreemptable servers, not with this program.

AUTHOR

Mark Lillibridge (MIT Project Athena), Jim Fulton (MIT X Consortium), and Phil Karlton (SGI)

X Version 11 Release 6

xmag

xmag—Magnify parts of the screen

SYNOPSIS

```
xmag [ -mag magfactor ][-source geom ][-toolkitoption ...]
```

DESCRIPTION

The xmag program allows you to magnify portions of an X screen. If no explicit region is specified, a square with the pointer in the upper-left corner is displayed indicating the area to be enlarged. The area can be dragged out to the desired size by pressing Button 2. After a region has been selected, a window is popped up showing a blown-up version of the region in which each pixel in the source image is represented by a small square of the same color. Pressing Button 1 in the enlargement window shows the position and RGB value of the pixel under the pointer until the button is released. Typing `q` or `^C` in the enlargement window exits the program. The application has five buttons across its top. Close deletes this particular magnification instance. Replace brings up the rubber band selector again to select another region for this magnification instance. New brings up the rubber band selector to create a new magnification instance. Cut puts the magnification image into the primary selection. Paste copies the primary selection buffer into xmag. Note that you can cut and paste between xmag and the bitmap program. Resizing xmag resizes the magnification area. xmag preserves the colormap, visual, and window depth of the source.

WIDGETS

xmag uses the X Toolkit and the Athena Widget Set. The magnified image is displayed in the Scale widget. For more information, see the Athena Widget Set documentation. Following is the widget structure of the xmag application. Indentation indicates hierarchical structure. The widget class name is given first, followed by the widget instance name.

```
Xmag xmag
  RootWindow root
    TopLevelShell xmag
      Paned pane1
        Paned pane2
          Command close
          Command replace
          Command new
          Command select
          Command paste
          Label xmag label1
        Paned pane2
          Scale scale
      OverrideShell pixShell
        Label pixLabel
```

OPTIONS

`-source geom`

This option specifies the size and/or location of the source region on the screen. By default, a 64×64 square is provided for the user to select an area of the screen.

`-mag integer`

This option indicates the magnification to be used. The default is 5.

AUTHORS

Dave Sternlicht and Davor Matic (MIT X Consortium)

X Version 11 Release 6

xmkmf

xmkmf—Create a Makefile from an Imakefile

SYNOPSIS

```
xmkmf [-a][topdir [ curdir ]]
```

DESCRIPTION

The `xmkmf` command is the normal way to create a Makefile from an Imakefile shipped with third-party software.

When invoked with no arguments in a directory containing an Imakefile, the `imake` program is run with arguments appropriate for your system (configured into `xmkmf` when X was built) and generates a Makefile.

When invoked with the `-a` option, `xmkmf` builds the Makefile in the current directory, and then automatically executes `make` Makefiles (in case there are subdirectories), `make includes`, and `make depend` for you. This is the normal way to configure software that is outside the X Consortium build tree.

If working inside the X Consortium build tree (unlikely unless you are an X developer, and even then this option is never really used), the `topdir` argument should be specified as the relative pathname from the current directory to the top of the build tree. Optionally, `curdir` may be specified as a relative pathname from the top of the build tree to the current directory. It is necessary to supply `curdir` if the current directory has subdirectories, or the Makefile will not be able to build the subdirectories. If a `topdir` is given, `xmkmf` assumes nothing is installed on your system and looks for files in the build tree instead of using the installed versions.

SEE ALSO

`imake(1)`

X Version 11 Release 6

xmodmap

xmodmap—Utility for modifying keymaps in X

SYNOPSIS

```
xmodmap [-options ...] [filename]
```

DESCRIPTION

The `xmodmap` program is used to edit and display the keyboard modifier map and keymap table that are used by client applications to convert event keycodes into keysyms. It is usually run from the user's session startup script to configure the keyboard according to personal tastes.

OPTIONS

The following options may be used with `xmodmap`:

`-display display`
`-help`

`-grammar`

`-verbose`

`-quiet`

`-n`

`-e expression`

`-pm`

`-pk`

`-pke`

`-pp`

`-`

This option specifies the host and display to use.

This option indicates that a brief description of the command-line arguments should be printed on the standard error channel. This will be done whenever an unhandled argument is given to `xmodmap`.

This option indicates that a help message describing the expression grammar used in files and with `-e` expressions should be printed on the standard error.

This option indicates that `xmodmap` should print logging information as it parses its input.

This option turns off the verbose logging. This is the default.

This option indicates that `xmodmap` should not change the mappings, but should display what it would do, like `make(1)` does when given this option.

This option specifies an expression to be executed. Any number of expressions may be specified from the command line.

This option indicates that the current modifier map should be printed on the standard output.

This option indicates that the current keymap table should be printed on the standard output.

This option indicates that the current keymap table should be printed on the standard output in the form of expressions that can be fed back to `xmodmap`.

This option indicates that the current pointer map should be printed on the standard output.

A lone dash means that the standard input should be used as the input file.

The filename specifies a file containing `xmodmap` expressions to be executed. This file is usually kept in the user's home directory with a name like `.xmodmaprc`.

EXPRESSION GRAMMAR

The `xmodmap` program reads a list of expressions and parses them all before attempting to execute any of them. This makes it possible to refer to keysyms that are being redefined in a natural way without having to worry as much about name conflicts.

`keycode NUMBER = KEYSYMNAME ...`

The list of keysyms is assigned to the indicated keycode (which may be specified in decimal, hex, or octal and can be determined by running the `xev` program).

`keycode any = KEYSYMNAME ...`

If no existing key has the specified list of keysyms assigned to it, a spare key on the keyboard is selected and the keysyms are assigned to it. The list of keysyms may be specified in decimal, hex, or octal.

`keysym KEYSYMNAME = KEYSYMNAME ...`

The `KEYSYMNAME` on the left side is translated into matching keycodes used to perform the corresponding set of `keycode` expressions. The list of keysym names may be found in the

```
clear MODIFIERNAME
```

```
add MODIFIERNAME = KEYSYMBOL ...
```

```
remove MODIFIERNAME = KEYSYMBOL ...
```

```
pointer = default
```

```
pointer = NUMBER ...
```

Lines that begin with an exclamation point (!) are taken as comments.

If you want to change the binding of a modifier key, you must also remove it from the appropriate modifier map.

EXAMPLES

Many pointers are designed such that the first button is pressed using the index finger of the right hand. People who are left-handed frequently find that it is more comfortable to reverse the button codes that are generated so that the primary button is pressed using the index finger of the left hand. This could be done on a 3 button pointer as follows: `% xmodmap -e "pointer = 3 2 1"`.

Many applications support the notion of Meta keys (similar to Control keys except that Meta is held down instead of Control). However, some servers do not have a Meta keysym in the default keymap table, so one needs to be added by hand. The following command will attach Meta to the Multilanguage key (sometimes labeled Compose Character). It also takes advantage of the fact that applications that need a Meta key simply need to get the keycode and don't require the keysym to be in the first column of the keymap table. This means that applications that are looking for a Multi key (including the default modifier map) won't notice any change. Example:

```
% xmodmap -e "keysym Multi_key = Multi_key Meta_L"
```

Similarly, some keyboards have an Alt key but no Meta key. In that case the following may be useful:

```
% xmodmap -e "keysym Alt_L = Meta_L Alt_L"
```

One of the more simple, yet convenient, uses of `xmodmap` is to set the keyboard's "rubout" key to generate an alternate keysym. This frequently involves exchanging Backspace with Delete to be more comfortable to the user. If the `ttymodes` resource in `xterm` is set as well, all terminal emulator windows will use the same key for erasing characters:

```
% xmodmap -e "keysym BackSpace = Delete"
% echo "XTerm*ttymodes: erase ^?" | xrdp -merge
```

header file `<X11/keysymdef.h` (without the `XK_prefix`) or the keysym database `<XRoot>/lib/X11/XKeysymDB`, where `<XRoot>` refers to the root of the X11 install tree. Note that if the same keysym is bound to multiple keys, the expression is executed for each matching keycode.

This removes all entries in the modifier map for the given modifier, where valid names are `Shift`, `Lock`, `Control`, `Mod1`, `Mod2`, `Mod3`, `Mod4`, and `Mod5` (case does not matter in modifier names, although it does matter for all other names). For example, `clear Lock` will remove any keys that were bound to the shift lock modifier.

This adds all keys containing the given keysyms to the indicated modifier map. The keysym names are evaluated after all input expressions are read to make it easy to write expressions to swap keys. (See the "Examples" subsection).

This removes all keys containing the given keysyms from the indicated modifier map. Unlike `add`, the keysym names are evaluated as the line is read in. This allows you to remove keys from a modifier without having to worry about whether or not they have been reassigned.

This sets the pointer map back to its default settings (button 1 generates a code of 1, button 2 generates a 2, and so on).

This sets to pointer map to contain the indicated button codes. The list always starts with the first physical button.

Some keyboards do not automatically generate less than and greater than characters when the comma and period keys are shifted. This can be remedied with `xmodmap` by resetting the bindings for the comma and period with the following scripts:

```
!
! make shift-, be $<$ and shift-. be $>$
!
keysym comma = comma less
keysym period = period greater
```

One of the more irritating differences between keyboards is the location of the Control and Shift Lock keys. A common use of `xmodmap` is to swap these two keys as follows:

```
!
! Swap Caps_Lock and Control_L
!
remove Lock = Caps_Lock
remove Control = Control_L
keysym Control_L = Caps_Lock
keysym Caps_Lock = Control_L
add Lock = Caps_Lock
add Control = Control_L
```

The `keycode` command is useful for assigning the same keysym to multiple keycodes. Although unportable, it also makes it possible to write scripts that can reset the keyboard to a known state. The following script sets the Backspace key to generate Delete (as shown earlier), flushes all existing caps lock bindings, makes the Caps Lock key be a control key, make F5 generate Escape, and makes Break/Reset be a shift lock.

```
!
! On the HP, the following keycodes have key caps as listed:
!
!      101 Backspace
!      55 Caps
!      14 Ctrl
!      15 Break/Reset
!      86 Stop
!      89F5
!
keycode 101 = Delete
keycode 55 = Control_R
clear Lock
add Control = Control_R
keycode 89 = Escape
keycode 15 = Caps_Lock
add Lock = Caps_Lock
```

ENVIRONMENT

DISPLAY

To get default host and display number

SEE ALSO

`x(1)`, `xev(1)`, Xlib documentation on key and pointer events

BUGS

Every time a keycode expression is evaluated, the server generates a `MappingNotify` event on every client. This can cause some thrashing. All of the changes should be batched together and done at once. Clients that receive keyboard input and ignore `MappingNotify` events will not notice any changes made to keyboard mappings.

`xmodmap` should generate `add` and `remove` expressions automatically whenever a keycode that is already bound to a modifier is changed.

There should be a way to have the `remove` expression accept keycodes as well as keysyms for those times when you really mess up your mappings.

AUTHOR

Jim Fulton (MIT X Consortium), rewritten from an earlier version by David Rosenthal (Sun Microsystems)

X Version 11 Release 6

xon

`xon`—Start an X program on a remote machine

SYNOPSIS

```
xon remote-host [-access] [-debug] [-name window-name] [-nols] [-screen screen-no] [-user user-name] [command ...]
```

DESCRIPTION

`xon` runs the specified command (default `xterm -ls`) on the remote machine using `rsh`, `remsh`, or `rcmd`. `xon` passes the `DISPLAY`, `XAUTHORITY`, and `XUSERFILESEARCHPATH` environment variables to the remote command.

When no command is specified, `xon` runs `xterm -ls`. It additionally specifies the application name to be `xterm-remote-host` and the window title to be `-fIremote-host`.

`xon` can only work when the remote host will allow you to log in without a password, by having an entry in the `.rhosts` file permitting access.

OPTIONS

Note that the options follow the remote hostname (as they do with `rlogin`).

<code>-access</code>	Runs <code>xhost</code> locally to add the remote host to the host access list in the X server. This won't work unless <code>xhost</code> is given permission to modify the access list.
<code>-debug</code>	Normally, <code>xon</code> disconnects the remote process from <code>stdin</code> , <code>stdout</code> , and <code>stderr</code> to eliminate the daemon processes that usually connect them across the network. Specifying the <code>-debug</code> option leaves them connected so that error messages from the remote execution are sent back to the originating host.
<code>-name window-name</code>	This specifies a different application name and window title for the default command (<code>xterm</code>).
<code>-nols</code>	Normally <code>xon</code> passes the <code>-ls</code> option to the remote <code>xterm</code> ; this option suspends that behavior.
<code>-screen screen-no</code>	This changes the screen number of the <code>DISPLAY</code> variable passed to the remote command.
<code>-user user-name</code>	By default, <code>xon</code> simply uses <code>rsh/remsh/rcmd</code> to connect to the remote machine using the same username as on the local machine. This option causes <code>xon</code> to specify an alternative username. This will not work unless you have authorization to access the remote account, by placing an appropriate entry in the remote user's <code>.rhosts</code> file.

BUGS

`xon` can get easily confused when the remote host, username, or various environment variable values contain whitespace.

`xon` has no way to send the appropriate X authorization information to the remote host.

X Version 11 Release 6

xpmtoppm

xpmtoppm—Convert an X11 pixmap into a portable pixmap

SYNOPSIS

```
xpmtoppm [xpmfile]
```

DESCRIPTION

Reads an X11 pixmap (XPM version 1 or 3) as input. Produces a portable pixmap as output.

KNOWN BUGS

The support to XPM version 3 is limited. Comments can only be single lines and there must be for every pixel a default color name for a color type visual.

SEE ALSO

ppmtoppm(1), ppm(5)

XPM Manual by Arnaud Le Hors (lehors@mirsa.inria.fr)

AUTHOR

Copyright (c) 1991 by Jef Poskanzer.

Upgraded to support XPM version 3 by Arnaud Le Hors (lehors@mirsa.inria.fr) 9 April 1991

16 August 1990

xprop

xprop—Property displayer for X

SYNOPSIS

```
xprop [-help] [-grammar] [-id id] [-root] [-name name] [-frame] [-font font]
[-display display] [-len n] [-notype] [-fs file] [-remove property-name]
[-spy] [-f atom format [dformat]]* [format [dformat] atom]*
```

SUMMARY

The xprop utility is for displaying window and font properties in an X server. One window or font is selected using the command-line arguments or possibly in the case of a window, by clicking on the desired window. A list of properties is then given, possibly with formatting information.

OPTIONS

-help

Print out a summary of command-line options.

-grammar

Print out a detailed grammar for all command-line options.

-id id

This argument allows the user to select window *id* on the command line rather than using the pointer to select the target window. This is very useful in debugging X applications where the target window is not mapped to the screen or where the use of the pointer might be impossible or interfere with the application.

-name name

This argument allows the user to specify that the window named *name* is the target window on the command line rather than using the pointer to select the target window.

<code>-font font</code>	This argument allows the user to specify that the properties of font <code>font</code> should be displayed.
<code>-root</code>	This argument specifies that X's root window is the target window. This is useful in situations where the root window is completely obscured.
<code>-display display</code>	This argument allows you to specify the server to connect to; see <code>x(1)</code> .
<code>-len n</code>	Specifies that at most, <i>n</i> bytes of any property should be read or displayed.
<code>-notype</code>	Specifies that the type of each property should not be displayed.
<code>-fs file</code>	Specifies that file <code>file</code> should be used as a source of more formats for properties.
<code>-frame</code>	Specifies that when selecting a window by hand (that is, if neither <code>-name</code> , <code>-root</code> , nor <code>-id</code> is given), look at the window manager frame (if any) instead of looking for the client window.
<code>-remove property-name</code>	Specifies the name of a property to be removed from the indicated window.
<code>-spy</code>	Examine window properties forever, looking for property change events.
<code>-f name format [dformat]</code>	Specifies that the format for <code>name</code> should be <code>format</code> and that the <code>dformat</code> for <code>name</code> should be <code>dformat</code> . If <code>dformat</code> is missing, " <code>= \$0+\\n</code> " is assumed.

DESCRIPTION

For each of these properties, its value on the selected window or font is printed using the supplied formatting information, if any. If no formatting information is supplied, internal defaults are used. If a property is not defined on the selected window or font, `not defined` is printed as the value for that property. If no property list is given, all the properties possessed by the selected window or font are printed.

A window may be selected in one of four ways. First, if the desired window is the root window, the `-root` argument may be used. If the desired window is not the root window, it may be selected in two ways on the command line, either by id number, such as might be obtained from `xwininfo`, or by name if the window possesses a name. The `-id` argument selects a window by id number in either decimal or hex (must start with `0x`) while the `-name` argument selects a window by name.

The last way to select a window does not involve the command line at all. If none of `-font`, `-id`, `-name`, and `-root` are specified, a crosshairs cursor is displayed and the user is allowed to choose any visible window by pressing any pointer button in the desired window. If it is desired to display properties of a font as opposed to a window, the `-font` argument must be used.

Other than the preceding four arguments and the `-help` argument for obtaining help, and the `-grammar` argument for listing the full grammar for the command line, all the other command-line arguments are used in specifying both the format of the properties to be displayed and how to display them. The `-len n` argument specifies that at most, *n* bytes of any given property will be read and displayed. This is useful, for example, when displaying the cut buffer on the root window, which could run to several pages if displayed in full.

Normally, each property name is displayed by printing first the property name then its type (if it has one) in parentheses, followed by its value. The `-notype` argument specifies that property types should not be displayed. The `-fs` argument is used to specify a file containing a list of formats for properties, while the `-f` argument is used to specify the format for one property.

The formatting information for a property actually consists of two parts, a format and a dformat. The *format* specifies the actual formatting of the property (that is, is it made up of words, bytes, or longs?, and so on) while the *dformat* specifies how the property should be displayed.

The following paragraphs describe how to construct formats and dformats. However, for the vast majority of users and uses, this should not be necessary as the built-in defaults contain the formats and dformats necessary to display all the standard properties. It should only be necessary to specify formats and dformats if a new property is being dealt with or the user dislikes the standard display format. New users especially are encouraged to skip this part.

A format consists of a 0, 8, 16, or 32 followed by a sequence of one or more format characters. The 0, 8, 16, or 32 specifies how many bits per field there are in the property.

Zero is a special case that means use the field size information associated with the property itself. (This is only needed for special cases like type `INTEGER`, which is actually three different types, depending on the size of the fields of the property.)

A value of 8 means that the property is a sequence of bytes, while a value of 16 means that the property is a sequence of words. The difference between these two lies in the fact that the sequence of words will be byte swapped while the sequence of bytes will not be when read by a machine of the opposite byte order of the machine that originally wrote the property. For more information on how properties are formatted and stored, consult the Xlib manual.

After the size of the fields has been specified, it is necessary to specify the type of each field (is it an integer, a string, an atom, or what?) This is done using one format character per field. If there are more fields in the property than format characters supplied, the last character will be repeated as many times as necessary for the extra fields. The format characters and their meaning are as follows:

a	The field holds an atom number. A field of this type should be of size 32.
b	The field is a Boolean. A 0 means false while anything else means true.
c	The field is an unsigned number, a cardinal.
i	The field is a signed integer.
m	The field is a set of bit flags, 1 meaning on.
s	This field and the next ones—until either a 0 or the end of the property—represent a sequence of bytes. This format character is only usable with a field size of 8 and is most often used to represent a string.
x	The field is a hex number (like c but displayed in hex—most useful for displaying window ids and the like).

An example format is `32ica`, which is the format for a property of three fields of 32 bits each—the first holding a signed integer, the second an unsigned integer, and the third an atom.

The format of a dformat, unlike that of a format, is not so rigid. The only limitations on a dformat is that one may not start with a letter or a dash. This is so that it can be distinguished from a property name or an argument. A dformat is a text string containing special characters instructing that various fields be printed at various points in a manner similar to the formatting string used by `printf`. For example, the dformat is `( $0, $1 \) \n` would render the `POINT 3, -4`, which has a format of `32ii` as `is ( 3, -4 ) \n`.

Any character other than a \$, ?, \, or a (in a dformat prints as itself. To print out a \$, ?, \, or (, precede it with a \. For example, to print out a \$, use \\$. Several special backslash sequences are provided as shortcuts. \n will cause a newline to be displayed, while \t will cause a tab to be displayed. \o, where o is an octal number, will display character number o.

A \$ followed by a number n causes field number n to be displayed. The format of the displayed field depends on the formatting character used to describe it in the corresponding format. In other words, if a cardinal is described by c, it will print in decimal, while if it is described by an x, it is displayed in hex.

If the field is not present in the property (this is possible with some properties), `<field not available>` is displayed instead. `$n+` will display field number `n`, then a comma, then field number `n+1`, then another comma, then ... until the last field defined. If field `n` is not defined, nothing is displayed. This is useful for a property that is a list of values.

A `?` is used to start a conditional expression, a kind of if-then statement. `?exp(text)` will display `text` if and only if `exp` evaluates to non-zero. This is useful for two things. First, it allows fields to be displayed if and only if a flag is set. And second, it allows a value such as a state number to be displayed as a name rather than as just a number. The syntax of `exp` is as follows:

```
exp ::= term | term=exp | !exp
term ::= n j $n j mn
```

The `!` operator is a logical NOT, changing `0` to `1` and any non-zero value to `0`. `=` is an equality operator. Note that internally, all expressions are evaluated as 32-bit numbers, so `-1` is not equal to `65535`. `=` returns `1` if the two values are equal and `0` if not. `n` represents the constant value `n` while `$n` represents the value of field number `n`. `mn` is `1` if flag number `n` in the first field having format character `m` in the corresponding format is `1`; `0` otherwise.

Examples: `?m3(count: $3\n)` displays field 3 with a label of `count` if and only if flag number 3 (count starts at `0!`) is on. `?$2=0(True)?!$2=0(False)` displays the inverted value of field 2 as a Boolean.

In order to display a property, `xprop` needs both a `format` and a `dformat`. Before `xprop` uses its default values of a `format` of `32x` and a `dformat` of `" = { $0+ }\n"`, it searches several places in an attempt to find more specific formats. First, a search is made using the name of the property. If this fails, a search is made using the type of the property. This allows type `STRING` to be defined with one set of formats while allowing property `WM_NAME`, which is of type `STRING` to be defined with a different format. In this way, the display formats for a given type can be overridden for specific properties.

The locations searched are in order: the `format`, if any, specified with the property name (as in `8x WM_NAME`), the formats defined by `-f` options in last to first order, the contents of the file specified by the `-fs` option if any, the contents of the file specified by the environmental variable `XPROPFFORMATS` if any, and finally `xprop`'s built-in file of formats.

The format of the files referred to by the `-fs` argument and the `XPROPFFORMATS` variable is one or more lines of the following form:

```
name format [dformat]
```

Where `name` is either the name of a property or the name of a type, `format` is the format to be used with `name`, and `dformat` is the `dformat` to be used with `name`. If `dformat` is not present, `"=$0+\n"` is assumed.

EXAMPLES

To display the name of the root window: `xprop -root WM_NAME`

To display the window manager hints for the clock: `xprop -name xclock WM_HINTS`

To display the start of the cut buffer: `xprop -root -len 100 CUT_BUFFER0`

To display the point size of the fixed font: `xprop -font fixed POINT_SIZE`

To display all the properties of window # `0x200007`: `xprop -id 0x200007`

ENVIRONMENT

`DISPLAY`

`XPROPFFORMATS`

To get default display.

Specifies the name of a file from which additional formats are to be obtained.

SEE ALSO

`x(1)`, `xwininfo(1)`

AUTHOR

Mark Lillibridge (MIT Project Athena)

X Version 11 Release 6

xrdp

xrdp—X server resource database utility

SYNOPSIS

```
xrdp [-option ...] [filename]
```

DESCRIPTION

xrdp is used to get or set the contents of the `RESOURCE_MANAGER` property on the root window of screen 0, or the `SCREEN_RESOURCES` property on the root window of any or all screens, or everything combined. You would normally run this program from your X startup file.

Most X clients use the `RESOURCE_MANAGER` and `SCREEN_RESOURCES` properties to get user preferences about color, fonts, and so on for applications. Having this information in the server (where it is available to all clients) instead of on disk solves the problem in previous versions of X that required you to maintain defaults files on every machine that you might use. It also allows for dynamic changing of defaults without editing files.

The `RESOURCE_MANAGER` property is used for resources that apply to all screens of the display. The `SCREEN_RESOURCES` property on each screen specifies additional (or overriding) resources to be used for that screen. (When there is only one screen, `SCREEN_RESOURCES` is normally not used; all resources are just placed in the `RESOURCE_MANAGER` property.)

The file specified by `filename` (or the contents from standard input if `-` or no filename is given) is optionally passed through the C preprocessor with the following symbols defined, based on the capabilities of the server being used:

<code>SERVERHOST=hostname</code>	The <code>hostname</code> portion of the display to which you are connected.
<code>SRVR_name</code>	The <code>SERVERHOSThostnamestring</code> turned into a legal identifier. For example, <code>my-dpy.lcs.mit.edu</code> becomes <code>SRVR my dpy lcs mit edu</code> .
<code>HOST=hostname</code>	The same as <code>SERVERHOST</code> .
<code>DISPLAY_NUM=num</code>	The number of the display on the server host.
<code>CLIENTHOST=hostname</code>	The name of the host on which xrdp is running.
<code>CLNT_name</code>	The <code>CLIENTHOST hostname</code> string turned into a legal identifier. For example, <code>"expo.lcs.mit.edu"</code> becomes <code>CLNT expo lcs mit edu</code> .
<code>RELEASE=num</code>	The vendor release number for the server. The interpretation of this number will vary depending on <code>VENDOR</code> .
<code>REVISION=num</code>	The X protocol minor version supported by this server (currently 0).
<code>VERSION=num</code>	The X protocol major version supported by this server (should always be 11).
<code>VENDOR="vendor"</code>	A string literal specifying the vendor of the server.
<code>VNDR_name</code>	The <code>VENDOR</code> name string turned into a legal identifier. For example, <code>"MIT X Consortium"</code> becomes <code>VNDR_MIT_X Consortium</code> .
<code>EXT_name</code>	A symbol is defined for each protocol extension supported by the server. Each extension string name is turned into a legal identifier. For example, <code>"X3D-PEX"</code> becomes <code>EXT_X3D_PEX</code> .

NUM_SCREENS=num
 SCREEN_NUM=num
 BITS_PER_RGB=num

CLASS=visualclass

CLASS_visualclass=visualid

COLOR

CLASS_visualclass_depth=num

HEIGHT=num

WIDTH=num

PLANES=num

X_RESOLUTION=num

Y_RESOLUTION=num

SRVR_name, CLNT_name, VNDR_name, and EXT_name identifiers are formed by changing all characters other than letters and digits into underscores.

Lines that begin with an exclamation mark (!) are ignored and may be used as comments.

Note that since xrdp can read from standard input, it can be used to change the contents of properties directly from a terminal or from a shell script.

OPTIONS

xrdp program accepts the following options:

-help

-display display

-all

The total number of screens.

The number of the current screen (from zero).

The number of significant bits in an RGB color specification. This is the log base 2 of the number of distinct shades of each primary that the hardware can generate. Note that it usually is not related to PLANES.

One of StaticGray, GrayScale, StaticColor, PseudoColor, TrueColor, DirectColor. This is the visual class of the root window.

The visual class of the root window in a form you can #ifdef on. The value is the numeric id of the visual.

Defined only if CLASS is one of StaticColor, PseudoColor, TrueColor, or DirectColor.

A symbol is defined for each visual supported for the screen. The symbol includes the class of the visual and its depth; the value is the numeric id of the visual. (If more than one visual has the same class and depth, the numeric id of the first one reported by the server is used.)

The height of the root window in pixels.

The width of the root window in pixels.

The number of bit planes (the depth) of the root window.

The x resolution of the screen in pixels per meter.

The y resolution of the screen in pixels per meter.

This option (or any unsupported option) will cause a brief description of the allowable options and parameters to be printed.

This option specifies the X server to be used; see x(1). It also specifies the screen to use for the -screen option, and it specifies the screen from which preprocessor symbols are derived for the -global option.

This option indicates that operation should be performed on the screen-independent resource property (RESOURCE_MANAGER), as well as the screen-specific property (SCREEN_RESOURCES) on every screen of the display. For example, when used in conjunction with -query, the contents of all properties are output. For -load, -override, and -merge, the input file is processed once for each screen. The resources that occur in common in the output for every screen are collected, and these are applied as the screen-independent resources. The remaining resources are applied for each individual per-screen property. This the default mode of operation.

<code>-global</code>	This option indicates that the operation should only be performed on the screen-independent <code>RESOURCE_MANAGER</code> property.
<code>-screen</code>	This option indicates that the operation should only be performed on the <code>SCREEN_RESOURCES</code> property of the default screen of the display.
<code>-screens</code>	This option indicates that the operation should be performed on the <code>SCREEN_RESOURCES</code> property of each screen of the display. For <code>-load</code> , <code>-override</code> , and <code>-merge</code> , the input file is processed for each screen.
<code>-n</code>	This option indicates that changes to the specified properties (when used with <code>-load</code> , <code>-override</code> , or <code>-merge</code>) or to the resource file (when used with <code>-edit</code>) should be shown on the standard output, but should not be performed.
<code>-quiet</code>	This option indicates that warning about duplicate entries should not be displayed.
<code>-cpp filename</code>	This option specifies the pathname of the C preprocessor program to be used. Although <code>xrdp</code> was designed to use CPP, any program that acts as a filter and accepts the <code>-D</code> , <code>-I</code> , and <code>-U</code> options may be used.
<code>-nocpp</code>	This option indicates that <code>xrdp</code> should not run the input file through a preprocessor before loading it into properties.
<code>-symbols</code>	This option indicates that the symbols that are defined for the preprocessor should be printed onto the standard output.
<code>-query</code>	This option indicates that the current contents of the specified properties should be printed onto the standard output. Note that since preprocessor commands in the input resource file are part of the input file, not part of the property, they won't appear in the output from this option. The <code>-edit</code> option can be used to merge the contents of properties back into the input resource file without damaging preprocessor commands.
<code>-load</code>	This option indicates that the input should be loaded as the new value of the specified properties, replacing whatever was there; that is, the old contents are removed. This is the default action.
<code>-override</code>	This option indicates that the input should be added to, instead of replacing, the current contents of the specified properties. New entries override previous entries.
<code>-merge</code>	This option indicates that the input should be merged and lexicographically sorted with, instead of replacing, the current contents of the specified properties.
<code>-remove</code>	This option indicates that the specified properties should be removed from the server.
<code>-retain</code>	This option indicates that the server should be instructed not to reset if <code>xrdp</code> is the first client. This should never be necessary under normal conditions, since <code>xdm</code> and <code>xinit</code> always act as the first client.
<code>-edit filename</code>	This option indicates that the contents of the specified properties should be edited into the given file, replacing any values already listed there. This allows you to put changes that you have made to your defaults back into your resource file, preserving any comments or preprocessor lines.

`-backup string`

This option specifies a suffix to be appended to the filename used with `-edit` to generate a backup file.

`-Dname[=value]`

This option is passed through to the preprocessor and is used to define symbols for use with conditionals such as `#ifdef`.

`-Uname`

This option is passed through to the preprocessor and is used to remove any definitions of this symbol.

`-Idirectory`

This option is passed through to the preprocessor and is used to specify a directory to search for files that are referenced with `#include`.

FILES

Generalizes `~/.Xdefaults` files

SEE ALSO

`x(1)`, Xlib Resource Manager documentation, `xt` resource documentation

ENVIRONMENT

`DISPLAY`

To figure out which display to use.

BUGS

The default for no arguments should be to query, not to overwrite, so that it is consistent with other programs.

AUTHORS

Bob Scheifler and Phil Karlton, rewritten from the original by Jim Gettys

X Version 11 Release 6

xrefresh

`xrefresh`—Refresh all or part of an X screen

SYNOPSIS

`xrefresh [-option ...]`

DESCRIPTION

`xrefresh` is a simple X program that causes all or part of your screen to be repainted. This is useful when system messages have messed up your screen. `xrefresh` maps a window on top of the desired area of the screen and then immediately unmaps it, causing refresh events to be sent to all applications. By default, a window with no background is used, causing all applications to repaint smoothly. However, the various options can be used to indicate that a solid background (of any color) or the root window background should be used instead.

ARGUMENTS

`-white`

Use a white background. The screen just appears to flash quickly, and then repaint.

`-black`

Use a black background (in effect, turning off all of the electron guns to the tube). This can be somewhat disorienting as everything goes black for a moment.

`-solid color`

Use a solid background of the specified color. Try green.

`-root`

Use the root window background.

-none
 -geometry WxH+X+Y
 -display display

This is the default. All of the windows simply repaint.
 Specifies the portion of the screen to be repainted; see `x(1)`.
 This argument allows you to specify the server and screen to refresh; see `x(1)`.

X DEFAULTS

The `xrefresh` program uses the routine `xGetDefault(3X)` to read defaults, so its resource names are all capitalized.

Black, White, Solid, None, Root
 Geometry

Determines what sort of window background to use
 Determines the area to refresh. Not very useful.

ENVIRONMENT

DISPLAY

To get default host and display number.

SEE ALSO

`x(1)`

BUGS

It should have just one default type for the background.

AUTHORS

Jim Gettys (Digital Equipment Corporation, MIT Project Athena)

X Version 11 Release 6

Xserver

xserver—X Window System display server

SYNOPSIS

`X [option ...]`

DESCRIPTION

`x` is the generic name for the X Window System display server. It is frequently a link or a copy of the appropriate server binary for driving the most frequently used server on a given machine.

STARTING THE SERVER

The `x` server is usually started from the X Display Manager program `xdm(1)`. This utility is run from the system boot files and takes care of keeping the server running, prompting for usernames and passwords, and starting up the user sessions.

Installations that run more than one window system may need to use the `xinit(1)` utility instead of `xdm`. However, `xinit` is to be considered a tool for building startup scripts and is not intended for use by end users. Site administrators are strongly urged to use `xdm`, or build other interfaces for novice users.

The `x` server may also be started directly by the user, though this method is usually reserved for testing and is not recommended for normal operation. On some platforms, the user must have special permission to start the `x` server, often because access to certain devices. (For example, `/dev/mouse` is restricted.)

When the `x` server starts up, it typically takes over the display. If you are running on a workstation whose console is the display, you may not be able to log into the console while the server is running.

OPTIONS

All of the `x` servers accept the following command-line options:

<code>:displaynumber</code>	The <code>x</code> server runs as the given <code>displaynumber</code> , which by default is 0. If multiple <code>x</code> servers are to run simultaneously on a host, each must have a unique display number. See the “Display Names” subsection of the <code>x(1)</code> manual page to learn how to specify which display number clients should try to use.
<code>-a number</code>	Sets pointer acceleration (that is, the ratio of how much is reported to how much the user actually moved the pointer).
<code>-ac</code>	Disables host-based access control mechanisms. Enables access by any host, and permits any host to modify the access control list. Use with extreme caution. This option exists primarily for running test suites remotely.
<code>-audit level</code>	Sets the audit trail level. The default level is 1, meaning only connection rejections are reported. Level 2 additionally reports all successful connections and disconnects. Level 0 turns off the audit trail. Audit lines are sent as standard error output.
<code>-auth authorization-file</code>	Specifies a file which contains a collection of authorization records used to authenticate access. See also the <code>xdm</code> and <code>xsecurity</code> manual pages.
<code>bc</code>	Disables certain kinds of error checking, for bug compatibility with previous releases (for example, to work around bugs in R2 and R3 <code>xterms</code> and toolkits). Deprecated.
<code>-bs</code>	Disables backing store support on all screens.
<code>-c</code>	Turns off key-click.
<code>c volume</code>	Sets key-click volume (allowable range: 0–100).
<code>-cc class</code>	Sets the visual class for the root window of color screens. The class numbers are as specified in the <code>x</code> protocol. Not obeyed by all servers.
<code>-co filename</code>	Sets name of RGB color database. The default is <code><XRoot>/lib/X11/rgb</code> , where <code><Xroot></code> refers to the root of the X11 install tree.
<code>-config filename</code>	Reads more options from the given file. Options in the file may be separated by newlines if desired. If a <code>#</code> character appears on a line, all characters between it and the next newline are ignored, providing a simple commenting facility. The <code>-config</code> option itself may appear in the file.
<code>-core</code>	Causes the server to generate a core dump on fatal errors.
<code>-dpi resolution</code>	Sets the resolution of the screen, in dots per inch. To be used when the server cannot determine the screen size from the hardware.
<code>-deferglyphs whichfonts</code>	Specifies the types of fonts for which the server should attempt to use deferred glyph loading. <code>whichfonts</code> can be <code>a11</code> (all fonts), <code>none</code> (no fonts), or <code>16</code> (16-bit fonts only).
<code>-f volume</code>	Sets beep (bell) volume (allowable range: 0–100).
<code>-fc cursorFont</code>	Sets default cursor font.
<code>-fn font</code>	Sets the default font.

<code>-fp fontPath</code>	Sets the search path for fonts. This path is a comma-separated list of directories that the X server searches for font databases. <code>-help</code> prints a usage message.
<code>-I</code>	Causes all remaining command-line arguments to be ignored.
<code>-kb</code>	Disables the <code>XKEYBOARD</code> extension if present.
<code>-p minutes</code>	Sets screen saver pattern cycle time in minutes.
<code>-pn</code>	Permits the server to continue running if it fails to establish all of its well-known sockets (connection points for clients), but establishes at least one.
<code>-r</code>	Turns off auto-repeat.
<code>r</code>	Turns on auto-repeat.
<code>-s minutes</code>	Sets screen saver time-out time in minutes.
<code>-su</code>	Disables save under support on all screens.
<code>-t number</code>	Sets pointer acceleration threshold in pixels (that is, sets after how many pixels pointer acceleration should take effect).
<code>-terminate</code>	Causes the server to terminate at server reset, instead of continuing to run.
<code>-to seconds</code>	Sets default connection time-out in seconds.
<code>-tst</code>	Disables all testing extensions (for example, <code>XTEST</code> , <code>XTrap</code> , <code>XTestExtension1</code>).
<code>ttyxx</code>	Ignored, for servers started the ancient way (from <code>init</code>).
<code>v</code>	Sets video-off screen saver preference.
<code>-v</code>	Sets video-on screen saver preference.
<code>-wm</code>	Forces the default backing-store of all windows to be <code>When-Mapped</code> . This is a backdoor way of getting backing-store to apply to all windows. Although all mapped windows will have backing-store, the backing-store attribute value reported by the server for a window will be the last value established by a client. If it has never been set by a client, the server will report the default value, <code>NotUseful</code> . This behavior is required by the <code>x</code> protocol, which allows the server to exceed the client's backing-store expectations but does not provide a way to tell the client that it is doing so.
<code>-x extension</code>	Loads the specified extension at <code>init</code> . This is a no-op for most implementations.

SERVER DEPENDENT OPTIONS

Some x servers accept the following options:

<code>-ld kilobytes</code>	Sets the data space limit of the server to the specified number of kilobytes. A value of zero makes the data size as large as possible. The default value of <code>-1</code> leaves the data space limit unchanged.
<code>-lf files</code>	Sets the number-of-open-files limit of the server to the specified number. A value of zero makes the limit as large as possible. The default value of <code>-1</code> leaves the limit unchanged.
<code>-ls kilobytes</code>	Sets the stack space limit of the server to the specified number of kilobytes. A value of zero makes the stack size as large as possible. The default value of <code>-1</code> leaves the stack space limit unchanged.

<code>-logo</code>	Turns on the X Window System logo display in the screen saver. There is currently no way to change this from a client.
<code>nologo</code>	Turns off the X Window System logo display in the screen saver. There is currently no way to change this from a client.

XDMCP OPTIONS

x servers that support XDMCP have the following options. (See the *X Display Manager Control Protocol* specification for more information.)

<code>-query host-name</code>	Enable XDMCP and send <code>Query</code> packets to the specified host.
<code>-broadcast</code>	Enable XDMCP and broadcast <code>BroadcastQuery</code> packets to the network. The first responding display manager will be chosen for the session.
<code>-indirect host-name</code>	Enable XDMCP and send <code>IndirectQuery</code> packets to the specified host.
<code>-port port-num</code>	Use an alternate port number for XDMCP packets. Must be specified before any <code>-query</code> , <code>-broadcast</code> , or <code>-indirect</code> options.
<code>-class display-class</code>	XDMCP has an additional display qualifier used in resource lookup for display-specific options. This option sets that value; by default it is <code>MIT-Unspecified</code> (not a very useful value).
<code>-cookie xdm-auth-bits</code>	When testing <code>XDM-AUTHENTICATION-1</code> , a private key is shared between the server and the manager. This option sets the value of that private data (not that it is very private, being on the command line!).
<code>-displayID display-id</code>	Yet another XDMCP-specific value, this one allows the display manager to identify each display so that it can locate the shared key.

XKEYBOARD OPTIONS

x servers that support the XKEYBOARD extension accept the following options:

<code>-xkbdir directory</code>	Base directory for keyboard layout files
<code>-xkbmap filename</code>	Keyboard description to load on startup
<code>[+-]accessx</code>	Enable(+) or disable(-) AccessX key sequences
<code>-ar1 milliseconds</code>	Sets the length of time in milliseconds that a key must be depressed before auto-repeat starts
<code>-ar2 milliseconds</code>	Sets the length of time in milliseconds that should elapse between auto-repeat-generated keystrokes

Many servers also have device-specific command-line options. See the manual pages for the individual servers for more details.

NETWORK CONNECTIONS

The x server supports client connections via a platform-dependent subset of the following transport types: TCP/IP, UNIX Domain sockets, DECnet, and several varieties of SVR4 local connections. See the “Display Names” subsection of the `x(1)` manual page to learn how to specify which transport type clients should try to use.

SECURITY

The x server implements a platform-dependent subset of the following authorization protocols: `-MIT-MAGICCOOKIE-1`, `XDM-AUTHORIZATION-1`, `SUN-DES-1`, and `MIT-KERBEROS-5`. See the `xsecurity(1)` manual page for information on the operation of these protocols.

Authorization data required by the preceding protocols is passed to the server in a private file named with the `-auth` command-line option. Each time the server is about to accept the first connection after a reset (or when the server is starting), it reads this file. If this file contains any authorization records, the local host is not automatically allowed access to the server, and only clients that send one of the authorization records contained in the file in the connection setup information will be allowed access. See the `xau` manual page for a description of the binary format of this file. See `xauth(1)` for maintenance of this file, and distribution of its contents to remote hosts.

The x server also uses a host-based access control list for deciding whether or not to accept connections from clients on a particular machine. If no other authorization mechanism is being used, this list initially consists of the host on which the server is running as well as any machines listed in the file `/etc/Xn.hosts`, where `n` is the display number of the server. Each line of the file should contain either an Internet hostname (for example `expo.lcs.mit.edu`) or a DECnet hostname in double colon format (for example, `hydra::`). There should be no leading or trailing spaces on any lines. For example,

```
joesworkstation
corporate.company.com
star::
bigcpu::
```

Users can add or remove hosts from this list and enable or disable access control using the `xhost` command from the same machine as the server.

The x protocol intrinsically does not have any notion of window operation permissions or place any restrictions on what a client can do; if a program can connect to a display, it has full run of the screen. Sites that have better authentication and authorization systems might wish to make use of the hooks in the libraries and the server to provide additional security models.

SIGNALS

The x server attaches special meaning to the following signals:

SIGHUP

This signal causes the server to close all existing connections, free all resources, and restore all defaults. It is sent by the display manager whenever the main user's main application (usually an `xterm` or window manager) exits to force the server to clean up and prepare for the next user.

SIGTERM

This signal causes the server to exit cleanly.

SIGUSR1

This signal is used quite differently from either of the above. When the server starts, it checks to see if it has inherited `SIGUSR1` as `SIG_IGN` instead of the usual `SIG_DFL`. In this case, the server sends a `SIGUSR1` to its parent process after it has set up the various connection schemes. `xdm` uses this feature to recognize when connecting to the server is possible.

FONTS

The x server can obtain fonts from directories or from font servers. The list of directories and font servers the x server uses when trying to open a font is controlled by the font path.

The default font path is

```
<XRoot>/lib/X11/fonts/misc/,
<XRoot>/lib/X11/fonts/Speedo/,
<XRoot>/lib/X11/fonts/Type1/,
<XRoot>/lib/X11/fonts/75dpi/,
<XRoot>/lib/X11/fonts/100dpi/
```

where `<XRoot>` refers to the root of the X11 install tree.

The font path can be set with the `-fp` option or by `xset(1)` after the server has started.

FILES

```

/etc/Xn.hosts
<XRoot>/lib/X11/fonts/misc
<XRoot>/lib/X11/fonts/75dpi
<XRoot>/lib/X11/fonts/100dpi
<XRoot>/lib/X11/fonts/Speedo
<XRoot>/lib/X11/fonts/Type1
<XRoot>/lib/X11/fonts/PEX
<XRoot>/lib/X11/rgb.txt
/tmp/.X11-unix/Xn
/tmp/rcXn
/usr/adm/Xmsgs
<XRoot>/lib/X11/xdm/xdm-errors

```

Initial access control list for display number *n*

Bitmap font directories

Outline font directories

PEX font directories

Color database

UNIX domain socket for display number *n*

Kerberos 5 replay cache for display number *n*

Error log file for display number *n* if run from `init(8)`

Default error log file if the server is run from `xdm(1)`

Note: <XRoot> refers to the root of the X11 install tree.

SEE ALSO

General information: `x(1)`

Protocols: X Window System Protocol, The X Font Service Protocol, X Display Manager Control Protocol

Fonts: `bdftopcf(1)`, `mkfontdir(1)`, `xfs(1)`, `xlsfonts(1)`, `xfontsel(1)`, `xfd(1)`, X Logical Font Description Conventions

Security: `xsecurity(1)`, `xauth(1)`, `xau(1)`, `xdm(1)`, `xhost(1)`

Starting the server: `xdm(1)`, `xinit(1)`

Controlling the server once started: `xset(1)`, `xsetroot(1)`, `xhost(1)`

Server-specific man pages: `xdec(1)`, `XmacII(1)`, `Xsun(1)`, `Xnest(1)`, `Xvfb(1)`, `XF86 Accel(1)`, `XF86 Mono(1)`, `XF86 SVGA(1)`, `XF86 VGA16(1)`, `XFree86(1)`

Server internal documentation: “Definition of the Porting Layer for the X v11 Sample Server,” “Strategies for Porting the X v11 Sample Server,” “Godzilla’s Guide to Porting the X v11 Sample Server”

AUTHORS

The sample server was originally written by Susan Angebrannt, Raymond Drewry, Philip Karlton, and Todd Newman, from Digital Equipment Corporation, with support from a large cast. It has since been extensively rewritten by Keith Packard and Bob Scheifler, from MIT.

X Version 11 Release 6

xset

`xset`—User preference utility for X

SYNOPSIS

```

xset [-display display] [-b] [b on/off] [b [volume [pitch [duration]]] [[-]bc]
[-c] [c on/off] [c [volume]] [[-+]fp[+]=] path[,path[,...]] [fp default]
[fp rehash] [[-]led [integer]] [led on/off] [m[mouse] [accel_mult[/accel_div]
[threshold]]] [m[mouse] default] [p pixel color] [[-]r [keycode]] [r on/off]
[s [length [period]]] [s blank/noblock] [s expose/noexpose] [s on/off]
[s default] [s activate] [s reset] [q]

```

DESCRIPTION

This program is used to set various user preference options of the display.

OPTIONS

`-display display`

`b`

This option specifies the server to use; see `x(1)`.

The `b` option controls bell volume, pitch, and duration. This option accepts up to three numerical parameters, a preceding dash (`-`), or an `on/off` flag. If no parameters are given, or the `on` flag is used, the system defaults will be used. If the dash or `off` is given, the bell will be turned off. If only one numerical parameter is given, the bell volume will be set to that value, as a percentage of its maximum. Likewise, the second numerical parameter specifies the bell pitch, in hertz, and the third numerical parameter specifies the duration in milliseconds. Note that not all hardware can vary the bell characteristics. The `x` server will set the characteristics of the bell as closely as it can to the user's specifications.

`bc`

The `bc` option controls bug compatibility mode in the server, if possible; a preceding dash (`-`) disables the mode; otherwise, the mode is enabled. Various pre-R4 clients pass illegal values in some protocol requests, and pre-R4 servers did not correctly generate errors in these cases. Such clients, when run against an R4 server, will terminate abnormally or otherwise fail to operate correctly. Bug compatibility mode explicitly reintroduces certain bugs into the `x` server, so that many such clients can still be run. This mode should be used with care; new application development should be done with this mode disabled. The server must support the MIT-SUNDRY-NONSTANDARD protocol extension in order for this option to work.

`c`

The `c` option controls key click. This option can take an optional value, a preceding dash (`-`), or an `on/off` flag. If no parameter or the `on` flag is given, the system defaults will be used. If the dash or `off` flag is used, key click will be disabled. If a value from 0 to 100 is given, it is used to indicate volume, as a percentage of the maximum. The `x` server will set the volume to the nearest value that the hardware can support.

`fp= path,...`

The `fp=` sets the font path to the entries given in the `path` argument. The entries are interpreted by the server, not by the client. Typically, they are directory names or font server names, but the interpretation is server-dependent.

`fp default`

The `default` argument causes the font path to be reset to the server's default.

`fp rehash`

The `rehash` argument resets the font path to its current value, causing the server to reread the font databases in the current font path. This is generally only used when adding new fonts to a font directory (after running `mkfontdir` to re-create the font database).

`-fp` or `fp-`

The `-fp` and `fp-` options remove elements from the current font path. They must be followed by a comma-separated list of entries.

`fp` or `fp`

This `fp` and `fp` options prepend and append elements to the current font path, respectively. They must be followed by a comma-separated list of entries.

`led`

The `led` option controls the keyboard LEDs. This controls the turning on or off of one or all of the LEDs. It accepts an optional integer, a preceding dash (-) or an `on/off` flag. If no parameter or the `on` flag is given, all LEDs are turned on. If a preceding dash or the flag `off` is given, all LEDs are turned off. If a value between 1 and 32 is given, that LED will be turned on or off depending on the existence of a preceding dash. A common LED that can be controlled is the Caps Lock LED. `xset led 3` would turn led #3 on. `xset -led 3` would turn it off. The particular LED values may refer to different LEDs on different hardware.

`m`

The `m` option controls the mouse parameters. The parameters for the mouse are `acceleration` and `threshold`. The acceleration can be specified as an integer, or as a simple fraction. The mouse, or whatever pointer the machine is connected to, will go acceleration times as fast when it travels more than threshold pixels in a short time. This way, the mouse can be used for precise alignment when it is moved slowly, yet it can be set to travel across the screen in a flick of the wrist when desired. One or both parameters for the `m` option can be omitted, but if only one is given, it will be interpreted as the acceleration. If no parameters or the flag `default` is used, the system defaults will be set.

`p`

The `p` option controls pixel color values. The parameters are the color map entry number in decimal, and a color specification. The root background colors may be changed on some servers by altering the entries for `BlackPixel` and `WhitePixel`. Although these are often 0 and 1, they need not be. Also, a server may choose to allocate those colors privately, in which case an error will be generated. The map entry must not be a read-only color, or an error will result.

`r`

The `r` option controls the auto-repeat. If a preceding dash or the `off` flag is used, auto-repeat will be disabled. If no parameters or the `on` flag is used, auto-repeat will be enabled. If a specific keycode is specified as a parameter, auto-repeat for that keycode is enabled or disabled.

`s`

The `s` option lets you set the screen saver parameters. This option accepts up to two numerical parameters, a `blank/noblank` flag, an `expose/noexpose` flag, an `on/off` flag, an `activate/reset` flag, or the `default` flag. If no parameters or the `default` flag is used, the system will be set to its default screen saver characteristics. The `on/off` flags simply turn the screen saver functions on or off. The `activate` flag forces activation of screen saver even if the screen saver had been turned off. The `reset` flag forces deactivation of screen saver if it is active. The `blank` flag sets the preference to blank the video (if the hardware can do so) rather than display a background pattern, while `noblank` sets the preference to display a pattern rather than blank the video. The `expose` flag sets the preference to allow window exposures (the server can

freely discard window contents), while `noexpose` sets the preference to disable screen saver unless the server can regenerate the screens without causing exposure events. The `length` and `period` parameters for the screen saver function determines how long the server must be inactive for screen saving to activate, and the `period` to change the background pattern to avoid burn in. The arguments are specified in seconds. If only one numerical parameter is given, it will be used for the `length`.

q

The `q` option gives you information on the current settings.

These settings will be reset to default values when you log out.

Note that not all x implementations are guaranteed to honor all of these options.

SEE ALSO

`x(1)`, `Xserver(1)`, `xmodmap(1)`, `xrdb(1)`, `xsetroot(1)`

AUTHOR

Bob Scheifler (MIT Laboratory for Computer Science), David Krikorian (MIT Project Athena; X11 version)

X Version 11 Release 6

xsetroot

xsetroot—Root window parameter setting utility for x

SYNOPSIS

```
xsetroot [-help] [-def] [-display display] [-cursor cursorfile maskfile]
[-cursor_name cursorname] [-bitmap filename] [-mod x y] [-gray] [-grey]
[-fg color] [-bg color] [-rv] [-solid color] [-name string]
```

DESCRIPTION

The `xsetroot` program allows you to tailor the appearance of the background (root) window on a workstation display running x. Normally, you experiment with `xsetroot` until you find a personalized look that you like, then put the `xsetroot` command that produces it into your x startup file. If no options are specified, or if `-def` is specified, the window is reset to its default state. The `-def` option can be specified along with other options and only the nonspecified characteristics will be reset to the default state.

Only one of the background color/tiling changing options (`-solid`, `-gray`, `-grey`, `-bitmap`, and `-mod`) may be specified at a time.

OPTIONS

The various options are as follows:

`-help`

Print a usage message and exit.

`-def`

Reset unspecified attributes to the default values. (Restores the background to the familiar gray mesh and the cursor to the hollow x shape.)

`-cursor cursorfile maskfile`

This lets you change the pointer cursor to whatever you want when the pointer cursor is outside of any window. Cursor and mask files are bitmaps (little pictures), and can be made with the `bitmap(1)` program. You probably want the mask file to be all black until you get used to the way masks work.

`-cursor_name cursorname`

This lets you change the pointer cursor to one of the standard cursors from the cursor font. Refer to Appendix B of the *x* protocol for the names (except that the *xc* prefix is elided for this option).

`-bitmap filename`

Use the bitmap specified in the file to set the window pattern. You can make your own bitmap files (little pictures) using the `bitmap(1)` program. The entire background will be made up of repeated “tiles” of the bitmap.

`-mod x y`

This is used if you want a plaid-like grid pattern on your screen. *x* and *y* are integers ranging from 1 to 16. Try the different combinations. Zero and negative numbers are taken as 1.

`-gray`

Make the entire background gray. (Easier on the eyes.)

`-grey`

Make the entire background grey.

`-fg color`

Use *color* as the foreground color. Foreground and background colors are meaningful only in combination with `-cursor`, `-bitmap`, or `-mod`.

`-bg color`

Use *color* as the background color.

`-rv`

This exchanges the foreground and background colors. Normally the foreground color is black and the background color is white.

`-solid color`

This sets the background of the root window to the specified color. This option is only useful on color servers.

`-name string`

Set the name of the root window to *string*. There is no default value. Usually a name is assigned to a window so that the window manager can use a text representation when the window is iconified. This option is unused because you can't iconify the background.

`-display display`

Specifies the server to connect to; see `x(1)`.

SEE ALSO

`x(1)`, `xset(1)`, `xrdb(1)`

AUTHOR

Mark Lillibridge (MIT Project Athena)

X Version 11 Release 6

Xsm

xsm—X Session Manager

SYNOPSIS

`xsm [-display display] [-session sessionName] [-verbose]`

DESCRIPTION

xsm is a session manager. A session is a group of applications, each of which has a particular state. *xsm* allows you to create arbitrary sessions. For example, you might have a light session, a development session, or an *xterminal* session. Each session can have its own set of applications. Within a session, you can perform a checkpoint to save application state, or a shutdown to save state and exit the session. When you log back in to the system, you can load a specific session, and you can delete sessions you no longer want to keep.

Some session managers simply allow you to manually specify a list of applications to be started in a session. `xsm` is more powerful because it lets you run applications and have them automatically become part of the session. On a simple level, `xsm` is useful because it gives you this ability to easily define which applications are in a session. The true power of `xsm`, however, can be taken advantage of when more and more applications learn to save and restore their state.

OPTIONS

<code>-display display</code>	Causes <code>xsm</code> to connect to the specified X display.
<code>-session sessionName</code>	Causes <code>xsm</code> to load the specified session, bypassing the session menu.
<code>-verbose</code>	Turns on debugging information.

SETUP

.xsession FILE

Using `xsm` requires a change to your `.xsession` file:

The last program executed by your `.xsession` file should be `xsm`. With this configuration, when the user chooses to shut down the session using `xsm`, the session will truly be over.

Because the goal of the session manager is to restart clients when logging into a session, your `.xsession` file, in general, should not directly start up applications. Rather, the applications should be started within a session. When `xsm` shuts down the session, `xsm` will know to restart these applications. Note, however, that there are some types of applications that are not “session aware”. `xsm` enables you to manually add these applications to your session. (See the subsection titled “Client List.”)

SM_SAVE_DIR ENVIRONMENT VARIABLE

If the `SM_SAVE_DIR` environment variable is defined, `xsm` will save all configuration files in this directory. Otherwise, they will be stored in the user’s home directory. Session-aware applications are also encouraged to save their checkpoint files in the `SM_SAVE_DIR` directory, although the user should not depend on this convention.

DEFAULT STARTUP APPLICATIONS

The first time `xsm` is started, it will need to locate a list of applications to start up. For example, this list might include a window manager, a session management proxy, and an `xterm`. `xsm` will first look for the file `.xsmstartup` in the user’s home directory. If that file does not exist, it will look for the `system.xsm` file that was set up at installation time. Note that `xsm` provides a `failsafe` option when the user chooses a session to start up. The `failsafe` option simply loads the default applications described above.

Each line in the startup file should contain a command to start an application. A sample startup file might look this:

```
<start of file>
twm
smproxy
xterm
<end of file>
```

STARTING A SESSION

When `xsm` starts up, it first checks to see if the user previously saved any sessions. If no saved sessions exist, `xsm` starts up a set of default applications (as described above in the subsection titled “Default Startup Applications”). If at least one session exists, a Session menu is presented. The `[-session sessionName]` option forces the specified session to be loaded, bypassing the session menu.

THE SESSION MENU

The Session menu presents the user with a list of sessions to choose from. The user can change the currently selected session with the mouse, or by using the up and down arrows on the keyboard. Note that sessions that are locked (that is, running on a different display) cannot be loaded or deleted.

The following operations can be performed from the Session menu:

Load Session	Pressing this button will load the currently selected session. Alternatively, hitting the Return key will also load the currently selected session, or the user can double-click a session from the list.
Delete Session	This operation will delete the currently selected session, along with all of the application checkpoint files associated with the session. After pressing this button, the user will be asked to press the button a second time in order to confirm the operation.
Default/Fail Safe	xsm will start up a set of default applications (as described earlier in the section titled “Default Startup Applications”). This is useful when the user wants to start a fresh session, or if the session configuration files were corrupted and the user wants a failsafe session.
Cancel	Pressing this button will cause xsm to exit. It can also be used to cancel a Delete Session operation.

CONTROLLING A SESSION

After xsm determines which session to load, it brings up its main window, then starts up all applications that are part of the session. The title bar for the session manager’s main window will contain the name of the session that was loaded.

The following options are available from xsm’s main window:

Client List	Pressing this button brings up a window containing a list of all clients that are in the current session. For each client, the host machine that the client is running on is presented. As clients are added and removed from the session, this list is updated to reflect the changes. The user is able to control how these clients are restarted. By pressing the View Properties button, the user can view the session management properties associated with the currently selected client. By pressing the Clone button, the user can start a copy of the selected application. By pressing the Kill Client button, the user can remove a client from the session. By selecting a restart hint from the Restart Hint menu, the user can control the restarting of a client. The following hints are available: ■ The Restart If Running hint indicates that the client should be restarted in the next session if it is connected to the session manager at the end of the current session. ■ The Restart Anyway hint indicates that the client should be restarted in the next session even if it exits before the current session is terminated. ■ The Restart Immediately hint is similar to the Restart Anyway hint, but in addition, the client is meant to run continuously. If the client exits, the session manager will try to restart it in the current session. ■ The Restart Never hint indicates that the client should not be restarted in the next session.

Session Log...

Checkpoint

Note that all X applications may not be session aware. Applications that are not session aware are ones that do not support the X Session Management Protocol or they cannot be detected by the Session Management Proxy. (See the subsection titled “The Proxy.”). *xsm* allows the user to manually add such applications to the session. The bottom of the Client List window contains a text entry field into which application commands can be typed. Each command should go on its own line. This information will be saved with the session at checkpoint or shutdown time. When the session is restarted, *xsm* will restart these applications in addition to the regular session aware applications. Pressing the Done button removes the Client List window.

The Session Log window presents useful information about the session. For example, when a session is restarted, all of the restart commands will be displayed in the log window.

By performing a checkpoint, all applications that are in the session are asked to save their state. Not every application will save its complete state, but at a minimum, the session manager is guaranteed that it will receive the command required to restart the application (along with all command-line options). A window manager participating in the session should guarantee that the applications will come back up with the same window configurations.

If the session being checkpointed was never assigned a name, the user will be required to specify a session name. Otherwise, the user can perform the checkpoint using the current session name, or a new session name can be specified. If the session name specified already exists, the user will be given the opportunity to specify a different name or to overwrite the already existing session. Note that a session that is locked can not be overwritten.

When performing a checkpoint, the user must specify a *Save Type* that informs the applications in the session how much state they should save.

The *Local* type indicates that the application should save enough information to restore the state as seen by the user. It should not affect the state as seen by other users. For example, an editor would create a temporary file containing the contents of its editing buffer, the location of the cursor, and so on.

The *Global* type indicates that the application should commit all of its data to permanent, globally accessible storage. For example, the editor would simply save the edited file.

The *Both* type indicates that the application should do both of these. For example, the editor would save the edited file, then create a temporary file with information such as the location of the cursor, and so on.

In addition to the *Save Type*, the user must specify an *Interact Style*.

The *None* type indicates that the application should not interact with the user while saving state.

Shutdown

The `Errors` type indicates that the application may interact with the user only if an error condition arises.

The `Any` type indicates that the application may interact with the user for any purpose. Note that `xsm` will only allow one application to interact with the user at a time.

After the checkpoint is completed, `xsm` will, if necessary, display a window containing the list of applications that did not report a successful save of state.

A shutdown provides all of the options found in a checkpoint, but, in addition, can cause the session to exit. Note that if the interaction style is `Errors` or `Any`, the user may cancel the shutdown. The user may also cancel the shutdown if any of the applications report an unsuccessful save of state. The user may choose to shut down the session with or without performing a checkpoint.

THE PROXY

Because not all applications have been ported to support the X Session Management Protocol, a proxy service exists to enable “old” clients to work with the session manager. In order for the proxy to detect an application joining a session, one of the following must be true:

- The application maps a top-level window containing the `WM_CLIENT_LEADER` property. This property provides a pointer to the client leader window that contains the `WM_CLASS`, `WM_NAME`, `WM_COMMAND`, and `WM_CLIENT_MACHINE` properties.
- or
- The application maps a top-level window that does not contain the `WM_CLIENT_LEADER` property. However, this top-level window contains the `WM_CLASS`, `WM_NAME`, `WM_COMMAND`, and `WM_CLIENT_MACHINE` properties.

An application that supports the `WM_SAVE_YOURSELF` protocol will receive a `WM_SAVE_YOURSELF` client message each time the session manager issues a checkpoint or shutdown. This allows the application to save state. If an application does not support the `WM_SAVE_YOURSELF` protocol, then the proxy will provide enough information to the session manager to restart the application (using `WM_COMMAND`), but no state will be restored.

REMOTE APPLICATIONS

`xsm` requires a remote execution protocol in order to restart applications on remote machines. Currently, `xsm` supports the `rstart` protocol. In order to restart an application on remote machine `X`, machine `X` must have `rstart` installed. In the future, additional remote execution protocols may be supported.

SEE ALSO

`smproxy(1)`, `rstart(1)`

AUTHORS

Ralph Mor (X Consortium), Jordan Brown (Quarterdeck Office Systems)

X Version 11 Release 6

xsmclient

`xsmclient`—X session manager tester

SYNOPSIS

`xsmclient` [`TBD`]

DESCRIPTION

The `xsmclient` program is used to test the session manager

AUTHOR

Ralph Mor (X Consortium)

X Version 11 Release 6

xstdcmap

xstdcmap—X standard colormap utility

SYNOPSIS

```
xstdcmap [-all] [-best] [-blue] [-default] [-delete map] [-display display]
          [-gray] [-green] [-help] [-red] [-verbose]
```

DESCRIPTION

The `xstdcmap` utility can be used to selectively define standard colormap properties. It is intended to be run from a user's X startup script to create standard colormap definitions in order to facilitate sharing of scarce colormap resources among clients. Where at all possible, colormaps are created with read-only allocations.

OPTIONS

The following options may be used with `xstdcmap`:

`-all`

This option indicates that all six standard colormap properties should be defined on each screen of the display. Not all screens will support visuals under which all six standard colormap properties are meaningful. `xst-dcmap` will determine the best allocations and visuals for the colormap properties of a screen. Any previously existing standard colormap properties will be replaced.

`-best`

This option indicates that the `RGB_BEST_MAP` should be defined.

`-blue`

This option indicates that the `RGB_BLUE_MAP` should be defined.

`-default`

This option indicates that the `RGB_DEFAULT_MAP` should be defined.

`-delete map`

This option specifies that a specific standard colormap property, or all such properties, should be removed. `map` may be one of: `default`, `best`, `red`, `green`, `blue`, `gray`, or `all`.

`-display display`

This option specifies the host and display to use; see `x(1)`.

`-gray`

This option indicates that the `RGB_GRAY_MAP` should be defined.

`-green`

This option indicates that the `RGB_GREEN_MAP` should be defined.

`-help`

This option indicates that a brief description of the command-line arguments should be printed on the standard error. This will be done whenever an unhandled argument is given to `xstdcmap`.

`-red`

This option indicates that the `RGB_RED_MAP` should be defined.

`-verbose`

This option indicates that `xstdcmap` should print logging information as it parses its input and defines the standard colormap properties.

ENVIRONMENT

DISPLAY

To get default host and display number

SEE ALSO

x(1)

AUTHOR

Donna Converse (MIT X Consortium)

X Version 11 Release 6

xterm

xterm—Terminal emulator for X

SYNOPSIS

xterm [-toolkitoption ...] [-option ...]

DESCRIPTION

The `xterm` program is a terminal emulator for the X Window System. It provides DEC VT102- and Tektronix 4014-compatible terminals for programs that can't use the window system directly. If the underlying operating system supports terminal resizing capabilities (for example, the `SIGWINCH` signal in systems derived from 4.3bsd), `xterm` will use the facilities to notify programs running in the window whenever it is resized.

The VT102 and Tektronix 4014 terminals all have their own windows so that you can edit text in one and look at graphics in the other at the same time. To maintain the correct aspect ratio (height/width), Tektronix graphics will be restricted to the largest box with a 4014's aspect ratio that will fit in the window. This box is located in the upper-left area of the window.

Although both windows may be displayed at the same time, one of them is considered the active window for receiving keyboard input and terminal output. This is the window that contains the text cursor. The active window can be chosen through escape sequences, the VT Options menu in the VT102 window, and the Tek Options menu in the 4014 window.

EMULATIONS

The VT102 emulation is fairly complete, but does not support smooth scrolling, VT52 mode, the blinking character attribute nor the double-wide and double-size character sets. `termcap(5)` entries that work with `xterm` include `xterm`, `vt102`, `vt100`, and `ansi`, and `xterm` automatically searches the `termcap` file in this order for these entries and then sets the `TERM` and the `TERMCAP` environment variables.

Many of the special `xterm` features may be modified under program control through a set of escape sequences different from the standard VT102 escape sequences. (See the “Xterm Control Sequences” document.)

The Tektronix 4014 emulation is also fairly good. It supports 12-bit graphics addressing, scaled to the window size. Four different font sizes and five different lines types are supported. There is no write-through or defocused mode support. The Tektronix text and graphics commands are recorded internally by `xterm` and may be written to a file by sending the `COPY` escape sequence (or through the Tektronix menu, discussed later in this section). The name of the file will be `COPYyy-MM-dd.hh:mm:ss`, where `yy`, `MM`, `dd`, `hh`, `mm`, and `ss` are the year, month, day, hour, minute, and second when the `COPY` was performed (the file is created in the directory `xterm` is started in, or the home directory for a login `xterm`).

OTHER FEATURES

`xterm` automatically highlights the text cursor when the pointer enters the window (selected) and unhighlights it when the pointer leaves the window (unselected). If the window is the focus window, then the text cursor is highlighted no matter where the pointer is. In VT102 mode, there are escape sequences to activate and deactivate an alternate screen buffer, which

is the same size as the display area of the window. When activated, the current screen is saved and replaced with the alternate screen. Saving of lines scrolled off the top of the window is disabled until the normal screen is restored. The `termcap(5)` entry for `xterm` allows the visual editor `vi(1)` to switch to the alternate screen for editing and to restore the screen on exit.

In either VT102 or Tektronix mode, there are escape sequences to change the name of the windows. See `xterm Control Sequences` for details.

OPTIONS

The `xterm` terminal emulator accepts all of the standard X Toolkit command-line options as well as the following (if the option begins with a `+` instead of a `-`, the option is restored to its default value):

<code>-help</code>	This causes <code>xterm</code> to print out a verbose message describing its options.
<code>-132</code>	Normally, the VT102 <code>DECCOLM</code> escape sequence that switches between 80 and 132 column mode is ignored. This option causes the <code>DECCOLM</code> escape sequence to be recognized, and the <code>xterm</code> window will resize appropriately.
<code>-ah</code>	This option indicates that <code>xterm</code> should always highlight the text cursor. By default, <code>xterm</code> will display a hollow text cursor whenever the focus is lost or the pointer leaves the window.
<code>ah</code>	This option indicates that <code>xterm</code> should do text cursor highlighting based on focus.
<code>-b number</code>	This option specifies the size of the inner border (the distance between the outer edge of the characters and the window border) in pixels. The default is 2.
<code>-cb</code>	Set the vt100 resource <code>cutToBeginningOfLine</code> to False.
<code>cb</code>	Set the vt100 resource <code>cutToBeginningOfLine</code> to True.
<code>-cc characterclassrange: value[,...]</code>	This sets classes indicated by the given ranges to use in selecting by words. See the subsection “Character Classes.”
<code>-cn</code>	This option indicates that newlines should not be cut in line-mode selections.
<code>cn</code>	This option indicates that newlines should be cut in line-mode selections.
<code>-cr color</code>	This option specifies the color to use for text cursor. The default is to use the same foreground color that is used for text.
<code>-cu</code>	This option indicates that <code>xterm</code> should work around a bug in the <code>more(1)</code> program that causes it to incorrectly display lines that are exactly the width of the window and are followed by a line beginning with a tab (the leading tabs are not displayed). This option is so named because it was originally thought to be a bug in the <code>curses(3x)</code> cursor motion package.
<code>cu</code>	This option indicates that <code>xterm</code> should not work around the <code>more(3x)</code> bug mentioned in the preceding paragraph.
<code>-e program [arguments . . .]</code>	This option specifies the program (and its command-line arguments) to be run in the <code>xterm</code> window. It also sets the window title and icon name to be the basename of the program being executed if neither <code>-T</code> nor <code>-n</code> are given on the command line. This must be the last option on the command line.
<code>-fb font</code>	This option specifies a font to be used when displaying bold text. This font must be the same height and width as the normal font. If only one of the normal or bold fonts is

	specified, it will be used as the normal font and the bold font will be produced by overstriking this font. The default is to do overstriking of the normal font.
-im	Turn on the <code>useInsertMode</code> resource.
+im	Turn off the <code>useInsertMode</code> resource.
-j	This option indicates that <code>xterm</code> should do jump scrolling. Normally, text is scrolled one line at a time; this option allows <code>xterm</code> to move multiple lines at a time so that it doesn't fall as far behind. Its use is strongly recommended because it makes <code>xterm</code> much faster when scanning through large amounts of text. The VT100 escape sequences for enabling and disabling smooth scroll as well as the VT Options menu can be used to turn this feature on or off.
j	This option indicates that <code>xterm</code> should not do jump scrolling.
-ls	This option indicates that the shell that is started in the <code>xterm</code> window will be a login shell (that is, the first character of <code>argv[0]</code> will be a dash, indicating to the shell that it should read the user's <code>.login</code> or <code>.profile</code>).
ls	This option indicates that the shell that is started should not be a login shell (that is, it will be a normal subshell).
-mb	This option indicates that <code>xterm</code> should ring a margin bell when the user types near the right end of a line. This option can be turned on and off from the VT Options menu.
mb	This option indicates that margin bell should not be rung.
-mcmilliseconds	This option specifies the maximum time between multiclick selections.
-ms color	This option specifies the color to be used for the pointer cursor. The default is to use the foreground color.
-nb number	This option specifies the number of characters from the right end of a line at which the margin bell, if enabled, will ring. The default is 10.
-rw	This option indicates that reverse-wraparound should be allowed. This allows the cursor to back up from the leftmost column of one line to the rightmost column of the previous line. This is very useful for editing long shell command lines and is encouraged. This option can be turned on and off from the VT Options menu.
rw	This option indicates that reverse-wraparound should not be allowed.
-aw	This option indicates that auto-wraparound should be allowed. This allows the cursor to automatically wrap to the beginning of the next line when it is at the rightmost position of a line and text is output.
aw	This option indicates that auto-wraparound should not be allowed.
-s	This option indicates that <code>xterm</code> may scroll asynchronously, meaning that the screen does not have to be kept completely up to date while scrolling. This allows <code>xterm</code> to run faster when network latencies are very high and is typically useful when running across a very large Internet or many gateways.

s	This option indicates that xterm should scroll synchronously.
-sb	This option indicates that some number of lines that are scrolled off the top of the window should be saved and that a scrollbar should be displayed so that those lines can be viewed. This option may be turned on and off from the VT Options menu.
sb	This option indicates that a scrollbar should not be displayed.
-sf	This option indicates that Sun Function Key escape codes should be generated for function keys.
sf	This option indicates that the standard escape codes should be generated for function keys.
-si	This option indicates that output to a window should not automatically reposition the screen to the bottom of the scrolling region. This option can be turned on and off from the VT Options menu.
si	This option indicates that output to a window should cause it to scroll to the bottom.
-sk	This option indicates that pressing a key while using the scrollbar to review previous lines of text should cause the window to be repositioned automatically in the normal position at the bottom of the scroll region.
sk	This option indicates that pressing a key while using the scrollbar should not cause the window to be repositioned.
-sl number	This option specifies the number of lines to save that have been scrolled off the top of the screen. The default is 64.
-t	This option indicates that xterm should start in Tektronix mode, rather than in VT102 mode. Switching between the two windows is done using the Options menus.
t	This option indicates that xterm should start in VT102 mode.
-tm string	This option specifies a series of terminal setting keywords followed by the characters that should be bound to those functions, similar to the stty program. Allowable keywords include: intr, quit, erase, kill, eof, eol, swtch, start, stop, brk, susp, dsusp, rprnt, flush, weras, and lnext. Control characters may be specified as ^char (for example, ^c or ^u) and ^? may be used to indicate delete.
-tn name	This option specifies the name of the terminal type to be set in the TERM environment variable. This terminal type must exist in the termcap(5) database and should have li# and co# entries.
-ut	This option indicates that xterm shouldn't write a record into the system log file /etc/utmp.
ut	This option indicates that xterm should write a record into the system log file /etc/utmp.
-vb	This option indicates that a visual bell is preferred over an audible one. Instead of ringing the terminal bell whenever a Ctrl+G is received, the window will be flashed.
vb	This option indicates that a visual bell should not be used.
-wf	This option indicates that xterm should wait for the window to be mapped the first time before starting the subprocess so that the initial terminal size settings and environment variables are

`wf`

correct. It is the application's responsibility to catch subsequent terminal size changes.

This option indicates that `xterm` should not wait before starting the subprocess.

`-C`

This option indicates that this window should receive console output. This is not supported on all systems. To obtain console output, you must be the owner of the console device, and you must have read and write permission for it. If you are running `x` under `xdm` on the console screen, you may need to have the session startup and reset programs explicitly change the ownership of the console device in order to get this option to work.

`-Sccn`

This option specifies the last two letters of the name of a pseudo-terminal to use in slave mode, plus the number of the inherited file descriptor. The option is parsed `"%c%c%d"`. This allows `xterm` to be used as an input and output channel for an existing program and is sometimes used in specialized applications.

The following command-line arguments are provided for compatibility with older versions. They may not be supported in the next release as the X Toolkit provides standard options that accomplish the same task.

`%geom`

This option specifies the preferred size and position of the Tektronix window. It is shorthand for specifying the `*tekGeometry` resource.

`geom`

This option specifies the preferred position of the icon window. It is shorthand for specifying the `*iconGeometry` resource.

`-T string`

This option specifies the title for `xterm`'s windows. It is equivalent to `-title`.

`-n string`

This option specifies the icon name for `xterm`'s windows. It is shorthand for specifying the `*iconName` resource. Note that this is not the same as the toolkit option `-name` (see below). The default icon name is the application name.

`-r`

This option indicates that reverse video should be simulated by swapping the foreground and background colors. It is equivalent to `-rv`.

`-w number`

This option specifies the width in pixels of the border surrounding the window. It is equivalent to `-borderwidth` or `-bw`.

The following standard X Toolkit command-line arguments are commonly used with `xterm`:

`-bg color`

This option specifies the color to use for the background of the window. The default is `white`.

`-bd color`

This option specifies the color to use for the border of the window. The default is `black`.

`-bw number`

This option specifies the width in pixels of the border surrounding the window.

`-fg color`

This option specifies the color to use for displaying text. The default is `black`.

`-fn font`

This option specifies the font to be used for displaying normal text. The default is `fixed`.

<code>-name name</code>	This option specifies the application name under which resources are to be obtained, rather than the default executable filename. Name should not contain <code>.</code> or <code>*</code> characters.
<code>-title string</code>	This option specifies the window title string, which may be displayed by window managers if the user so chooses. The default title is the command line specified after the <code>-e</code> option, if any; otherwise, the application name.
<code>-rv</code>	This option indicates that reverse video should be simulated by swapping the foreground and background colors.
<code>-geometry geometry</code>	This option specifies the preferred size and position of the VT102 window; see <code>x(1)</code> .
<code>-display display</code>	This option specifies the X server to contact; see <code>x(1)</code> .
<code>-xrm resourcestring</code>	This option specifies a resource string to be used. This is especially useful for setting resources that do not have separate command-line options.
<code>-iconic</code>	This option indicates that <code>xterm</code> should ask the window manager to start it as an icon rather than as the normal window.

RESOURCES

The program understands all of the core X Toolkit resource names and classes as well as the following:

<code>iconGeometry</code> (class <code>IconGeometry</code>)	Specifies the preferred size and position of the application when iconified. It is not necessarily obeyed by all window managers.
<code>iconName</code> (class <code>IconName</code>)	Specifies the icon name. The default is the application name.
<code>termName</code> (class <code>TermName</code>)	Specifies the terminal type name to be set in the <code>TERM</code> environment variable.
<code>title</code> (class <code>Title</code>)	Specifies a string that may be used by the window manager when displaying this application.
<code>ttyModes</code> (class <code>TtyModes</code>)	Specifies a string containing terminal setting keywords and the characters to which they may be bound. Allowable keywords include <code>intr</code> , <code>quit</code> , <code>erase</code> , <code>kill</code> , <code>eof</code> , <code>eol</code> , <code>swtch</code> , <code>start</code> , <code>stop</code> , <code>brk</code> , <code>susp</code> , <code>dsusp</code> , <code>rprnt</code> , <code>flush</code> , <code>weras</code> , and <code>lnext</code> . Control characters may be specified as <code>^char</code> (for example, <code>^c</code> or <code>^u</code>) and <code>^?</code> may be used to indicate delete. This is very useful for overriding the default terminal settings without having to do an <code>stty</code> every time an <code>xterm</code> is started.
<code>useInsertMode</code> (class <code>UseInsertMode</code>)	Force use of insert mode by adding appropriate entries to the <code>TERMCAP</code> environment variable. This is useful if the system <code>termcap</code> is broken. The default is <code>False</code> .
<code>utmpInhibit</code> (class <code>UtmpInhibit</code>)	Specifies whether or not <code>xterm</code> should try to record the user's terminal in <code>/etc/utmp</code> .
<code>sunFunctionKeys</code> (class <code>SunFunctionKeys</code>)	Specifies whether or not Sun Function Key escape codes should be generated for function keys instead of standard escape sequences.
<code>waitForMap</code> (class <code>WaitForMap</code>)	Specifies whether or not <code>xterm</code> should wait for the initial window map before starting the subprocess. The default is <code>false</code> .

The following resources are specified as part of the vt100 widget (class `VT100`):

<code>allowSendEvents</code> (class <code>AllowSendEvents</code>)	Specifies whether or not synthetic key and button events (generated using the x protocol <code>SendEvent</code> request) should be interpreted or discarded. The default is <code>false</code> , meaning they are discarded. Note that allowing such events creates a very large security hole.
<code>alwaysHighlight</code> (class <code>AlwaysHighlight</code>)	Specifies whether or not xterm should always display a highlighted text cursor. By default, a hollow text cursor is displayed whenever the pointer moves out of the window or the window loses the input focus.
<code>appcursorDefault</code> (class <code>AppcursorDefault</code>)	If <code>true</code> , the cursor keys are initially in application mode. The default is <code>false</code> .
<code>appkeypadDefault</code> (class <code>AppkeypadDefault</code>)	If <code>true</code> , the keypad keys are initially in application mode. The default is <code>false</code> .
<code>autoWrap</code> (class <code>AutoWrap</code>)	Specifies whether or not auto-wraparound should be enabled. The default is <code>true</code> .
<code>bellSuppressTime</code> (class <code>BellSuppressTime</code>)	Number of milliseconds after a bell command is sent during which additional bells will be suppressed. Default is <code>200</code> . If set non-zero, additional bells will also be suppressed until the server reports that processing of the first bell has been completed; this feature is most useful with the visible bell.
<code>boldFont</code> (class <code>BoldFont</code>)	Specifies the name of the bold font to use instead of overstriking.
<code>c132</code> (class <code>C132</code>)	Specifies whether or not the VT102 <code>DECCOLM</code> escape sequence should be honored. The default is <code>false</code> .
<code>cutNewline</code> (class <code>CutNewline</code>)	If <code>false</code> , triple-clicking to select a line does not include the <code>Newline</code> at the end of the line. If <code>true</code> , the <code>Newline</code> is selected. The default is <code>true</code> .
<code>cutToBeginningOfLine</code> (class <code>CutToBeginningOfLine</code>)	If <code>false</code> , triple-clicking to select a line selects only from the current word forward. If <code>true</code> , the entire line is selected. The default is <code>true</code> .
<code>charClass</code> (class <code>CharClass</code>)	Specifies comma-separated lists of character class bindings of the form <code>[low-high:value]</code> . These are used in determining which sets of characters should be treated the same when doing cut and paste. See the section on specifying character classes.
<code>curses</code> (class <code>Curses</code>)	Specifies whether or not the last column bug in <code>more(1)</code> should be worked around. See the <code>-cu</code> option for details. The default is <code>false</code> .
<code>background</code> (class <code>Background</code>)	Specifies the color to use for the background of the window. The default is <code>white</code> .
<code>foreground</code> (class <code>Foreground</code>)	Specifies the color to use for displaying text in the window. Setting the class name instead of the instance name is an easy way to have everything that would normally appear in the text color change color. The default is <code>black</code> .
<code>cursorColor</code> (class <code>Foreground</code>)	Specifies the color to use for the text cursor. The default is <code>black</code> .
<code>eightBitInput</code> (class <code>EightBitInput</code>)	If <code>true</code> , metacharacters input from the keyboard are presented as a single character with the eighth bit turned on. If <code>false</code> , metacharacters are converted into a two-character sequence with the character itself preceded by <code>ESC</code> . The default is <code>true</code> .

eightBitOutput
(class EightBitOutput)

Specifies whether or not eight-bit characters sent from the host should be accepted as is or stripped when printed. The default is `true`.

font (class Font)

Specifies the name of the normal font. The default is `fixed`.

font1 (class Font1)

Specifies the name of the first alternative font.

font2 (class Font2)

Specifies the name of the second alternative font.

font3 (class Font3)

Specifies the name of the third alternative font.

font4 (class Font4)

Specifies the name of the fourth alternative font.

font5 (class Font5)

Specifies the name of the fifth alternative font.

font6 (class Font6)

Specifies the name of the sixth alternative font.

geometry (class Geometry)

Specifies the preferred size and position of the VT102 window.

hpLowerLeftBugCompat

(class HpLowerLeftBugCompat)

Specifies whether to work around a bug in HP's `xdm`, which ignores `termcap` and always sends ESC F to move to the lower-left corner. `true` causes `xterm` to interpret ESC F as a request to move to the lower-left corner of the screen. The default is `false`.

internalBorder

(class BorderWidth)

Specifies the number of pixels between the characters and the window border. The default is 2.

jumpScroll

(class JumpScroll)

Specifies whether or not jump scroll should be used. The default is `true`.

loginShell

(class LoginShell)

Specifies whether or not the shell to be run in the window should be started as a login shell. The default is `false`.

marginBell

(class MarginBell)

Specifies whether or not the bell should be rung when the user types near the right margin. The default is `false`.

multiClickTime

(class MultiClickTime)

Specifies the maximum time in milliseconds between multiclick select events. The default is 250 milliseconds.

multiScroll

(class MultiScroll)

Specifies whether or not scrolling should be done asynchronously. The default is `false`.

nMarginBell (class Column)

Specifies the number of characters from the right margin at which the margin bell should be rung, when enabled.

pointerColor

(class Foreground)

Specifies the foreground color of the pointer. The default is `XtDefaultForeground`.

pointerColorBackground

(class Background)

Specifies the background color of the pointer. The default is `XtDefaultBackground`.

pointerShape

(class Cursor)

Specifies the name of the shape of the pointer. The default is `xterm`.

resizeGravity

(class ResizeGravity)

Affects the behavior when the window is resized to be taller or shorter. `NorthWest` specifies that the top line of text on the screen stay fixed. If the window is made shorter, lines are dropped from the bottom; if the window is made taller, blank lines are added at the bottom. This is compatible with the behavior in R4. `SouthWest` (the default) specifies that the bottom line of text on the screen stay fixed. If the window is made taller, additional saved lines will be scrolled down onto the screen; if the window is made shorter, lines will be scrolled off the top of the screen, and the top saved lines will be dropped.

reverseVideo

(class ReverseVideo)

Specifies whether `reverse video` should be simulated. The default is `false`.

```

reverseWrap
(class ReverseWrap)

saveLines
(class SaveLines)

scrollBar
(class ScrollBar)

scrollTTYOutput
(class ScrollCond)

scrollKey
(class ScrollCond)

scrollLines
(class ScrollLines)

signalInhibit
(class SignalInhibit)

tekGeometry
(class Geometry)

tekInhibit
(class TekInhibit)

tekSmall (class TekSmall)

tekStartup
(class TekStartup)

titeInhibit
(class TiteInhibit)

translations
(class Translations)

visualBell
(class VisualBell)

```

The following resources are specified as part of the `tek4014` widget (class `Tek4014`):

```

width (class Width)
height (class Height)
fontLarge (class Font)
font2 (class Font)
font3 (class Font)
fontSmall (class Font)
initialFont (class InitialFont)

```

Specifies whether or not reverse-wraparound should be enabled. The default is `false`.

Specifies the number of lines to save beyond the top of the screen when a scrollbar is turned on. The default is 64.

Specifies whether or not the scrollbar should be displayed. The default is `false`.

Specifies whether or not output to the terminal should automatically cause the scrollbar to go to the bottom of the scrolling region. The default is `true`.

Specifies whether or not pressing a key should automatically cause the scrollbar to go to the bottom of the scrolling region. The default is `false`.

Specifies the number of lines that the `scroll-back` and `scroll-forward` actions should use as a default. The default value is 1.

Specifies whether or not the entries in the Main Options menu for sending signals to `xterm` should be disallowed. The default is `false`.

Specifies the preferred size and position of the Tektronix window.

Specifies whether or not the escape sequence to enter Tektronix mode should be ignored. The default is `false`.

Specifies whether or not the Tektronix mode window should start in its smallest size if no explicit geometry is given. This is useful when running `xterm` on displays with small screens. The default is `false`.

Specifies whether or not `xterm` should start up in Tektronix mode. The default is `false`.

Specifies whether or not `xterm` should remove `ti` and `termcap` entries (used to switch between alternate screens on startup of many screen-oriented programs) from the `TERMCAP` string. If set, `xterm` also ignores the escape sequence to switch to the alternate screen.

Specifies the key and button bindings for menus, selections, “programmed strings,” and so on. See the “ACTIONS” subsection, later in this section.

Specifies whether or not a visible bell (that is, flashing) should be used instead of an audible bell when Control-G is received. The default is `false`.

Specifies the width of the Tektronix window in pixels.

Specifies the height of the Tektronix window in pixels.

Specifies the large font to use in the Tektronix window.

Specifies font number 2 to use in the Tektronix window.

Specifies font number 3 to use in the Tektronix window.

Specifies the small font to use in the Tektronix window.

Specifies which of the four Tektronix fonts to use initially.

Values are the same as for the `set-tek-text` action. The default is `large`.


```
ginTerminator
(class GinTerminator)
```

Specifies what character(s) should follow a GIN report or status report. The possibilities are `none`, which sends no terminating characters, `CRonly`, which sends `CR`, and `CR&EOT`, which sends both `CR` and `EOT`. The default is `none`.

The resources that may be specified for the various menus are described in the documentation for the Athena `SimpleMenu` widget. The name and classes of the entries in each of the menus are listed next.

The `mainMenu` has the following entries:

```
securekbd (class SmeBSB)
allowsends (class SmeBSB)
redraw (class SmeBSB)
line1 (class SmeLine)
suspend (class SmeBSB)
```

```
continue (class SmeBSB)
```

```
interrupt (class SmeBSB)
hangup (class SmeBSB)
terminate (class SmeBSB)
kill (class SmeBSB)
line2 (class SmeLine)
quit (class SmeBSB)
```

This entry invokes the `secure()` action.

This entry invokes the `allow-send-events(toggle)` action.

This entry invokes the `redraw()` action.

This is a separator.

This entry invokes the `send-signal(tstp)` action on systems that support job control.

This entry invokes the `send-signal(cont)` action on systems that support job control.

This entry invokes the `send-signal(int)` action.

This entry invokes the `send-signal(hup)` action.

This entry invokes the `send-signal(term)` action.

This entry invokes the `send-signal(kill)` action.

This is a separator.

This entry invokes the `quit()` action.

The `vtMenu` has the following entries:

```
scrollbar (class SmeBSB)
jumpscroll (class SmeBSB)
reversevideo (class SmeBSB)
autowrap (class SmeBSB)
reversewrap (class SmeBSB)
autolinefeed (class SmeBSB)
appcursor (class SmeBSB)
appkeypad (class SmeBSB)
scrollkey (class SmeBSB)
scrollttyoutput
(class SmeBSB)
allow132 (class SmeBSB)
cursesemul (class SmeBSB)
visualbell (class SmeBSB)
marginbell (class SmeBSB)
altscreen (class SmeBSB)
line1 (class SmeLine)
softreset (class SmeBSB)
hardreset (class SmeBSB)
clearsavedlines (class SmeBSB)"
line2 (class SmeLine)
tekshow (class SmeBSB)
tekmode (class SmeBSB)
```

This entry invokes the `set-scrollbar(toggle)` action.

This entry invokes the `set-jumpscroll(toggle)` action.

This entry invokes the `set-reverse-video(toggle)` action.

This entry invokes the `set-autowrap(toggle)` action.

This entry invokes the `set-reversewrap(toggle)` action.

This entry invokes the `set-autolinefeed(toggle)` action.

This entry invokes the `set-appcursor(toggle)` action.

This entry invokes the `set-appkeypad(toggle)` action.

This entry invokes the `set-scroll-on-key(toggle)` action.

This entry invokes the `set-scroll-on-tty-output(toggle)` action.

This entry invokes the `set-allow132(toggle)` action.

This entry invokes the `set-cursesemul(toggle)` action.

This entry invokes the `set-visualbell(toggle)` action.

This entry invokes the `set-marginbell(toggle)` action.

This entry is currently disabled.

This is a separator.

This entry invokes the `soft-reset()` action.

This entry invokes the `hard-reset()` action.

This entry invokes the `clear-saved-lines()` action.

This is a separator.

This entry invokes the `set-visibility(tek,toggle)` action.

This entry invokes the `set-terminal-type(tek)` action.

`vthide (class SmeBSB)`

This entry invokes the `set-visibility(vt,off)` action.

The `fontMenu` has the following entries:

`fontdefault (class SmeBSB)`

This entry invokes the `set-vt-font(d)` action.

`font1 (class SmeBSB)`

This entry invokes the `set-vt-font(1)` action.

`font2 (class SmeBSB)`

This entry invokes the `set-vt-font(2)` action.

`font3 (class SmeBSB)`

This entry invokes the `set-vt-font(3)` action.

`font4 (class SmeBSB)`

This entry invokes the `set-vt-font(4)` action.

`font5 (class SmeBSB)`

This entry invokes the `set-vt-font(5)` action.

`font6 (class SmeBSB)`

This entry invokes the `set-vt-font(6)` action.

`fontescape (class SmeBSB)`

This entry invokes the `set-vt-font(e)` action.

`fontsel (class SmeBSB)`

This entry invokes the `set-vt-font(s)` action.

The `tekMenu` has the following entries:

`tektextlarge (class SmeBSB)`

This entry invokes the `set-tek-text(1)` action.

`tektext2 (class SmeBSB)`

This entry invokes the `set-tek-text(2)` action.

`tektext3 (class SmeBSB)`

This entry invokes the `set-tek-text(3)` action.

`tektextsmall (class SmeBSB)`

This entry invokes the `set-tek-text(s)` action.

`line1 (class SmeLine)`

This is a separator.

`tekpage (class SmeBSB)`

This entry invokes the `tek-page()` action.

`tekreset (class SmeBSB)`

This entry invokes the `tek-reset()` action.

`tekcopy (class SmeBSB)`

This entry invokes the `tek-copy()` action.

`line2 (class SmeLine)`

This is a separator.

`vtshow (class SmeBSB)`

This entry invokes the `set-visibility(vt,toggle)` action.

`vtmode (class SmeBSB)`

This entry invokes the `set-terminal-type(vt)` action.

`tekhide (class SmeBSB)`

This entry invokes the `set-visibility(tek,toggle)` action.

The following resources are useful when specified for the Athena Scrollbar widget:

`thickness (class Thickness)`

Specifies the width in pixels of the scrollbar.

`background (class Background)`

Specifies the color to use for the background of the scrollbar.

`foreground (class Foreground)`

Specifies the color to use for the foreground of the scrollbar. The “thumb” of the scrollbar is a simple checkerboard pattern alternating pixels for foreground and background color.

POINTER USAGE

Once the VT102 window is created, `xterm` allows you to select text and copy it within the same or other windows.

The selection functions are invoked when the pointer buttons are used with no modifiers, and when they are used with the Shift key. The assignment of the functions described in this subsection to keys and buttons may be changed through the resource database; see the “Actions” subsection later in this section.

Pointer button one (usually left) is used to save text into the cut buffer. Move the cursor to the beginning of the text, and then hold the button down while moving the cursor to the end of the region and releasing the button. The selected text is highlighted and is saved in the global cut buffer and made the PRIMARY selection when the button is released. Double-clicking selects by words. Triple-clicking selects by lines. Quadruple-clicking goes back to characters, and so on. Multiple-click is determined by the time from button up to button down, so you can change the selection unit in the middle of a selection. If the key/button bindings specify that an X selection is to be made, `xterm` will leave the selected text highlighted for as long as it is the selection owner.

Pointer button two (usually middle) “types” (pastes) the text from the PRIMARY selection, if any, otherwise from the cut buffer, inserting it as keyboard input.

Pointer button three (usually right) extends the current selection. (Without loss of generality, you can swap “right” and “left” everywhere in the rest of this paragraph.) If pressed while closer to the right edge of the selection than the left, it extends/contracts the right edge of the selection. If you contract the selection past the left edge of the selection, xterm assumes you really meant the left edge, restores the original selection, then extends/contracts the left edge of the selection. Extension starts in the selection unit mode that the last selection or extension was performed in; you can multiple-click to cycle through them.

By cutting and pasting pieces of text without trailing new lines, you can take text from several places in different windows and form a command to the shell, for example, or take output from a program and insert it into your favorite editor. Since the cut buffer is globally shared among different applications, you should regard it as a file whose contents you know. The terminal emulator and other text programs should be treating it as if it were a text file; that is, the text is delimited by new lines.

The scroll region displays the position and amount of text currently showing in the window (highlighted) relative to the amount of text actually saved. As more text is saved (up to the maximum), the size of the highlighted area decreases.

Clicking button one with the pointer in the scroll region moves the adjacent line to the top of the display window.

Clicking button three moves the top line of the display window down to the pointer position.

Clicking button two moves the display to a position in the saved text that corresponds to the pointer’s position in the scrollbar.

Unlike the VT102 window, the Tektronix window does not allow the copying of text. It does allow Tektronix GIN mode, and in this mode the cursor will change from an arrow to a cross. Pressing any key will send that key and the current coordinate of the cross cursor. Pressing button one, two, or three will return the letters `1`, `m`, and `r`, respectively. If the Shift key is pressed when a pointer button is pressed, the corresponding uppercase letter is sent. To distinguish a pointer button from a key, the high bit of the character is set (but this bit is normally stripped unless the terminal mode is RAW; see `tty(4)` for details).

MENUS

xterm has four menus: `mainMenu`, `vtMenu`, `fontMenu`, and `tekMenu`. Each menu pops up under the correct combinations of key and button presses. Most menus are divided into two sections, separated by a horizontal line. The top portion contains various modes that can be altered. A check mark appears next to a mode that is currently active. Selecting one of these modes toggles its state. The bottom portion of the menu consists of command entries; selecting one of these performs the indicated function.

The `xterm` menu pops up when the Control key and pointer button one are pressed in a window. The `mainMenu` contains items that apply to both the VT102 and Tektronix windows. The Secure Keyboard mode is used when typing in passwords or other sensitive data in an unsecured environment. (See the “SECURITY” subsection.) Notable entries in the command section of the menu are the Continue, Suspend, Interrupt, Hangup, Terminate, and Kill, which send the `SIGCONT`, `SIGTSTP`, `SIGINT`, `SIGHUP`, `SIGTERM`, and `SIGKILL` signals, respectively, to the process group of the process running under xterm (usually the shell). The Continue function is especially useful if the user has accidentally typed CTRL-Z, suspending the process.

The `vtMenu` sets various modes in the VT102 emulation, and is popped up when the Control key and pointer button two are pressed in the VT102 window. In the command section of this menu, the Soft Reset entry will reset scroll regions. This can be convenient when some program has left the scroll regions set incorrectly (often a problem when using VMS or TOPS-20). The Full Reset entry will clear the screen, reset tabs to every eight columns, and reset the terminal modes (such as wrap and smooth scroll) to their initial states just after xterm has finished processing the command-line options.

The `fontMenu` sets the font used in the VT102 window. In addition to the default font and a number of alternatives that are set with resources, the menu offers the font last specified by the Set Font escape sequence (see the document “Xterm Control Sequences”) and the current selection as a font name (if the PRIMARY selection is owned).

The `tekMenu` sets various modes in the Tektronix emulation, and is popped up when the Control key and pointer button two are pressed in the Tektronix window. The current font size is checked in the Modes section of the menu. The `PAGE` entry in the Command section clears the Tektronix window.

SECURITY

X environments differ in their security consciousness. Most servers, run under `xdm`, are capable of using a “magic cookie” authorization scheme that can provide a reasonable level of security for many people. If your server is only using a host-based mechanism to control access to the server (see `xhost(1)`), then if you enable access for a host and other users are also permitted to run clients on that same host, there is every possibility that someone can run an application that will use the basic services of the X protocol to snoop on your activities, potentially capturing a transcript of everything you type at the keyboard. This is of particular concern when you want to type in a password or other sensitive data. The best solution to this problem is to use a better authorization mechanism than host-based control, but a simple mechanism exists for protecting keyboard input in `xterm`.

The `xterm` menu (see “Menus,” earlier in this section) contains a `Secure Keyboard` entry which, when enabled, ensures that all keyboard input is directed only to `xterm` (using the `GrabKeyboard` protocol request). When an application prompts you for a password (or other sensitive data), you can enable `Secure Keyboard` using the menu, type in the data, and then disable `Secure Keyboard` using the menu again. Only one X client at a time can secure the keyboard, so when you attempt to enable `Secure Keyboard`, it may fail. In this case, the bell will sound. If the `Secure Keyboard` succeeds, the foreground and background colors will be exchanged (as if you selected the `Reverse Video` entry in the Modes menu); they will be exchanged again when you exit secure mode. If the colors do not switch, then you should be very suspicious that you are being spoofed. If the application you are running displays a prompt before asking for the password, it is safest to enter secure mode before the prompt gets displayed, and to make sure that the prompt gets displayed correctly (in the new colors), to minimize the probability of spoofing. You can also bring up the menu again and make sure that a check mark appears next to the entry.

`Secure Keyboard` mode will be disabled automatically if your `xterm` window becomes iconified (or otherwise unmapped), or if you start up a reparenting window manager (that places a title bar or other decoration around the window) while in `Secure Keyboard` mode. (This is a feature of the X protocol that isn’t easily overcome.) When this happens, the foreground and background colors will be switched back and the bell will sound in warning.

CHARACTER CLASSES

Clicking the middle mouse button twice in rapid succession will cause all characters of the same class (for example, letters, whitespace, punctuation) to be selected. Since different people have different preferences for what should be selected (for example, should filenames be selected as a whole or only the separate subnames?), the default mapping can be overridden through the use of the `charClass` (class `CharClass`) resource.

This resource is a series of comma-separated `range:value` pairs. The range is either a single number or low-high in the range of 0 to 127, corresponding to the ASCII code for the character or characters to be set. The value is arbitrary, although the default table uses the character number of the first character occurring in the set.

The default table is

```
static int charClass[128] = {
/* NUL SOH STX ETX EOT ENQ ACK BEL */
32, 1, 1, 1, 1, 1, 1, 1,
/* BS HT NL VT NP CR SO SI */
1, 32, 1, 1, 1, 1, 1, 1,
/* DLE DC1 DC2 DC3 DC4 NAK SYN ETB */
1, 1, 1, 1, 1, 1, 1, 1,
/* CAN EM SUB ESC FS GS RS US */
1, 1, 1, 1, 1, 1, 1, 1,
/*SP!"#$%&'*/
32, 33, 34, 35, 36, 37, 38, 39,
/*()*+,-./*/
40, 41, 42, 43, 44, 45, 46, 47,
/*0 1 2 3 4 5 6 7 */

```

```

48, 48, 48, 48, 48, 48, 48, 48,
/*8 9 :;< => ?*/
48, 48, 58, 59, 60, 61, 62, 63,
/*@ABC D E F G*/
64, 48, 48, 48, 48, 48, 48, 48,
/* H I J K L M N O */
48, 48, 48, 48, 48, 48, 48, 48,
/*P QR S T UVW*/
48, 48, 48, 48, 48, 48, 48, 48,
/*XY Z [\]^ */
48, 48, 48, 91, 92, 93, 94, 48,
/*'ab c d e fg */
96, 48, 48, 48, 48, 48, 48, 48,
/*h ijklm n o */
48, 48, 48, 48, 48, 48, 48, 48,
/*p q rs tu v w */
48, 48, 48, 48, 48, 48, 48, 48,
/*x y zf jg` DEL */
48, 48, 48, 123, 124, 125, 126, 1};

```

For example, the string 33:48,37:48,45-47:48,64:48 indicates that the exclamation mark, percent sign, dash, period, slash, and ampersand characters should be treated the same way as characters and numbers. This is useful for cutting and pasting electronic mailing addresses and filenames.

ACTIONS

It is possible to rebind keys (or sequences of keys) to arbitrary strings for input by changing the translations for the vt100 or tek4014 widgets. Changing the translations for events other than key and button events is not expected, and will cause unpredictable behavior. The following actions are provided for using within the vt100 or tek4014 translations resources:

<code>bell([percent])</code>	This action rings the keyboard bell at the specified percentage above or below the base volume.
<code>ignore()</code>	This action ignores the event but checks for special pointer position escape sequences.
<code>insert()</code>	This action inserts the character or string associated with the key that was pressed.
<code>insert-seven-bit()</code>	This action is a synonym for <code>insert()</code> .
<code>insert-eight-bit()</code>	This action inserts an eight-bit (Meta) version of the character or string associated with the key that was pressed. The exact action depends on the value of the <code>eightBitInput</code> resource.
<code>insert-selection</code> <code>(sourcename [, ...])</code>	This action inserts the string found in the selection or cut buffer indicated by <code>sourcename</code> . Sources are checked in the order given (case is significant) until one is found. Commonly used selections include <code>PRIMARY</code> , <code>SECONDARY</code> , and <code>CLIPBOARD</code> . Cut buffers are typically named <code>CUT_BUFFER0</code> through <code>CUT_BUFFER7</code> .
<code>keymap(name)</code>	This action dynamically defines a new translation table whose resource name is <code>name</code> with the suffix <code>keymap</code> (case is significant). The name <code>None</code> restores the original translation table.
<code>popup-menu(menuname)</code>	This action displays the specified pop-up menu. Valid names (case is significant) include <code>mainMenu</code> , <code>vtMenu</code> , <code>fontMenu</code> , and <code>tekMenu</code> .
<code>secure()</code>	This action toggles the Secure Keyboard mode described in the “Security” subsection, and is invoked from the <code>securekbd</code> entry in <code>mainMenu</code> .

`select-start()`

This action begins text selection at the current pointer location. See the subsection on “Pointer Usage” for information on making selections.

`select-extend()`

This action tracks the pointer and extends the selection. It should only be bound to Motion events.

`select-end`
(*destname* [, ...])

This action puts the currently selected text into all of the selections or cut buffers specified by *destname*.

`select-cursor-start()`

This action is similar to `select-start` except that it begins the selection at the current text cursor position.

`select-cursor-end`
(*destname* [, ...])

This action is similar to `select-end` except that it should be used with `select-cursor-start`.

`set-vt-font`
(*d*/1/2/3/4/5/6/*e*/*s*
[,*normalfont* [, *boldfont*]])

This action sets the font or fonts currently being used in the VT102 window. The first argument is a single character that specifies the font to be used: *d* or *D* indicate the default font (the font initially used when `xterm` was started), 1 through 6 indicate the fonts specified by the `font1` through `font6` resources, *e* or *E* indicate the normal and bold fonts that have been set through escape codes (or specified as the second and third action arguments, respectively), and *s* or *S* indicate the font selection (as made by programs such as `xfontsel(1)`) indicated by the second action argument.

`start-extend()`

This action is similar to `select-start` except that the selection is extended to the current pointer location.

`start-cursor-extend()`

This action is similar to `select-extend` except that the selection is extended to the current text cursor position.

`string(string)`

This action inserts the specified text string as if it had been typed. Quotation is necessary if the string contains whitespace or nonalphanumeric characters. If the string argument begins with the characters `0x`, it is interpreted as a hex character constant.

`scroll-back(count [,units])`

This action scrolls the text window backward so that text that had previously scrolled off the top of the screen is now visible. The count argument indicates the number of units (which may be page, half page, pixel, or line) by which to scroll.

`scroll-forw(count [,units])`

This action scroll is similar to `scroll-back` except that it scrolls the other direction.

`allow-send-events`
(*on/off/toggle*)

This action set or toggles the `allowSendEvents` resource and is also invoked by the `allowsends` entry in `mainMenu`.

`redraw()`

This action redraws the window and is also invoked by the `redraw` entry in `mainMenu`.

`send-signal(signame)`

This action sends the signal named by *signame* to the `xterm` subprocess (the shell or program specified with the `-e` command-line option) and is also invoked by the `suspend`, `continue`, `interrupt`, `hangup`, `terminate`, and `kill` entries in `mainMenu`. Allowable signal names are (case is not significant) `tsft` (if supported by the operating system), `suspend` (same as `tsft`), `cont` (if supported by the operating system), `int`, `hup`, `term`, `quit`, `alarm` (same as `alarm`), and `kill`.

`quit()`

This action sends a `SIGHUP` to the subprogram and exits. It is also invoked by the `quit` entry in `mainMenu`.

<code>set-scrollbar(on/off/toggle)</code>	This action toggles the <code>scrollbar</code> resource and is also invoked by the <code>scrollbar</code> entry in <code>vtMenu</code> .
<code>set-jumpscroll(on/off/toggle)</code>	This action toggles the <code>jumpscroll</code> resource and is also invoked by the <code>jumpscroll</code> entry in <code>vtMenu</code> .
<code>set-reverse-video(on/off/toggle)</code>	This action toggles the <code>reverseVideo</code> resource and is also invoked by the <code>reversevideo</code> entry in <code>vtMenu</code> .
<code>set-autowrap(on/off/toggle)</code>	This action toggles automatic wrapping of long lines and is also invoked by the <code>autowrap</code> entry in <code>vtMenu</code> .
<code>set-reversewrap(on/off/toggle)</code>	This action toggles the <code>reverseWrap</code> resource and is also invoked by the <code>reversewrap</code> entry in <code>vtMenu</code> .
<code>set-autolinefeed(on/off/toggle)</code>	This action toggles automatic insertion of line-feeds and is also invoked by the <code>autolinefeed</code> entry in <code>vtMenu</code> .
<code>set-appcursor(on/off/toggle)</code>	This action toggles the handling Application Cursor Key mode and is also invoked by the <code>appcursor</code> entry in <code>vtMenu</code> .
<code>set-appkeypad(on/off/toggle)</code>	This action toggles the handling of Application Key-pad mode and is also invoked by the <code>appkeypad</code> entry in <code>vtMenu</code> .
<code>set-scroll-on-key(on/off/toggle)</code>	This action toggles the <code>scrollKey</code> resource and is also invoked from the <code>scrollkey</code> entry in <code>vtMenu</code> .
<code>set-scroll-on-tty-output(on/off/toggle)</code>	This action toggles the <code>scrollTtyOutput</code> resource and is also invoked from the <code>scrollttyoutput</code> entry in <code>vtMenu</code> .
<code>set-allow132(on/off/toggle)</code>	This action toggles the <code>c132</code> resource and is also invoked from the <code>allow132</code> entry in <code>vtMenu</code> .
<code>set-cursesemul(on/off/toggle)</code>	This action toggles the <code>curses</code> resource and is also invoked from the <code>cursesemul</code> entry in <code>vtMenu</code> .
<code>set-visual-bell(on/off/toggle)</code>	This action toggles the <code>visualBell</code> resource and is also invoked by the <code>visualbell</code> entry in <code>vtMenu</code> .
<code>set-marginbell(on/off/toggle)</code>	This action toggles the <code>marginBell</code> resource and is also invoked from the <code>marginbell</code> entry in <code>vtMenu</code> .
<code>set-altscreen(on/off/toggle)</code>	This action toggles between the alternate and current screens.
<code>soft-reset()</code>	This action resets the scrolling region and is also invoked from the <code>softreset</code> entry in <code>vtMenu</code> .
<code>hard-reset()</code>	This action resets the scrolling region, tabs, window size, and cursor keys, and clears the screen. It is also invoked from the <code>hardreset</code> entry in <code>vtMenu</code> .
<code>clear-saved-lines()</code>	This action does <code>hard-reset()</code> and also clears the history of lines saved off the top of the screen. It is also invoked from the <code>clearsavedlines</code> entry in <code>vtMenu</code> .
<code>set-terminal-type(type)</code>	This action directs output to either the <code>vt</code> or <code>tek</code> windows, according to the <code>type</code> string. It is also invoked by the <code>tekmode</code> entry in <code>vtMenu</code> and the <code>vtmode</code> entry in <code>tekMenu</code> .
<code>set-visibility(vt/tek,on/off/toggle)</code>	This action controls whether or not the <code>vt</code> or <code>tek</code> windows are visible. It is also invoked from the <code>tekshow</code> and <code>vhide</code> entries in <code>vtMenu</code> and the <code>vtshow</code> and <code>tekhide</code> entries in <code>tekMenu</code> .
<code>set-tek-text(large/2/3/small)</code>	This action sets font used in the Tektronix window to the value of the resources <code>tektextlarge</code> , <code>tektext2</code> , <code>tektext3</code> , and <code>tektextsmall</code> according to the argument. It is also by the entries of the same names as the resources in <code>tekMenu</code> .
<code>tek-page()</code>	This action clears the Tektronix window and is also invoked by the <code>tekpage</code> entry in <code>tekMenu</code> .

tek-reset()

This action resets the Tektronix window and is also invoked by the `tekreset` entry in `tekMenu`.

tek-copy()

This action copies the escape codes used to generate the current window contents to a file in the current directory beginning with the name `COPY`. It is also invoked from the `tekcopy` entry in `tekMenu`.

visual-bell()

This action flashes the window quickly.

The Tektronix window also has the following action:

gin-press(l/l/m/m/r/r)

This action sends the indicated graphics input code.

The default bindings in the VT102 window are

```
Shift <KeyPress> Prior: scroll-back(1,halpage) \n\
Shift <KeyPress> Next: scroll-forw(1,halpage) \n\
Shift <KeyPress> Select: select-cursor-start() \
select-cursor-end(PRIMARY, CUT_BUFFER0) \n\
Shift <KeyPress> Insert: insert-selection(PRIMARY, CUT_BUFFER0) \n\
~Meta<KeyPress>: insert-seven-bit() \n\
Meta<KeyPress>: insert-eight-bit() \n\
!Ctrl <Btn1Down>: popup-menu(mainMenu) \n\
!Lock Ctrl <Btn1Down>: popup-menu(mainMenu) \n\
!Mod2 Ctrl <Btn1Down>: popup-menu(mainMenu) \n\
!Mod2 Lock Ctrl <Btn1Down>: popup-menu(mainMenu) \n\
~Meta <Btn1Down>: select-start() \n\
~Meta <Btn1Motion>: select-extend() \n\
!Ctrl <Btn2Down>: popup-menu(vtMenu) \n\
!Lock Ctrl <Btn2Down>: popup-m
```

The default bindings in the Tektronix window are

```
~Meta<KeyPress>: insert-seven-bit() \n\
Meta<KeyPress>: insert-eight-bit() \n\
!Ctrl <Btn1Down>: popup-menu(mainMenu) \n\
!Lock Ctrl <Btn1Down>: popup-menu(mainMenu) \n\
!Mod2 Ctrl <Btn1Down>: popup-menu(mainMenu) \n\
!Mod2 Lock Ctrl <Btn1Down>: popup-menu(mainMenu) \n\
!Ctrl <Btn2Down>: popup-menu(tekMenu) \n\
!Lock Ctrl <Btn2Down>: popup-menu(tekMenu) \n\
!Mod2 Ctrl <Btn2Down>: popup-menu(tekMenu) \n\
!Mod2 Lock Ctrl <Btn2Down>: popup-menu(tekMenu) \n\
Shift ~Meta<Btn1Down>: gin-press(L) \n\
~Meta<Btn1Down>: gin-press(l) \n\
Shift ~Meta<Btn2Down>: gin-press(M) \n\
~Meta<Btn2Down>: gin-press(m) \n\
Shift ~Meta<Btn3Down>: gin-press(R) \n\
~Meta<Btn3Down>: gin-press(r)
```

Below is a sample how of the `keymap()` action is used to add special keys for entering commonly typed works:

```
*VT100.Translations: #override <Key>F13: keymap(dbx)
VT100.dbxKeymap.translations: \
<Key>F14: keymap(None) \n\
<Key>F17: string("next") string(0x0d) \n\
<Key>F18: string("step") string(0x0d) \n\
<Key>F19: string("continue") string(0x0d) \n\
<Key>F20: string("print ") insert-selection(PRIMARY, CUT_BUFFER0)
```


ENVIRONMENT

`xterm` sets the environment variables `TERM` and `TERMCAP` properly for the size window you have created. It also uses and sets the environment variable `DISPLAY` to specify which bit map display terminal to use. The environment variable `WINDOWID` is set to the X window id number of the `xterm` window.

SEE ALSO

`resize(1)`, `x(1)`, `pty(4)`, `tty(4)`

Xterm Control Sequences

BUGS

Large pastes do not work on some systems. This is not a bug in `xterm`; it is a bug in the pseudo-terminal driver of those systems. `xterm` feeds large pastes to the `pty` only as fast as the `pty` will accept data, but some `pty` drivers do not return enough information to know if the write has succeeded.

Many of the options are not resettable after `xterm` starts.

Only fixed-width, character-cell fonts are supported.

This program still needs to be rewritten. It should be split into very modular sections, with the various emulators being completely separate widgets that don't know about each other. Ideally, you'd like to be able to pick and choose emulator widgets and stick them into a single control widget.

There needs to be a dialog box to allow entry of the Tek COPY filename.

AUTHORS

Far too many people, including Loretta Guarino Reid (DEC-UEG-WSL), Joel McCormack (DEC-UEG-WSL), Terry Weissman (DEC-UEG-WSL), Edward Moy (Berkeley), Ralph R. Swick (MIT-Athena), Mark Vandevoorde (MIT-Athena), Bob McNamara (DEC-MAD), Jim Gettys (MIT-Athena), Bob Scheifler (MIT X Consortium), Doug Mink (SAO), Steve Pitschke (Stellar), Ron Newman (MIT-Athena), Jim Fulton (MIT X Consortium), Dave Serisky (HP), Jonathan Kamens (MIT-Athena)

X Version 11 Release 6

Xvfb

xvfb—Virtual framebuffer X server for X Version 11

SYNOPSIS

`xvfb [ option ] ...`

DESCRIPTION

`xvfb` is an X server that can run on machines with no display hardware and no physical input devices. It emulates a dumb framebuffer using virtual memory.

The primary use of this server is intended to be server testing. The `mfb` or `cfb` code for any depth can be exercised with this server without the need for real hardware that supports the desired depths.

A secondary use is testing clients against unusual depths and screen configurations.

OPTIONS

In addition to the normal server options described in the `xserver(1)` manual page, `xvfb` accepts the following command-line switches:

`-screen screennum WxHxD`

This option creates screen `screennum` and sets its width, height, and depth to `w`, `h`, and `d`, respectively. By default, only screen 0 exists and has the dimensions 1280×1024×8.

`-pixdepths list-of-depths`

This option specifies a list of pixmap depths that the server should support in addition to the depths implied by the supported screens. `list-of-depths` is a space-separated list of integers that can have values from 1 to 32.

`-fbdir framebuffer-directory`

This option specifies the directory in which the memory-mapped files containing the framebuffer memory should be created. (See “Files.”) This option only exists on machines that have the `mmap` and `msync` system calls.

`-shmem`

This option specifies that the framebuffer should be put in shared memory. The shared memory ID for each screen will be printed by the server. The shared memory is in `xwd` format. This option only exists on machines that support the System V shared memory interface.

If neither `-shmem` nor `-fbdir` is specified, the framebuffer memory will be allocated with `malloc()`.

FILES

The following file is created if the `-fbdir` option is given:

```
framebuffer-directory
/Xvfb_screen<n>
```

Memory-mapped file containing screen `n`’s framebuffer memory, one file per screen. The file is in `xwd` format.

EXAMPLES

```
Xvfb :1 -screen 0 1600x1200x32
```

The server will listen for connections as server number 1, and screen 0 will be depth 32 1600×1200.

```
Xvfb :1 -screen 1 1600x1200x16
```

The server will listen for connections as server number 1, will have the default screen configuration (one screen, 1280×1024×8), and screen 1 will be depth 16 1600×1200.

```
Xvfb -pixdepths 3 27
```

```
-fbdir /usr/tmp
```

The server will listen for connections as server number 0, will have the default screen configuration (one screen, 1280×1024×8), will also support pixmap depths of 3 and 27, and will use memory-mapped files in `/usr/tmp` for the framebuffer.

```
xwud -in /usr/tmp/Xvfb screen0
```

Displays screen 0 of the server started by the preceding example.

SEE ALSO

`x(1)`, `Xserver(1)`, `xwd(1)`, `xwud(1)`, `XWDFFile.h`

AUTHORS

David P. Wiggins (X Consortium, Inc.)

xvidtune

xvidtune—Video mode tuner for XFree86

SYNOPSIS

```
xvidtune [ -prev j -next j -unlock j -query j -saver suspendtime [ offtime ] ][-toolkitoption ... ]
```

DESCRIPTION

xvidtune is a client interface to the XFree86 X server video mode extension (XFree86-VidModeExtension).

When given one of the nontoolkit options, xvidtune provides a command-line interface to either switch the video mode or get/set monitor powersaver time-outs.

Without any options (or with only toolkit options) it presents the user with various buttons and sliders that can be used to interactively adjust existing video modes. It will also print the settings in a format suitable for inclusion in an XF86Config file.

NOTE

The original mode settings can be restored by pressing the **R** key, and this can be used to restore a stable screen in situations where the screen becomes unreadable.

The available buttons are

Left
Right
Up
Down

Adjust the video mode so that the display will be moved in the appropriate direction:

Wider
Narrower
Shorter
Taller

Adjust the video mode so that the display size is altered appropriately:

Quit
Apply
Auto

Test
Restore
Fetch
Show

Next
Prev

Exit the program.

Adjust the current video mode to match the selected settings.

Cause the Up/Down/Right/Left, Wider/Narrower/Shorter/Taller, Restore, and the special S3 buttons to be applied immediately. This button can be toggled.

Temporarily switch to the selected settings.

Return the settings to their original values.

Query the server for its current settings.

Print the currently selected settings to stdout in XF86Config Modeline format. The primary selection is similarly set.

Switch the xserver to the next video mode.

Switch the xserver to the previous video mode.

For some S3-based cards (964 and 968) the following are also available:

InvertVCLK
EarlySC

Change the VCLK invert/noninvert state.

Change the Early SC state. This affects screen wrapping.

BlankDelay1, BlankDelay2

Set the blank delay values. This affects screen wrapping. Acceptable values are in the range 0–7. The values may be incremented or decremented with the + and - buttons, or by pressing the + or - keys in the text field.

For S3-864/868 based cards, InvertVCLK and BlankDelay1 may be useful. For S3 Trio32/Trio64 cards, only InvertVCLK is available. At the moment there are no default settings available for these chips in the video mode extension and thus this feature is disabled in xvidtune. It can be enabled by setting any of the optional S3 commands in the screen section of XF86Config, for example, using

```
blank delay "" 0
```

OPTIONS

xvidtune accepts the standard X Toolkit command-line options as well as the following:

-prev

Switch the Xserver to the previous video mode.

-next

Switch the Xserver to the next video mode.

-unlock

Normally, xvidtune will disable the switching of video modes via hot keys while it is running. If for some reason the program did not exit cleanly and they are still disabled, the program can be rerun with this option to reenable the mode switching key combinations.

-saver suspendtime [offtime]

Set the suspend and off screen saver inactivity time-outs. The values are in seconds.

-query

Display the monitor parameters and extended screen saver time-outs.

SEE ALSO

XF86Config(4/5)

AUTHORS

Kaleb S. Keithley (X Consortium), additions and modifications by Jon Tombs, David Dawes, and Joe Moss

X Version 11 Release 6

xvminitoppm

xvminitoppm—Convert an XV thumbnail picture to PPM

SYNOPSIS

```
xvminitoppm [xvminipic]
```

DESCRIPTION

Reads an XV *thumbnail* picture (a miniature picture generated by the VisualSchnauzer browser) as input. Produces a portable pixmap as output.

SEE ALSO

ppm(5), xv(1)

AUTHOR

Copyright (c) 1993 by Ingo Wilken

14 December 1993

xwd

xwd—Dump an image of an X window

SYNOPSIS

```
xwd [-debug] [-help] [-nobdrs] [-out file] [-xy] [-frame] [-add value]
[-root j -id id j -name name ] [-icmap] [-screen] [-display display]
```

DESCRIPTION

xwd is an X Window System window dumping utility. xwd allows X users to store window images in a specially formatted dump file. This file can then be read by various other X utilities for redisplay, printing, editing, formatting, archiving, image processing, and so on. The target window is selected by clicking the pointer in the desired window. The keyboard bell is rung once at the beginning of the dump and twice when the dump is completed.

OPTIONS

-display display

This argument allows you to specify the server to connect to; see `x(1)`.

-help

Print out the Usage: command syntax summary.

-nobdrs

This argument specifies that the window dump should not include the pixels that compose the X window border. This is useful in situations in which you may wish to include the window contents in a document as an illustration.

-out file

This argument allows the user to explicitly specify the output file on the command line. The default is to output to standard out.

-xy

This option applies to color displays only. It selects xy format dumping instead of the default z format.

-add value

This option specifies a signed value to be added to every pixel.

-frame

This option indicates that the window manager frame should be included when manually selecting a window.

-root

This option indicates that the root window should be selected for the window dump, without requiring the user to select a window with the pointer.

-id id

This option indicates that the window with the specified resource `id` should be selected for the window dump, without requiring the user to select a window with the pointer.

-name name

This option indicates that the window with the specified `WM_NAME` property should be selected for the window dump, without requiring the user to select a window with the pointer.

-icmap

Normally, the colormap of the chosen window is used to obtain RGB values. This option forces the first installed colormap of the screen to be used instead.

-screen

This option indicates that the `GetImage` request used to obtain the image should be done on the root window, rather than directly on the specified window. In this way, you can obtain pieces of other windows that overlap the specified window, and more importantly, you can capture menus or other popups that are independent windows but that appear over the specified window.

ENVIRONMENT

DISPLAY

To get default host and display number

FILES

XWDFile.h X

Window dump file format definition file.

SEE ALSO

xwud(1), xpr(1), x(1)

AUTHORS

Tony Della Fera (Digital Equipment Corporation, MIT Project Athena) and William F. Wyatt (Smithsonian Astrophysical Observatory)

X Version 11 Release 6

xwdtopnm

xwdtopnm—Convert an X11 or X10 window dump file into a portable anymap

SYNOPSIS

xwdtopnm [xwdfile]

DESCRIPTION

Reads an X11 or X10 window dump file as input. Produces a portable anymap as output. The type of the output file depends on the input file. If it's black and white, a pbm file is written; if it's grayscale, a pgm file, else a ppm file. The program tells you which type it is writing.

Using this program, you can convert anything on an X workstation's screen into an anymap. Just display whatever you're interested in, do an xwd, run it through xwdtopnm, and then use pnmcut to select the part you want.

BUGS

I haven't tested this tool with very many configurations, so there are probably bugs. Please let me know if you find any.

SEE ALSO

pnmtoxwd(1), pnm(5), xwd(1)

AUTHOR

Copyright (c) 1989, 1991 by Jef Poskanzer.

11 January 1991

xwininfo

xwininfo—Window information utility for X

SYNOPSIS

```
xwininfo [-help] [-id id] [-root] [-name name] [-int] [-children] [-tree]
[-stats] [-bits] [-events] [-size] [-wm] [-shape] [-frame] [-all] [-english]
[-metric] [-display display]
```

DESCRIPTION

`xwininfo` is a utility for displaying information about windows. Various information is displayed depending on which options are selected. If no options are chosen, `-stats` is assumed.

The user has the option of selecting the target window with the mouse (by clicking any mouse button in the desired window) or by specifying its window `id` on the command line with the `-id` option. Or instead of specifying the window by its `id` number, the `-name` option may be used to specify which window is desired by name. There is also a special `-root` option to quickly obtain information on the screen's root window.

OPTIONS

<code>-help</code>	Print out the usage: command syntax summary.
<code>-id id</code>	This option allows the user to specify a target window <code>id</code> on the command line rather than using the mouse to select the target window. This is very useful in debugging X applications where the target window is not mapped to the screen or where the use of the mouse might be impossible or interfere with the application.
<code>-name name</code>	This option allows the user to specify that the window <code>name</code> is the target window on the command line rather than using the mouse to select the target window.
<code>-root</code>	This option specifies that X's root window is the target window. This is useful in situations where the root window is completely obscured.
<code>-int</code>	This option specifies that all X window <code>ids</code> should be displayed as integer values. The default is to display them as hexadecimal values.
<code>-children</code>	This option causes the root, parent, and children windows' <code>ids</code> and names of the selected window to be displayed.
<code>-tree</code>	This option is like <code>-children</code> but displays all children recursively.
<code>-stats</code>	This option causes the display of various attributes pertaining to the location and appearance of the selected window. Information displayed includes the location of the window, its width and height, its depth, border width, class, colormap <code>id</code> if any, map state, backing-store hint, and location of the corners.
<code>-bits</code>	This option causes the display of various attributes pertaining to the selected window's raw bits and how the selected window is to be stored. Displayed information includes the selected window's bit gravity, window gravity, backing-store hint, backing-planes value, backing pixel, and whether or not the window has <code>save-under</code> set.
<code>-events</code>	This option causes the selected window's event masks to be displayed. Both the event mask of events wanted by some client and the event mask of events not to propagate are displayed.
<code>-size</code>	This option causes the selected window's sizing hints to be displayed. Displayed information includes the following: for both the normal size hints and the zoom size hints, the user supplied location, if any; the program supplied location, if any; the user supplied size, if any; the program supplied size, if any;

`-wm`

the minimum size, if any; the maximum size, if any; the resize increments, if any; and the minimum and maximum aspect ratios, if any.

This option causes the selected window's window manager hints to be displayed. Information displayed may include whether or not the application accepts input, what the window's icon window # and name is, where the window's icon should go, and what the window's initial state should be.

`-shape`

This option causes the selected window's window and border shape extents to be displayed.

`-frame`

This option causes window manager frames to be considered when manually selecting windows.

`-metric`

This option causes all individual height, width, and x and y positions to be displayed in millimeters as well as number of pixels, based on what the server thinks the resolution is.

Geometry specifications that are in +x+y form are not changed.

`-english`

This option causes all individual height, width, and x and y positions to be displayed in inches (and feet, yards, and miles if necessary) as well as number of pixels. `-metric` and `-english` may both be enabled at the same time.

`-all`

This option is a quick way to ask for all information possible.

`-display display`

This option allows you to specify the server to connect to; see `x(1)`.

EXAMPLE

The following is a sample summary taken with no options specified:

```
xwininfo: Window id: 0x60000f "xterm" Absolute upper-left X: 2
Absolute upper-left Y: 85 Relative upper-left X: 0 Relative upper-left Y: 25
Width: 579 Height: 316 Depth: 8 Visual Class: PseudoColor Border width: 0
Class: InputOutput Colormap: 0x27 (installed) Bit Gravity State:
NorthWestGravity Window Gravity State: NorthWestGravity Backing Store State:
NotUseful Save Under State: no Map State: IsViewable Override Redirect State:
no Corners: +2+85 -699+85 -699-623 +2-623 -geometry 80x24+0+58
```

ENVIRONMENT

`DISPLAY`

To get the default host and display number

SEE ALSO

`x(1)`, `xprop(1)`

BUGS

Using `-stats -bits` shows some redundant information.

The `-geometry` string displayed must make assumptions about the window's border width and the behavior of the application and the window manager. As a result, the location given is not always correct.

AUTHOR

Mark Lillibridge (MIT Project Athena)

xwud

xwud—Image display for X

SYNOPSIS

```
xwud [-in file] [-noclick] [-geometry geom] [-display display]
[-new] [-std <matype>] [-raw] [-vis <vis-type-or-id>] [-help] [-rv]
[-plane number] [-fg color] [-bg color]
```

DESCRIPTION

xwud is an X Window System image undumping utility. xwud allows X users to display in a window an image saved in a specially formatted dump file, such as produced by xwd(1).

OPTIONS

-bg color	If a bitmap image (or a single plane of an image) is displayed, this option can be used to specify the color to display for the 0 bits in the image.
-display display	This option allows you to specify the server to connect to; see x(1).
-fg color	If a bitmap image (or a single plane of an image) is displayed, this option can be used to specify the color to display for the 1 bits in the image.
-geometry geom	This option allows you to specify the size and position of the window. Typically, you will only want to specify the position, and let the size default to the actual size of the image.
-help	Print out a short description of the allowable options.
-in file	This option enables the user to explicitly specify the input file on the command line. If no input file is given, the standard input is assumed.
-new	This option forces creation of a new colormap for displaying the image. If the image characteristics happen to match those of the display, this can get the image on the screen faster, but at the cost of using a new colormap (which on most displays will cause other windows to go Technicolor).
-noclick	Clicking any button in the window will terminate the application, unless this option is specified. Termination can always be achieved by typing q, Q, or Ctrl+C.
-plane number	You can select a single bit plane of the image to display with this option. Planes are numbered with zero being the least significant bit. This option can be used to figure out which plane to pass to xpr(1) for printing.
-raw	This option forces the image to be displayed with whatever color values happen to currently exist on the screen. This option is mostly useful when undumping an image back onto the same screen that the image originally came from, while the original windows are still on the screen, and results in getting the image on the screen faster.
-rv	If a bitmap image (or a single plane of an image) is displayed, this option forces the foreground and background colors to be swapped. This may be needed when displaying a bitmap image that has the color sense of pixel values 0 and 1 reversed from what they are on your display.

`-std maptype`

`-vis vis-type-or-id`

This option causes the image to be displayed using the specified standard colormap. The property name is obtained by converting the type to uppercase, prepending `RGB`, and appending `MAP`. Typical types are `best`, `default`, and `gray`. See `xstd-cmap(1)` for one way of creating standard colormaps.

This option allows you to specify a particular visual or visual class. The default is to pick the “best” one. A particular class can be specified: `StaticGray`, `GrayScale`, `StaticColor`, `PseudoColor`, `DirectColor`, or `TrueColor`. Or `Match` can be specified, meaning use the same class as the source image. Alternatively, an exact visual `id` (specific to the server) can be specified, either as a hexadecimal number (prefixed with `0x`) or as a decimal number. Finally, `default` can be specified, meaning to use the same class as the colormap of the root window. Case is not significant in any of these strings.

ENVIRONMENT

`DISPLAY`

To get default display

FILES

`XWDFile.h`

X Window dump file format definition file

SEE ALSO

`xwd(1)`, `xpr(1)`, `xstdcmap(1)`, `X(1)`

AUTHOR

Bob Scheifler (MIT X Consortium)

X Version 11 Release 6

ybmtopbm

`ybmtopbm`—Convert a Bennet Yee “face” file into a portable bitmap

SYNOPSIS

`ybmtopbm [ facefile ]`

DESCRIPTION

Reads a file acceptable to the `face` and `xbm` programs by Bennet Yee (`bsy+@cs.cmu.edu`). Writes a portable bitmap as output.

SEE ALSO

`pbmtoybm(1)`, `pbm(5)`, `face(1)`, `face(5)`, `xbm(1)`

AUTHOR

Copyright (c) 1991 by Jamie Zawinski and Jef Poskanzer.

6 March 1990

y`talk`

y`talk`—A multiuser chat program.

SYNOPSIS

```
ytalk [-x] username...
```

DESCRIPTION

y`talk` (V3.0 Patch Level 1) is in essence a multiuser chat program. It works almost exactly like the UNIX `talk` program and even communicates with the same `talk` daemon(s), but y`talk` allows for multiple connections.

The `username` field may be formatted in several different ways:

<code>name</code>	Some user on your machine
<code>name@host</code>	Some user on a different machine
<code>name#tty</code>	Some user on a particular terminal
<code>name#tty@host</code>	Some user on a particular tty on a different machine
<code>name@host#tty</code>	Same as <code>name#tty@host</code>

You can specify multiple usernames on the command line, for example,

```
ytalk george fred@hissun.edu marc@grumpy.cc
```

The `-x` option disables the X11 interface (described below).

For each user on the command line, y`talk` will attempt to connect to the `talk` daemon on the specified user's host and determine if that user has left an invitation for you to call. If not, y`talk` leaves an invitation for him and tells his `talk` daemon to send an announcement to his screen. There is not yet a dedicated y`talk` daemon, but there will be. Right now, y`talk` is able to communicate with both existing versions of UNIX `talk` daemons. For any particular host, y`talk` will attempt to communicate with a `talk` daemon the caller's host also supports. If the two hosts have no daemon in common, then UNIX `talk` will not function at all, but a connection is possible through (and only through) y`talk`.

After a connection has been established between two users, they can chat back and forth to their hearts' content. The connection is terminated when one of them hits Control-C or selects Quit from the main menu.

y`talk` is perfectly compatible with UNIX `talk` and they can even converse with each other without any problems. However, many of the features of y`talk` can only operate when you are connected to a user who is also using y`talk`. For the rest of this document, it will be assumed that all connected users are using y`talk` unless otherwise stated.

If you specified more than one user on the y`talk` command line, then y`talk` will process and add each user to the conversation as they respond to your invitation. As each new user enters the conversation, the screen is further subdivided into smaller and smaller windows, one for each connected user. Right now, the number of connected users is limited by the number of lines on your terminal (or window), for each connected user needs at least three lines.

y`talk` does implement primitive support of the X11 Windowing System. If the environment variable `DISPLAY` is set, then y`talk` attempts to connect to that X server. Further details about the X11 interface (and how to turn it off) are given later in this section.

As each new user is added to the conversation, y`talk` will transmit information about that user to all other connected y`talk` users so that their screens will also subdivide and incorporate the new user. If the new user is using UNIX `talk`, then information about him will NOT be transmitted, as his screen would be unable to accept multiple connections. I have given brief thought to allowing at least the output of UNIX `talk` users to be transmitted to all connected y`talk` users, but I have not written any code to do so. Note that even though UNIX `talk` cannot handle multiple connections, it is still possible for y`talk` to handle multiple UNIX "talk" connections. For example, george (using y`talk`) could communicate with fred and joe (both using UNIX `talk`), but fred and joe would be unaware of each other. The best way to understand the limitations that UNIX "talk" places on y`talk` is to test various connections between the two and see how things work.

ESCAPE MENU

Whenever you are using `ytalk`, you can hit the Escape key to bring up a menu that at this moment has these options:

a	Add a user
d	Delete a user
o	Options
s	Shell
u	User list
w	Output user to file
q	Quit

By choosing option `a`, you are given the opportunity to type the name of any user you wish to include into the conversation. Again, `YTALK` will accept an invitation from that user if an invitation exists, or will leave an invitation and ring the given user.

By choosing option `d`, you can select the name of a connection to terminate.

By choosing option `o`, you can view and/or modify any of the `ytalk` options. (See the “Options” subsection for a list of `ytalk` options.)

By choosing option `s`, you can invoke a shell in your `ytalk` window. All other users will see what happens in your shell. `ytalk` will automatically resize your window down to the size of the smallest window you are connected to, in order to ensure that all users always see the same thing.

The `u` option displays a list of connected and unconnected users, as well as their window sizes and what version of talk software they are running.

By choosing option `w`, you can select any connected user and type the name of a file, and all further output from that user will be dumped to the specified file. The file, if it exists, will be overwritten. If you choose `w` and the same user again, further output to the file will be terminated.

Oh, one other thing: when user A attempts to `ytalk` to user B, but user B is already `ytalking` with user C, user A’s `ytalk` program will realize that user B is already using `ytalk`, and will communicate with user B’s `ytalk` program directly in order to initialize the conversation. User B will see a nice windowed message such as

Do you wish to talk with user A?

and he will be prompted for a yes/no answer. This, in my opinion, is much preferable to blitting the announcement message and messing up user B’s screen.

RUNTIME OPTIONS

When you select Options from the main menu, you are given the opportunity to edit the `ytalk` options. The current options are

s	Turn scrolling [off/on]
w	Turn word-wrap [off/on]
i	Turn auto-import [off/on]
v	Turn auto-invite [off/on]
r	Turn auto-rering [off/on]
a	Turn asides [off/on]

If `scrolling` is turned on, then a user’s window will scroll when he reaches the bottom, instead of wrapping back around to the top.

If `word-wrap` is turned on, then any word that would overextend the right margin will be automatically moved to the next line on your screen.

If `auto-import` is turned on, then `ytalk` will assume that you wish to talk to any users that connect to other `ytalk` users that are connected to you. That last sentence does make sense; try again. `ytalk` will add these users to your session automatically, without asking you for verification.

If `auto-invite` is turned on, then `ytalk` will automatically accept any connection requested by another user and add the user to your session. You will not be asked for verification.

If `auto-rering` is turned on, then `ytalk` will automatically re-ring any user who does not respond to your invitation within 30 seconds. You will not be asked for verification.

If `asides` is turned on (it may not be available), then keyboard input received while the input focus is in a specific user's window will only be sent to that user. (See the “X11 Interface” subsection.)

Any of these options can be set to your preference in your `.ytalkrc` file, as described in the next subsection.

Y^TALK STARTUP FILE

If your home directory contains a file named `.ytalkrc`, then `ytalk` will read this file while starting up. All `ytalk` runtime options, as well as some startup options, can be set in this file.

SETTING BOOLEAN OPTIONS

Boolean options can be preset with the following syntax:

```
turn option [off | on]
```

where `option` is one of `scrolling`, `word-wrap`, `auto-import`, `auto-invite`, `auto-rering`, `asides`, or `X`. Setting these options works just like described earlier in this section. Turning `X` on or off will enable or disable the X11 Interface. For example, one could enable `word-wrap` with the line:

```
turn word-wrap on
```

SETTING READDRESS MODES

The purpose of `readdress` is to allow `ytalk` connections across point-to-point network gateways where the local machines know themselves by a different address (and typically hostname) than the remote machines. The basic syntax of a `readdress` command is this:

```
readdress from-address to-address domain
```

The `readdress` statement simply makes a claim that the machine(s) in `domain` communicate with the machine(s) at `from-address` by sending a packet to `to-address`. Because most users have no use for this whatsoever, I'll describe it only briefly.

THIS IS NOT ROUTING. For example, my machine at home is connected via PPP to the network at my office. My machine at home thinks its Ethernet address is `192.188.253.1` and its hostname is “`talisman.com`”. The network at my office has the address `192.67.141.0`. When I'm connected via PPP, my home machine is placed into the office network as address `192.67.141.9` with hostname “`talisman.austin.eds.com`”.

`ytalk` needs to know that if it is running on domain `192.67.141.0` and receives packets from `192.188.253.1` that it should respond to `192.67.141.9`, not `192.188.253.1`. Right? Right. Okay, okay, okay. I put this line into my `.ytalkrc` on both ends:

```
readdress talisman talisman.austin.eds.com 192.67.141.0
```

On my home end, this translates to

```
readdress 192.188.253.1 192.67.141.9 192.67.141.0
```

which tells my home machine to advertise itself as `192.67.141.9` instead of `192.188.253.1` when `ytalking` to machines on the network `192.67.141.0`. On the office end, the `readdress` command translates to

```
readdress 192.67.141.9 192.67.141.9 192.67.141.0
```

which the office machines basically ignore.

Enough. For more information on how to use this, consult the source code or send me a letter. :-)

X11 INTERFACE

If the `DISPLAY` environment variable is defined when `ytalk` starts up, then `ytalk` will attempt to communicate with that X server. A window will be created for you and each user you are connected to. The X11 Interface can be disabled either by specifying `-x` on the command line or by putting this line into your `.ytalkrc` file:

```
turn X off
```

A window is created for each individual user in the conversation. If the input focus is in the main window (the one with `ytalk` in the title bar) then anything typed will be sent to all connected users. If the input focus is in one of the user's windows, then anything typed will be sent as an aside to only that user. If the `aside` option is turned off, then `ytalk` will beep and not accept anything typed when the input focus is not in the main window.

`ytalk` consults the X11 Resource Database for these user-definable configuration options:

`ytalk.display`: X server to connect to, defaulting to the `DISPLAY` environment variable.

`ytalk.reverse`: Reverse black/white pixels.

`ytalk.font`: Font to use, defaulting to 9x15.

`ytalk.geometry`: Window size, defaulting to 80x24.

FUTURE WORK

Work is being done on the following ideas:

- Private conversations that do not get interrupted or transmitted to all `ytalk` connections
- A dedicated `ytalk` daemon

FILES

`/usr/local/etc/ytalkrc`

`$HOME/.ytalkrc`

Systemwide defaults file.

User's local configuration file. This file overrides options set in the system `ytalkrc` file.

AUTHOR

Britt Yenne (yenne@austin.eds.com)

CONTRIBUTORS

Special thanks to Carl Edman for numerous code patches, beta testing, and comments. I think this guy spends as much time on `ytalk` as I do. Special thanks to Tobias Hahn and Geoff W. for beta testing and suggestions. Thanks to Sitaram Ramaswamy for the original `ytalk` man page. Thanks to Magnus Hammerin for Solaris 2.* support. Thanks to Jonas Yngvesson for `aside` messages in X. Thanks to Andreas Stolcke for fixing the X resource database calls. Thanks to John Vanderpool, Shih-Chen Huang, Andrew Myers, Duncan Sinclair, Evan McLean, and Larry Schwimmer for comments and ideas. The `README` file shipped with `ytalk` gives detailed attributions.

BUGS

If you have any ideas, comments, or questions, I'd be happy to hear from you at ytalk@austin.eds.com.

24 June 1993

yuvplittoppm

`yuvplittoppm`—Convert a Y-, a U-, and a V- file into a portable pixmap.

SYNOPSIS

```
yuvsplittoppm basename width height [-ccir601]
```

DESCRIPTION

Reads three files, containing the YUV components, as input. These files are `basename.Y`, `basename.U` and `basename.V`. Produces a portable pixmap on `stdout`.

Since the YUV files are raw files, the dimensions width and height must be specified on the command line.

OPTIONS

`-ccir601`

Assumes that the YUV triplets are scaled into the smaller range of the CCIR 601 (MPEG) standard. Otherwise, the JFIF (JPEG) standard is assumed.

SEE ALSO

`ppmtoyuvsplit(1)`, `yuvtoppm(1)`, `ppm(5)`

AUTHOR

Marcel Wijkstra (<wijkstra@fwi.uva.nl>), based on `ppmtoyuvsplit`

26 August 1993

yuvtoppm

`yuvtoppm`—Convert Abekas YUV bytes into a portable pixmap

SYNOPSIS

`yuvtoppm width height [imagedata]`

DESCRIPTION

Reads raw Abekas YUV bytes as input. Produces a portable pixmap as output. The input file is just YUV bytes. You have to specify the width and height on the command line, since the program obviously can't get them from the file. The `maxval` is assumed to be 255.

SEE ALSO

`ppmtoyuv(1)`, `ppm(5)`

AUTHOR

Marc Boucher (<marc@PostImage.COM>)), based on Example Conversion Program, *A60/A64 Digital Video Interface Manual*, page 69. Copyright (c) 1991 by DHD PostImage, Inc. Copyright (c) 1987 by Abekas Video Systems, Inc.

25 March 1991

zcmp, zdiff

`zcmp`, `zdiff`—Compare compressed files

SYNOPSIS

`zcmp [ cmp_options ] file1 [ file2 ]`
`zdiff [diff_options ] file1 [ file2 ]`

DESCRIPTION

`zcmp` and `zdiff` are used to invoke the `cmp` or the `diff` program on compressed files. All options specified are passed directly to `cmp` or `diff`. If only one file is specified, then the files compared are `file1` and an uncompressed `file1.gz`. If two files are specified, then they are uncompressed if necessary and fed to `cmp` or `diff`. The exit status from `cmp` or `diff` is preserved.

SEE ALSO

`cmp(1)`, `diff(1)`, `zmore(1)`, `zgrep(1)`, `znew(1)`, `zforce(1)`, `gzip(1)`, `gzexe(1)`

BUGS

Messages from the `cmp` or `diff` programs refer to temporary filenames instead of those specified.

zeisstopnm

`zeisstopnm`—Convert a Zeiss confocal file into a portable anymap

SYNOPSIS

```
zeisstopnm [-pgm j -ppm][zeissfile]
```

DESCRIPTION

Reads a Zeiss confocal file as input. Produces a portable anymap as output. The type of the output file depends on the input file—if it's grayscale, a `pgm` file will be produced; otherwise, it will be a `ppm` file. The program tells you which type it is writing.

OPTIONS

<code>-pgm</code>	Force the output to be a <code>pgm</code> file
<code>-ppm</code>	Force the output to be a <code>ppm</code> file

SEE ALSO

`pnm(5)`

AUTHOR

Copyright (c) 1993 by Oliver Trepte.

15 June 1993

zforce

`zforce`—Force a `.gz` extension on all `gzip` files

SYNOPSIS

```
zforce [ name ... ]
```

DESCRIPTION

`zforce` forces a `.gz` extension on all `gzip` files so that `gzip` will not compress them twice. This can be useful for files with names truncated after a file transfer. On systems with a 14-character limitation on filenames, the original name is truncated to make room for the `.gz` suffix. For example, `12345678901234` is renamed to `12345678901.gz`. A filename such as `foo.tgz` is left intact.

SEE ALSO

gzip(1), znew(1), zmore(1), zgrep(1), zdiff(1), gzexe(1)

zgrep

zgrep—Search possibly compressed files for a regular expression

SYNOPSIS

```
zgrep [ grep_options ] [-e] pattern filename...
```

DESCRIPTION

zgrep is used to invoke the grep on compressed or gzipped files. All options specified are passed directly to grep. If no file is specified, then the standard input is decompressed if necessary and fed to grep. Otherwise, the given files are uncompressed if necessary and fed to grep.

If zgrep is invoked as zegrep or zfgrep, then egrep or fgrep is used instead of grep. If the GREP environment variable is set, zgrep uses it as the grep program to be invoked. For example,

```
for sh: GREP=fgrep zgrep string files for csh: (setenv GREP fgrep; zgrep string files)
```

AUTHOR

Charles Levert (charles@comm.polymtl.ca)

SEE ALSO

grep(1), egrep(1), fgrep(1), zdiff(1), zmore(1), znew(1), zforce(1), gzip(1), gzexe(1)

zmore

zmore—File perusal filter for crt viewing of compressed text

SYNOPSIS

```
zmore [ name ... ]
```

DESCRIPTION

zmore is a filter that allows examination of compressed or plain text files one screenful at a time on a soft-copy terminal. zmore works on files compressed with compress, pack, or gzip, and also on uncompressed files. If a file does not exist, zmore looks for a file of the same name with the addition of a .gz, .z, or .Z suffix.

zmore normally pauses after each screenful, printing -More- at the bottom of the screen. If the user then types a carriage return, one more line is displayed. If the user hits a space, another screenful is displayed. Other possibilities are enumerated later.

zmore looks in the file /etc/termcap to determine terminal characteristics, and to determine the default window size. On a terminal capable of displaying 24 lines, the default window size is 22 lines. To use a pager other than the default more, set environment variable PAGER to the name of the desired program, such as less.

Other sequences that may be typed when zmore pauses, and their effects, are as follows (i is an optional integer argument, defaulting to 1) :

i <space>	Display i more lines, (or another screenful if no argument is given).
^D	Display 11 more lines (a “scroll”). If i is given, then the scroll size is set to i.
d	Same as ^D (control-D)

i z

Same as typing a space except that **i**, if present, becomes the new window size. Note that the window size reverts back to the default at the end of the current file.

i s

Skip **i** lines and print a screenful of lines.

i f

Skip **i** screenfuls and print a screenful of lines.

q or **Q**

Quit reading the current file; go on to the next (if any).

e or **q**

When the prompt **-More-(Next file: file)** is printed, this command causes **zmore** to exit.

s

When the prompt **-More-(Next file: file)** is printed, this command causes **zmore** to skip the next file and continue.

=

Display the current line number.

i /expr

Search for the **i**th occurrence of the regular expression **expr**. If the pattern is not found, **zmore** goes on to the next file (if any). Otherwise, a screenful is displayed, starting two lines before the place where the expression was found. The user's erase and kill characters may be used to edit the regular expression. Erasing back past the first column cancels the search command.

i n

Search for the **i**th occurrence of the last regular expression entered.

!command

Invoke a shell with **command**. The character **!** in **command** is replaced with the previous shell command. The sequence **\!** is replaced by **!**.

:q or **:Q**

Quit reading the current file; go on to the next (if any) (same as **q** or **Q**).

.

(dot) Repeat the previous command.

The commands take effect immediately; that is, it is not necessary to type a carriage return. Up to the time when the command character itself is given, the user may hit the line kill character to cancel the numerical argument being formed. In addition, the user may hit the erase character to redisplay the **-More-** message.

At any time when output is being sent to the terminal, the user can hit the quit key (normally Control-n). **zmore** will stop sending output, and will display the usual **-More-** prompt. The user may then enter one of the preceding commands in the normal manner. Unfortunately, some output is lost when this is done because any characters waiting in the terminal's output queue are flushed when the quit signal occurs.

The terminal is set to **noecho** mode by this program so that the output can be continuous. What you type will thus not show on your terminal, except for the **/** and **!** commands.

If the standard output is not a teletype, then **zmore** acts just like **zcat**, except that a header is printed before each file.

FILES

/etc/termcap Terminal database

SEE ALSO

more(1), **gzip(1)**, **zdiff(1)**, **zgrep(1)**, **znew(1)**, **zforce(1)**, **gzexe(1)**

znew

znew—Recompress Z files to GZ files

SYNOPSIS

znew [**-ftv9PK**] [**name.Z ...**]

DESCRIPTION

znew recompresses files from Z (compress) format to GZ (gzip) format. If you want to recompress a file already in gzip format, rename the file to force a .Z extension, then apply znew.

OPTIONS

-f	Force recompression from Z to GZ format even if a GZ file already exists.
-t	Test the new files before deleting originals.
-v	Verbose. Display the name and percentage reduction for each file compressed.
-9	Use the slowest compression method (optimal compression).
-P	Use pipes for the conversion to reduce disk space usage.
-K	Keep a Z file when it is smaller than the GZ file.

SEE ALSO

gzip(1), zmore(1), zdiff(1), zgrep(1), zforce(1), gzexe(1), compress(1)

BUGS

znew does not maintain the timestamp with the -P option if cpmmod(1) is not available and touch(1) does not support the -r option.

Part II:

System Calls

intro

intro—Introduction to system calls

DESCRIPTION

This chapter describes the Linux system calls.

CALLING DIRECTLY

In most cases, it is unnecessary to invoke a system call directly, but there are times when the standard C library does not implement a nice function call for you.

SYNOPSIS

```
#include <linux/unistd.h>
```

A `_syscall` macro

Desired system call

SETUP

The important thing to know about a system call is its prototype. You need to know how many arguments, their types, and the function return type. Six macros make the actual call into the system easier. They have the form

```
syscallX(type,name,type1,arg1,type2,arg2,...)
```

where

x	0–5, which are the number of arguments taken by the system call
type	The return type of the system call
name	The name of the system call
typeN	The Nth argument's type
argN	The name of the Nth argument

These macros create a function called `name` with the arguments you specify. Once you include `_syscall()` in your source file, you call the system call by name.

EXAMPLE

```
{
    struct sysinfo s_info;
    int error;

    error = sysinfo(&s_info);
    printf("code error = %d\n", error);
    printf("Uptime = %ds\nLoad: 1 min %d / 5 min %d / 15 min %d\n"
        "RAM: total %d / free %d / shared %d\n"
        "Memory in buffers = %d\nSwap: total %d / free %d\n"
        "Number of processes = %d\n",
        s_info.uptime, s_info.loads[0],
        s_info.loads[1], s_info.loads[2],
        s_info.totalram, s_info.freeram,
        s_info.sharedram, s_info.bufferram,
        s_info.totalswap, s_info.freeswap,
        s_info.procs);
    return(0);
}
```

SAMPLE OUTPUT

```
code error = 0
uptime = 502034s
Load: 1 min 13376 / 5 min 5504 / 15 min 1152
RAM: total 15343616 / free 827392 / shared 8237056
Memory in buffers = 5066752
Swap: total 27881472 / free 24698880
Number of processes = 40
```

NOTES

The `_syscall()` macros *do not* produce a prototype. You might have to create one, especially for C++ users.

System calls are not required to return only positive or negative error codes. You need to read the source to be sure how it will return errors. Usually, it is the negative of a standard error code, for example, `-EPERM`. The `_syscall()` macros will return the result `r` of the system call when `r` is nonnegative, but will return `-1` and set the variable `errno` to `-r` when `r` is negative.

Some system calls, such as `mmap`, require more than five arguments. These are handled by pushing the arguments on the stack and passing a pointer to the block of arguments.

When defining a system call, the argument types *must* be passed by value or by pointer (for aggregates such as structs).

FILES

```
/usr/include/linux/unistd.h
```

AUTHORS

Look at the header of the manual page for the author(s) and copyright conditions. Note that these can be different from page to page.

Linux 1.2.13, 22 May 1996

exit

`exit`—Terminate the current process

SYNOPSIS

```
#include <unistd.h>
void exit(int status);
```

DESCRIPTION

`exit` terminates the calling process immediately. Any open file descriptors belonging to the process are closed; any children of the process are inherited by process 1, `init`, and the process's parent is sent a `SIGCHLD` signal.

`status` is returned to the parent process as the process's exit status and can be collected using one of the `wait` family of calls.

RETURN VALUE

`exit` never returns.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

NOTES

`exit` does not call any functions registered with the ANSI C `atexit` function and does not flush standard I/O buffers. To do these things, use `exit(3)`.

SEE ALSO

`fork(2)`, `execve(2)`, `waitpid(2)`, `wait4(2)`, `kill(2)`, `wait(3)`, `exit(3)`

Linux, 21 July 1993

accept

`accept`—Accept a connection on a socket

SYNOPSIS

```
#include <sys/types.h>
#include <sys/socket.h>
int accept(int s, struct sockaddr *addr, int*addrlen);
```

DESCRIPTION

The argument `s` is a socket that has been created with `socket(2)`, bound to an address with `bind(2)`, and is listening for connections after a `listen(2)`. The `accept` function extracts the first connection request on the queue of pending connections, creates a new socket with the same properties of `s`, and allocates a new file descriptor for the socket. If no pending connections are present on the queue and the socket is not marked as nonblocking, `accept` blocks the caller until a connection is present. If the socket is marked nonblocking and no pending connections are present on the queue, `accept` returns an error as described below. The accepted socket may not be used to accept more connections. The original socket `s` remains open.

The argument `addr` is a result parameter that is filled in with the address of the connecting entity, as known to the communications layer. The exact format of the `addr` parameter is determined by the domain in which the communication is occurring. The `addrlen` is a value-result parameter; it should initially contain the amount of space pointed to by `addr`; on return it will contain the actual length (in bytes) of the address returned. This call is used with connection-based socket types, currently with `SOCK_STREAM`.

It is possible to `select(2)` a socket for the purposes of doing an `accept` by selecting it for read.

For certain protocols that require an explicit confirmation, such as ISO and DATAKIT, `accept` can be thought of as merely dequeuing the next connection request and not implying confirmation. Confirmation can be implied by a normal read or write on the new file descriptor, and rejection can be implied by closing the new socket.

One can obtain user connection request data without confirming the connection by issuing a `recvmsg(2)` call with a `msg_iovlen` of 0 and a nonzero `msg_controllen`, or by issuing a `getsockopt(2)` request. Similarly, one can provide user connection rejection information by issuing a `sendmsg(2)` call providing only the control information, or by calling `setsockopt(2)`.

RETURN VALUES

The call returns `-1` on error. If it succeeds, it returns a nonnegative integer that is a descriptor for the accepted socket.

ERRORS

<code>EBADF</code>	The descriptor is invalid.
<code>ENOTSOCK</code>	The descriptor references a file, not a socket.
<code>EOPNOTSUPP</code>	The referenced socket is not of type <code>SOCK_STREAM</code> .
<code>EFAULT</code>	The <code>addr</code> parameter is not in a writable part of the user address space.
<code>EWOULDBLOCK</code>	The socket is marked nonblocking and no connections are present to be accepted.

HISTORY

The `accept` function appeared in BSD 4.2.

SEE ALSO

`bind(2)`, `connect(2)`, `listen(2)`, `select(2)`, `socket(2)`

BSD Man Page, 24 July 1993

access

`access`—Checks user's permissions for a file

SYNOPSIS

```
#include <unistd.h>
int access(const char *pathname, int mode);
```

DESCRIPTION

`access` checks whether the process would be allowed to read, write, or test for existence of the file (or other file system object) whose name is `pathname`. If `pathname` is a symbolic link, permissions of the file referred by this symbolic link are tested.

`mode` is a mask consisting of one or more of `R_OK`, `W_OK`, `X_OK`, and `F_OK`.

`R_OK`, `W_OK`, and `X_OK` request checking whether the file exists and has read, write, and execute permissions, respectively. `F_OK` just requests checking for the existence of the file.

The tests depend on the permissions of the directories occurring in the path to the file, as given in `pathname`, and on the permissions of directories and files referred by symbolic links encountered on the way.

The check is done with the process's real UID and GID, rather than with the effective IDs as is done when actually attempting an operation. This is to allow set-UID programs to easily determine the invoking user's authority.

Only access bits are checked, not the file type or contents. Therefore, if a directory is found to be “writable,” it probably means that files can be created in the directory, and not that the directory can be written as a file. Similarly, a DOS file may be found to be “executable,” but the `execve(2)` call will still fail.

RETURN VALUE

On success (all requested permissions granted), 0 is returned. On error (at least 1 bit in `mode` asked for a permission that is denied, or some other error occurred), -1 is returned and `errno` is set appropriately.

ERRORS

EACCES	The requested access would be denied, either to the file itself or one of the directories in <code>pathname</code> .
EFAULT	<code>pathname</code> points outside your accessible address space.
EINVAL	<code>mode</code> was incorrectly specified.
ENAMETOOLONG	<code>pathname</code> is too long.
ENOENT	A directory component in <code>pathname</code> would have been accessible but does not exist or was a dangling symbolic link.
ENOTDIR	A component used as a directory in <code>pathname</code> is not, in fact, a directory.
ENOMEM	Insufficient kernel memory was available.
ELOOP	<code>pathname</code> contains a reference to a circular symbolic link, that is, a symbolic link containing a reference to itself.

RESTRICTIONS

`access` returns an error if any of the access types in the requested call fails, even if other types might be successful. `access` may not work correctly on NFS file systems with UID mapping enabled because UID mapping is done on the server and hidden from the client, which checks permissions.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

SEE ALSO

stat(2), open(2), chmod(2), chown(2), setuid(2), setgid(2)

Linux 1.2.13, 17 March 1996

acct

acct—Switches process accounting on or off

SYNOPSIS

```
#include <unistd.h>
int acct(const char *filename);
```

DESCRIPTION

Warning: Since this function is not implemented as of Linux 0.99.11, it will always return `-1` and set `errno` to `ENOSYS`. If `acctkit` is installed, the function performs as advertised.

When called with the name of an existing file as argument, accounting is turned on and records for each terminating process are appended to `filename` as it terminates. An argument of `NULL` causes accounting to be turned off.

RETURN VALUE

On success, `0` is returned. On error, `-1` is returned and `errno` is set appropriately.

NOTES

No accounting is produced for programs running when a crash occurs. In particular, nonterminating processes are never accounted for.

SEE ALSO

acct(5)

Linux 0.99.11, 10 August 1993

adjtimex

adjtimex—Tunes kernel clock

SYNOPSIS

```
#include <sys/timex.h>
int adjtimex(struct timex *buf);
```

DESCRIPTION

Linux uses David Mill's clock adjustment algorithm. `adjtimex` reads and optionally sets adjustment parameters for this algorithm.

`adjtimex` takes a pointer to a `timex` structure, updates kernel parameters from field values, and returns the same structure with current kernel values. This structure is declared as follows:

```

struct timex
{
    int mode;           /* mode selector */
    long offset;        /* time offset (usec) */
    long frequency;     /* frequency offset (scaled ppm) */
    long maxerror;      /* maximum error (usec) */
    long esterror;      /* estimated error (usec) */
    int status;         /* clock command/status */
    long time_constant; /* pll time constant */
    long precision;     /* clock precision (usec) (read only) */
    long tolerance;     /* clock frequency tolerance (ppm)
                        (read only) */
    struct timeval time; /* (read only) */
    long tick;          /* usecs between clock ticks */
};

```

The mode field determines which parameters, if any, to set. It may contain a bitwise-or combination of zero or more of the following bits:

```

#define ADJ_OFFSET      0x0001 /* time offset */
#define ADJ_FREQUENCY   0x0002 /* frequency offset */
#define ADJ_MAXERROR    0x0004 /* maximum time error */
#define ADJ_ESTERROR    0x0008 /* estimated time error */
#define ADJ_STATUS      0x0010 /* clock status */
#define ADJ_TIMECONST   0x0020 /* pll time constant */
#define ADJ_TICK        0x4000 /* tick value */
#define ADJ_OFFSET_SINGLESHOT 0x8001 /* old-fashioned adjtime */

```

Ordinary users are restricted to a 0 value for mode. Only the superuser may set any parameters.

RETURN VALUE

On success, adjtimex returns the value of buf.status:

```

#define TIME_OK 0 /* clock synchronized */
#define TIME_INS 1 /* insert leap second */
#define TIME_DEL 2 /* delete leap second */
#define TIME_OOP 3 /* leap second in progress */
#define TIME_BAD 4 /* clock not synchronized */

```

On failure, adjtimex returns -1 and sets errno.

ERRORS

EFAULT	buf does not point to writable memory.
EPERM	buf.mode is nonzero and the user is not superuser.
EINVAL	An attempt is made to set buf.offset to a value outside the range -131071 to +131071, or to set buf.status to a value other than those listed above, or to set buf.tick to a value outside the range 900000/HZ to 1100000/HZ, where HZ is the system timer interrupt frequency.

SEE ALSO

settimeofday(2)

alarm

alarm—Sets an alarm clock for delivery of a signal

SYNOPSIS

```
#include <unistd.h>
unsigned int alarm(unsigned int seconds);
```

DESCRIPTION

alarm arranges for a **SIGALRM** signal to be delivered to the process in *seconds* seconds.

If *seconds* is 0, no new **alarm** is scheduled.

In any event, any previously set **alarm** is canceled.

RETURN VALUE

alarm returns the number of seconds remaining until any previously scheduled **alarm** was due to be delivered, or 0 if there was no previously scheduled **alarm**.

NOTES

alarm and **setitimer** share the same timer; calls to one will interfere with use of the other.

Scheduling delays can, as ever, cause the execution of the process to be delayed by an arbitrary amount of time.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

SEE ALSO

setitimer(2), **signal(2)**, **sigaction(2)**, **gettimeofday(2)**, **select(2)**, **pause(2)**, **sleep(3)**

Linux, 21 July 1993

bdflush

bdflush—Starts, flushes, or tunes the buffer-dirty-flush daemon

SYNOPSIS

```
int bdflush(int func, long *address);
int bdflush(int func, long data);
```

DESCRIPTION

bdflush starts, flushes, or tunes the buffer-dirty-flush daemon. Only the superuser may call **bdflush**.

If *func* is negative or 0 and no daemon has been started, **bdflush** enters the daemon code and never returns.

If *func* is 1, some dirty buffers are written to disk.

If *func* is 2 or more and is even (low bit is 0), *address* is the address of a long word, and the tuning parameter numbered $(\text{func}-2)/2$ is returned to the caller in that address.

If *func* is 3 or more and is odd (low bit is 1), *data* is a long word and the kernel sets tuning parameter numbered $(\text{func}-3)/2$ to that value.

The set of parameters, their values, and their legal ranges are defined in the kernel source file `fs/buffer.c`.

RETURN VALUE

If `func` is negative or 0 and the daemon successfully starts, `bindflush` never returns. Otherwise, the return value is 0 on success and -1 on failure, with `errno` set to indicate the error.

ERRORS

EPERM	Caller is not superuser.
EFAULT	address points outside your accessible address space.
EBUSY	An attempt was made to enter the daemon code after another process has already been entered.
EINVAL	An attempt was made to read or write an invalid parameter number, or to write an invalid value to a parameter.

SEE ALSO

`fsync(2)`, `sync(2)`, `update(8)`, `sync(8)`

Linux 1.2.4, 15 April 1995

bind

`bind`—Binds a name to a socket

SYNOPSIS

```
#include <sys/types.h>
#include <sys/socket.h>
int bind(int sockfd, struct sockaddr *my_addr, int addrlen);
```

DESCRIPTION

`bind` gives the socket, `sockfd`, the local address `my_addr`. `my_addr` is `addrlen` bytes long. Traditionally, this is called assigning a name to a socket. (When a socket is created with `socket(2)`, it exists in a name space—an address family—but has no name assigned.)

NOTES

Binding a name in the UNIX domain creates a socket in the file system that must be deleted by the caller—using `unlink(2)`—when it is no longer needed.

The rules used in name binding vary between communication domains. Consult the manual entries in section 4 for detailed information.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

EBADF	<code>sockfd</code> is not a valid descriptor.
EINVAL	The socket is already bound to an address. This may change in the future. See <code>linux/unix/socket.c</code> for details.
EACCES	The address is protected and the user is not the superuser.

The following errors are specific to UNIX domain (AF_UNIX) sockets:

EINVAL	<code>addrlen</code> was wrong, or the socket was not in the AF_UNIX family.
EROFS	The socket inode would reside on a read-only file system.
EFAULT	<code>my_addr</code> points outside your accessible address space.

ENAMETOOLONG	<code>my_addr</code> is too long.
ENOENT	The file does not exist.
ENOMEM	Insufficient kernel memory was available.
ENOTDIR	A component of the path prefix is not a directory.
EACCES	Search permission is denied on a component of the path prefix.
ELOOP	<code>my_addr</code> contains a circular reference (that is, via a symbolic link).

HISTORY

The `bind` function call appeared in BSD 4.2.

SEE ALSO

`accept(2)`, `connect(2)`, `listen(2)`, `socket(2)`, `getsockname(2)`

Linux 0.99.11, 23 July 1993

brk, sbrk

`brk`, `sbrk`—Change data segment size

SYNOPSIS

```
#include <unistd.h>
int brk(void *end_data_segment);
void *sbrk(ptrdiff_t increment);
```

DESCRIPTION

`brk` sets the end of the data segment to the value specified by `end_data_segment`.

`end_data_segment` must be greater than the end of the text segment and it must be 16KB before the end of the stack.

`sbrk` increments the program's data space by `increment` bytes. `sbrk` isn't a system call; it is just a C library wrapper.

RETURN VALUE

On success, `brk` returns 0, and `sbrk` returns a pointer to the start of the new area. On error, -1 is returned and `errno` is set to `ENOMEM`.

CONFORMS TO

BSD 4.3

`brk` and `sbrk` are not defined in the C standard and are deliberately excluded from the POSIX.1 standard (see paragraphs B.1.1.1.3 and B.8.3.3).

SEE ALSO

`execve(2)`, `getrlimit(2)`, `malloc(3)`, `end(3)`

Linux 0.99.11, 21 July 1993

cacheflush

`cacheflush`—Flushes contents of the instruction and/or data cache

SYNOPSIS

```
#include <asm/cachectl.h>
int cacheflush(char *addr,intnbytes,intcache);
```

DESCRIPTION

`cacheflush` flushes contents of indicated cache(s) for user addresses in the range `addr` to `(addr+nbytes-1)`. The cache may be one of the following:

ICACHE	Flush the instruction cache.
DCACHE	Write back to memory and invalidate the affected valid cache lines.
BCACHE	Same as (ICACHE DCACHE).

RETURN VALUE

`cacheflush` returns 0 on success or -1 on error. If errors are detected, `errno` will indicate the error.

ERRORS

EINVAL	The cache parameter is not one of ICACHE, DCACHE, or BCACHE.
EFAULT	Some or all of the address range <code>addr</code> to <code>(addr+nbytes-1)</code> is not accessible.

BUGS

The current implementation ignores the `addr` and `nbytes` parameters. Therefore, the whole cache is always flushed.

NOTE

This system call is only available on MIPS-based systems.

SEE ALSO

`cachectl(2)`

Linux, 27 June 95

chdir, fchdir

`chdir`, `fchdir`—Changes the working directory

SYNOPSIS

```
#include <unistd.h>
int chdir(const char *path);
int fchdir(int fd);
```

DESCRIPTION

`chdir` changes the current directory to that specified in `path`.

`fchdir` is identical to `chdir`, only the directory is given as an open file descriptor.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

Depending on the file system, other errors can be returned. The more general errors are listed here:

EPERM	The process does not have execute permission on the directory.
EFAULT	<code>path</code> points outside your accessible address space.
ENAMETOOLONG	<code>path</code> is too long.

EBADF	<code>fd</code> is not a valid file descriptor.
ENOENT	The file does not exist.
ENOMEM	Insufficient kernel memory was available.
ENOTDIR	A component of the path prefix is not a directory.
EACCES	Search permission is denied on a component of the path prefix.
ELOOP	path contains a circular reference (that is, via a symbolic link)

SEE ALSO

`getcwd(3)`, `chroot(2)`

Linux 1.2.4, 15 April 1995

chmod, fchmod

`chmod`, `fchmod`—Changes permissions of a file

SYNOPSIS

```
#include <sys/types.h>
#include <sys/stat.h>
int chmod(const char *path, mode_t mode);
int fchmod(int fd, mode_t mode);
```

DESCRIPTION

The mode of the file given by `path` or referenced by `fd` is changed.

Modes are specified by or'ing the following:

<code>S_ISUID</code>	04000 Set user ID on execution
<code>S_ISGID</code>	02000 Set group ID on execution
<code>S_ISVTX</code>	01000 Sticky bit
<code>S_IRUSR</code> (<code>S_IREAD</code>)	00400 Read by owner
<code>S_IWUSR</code> (<code>S_IWRITE</code>)	00200 Write by owner
<code>S_IXUSR</code> (<code>S_IEXEC</code>)	00100 Execute/search by owner
<code>S_IRGRP</code>	00040 Read by group
<code>S_IWGRP</code>	00020 Write by group
<code>S_IXGRP</code>	00010 Execute/search by group
<code>S_IROTH</code>	00004 Read by others
<code>S_IWOTH</code>	00002 Write by others
<code>S_IXOTH</code>	00001 Execute/search by others

The effective UID of the process must be 0 or must match the owner of the file.

The effective UID or GID must be appropriate for setting execution bits.

Depending on the file system, set user ID and set group ID execution bits may be turned off if a file is written. On some file systems, only the superuser can set the sticky bit, which may have a special meaning (that is, for directories, a file can only be deleted by the owner or the superuser).

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and `errno` is set appropriately.

ERRORS

Depending on the file system, other errors can be returned. The more general errors for `chmod` are listed here:

<code>EPERM</code>	The effective UID does not match the owner of the file and is not 0.
<code>EROFS</code>	The named file resides on a read-only file system.
<code>EFAULT</code>	path points outside your accessible address space.
<code>ENAMETOOLONG</code>	path is too long.
<code>ENOENT</code>	The file does not exist.
<code>ENOMEM</code>	Insufficient kernel memory was available.
<code>ENOTDIR</code>	A component of the path prefix is not a directory.
<code>EACCES</code>	Search permission is denied on a component of the path prefix.
<code>ELoop</code>	path contains a circular reference (that is, via a symbolic link)

The general errors for `fchmod` are listed here:

<code>EBADF</code>	The descriptor is not value.
<code>ENOENT</code>	See above.
<code>EPERM</code>	See above.
<code>EROFS</code>	See above.

SEE ALSO

`open(2)`, `chown(2)`, `stat(2)`

Linux 0.99.11, 21 July 1993

chown, fchown

`chown`, `fchown`—Changes ownership of a file

SYNOPSIS

```
#include <sys/types.h>
#include <unistd.h>
int chown(const char *path, uid_t owner, gid_t group);
int fchown(int fd, uid_t owner, gid_t group);
```

DESCRIPTION

The owner of the file specified by `path` or by `fd` is changed. Only the superuser may change the owner of a file. The owner of a file may change the group of the file to any group of which that owner is a member. The superuser may change the group arbitrarily.

If the `owner` or `group` is specified as `-1`, that ID is not changed.

RETURN VALUE

On success, `0` is returned. On error, `-1` is returned and `errno` is set appropriately.

ERRORS

Depending on the file system, other errors can be returned. The more general errors for `chown` are listed here:

<code>EPERM</code>	The effective UID does not match the owner of the file, and is not 0; or the <code>owner</code> or <code>group</code> were specified incorrectly.
<code>EROFS</code>	The named file resides on a read-only file system.
<code>EFAULT</code>	path points outside your accessible address space.

ENAMETOOLONG	path is too long.
ENOENT	The file does not exist.
ENOMEM	Insufficient kernel memory was available.
ENOTDIR	A component of the path prefix is not a directory.
EACCES	Search permission is denied on a component of the path prefix.
ELOOP	path contains a circular reference (that is, via a symbolic link).

The general errors for `fchown` are listed here:

EBADF	The descriptor is not value.
ENOENT	See above.
EPERM	See above.
EROFS	See above.

NOTES

`chown` does not follow symbolic links. The prototype for `fchown` is only available if `USE BSD` is defined.

SEE ALSO

`chmod(2)`, `flock(2)`

Linux 0.99.11, 21 July 1993

chroot

`chroot`—Changes root directory

SYNOPSIS

```
#include <unistd.h>
int chroot(const char *path);
```

DESCRIPTION

`chroot` changes the root directory to that specified in `path`. This directory will be used for pathnames beginning with `/`. The root directory is inherited by all children of the current process.

Only the superuser may change the root directory.

Note that this call does not change the current working directory, so that `.` can be outside the tree rooted at `/`.

RETURN VALUE

On success, `0` is returned. On error, `-1` is returned and `errno` is set appropriately.

ERRORS

Depending on the file system, other errors can be returned. The more general errors are listed here:

EPERM	The effective UID does not match the owner of the file, and is not 0; or the owner or group were specified incorrectly.
EROFS	The named file resides on a read-only file system.
EFAULT	path points outside your accessible address space.
ENAMETOOLONG	path is too long.
ENOENT	The file does not exist.
ENOMEM	Insufficient kernel memory was available.

ENOTDIR

A component of the path prefix is not a directory.

EACCES

Search permission is denied on a component of the path prefix.

ELOOP

path contains a circular reference (that is, via a symbolic link)

SEE ALSO

chdir(2)

Linux 1.1.46, 21 August 1994

clone

clone—Creates a child process

SYNOPSIS

#include <linux/sched.h>

#include <linux/unistd.h>

pid_t clone(void *sp, unsigned long flags);

DESCRIPTION

clone is an alternate interface to fork, with more options. fork is equivalent to clone(0, SIGCLD|COPYVM).

If sp is nonzero, the child process uses sp as its initial stack pointer.

The low byte of flags contains the signal sent to the parent when the child dies. flags may also be bitwise ored with either or both of COPYVM and COPYFD.

If COPYVM is set, child pages are copy-on-write images of the parent pages. If COPYVM is not set, the child process shares the same pages as the parent, and both parent and child may write on the same data.

If COPYFD is set, the child's file descriptors are copies of the parent's file descriptors. If COPYFD is not set, the child's file descriptors are shared with the parent.

RETURN VALUE

On success, the PID of the child process is returned in the parent's thread of execution, and 0 is returned in the child's thread of execution. On failure, a -1 will be returned in the parent's context, no child process will be created, and errno will be set appropriately.

ERRORS

ENOSYS

clone will always return this error, unless your kernel was compiled with CLONE_ACTUALLY_WORKS_OK defined.

EAGAIN

fork cannot allocate sufficient memory to copy the parent's page tables and allocate a task structure for the child.

BUGS

By default, CLONE_ACTUALLY_WORKS_OK is not defined.

There is no entry for clone in /lib/libc.so.4.5.26.

Comments in the kernel as of 1.1.46 indicate that it mishandles the case where COPYVM is not set.

SEE ALSO

fork(2)

Linux 1.2.9, 10 June 1995

close

`close`—Closes a file descriptor

SYNOPSIS

```
#include <unistd.h>
int close(int fd);
```

DESCRIPTION

`close` closes a file descriptor so that it no longer refers to any file and may be reused. Any locks held on the file it was associated with, and owned by the process, are removed (regardless of the file descriptor that was used to obtain the lock).

If `fd` is the last copy of a particular file descriptor, the resources associated with it are freed; if the descriptor was the last reference to a file that has been removed using `unlink`, the file is deleted.

RETURN VALUE

`close` returns 0 on success, or -1 if an error occurred.

ERRORS

`EBADF` `fd` isn't a valid open file descriptor.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

NOTES

Not checking the return value of `close` is a common but nevertheless serious programming error. File system implementations that use techniques as write-behind to increase performance may lead to `write(2)` succeeding, although the data has not been written yet. The error status may be reported at a later write operation, but it is guaranteed to be reported on closing the file. Not checking the return value when closing the file may lead to silent loss of data. This can especially be observed with NFS and disk quotas.

SEE ALSO

`open(2)`, `fcntl(2)`, `shutdown(2)`, `unlink(2)`, `fclose(3)`

14 April 1996

connect

`connect`—Initiates a connection on a socket

SYNOPSIS

```
#include <sys/types.h>
#include <sys/socket.h>
int connect(int sockfd, struct sockaddr *serv_addr, int addrlen);
```

DESCRIPTION

The parameter `sockfd` is a socket. If it is of type `SOCK_DGRAM`, this call specifies the peer with which the socket is to be associated; this address is that to which datagrams are to be sent, and the only address from which datagrams are to be received. If the socket is of type `SOCK_STREAM`, this call attempts to make a connection to another socket. The other socket is

specified by `serv_addr`, which is an address in the communications space of the socket. Each communications space interprets the `serv_addr` parameter in its own way. Generally, stream sockets may successfully connect only once; datagram sockets may use `connect` multiple times to change their association. Datagram sockets may dissolve the association by connecting to an invalid address, such as a null address.

RETURN VALUE

If the connection or binding succeeds, 0 is returned. On error, -1 is returned and `errno` is set appropriately.

ERRORS

See the Linux kernel source code for details.

HISTORY

The `connect` function call first appeared in BSD 4.2.

SEE ALSO

`accept(2)`, `bind(2)`, `listen(2)`, `socket(2)`, `getsockname(2)`

Linux 0.99.11, 23 July 1993

dup, dup2

`dup`, `dup2`—Duplicate a file descriptor

SYNOPSIS

```
#include <unistd.h>
int dup(int oldfd);
int dup2(int oldfd, int newfd);
```

DESCRIPTION

`dup` and `dup2` create a copy of the file descriptor `oldfd`.

The old and new descriptors can be used interchangeably. They share locks, file position pointers and flags; for example, if the file position is modified by using `lseek` on one of the descriptors, the position is also changed for the other.

The two descriptors do not share the close-on-exec flag, however.

`dup` uses the lowest-numbered unused descriptor for the new descriptor.

`dup2` makes `newfd` be the copy of `oldfd`, closing `newfd` first if necessary.

RETURN VALUE

`dup` and `dup2` return the new descriptor, or -1 if an error occurred (in which case `errno` is set appropriately).

ERRORS

<code>EBADF</code>	<code>oldfd</code> isn't an open file descriptor, or <code>newfd</code> is out of the allowed range for file descriptors.
<code>EMFILE</code>	The process already has the maximum number of file descriptors open and tried to open a new one.

WARNING

The error returned by `dup2` is different from that returned by `fcntl(..., F_DUPFD, ...)` when `newfd` is out of range. On some systems `dup2` also sometimes returns `EINVAL` like `F_DUPFD`.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

SEE ALSO

`fcntl(2)`, `open(2)`, `close(2)`.

Linux 1.1.46, 21 August 1994

execve

`execve`—Execute program

SYNOPSIS

```
#include <unistd.h>
int execve (const char *filename, const char *argv [], const char *envp[]);
```

DESCRIPTION

`execve()` executes the program pointed to by `filename`. `filename` must be either a binary executable or a shell script starting with a line in the format `#! interpreter [arg]`.

`execve()` does not return on success, and the text, data, bss, and stack of the calling process are overwritten by that of the program loaded. The program invoked inherits the calling process's PID, and any open file descriptors that are not set to close on exec. Signals pending on the parent process are cleared.

If the current program is being ptraced, a SIGTRAP is sent to it after a successful `execve()`.

RETURN VALUE

On success, `execve()` does not return; on error `-1` is returned and `errno` is set appropriately.

ERRORS

EACCES	The file is not a regular file.
EACCES	Execute permission is denied for the file.
EPERM	The file system is mounted <code>noexec</code> .
EPERM	The file system is mounted <code>nosuid</code> and the file has an SUID or SGID bit set.
E2BIG	The argument list is too big.
ENOEXEC	The magic number in the file is incorrect.
EFAULT	<code>filename</code> points outside your accessible address space.
ENAMETOOLONG	<code>filename</code> is too long.
ENOENT	The file does not exist.
ENOMEM	Insufficient kernel memory was available.
ENOTDIR	A component of the path prefix is not a directory.
EACCES	Search permission is denied on a component of the path prefix.
ELoop	<code>filename</code> contains a circular reference (that is, via a symbolic link).

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

NOTES

SUID and SGID processes can not be `ptrace()`'d SUID or SGID.

A maximum line length of 127 characters is allowed for the first line in a `#!` executable shell script. This may be circumvented by changing the max size of `buf`, in which case you will become bound by the 1024 byte size of a buffer, which is not easily worked around.

SEE ALSO

`exec1(3)`, `fork(2)`

Linux 1.1.46, 21 August 1994

fcntl

fcntl—Manipulate file descriptor

SYNOPSIS

```
#include <unistd.h>
#include <fcntl.h>
int fcntl(int fd,intcmd);
int fcntl(int fd,intcmd,longarg);
```

DESCRIPTION

`fcntl` performs one of various miscellaneous operations on `fd`. The operation in question is determined by `cmd`:

<code>F_DUPFD</code>	Makes <code>arg</code> be a copy of <code>fd</code> , closing <code>fd</code> first if necessary. The same functionality can be more easily achieved by using <code>dup2(2)</code> . The old and new descriptors may be used interchangeably. They share locks, file position pointers, and flags; for example, if the file position is modified by using <code>lseek</code> on one of the descriptors, the position is also changed for the other. The two descriptors do not share the close-on-exec flag, however. On success, the new descriptor is returned.
<code>F_GETFD</code>	Read the close-on-exec flag. If the low-order bit is 0, the file will remain open across <code>exec</code> ; otherwise, it will be closed.
<code>F_SETFD</code>	Set the close-on-exec flag to the value specified by <code>arg</code> (only the least significant bit is used).
<code>F_GETFL</code>	Read the descriptor's flags (all flags—as set by <code>open(2)</code> —are returned).
<code>F_SETFL</code>	Set the descriptor's flags to the value specified by <code>arg</code> . Only <code>O_APPEND</code> and <code>O_NONBLOCK</code> may be set. The flags are shared between copies (made with <code>dup</code> and so on) of the same file descriptor. The flags and their semantics are described in <code>open(2)</code> .
<code>F_GETLK</code> , <code>F_SETLK</code> , and <code>F_SETLKW</code>	Manage discretionary file locks. The third argument <code>arg</code> is a pointer to a struct <code>flock</code> (that may be overwritten by this call).
<code>F_GETLK</code>	Return the <code>flock</code> structure that prevents us from obtaining the lock, or set the <code>l_type</code> field of the lock to <code>F_UNLCK</code> if there is no obstruction.
<code>F_SETLK</code>	The lock is set (when <code>l_type</code> is <code>F_RDLCK</code> or <code>F_WRLCK</code>) or cleared (when it is <code>F_UNLCK</code>). If the lock is held by someone else, this call returns <code>-1</code> and sets <code>errno</code> to <code>EACCES</code> or <code>EAGAIN</code> .
<code>F_SETLKW</code>	Like <code>F_SETLK</code> , but instead of returning an error, we wait for the lock to be released.
<code>F_GETOWN</code>	Get the process ID (or process group) of the owner of a socket. Process groups are returned as negative values.
<code>F_SETOWN</code>	Set the process or process group that owns a socket. For these commands, ownership means receiving <code>SIGIO</code> or <code>SIGURG</code> signals. Process groups are specified using negative values.

RETURN VALUE

The return value depends on the operation:

<code>F_DUPFD</code>	The new descriptor.
<code>F_GETFD</code>	Value of flag.
<code>F_GETFL</code>	Value of flags.
<code>F_GETOWN</code>	Value of descriptor owner.

On error, `-1` is returned and `errno` is set appropriately.

ERRORS

<code>EBADF</code>	<code>fd</code> is not an open file descriptor.
<code>EINVAL</code>	For <code>F_DUPFD</code> , <code>arg</code> is negative or is greater than the maximum allowable value.
<code>EMFILE</code>	For <code>F_DUPFD</code> , the process already has the maximum number of file descriptors open.

NOTES

The errors returned by `dup2` are different from those returned by `F_DUPFD`.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

SEE ALSO

`dup2(2)`, `open(2)`, `socket(2)`.

Linux, 26 September 1995

fdatasync

`fdatasync`—Synchronizes a file's in-core data with that on disk

SYNOPSIS

```
#include <unistd.h>
#ifdef POSIX SYNCHRONIZED IO
int fdatasync(int fd);
#endif
```

DESCRIPTION

`fdatasync` flushes all data buffers of a file to disk (before the system call returns). It resembles `fsync` but is not required to update the metadata such as access time.

Applications that access databases or log files often write a tiny data fragment (for example, one line in a log file) and then call `fsync` immediately in order to ensure that the written data is physically stored on the hard disk. Unfortunately, `fsync` will always initiate two write operations: one for the newly written data and another one in order to update the modification time stored in the inode. If the modification time is not a part of the transaction concept `fdatasync` can be used to avoid unnecessary inode disk write operations.

RETURN VALUE

On success, `0` is returned. On error, `-1` is returned and `errno` is set appropriately.

ERRORS

EBADF	<code>fd</code> is not a valid file descriptor open for writing.
EROFS, EINVAL	<code>fd</code> is bound to a special file which does not support synchronization.
EIO	An error occurred during synchronization.

BUGS

Currently (Linux 1.3.86) `fdatasync` is equivalent to `fsync`.

CONFORMS TO

POSIX.4

SEE ALSO

`fsync(2)`, B.O. Gallmeister, *POSIX.4*, O'Reilly, pp. 220–223, 343.

Linux 1.3.86, 13 April 1996

flock

`flock`—Applies or removes an advisory lock on an open file

SYNOPSIS

```
#include <sys/file.h>
int flock(int fd,intoperation);
```

DESCRIPTION

Apply or remove an advisory lock on an open file. The file is specified by `fd`. Valid operations are given here:

LOCK_SH	Shared lock. More than one process may hold a shared lock for a given file at a given time.
LOCK_EX	Exclusive lock. Only one process may hold an exclusive lock for a given file at a given time.
LOCK_UN	Unlock.
LOCK_NB	Don't block when locking. May be specified (by or'ing) along with one of the other operations. A single file may not have both shared and exclusive locks. A file is locked (that is, the inode), <i>not</i> the file descriptor. So, <code>dup(2)</code> and <code>fork(2)</code> do not create multiple instances of a lock.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and `errno` is set appropriately.

ERRORS

EWOLDBLOCK	The file is locked and the <code>LOCK_NB</code> flag was selected.

NOTES

Under Linux, `flock` is implemented as a call to `fcntl`. Please see `fcntl(2)` for more details on errors.

SEE ALSO

`open(2)`, `close(2)`, `dup(2)`, `execve(2)`, `fcntl(2)`, `fork(2)`

Linux 0.99.11, 22 July 1993

fork, vfork

fork, vfork—Creates a child process

SYNOPSIS

```
#include <unistd.h>
pid_t fork(void);
pid_t vfork(void);
```

DESCRIPTION

fork creates a child process that differs from the parent process only in its PID and PPID, and in the fact that resource utilizations are set to 0. File locks and pending signals are not inherited.

Under Linux, fork is implemented using copy-on-write pages, so the only penalties incurred by fork are the time and memory required to duplicate the parent's page tables and to create a unique task structure for the child.

RETURN VALUE

On success, the PID of the child process is returned in the parent's thread of execution, and a 0 is returned in the child's thread of execution. On failure, a -1 will be returned in the parent's context, no child process will be created, and errno will be set appropriately.

ERRORS

EAGAIN	fork cannot allocate sufficient memory to copy the parent's page tables and allocate a task structure for the child.

BUGS

Under Linux, vfork is merely an alias for fork. fork never returns the error ENOMEM.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

SEE ALSO

clone(2), execve(2), wait(2)

Linux 1.2.9, 10 June 1995

fsync

fsync—Synchronizes a file's complete in-core state with that on disk

SYNOPSIS

```
#include <unistd.h>
int fsync(int fd);
```

DESCRIPTION

fsync copies all in-core parts of a file to disk.

In some applications, fdatasync is a more efficient alternative to fsync.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and errno is set appropriately.

ERRORS

EBADF	<code>fd</code> is not a valid file descriptor open for writing.
EROFS, EINVAL	<code>fd</code> is bound to a special file that does not support synchronization.
EIO	An error occurred during synchronization.

CONFORMS TO

POSIX.1b

SEE ALSO

bdflush(2), fdatsync(2), sync(2), update(8), sync(8)

Linux 1.3.85, 13 April 1996

getdents

getdents—Gets directory entries

SYNOPSIS

```
#include <unistd.h>
#include <linux/dirent.h>
#include <linux/unistd.h>
syscall3(int, getdents, uint, fd, struct dirent *, dirp, uint, count);
int getdents(unsigned int fd, struct dirent *dirp, unsigned int count);
```

DESCRIPTION

`getdents` reads several `dirent` structures from the directory pointed at by `fd` into the memory area pointed to by `dirp`. The parameter `count` is the size of the memory area.

The `dirent` structure is declared as follows:

```
struct dirent
{
    long d_ino;           /* inode number */
    off_t d_off;          /* offset to next dirent */
    unsigned short d_reclen; /* length of this dirent */
    char d_name [NAME_MAX+1]; /* file name (null-terminated) */
}
```

`d_ino` is an inode number. `d_off` is the distance from the start of the directory to the start of the next `dirent`. `d_reclen` is the size of this entire `dirent`. `d_name` is a null-terminated filename.

This call supersedes `readdir(2)`.

RETURN VALUE

On success, the number of bytes read is returned. On end of directory, 0 is returned. On error, -1 is returned and `errno` is set appropriately.

ERRORS

EBADF	Invalid file descriptor <code>fd</code> .
ENOTDIR	File descriptor does not refer to a directory.

SEE ALSO

readdir(2), readdir(3)

Linux 1.3.6, 22 July 1995

getdomainname, setdomainname

getdomainname, setdomainname—Gets/sets domain name

SYNOPSIS

```
#include <unistd.h>
int getdomainname(char *name, size_t len);
int setdomainname(const char *name, size_t len);
```

DESCRIPTION

These functions are used to access or to change the domain name of the current processor.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and `errno` is set appropriately.

ERRORS

EINVAL	For <code>getdomainname</code> , <code>name</code> points to NULL or <code>name</code> is longer than <code>len</code> .
EPERM	For <code>setdomainname</code> , the caller was not the superuser.
EINVAL	For <code>setdomainname</code> , <code>len</code> was too long.

CONFORMS TO

POSIX does not specify these calls.

BUGS

`getdomainname` is not compliant with other implementations because they always return `len` bytes, even if `name` is longer. Linux, however, returns `EINVAL` in this case (as of DLL 4.4.1 libraries).

NOTES

Under Linux, `getdomainname` is implemented at the library level by calling `uname(2)`.

SEE ALSO

`gethostname(2)`, `sethostname(2)`, `uname(2)`

Linux 0.99.11, 22 July 1993

getdtablesize

getdtablesize—Gets descriptor table size

SYNOPSIS

```
#include <unistd.h>
int getdtablesize(void);
```

DESCRIPTION

`getdtablesize` returns the maximum number of files a process can have open.

NOTES

`getdtablesize` is implemented as a library function in DLL 4.4.1. This function returns `OPEN_MAX` (set to 256 in Linux 0.99.11) if `OPEN_MAX` was defined when the library was compiled. Otherwise, -1 is returned and `errno` is set to `ENOSYS`.

SEE ALSO

close(2), dup(2), open(2)

Linux 0.99.11, 22 July 1993

getgid, getegid

getgid, getegid—Gets group identity

SYNOPSIS

```
#include <unistd.h>
gid_t getgid(void);
gid_t getegid(void);
```

DESCRIPTION

getgid returns the real group ID of the current process.

getegid returns the effective group ID of the current process.

The real ID corresponds to the ID of the calling process. The effective ID corresponds to the set ID bit on the file being executed.

ERRORS

These functions are always successful.

CONFORMS TO

POSIX, BSD 4.3

SEE ALSO

setregid(2), setgid(2)

Linux 0.99.11, 23 July 1993

getgroups, setgroups

getgroups, setgroups—Gets/sets group access list

SYNOPSIS

```
#include <unistd.h>
int getgroups(int size, gid_t list[]);
#define _USE_BSD
#include <grp.h>
int setgroups(size_t size, const gid_t *list);
```

DESCRIPTION

getgroups

Up to size supplemental groups are returned in list. If size is 0, list is not modified, but the total number of supplemental groups for the process is returned.

setgroups

Sets the supplemental groups for the process. Only the superuser may use this function.

RETURN VALUE

<code>getgroups</code>	On success, the number of groups stored in <i>list</i> is returned (if <i>size</i> is 0, however, the number of supplemental group IDs associated with the process is returned). On error, -1 is returned and <code>errno</code> is set appropriately.
<code>setgroups</code>	On success, 0 is returned. On error, -1 is returned and <code>errno</code> is set appropriately.

ERRORS

<code>EFAULT</code>	<i>list</i> has an invalid address.
<code>EPERM</code>	For <code>setgroups</code> , the user is not the superuser.
<code>EINVAL</code>	For <code>setgroups</code> , <code>gidsetsize</code> is greater than <code>NGROUPS</code> (32 for Linux 0.99.11).

CONFORMS TO

`getgroups` conforms to POSIX.1 (and is present in BSD 4.3). Since `setgroups` requires privilege, it is not covered under POSIX.1.

BUGS

The `USE_BSD` flag probably shouldn't be required for `setgroups`.

SEE ALSO

`initgroups(3)`

Linux 0.99.11, 23 July 1993

gethostid, sethostid

`gethostid, sethostid`—Gets/sets the unique identifier of the current host

SYNOPSIS

```
#include <unistd.h>

long int gethostid(void);
int sethostid(long int hostid);
```

DESCRIPTION

Get or set a unique 32-bit identifier for the current machine. The 32-bit identifier is intended to be unique among all UNIX systems in existence. This normally resembles the Internet address for the local machine, as returned by `gethostbyname(3)`, and thus usually never needs to be set.

The `sethostid` call is restricted to the superuser.

The `hostid` argument is stored in the file `/etc/hostid`.

RETURN VALUES

`gethostid` returns the 32-bit identifier for the current host as set by `sethostid(2)`.

CONFORMS TO

POSIX.1 does not define these functions, but ISO/IEC 9945-1:1990 mentions them in B.4.4.1.

FILES

`/etc/hostid`

SEE ALSO

hostid(1), gethostbyname(3)

Linux 0.99.13, 29 November 1993

gethostname, sethostname

gethostname, sethostname—Gets/sets hostname

SYNOPSIS

```
#include <unistd.h>
int gethostname(char *name, size_t len);
int sethostname(const char *name, size_t len);
```

DESCRIPTION

These functions are used to access or to change the hostname of the current processor.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and `errno` is set appropriately.

ERRORS

EINVAL	<code>len</code> is negative or, for <code>sethostname</code> , larger than the maximum allowed size. For <code>gethostname</code> on Linux/i386, <code>len</code> is smaller than the actual size.
EPERM	For <code>sethostname</code> , the caller was not the superuser.
EFAULT	<code>name</code> is an invalid address.

CONFORMS TO

POSIX.1 does not define these functions, but ISO/IEC 9945-1:1990 mentions them in B.4.4.1.

BUGS

Some other implementations of `gethostname` successfully return `len` bytes even if `name` is longer. Linux/Alpha complies with this behavior. Linux/i386, however, returns `EINVAL` in this case (as of DLL 4.6.27 libraries).

NOTES

Under Linux/Alpha, `gethostname` is a system call. Under Linux/i386, `gethostname` is implemented at the library level by calling `uname(2)`.

SEE ALSO

getdomainname(2), setdomainname(2), `uname(2)`

Linux 1.3.6, 22 July 1995

getitimer, setitimer

getitimer, setitimer—Gets/sets value of an interval timer

SYNOPSIS

```
#include <sys/time.h>
int getitimer(int which, struct itimerval *value);
int setitimer(int which, const struct itimerval *value, struct itimerval *ovalue);
```

DESCRIPTION

The system provides each process with three interval timers, each decrementing in a distinct time domain. When any timer expires, a signal is sent to the process, and the timer (potentially) restarts.

ITIMER_REAL	Decrements in real time and delivers SIGALRM upon expiration.
ITIMER_VIRTUAL	Decrements only when the process is executing, and delivers SIGVTALRM upon expiration.
ITIMER_PROF	Decrements both when the process executes and when the system is executing on behalf of the process. Coupled with ITIMER_VIRTUAL, this timer is usually used to profile the time spent by the application in user and kernel space. SIGPROF is delivered upon expiration.

Timer values are defined by the following structures:

```
struct itimerval {
    struct timeval it_interval; /* next value */
    struct timeval it_value;   /* current value */
};
struct timeval {
    long tv_sec;               /* seconds */
    long tv_usec;             /* microseconds */
};
```

getitimer(2) fills the structure indicated by value with the current setting for the timer indicated by which (one of ITIMER_REAL, ITIMER_VIRTUAL, or ITIMER_PROF). The element it_value is set to the amount of time remaining on the timer, or 0 if the timer is disabled. Similarly, it_interval is set to the reset value. setitimer(2) sets the indicated timer to the value in value. If ovalue is nonzero, the old value of the timer is stored there.

Timers decrement from it_value to 0, generate a signal, and reset to it_interval. A timer that is set to 0 (it_value is 0 or the timer expires and it_interval is 0) stops.

Both tv_sec and tv_usec are significant in determining the duration of a timer.

Timers will never expire before the requested time, instead expiring some short, constant time afterward, dependent on the system timer resolution (currently 10ms). Upon expiration, a signal will be generated and the timer reset. If the timer expires while the process is active (always true for ITIMER_VIRT), the signal will be delivered immediately when generated. Otherwise, the delivery will be offset by a small time dependent on the system loading.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and errno is set appropriately.

ERRORS

EFAULT	value and ovalue are not valid pointers.
EINVAL	which is not one of ITIMER_REAL, ITIMER_VIRT, or ITIMER_PROF.

SEE ALSO

gettimeofday(2), sigaction(2), signal(2)

BUGS

Under Linux, the generation and delivery of a signal are distinct and there each signal is permitted only one outstanding event. It's therefore conceivable that under pathologically heavy loading, ITIMER_REAL will expire before the signal from a previous expiration has been delivered. The second signal in such an event will be lost.

Linux 0.99.11, 5 August 1993

getpagesize

getpagesize—Gets system page size

SYNOPSIS

```
#include <unistd.h>
size_t getpagesize(void);
```

DESCRIPTION

Returns the number of bytes in a page. This is the system's page size, which is not necessarily the same as the hardware page size.

NOTES

getpagesize is implemented as a library function in DLL 4.4.1. Depending on what is defined when the library is compiled, this function returns EXEC_PAGESIZE (set to 4096 in Linux 0.99.11), NBPG (set to 4096 in Linux 0.99.11), or NBPG (not defined in Linux 0.99.11 or DLL 4.4.1 libraries).

SEE ALSO

sbrk(2)

Linux 0.99.11, 23 July 1993

getpeername

getpeername—Gets the name of the connected peer

SYNOPSIS

```
int getpeername(int s, struct sockaddr *name, int*namelen);
```

DESCRIPTION

getpeername returns the name of the peer connected to socket *s*. The *namelen* parameter should be initialized to indicate the amount of space pointed to by *name*. On return it contains the actual size of the name returned (in bytes). The name is truncated if the buffer provided is too small.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and *errno* is set appropriately.

ERRORS

EBADF	The argument <i>s</i> is not a valid descriptor.
ENOTSOCK	The argument <i>s</i> is a file, not a socket.
ENOTCONN	The socket is not connected.
ENOBUFS	Insufficient resources were available in the system to perform the operation.
EFAULT	The <i>name</i> parameter points to memory not in a valid part of the process address space.

HISTORY

The *getpeername* function call appeared in BSD 4.2.

SEE ALSO

accept(2), bind(2), getsockname(2)

BSD Man Page, 24 July 1993

getpid, getppid

getpid, getppid—Gets process identification

SYNOPSIS

```
#include <unistd.h>
pid_t getpid(void);
pid_t getppid(void);
```

DESCRIPTION

getpid returns the process ID of the current process. (This is often used by routines that generate unique temporary filenames.)

getppid returns the process ID of the parent of the current process.

CONFORMS TO

POSIX, BSD 4.3, SVID

SEE ALSO

exec(2), fork(2), kill(2), mkstemp(3), tmpnam(3), tempnam(3), tmpfile(3)

Linux 0.99.11, 23 July 1993

getpriority, setpriority

getpriority, setpriority—Gets/sets program scheduling priority

SYNOPSIS

```
#include <sys/time.h>
#include <sys/resource.h>
int getpriority(int which,int who);
int setpriority(int which,int who,int prio);
```

DESCRIPTION

The scheduling priority of the process, process group, or user, as indicated by *which* and *who*, is obtained with the `getpriority` call and set with the `setpriority` call. *which* is one of `PRIO_PROCESS`, `PRIO_PGRP`, or `PRIO_USER`, and *who* is interpreted relative to *which* (a process identifier for `PRIO_PROCESS`, process group identifier for `PRIO_PGRP`, and a user ID for `PRIO_USER`). A 0 value of *who* denotes the current process, process group, or user. *prio* is a value in the range -20 to 20. The default priority is 0; lower priorities cause more favorable scheduling.

The `getpriority` call returns the highest priority (lowest numerical value) enjoyed by any of the specified processes. The `setpriority` call sets the priorities of all the specified processes to the specified value. Only the superuser may lower priorities.

RETURN VALUES

Because `getpriority` can legitimately return the value -1, it is necessary to clear the external variable `errno` prior to the call, and then check it afterward to determine whether a -1 is an error or a legitimate value. The `setpriority` call returns 0 if there is no error, or -1 if there is.

ERRORS

ESRCH
EINVAL

No process was located using the *which* and *who* values specified.
which was not one of `PRIO_PROCESS`, `PRIO_PGRP`, or `PRIO_USER`.

In addition to these errors, setpriority will fail with the following:

EPERM	A process was located, but neither its effective nor real user ID matched the effective user ID of the caller.
EACCES	A nonsuperuser attempted to lower a process priority.

HISTORY

These function calls appeared in BSD 4.2.

SEE ALSO

nice(1), fork(2), renice(8)

BSD Man Page, 24 July 1993

getrlimit, getrusage, setrlimit

getrlimit, getrusage, setrlimit—Get/set resource limits and usage

SYNOPSIS

```
#include <sys/time.h>
#include <sys/resource.h>
#include <unistd.h>

int getrlimit (int resource, struct rlimit *rlim);
int getrusage (int who, struct rusage *usage);
int setrlimit (int resource, const struct rlimit *rlim);
```

DESCRIPTION

getrlimit and setrlimit get and set resource limits. resource should be one of the following:

```
RLIMIT CPU /* CPU time in seconds */
RLIMIT FSIZE /* Maximum filesize */
RLIMIT DATA /* max data size */
RLIMIT STACK /* max stack size */
RLIMIT CORE /* max core file size */
RLIMIT RSS /* max resident set size */
RLIMIT NPROC /* max number of processes */
RLIMIT NOFILE /* max number of open files */
RLIMIT MEMLOCK /* max locked-in-memory address space*/
```

A resource may be unlimited if you set the limit to RLIM_INFINITY. RLIMIT_OFILE is the BSD name for RLIMIT_NOFILE.

The rlimit structure is defined as follows :

```
struct rlimit
{
    int rlim_cur;
    int rlim_max;
};
```

getrusage returns the current resource usages for a who of either RUSAGE_SELF or RUSAGE_CHILDREN:

```
struct rusage
{
    struct timeval ru_utime; /* user time used */
    struct timeval ru_stime; /* system time used */
    long ru_maxrss; /* maximum resident set size */
    long ru_ixrss; /* integral shared memory size */
};
```

```

    long ru_idrss;           /* integral unshared data size */
    long ru_isrss;           /* integral unshared stack size */
    long ru_minflt;         /* page reclaims */
    long ru_majflt;         /* page faults */
    long ru_nswap;          /* swaps */
    long ru_inblock;        /* block input operations */
    long ru_oublock;        /* block output operations */
    long ru_msgsnd;         /* messages sent */
    long ru_msgrcv;         /* messages received */
    long ru_nsignals;       /* signals received */
    long ru_nvcsw;          /* voluntary context switches */
    long ru_nivcsw;         /* involuntary context switches */
};

```

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and `errno` is set appropriately.

ERRORS

EINVAL	getrlimit or setrlimit is called with a bad resource. getrusage is called with a bad who.
EPERM	A nonsuperuser tries to use setrlimit() to increase the soft or hard limit above the current hard limit, or a superuser tries to increase RLIMIT_NOFILE above the current kernel maximum.

CONFORMS TO

BSD 4.3

SEE ALSO

`ulimit(2)`, `quota(2)`

Linux, 23 July 1993

getsid

getsid—Gets session ID

SYNOPSIS

```

#include <unistd.h>
pid_t getsid(void);

```

DESCRIPTION

`getsid(0)` returns the session ID of the calling process. `getsid(p)` returns the session ID of the process with process ID `p`.

ERRORS

On error, -1 will be returned. The only error that can happen is `ESRCH`, when no process with process ID `p` was found.

CONFORMS TO

This call is Linux specific.

SEE ALSO

`setsid(2)`

Linux 1.3.85, 11 April 1996

getsockname

getsockname—Gets socket name

SYNOPSIS

```
int getsockname(int s, struct sockaddr * name, int * namelen);
```

DESCRIPTION

getsockname returns the current name for the specified socket. The `namelen` parameter should be initialized to indicate the amount of space pointed to by `name`. On return it contains the actual size of the name returned (in bytes).

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and `errno` is set appropriately.

ERRORS

EBADF	The argument <code>s</code> is not a valid descriptor.
ENOTSOCK	The argument <code>s</code> is a file, not a socket.
ENOBUFS	Insufficient resources were available in the system to perform the operation.
EFAULT	The <code>name</code> parameter points to memory not in a valid part of the process address space.

HISTORY

The `getsockname` function call appeared in BSD 4.2.

BUGS

Names bound to sockets in the UNIX domain are inaccessible; `getsockname` returns a 0-length name.

SEE ALSO

`bind(2)`, `socket(2)`

BSD Man Page, 24 July 1993

getsockopt, setsockopt

getsockopt, setsockopt—Get and set options on sockets

SYNOPSIS

```
#include <sys/types.h>
#include <sys/socket.h>
int getsockopt(int s, int level, intoptname, void*optval, int*optlen);
int setsockopt(int s, int level, intoptname, const void *optval, intoptlen);
```

DESCRIPTION

getsockopt and setsockopt manipulate the options associated with a socket. Options may exist at multiple protocol levels; they are always present at the uppermost socket level.

When manipulating socket options, the level at which the option resides and the name of the option must be specified. To manipulate options at the socket level, `level` is specified as `SOL_SOCKET`. To manipulate options at any other level, the protocol number of the appropriate protocol controlling the option is supplied. For example, to indicate that an option is to be interpreted by the TCP protocol, `level` should be set to the protocol number of TCP; see `getprotoent(3)`.

The parameters `optval` and `optlen` are used to access option values for `setsockopt`. For `getsockopt` they identify a buffer in which the value for the requested option(s) is to be returned. For `getsockopt`, `optlen` is a value-result parameter, initially containing the size of the buffer pointed to by `optval`, and modified on return to indicate the actual size of the value returned. If no option value is to be supplied or returned, `optval` may be `NULL`.

`optname` and any specified options are passed uninterpreted to the appropriate protocol module for interpretation. The include file `<sys/socket.h>` contains definitions for socket-level options, described below. Options at other protocol levels vary in format and name; consult the appropriate entries in section 4 of the manual.

Most socket-level options utilize an `int` parameter for `optval`. For `setsockopt`, the parameter should be nonzero to enable a boolean option, or 0 if the option is to be disabled. `SO_LINGER` uses a `struct linger` parameter, defined in `<linux/socket.h>`, which specifies the desired state of the option and the linger interval (see below). `SO_SNDTIMEO` and `SO_RCVTIMEO` use a `struct timeval` parameter, defined in `<sys/time.h>`.

The following options are recognized at the socket level. Except as noted, each may be examined with `getsockopt` and set with `setsockopt`:

<code>SO_DEBUG</code>	Enables recording of debugging information.
<code>SO_REUSEADDR</code>	Enables local address reuse.
<code>SO_KEEPAIVE</code>	Enables keep connections alive.
<code>SO_DONTROUTE</code>	Enables routing bypass for outgoing messages.
<code>SO_LINGER</code>	Linger on close if data present.
<code>SO_BROADCAST</code>	Enables permission to transmit broadcast messages.
<code>SO_OOINLINE</code>	Enables reception of out-of-band data in band.
<code>SO_SNDBUF</code>	Sets buffer size for output.
<code>SO_RCVBUF</code>	Sets buffer size for input.
<code>SO_SNDLOWAT</code>	Sets minimum count for output.
<code>SO_RCVLOWAT</code>	Sets minimum count for input.
<code>SO_SNDTIMEO</code>	Sets time-out value for output.
<code>SO_RCVTIMEO</code>	Sets time-out value for input.
<code>SO_TYPE</code>	Gets the type of the socket (get only).
<code>SO_ERROR</code>	Gets and clears error on the socket (get only).

`SO_DEBUG` enables debugging in the underlying protocol modules.

`SO_REUSEADDR` indicates that the rules used in validating addresses supplied in a `bind(2)` call should allow reuse of local addresses.

`SO_KEEPAIVE` enables the periodic transmission of messages on a connected socket. Should the connected party fail to respond to these messages, the connection is considered broken and processes using the socket are notified via a `SIGPIPE` signal when attempting to send data.

`SO_DONTROUTE` indicates that outgoing messages should bypass the standard routing facilities. Instead, messages are directed to the appropriate network interface according to the network portion of the destination address.

`SO_LINGER` controls the action taken when unsent messages are queued on socket and a `close(2)` is performed. If the socket promises reliable delivery of data and `SO_LINGER` is set, the system will block the process on the close attempt until it is able to transmit the data or until it decides it is unable to deliver the information (a time-out period, termed the linger interval, is specified in the `setsockopt` call when `SO_LINGER` is requested). If `SO_LINGER` is disabled and a close is issued, the system will process the close in a manner that allows the process to continue as quickly as possible.

The `linger` structure is defined in `<linux/socket.h>` as follows:

```
struct linger {
    int l_onoff; /* Linger active */
    int l_linger; /* How long to linger for */
};
```

`l_onoff` indicates whether to linger. If it is set to 1, `l_linger` contains the time in hundredths of seconds how long the process should linger to complete the close. If `l_onoff` is set to 0, the process returns immediately.

The option `SO_BROADCAST` requests permission to send broadcast datagrams on the socket. Broadcast was a privileged operation in earlier versions of the system. With protocols that support out-of-band data, the `SO_OOBINLINE` option requests that out-of-band data be placed in the normal data input queue as received; it will then be accessible with `recv` or `read` calls without the `MSG_OOB` flag. Some protocols always behave as if this option is set.

`SO_SNDBUF` and `SO_RCVBUF` are options to adjust the normal buffer sizes allocated for output and input buffers, respectively. The buffer size may be increased for high-volume connections or may be decreased to limit the possible backlog of incoming data. The system places an absolute limit on these values.

`SO_SNDLOWAT` is an option to set the minimum count for output operations. Most output operations process all of the data supplied by the call, delivering data to the protocol for transmission and blocking as necessary for flow control. Nonblocking output operations will process as much data as permitted subject to flow control without blocking, but will process no data if flow control does not allow the smaller of the low water mark value or the entire request to be processed. A `select(2)` operation testing the ability to write to a socket will return true only if the low water mark amount could be processed. The default value for `SO_SNDLOWAT` is set to a convenient size for network efficiency, often 1024.

`SO_RCVLOWAT` is an option to set the minimum count for input operations. In general, receive calls will block until any (nonzero) amount of data is received, then return with the smaller of the amount available or the amount requested. The default value for `SO_RCVLOWAT` is 1. If `SO_RCVLOWAT` is set to a larger value, blocking receive calls normally wait until they have received the smaller of the low water mark value or the requested amount. Receive calls may still return less than the low water mark if an error occurs, a signal is caught, or the type of data next in the receive queue is different than that returned.

`SO_SNDTIMEO` is an option to set a time-out value for output operations. It accepts a `struct timeval` parameter with the number of seconds and microseconds used to limit waits for output operations to complete. If a send operation has blocked for this much time, it returns with a partial count or with the error `EWOULDBLOCK` if no data were sent. In the current implementation, this timer is restarted each time additional data are delivered to the protocol, implying that the limit applies to output portions ranging in size from the low water mark to the high water mark for output.

`SO_RCVTIMEO` is an option to set a time-out value for input operations. It accepts a `struct timeval` parameter with the number of seconds and microseconds used to limit waits for input operations to complete. In the current implementation, this timer is restarted each time additional data are received by the protocol, and thus the limit is in effect an inactivity timer. If a receive operation has been blocked for this much time without receiving additional data, it returns with a short count or with the error `EWOULDBLOCK` if no data were received.

Finally, `SO_TYPE` and `SO_ERROR` are options used only with `setsockopt`.

`SO_TYPE` returns the type of the socket, such as `SOCK_STREAM`; it is useful for servers that inherit sockets on startup.

`SO_ERROR` returns any pending error on the socket and clears the error status. It may be used to check for asynchronous errors on connected datagram sockets or for other asynchronous errors.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and `errno` is set appropriately.

ERRORS

<code>EBADF</code>	The argument <code>s</code> is not a valid descriptor.
<code>ENOTSOCK</code>	The argument <code>s</code> is a file, not a socket.
<code>ENOPROTOPT</code>	The option is unknown at the level indicated.
<code>EFAULT</code>	The address pointed to by <code>optval</code> is not in a valid part of the process address space. For <code>getsockopt</code> , this error may also be returned if <code>optlen</code> is not in a valid part of the process address space.

HISTORY

These system calls appeared in BSD 4.2.

BUGS

Several of the socket options should be handled at lower levels of the system.

SEE ALSO

`ioctl(2)`, `socket(2)`, `getprotoent(3)`, `protocols(5)`

BSD Man Page, 22 April 1996

gettimeofday, settimeofday

`gettimeofday`, `settimeofday`—Get/set time

SYNOPSIS

```
#include <sys/time.h>
#include <unistd.h>

int gettimeofday(struct timeval *tv, struct timezone *tz);
int settimeofday(const struct timeval *tv, const struct timezone *tz);
```

DESCRIPTION

`gettimeofday` and `settimeofday` can set the time as well as a time zone. `tv` is a `timeval` struct, as specified in `/usr/include/sys/time.h`:

```
struct timeval {
    long tv_sec;        /* seconds */
    long tv_usec;       /* microseconds */
};
```

and `tz` is a `timezone`:

```
struct timezone {
    int  tz_minuteswest;
    /* minutes west of Greenwich */
    int  tz_dsttime;
    /* type of dst correction */
};
```

with daylight savings times defined as follows:

```
DST_NONE    /* not on dst */
DST_USA     /* USA style dst */
DST_AUST    /* Australian style dst */
DST_WET     /* Western European dst */
DST_MET     /* Middle European dst */
DST_EET     /* Eastern European dst */
DST_CAN     /* Canada */
DST_GB      /* Great Britain and Eire */
DST_RUM     /* Rumania */
DST_TUR     /* Turkey */
DST_AUSTALT /* Australian style with shift in 1986 */
```


And the following macros are defined to operate on this :

```
#define timerisset(tvp)\
    ((tvp)->tv_sec || (tvp)->tv_usec)
#define timercmp(tvp, uvp, cmp)\
    ((tvp)->tv_sec cmp (uvp)->tv_sec ||\
    (tvp)->tv_sec == (uvp)->tv_sec &&\
    (tvp)->tv_usec cmp (uvp)->tv_usec)
#define timerclear(tvp)\
    ((tvp)->tv_sec = (tvp)->tv_usec = 0)
```

If either tv or tz is null, the corresponding structure is not set or returned.

Only the superuser can use settimeofday.

ERRORS

EPERM	settimeofday is called by someone other than the superuser.
EINVAL	Time zone (or something else) is invalid.

CONFORMS TO

BSD 4.3

SEE ALSO

date(1), adjtimex(2), time(2), ctime(3), ftime(3)

Linux 1.2.4, 15 April 1995

getuid, geteuid

getuid, geteuid—Get user identity

SYNOPSIS

```
#include <unistd.h>
uid_t getuid(void);
uid_t geteuid(void);
```

DESCRIPTION

getuid returns the real user ID of the current process.

geteuid returns the effective user ID of the current process.

The real ID corresponds to the ID of the calling process. The effective ID corresponds to the set ID bit on the file being executed.

ERRORS

These functions are always successful.

CONFORMS TO

POSIX, BSD 4.3

SEE ALSO

setreuid(2), setuid(2)

Linux 0.99.11, 23 July 1993

idle

`idle`—Makes process 0 idle

SYNOPSIS

```
#include <unistd.h>
void idle(void);
```

DESCRIPTION

`idle` is an internal system call used during bootstrap. It marks the process's pages as swappable, lowers its priority, and enters the main scheduling loop. `idle` never returns.

Only process 0 may call `idle`. Any user process, even a process with superuser permission, will receive `EPERM`.

RETURN VALUE

`idle` never returns for process 0, and always returns `-1` for a user process.

ERRORS

<code>EPERM</code>	Always, for a user process.

Linux 1.1.46, 21 August 1994

ioctl

`ioctl`—Controls devices

SYNOPSIS

```
#include <sys/ioctl.h>
int ioctl(int d, int request, ...);
```

(The “third” argument is traditionally `char *argp` and will be so named for this discussion.)

DESCRIPTION

The `ioctl` function manipulates the underlying device parameters of special files. In particular, many operating characteristics of character special files (for example, terminals) may be controlled with `ioctl` requests. The argument `d` must be an open file descriptor.

An `ioctl` request has encoded in it whether the argument is an `in` parameter or `out` parameter, and the size of the argument `argp` in bytes. Macros and defines used in specifying an `ioctl` request are located in the file `<sys/ioctl.h>`.

RETURN VALUE

On success, `0` is returned. On error, `-1` is returned and `errno` is set appropriately.

ERRORS

<code>EBADF</code>	<code>d</code> is not a valid descriptor.
<code>ENOTTY</code>	<code>d</code> is not associated with a character special device.
<code>ENOTTY</code>	The specified request does not apply to the kind of object that the descriptor <code>d</code> references.
<code>EINVAL</code>	request or <code>argp</code> is not valid.

HISTORY

An `ioctl` function call appeared in version 7 AT&T UNIX.

SEE ALSO

```
execve(2), fcntl(2), mt(4), sd(4), tty(4)
```

INTRODUCTION

This is ioctl List 1.3.27, a list of ioctl calls in Linux/i386 kernel 1.3.27. It contains 421 ioctls from /usr/include/fasm,linuxg/*.h. For each ioctl, you'll find the numerical value, name, and argument type.

An argument type of `const struct foo *` means the argument is input to the kernel. `struct foo *` means the kernel outputs the argument. If the kernel uses the argument for both input and output, this is marked with `// I-O`.

Some ioctls take more arguments or return more values than a single structure. These are marked `// MORE` and are documented further in a separate section.

This list is incomplete. It does not include

- ioctls defined internal to the kernel (scsi ioctl.h).
- ioctls defined in modules distributed separately from the kernel.

And, of course, I may have errors and omissions.

Please e-mail changes and comments to mec@duracef.shout.net. I am particularly interested in loadable modules that define their own ioctls. If you know of such a module, tell me where I can ftp it, and I'll include its ioctls in my next release.

MAIN TABLE

<include/asm-i386/socket.h>		
0x00008901	FIOSETOWN	const int *
0x00008902	SIOCSPGRP	const int *
0x00008903	FIOGETOWN	int *
0x00008904	SIOCGPGRP	int *
0x00008905	SIOCATMARK	int *
0x00008906	SIOCGSTAMP	timeval *
<include/asm-i386/termios.h>		
0x00005401	TCGETS	struct termios *
0x00005402	TCSETS	const struct termios *
0x00005403	TCSETSW	const struct termios *
0x00005404	TCSETSF	const struct termios *
0x00005405	TCGETA	struct termio *
0x00005406	TCSETA	const struct termio *
0x00005407	TCSETAW	const struct termio *
0x00005408	TCSETAF	const struct termio *
0x00005409	TCSBRK	int
0x0000540A	TCXONC	int
0x0000540B	TCFLSH	int
0x0000540C	TIOCEXCL	void
0x0000540D	TIOCNXCL	void
0x0000540E	TIOCSTTY	int
0x0000540F	TIOCGPGRP	pid_t *
0x00005410	TIOCPGRP	const pid_t *

```
<include/asm-i386/termios.h>
```

0x00005411	TIOCOUTQ	int *
0x00005412	TIOCSSTI	const char *
0x00005413	TIOCGWINSZ	const struct winsize *
0x00005414	TIOCSWINSZ	struct winsize *
0x00005415	TIOCMGET	int *
0x00005416	TIOCMBIS	const int *
0x00005417	TIOCMBIC	const int *
0x00005418	TIOCMSET	const int *
0x00005419	TIOCGSOFTCAR	int *
0x0000541A	TIOCSSOFTCAR	const int *
0x0000541B	FIONREAD	int *
0x0000541B	TIOCINQ	int *
0x0000541C	TIOCLINUX	const char *
0x0000541D	TIOCCONS	void
0x0000541E	TIOCGSERIAL	struct serial_struct *
0x0000541F	TIOCSSERIAL	const struct serial_struct *
0x00005420	TIOCPKT	const int *
0x00005421	FIONBIO	const int *
0x00005422	TIOCNOTTY	void
0x00005423	TIOCSETD	const int *
0x00005424	TIOCGETD	int *
0x00005425	TCSBRKP	int
0x00005426	TIOCTTYGSTRUCT	struct tty_struct *
0x00005450	FIONCLEX	void
0x00005451	FIOCLEX	void
0x00005452	FIOASYNC	const int *
0x00005453	TIOCSERCONFIG	void
0x00005454	TIOCSERGWILD	int *
0x00005455	TIOCSERSWILD	const int *
0x00005456	TIOCGLKTRMIOS	struct termios *
0x00005457	TIOCSLKTRMIOS	const struct termios *
0x00005458	TIOCSERGSTRUCT	struct async_struct *
0x00005459	TIOCSERGETLSR	int *
0x0000545A	TIOCSERGETMULTI	struct serial_multiport_struct *
0x0000545B	TIOCSERSETMULTI	const struct serial_multiport_struct *

```
<include/linux/ax25.h>
```

0x000089E0	SIOCX25GETUID	const struct sockaddr_ax25 *
0x000089E1	SIOCX25ADDUID	const struct sockaddr_ax25 *
0x000089E2	SIOCX25DELUID	const struct sockaddr_ax25 *
0x000089E3	SIOCX25NOUID	const int *

```
<include/linux/ax25.h>
```

0x000089E4	SIOCX25DIGCTL	const int *
0x000089E5	SIOCX25GETPARMS	struct ax25_parms_struct * // I-O
0x000089E6	SIOCX25SETPARMS	const struct ax25_parms_struct *

```
<include/linux/cdk.h>
```

0x00007314	STL_BINTR	void
0x00007315	STL_BSTART	void
0x00007316	STL_BSTOP	void
0x00007317	STL_BRESET	void

```
<include/linux/cdrom.h>
```

0x00005301	CDROMPAUSE	void
0x00005302	CDROMRESUME	void
0x00005303	CDROMPLAYMSF	const struct cdrom_msf *
0x00005304	CDROMPLAYTRKIND	const struct cdrom_ti *
0x00005305	CDROMREADTOCHDR	struct cdrom_tochdr *
0x00005306	CDROMREADTOCENTRY	struct cdrom_tocentry *// I-O
0x00005307	CDROMSTOP	void
0x00005308	CDROMSTART	void
0x00005309	CDROMEJECT	void
0x0000530A	CDROMVOLCTRL	const struct cdrom_volctrl *
0x0000530B	CDROMSUBCHNL	struct cdrom_subchnl * // I-O
0x0000530C	CDROMREADMODE2	const struct cdrom_msf * // MORE
0x0000530D	CDROMREADMODE1	const struct cdrom_msf * // MORE
0x0000530E	CDROMREADAUDIO	const struct cdrom_read_audio *
0x0000530F	CDROMEJECT	SW int
0x00005310	CDROMMULTISESSION	struct cdrom_multisession * // I-O
0x00005311	CDROM_GET_UPC	struct f char [8]; g *
0x00005312	CDROMRESET	void
0x00005313	CDROMVOLREAD	struct cdrom_volctrl *
0x00005314	CDROMREADRAW	const struct cdrom_msf * // MORE
0x00005315	CDROMREADCOOKED	const struct cdrom_msf * // MORE
0x00005316	CDROMSEEK	const struct cdrom_msf *

```
<include/linux/cm206.h>
```

0x00002000	CM206CTL_GET_STAT	int
0x00002001	CM206CTL_GET_LAST_STAT	int

```
<include/linux/cyclades.h>
```

0x00435901	CYGETMON	struct cyclades_monitor *
0x00435902	CYGETTHRESH	int *
0x00435903	CYSETTHRESH	int
0x00435904	CYGETDEFTHRESH	int *
0x00435905	CYSETDEFTHRESH	int
0x00435906	CYGETTIMEOUT	int *
0x00435907	CYSETTIMEOUT	int
0x00435908	CYGETDEFTIMEOUT	int *
0x00435909	CYSETDEFTIMEOUT	int

```
<include/linux/ext2_fs.h>
```

0x80046601	EXT2_IOC_GETFLAGS	int *
0x40046602	EXT2_IOC_SETFLAGS	const int *
0x80047601	EXT2_IOC_GETVERSION	int *
0x40047602	EXT2_IOC_SETVERSION	const int *

```
<include/linux/fd.h>
```

0x00000000	FDCLRPRM	void
0x00000001	FDSETPRM	const struct floppy_struct *
0x00000002	FDDEFPRM	const struct floppy_struct *
0x00000003	FDGETPRM	struct floppy_struct *
0x00000004	FDMSGON	void
0x00000005	FDMSGOFF	void
0x00000006	FDfmtBEG	void
0x00000007	FDfmtTRK	const struct format_descr *
0x00000008	FDfmtEND	void
0x0000000A	FDSETEMSGTRESH	int
0x0000000B	FDFLUSH	void
0x0000000C	FDSETMAXERRS	const struct floppy_max_errors *
0x0000000E	FDGETMAXERRS	struct floppy_max_errors *
0x00000010	FDGETDRVTYPE	struct f_char [16]; g *
0x00000014	FDSETDRVPRM	const struct floppy_drive_params *
0x00000015	FDGETDRVPRM	struct floppy_drive_params *
0x00000016	FDGETDRVSTAT	struct floppy_drive_struct *
0x00000017	FDPOLLDRVSTAT	struct floppy_drive_struct *
0x00000018	FDRESET	int
0x00000019	FDGETFDCSTAT	struct floppy_fdc_state *
0x0000001B	FDWERRORCLR	void
0x0000001C	FDWERRORGET	struct floppy_write_errors *
0x0000001E	FDRAWCMD	struct floppy_raw_cmd * // MORE // I-O
0x00000028	FDTWADDLE	void

```
<include/linux/fs.h>
```

0x0000125D	BLKROSET	const int *
0x0000125E	BLKROGET	int *
0x0000125F	BLKRRPART	void
0x00001260	BLKGETSIZE	int *
0x00001261	BLKFLSBUF	void
0x00001262	BLKRASET	int
0x00001263	BLKRASET	int *
0x00000001	FIBMAP	int * // I-O
0x00000002	FIGETBSZ	int *

```
<include/linux/hdreg.h>
```

0x00000301	HDIO_GETGEO	struct hd geometry *
0x00000302	HDIO_GET_UNMASKINTR	int *
0x00000304	HDIO_GET_MULTCOUNT	int *
0x00000307	HDIO_GET_IDENTITY	struct hd driveid *
0x00000308	HDIO_GET_KEEPPSETTINGS	int *
0x00000309	HDIO_GET_CHIPSET	int *
0x0000030A	HDIO_GET_NOWERR	int *
0x0000030B	HDIO_GET_DMA	int *
0x0000031F	HDIO_DRIVE_CMD	int * // I-O
0x00000321	HDIO_SET_MULTCOUNT	int
0x00000322	HDIO_SET_UNMASKINTR	int
0x00000323	HDIO_SET_KEEPPSETTINGS	int
0x00000324	HDIO_SET_CHIPSET	int
0x00000325	HDIO_SET_NOWERR	int
0x00000326	HDIO_SET_DMA	int

```
<include/linux/if_eq1.h>
```

0x000089F0	EQL_ENSLAVE	struct ifreq * // MORE // I-O
0x000089F1	EQL_EMANCIPATE	struct ifreq * // MORE // I-O
0x000089F2	EQL_GETSLAVECFG	struct ifreq * // MORE // I-O
0x000089F3	EQL_SETSLAVECFG	struct ifreq * // MORE // I-O
0x000089F4	EQL_GETMASTRCFG	struct ifreq * // MORE // I-O
0x000089F5	EQL_SETMASTRCFG	struct ifreq * // MORE // I-O

```
<include/linux/if_plip.h>
```

0x000089F0	SIOCDEVPLIP	struct ifreq * // I-O

```
<include/linux/iffpp.h>
```

0x00005490	PPPIOCGFLAGS	int *
0x00005491	PPPIOCSFLAGS	const int *
0x00005492	PPPIOCGASYNCMAP	int *
0x00005493	PPPIOCSASYNCMAP	const int *
0x00005494	PPPIOCGUNIT	int *
0x00005495	PPPIOCSINPSIG	const int *
0x00005497	PPPIOCSDEBUG	const int *
0x00005498	PPPIOCGDEBUG	int *
0x00005499	PPPIOCGSTAT	struct ppp_stats *
0x0000549A	PPPIOCGTIME	struct ppp_ddinfo *
0x0000549B	PPPIOCGXASYNCMAP	struct f int [8]; g *
0x0000549C	PPPIOCSXASYNCMAP	const struct f int [8]; g *
0x0000549D	PPPIOCSMRU	const int *
0x0000549E	PPPIOCRASYNCMAP	const int *
0x0000549F	PPPIOCSMAXCID	const int *

```
<include/linux/ipx.h>
```

0x000089E0	SIOCAIPXITFCRT	const char *
0x000089E1	SIOCAIPXPRISLT	const char *
0x000089E2	SIOCIPIXCFGDATA	struct ipx_config_data *

```
<include/linux/kd.h>
```

0x00004B60	GIO_FONT	struct f char [8192]; g *
0x00004B61	PIO_FONT	const struct f char [8192]; g *
0x00004B6B	GIO_FONTX	struct console_font_desc * // MORE I-O
0x00004B6C	PIO_FONTX	const struct console_font_desc * //MORE
0x00004B70	GIO_CMAP	struct f char [48]; g *
0x00004B71	PIO_CMAP	const struct f char [48]; g
0x00004B2F	KIOCSOUND	int
0x00004B30	KDMKTONE	int
0x00004B31	KDGETLED	char *
0x00004B32	KDSETLED	int
0x00004B33	KDGKBTYPE	char *
0x00004B34	KDADDIO	int // MORE
0x00004B35	KDDELIO	int // MORE
0x00004B36	KDENABIO	void // MORE
0x00004B37	KDDISABIO	void // MORE
0x00004B3A	KDSETMODE	int
0x00004B3B	KDGETMODE	int *
0x00004B3C	KDMAPDISP	void // MORE

<include/linux/kd.h>

0x00004B3D	KDUNMAPDISP	void // MORE
0x00004B40	GIO_SCRNMAP	struct f char [E_TABSZ]; g *
0x00004B41	PIO_SCRNMAP	const struct f char [E_TABSZ]; g *
0x00004B69	GIO_UNISCRNMAP	struct f short [E_TABSZ]; g *
0x00004B6A	PIO_UNISCRNMAP	const struct f short [E_TABSZ]; g *
0x00004B66	GIO_UNIMAP	struct unimapdesc * // MORE // I-0
0x00004B67	PIO_UNIMAP	const struct unimapdesc * // MORE
0x00004B68	PIO_UNIMAPCLR	const struct unimapinit *
0x00004B44	KDGKBMODE	int *
0x00004B45	KDSKBMODE	int
0x00004B62	KDGKBMETA	int *
0x00004B63	KDSKBMETA	int
0x00004B64	KDGKBLED	int *
0x00004B65	KDSKBLED	int
0x00004B46	KDGKBENT	struct kbentry * // I-0
0x00004B47	KDSKBENT	const struct kbentry *
0x00004B48	KDGKBSENT	struct kbsentry * // I-0
0x00004B49	KDSKBSENT	const struct kbsentry *
0x00004B4A	KDGKBDIACR	struct kbdiacrs *
0x00004B4B	KDSKBDIACR	const struct kbdiacrs *
0x00004B4C	KDGETKEYCODE	struct kbkeycode * // I-0
0x00004B4D	KDSETKEYCODE	const struct kbkeycode *
0x00004B4E	KDSIGACCEPT	int

<include/linux/lp.h>

0x00000601	LPCHAR	int
0x00000602	LPTIME	int
0x00000604	LPABORT	int
0x00000605	LPSETIRQ	int
0x00000606	LPGETIRQ	int *
0x00000608	LPWAIT	int
0x00000609	LP CAREFUL	int
0x0000060A	LPABORTOPEN	int
0x0000060B	LPGETSTATUS	int *
0x0000060C	LPRESET	void
0x0000060D	LPGETSTATS	struct lp stats *

<include/linux/mroute.h>

0x000089E0	SIOCGETVIFCNT	struct sioc_vif_req * // I-0
0x000089E1	SIOCGETSGCNT	struct sioc_sg_req * // I-0

```
<include/linux/mtio.h>
```

0x40086D01	MTIOCTOP	const struct mtop *
0x801C6D02	MTIOCGET	struct mtget *
0x80046D03	MTIOCPOS	struct mtpos *
0x80206D04	MTIOCGETCONFIG	struct mtconfiginfo *
0x40206D05	MTIOCSETCONFIG	const struct mtconfiginfo *

```
<include/linux/netrom.h>
```

0x000089E0	SIOCNRGETPARMS	struct nr_parms_struct * // I-O
0x000089E1	SIOCNRSETPARMS	const struct nr_parms_struct *
0x000089E2	SIOCNRDECOBS	void
0x000089E3	SIOCNRTCTL	const int *

```
<include/linux/sbpcd.h>
```

0x00009000	DDIOCSDBG	const int *
0x00005382	CDROMAUDIOBUFSIZ	int

```
<include/linux/scc.h>
```

0x00005470	TIOCCSCINI	void
0x00005471	TIOCCHANINI	const struct scc_modem *
0x00005472	TIOCGKISS	struct ioctl_command * // I-O
0x00005473	TIOCSKISS	const struct ioctl_command *
0x00005474	TIOCCSCSTAT	struct scc_stat *

```
<include/linux/scsi.h>
```

0x00005382	SCSI_IOCTL_GET_IDLUN	struct f int [2]; g *
0x00005383	SCSI_IOCTL_TAGGED_ENABLE	void
0x00005384	SCSI_IOCTL_TAGGED_DISABLE	void
0x00005385	SCSI_IOCTL_PROBE_HOST	const int * // MORE

```
<include/linux/smb fs.h>
```

0x80027501	SMB_IOC_GETMOUNTUID	uid t *

```
<include/linux/sockios.h>
```

0x0000890B	SIOCADDRT	const struct rtenry * // MORE
0x0000890C	SIOCDELRT	const struct rtenry * // MORE
0x00008910	SIOCGIFNAME	char []
0x00008911	SIOCSIFLINK	void
0x00008912	SIOCGIFCONF	struct ifconf * // MORE // I-O
0x00008913	SIOCGIFFLAGS	struct ifreq * // I-O
0x00008914	SIOCSIFFLAGS	const struct ifreq *

```
<include/linux/sockios.h>
```

0x00008915	SIOCGIFADDR	struct ifreq * // I-O
0x00008916	SIOCSIFADDR	const struct ifreq *
0x00008917	SIOCGIFDSTADDR	struct ifreq * // I-O
0x00008918	SIOCSIFDSTADDR	const struct ifreq *
0x00008919	SIOCGIFBRDADDR	struct ifreq * // I-O
0x0000891A	SIOCSIFBRDADDR	const struct ifreq *
0x0000891B	SIOCGIFNETMASK	struct ifreq * // I-O
0x0000891C	SIOCSIFNETMASK	const struct ifreq *
0x0000891D	SIOCGIFMETRIC	struct ifreq * // I-O
0x0000891E	SIOCSIFMETRIC	const struct ifreq *
0x0000891F	SIOCGIFMEM	struct ifreq * // I-O
0x00008920	SIOCSIFMEM	const struct ifreq *
0x00008921	SIOCGIFMTU	struct ifreq * // I-O
0x00008922	SIOCSIFMTU	const struct ifreq *
0x00008923	OLD SIOCGIFHWADDR	struct ifreq * // I-O
0x00008924	SIOCSIFHWADDR	const struct ifreq * // MORE
0x00008925	SIOCGIFENCAP	int *
0x00008926	SIOCSIFENCAP	const int *
0x00008927	SIOCGIFHWADDR	struct ifreq * // I-O
0x00008929	SIOCGIFSLAVE	void
0x00008930	SIOCSIFSLAVE	void
0x00008931	SIOCADDMULTI	const struct ifreq *
0x00008932	SIOCDELMULTI	const struct ifreq *
0x00008940	SIOCADDRTOLD	void
0x00008941	SIOCDELRTOld	void
0x00008950	SIOCDDARP	const struct arpreq *
0x00008951	SIOCGARP	struct arpreq * // I-O
0x00008952	SIOCSARP	const struct arpreq *
0x00008960	SIOCRRARP	const struct arpreq *
0x00008961	SIOCGRRARP	struct arpreq * // I-O
0x00008962	SIOCSRRARP	const struct arpreq *
0x00008970	SIOCGIFMAP	struct ifreq * // I-O
0x00008971	SIOCSIFMAP	const struct ifreq *

```
<include/linux/soundcard.h>
```

0x00005100	SNDCCTL_SEQ_RESET	void
0x00005101	SNDCCTL_SEQ_SYNC	void
0xC08C5102	SNDCCTL_SYNTH_INFO	struct synth_info * // I-O
0xC045103	SNDCCTL_SEQ_CTRLRATE	int * // I-O
0x8045104	SNDCCTL_SEQ_GETOUTCOUNT	int *
0x8045105	SNDCCTL_SEQ_GETINCOUNT	int *
0x4045106	SNDCCTL_SEQ_PERCMODE	void

```
<include/linux/soundcard.h>
```

0x40285107	SNDCCTL_FM_LOAD_INSTR	const struct sbi_instrument *
0x40045108	SNDCCTL_SEQ_TESTMIDI	const int *
0x40045109	SNDCCTL_SEQ_RESETSAMPLES	const int *
0x8004510A	SNDCCTL_SEQ_NRSYNTHS	int *
0x8004510B	SNDCCTL_SEQ_NRMIDIS	int *
0xC074510C	SNDCCTL_MIDI_INFO	struct midi_info * // I-O
0x4004510D	SNDCCTL_SEQ_THRESHOLD	const int *
0xC004510E	SNDCCTL_SYNTH_MEMAVL	int * // I-O
0x4004510F	SNDCCTL_FM_4OP_ENABLE	const int *
0xCFB85110	SNDCCTL_PMGR_ACCESS	struct patmgr_info * // I-O
0x00005111	SNDCCTL_SEQ_PANIC	void
0x40085112	SNDCCTL_SEQ_OUTOFBAND	const struct seq_event_rec *
0xC0045401	SNDCCTL_TMR_TIMEBASE	int * // I-O
0x00005402	SNDCCTL_TMR_START	void
0x00005403	SNDCCTL_TMR_STOP	void
0x00005404	SNDCCTL_TMR_CONTINUE	void
0xC0045405	SNDCCTL_TMR_TEMPO	int * // I-O
0xC0045406	SNDCCTL_TMR_SOURCE	int * // I-O
0x40045407	SNDCCTL_TMR_METRONOME	const int *
0x40045408	SNDCCTL_TMR_SELECT	int * // I-O
0xCFB85001	SNDCCTL_PMGR_IFACE	struct patmgr_info * // I-O
0xC0046D00	SNDCCTL_MIDI_PRETIME	int * // I-O
0xC0046D01	SNDCCTL_MIDI_MPUMODE	const int *
0xC0216D02	SNDCCTL_MIDI_MPUCMD	struct mpu_command_rec * // I-O
0x00005000	SNDCCTL_DSP_RESET	void
0x00005001	SNDCCTL_DSP_SYNC	void
0xC0045002	SNDCCTL_DSP_SPEED	int * // I-O
0xC0045003	SNDCCTL_DSP_STEREO	int * // I-O
0xC0045004	SNDCCTL_DSP_GETBLKSIZE	int * // I-O
0xC0045006	SOUND_PCM_WRITE CHANNELS	int * // I-O
0xC0045007	SOUND_PCM_WRITE FILTER	int * // I-O
0x00005008	SNDCCTL_DSP_POST	void
0xC0045009	SNDCCTL_DSP_SUBDIVIDE	int * // I-O
0xC004500A	SNDCCTL_DSP_SETFRAGMENT	int * // I-O
0x8004500B	SNDCCTL_DSP_GETFMTS	int *
0xC0045005	SNDCCTL_DSP_SETFMT	int * // I-O
0x800C500C	SNDCCTL_DSP_GETOSPACE	struct audio-buf-info *
0x800C500D	SNDCCTL_DSP_GETISPACE	struct audio-buf-info *
0x0000500E	SNDCCTL_DSP_NONBLOCK	void
0x80045002	SOUND_PCM_READ RATE	int *
0x80045006	SOUND_PCM_READ CHANNELS	int *
0x80045005	SOUND_PCM_READ BITS	int *

```
<include/linux/soundcard.h>
```

0x80045007	SOUND_PCM_READ_FILTER	int *
0x00004300	SNDCTL_COPR_RESET	void
0xCFB04301	SNDCTL_COPR_LOAD	const struct copr_buffer *
0xC0144302	SNDCTL_COPR_RDATA	struct copr_debug_buf * // I-O
0xC0144303	SNDCTL_COPR_RCODE	struct copr_debug_buf * // I-O
0x40144304	SNDCTL_COPR_WDATA	const struct copr_debug_buf *
0x40144305	SNDCTL_COPR_WCODE	const struct copr_debug_buf *
0xC0144306	SNDCTL_COPR_RUN	struct copr_debug_buf * // I-O
0xC0144307	SNDCTL_COPR_HALT	struct copr_debug_buf * // I-O
0x4FA44308	SNDCTL_COPR_SENMSG	const struct copr_msg *
0x8FA44309	SNDCTL_COPR_RCVMSG	struct copr_msg *
0x80044D00	SOUND_MIXER_READ_VOLUME	int *
0x80044D01	SOUND_MIXER_READ_BASS	int *
0x80044D02	SOUND_MIXER_READ_TREBLE	int *
0x80044D03	SOUND_MIXER_READ_SYNTH	int *
0x80044D04	SOUND_MIXER_READ_PCM	int *
0x80044D05	SOUND_MIXER_READ_SPEAKER	int *
0x80044D06	SOUND_MIXER_READ_LINE	int *
0x80044D07	SOUND_MIXER_READ_MIC	int *
0x80044D08	SOUND_MIXER_READ_CD	int *
0x80044D09	SOUND_MIXER_READ_IMIX	int *
0x80044D0A	SOUND_MIXER_READ_ALTPCM	int *
0x80044D0B	SOUND_MIXER_READ_RECLEV	int *
0x80044D0C	SOUND_MIXER_READ_IGAIN	int *
0x80044D0D	SOUND_MIXER_READ_OGAIN	int *
0x80044D0E	SOUND_MIXER_READ_LINE1	int *
0x80044D0F	SOUND_MIXER_READ_LINE2	int *
0x80044D10	SOUND_MIXER_READ_LINE3	int *
0x80044D1C	SOUND_MIXER_READ_MUTE	int *
0x80044D1D	SOUND_MIXER_READ_ENHANCE	int *
0x80044D1E	SOUND_MIXER_READ_LOUD	int *
0x80044DFF	SOUND_MIXER_READ_RECSRC	int *
0x80044DFE	SOUND_MIXER_READ_DEVMASK	int *
0x80044DFD	SOUND_MIXER_READ_RECMASK	int *
0x80044DFB	SOUND_MIXER_READ_STEREODEVS	int *
0x80044DFC	SOUND_MIXER_READ_CAPS	int *
0xC0044D00	SOUND_MIXER_WRITE_VOLUME	int * // I-O
0xC0044D01	SOUND_MIXER_WRITE_BASS	int * // I-O
0xC0044D02	SOUND_MIXER_WRITE_TREBLE	int * // I-O
0xC0044D03	SOUND_MIXER_WRITE_SYNTH	int * // I-O
0xC0044D04	SOUND_MIXER_WRITE_PCM	int * // I-O
0xC0044D05	SOUND_MIXER_WRITE_SPEAKER	int * // I-O

```
<include/linux/soundcard.h>
```

0xC0044D06	SOUND_MIXER_WRITE_LINE	int * // I-O
0xC0044D07	SOUND_MIXER_WRITE_MIC	int * // I-O
0xC0044D08	SOUND_MIXER_WRITE_CD	int * // I-O
0xC0044D09	SOUND_MIXER_WRITE_IMIX	int * // I-O
0xC0044D0A	SOUND_MIXER_WRITE_ALTPCM	int * // I-O
0xC0044D0B	SOUND_MIXER_WRITE_RECLEV	int * // I-O
0xC0044D0C	SOUND_MIXER_WRITE_IGAIN	int * // I-O
0xC0044D0D	SOUND_MIXER_WRITE_OGAIN	int * // I-O
0xC0044D0E	SOUND_MIXER_WRITE_LINE1	int * // I-O
0xC0044D0F	SOUND_MIXER_WRITE_LINE2	int * // I-O
0xC0044D10	SOUND_MIXER_WRITE_LINE3	int * // I-O
0xC0044D1C	SOUND_MIXER_WRITE_MUTE	int * // I-O
0xC0044D1D	SOUND_MIXER_WRITE_ENHANCE	int * // I-O
0xC0044D1E	SOUND_MIXER_WRITE_LOUD	int * // I-O
0xC0044DFF	SOUND_MIXER_WRITE_RECSRC	int * // I-O

```
<include/linux/umsdos fs.h>
```

0x000004D2	UMSDOS_READDIR_DOS	struct umsdos_ioc1 * // I-O
0x000004D3	UMSDOS_UNLINK_DOS	const struct umsdos_ioc1 *
0x000004D4	UMSDOS_RMDIR_DOS	const struct umsdos_ioc1 *
0x000004D5	UMSDOS_STAT_DOS	struct umsdos_ioc1 * // I-O
0x000004D6	UMSDOS_CREAT_EMD	const struct umsdos_ioc1 *
0x000004D7	UMSDOS_UNLINK_EMD	const struct umsdos_ioc1 *
0x000004D8	UMSDOS_READDIR_EMD	struct umsdos_ioc1 * // I-O
0x000004D9	UMSDOS_GETVERSION	struct umsdos_ioc1 *
0x000004DA	UMSDOS_INIT_EMD	void
0x000004DB	UMSDOS_DOS_SETUP	const struct umsdos_ioc1 *
0x000004DC	UMSDOS_RENAME_DOS	const struct umsdos_ioc1 *

```
<include/linux/vt.h>
```

0x00005600	VT_OPENQRY	int *
0x00005601	VT_GETMODE	struct vt_mode *
0x00005602	VT_SETMODE	const struct vt_mode *
0x00005603	VT_GETSTATE	struct vt_stat *
0x00005604	VT_SENDSIG	void
0x00005605	VT_RELDISP	int
0x00005606	VT_ACTIVATE	int
0x00005607	VT_WAI TACTI VE	int
0x00005608	VT_DISALLOCATE	int
0x00005609	VT_RESIZE	const struct vt_sizes *
0x0000560A	VT_RESIZEX	const struct vt_consize *

MORE ARGUMENTS

Some `ioctl`s take a pointer to a structure that contains additional pointers. These are documented here in alphabetical order.

`CDROMREADAUDIO` takes an input pointer `const struct cdrom read audio *`. The `buf` field points to an output buffer of length `nframes * CD_FRAMESIZE_RAW`.

`CDROMREADCOOKED`, `CDROMREADMODE1`, `CDROMREADMODE2`, and `CDROM-READRAW` take an input pointer `const struct cdrom msf *`. They use the same pointer as an output pointer to `char []`. The length varies by request. For `CDROMREADMODE1`, most drivers use `CD_FRAMESIZE`, but the optics storage driver uses `OPT_BLOCKSIZE` instead (both have the numerical value 2048).

<code>CDROMREADCOOKED</code>	<code>char [CD_FRAMESIZE]</code>
<code>CDROMREADMODE1</code>	<code>char [CD_FRAMESIZE or OPT_BLOCKSIZE]</code>
<code>CDROMREADMODE2</code>	<code>char [CD_FRAMESIZE_RAW0]</code>
<code>CDROMREADRAW</code>	<code>char [CD_FRAMESIZE_RAW]</code>

`EQL_ENSLAVE`, `EQL_EMANCIPATE`, `EQL_GETSLAVECFG`, `EQL_SETSLAVECFG`, `EQL_GETMASTERCFG`, and `EQL_SETMASTERCFG` take a `struct ifreq *`. The `ifr` data field is a pointer to another structure as follows:

<code>EQL_ENSLAVE</code>	<code>const struct slaving_request *</code>
<code>EQL_EMANCIPATE</code>	<code>const struct slaving_request *</code>
<code>EQL_GETSLAVECFG</code>	<code>struct slave_config * // I-O</code>
<code>EQL_SETSLAVECFG</code>	<code>const struct slave_config *</code>
<code>EQL_GETMASTERCFG</code>	<code>struct master_config *</code>
<code>EQL_SETMASTERCFG</code>	<code>const struct master_config *</code>

`FDRAWCMD` takes a `struct floppy raw cmd *`. If `flags & FD_RAW_WRITE` is nonzero, then `data` points to an input buffer of length `length`. If `flags & FD_RAW_READ` is nonzero, then `data` points to an output buffer of length `length`.

`GIO_FONTX` and `PIO_FONTX` take a `struct console font desc *` or a `const struct console_font_desc *`, respectively. `chardata` points to a buffer of `char [charcount]`. This is an output buffer for `GIO_FONTX` and an input buffer for `PIO_FONTX`.

`GIO_UNIMAP` and `PIO_UNIMAP` take a `struct unimapdesc *` or a `const struct unimapdesc *`, respectively. `entries` points to a buffer of `struct unipair [entry ct]`. This is an output buffer for `GIO_UNIMAP` and an input buffer for `PIO_UNIMAP`.

`KDADDIO`, `KDDELIO`, `KDDISABIO`, and `KDENABIO` enable or disable access to I/O ports. They are essentially alternate interfaces to `ioperm`.

`KDMAPDISP` and `KDUNMAPDISP` enable or disable memory mappings or I/O port access. They are not implemented in the kernel.

`SCSI_IOCTL_PROBE_HOST` takes an input pointer `const int *`, which is a length. It uses the same pointer as an output pointer to a `char []` buffer of this length.

`SIOCADDRT` and `SIOCDELRT` take an input pointer whose type depends on the protocol:

Most protocols	<code>const struct rtentry *</code>
<code>AX.25</code>	<code>const struct ax25_route *</code>
<code>NET/ROM</code>	<code>const struct nr_route_struct *</code>

`SIOCGIFCONF` takes a `struct ifconf *`. The `ifc buf` field points to a buffer of length `ifc len` bytes, into which the kernel writes a list of type `struct ifreq []`.

`SIOCSIFHWADDR` takes an input pointer whose type depends on the protocol:

Most protocols	<code>const struct ifreq *</code>
<code>AX.25</code>	<code>const char [AX25_ADDR_LEN]</code>

`TIOCLINUX` takes a `const char *`. It uses this to distinguish several independent subcases. In the following table, `N + foo` means `foo` after an `N`-byte pad. `struct selection` is implicitly defined in `drivers/char/selection.c`:

TIOCLINUX-2	1 + const struct selection *
TIOCLINUX-3	void
TIOCLINUX-4	void
TIOCLINUX-5	4 + const struct f long [8]; g *
TIOCLINUX-6	char *
TIOCLINUX-7	char *
TIOCLINUX-10	1 + const char *

DUPLICATE ioctls

This list does not include `ioctl`s in the range `SIOCDEVPRIVATE` and `SIOCPROTOPRIVATE`:

0x00000001	FDSETPRM	FIBMAP
0x00000002	FDDEFPRM	FIGETBSZ
0x00005382	CDROMAUDIOBUFSIZ	SCSI_IOCTL_GET_IDLUN
0x00005402	SNDCTL_TMR_START	TCSETS
0x00005403	SNDCTL_TMR_STOP	TCSETSW
0x00005404	SNDCTL_TMR_CONTINUE	TCSETSF

Linux, 17 September 1995

ioperm

`ioperm`—Sets port input/output permissions

SYNOPSIS

```
#include <unistd.h>
int ioperm(unsigned long from, unsigned long num,intturn_on);
```

DESCRIPTION

`ioperm` sets the port access permission bits for the process for `num` bytes starting from port address `from` to the value `turn_on`. The use of `ioperm` requires root privileges.

Only the first 0x3ff I/O ports can be specified in this manner. For more ports, the `iopl` function must be used. Permissions are not inherited on `fork`, but on `exec` they are. This is useful for giving port access permissions to nonprivileged tasks.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and `errno` is set appropriately.

CONFORMS TO

`ioperm` is Linux specific.

SEE ALSO

`iopl(2)`

Linux, 21 January 1993

iopl

`iopl`—Changes I/O privilege level

SYNOPSIS

```
#include <unistd.h>
int iopl(int level);
```

DESCRIPTION

`ioPl` changes the I/O privilege level of the current process, as specified in `level`.

This call is necessary to allow 8514-compatible X servers to run under Linux. Because these X servers require access to all 65536 I/O ports, the `ioperm` call is not sufficient.

In addition to granting unrestricted I/O port access, running at a higher I/O privilege level also allows the process to disable interrupts. This will probably crash the system and is not recommended.

The I/O privilege level for a normal process is 0.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and `errno` is set appropriately.

ERRORS

EINVAL	<code>level</code> is greater than 3.
EPERM	The current user is not the superuser.

NOTES FROM THE KERNEL SOURCE

`ioPl` has to be used when you want to access the I/O ports beyond the 0x3ff range: To get the full 65536 ports bitmapped, you'd need 8KB of bitmaps/process, which is a bit excessive.

SEE ALSO

`ioperm(2)`

Linux 0.99.11, 24 July 1993

ipc

`ipc`—System V IPC system calls

SYNOPSIS

```
int ipc(unsigned int call, int first, int second,
int third, void *ptr, long fifth);
```

DESCRIPTION

`ipc` is a common kernel entry point for the System V IPC calls for messages, semaphores, and shared memory. `call` determines which IPC function to invoke; the other arguments are passed through to the appropriate call.

User programs should call the appropriate functions by their usual names. Only standard library implementors and kernel hackers need to know about `ipc`.

SEE ALSO

`msgctl(2)`, `msgget(2)`, `msgrcv(2)`, `msgsnd(2)`, `semctl(2)`, `semget(2)`, `semop(2)`, `shmat(2)`, `shmctl(2)`, `shmdt(2)`, `shmget(2)`

Linux 1.2.4, 15 April 1995

kill

kill—Sends signal to a process

SYNOPSIS

```
#include <sys/types.h>
#include <signal.h>
int kill(pid_t pid, int sig);
```

DESCRIPTION

The `kill` system call can be used to send any signal to any process group or process.

If `pid` is positive, then signal `sig` is sent to `pid`. In this case, `0` is returned on success and a negative value is returned on error.

If `pid` equals `-1`, then `sig` is sent to every process except the first one, from higher numbers in the `proc` table to lower. In this case, `0` is returned on success, or the error condition resulting from signaling the last process is returned.

If `pid` is less than `-1`, then `sig` is sent to every process in the process group `-pid`. In this case, the number of processes the signal was sent to is returned and a negative value is returned for failure.

RETURN VALUE

On success, `0` is returned. On error, `-1` is returned and `errno` is set appropriately.

ERRORS

EINVAL	An invalid signal is sent.
ESRCH	The <code>pid</code> or process group does not exist. Note that an existing process might be a zombie, a process that already committed termination, but has not yet been <code>wait()</code> ed for.
EPERM	The effective userID of the process calling <code>kill()</code> is not equal to the effective user ID of <code>pid</code> , unless the superuser called <code>kill()</code> .

BUGS

It is impossible to send a signal to task number one, the `init` process, for which it has not installed a signal handler. This is done to ensure that the system is not brought down accidentally.

CONFORMS TO

SVID, AT&T, POSIX.1, X/OPEN, BSD 4.3

SEE ALSO

`exit(2)`, `exit(2)`, `signal(2)`, `signal(7)`

Linux, 1 November 1995

killpg

killpg—Sends signal to a process group

SYNOPSIS

```
#include <signal.h>
int killpg(int pgrp, int sig);
```

DESCRIPTION

`killpg` sends the signal `sig` to the process group `pgrp`. See `sigaction(2)` for a list of signals. If `pgrp` is `0`, `killpg` sends the signal to the sending process's process group.

The sending process and members of the process group must have the same effective user ID, or the sender must be the superuser. As a single special case, the continue signal `SIGCONT` may be sent to any process that is a descendant of the current process.

RETURN VALUE

On success, `0` is returned. On error, `-1` is returned and `errno` is set appropriately.

ERRORS

<code>EINVAL</code>	<code>sig</code> is not a valid signal number.
<code>ESRCH</code>	No process can be found in the process group specified by <code>pgroup</code> .
<code>ESRCH</code>	The process group was given as <code>0</code> , but the sending process does not have a process group.
<code>EPERM</code>	The sending process is not the superuser and one or more of the target processes has an effective user ID different from that of the sending process.

HISTORY

The `killpg` function call appeared in BSD4.0.

SEE ALSO

`kill(2)`, `getpgid(2)`, `signal(2)`

BSD Man Page, 23 July 1993

link

`link`—Makes a new name for a file

SYNOPSIS

```
#include <unistd.h>
int link(const char *oldpath, const char *newpath);
```

DESCRIPTION

`link` creates a new link (also known as a hard link) to an existing file.

If `newpath` exists, it will *not* be overwritten.

This new name may be used exactly as the old one for any operation; both names refer to the same file (and so have the same permissions and ownership) and it is impossible to tell which name was the original.

RETURN VALUE

On success, `0` is returned. On error, `-1` is returned and `errno` is set appropriately.

ERRORS

<code>EXDEV</code>	<code>oldpath</code> and <code>newpath</code> are not on the same filesystem.
<code>EPERM</code>	The filesystem containing <code>oldpath</code> and <code>newpath</code> does not support the creation of hard links.
<code>EFAULT</code>	<code>oldpath</code> or <code>newpath</code> points outside your accessible address space.
<code>EACCES</code>	Write access to the directory containing <code>newpath</code> is not allowed for the process's effective UID, or one of the directories in <code>oldpath</code> or <code>newpath</code> did not allow search (execute) permission.
<code>ENAMETOOLONG</code>	<code>oldpath</code> or <code>newpath</code> was too long.
<code>ENOENT</code>	A directory component in <code>oldpath</code> or <code>newpath</code> does not exist or is a dangling symbolic link.
<code>ENOTDIR</code>	A component used as a directory in <code>oldpath</code> or <code>newpath</code> is not, in fact, a directory.

ENOMEM	Insufficient kernel memory was available.
EROFS	The file is on a read-only filesystem.
EEXIST	<code>newpath</code> already exists.
EMLINK	The file referred to by <code>oldpath</code> already has the maximum number of links to it.
ELoop	<code>oldpath</code> or <code>newpath</code> contains a reference to a circular symbolic link, that is, a symbolic link whose expansion contains a reference to itself.
ENOSPC	The device containing the file has no room for the new directory entry.
EPERM	<code>oldpath</code> is the <code>.</code> or <code>..</code> entry of a directory.

NOTES

Hard links, as created by `link`, cannot span filesystems. Use `symlink` if this is required.

CONFORMS TO

SVID, AT&T, POSIX, BSD 4.3

BUGS

On NFS file systems, the return code may be wrong in case the NFS server performs the link creation and dies before it can say so. Use `stat(2)` to find out if the link was created.

SEE ALSO

`symlink(2)`, `unlink(2)`, `rename(2)`, `open(2)`, `stat(2)`, `ln(1)`, `link(8)`

Linux, 17 August 1994

listen

`listen`—Listens for connections on a socket

SYNOPSIS

```
#include <sys/socket.h>
int listen(int s, int backlog);
```

DESCRIPTION

To accept connections, a socket is first created with `socket(2)`, a willingness to accept incoming connections and a queue limit for incoming connections are specified with `listen`, and then the connections are accepted with `accept(2)`. The `listen` call applies only to sockets of type `SOCK_STREAM` or `SOCK_SEQPACKET`.

The `backlog` parameter defines the maximum length the queue of pending connections may grow to. If a connection request arrives with the queue full, the client might receive an error with an indication of `ECONNREFUSED`, or, if the underlying protocol supports retransmission, the request may be ignored so that retries may succeed.

RETURN VALUE

On success, `0` is returned. On error, `-1` is returned and `errno` is set appropriately.

ERRORS

EBAADF	The argument <code>s</code> is not a valid descriptor.
ENOTSOCK	The argument <code>s</code> is not a socket.
EOPNOTSUPP	The socket is not of a type that supports the operation <code>listen</code> .

HISTORY

The `listen` function call appeared in BSD 4.2.

BUGS

If the socket is of type `af_inet` and the `backlog` argument is greater than 128, it is silently truncated to 128. For portable applications, don't rely on this value since BSD (and at least some BSD-derived systems) limit the backlog to 5.

SEE ALSO

`accept(2)`, `connect(2)`, `socket(2)`

BSD Man Page, 23 July 1993

llseek

`_llseek`—Repositions the read/write file offset

SYNOPSIS

```
#include <unistd.h>
#include <linux/unistd.h>
_syscall5(int, llseek, uint, fd, ulong, hi, ulong, lo, loff_t*,res,uint,wh);
int llseek(unsigned int fd, unsigned long offset_high,
            unsigned long offset_low, loff_t * result , unsigned int whence);
```

DESCRIPTION

The `_llseek` function repositions the offset of the file descriptor `fd` to `(offset_high<<32) | offset_low` bytes relative to the beginning of the file, the current position in the file, or the end of the file, depending on whether `whence` is `SEEK_SET`, `SEEK_CUR`, or `SEEK_END`, respectively. It returns the resulting file position in the argument `result`.

RETURN VALUES

Upon successful completion, `_llseek` returns 0. Otherwise, a value of -1 is returned and `errno` is set to indicate the error.

ERRORS

<code>EBADF</code>	<code>fd</code> is not an open file descriptor.
<code>EINVAL</code>	<code>whence</code> is invalid.

CONFORMS TO

This function is Linux specific.

BUGS

There is no support for files with a size of 2GB or more.

SEE ALSO

`lseek(2)`

Linux 1.2.9, 10 June 1995

lseek

`lseek`—Repositions read/write file offset

SYNOPSIS

```
#include <unistd.h>
off_t lseek(int fildes, off_t offset, int whence);
```

DESCRIPTION

The `lseek` function repositions the offset of the file descriptor `fd` to the argument `offset` according to the directive `whence`. The argument `fd` must be an open file descriptor. `lseek` repositions the file pointer `fd` as follows:

If `whence` is `SEEK_SET`, the offset is set to `offset` bytes.

If `whence` is `SEEK_CUR`, the offset is set to its current location plus `offset` bytes.

If `whence` is `SEEK_END`, the offset is set to the size of the file plus `offset` bytes.

The `lseek` function allows the file offset to be set beyond the end of the existing end-of-file of the file. If data is later written at this point, subsequent reads of the data in the gap return bytes of zeros (until data is actually written into the gap).

Some devices are incapable of seeking. The value of the pointer associated with such a device is undefined.

RETURN VALUES

Upon successful completion, `lseek` returns the resulting offset location as measured in bytes from the beginning of the file. Otherwise, a value of `-1` is returned and `errno` is set to indicate the error.

ERRORS

<code>EBADF</code>	<code>fd</code> is not an open file descriptor.
<code>ESPIPE</code>	<code>fd</code> is associated with a pipe, socket, or FIFO.
<code>EINVAL</code>	<code>whence</code> is not a proper value.

CONFORMS TO

POSIX, BSD 4.3

BUGS

This document's use of `whence` is incorrect English, but maintained for historical reasons.

SEE ALSO

`dup(2)`, `open(2)`, `fseek(3)`

Linux 1.2.9, 10 June 1995

mkdir

`mkdir`—Creates a directory

SYNOPSIS

```
#include <sys/types.h>
#include <fcntl.h>
#include <unistd.h>
int mkdir(const char *pathname, mode_t mode);
```

DESCRIPTION

`mkdir` attempts to create a directory named `pathname`.

`mode` specifies the permissions to use. It is modified by the process's `umask` in the usual way: the permissions of the created file is `(mode & ~umask)`.

The newly created directory will be owned by the effective UID of the process. If the directory containing the file has the set group ID bit set, or if the filesystem is mounted with BSD group semantics, the new directory will inherit the group ownership from its parent; otherwise, it will be owned by the effective GID of the process.

If the parent directory has the set group ID bit set, so will the newly created directory.

RETURN VALUE

`mkdir` returns 0 on success, or -1 if an error occurred (in which case, `errno` is set appropriately).

ERRORS

EEXIST	<code>pathname</code> already exists (not necessarily as a directory).
EFAULT	<code>pathname</code> points outside your accessible address space.
EACCES	The parent directory does not allow write permission to the process, or one of the directories in <code>pathname</code> did not allow search (execute) permission.
ENAMETOOLONG	<code>pathname</code> was too long.
ENOENT	A directory component in <code>pathname</code> does not exist or is a dangling symbolic link.
ENOTDIR	A component used as a directory in <code>pathname</code> is not, in fact, a directory.
ENOMEM	Insufficient kernel memory was available.
EROFS	<code>pathname</code> refers to a file on a read-only filesystem and write access was requested.
ELOOP	<code>pathname</code> contains a reference to a circular symbolic link, that is, a symbolic link whose expansion contains a reference to itself.
ENOSPC	The device containing <i>pathname</i> has no room for the new directory.
ENOSPC	The new directory cannot be created because the user's disk quota is exhausted.

BUGS

In some older versions of Linux (for example, 0.99pl7) all the normal filesystems sometime allow the creation of two files in the same directory with the same name. This occurs only rarely and only on a heavily loaded system. It is believed that this bug was fixed in the Minix filesystem in Linux 0.99pl8 prerelease; and it is hoped that it was fixed in the other filesystems shortly afterward.

There are many infelicities in the protocol underlying NFS.

SEE ALSO

`read(2)`, `write(2)`, `fcntl(2)`, `close(2)`, `unlink(2)`, `open(2)`, `mknod(2)`, `stat(2)`, `umask(2)`, `mount(2)`, `socket(2)`, `socket(2)`, `fopen(3)`

Linux 1.0, 29 March 1994

mknod

`mknod`—Creates a directory

SYNOPSIS

```
#include <sys/types.h>
#include <sys/stat.h>
#include <fcntl.h>
#include <unistd.h>
int mknod(const char *pathname, mode_t mode, dev_t dev);
```

DESCRIPTION

`mknod` attempts to create a filesystem node (file, device special file, or named pipe) named `pathname`, specified by `mode` and `dev`. `mode` specifies both the permissions to use and the type of node to be created.

It should be a combination (using bitwise OR) of one of the file types listed below and the permissions for the new node.

The permissions are modified by the process's `umask` in the usual way: The permissions of the created node is `(mode & ~umask)`.

The file type should be one of `S_IFREG`, `S_IFCHR`, `S_IFBLK`, or `S_IFIFO` to specify a normal file (which will be created empty), character special file, block special file, or FIFO (named pipe), respectively, or 0, which will create a normal file.

If the file type is `S_IFCHR` or `S_IFBLK`, then `dev` specifies the major and minor numbers of the newly created device special file; otherwise, it is ignored.

The newly created node will be owned by the effective UID of the process. If the directory containing the node has the set group ID bit set, or if the filesystem is mounted with BSD group semantics, the new node will inherit the group ownership from its parent directory; otherwise it will be owned by the effective GID of the process.

RETURN VALUE

`mknod` returns 0 on success, or -1 if an error occurred (in which case, `errno` is set appropriately).

ERRORS

<code>EPERM</code>	mode requested creation of something other than a FIFO (named pipe), and the caller is not the superuser; also returned if the filesystem containing <code>pathname</code> does not support the type of node requested.
<code>EINVAL</code>	mode requested creation of something other than a normal file, device special file or FIFO.
<code>EEXIST</code>	<code>pathname</code> already exists.
<code>EFAULT</code>	<code>pathname</code> points outside your accessible address space.
<code>EACCES</code>	The parent directory does not allow write permission to the process, or one of the directories in <code>pathname</code> did not allow search (execute) permission.
<code>ENAMETOOLONG</code>	<code>pathname</code> was too long.
<code>ENOENT</code>	A directory component in <code>pathname</code> does not exist or is a dangling symbolic link.
<code>ENOTDIR</code>	A component used as a directory in <code>pathname</code> is not, in fact, a directory.
<code>ENOMEM</code>	Insufficient kernel memory was available.
<code>EROFS</code>	<code>pathname</code> refers to a file on a read-only filesystem and write access was requested.
<code>ELOOP</code>	<code>pathname</code> contains a reference to a circular symbolic link, that is, a symbolic link whose expansion contains a reference to itself.
<code>ENOSPC</code>	The device containing <code>pathname</code> has no room for the new node.

BUGS

In some older versions of Linux (for example, 0.99pl7) all the normal filesystems sometime allow the creation of two files in the same directory with the same name. This occurs only rarely and only on a heavily loaded system. It is believed that this bug was fixed in the Minix filesystem in Linux 0.99pl8 prerelease; and it is hoped that it was fixed in the other filesystems shortly afterward.

`mknod` cannot be used to create directories or socket files, and cannot be used to create normal files by users other than the superuser.

There are many infelicities in the protocol underlying NFS.

SEE ALSO

`read(2)`, `write(2)`, `fcntl(2)`, `close(2)`, `unlink(2)`, `open(2)`, `mkdir(2)`, `stat(2)`, `umask(2)`, `mount(2)`, `socket(2)`, `fopen(3)`

Linux 1.0, 29 March 1994

mlock

`mlock`—Disables paging for some parts of memory

SYNOPSIS

```
#include <sys/mman.h>
int mlock(const void *addr, size_t len);
```

DESCRIPTION

`mlock` disables paging for the memory in the range starting at `addr` with length `len` bytes. All pages that contain a part of the specified memory range are guaranteed to be resident in RAM when the `mlock` system call returns successfully and they are guaranteed to stay in RAM until the pages are unlocked again by `munlock` or `munlockall` or until the process terminates or starts another program with `exec`. Child processes do not inherit page locks across a fork.

Memory locking has two main applications: real-time algorithms and high-security data processing. Real-time applications require deterministic timing, and, like scheduling, paging is one major cause of unexpected program execution delays. Real-time applications will usually also switch to a real-time scheduler with `sched_setscheduler`.

Cryptographic security software often handles critical bytes such as passwords or secret keys as data structures. As a result of paging, these secrets could be transferred onto a persistent swap store medium, where they might be accessible to the enemy long after the security software has erased the secrets in RAM and terminated.

Memory locks do not stack, that is, pages that have been locked several times by calls to `mlock` or `mlockall` will be unlocked by a single call to `munlock` for the corresponding range or by `munlockall`. Pages that are mapped to several locations or by several processes stay locked into RAM as long as they are locked at least at one location or by at least one process.

On POSIX systems on which `mlock` and `munlock` are available, `_POSIX_MEMLOCK_RANGE` is defined in `<unistd.h>` and the value `PAGESIZE` from `<limits.h>` indicates the number of bytes per page.

RETURN VALUE

On success, `mlock` returns 0. On error, -1 is returned, `errno` is set appropriately, and no changes are made to any locks in the address space of the process.

ERRORS

<code>ENOMEM</code>	Some of the specified address range does not correspond to mapped pages in the address space of the process or the process tried to exceed the maximum number of allowed locked pages.
<code>EPERM</code>	The calling process does not have appropriate privileges. Only root processes are allowed to lock pages.
<code>EINVAL</code>	<code>len</code> was not a positive number.

STANDARDS

POSIX.1b, SVR4

SEE ALSO

`munlock(2)`, `mlockall(2)`, `munlockall(2)`.

Linux 1.3.43, 26 November 1995

mlockall

`mlockall`—Disables paging for calling process

SYNOPSIS

```
#include <sys/mman.h>
int mlockall(int flags);
```

DESCRIPTION

`mlockall` disables paging for all pages mapped into the address space of the calling process. This includes the pages of the code, data and stack segments, shared libraries, user space kernel data, shared memory, and memory-mapped files. All mapped pages are guaranteed to be resident in RAM when the `mlockall` system call returns successfully and they are guaranteed to stay in RAM until the pages are unlocked again by `munlock` or `munlockall` or until the process terminates or starts another program with `exec`. Child processes do not inherit page locks across a fork.

Memory locking has two main applications: real-time algorithms and high-security data processing. Real-time applications require deterministic timing, and, like scheduling, paging is one major cause of unexpected program execution delays. Real-time applications will usually also switch to a real-time scheduler with `sched_setscheduler`. Cryptographic security software often handles critical bytes such as passwords or secret keys as data structures. As a result of paging, these secrets could be transferred onto a persistent swap store medium, where they might be accessible to the enemy long after the security software has erased the secrets in RAM and terminated. For security applications, only small parts of memory have to be locked, for which `mlock` is available.

The `flags` parameter can be constructed from the logical OR of the following constants:

<code>MCL_CURRENT</code>	Lock all pages that are currently mapped into the address space of the process.
<code>MCL_FUTURE</code>	Lock all pages that will become mapped into the address space of the process in the future. These could be, for instance, new pages required by a growing heap and stack as well as new memory mapped files or shared memory regions.

If `MCL_FUTURE` has been specified and the number of locked pages exceeds the upper limit of allowed locked pages, the system call that caused the new mapping will fail with `ENOMEM`. If these new pages have been mapped by the growing stack, the kernel will deny stack expansion and send a `SIGSEGV`.

Real-time processes should reserve enough locked stack pages before entering the time-critical section, so no page fault can be caused by function calls. This can be achieved by calling a function that has a sufficiently large automatic variable and that writes to the memory occupied by this large array in order to touch these stack pages. This way, enough pages will be mapped for the stack and can be locked into RAM. The dummy writes ensure that not even copy-on-write page faults can occur in the critical section.

Memory locks do not stack, that is, pages that have been locked several times by calls to `mlockall` or `mlock` will be unlocked by a single call to `munlockall`. Pages that are mapped to several locations or by several processes stay locked into RAM as long as they are locked at least at one location or by at least one process.

On POSIX systems on which `mlockall` and `munlockall` are available, `POSIX_MEMLOCK` is defined in `<unistd.h>`.

RETURN VALUE

On success, `mlockall` returns 0. On error, -1 is returned and `errno` is set appropriately.

ERRORS

<code>ENOMEM</code>	The process tried to exceed the maximum number of allowed locked pages.
<code>EPERM</code>	The calling process does not have appropriate privileges. Only root processes are allowed to lock pages.
<code>EINVAL</code>	Unknown flags were specified.

STANDARDS

POSIX.1b, SVR4

SEE ALSO

`munlockall(2)`, `mlock(2)`, `munlock(2)`

mmap, munmap

mmap, munmap—Map or unmap files or devices into memory

SYNOPSIS

```
#include <unistd.h>
#include <sys/mman.h>
#ifdef POSIX MAPPED FILES
void * mmap(void *start, size_t length, int prot, int flags, int fd, off_t offset);
int munmap(void *start, size_t length);
#endif
```

DESCRIPTION

The `mmap` function asks to map `length` bytes starting at offset `offset` from the file (or other object) specified by `fd` into memory, preferably at address `start`. This latter address is a hint only, and is usually specified as `0`. The actual place where the object is mapped is returned by `mmap`. The `prot` argument describes the desired memory protection. It has the following bits:

<code>PROT_EXEC</code>	Pages may be executed.
<code>PROT_READ</code>	Pages may be read.
<code>PROT_WRITE</code>	Pages may be written.

The `flags` parameter specifies the type of the mapped object, mapping options, and whether modifications made to the mapped copy of the page are private to the process or are to be shared with other references. It has the following bits:

<code>MAP_FIXED</code>	Do not select a different address than the one specified. If the specified address cannot be used, <code>mmap</code> will fail. If <code>MAP_FIXED</code> is specified, <code>start</code> must be a multiple of the pagesize. Use of this option is discouraged.
<code>MAP_SHARED</code>	Share this mapping with all other processes that map this object.
<code>MAP_PRIVATE</code>	Create a private copy-on-write mapping.

These three flags are described in POSIX.4. Linux also knows about `MAP_DENYWRITE`, `MAP_EXECUTABLE`, and `MAP_ANON` (YMOUS).

The `munmap` system call deletes the mappings for the specified address range and causes further references to addresses within the range to generate invalid memory references.

RETURN VALUE

On success, `mmap` returns a pointer to the mapped area. On error, `MAP_FAILED` (`-1`) is returned and `errno` is set appropriately. On success, `munmap` returns `0`, and on failure it returns `-1` and sets `errno` (probably to `EINVAL`).

ERRORS

<code>EBADF</code>	<code>fd</code> is not a valid file descriptor (and <code>MAP_ANONYMOUS</code> was not set).
<code>EACCES</code>	<code>MAP_PRIVATE</code> was asked, but <code>fd</code> is not open for reading. Or <code>MAP_SHARED</code> was asked and <code>PROT_WRITE</code> is set, <code>fd</code> is not open for writing.
<code>EINVAL</code>	<code>start</code> or <code>length</code> , and <code>offset</code> are too large, or not aligned on a <code>PAGESIZE</code> boundary.
<code>ETXTBUSY</code>	<code>MAP_DENYWRITE</code> was set but the object specified by <code>fd</code> is open for writing.
<code>EAGAIN</code>	The file has been locked, or too much memory has been locked.
<code>ENOMEM</code>	No memory is available.

CONFORMS TO

POSIX.4.

SEE ALSO

getpagesize(2), msync(2), shm_open(2), B. O. Gallmeister, *POSIX.4*, O'Reilly, pp. 128–129, 389–391.

Linux 1.3.86, 12 April 1996

modify_ldt

modify_ldt—Gets or sets ldt

SYNOPSIS

```
#include <linux/ldt.h> #include <linux/unistd.h>

_syscall3( int, modify_ldt, int, func, void *, ptr, unsigned long, bytecount )

int modify_ldt(int func,void *ptr, unsigned long bytecount);
```

DESCRIPTION

modify_ldt reads or writes the local descriptor table (ldt) for a process. The ldt is a per-process memory-management table used by the i386 processor. For more information on this table, see an Intel 386 processor handbook.

When func is 0, modify_ldt reads the ldt into the memory pointed to by ptr. The number of bytes read is the smaller of bytecount and the actual size of the ldt.

When func is 1, modify_ldt modifies one ldt entry. ptr points to a modify_ldt_ldt_s structure and bytecount must equal the size of this structure.

RETURN VALUE

On success, modify_ldt returns either the actual number of bytes read (for reading) or 0 (for writing). On failure, modify_ldt returns -1 and sets errno.

ERRORS

ENOSYS	func is neither 0 nor 1.
EINVAL	ptr is 0, or func is 1 and bytecount is not equal to the size of the structure modify_ldt_ldt_s, or func is 1 and the new ldt entry has illegal values.
EFAULT	ptr points outside the address space.

SEE ALSO

vm86(2)

Linux 1.3.6, 22 July 1995

get_kernel_syms, create_module, init_module, delete_module

get_kernel_syms, create_module, init_module, delete_module—Loadable module support

SYNOPSIS

```
#include <linux/module.h>

int get_kernel_syms(struct kernel_sym *table);

int create_module(char *module_name, unsigned long size);
```

```

int init_module(char *module_name, char *code, unsigned codesize,
                struct mod_routines *routines, struct symbol_table *symtab);

int delete_module(char *module_name);

struct kernel_sym {
    unsigned long value;
    char name[SYM_MAX_NAME];
};

struct mod_routines {
    int (*init)(void);
    void (*cleanup)(void);
};

struct module_ref {
    struct module *module;
    struct module_ref *next;
};

struct internal_symbol {
    void *addr;
    char *name;
};

struct symbol_table {
    int size; /* total, including string table!!! */
    int n_symbols;
    int n_refs;
    struct internal_symbol symbol[0];
    struct module_ref ref[0];
};

```

DESCRIPTION

These system calls have not yet been included in any library, which means that they have to be called by the `syscall(_NR_function)` mechanism. `get_kernel_syms(table)`; has two uses: First, if `table` is `NULL`, this call will only return the number of symbols, including module names, that are available. This number should be used to reserve memory for that many items of `struct kernel_sym`.

If `table` is not `NULL`, this call will copy all kernel symbols and module names (and version info) from the kernel to the space pointed to by `table`. The entries are ordered in module LIFO order. For each module an entry that describes the module will be followed by entries describing the symbols exported by this module.

Note that for symbols that describe a module, the `value` part of the structure will contain the kernel address of the structure that describes the module.

The `name` part of the structure is the module name prepended with `#`, as in `#my module`. The symbol that describes a module will appear before the symbols defined by this module.

Ahead of the kernel resident symbols, a module name symbol with the “dummy” name `#` will appear. This information can be used to build a table of module references when modules are stacked (or layered). `create_module(module_name, size)`; will allocate `size` bytes of kernel space for a module and also create the necessary kernel structures—called `name`—for the new module. The module will now exist in kernel space, with the status `MOD_UNINITIALIZED`. `init_module(module_name, code, codesize, routines, symtab)`;

This is the actual “module loader” that will load the module named `name` into the kernel. The parameters `code` and `codesize` refer to the relocated binary object module that is `codesize` bytes long. Note that the first 4 bytes will be used as a reference counter in kernel space, updated by the `MOD_INC_USE_COUNT` and `MOD_DEC_USE_COUNT` macros.

The functions described in routines will be used to start and stop the module. These pointers should therefore contain the addresses of the `init_module()` and `cleanup_module()` functions that have to be defined for all loadable modules.

If a module wants to export symbols for use by other modules, or if the module makes references to symbols defined by other modules, the parameter `symtab` has to point to a structure that describes these. A `NULL` value for `symtab` means that no symbols are exported and no references to other modules are made.

The `symtab` that will be copied into the kernel consists of a symbol table structure immediately followed by a string table, containing the names of the symbols defined by the module. The size element has to include the size of this string table as well. Special considerations follow.

The `n_symbols` and `n_refs` elements tell how many symbols and how many module references are included in the symbol table structure. Immediately after these integers, the array of symbol definitions follows. The name element in each `struct` internal symbol should actually not be an ordinary pointer, but instead the offset of the corresponding string table entry relative to the start of the symbol table structure.

When all defined symbols have been listed, the `symbol_table` structure continues with the array of module references, as described by the `struct module_ref` elements. Only the module field of these structures has to be initialized. The module addresses that were obtained from a previous `get_kernel_syms` call, for elements with names starting with `#` should be copied to this field.

If the module could be successfully loaded, and if the call to the module function `init_module()` also succeeds, the status of the module will be changed to `MOD_RUNNING`. Otherwise, the kernel memory occupied by module will be freed.

`delete_module(module_name);` should be used to unload a module. If the module reference count shows that the module is not active, and if there are no references to this module from other modules, the module function `cleanup_module()` will be called. If all these steps succeed, the kernel memory occupied by the module and its structures will be freed.

DIAGNOSTICS

If there are any errors, these functions will return the value `-1`, and the global variable `errno` will contain the error number. A descriptive text will also be written on the console device.

SEE ALSO

`insmod(1)`, `rmmod(1)`, `lsmod(1)`, `ksyms(1)`

HISTORY

The module support was first conceived by Anonymous.

Linux version by Bas Laarhoven (bas@vimec.nl), 0.99.14 version by Jon Tombs (jon@gtex02.us.es), extended by Bjorn Ekwall (bjorn@blox.se).

BUGS

Naah...

Linux, 25 January 1995

mount, umount

`mount`, `umount`—Mount and unmount filesystems.

SYNOPSIS

```
#include <sys/mount.h>
#include <linux/fs.h>
int mount(const char *specialfile, const char *dir ,
const char * filesystemtype, unsigned long rwflag , const void * data);
int umount(const char *specialfile);
int umount(const char *dir);
```

DESCRIPTION

mount attaches the filesystem specified by `specialfile` (which is often a device name) to the directory specified by `dir`.

umount removes the attachment of the filesystem specified by `specialfile` or `dir`.

Only the superuser may mount and unmount filesystems.

The `filesystemtype` argument may take one of the values listed in `/proc/filesystems` (such as `minix`, `ext2`, `msdos`, `proc`, `nfs`, `iso9660`).

The `rwflag` argument has the magic number `0xC0ED` in the top 16 bits, and various mount flags (as defined in `<linux/fs.h>`) in the low order 16 bits:

```
#define MS_RDONLY 1 /* mount read-only */
#define MS_NOSUID 2 /* ignore suid and sgid bits */
#define MS_NODEV 4 /* disallow access to device special files */
#define MS_NOEXEC 8 /* disallow program execution */
#define MS_SYNC 16 /* writes are synced at once */
#define MS_REMOUNT 32 /* alter flags of a mounted FS */
#define MS_MGC_VAL 0xC0ED0000
```

If the magic number is absent, then the last two arguments are not used.

The `data` argument is interpreted by the different filesystems.

RETURN VALUE

On success, `0` is returned. On error, `-1` is returned and `errno` is set appropriately.

ERRORS

The following error values result from filesystem type independent errors. Each filesystem type may have its own special errors and its own special behavior. See the kernel source code for details.

EPERM	The user is not the superuser.
ENODEV	filesystemtype not configured in the kernel.
ENOTBLK	specialfile is not a block device (if a device was required).
EBUSY	specialfile is already mounted. Or it cannot be remounted read-only because it still holds files open for writing. Or, it cannot be mounted on dir because dir is still busy (it is the working directory of some task, the mount point of another device, has open files, and so on).
EINVAL	specialfile had an invalid superblock. Or, a remount was attempted, while specialfile was not already mounted on dir. Or, an umount was attempted, while dir was not a mount point.
EFAULT	One of the pointer arguments points outside the user address space.
ENOMEM	The kernel could not allocate a free page to copy filenames or data into.
ENAMETOOLONG	A pathname was longer than MAXPATHLEN.
ENOENT	A pathname was empty or had a nonexistent component.
ENOTDIR	The second argument, or a prefix of the first argument, is not a directory.
EACCES	A component of a path was not searchable. Or, mounting a read-only filesystem was attempted without giving the MS_RDONLY flag. Or, the block device specialfile is located on a filesystem mounted with the MS_NODEV option.
ENXIO	The major number of the block device specialfile is out of range.
EMFILE	(In case no block device is required:) Table of dummy devices is full.

CONFORMS TO

These functions are rather Linux specific.

SEE ALSO

mount(8), umount(8)

Linux 1.1.67, 28 November 1994

mprotect

mprotect—Controls allowable accesses to a region of memory

SYNOPSIS

```
#include <sys/mman.h>
int mprotect(caddr_t addr, size_t *len, int prot);
```

DESCRIPTION

mprotect controls how a section of memory can be accessed. If an access is disallowed by the protection given it, the program receives a SIGSEGV.

prot is a bitwise-OR of the following values:

PROT_NONE	The memory cannot be accessed at all.
PROT_READ	The memory can be read.
PROT_WRITE	The memory can be written to.
PROT_EXEC	The memory can contain executing code.

The new protection replaces any existing protection. For example, if the memory had previously been marked PROT_READ, and mprotect is then called with prot PROT_WRITE, it will no longer be readable.

RETURN VALUE

On success, mprotect returns 0. On error, -1 is returned and errno is set appropriately.

ERRORS

EINVAL	addr is not a valid pointer.
EFAULT	The memory cannot be accessed.
EACCES	The memory cannot be given the specified access. This can happen, for example, if you mmap(2) a file to which you have read-only access, then ask mprotect to mark it PROT_WRITE.
ENOMEM	Internal kernel structures could not be allocated.

EXAMPLE

```
#include <stdio.h>
#include <stdlib.h>
#include <errno.h>
#include <sys/mman.h>

int
main(void)
{
    char *p;
    char c;
```



```

/* Allocate a buffer; it will have the default
   protection of PROT_READ|PROT_WRITE. */
p = malloc(1024);
if (!p) {
    perror("Couldn't malloc(1024)");
    exit(errno);
}

c = p[666];          /* Read; ok */
p[666] = 42;         /* Write; ok */

/* Mark the buffer read-only. */
if (mprotect(p, 1024, PROT_READ)) {
    perror("Couldn't mprotect");
    exit(errno);
}

c = p[666];          /* Read; ok */
p[666] = 42;         /* Write; program dies on SIGSEGV */

exit(0);
}

```

SEE ALSO

mmap(2)

Linux 1.2, 23 June 1995

mremap

mremap—Remaps a virtual memory address

SYNOPSIS

```

#include <unistd.h>
#include <sys/mman.h>
void * mremap(void * old_address, size_t old_size , size_t new_size, unsigned long flags)

```

DESCRIPTION

mremap expands (or shrinks) an existing memory mapping, potentially moving it at the same time (controlled by the `flags` argument and the available virtual address space).

`old_address` is the old address of the virtual memory block that you want to expand (or shrink). Note that `old_address` has to be page aligned. `old_size` is the old size of the virtual memory block. `new_size` is the requested size of the virtual memory block after the resize.

The `flags` argument is a bitmap of flags.

In Linux the memory is divided into pages. A user process has one or linear virtual memory segments. Each virtual memory segment has one or more mappings to real memory pages (in the page table). Each virtual memory segment has its own protection (access rights), which may cause a segmentation violation if the memory is accessed incorrectly (for example, writing to a read-only segment). Accessing virtual memory outside of the segments will also cause a segmentation violation.

mremap uses the Linux page table scheme. mremap changes the mapping between virtual addresses and memory pages. This can be used to implement a very efficient `realloc`.

FLAGS

`MREMAP_MAYMOVE`

Indicates whether the operation should fail, or changes the virtual address if the resize cannot be done at the current virtual address.

RETURN VALUE

On success, `mremap` returns a pointer to the new virtual memory area. On error, `-1` is returned, and `errno` is set appropriately.

ERRORS

`EINVAL`

An invalid argument was given. Most likely `old_address` was not page aligned.

`EFAULT`

Segmentation fault. Some address in the range `old_address` to `old_address+old_size` is an invalid virtual memory address for this process. You can also get `EFAULT` even if there exist mappings that cover the whole address space requested, but those mappings are of different types.

`EAGAIN`

The memory segment is locked and cannot be remapped.

`ENOMEM`

The memory area cannot be expanded at the current virtual address, and the `MREMAP_MAYMOVE` flag is not set in `flags`. Or there is not enough (virtual) memory available.

SEE ALSO

`getpagesize(2)`, `realloc(3)`, `malloc(3)`, `brk(2)`, `sbrk(2)`, `mmap(2)`, your favorite OS text book for more information on paged memory. (*Modern Operating Systems* by Andrew S. Tannenbaum, *Inside Linux* by Randolph Bentson, *The Design of the UNIX Operating System* by Maurice J. Bach.)

Linux 1.3.87, 12 April 1996

msgctl

`msgctl`—Handles message control operations

SYNOPSIS

```
# include <sys/types.h>
# include <sys/ipc.h>
# include <sys/msg.h>
int msgctl ( int msqid, int cmd , struct msqid_ds *buf );
int cmd, struct msqid_ds *buf;
```

DESCRIPTION

The function performs the control operation specified by `cmd` on the message queue with identifier `msqid`. Legal values for `cmd` are

`IPC_STAT`

Copies info from the message queue data structure into the structure pointed to by `buf`. The user must have read access privileges on the message queue.

`IPC_SET`

Writes the values of some members of the `msqid_ds` structure pointed to by `buf` to the message queue data structure, updating also its `msg_ctime` member. Considered members from the user-supplied struct `msqid_ds` pointed to by `buf` are `msg_perm.uid`, `msg_perm.gid`, and `msg_perm.mode` /* only lowest 9-bits */ `msg_qbytes`.

The calling process effective user ID must be one among superuser, creator or owner of the message queue. Only the superuser can raise the `msg_qbytes` value beyond the system parameter `MSGMNB`.

`IPC_RMID`

Remove immediately the message queue and its data structures awakening all waiting reader and writer processes (with an error return and `errno` set to `EIDRM`). The calling process effective user ID must be one among superuser, creator or owner of the message queue.

RETURN VALUE

If successful, the return value will be 0; otherwise, the return value will be -1 with `errno` indicating the error.

ERRORS

For a failing return, `errno` will be set to one of the following values:

EACCESS	The argument <code>cmd</code> is equal to <code>IPC_STAT</code> , but the calling process has no read access permissions on the message queue <code>msqid</code> .
EFAULT	The argument <code>cmd</code> has value <code>IPC_SET</code> or <code>IPC_STAT</code> , but the address pointed to by <code>buf</code> isn't accessible.
EIDRM	The message queue was removed.
EINVAL	Invalid value for <code>cmd</code> or <code>msqid</code> .
EPERM	The argument <code>cmd</code> has value <code>IPC_SET</code> or <code>IPC_RMID</code> , but the calling process effective user ID has insufficient privileges to execute the command. Note that this is also the case of a nonsuperuser process trying to increase the <code>msg_qbytes</code> value beyond the value specified by the system parameter <code>MSGMNB</code> .

NOTES

The `IPC_INFO`, `MSG_STAT`, and `MSG_INFO` control calls are used by the `ipcs(1)` program to provide information on allocated resources. In the future these can be modified as needed or moved to a `proc` file system interface.

SEE ALSO

`ipc(5)`, `msgget(2)`, `msgsnd(2)`, `msgrcv(2)`

Linux 0.99.13, 1 November 1993

msgget

`msgget`—Gets a message queue identifier

SYNOPSIS

```
# include <sys/types.h>
# include <sys/ipc.h>
# include <sys/msg.h>
int msgget ( key_t key, int msgflg );
```

DESCRIPTION

The function returns the message queue identifier associated to the value of the `key` argument. A new message queue is created if `key` has value `IPC_PRIVATE` or `key` isn't `IPC_PRIVATE`, no existing message queue is associated to `key`, and `IPC_CREAT` is asserted in `msgflg` (that is, `msgflg & IPC_CREAT` isn't 0). The presence in `msgflg` of the fields `IPC_CREAT` and `IPC_EXCL` plays the same role, with respect to the existence of the message queue, as the presence of `O_CREAT` and `O_EXCL` in the mode argument of the `open(2)` system call: That is, the `msgget` function fails if `msgflg` asserts both `IPC_CREAT` and `IPC_EXCL` and a message queue already exists for `key`.

Upon creation, the lower 9 bits of the argument `msgflg` define the access permissions (for owner, group, and others) to the message queue in the same format, and with the same meaning, as for the access permissions parameter in the `open(2)` or `creat(2)` system calls (though the execute permissions are not used by the system).

Furthermore, while creating, the system call initializes the system message queue data structure `msqid_ds` as follows:

`msg_perm.cuid` and `msg_perm.uid` are set to the effective user ID of the calling process.

`msg_perm.cgid` and `msg_perm.gid` are set to the effective group ID of the calling process.

The lowest-order 9 bits of `msg_perm.mode` are set to the lowest-order 9 bit of `msgflg`.

`msg_qnum`, `msg_lspid`, `msg_lrpid`, `msg_stime`, and `msg_rtime` are set to 0.

`msg_ctime` is set to the current time.

`msg_qbytes` is set to the system limit `MSGMNB`.

If the message queue already exists, the access permissions are verified, and a check is made to see whether it is marked for destruction.

RETURN VALUE

If successful, the return value will be the message queue identifier (a positive integer), otherwise -1 with `errno` indicating the error.

ERRORS

For a failing return, `errno` will be set to one of the following values:

EACCESS	A message queue exists for key, but the calling process has no access permissions to the queue.
EEXIST	A message queue exists for key and <code>msgflg</code> was asserting both <code>IPC_CREAT</code> and <code>IPC_EXCL</code> .
EIDRM	The message queue is marked as to be removed.
ENOENT	No message queue exists for key and <code>msgflg</code> wasn't asserting <code>IPC_CREAT</code> .
ENOMEM	A message queue has to be created but the system has not enough memory for the new data structure.
ENOSPC	A message queue has to be created but the system limit for the maximum number of message queues (<code>MSGMNI</code>) would be exceeded.

NOTES

`IPC_PRIVATE` isn't a flag field, but a `key_t` type. If this special value is used for key, the system call ignores everything but the lowest-order 9 bits of `msgflg` and creates a new message queue (on success).

The following is a system limit on message queue resources affecting a `msgget` call:

<code>MSGMNI</code>	Systemwide maximum number of message queues; policy dependent.

BUGS

Use of `IPC_PRIVATE` doesn't inhibit other processes the access to the allocated message queue.

As for the files, there is currently no intrinsic way for a process to ensure exclusive access to a message queue. Asserting both `IPC_CREAT` and `IPC_EXCL` in `msgflg` only ensures (on success) that a new message queue will be created; it doesn't imply exclusive access to the message queue.

SEE ALSO

`ftok(3)`, `ipc(5)`, `msgctl(2)`, `msgsnd(2)`, `msgrcv(2)`

Linux 0.99.13, 1 November 1993

msgop

`msgop`—Completes message operations

SYNOPSIS

```
# include <sys/types.h>
# include <sys/ipc.h>
# include <sys/msg.h>
```

```
int msgsnd ( int msqid, struct msgbuf *msgp,int msgsz,int msgflg );

int msgrcv ( int msqid, struct msgbuf *msgp,int msgsz,long msgtyp,int msgflg );
```

DESCRIPTION

To send or receive a message, the calling process allocates a structure that looks like the following:

```
struct msgbuf {
    long mtype; /* message type, must be > 0 */
    char mtext[1]; /* message data */
};
```

but with an array `mtext` of size `msgsz`, a nonnegative integer value. The structure member `mtype` must have a strictly positive integer value that can be used by the receiving process for message selection (see the section about `msgrcv`).

The calling process must have write access permissions to send and read access permissions to receive a message on the queue.

The `msgsnd` system call queues a copy of the message pointed to by the `msgp` argument on the message queue whose identifier is specified by the value of the `msqid` argument.

The argument `msgflg` specifies the system call behavior if queuing the new message will require more than `msg_qbytes` in the queue. Asserting `IPC_NOWAIT`, the message will not be sent and the system call fails, returning with `errno` set to `EAGAIN`. Otherwise the process is suspended until the condition for the suspension no longer exists (in which case the message is sent and the system call succeeds), or the queue is removed (in which case the system call fails with `errno` set to `EIDRM`), or the process receives a signal that has to be caught (in which case the system call fails with `errno` set to `EINTR`).

Upon successful completion, the message queue data structure is updated as follows:

<code>msg_lspid</code>	Set to the process ID of the calling process.
<code>msg_qnum</code>	Incremented by 1.
<code>msg_stime</code>	Set to the current time.

The system call `msgrcv` reads a message from the message queue specified by `msqid` into the `msgbuf` pointed to by the `msgp` argument, removing from the queue, on success, the read message.

The argument `msgsz` specifies the maximum size in bytes for the member `mtext` of the structure pointed to by the `msgp` argument. If the message text has length greater than `msgsz`, then if the `msgflg` argument asserts `MSG_NOERROR`, the message text will be truncated (and the truncated part will be lost); otherwise, the message isn't removed from the queue and the system call fails, returning with `errno` set to `E2BIG`.

The argument `msgtyp` specifies the type of message requested as follows:

If `msgtyp` is 0, the message on the queue's front is read.

If `msgtyp` is greater than 0, the first message on the queue of type `msgtyp` is read if `MSG_EXCEPT` isn't asserted by the `msgflg` argument; otherwise, the first message on the queue of type not equal to `msgtyp` will be read.

If `msgtyp` is less than 0, the first message on the queue with the lowest type less than or equal to the absolute value of `msgtyp` will be read.

The `msgflg` argument asserts none, one, or more (OR-ing them) among the following flags:

<code>IPC_NOWAIT</code>	For immediate return if no message of the requested type is on the queue. The system call fails with <code>errno</code> set to <code>ENOMSG</code> .
<code>MSG_EXCEPT</code>	Used with <code>msgtyp</code> greater than 0 to read the first message on the queue with message type that differs from <code>msgtyp</code> .
<code>MSG_NOERROR</code>	To truncate the message text if longer than <code>msgsz</code> bytes.

If no message of the requested type is available and `IPC_NOWAIT` isn't asserted in `msgflg`, the calling process is blocked until one of the following conditions occurs:

A message of the desired type is placed on the queue.

The message queue is removed from the system. In such a case the system call fails with `errno` set to `EIDRM`.

The calling process receives a signal that has to be caught. In such a case the system call fails with `errno` set to `EINTR`.

Upon successful completion, the message queue data structure is updated as follows:

<code>msg_lrpId</code>	Set to the process ID of the calling process.
<code>msg_qnum</code>	Decrement by 1.
<code>msg_rtime</code>	Set to the current time.

RETURN VALUE

On a failure, both functions return `-1` with `errno` indicating the error; otherwise, `msgsnd` returns `0` and `msgrcv` returns the number of bytes actually copied into the `mtext` array.

ERRORS

When `msgsnd` fails, at return `errno` will be set to one of the following values:

<code>EAGAIN</code>	The message can't be sent due to the <code>msg_qbytes</code> limit for the queue, and <code>IPC_NOWAIT</code> was asserted in <code>msgflg</code> .
<code>EACCES</code>	The calling process has no write access permissions on the message queue.
<code>EFAULT</code>	The address pointed to by <code>msgp</code> isn't accessible.
<code>EIDRM</code>	The message queue was removed.
<code>EINTR</code>	Sleeping on a full message queue condition, the process received a signal that had to be caught.
<code>EINVAL</code>	Invalid <code>msgid</code> value, or nonpositive <code>mtype</code> value, or invalid <code>msgsz</code> value (less than <code>0</code> or greater than the system value <code>MSGMAX</code>).
<code>ENOMEM</code>	The system has not enough memory to make a copy of the supplied <code>msgbuf</code> .

When `msgrcv` fails, at return `errno` will be set to one of the following values:

<code>E2BIG</code>	The message text length is greater than <code>msgsz</code> and <code>MSG_NOERROR</code> isn't asserted in <code>msgflg</code> .
<code>EACCES</code>	The calling process has no read access permissions on the message queue.
<code>EFAULT</code>	The address pointed to by <code>msgp</code> isn't accessible.
<code>EIDRM</code>	While the process was sleeping to receive a message, the message queue was removed.
<code>EINTR</code>	While the process was sleeping to receive a message, the process received a signal that had to be caught.
<code>EINVAL</code>	Illegal <code>msgid</code> value, or <code>msgsz</code> less than <code>0</code> .
<code>ENOMSG</code>	<code>IPC_NOWAIT</code> was asserted in <code>msgflg</code> and no message of the requested type existed on the message queue.

NOTES

The followings are system limits affecting a `msgsnd` system call:

<code>MSGMAX</code>	Maximum size for a message text; the implementation set this value to 4080 bytes.
<code>MSGMNB</code>	Default maximum size in bytes of a message queue; policy dependent. The superuser can increase the size of a message queue beyond <code>MSGMNB</code> by a <code>msgctl</code> system call.

The implementation has no intrinsic limits for the systemwide maximum number of message headers (`MSGTQL`) and for the systemwide maximum size in bytes of the message pool (`MSGPOOL`).

SEE ALSO

ipc(5), msgctl(2), msgget(2), msgrcv(2), msgsnd(2)

Linux 0.99.13, 1 November 1993

msync

msync—Synchronizes a file with a memory map

SYNOPSIS

```
#include <unistd.h>
#include <sys/mman.h>

#ifdef POSIX_MAPPED_FILES
#ifdef POSIX_SYNCHRONIZED_IO

int msync(const void *start, size_t length, int flags);
#endif
#endif
```

DESCRIPTION

msync flushes changes made to the in-core copy of a file that was mapped into memory using **mmap(2)** back to disk. Without use of this call, there is no guarantee that changes are written back before **munmap(2)** is called. To be more precise, the part of the file that corresponds to the memory area starting at **start** and having length **length** is updated. The **flags** argument may have the bits **MS_ASYNC**, **MS_SYNC**, and **MS_INVALIDATE** set, but not both **MS_ASYNC** and **MS_SYNC**. **MS_ASYNC** specifies that an update be scheduled, but the call returns immediately. **MS_SYNC** asks for an update and waits for it to complete. **MS_INVALIDATE** asks to invalidate other mappings of the same file (so that they can be updated with the fresh values just written).

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and **errno** is set appropriately.

ERRORS

EINVAL	start is not a multiple of PAGESIZE , or any bit other than MS_ASYNC MS_INVALIDATE MS_SYNC is set in flags .
EFAULT	The indicated memory (or part of it) was not mapped.

CONFORMS TO

POSIX.4.

SEE ALSO

mmap(2), B.O. Gallmeister, POSIX.4, O'Reilly, pp. 128–129, 389–391.

Linux 1.3.86, 12 April 1996

munlock

munlock—Reenables paging for some parts of memory

SYNOPSIS

```
#include <sys/mman.h>

int munlock(const void *addr, size_t len);
```

DESCRIPTION

`munlock` reenables paging for the memory in the range starting at `addr` with length `len` bytes. All pages that contain a part of the specified memory range can after calling `munlock` be moved to external swap space again by the kernel.

Memory locks do not stack, that is, pages that have been locked several times by calls to `mlock` or `mlockall` will be unlocked by a single call to `munlock` for the corresponding range or by `munlockall`. Pages that are mapped to several locations or by several processes stay locked into RAM as long as they are locked at least at one location or by at least one process.

On POSIX systems on which `mlock` and `munlock` are available, `_POSIX_MEMLOCK_RANGE` is defined in `<unistd.h>` and the value `PAGESIZE` from `<limits.h>` indicates the number of bytes per page.

RETURN VALUE

On success, `munlock` returns 0. On error, -1 is returned, `errno` is set appropriately, and no changes are made to any locks in the address space of the process.

ERRORS

<code>ENOMEM</code>	Some of the specified address range does not correspond to mapped pages in the address space of the process.
<code>EINVAL</code>	<code>len</code> was not a positive number.

STANDARDS

POSIX.1b, SVR4

SEE ALSO

`mlock(2)`, `mlockall(2)`, `munlockall(2)`.

Linux 1.3.43, 26 November 1995

munlockall

`munlockall`—Reenables paging for calling process

SYNOPSIS

```
#include <sys/mman.h>
int munlockall(void);
```

DESCRIPTION

`munlockall` reenables paging for all pages mapped into the address space of the calling process.

Memory locks do not stack, that is, pages that have been locked several times by calls to `mlock` or `mlockall` will be unlocked by a single call to `munlockall`. Pages that are mapped to several locations or by several processes stay locked into RAM as long as they are locked at least at one location or by at least one process.

On POSIX systems on which `mlockall` and `munlockall` are available, `_POSIX_MEMLOCK` is defined in `<unistd.h>`.

RETURN VALUE

On success, `munlockall` returns 0. On error, -1 is returned and `errno` is set appropriately.

STANDARDS

POSIX.1b, SVR4

SEE ALSO

mlockall(2), mlock(2), munlock(2)

Linux 1.3.43, 26 November 1995

nanosleep

nanosleep—Pauses execution for a specified time

SYNOPSIS

```
#include <time.h>

int nanosleep(const struct timespec *req, struct timespec *rem);
```

DESCRIPTION

nanosleep delays the execution of the program for at least the time specified in **req*. The function can return earlier if a signal has been delivered to the process. In this case, it returns -1, sets *errno* to *EINTR*, and writes the remaining time into the structure pointed to by *rem* unless *rem* is NULL. The value of **rem* can then be used to call nanosleep again and complete the specified pause.

The structure *timespec* is used to specify intervals of time with nanosecond precision. It is specified in *<time.h>* and has the form

```
struct timespec
{
    time_t tv_sec; /* seconds */
    long tv_nsec; /* nanoseconds */
};
```

The value of the nanoseconds field must be in the range 0 to 999 999 999.

Compared to *sleep(3)* and *usleep(3)*, nanosleep has the advantage of not affecting any signals; it is standardized by POSIX, it provides higher timing resolution, and it allows to continue a sleep that has been interrupted by a signal more easily.

ERRORS

In case of an error or exception, the nanosleep system call returns -1 instead of 0 and sets *errno* to one of the following values:

EINTR	The pause has been interrupted by a nonblocked signal that was delivered to the process. The remaining sleep time has been written into <i>*rem</i> so that the process can easily call nanosleep again and continue with the pause.
EINVAL	The value in the <i>tv_nsec</i> field was not in the range 0 to 999 999 999 or <i>tv_sec</i> was negative.

BUGS

The current implementation of nanosleep is based on the normal kernel timer mechanism, which has a resolution of 1/HZ s (that is, 10ms on Linux/i386 and 1ms on Linux/Alpha). Therefore, nanosleep pauses always for at least the specified time; however, it can take up to 10ms longer than specified until the process becomes runnable again. For the same reason, the value returned in case of a delivered signal in **rem* is usually rounded to the next larger multiple of 1/HZ s.

Because some applications require much more precise pauses (for example, in order to control some time-critical hardware), nanosleep is also capable of short high-precision pauses. If the process is scheduled under a real-time policy such as *SCHED_FIFO* or *SCHED_RR*, then pauses of up to 2ms will be performed as busy waits with microsecond precision.

STANDARDS

POSIX.1b

SEE ALSO

`sleep(3)`, `usleep(3)`, `sched_setscheduler(2)`, `timer_create(2)`

Linux 1.3.85, 10 April 1996

nice

`nice`—Changes process priority

SYNOPSIS

```
#include <unistd.h>
int nice(int inc);
```

DESCRIPTION

`nice` adds `inc` to the priority for the calling PID. Note that only the superuser may specify a negative increment, or priority increase. Note that internally, a higher number is a higher priority. Do not confuse this with the priority scheme as used by the `nice` interface.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and `errno` is set appropriately.

ERRORS

<code>EPERM</code>	A nonsuperuser attempts to do a priority increase, a numerical decrease, by supplying a negative <code>inc</code> .

CONFORMS TO

SVID EXT, AT&T, X/OPEN, BSD 4.3

SEE ALSO

`nice(1)`, `setpriority(2)`, `fork(2)`, `renice(8)`

Linux, 28 March 1992

oldfstat, oldlstat, oldstat, oldolduname, olduname

`oldfstat`, `oldlstat`, `oldstat`, `oldolduname`, `olduname`—Obsolete system calls

SYNOPSIS

Obsolete system calls.

DESCRIPTION

The Linux 1.3.6 kernel implements these calls to support old executables. These calls return structures that have grown since their first implementations, but old executables must continue to receive old smaller structures.

Current executables should be linked with current libraries and never use these calls.

SEE ALSO

`fstat(2)`, `lstat(2)`, `stat(2)`, `uname(2)`, `undocumented(2)`, `unimplemented(2)`

Linux 1.3.6, 22 July 1995

open, creat

open, creat—Open and possibly create a file or device

SYNOPSIS

```
#include <sys/types.h>
#include <sys/stat.h>
#include <fcntl.h>
int open(const char *pathname, int flags);
int open(const char *pathname, int flags, mode_t mode);
int creat(const char *pathname, mode_t mode);
```

DESCRIPTION

open attempts to open a file and return a file descriptor (a small, nonnegative integer for use in read, write, and so on).

flags is one of O_RDONLY, O_WRONLY, or O_RDWR, which request opening the file read-only, write-only, or read/write, respectively.

flags may also be bitwise-ORed with one or more of the following:

O_CREAT	If the file does not exist it will be created.
O_EXCL	When used with O_CREAT, if the file already exists, it is an error and the open will fail. See the “Bugs” section, though.
O_NOCTTY	If pathname refers to a terminal device—see tty(4)—it will not become the process’s controlling terminal even if the process does not have one.
O_TRUNC	If the file already exists, it will be truncated.
O_APPEND	The file is opened in append mode. Initially, and before each write, the file pointer is positioned at the end of the file, as if with lseek.
O_NONBLOCK or O_NDELAY	The file is opened in nonblocking mode. Neither the open nor any subsequent operations on the file descriptor that is returned will cause the calling process to wait.
O_SYNC	The file is opened for synchronous I/O. Any writes on the resulting file descriptor will block the calling process until the data has been physically written to the underlying hardware. See the “Bugs” section, though.

Some of these optional flags can be altered using fcntl after the file has been opened.

mode specifies the permissions to use if a new file is created. It is modified by the process’s umask in the usual way: The permission of the created file is (mode & ~umask).

The following symbolic constants are provided for mode:

S_IRWXU	00700 user (file owner) has read, write, and execute permission.
S_IRUSR (S_IREAD)	00400 user has read permission.
S_IWUSR (S_IWRITE)	00200 user has write permission.
S_IXUSR (S_IEXEC)	00100 user has execute permission.
S_IRWXG	00070 group has read, write, and execute permission.
S_IRGRP	00040 group has read permission.
S_IWGRP	00020 group has write permission.
S_IXGRP	00010 group has execute permission.
S_IRWXO	00007 others have read, write, and execute permission.
S_IROTH	00004 others have read permission.
S_IWOTH	00002 others have write permission.
S_IXOTH	00001 others have execute permission.

mode should always be specified when O_CREAT is in the flags, and is ignored otherwise.

creat is equivalent to open with flags equal to O_CREAT|O_WRONLY|O_TRUNC.

RETURN VALUE

`open` and `creat` return the new file descriptor, or `-1` if an error occurred (in which case `errno` is set appropriately). Note that `open` can open device-special files, but `creat` cannot create them—use `mknod(2)` instead.

ERRORS

EEXIST	<code>pathname</code> already exists and <code>O_CREAT</code> and <code>O_EXCL</code> were used.
EISDIR	<code>pathname</code> refers to a directory and the access requested involved writing.
ETXTBSY	<code>pathname</code> refers to an executable image which is currently being executed and write access was requested.
EFAULT	<code>pathname</code> points outside your accessible address space.
EACCES	The requested access to the file is not allowed, or one of the directories in <code>pathname</code> did not allow search (execute) permission.
ENAMETOOLONG	<code>pathname</code> was too long.
ENOENT	A directory component in <code>pathname</code> does not exist or is a dangling symbolic link.
ENOTDIR	A component used as a directory in <code>pathname</code> is not, in fact, a directory.
EMFILE	The process already has the maximum number of files open.
ENFILE	The limit on the total number of files open on the system has been reached.
ENOMEM	Insufficient kernel memory was available.
EROFS	<code>pathname</code> refers to a file on a read-only filesystem and write access was requested.
ELOOP	<code>pathname</code> contains a reference to a circular symbolic link, that is, a symbolic link whose expansion contains a reference to itself.
ENOSPC	<code>pathname</code> was to be created but the device containing <code>pathname</code> has no room for the new file.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

BUGS

`O_SYNC` is not currently implemented (as of Linux 0.99pl7).

There are many infelicities in the protocol underlying NFS, affecting amongst others `O_SYNC`, `O_NDELAY`, and `O_APPEND`.

`O_EXCL` is broken on NFS filesystems; programs that rely on it for performing locking tasks will contain a race condition. The solution for performing atomic file locking using a lockfile is to create a unique file on the same `fs` (for example, incorporating hostname and PID), use `link(2)` to make a link to the lockfile, and use `stat(2)` on the unique file to check if its link count has increased to 2. Do not use the return value of the `link()` call.

SEE ALSO

`read(2)`, `write(2)`, `fcntl(2)`, `close(2)`, `unlink(2)`, `mknod(2)`, `stat(2)`, `umask(2)`, `mount(2)`, `socket(2)`, `socket(2)`, `fopen(3)`, `link(2)`

Linux 0.99.7, 21 July 1993

outb, outw, outl, outsb, outsw, outsl

`outb`, `outw`, `outl`, `outsb`, `outsw`, `outsl`—Port output

`inb`, `inw`, `inl`, `insb`, `insw`, `insl`—Port input

`outb_p`, `outw_p`, `outl_p`, `inb_p`, `inw_p`, `inl_p`—Pause I/O

DESCRIPTION

This family of functions is used to do low-level port input and output. They are primarily designed for internal kernel use, but can be used from user space, given the following information in addition to that given in `outb(9)`.

You compile with `-O` or `-O2` or something similar. The functions are defined as inline macros and will not be substituted in without optimization enabled, causing unresolved references at link time.

You use `ioperm(2)` or alternatively `iopl(2)` to tell the kernel to allow the user space application to access the I/O ports in question. Failure to do this will cause the application to receive a segmentation fault.

CONFORMS TO

`outb` and friends are hardware specific. The `port` and `value` arguments are in the opposite order from most DOS implementations.

SEE ALSO

`outb(9)`, `ioperm(2)`, `iopl(2)`

Linux, 29 November 1995

pause

`pause`—Waits for signal

SYNOPSIS

```
#include <unistd.h>
int pause(void);
```

DESCRIPTION

The `pause` system call causes the invoking process to sleep until a signal is received.

RETURN VALUE

`pause` always returns `-1`, and `errno` is set to `ERESTARTNOHAND`.

ERRORS

<code>EINTR</code>	Signal was received.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

SEE ALSO

`kill(2)`, `select(2)`, `signal(2)`

Linux, 31 August 1995

personality

`personality`—Sets the process execution domain

SYNOPSIS

```
int personality(unsigned long persona);
```

DESCRIPTION

Linux supports different execution domains, or personalities, for each process. Among other things, execution domains tell Linux how to map signal numbers into signal actions. The execution domain system allows Linux to provide limited support for binaries compiled under other UNIX-like operating systems.

`personality` will make the execution domain referenced by `persona` the new execution domain of the current process.

RETURN VALUE

On success, *persona* is made the new execution domain and the previous *persona* is returned. On error, `-1` is returned and `errno` is set appropriately.

ERRORS

`EINVAL` *persona* does not refer to a valid execution domain.

FILE

`/usr/include/linux/personality.h`

CONFORMS TO

personality is Linux specific.

Linux 2.0, 22 July 1996

phys

phys—Allows a process to access physical addresses (this command is not implemented)

SYNOPSIS

```
int phys(int physnum, char *virtaddr, longsize, char *physaddr);
```

DESCRIPTION

Warning: Because this function is not implemented as of Linux 0.99.11, it will always return `-1` and set `errno` to `ENOSYS`.

phys maps arbitrary physical memory into a process's virtual address space. *physnum* is a number (0–3) that specifies which of the four physical spaces to set up. Up to four *phys* calls can be active at any one time. *virtaddr* is the process's virtual address. *size* is the number of bytes to map in. *physaddr* is the physical address to map in.

Valid *virtaddr* and *physaddr* values are constrained by hardware and must be at an address multiple of the resolution of the CPU's memory management scheme. If *size* is nonzero, *size* is rounded up to the next MMU resolution boundary. If *size* is 0, any previous *phys*(2) mapping for that *physnum* is nullified.

RETURN VALUE

On success, 0 is returned. On error, `-1` is returned and `errno` is set appropriately.

CONFORMS TO

version 7 AT&T UNIX

BUGS

phys is very machine dependent.

SEE ALSO

mmap(2), *munmap*(2)

Linux 0.99.11, 24 July 1993

pipe

pipe—Creates a pipe

SYNOPSIS

```
#include <unistd.h>
int pipe(int filedес[2]);
```

DESCRIPTION

pipe creates a pair of file descriptors, pointing to a pipe inode, and places them in the array pointed to by `filedes`. `filedes[0]` is for reading, `filedes[1]` is for writing.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and `errno` is set appropriately.

ERRORS

EMFILE	Too many file descriptors are in use by the process.
ENFILE	The system file table is full.
EFAULT	<code>filedes</code> is not valid.

SEE ALSO

`read(2)`, `write(2)`, `fork(2)`, `socketpair(2)`

Linux 0.99.11, 23 July 1993

profil

`profil`—Execution time profile

SYNOPSIS

```
#include <unistd.h>
int profil(char *buf, int bufsiz, int offset, int scale);
```

DESCRIPTION

Under Linux 0.99.11, `profil` is not implemented in the kernel. Instead, the DLL 4.4.1 libraries provide a user-space implementation.

`buf` points to `bufsiz` bytes of core. Every virtual 10 milliseconds, the user's program counter (PC) is examined: `offset` is subtracted and the result is multiplied by `scale`. If this address is in `buf`, the word pointed to is incremented.

If `scale` is less than 2 or `bufsiz` is 0, profiling is disabled.

RETURN VALUE

0 is always returned.

BUGS

`profil` cannot be used on a program that also uses `ITIMER_PROF` itimers.

Calling `profil` with an invalid `buf` will result in a core dump.

True kernel profiling provides more accurate results.

SEE ALSO

`gprof(1)`, `setitimer(2)`, `signal(2)`, `sigaction(2)`

Linux 0.99.11, 23 July 1993

ptrace

ptrace—Process trace

SYNOPSIS

```
#include <sys/ptrace.h>
int ptrace(int request, int pid, int addr, int data);
```

DESCRIPTION

ptrace provides a means by which a parent process can control the execution of a child process and examine and change its core image. Its primary use is for the implementation of breakpoint debugging. A traced process runs until a signal occurs. Then it stops and the parent is notified with `wait(2)`. When the process is in the stopped state, its memory can be read and written. The parent can also cause the child to continue execution, optionally ignoring the signal which caused stopping.

The value of the request argument determines the precise action of the system call:

<code>PTRACE_TRACEME</code>	This process is to be traced by its parent. The parent should be expecting to trace the child.
<code>PTRACE_PEEKTEXT</code> , <code>PTRACE_PEEKDATA</code>	Read word at location <code>addr</code> .
<code>PTRACE_PEEKUSR</code>	Read word at location <code>addr</code> in the USER area.
<code>PTRACE_POKETEXT</code> , <code>PTRACE_POKEDATA</code>	Write word at location <code>addr</code> .
<code>PTRACE_POKEUSR</code>	Write word at location <code>addr</code> in the USER area.
<code>PTRACE_SYSCALL</code> , <code>PTRACE_CONT</code>	Restart after signal.
<code>PTRACE_KILL</code>	Send the child a <code>SIGKILL</code> to make it exit.
<code>PTRACE_SINGLESTEP</code>	Set the trap flag for single stepping.
<code>PTRACE_ATTACH</code>	Attach to the process specified in <code>pid</code> .
<code>PTRACE_DETACH</code>	Detach a process that was previously attached.

NOTES

`init`, the process with process ID 1, may not use this function.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned and `errno` is set appropriately.

ERRORS

<code>EPERM</code>	The specified process (that is, <code>init</code>), cannot be traced or is already being traced.
<code>ESRCH</code>	The specified process does not exist.
<code>EIO</code>	Request is not valid.

CONFORMS TO

SVID EXT, AT&T, X/OPEN, BSD 4.3

SEE ALSO

`gdb(1)`, `exec(2)`, `signal(2)`, `wait(2)`

quotactl

quotactl—Manipulates disk quotas

SYNOPSIS

```
#include <sys/types.h>
#include <sys/quota.h>
int quotactl (int cmd, const char *special, intid , caddr_t addr);
#include <linux/unistd.h>
syscall14(int, quotactl, int, cmd, const char *, special ,int, id, caddr_t, addr);
```

DESCRIPTION

The quota system defines for each user or group a soft limit and a hard limit bounding the amount of disk space that can be used on a given filesystem. The hard limit cannot be crossed. The soft limit can be crossed, but warnings will ensue. Moreover, the user cannot be above the soft limit for more than one week (by default) at a time: After this week the soft limit counts as a hard limit.

The quotactl system call manipulates these quotas. Its first argument is of the form

QCMD(subcmd, type)

where type is either `USRQUOTA` or `GRPQUOTA` (for user quota and group quota, respectively).

The second argument `special` is the block special device these quotas apply to. It must be mounted.

The third argument `ID` is the user or group ID these quotas apply to (when relevant).

The fourth argument, `addr`, is the address of a data structure, depending on the command.

The subcmd is one of the following:

<code>Q_QUOTAON</code>	Enables quotas. The <code>addr</code> argument is the pathname of the file containing the quotas for the filesystem.
<code>Q_QUOTAOFF</code>	Disables quotas.
<code>Q_GETQUOTA</code>	Gets limits and current usage of disk space. The <code>addr</code> argument is a pointer to a <code>dqb1k</code> structure (defined in <code><sys/quota.h></code>).
<code>Q_SETQUOTA</code>	Sets limits and current usage; <code>addr</code> is as before.
<code>Q_SETQLIM</code>	Sets limits; <code>addr</code> is as before.
<code>Q_SETUSE</code>	Sets usage.
<code>Q_SYNC</code>	Syncs disk copy of a filesystem's quotas.
<code>Q_GETSTATS</code>	Gets collected stats.

RETURN VALUE

On success, quotactl returns 0. On error, -1 is returned and `errno` is set appropriately.

ERRORS

<code>ENOPKG</code>	The kernel was compiled without quota support.
<code>EFAULT</code>	Bad <code>addr</code> value.
<code>EINVAL</code>	<code>type</code> is not a known quota type. Or <code>special</code> could not be found.
<code>ENOTBLK</code>	<code>special</code> is not a block special device.
<code>ENODEV</code>	<code>special</code> cannot be found in the mount table.
<code>EACCES</code>	The quota file is not an ordinary file.
<code>EIO</code>	Cannot read or write the quota file.
<code>EMFILE</code>	Too many open files: Cannot open quota file.

EBUSY	Q_QUOTAON was asked, but quota were enabled already.
ESRCH	Q_GETQUOTA or Q_SETQUOTA or Q_SETUSE or Q_SETQLIM was asked for a filesystem that didn't have quota enabled.
EPERM	The process was not root (for the filesystem), and Q_GETQUOTA was asked for another ID than that of the process itself, or anything other than Q_GETSTATS or Q_SYNC was asked.

CONFORMS TO

BSD

Linux 1.3.88, 14 April 1996

read

read—Reads from a file descriptor

SYNOPSIS

```
#include <unistd.h>
ssize_t read(int fd, void* buf, size_t count);
```

DESCRIPTION

read() attempts to read up to count bytes from file descriptor fd into the buffer starting at buf.

If count is 0, read() returns 0 and has no other results. If count is greater than SSIZE_MAX, the result is unspecified.

RETURN VALUE

On success, the number of bytes read is returned (0 indicates end of file) and the file position is advanced by this number. It is not an error if this number is smaller than the number of bytes requested; this may happen, for example, because fewer bytes are actually available right now (maybe because we were close to end-of-file or because we are reading from a pipe, or from a terminal), or because read() was interrupted by a signal. On error, -1 is returned and errno is set appropriately. In this case it is left unspecified whether the file position (if any) changes.

ERRORS

EINTR	The call was interrupted by a signal before any data was read.
EAGAIN	Non-blocking I/O has been selected using O_NONBLOCK and no data was immediately available for reading.
EIO	I/O error. This will happen, for example, when the process is in a background process group, tries to read from its controlling tty, and it is ignoring or blocking SIGTTIN or its process group is orphaned.
EISDIR	fd refers to a directory.
EBADF	fd is not a valid file descriptor or is not open for reading.
EINVAL	fd is attached to an object that is unsuitable for reading.
EFAULT	buf is outside your accessible address space.

Other errors may occur, depending on the object connected to fd. POSIX allows a read that is interrupted after reading some data to return -1 (with errno set to EINTR) or to return the number of bytes already read.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

SEE ALSO

readdir(2), write(2), write(2), fcntl(2), close(2), lseek(2), select(2), readlink(2), ioctl(2), fread(3)

Linux, 17 January 1996

readdir

readdir—Reads directory entry

SYNOPSIS

```
#include <unistd.h>
#include <linux/dirent.h>
#include <linux/unistd.h>
syscall3(int, readdir, uint, fd, struct dirent *, dirp, uint, count);
int readdir(unsigned int fd, struct dirent *dirp, unsigned int count);
```

DESCRIPTION

This is not the function you are interested in. Look at `readdir(3)` for the POSIX-conforming C library interface. This page documents the bare kernel system call interface, which can change, and which is superseded by `getdents(2)`.

`readdir` reads one `dirent` structure from the directory pointed at by `fd` into the memory area pointed to by `dirp`. The parameter `count` is ignored; at most one `dirent` structure is read.

The `dirent` structure is declared as follows:

```
struct dirent
{
    long d_ino;           /* inode number */
    off_t d_off;          /* offset to this dirent */
    unsigned short d_reclen; /* length of this d_name */
    char d_name [NAME_MAX+1]; /* file name (null-terminated) */
}
```

`d_ino` is an inode number. `d_off` is the distance from the start of the directory to this `dirent`. `d_reclen` is the size of `d_name`, not counting the null terminator. `d_name` is a null-terminated filename.

RETURN VALUE

On success, 1 is returned. On end of directory, 0 is returned. On error, -1 is returned and `errno` is set appropriately.

ERRORS

EBADF	Invalid file descriptor <code>fd</code> .
ENOTDIR	File descriptor does not refer to a directory.

CONFORMS TO

This system call is Linux specific.

SEE ALSO

`getdents(2)`, `readdir(3)`

Linux 1.3.6, 22 July 1995

readlink

readlink—Reads value of a symbolic link

SYNOPSIS

```
#include <unistd.h>
int readlink(const char *path, char *buf, size_t bufsiz);
```

DESCRIPTION

`readlink` places the contents of the symbolic link path in the buffer `buf`, which has size `bufsiz`. `Readlink` does not append a NUL character to `buf`.

RETURN VALUES

The call returns the count of characters placed in the buffer if it succeeds, or a -1 if an error occurs, placing the error code in the global variable `errno`.

ERRORS

<code>ENOTDIR</code>	A component of the path prefix is not a directory.
<code>EINVAL</code>	The pathname contains a character with the high-order bit set.
<code>ENAMETOOLONG</code>	A component of a pathname exceeded 255 characters, or an entire path name exceeded 1023 characters.
<code>ENOENT</code>	The named file does not exist.
<code>EACCES</code>	Search permission is denied for a component of the path prefix.
<code>ELOOP</code>	Too many symbolic links were encountered in translating the pathname.
<code>EINVAL</code>	The named file is not a symbolic link.
<code>EIO</code>	An I/O error occurred while reading from the filesystem.
<code>EFAULT</code>	<code>buf</code> extends outside the process's allocated address space.

HISTORY

The `readlink` function call appeared in BSD 4.2.

SEE ALSO

`stat(2)`, `lstat(2)`, `symlink(2)`

BSD Man Page, 24 July 1993

readv, writev

`readv, writev`—Reads or writes a vector

SYNOPSIS

```
#include <sys/uio.h>
int readv(int fd, const struct iovec * vector, size_t count);
int writev(int fd, const struct iovec * vector, size_t count);
struct iovec {
    ptr_t iov_base; /* Starting address. */
    size_t iov_len; /* Length in bytes. */
};
```

DESCRIPTION

`readv` reads data from file descriptor `fd` and puts the result in the buffers described by `vector`. The number of buffers is specified by `count`. The buffers are filled in the order specified. Operates just like `read` except that data is put in `vector` instead of a contiguous buffer.

`writev` writes data to file descriptor `fd`, and from the buffers described by `vector`. The number of buffers is specified by `count`. The buffers are used in the order specified. Operates just like `write` except that data is taken from `vector` instead of a contiguous buffer.

RETURN VALUE

On success, `readv` returns the number of bytes read. On success, `writev` returns the number of bytes written. On error, `-1` is returned, and `errno` is set appropriately.

ERRORS

<code>EINVAL</code>	An invalid argument was given. For instance <code>count</code> might be greater than <code>MAX_IOVEC</code> , or <code>0</code> . <code>fd</code> could also be attached to an object that is unsuitable for reading.
<code>EFAULT</code>	Segmentation fault. Most likely <code>vector</code> or some of the <code>iov_base</code> pointers points to memory that is not properly allocated.
<code>EBADF</code>	The file descriptor <code>fd</code> is not valid.
<code>EINTR</code>	The call was interrupted by a signal before any data was read/written.
<code>EAGAIN</code>	Non-blocking I/O has been selected using <code>O_NONBLOCK</code> and no data was immediately available for reading. (Or the file descriptor <code>fd</code> is for an object that is locked.)
<code>EISDIR</code>	<code>fd</code> refers to a directory.
<code>EOPNOTSUPP</code>	<code>fd</code> refers to a socket or device that does not support reading/writing.

Other errors may occur, depending on the object connected to `fd`.

SEE ALSO

`read(2)`, `write(2)`, `fprintf(3)`, `fscanf(2)`

Linux 1.3.86, 12 April 1996

reboot

`reboot`—Reboots or disables `Ctrl+Alt+Del`

SYNOPSIS

```
#include <unistd.h>
int reboot (int magic,int magic_too,int flag);
```

DESCRIPTION

`reboot` reboots the system or enables/disables CAD.

If `magic = 0xfee1dead` and `magic_too = 672274793`, the action performed will be based on `flag`.

If `flag=0x1234567`, a hard reset is performed.

If `flag=0x89abcdef`, CAD is enabled.

If `flag=0`, CAD is disabled and a signal is sent to process ID 1.

Note that `reboot()` does *not* `sync()`!

Only the superuser may use this function.

RETURN VALUE

On success, `0` is returned. On error, `-1` is returned, and `errno` is set appropriately.

ERRORS

<code>EINVAL</code>	Bad <code>magic</code> numbers or <code>flag</code> .
<code>EPERM</code>	A non-root user has attempted to call <code>reboot</code> .

CONFORMS TO

reboot is Linux specific.

SEE ALSO

sync(2), ctrlaltdel(8), halt(8), reboot(8)

Linux 0.99.10, 28 March 1992

recv, recvfrom, recvmsg

recv, recvfrom, recvmsg—Receives a message from a socket

SYNOPSIS

```
#include <sys/types.h>
#include <sys/socket.h>
int recv(int s, void *buf, intlen, unsigned int flags);
int recvfrom(int s, void*buf, int len, unsigned int flags,
    struct sockaddr *from, int *fromlen);
int recvmsg(int s, struct msghdr *msg, unsigned int flags);
```

DESCRIPTION

Warning: This is a BSD man page. As of Linux 0.99.11, recvmsg was not implemented.

recvfrom and recvmsg are used to receive messages from a socket, and may be used to receive data on a socket whether or not it is connection oriented.

If from is non-nil, and the socket is not connection-oriented, the source address of the message is filled in. fromlen is a value-result parameter, initialized to the size of the buffer associated with from and modified on return to indicate the actual size of the address stored there.

The recv call is normally used only on a connected socket (see connect(2)) and is identical to recvfrom with a nil from parameter. Because it is redundant, it might not be supported in future releases.

All three routines return the length of the message on successful completion. If a message is too long to fit in the supplied buffer, excess bytes might be discarded depending on the type of socket from which the message is received (see socket(2)).

If no messages are available at the socket, the receive call waits for a message to arrive—unless the socket is nonblocking (see fcntl(2)), in which case the value -1 is returned and the external variable errno is set to EWOULDBLOCK. The receive calls normally return any data available, up to the requested amount, rather than wait for receipt of the full amount requested; this behavior is affected by the socket-level options SO_RCVLOWAT and SO_RCVTIMEO, described in getsockopt(2).

The select(2) call may be used to determine when more data arrives.

The flags argument to a recv call is formed by oring one or more of the values:

MSG_OOB	Process out-of-band data
MSG_PEEK	Peek at incoming message
MSG_WAITALL	Wait for full request or error

The MSG_OOB flag requests receipt of out-of-band data that would not be received in the normal data stream. Some protocols place expedited data at the head of the normal data queue; thus this flag cannot be used with such protocols. The MSG_PEEK flag causes the receive operation to return data from the beginning of the receive queue without removing that data from the queue; thus, a subsequent receive call will return the same data. The MSG_WAITALL flag requests that the operation block until the full request is satisfied. However, the call might still return less data than requested if a signal is caught, an error or disconnect occurs, or the next data to be received is of a different type than that returned.

The `recvmsg` call uses a `msghdr` structure to minimize the number of directly supplied parameters. This structure has the following form, as defined in `sys/socket.h`:

```
struct msghdr {
    caddr_t msg_name; /* optional address */
    u_int msg_namelen; /* size of address */
    struct iovec *msg_iov; /* scatter/gather array */
    u_int msg_iovlen; /* # elements in msg_iov */
    caddr_t msg_control; /* ancillary data, see below */
    u_int msg_controllen; /* ancillary data buffer len */
    int msg_flags; /* flags on received message */
};
```

Here `msg_name` and `msg_namelen` specify the destination address if the socket is unconnected; `msg_name` may be given as a null pointer if no names are desired or required. `msg_iov` and `msg_iovlen` describe scatter gather locations, as discussed in `read(2)`. `msg_control`, which has length `msg_controllen`, points to a buffer for other protocol control-related messages or other miscellaneous ancillary data. The messages are of the form

```
struct cmsghdr {
    u_int cmsg_len; /* data byte count, including hdr */
    int cmsg_level; /* originating protocol */
    int cmsg_type; /* protocol-specific type */
/* followed by
    u_char cmsg_data[]; */
};
```

You could use this, for example, to learn of changes in the data stream in XNS/SPP, or in ISO, to obtain user-connection-request data by requesting a `recvmsg` with no data buffer provided immediately after an `accept` call.

Open file descriptors are now passed as ancillary data for `AF_UNIX` domain sockets, with `cmsg_level` set to `SOL_SOCKET` and `cmsg_type` set to `SCM_RIGHTS`.

The `msg_flags` field is set on return according to the message received. `MSG_EOR` indicates end-of-record; the data returned completed a record (generally used with sockets of type `SOCK_SEQPACKET`). `MSG_TRUNC` indicates that the trailing portion of a datagram was discarded because the datagram was larger than the buffer supplied. `MSG_CTRUNC` indicates that some control data was discarded due to lack of space in the buffer for ancillary data. `MSG_OOB` is returned to indicate that expedited or out-of-band data was received.

RETURN VALUES

These calls return the number of bytes received, or -1 if an error occurred.

ERRORS

<code>EBAADF</code>	The argument <code>s</code> is an invalid descriptor.
<code>ENOTCONN</code>	The socket is associated with a connection-oriented protocol and has not been connected (see <code>connect(2)</code> and <code>accept(2)</code>).
<code>ENOTSOCK</code>	The argument <code>s</code> does not refer to a socket.
<code>EWOULDBLOCK</code>	The socket is marked non-blocking, and the receive operation would block, or a receive timeout had been set, and the timeout expired before data was received.
<code>EINTR</code>	The receive was interrupted by delivery of a signal before any data was available.
<code>EFAULT</code>	The receive buffer pointer(s) point outside the process's address space.

HISTORY

These function calls appeared in BSD 4.2.

SEE ALSO

`fcntl(2)`, `read(2)`, `select(2)`, `getsockopt(2)`, `socket(2)`

BSD Man Page, 24 July 1993

rename

`rename`—Changes the name or location of a file

SYNOPSIS

```
#include <unistd.h>
int rename(const char *oldpath, const char *newpath);
```

DESCRIPTION

`rename` renames a file, moving it between directories if required.

Any other hard links to the file (as created using `link`) are unaffected.

If `newpath` already exists it will be automatically overwritten (subject to a few conditions—see the “Errors” section), so that there is no point at which another process attempting to access `newpath` will find it missing.

If `newpath` exists but the operation fails for some reason or the system crashes, `rename` guarantees to leave an instance of `newpath` in place.

However, when overwriting there will probably be a window in which both `oldpath` and `newpath` refer to the file being renamed.

If `oldpath` refers to a symbolic link, the link will be renamed; if `newpath` refers to a symbolic link, the link will be overwritten.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

<code>EISDIR</code>	<code>newpath</code> is an existing directory, but <code>oldpath</code> is not a directory.
<code>EXDEV</code>	<code>oldpath</code> and <code>newpath</code> are not on the same filesystem.
<code>ENOTEMPTY</code>	<code>newpath</code> is a non-empty directory.
<code>EBUSY</code>	<code>newpath</code> exists and is the current working directory or root directory of some process.
<code>EINVAL</code>	An attempt was made to make a directory a subdirectory of itself.
<code>EMLINK</code>	<code>oldpath</code> already has the maximum number of links to it, or it was a directory and the directory containing <code>newpath</code> has the maximum number of links.
<code>ENOTDIR</code>	A component used as a directory in <code>oldpath</code> or <code>newpath</code> is not, in fact, a directory.
<code>EFAULT</code>	<code>oldpath</code> or <code>newpath</code> points outside your accessible address space.
<code>EACCES</code>	Write access to the directory containing <code>oldpath</code> or <code>newpath</code> is not allowed for the process's effective UID, or one of the directories in <code>oldpath</code> or <code>newpath</code> did not allow search (execute) permission, or <code>oldpath</code> was a directory and did not allow write permission (needed to update the <code>..</code> entry).
<code>EPERM</code>	The directory containing <code>oldpath</code> has the sticky bit set, and the process's effective UID is neither the UID of the file to be deleted nor that of the directory containing it, or the filesystem containing <code>pathname</code> does not support renaming of the type requested.
<code>ENAMETOOLONG</code>	<code>oldpath</code> or <code>newpath</code> was too long.
<code>ENOENT</code>	A directory component in <code>oldpath</code> or <code>newpath</code> does not exist or is a dangling symbolic link.
<code>ENOMEM</code>	Insufficient kernel memory was available.
<code>EROFS</code>	The file is on a read-only filesystem.

ELOOP	oldpath or newpath contains a reference to a circular symbolic link; that is, a symbolic link whose expansion contains a reference to itself.
ENOSPC	The device containing the file has no room for the new directory entry.

CONFORMS TO

POSIX, BSD 4.3, ANSI C

BUGS

Currently (Linux 0.99pl7), most of the filesystems except Minix will not allow any overwriting renames involving directories. You get EEXIST if you try.

On NFS filesystems, you cannot assume that just because the operation failed, the file was not renamed. If the server does the rename operation and then crashes, the retransmitted RPC, which will be processed when the server is up again, causes a failure. The application is expected to deal with this. See link(2) for a similar problem.

SEE ALSO

link(2), unlink(2), symlink(2), mv(1), link(8)

Linux 0.99.7, 24 July 1993

rmdir

rmdir—Deletes a directory

SYNOPSIS

```
#include <unistd.h>
int rmdir(const char *pathname);
```

DESCRIPTION

rmdir deletes a directory, which must be empty.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and errno is set appropriately.

ERRORS

EPERM	The filesystem containing pathname does not support the removal of directories.
EFAULT	pathname points outside your accessible address space.
EACCES	Write access to the directory containing pathname was not allowed for the process's effective UID, or one of the directories in pathname did not allow search (execute) permission.
EPERM	The directory containing pathname has the sticky bit (S_ISVTX) set, and the process's effective UID is neither the UID of the file to be deleted nor that of the directory containing it.
ENAMETOOLONG	pathname was too long.
ENOENT	A directory component in pathname does not exist or is a dangling symbolic link.
ENOTDIR	pathname, or a component used as a directory in pathname, is not, in fact, a directory.
ENOTEMPTY	pathname contains entries other than . and ...
EBUSY	pathname is the current working directory or root directory of some process.
ENOMEM	Insufficient kernel memory was available.
EROFS	pathname refers to a file on a read-only filesystem.
ELOOP	pathname contains a reference to a circular symbolic link; that is, a symbolic link containing a reference to itself.

CONFORMS TO

SVID, AT&T, POSIX, BSD 4.3

BUGS

Infelicities in the protocol underlying NFS can cause the unexpected disappearance of directories that are still being used.

SEE ALSO

`rename(2)`, `mkdir(2)`, `chdir(2)`, `unlink(2)`, `rmdir(1)`, `rm(1)`

Linux 0.99.7, 24 July 1993

`sched_get_priority_max, sched_get_priority_min`

`sched_get_priority_max, sched_get_priority_min`—Gets static priority range

SYNOPSIS

```
#include <sched.h>
int sched_get_priority_max(int policy);
int sched_get_priority_min(int policy);
```

DESCRIPTION

`sched_get_priority_max` returns the maximum priority value that can be used with the scheduling algorithm identified by `policy`. `sched_get_priority_min` returns the minimum priority value that can be used with the scheduling algorithm identified by `policy`. Supported `policy` values are `SCHED_FIFO`, `SCHED_RR`, and `SCHED_OTHER`.

Processes with numerically higher priority values are scheduled before processes with numerically lower priority values. Therefore, the value returned by `sched_get_priority_max` will be greater than the value returned by `sched_get_priority_min`.

Linux allows the static priority value range 1 to 99 for `SCHED_FIFO` and `SCHED_RR`, and the priority 0 for `SCHED_OTHER`. Scheduling priority ranges for the various policies are not alterable.

The range of scheduling priorities may vary on other POSIX systems, so it is a good idea for portable applications to use a virtual priority range and map it to the interval given by `sched_get_priority_max` and `sched_get_priority_min`. POSIX.1b requires a spread of at least 32 between the maximum and the minimum values for `SCHED_FIFO` and `SCHED_RR`.

POSIX systems on which `sched_get_priority_max` and `sched_get_priority_min` are available define `_POSIX_PRIORITY_SCHEDULING` in `<unistd.h>`.

RETURN VALUE

On success, `sched_get_priority_max` and `sched_get_priority_min` return the maximum and minimum priority values for the named scheduling policy. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

`EINVAL` The parameter `policy` does not identify a defined scheduling policy.

STANDARDS

POSIX.1b (formerly POSIX.4)

SEE ALSO

`sched_setscheduler(2)`, `sched_getscheduler(2)`, `sched_setparam(2)`, `sched_getparam(2)`

`sched_setscheduler(2)` has a description of the Linux scheduling scheme.

Programming for the Real World—POSIX.4 by Bill O. Gallmeister, O'Reilly & Associates, Inc., ISBN 1-56592-074-0

IEEE Std 1003.1b-1003 (POSIX.1b standard)

ISO/IEC 9945-1:1996

Linux 1.3.81, 10 April 1996

sched_rr_get_interval

`sched_rr_get_interval`—Gets the SCHED_RR interval for the named process

SYNOPSIS

```
#include <sched.h>
int sched_rr_get_interval(pid_t pid, struct timespec *tp);
struct timespec {
    time_t tv_sec; /* seconds */
    long tv_nsec; /* nanoseconds */
};
```

DESCRIPTION

`sched_rr_get_interval` writes into the `timespec` structure pointed to by `tp` the round-robin time quantum for the process identified by `pid`. If `pid` is 0, the time quantum for the calling process is written into `*tp`. The identified process should be running under the SCHED_RR scheduling policy.

The round robin time quantum value is not alterable under Linux 1.3.81.

POSIX systems on which `sched_rr_get_interval` is available define `_POSIX_PRIORITY_SCHEDULING` in `<unistd.h>`.

RETURN VALUE

On success, `sched_rr_get_interval` returns 0. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

ESRCH	The process whose ID is <code>pid</code> could not be found.
ENOSYS	The system call is not yet implemented.

STANDARDS

POSIX.1b (formerly POSIX.4)

BUGS

As of Linux 1.3.81, `sched_rr_get_interval` returns with error ENOSYS, because SCHED_RR has not yet been fully implemented or tested properly.

SEE ALSO

`sched_setscheduler(2)` has a description of the Linux scheduling scheme.

Programming for the Real World—POSIX.4 by Bill O. Gallmeister, O'Reilly & Associates, Inc., ISBN 1-56592-074-0

IEEE Std 1003.1b-1993 (POSIX.1b standard)

ISO/IEC 9945-1:1996

Linux 1.3.81, 10 April 1996

sched_setparam, sched_getparam

sched_setparam, sched_getparam—Sets and get scheduling parameters

SYNOPSIS

```
#include <sched.h>
int sched_setparam(pid_t pid, const struct sched_param *p);
int sched_getparam(pid_t pid, struct sched_param *p);
struct sched_param {
    ...
    int sched_priority;
    ...
};
```

DESCRIPTION

sched_setparam sets the scheduling parameters associated with the scheduling policy for the process identified by *pid*. If *pid* is 0, the parameters of the current process are set. The interpretation of the parameter *p* depends on the selected policy. Currently, the following three scheduling policies are supported under Linux: SCHED_FIFO, SCHED_RR, and SCHED_OTHER.

sched_getparam retrieves the scheduling parameters for the process identified by *pid*. If *pid* is 0, the parameters of the current process are retrieved.

sched_setparam checks the validity of *p* for the scheduling policy of the process. The parameter *p*→*sched_priority* must lie within the range given by *sched_get_priority_min* and *sched_get_priority_max*.

POSIX systems on which sched_setparam and sched_getparam are available define _POSIX_PRIORITY_SCHEDULING in <unistd.h>.

RETURN VALUE

On success, sched_setparam and sched_getparam return 0. On error, -1 is returned, and *errno* is set appropriately.

ERRORS

ESRCH	The process whose ID is <i>pid</i> could not be found.
EPERM	The calling process does not have appropriate privileges. The process calling sched_setparam needs an effective UID equal to the UID or UID of the process identified by <i>pid</i> , or it must be a superuser process.
EINVAL	The parameter <i>p</i> does not make sense for the current scheduling policy.

STANDARDS

POSIX.1b (formerly POSIX.4)

SEE ALSO

sched_setscheduler(2), sched_getscheduler(2), sched_get_priority_max(2), sched_get_priority_min(2), nice(2), setpriority(2), getpriority(2)

sched_setscheduler(2) has a description of the Linux scheduling scheme.

Programming for the Real World—POSIX.4 by Bill O. Gallmeister, O'Reilly & Associates, Inc., ISBN 1-56592-074-0

IEEE Std 1003.1b-1993 (POSIX.1b standard)

ISO/IEC 9945-1:1996

Linux 1.3.81, 10 April 1996

sched_setscheduler, sched_getscheduler

sched_setscheduler, sched_getscheduler—Sets and gets scheduling algorithm/parameters

SYNOPSIS

```
#include <sched.h>
int sched_setscheduler(pid_t pid, int policy, const struct sched_param *p);
int sched_getscheduler(pid_t pid);
struct sched_param {
    ...
    int sched_priority;
    ...
};
```

DESCRIPTION

`sched_setscheduler` sets both the scheduling policy and the associated parameters for the process identified by `pid`. If `pid` is 0, the scheduler of the calling process will be set. The interpretation of the parameter `p` depends on the selected policy.

Currently, the following three scheduling policies are supported under Linux: `SCHED_FIFO`, `SCHED_RR`, and `SCHED_OTHER`; their respective semantics are described in the following section.

`sched_getscheduler` queries the scheduling policy currently applied to the process identified by `pid`. If `pid` is 0, the policy of the calling process will be retrieved.

SCHEDULING POLICIES

The scheduler is the kernel part that decides which runnable process will be executed next by the CPU. The Linux scheduler offers three different scheduling policies, one for normal processes and two for real-time applications. A static priority value, `sched_priority`, is assigned to each process, and this value can be changed only via system calls. Conceptually, the scheduler maintains a list of runnable processes for each possible `sched_priority` value, and `sched_priority` can have a value in the range 0 to 99. To determine the process that runs next, the Linux scheduler looks for the non-empty list with the highest static priority and takes the process at the head of this list. The scheduling policy determines, for each process, where it will be inserted into the list of processes with equal static priority and how it will move inside this list.

`SCHED_OTHER` is the default universal time-sharing scheduler policy used by most processes; `SCHED_FIFO` and `SCHED_RR` are intended for special, time-critical applications that need precise control over the way in which runnable processes are selected for execution. Processes scheduled with `SCHED_OTHER` must be assigned the static priority 0; processes scheduled under `SCHED_FIFO` or `SCHED_RR` can have a static priority in the range 1 to 99. Only processes with superuser privileges can get a static priority higher than 0 and can therefore be scheduled under `SCHED_FIFO` or `SCHED_RR`. The system calls `sched_get_priority_min` and `sched_get_priority_max` can be used to find out the valid priority range for a scheduling policy in a portable way on all POSIX.1b-conforming systems.

All scheduling is preemptive: If a process with a higher static priority gets ready to run, the current process will be preempted and returned into its wait list. The scheduling policy determines the ordering within the list of runnable processes only among those with equal static priority.

SCHED_FIFO: FIRST IN-FIRST OUT SCHEDULING

`SCHED_FIFO` can only be used with static priorities higher than 0, which means that when a `SCHED_FIFO` process becomes runnable, it will always preempt immediately any currently running normal `SCHED_OTHER` process. `SCHED_FIFO` is a simple scheduling algorithm without time slicing.

For processes scheduled under the `SCHED_FIFO` policy, the following rules are applied: A `SCHED_FIFO` process that has been preempted by another process of higher priority will stay at the head of the list for its priority and will resume execution as soon as all processes of higher priority are blocked again. When a `SCHED_FIFO` process becomes runnable, it will be inserted at the end of the list for its priority. A call to `sched_setscheduler` or `sched_setparam` will put the `SCHED_FIFO` process identified by

`pid` at the end of the list if it was runnable. A process calling `sched_yield` will be put at the end of the list. No other events will move a process scheduled under the `SCHED_FIFO` policy in the wait list of runnable processes with equal static priority. A `SCHED_FIFO` process runs until it is blocked by an I/O request, it is preempted by a higher-priority process, or it calls `sched_yield`.

SCHED_RR: ROUND-ROBIN SCHEDULING

`SCHED_RR` is a simple enhancement of `SCHED_FIFO`. Everything described in the preceding section for `SCHED_FIFO` also applies to `SCHED_RR`, except that each process is only allowed to run for a maximum time quantum. If a `SCHED_RR` process has been running for a time period equal to or longer than the time quantum, it will be put at the end of the list for its priority. A `SCHED_RR` process that has been preempted by a higher-priority process and subsequently resumes execution as a running process will complete the unexpired portion of its round-robin time quantum. The length of the time quantum can be retrieved by `sched_rr_get_interval`.

SCHED_OTHER: DEFAULT LINUX TIME-SHARING SCHEDULING

`SCHED_OTHER` can only be used at static priority 0. `SCHED_OTHER` is the standard Linux time-sharing scheduler that is intended for all processes that do not require special static-priority real-time mechanisms. The process to run is chosen from the static priority 0 list based on a dynamic priority that is determined only inside this list. The dynamic priority is based on the nice level (set by the `nice` or `setpriority` system call) and is increased for each time quantum the process is ready to run but is denied to run by the scheduler. This ensures fair progress among all `SCHED_OTHER` processes.

RESPONSE TIME

A blocked high-priority process waiting for the I/O has a certain response time before it is scheduled again. The device driver writer can greatly reduce this response time by using a *slow interrupt* interrupt handler, as described in `request_irq(9)`.

MISCELLANEOUS

Child processes inherit the scheduling algorithm and parameters across a `fork`.

Memory locking is usually needed for real-time processes to avoid paging delays; this can be done with `mlock` or `mlockall`.

Because a non-blocking endless loop in a process scheduled under `SCHED_FIFO` or `SCHED_RR` will block all processes with lower priority forever, a software developer should always keep available on the console a shell scheduled under a higher static priority than the tested application. This will allow an emergency kill of tested real-time applications that do not block or terminate as expected. Because `SCHED_FIFO` and `SCHED_RR` processes can preempt other processes forever, only root processes are allowed to activate these policies under Linux.

POSIX systems on which `sched_setscheduler` and `sched_getscheduler` are available define `_POSIX_PRIORITY_SCHEDULING` in `<unistd.h>`.

RETURN VALUE

On success, `sched_setscheduler` returns 0. On success, `sched_getscheduler` returns the policy for the process (a non-negative integer). On error, -1 is returned, and `errno` is set appropriately.

ERRORS

ESRCH	The process whose ID is <code>pid</code> could not be found.
EPERM	The calling process does not have appropriate privileges. Only root processes are allowed to activate the <code>SCHED_FIFO</code> and <code>SCHED_RR</code> policies. The process calling <code>sched_setscheduler</code> needs an effective UID equal to the EUID or UID of the process identified by <code>pid</code> , or it must be a superuser process.
EINVAL	The scheduling policy is not one of the recognized policies, or the parameter <code>p</code> does not make sense for the policy.

STANDARDS

POSIX.1b (formerly POSIX.4)

BUGS

As of Linux 1.3.81, `SCHED_RR` has not yet been tested carefully and might not behave exactly as described or required by POSIX.1b.

SEE ALSO

`sched_setparam(2)`, `sched_getparam(2)`, `sched_yield(2)`, `sched_get_priority_max(2)`, `sched_get_priority_min(2)`, `nice(2)`, `setpriority(2)`, `getpriority(2)`, `mlockall(2)`, `munlockall(2)`, `mlock(2)`, `munlock(2)`.

Programming for the Real World—POSIX.4 by Bill O. Gallmeister, O'Reilly & Associates, Inc., ISBN 1-56592-074-0

IEEE Std 1003.1b-1003 (POSIX.1b standard)

ISO/IEC 9945-1:1996—This is the new 1996 revision of POSIX.1, which contains in one single standard POSIX.1(1990), POSIX.1b(1993), POSIX.1c(1995), and POSIX.1i(1995).

Linux 1.3.81, 10 April 1996

sched_yield

`sched_yield`—Yields the processor

SYNOPSIS

```
#include <sched.h>
int sched_yield(void);
```

DESCRIPTION

A process can relinquish the processor voluntarily without blocking by calling `sched_yield`. The process will then be moved to the end of the queue for its static priority and a new process gets to run.

Note: If the current process is the only process in the highest priority list at that time, this process will continue to run after a call to `sched_yield`.

POSIX systems on which `sched_yield` is available define `_POSIX_PRIORITY_SCHEDULING` in `<unistd.h>`.

RETURN VALUE

On success, `sched_yield` returns 0. On error, -1 is returned, and `errno` is set appropriately.

STANDARDS

POSIX.1b (formerly POSIX.4)

SEE ALSO

`sched_setscheduler(2)` for a description of Linux scheduling

Programming for the Real World—POSIX.4 by Bill O. Gallmeister, O'Reilly & Associates, Inc., ISBN 1-56592-074-0

IEEE Std 1003.1b-1993 (POSIX.1b standard)

ISO/IEC 9945-1:1996

Linux 1.3.81, 10 April 1996

select, FD_CLR, FD_ISSET, FD_SET, FD_ZERO

`select`, `FD_CLR`, `FD_ISSET`, `FD_SET`, `FD_ZERO`—Synchronous I/O multiplexing

SYNOPSIS

```
#include <sys/time.h>
#include <sys/types.h>
#include <unistd.h>
int select(int n, fd_set *readfds, fd_set *writefds, fd_set *exceptfds,
           struct timeval *timeout);
FD_CLR(int fd, fd_set *set);
FD_ISSET(int fd, fd_set *set);
FD_SET(int fd, fd_set *set);
FD_ZERO(fd_set *set)
```

DESCRIPTION

`select` waits for a number of file descriptors to change status.

Three independent sets of descriptors are watched. Those listed in `readfds` will be watched to see if characters become available for reading, those in `writefds` will be watched to see if it is okay to immediately write on them, and those in `exceptfds` will be watched for exceptions. On exit, the sets are modified in place to indicate which descriptors actually changed status.

Four macros are provided to manipulate the sets. `FD_ZERO` will clear a set. `FD_SET` and `FD_CLR` add or remove a given descriptor from a set. `FD_ISSET` tests to see if a descriptor is part of the set; this is useful after `select` returns.

`n` is the highest-numbered descriptor in any of the three sets, plus 1.

`timeout` is an upper bound on the amount of time elapsed before `select` returns. It may be 0, which causes `select` to return immediately. If `timeout` is NULL (no timeout), `select` can block indefinitely.

RETURN VALUE

On success, `select` returns the number of descriptors contained in the descriptor sets, which may be 0 if the timeout expires before anything interesting happens. On error, -1 is returned, and `errno` is set appropriately; the sets and `timeout` become undefined, so do not rely on their contents after an error.

ERRORS

EBADF	An invalid file descriptor was given in one of the sets.
EINTR	A non-blocked signal was caught.
EINVAL	<code>n</code> is negative.
ENOMEM	<code>select</code> was unable to allocate memory for internal tables.

NOTES

Some code calls `select` with all three sets empty, `n=0`, and a non-null timeout; this is a fairly portable way to sleep with subsecond precision.

On Linux, `timeout` is modified to reflect the amount of time not slept; most other implementations do not do this. This causes problems both when Linux code that reads `timeout` is ported to other operating systems and when code is ported to Linux that reuses a `struct timeval` for multiple `selects` in a loop without reinitializing it. Consider `timeout` to be undefined after `select` returns.

EXAMPLE

```
#include <stdio.h>
#include <sys/time.h>
#include <sys/types.h>
#include <unistd.h>
```



```

int
main(void)
{
    fd_set rfds;
    struct timeval tv;
    int retval;

    /* Watch stdin (fd 0) to see when it has input. */
    FD_ZERO(&rfds);
    FD_SET(0, &rfds);
    /* Wait up to five seconds. */
    tv.tv_sec = 5;
    tv.tv_usec = 0;

    retval = select(1, &rfds, NULL, NULL, &tv);
    /* Don't rely on the value of tv now! */

    if (retval)
        printf("Data is available now.nn");
        /* FD_ISSET(0, &rfds) will be true. */
    else
        printf("No data within five seconds.nn");
    exit(0);
}

```

SEE ALSO

accept(2), connect(2), read(2), recv(2), send(2), write(2)

Linux 1.2, 11 February 1996

semctl

semctl—Semaphore-control operations

SYNOPSIS

```

#include <sys/types.h>
#include <sys/ipc.h>
#include <sys/sem.h>
int semctl ( int semid,int semnum,int cmd, union semun arg );

```

DESCRIPTION

The function performs the control operation specified by `cmd` on the semaphore set (or on the `sumun`-nth semaphore of the set) identified by `semid`. The first semaphore of the set is indicated by a value of 0 for `semun`.

The type of `arg` is the union

```

union semun {
    int val; /* used for SETVAL only */
    struct semid_ds *buf; /* for IPC_STAT and IPC_SET */
    ushort *array; /* used for GETALL and SETALL */
};

```

Legal values for `cmd` are

IPC_STAT	Copies info from the semaphore set data structure into the structure pointed to by <code>arg.buf</code> . The argument <code>semnum</code> is ignored. The calling process must have read access privileges on the semaphore set.

IPC_SET	Writes the values of some members of the <code>semid_ds</code> structure pointed to by <code>arg.buf</code> to the semaphore set data structure, updating also its <code>sem_ctime</code> member. Considered members from the user-supplied struct <code>semid_ds</code> pointed to by <code>arg.buf</code> are <pre>sem_perm.uid sem_perm.gid sem_perm.mode /* only lowest 9-bits */</pre> The calling process's effective user ID must be super-user, creator, or owner of the semaphore set. The argument <code>semnum</code> is ignored.
IPC_RMID	Removes the semaphore set and its data structures immediately, awakening all waiting processes (with an error return and <code>errno</code> set to <code>EIDRM</code>). The calling process's effective user ID must be super-user, creator, or owner of the semaphore set. The argument <code>semnum</code> is ignored.
GETALL	Returns <code>semval</code> for all semaphores of the set into <code>arg.array</code> . The argument <code>semnum</code> is ignored. The calling process must have read access privileges on the semaphore set.
GETNCNT	The system call returns the value of <code>semncnt</code> for the <code>semno</code> -th semaphore of the set (that is, the number of processes waiting for an increase of <code>semval</code> for the <code>semno</code> -th semaphore of the set). The calling process must have read access privileges on the semaphore set.
GETPID	The system call returns the value of <code>sempid</code> for the <code>semno</code> -th semaphore of the set (that is, the <code>pid</code> of the process that executed the last <code>semop</code> call for the <code>semno</code> -th semaphore of the set). The calling process must have read access privileges on the semaphore set.
GETVAL	The system call returns the value of <code>semval</code> for the <code>semno</code> -th semaphore of the set. The calling process must have read access privileges on the semaphore set.
GETZCNT	The system call returns the value of <code>semzcnt</code> for the <code>semno</code> -th semaphore of the set (that is, the number of processes waiting for the <code>semval</code> of the <code>semno</code> -th semaphore of the set to become 0). The calling process must have read access privileges on the semaphore set.
SETALL	Sets <code>semval</code> for all semaphores of the set using <code>arg.array</code> , updating also the <code>sem_ctime</code> member of the <code>semid_ds</code> structure associated with the set. Undo entries are cleared for altered semaphores in all processes. Processes sleeping on the wait queue are awakened if some <code>semval</code> becomes 0 or increases. The argument <code>semnum</code> is ignored. The calling process must have alter access privileges on the semaphore set.
SETVAL	Sets the value of <code>semval</code> to <code>arg.val</code> for the <code>semnum</code> -th semaphore of the set, updating also the <code>sem_ctime</code> member of the <code>semid_ds</code> structure associated to the set. The undo entry is cleared for the altered semaphore in all processes. Processes sleeping on the wait queue are awakened if <code>semval</code> becomes 0 or increases. The calling process must have alter access privileges on the semaphore set.

RETURN VALUE

On fail, the system call returns -1, with `errno` indicating the error. Otherwise the system call returns a non-negative value, depending on `cmd`, as follows:

GETNCNT	The value of <code>semncnt</code> .
GETPID	The value of <code>sempid</code> .
GETVAL	The value of <code>semval</code> .
GETZCNT	The value of <code>semzcnt</code> .

ERRORS

For a failing return, `errno` will be set to one of the following values:

EACCESS	The calling process has no access permissions needed to execute <code>cmd</code> .
EFAULT	The address pointed to by <code>arg.buf</code> or <code>arg.array</code> isn't accessible.
EIDRM	The semaphore set was removed.
EINVAL	Invalid value for <code>cmd</code> or <code>semid</code> .

EPERM	The argument <code>cmd</code> has the value <code>IPC_SET</code> or <code>IPC_RMID</code> , but the calling process's effective user ID has insufficient privileges to execute the command.
ERANGE	The argument <code>cmd</code> has the value <code>SETALL</code> or <code>SETVAL</code> , and the value to which <code>semval</code> has to be set (for some semaphore of the set) is less than 0 or greater than the implementation value <code>SEMVMX</code> .

NOTES

The `IPC_INFO`, `SEM_STAT`, and `SEM_INFO` control calls are used by the `ipcs(1)` program to provide information on allocated resources. In the future these can be modified as needed or moved to a `proc` filesystem interface.

The following system limit on semaphore sets affects a `semctl` call:

SEMVMX	Maximum value for <code>semval</code> ; implementation dependent (32767).

SEE ALSO

`ipc(5)`, `shmget(2)`, `shmat(2)`, `shmdt(2)`

Linux 0.99.13, 1 November 1993

semget

`semget`—Gets a semaphore set identifier

SYNOPSIS

```
# include <sys/types.h>
# include <sys/ipc.h>
# include <sys/sem.h>
int semget ( key_t key, int nsems, int semflg );
```

DESCRIPTION

This function returns the semaphore set identifier associated with the value of the argument `key`. A new set of `nsems` semaphores is created if `key` has the value `IPC_PRIVATE` or `key` isn't `IPC_PRIVATE`, if no existing message queue is associated to `key`, and if `IPC_CREAT` is asserted in `semflg` (that is, `semflg & IPC_CREAT` isn't 0). The presence in `semflg` of the fields `IPC_CREAT` and `IPC_EXCL` plays the same role, with respect to the existence of the semaphore set, as the presence of `O_CREAT` and `O_EXCL` in the mode argument of the `open(2)` system call—that is, the `msgget` function fails if `semflg` asserts both `IPC_CREAT` and `IPC_EXCL` and a semaphore set already exists for `key`.

Upon creation, the lower 9 bits of the argument `semflg` define the access permissions (for owner, group, and others) to the semaphore set in the same format, and with the same meaning, as for the access permissions parameter in the `open(2)` or `creat(2)` system call (although the execute permissions are not used by the system, and the term *write permissions*, for a semaphore set, effectively means *alter permissions*).

Furthermore, while creating, the system call initializes the system semaphore set data structure `semid_ds` as follows:

- `sem_perm.cuid` and `sem_perm.uid` are set to the effective user ID of the calling process.
- `sem_perm.cgid` and `sem_perm.gid` are set to the effective group ID of the calling process.
- The lowest-order 9 bits of `sem_perm.mode` are set to the lowest-order 9 bits of `semflg`.
- `sem_nsems` is set to the value of `nsems`.
- `sem_otime` is set to 0.
- `sem_ctime` is set to the current time.

The argument `nsems` can be 0 (a “don't care”) when the system call isn't `create(2)`. Otherwise, `nsems` must be greater than 0 and less or equal to the maximum number of semaphores per `semid` (`SEMMSL`).

If the semaphore set already exists, the access permissions are verified, and a check is made to see if it is marked for destruction.

RETURN VALUE

If successful, the return value will be the semaphore set identifier (a positive integer); otherwise it will be `-1`, with `errno` indicating the error.

ERRORS

For a failing return, `errno` will be set to one of the following values:

<code>EACCES</code>	A semaphore set exists for <code>key</code> , but the calling process has no access permissions to the set.
<code>EEXIST</code>	A semaphore set exists for <code>key</code> , and <code>semflg</code> was asserting both <code>IPC_CREAT</code> and <code>IPC_EXCL</code> .
<code>EIDRM</code>	The semaphore set is marked to be deleted.
<code>ENOENT</code>	No semaphore set exists for <code>key</code> , and <code>semflg</code> wasn't asserting <code>IPC_CREAT</code> .
<code>ENOMEM</code>	A semaphore set has to be created, but the system does not have enough memory for the new data structure.
<code>ENOSPC</code>	A semaphore set has to be created, but the system limit for the maximum number of semaphore sets (<code>SEMMNI</code>) or the system-wide maximum number of semaphores (<code>SEMMNS</code>) would be exceeded.

NOTES

`IPC_PRIVATE` isn't a flag field but a `key_t` type. If this special value is used for `key`, the system call ignores everything but the lowest-order 9 bits of `semflg` and creates a new semaphore set (on success).

The followings are limits on semaphore set resources affecting a `semget` call:

<code>SEMMNI</code>	System-wide maximum number of semaphore sets; policy dependent.
<code>SEMMSL</code>	Maximum number of semaphores per <code>semid</code> ; implementation dependent (500 currently).
<code>SEMMNS</code>	System-wide maximum number of semaphores; policy dependent. A value greater than <code>SEMMSL×SEMMNI</code> makes it irrelevant.

BUGS

Use of `IPC_PRIVATE` doesn't inhibit other processes' access to the allocated semaphore set.

As for the files, there is currently no intrinsic way for a process to ensure exclusive access to a semaphore set. Asserting both `IPC_CREAT` and `IPC_EXCL` in `semflg` only ensures (on success) that a new semaphore set will be created; it doesn't imply exclusive access to the semaphore set.

The data structure associated with each semaphore in the set isn't initialized by the system call. In order to initialize those data structures, you have to execute a subsequent call to `semctl(2)` to perform a `SETVAL` or a `SETALL` command on the semaphore set.

SEE ALSO

`ftok(3)`, `ipc(5)`, `semctl(2)`, `semop(2)`

Linux 0.99.13, 1 November 1993

semop

`semop`—Semaphore operations

SYNOPSIS

```
# include <sys/types.h>
# include <sys/ipc.h>
# include <sys/sem.h>
int semop ( int semid, struct sembuf *sops, unsigned nsops );
```

DESCRIPTION

The function performs operations on selected members of the semaphore set indicated by `semid`. Each of the `nsops` elements in the array pointed to by `sops` specifies an operation to be performed on a semaphore by a struct `sembuf` including the following members:

```
short sem_num; /* semaphore number: 0 = first */
short sem_op; /* semaphore operation */
short sem_flg; /* operation flags */
```

Flags recognized in `sem_flg` are `IPC_NOWAIT` and `SEM_UNDO`. If an operation asserts `SEM_UNDO`, it will be undone when the process exits.

The system call semantic assures that the operations will be performed if and only if all of them will succeed. Each operation is performed on the `sem_num`-th semaphore of the semaphore set, where the first semaphore of the set is semaphore 0 and is one of the following three:

- If `sem_op` is a positive integer, the operation adds this value to `semval`. Furthermore, if `SEM_UNDO` is asserted for this operation, the system updates the process undo count for this semaphore. The operation always goes through, so no process sleeping can happen. The calling process must have alter permissions on the semaphore set.
- If `sem_op` is 0, the process must have read access permissions on the semaphore set. If `semval` is 0, the operation goes through. Otherwise, if `IPC_NOWAIT` is asserted in `sem_flg`, the system call fails (undoing all previous actions performed), with `errno` set to `EAGAIN`. Otherwise, `semzcnt` is incremented by 1, and the process sleeps until one of the following occurs:
 - `semval` becomes 0, at which time the value of `semzcnt` is decremented.
 - The semaphore set is removed, causing the system call to fail with `errno` set to `EIDRM`.
 - The calling process receives a signal that has to be caught; which causes the value of `semzcnt` to be decremented and the system call to fail with `errno` set to `EINTR`.
- If `sem_op` is less than 0, the process must have alter permissions on the semaphore set. If `semval` is greater than or equal to the absolute value of `sem_op`, the absolute value of `sem_op` is subtracted by `semval`. Furthermore, if `SEM_UNDO` is asserted for this operation, the system updates the process undo count for this semaphore. Then the operation goes through. Otherwise, if `IPC_NOWAIT` is asserted in `sem_flg`, the system call fails (undoing all previous actions performed), with `errno` set to `EAGAIN`. Otherwise, `semncnt` is incremented by 1 and the process sleeps until one of the following occurs:
 - `semval` becomes greater than or equal to the absolute value of `sem_op`, at which time the value of `semncnt` is decremented, the absolute value of `sem_op` is subtracted from `semval` and, if `SEM_UNDO` is asserted for this operation, the system updates the process undo count for this semaphore.
 - The semaphore set is removed from the system: the system call fails, with `errno` set to `EIDRM`.
 - The calling process receives a signal that has to be caught; the value of `semncnt` is decremented, and the system call fails with `errno` set to `EINTR`.

In case of success, the `sempid` member of the structure `sem` for each semaphore specified in the array pointed to by `sops` is set to the process ID of the calling process. Furthermore both `sem_otime` and `sem_ctime` are set to the current time.

RETURN VALUE

If successful, the system call returns 0; otherwise, it returns -1, with `errno` indicating the error.

ERRORS

For a failing return, `errno` will be set to one of the following values:

E2BIG	The argument <code>nsops</code> is greater than <code>SEMOPM</code> , the maximum number of operations allowed per system call.
EACCES	The calling process has no access permissions on the semaphore set as required by one of the specified operations.
EAGAIN	An operation could not go through, and <code>IPC_NOWAIT</code> was asserted in its <code>sem_flg</code> .
EFAULT	The address pointed to by <code>sops</code> isn't accessible.

EFBIG	For some operation, the value of <code>sem_num</code> is less than 0 or greater than or equal to the number of semaphores in the set.
EIDRM	The semaphore set was removed.
EINTR	Sleeping on a wait queue, the process received a signal that had to be caught.
EINVAL	The semaphore set doesn't exist, or <code>semid</code> is less than 0, or <code>nsops</code> has a non-positive value.
ENOMEM	The <code>sem_flg</code> of some operation asserted <code>SEM_UNDO</code> , and the system does not have enough memory to allocate the undo structure.
ERANGE	For some operation, <code>semop+semvalis</code> is greater than <code>SEMVMX</code> , the implementation-dependent maximum value for <code>semval</code> .

NOTES

The `sem_undo` structures of a process aren't inherited by its child on execution of a `fork(2)` system call. They are instead inherited by the substituting process resulting from the execution of the `exec(2)` system call.

The following are limits on semaphore set resources affecting a `semop` call:

<code>SEMOPM</code>	Maximum number of operations allowed for one <code>semop</code> call; policy dependent.
<code>SEMVMX</code>	Maximum allowable value for <code>semval</code> ; implementation dependent (32767).

The implementation has no intrinsic limits for the adjust on exit maximum value (`SEMAEM`), the system-wide maximum number of undo structures (`SEMMNU`), or the per-process maximum number of undo entries system parameters.

BUGS

The system maintains a per-process `sem_undo` structure for each semaphore altered by the process with undo requests. Those structures are free at process exit. One major cause for unhappiness with the undo mechanism is that it does not fit in with the notion of having an atomic set of operations in an array of semaphores. The undo requests for an array and each semaphore therein might have been accumulated over many `semop` calls. Should the process sleep when exiting, or should all undo operations be applied with the `IPC_NOWAIT` flag in effect? Currently those undo operations that go through immediately are applied, and those that require a wait are ignored silently. Therefore harmless undo usage is guaranteed with private semaphores only.

SEE ALSO

`ipc(5)`, `semctl(2)`, `semget(2)`

Linux 0.99.13, 1 November 1993

send, sendto, sendmsg

`send`, `sendto`, `sendmsg`—Sends a message from a socket

SYNOPSIS

```
#include <sys/types.h>
#include <sys/socket.h>
int send(int s, const void *msg, int len, unsigned int flags);
int sendto(int s, const void *msg, int len, unsigned int flags,
           const struct sockaddr *to, int tolen);
int sendmsg(int s, const struct msghdr *msg, unsigned int flags);
```

DESCRIPTION

Warning: This is a BSD man page. As of Linux 0.99.11, `sendmsg` was not implemented.

`send`, `sendto`, and `sendmsg` are used to transmit a message to another socket. `send` may be used only when the socket is in a connected state, whereas `sendto` and `sendmsg` may be used at any time.

The address of the target is given by `to`, with `toLen` specifying its size. The length of the message is given by `len`. If the message is too long to pass atomically through the underlying protocol, the error `EMSGSIZE` is returned, and the message is not transmitted.

No indication of failure to deliver is implicit in a `send`. Locally detected errors are indicated by a return value of `-1`.

If no message space is available at the socket to hold the message to be transmitted, `send` normally blocks, unless the socket has been placed in non-blocking I/O mode. The `select(2)` call may be used to determine when it is possible to send more data.

The `flags` parameter may include one or more of the following:

```
#define MSG_OOB 0x1 /* process out-of-band data */
#define MSG_DONTROUTE 0x4 /* bypass routing, use direct interface */
```

The flag `MSG_OOB` is used to send out-of-band data on sockets that support this notion (for example, `SOCK_STREAM`); the underlying protocol must also support out-of-band data. `MSG_DONTROUTE` is usually used only by diagnostic or routing programs.

See `recv(2)` for a description of the `msghdr` structure.

RETURN VALUES

The call returns the number of characters sent, or `-1` if an error occurred.

ERRORS

<code>EBADF</code>	An invalid descriptor was specified.
<code>ENOTSOCK</code>	The argument <code>s</code> is not a socket.
<code>EFAULT</code>	An invalid user space address was specified for a parameter.
<code>EMSGSIZE</code>	The socket requires that message be sent atomically, and the size of the message to be sent made this impossible.
<code>EWOULDBLOCK</code>	The socket is marked non-blocking, and the requested operation would block.
<code>ENOBUFS</code>	The system was unable to allocate an internal buffer. The operation might succeed when buffers become available.
<code>ENOBUFS</code>	The output queue for a network interface was full. This generally indicates that the interface has stopped sending, but it might be caused by transient congestion.

HISTORY

These function calls appeared in BSD 4.2.

SEE ALSO

`fcntl(2)`, `recv(2)`, `select(2)`, `getsockopt(2)`, `socket(2)`, `write(2)`

BSD Man Page, 24 July 1993

setfsgid

`setfsgid`—Sets group identity used for filesystem checks

SYNOPSIS

```
int setfsgid(uid_t fsgid);
```

DESCRIPTION

`setfsgid` sets the group ID that the Linux kernel uses to check for all accesses to the filesystem. Normally, the value of `fsgid` will shadow the value of the effective group ID. In fact, whenever the effective group ID is changed, `fsgid` will also be changed to the new value of the effective group ID.

An explicit call to `setfsgid` is usually only used by programs such as the Linux NFS server that need to change what group ID is used for file access without a corresponding change in the real and effective group IDs. A change in the normal group IDs for a program such as the NFS server is a security hole that can expose it to unwanted signals from other group IDs.

`setfsgid` will succeed only if the caller is the superuser or if `fsgid` matches either the real group ID, effective group ID, saved group ID, or the current value of `fsgid`.

RETURN VALUE

On success, the previous value of `fsgid` is returned. On error, the current value of `fsgid` is returned.

CONFORMS TO

`setfsgid` is Linux specific.

BUGS

No error messages of any kind are returned to the caller. At the very least, `EPERM` should be returned when the call fails.

SEE ALSO

`setfsuid(2)`

Linux 1.3.15, 6 August 1995

setfsuid

`setfsuid`—Sets user identity used for filesystem checks

SYNOPSIS

```
int setfsuid(uid_t fsuid);
```

DESCRIPTION

`setfsuid` sets the user ID that the Linux kernel uses to check for all accesses to the filesystem. Normally, the value of `fsuid` will shadow the value of the effective user ID. In fact, whenever the effective user ID is changed, `fsuid` will also be changed to the new value of the effective user ID.

An explicit call to `setfsuid` is usually used only by programs such as the Linux NFS server that need to change what user ID is used for file access without a corresponding change in the real and effective user IDs. A change in the normal user IDs for a program such as the NFS server is a security hole that can expose it to unwanted signals from other user IDs.

`setfsuid` will succeed only if the caller is the superuser or if `fsuid` matches either the real user ID, effective user ID, saved user ID, or the current value of `fsuid`.

RETURN VALUE

On success, the previous value of `fsuid` is returned. On error, the current value of `fsuid` is returned.

CONFORMS TO

`setfsuid` is Linux specific.

BUGS

No error messages of any kind are returned to the caller. At the very least, `EPERM` should be returned when the call fails.

SEE ALSO

`setfsgid(2)`

Linux 1.3.15, 6 August 1995

setgid

setgid—Sets group identity

SYNOPSIS

```
#include <unistd.h>
int setgid(gid_t gid);
```

DESCRIPTION

setgid sets the effective group ID of the current process. If the caller is the superuser, the real and saved group IDs are also set.

Under Linux, setgid is implemented like sysv, with SAVED_IDS. This allows a setgid (other than root) program to drop all its group privileges, do some unprivileged work, and then re-engage the original effective group ID in a secure manner.

If the user is root or the program is setgid root, special care must be taken. The setgid function checks the effective gid of the caller and, if it is that of the superuser, all process-related group IDs are set to gid. After this has occurred, it is impossible for the program to regain root privileges.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and errno is set appropriately.

ERRORS

EPERM The user is not the superuser, and gid does not match the effective or saved group ID of the calling process.

CONFORMS TO

System V

SEE ALSO

getgid(2), setregid(2), setegid(2)

Linux 1.1.36, 29 July 1994

setpgid, getpgid, setpgrp, getpgrp

setpgid, getpgid, setpgrp, getpgrp—Sets/gets process group

SYNOPSIS

```
#include <unistd.h>
int setpgid(pid_t pid, pid_t pgid);
pid_t getpgid(pid_t pid);
int setpgrp(void);
pid_t getpgrp(void);
```

DESCRIPTION

setpgid sets the process group ID of the process specified by pid to pgid. If pid is 0, the process ID of the current process is used. If pgid is 0, the process ID of the process specified by pid is used.

getpgid returns the process group ID of the process specified by pid. If pid is 0, the process ID of the current process is used.

In the Linux DLL 4.4.1 library, setpgrp simply calls setpgid(0,0).

getpgrp is equivalent to getpgid(0).

Process groups are used for distribution of signals, and by terminals to arbitrate requests for their input; processes that have the same process group as the terminal are foreground and may read, whereas others will block with a signal if they attempt to read.

These calls are thus used by programs such as `csh(1)` to create process groups in implementing job control. The `TIOCGPGRP` and `TIOCSPGRP` calls described in `termios(4)` are used to get/set the process group of the control terminal.

RETURN VALUE

On success, `setpgid` and `setpgrp` return `0`. On error, `-1` is returned, and `errno` is set appropriately.

`getpgid` returns a process group on success. On error, `-1` is returned, and `errno` is set appropriately.

`getpgrp` always returns the current process group.

ERRORS

<code>EINVAL</code>	<code>pgid</code> is less than <code>0</code> .
<code>EPERM</code>	Various permission violations.
<code>ESRCH</code>	<code>pid</code> does not match any process.

CONFORMS TO

The functions `setpgid` and `getpgrp` conform to POSIX.1. The function `setpgrp` is from BSD 4.2. I have no information on the source of `getpgid`.

SEE ALSO

`getuid(2)`, `setuid(2)`, `tcsetpgrp(3)`, `termios(4)`

Linux 1.2.4, 15 April 1995

setregid, setegid

`setregid`, `setegid`—Sets real and/or effective group ID

SYNOPSIS

```
#include <unistd.h>
int setregid(gid_t rgid, gid_t egid);
int setegid(gid_t egid);
```

DESCRIPTION

`setregid` sets real and effective group IDs of the current process. Unprivileged users may change the real group ID to the effective group ID, and vice versa.

Prior to Linux 1.1.38, the saved ID paradigm, when used with `setregid` or `setegid`, was broken. Starting at 1.1.38, it is also possible to set the effective group ID from the saved user ID.

Only the superuser may make other changes.

Supplying a value of `-1` for either the real or effective group ID forces the system to leave that ID unchanged.

Currently (`libc-4.x.x`), `setegid(egid)` is functionally equivalent to `setregid(-1, egid)`.

If the real group ID is changed or the effective group ID is set to a value not equal to the previous real group ID, the saved group ID will be set to the new effective group ID.

RETURN VALUE

On success, `0` is returned. On error, `-1` is returned, and `errno` is set appropriately.

ERRORS

EPERM

The current process is not the superuser, and changes other than swapping the effective group ID with the real group ID, setting one to the value of the other, or setting the effective group ID to the value of the saved group ID was specified.

HISTORY

The `setregid` function call appeared in BSD 4.2.

CONFORMS TO

BSD 4.3

SEE ALSO

`getgid(2)`, `setgid(2)`

Linux 1.1.38, 2 August 1994

setreuid, seteuid

setreuid, seteuid—Sets real and / or effective user ID

SYNOPSIS

```
#include <unistd.h>
int setreuid(uid_t ruid, uid_t euid);
int seteuid(uid_t euid);
```

DESCRIPTION

setreuid sets real and effective user IDs of the current process. Unprivileged users may change the real user ID to the effective user ID, and vice versa.

Prior to Linux 1.1.37, the saved ID paradigm, when used with `setreuid` or `seteuid`, was broken.

Starting at 1.1.37, it is also possible to set the effective user ID from the saved user ID.

Only the superuser may make other changes.

Supplying a value of -1 for either the real or effective user ID forces the system to leave that ID unchanged.

Currently (libc-4.x.x), `seteuid(euid)` is functionally equivalent to `setreuid(-1, euid)`.

If the real user ID is changed or the effective user ID is set to a value not equal to the previous real user ID, the saved user ID will be set to the new effective user ID.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

EPERM

The current process is not the superuser, and changes other than swapping the effective user ID with the real user ID, setting one to the value of the other, or setting the effective user ID to the value of the saved user ID was specified.

HISTORY

The `setreuid` function call appeared in BSD 4.2.

CONFORMS TO

BSD 4.3

SEE ALSO

`getuid(2)`, `setuid(2)`

Linux 1.1.38, 2 August 1994

setsid

`setsid`—Creates a session and sets the process group ID

SYNOPSIS

```
#include <unistd.h>
pid_t setsid(void);
```

DESCRIPTION

`setsid()` creates a new session if the calling process is not a process group leader. The calling process is the leader of the new session, the process group leader of the new process group, and has no controlling tty. The process group ID and session ID of the calling process are set to the PID of the calling process. The calling process will be the only process in this new process group and in this new session.

RETURN VALUE

It returns the session ID of the calling process.

ERRORS

On error, `-1` will be returned. The only error that can happen is `EPERM`, which is returned when the process group ID of any process equals the PID of the calling process. Thus, in particular, `setsid` fails if the calling process is already a process group leader.

NOTES

A *process group leader* is a process with process group ID equal to its PID. In order to be sure that `setsid` will succeed, `fork`, `and exit`, and have the child do `setsid()`.

CONFORMS TO

POSIX

SEE ALSO

`setpgid(2)`, `setpgrp(2)`

27 August 1994

setuid

`setuid`—Sets user identity

SYNOPSIS

```
#include <unistd.h>
int setuid(uid_t uid);
```

DESCRIPTION

`setuid` sets the effective user ID of the current process. If the caller is the superuser, the real and saved user IDs are also set.

Under Linux, `setuid` is implemented like `sysv`, with `SAVED_IDS`. This allows a `setuid` (other than `root`) program to drop all its user privileges, do some unprivileged work, and then re-engage the original effective user ID in a secure manner.

If the user is `root` or the program is `setuid root`, special care must be taken. The `setuid` function checks the effective UID of the caller, and, if it is the superuser, all process-related user IDs are set to `uid`. After this has occurred, it is impossible for the program to regain root privileges.

RETURN VALUE

On success, `0` is returned. On error, `-1` is returned, and `errno` is set appropriately.

ERRORS

<code>EPERM</code>	The user is not the superuser, and <code>uid</code> does not match the effective or saved user ID of the calling process.

CONFORMS TO

System V

SEE ALSO

`getuid(2)`, `setreuid(2)`, `seteuid(2)`

Linux 1.1.36 29 July 1994

setup

`setup`—Sets up devices and filesystems, mount root filesystem

SYNOPSIS

```
#include <unistd.h>
syscall0(int, setup);
int setup(void);
```

DESCRIPTION

`setup` is called once from within `linux/init/main.c`. It calls initialization functions for devices and filesystems configured into the kernel and then mounts the root filesystem.

No user process may call `setup`. Any user process, even a process with superuser permission, will receive `EPERM`.

RETURN VALUE

`setup` always returns `-1` for a user process.

ERRORS

<code>EPERM</code>	Always, for a user process.

CONFORMS TO

This function is Linux specific.

Linux 1.2.9, 3 May 1996

shmctl

`shmctl`—Shared memory control

SYNOPSIS

```
#include <sys/ipc.h>
#include <sys/shm.h>
int shmctl(int shmid,int cmd, struct shmid_ds *buf);
```

DESCRIPTION

shmctl() allows the user to receive information on a shared memory segment, set the owner, group, and permissions of a shared memory segment, or destroy a segment. The information about the segment identified by shmid is returned in a shmid_ds structure:

```
struct shmid_ds {
    struct ipc_perm shm_perm; /* operation perms */
    int shm_segsz; /* size of segment (bytes) */
    time_t shm_atime; /* last attach time */
    time_t shm_dtime; /* last detach time */
    time_t shm_ctime; /* last change time */
    unsigned short shm_cpid; /* pid of creator */
    unsigned short shm_lpid; /* pid of last operator */
    short shm_nattch; /* no. of current attaches */
    /* the following are private */
    unsigned short shm_npages; /* size of segment (pages) */
    unsigned long *shm_pages;
    struct shm_desc *attaches; /* descriptors for attaches */
};
```

The fields in the member shm_perm can be set:

```
struct ipc_perm
{
    key_t key;
    ushort uid; /* owner euid and egid */
    ushort gid;
    ushort cuid; /* creator euid and egid */
    ushort cgid;
    ushort mode; /* lower 9 bits of access modes */
    ushort seq; /* sequence number */
};
```

The following cmds are available:

IPC_STAT	Used to copy the information about the shared memory segment into the buffer, buf. The user must have read access to the shared memory segment.
IPC_SET	Used to apply the changes the user has made to the uid, gid, or mode members of the shm_perms field. Only the lowest 9 bits of mode are used. The shm_ctime member is also updated. The user must be the owner, the creator, or the superuser.
IPC_RMID	Used to mark the segment as destroyed. It will actually be destroyed after the last detach. (That is, when the shm_nattch member of the associated structure shmid_ds is zero.) The user must be the owner, the creator, or the superuser.

The user must ensure that a segment is eventually destroyed; otherwise the pages that were faulted in will remain in memory or swap.

In addition, the superuser can prevent or allow swapping of a shared memory segment with the following cmds: (Linux only)

SHM_LOCK	Prevents swapping of a shared memory segment. The user must fault in any pages that are required to be present after locking is enabled.
SHM_UNLOCK	Allows the shared memory segment to be swapped out.

The IPC_INFO, SHM_STAT, and SHM_INFO control calls are used by the ipcs(1) program to provide information on allocated resources. In the future, these may be modified as needed or moved to a proc filesystem interface.

SYSTEM CALLS

<code>fork()</code>	After a <code>fork()</code> , the child inherits the attached shared memory segments.
<code>exec()</code>	After an <code>exec()</code> , all attached shared memory segments are detached (not destroyed).
<code>exit()</code>	On <code>exit()</code> , all attached shared memory segments are detached (not destroyed).

RETURN VALUE

0 is returned on success; -1 on error.

ERRORS

On error, `errno` will be set to one of the following:

<code>EACCESS</code>	Returned if <code>IPC_STAT</code> is requested and <code>shm_perm.modes</code> does not allow read access for <code>msqid</code> .
<code>EFAULT</code>	The argument <code>cmd</code> has the value <code>IPC_SET</code> or <code>IPC_STAT</code> , but the address pointed to by <code>buf</code> isn't accessible.
<code>EINVAL</code>	Returned if <code>shmid</code> is not a valid identifier, or <code>cmd</code> is not a valid command.
<code>EIDRM</code>	Returned if <code>shmid</code> points to a removed identifier.
<code>EPERM</code>	Returned if <code>IPC_SET</code> or <code>IPC_RMID</code> is attempted, if the user is not the creator, the owner, or the superuser, and if the user does not have permission granted to his group or to the world.

SEE ALSO

`shmget(2)`, `shmop(2)`

Linux 0.99.11, 28 November 1993

shmget

`shmget`—Allocates a shared memory segment

SYNOPSIS

```
#include <sys/ipc.h>
#include <sys/shm.h>
int shmget(key_t key, int size, int shmflg);
```

DESCRIPTION

`shmget()` returns the identifier of the shared memory segment associated with the value of the argument `key`. A new shared memory segment, with its size equal to the rounding up of `size` to a multiple of `PAGE_SIZE`, is created if `key` has the value `IPC_PRIVATE` or if `key` isn't `IPC_PRIVATE`, if no shared memory segment is associated to `key`, and if `IPC_CREAT` is asserted in `shmflg` (that is, `shmflg & IPC_CREAT` isn't 0). The presence in `shmflg` is composed of

<code>IPC_CREAT</code>	Creates a new segment. If this flag is not used, <code>shmget()</code> will find the segment associated with <code>key</code> , check to see if the user has permission to receive the <code>shmid</code> associated with the segment, and ensure the segment is not marked for destruction.
<code>IPC_EXCL</code>	Used with <code>IPC_CREAT</code> to ensure failure if the segment exists.
<code>mode_flags</code>	(lowest 9 bits) Specifies the permissions granted to the owner, group, and world. Presently, the execute permissions are not used by the system.

If a new segment is created, the access permissions from `shmflg` are copied into the `shm_perm` member of the `shmid_ds` structure that defines the segment. Following is the `shmid_ds` structure:

```
struct shmid_ds {
    struct ipc_perm shm_perm; /* operation perms */
    int shm_segsz; /* size of segment (bytes) */
};
```

```

time_t shm_atime; /* last attach time */
time_t shm_dtime; /* last detach time */
time_t shm_ctime; /* last change time */
unsigned short shm_cpid; /* pid of creator */
unsigned short shm_lpid; /* pid of last operator */
short shm_nattch; /* no. of current attaches */
};

struct ipc_perm
{
    key_t key;
    ushort uid; /* owner euid and egid */
    ushort gid;
    ushort cuid; /* creator euid and egid */
    ushort cgid;
    ushort mode; /* lower 9 bits of shmflg */
    ushort seq; /* sequence number */
};

```

Furthermore, while creating, the system call initializes the system shared memory segment data structure `shmid_ds` as follows:

- `shm_perm.cuid` and `shm_perm.uid` are set to the effective user ID of the calling process.
- `shm_perm.cgid` and `shm_perm.gid` are set to the effective group ID of the calling process.
- The lowest-order 9 bits of `shm_perm.mode` are set to the lowest-order 9 bit of `shmflg`.
- `shm_segsz` is set to the value of `size`.
- `shm_lpid`, `shm_nattch`, `shm_atime`, and `shm_dtime` are set to 0.
- `shm_ctime` is set to the current time.

If the shared memory segment already exists, the access permissions are verified, and a check is made to see if it is marked for destruction.

SYSTEM CALLS

<code>fork()</code>	After a <code>fork()</code> , the child inherits the attached shared memory segments.
<code>exec()</code>	After an <code>exec()</code> , all attached shared memory segments are detached (not destroyed).
<code>exit()</code>	On <code>exit()</code> , all attached shared memory segments are detached (not destroyed).

RETURN VALUE

A valid segment identifier, `shmid`, is returned on success, -1 on error.

ERRORS

On failure, `errno` is set to one of the following:

<code>EINVAL</code>	Returned if <code>SHMMIN</code> is greater than <code>size</code> , if <code>size</code> is greater than <code>SHMMAX</code> , or if <code>size</code> is greater than the size of the segment.
<code>EEXIST</code>	Returned if <code>IPC_CREAT</code> <code>IPC_EXCL</code> was specified and the segment exists.
<code>EIDRM</code>	Returned if the segment is marked as destroyed or was removed.
<code>ENOSPC</code>	Returned if all possible shared memory IDs have been taken (<code>SHMMNI</code>) or if allocating a segment of the requested size would cause the system to exceed the system-wide limit on shared memory (<code>SHMALL</code>).
<code>ENOENT</code>	Returned if no segment exists for the given key, and <code>IPC_CREAT</code> was not specified.
<code>EACCES</code>	Returned if the user does not have permission to access the shared memory segment.
<code>ENOMEM</code>	Returned if no memory could be allocated for segment overhead.

NOTES

`IPC_PRIVATE` isn't a flag field but a `key_t` type. If this special value is used for key, the system call ignores everything but the lowest order 9 bits of `shmflg` and creates a new shared memory segment (on success).

The following are limits on shared memory segment resources affecting a `shmget` call:

<code>SHMALL</code>	System-wide maximum of shared memory pages; policy dependent.
<code>SHMMAX</code>	Maximum size, in bytes, for a shared memory segment; implementation dependent (currently 4MB).
<code>SHMMIN</code>	Minimum size, in bytes, for a shared memory segment; implementation dependent (currently 1 byte, although <code>PAGE_SIZE</code> is the effective minimum size).
<code>SHMMNI</code>	System-wide maximum number of shared memory segments; implementation dependent (currently 4096).

The implementation has no specific limits for the per-process maximum number of shared memory segments (`SHMSEG`).

BUGS

Use of `IPC_PRIVATE` does not inhibit other processes' access to the allocated shared memory segment.

As for the files, there is currently no intrinsic way for a process to ensure exclusive access to a shared memory segment. Asserting both `IPC_CREAT` and `IPC_EXCL` in `shmflg` only ensures (on success) that a new shared memory segment will be created; it doesn't imply exclusive access to the segment.

SEE ALSO

`ftok(3)`, `ipc(5)`, `shmctl(2)`, `shmat(2)`, `shmdt(2)`

Linux 0.99.11, 28 November 1993

shmop

shmop—Shared memory operations

SYNOPSIS

```
#include <sys/types.h>
#include <sys/ipc.h>
#include <sys/shm.h>
char *shmat ( int shmid, char *shmaddr, int shmflg );
int shmdt ( char *shmaddr );
```

DESCRIPTION

The function `shmat` attaches the shared memory segment identified by `shmid` to the data segment of the calling process. The attaching address is specified by `shmaddr` with one of the following criteria:

- If `shmaddr` is 0, the system tries to find an unmapped region in the range 1–1.5GB, starting from the upper value and coming down from there.
- If `shmaddr` isn't 0 and `SHM_RND` is asserted in `shmflg`, the attach occurs at the address equal to the rounding down of `shmaddr` to a multiple of `SHMLBA`. Otherwise, `shmaddr` must be a page-aligned address at which the attach occurs.

If `SHM_RDONLY` is asserted in `shmflg`, the segment is attached for reading, and the process must have read access permissions to the segment. Otherwise the segment is attached for read and write, and the process must have read and write access permissions to the segment. There is no notion of a write-only shared memory segment.

The `brk` value of the calling process is not altered by the attach. The segment will automatically be detached at process exit. The same segment may be attached as a read and as a read-write segment, more than once, in the process's address space.

On a successful `shmat` call, the system updates the members of the structure `shmid_ds` associated to the shared memory segment as follows:

- `shm_atime` is set to the current time.
- `shm_lpid` is set to the process ID of the calling process.
- `shm_nattch` is incremented by 1.

Note that the attachment will also succeed if the shared memory segment is marked to be deleted.

The function `shmdt` detaches from the calling process's data segment the shared memory segment located at the address specified by `shmaddr`. The detaching shared memory segment must be one among the currently attached ones (to the process's address space) with `shmaddr` equal to the value returned by its attaching `shmat` call.

On a successful `shmdt` call, the system updates the members of the structure `shmid_ds` associated to the shared memory segment as follows:

- `shm_dtime` is set to the current time.
- `shm_lpid` is set to the process ID of the calling process.
- `shm_nattch` is decremented by 1. If it becomes 0 and the segment is marked for deletion, the segment is deleted.

The occupied region in the user space of the calling process is unmapped.

SYSTEM CALLS

<code>fork()</code>	After a <code>fork()</code> , the child inherits the attached shared memory segments.
<code>exec()</code>	After an <code>exec()</code> , all attached shared memory segments are detached (not destroyed).
<code>exit()</code>	On <code>exit()</code> , all attached shared memory segments are detached (not destroyed).

RETURN VALUE

On a failure, both functions return `-1` with `errno` indicating the error; otherwise, `shmat` returns the address of the attached shared memory segment, and `shmdt` returns `0`.

ERRORS

When `shmat` fails, at return `errno` will be set to one of the following values:

<code>EACCES</code>	The calling process has no access permissions for the requested attach type.
<code>EINVAL</code>	Invalid <code>shmid</code> value, unaligned (that is, not page-aligned and <code>SHM_RND</code> was not specified) or invalid <code>shmaddr</code> value, or failing attach at <code>brk</code> .
<code>ENOMEM</code>	Could not allocate memory for the descriptor or for the page tables.

The function `shmdt` can fail only if there is no shared memory segment attached at `shmaddr`; in such a case, `errno` will be set to `EINVAL` at return.

NOTES

On executing a `fork(2)` system call, the child inherits all the attached shared memory segments.

The shared memory segments attached to a process executing an `exec(2)` system call will not be attached to the resulting process.

The following is a system parameter affecting a `shmat` system call:

<code>SHMLBA</code>	Segments low-boundary address multiple. Must be page aligned. For the current implementation, the <code>SHMLBA</code> value is <code>PAGE_SIZE</code> .

The implementation has no intrinsic limit to the per-process maximum number of shared memory segments (`SHMSEG`)

SEE ALSO

`ipc(5)`, `shmctl(2)`, `shmget(2)`

shutdown

shutdown—Shuts down part of a full-duplex connection

SYNOPSIS

```
#include <sys/socket.h>
int shutdown(int s,int how);
```

DESCRIPTION

The shutdown call causes all or part of a full-duplex connection on the socket associated with *s* to be shut down. If *how* is 0, further receives will be disallowed. If *how* is 1, further sends will be disallowed. If *how* is 2, further sends and receives will be disallowed.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and *errno* is set appropriately.

ERRORS

EBAADF	<i>s</i> is not a valid descriptor.
ENOTSOCK	<i>s</i> is a file, not a socket.
ENOTCONN	The specified socket is not connected.

HISTORY

The shutdown function call appeared in BSD 4.2.

SEE ALSO

connect(2), socket(2)

BSD Man Page, 24 July 1993

sigaction, sigprocmask, sigpending, sigsuspend

sigaction, sigprocmask, sigpending, sigsuspend—POSIX signal-handling functions.

SYNOPSIS

```
#include <signal.h>
int sigaction(int signum, const struct sigaction *act, struct sigaction *oldact);
int sigprocmask(int how, const sigset_t *set, sigset_t *oldset);
int sigpending(sigset_t *set);
int sigsuspend(const sigset_t *mask);
```

DESCRIPTION

The sigaction system call is used to change the action taken by a process on receipt of a specific signal.

signum specifies the signal and can be any valid signal except SIGKILL and SIGSTOP.

If *act* is non-null, the new action for signal signum is installed from *act*. If *oldact* is non-null, the previous action is saved in *oldact*.

The sigaction structure is defined as

```
struct sigaction {
    void (*sa_handler)(int);
    sigset_t sa_mask;
    int sa_flags;
```

```
void (*sa_restorer)(void);
}
```

`sa_handler` specifies the action to be associated with `signum` and can be `SIG_DFL` for the default action, `SIG_IGN` to ignore this signal, or a pointer to a signal-handling function.

`sa_mask` gives a mask of signals that should be blocked during execution of the signal handler. In addition, the signal that triggered the handler will be blocked unless the `SA_NOCLDSTOP` or `SA_NOMASK` flag is used.

`sa_flags` specifies a set of flags that modify the behavior of the signal-handling process. It is formed by the bitwise OR of zero or more of the following:

<code>SA_NOCLDSTOP</code>	If <code>signum</code> is <code>SIGCHLD</code> , do not receive notification when child processes stop (that is, when child processes receive one of <code>SIGSTOP</code> , <code>SIGTSTP</code> , <code>SIGTTIN</code> , or <code>SIGTTOU</code>).
<code>SA_ONESHOT</code> or <code>SA_RESETHAND</code>	Restores the signal action to the default state once the signal handler has been called. (This is the default behavior of the <code>signal(2)</code> system call.)
<code>SA_RESTART</code>	Provides behavior compatible with BSD signal semantics by making certain system calls restartable across signals.
<code>SA_NOMASK</code> or <code>SA_NODEFER</code>	Does not prevent the signal from being received from within its own signal handler.

The `sa_restorer` element is obsolete and should not be used.

The `sigprocmask` call is used to change the list of currently blocked signals. The behavior of the call is dependent on the value of `how`, as follows:

<code>SIG_BLOCK</code>	The set of blocked signals is the union of the current set and the <code>set</code> argument.
<code>SIG_UNBLOCK</code>	The signals in <code>set</code> are removed from the current set of blocked signals. It is legal to attempt to unblock a signal that is not blocked.
<code>SIG_SETMASK</code>	The set of blocked signals is set to the argument <code>set</code> .

If `oldset` is non-null, the previous value of the signal mask is stored in `oldset`.

The `sigpending` call allows the examination of pending signals (those that have been raised while blocked). The signal mask of pending signals is stored in `set`.

The `sigsuspend` call temporarily replaces the signal mask for the process with that given by `mask` and then suspends the process until a signal is received.

RETURN VALUES

`sigaction`, `sigprocmask`, `sigpending`, and `sigsuspend` return 0 on success and -1 on error.

ERRORS

<code>EINVAL</code>	An invalid signal was specified. This will also be generated if an attempt is made to change the action for <code>SIGKILL</code> or <code>SIGSTOP</code> , which cannot be caught.
<code>EFAULT</code>	<code>act</code> , <code>oldact</code> , <code>set</code> , or <code>oldset</code> points to memory that is not a valid part of the process address space.
<code>EINTR</code>	System call was interrupted.

NOTES

It is not possible to block `SIGKILL` or `SIGSTOP` with the `sigprocmask` call. Attempts to do so will be silently ignored.

Setting `SIGCHLD` to `SIG_IGN` provides automatic reaping of child processes.

The POSIX spec only defines `SA_NOCLDSTOP`. Use of other `sa` flags is non-portable.

The `SA_RESETHAND` flag is compatible with the SVR4 flag of the same name.

The SA_NODEFER flag is compatible with the SVR4 flag of the same name under kernels 1.3.9 and newer. On older kernels, the Linux implementation will allow the receipt of any signal, not just the one you are installing (effectively overriding any sa_mask settings).

The SA_RESETHAND and SA_NODEFER names for SVR4 compatibility are present only in library versions 3.0.9 and greater.

sigaction can be called with a null second argument to query the current signal handler. It can also be used to check whether a given signal is valid for the current machine by calling it with null second and third arguments.

See sigsetops(3) for details on manipulating signal sets.

CONFORMS TO

POSIX, SVR4

SEE ALSO

kill(1), kill(2), killpg(2), pause(2), raise(3), siginterrupt(3), signal(2), signal(7), sigsetops(3), sigvec(2)

Linux 1.3, 24 August 1995

signal

signal—ANSI C signal handling

SYNOPSIS

```
#include <signal.h>
void (*signal(int signum, void (*handler)(int)))(int);
```

DESCRIPTION

The signal system call installs a new signal handler for the signal with number signum. The signal handler is set to handler, which can be a user-specified function or one of the following:

SIG_IGN	Ignores the signal.
SIG_DFL	Resets the signal to its default behavior.

The integer argument that is handed over to the signal-handling routine is the signal number. This makes it possible to use one signal handler for several signals.

RETURN VALUE

signal returns the previous value of the signal handler, or SIG_ERR on error.

NOTES

Signal handlers cannot be set for SIGKILL or SIGSTOP.

Unlike on BSD systems, signals under Linux are reset to their default behavior when raised. However, if you include <bsd/signal.h> instead of <signal.h>, signal is redefined as _bsd_signal, and signal has the BSD semantics. Both versions of signal are library routines built on top of sigaction(2).

If you're confused by the prototype at the top of this man page, it may help to see it separated out like this:

```
typedef void (*sighandler_t)(int);
sighandler_t signal(int signum, sighandler_t handler);
```

According to POSIX, the behavior of a process is undefined after it ignores a SIGFPE, SIGILL, or SIGSEGV signal that was not generated by the kill() or raise() function. Integer division by 0 has undefined result. On some architectures it will generate a SIGFPE signal. Ignoring this signal might lead to an endless loop.

CONFORMS TO

ANSI C

SEE ALSO

kill(1), kill(2), killpg(2), pause(2), raise(3), sigaction(2), signal(7), sigsetops(3), sigvec(2), alarm(2)

Linux 2.0, 21 July 1996

sigblock, siggetmask, sigsetmask, sigmask

sigblock, siggetmask, sigsetmask, sigmask—Manipulate the signal mask

SYNOPSIS

```
#include <signal.h>
int sigblock(int mask);
int siggetmask(void);
int sigsetmask(int mask);
int sigmask(int signum);
```

DESCRIPTION

This interface is made obsolete by sigprocmask(2).

The sigblock system call adds the signals specified in mask to the set of signals currently being blocked from delivery.

The sigsetmask system call replaces the set of blocked signals totally with a new set specified in mask. Signals are blocked if the corresponding bit in mask is a 1.

The current set of blocked signals can be obtained using siggetmask.

The sigmask macro is provided to construct the mask for a given signum.

RETURN VALUES

siggetmask returns the current set of masked signals.

sigsetmask and sigblock return the previous set of masked signals.

NOTES

Prototypes for these functions are only available if __USE_BSD is defined before <signal.h> is included.

It is not possible to block SIGKILL or SIGSTOP—this restriction is silently imposed by the system.

HISTORY

These function calls appeared in BSD 4.3 and are deprecated.

SEE ALSO

kill(2), sigprocmask(2), signal(7)

Linux 1.3, 31 August 1995

sigpause

sigpause—Atomically releases blocked signals and waits for interrupt

SYNOPSIS

```
#include <signal.h>
int sigpause(int sigmask);
```

DESCRIPTION

This interface is made obsolete by `sigsuspend(2)`.

`sigpause` assigns `sigmask` to the set of masked signals and then waits for a signal to arrive; on return, the set of masked signals is restored.

`sigmask` is usually `0` to indicate that no signals are to be blocked. `sigpause` always terminates by being interrupted, returning `-1` with `errno` set to `EINTR`.

HISTORY

The `sigpause` function call appeared in BSD 4.3 and is deprecated.

SEE ALSO

`sigsuspend(2)`, `kill(2)`, `sigaction(2)`, `sigprocmask(2)`, `sigblock(2)`, `sigvec(2)`

Linux 1.3, 24 July 1993

sigreturn

`sigreturn`—Returns from the signal handler and cleans up the stack frame

SYNOPSIS

```
int sigreturn(unsigned long __unused);
```

DESCRIPTION

When the Linux kernel creates the stack frame for a signal handler, a call to `sigreturn` is inserted into the stack frame so that the signal handler will call `sigreturn` upon return. This inserted call to `sigreturn` cleans up the stack so that the process can restart from where it was interrupted by the signal.

RETURN VALUE

`sigreturn` never returns.

WARNING

The `sigreturn` call is used by the kernel to implement signal handlers. It should never be called directly. Better yet, the specific use of the unused argument varies depending on the architecture.

CONFORMS TO

`sigreturn` is specific to Linux.

FILES

```
/usr/src/linux/arch/i386/kernel/signal.c
/usr/src/linux/arch/alpha/kernel/entry.S
```

SEE ALSO

`kill(2)`, `signal(2)`, `signal(7)`

Linux 1.3.20, 21 August 1995

sigvec

sigvec—BSD software signal facilities

SYNOPSIS

```
#include <bsd/signal.h>
int sigvec(int sig, struct sigvec *vec, struct sigvec *ovec);
```

DESCRIPTION

This interface is made obsolete by `sigaction(2)`.

Under Linux, `sigvec` is `#defined` to `sigaction`, and provides at best a rough approximation of the BSD `sigvec` interface.

SEE ALSO

`sigaction(2)`, `signal(2)`

Linux 1.3 31 August 1995

socket

socket—Creates an endpoint for communication

SYNOPSIS

```
#include <sys/types.h>
#include <sys/socket.h>
int socket(int domain, int type, int protocol);
```

DESCRIPTION

`socket` creates an endpoint for communication and returns a descriptor.

The `domain` parameter specifies a communications domain within which communication will take place; this selects the protocol family that should be used. These families are defined in the include file `sys/socket.h`. The currently understood formats are

<code>AF_UNIX</code>	UNIX internal protocols
<code>AF_INET</code>	ARPA Internet protocols
<code>AF_ISO</code>	ISO protocols
<code>AF_NS</code>	Xerox Network Systems protocols
<code>AF_IMPLINK</code>	IMP host at IMP link layer

The `socket` has the indicated type, which specifies the semantics of communication. The currently defined types are

```
SOCK_STREAM
SOCK_DGRAM
SOCK_RAW
SOCK_SEQPACKET
SOCK_RDM
```

A `SOCK_STREAM` type provides sequenced, reliable, two-way connection-based byte streams. An out-of-band data transmission mechanism may be supported. A `SOCK_DGRAM` socket supports datagrams (connectionless, unreliable messages of a fixed, typically small, maximum length). A `SOCK_SEQPACKET` socket may provide a sequenced, reliable, two-way connection-based data transmission path for datagrams of fixed maximum length; a consumer might be required to read an entire packet with each read system call. This facility is protocol specific, and presently is implemented only for `PF_NS`. `SOCK_RAW` sockets provide

access to internal network protocols and interfaces. The types `SOCK_RAW`, which is available only to the superuser, and `SOCK_RDM`, which is planned but not yet implemented, are not described here.

The `protocol` specifies a particular protocol to be used with the socket. Normally only a single protocol exists to support a particular socket type within a given protocol family. However, it is possible that many protocols may exist, in which case a particular protocol must be specified in this manner. The protocol number to use is particular to the communication domain in which communication is to take place; see `protocols(5)`.

Sockets of type `SOCK_STREAM` are full-duplex byte streams, similar to pipes. A stream socket must be in a connected state before any data can be sent or received on it. A connection to another socket is created with a `connect(2)` call. Once connected, data may be transferred using `read(2)` and `write(2)` calls or some variant of the `send(2)` and `recv(2)` calls. When a session has been completed, a `close(2)` may be performed. Out-of-band data can also be transmitted as described in `send(2)` and received as described in `recv(2)`.

The communications protocols used to implement a `SOCK_STREAM` ensure that data is not lost or duplicated. If a piece of data for which the peer protocol has buffer space cannot be successfully transmitted within a reasonable length of time, the connection is considered broken, and calls will indicate an error with `-1` returns and with `ETIMEDOUT` as the specific code in the global variable `errno`. The protocols optionally keep sockets warm by forcing transmissions roughly every minute in the absence of other activity. An error is then indicated if no response can be elicited on an otherwise idle connection for a extended period (for example, 5 minutes). A `SIGPIPE` signal is raised if a process sends on a broken stream; this causes naive processes, which do not handle the signal, to exit.

`SOCK_SEQPACKET` sockets employ the same system calls as `SOCK_STREAM` sockets. The only difference is that `read(2)` calls will return only the amount of data requested, and any that is remaining in the arriving packet will be discarded.

`SOCK_DGRAM` and `SOCK_RAW` sockets allow the sending of datagrams to correspondents named in `send(2)` calls. Datagrams are generally received with `recvfrom(2)`, which returns the next datagram with its return address.

An `fcntl(2)` call can be used to specify a process group to receive a `SIGURG` signal when the out-of-band data arrives. It can also enable non-blocking I/O and asynchronous notification of I/O events via `SIGIO`.

The operation of sockets is controlled by socket-level options. These options are defined in the file `sys/socket.h`. `setsockopt(2)` and `getsockopt(2)` are used to set and get options, respectively.

RETURN VALUES

A `-1` is returned if an error occurs; otherwise, the return value is a descriptor referencing the socket.

ERRORS

<code>EPROTONOSUPPORT</code>	The protocol type or the specified protocol is not supported within this domain.
<code>EMFILE</code>	The per-process descriptor table is full.
<code>ENFILE</code>	The system file table is full.
<code>EACCESS</code>	Permission to create a socket of the specified type and/or protocol is denied.
<code>ENOBUFS</code>	Insufficient buffer space is available. The socket cannot be created until sufficient resources are freed.

HISTORY

The `socket` function call appeared in BSD 4.2.

SEE ALSO

`accept(2)`, `bind(2)`, `connect(2)`, `getprotoent(3)`, `getsockname(2)`, `getsockopt(2)`, `ioctl(2)`, `listen(2)`, `read(2)`, `recv(2)`, `select(2)`, `send(2)`, `shutdown(2)`, `socketpair(2)`, `write(2)`

“An Introductory 4.3 BSD Interprocess Communication Tutorial” is reprinted in UNIX Programmer’s Supplementary Documents Volume 1

“BSD Interprocess Communication Tutorial” is reprinted in UNIX Programmer’s Supplementary Documents Volume 1

socketcall

socketcall—Socket system calls

SYNOPSIS

```
int socketcall(int call, unsigned long *args);
```

DESCRIPTION

socketcall is a common kernel entry point for the socket system calls. `call` determines which socket function to invoke. `args` points to a block containing the actual arguments, which are passed through to the appropriate call.

User programs should call the appropriate functions by their usual names. Only standard library implementors and kernel hackers need to know about socketcall.

SEE ALSO

accept(2), bind(2), connect(2), getpeername(2), getsockname(2), getsockopt(2), listen(2), recv(2), recvfrom(2), send(2), sendto(2), setsockopt(2), shutdown(2), socket(2), socketpair(2)

Linux 1.2.4, 15 April 1995

socketpair

socketpair—Creates a pair of connected sockets

SYNOPSIS

```
#include <sys/types.h>
#include <sys/socket.h>
int socketpair(int d, int type, int protocol, int sv[2]);
```

DESCRIPTION

The call creates an unnamed pair of connected sockets in the specified domain `d`, of the specified `type`, and using the optionally specified `protocol`. The descriptors used in referencing the new sockets are returned in `sv[0]` and `sv[1]`. The two sockets are indistinguishable.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

EMFILE	Too many descriptors are in use by this process.
EAFNOSUPPORT	The specified address family is not supported on this machine.
EPROTONOSUPPORT	The specified protocol is not supported on this machine.
EOPNOSUPPORT	The specified protocol does not support creation of socket pairs.
EFAULT	The address <code>sv</code> does not specify a valid part of the process's address space.

HISTORY

The socketpair function call appeared in BSD 4.2.

BUGS

This call is currently implemented only for the UNIX domain.

SEE ALSO

read(2), write(2), pipe(2)

BSD Man Page, 24 July 1993

stat, fstat, lstat

stat, fstat, lstat—Get file status

SYNOPSIS

```
#include <sys/stat.h>
#include <unistd.h>
int stat(const char *file_name, struct stat *buf);
int fstat(int fildes, struct stat *buf);
int lstat(const char *file_name, struct stat *buf);
```

DESCRIPTION

These functions return information about the specified file. You do not need any access rights to the file to get this information, but you need search rights to all directories named in the path leading to the file.

stat stats the file pointed to by `file_name` and fills in `buf`.

lstat is identical to stat, except that the link itself is stated, not the file that is obtained by tracing the links.

fstat is identical to stat, except that the open file pointed to by `fildes` (as returned by `open(2)`) is stated in place of `file_name`.

They all return a stat structure, which is declared as follows:

```
struct stat
{
    dev_t      st_dev;      /* device */
    ino_t      st_ino;      /* inode */
    umode_t    st_mode;     /* protection */
    nlink_t    st_nlink;    /* number of hard links */
    uid_t      st_uid;      /* user ID of owner */
    gid_t      st_gid;      /* group ID of owner */
    dev_t      st_rdev;     /* device type (if inode device) */
    off_t      st_size;     /* total size, in bytes */
    unsigned long st_blksize; /* blocksize for filesystem I/O */
    unsigned long st_blocks; /* number of blocks allocated */
    time_t     st_atime;     /* time of last access */
    time_t     st_mtime;     /* time of last modification */
    time_t     st_ctime;     /* time of last change */
};
```

Note that `st_blocks` may not always be in terms of blocks of size `st_blksize`, and that `st_blksize` may instead provide a notion of the “preferred” block size for efficient filesystem I/O.

Not all the Linux filesystems implement all the time fields. Traditionally, `st_atime` is changed by `mknod(2)`, `utime(2)`, `read(2)`, `write(2)`, and `truncate(2)`.

Traditionally, `st_mtime` is changed by `mknod(2)`, `utime(2)`, and `write(2)`. `st_mtime` is not changed for changes in owner, group, hard link count, or mode.

Traditionally, `st_ctime` is changed by writing or by setting inode information (that is, owner, group, link count, mode, and so on).

The following macros are defined to check the file type:

<code>S_ISLNK(m)</code>	Is it a symbolic link?
<code>S_ISREG(m)</code>	Is it a regular file?
<code>S_ISDIR(m)</code>	Is it a directory?
<code>S_ISCHR(m)</code>	Is it a character device?
<code>S_ISBLK(m)</code>	Is it a block device?
<code>S_ISFIFO(m)</code>	Is it fifo?
<code>S_ISSOCK(m)</code>	Is it a socket?

The following flags are defined for the `st_mode` field:

<code>S_IFMT</code>	00170000 Bitmask for the file type bitfields
<code>S_IFSOCK</code>	0140000 Socket
<code>S_IFLNK</code>	0120000 Symbolic link
<code>S_IFREG</code>	0100000 Regular file
<code>S_IFBLK</code>	0060000 Block device
<code>S_IFDIR</code>	0040000 Directory
<code>S_IFCHR</code>	0020000 Character device
<code>S_IFIFO</code>	0010000 Fifo
<code>S_ISUID</code>	0004000 Set UID bit
<code>S_ISGID</code>	0002000 Set GID bit
<code>S_ISVTX</code>	0001000 Sticky bit
<code>S_IRWXU</code>	00700 User (file owner) has read, write, and execute permission
<code>S_IRUSR (S_IREAD)</code>	00400 User has read permission
<code>S_IWUSR (S_IWRITE)</code>	00200 User has write permission
<code>S_IXUSR (S_IEXEC)</code>	00100 User has execute permission
<code>S_IRWXG</code>	00070 Group has read, write, and execute permission
<code>S_IRGRP</code>	00040 Group has read permission
<code>S_IWGRP</code>	00020 Group has write permission
<code>S_IXGRP</code>	00010 Group has execute permission
<code>S_IRWXO</code>	00007 others have read, write, and execute permission
<code>S_IROTH</code>	00004 Others have read permission
<code>S_IWOTH</code>	00002 Others have write permission
<code>S_IXOTH</code>	00001 Others have execute permission

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

<code>EBADF</code>	<code>filedes</code> is bad.
<code>ENOENT</code>	File does not exist.

CONFORMS TO

SVID (not `lstat()`), AT&T (not `lstat()`), POSIX (not `lstat()`), X/OPEN (not `lstat()`), BSD 4.3

SEE ALSO

`chmod(2)`, `chown(2)`, `readlink(2)`, `utime(2)`

statfs, fstatfs

statfs, fstatfs—Get filesystem statistics

SYNOPSIS

```
#include <sys/vfs.h>
int statfs(const char *path, struct statfs *buf);
int fstatfs(int fd, struct statfs *buf);
```

DESCRIPTION

statfs returns information about a mounted filesystem. path is the pathname of any file within the mounted filesystem. buf is a pointer to a statfs structure defined as follows:

```
struct statfs {
    long    f_type;          /* type of filesystem (see below) */
    long    f_bsize;         /* optimal transfer block size */
    long    f_blocks;        /* total data blocks in filesystem */
    long    f_bfree;         /* free blocks in fs */
    long    f_bavail;        /* free blocks avail to non-superuser */
    long    f_files;         /* total file nodes in filesystem */
    long    f_ffree;         /* free file nodes in fs */
    fsid_t  f_fsid;          /* filesystem id */
    long    f_namelen;       /* maximum length of filenames */
    long    f_spare[6];      /* spare for later */
};
```

Filesystem types:

```
linux/ext2_fs.h:  EXT2_OLD_SUPER_MAGIC  0xEF51
linux/ext2_fs.h:  EXT2_SUPER_MAGIC      0xEF53
linux/ext_fs.h:   EXT_SUPER_MAGIC        0x137D
linux/iso_fs.h:   ISOFS_SUPER_MAGIC      0x9660
linux/minix_fs.h: MINIX_SUPER_MAGIC      0x137F /* orig. minix */
linux/minix_fs.h: MINIX_SUPER_MAGIC2     0x138F /* 30 char minix */
linux/minix_fs.h: NEW_MINIX_SUPER_MAGIC  0x2468 /* minix V2 */
linux/msdos_fs.h: MSDOS_SUPER_MAGIC      0x4d44
linux/nfs_fs.h:   NFS_SUPER_MAGIC        0x6969
linux/proc_fs.h:  PROC_SUPER_MAGIC       0x9fa0
linux/xia_fs.h:   XIAFS_SUPER_MAGIC       0x012FD16D
```

Fields that are undefined for a particular filesystem are set to -1. fstatfs returns the same information about an open file referenced by descriptor fd.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and errno is set appropriately.

ERRORS

For statfs:

ENOTDIR	A component of the path prefix of path is not a directory.
EINVAL	path contains a character with the high-order bit set.
ENAMETOOLONG	The length of a component of path exceeds 255 characters, or the length of path exceeds 1,023 characters.
ENOENT	The file referred to by path does not exist.
EACCESS	Search permission is denied for a component of the path prefix of path.
ELOOP	Too many symbolic links were encountered in translating path.

EFAULT	buf or path points to an invalid address.
EIO	An I/O error occurred while reading from or writing to the filesystem.
For fstatfs:	
EBADF	fd is not a valid open file descriptor.
EFAULT	buf points to an invalid address.
EIO	An I/O error occurred while reading from or writing to the filesystem.

SEE ALSO

stat(2)

Linux 0.99.11, 24 July 1993

stime

stime—Set time

SYNOPSIS

```
#include <time.h>
int stime(time_t *t);
```

DESCRIPTION

stime sets the system's idea of the time and date. time, pointed to by t, is measured in seconds from 00:00:00 GMT January 1, 1970. stime() may only be executed by the superuser.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and errno is set appropriately.

ERRORS

EPERM The caller is not the superuser.

CONFORMS TO

SVID, AT&T, X/OPEN

SEE ALSO

date(1)

Linux 0.99.11, 24 July 1993

swapon, swapoff

swapon, swapoff—Start/stop swapping to file/device

SYNOPSIS

```
#include <unistd.h>
#include <linux/swap.h>
int swapon(const char *path, int swapflags);
int swapoff(const char *path);
```

DESCRIPTION

`swapon` sets the swap area to the file or block device specified by `path`. `swapoff` stops swapping to the file or block device specified by `path`.

`swapon` takes a `swapflags` argument. If `swapflags` has the `SWAP_FLAG_PREFER` bit turned on, the new swap area will have a higher priority than default. The priority is encoded as `(prio << SWAP_FLAG_Prio_SHIFT) & SWAP_FLAG_Prio_MASK`. These functions may only be used by the superuser.

PRIORITY

Each swap area has a priority, either high or low. The default priority is low. Within the low-priority areas, newer areas are of even lower priority than older areas.

All priorities set with `swapflags` are high priority, higher than the default. They may have any non-negative value chosen by the caller. Higher numbers mean higher priority.

Swap pages are allocated from areas in priority order, highest priority first. For areas with different priorities, a higher-priority area is exhausted before using a lower-priority area. If two or more areas have the same priority, and that is the highest priority available, pages are allocated on a round-robin basis between them.

As of Linux 1.3.6, the kernel usually follows these rules, but there are exceptions.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

Many other errors besides the following can occur if `path` is not valid:

<code>EPERM</code>	The user is not the superuser, or more than <code>MAX_SWAPFILES</code> (defined to be 8 in Linux 1.3.6) are in use.
<code>EINVAL</code>	Returned if <code>path</code> exists, but is neither a regular path nor a block device.
<code>ENOENT</code>	Returned if <code>path</code> does not exist.
<code>ENOMEM</code>	Returned if there is insufficient memory to start swapping.

CONFORMS TO

These functions are Linux specific.

NOTES

The partition or path must be prepared with `mkswap(8)`.

HISTORY

The second (`swapflags`) argument was introduced in Linux 1.3.2.

SEE ALSO

`mkswap(8)`, `swapon(8)`, `swapoff(8)`

Linux 1.3.6, 22 July 1995

symlink

`symlink`—Makes a new name for a file

SYNOPSIS

```
#include <unistd.h>
int symlink(const char *oldpath, const char *newpath);
```

DESCRIPTION

`symlink` creates a symbolic link named `oldpath` that contains `newpath`.

Symbolic links are interpreted at runtime, as if the contents of the link were substituted into the path being followed to find a file or directory.

Symbolic links may contain `..` path components that (if used at the start of the link) refer to the parent directories of the one in which the link resides.

A symbolic link (also known as a *soft link*) can point to an existing file or to a nonexistent one; the latter case is known as a *dangling link*.

The permissions of a symbolic link are irrelevant; the ownership is ignored when following the link, but is checked when removal or renaming of the link is requested and the link is in a directory with the sticky bit set.

If `newpath` exists, it will not be overwritten.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

EPERM	The filesystem containing <code>pathname</code> does not support the creation of symbolic links.
EFAULT	<code>oldpath</code> or <code>newpath</code> points outside your accessible address space.
EACCES	Write access to the directory containing <code>newpath</code> is not allowed for the process's effective UID, or one of the directories in <code>newpath</code> did not allow search (execute) permission.
ENAMETOOLONG	<code>oldpath</code> or <code>newpath</code> was too long.
ENOENT	A directory component in <code>newpath</code> does not exist or is a dangling symbolic link, or <code>oldpath</code> is the empty string.
ENOTDIR	A component used as a directory in <code>newpath</code> is not, in fact, a directory.
ENOMEM	Insufficient kernel memory was available.
EROFS	The file is on a read-only filesystem.
EEXIST	<code>newpath</code> already exists.
ELoop	<code>newpath</code> contains a reference to a circular symbolic link—that is, a symbolic link whose expansion contains a reference to itself.
ENOSPC	The device containing the file has no room for the new directory entry.

NOTES

No checking of `oldpath` is done.

Deleting the name referred to by a `symlink` will actually delete the file (unless it also has other hard links). If this behavior is not desired, use `link`.

CONFORMS TO

SVID, AT&T, POSIX, BSD 4.3

BUGS

See `open(2)` regarding multiple files with the same name, and NFS.

SEE ALSO

link(2), unlink(2), rename(2), open(2), lstat(2), ln(1), link(8)

Linux, 24 July 1993

sync

sync—Commits buffer cache to disk

SYNOPSIS

```
#include <unistd.h>
int sync(void);
```

DESCRIPTION

sync first commits inodes to buffers, and then buffers to disk.

RETURN VALUE

sync always returns 0.

CONFORMS TO

SVID, AT&T, X/OPEN, BSD 4.3

BUGS

According to the standard specification (for example, SVID), sync() schedules the writes, but it might return before the actual writing is done. However, since version 1.3.20, Linux does actually wait. (This still does not guarantee data integrity; modern disks have large caches.)

SEE ALSO

bdflush(2), fsync(2), fdatasync(2), update(8), sync(8)

Linux 1.3.88, 15 April 1995

sysctl

sysctl—Reads/writes system parameters

SYNOPSIS

```
#include <unistd.h>
#include <linux/unistd.h>
#include <linux/sysctl.h>
_syscall1(int sysctl, struct __sysctl_args *args);
int sysctl(struct __sysctl_args *args);
```

DESCRIPTION

The sysctl call reads and/or writes kernel parameters—for example, the hostname or the maximum number of open files. The argument has the form

```
struct __sysctl_args {
    int *name; /* integer vector describing variable */
    int nlen; /* length of this vector */
    void *oldval; /* 0 or address where to store old value */
    size_t *oldlenp; /* available room for old value,
```

```

        overwritten by actual size of old value */
void *newval; /* 0 or address of new value */
size_t newlen; /* size of new value */
};

```

This call does a search in a tree structure, possibly resembling a directory tree under `/proc/sys`, and, if the requested item is found, calls some appropriate routine to read or modify the value.

EXAMPLE

```

#include <linux/unistd.h>
#include <linux/types.h>
#include <linux/sysctl.h>

_syscall1(int, _sysctl, struct __sysctl_args *, args);
int sysctl(int *name, int nlen, void *oldval, size_t *oldlenp,
          void *newval, size_t newlen)
{
    struct __sysctl_args args={name,nlen,oldval,oldlenp,newval,newlen};
    return _sysctl(&args);
}

#define SIZE(x) sizeof(x)/sizeof(x[0])
#define OSNAMESZ 100

char osname[OSNAMESZ];
int osnamelth;
int name[] = { CTL_KERN, KERN_OSTYPE };

main(){
    osnamelth = SIZE(osname);
    if (sysctl(name, SIZE(name), osname, &osnamelth, 0, 0))
        perror("sysctl");
    else
        printf("This machine is running %s\n", osnamelth, osname);
    return 0;
}

```

RETURN VALUES

Upon successful completion, `sysctl` returns 0. Otherwise, a value of -1 is returned, and `errno` is set to indicate the error.

ERRORS

ENOTDIR	name was not found.
EPERM	No search permission for one of the encountered directories, or no read permission where <code>oldval</code> was nonzero, or no write permission where <code>newval</code> was nonzero.
EFAULT	The invocation asked for the previous value by setting <code>oldval</code> non-NULL, but allowed zero room in <code>oldlenp</code> .

CONFORMS TO

This call is Linux specific.

HISTORY

A `sysctl` call has been present in Linux since version 1.3.57. It originated in BSD-4.4. Only Linux has the `/proc/sys` mirror, and the object-naming schemes differ between Linux and BSD 4.4, but the declaration of the `sysctl(2)` function is the same in both.

BUGS

Not all available objects are properly documented.

It is not yet possible to change operating system by writing to `/proc/sys/kernel/ostype`.

SEE ALSO

`proc(5)`

Linux 1.3.85, 11 April 1996

sysfs

`sysfs`—Gets filesystem type information

SYNOPSIS

```
int sysfs(int option, const char * fsname);
int sysfs(int option, unsigned int fs_index, char * buf);
int sysfs(int option);
```

DESCRIPTION

`sysfs` returns information about the filesystem types currently present in the kernel. The specific form of the `sysfs` call and the information returned depend on the option in effect. You can

- Translate the filesystem identifier string `fsname` into a filesystem type index.
- Translate the filesystem type index `fs_index` into a null-terminated filesystem identifier string. This string will be written to the buffer pointed to by `buf`. Make sure that `buf` has enough space to accept the string.
- Return the total number of filesystem types currently present in the kernel.

The numbering of the filesystem type indexes begins with 0.

RETURN VALUE

On success, `sysfs` returns the filesystem index for the first option, 0 for the second option, and the number of currently configured filesystems for the third option. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

<code>EINVAL</code>	<code>fsname</code> is not a valid filesystem type identifier; <code>fs_index</code> is out of bounds; <code>option</code> is invalid.
<code>EFAULT</code>	Either <code>fsname</code> or <code>buf</code> is outside your accessible address space.

CONFORMS TO

System V

Linux 1.3.16, 9 August 1995

sysinfo

`sysinfo`—Returns information on overall system statistics

SYNOPSIS

As of Linux 0.99.10 and image release 4.4,

```
#include <linux/kernel.h>
#include <linux/sys.h>
int sysinfo(struct sysinfo *info);
```

DESCRIPTION

`sysinfo` returns information in the following structure:

```
struct sysinfo {
    long uptime;           /* Seconds since boot */
    unsigned long loads[3]; /* 1, 5, and 15 minute load averages */
    unsigned long totalram; /* Total usable main memory size */
    unsigned long freeram;  /* Available memory size */
    unsigned long sharedram; /* Amount of shared memory */
    unsigned long bufferram; /* Memory used by buffers */
    unsigned long totalswap; /* Total swap space size */
    unsigned long freeswap;  /* swap space still available */
    unsigned short procs;    /* Number of current processes */
    char _f[22];            /* Pads structure to 64 bytes */
};
```

`sysinfo` provides a simple way of getting overall system statistics. This is more portable than reading `/dev/kmem`.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

EFAULT The pointer to `struct sysinfo` is invalid.

CONFORMS TO

This function is Linux specific.

BUGS

The Linux DLL 4.4.1 libraries do not contain a proper prototype for this function.

Linux 0.99.10, 24 July 1993

syslog

`syslog`—Reads and/or clears kernel message ring buffer; sets `console_loglevel`

SYNOPSIS

```
#include <unistd.h>
#include <linux/unistd.h>
_syscall3(int syslog, int type, char *bufp, int len);
int syslog(int type, char *bufp, int len);
```

DESCRIPTION

This is probably not the function you are interested in. Look at `syslog(3)` for the C library interface. This page only documents the bare kernel system call interface.

The `type` argument determines the action taken by `syslog`.

From `kernel/printk.c`:/*

Valid commands to `syslog` are

- 0—Close the log. Currently a NOP.
- 1—Open the log. Currently a NOP.
- 2—Read from the log.

- 3—Read up to the last 4KB of messages in the ring buffer.
- 4—Read and clear last 4KB of messages in the ring buffer.
- 5—Clear ring buffer.
- 6—Disable printk to console.
- 7—Enable printk to console.
- 8—Set level of messages printed to console.

Only function 3 is allowed to non-root processes.

THE KERNEL LOG BUFFER

The kernel has a cyclic buffer of length `LOG_BUF_LEN` (4096) in which messages given as argument to the kernel function `printk()` are stored (regardless of their loglevel).

The call `syslog (2,buf,len)` waits until this kernel log buffer is nonempty, and then reads at most `len` bytes into the buffer `buf`. It returns the number of bytes read. Bytes read from the log disappear from the log buffer; the information can only be read once. This is the function executed by the kernel when a user program reads `/proc/kmsg`.

The call `syslog (3,buf,len)` will read the last `len` bytes from the log buffer (nondestructively), but will not read more than was written into the buffer since the last “clear ring buffer” command (which does not clear the buffer at all). It returns the number of bytes read.

The call `syslog (4,buf,len)` does precisely the same, but also executes the “clear ring buffer” command.

The call `syslog (5,dummy,idummy)` only executes the “clear ring buffer” command.

THE LOGLEVEL

The kernel routine `printk()` will print a message on the console only if it has a loglevel less than the value of the variable `console_loglevel` (initially `DEFAULT_CONSOLE_LOGLEVEL` (7), but set to 10 if the kernel command line contains the word `debug`, and to 15 in case of a kernel fault—the 10 and 15 are just silly, and are equivalent to 8). This variable is set (to a value in the range 1–8) by the call `syslog (8,dummy,value)`. The call `syslog (type,dummy,idummy)` with `type` equal to 6 or 7, sets it to 1 (kernel panics only) or 7 (all except debugging messages), respectively.

Every text line in a message has its own loglevel. This level is `DEFAULT_MESSAGE_LOGLEVEL - 1` (6) unless the line starts with `<d>` where `d` is a digit in the range 1–7, in which case the level is `d`. The conventional meaning of the loglevel is defined in `<linux/kernel.h>` as follows:

```
#define KERN_EMERG    "<0>" /* system is unusable          */
#define KERN_ALERT    "<1>" /* action must be taken immediately */
#define KERN_CRIT     "<2>" /* critical conditions             */
#define KERN_ERR      "<3>" /* error conditions                */
#define KERN_WARNING  "<4>" /* warning conditions              */
#define KERN_NOTICE   "<5>" /* normal but significant condition */
#define KERN_INFO     "<6>" /* informational                   */
#define KERN_DEBUG    "<7>" /* debug-level messages            */
```

RETURN VALUE

In case of error, -1 is returned, and `errno` is set. On success, for `type` equal to 2, 3, or 4, `syslog()` returns the number of bytes read; otherwise, it returns 0.

ERRORS

EPERM	An attempt was made to change <code>console_loglevel</code> or clear the kernel message ring buffer by a process without root permissions.
EINVAL	Bad parameters.
ERESTARTSYS	System call was interrupted by a signal—nothing was read.

CONFORMS TO

This system call is Linux specific.

SEE ALSO

syslog(3)

Linux 1.2.9, 11 June 1995

termios, tcgetattr, tcsetattr, tcsendbreak, tcdrain, tcflush, tcflow, cfgetospeed, cfgetispeed, cfsetispeed, cfsetospeed, tcgetpgrp, tcsetpgrp

termios, tcgetattr, tcsetattr, tcsendbreak, tcdrain, tcflush, tcflow, cfgetospeed, cfgetispeed, cfsetispeed, cfsetospeed, tcgetpgrp, tcsetpgrp—Get and set terminal attributes, do line control, get and set baud rate, get and set terminal foreground process group ID

SYNOPSIS

```
#include <termios.h>
#include <unistd.h>
int tcgetattr ( int fd, struct termios *termios_p );
int tcsetattr ( int fd, int optional_actions, struct termios *termios_p );
int tcsendbreak ( int fd, int duration );
int tcdrain ( int fd );
int tcflush ( int fd, int queue_selector );
int tcflow ( int fd, int action );
speed_t cfgetospeed ( struct termios *termios_p );
int cfsetospeed ( struct termios *termios_p, speed_t speed );
speed_t cfgetispeed ( struct termios *termios_p );
int cfsetispeed ( struct termios *termios_p, speed_t speed );
pid_t tcgetpgrp ( int fd );
int tcsetpgrp ( int fd, pid_t pgrp );
```

DESCRIPTION

The termios functions describe a general terminal interface that is provided to control asynchronous communications ports.

Many of the functions described here have a `termios_p` argument that is a pointer to a `termios` structure. This structure contains the following members:

```
tcflag_t c_iflag; /* input modes */
tcflag_t c_oflag; /* output modes */
tcflag_t c_cflag; /* control modes */
tcflag_t c_lflag; /* local modes */
cc_t c_cc[NCCS]; /* control chars */
```

The following are the `c_iflag` flag constants:

IGNBRK	Ignore BREAK condition on input.
BRKINT	If IGNBRK is not set, generate SIGINT on BREAK condition; otherwise, read BREAK as character \0.
IGNPAR	Ignore framing errors and parity errors.
PARMRK	If IGNPAR is not set, prefix a character with a parity error or framing error with \377 \0. If neither IGNPAR nor PARMRK is set, read a character with a parity error or framing error as \0.
INPCK	Enable input parity checking.

termios, tcgetattr, tcsetattr, tcsendbreak, tcdrain, tcflush, tcflow, cfgetospeed, cfgetispeed, cfsetispeed, cfsetospeed, tcgetpgrp, tcsetpgrp

ISTRIP	Strip off the eighth bit.
INLCR	Translate NL to CR on input.
IGNCR	Ignore carriage return on input.
ICRNL	Translate carriage return to newline on input (unless IGNCR is set).
IUCLC	Map uppercase characters to lowercase on input.
IXON	Enable XON/XOFF flow control on output.
IXANY	Enable any character to restart output.
IXOFF	Enable XON/XOFF flow control on input IMAXBEL ring bell when input queue is full.

The following are the `c_oflag` flag constants:

OPOST	Enable implementation-defined output processing.
OLCUC	Map lowercase characters to uppercase on output.
ONLCR	Map NL to CR-NL on output.
OCRNL	Map CR to NL on output.
ONOCR	Don't output CR at column 0.
ONLRET	Don't output CR.
OFILL	Send fill characters for a delay rather than use a timed delay.
OFDEL	Fill character is ASCII DEL. If unset, fill character is ASCII NUL.
NLDLY	Newline delay mask. Values are NL0 and NL1.
CRDLY	Carriage-return delay mask. Values are CR0, CR1, CR2, and CR3.
TABDLY	Horizontal-tab delay mask. Values are TAB0, TAB1, TAB2, TAB3, and XTABS. A value of XTABS expands tabs to spaces (with tab stops every eight columns).
BSDLY	Backspace delay mask. Values are BS0 and BS1.
VTDLY	Vertical-tab delay mask. Values are VT0 and VT1.
FFDLY	Form-feed delay mask. Values are FF0 and FF1.

The following are the `c_cflag` flag constants:

CSIZE	Character size mask. Values are CS5, CS6, CS7, and CS8.
CSTOPB	Set two stop bits rather than one.
CREAD	Enable receiver.
PARENB	Enable parity generation on output and parity checking for input.
PARODD	Parity for input and output is odd.
HUPCL	Lower modem control lines after last process closes the device (hangs up).
CLOCAL	Ignore modem control lines.
CIBAUD	Mask for input speeds (not used).
CRTSCTS	Flow control.

The following are the `c_lflag` flag constants:

ISIG	When any of the characters INTR, QUIT, SUSP, or DSUSP are received, generate the corresponding signal.
ICANON	Enables canonical mode. This allows the special characters EOF, EOL, EOL2, ERASE, KILL, REPRINT, STATUS, and WERASE, and also buffers by lines.
XCASE	If ICANON is also set, terminal is uppercase only. Input is converted to lowercase, except for characters preceded by \. On output, uppercase characters are preceded by \, and lowercase characters are converted to uppercase.
ECHO	Echo input characters.

ECHOE	If ICANON is also set, the ERASE character erases the preceding input character, and WERASE erases the preceding word.
ECHOK	If ICANON is also set, the KILL character erases the current line.
ECHONL	If ICANON is also set, echo the NL character even if ECHO is not set.
ECHOCTL	If ECHO is also set, ASCII control signals other than TAB, NL, START, and STOP are echoed as Ctrl+X, where X is the character with ASCII code 0x10 greater than the control signal. For example, character 0x28 (BS) is echoed as Ctrl+H.
ECHOPRT	If ICANON and IECHO are also set, characters are printed as they are being erased.
ECHOKE	If ICANON is also set, KILL is echoed by erasing each character on the line, as specified by ECHOE and ECHOPRT.
FLUSHO	Output is being flushed. This flag is toggled by typing the DISCARD character.
NOFLSH	Disables flushing of the input and output queues when generating the SIGINT and SIGQUIT signals, and flushing of the input queue when generating the SIGSUSP signal.
TOSTOP	Sends the SIGTTOU signal to the process group of a background process that tries to write to its controlling terminal.
PENDIN	All characters in the input queue are reprinted when the next character is read. (bash handles typeahead this way.)
IEXTEN	Enable implementation-defined input processing.

`tcgetattr()` gets the parameters associated with the object referred to by `fd` and stores them in the `termios` structure referenced by `termios_p`. This function may be invoked from a background process; however, the terminal attributes may be subsequently changed by a foreground process.

`tcsetattr()` sets the parameters associated with the terminal (unless support is required from the underlying hardware that is not available) from the `termios` structure referred to by `termios_p`. `optional_actions` specifies when the changes take effect:

TCSANOW	The change occurs immediately.
TCSADRAIN	The change occurs after all output written to <code>fd</code> has been transmitted. This function should be used when changing parameters that affect output.
TCSAFLUSH	The change occurs after all output written to the object referred to by <code>fd</code> has been transmitted, and all input that has been received but not read will be discarded before the change is made.

`tcsendbreak()` transmits a continuous stream of zero-valued bits for a specific duration, if the terminal is using asynchronous serial data transmission. If `duration` is 0, it transmits zero-valued bits for at least 0.25 seconds, and not more than 0.5 seconds. If `duration` is not 0, it sends zero-valued bits for `duration*N` seconds, where `N` is at least 0.25, and not more than 0.5.

If the terminal is not using asynchronous serial data transmission, `tcsendbreak()` returns without taking any action.

`tcdrain()` waits until all output written to the object referred to by `fd` has been transmitted.

`tcflush()` discards data written to the object referred to by `fd` but not transmitted, or data received but not read, depending on the value of `queue_selector`:

TCIFLUSH	Flushes data received but not read.
TCOFLUSH	Flushes data written but not transmitted.
TCIOFLUSH	Flushes both data received but not read and data written but not transmitted.

`tcflow()` suspends transmission or reception of data on the object referred to by `fd`, depending on the value of `action`:

TCOOFF	Suspends output.
TCOON	Restarts suspended output.
TCIOFF	Transmits a STOP character, which stops the terminal device from transmitting data to the system.
TCION	Transmits a START character, which starts the terminal device transmitting data to the system.

The default on open of a terminal file is that neither its input nor its output is suspended.

The baud rate functions are provided for getting and setting the values of the input and output baud rates in the `termios` structure. The new values do not take effect until `tcsetattr()` is successfully called.

Setting the speed to `B0` instructs the modem to hang up. The actual bit rate corresponding to `B38400` may be altered with `setserial(8)`.

The input and output baud rates are stored in the `termios` structure.

`cfgetospeed()` returns the output baud rate stored in the `termios` structure pointed to by `termios_p`.

`cfsetospeed()` sets the output baud rate stored in the `termios` structure pointed to by `termios_p` to `speed`, which must be one of these constants:

`B0`
`B50`
`B75`
`B110`
`B134`
`B150`
`B200`
`B300`
`B600`
`B1200`
`B1800`
`B2400`
`B4800`
`B9600`
`B19200`
`B38400`
`B57600`
`B115200`
`B230400`

The zero baud rate, `B0`, is used to terminate the connection. If `B0` is specified, the modem control lines will no longer be asserted. Normally, this will disconnect the line. `CBAUDEx` is a mask for the speeds beyond those defined in POSIX.1 (57600 and later). Thus, `B57600 & CBAUDEx` is nonzero.

`cfgetispeed()` returns the input baud rate stored in the `termios` structure.

`cfsetispeed()` sets the input baud rate stored in the `termios` structure to `speed`. If the input baud rate is set to `0`, it will be equal to the output baud rate.

`tcgetpgrp()` returns the process group ID of the foreground processing group, or `-1` on error.

`tcsetpgrp()` sets the process group ID to `pgrp_id`. `pgrp_id` must be the ID of a process group in the same session.

RETURN VALUES

`cfgetispeed()` returns the input baud rate stored in the `termios` structure.

`cfgetospeed()` returns the output baud rate stored in the `termios` structure.

`tcgetpgrp()` returns the process group ID of foreground processing group, or `-1` on error.

All other functions return

0 On success.
 -1 on failure (and set `errno` to indicate the error).

SEE ALSO

`setserial(8)`

Linux, 25 February 1995

time

`time`—Gets time in seconds

SYNOPSIS

```
#include <time.h>
time_t time(time_t *t);
```

DESCRIPTION

`time` returns the time since 00:00:00 GMT, January 1, 1970, measured in seconds.

If `t` is non null, the return value is also stored in the memory pointed to by `t`.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

(Under BSD 4.3, this call is made obsolete by `gettimeofday(2)`.)

SEE ALSO

`ctime(3)`, `date(1)`, `ftime(3)`, `gettimeofday(2)`

Linux, 24 July 1993

times

`times`—Gets process times

SYNOPSIS

```
#include <sys/times.h>
clock_t times(struct tms *buf);
```

DESCRIPTION

`times` stores the current process times in `buf`.

`struct tms` is as defined in `/usr/include/sys/times.h`:

```
struct tms {
    time_t tms_utime; /* user time */
    time_t tms_stime; /* system time */
    time_t tms_cutime; /* user time of children */
    time_t tms_cstime; /* system time of children */
};
```

`times` returns the number of clock ticks that have elapsed since the system has been up.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

SEE ALSO

time(1), getrusage(2), wait(2)

Linux 0.99.11, 24 July 1993

truncate, ftruncate

truncate, ftruncate—Truncate a file to a specified length

SYNOPSIS

```
#include <unistd.h>
int truncate(const char *path, size_t length);
int ftruncate(int fd, size_t length);
```

DESCRIPTION

truncate causes the file named by path or referenced by fd to be truncated to at most length bytes in size. If the file previously was larger than this size, the extra data is lost. With ftruncate, the file must be open for writing.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and errno is set appropriately.

ERRORS

The errors for truncate are

ENOTDIR	A component of the path prefix is not a directory.
EINVAL	The pathname contains a character with the high-order bit set.
ENAMETOOLONG	A component of a pathname exceeded 255 characters, or an entire pathname exceeded 1,023 characters.
ENOENT	The named file does not exist.
EACCES	Search permission is denied for a component of the path prefix.
EACCES	The named file is not writeable by the user.
ELOOP	Too many symbolic links were encountered in translating the pathname.
EISDIR	The named file is a directory.
EROFS	The named file resides on a read-only filesystem.
ETXTBSY	The file is a pure procedure (shared text) file that is being executed.
EIO	An I/O error occurred updating the inode.
EFAULT	path points outside the process's allocated address space.

The errors for ftruncate are

EBADF	fd is not a valid descriptor.
EINVAL	fd references a socket, not a file.
EINVAL	fd is not open for writing.

HISTORY

These function calls appeared in BSD 4.2.

BUGS

These calls should be generalized to allow ranges of bytes in a file to be discarded.

SEE ALSO

`open(2)`

BSD Man Page, 24 July 1993

umask

`umask`—Sets a file-creation mask

SYNOPSIS

```
#include <sys/stat.h>
int umask(int mask);
```

DESCRIPTION

`umask` sets the umask to `mask & 0777`.

RETURN VALUE

The previous value of the mask is returned.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

SEE ALSO

`creat(2)`, `open(2)`

Linux 24 July 93

uname

`uname`—Gets name and information about the current kernel

SYNOPSIS

```
#include <sys/utsname.h>
int uname(struct utsname *buf);
```

DESCRIPTION

`uname` returns system information in `buf`. The `utsname` struct is as defined in `/usr/include/sys/utsname.h`:

```
struct utsname {
    char sysname[65];
    char nodename[65];
    char release[65];
    char version[65];
    char machine[65];
    char domainname[65];
};
```

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

EFAULT buf is not valid.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN

SEE ALSO

uname(1), getdomainname(2), gethostname(2)

Linux 0.99.11 24 July 93

none

none—Undocumented system calls

SYNOPSIS

Undocumented system calls.

DESCRIPTION

As of Linux 1.3.88, there are 163 system calls listed in `/usr/include/asm/unistd.h`. This man page mentions those calls that are implemented in the kernel but not yet documented in man pages. Some of these calls do not yet have prototypes in the libc include files.

SOLICITATION

If you have information about these system calls, please look in the kernel source code, write a man page (using a style similar to that of the other Linux section 2 man pages), and send it to `aeb@cw1.n1` for inclusion in the next man page release from the Linux Documentation Project.

STATUS

Undocumented are `msync`, `readv`, `writev`, `getsid`, `fdatasync`, `sysctl`, `sched_setparam`, `sched_getparam`, `sched_setscheduler`, `sched_getscheduler`, `sched_yield`, `sched_get_priority_max`, `sched_get_priority_min`, `sched_rr_get_interval`.

SEE ALSO

`obsolete(2)`, `unimplemented(2)`

Linux 1.3.86 12 April 1996

afs_syscall, break, gtty, lock, mpx, prof, quotactl, stty, ustat

`afs_syscall`, `break`, `gtty`, `lock`, `mpx`, `prof`, `quotactl`, `stty`, `ustat`—Unimplemented system calls

SYNOPSIS

Unimplemented system calls.

DESCRIPTION

These system calls are not implemented in the Linux 1.2.4 kernel.

RETURN VALUE

These system calls always return `-1` and set `errno` to `ENOSYS`.

SEE ALSO

`obsolete(2)`, `undocumented(2)`

Linux 1.2.4, 15 April 1995

unlink

`unlink`—Deletes a name and possibly the file it refers to

SYNOPSIS

```
#include <unistd.h>
int unlink(const char *pathname);
```

DESCRIPTION

`unlink` deletes a name from the filesystem. If that name was the last link to a file and no processes have the file open, the file is deleted, and the space it was using is made available for reuse.

If the name was the last link to a file but any processes still have the file open, the file will remain in existence until the last file descriptor referring to it is closed.

If the name referred to a symbolic link, the link is removed.

If the name referred to a socket, fifo, or device, the name for it is removed but processes that have the object open can continue to use it.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

EFAULT	<code>pathname</code> points outside your accessible address space.
EACCES	Write access to the directory containing <code>pathname</code> is not allowed for the process's effective UID, or one of the directories in <code>pathname</code> did not allow search (execute) permission.
EPERM	The directory containing <code>pathname</code> has the sticky bit (<code>S_ISVTX</code>) set, and the process's effective UID is neither the UID of the file to be deleted nor that of the directory containing it, or <code>pathname</code> is a directory.
ENAMETOOLONG	<code>pathname</code> was too long.
ENOENT	A directory component in <code>pathname</code> does not exist or is a dangling symbolic link.
ENOTDIR	A component used as a directory in <code>pathname</code> is not, in fact, a directory.
EISDIR	<code>pathname</code> refers to a directory.
ENOMEM	Insufficient kernel memory was available.
EROFS	<code>pathname</code> refers to a file on a read-only filesystem.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

BUGS

Unfelicities in the protocol underlying NFS can cause the unexpected disappearance of files that are still being used.

SEE ALSO

`link(2)`, `rename(2)`, `open(2)`, `rmdir(2)`, `mknod(2)`, `mkfifo(3)`, `remove(3)`, `rm(1)`, `unlink(8)`.

Linux, 24 July 1993

uselib

uselib—Selects shared library

SYNOPSIS

```
#include <unistd.h>
int uselib(const char *library);
```

DESCRIPTION

uselib selects the shared library binary that will be used by this process.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

In addition to all the error codes returned by `open(2)` and `mmap(2)`, the following may also be returned:

ENOEXEC	The file specified by <code>library</code> is not executable, or does not have the correct magic numbers.
EACCES	The library specified by <code>library</code> is not readable.

CONFORMS TO

uselib() is Linux specific.

SEE ALSO

`open(2)`, `mmap(2)`, `ldd(1)`, `gcc(1)`, `ar(1)`, `ld(1)`

Linux 0.99.11, 24 July 1993

ustat

ustat—Gets filesystem statistics

SYNOPSIS

```
#include <sys/types.h>
int ustat(dev_t dev, struct ustat * ubuf);
```

DESCRIPTION

ustat returns information about a mounted filesystem. `dev` is a device number identifying a device containing a mounted filesystem. `ubuf` is a pointer to a `ustat` structure that contains the following members:

```
daddr_t f_tfree; /* Total free blocks */
ino_t f_tinode; /* Number of free inodes */
char f_fname[6]; /* Filsys name */
char f_fpack[6]; /* Filsys pack name */
```

The last two fields, `f_fname` and `f_fpack`, are not implemented and will always be filled with null characters.

RETURN VALUE

On success, 0 is returned, and the `ustat` structure pointed to by `ubuf` will be filled in. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

EINVAL	<code>dev</code> does not refer to a device containing a mounted filesystem.
EFAULT	<code>ubuf</code> points outside of your accessible address space.
ENOSYS	The mounted filesystem referenced by <code>dev</code> does not support this operation, or any version of Linux before 1.3.16.

NOTES

`ustat` has been provided for compatibility only. All new programs should use `statfs(2)` instead.

HISTORY

`ustat` was first implemented in Linux 1.3.16. All versions of Linux before 1.3.16 will return `ENOSYS`.

CONFORMS TO

System V

SEE ALSO

`statfs(2)`, `stat(2)`

Linux 1.3.16, 9 August 1995

utime, utimes

`utime`, `utimes`—Change access and/or modification times of an inode

SYNOPSIS

```
#include <sys/types.h>
#include <utime.h>
int utime(const char *filename, struct utimbuf *buf);
#include <sys/time.h>
int utimes(char *filename, struct timeval *tvp);
```

DESCRIPTION

`utime` changes the access and modification times of the inode specified by `filename` to the `actime` and `modtime` fields of `buf`, respectively. If `buf` is `NULL`, the access and modification times of the file are set to the current time. The `utimbuf` structure is

```
struct utimbuf {
    time_t actime; /* access time */
    time_t modtime; /* modification time */
};
```

In the Linux DLL 4.4.1 libraries, `utimes` is just a wrapper for `utime`, `tvp[0].tv_sec` is `actime`, and `tvp[1].tv_sec` is `modtime`. The `timeval` structure is

```
struct timeval {
    long tv_sec; /* seconds */
    long tv_usec; /* microseconds */
};
```

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

Other errors may occur.

EACCESS	Permission to write the file is denied.
ENOENT	<code>filename</code> does not exist.

CONFORMS TO

utime: SVID, POSIX
 utimes: BSD4.3

SEE ALSO

`stat(2)`

Linux, 10 June 1995

vhangup

`vhangup`—Virtually hangs up the current tty

SYNOPSIS

```
#include <unistd.h>
int vhangup(void);
```

DESCRIPTION

`vhangup` simulates a hangup on the current terminal. This call arranges for other users to have a clean tty at login time.

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

EPERM	The user is not the superuser.

SEE ALSO

`init(8)`

Linux 0.99.11, 24 July 1993

vm86

`vm86`—Enters virtual 8086 mode

SYNOPSIS

```
#include <sys/vm86.h>
int vm86(struct vm86_struct * info);
```

DESCRIPTION

Enter VM86 mode with information as specified in `info`:

```
struct vm86_struct {
    struct vm86_regs regs;
    unsigned long flags;
```

```

        unsigned long screen_bitmap;
    };

    struct vm86_regs {
    /*
     * normal regs, with special meaning for the segment descriptors..
     */
        long ebx;
        long ecx;
        long edx;
        long esi;
        long edi;
        long ebp;
        long eax;
        long __null_ds;
        long __null_es;
        long __null_fs;
        long __null_gs;
        long orig_eax;
        long eip;
        long cs;
        long eflags;
        long esp;
        long ss;

    /*
     * these are specific to v86 mode:
     */
        long es;
        long ds;
        long fs;
        long gs;
    };

    these are specific to v86 mode:

    /
    long es;
    long ds;
    long fs;
    long gs;
    };

```

RETURN VALUE

On success, 0 is returned. On error, -1 is returned, and `errno` is set appropriately.

ERRORS

`EPERM` Saved kernel stack exists.

Linux 0.99.11, 24 July 1993

wait, waitpid

`wait, waitpid`—Wait for process termination

SYNOPSIS

```

#include <sys/types.h>
#include <sys/wait.h>

```

```
pid_t wait(int *status)
pid_t waitpid(pid_t pid, int *status, int options);
```

DESCRIPTION

The `wait` function suspends execution of the current process until a child has exited, or until a signal is delivered whose action is to terminate the current process or to call a signal-handling function. If a child has already exited by the time of the call (a so-called *zombie* process), the function returns immediately. Any system resources used by the child are freed.

The `waitpid` function suspends execution of the current process until a child as specified by the `pid` argument has exited, or until a signal is delivered whose action is to terminate the current process or to call a signal-handling function. Just as with `wait`, if a child requested by `pid` has already exited by the time of the call, the function returns immediately. Any system resources used by the child are freed.

The value of `pid` can be one of the following:

< -1	Wait for any child process whose process group ID is equal to the absolute value of <code>pid</code> .
-1	Wait for any child process; this is the same behavior that <code>wait</code> exhibits.
0	Wait for any child process whose process group ID is equal to that of the calling process.
> 0	Wait for the child whose process ID is equal to the value of <code>pid</code> .

The value of `options` is an OR of zero or more of the following constants:

WNOHANG	Return immediately if no child has exited.
WUNTRACED	Also return for children that are stopped and whose status has not been reported.

If `status` is not NULL, `wait` or `waitpid` stores status information in the location pointed to by `statloc`.

This status can be evaluated with the following macros (these macros take the `stat` buffer as an argument—not a pointer to the buffer!):

WIFEXITED(<code>status</code>)	Is nonzero if the child exited normally.
WEXITSTATUS(<code>status</code>)	Evaluates to the least significant eight bits of the return code of the child that terminated, which may have been set as the argument to a call to <code>exit()</code> or as the argument for a return statement in the main program. This macro can only be evaluated if <code>WIFEXITED</code> returned nonzero.
WIFSIGNALED(<code>status</code>)	Returns true if the child process exited because of a signal that was not caught.
WTERMSIG(<code>status</code>)	Returns the number of the signal that caused the child process to terminate. This macro can only be evaluated if <code>WIFSIGNALED</code> returned nonzero.
WIFSTOPPED(<code>status</code>)	Returns true if the child process that caused the return is currently stopped; this is only possible if the call was done using <code>WUNTRACED</code> .
WSTOPSIG(<code>status</code>)	Returns the number of the signal that caused the child to stop. This macro can only be evaluated if <code>WIFSTOPPED</code> returned nonzero.

RETURN VALUE

The process ID of the child that exited returns -1 on error or 0 if `WNOHANG` was used and no child was available (in which case `errno` is set to an appropriate value).

ERRORS

ECHILD	If the child process specified in <code>pid</code> does not exist.
EPERM	If the effective user ID of the calling process does not match that of the process being waited for, and the effective user ID of the calling process is not that of the superuser.
ERESTARTSYS	If <code>WNOHANG</code> was not set and an unblocked signal or a <code>SIGCHLD</code> was caught; this is an extension to the POSIX.1 standard.

CONFORMS TO

POSIX.1

SEE ALSO

signal(2), wait4(2), signal(7)

Linux, 24 July 1993

wait3, wait4

wait3, wait4—Wait for process termination, BSD style

SYNOPSIS

```
#define _USE_BSD
#include <sys/types.h>
#include <sys/resource.h>
#include <sys/wait.h>
pid_t wait3(int *status,int options,
struct rusage *rusage);
pid_t wait4(pid_t pid,int*status,int options,
struct rusage *rusage);
```

DESCRIPTION

The `wait3` function suspends execution of the current process until a child has exited, or until a signal is delivered whose action is to terminate the current process or to call a signal-handling function. If a child has already exited by the time of the call (a zombie process), the function returns immediately. Any system resources used by the child are freed.

The `wait4` function suspends execution of the current process until a child as specified by the `pid` argument has exited, or until a signal is delivered whose action is to terminate the current process or to call a signal-handling function. If a child as requested by `pid` has already exited by the time of the call (a zombie process), the function returns immediately. Any system resources used by the child are freed.

The value of `pid` can be one of the following:

< -1	Wait for any child process whose process group ID is equal to the absolute value of <code>pid</code> .
-1	Wait for any child process; this is equivalent to calling <code>wait3</code> .
0	Wait for any child process whose process group ID is equal to that of the calling process.
> 0	Wait for the child whose process ID is equal to the value of <code>pid</code> .

The value of `options` is an exclusive OR of zero or more of the following constants:

WNOHANG	Return immediately if no child is there to be waited for.
WUNTRACED	Also return for children that are stopped and whose status has not been reported.

If `status` is not NULL, `wait3` and `wait4` store status information in the location pointed to by `statloc`.

This status can be evaluated with the following macros:

WIFEXITED(*status)	Is nonzero if the child exited normally.
WEXITSTATUS(*status)	Evaluates to the least significant eight bits of the return code of the child that terminated, which may have been set as the argument to a call to <code>exit</code> or as the argument for a <code>return</code> statement in the main program. This macro can only be evaluated if <code>WIFEXITED</code> returned nonzero.
WIFSIGNALED(*status)	Returns true if the child process exited because of a signal that was not caught.
WTERMSIG(*status)	Returns the number of the signal that caused the child process to terminate. This macro can only be evaluated if <code>WIFSIGNALED</code> returned nonzero.

WIFSTOPPED(*status)	Returns true if the child process that caused the return is currently stopped; this is only possible if the call was done using WUNTRACED.
WSTOPSIG(*status)	Returns the number of the signal that caused the child to stop. This macro can only be evaluated if WIFSTOPPED returned nonzero. If <i>rusage</i> is not NULL, the struct <i>rusage</i> as defined in <code><sys/resource.h></code> it points to will be filled with accounting information. See <code>getrusage(2)</code> for details.

RETURN VALUE

These calls return the process ID of the child that exited, -1 on error, or 0 if WNOHANG was used and no child was available (in which case *errno* will be set appropriately).

ERRORS

ECHILD	If the child process specified in <i>pid</i> does not exist.
EPERM	If the effective user ID of the calling process does not match that of the process being waited for, and the effective user ID of the calling process is not that of the superuser.
ERESTARTSYS	If WNOHANG was not set and an unblocked signal or a SIGCHLD was caught; this is an extension to the POSIX.1 standard.

CONFORMS TO

POSIX.1

SEE ALSO

`signal(2)`, `getrusage(2)`, `wait(2)`, `signal(7)`

Linux, 24 July 1993

write

write—Writes to a file descriptor

SYNOPSIS

```
#include <unistd.h>
ssize_t write(int fd, const void *buf, size_t count);
```

DESCRIPTION

write writes up to *count* bytes to the file referenced by the file descriptor *fd* from the buffer starting at *buf*. POSIX requires that a `read()` that can be proved to occur after a `write()` returned returns the new data. Note that not all filesystems are POSIX conforming.

RETURN VALUE

On success, the number of bytes written is returned (0 indicates nothing was written). On error, -1 is returned, and *errno* is set appropriately. If *count* is 0 and the file descriptor refers to a regular file, 0 will be returned without causing any other effect. For a special file, the results are not portable.

ERRORS

EBADF	<i>fd</i> is not a valid file descriptor or is not open for writing.
EINVAL	<i>fd</i> is attached to an object that is unsuitable for writing.
EFAULT	<i>buf</i> is outside your accessible address space.

EPIPE	<code>fd</code> is connected to a pipe or socket whose reading end is closed. When this happens, the writing process will receive a SIGPIPE signal; if it catches, blocks, or ignores this, the error EPIPE is returned.
EAGAIN	Non-blocking I/O has been selected using <code>O_NONBLOCK</code> , and there was no room in the pipe or socket connected to <code>fd</code> to write the data immediately.
EINTR	The call was interrupted by a signal before any data was written.
ENOSPC	The device containing the file referred to by <code>fd</code> has no room for the data.

Other errors may occur, depending on the object connected to `fd`.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

SEE ALSO

`open(2)`, `read(2)`, `fcntl(2)`, `close(2)`, `lseek(2)`, `select(2)`, `ioctl(2)`, `fsync(2)`, `fwrite(3)`

Linux, 13 January 1996

Part III:

Library Functions

Intro

DESCRIPTION

This chapter describes all the library functions, excluding the library functions described in Part 2, which implement system calls. The various function groups are identified by a letter that is appended to the chapter number:

- (3C) These functions—the functions from Chapter 2 and from Chapter 3S—are contained in the C standard library `libc`, which will be used by `cc(1)` by default.
- (3S) These functions are parts of the `stdio(3S)` library. They are contained in the standard C library `libc`.
- (3M) These functions are contained in the arithmetic library `libm`. They are used by the `f77(1)` FORTRAN compiler by default, but not by the `cc(1)` C compiler, which needs the option `-lm`.
- (3F) These functions are part of the FORTRAN library `libF77`. There are no special compiler flags needed to use these functions.
- (3X) Various special libraries. The manual pages documenting their functions specify the library names.

AUTHORS

Look at the header of the manual page for the author(s) and copyright conditions. Note that these can be different from page to page!

Linux, 13 December 1995

abort

abort—Causes abnormal program termination

SYNOPSIS

```
#include <stdlib.h>
void abort(void);
```

DESCRIPTION

The `abort()` function causes abnormal program termination unless the signal `SIGABORT` is caught and the signal handler does not return. If the `abort()` function causes program termination, all open streams are closed and flushed.

If the `SIGABORT` function is blocked or ignored, the `abort()` function will still override it.

RETURN VALUE

The `abort()` function never returns.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`sigaction(2)`, `exit(3)`

GNU, 12 April 1993

abs

abs—Computes the absolute value of an integer

SYNOPSIS

```
#include <stdlib.h>
int abs(int j);
```

DESCRIPTION

The `abs()` function computes the absolute value of the integer argument `j`.

RETURN VALUE

Returns the absolute value of the integer argument.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

NOTES

Trying to take the absolute value of the most negative integer is not defined.

SEE ALSO

`ceil(3)`, `floor(3)`, `fabs(3)`, `labs(3)`, `rint(3)`

GNU, 6 June 1993

acos

`acos`—Arc cosine function

SYNOPSIS

```
#include <math.h>
double acos(double x);
```

DESCRIPTION

The `acos()` function calculates the arc cosine of `x`; that is the value whose cosine is `x`. If `x` falls outside the range -1 to 1 , `acos()` fails and `errno` is set.

RETURN VALUE

The `acos()` function returns the arc cosine in radians; the value is mathematically defined to be between 0 and π (inclusive).

ERRORS

EDOM `x` is out of range.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`asin(3)`, `atan(3)`, `atan2(3)`, `cos(3)`, `sin(3)`, `tan(3)`

8 June 1993

acosh

`acosh`—Inverse hyperbolic cosine function

SYNOPSIS

```
#include <math.h>
double acosh(double x);
```

DESCRIPTION

The `acosh()` function calculates the inverse hyperbolic cosine of `x`; that is the value whose hyperbolic cosine is `x`. If `x` is less than 1.0, `acosh()` returns not-a-number (NaN), and `errno` is set.

ERRORS

EDOM `x` is out of range.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`asinh(3)`, `atanh(3)`, `cosh(3)`, `sinh(3)`, `tanh(3)`

13 June 1993

alloca

`alloca`—Memory allocator

SYNOPSIS

```
#include <stdlib.h>
void *alloca( size_t size);
```

DESCRIPTION

The `alloca` function allocates `size` bytes of space in the stack frame of the caller. This temporary space is automatically freed on return.

RETURN VALUES

The `alloca` function returns a pointer to the beginning of the allocated space. If the allocation fails, a NULL pointer is returned.

CONFORMS TO

There is evidence that the `alloca` function appeared in 32v, pwb, pwb.2, 3bsd, and 4bsd. There is a man page for it in BSD 4.3. Linux uses the GNU version.

BUGS

The `alloca` function is machine dependent.

SEE ALSO

`brk(2)`, `pagesize(2)`, `calloc(3)`, `malloc(3)`, `realloc(3)`

GNU, 29 November 1993

asin

`asin`—Arc sine function

SYNOPSIS

```
#include <math.h>
double asin(double x);
```

DESCRIPTION

The `asin()` function calculates the arc sine of x , which is the value whose sine is x . If x falls outside the range -1 to 1 , `asin()` fails and `errno` is set.

RETURN VALUE

The `asin()` function returns the arc sine in radians, and the value is mathematically defined to be between $-\pi/2$ and $\pi/2$ (inclusive).

ERRORS

EDOM x is out of range.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`acos(3)`, `atan(3)`, `atan2(3)`, `cos(3)`, `sin(3)`, `tan(3)`

8 June 1993

asinh

`asinh`—Inverse hyperbolic sine function

SYNOPSIS

```
#include <math.h>
double asinh(double x);
```

DESCRIPTION

The `asinh()` function calculates the inverse hyperbolic sine of x —that is, the value whose hyperbolic sine is x .

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`acosh(3)`, `atanh(3)`, `cosh(3)`, `sinh(3)`, `tanh(3)`

13 June 1993

assert

`assert`—Abort the program if assertion is false

SYNOPSIS

```
#include <assert.h>
void assert (int expression);
```

DESCRIPTION

`assert()` prints an error message to standard output and terminates the program by calling `abort()` if `expression` is false (that is, evaluates to 0). This only happens when the macro `NDEBUG` is undefined.

RETURN VALUE

No value is returned.

CONFORMS TO

ISO9899 (ANSI C)

BUGS

`assert()` is implemented as a macro; if the expression tested has side effects, program behavior will be different depending on whether `NDEBUG` is defined. This may create Heisenbugs, which go away when debugging is turned on.

SEE ALSO

`exit(3)`, `abort(3)`

GNU, 4 April 1993

atan

`atan`—Arc tangent function

SYNOPSIS

```
#include <math.h>
double atan(double x);
```

DESCRIPTION

The `atan()` function calculates the arc tangent of `x`—that is, the value whose tangent is `x`.

RETURN VALUE

The `atan()` function returns the arc tangent in radians, and the value is mathematically defined to be between $-\pi/2$ and $\pi/2$ (inclusive).

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`acos(3)`, `asin(3)`, `atan2(3)`, `cos(3)`, `sin(3)`, `tan(3)`

8 June 1993

atan2

`atan2`—Arc tangent function of two variables

SYNOPSIS

```
#include <math.h>
double atan2(double y, double x);
```

DESCRIPTION

The `atan2()` function calculates the arc tangent of the two variables, `x` and `y`. It is similar to calculating the arc tangent of `y/x`, except that the sines of both arguments are used to determine the quadrant of the result.

RETURN VALUE

The `atan2()` function returns the result in radians, which is between $-\pi$ and π (inclusive).

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`acos(3)`, `asin(3)`, `atan(3)`, `cos(3)`, `sin(3)`, `tan(3)`

8 June 1993

atanh

`atanh`—Inverse hyperbolic tangent function

SYNOPSIS

```
#include <math.h>
double atanh(double x);
```

DESCRIPTION

The `atanh()` function calculates the inverse hyperbolic tangent of `x`; that is the value whose hyperbolic tangent is `x`. If the absolute value of `x` is greater than 1.0, `acosh()` returns not-a-number (NaN), and `errno` is set.

ERRORS

EDOM `x` is out of range.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`asinh(3)`, `acosh(3)`, `cosh(3)`, `sinh(3)`, `tanh(3)`

13 June 1993

atexit

`atexit`—Register a function to be called at normal program termination

SYNOPSIS

```
#include <stdlib.h>
int atexit(void *function)(void);
```

DESCRIPTION

The `atexit()` function registers the given function to be called at normal program termination, whether via `exit(2)` or via return from the program's main. Functions so registered are called in the reverse order of their registration; no arguments are passed.

RETURN VALUE

The `atexit()` function returns the value 0 if successful; otherwise, the value -1 is returned, and the global variable `errno` is set to indicate the error.

ERRORS

ENOMEM Insufficient memory available to add the function.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

SEE ALSO

`exit(3)`, on `exit(3)`

GNU, 29 March 1993

atof

atof—Convert a string to a double

SYNOPSIS

```
#include <stdlib.h>
double atof(const char *nptr);
```

DESCRIPTION

The `atof()` function converts the initial portion of the string pointed to by `nptr` to double. The behavior is the same as `strtod(nptr, (char **)NULL)`;

except that `atof()` does not detect errors.

RETURN VALUE

The converted value.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`atoi(3)`, `atol(3)`, `strtod(3)`, `strtol(3)`, `strtoul(3)`

GNU, 29 March 1993

atoi

atoi—Convert a string to an integer

SYNOPSIS

```
#include <stdlib.h>
int atoi(const char *nptr);
```

DESCRIPTION

The `atoi()` function converts the initial portion of the string pointed to by `nptr` to `int`. The behavior is the same as `strtol(nptr, (char **)NULL, 10)`; except that `atoi()` does not detect errors.

RETURN VALUE

The converted value.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`atof(3)`, `atol(3)`, `strtod(3)`, `strtol(3)`, `strtoul(3)`

GNU, 29 March 1993

atol

`atol`—Convert a string to a long integer

SYNOPSIS

```
#include <stdlib.h>
long atol(const char *nptr);
```

DESCRIPTION

The `atol()` function converts the initial portion of the string pointed to by `nptr` to `long`. The behavior is the same as `strtol(nptr, (char **)NULL, 10)`; except that `atol()` does not detect errors.

RETURN VALUE

The converted value.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`atof(3)`, `atoi(3)`, `strtod(3)`, `strtol(3)`, `strtoul(3)`

GNU, 29 March 1993

bcmp

`bcmp`—Compare byte strings

SYNOPSIS

```
#include <string.h>
int bcmp(const void *s1, const void *s2, int n);
```

DESCRIPTION

The `bcmp()` function compares the first `n` bytes of the strings `s1` and `s2`. If the two strings are equal, `bcmp()` returns 0; otherwise, it returns a nonzero result. If `n` is 0, the two strings are assumed to be equal.

RETURN VALUE

The `bcmp()` function returns 0 if the strings are equal; otherwise, a nonzero result is returned.

CONFORMS TO

4.3BSD. This function is deprecated—use `memcmp` in new programs.

SEE ALSO

`memcmp(3)`, `strcasemp(3)`, `strcmp(3)`, `strcoll(3)`, `strncmp(3)`, `strncasemp(3)`

GNU, 9 April 1993

bcopy

`bcopy`—Copy byte strings

SYNOPSIS

```
#include <string.h>
void bcopy (const void *src, void*dest, int n);
```

DESCRIPTION

The `bcopy()` function copies the first `n` bytes of the source string `src` to the destination string `dest`. If `n` is 0, no bytes are copied.

RETURN VALUE

The `bcopy()` function returns no value.

CONFORMS TO

4.3BSD. This function is deprecated—use `memcpy` in new programs.

SEE ALSO

`memcpy(3)`, `memcopy(3)`, `memmove(3)`, `strcpy(3)`, `strncpy(3)`

GNU, 9 April 1993

bsearch

`bsearch`—Binary search of a sorted array.

SYNOPSIS

```
#include <stdlib.h>
void *bsearch(const void *key, const void *base, size_t nmemb,
size_t size, int(*compar)(const void *, const void *));
```

DESCRIPTION

The `bsearch()` function searches an array of `nmemb` objects, the initial member of which is pointed to by `base`, for a member that matches the object pointed to by `key`. The size of each member of the array is specified by `size`.

The contents of the array should be in ascending sorted order according to the comparison function referenced by `compar`.

The `compar` routine is expected to have two arguments that point to the key object and to an array member, in that order, and should return an integer less than, equal to, or greater than 0, respectively, if the key object is found to be less than, match, or be greater than the array member.

RETURN VALUE

The `bsearch()` function returns a pointer to a matching member of the array, or `NULL` if no match is found. If there are multiple elements that match the key, the element returned is unspecified.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

SEE ALSO

`qsort(3)`

GNU, 29 March 1993

bcmp, bcopy, bzero, memccpy, memchr, memcmp, memcpy, memfrob, memmem, memmove, memset

`bcmp`, `bcopy`, `bzero`, `memccpy`, `memchr`, `memcmp`, `memcpy`, `memfrob`, `memmem`, `memmove`, `memset`—Byte string operations

SYNOPSIS

```
#include <string.h>
int bcmp(const void *s1, const void *s2, int n);
void bcopy(const void *src, void *dest, int n);
void bzero(void *s, int n);
void *memccpy(void *dest, const void *src, int c, size_t n);
void *memchr(const void *s, int c, size_t n);
int memcmp(const void *s1, const void *s2, size_t n);
void *memcpy(void *dest, const void *src, size_t n);
void *memfrob(void *s, size_t n);
void *memmem(const void *needle, size_t needlelen,
const void *haystack, size_t haystacklen);
void *memmove(void *dest, const void *src, size_t n);
void *memset(void *s, int c, size_t n);
```

DESCRIPTION

The byte string functions perform operations on strings that are not `NULL` terminated. See the individual man pages for descriptions of each function.

SEE ALSO

`bcmp(3)`, `bcopy(3)`, `bzero(3)`, `memccpy(3)`, `memchr(3)`, `memcmp(3)`, `memcpy(3)`, `memfrob(3)`, `memmem(3)`, `memmove(3)`, `memset(3)`

GNU, 12 April 1993

htonl, htons, ntohl, ntohs

`htonl`, `htons`, `ntohl`, `ntohs`—Convert values between host and network byte order

SYNOPSIS

```
#include <netinet/in.h>
unsigned long int htonl(unsigned long int hostlong);
unsigned short int htons(unsigned short int hostshort);
```

```
unsigned long int ntohl(unsigned long int netlong);
unsigned short int ntohs(unsigned short int netshort);
```

DESCRIPTION

The `htonl()` function converts the long integer `hostlong` from host byte order to network byte order.

The `htons()` function converts the short integer `hostshort` from host byte order to network byte order.

The `ntohl()` function converts the long integer `netlong` from network byte order to host byte order.

The `ntohs()` function converts the short integer `netshort` from network byte order to host byte order.

On the i80x86, the host byte order is least significant byte first, whereas the network byte order, as used on the Internet, is most significant byte first.

CONFORMS TO

BSD 4.3

SEE ALSO

`gethostbyname(3)`, `getservent(3)`

BSD, 15 April 1993

bzero

`bzero`—Writes 0s to a byte string

SYNOPSIS

```
#include <string.h>
void bzero(void *s, int n);
```

DESCRIPTION

The `bzero()` function sets the first `n` bytes of the byte string `s` to 0.

RETURN VALUE

The `bzero()` function returns no value.

CONFORMS TO

4.3BSD. This function is deprecated—use `memset` in new programs.

SEE ALSO

`memset(3)`, `swab(3)`

GNU, 9 April 1993

catgets

`catgets`—Gets message from a message catalog

SYNOPSIS

```
#include <features.h>
#include <nl_types.h>
char *catgets(nl_catd catalog, int set_number, int
message_number, char *message);
```

DESCRIPTION

`catgets()` reads the message `message_number`, in set `set_number`, from the message catalog identified by `catalog`. (`catalog` is a catalog descriptor returned from an earlier call to `catopen(3)`.) The fourth argument `message` points to a default message string that will be returned by `catgets()` if the identified message catalog is not currently open or is damaged. The message text is contained in an internal buffer area and should be copied by the application if it is to be saved or modified. The return string is always terminated with a null byte.

RETURN VALUES

On success, `catgets()` returns a pointer to an internal buffer area containing the null-terminated message string. `catgets()` returns a pointer to message if it fails because the message catalog specified by `catalog` is not currently open. Otherwise, `catgets()` returns a pointer to an empty string if the message catalog is available but does not contain the specified message.

NOTES

These functions are only available in `libc.so.4.4.4c` and above.

SEE ALSO

`catopen(3)`, `setlocale(3)`

29 November 1993

catopen, catclose

`catopen, catclose`—Open/close a message catalog

SYNOPSIS

```
#include <features.h>
#include <nl_types.h>
nl_catd catopen(char *name, int flag);
void catclose(nl_catd catalog);
```

DESCRIPTION

`catopen()` opens a message catalog and returns a catalog descriptor. `name` specifies the name of the message catalog to be opened. If `name` specifies an absolute path (that is, contains a `/`), `name` specifies a pathname for the message catalog. Otherwise, the environment variable `NLSPATH` is used, with `name` substituted for `%N` (see `locale(5)`). If `NLSPATH` does not exist in the environment, or if a message catalog cannot be opened in any of the paths specified by `NLSPATH`, the following paths are searched in order:

```
/etc/locale/LC_MESSAGES
/usr/lib/locale/LC_MESSAGES
/usr/lib/locale/name/LC_MESSAGES
```

In all cases, `LC_MESSAGES` stands for the current setting of the `LC_MESSAGES` category of locale from a previous call to `setlocale()` and defaults to the `C` locale. In the last search path, `name` refers to the catalog name.

The `flag` argument to `catopen` is used to indicate the type of loading desired. This should be either `MCLoadBySet` or `MCLoadAll`. The former value indicates that only the required set from the catalog is loaded into memory when needed, whereas the latter causes the initial call to `catopen()` to load the entire catalog into memory.

`catclose()` closes the message catalog identified by `catalog`. It invalidates any subsequent references to the message catalog defined by `catalog`.

RETURN VALUES

`catopen()` returns a message catalog descriptor of type `nl_catd` on success. On failure, it returns `-1`.

`catclose()` returns `0` on success, or `-1` on failure.

NOTES

These functions are only available in `libc.so.4.4.4c` and above. In the case of Linux, the catalog descriptor `n1_catd` is actually an area of memory assigned by `mmap()` and not a file descriptor, thus allowing catalogs to be shared.

SEE ALSO

`catgets(3)`, `setlocale(3)`

30 November 1993

ceil

`ceil`—Smallest integral value not less than *x*

SYNOPSIS

```
#include <math.h>
double ceil (double x);
```

DESCRIPTION

The `ceil()` function rounds up *x* to the nearest integer, returning that value as a double.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`abs(3)`, `fabs(3)`, `floor(3)`, `labs(3)`, `rint(3)`

6 June 1993

clientlib

`clientlib`—NNTP clientlib part of InterNetNews library

SYNOPSIS

```
extern FILE *ser_rd_fp;
extern FILE *ser_wr_fp;
extern char ser_line[];
char * getserverbyfile(file);
char *file; int server_init(host);
char *host;
int handle_server_response(response, host);
int reponse;
char *host;
void put_server(text);
char *text;
int get_server(buff, buffsize);
char *buff;
int buffsize;
void close_server();
```

DESCRIPTION

The routines described in this manual page are part of the InterNetNews library, `libinn(3)`. They are replacements for the `clientlib` part of the NNTP distribution, and are intended to be used in building programs such as `rrn`.

`getserverbyfile` calls `GetConfigValue` to get the name of the local NNTP server. It returns a pointer to static space. The `file` parameter is ignored.

`server_init` opens a connect to the NNTP server at the specified `host`. It returns the server's response code or `-1` on error. If a connection was made, `ser_rd_fp` and `ser_wr_fp` can be used to read from and write to the server, respectively, and `ser_line` will contain the server's response. `ser_line` can also be used in other routines.

`handle_server_response` decodes the response, which comes from the server on `host`. If the client is authorized, it returns `0`. A client that is only allowed to read is authorized, but `handle_server_response` will print a message on the standard output. If the client is not authorized to talk to the server, a message is printed, and the routine returns `-1`.

`put_server` sends the text in `buff` to the server, adding the necessary NNTP line terminators and flushing the I/O buffer.

`get_server` reads a line of text from the server into `buff`, reading at most `buffsize` characters. Any trailing `\r\n` terminators are stripped off. `get_server` returns `-1` on error.

`close_server` sends a quit command to the server and closes the connection.

HISTORY

Written by Rich Salz (`rsalz@uunet.uu.net`) for InterNetNews.

SEE ALSO

`libinn(3)`

clock

`clock`—Determine processor time

SYNOPSIS

```
#include <time.h>
clock_t clock(void);
```

DESCRIPTION

The `clock()` function returns an approximation of processor time used by the program.

RETURN VALUE

The value returned is the CPU time used so far as a `clock_t`; to get the number of seconds used, divide by `CLOCKS_PER_SEC`.

CONFORMS TO

ANSI C

BUGS

The C standard allows for arbitrary values at the start of the program; take the difference between the value returned from a call to `clock()` at the start of the program and the value returned at the end for maximum portability.

The `times()` function call returns more information.

SEE ALSO

`times(2)`

GNU, 21 April 1993

closedir

`closedir`—Close a directory

SYNOPSIS

```
#include <sys/types.h>
#include <dirent.h>
int closedir(DIR *dir);
```

DESCRIPTION

The `closedir()` function closes the directory stream associated with `dir`. The directory stream descriptor `dir` is not available after this call.

RETURN VALUE

The `closedir()` function returns 0 on success or -1 on failure.

ERRORS

EBADF Invalid directory stream descriptor `dir`.

CONFORMS TO

SVID 3, POSIX, BSD 4.3

SEE ALSO

`close(2)`, `opendir(3)`, `readdir(3)`, `rewinddir(3)`, `seekdir(3)`, `telldir(3)`, `scandir(3)`

11 June 1995

confstr

`confstr`—Get configuration-dependent string variables

SYNOPSIS

```
#define __USE_POSIX_2
#include <unistd.h>
size_t confstr(int name, char *buf, size_t len);
```

DESCRIPTION

`confstr()` gets the value of configuration-dependent string variables.

The `name` argument is the system variable to be queried. The following variables are supported:

_CS_PATH A value for the `PATH` variable that indicates where all the POSIX.2 standard utilities can be found.

If `buf` is not `NULL`, and `len` is not 0, `confstr()` copies the value of the string to `buf` truncated to `len-1` characters if necessary, with a null character as termination. This can be detected by comparing the return value of `confstr()` against `len`.

If `len` is 0 and `buf` is `NULL`, `confstr()` just returns the value in `Return Value`.

RETURN VALUE

If `name` does not correspond to a valid configuration variable, `confstr()` returns 0.

EXAMPLES

The following code fragment determines the path where you can find the POSIX.2 system utilities:

```
char *pathbuf; size_t n;
n = confstr(_CS_PATH, NULL, (size_t)0);
if ((pathbuf = malloc(n)) == NULL) abort();
confstr(_CS_PATH, pathbuf, n);
```

ERRORS

If the value of `name` is invalid, `errno` is set to `EINVAL`.

CONFORMS TO

Proposed POSIX.2

BUGS

POSIX.2 is not yet an approved standard; the information in this man page is subject to change.

SEE ALSO

`sh(1)`, `exec(2)`, `system(3)`

GNU, 17 April 1993

copysign

`copysign`—Copies the sign of a number

SYNOPSIS

```
#include <math.h>
double copysign(double x, double y);
```

DESCRIPTION

The `copysign()` function returns a value whose absolute value matches `x`, but whose sign matches that of `y`.

CONFORMS TO

BSD 4.3

GNU, 6 June 1993

COS

`cos`—Cosine function

SYNOPSIS

```
#include <math.h>
double cos(double x);
```

DESCRIPTION

The `cos()` function returns the cosine of `x`, where `x` is given in radians.

RETURN VALUE

The `cos()` function returns a value between -1 and 1 .

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`acos(3)`, `asin(3)`, `atan(3)`, `atan2(3)`, `sin(3)`, `tan(3)`

8 June 1993

cosh

cosh—Hyperbolic cosine function

SYNOPSIS

```
#include <math.h>
double cosh(double x);
```

DESCRIPTION

The `cosh()` function returns the hyperbolic cosine of `x`, which is defined mathematically as $(\exp(x) + \exp(-x)) / 2$.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`acosh(3)`, `asinh(3)`, `atanh(3)`, `sinh(3)`, `tanh(3)`

13 June 1993

crypt

crypt—Password and data encryption

SYNOPSIS

```
#include <unistd.h>
char *crypt(const char *key, const char *salt);
```

DESCRIPTION

`crypt` is the password-encryption function. It is based on the Data Encryption Standard algorithm, with variations intended (among other things) to discourage the use of hardware implementations of a key search.

`key` is a user's typed password.

`salt` is a two-character string chosen from the set `[a-zA-Z0-9./]`. This string is used to perturb the algorithm in one of 4,096 different ways.

By taking the lowest seven bits of each character of the key, a 56-bit key is obtained. This 56-bit key is used to repeatedly encrypt a constant string (usually a string consisting of all 0s). The returned value points to the encrypted password, a series of 13 printable ASCII characters (with the first two characters representing the salt itself). The return value points to static data whose content is overwritten by each call.

Warning: The key space consists of equal 7.2×10^{16} possible values. Exhaustive searches of this key space are possible using massively parallel computers. Software, such as `crack(1)`, is available to search the portion of this key space that is generally used by humans for passwords. Hence, password selection should, at minimum, avoid common words and names. Using a `passwd(1)` program that checks for crackable passwords during the selection process is recommended.

The DES algorithm itself has a few quirks that make using the `crypt(3)` interface a very poor choice for anything other than password authentication. If you are planning to use the `crypt(3)` interface for a cryptography project, don't do it; get a good book on encryption and one of the widely available DES libraries instead.

CONFORMS TO

SVID, X/OPEN, BSD 4.3

SEE ALSO

login(1), passwd(1), encrypt(3), getpass(3), passwd(5)

3 September 1994

ctermid

ctermid—Gets controlling terminal name

SYNOPSIS

```
#include <stdio.h>
char *ctermid(char *s);
```

DESCRIPTION

ctermid() returns a string that is the pathname for the current controlling terminal for this process. If s is NULL, a static buffer is used; otherwise, s points to a buffer used to hold the terminal pathname. The symbolic constant L_ctermid is the maximum number of characters in the returned pathname.

RETURN VALUE

This function returns the pointer to the pathname.

CONFORMS TO

POSIX.1

BUGS

The path returned might not uniquely identify the controlling terminal; it might, for example, be /dev/tty.

It is not assured that the program can open the terminal.

SEE ALSO

ttyname(3)

GNU, 6 April 1993

asctime, ctime, gmtime, localtime, mktime

asctime, ctime, gmtime, localtime, mktime—Transform binary date and time to ASCII

SYNOPSIS

```
#include <time.h>
char *asctime(const struct tm *timeptr);
char *ctime(const time_t *timep);
struct tm *gmtime(const time_t *timep);
struct tm *localtime(const time_t *timep);
time_t mktime(struct tm *timeptr);
extern char *tzname[2];
long int timezone;
extern int daylight;
```

DESCRIPTION

The ctime(), gmtime(), and localtime() functions all take an argument of data type time_t, which represents calendar time. When interpreted as an absolute time value, it represents the number of seconds elapsed since 00:00:00 on January 1, 1970, Coordinated Universal Time (UTC).

The `asctime()` and `mktime()` functions both take an argument representing broken-down time, which is a binary representation separated into year, month, day, and so on. Broken-down time is stored in the structure `tm`, which is defined in `<time.h>` as follows:

```
struct tm
{
    int tm_sec; /* seconds */
    int tm_min; /* minutes */
    int tm_hour; /* hours */
    int tm_mday; /* day of the month */
    int tm_mon; /* month */
    int tm_year; /* year */
    int tm_wday; /* day of the week */
    int tm_yday; /* day in the year */
    int tm_isdst; /* daylight saving time */
};
```

The members of the `tm` structure are

<code>tm_sec</code>	The number of seconds after the minute, normally in the range 0 to 59, but can be up to 61 to allow for leap seconds.
<code>tm_min</code>	The number of minutes after the hour, in the range 0 to 59.
<code>tm_hour</code>	The number of hours past midnight, in the range 0 to 23.
<code>tm_mday</code>	The day of the month, in the range 1 to 31.
<code>tm_mon</code>	The number of months since January, in the range 0 to 11.
<code>tm_year</code>	The number of years since 1900.
<code>tm_wday</code>	The number of days since Sunday, in the range 0 to 6.
<code>tm_yday</code>	The number of days since January 1, in the range 0 to 365.
<code>tm_isdst</code>	A flag that indicates whether daylight savings time is in effect at the time described. The value is positive if daylight saving time is in effect, 0 if it is not, and negative if the information is not available.

The `ctime()` function converts the calendar time `timep` into a string of the form

```
"Wed Jun 30 21:49:08 1993\n"
```

The abbreviations for the days of the week are Sun, Mon, Tue, Wed, Thu, Fri, and Sat. The abbreviations for the months are Jan, Feb, Mar, Apr, May, Jun, Jul, Aug, Sep, Oct, Nov, and Dec. The return value points to a statically allocated string that might be overwritten by subsequent calls to any of the date and time functions. The function also sets the external variable `tzname` with information about the current time zone.

The `gmtime()` function converts the calendar time `timep` to broken-down time representation, expressed in Coordinated Universal Time (UTC).

The `localtime()` function converts the calendar time `timep` to broken-time representation, expressed relative to the user's specified time zone. The function sets the external variables `tzname` with information about the current time zone, `timezone` with the difference between Coordinated Universal Time and local standard time in seconds, and `daylight` to a nonzero value if standard U.S. daylight saving time rules apply.

The `asctime()` function converts the broken-down time value `timeptr` into a string with the same format as `ctime()`. The return value points to a statically allocated string that might be overwritten by subsequent calls to any of the date and time functions.

The `mktime()` function converts a broken-down time structure, expressed as local time, to calendar time representation. The function ignores the specified contents of the structure members `tm_wday` and `tm_yday` and recomputes them from the other information in the broken-down time structure. Calling `mktime()` also sets the external variable `tzname` with information about the current time zone. If the specified broken-down time cannot be represented as calendar time, `mktime()` returns a value of `(time_t)(-1)` and does not alter the `tm_wday` and `tm_yday` members of the broken-down time structure.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`date(1)`, `gettimeofday(2)`, `time(2)`, `tzset(3)`, `difftime(3)`, `strftime(3)`, `newtime(3)`

BSD, 26 April 1996

difftime

`difftime`—Calculates time difference

SYNOPSIS

```
#include <time.h>
double difftime(time_t time1, time_t time0);
```

DESCRIPTION

The `difftime()` function returns the number of seconds elapsed between time `time1` and time `time0`. The two times are specified in calendar time, which represents the time elapsed since 00:00:00 on January 1, 1970, Coordinated Universal Time (UTC).

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

SEE ALSO

`date(1)`, `gettimeofday(2)`, `time(2)`, `ctime(3)`, `gmtime(3)`, `localtime(3)`

GNU, 2 July 1993

div

`div`—Computes the quotient and remainder of integer division

SYNOPSIS

```
#include <stdlib.h>
div_t div(int numer, int denom);
```

DESCRIPTION

The `div()` function computes the value `numer/denom` and returns the quotient and remainder in a structure named `div_t` that contains two integer members named `quot` and `rem`.

RETURN VALUE

The `div_t` structure.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

SEE ALSO

`ldiv(3)`

6 June 1993

drand48, erand48, lrand48, nrand48, mrand48, jrand48, srand48, seed48, lcong48

drand48, erand48, lrand48, nrand48, mrand48, jrand48, srand48, seed48, lcong48—Generate uniformly distributed pseudo-random numbers

SYNOPSIS

```
#include <stdlib.h>
double drand48(void);
double erand48(unsigned short int xsubi[3]);
long int lrand48(void);
long int nrand48(unsigned short int xsubi[3]);
long int mrand48(void);
long int jrand48(unsigned short int xsubi[3]);
void srand48(long int seedval);
unsigned short int * seed48(unsigned short int seed16v [3]);
void lcong48(unsigned short int param[7]);
```

DESCRIPTION

These functions generate pseudo-random numbers using the linear congruential algorithm and 48-bit integer arithmetic.

The `drand48()` and `erand48()` functions return non-negative double-precision floating-point values uniformly distributed between [0.0, 1.0].

The `lrand48()` and `nrand48()` functions return non-negative long integers uniformly distributed between 0 and 2^{31} .

The `mrnd48()` and `jrand48()` functions return signed long integers uniformly distributed between -2^{31} and 2^{31} .

The `srand48()`, `seed48()`, and `lcong48()` functions are initialization functions, one of which should be called before using `drand48()`, `lrand48()`, or `mrnd48()`. The functions `erand48()`, `nrand48()`, and `jrand48()` do not require an initialization function to be called first.

All the functions work by generating a sequence of 48-bit integers, X_i , according to the linear congruential formula

$X_{i+1} = (aX_i + c) \bmod m$, where $i \geq 0$

The parameter $m = 2^{48}$; hence 48-bit integer arithmetic is performed. Unless `lcong48()` is called, a and c are given by

```
a = 0x5DEECE66D
c = 0xB
```

The value returned by any of the functions `drand48()`, `erand48()`, `lrand48()`, `nrand48()`, `mrnd48()`, or `jrand48()` is computed by first generating the next 48-bit x_i in the sequence. Then the appropriate number of bits, according to the type of data item to be returned, is copied from the high-order bits of x_i and transformed into the returned value.

The functions `drand48()`, `lrand48()`, and `mrnd48()` store the last 48-bit x_i generated in an internal buffer. The functions `erand48()`, `nrand48()`, and `jrand48()` require the calling program to provide storage for the successive x_i values in the array argument `xsubi`. The functions are initialized by placing the initial value of x_i into the array before calling the function for the first time.

The initializer function `srand48()` sets the high-order 32 bits of x_i to the argument `seedval`. The low-order 16 bits are set to the arbitrary value 0x330E.

The initializer function `seed48()` sets the value of x_i to the 48-bit value specified in the array argument `seed16v`. The previous value of x_i is copied into an internal buffer and a pointer to this buffer is returned by `seed48()`.

The initialization function `lcong48()` allows the user to specify initial values for x_i , a and c . Array argument elements `param[0-2]` specify x_i , `param[3-5]` specify a , and `param[6]` specifies c . After `lcong48()` has been called, a subsequent call to either `srand48()` or `seed48()` will restore the standard values of a and c .

CONFORMS TO

SVID 3

NOTES

These functions are declared obsolete by SVID 3, which states that `rand(3)` should be used instead.

SEE ALSO

`rand(3)`, `random(3)`

2 July 1993

drem

drem—Floating-point remainder function

SYNOPSIS

```
#include <math.h>
double drem(double x, double y);
```

DESCRIPTION

The `drem()` function computes the remainder of dividing `x` by `y`. The return value is $x - n * y$, where n is the quotient of `x` divided by `y`, rounded to the nearest integer. If the quotient is $\frac{1}{2}$, it is rounded to the even number.

RETURN VALUE

The `drem()` function returns the remainder unless `y` is 0, in which case the function fails and `errno` is set.

ERRORS

EDOM The denominator `y` is 0.

CONFORMS TO

BSD 4.3

SEE ALSO

`fmod(3)`

6 June 1993

ecvt, fcvt

ecvt, fcvt—Convert a floating-point number to a string

SYNOPSIS

```
#include <stdlib.h>
char *ecvt(double number, size_t ndigits, int*decpt, int*sign);
char *fcvt(double number, size_t ndigits, int*decpt, int*sign);
```

DESCRIPTION

The `ecvt()` function converts `number` to a NULL-terminated string of `ndigits` digits and returns a pointer to the string. The string itself does not contain a decimal point; however, the position of the decimal point relative to the start of the string is

stored in `decpt`. A negative value for `decpt` means that the decimal point is to the left of the start of the string. If the sign of `number` is negative, `sign` is set to a nonzero value; otherwise, it's set to 0.

The `fcvt()` function is identical to `ecvt()`, except that `ndigits` specifies the number of digits after the decimal point.

RETURN VALUE

Both the `ecvt()` and `fcvt()` functions return a pointer to a static string containing the ASCII representation of `number`. The static string is overwritten by each call to `ecvt()` or `fcvt()`.

SEE ALSO

`gcvt(3)`, `sprintf(3)`

28 March 1993

erf, erfc

`erf`, `erfc`—Error function and complementary error function

SYNOPSIS

```
#include <math.h>
double erf(double x);
double erfc (double x);
```

DESCRIPTION

The `erf()` function returns the error function of `x`, defined as

$$\text{erf}(x) = \frac{2}{\sqrt{\pi}} \int_0^x \exp(-t^2) dt$$

The `erfc()` function returns the complementary error function of `x`—that is, $1.0 - \text{erf}(x)$.

CONFORMS TO

SVID 3, BSD 4.3

SEE ALSO

`exp(3)`

BSD, 25 June 1993

execl, execlp, execl, exect, execv, execvp

`execl`, `execlp`, `execl`, `exect`, `execv`, `execvp`—Execute a file

SYNOPSIS

```
#include <unistd.h>
extern char **environ;
int execl(const char *path, const char *arg, ...);
int execlp(const char *file, const char *arg, ...);
int execl(const char *path, const char *arg, ...);
int execlp(const char *file, const char *arg, ...);
int execl(const char *path, const char *arg, ...);
int execl(const char *path, const char *arg, ..., char * const envp[]);
int exect(const char *path, char *const argv[]);
int execv(const char *path, char *const argv[]);
int execvp(const char *file, char *const argv[]);
```

DESCRIPTION

The `exec` family of functions replaces the current process image with a new process image. The functions described in this manual page are front ends for the function `execve(2)`. (See the manual page for `execve` for detailed information about the replacement of the current process.)

The initial argument for these functions is the pathname of a file that is to be executed.

The `const char *arg` and subsequent ellipses in the `exec1`, `execlp`, and `execl` functions can be thought of as `arg0`, `arg1`, ..., `argn`. Together they describe a list of one or more pointers to null-terminated strings that represent the argument list available to the executed program. The first argument, by convention, should point to the file name associated with the file being executed. The list of arguments must be terminated by a `NULL` pointer.

The `exect`, `execv`, and `execvp` functions provide an array of pointers to null-terminated strings that represent the argument list available to the new program. The first argument, by convention, should point to the filename associated with the file being executed. The array of pointers must be terminated by a `NULL` pointer.

The `execl` and `exect` functions also specify the environment of the executed process by following the `NULL` pointer that terminates the list of arguments in the parameter list or the pointer to the `argv` array with an additional parameter. This additional parameter is an array of pointers to null-terminated strings and must be terminated by a `NULL` pointer. The other functions take the environment for the new process image from the external variable `environ` in the current process.

Some of these functions have special semantics.

The functions `execlp` and `execvp` will duplicate the actions of the shell in searching for an executable file if the specified filename does not contain a slash (/) character. The search path is the path specified in the environment by the `PATH` variable. If this variable isn't specified, the default path `/bin:/usr/bin:` is used (is this true for Linux?). In addition, certain errors are treated specially.

If permission is denied for a file (the attempted `execve` returned `EACCES`), these functions will continue searching the rest of the search path. If no other file is found, however, they will return with the global variable `errno` set to `EACCES`.

If the header of a file isn't recognized (the attempted `execve` returned `ENOEXEC`), these functions will execute the shell with the path of the file as its first argument. (If this attempt fails, no further searching is done.)

If the file is currently busy (the attempted `execve` returned `ETXTBUSY`), these functions will sleep for several seconds, periodically re-attempting to execute the file. (Is this true for Linux?)

The function `exect` executes a file with the program-tracing facilities enabled (see `ptrace(2)`).

RETURN VALUES

If any of the `exec` functions returns, an error will have occurred. The return value is `-1`, and the global variable `errno` will be set to indicate the error.

FILES

`/bin/sh`

ERRORS

`exec1`, `execl`, `execlp`, and `execvp` may fail and set `errno` for any of the errors specified for the library functions `execve(2)` and `malloc(3)`.

`exect` and `execv` may fail and set `errno` for any of the errors specified for the library function `execve(2)`.

SEE ALSO

`sh(1)`, `execve(2)`, `fork(2)`, `trace(2)`, `environ(5)`, `ptrace(2)`

COMPATIBILITY

Historically, the default path for the `execlp` and `execvp` functions was `/bin:/usr/bin`. This was changed to place the current directory last to enhance system security.

The behavior of `execlp` and `execvp` when errors occur while attempting to execute the file is historic practice, but has not traditionally been documented and is not specified by the POSIX standard.

Traditionally, the functions `execlp` and `execvp` ignored all errors except for the ones described above and `ENOMEM` and `E2BIG`, upon which they returned. They now return if any error other than the ones described in the “Errors” section occurs.

STANDARDS

`execl`, `execv`, `execl`, `execlp`, and `execvp` conform to IEEE Std1003.1-88 (POSIX.1).

BSD Man Page, 29 November 1993

errno

`errno`—Number of last error

SYNOPSIS

```
#include <errno.h>
extern int errno;
```

DESCRIPTION

The integer `errno` is set by system calls (and some library functions) to indicate what went wrong. Its value is significant only when the call returns an error (usually `-1`), and a library function that does succeed is allowed to change `errno`.

Sometimes, when `-1` is also a legal return value, you have to set `errno` to `0` before the call in order to detect possible errors.

POSIX lists the following symbolic error names:

<code>E2BIG</code>	Arg list too long
<code>EACCES</code>	Permission denied
<code>EAGAIN</code>	Resource temporarily unavailable
<code>EBADF</code>	Bad file descriptor
<code>EBUSY</code>	Resource busy
<code>ECHILD</code>	No child processes
<code>EDEADLK</code>	Resource deadlock avoided
<code>EDOM</code>	Domain error
<code>EEXIST</code>	File exists
<code>EFAULT</code>	Bad address
<code>EFBIG</code>	File too large
<code>EINTR</code>	Interrupted function call
<code>EINVAL</code>	Invalid argument
<code>EIO</code>	Input/output error
<code>EISDIR</code>	Is a directory
<code>EMFILE</code>	Too many open files
<code>EMLINK</code>	Too many links
<code>ENAMETOOLONG</code>	Filename too long
<code>ENFILE</code>	Too many open files in system
<code>ENODEV</code>	No such device
<code>ENOENT</code>	No such file or directory
<code>ENOEXEC</code>	Exec format error
<code>ENOLCK</code>	No locks available
<code>ENOMEM</code>	Not enough space

ENOSPC	No space left on device
ENOSYS	Function not implemented
ENOTDIR	Not a directory
ENOTEMPTY	Directory not empty
ENOTTY	Inappropriate I/O control operation
ENXIO	No such device or address
EPERM	Operation not permitted
EPIPE	Broken pipe
ERANGE	Result too large
EROFS	Read-only filesystem
ESPIPE	Invalid seek
ESRCH	No such process
EXDEV	Improper link

SEE ALSO

perror(3)

21 July 1996

exit

exit—Causes normal program termination

SYNOPSIS

```
#include <stdlib.h>
void exit(int status);
```

DESCRIPTION

The `exit()` function causes normal program termination, and the value of `status` is returned to the parent. All functions registered with `atexit()` and on `exit()` are called in the reverse order of their registration, and all open streams are flushed and closed.

RETURN VALUE

The `exit()` function does not return.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`_exit(2)`, `atexit(3)`, `on_exit(3)`

GNU, 2 April 1993

exp, log, log10, pow

exp, log, log10, pow—Exponential, logarithmic, and power functions

SYNOPSIS

```
#include <math.h>
double exp(double x);
```

```
double log(double x);
double log10(double x);
double pow(double x, double y);
```

DESCRIPTION

The `exp()` function returns the value of *e* (the base of natural logarithms) raised to the power of *x*.

The `log()` function returns the natural logarithm of *x*.

The `log10()` function returns the base-10 logarithm of *x*.

The `pow()` function returns the value of *x* raised to the power of *y*.

ERRORS

The `log()` and `log10()` functions can return the following errors:

EDOM	The argument <i>x</i> is negative.
ERANGE	The argument <i>x</i> is 0. The log of 0 is not defined.

The `pow()` function can return the following error:

EDOM	The argument <i>x</i> is negative and <i>y</i> is not an integral value. This would result in a complex number.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`sqrt(3)`, `cbrt(3)`

GNU June 16, 1993

expm1, log1p

`expm1`, `log1p`—Exponential minus 1, logarithm of 1 plus argument

SYNOPSIS

```
#include <math.h>
double expm1 (double x);
double log1p (double x);
```

DESCRIPTION

`expm1(x)` returns a value equivalent to $\exp(x) - 1$. It is computed in a way that is accurate even if the value of *x* is near 0—a case where $\exp(x) - 1$ would be inaccurate due to subtraction of two numbers that are nearly equal.

`log1p(x)` returns a value equivalent to $\log(1 + x)$. It is computed in a way that is accurate even if the value of *x* is near 0.

CONFORMS TO

BSD

SEE ALSO

`exp(3)`, `log(3)`

GNU, 16 September 1995

fabs

Fabs—Absolute value of floating-point number

SYNOPSIS

```
#include <math.h>
double fabs(double x);
```

DESCRIPTION

The `fabs()` function returns the absolute value of the floating-point number `x`.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`abs(3)`, `ceil(3)`, `floor(3)`, `labs(3)`, `rint(3)`

25 June 1993

fclose

`fclose`—Closes a stream

SYNOPSIS

```
#include <stdio.h>
int fclose(FILE *stream);
```

DESCRIPTION

The `fclose` function dissociates the named `stream` from its underlying file or set of functions. If the stream was being used for output, any buffered data is written first, using `fflush(3)`.

RETURN VALUES

Upon successful completion, `0` is returned. Otherwise, `EOF` is returned, and the global variable `errno` is set to indicate the error. In either case, no further access to the stream is possible.

ERRORS

EBADF The argument `stream` is not an open stream.

The `fclose` function may also fail and set `errno` for any of the errors specified for the routines `close(2)` or `fflush(3)`.

SEE ALSO

`close(2)`, `fflush(3)`, `fopen(3)`, `setbuf(3)`

STANDARDS

The `fclose` function conforms to ANSI C3.159-1989 ("ANSI C").

BSD Man Page, 29 November 1993

clearerr, feof, ferror, fileno

`clearerr`, `feof`, `ferror`, `fileno`—Check and reset stream status

SYNOPSIS

```
#include <stdio.h>
void clearerr( FILE *stream);
int feof(FILE *stream);
int ferror(FILE *stream);
int fileno(FILE *stream);
```

DESCRIPTION

The function `clearerr` clears the end-of-file and error indicators for the stream pointed to by `stream`.

The function `feof` tests the end-of-file indicator for the stream pointed to by `stream`, returning nonzero if it is set. The end-of-file indicator can only be cleared by the function `clearerr`.

The function `ferror` tests the error indicator for the stream pointed to by `stream`, returning nonzero if it is set. The error indicator can only be reset by the `clearerr` function.

The function `fileno` examines the argument `stream` and returns its integer descriptor.

ERRORS

These functions should not fail and do not set the external variable `errno`.

SEE ALSO

`open(2)`, `stdio(3)`

STANDARDS

The functions `clearerr`, `feof`, and `ferror` conform to C3.159-1989 (“ANSI C”).

BSD Man Page, 29 November 1993

fflush, fpurge

`fflush`, `fpurge`—Flush a stream

SYNOPSIS

```
#include <stdio.h>
int fflush( FILE *stream);
int fpurge( FILE *stream);
```

DESCRIPTION

The function `fflush` forces a write of all buffered data for the given output or update stream via the stream’s underlying write function. The open status of the stream is unaffected.

If the stream argument is `NULL`, `fflush` flushes all open output streams. (Does this happen under Linux?)

The function `fpurge` erases any input or output buffered in the given stream. For output streams, this discards any unwritten output. For input streams, this discards any input read from the underlying object but not yet obtained via `getc(3)`; this includes any text pushed back via `ungetc`.

RETURN VALUES

Upon successful completion, `0` is returned. Otherwise, `EOF` is returned, and the global variable `errno` is set to indicate the error.

ERRORS

EBADF Stream is not an open stream, or, in the case of `fflush`, not a stream open for writing.

The function `fflush` may also fail and set `errno` for any of the errors specified for the routine `write(2)`.

BUGS

Linux may not support `fpurge`.

SEE ALSO

`write(2)`, `fopen(3)`, `fclose(3)`, `setbuf(3)`

STANDARDS

The `fflush` function conforms to ANSI C3.159-1989 (“ANSI C”).

BSD Man Page, 29 November 1993

ffs

`ffs`—Finds first bit set in a word

SYNOPSIS

```
#include <string.h>
int ffs(int i);
```

DESCRIPTION

The `ffs()` function returns the position of the first bit set in the word `i`. The least significant bit is position 1, and the most significant position 32.

RETURN VALUE

The `ffs()` function returns the position of the first bit set, or `NULL` if no bits are set.

CONFORMS TO

BSD 4.3

GNU, 13 April 1993

fgetgrent

`fgetgrent`—Gets group file entry

SYNOPSIS

```
#include <grp.h>
#include <stdio.h>
#include <sys/types.h>
struct group *fgetgrent(FILE *stream);
```

DESCRIPTION

The `fgetgrent()` function returns a pointer to a structure containing the group information from the file `stream`. The first time it is called it returns the first entry; thereafter, it returns successive entries. The file `stream` must have the same format as `/etc/group`.

The group structure is defined in `<grp.h>` as follows:

```
struct group {
    char    *gr_name;        /* group name */
    char    *gr_passwd;      /* group password */
    gid_t   gr_gid;         /* group id */
    char    **gr_mem;        /* group members */
};
```

RETURN VALUE

The `fgetgrent()` function returns the group information structure, or `NULL` if there are no more entries or an error occurs.

ERRORS

`ENOMEM` Insufficient memory to allocate group information structure.

CONFORMS TO

SVID 3

SEE ALSO

`getgrnam(3)`, `getgrgid(3)`, `getgrent(3)`, `setgrent(3)`, `endgrent(3)`

GNU, 4 April 1993

fgetpwent

`fgetpwent`—Gets password file entry

SYNOPSIS

```
#include <pwd.h>
#include <stdio.h>
#include <sys/types.h>
struct passwd *fgetpwent(FILE *stream);
```

DESCRIPTION

The `fgetpwent()` function returns a pointer to a structure containing the broken-out fields of a line in the file `stream`. The first time it is called it returns the first entry; thereafter, it returns successive entries. The file `stream` must have the same format as `/etc/passwd`.

The `passwd` structure is defined in `<pwd.h>` as follows:

```
struct passwd {
    char    *pw_name;        /* username */
    char    *pw_passwd;      /* user password */
    uid_t   pw_uid;          /* user id */
    gid_t   pw_gid;          /* group id */
    char    *pw_gecos;       /* real name */
    char    *pw_dir;         /* home directory */
    char    *pw_shell;       /* shell program */
};
```

RETURN VALUE

The `fgetpwent()` function returns the `passwd` structure, or `NULL` if there are no more entries or an error occurs.

ERRORS

`ENOMEM` Insufficient memory to allocate `passwd` structure.

FILES

`/etc/passwd` password database file

CONFORMS TO

SVID 3

SEE ALSO

getpwnam(3), getpwuid(3), getpwent(3), setpwent(3), endpwent(3), getpw(3), putpwent(3), passwd(5)

GNU, 17 May 1996

floor

floor—Largest integral value not greater than *x*

SYNOPSIS

```
#include <math.h>
double floor(double x);
```

DESCRIPTION

The `floor()` function rounds *x* downward to the nearest integer, returning that value as a double.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`abs(3)`, `fabs(3)`, `ceil(3)`, `rint(3)`

6 June 1993

fmod

fmod—Floating-point remainder function

SYNOPSIS

```
#include <math.h>
double fmod(double x, double y);
```

DESCRIPTION

The `modf()` function computes the remainder of dividing *x* by *y*. The return value is $x - n * y$, where *n* is the quotient of *x*/*y*, rounded toward 0 to an integer.

RETURN VALUE

The `fmod()` function returns the remainder unless *y* is 0, in which case the function fails and `errno` is set.

ERRORS

EDOM The denominator *y* is 0.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`drem(3)`

6 June 1993

fnmatch

fnmatch—Matches filename or pathname

SYNOPSIS

```
#include <fnmatch.h>
int fnmatch(const char *pattern, const char *strings, int flags);
```

DESCRIPTION

fnmatch() checks the `strings` argument and checks whether it matches the `pattern` argument, which is a shell wildcard pattern.

The `flags` argument modifies the behavior; it is the bitwise OR of zero or more of the following flags:

<code>FNM_NOESCAPE</code>	If this flag is set, treat backslash as an ordinary character instead of as an escape character.
<code>FNM_PATHNAME</code>	If this flag is set, match a slash in <code>string</code> only with a slash in <code>pattern</code> and not, for example, with a <code>[] -</code> sequence containing a slash.
<code>FNM_PERIOD</code>	If this flag is set, a leading period in <code>string</code> has to be matched exactly by a period in <code>pattern</code> . A period is considered to be leading if it is the first character in <code>string</code> , or if both <code>FNM_PATHNAME</code> is set and the period immediately follows a slash.

RETURN VALUE

Zero if `string` matches `pattern`, `FNM_NOMATCH` if there is no match, or another value if there is an error.

CONFORMS TO

Proposed POSIX.2

BUGS

POSIX.2 is not yet an approved standard; the information in this man page is subject to change.

SEE ALSO

sh(1), glob(3), glob(7)

GNU, 19 April 1993

fopen, fdopen, freopen

fopen, fdopen, freopen—Stream open functions

SYNOPSIS

```
#include <stdio.h>
FILE *fopen( char *path, char *mode);
FILE *fdopen( int fildes, char *mode);
FILE *freopen( char *path, char *mode, FILE *stream);
```

DESCRIPTION

The `fopen` function opens the file whose name is the string pointed to by `path` and associates a stream with it.

The argument `mode` points to a string beginning with one of the following sequences (additional characters may follow these sequences):

<code>r</code>	Open text file for reading. The stream is positioned at the beginning of the file.
<code>r+</code>	Open for reading and writing. The stream is positioned at the beginning of the file.

w	Truncate file to zero length or create a text file for writing. The stream is positioned at the beginning of the file.
w+	Open for reading and writing. The file is created if it does not exist; otherwise it is truncated. The stream is positioned at the beginning of the file.
a	Open for writing. The file is created if it does not exist. The stream is positioned at the end of the file.
a+	Open for reading and writing. The file is created if it does not exist. The stream is positioned at the end of the file.

The mode string can also include the letter `b` either as a third character or as a character between the characters in any of the two-character strings described previously. This is strictly for compatibility with ANSI C3.159-1989 (ANSI C) and has no effect; the `b` is ignored.

Any created files will have mode `S_IRUSR|S_IWUSR|S_IRGRP|S_IWGRP|S_IROTH|S_IWOTH` (0666), as modified by the process's `umask` value. (See `umask(2)`.)

Reads and writes may be intermixed on read/write streams in any order. Note that ANSI C requires that a file positioning function intervene between output and input, unless an input operation encounters end-of-file. (If this condition is not met, then a read is allowed to return the result of writes other than the most recent.) Therefore it is good practice (and indeed sometimes necessary under Linux) to put an `fseek` or `fgetpos` operation between write and read operations on such a stream. This operation may be an apparent no-op (as in `fseek(..., 0L, SEEK_CUR)`) called for its synchronizing side effect.

The `fdopen` function associates a stream with the existing file descriptor, `fdes`. The mode of the stream must be compatible with the mode of the file descriptor. The file descriptor is not duplicated.

The `freopen` function opens the file whose name is the string pointed to by `path` and associates the stream pointed to by `stream` with it. The original stream (if it exists) is closed. The `mode` argument is used just as in the `fopen` function. The primary use of the `freopen` function is to change the file associated with a standard text stream (`stderr`, `stdin`, or `stdout`).

RETURN VALUES

On successful completion, `fopen`, `fdopen`, and `freopen` return a `FILE` pointer. Otherwise, `NULL` is returned, and the global variable `errno` is set to indicate the error.

ERRORS

`EINVAL` The mode provided to `fopen`, `fdopen`, or `freopen` was invalid.

The `fopen`, `fdopen`, and `freopen` functions may also fail and set `errno` for any of the errors specified for the routine `malloc(3)`.

The `fopen` function may also fail and set `errno` for any of the errors specified for the routine `open(2)`.

The `fdopen` function may also fail and set `errno` for any of the errors specified for the routine `fcntl(2)`.

The `freopen` function may also fail and set `errno` for any of the errors specified for the routines `open(2)`, `fclose(3)` and `fflush(3)`.

SEE ALSO

`open(2)`, `fclose(3)`

STANDARDS

The `fopen` and `freopen` functions conform to ANSI C3.159-1989 (ANSI C). The `fdopen` function conforms to IEEE Std1003.1-1988 (POSIX.1).

BSD Man Page, 13 December 1995

fpathconf, pathconf

fpathconf, pathconf—Get configuration values for files

SYNOPSIS

```
#include <unistd.h>
long fpathconf(int filedес, int name);
long pathconf(char *path, int name);
```

DESCRIPTION

`fpathconf()` gets a value for the configuration option `name` for the open file descriptor `filedes`.

`pathconf()` gets a value for configuration option `name` for the filename `path`.

The corresponding macros defined in `<unistd.h>` are the minimum values; if an application wants to take advantage of values that may change, a call to `fpathconf()` or `pathconf()` can be made, which may yield more liberal results.

Setting `name` equal to one of the following constants returns the following configuration options:

<code>_PC_LINK_MAX</code>	Returns the maximum number of links to the file. If <code>filedes</code> or <code>path</code> refers to a directory, the value applies to the whole directory. The corresponding macro is <code>_POSIX_LINK_MAX</code> .
<code>_PC_MAX_CANON</code>	Returns the maximum length of a formatted input line, where <code>filedes</code> or <code>path</code> must refer to a terminal. The corresponding macro is <code>_POSIX_MAX_CANON</code> .
<code>_PC_MAX_INPUT</code>	Returns the maximum length of an input line, where <code>filedes</code> or <code>path</code> must refer to a terminal. The corresponding macro is <code>_POSIX_MAX_INPUT</code> .
<code>_PC_NAME_MAX</code>	Returns the maximum length of a filename in the directory <code>path</code> or <code>filedes</code> the process is allowed to create. The corresponding macro is <code>_POSIX_NAME_MAX</code> .
<code>_PC_PATH_MAX</code>	Returns the maximum length of a relative pathname when <code>path</code> or <code>filedes</code> is the current working directory. The corresponding macro is <code>_POSIX_PATH_MAX</code> .
<code>_PC_PIPE_BUF</code>	Returns the size of the pipe buffer, where <code>filedes</code> must refer to a pipe or FIFO, and <code>path</code> must refer to a FIFO. The corresponding macro is <code>_POSIX_PIPE_BUF</code> .
<code>_PC_CHOWN_RESTRICTED</code>	Returns nonzero if the <code>chown(2)</code> call may not be used on this file. If <code>filedes</code> or <code>path</code> refers to a directory, this applies to all files in that directory. The corresponding macro is <code>_POSIX_CHOWN_RESTRICTED</code> .
<code>_PC_NO_TRUNC</code>	Returns nonzero if accessing filenames longer than <code>_POSIX_NAME_MAX</code> generates an error. The corresponding macro is <code>_POSIX_NO_TRUNC</code> .
<code>_PC_VDISABLE</code>	Returns nonzero if special character processing can be disabled, where <code>filedes</code> or <code>path</code> must refer to a terminal.

RETURN VALUE

The limit is returned, if one exists. If the system does not have a limit for the requested resource, `-1` is returned, and `errno` is unchanged. If there is an error, `-1` is returned, and `errno` is set to reflect the nature of the error.

CONFORMS TO

POSIX.1. Files with name lengths longer than the value returned for `name` equal to `_PC_NAME_MAX` may exist in the given directory.

Some returned values may be huge; they are not suitable for allocating memory.

SEE ALSO

`getconf(1)`, `statfs(2)`, `open(2)`, `sysconf(3)`

GNU, 4 April 1993

fread, fwrite

`fread`, `fwrite`—Binary stream input/output

SYNOPSIS

```
#include <stdio.h>
size_t fread(void *ptr, size_t size, size_t nmemb, FILE*stream);
size_t fwrite(void *ptr, size_t size, size_t nmemb, FILE*stream);
```

DESCRIPTION

The function `fread` reads `nmemb` elements of data, each `size` bytes long, from the stream pointed to by `stream`, storing them at the location given by `ptr`.

The function `fwrite` writes `nmemb` elements of data, each `size` bytes long, to the stream pointed to by `stream`, obtaining them from the location given by `ptr`.

RETURN VALUES

`fread` and `fwrite` return the number of items successfully read or written (that is, not the number of characters). If an error occurs, or the end-of-file is reached, the return value is a short item count (or 0).

`fread` does not distinguish between end-of-file and error, and callers must use `feof(3)` and `ferror(3)` to determine which occurred.

SEE ALSO

`feof(3)`, `ferror(3)`, `read(2)`, `write(2)`

STANDARDS

The functions `fread` and `fwrite` conform to ANSI C3.159-1989 ("ANSI C").

BSD Man Page, 17 May 1996

frexp

`frexp`—Converts floating-point number to fractional and integral components

SYNOPSIS

```
#include <math.h>
double frexp(double x, int *exp);
```

DESCRIPTION

The `frexp()` function is used to split the number `x` into a normalized fraction and an exponent that is stored in `exp`.

RETURN VALUE

The `frexp()` function returns the normalized fraction. If the argument `x` is not 0, the normalized fraction is `x` times a power of 2, and is always in the range $\frac{1}{2}$ (inclusive) to 1 (exclusive). If `x` is 0, the normalized fraction is 0, and 0 is stored in `exp`.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`ldexp(3)`, `modf(3)`

GNU, 6 June 1993

fgetpos, fseek, fsetpos, ftell, rewind

`fgetpos`, `fseek`, `fsetpos`, `ftell`, `rewind`—Reposition a stream

SYNOPSIS

```
#include <stdio.h>
int fseek(FILE *stream, longo fset, int whence);
long ftell(FILE *stream);
void rewind(FILE *stream);
int fgetpos(FILE *stream, fpos_t *pos);
int fsetpos(FILE *stream, fpos_t *pos);
```

DESCRIPTION

The `fseek` function sets the file position indicator for the stream pointed to by `stream`. The new position, measured in bytes, is obtained by adding offset bytes to the position specified by `whence`. If `whence` is set to `SEEK_SET`, `SEEK_CUR`, or `SEEK_END`, the offset is relative to the start of the file, the current position indicator, or end-of-file, respectively. A successful call to the `fseek` function clears the end-of-file indicator for the stream and undoes any effects of the `ungetc(3)` function on the same stream.

The `ftell` function obtains the current value of the file position indicator for the stream pointed to by `stream`.

The `rewind` function sets the file position indicator for the stream pointed to by `stream` to the beginning of the file. It is equivalent to

```
(void)fseek(stream, 0L, SEEK_SET);
```

except that the error indicator for the stream is also cleared. (See `clearerr(3)`.)

The `fgetpos` and `fsetpos` functions are alternate interfaces equivalent to `ftell` and `fseek` (with `whence` set to `SEEK_SET`), setting and storing the current value of the file offset into or from the object referenced by `pos`. On some non-UNIX systems, an `fpos_t` object may be a complex object, and these routines might be the only way to portably reposition a text stream.

RETURN VALUES

The `rewind` function returns no value. Upon successful completion, `fgetpos`, `fseek`, and `fsetpos` return 0, and `ftell` returns the current offset. Otherwise, -1 is returned, and the global variable `errno` is set to indicate the error.

ERRORS

EBAADF	The stream specified is not a seekable stream.
EINVAL	The <code>whence</code> argument to <code>fseek</code> was not <code>SEEK_SET</code> , <code>SEEK_END</code> , or <code>SEEK_CUR</code> .

The function `fgetpos`, `fseek`, `fsetpos`, and `ftell` might also fail and set `errno` for any of the errors specified for the routines `fflush(3)`, `fstat(2)`, `lseek(2)`, and `malloc(3)`.

SEE ALSO

`lseek(2)`

STANDARDS

The `fgetpos`, `fsetpos`, `fseek`, `ftell`, and `rewind` functions conform to ANSI C3.159-1989 (ANSI C).

BSD Man Page, 29 November 1993

ftime

`ftime`—Returns date and time

SYNOPSIS

```
#include <sys/timex.h>
int ftime(struct timex *tp);
```

DESCRIPTION

Return current date and time in `tp`, which is declared as follows:

```
struct timeb {
    time_t time;
    unsigned short millitm;
    short timezone;
    short dstflag;
};
```

RETURN VALUE

This function always returns 0.

NOTES

Under Linux, this function is implemented in a compatibility library instead of in the kernel.

CONFORMS TO

Version 7, BSD 4.3

Under BSD 4.3, this call is obsoleted by `gettimeofday(2)`.

SEE ALSO

`time(2)`

Linux, 24 July 1993

ftok

`ftok`—Converts a pathname and a project identifier to a System V IPC key

SYNOPSIS

```
#include <sys/types.h>
#include <sys/ipc.h>
key_t ftok (char *pathname, char proj);
```

DESCRIPTION

The function converts the pathname of an existing accessible file and a project identifier into a `key_t` type System V IPC key.

RETURN VALUE

On success, the return value will be the converted `key_t` value; otherwise it will be -1, with `errno` indicating the error as for the `stat(2)` system call.

BUGS

The generated `key_t` value is obtained by stating the disk file corresponding to `pathname` in order to get its i-node number and the minor device number of the filesystem on which the disk file resides, then by combining the 8-bit `proj` value along with the lower 16 bits of the inode number with the 8 bits of the minor device number. The algorithm does not guarantee a unique key value. In fact,

- Two different names linking to the same file produce the same key values.
- Using the lower 16 bits of the i-node number gives some chance (although usually small) to have the same key values for filenames referring to different inodes.
- Not discriminating among major device numbers gives some chance of collision (also usually small) for systems with multiple disk controllers.

SEE ALSO

`ipc(5)`, `msgget(2)`, `semget(2)`, `shmget(2)`, `stat(2)`

Linux 0.99.13, 1 November 1993

ftw

`ftw`—File tree walk

SYNOPSIS

```
#include <ftw.h>
int ftw(const char *directory,
int(*funcptr)(const char *file, struct stat *sb, int flag), int depth);
```

DESCRIPTION

`ftw()` walks through the directory tree, starting from the indicated `directory`. For each found entry in the tree, it calls `funcptr` with the full pathname of the entry relative to `directory`, a pointer to the `stat(2)` structure for the entry and an `int` whose value will be one of the following:

<code>FTW_F</code>	Item is a normal file
<code>FTW_D</code>	Item is a directory
<code>FTW_NS</code>	The <code>stat</code> failed on the item
<code>FTW_DNR</code>	Item is a directory which can't be read

Warning: Anything other than directories, such as symbolic links, gets the `FTW_F` tag.

`ftw()` recursively calls itself for traversing found directories. To avoid using up all a program's file descriptors, `depth` specifies the number of simultaneous open directories. When the depth is exceeded, `ftw()` will become slower because directories have to be closed and reopened.

To stop the tree walk, `funcptr` returns a nonzero value; this value will become the return value of `ftp()`. Otherwise, `ftw()` will continue until it has traversed the entire tree (in which case it will return 0), or until it hits an error such as a `malloc(3)` failure, in which case it will return -1.

Because `ftp()` uses dynamic data structures, the only safe way to exit a tree walk is to return a nonzero value. To handle interrupts, for example, mark that the interrupt occurred and return a nonzero value—don't use `longjmp(3)` unless the program is going to terminate.

SEE ALSO

`stat(2)`

Linux, 18 July 1993

gcvt

`gcvt`—Converts a floating-point number to a string

SYNOPSIS

```
#include <stdlib.h>
char *gcvt(double number, size_t ndigit, char *buf);
```

DESCRIPTION

The `gcvt()` function converts `number` to a minimal-length, NULL-terminated ASCII string and stores the result in `buf`. It produces `ndigit` significant digits in either `printf()` F format or E format.

RETURN VALUE

The `gcvt()` function returns the address of the string pointed to by `buf`.

SEE ALSO

`ecvt(3)`, `fcvt(3)`, `sprintf(3)`

29 March 1993

getcwd, get_current_dir_name, getwd

`getcwd`, `get_current_dir_name`, `getwd`—Get current working directory

SYNOPSIS

```
#include <unistd.h>
char *getcwd(char *buf, size_t size);
char *get_current_working_dir_name(void);
char *getwd(char *buf);
```

DESCRIPTION

The `getcwd()` function copies the absolute pathname of the current working directory to the array pointed to by `buf`, which is of length `size`.

If the current absolute pathname would require a buffer longer than `size` elements, `NULL` is returned, and `errno` is set to `ERANGE`; an application should check for this error, and allocate a larger buffer if necessary.

As an extension to the POSIX.1 standard, `getcwd()` allocates the buffer dynamically using `malloc()` if `buf` is `NULL` on call. In this case, the allocated buffer has the length `size` unless `size` is less than 0, when `buf` is allocated as large as necessary. It is possible (and, indeed, advisable) to free the buffers if they have been obtained this way.

`get_current_dir_name`, which is only prototyped if `__USE_GNU` is defined, will `malloc(3)` an array big enough to hold the current directory name. If the environment variable `PWD` is set, and its value is correct, that value will be returned.

`getwd`, which is only prototyped if `__USE_BSD` is defined, will not `malloc(3)` any memory. The `buf` argument should be a pointer to an array at least `PATH_MAX` bytes long. `getwd` returns only the first `PATH_MAX` bytes of the actual pathname.

RETURN VALUE

`NULL` on failure (for example, if the current directory is not readable), with `errno` set accordingly, and `buf` on success.

CONFORMS TO

POSIX.1

SEE ALSO

`chdir(2)`, `free(3)`, `malloc(3)`.

GNU, 21 July 1993

getdirentries

`getdirentries`—Gets directory entries in a filesystem-independent format

SYNOPSIS

```
#define __USE_BSD or #define __USE_MISC
#include <dirent.h>
ssize_t getdirentries(int fd, char *buf, size_t nbytes, off_t *basep);
```

DESCRIPTION

This function reads directory entries from the directory specified by *fd* into *buf*. At most, *nbytes* are read. Reading starts at offset **basep*, and **basep* is updated with the new position after reading.

RETURN VALUE

`getdirent` returns the number of bytes read, or 0 when at the end of the directory. If an error occurs, -1 is returned, and *errno* is set appropriately.

ERRORS

See the Linux library source code for details.

SEE ALSO

`open(2)`, `lseek(2)`

BSD/MISC, 22 July 1993

getenv

`getenv`—Gets an environment variable

SYNOPSIS

```
#include <stdlib.h>
char *getenv(const char *name);
```

DESCRIPTION

The `getenv()` function searches the environment list for a string that matches the string pointed to by *name*. The strings are of the form *name=value*.

RETURN VALUE

The `getenv()` function returns a pointer to the value in the environment, or NULL if there is no match.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`putenv(3)`, `setenv(3)`, `unsetenv(3)`

GNU, 3 April 1993

getgrent, setgrent, endgrent

`getgrent`, `setgrent`, `endgrent`—Get group file entry

SYNOPSIS

```
#include <grp.h>
#include <sys/types.h>
struct group *getgrent(void);
void setgrent(void);
void endgrent(void);
```


DESCRIPTION

The `getgrent()` function returns a pointer to a structure containing the group information from `/etc/group`. The first time it is called it returns the first entry; thereafter, it returns successive entries.

The `setgrent()` function rewinds the file pointer to the beginning of the `/etc/group` file.

The `endgrent()` function closes the `/etc/group` file.

The group structure is defined in `<grp.h>` as follows:

```
struct group {
    char    *gr_name;    /* group name */
    char    *gr_passwd;  /* group password */
    gid_t   gr_gid;      /* group id */
    char    **gr_mem;    /* group members */
};
```

RETURN VALUE

The `getgrent()` function returns the group information structure, or `NULL` if there are no more entries or an error occurs.

ERRORS

`ENOMEM` Insufficient memory to allocate group information structure.

FILES

`/etc/group` group database file

CONFORMS TO

SVID 3, BSD 4.3

SEE ALSO

`fgetgrent(3)`, `getgrnam(3)`, `getgrgid(3)`

GNU, 4 April 1993

getgrnam, getgrgid

getgrnam, getgrgid—Get group file entry

SYNOPSIS

```
#include <grp.h>
#include <sys/types.h>
struct group *getgrnam(const char *name);
struct group *getgrgid(gid_t gid);
```

DESCRIPTION

The `getgrnam()` function returns a pointer to a structure containing the group information from `/etc/group` for the entry that matches the group name `name`.

The `getgrgid()` function returns a pointer to a structure containing the group information from `/etc/group` for the entry that matches the group id `gid`.

The group structure is defined in `<grp.h>` as follows:

```
struct group {
    char    *gr_name;    /* group name */
    char    *gr_passwd;  /* group password */
```

```

        gid_t    gr_gid;        /* group id */
        char     **gr_mem;      /* group members */
};

```

RETURN VALUE

The `getgrnam()` and `getgrgid()` functions return the group information structure, or `NULL` if the matching entry is not found or an error occurs.

ERRORS

ENOMEM Insufficient memory to allocate group information structure.

FILES

`/etc/group` group database file

CONFORMS TO

SVID 3, POSIX, BSD 4.3

SEE ALSO

`fgetgrent(3)`, `getgrent(3)`, `setgrent(3)`, `endgrent(3)`

GNU, 4 April 1993

getlogin, cuserid

`getlogin`, `cuserid`—Get username

SYNOPSIS

```

#include <unistd.h>
char * getlogin ( void );
#include <stdio.h>
char * cuserid ( char *string );

```

DESCRIPTION

`getlogin` returns a pointer to a string containing the name of the user logged in on the controlling terminal of the process, or a null pointer if this information cannot be determined. The string is statically allocated and might be overwritten on subsequent calls to this function or to `cuserid`.

`cuserid` returns a pointer to a string containing a username associated with the effective user ID of the process. If `string` is not a null pointer, it should be an array that can hold at least `L_cuserid` characters; the string is returned in this array. Otherwise, a pointer to a string in a static area is returned. This string is statically allocated and might be overwritten on subsequent calls to this function or to `getlogin`.

The macro `L_cuserid` is an integer constant that indicates how long an array you might need to store a username. `L_cuserid` is declared in `stdio.h`.

These functions let your program positively identify the user who is running (`cuserid`) or the user who logged in this session (`getlogin`). (These can differ when `setuid` programs are involved.) The user cannot do anything to fool these functions.

For most purposes, it is more useful to use the environment variable `LOGNAME` to find out who the user is. This is more flexible precisely because the user can set `LOGNAME` arbitrarily.

ERRORS

ENOMEM Insufficient memory to allocate `passwd` structure.

FILES

The `/etc/passwd` password database file `/etc/utmp` (or `/var/adm/utmp`, or wherever your `utmp` file lives these days—the proper location depends on your `libc` version)

CONFORMS TO

POSIX.1. System V has a `cuserid` function that uses the real user ID rather than the effective user ID. The `cuserid` function was included in the 1988 version of POSIX, but was removed from the 1990 version.

BUGS

Unfortunately, it is often rather easy to fool `getlogin()`. Sometimes it does not work at all, because some program messed up the `utmp` file. Often, it gives only the first eight characters of the login name. The user currently logged in on the controlling tty of your program need not be the user who started it.

Nobody knows precisely what `cuserid()` does; so

- Avoid it in portable programs
- Avoid it altogether
- Use `getpwuid(geteuid())` instead, if that is what you meant.

Simply, *do not use* `cuserid()`.

SEE ALSO

`geteuid(2)`, `getuid(2)`

Linux 1.2.13, 3 September 1995

getmntent, setmntent, addmntent, endmntent, hasmntopt

`getmntent`, `setmntent`, `addmntent`, `endmntent`, `hasmntopt`—Get filesystem descriptor file entry

SYNOPSIS

```
#include <stdio.h>
#include <mntent.h>
FILE *setmntent(const char *filep, const char *type);
struct mntent *getmntent(FILE *filep);
int addmntent(FILE *filep, const struct mntent *mnt);
int endmntent(FILE *filep);
char *hasmntopt(const struct mntent *mnt, const char *opt);
```

DESCRIPTION

These routines are used to access the filesystem description file `/etc/fstab` and the mounted filesystem description file `/etc/mstab`.

The `setmntent()` function opens the filesystem description file `filep` and returns a file pointer that can be used by `getmntent()`. The argument `type` is the type of access required and can take the same values as the `mode` argument of `fopen(3)`.

The `getmntent()` function reads the next line from the filesystem description file `filep` and returns a pointer to a structure containing the broken-out fields from a line in the file. The pointer points to a static area of memory that is overwritten by subsequent calls to `getmntent()`.

The `addmntent()` function adds the `mntent` structure `mnt` to the end of the open file `filep`.

The `endmntent()` function closes the filesystem description file `filep`.

The `hasmntopt()` function scans the `mnt_opts` field of the `mntent` structure `mnt` for a substring that matches `opt`. (See `<mntent.h>` for valid mount options.)

The `mntent` structure is defined in `<mntent.h>` as follows:

```
struct mntent {
    char    *mnt_fstype;    /* name of mounted filesystem */
    char    *mnt_dir;       /* filesystem path prefix */
    char    *mnt_type;      /* mount type (see mntent.h) */
    char    *mnt_opts;      /* mount options (see mntent.h) */
    int     mnt_freq;       /* dump frequency in days */
    int     mnt_passno;     /* pass number on parallel fsck */
};
```

RETURN VALUE

The `getmntent()` function returns a pointer to the `mntent` structure or `NULL` on failure.

The `addmntent()` function returns 0 on success and 1 on failure.

The `endmntent()` functions always returns 1.

The `hasmntopt()` function returns the address of the substring if a match is found, and `NULL` otherwise.

FILES

`/etc/fstab` filesystem description file

`/etc/mtab` mounted filesystem description file

CONFORMS TO

BSD 4.3

SEE ALSO

`fopen(3)`, `fstab(5)`

27 June 1993

getnetent, getnetbyaddr, getnetbyname, setnetent, endnetent

`getnetent`, `getnetbyaddr`, `getnetbyname`, `setnetent`, `endnetent`—Get network entry

SYNTAX

```
#include <netdb.h>
struct netent *getnetent()
struct netent *getnetbyname(name)
char *name;
struct netent *getnetbyaddr(net, type)
long net; int type;
void setnetent(stayopen)
int stayopen;
void endnetent()
```

DESCRIPTION

The `getnetent`, `getnetbyname`, and `getnetbyaddr` subroutines each return a pointer to an object with the following structure, containing the broken-out fields of a line in the network database, `/etc/networks`:

```
struct netent {
    char    *n_name;       /* official name of net */
    char    **n_aliases;   /* alias list */
    int     n_addrtype;     /* net number type */
    long    n_net;         /* net number */
};
```

The members of this structure are

<code>n_name</code>	The official name of the network.
<code>n_aliases</code>	A zero-terminated list of alternate names for the network.
<code>n_addrtype</code>	The type of the network number returned: <code>AF_INET</code> .
<code>n_net</code>	The network number. Network numbers are returned in machine byte order.

If the `stayopen` flag on a `setnetent` subroutine is `NULL`, the network database is opened. Otherwise the `setnetent` has the effect of rewinding the network database. The `endnetent` may be called to close the network database when processing is complete.

The `getnetent` subroutine simply reads the next line whereas `getnetbyname` and `getnetbyaddr` search until a matching name or net number is found (or until EOF is encountered). The type must be `AF_INET`. The `getnetent` subroutine keeps a pointer in the database, allowing successive calls to be used to search the entire file.

A call to `setnetent` must be made before a while loop using `getnetent` to perform initialization, and an `endnetent` must be used after the loop. Both `getnetbyname` and `getnetbyaddr` make calls to `setnetent` and `endnetent`.

FILES

`/etc/networks`

DIAGNOSTICS

Null pointer (`0`) returned on EOF or error.

SEE ALSO

`networks(5)`, RFC 1101

HISTORY

The `getnetent()`, `getnetbyaddr()`, `getnetbyname()`, `setnetent()`, and `endnetent()` functions appeared in 4.2BSD.

BUGS

The data space used by these functions is static; if future use requires the data, it should be copied before any subsequent calls to these functions overwrite it. Only Internet network numbers are currently understood. Expecting network numbers to fit in no more than 32 bits is probably naive.

getopt

`getopt`—Parses command-line options

SYNOPSIS

```
#include <unistd.h>
int getopt(int argc, char * const argv[],
    const char *optstring);
extern char *optarg;
extern int optind, opterr, optopt;
#include <getopt.h>
int getopt_long(int argc, char * const argv[],

    const char *optstring,
    const struct option *longopts, int *longindex);
int getopt_long_only(int argc, char * const argv[],

    const char *optstring,
    const struct option *longopts, int *longindex);
```

DESCRIPTION

The `getopt()` function parses the command-line arguments. Its arguments `argc` and `argv` are the argument count and array as passed to the `main()` function on program invocation. An element of `argv` that starts with `-` (and is not exactly `-` or `--`) is an option element. The characters of this element (aside from the initial `-`) are option characters. If `getopt()` is called repeatedly, it returns successively each of the option characters from each of the option elements.

If `getopt()` finds another option character, it returns that character, updating the external variable `optind` and a static variable `nextchar` so that the next call to `getopt()` can resume the scan with the following option character or `argv` element.

If there are no more option characters, `getopt()` returns `EOF`. Then `optind` is the index in `argv` of the first `argv` element that is not an option.

`optstring` is a string containing the legitimate option characters. If such a character is followed by a colon, the option requires an argument, so `getopt` places a pointer to the following text in the same `argv` element, or the text of the following `argv` element, in `optarg`. Two colons mean an option takes an optional arg; if there is text in the current `argv` element, it is returned in `optarg`; otherwise, `optarg` is set to `0`.

By default, `getargs()` permutes the contents of `argv` as it scans, so that eventually all the non-options are at the end. Two other modes are also implemented. If the first character of `optstring` is `+` or the environment variable `POSIXLY_CORRECT` is set, option processing stops as soon as a non-option argument is encountered. If the first character of `optstring` is `-`, each non-option `argv` element is handled as if it were the argument of an option with character code 1. (This is used by programs that were written to expect options and other `argv` elements in any order and that care about the ordering of the two.) The special argument `-` forces an end of option-scanning regardless of the scanning mode.

If `getopt()` does not recognize an option character, it prints an error message to `stderr`, stores the character in `optopt`, and returns `?`. The calling program may prevent the error message by setting `opterr` to `0`.

The `getopt_long()` function works like `getopt()`, except that it also accepts long options, started out by two dashes. Long option names may be abbreviated if the abbreviation is unique or is an exact match for some defined option. A long option may take a parameter, of the form `--arg=param` or `--arg param`.

`longopts` is a pointer to the first element of an array of `struct option` declared in `<getopt.h>`:

```
as struct option {
    const char *name;
    int has_arg;
    int *flag;
    int val;
};
```

The meanings of the different fields are

<code>name</code>	The name of the long option.
<code>has_arg</code>	<code>no_argument</code> (or <code>0</code>) if the option does not take an argument, <code>required_argument</code> (or <code>1</code>) if the option requires an argument, or <code>optional_argument</code> (or <code>2</code>) if the option takes an optional argument.
<code>flag</code>	Specifies how results are returned for a long option. If <code>flag</code> is <code>NULL</code> , <code>getopt_long()</code> returns <code>val</code> . (For example, the calling program might set <code>val</code> to the equivalent short option character.) Otherwise, <code>getopt_long()</code> returns <code>0</code> , and <code>flag</code> points to a variable that is set to <code>val</code> if the option is found, but left unchanged if the option is not found.
<code>val</code>	The value to return or to load into the variable pointed to by <code>flag</code> .

The last element of the array has to be filled with zeroes.

If `longindex` is not `NULL`, it points to a variable that is set to the index of the long option relative to `longopts`.

`getopt_long_only()` is like `getopt_long()`, but `-` as well as `--` can indicate a long option. If an option that starts with `-` (not `--`) doesn't match a long option but does match a short option, it is parsed as a short option instead.

RETURN VALUE

The `getopt()` function returns the option character if the option was found successfully, `:` if there was a missing parameter for one of the options, `?` for an unknown option character, or `EOF` for the end of the option list.

`getopt_long()` and `getopt_long_only()` also return the option character when a short option is recognized. For a long option, they return `val` if `flag` is `NULL`, and `0` otherwise. Error and `EOF` returns are the same as for `getopt()`, plus `?` for an ambiguous match or an extraneous parameter.

ENVIRONMENT VARIABLES

`POSIXLY_CORRECT`

If this is set, option processing stops as soon as a non-option argument is encountered.

EXAMPLE

The following example program, from the source code, illustrates the use of `getopt_long()` with most of its features:

```
#include <stdio.h>
int
main (argc, argv)
    int argc;
    char **argv;
{
    int c;
    int digit_optind = 0;
    while (1)
    {
        int this_option_optind = optind ? optind : 1;
        int option_index = 0;
        static struct option long_options[] =
        {
            {"add", 1, 0, 0},
            {"append", 0, 0, 0},
            {"delete", 1, 0, 0},
            {"verbose", 0, 0, 0},
            {"create", 1, 0, 'c'},
            {"file", 1, 0, 0g, f0, 0, 0, 0}
        };
        c = getopt_long (argc, argv, "abc:d:012",
            long_options, &option_index);
        if (c == -1)
            break;
        switch(c)
        {
            case 0:
                printf ("option %s", long_options[option_index].name);
                if (optarg)
                    printf (" with arg %s", optarg);
                printf ("\n");
                break;
            case '0':
            case '1':
            case '2':
                if (digit_optind != 0 && digit_optind != this_option_optind)
                    printf ("digits occur in two different argv-elements.\n");
                digit_optind = this_option_optind;
                printf ("option %c\n", c);
                break;
            case 'a':
                printf ("option a\n");
                break;
            case 'b':
```

```

        printf ("option b\n");
        break;
    case 'c':
        printf ("option c with value '%s'\n", optarg);
        break;
    case 'd':
        printf ("option d with value '%s' \n", optarg);
        break;
    case '?':
        break;
    default:
        printf ("?? getopt returned character code 0%o ??\n", c);
    }
}
if (optind < argc)
{
    printf ("non-option ARGV-elements: ");
    while (optind < argc)
        printf ("%s ", argv[optind++]);
    printf ("\n");
}
exit (0);
}

```

BUGS

This man page is confusing.

CONFORMS TO

`getopt()`: POSIX.1, provided the environment variable `POSIXLY_CORRECT` is set. Otherwise, the elements of `argv` aren't really `const`, because they get permuted. They're set `const` in the prototype to be compatible with other systems.

GNU, 30 August 1995

getpass

`getpass`—Gets a password

SYNOPSIS

```

#include <pwd.h>
#include <unistd.h>
char *getpass( const char * prompt );

```

DESCRIPTION

The `getpass` function displays a prompt to, and reads in, a password from, `/dev/tty`. If this file is not accessible, `getpass` displays the prompt on the standard error output and reads from the standard input.

The password may be up to `_PASSWORD_LEN` (currently 128) characters in length. Any additional characters and the terminating newline character are discarded. (This might be different in Linux.)

`getpass` turns off character echoing while reading the password.

RETURN VALUES

`getpass` returns a pointer to the null-terminated password.

FILES

/dev/tty

SEE ALSO

crypt(3)

HISTORY

A `getpass` function appeared in Version 7 AT&T UNIX.

BUGS

The `getpass` function leaves its result in an internal static object and returns a pointer to that object. Subsequent calls to `getpass` will modify the same object.

The calling process should zero the password as soon as possible to avoid leaving the cleartext password visible in the process's address space.

BSD Man Page 29 November 1993

getprotoent, getprotobyname, getprotobynumber, setprotoent, endprotoent

getprotoent, getprotobyname, getprotobynumber, setprotoent, endprotoent—Get protocol entry

SYNOPSIS

```
#include <netdb.h>
struct protoent *getprotoent(void);
struct protoent *getprotobyname(const char *name);
struct protoent *getprotobynumber(int proto);
void setprotoent(int stayopen);
void endprotoent(void);
```

DESCRIPTION

The `getprotoent()` function reads the next line from the file `/etc/protocols` and returns a structure `protoent` containing the broken-out fields from the line. The `/etc/protocols` file is opened if necessary.

The `getprotobyname()` function returns a `protoent` structure for the line from `/etc/protocols` that matches the protocol name `name`.

The `getprotobynumber()` function returns a `protoent` structure for the line that matches the protocol number `number`.

The `setprotoent()` function opens and rewinds the `/etc/protocols` file. If `stayopen` is true (1), the file will not be closed between calls to `getprotobyname()` or `getprotobynumber()`.

The `endprotoent()` function closes `/etc/protocols`.

The `protoent` structure is defined in `<netdb.h>` as follows:

```
struct protoent {
    char    *p_name;        /* official protocol name */
    char    **p_aliases;    /* alias list */
    int     p_proto;        /* protocol number */
}
```

The members of the `protoent` structure are

<code>p_name</code>	The official name of the protocol.
<code>p_aliases</code>	A zero-terminated list of alternative names for the protocol.
<code>p_proto</code>	The protocol number.

RETURN VALUE

The `getprotoent()`, `getprotobyname()`, and `getprotobynumber()` functions return the `protoent` structure, or a `NULL` pointer if an error occurs or the end of the file is reached.

FILES

`/etc/protocols` protocol database file

CONFORMS TO

BSD 4.3

SEE ALSO

`getservent(3)`, `getnetent(3)`, `protocols(5)`

BSD, 24 April 1993

getpw

`getpw`—Reconstructs password line entry

SYNOPSIS

```
#include <pwd.h>
#include <sys/types.h>
int getpw(uid_t uid, char *buf);
```

DESCRIPTION

The `getpw()` function reconstructs the password line entry for the given user UID `uid` in the buffer `buf`. The returned buffer contains a line of format

```
name:passwd:uid:gid:gecos:dir:shell
```

The `passwd` structure is defined in `<pwd.h>` as follows:

```
struct passwd {
    char    *pw_name;      /*username*/
    char    *pw_passwd;    /* user password */
    uid_t   pw_uid;        /* user id */
    gid_t    pw_gid;        /* group id */
    char    *pw_gecos;     /* real name */
    char    *pw_dir;        /* home directory */
    char    *pw_shell;     /* shell program */
};
```

RETURN VALUE

The `getpw()` function returns `0` on success, or `-1` if an error occurs.

ERRORS

`ENOMEM` Insufficient memory to allocate `passwd` structure.

FILES

`/etc/passwd` Password database file

SEE ALSO

`fgetpwent(3)`, `getpwent(3)`, `setpwent(3)`, `endpwent(3)`, `getpwnam(3)`, `getpwuid(3)`, `putpwent(3)`, `passwd(5)`

GNU, 27 May 1996

getpwent, setpwent, endpwent

`getpwent`, `setpwent`, `endpwent`—get password file entry

SYNOPSIS

```
#include <pwd.h>
#include <sys/types.h>
struct passwd *getpwent(void);
void setpwent(void);
void endpwent(void);
```

DESCRIPTION

The `getpwent()` function returns a pointer to a structure containing the broken-out fields of a line from `/etc/passwd`. The first time it is called it returns the first entry; thereafter, it returns successive entries.

The `setpwent()` function rewinds the file pointer to the beginning of the `/etc/passwd` file.

The `endpwent()` function closes the `/etc/passwd` file.

The `passwd` structure is defined in `<pwd.h>` as follows:

```
struct passwd {
    char    *pw_name;      /* username */
    char    *pw_passwd;    /* user password */
    uid_t   pw_uid;        /* user id */
    gid_t    pw_gid;        /* group id */
    char    *pw_gecos;     /* real name */
    char    *pw_dir;       /* home directory */
    char    *pw_shell;     /* shell program */
};
```

RETURN VALUE

The `getpwent()` function returns the `passwd` structure, or `NULL` if there are no more entries or an error occurs.

ERRORS

`ENOMEM` Insufficient memory to allocate `passwd` structure.

FILES

`/etc/passwd` Password database file

CONFORMS TO

SVID 3, BSD 4.3

SEE ALSO

`fgetpwent(3)`, `getpwnam(3)`, `getpwuid(3)`, `getpw(3)`, `putpwent(3)`, `passwd(5)`.

GNU, 27 May 1996

getpwnam, getpwuid

getpwnam, getpwuid—Get password file entry

SYNOPSIS

```
#include <pwd.h>
#include <sys/types.h>
struct passwd *getpwnam(const char * name);
struct passwd *getpwuid(uid_t uid);
```

DESCRIPTION

The `getpwnam()` function returns a pointer to a structure containing the broken out fields of a line from `/etc/passwd` for the entry that matches the username `name`.

The `getpwuid()` function returns a pointer to a structure containing the broken-out fields of a line from `/etc/passwd` for the entry that matches the user UID `uid`.

The `passwd` structure is defined in `<pwd.h>` as follows:

```
struct passwd {
    char    *pw_name;        /*username*/
    char    *pw_passwd;      /* user password */
    uid_t   pw_uid;          /* user id */
    gid_t   pw_gid;          /* group id */
    char    *pw_gecos;       /* real name */
    char    *pw_dir;         /* home directory */
    char    *pw_shell;       /* shell program */
};
```

RETURN VALUE

The `getpwnam()` and `getpwuid()` functions return the `passwd` structure, or `NULL` if the matching entry is not found or an error occurs.

ERRORS

ENOMEM Insufficient memory to allocate `passwd` structure.

FILES

`/etc/passwd` Password database file

CONFORMS TO

SVID 3, POSIX, BSD 4.3

SEE ALSO

`fgetpwent(3)`, `getpwent(3)`, `setpwent(3)`, `endpwent(3)`, `getpw(3)`, `putpwent(3)`, `passwd(5)`

GNU, 27 May 1996

fgetc, fgets,getc, getchar, gets, ungetc

fgetc, fgets,getc, getchar, gets, ungetc—Input of characters and strings

SYNOPSIS

```
#include <stdio.h>
int fgetc(FILE *stream);
char *fgets(char *s,int size, FILE *stream);
```

```
int getc(FILE *stream);
int getchar(void);
char *gets(char *s);
int ungetc(int c, FILE *stream);
```

DESCRIPTION

`fgetc()` reads the next character from `stream` and returns it as an unsigned char cast to an int, or EOF on end of file or error.

`getc()` is equivalent to `fgetc()` except that it can be implemented as a macro that evaluates `stream` more than once.

`getchar()` is equivalent to `getc(stdin)`.

`gets()` reads a line from `stdin` into the buffer pointed to by `s` until either a terminating newline or EOF, which it replaces with `\0`. No check for buffer overrun is performed (see the following “Bus” section).

`fgets()` reads in at most one less than `n` characters from `stream` and stores them into the buffer pointed to by `s`. Reading stops after an EOF or a newline. If a newline is read, it is stored into the buffer. `\0` is stored after the last character in the buffer.

`ungetc()` pushes `c` back to `stream`, cast to unsigned char, where it is available for subsequent read operations. Pushed-back characters will be returned in reverse order; only one pushback is guaranteed.

Calls to the functions described here can be mixed with each other and with calls to other input functions from the `stdio` library for the same input stream.

RETURN VALUES

`fgetc()`, `getc()`, and `getchar()` return the character read as an unsigned char cast to an int, or EOF on end of file or error.

`gets()` and `fgets()` return `s` on success, and `NULL` on error or when end of file occurs while no characters have been read.

`ungetc()` returns `c` on success, or EOF on error.

CONFORMS TO

ANSI—C, POSIX.1

BUGS

Because it is impossible to tell without knowing the data in advance how many characters `gets()` will read, and because `gets()` will continue to store characters past the end of the buffer, it is extremely dangerous to use. It has been used to break computer security. Use `fgets()` instead.

It is not advisable to mix calls to input functions from the `stdio` library with low-level calls to `read()` for the file descriptor associated with the input stream; the results will be undefined and very probably not what you want.

SEE ALSO

`read(2)`, `write(2)`, `fopen(3)`, `fread(3)`, `scanf(3)`, `puts(3)`, `fseek(3)`, `ferror(3)`

GNU, 4 April 1993

getservent, getservbyname, getservbyport, setservent, endservent

`getservent`, `getservbyname`, `getservbyport`, `setservent`, `endservent`—Get service entry

SYNOPSIS

```
#include <netdb.h>
struct servent *getservent(void);
struct servent *getservbyname(const char *name, const char *proto);
struct servent *getservbyport(int port, const char *proto);
```

```
void setservent(int stayopen);
void endservent(void);
```

DESCRIPTION

The `getservent()` function reads the next line from the file `/etc/services` and returns a structure, `servent`, containing the broken out fields from the line. The `/etc/services` file is opened if necessary.

The `getservbyname()` function returns a `servent` structure for the line from `/etc/services` that matches the service name using protocol `proto`.

The `getservbyport()` function returns a `servent` structure for the line that matches the port `port` given in network byte order using protocol `proto`.

The `setservent()` function opens and rewinds the `/etc/services` file. If `stayopen` is true (1), the file will not be closed between calls to `getservbyname()` and `getservbyport()`.

The `endservent()` function closes `/etc/services`.

The `servent` structure is defined in `<netdb.h>` as follows:

```
struct servent {
    char *s_name; /* official service name */
    char **s_aliases; /* alias list */
    int s_port; /* port number */
    char *s_proto; /* protocol to use */
}
```

The members of the `servent` structure are:

<code>s_name</code>	The official name of the service.
<code>s_aliases</code>	A zero-terminated list of alternative names for the service.
<code>s_port</code>	The port number for the service, given in network byte order.
<code>s_proto</code>	The name of the protocol to use with this service.

RETURN VALUE

The `getservent()`, `getservbyname()`, and `getservbyport()` functions return the `servent` structure, or a `NULL` pointer if an error occurs or the end of the file is reached.

FILES

`/etc/services` Services database file

CONFORMS TO

BSD 4.3

SEE ALSO

`getprotoent(3)`, `getnetent(3)`, `services(5)`

BSD, 22 April 1996

getusershell, setusershell, endusershell

`getusershell`, `setusershell`, `endusershell`—Get legal user shells

SYNOPSIS

```
#include <unistd.h>
char *getusershell(void);
```

```
void setusershell(void);
void endusershell(void);
```

DESCRIPTION

The `getusershell()` function returns the next line from the file `/etc/shells`, opening the file if necessary. The line should contain the pathname of a valid user shell. If `/etc/shells` does not exist or is unreadable, `getusershell()` behaves as if `/bin/sh` and `/bin/csh` were listed in the file.

The `setusershell()` function rewinds `/etc/shells`.

The `endusershell()` function closes `/etc/shells`.

RETURN VALUE

The `getusershell()` function returns a NULL pointer on end of file.

FILES

`/etc/shells`

CONFORMS TO

BSD 4.3

SEE ALSO

`shells(5)`

BSD, 4 July 1993

getutent, getutid, getutline, pututline, setutent, endutent, utmpname

`getutent, getutid, getutline, pututline, setutent, endutent, utmpname`—Access utmp file entries

SYNOPSIS

```
#include <utmp.h>
struct utmp *getutent(void);
struct utmp *getutid(struct utmp *ut);
struct utmp *getutline(struct utmp *ut);
void pututline(struct utmp *ut);
void setutent(void);
void endutent(void);
void utmpname(const char *file);
```

DESCRIPTION

`utmpname()` sets the name of the utmp-format file for the other utmp functions to access. If `utmpname()` is not used to set the filename before the other functions are used, they assume `PATH_UTMP`, as defined in `<paths.h>`.

`setutent()` rewinds the file pointer to the beginning of the utmp file. It is generally a good idea to call it before any of the other functions.

`endutent()` closes the utmp file. It should be called when the user code is done accessing the file with the other functions.

`getutent()` reads a line from the current file position in the utmp file. It returns a pointer to a structure containing the fields of the line.

`getutid()` searches forward from the current file position in the utmp file based on `ut`. If `ut->ut_type` is `RUN_LVL`, `BOOT_TIME`, `NEW_TIME`, or `OLD_TIME`, `getutid()` will find the first entry whose `ut_type` field matches `ut->ut_type`. If `ut->ut_type` is

INIT_PROCESS, LOGIN_PROCESS, USER_PROCESS, or DEAD_PROCESS, `getutid()` will find the first entry whose `ut_id` field matches `ut->ut_id`.

`getutline()` searches forward from the current file position in the `utmp` file. It scans entries whose `ut_type` is `USER_PROCESS` or `LOGIN_PROCESS` and returns the first one whose `ut_line` field matches `ut->ut_line`.

`pututline()` writes the `utmp` structure `ut` into the `utmp` file. It uses `getutid()` to search for the proper place in the file to insert the new entry. If it cannot find an appropriate slot for `ut`, `pututline()` will append the new entry to the end of the file.

RETURN VALUE

`getutent()`, `getutid()`, and `getutline()` return a pointer to a struct `utmp`, which is defined in `<utmp.h>`.

FILES

`/var/run/utmp`—Database of currently logged-in users

`/var/log/wtmp`—Database of past user logins

CONFORMS TO

XPG 2, SVID 2, Linux FSSTND 1.2

SEE ALSO

`utmp(5)`

Linux libc 5.0.0, 22 March 1995

getw, putw

`getw`, `putw`—Input and output of words (ints)

SYNOPSIS

```
#include <stdio.h>
int getw(FILE *stream);
int putw(int w, FILE *stream);
```

DESCRIPTION

`getw` reads a word (that is, an `int`) from `stream`. It's provided for compatibility with SVID. I recommend you use `fread(3)` instead. `putw` writes the word `w` (that is, an `int`) to `stream`. It is provided for compatibility with SVID, but I recommend you use `fwrite(3)` instead.

RETURN VALUES

Normally, `getw` returns the word read, and `putw` returns the word written. On error, they return `Eof`.

BUGS

The value returned on error is also a legitimate data value. `ferror(3)` can be used to distinguish between the two cases.

CONFORMS TO

SVID

SEE ALSO

`fread(3)`, `fwrite(3)`, `ferror(3)`, `getc(3)`, `putc(3)`

GNU, 16 September 1995

glob, globfree

glob, globfree—Find pathnames matching a pattern; free memory from glob()

SYNOPSIS

```
#include <glob.h>
int glob(const char *pattern, int flags,
int errfunc(const char *epath, int eerrno),
glob_t *pglob);
void globfree(glob_t *pglob);
```

DESCRIPTION

The glob() function searches for all the pathnames matching pattern according to the rules used by the shell (see glob(7)). No tilde expansion or parameter substitution is done.

The globfree() function frees the dynamically allocated storage from an earlier call to glob().

The results of a glob() call are stored in the structure pointed to by pglob, which is a glob_t that is declared in <glob.h> as

```
typedef struct
{
    int gl_pathc;           /* Count of paths matched so far */
    char **gl_pathv;        /* List of matched pathnames. */
    int gl_offs;            /* Slots to reserve in 'gl_pathv'. */
    int gl_flags;           /* Flags for globbing */
} glob_t;
```

Results are stored in dynamically allocated storage.

The parameter flags is made up of bitwise OR of zero or more the following symbolic constants, which modify the of behavior of glob():

GLOB_ERR	Return on read error (because a directory does not have read permission, for example).
GLOB_MARK	Append a slash to each path which corresponds to a directory.
GLOB_NOSORT	Don't sort the returned pathnames (they are by default).
GLOB_DOOFS	pglob->gl_offs slots will be reserved at the beginning of the list of strings in pglob->pathv.
GLOB_NOCHECK	If no pattern matches, return the original pattern.
GLOB_APPEND	Append to the results of a previous call. Do not set this flag on the first invocation of glob().
GLOB_NOESCAPE	Meta characters cannot be quoted by backslashes.
GLOB_PERIOD	A leading period can be matched by meta characters.

If errfunc is not NULL, it will be called in case of an error with the arguments epath, a pointer to the path that failed, and eerrno, the value of errno as returned from one of the calls to opendir(), readdir(), or stat(). If errfunc returns nonzero, or if GLOB_ERR is set, glob() will terminate after the call to errfunc.

Upon successful return, pglob->gl_pathc contains the number of matched pathnames and pglob->gl_pathv a pointer to the list of matched pathnames. The first pointer after the last pathname is NULL.

It is possible to call glob() several times. In that case, the GLOB_APPEND flag has to be set in flags on the second and later invocations.

RETURN VALUES

On successful completion, glob() returns 0. Other possible returns are

GLOB_NOSPACE	For running out of memory,
GLOB_ABEND	For a read error, and
GLOB_NOMATCH	For no found matches.

EXAMPLES

One example of use is the following code, which simulates typing in the shell:

```
ls -l *.c ../*.c

glob_t globbuf;
globbuf.gl_offs = 2;
glob("*.c", GLOB_DOOFS, NULL, &globbuf);
glob("../*.c", GLOB_DOOFS | GLOB_APPEND, NULL, &globbuf);
globbuf.gl_pathv[0] = "ls";
globbuf.gl_pathv[1] = "-l";
execvp("ls", &globbuf.gl_pathv[0]);
```

CONFORMS TO

Proposed POSIX.2

BUGS

The `glob()` function may fail due to failure of underlying function calls, such as `malloc()` or `opendir()`. These will store their error code in `errno`.

POSIX.2 is not yet an approved standard; the information in this man page is subject to change.

SEE ALSO

`ls(1)`, `sh(1)`, `exec(2)`, `stat(2)`, `malloc(3)`, `opendir(3)`, `readdir(3)`, `wordexp(3)`, `glob(7)`

GNU, 13 May 1996

hosts_access, hosts_ctl

`hosts_access`, `hosts_ctl`—Access-control library functions

SYNOPSIS

```
#include "log_tcp.h"
extern int allow_severity;
extern int deny_severity;
int hosts_access(daemon, client)
char *daemon;
struct client_info *client;
int hosts_ctl(daemon, client_name, client_addr, client_user)
char *daemon;
char *client_name;
char *client_addr;
char *client_user;
```

DESCRIPTION

The routines described in this document are part of the `libwrap.a` library. They implement a pattern-based access-control language with optional shell commands that are executed when a pattern fires.

In all cases, the `daemon` argument should specify a daemon process name (`argv[0]` value). The client host address should be a valid address, or `FROM_UNKNOWN` if the address lookup failed. The client hostname and username should be empty strings if no information is available, `FROM_UNKNOWN` if the lookup failed, or an actual hostname or username.

`hosts_access()` consults the access-control tables described in the `hosts_access(5)` manual page. `hosts_access()` returns 0 if access should be denied.

`hosts_ctl()` is a wrapper around the `hosts_access()` routine with a perhaps more convenient interface (although it does not pass on enough information to support automated remote username lookups). `hosts_ctl()` returns 0 if access should be denied.

The `allow_severity` and `deny_severity` variables determine how accepted and rejected requests can be logged. They must be provided by the caller and can be modified by rules in the access-control tables.

DIAGNOSTICS

Problems are reported via the `syslog` daemon.

SEE ALSO

`hosts_access(5)` (format of the access control tables), `hosts_options(5)`, optional extensions to the base language

FILES

`/etc/hosts.access`, `/etc/hosts.deny` access-control tables

BUGS

The functions described here do not make copies of their string-valued arguments. Beware of data from functions that overwrite their results on each call.

`hosts_access()` uses the `strtok()` library function. This may interfere with other code that relies on `strtok()`.

AUTHOR

Wietse Venema (wietse@wzv.win.tue.nl)

Department of Mathematics and Computing Science

Eindhoven University of Technology

Den Dolech 2, P.O. Box 513, 5600 MB Eindhoven, The Netherlands

hcreate, hdestroy, hsearch

`hcreate`, `hdestroy`, `hsearch`—Hash table management

SYNOPSIS

```
#include <search.h>
ENTRY *hsearch(ENTRY item, ACTION action);
int hcreate(unsigned nel);
void hdestroy(void);
```

DESCRIPTION

These three functions allow the user to create a hash table that associates a key with any data.

First, the table must be created with the function `hcreate()`. `nel` is an estimate of the number of entries in the table. `hcreate()` may adjust this value upward to improve the performance of the resulting hash table. The GNU implementation of `hsearch()` will also enlarge the table if it gets nearly full. `malloc(3)` is used to allocate space for the table.

The corresponding function `hdestroy()` frees the memory occupied by the hash table so that a new table can be constructed.

`item` is of type `ENTRY`, which is a typedef defined in `<search.h>` and includes these elements:

```
typedef struct entry
{
    char *key;
    char *data;
} ENTRY;
```

`key` points to the zero-terminated ASCII string that is the search key. `data` points to the data associated with that key. (A pointer to a type other than character should be cast to pointer-to-character.) `hsearch()` searches the hash table for an item with the same key as `item`, and if successful returns a pointer to it. `action` determines what `hsearch()` does after an unsuccessful search. A value of `ENTER` instructs it to insert the new item, whereas a value of `FIND` means to return `NULL`.

RETURN VALUE

`hcreate()` returns `NULL` if the hash table cannot be successfully installed.

`hsearch()` returns `NULL` if `action` is `ENTER` and there is insufficient memory to expand the hash table, or if `action` is `FIND` and `item` cannot be found in the hash table.

CONFORMS TO

SVID, except that in SysV, the hash table cannot grow.

BUGS

The implementation can manage only one hash table at a time. Individual hash table entries can be added, but not deleted.

EXAMPLE

The following program inserts 24 items into a hash table and then prints some of them:

```
#include <stdio.h>
#include <search.h>
char *data[]={ "alpha", "bravo", "charley", "delta",
    "echo", "foxtrot", "golf", "hotel", "india", "juliette",
    "kilo", "lima", "mike", "november", "oscar", "papa",
    "quebec", "romeo", "sierra", "tango", "uniform",
    "victor", "whiskey", "x-ray", "yankee", "zulu"
};
int main()
{
    ENTRY e, *ep;
    int i;
    /* start with small table, and let it grow */
    hcreate(3);
    for (i = 0; i < 24; i++)
    {
        e.key = data[i];
        /* data is just an integer, instead of a pointer
           to something */
        e.data = (char *)i;
        ep = hsearch(e, ENTER);
        /* there should be no failures */
        if(ep == NULL) {fprintf(stderr, "entry failed\n"); exit(1);}
    }
    for (i = 22; i < 26; i++)
        /* print two entries from the table, and show that
           two are not in the table */
    {
        e.key = data[i];
        ep = hsearch(e, FIND);
        printf("%9.9s -> %9.9s:%d\n", e.key, ep?ep->key:"NULL",
            ep?(int)(ep->data):0);
    }
    return 0;
}
```

SEE ALSO

`bsearch(3)`, `lsearch(3)`, `tsearch(3)`, `malloc(3)`

hypot

hypot—Euclidean distance function

SYNOPSIS

```
#include <math.h>
double hypot(double x, double y);
```

DESCRIPTION

The `hypot()` function returns the `sqrt(x*x+y*y)`. This is the length of the hypotenuse of a right-angle triangle with sides of length `x` and `y`, or the distance of the point `(x, y)` from the origin.

CONFORMS TO

SVID 3, BSD 4.3

SEE ALSO

`sqrt(3)`

25 June 1993

index, rindex

index, rindex—Locate character in string

SYNOPSIS

```
#include <string.h>
char *index(const char *s, int c);
char *rindex(const char *s, int c);
```

DESCRIPTION

The `index()` function returns a pointer to the first occurrence of the character `c` in the string `s`.

The `rindex()` function returns a pointer to the last occurrence of the character `c` in the string `s`.

The terminating NULL character is considered to be a part of the strings.

RETURN VALUE

The `index()` and `rindex()` functions return a pointer to the matched character, or NULL if the character is not found.

CONFORMS TO

BSD 4.3

SEE ALSO

`memchr(3)`, `strchr(3)`, `strpbrk(3)`, `strrchr(3)`, `strsep(3)`, `strspn(3)`, `strstr(3)`, `strtok(3)`

GNU, 12 April 1993

inet_aton, inet_addr, inet_network, inet_ntoa, inet_makeaddr, inet_lnaof, inet_netof

`inet_aton`, `inet_addr`, `inet_network`, `inet_ntoa`, `inet_makeaddr`, `inet_lnaof`, `inet_netof`—Internet address—manipulation routines

SYNOPSIS

```
#include <sys/socket.h>
#include <netinet/in.h>
#include <arpa/inet.h>
int inet_aton(const char *cp, struct in_addr *inp);
unsigned long int inet_addr(const char *cp);
unsigned long int inet_network(const char *cp);
char *inet_ntoa(struct in_addr in);
struct in_addr inet_makeaddr(int net, int host);
unsigned long int inet_lnaof(struct in_addr in);
unsigned long int inet_netof(struct in_addr in);
```

DESCRIPTION

`inet_aton()` converts the Internet host address `cp` from the standard numbers-and-dots notation into binary data and stores it in the structure that `inp` points to. `inet_aton` returns nonzero if the address is valid, and 0 if it is not.

The `inet_addr()` function converts the Internet host address `cp` from numbers-and-dots notation into binary data in network byte order. If the input is invalid, -1 is returned. This is an obsolete interface to `inet_aton`; it is obsolete because -1 is a valid address (255.255.255.255), and `inet_aton` provides a cleaner way to indicate error return.

The `inet_network()` function extracts the network number in network byte order from the address `cp` in numbers-and-dots notation. If the input is invalid, -1 is returned.

The `inet_ntoa()` function converts the Internet host address given in network byte order to a string in standard numbers-and-dots notation. The string is returned in a statically allocated buffer, which subsequent calls will overwrite.

The `inet_makeaddr()` function makes an Internet host address in network byte order by combining the network number `net` with the local address `host` in network `net`, both in local host byte order.

The `inet_lnaof()` function returns the local host address part of the Internet address `in`. The local host address is returned in local host byte order.

The `inet_netof()` function returns the network number part of the Internet address `in`. The network number is returned in local host byte order.

The structure `in_addr` as used in `inet_ntoa()`, `inet_makeaddr()`, `inet_lnaof()`, and `inet_netof()` is defined in `netinet/in.h` as

```
struct in_addr {
    unsigned long int s_addr;
}
```

Note that on the i80x86 the host byte order is Least Significant Byte first, whereas the network byte order, as used on the Internet, is Most Significant Byte first.

CONFORMS TO

BSD 4.3

SEE ALSO

`gethostbyname(3)`, `getnetent(3)`, `hosts(5)`, `networks(5)`

BSD, 3 September 1995

infnan

`infnan`—Deals with infinite or not-a-number (NaN) result

SYNOPSIS

```
#include <math.h>
double infnan(int error);
```

DESCRIPTION

The `infnan()` function returns a suitable value for infinity and not-a-number (NaN) results. The value of `error` can be `ERANGE` to represent infinity, or anything else to represent NaN. `errno` is also set.

RETURN VALUE

If `error` is `ERANGE` (Infinity), `HUGE_VAL` is returned.

If `error` is `-ERANGE` (-Infinity), `-HUGE_VAL` is returned.

If `error` is anything else, NaN is returned.

ERRORS

<code>ERANGE</code>	The value of <code>error</code> is positive or negative infinity.
<code>EDOM</code>	The value of <code>error</code> is not-a-number (NaN).

CONFORMS TO

BSD 4.3

GNU, 2 June 1993

initgroups

`initgroups`—Initializes the supplementary group access list

SYNOPSIS

```
#include <grp.h>
#include <sys/types.h>
int initgroups(const char *user, gid_t group);
```

DESCRIPTION

The `initgroups()` function initializes the group access list by reading the group database `/etc/group` and using all groups of which `user` is a member. The additional group `group` is also added to the list.

RETURN VALUE

The `initgroups()` function returns 0 on success, or -1 if an error occurs.

ERRORS

<code>EPERM</code>	The calling process does not have sufficient privileges.
<code>ENOMEM</code>	Insufficient memory to allocate group information structure.

FILES

`/etc/group` group database file

CONFORMS TO

SVID 3, BSD 4.3

SEE ALSO

`getgroups(2)`, `setgroups(2)`

GNU, 5 April 1993

inndcomm

inndcomm—INND communication part of InterNetNews library

SYNOPSIS

```
#include "inndcomm.h"
int ICCopen()
int ICCclose()
void ICCsettimeout(i)
int i;
int ICCcommand(cmd, argv, reply)
char cmd;
char *argv[];
char **reply;
int ICCcancel(mesgid)
char *mesgid;
int ICCreserve(why)
char *why;
int ICCpause(why)
char *why;
int ICCgo(why)
char *why;
extern char *ICCfailure;
```

DESCRIPTION

The routines described in this manual page are part of the InterNetNews library, `libinn(3)`. They are used to send commands to a running `innd(8)` daemon on the local host. The letters *ICC* stand for Innd Control Command.

`ICCopen` creates a UNIX-domain datagram socket and binds it to the server's control socket. It returns `-1` on failure or `0` on success. This routine must be called before any other routine.

`ICCclose` closes any descriptors that have been created by `ICCopen`. It returns `-1` on failure or `0` on success.

`ICCsettimeout` can be called before any of the following routines to determine how long the library should wait before giving up on getting the server's reply. This is done by setting and catching a `SIGALRM` signal(2). If the timeout is less than 0, no reply will be waited for. The `SC_SHUTDOWN`, `SC_XABORT`, and `SC_XEXEC` commands do not get a reply either. The default, which can be obtained by setting the timeout to 0, is to wait until the server replies.

`ICCcommand` sends the command `cmd` with parameters `argv` to the server. It returns `-1` on error. If the server replies, and `reply` is not `NULL`, it will be filled in with an allocated buffer that contains the full text of the server's reply. This buffer is a string in the form `<digits><space><text>` where `digits` is the text value of the recommended exit code; `0` indicates success. Replies longer than 4,000 bytes will be truncated. The possible values of `cmd` are defined in the `inndcomm.h` header file. The parameters for each command are described in `ctlinnd(8)`. This routine returns `-1` on communication failure; on success it returns the exit status sent by the server, which will never be negative.

`ICCcancel` sends a cancel message to the server. `mesgid` is the message ID of the article that should be canceled. The return value is the same as for `ICCcommand`.

`ICCPause`, `ICCreserve`, and `ICCgo` send a pause, reserve, or go command to the server, respectively. If `ICCreserve` is used, the `why` value used in the `ICCPause` invocation must match; the value used in the `ICCgo` invocation must always match the one used in the `ICCPause` invocation. The return value for all three routines is the same as for `ICCcommand`.

If any of these routines fail, the `ICCfailure` variable will identify the system call that failed.

HISTORY

Written by Rich Salz (`rsalz@uunet.uu.net`) for InterNetNews.

SEE ALSO

`ctlinnd(8)`, `innd(8)`, `libinn(3)`.

insque, remque

insque, remque—Insert/Remove an item from a queue

SYNOPSIS

```
#include <stdlib.h>
void insque(struct qelem * elem, struct qelem * prev);
void remque(struct qelem*elem);
```

DESCRIPTION

insque() and remque() are functions for manipulating queues made from doubly linked lists. Each element in this list is of type struct qelem.

The qelem structure is defined as

```
struct qelem {
    struct qelem *q_forw;
    struct qelem *q_back;
    char q_data[1];
};
```

insque() inserts the element pointed to by elem immediately after the element pointed to by prev, which must *not* be NULL.

remque() removes the element pointed to by elem from the doubly linked list.

CONFORMS TO

SVR4

BUGS

The q_data field is sometimes defined to be of type char *, and under Solaris 2.x, it doesn't appear to exist at all.

The location of the prototypes for these functions differs among several versions of UNIX. Some systems place them in <search.h>, others in <string.h>. Linux places them in <stdlib.h> because that seems to make the most sense.

Some versions of UNIX (such as HP-UX 10.x) do not define a struct qelem but rather have the arguments to insque() and remque() be of type void *.

GNU, 30 October 1996

isalnum, isalpha, isascii, isblank, iscntrl, isdigit, isgraph, islower, isprint, ispunct, isspace, isupper, isxdigit

isalnum, isalpha, isascii, isblank, iscntrl, isdigit, isgraph, islower, isprint, ispunct, isspace, isupper, isxdigit—Character classification routines

SYNOPSIS

```
#include <ctype.h>
int isalnum (int c);
int isalpha (int c);
int isascii (int c);
int isblank (int c);
int iscntrl (int c);
int isdigit (int c);
int isgraph (int c);
int islower (int c);
int isprint (int c);
int ispunct (int c);
```

```
int isspace (int c);
int isupper (int c);
int isxdigit (int c);
```

DESCRIPTION

These functions check whether *c*, which must have the value of an unsigned char or EOF, falls into a certain character class according to the current locale:

<code>isalnum()</code>	Checks for an alphanumeric character; it is equivalent to <code>(isalpha(c) isdigit(c))</code> .
<code>isalpha()</code>	Checks for an alphabetic character; in the standard C locale, it is equivalent to <code>(isupper(c) islower(c))</code> . In some locales, there may be additional characters for which <code>isalpha()</code> is true—letters that are neither uppercase nor lowercase.
<code>isascii()</code>	Checks whether <i>c</i> is a 7-bit unsigned char value that fits into the ASCII character set. This function is a BSD extension and is also an SVID extension.
<code>isblank()</code>	Checks for a blank character; that is, a space or a tab. This function is a GNU extension.
<code>iscntrl()</code>	Checks for a control character.
<code>isdigit()</code>	Checks for a digit (0 through 9).
<code>isgraph()</code>	Checks for any printable character except space.
<code>islower()</code>	Checks for a lowercase character.
<code>isprint()</code>	Checks for any printable character, including space.
<code>ispunct()</code>	Checks for any printable character that is not a space or an alphanumeric character.
<code>isspace()</code>	Checks for whitespace characters. They are space, form-feed ('\f'), newline ('\n'), carriage return ('\r'), horizontal tab ('\t'), and vertical tab ('\v').
<code>isupper()</code>	Checks for an uppercase letter.
<code>isxdigit()</code>	Checks for a hexadecimal digit (that is, one of 0 1 2 3 4 5 6 7 8 9 0 a b c d e f A B C D E F).

RETURN VALUE

The values returned are nonzero if the character *c* falls into the tested class, and 0 if it does not.

CONFORMS TO

ANSI C, BSD 4.3. `isascii()` is a BSD extension and is also an SVID extension. `isblank()` is a GNU extension.

BUGS

The details of what characters belong in which class depend on the current locale. For example, `isupper()` will not recognize an A with an umlaut (Ä) as an uppercase letter in the default C locale.

SEE ALSO

`tolower(3)`, `toupper(3)`, `setlocale(3)`, `ascii(7)`, `locale(7)`

GNU, 2 September 1995

isatty

`isatty`—Tests whether this descriptor refers to a terminal

SYNOPSIS

```
#include <unistd.h>
int isatty (int desc );
```

DESCRIPTION

`isatty` returns 1 if *desc* is an open descriptor connected to a terminal, and 0 otherwise.

CONFORMS TO

SVID, AT&T, X/OPEN, BSD 4.3

SEE ALSO

fstat(2), ttyname(3)

Linux, 20 April 1995

isinf, isnan, finite

isinf, isnan, finite—Test for infinity or not-a-number (NaN)

SYNOPSIS

```
#include <math.h>
int isinf(double value);
int isnan(double value);
int finite(double value);
```

DESCRIPTION

The `isinf()` function returns `-1` if `value` represents negative infinity, `1` if `value` represents positive infinity, and `0` otherwise.

The `isnan()` function returns a nonzero value if `value` is not-a-number (NaN), and `0` otherwise.

The `finite()` function returns a nonzero value if `value` is finite or is not a not-a-number (NaN) value, and `0` otherwise.

CONFORMS TO

BSD 4.3

GNU, 2 June 1993

j0, j1, jn, y0, y1, yn

j0, j1, jn, y0, y1, yn—Bessel functions

SYNOPSIS

```
#include <math.h>
double j0(double x);
double j1(double x);
double jn(int n, double x);
double y0(double x);
double y1(double x);
double yn(int n, double x);
```

DESCRIPTION

The `j0()` and `j1()` functions return Bessel functions of `x` of the first kind of orders 0 and 1, respectively. The `jn()` function returns the Bessel function of `x` of the first kind of order `n`.

The `y0()` and `y1()` functions return Bessel functions of `x` of the second kind, orders 0 and 1, respectively. The `yn()` function returns the Bessel function of `x` of the second kind, order `n`.

For the functions `y0()`, `y1()` and `yn()`, the value of `x` must be positive. For negative values of `x`, these functions return `-HUGE_VAL`.

CONFORMS TO

SVID 3, BSD 4.3

BUGS

There are errors of up to $2e-16$ in the values returned by `j0()`, `j1()`, and `jn()` for values of `x` between -8 and 8 .

26 June 1993

killpg

`killpg`—Sends a signal to all members of a process group

SYNOPSIS

```
#include <signal.h>
int killpg(pid_t pidgrp, int signal);
```

DESCRIPTION

The `killpg()` function causes the signal `signal` to be sent to all the processes in the process group `pidgrp` or to the processes' own process group if `pidgrp` is equal to `0`.

It is equivalent to `kill(-pidgrp, signal);`.

RETURN VALUE

The value returned is -1 on error, or 0 for success.

ERRORS

Errors are returned in `errno` and can be one of the following:

<code>EINVAL</code>	Signal is invalid.
<code>ESRCH</code>	Process group does not exist.
<code>EPERM</code>	The user ID of the calling process is not equal to that of the process the signal is sent to, and the user ID is not that of the super-user.

SEE ALSO

`kill(2)`, `signal(2)`, `signal(7)`

GNU, 4 April 1993

labs

`labs`—Computes the absolute value of a long integer

SYNOPSIS

```
#include <stdlib.h>
long int labs(long int j);
```

DESCRIPTION

The `labs()` function computes the absolute value of the long integer argument `j`.

RETURN VALUE

Returns the absolute value of the long integer argument.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

NOTES

Trying to take the absolute value of the most negative integer is not defined.

SEE ALSO

`abs(3)`, `ceil(3)`, `floor(3)`, `fabs(3)`, `rint(3)`

GNU, 6 June 1993

ldexp

`ldexp`—Multiplies floating-point number by integral power of 2

SYNOPSIS

```
#include <math.h>
double ldexp(double x, int exp);
```

DESCRIPTION

The `ldexp()` function returns the result of multiplying the floating-point number `x` by 2 raised to the power `exp`.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`frexp(3)`, `modf(3)`

BSD, 6 June 1993

ldiv

`ldiv`—Computes the quotient and remainder of long integer division

SYNOPSIS

```
#include <stdlib.h>
ldiv_t ldiv(long int numer, long int denom);
```

DESCRIPTION

The `ldiv()` function computes the value `numer/denom` and returns the quotient and remainder in a structure named `ldiv_t` that contains two long integer members named `quot` and `rem`.

RETURN VALUE

The `ldiv_t` structure.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

SEE ALSO

`div(3)`

GNU, 29 March 1993

lgamma

lgamma—Logs gamma function

SYNOPSIS

```
#include <math.h>
double lgamma(double x);
```

DESCRIPTION

The `lgamma()` function returns the log of the absolute value of the Gamma function. The sign of the Gamma function is returned in the external integer `signgam`.

For negative integer values of `x`, `lgamma()` returns `HUGE_VAL`, and `errno` is set to `ERANGE`.

ERRORS

`ERANGE` Invalid argument—negative integer value of `x`.

CONFORMS TO

SVID 3, BSD 4.3

SEE ALSO

`infnan(3)`

BSD, 25 June 1993

libinn

libinn—InterNetNews library routines

SYNOPSIS

```
#include "libinn.h"
typedef struct _TIMEINFO {
    time_t time;
    long usec;
    long tzone;
} TIMEINFO;

char *GenerateMessageID()

void HeaderCleanFrom(from)
char *from;

char *HeaderFind(Article, Header, size)
char *Article;
char *Header;
int size;

FILE *CAopen(FromServer, ToServer)
FILE *FromServer;
FILE *ToServer;

FILE *CAListopen(FromServer, ToServer, request)
FILE *FromServer;
FILE *ToServer;
char *request;
```

```
void CAClose()

struct _DDHANDLE *DDstart(FromServer, ToServer)
FILE *FromServer;
FILE *ToServer;
} DDHANDLE;

void DDcheck(h, group)
DDHANDLE *h;
char *group;

char * DDend(h)
DDHANDLE *h;

void CloseOnExec(fd, flag)
int fd;
int flag;

int SetNonBlocking(fd, flag)
int fd;
int flag;

int LockFile(fd, flag)
int fd;
int flag;

char * GetConfigValue(value)
char *value;

char * GetFileConfigValue(value)
char *value;

char * GetFQDN()

char * GetModeratorAddress(group)
char *group;

int GetResourceUsage(usertime, systime)
double *usertime;
double *systime;

int GetTimeInfo(now)
TIMEINFO *now;

int NNTPlocalopen(FromServerp, ToServerp, errbuff)
FILE **FromServerp;
FILE **ToServerp;
char *errbuff;

int NNTPremoteopen(FromServerp, ToServerp, errbuff)
FILE **FromServerp;
FILE **ToServerp;
char *errbuff;

int NNTPconnect(host, FromServerp, ToServerp, errbuff)
char *host;
FILE **FromServerp;
FILE **ToServerp;
char *errbuff;

int NNTPcheckarticle(text)
```

```

char *text;

int NNTPsendarticle(text, ToServer, Terminate)
char *text;
FILE *ToServer;
int Terminate;

int NNTPsendpassword(server, FromServer, ToServer)
char *server;
FILE *FromServer;
FILE *ToServer;

void Radix32(value, p)
unsigned long value;
char *p;

char * ReadInFile(name, Sbp)
char *name;
struct stat *Sbp;

char * ReadInDescriptor(fd, Sbp)
int fd;
struct stat *Sbp;

char * INNVersion()

```

DESCRIPTION

`libinn` is a library of utility routines for manipulating Usenet articles and related data. It is not necessary to use the header file `libinn.h`; if it is not available, it is only necessary to properly declare the `TIMEINFO` datatype, as shown in the preceding code.

`GenerateMessageID` uses the current time, process ID, and fully qualified domain name of the local host to create a Message ID header that is highly likely to be unique. The returned value points to static space that is reused on subsequent calls.

`HeaderCleanFrom` removes the extraneous information from the value of a `From` or `Reply-To` header and leaves just the official mailing address. In particular, the following transformations are made to the `from` parameter:

```

address -> address
address (stuff) -> address
stuff <address>-> address

```

The transformations are simple and are based on RFC 1036, which limits the format of the header.

`HeaderFind` searches through `Article` looking for the specified `Header`. `size` should be the length of the header name. It returns a pointer to the value of the header, skipping leading whitespace, or `NULL` if the header cannot be found. `Article` should be a standard C string containing the text of the article; the end of a header is indicated by a blank line: two consecutive `\n` characters.

`CAopen` and `CAClose` provide news clients with access to the active file; the CA stands for Client Active. `CAopen` opens the `active(5)` file for reading. It returns a pointer to an open `FILE`, or `NULL` on error. If a local or an NFS-mounted copy exists, `CAopen` will use that file. The `FromServer` and `ToServer` parameters should be `FILE`s connected to the NNTP server for input and output, respectively. (See the discussions of `NNTPremoteopen` and `NNTPlocalopen` later in this section.) If either parameter is `NULL`, `CAopen` will just return `NULL` if the file is not locally available. If neither is `NULL`, `CAopen` will use them to query the NNTP server using the “list” command to make a local temporary copy.

The `CAlistopen` sends a “list” command to the server and returns a temporary file containing the results. The `request` parameter, if not `NULL`, will be sent as an argument to the command. Unlike `CAopen`, this routine will never use a locally available copy of the active file.

`CAClose` closes the active file and removes any temporary file that might have been created by `CAopen` or `CAlistopen`.

`CloseOnExec` can make a descriptor *close-on-exec* so that it is not shared with any child processes. If the flag is nonzero, the file is so marked; if it is 0, the close-on-exec mode is cleared.

`DDstart`, `DDcheck`, and `DDend` are used to set the `Distribution` header; the `DD` stands for `Default Distribution`. The `distrib.pats(5)` file is consulted to determine the proper value for the `Distribution` header after all newsgroups have been checked. `DDstart` begins the parsing. It returns a pointer to an opaque handle that should be used on subsequent calls. The `FromServer` and `ToServer` parameters should be `FILES` connected to the NNTP server for input and output, respectively. If either parameter is `NULL`, an empty default will ultimately be returned if the file is not locally available.

`DDcheck` should be called with the handle, `h`, returned by `DDstart` and a new group, `group`, to check. It can be called as often as necessary.

`DDend` releases any state maintained in the handle and returns an allocated copy of the text that should be used for the `Distribution` header.

`SetNonBlocking` enables (if `flag` is nonzero) or disables (if `flag` is 0) non-blocking I/O on the indicated descriptor. It returns -1 on failure and 0 on success.

`LockFile` tries to lock the file descriptor `fd`. If `flag` is nonzero it will block until the lock can be made; otherwise it will return -1 if the file cannot be locked. It returns -1 on failure and 0 on success.

`GetConfigValue` returns the value of the specified configuration parameter. (See `inn.conf(5)` for details on the parameters and their interpretation.) The returned value points to static space that is reused on subsequent calls.

`GetFileConfigValue` returns the specified configuration parameter from the `inn.conf` file without checking for any defaults. The returned value points to static space that is reused on subsequent calls, or `NULL` if the value is not present.

`GetFQDN` returns the fully qualified domain name of the local host. The returned value points to static space that is reused on subsequent calls, or `NULL` on error.

`GetModeratorAddress` returns the mailing address of the moderator for the specified group or `NULL` on error. (See `moderators(5)` for details on how the address is determined.) `GetModeratorAddress` does no checking to see if the specified group is actually moderated. The returned value points to static space that is reused on subsequent calls.

`GetResourceUsage` fills in the `usertime` and `systime` parameters with the total user and system time used by the current process and any children it may have spawned. It gets the values by doing a `times(2)` system call. It returns -1 on failure, or 0 on success.

`GetTimeInfo` fills in the `now` parameter with information about the current time and `tzone`. The `time` and `usec` fields will be filled in by a call to `gettimeofday(2)`. The `time` field will be filled in by a call to `time(2)`, and the `usec` field will be set to 0. The `tzone` field will be filled in with the current offset from GMT. This is done by calling `localtime(3)` and taking the value of the `tm_gmtoff` field, negating it, and dividing it by 60. This is done by calling `localtime(3)` and comparing the value with that returned by a call to `gmtime(3)`. For efficiency, the `tzone` field is only recalculated if more than an hour has passed since the last time `GetTimeInfo` was called. This routine returns -1 on failure, and 0 on success.

`NNTPlocalopen` opens a connection to the private port of an InterNetNews server running on the local host. It returns -1 on failure, or 0 on success. `FromServerp` and `ToServerp` will be filled in with `FILES` that can be used to communicate with the server. `errbuff` can either be `NULL` or a pointer to a buffer at least 512 bytes long. If it is not `NULL`, and the server refuses the connection, it will be filled in with the text of the server's reply. This routine is not for general use; it is a subroutine for compatibility with systems that have UNIX-domain stream sockets. It always returns -1.

`NNTPremoteopen` does the same as `NNTPlocalopen`, except that it calls `GetConfigValue` to find the name of the local server and opens a connection to the standard NNTP port. Any client program can use this routine. It returns -1 on failure, or 0 on success.

`NNTPconnect` is the same as `NNTPremoteopen`, except that the desired host is given as the `host` parameter.

`NNTPcheckarticle` verifies that the text meets the NNTP limitations on line length. It returns -1 on failure, or 0 if the text is valid.

`NNTPsendarticle` writes text on `ToServer` using NNTP conventions for line termination. The text should consist of one or more lines ending with a newline. If `Terminate` is nonzero, the routine will also write the NNTP data-termination marker on the stream. It returns `-1` on failure, or `0` on success.

`NNTPsendpassword` sends authentication information to an NNTP server by finding the appropriate entry in the `passwd.nntp(5)` file. `server` contains the name of the host; `GetConfigValue` will be used if `server` is `NULL`. `FromServer` and `ToServer` should be `FILES` that are connected to the server. No action is taken if the specified host is not listed in the password file.

`Radix32` converts the number in `value` into a radix-32 string in the buffer pointed to by `p`. The number is split into five-bit pieces, and each piece is converted into a character using the alphabet `0...9a...v` to represent the numbers `0–32`. Only the lowest 32 bits of `value` are used, so `p` need only point to a buffer of eight bytes (seven characters and the trailing `\0`).

`ReadInFile` reads the file named `name` into allocated memory, appending a terminating `\0` byte. It returns a pointer to the space, or `NULL` on error. If `Sbp` is not `NULL`, it is taken as the address of a place to store the results of a `stat(2)` call.

`ReadInDescriptor` performs the same function as `ReadInFile`, except that `fd` refers to an already-open file.

`INNVersion` returns a pointer to a string identifying the INN version, suitable for printing in logon banners.

EXAMPLES

```
char *p;
char *Article;
char buff[256];
FILE *F;
FILE *ToServer;
FILE *FromServer;
if ((p = HeaderFind(Article, "From", 4)) == NULL)
    Fatal("Can't find From line");
(void)strcpy(buff, p);
HeaderCleanFrom(buff);
if ((F = CAopen(FromServer, ToServer)) == NULL)
    Fatal("Can't open active file");
/* Don't pass the file on to our children. */
CloseOnExec(fileno(F), 1);
/* Make a local copy. */
p = ReadInDescriptor(fileno(F), (struct stat *)NULL);
/* Close the file. */
CAclose();
if (NNTPremoteopen(&FromServer, &ToServer) < 0)
    Fatal("Can't connect to server");
if ((p = GetModeratorAddress("comp.sources.unix")) == NULL)
    Fatal("Can't find moderator's address");
```

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for InterNetNews.

SEE ALSO

`active(5)`, `dbz(3z)`, `parsedate(3)`, `inn.conf(5)`, `inncomm(3)`, `moderators(5)`, `passwd.nntp(5)`

GNU, 30 October 1996

libpbm

`libpbm`—Functions to support portable bitmap programs

SYNOPSIS

```
#include <pbm.h>
cc ... libpbm.a
```

DESCRIPTION—PACKAGEWIDE ROUTINES

The following sections describe string and file management routines available in `libpbm`.

KEYWORD MATCHING

The following does a case-insensitive match of `str` against `keyword`:

```
int pm_keymatch( char* str, char* keyword, int minchars )
```

`str` can be a leading substring of `keyword`, but at least `minchars` must be present.

LOG BASE TWO

This converts between a `maxval` and the minimum number of bits required to hold it:

```
int pm_maxvaltobits(int maxval)
int pm_bitstomaxval(int bits)
```

MESSAGES AND ERRORS

This is a `printf()`-style routine to write an informational message:

```
void pm_message(char* fmt, ... )
```

This is a `printf()` style routine to write an error message and abort:

```
void pm_error(char* fmt, ... )
```

The following writes a usage message; the string should indicate what arguments are to be provided to the program:

```
void pm_usage(char* usage)
```

GENERIC FILE MANAGEMENT

The following opens the given file for reading, with appropriate error checking:

```
FILE* pm_openr(char* name)
```

A filename of `-` is taken as equivalent to `stdin`.

The following opens the given file for writing, with appropriate error checking:

```
FILE* pm_openw(char* name)
```

The following closes the file descriptor, with appropriate error checking:

```
void pm_close(FILE* fp)
```

ENDIAN I/O

The following are routines to read and write short and long ints in either big- or little-endian byte order:

```
int pm_readbigshort(FILE* in, short* sP)
int pm_writebigshort(FILE* out, short s)
int pm_readbiglong(FILE* in, long* lP)
int pm_writebiglong(FILE* out, long l)
int pm_readlittleshort(FILE* in, short* sP)
int pm_writelittleshort(FILE* out, short s)
int pm_readlittlelong(FILE* in, long* lP)
int pm_writelittlelong(FILE* out, long l)
```

DESCRIPTION—PBM-SPECIFIC ROUTINES

The following sections describe file management routines available in `libpbm`.

TYPES AND CONSTANTS

Each bit should contain only the values of `PBM_WHITE` or `PBM_BLACK`:

```
typedef ... bit;
#define PBM_WHITE ...
#define PBM_BLACK ...
```

These are routines for distinguishing different file formats and types:

```
#define PBM_FORMAT ...
#define RPBM_FORMAT ...
#define PBM_TYPE PBM_FORMAT
#define PBM_FORMAT TYPE(f) ...
```

INITIALIZATION

All PBM programs must call this routine:

```
void pbm_init(int* argcP, char* argv[] )
```

MEMORY MANAGEMENT

This allocates an array of bits:

```
bit** pbm_allocarray(int cols, int rows)
```

This allocates a row of the given number of bits:

```
bit* pbm_alloccrow(int cols)
```

This frees the array allocated with `pbm_allocarray()` containing the given number of rows:

```
void pbm_freearray(bit** bits, int rows)
```

This frees a row of bits:

```
void pbm_freerow(bit* bitrow)
```

READING FILES

This reads the header from a PBM file, filling in the `rows`, `cols`, and `format` variables:

```
void pbm_readpbminit(FILE* fp, int* colsP, int* rowsP, int* formatP)
```

This reads a row of bits into the `bitrow` array (`format` and `cols` are filled in by `pbm_readpbminit()`):

```
void pbm_readpbmrow(FILE* fp, bit* bitrow, int cols, int format)
```

This function combines `pbm_readpbminit()`, `pbm_allocarray()`, and `pbm_readpbmrow()`:

```
bit** pbm_readpbm(FILE* fp, int* colsP, int* rowsP)
```

It reads an entire bitmap file into memory, returning the allocated array and filling in the `rows` and `cols` variables.

This reads an entire file or input stream of unknown size to a buffer and allocates more memory as needed:

```
char* pm_read_unknown_size(FILE* fp, long* nread)
```

The calling routine has to free the allocated buffer with `free()`. `pm_read_unknown_size()` returns a pointer to the allocated buffer; the `nread` argument returns the number of bytes read.

WRITING FILES

This writes the header for a portable bitmap file:

```
void pbm_writepbminit(FILE* fp, int cols, int rows, int forceplain)
```

The `forceplain` flag forces a plain-format file to be written, as opposed to a raw-format one.

This writes a row from a portable bitmap:

```
void pbm_writepbmrow(FILE* fp, bit* bitrow, int cols, int forceplain)
```

This writes the header and all data for a portable bitmap:

```
void pbm_writepbm(FILE* fp, bit** bits, int cols, int rows, int forceplain)
```

This function combines `pbm_writepbminit()` and `pbm_writepbmrow()`.

SEE ALSO

`libpgm(3)`, `libppm(3)`, `libpnm(3)`

AUTHOR

Copyright © 1989, 1991 by Tony Hansen and Jef Poskanzer

libpgm

libpgm—Functions to support portable graymap programs

SYNOPSIS

```
#include <pgm.h>
cc ... libpgm.a libpbm.a
```

DESCRIPTION

The following sections describe memory and file management routines available in libpgm.

TYPES AND CONSTANTS

Each gray should contain only the values between 0 and `PGM_MAXMAXVAL`.

`pgm_pbmmaxval` is the `maxval` used when a PGM program reads a PBM file. Normally it is 1, but for some programs, a larger value gives better results.

```
typedef ... gray;
#define PGM_MAXMAXVAL ...
extern gray pgm_pbmmaxval;
```

The following are for distinguishing different file formats and types:

```
#define PGM_FORMAT ...
#define RPGM_FORMAT ...
#define PGM_TYPE PGM_FORMAT
int PGM_FORMAT_TYPE(int format)
```

INITIALIZATION

All PGM programs must call this routine:

```
void pgm_init(int* argcP, char* argv[])
```

MEMORY MANAGEMENT

This allocates an array of grays:

```
gray** pgm_alloccarray(int cols, int rows)
```

This allocates a row of the given number of grays:

```
gray* pgm_allocrow(int cols)
```

This frees the array allocated with `pgm_alloccarray()` containing the given number of rows:

```
void pgm_freearray(gray** grays, int rows)
```

This frees a row of grays:

```
void pgm_freerow(gray* grayrow)
```

READING FILES

This reads the header from a PGM file, filling in the `rows`, `cols`, `maxval`, and `format` variables:

```
void pgm_readpgminit(FILE* fp, int* colsP, int* rowsP, gray* maxvalP,
int* formatP)
```

This reads a row of grays into the `grayrow` array. `format`, `cols`, and `maxval` are filled in by `pgm_readpgminit()`:

```
void pgm_readpgmrow(FILE* fp, gray* grayrow, int cols, gray maxval, int format)
```

This function combines `pgm_readpgminit()`, `pgm_allocarray()`, and `pgm_readpgmrow()`:

```
gray** pgm_readpgm(FILE* fp, int* colsP, int* rowsP, gray* maxvalP)
```

It reads an entire graymap file into memory, returning the allocated array and filling in the `rows`, `cols`, and `maxval` variables.

WRITING FILES

This writes the header for a portable graymap file:

```
void pgm_writepgminit( FILE* fp, int cols, int rows, gray maxval,
int forceplain )
```

The `forceplain` flag forces a plain-format file to be written, as opposed to a raw-format one.

This writes a row from a portable graymap:

```
void pgm_writepgmrow(FILE* fp, gray* grayrow, int cols, gray maxval,
int forceplain)
```

This function combines `pgm_writepgminit()` and `pgm_writepgmrow()`; it writes the header and all data for a portable graymap:

```
void pgm_writepgm( FILE* fp, gray** grays, int cols, int rows, gray maxval, int forceplain)
```

SEE ALSO

`libpbm(3)`, `libppm(3)`, `libpnm(3)`

AUTHOR

Copyright © 1989, 1991 by Tony Hansen and Jef Poskanzer.

libpnm

`libpnm`—Functions to support portable anymap programs

SYNOPSIS

```
#include <pnm.h>
cc ... libpnm.a libppm.a libpgm.a libpbm.a
```

DESCRIPTION

The following sections describe memory and file management routines available in `libpnm`.

TYPES AND CONSTANTS

Each `xel` contains three `xelvals`, each of which should contain only a value between 0 and `PNM_MAXMAXVAL`. `pnm_pbmmaxval` is the `maxval` used when a PNM program reads a PBM file. Normally it is 1, but for some programs, a larger value gives better results.

```
typedef ... xel;
typedef ... xelval;
#define PNM_MAXMAXVAL ...
extern xelval pnm_pbmmaxval;
```

XEL MANIPULATIONS

This macro extracts a single value from an `xel` when you know it's from a PBM or PGM file:

```
xelval PNM_GET1( xel x )
```

When the `xel` is from a PPM file, use `PPM_GETR()`, `PPM_GETG()`, and `PPM_GETB()`.

This macro assigns a single value to an `xel` when you know it's from a PBM or PGM file:

```
void PNM_ASSIGN1( xel x, xelval v )
```

When the `xel` is from a PPM file, use `PPM_ASSIGN()`.

This macro checks two `xels` for equality:

```
int PNM_EQUAL( xel x, xel y )
```

This one is for distinguishing different file types:

```
int PNM_FORMAT_TYPE( int format )
```

INITIALIZATION

All PNM programs must call this routine:

```
void pnm_init( int* argcP, char* argv[] )
```

MEMORY MANAGEMENT

This allocates an array of `xels`:

```
xel** pnm_allocarray( int cols, int rows )
```

This allocates a row of the given number of `xels`:

```
xel* pnm_alloccrow( int cols )
```

This frees the array allocated with `pnm_allocarray()` that contains the given number of rows:

```
void pnm_freearray( xel** xels, int rows )
```

This frees a row of `xels`:

```
void pnm_freerow( xel* xelrow )
```

READING FILES

This reads the header from a PNM file, filling in the `rows`, `cols`, `maxval`, and `format` variables:

```
void pnm_readpnminit( FILE* fp, int* colsP, int* rowsP, xelval* maxvalP,
int* formatP )
```

This reads a row of `xels` into the `xelrow` array. `format`, `cols`, and `maxval` are filled in by `pnm_readpnminit()`:

```
void pnm_readpnmrow( FILE* fp, xel* xelrow, int cols, xelval maxval, int format )
```

This reads an entire anymap file into memory, returning the allocated array and filling in the `rows`, `cols`, `maxval`, and `format` variables:

```
xel** pnm_readpnm( FILE* fp, int* colsP, int* rowsP, xelval* maxvalP,
int* formatP )
```

This function combines `pnm_readpnminit()`, `pnm_allocarray()`, and `pnm_readpnmrow()`. Unlike the equivalent functions in PBM, PGM, and PPM, it returns the format so you can tell what type the file is.

WRITING FILES

This writes the header for a portable anymap file:

```
void pnm_writepnminit( FILE* fp, int cols, int rows, xelval maxval, int format,
int force-plain)
```

Unlike the equivalent functions in PBM, PGM, and PPM, you have to specify the output type. The `forceplain` flag forces a plain-format file to be written, as opposed to a raw-format one.

This writes a row from a portable anymap:

```
void pnm_writepnmrow( FILE* fp, xel* xelrow, int cols, xelval maxval, int format,
int forceplain )
```

This writes the header and all data for a portable anymap:

```
void pnm_writepnm( FILE* fp, xel** xels, int cols, int rows, xelval maxval, int format,
int forceplain )
```

This function combines `pnm_writepnminit()` and `pnm_writepnmrow()`.

FORMAT PROMOTION

This promotes a row of xels from one `maxval` and `format` to a new set:

```
void pnm_promoteformatrow( xel* xelrow, int cols, xelval maxval, int format, xelval new-maxval,
int newformat )
```

Use this when combining multiple anymaps of different types—just take the maximum value of the `maxvals` and the max of the `formats`, and promote them all to that.

This promotes an entire anymap:

```
void pnm_promoteformat( xel** xels, int cols, int rows, xelval maxval,
int format, xelval newmaxval, int newformat )
```

XEL MANIPULATION

These return a white or black `xel`, respectively, for the given `maxval` and `format`:

```
xel pnm_whitexel( xelval maxval, int format )
xel pnm_blackxel( xelval maxval, int format )
```

This inverts an `xel`:

```
void pnm_invertxel( xel* x, xelval maxval, int format )
```

This figures out an appropriate background `xel` based on this row:

```
xel pnm_backgroundxelrow( xel* xelrow, int cols, xelval maxval, int format )
```

This figures out a background `xel` based on an entire anymap:

```
xel pnm_backgroundxel( xel** xels, int cols, int rows, xelval maxval,
int format )
```

This can do a slightly better job than `pnm_backgroundxelrow()`.

SEE ALSO

`pbm(3)`, `pgm(3)`, `ppm(3)`

AUTHOR

Copyright © 1989, 1991 by Tony Hansen and Jef Poskanzer.

libppm

libppm—Functions to support portable pixmap programs

SYNOPSIS

```
#include <ppm.h>
cc ... libppm.a libpgm.a libpbm.a
```

TYPES AND CONSTANTS

```
typedef ... pixel;
typedef ... pixval;
#define PPM_MAXMAXVAL ...
extern pixval ppm_pbmmmaxval;
```

Each pixel contains three `pixvals`, each of which should contain only the values between 0 and `PPM_MAXMAXVAL`. `ppm_pbmmmaxval` is the `maxval` used when a PPM program reads a PBM file. Normally it is 1; however, for some programs, a larger value gives better results.

For distinguishing different file formats and types, use

```
#define PPM_FORMAT ...
#define RPPM_FORMAT ...
#define PPM_TYPE PPM_FORMAT
int PPM_FORMAT_TYPE( int format )
```

These three macros retrieve the red, green, or blue value from the given pixel:

```
pixval PPM_GETR( pixel p )
pixval PPM_GETG( pixel p )
pixval PPM_GETB( pixel p )
```

This macro assigns the given red, green, and blue values to the pixel:

```
void PPM_ASSIGN( pixel p, pixval red, pixval grn, pixval blu )
```

This macro checks two pixels for equality:

```
int PPM_EQUAL( pixel p, pixel q )
```

The following macro scales the colors of pixel `p` according the old and new maximum values and assigns the new values to `newp`. It is intended to make writing `ppm` to whatever easier.

```
void PPM_DEPTH( pixel newp, pixel p, pixval oldmaxval, pixval newmaxval )
```

This macro determines the luminance of the pixel `p`:

```
float PPM_LUMIN( pixel p )
```

MEMORY MANAGEMENT

Allocate an array of pixels:

```
pixel** ppm_allocarray( int cols, int rows )
```

Allocate a row of the given number of pixels:

```
pixel* ppm_allocrow( int cols )
```

Free the array allocated with `ppm_allocarray()` containing the given number of rows:

```
void ppm_freearray( pixel** pixels, int rows )
```

Free a row of pixels:

```
void ppm_freerow( pixel* pixelrow )
```

READING PBM FILES

```
void ppm_readppminit( FILE* fp, int* colsP, int* rowsP, pixval* maxvalP, int* formatP )
```

Read the header from a PPM file, filling in the rows, cols, maxval, and format variables.

```
void ppm_readppmrow( FILE* fp, pixel* pixelrow, int cols, pixval maxval, int format )
```

Read a row of pixels into the pixelrow array. Format, cols, and maxval were filled in by ppm_readppminit().

```
pixel** ppm_readppm( FILE* fp, int* colsP, int* rowsP, pixval* maxvalP )
```

Read an entire pixmap file into memory, returning the allocated array and filling in the rows, cols, and maxval variables. This function combines ppm_readppminit(), ppm_allocarray(), and ppm_readppmrow().

WRITING FILES

```
void ppm_writeppminit( FILE* fp, int cols, int rows, pixval maxval, int forceplain )
```

Write the header for a portable pixmap file. The forceplain flag forces a plain-format file to be written, as opposed to a raw-format one.

```
void ppm_writeppmrow( FILE* fp, pixel* pixelrow, int cols, pixval maxval, int forceplain)
```

Write a row from a portable pixmap.

```
void ppm_writeppm( FILE* fp, pixel** pixels, int cols, int rows, pixval maxval, int force-plain)
```

Write the header and all data for a portable pixmap. This function combines ppm_writeppminit() and ppm_writeppmrow().

COLOR NAMES

This line parses an ASCII color name into a pixel:

```
pixel ppm_parsecolor( char* colorname, pixval maxval )
```

The color can be specified in three ways: as a name, assuming that a pointer to an X11-style color names file was compiled in; as an X11-style hexadecimal number (#rgb, #rrggbb, #rrrgggbbb, or #rrrrggggbbb); or as a triplet of decimal floating point numbers separated by commas (r.r,g.g,b.b).

This line returns a pointer to a string describing the given color:

```
char* ppm_colorname( pixel* colorP, pixval maxval, int hexok )
```

If the X11 color names file is available and the color appears in it, that name is returned. Otherwise, if the hexok flag is true, then a hexadecimal colorspec is returned; if hexok is false and the X11 color names file is available, then the closest matching color is returned; otherwise, it's an error.

SEE ALSO

pbm(3), pgm(3)

AUTHOR

Copyright © 1989, 1991 by Tony Hansen and Jef Poskanzer

localeconv

localeconv—Gets numeric formatting information

SYNOPSIS

```
#include <locale.h>
struct lconv *localeconv(void);
```

DESCRIPTION

The `localeconf()` function returns a string to a `struct lconv` for the current locale.

CONFORMS TO

This command conforms to ANSI C and POSIX.1.

Linux supports the portable locales C and POSIX and also the European Latin-1 ISO-8859-1, and Russian KOI-8 locales.

The `printf()` family of functions may or may not honor the current locale.

SEE ALSO

`locale(1)`, `localedef(1)`, `strcoll(3)`, `isalpha(3)`, `setlocale(3)`, `strftime(3)`, `locale(7)`

GNU, 25 April 1993

longjmp

`longjmp`—Nonlocal jump to a saved stack context

SYNOPSIS

```
#include <setjmp.h>
void longjmp(jmp_buf env, int val);
```

DESCRIPTION

`longjmp()` and `setjmp(3)` are useful for dealing with errors and interrupts encountered in a low-level subroutine of a program. `longjmp()` restores the environment saved by the last call of `setjmp()` with the corresponding `env` argument. After `longjmp()` is completed, program execution continues as if the corresponding call of `setjmp()` had just returned the value `val`. `longjmp()` cannot cause 0 to be returned. If `longjmp` is invoked with a second argument of 0, 1 will be returned instead.

RETURN VALUE

This function never returns.

CONFORMS TO

POSIX

NOTES

POSIX does not specify if the signal context will be restored or not. If you want to save restore signal masks, use `siglongjmp(3)`. `longjmp()` makes programs hard to understand and maintain. If possible, an alternative should be used.

SEE ALSO

`setjmp(3)`, `sigsetjmp(2)`, `siglongjmp(2)`

25 November 1994

lfind, lsearch

`lfind`, `lsearch`—Linear search of an array

SYNOPSIS

```
#include <stdlib.h>
void *lfind(const void *key, const void *base, size_t *nmemb,
```

```
size_t size,int(*compar)(const void *, const void *));
void *lsearch(const void *key, const void *base, size_t *nmemb,
size_t size,int(*compar)(const void *, const void *));
```

DESCRIPTION

`lfind()` and `lsearch()` perform a linear search for `key` in the array `base`, which has `*nmemb` elements of size bytes each. The comparison function referenced by `compar` is expected to have two arguments that point to the key object and to an array member, in that order, and which returns zero if the key object matches the array member, and non-zero otherwise.

If `lsearch()` does not find a matching element, then the key object is inserted at the end of the table, and `*nmemb` is incremented.

RETURN VALUE

`lfind()` returns a pointer to a matching member of the array, or `NULL` if no match is found. `lsearch()` returns a pointer to a matching member of the array, or to the newly added member if no match is found.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

SEE ALSO

`bsearch(3)`, `hsearch(3)`, `tsearch(3)`

GNU, 17 September 1995

calloc, malloc, free, realloc

`calloc`, `malloc`, `free`, `realloc`—Allocate and free dynamic memory

SYNOPSIS

```
#include <stdlib.h>
void *calloc(size_t nmemb, size_t size);
void *malloc(size_t size);
void free(void *ptr);
void *realloc(void *ptr, size_t size);
```

DESCRIPTION

`calloc()` allocates memory for an array of `nmemb` elements of size bytes each and returns a pointer to the allocated memory. The memory is set to zero.

`malloc()` allocates size bytes and returns a pointer to the allocated memory. The memory is not cleared.

`free()` frees the memory space pointed to by `ptr`, which must have been returned by a previous call to `malloc()`, `calloc()` or `realloc()`. If `ptr` is `NULL`, no operation is performed.

`realloc()` changes the size of the memory block pointed to by `ptr` to size bytes. The contents will be unchanged to the minimum of the old and new sizes; newly allocated memory will be uninitialized. If `ptr` is `NULL`, the call is equivalent to `malloc(size)`; if size is equal to zero, the call is equivalent to `free(ptr)`. Unless `ptr` is `NULL`, it must have been returned by an earlier call to `malloc()`, `calloc()`, or `realloc()`.

RETURN VALUES

For `calloc()` and `malloc()`, the value returned is a pointer to the allocated memory, which is suitably aligned for any kind of variable, or `NULL` if the request fails.

`free()` returns no value.

`realloc()` returns a pointer to the newly allocated memory, which is suitably aligned for any kind of variable and may be different from `ptr`, or `NULL` if the request fails or if `size` was equal to 0. If `realloc()` fails, the original block is left untouched; it is not freed or moved.

CONFORMS TO

ANSI C

SEE ALSO

`brk(2)`

GNU, 4 April 1993

mblen

`mblen`—Determines the number of bytes in a character

SYNOPSIS

```
#include <stdlib.h>
int_mblen(const char *s, size_t n);
```

DESCRIPTION

The `mblen()` function scans the first `n` bytes of the string `s` and returns the number of bytes in a character. The `mblen()` function is equivalent to

```
mbtowc((wchar_t*)0,s,n);
```

except that the shift state of the `mbtowc()` function is not affected.

RETURN VALUE

The `mblen()` returns the number of bytes in a character, or `-1` if the character is invalid, or 0 if it is a `NULL` string.

CONFORMS TO

SVID 3, ISO 9899

SEE ALSO

`mbstowcs(3)`, `mbtowc(3)`, `wcstombs(3)`, `wctomb(3)`

GNU, 29 March 1993

mbstowcs

`mbstowcs`—Converts a multibyte string to a wide character string

SYNOPSIS

```
#include <stdlib.h>
size_t mbstowcs(wchar_t *pwcs, const char *s, size_t n);
```

DESCRIPTION

The `mbstowcs()` function converts a sequence of multibyte characters from the array `s` into a sequence of wide characters and stores up to `n` wide characters in the array `pwcs`.

RETURN VALUE

`mbstowcs()` returns the number of wide characters stored, or -1 if `s` contains an invalid multibyte character.

CONFORMS TO

SVID 3, ISO 9899

SEE ALSO

`mblen(3)`, `mbtowl(3)`, `wcstombs(3)`, `wctomb(3)`

GNU, 29 March 1993

mbtowl

`mbtowl`—Converts a multibyte character to a wide character

SYNOPSIS

```
#include <stdlib.h>
int mbtowl(wchar_t *pwc, const char *s, size_t n);
```

DESCRIPTION

The `mbtowl()` function converts a multibyte character `s`, which is no longer than `n` bytes, into a wide character and, if `pwc` is not NULL, stores the wide character in `pwc`.

RETURN VALUE

`mbtowl()` returns the number of bytes in the multibyte character, or -1 if the multibyte character is not valid.

CONFORMS TO

SVID 3, ISO 9899

SEE ALSO

`mblen(3)`, `mbstowcs(3)`, `wcstombs(3)`, `wctomb(3)`

GNU, 29 March 1993

memccpy

`memccpy`—Copies memory area

SYNOPSIS

```
#include <string.h>
void *memccpy(void *dest, const void *src, int c, size_t n);
```

DESCRIPTION

The `memccpy()` function copies no more than `n` bytes from memory area `src` to memory area `dest`, stopping when the character `c` is found.

RETURN VALUE

The `memccpy()` function returns a pointer to the next character in `dest` after `c`, or NULL if `c` was not found in the first `n` characters of `src`.

CONFORMS TO

SVID 3, BSD 4.3

SEE ALSO

bcopy(3), memcpy(3), memmove(3), strcpy(3), strncpy(3)

GNU, 10 April 1993

memchr

memchr—Scans memory for a character

SYNOPSIS

```
#include <string.h>
void *memchr(const void *s, int c, size_t n);
```

DESCRIPTION

The `memchr()` function scans the first `n` bytes of the memory area pointed to by `s` for the character `c`. The first byte to match `c` (interpreted as an unsigned character) stops the operation.

RETURN VALUE

The `memchr()` function returns a pointer to the matching byte or `NULL` if the character does not occur in the given memory area.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

SEE ALSO

index(3), rindex(3), strchr(3), strpbrk(3), strrchr(3), strsep(3), strspn(3), strstr(3)

GNU, 12 April 1993

memcmp

memcmp—Compares memory areas

SYNOPSIS

```
#include <string.h>
int memcmp(const void *s1, const void *s2, size_t n);
```

DESCRIPTION

The `memcmp()` function compares the first `n` bytes of the memory areas `s1` and `s2`. It returns an integer less than, equal to, or greater than zero if `s1` is found, respectively, to be less than, to match, or to be greater than `s2`.

RETURN VALUE

The `memcmp()` function returns an integer less than, equal to, or greater than zero if the first `n` bytes of `s1` is found, respectively, to be less than, to match, or be greater than the first `n` bytes of `s2`.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

SEE ALSO

bcmp(3), strcasecmp(3), strcmp(3), strcoll(3), strncmp(3), strncasecmp(3)

10 April 1993

memcpy

memcpy—Copies memory area

SYNOPSIS

```
#include <string.h>
void *memcpy(void *dest, const void *src, size_t n);
```

DESCRIPTION

The `memcpy()` function copies `n` bytes from memory area `src` to memory area `dest`. The memory areas may not overlap. Use `memmove(3)` if the memory areas do overlap.

RETURN VALUE

The `memcpy()` function returns a pointer to `dest`.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

SEE ALSO

bcopy(3), memccpy(3), memmove(3), strcpy(3), strncpy(3)

GNU, 10 April 1993

memfrob

memfrob—Frobnicates (encrypts) a memory area

SYNOPSIS

```
#include <string.h>
void *memfrob(void *s, size_t n);
```

DESCRIPTION

The `memfrob()` function encrypts the first `n` bytes of the memory area `s` by using exclusive OR on each character with the number 42. The effect can be reversed by using `memfrob()` on the encrypted memory area.

Note that this function is not a proper encryption routine as the XOR constant is fixed, and is only suitable for hiding strings.

RETURN VALUE

The `memfrob()` function returns a pointer to the encrypted memory area.

CONFORMS TO

The `memfrob()` function is unique to the Linux C Library and GNU C Library.

SEE ALSO

`strfry(3)`

GNU, 12 April 1993

memmem

`memmem`—Locates a substring

SYNOPSIS

```
#include <string.h>
void *memmem(const void *needle, size_t needlen,
const void *haystack, size_t haystacklen);"
```

DESCRIPTION

The `memmem()` function finds the first occurrence of the substring `needle` of length `needlen` in the memory area `haystack` of length `haystacklen`.

RETURN VALUE

The `memmem()` function returns a pointer to the beginning of the substring, or `NULL` if the substring is not found.

SEE ALSO

`strstr(3)`

GNU, 11 April 1993

memmove

`memmove`—Copies memory area

SYNOPSIS

```
#include <string.h>
void *memmove(void *dest, const void *src, size_t n);
```

DESCRIPTION

The `memmove()` function copies `n` bytes from memory area `src` to memory area `dest`. The memory areas may overlap.

RETURN VALUE

The `memmove()` function returns a pointer to `dest`.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

SEE ALSO

`bcopy(3)`, `memccpy(3)`, `memcpy(3)`, `strcpy(3)`, `strncpy(3)`

GNU, 10 April 1993

memset

`memset`—Fills memory with a constant byte

SYNOPSIS

```
#include <string.h>
void *memset(void *s, int c, size_t n);
```

DESCRIPTION

The `memset()` function fills the first `n` bytes of the memory area pointed to be `s` with the constant byte `c`.

RETURN VALUE

The `memset()` function returns a pointer to the memory area `s`.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

SEE ALSO

`bzero(3)`, `swab(3)`

GNU, 11 April 1993

mkfifo

`mkfifo`—Makes a FIFO special file (a named pipe)

SYNOPSIS

```
#include <sys/types.h>
#include <sys/stat.h>
int mkfifo ( const char *pathname, mode_t mode );
```

DESCRIPTION

`mkfifo` makes a FIFO special file with name `pathname`. `mode` specifies the FIFO's permissions. It is modified by the process's `umask` in the usual way: the permissions of the created file are `(mode&umask)`.

A FIFO special file is similar to a pipe, except that it is created in a different way. Instead of being an anonymous communications channel, a FIFO special file is entered into the filesystem by calling `mkfifo`.

After you have created a FIFO special file in this way, any process can open it for reading or writing, in the same way as an ordinary file. However, it has to be open at both ends simultaneously before you can proceed to do any input or output operations on it. Opening a FIFO for reading normally blocks until some other process opens the same FIFO for writing, and vice versa.

RETURN VALUE

The normal, successful return value from `mkfifo` is `0`. In the case of an error, `-1` is returned (in which case, `errno` is set appropriately).

ERRORS

`EACCES`
`EEXIST`

One of the directories in `pathname` did not allow search (execute) permission.
`pathname` already exists.

ENAMETOOLONG	Either the total length of <code>pathname</code> is greater than <code>PATH_MAX</code> , or an individual filename component has a length greater than <code>NAME_MAX</code> . In the GNU system, there is no imposed limit on overall filename length, but some filesystems may place limits on the length of a component.
ENOENT	A directory component in <code>pathname</code> does not exist or is a dangling symbolic link.
ENOSPC	The directory or filesystem has no room for the new file.
ENOTDIR	A component used as a directory in <code>pathname</code> is not, in fact, a directory.
EROFS	<code>pathname</code> refers to a read-only filesystem.

CONFORMS TO

POSIX.1

SEE ALSO

`mkfifo(1)`, `read(2)`, `write(2)`, `open(2)`, `close(2)`, `stat(2)`, `umask(2)`

Linux 1.2.13, 3 September 1995

mkstemp

`mkstemp`—Creates a unique temporary file

SYNOPSIS

```
#include <unistd.h>
int *mkstemp(char *template);
```

DESCRIPTION

The `mkstemp()` function generates a unique temporary filename from `template`. The last six characters of `template` must be `xxxxxx` and these are replaced with a string that makes the filename unique. The file is then created with mode read/write and permissions `0666`.

RETURN VALUE

The `mkstemp()` function returns the file descriptor `fd` of the temporary file.

ERRORS

EINVAL	The last six characters of <code>template</code> were not <code>xxxxxx</code> .
EEXIST	The temporary file is not unique.

CONFORMS TO

BSD 4.3

SEE ALSO

`mktemp(3)`, `tmpnam(3)`, `tempnam(3)`, `tmpfile(3)`

GNU, 3 April 1993

mktemp

`mktemp`—Makes a unique temporary filename

SYNOPSIS

```
#include <unistd.h>
char *mktemp(char *template);
```

DESCRIPTION

The `mktemp()` function generates a unique temporary filename from `template`. The last six characters of `template` must be `xxxxxx` and these are replaced with a string that makes the filename unique.

RETURN VALUE

The `mktemp()` function returns a pointer to `template` on success, and `NULL` on failure.

ERRORS

`EINVAL` The last six characters of `template` were not `xxxxxx`.

CONFORMS TO

BSD 4.3. POSIX dictates `tmpnam()`.

SEE ALSO

`mkstemp(3)`, `tmpnam(3)`, `tempnam(3)`, `tmpfile(3)`

GNU, 3 April 1993

modf

`modf`—Extracts signed integral and fractional values from floating-point number

SYNOPSIS

```
#include <math.h>
double modf(double x, double *iptr);
```

DESCRIPTION

The `modf()` function breaks the argument `x` into an integral part and a fractional part, each of which has the same sign as `x`. The integral part is stored in `iptr`.

RETURN VALUE

The `modf()` function returns the fractional part of `x`.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`frexp(3)`, `ldexp(3)`

6 June 1993

asctime, ctime, difftime, gmtime, localtime, mktime

`asctime`, `ctime`, `difftime`, `gmtime`, `localtime`, `mktime`—Convert date and time to ASCII

SYNOPSIS

```
extern char *tzname[2];

void tzset()

#include <sys/types.h>

char *ctime(clock)
const time_t *clock;

double difftime(time1, time0)
time_t time1;
time_t time0;

#include <time.h>

char *asctime(tm)
const struct tm *tm;

struct tm *localtime(clock)
const time_t *clock;

struct tm *gmtime(clock)
const time_t *clock;

time_t mktime(tm)
struct tm *tm;

cc ... -lz
```

DESCRIPTION

`ctime` converts a long integer, pointed to by `clock`, representing the time in seconds since 00:00:00 UTC, January 1, 1970, and returns a pointer to a 26-character string of the form Thu Nov 24 18:22:48 1986. (Note: UTC is Coordinated Universal Time.) All the fields have constant width.

`localtime` and `gmtime` return pointers to `tm` structures, described in the following paragraphs. `localtime` corrects for the time zone and any time zone adjustments (such as Daylight Saving Time in the United States). Before doing so, `localtime` calls `tzset` (if `tzset` has not been called in the current process). After filling in the `tm` structure, `localtime` sets the `tm_isdst`'th element of `tzname` to a pointer to an ASCII string that's the time zone abbreviation to be used with `localtime`'s return value.

`gmtime` converts to Coordinated Universal Time.

`asctime` converts a time value contained in a `tm` structure to a 26-character string, as shown in the preceding example, and returns a pointer to the string.

`mktime` converts the broken-down time, expressed as local time, in the structure pointed to by `tm` into a calendar time value with the same encoding as that of the values returned by the `time` function. The original values of the `tm_wday` and `tm_yday` components of the structure are ignored, and the original values of the other components are not restricted to their normal ranges. (A positive or zero value for `tm_isdst` causes `mktime` to presume initially that summer time (for example, Daylight Saving Time in the United States) respectively, is or is not in effect for the specified time. A negative value for `tm_isdst` causes the `mktime` function to attempt to divine whether summer time is in effect for the specified time.) On successful completion, the values of the `tm_wday` and `tm_yday` components of the structure are set appropriately, and the other components are set to represent the specified calendar time, but with their values forced to their normal ranges; the final value of `tm_mday` is not set until `tm_mon` and `tm_year` are determined. `mktime` returns the specified calendar time; if the calendar time cannot be represented, it returns -1.

`difftime` returns the difference between two calendar times, (`time1 - time0`), expressed in seconds.

Declarations of all the functions and externals, and the `tm` structure, are in the `<time.h>` header file. The structure (of type) `struct tm` includes the following fields:

```
int tm_sec;      / seconds (0 - 60) /
int tm_min;      / minutes (0 - 59) /
int tm_hour;     / hours (0 - 23) /
int tm_mday;     / day of month (1 - 31) /
int tm_mon;      / month of year (0 - 11) /
int tm_year;     / year - 1900 /
int tm_wday;     / day of week (Sunday = 0) /
int tm_yday;     / day of year (0 - 365) /
int tm_isdst;    / is summer time in effect? /
char tm_zone;    / abbreviation of timezone name /
long tm_gmtoff;  / offset from UTC in seconds /
```

The `tm_zone` and `tm_gmtoff` fields exist, and are filled in, only if arrangements to do so were made when the library containing these functions was created. There is no guarantee that these fields will continue to exist in this form in future releases of this code.

`tm_isdst` is non-zero if summer time is in effect.

`tm_gmtoff` is the offset (in seconds) of the time represented from UTC, with positive values indicating east of the Prime Meridian.

FILES

<code>/usr/local/etc/zoneinfo</code>	Time zone information directory
<code>/usr/local/etc/zoneinfo/localtime</code>	Local time zone file
<code>/usr/local/etc/zoneinfo/posixrules</code>	Used with POSIX-style TZs
<code>/usr/local/etc/zoneinfo/GMT</code>	For UTC leap seconds

If `/usr/local/etc/zoneinfo/GMT` is absent, UTC leap seconds are loaded from `/usr/local/etc/zoneinfo/posixrules`.

SEE ALSO

`getenv(3)`, `newtztset(3)`, `time(2)`, `tzfile(5)`

NOTES

The return values point to static data; the data is overwritten by each call. The `tm_zone` field of a returned `struct tm` points to a static array of characters, which will also be overwritten at the next call (and by calls to `tzset`).

Avoid using out-of-range values with `mktime` when setting up lunch with promptness sticklers in Riyadh.

tzset

`tzset`—Initializes time conversion information

SYNOPSIS

```
void tzset();
cc ... -lz
```

DESCRIPTION

`tzset` uses the value of the environment variable `TZ` to set time conversion information used by `localtime`. If `TZ` does not appear in the environment, the best available approximation to local wall clock time, as specified by the `tzfile(5)`-format file `localtime` in the system time conversion information directory, is used by `localtime`. If `TZ` appears in the environment but its value is a null string, Coordinated Universal Time (UTC) is used (without leap second correction). If `TZ` appears in the environment and its value is not a null string, it is used in one of the following ways:

If the value begins with a colon, it is used as a pathname of a file from which to read the time conversion information.

If the value does not begin with a colon, it is first used as the pathname of a file from which to read the time conversion information, and, if that file cannot be read, is used directly as a specification of the time conversion information.

When `TZ` is used as a pathname, if it begins with a slash, it is used as an absolute pathname; otherwise, it is used as a pathname relative to a system time conversion information directory. The file must be in the format specified in `tzfile(5)`.

When `TZ` is used directly as a specification of the time conversion information, it must have the following syntax (spaces inserted for clarity):

```
std offset [dst[offset][,rule]]
```

The elements are as follows:

`std` and `dst`

Three or more bytes that are the designation for the standard (`std`) or summer (`dst`) time zone. Only `std` is required; if `dst` is missing, then summer time does not apply in this locale. Uppercase and lowercase letters are explicitly allowed. Any characters except a leading colon (:), digits, comma (,), minus (-), plus (+), and ASCII NUL are allowed.

`offset`

Indicates the value one must add to the local time to arrive at Coordinated Universal Time. The `offset` has the form:

```
hh[:mm[:ss]]
```

The minutes (`mm`) and seconds (`ss`) are optional. The hour (`hh`) is required and may be a single digit. The `offset` following `std` is required. If no `offset` follows `dst`, summer time is assumed to be one hour ahead of standard time. One or more digits may be used; the value is always interpreted as a decimal number. The hour must be between zero and 24, and the minutes (and seconds)—if present—between zero and 59. If preceded by a "+", the time zone shall be east of the Prime Meridian; otherwise, it shall be west (which may be indicated by an optional preceding "-").

`rule`

Indicates when to change to and back from summer time. The `rule` has the form:

```
date/time,date/time
```

where the first date describes when the change from standard to summer time occurs and the second date describes when the change back happens. Each `time` field describes when, in current local time, the change to the other time is made.

The format of `date` is one of the following:

The *d*'th day ($0 \leq d \leq 6$) of week *n* of month *m* of the year ($1 \leq n \leq 5$, $1 \leq m \leq 12$, where week 5 means "the last *d* day in month *m*" which may occur in either the fourth or the fifth week). Week 1 is the first week in which the *d*'th day occurs. Day zero is Sunday.

`Jn`

The Julian day *n* ($1 \leq n \leq 365$). Leap days are not counted; that is, in all years—including leap years—February 28 is day 59 and March 1 is day 60. It is impossible to explicitly refer to the occasional February 29.

`n` The zero-based Julian day ($0 \leq n \leq 365$). Leap days are counted, and it is possible to refer to February 29.

`Mm.n.d` The *d*'th day ($0 \leq d \leq 6$) of week *n* of month *m* of the year ($1 \leq n \leq 5$, $1 \leq m \leq 12$, where week 5 means “the last *d* day in month *m*,” which may occur in either the fourth or the fifth week). Week 1 is the first week in which the *d*'th day occurs. Day zero is Sunday.

The `time` has the same format as `offset` except that no leading sign (“+” or “-”) is allowed. The default, if `time` is not given, is 02:00:00.

If no `rule` is present in `TZ`, the rules specified by the `tzfile(5)`-format file `posixrules` in the system time conversion information directory are used, with the standard and summer time offsets from UTC replaced by those specified by the `offset` values in `TZ`.

For compatibility with System V Release 3.1, a semicolon (;) may be used to separate the `rule` from the rest of the specification.

If the `TZ` environment variable does not specify a `tzfile(5)`-format and cannot be interpreted as a direct specification, UTC is used.

FILES

<code>/usr/local/etc/zoneinfo</code>	Time zone information directory
<code>/usr/local/etc/zoneinfo/localtime</code>	Local time zone file
<code>/usr/local/etc/zoneinfo/posixrules</code>	Used with POSIX-style <code>TZs</code>
<code>/usr/local/etc/zoneinfo/GMT</code>	For UTC leap seconds

If `/usr/local/etc/zoneinfo/GMT` is absent, UTC leap seconds are loaded from `/usr/local/etc/zoneinfo/posixrules`.

SEE ALSO

`getenv(3)`, `newtime(3)`, `time(2)`, `tzfile(5)`

on_exit

`on_exit`—Registers a function to be called at normal program termination

SYNOPSIS

```
#include <stdlib.h>
int on_exit(void (*function)(int , void *), void *arg);
```

DESCRIPTION

The `on_exit()` function registers the given function to be called at normal program termination, whether via `exit(2)` or via return from the program's main. The function is passed the argument to `exit(3)` and the `arg` argument from `on_exit()`.

RETURN VALUE

The `on_exit()` function returns the value 0 if successful; otherwise, the value -1 is returned.

SEE ALSO

`exit(3)`, `atexit(3)`

opendir

`opendir`—Opens a directory

SYNOPSIS

```
#include <sys/types.h>
#include <dirent.h>
DIR *opendir(const char *name);
```

DESCRIPTION

The `opendir()` function opens a directory stream corresponding to the directory name, and returns a pointer to the directory stream. The stream is positioned at the first entry in the directory.

RETURN VALUE

The `opendir()` function returns a pointer to the directory stream or `NULL` if an error occurred.

ERRORS

<code>EACCESS</code>	Permission denied
<code>EMFILE</code>	Too many file descriptors in use by process
<code>ENFILE</code>	Too many files are currently open in the system
<code>ENOENT</code>	Directory does not exist, or name is an empty string
<code>ENOMEM</code>	Insufficient memory to complete the operation
<code>ENOTDIR</code>	name is not a directory

CONFORMS TO

SVID 3, POSIX, BSD 4.3

SEE ALSO

`open(2)`, `readdir(3)`, `closedir(3)`, `rewinddir(3)`, `seekdir(3)`, `telldir(3)`, `scandir(3)`

11 June 1995

parsedate

`parsedate`—Converts time and date string to number

SYNOPSIS

```
#include <sys/types.h>
typedef struct _TIMEINFO f
time_t time;
long usec;
long tzone;
} TIMEINFO;
time_t
parsedate(text, now)
char *text;
TIMEINFO *now;
```

DESCRIPTION

`parsedate` converts many common time specifications into the number of seconds since the epoch, that is, a `time_t`; see `time(2)`.

`parsedate` returns the time, or `-1` on error. `text` is a character string containing the time and date. `now` is a pointer to the time that should be used for calculating relative dates. If `now` is `NULL`, then `GetTimeInfo` in `libinn(3)` is used to obtain the current time and time zone.

The character string consists of zero or more specifications of the following form:

<code>time</code>	A time of day, which is of the form <code>hh[:mm[:ss]] [meridian][zone]</code> or <code>hhmm [meridian][zone]</code> . If no meridian is specified, <code>hh</code> is interpreted on a 24-hour clock.
<code>date</code>	A specific month and day with optional year. The acceptable formats are <code>mm/dd[/yy]</code> , <code>yyyy/mm/dd</code> , <code>monthname dd[, yy]</code> , <code>dd monthname [yy]</code> , and <code>day,ddmonthnameyy</code> , and <code>day, dd monthname yy</code> . The default year is the current year. If the year is less than 100, then 1900 is added to it; if it is less than 21, then 2000 is added to it.
<code>relative time</code>	A specification relative to the current time. The format is <code>number unit</code> ; acceptable units are <code>year</code> , <code>month</code> , <code>week</code> , <code>day</code> , <code>hour</code> , <code>minute</code> (or <code>min</code>), and <code>second</code> (or <code>sec</code>). The unit can be specified as a singular or plural, as in <code>3 weeks</code> .

The actual date is calculated according to the following steps. First, any absolute date or time is processed and converted. Using that time as the base, day-of-week specifications are added. Next, relative specifications are used. If a date or day is specified, and no absolute or relative time is given, midnight is used. Finally, a correction is applied so that the correct hour of the day is produced after allowing for Daylight Savings Time differences.

`parsedate` ignores case when parsing all words; unknown words are taken to be unknown time zones, which are treated as GMT. The names of the months and days of the week can be abbreviated to their first three letters, with optional trailing period. Periods are ignored in any time zone or meridian values.

BUGS

`parsedate` does not accept all desirable and unambiguous constructions. Semantically incorrect dates such as “February 31” are accepted.

Daylight Savings Time is always taken as a one-hour change that is wrong for some places. The Daylight Savings Time correction can get confused if parsing a time within an hour of when the reckoning changes, or if given a partial date.

HISTORY

Originally written by Steven M. Bellovin (smb@research.att.com) while at the University of North Carolina at Chapel Hill and distributed under the name `getdate`.

A major overhaul was done by Rich Salz (rsalz@bbn.com) and Jim Berets (jberets@bbn.com) in August, 1990.

It was further revised (primarily to remove obsolete constructs and time zone names) a year later by Rich (now rsalz@osf.org) for InterNetNews, and the name was changed.

SEE ALSO

`date(1)`, `ctime(3)`, `libinn(3)`, `time(2)`

perror

`perror`—Prints a system error message

SYNOPSIS

```
#include <stdio.h>

void perror(const char *s);

#include <errno.h>
```

```
const char *sys_errlist[];
int sys_nerr;
```

DESCRIPTION

The routine `perror()` produces a message on the standard error output, describing the last error encountered during a call to a system or library function. The argument string `s` is printed first, then a colon and a blank, then the message and a newline. To be of most use, the argument string should include the name of the function that incurred the error. The error number is taken from the external variable `errno`, which is set when errors occur but not cleared when nonerroneous calls are made.

The global error list `sys_errlist[]` indexed by `errno` can be used to obtain the error message without the newline. The largest message number provided in the table is `sys_nerr - 1`. Be careful when directly accessing this list because new error values may not have been added to `sys_errlist[]`.

When a system call fails, it usually returns `-1` and sets the variable `errno` to a value describing what went wrong. (These values can be found in `<errno.h>`.) Many library functions do likewise. The function `perror()` serves to translate this error code into human-readable form. Note that `errno` is undefined after a successful library call. This call may well change this variable, even though it succeeds, for example, because it internally used some other library function that failed. Thus, if a failing call is not immediately followed by a call to `perror`, the value of `errno` should be saved.

CONFORMS TO

ANSI C, BSD 4.3, POSIX, X/OPEN

SEE ALSO

`strerror(3)`

16 May 1996

popen, pclose

popen, pclose—Process I/O

SYNOPSIS

```
#include <stdio.h>

FILE *popen(const char *command, const char *type);

int pclose(FILE *stream);
```

DESCRIPTION

The `popen()` function opens a process by creating a pipe, forking, and invoking the shell. Because a pipe is by definition unidirectional, the `type` argument may specify only reading or writing, not both; the resulting stream is correspondingly read-only or write-only.

The `command` argument is a pointer to a null-terminated string containing a shell command line. This command is passed to `/bin/sh` using the `-c` flag; interpretation, if any, is performed by the shell. The `mode` argument is a pointer to a null-terminated string which must be either `r` for reading or `w` for writing.

The return value from `popen()` is a normal standard I/O stream in all respects save that it must be closed with `pclose()` rather than `fclose()`. Writing to such a stream writes to the standard input of the command; the command's standard output is the same as that of the process that called `popen()`, unless this is altered by the command itself. Conversely, reading from a “popened” stream reads the command's standard output, and the command's standard input is the same as that of the process that called `popen`.

Note that output `popen` streams are fully buffered by default.

The `pclose` function waits for the associated process to terminate and returns the exit status of the command as returned by `wait4`.

RETURN VALUE

The `popen` function returns `NULL` if the `fork(2)` or `pipe(2)` calls fail, or if it cannot allocate memory.

The `pclose` function returns `-1` if stream is not associated with a “popened” command, if stream already “pclosed,” or if `wait4` returns an error.

ERRORS

The `popen` function does not reliably set `errno`. (Is this true for Linux?)

BUGS

The standard input of a command opened for reading shares its seek offset with the process that called `popen()`; therefore, if the original process has done a buffered read, the command’s input position may not be as expected. Similarly, the output from a command opened for writing may become intermingled with that of the original process. The latter can be avoided by calling `fflush(3)` before `popen`.

Failure to execute the shell is indistinguishable from the shell’s failure to execute `command`, or an immediate exit of the command. The only hint is an exit status of 127. (Is this true under Linux?)

The function `popen()` always calls `sh`, never calls `csh`.

HISTORY

A `popen()` and a `pclose()` function appeared in Version 7 AT&T UNIX.

SEE ALSO

`fork(2)`, `sh(1)`, `pipe(2)`, `wait4(2)`, `fflush(3)`, `fclose(3)`, `fopen(3)`, `stdio(3)`, `system(3)`, `fclose(3)`, `fopen(3)`, `stdio(3)`, `system(3)`.

BSD man page, 17 May 1996

printf, fprintf, sprintf, snprintf, vprintf, vfprintf, vsprintf, vsnprintf

`printf`, `fprintf`, `sprintf`, `snprintf`, `vprintf`, `vfprintf`, `vsprintf`, `vsnprintf`—Formatted output conversion

SYNOPSIS

```
#include <stdio.h>

int printf( const char *format, ...);
int fprintf( FILE *stream, const char *format, ...);
int sprintf( char *str, const char *format, ...);
int snprintf( char *str, size_t size, const char *format, ...);

#include <stdarg.h>

int vprintf( const char *format, va_list ap);
int vfprintf( FILE *stream, const char *format, va_list ap);
int vsprintf( char *str, const char *format, va_list ap);
int vsnprintf( char *str, size_t size, const char *format, va_list ap);
```

DESCRIPTION

The `printf` family of functions produces output according to a `format`, as described in the following paragraphs. The functions `printf` and `vprintf` write output to `stdout`, the standard output stream; `fprintf` and `vfprintf` write output to the given output stream; `sprintf`, `snprintf`, `vsprintf`, and `vsnprintf` write to the character string `str`.

These functions write the output under the control of a `format` string that specifies how subsequent arguments (or arguments accessed via the variable-length argument facilities of `stdarg(3)`) are converted for output.

These functions return the number of characters printed (not including the trailing `\0` used to end output to strings). `snprintf` and `vsnprintf` do not write more than `size` bytes (including the trailing `\0`), and return `-1` if the output was truncated due to this limit.

The `format` string is composed of zero or more directives: ordinary characters (not `%`), which are copied unchanged to the output stream; and conversion specifications, each of which results in fetching zero or more subsequent arguments. Each conversion specification is introduced by the character `%`. The arguments must correspond properly (after type promotion) with the conversion specifier. After the `%`, zero or more of the following flags appear in sequence:

- # Specifying that the value should be converted to an alternate form. For `c`, `d`, `i`, `n`, `p`, `s`, and `u` conversions, this option has no effect. For `o` conversions, the precision of the number is increased to force the first character of the output string to a zero (except if a zero value is printed with an explicit precision of zero). For `x` and `X` conversions, a non-zero result has the string `0x` (or `0X` for `X` conversions) prepended to it. For `e`, `E`, `f`, `g`, and `G` conversions, the result will always contain a decimal point, even if no digits follow it (normally, a decimal point appears in the results of those conversions only if a digit follows). For `g` and `G` conversions, trailing zeros are not removed from the result as they would otherwise be.
 - 0 Specifying zero padding. For all conversions except `n`, the converted value is padded on the left with zeros rather than blanks. If a precision is given with a numeric conversion (`d`, `i`, `o`, `u`, `i`, `x`, and `X`), the `0` flag is ignored.
 - (a negative field width flag) Indicates the converted value is to be left adjusted on the field boundary. Except for `n` conversions, the converted value is padded on the right with blanks, rather than on the left with blanks or zeros. A `-` overrides a `0` if both are given.
 - ' ' (a space) Specifying that a blank should be left before a positive number produced by a signed conversion (`d`, `e`, `E`, `f`, `g`, `G`, or `i`).
 - + Specifying that a sign always be placed before a number produced by a signed conversion. A `+` overrides a space if both are used.
 - ' Specifying that in a numerical argument the output is to be grouped if the locale information indicates any. Note that many versions of `gcc` cannot parse this option and will issue a warning.
- An optional decimal digit string specifying a minimum field width. If the converted value has fewer characters than the field width, it will be padded with spaces on the left (or right, if the left-adjustment flag has been given) to fill out the field width.
- An optional precision, in the form of a period (`.`) followed by an optional digit string. If the digit string is omitted, the precision is taken as zero. This gives the minimum number of digits to appear for `d`, `i`, `o`, `u`, `x`, and `X` conversions; the number of digits to appear after the decimal point for `e`, `E`, and `f` conversions; the maximum number of significant digits for `g` and `G` conversions; or the maximum number of characters to be printed from a string for `s` conversions.
- The optional character `h`, specifying that a following `d`, `i`, `o`, `u`, `x`, or `X` conversion corresponds to a short `int` or unsigned short `int` argument, or that a following `n` conversion corresponds to a pointer to a short `int` argument.
- The optional character `l` (ell) specifying that a following `d`, `i`, `o`, `u`, `x`, or `X` conversion applies to a pointer to a long `int` or unsigned long `int` argument, or that a following `n` conversion corresponds to a pointer to a long `int` argument. Linux provides a non-ANSI-compliant use of two `l` flags as a synonym to `q` or `L`. Thus, `ll` can be used in combination with float conversions. This usage is, however, strongly discouraged.

The character `L` specifying that a following `e`, `E`, `f`, `g`, or `G` conversion corresponds to a `long double` argument, or a following `d`, `i`, `o`, `u`, `x`, or `X` conversion corresponds to a `long long` argument. Note that `long long` is not specified in ANSI C and therefore not portable to all architectures.

The optional character `q`. This is equivalent to `L`. See the “Standards” and “Bugs” sections for comments on the use of `ll`, `L`, and `q`.

A `z` character specifying that the following integer (`d`, `i`, `o`, `u`, `i`, `x`, and `X`) conversion corresponds to a `size_t` argument.

A character that specifies the type of conversion to be applied.

A field width or precision, or both, may be indicated by an asterisk `*` instead of a digit string. In this case, an `int` argument supplies the field width or precision. A negative field width is treated as a left adjustment flag followed by a positive field width; a negative precision is treated as though it were missing.

The conversion specifiers and their meanings are as follows:

<code>diouxX</code>	The <code>int</code> (or appropriate variant) argument is converted to signed decimal (<code>d</code> and <code>i</code>), unsigned octal (<code>o</code>), unsigned decimal (<code>u</code>), or unsigned hexadecimal (<code>x</code> and <code>X</code>) notation. The letters <code>abcdef</code> are used for <code>x</code> conversions; the letters <code>ABCDEF</code> are used for <code>X</code> conversions. The precision, if any, gives the minimum number of digits that must appear; if the converted value requires fewer digits, it is padded on the left with zeros.
<code>eE</code>	The <code>double</code> argument is rounded and converted in the style <code>[-]d.ddde\dd</code> where there is one digit before the decimal-point character and the number of digits after it is equal to the precision; if the precision is missing, it is taken as 6; if the precision is zero, no decimal-point character appears. An <code>E</code> conversion uses the letter <code>E</code> (rather than <code>e</code>) to introduce the exponent. The exponent always contains at least two digits; if the value is zero, the exponent is <code>00</code> .
<code>f</code>	The <code>double</code> argument is rounded and converted to decimal notation in the style <code>[-].ddd.ddd</code> , where the number of digits after the decimal-point character is equal to the precision specification. If the precision is missing, it is taken as 6; if the precision is explicitly zero, no decimal-point character appears. If a decimal point appears, at least one digit appears before it.
<code>g</code>	The <code>double</code> argument is converted in style <code>f</code> or <code>e</code> (or <code>E</code> for <code>G</code> conversions). The precision specifies the number of significant digits. If the precision is missing, 6 digits are given; if the precision is zero, it is treated as 1. Style <code>e</code> is used if the exponent from its conversion is less than negative 4 or greater than or equal to the precision. Trailing zeros are removed from the fractional part of the result; a decimal point appears only if it is followed by at least one digit.
<code>c</code>	The <code>int</code> argument is converted to an unsigned <code>char</code> , and the resulting character is written.
<code>s</code>	The <code>char *</code> argument is expected to be a pointer to an array of character type (pointer to a string). Characters from the array are written up to (but not including) a terminating <code>NUL</code> character; if a precision is specified, no more than the number specified are written. If a precision is given, no null character need be present; if the precision is not specified, or is greater than the size of the array, the array must contain a terminating <code>NUL</code> character.
<code>p</code>	The <code>void *</code> pointer argument is printed in hexadecimal (as if by <code>%#x</code> or <code>%#lx</code>).
<code>n</code>	The number of characters written so far is stored into the integer indicated by the <code>int *</code> (or variant) pointer argument. No argument is converted.
<code>%</code>	A <code>%</code> is written. No argument is converted. The complete conversion specification is <code>%%</code> .

In no case does a nonexistent or small field width cause truncation of a field; if the result of a conversion is wider than the field width, the field is expanded to contain the conversion result.

EXAMPLES

To print a date and time in the form “Sunday, July 3, 10:02,” where weekday and month are pointers to strings:

```
#include <stdio.h>
fprintf(stdout, "%s, %s %d, %.2d:%.2d\n",
weekday, month, day, hour, min);
```

To print to five decimal places:

```
#include <math.h>
#include <stdio.h>
fprintf(stdout, "pi = %.5f\n", 4 * atan(1.0));
```

To allocate a 128-byte string and print into it:

```
#include <stdio.h>
#include <stdlib.h>
#include <stdarg.h>

char *newfmt(const char *fmt, ...)
{
    char *p;
    va_list ap;
    if ((p = malloc(128)) == NULL)
        return (NULL);
    va_start(ap, fmt);
    (void) vsnprintf(p, 128, fmt, ap);
    va_end(ap);
    return (p);
}
```

SEE ALSO

printf(1), scanf(3)

STANDARDS

The fprintf, printf, sprintf, vprintf, vfprintf, and vsprintf functions conform to ANSI C3.159-1989 (“ANSI C”).

The q flag is the BSD 4.4 notation for long long, while ll or the usage of L in integer conversions is the GNU notation.

The Linux version of these functions is based on the GNU libio library. Take a look at the info documentation of GNU libc (glibc-1.08) for a more concise description.

BUGS

Some floating point conversions under Linux cause memory leaks.

All functions are fully ANSI C3.159-1989 conformant, but provide the additional flags q, z, and ' as well as an additional behavior of the L and l flags. The latter may be considered to be a bug, as it changes the behavior of flags defined in ANSI C3.159-1989.

The effect of padding the %p format with zeros (either by the 0 flag or by specifying a precision), and the benign effect (that is, none) of the # flag on %n and %p conversions, as well as nonsensical combinations that are not standard; such combinations should be avoided.

Some combinations of flags defined by ANSI C are not making sense (for example, %Ld). While they may have a well-defined behavior on Linux, this need not to be so on other architectures. Therefore, it usually is better not to use flags that are not defined by ANSI C at all; in other words, that use q instead of L in combination with diouxX conversions or ll.

The usage of q is not the same as on BSD 4.4, as it may be used in float conversions equivalently to L.

Because `sprintf` and `vsprintf` assume an infinitely long string, callers must be careful not to overflow the actual space; this is often impossible to assure.

Linux man page, 28 January 1996

psignal

`psignal`—Prints signal message

SYNOPSIS

```
#include <signal.h>
void psignal(int sig, const char *s);
extern const char *const sys_siglist[]
```

DESCRIPTION

The `psignal()` function displays a message on `stderr` consisting of the string `s`, a colon, a space, and a string describing the signal number `sig`. If `sig` is invalid, the message displayed will indicate an unknown signal.

The array `sys_siglist` holds the signal description strings indexed by signal number.

RETURN VALUE

The `psignal()` function returns no value.

CONFORMS TO

BSD 4.3

SEE ALSO

`perror(3)`, `strsignal(3)`

GNU, 13 April 1993

putenv

`putenv`—Changes or adds an environment variable

SYNOPSIS

```
#include <stdlib.h>
int putenv(const char *string);
```

DESCRIPTION

The `putenv()` function adds or changes the value of environment variables. The argument `string` is of the form `name = value`. If `name` does not already exist in the environment, then `string` is added to the environment. If `name` does exist, then the value of `name` in the environment is changed to `value`.

RETURN VALUE

The `putenv()` function returns zero on success, or `-1` if an error occurs.

ERRORS

`ENOMEM`

Insufficient space to allocate new environment

CONFORMS TO

SVID 3, POSIX, BSD 4.3

SEE ALSO

getenv(3), setenv(3), unsetenv(3)

GNU, 8 April 1993

putpwent

putpwent—Writes a password file entry

SYNOPSIS

```
#include <pwd.h>
#include <stdio.h>
#include <sys/types.h>
int putpwent(const struct passwd *p, FILE *stream);
```

DESCRIPTION

The `putpwent()` function writes a password entry from the structure `p` in the file associated with `stream`.

The `passwd` structure is defined in `<pwd.h>` as follows:

```
struct passwd {
    char    *pw_name;        /* user name */
    char    *pw_passwd;      /* user password */
    uid_t   pw_uid;          /* user id */
    gid_t    pw_gid;          /* group id */
    char    *pw_gecos;        /* real name */
    char    *pw_dir;          /* home directory */
    char    *pw_shell;        /* shell program */
};
```

RETURN VALUE

The `putpwent()` function returns 0 on success, or -1 if an error occurs.

ERRORS

EINVAL Invalid (NULL) argument given

CONFORMS TO

SVID 3

SEE ALSO

fgetpwent(3), getpwent(3), setpwent(3), endpwent(3), getpwnam(3), getpwuid(3), getpw(3)

GNU, 9 April 1993

fputc, fputs, putc, putchar, puts

fputc, fputs, putc, putchar, puts—Output of characters and strings

SYNOPSIS

```
#include <stdio.h>
int fputc(int c, FILE* stream);
int fputs(const char *s, FILE* stream);
int putc(int c, FILE *stream);
int putchar(int c);
int puts(char *s);
int ungetc(int c, FILE *stream);
```

DESCRIPTION

`fputc()` writes the character `c`, cast to an unsigned char, to stream.

`fputs()` writes the string `s` to stream, without its trailing `\0`.

`putc()` is equivalent to `fputc()` except that it may be implemented as a macro that evaluates `stream` more than once.

`putchar(c)`; is equivalent to `putc(c, stdout)`.

`puts()` writes the string `s` and a trailing newline to `stdout`.

Calls to the functions described here can be mixed with each other and with calls to other output functions from the `stdio` library for the same output stream.

RETURN VALUES

`fputc()`, `putc()`, and `putchar()` return the character written as an unsigned char cast to an `int` or `EOF` on error.

`puts()` and `fputs()` return a non-negative number on success, or `EOF` on error.

CONFORMS TO

ANSI C, POSIX.1

BUGS

It is not advisable to mix calls to output functions from the `stdio` library with low-level calls to `write()` for the file descriptor associated with the same output stream; the results will be undefined and very probably not what you want.

SEE ALSO

`write(2)`, `fopen(3)`, `fwrite(3)`, `scanf(3)`, `gets(3)`, `fseek(3)`, `ferror(3)`

GNU, 4 April 1993

qio

`qio`—Quick I/O part of InterNetNews library

SYNOPSIS

```
#include "qio.h"
QIOSTATE *
QIOOpen(name, size)
char *name;
int size;
QIOSTATE * QIOfdopen(fd, size)
int fd;
int size;
void QIOclose(qp)
QIOSTATE *qp;
```

```

char * QIOread(qp)
QIOSTATE *qp;
int QIOlength(qp)
QIOSTATE *qp;
int QIOtoolong(qp)
QIOSTATE *qp;
int QIOerror(qp)
QIOSTATE *qp;
int QIOtell(qp)
QIOSTATE *qp;
int QIOrewind(qp)
QIOSTATE *qp;
int QIOfileno(qp)
QIOSTATE *qp;

```

DESCRIPTION

The routines described in this manual page are part of the InterNetNews library, `libinn(3)`. They are used to provide quick read access to files. The letters `QIO` stand for Quick I/O.

`QIOopen` opens the file name for reading. It uses a buffer of size bytes, which must also be larger than the longest expected line. The header file defines the constant `QIO_BUFFER` as a reasonable default. If size is zero, then `QIOopen` will call `stat(2)` and use the returned block size; if that fails it will use `QIO_BUFFER`. It returns `NULL` on error, or a pointer to a handle to be used in other calls. `QIOfdopen` performs the same function except that `fd` refers to an already-open descriptor.

`QIOclose` closes the open file and releases any resources used by it.

`QIOread` returns a pointer to the next line in the file. The trailing newline will be replaced with a `\0`. If `E0F` is reached, an error occurs, or if the line is longer than the buffer, `QIOread` returns `NULL`.

After a successful call to `QIOread`, `QIOlength` will return the length of the current line.

The functions `QIOtoolong` and `QIOerror` can be called after `QIOread` returns `NULL` to determine if there was an error, or if the line was too long. If `QIOtoolong` returns non-zero, then the current line did not fit in the buffer, and the next call to `QIOread` will try read the rest of the line. Long lines can only be discarded. If `QIOerror` returns non-zero, then a serious I/O error occurred.

`QIOtell` returns the `lseek(2)` offset at which the next line will start.

`QIOrewind` sets the read pointer back to the beginning of the file.

`QIOfileno` returns the descriptor of the open file.

`QIOlength`, `QIOtoolong`, `QIOerror`, `QIOtell`, and `QIOfileno` are implemented as macros defined in the header file.

EXAMPLE

```

QIOSTATE *h;
long offset;
char *p;
h = QIOopen("/etc/motd", QIO_BUFFER);
for (offset = QIOtell(h); (p = QIOread(h)) != NULL; offset = QIOtell(h))
printf("At %ld, %s\n", offset, p);
if (QIOerror(h)) {
    perror("Read error");
    exit(1);
}
QIOclose(h);

```

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for InterNetNews.

qsort

qsort—Sorts an array

SYNOPSIS

```
#include <stdlib.h>
void qsort(void *base, size_t nmemb, size_t size, int(*compar)
(const void *, const void *));
```

DESCRIPTION

The `qsort()` function sorts an array with `nmemb` elements of size `size`. The `base` argument points to the start of the array.

The contents of the array are sorted in ascending order according to a comparison function pointed to by `compar`, which is called with two arguments that point to the objects being compared.

The comparison function must return an integer less than, equal to, or greater than zero if the first argument is considered to be respectively less than, equal to, or greater than the second. If two members compare as equal, their order in the sorted array is undefined.

RETURN VALUE

The `qsort()` function returns no value.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`sort(1)`

GNU, 29 March 1993

raise

raise—Sends a signal to the current process

SYNOPSIS

```
#include <signal.h>
int raise (int sig);
```

DESCRIPTION

The `raise` function sends a signal to the current process. It is equivalent to

`kill(getpid(), sig)`

RETURN VALUE

Zero on success, non-zero for failure.

CONFORMS TO

ANSI C

SEE ALSO

`kill(2)`, `signal(2)`, `getpid(2)`

GNU, 31 August 1995

rand, srand

rand, srand—Random number generator

SYNOPSIS

```
#include <stdlib.h>
int rand(void);
void srand(unsigned int seed);
```

DESCRIPTION

The `rand()` function returns a pseudo-random integer between 0 and `RAND_MAX`.

The `srand()` function sets its argument as the seed for a new sequence of pseudo-random integers to be returned by `rand()`. These sequences are repeatable by calling `srand()` with the same seed value.

If no seed value is provided, the `rand()` function is automatically seeded with a value of 1.

RETURN VALUE

The `rand()` function returns a value between 0 and `RAND_MAX`. The `srand()` returns no value.

NOTES

The versions of `rand()` and `srand()` in the Linux C Library use the same random number generator as `random()` and `srandom()`, so the lower-order bits should be as random as the higher-order bits. However, on older `rand()` implementations, the lower-order bits are much less random than the higher-order bits.

In *Numerical Recipes in C: The Art of Scientific Computing* (William H. Press, Brian P. Flannery, Saul A. Teukolsky, William T. Vetterling; New York: Cambridge University Press, 1990, first ed, p. 207), the following comments are made:

“If you want to generate a random integer between 1 and 10, you should always do it by

```
j=1+(int) (10.0*rand()/(RAND+MAX+1.0));
```

and never by anything resembling

```
j=1+((int) (1000000.0*rand()) % 10);
```

(which uses lower-order bits).”

Random-number generation is a complex topic. The *Numerical Recipes in C* book (see preceding reference) provides an excellent discussion of practical random-number generation issues in Chapter 7, “Random Numbers.”

For a more theoretical discussion that also covers many practical issues in depth, please see Chapter 3, “Random Numbers,” in Donald E. Knuth’s *The Art of Computer Programming, Volume 2* (Seminumerical Algorithms), 2nd ed.; Reading, Massachusetts: Addison-Wesley Publishing Company, 1981.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

SEE ALSO

`random(3)`, `srandom(3)`, `initstate(3)`, `setstate(3)`

GNU, 18 May 1995

random, srandom, initstate, setstate

random, srandom, initstate, setstate—Random number generator

SYNOPSIS

```
#include <stdlib.h>
long int random(void);
void srand(unsigned int seed);
char *initstate(unsigned int seed, char *state, int n);
char *setstate(char *state);
```

DESCRIPTION

The `random()` function uses a nonlinear additive feedback random number generator employing a default table of size 31 long integers to return successive pseudo-random numbers in the range from 0 to `RAND_MAX`. The period of this random number generator is very large, approximately $16 * ((2^{**31}) - 1)$.

The `srand()` function sets its argument as the seed for a new sequence of pseudo-random integers to be returned by `random()`. These sequences are repeatable by calling `srand()` with the same seed value. If no seed value is provided, the `random()` function is automatically seeded with a value of 1.

The `initstate()` function allows a state array `state` to be initialized for use by `random()`. The size of the state array `n` is used by `initstate()` to decide how sophisticated a random number generator it should use—the larger the state array, the better the random numbers will be. `seed` is the seed for the initialization, which specifies a starting point for the random number sequence, and provides for restarting at the same point.

The `setstate()` function changes the state array used by the `random()` function. The state array `state` is used for random number generation until the next call to `initstate()` or `setstate()`. `state` must first have been initialized using `initstate()`.

RETURN VALUE

The `random()` function returns a value between 0 and `RAND_MAX`. The `srand()` function returns no value. The `initstate()` and `setstate()` functions return a pointer to the previous state array.

ERRORS

EINVAL A state array of less than 8 bytes was specified to `initstate()`.

NOTES

Current “optimal” values for the size of the state array `n` are 8, 32, 64, 128, and 256 bytes; other amounts will be rounded down to the nearest known amount. Using less than 8 bytes will cause an error.

CONFORMS TO

BSD 4.3

SEE ALSO

`rand(3)`, `srand(3)`

GNU, 28 March 1993

readdir

`readdir`—Reads a directory

SYNOPSIS

```
#include <sys/types.h>
#include <dirent.h>
struct dirent *readdir(DIR *dir);
```

DESCRIPTION

The `readdir()` function returns a pointer to a `dirent` structure representing the next directory entry in the directory stream pointed to by `dir`. It returns `NULL` on reaching the end-of-file or if an error occurred.

The data returned by `readdir()` is overwritten by subsequent calls to `readdir()` for the same directory stream.

According to POSIX, the `dirent` structure contains a field `char d_name[]` of unspecified size, with at most `NAME_MAX` characters preceding the terminating null character. Use of other fields will harm the portability of your programs.

RETURN VALUE

The `readdir()` function returns a pointer to a `dirent` structure, or `NULL` if an error occurs or end-of-file is reached.

ERRORS

`EBADF` Invalid directory stream descriptor `dir`

CONFORMS TO

SVID 3, POSIX, BSD 4.3

SEE ALSO

`read(2)`, `opendir(3)`, `closedir(3)`, `rewinddir(3)`, `seekdir(3)`, `telldir(3)`, `scandir(3)`

22 April 1996

readv, writev

`readv, writev`—Reads or writes data into multiple buffers

SYNOPSIS

```
#include <sys/uio.h>
int readv(int filedes, const struct iovec *vector,
size_t count);
int writev(int filedes, const struct iovec *vector,
size_t count);
```

DESCRIPTION

The `readv()` function reads `count` blocks from the file associated with the file descriptor `filedes` into the multiple buffers described by `vector`.

The `writev()` function writes at most `count` blocks described by `vector` to the file associated with the file descriptor `filedes`.

The pointer `vector` points to a struct `iovec` defined in `<sys/uio.h>` as

```
struct iovec
{
void *iovbase; /* Starting address */
size_t iov_len; /* Number of bytes */
} ;
```

Buffers are processed in the order `vector[0]`, `vector[1]`, ... `vector[count]`.

The `readv()` function works just like `read(2)` except that multiple buffers are filled.

The `writev()` function works just like `write(2)` except that multiple buffers are written out.

RETURN VALUES

The `readv()` function returns the number of bytes or `-1` on error; the `writev()` function returns the number of bytes written.

ERRORS

The `readv()` and `writev()` functions can fail and set `errno` to the following values:

<code>EBADF</code>	<code>fd</code> is not a valid file descriptor.
<code>EINVAL</code>	<code>fd</code> is unsuitable for reading (for <code>readv()</code>) or writing (for <code>writev()</code>).
<code>EFAULT</code>	<code>buf</code> is outside the processes' address space.
<code>EAGAIN</code>	Nonblocking I/O had been selected in the <code>open()</code> call, and reading or writing could not be done immediately.
<code>EINTR</code>	Reading or writing was interrupted before any data was transferred.

CONFORMS TO

unknown

BUGS

It is not advisable to mix calls to functions like `readv()` or `writev()`, which operate on file descriptors, with the functions from the `stdio` library; the results will be undefined and probably not what you want.

SEE ALSO

`read(2)`, `write(2)`

GNU, 25 April 1993

realpath

`realpath`—Returns the canonicalized absolute pathname.

SYNOPSIS

```
#include <sys/param.h>
#include <unistd.h>
char *realpath(char *path, char resolved_path[]);
```

DESCRIPTION

`realpath` expands all symbolic links and resolves references to `./`, `../` and extra `/` characters in the null-terminated string named by `path` and stores the canonicalized absolute pathname in the buffer of size `MAXPATHLEN` named by `resolved_path`. The resulting path will have no symbolic link, `./`, or `../` components.

RETURN VALUE

If there is no error, it returns a pointer to the `resolved_path`.

Otherwise, it returns a `NULL` pointer and places in `resolved_path` the absolute pathname of the path component that could not be resolved. The global variable `errno` is set to indicate the error.

ERRORS

<code>ENOTDIR</code>	A component of the path prefix is not a directory.
<code>EINVAL</code>	The pathname contains a character with the high-order bit set.
<code>ENAMETOOLONG</code>	A component of a pathname exceeded <code>MAXNAMLEN</code> characters, or an entire path name exceeded <code>MAXPATHLEN</code> characters.
<code>ENOENT</code>	The named file does not exist.
<code>EACCES</code>	Search permission is denied for a component of the path prefix.
<code>ELOOP</code>	Too many symbolic links were encountered in translating the pathname.
<code>EIO</code>	An I/O error occurred while reading from the filesystem.

SEE ALSO

readlink(2), getcwd(3)

GNU, 29 July 1994

Re_comp, re_exec

re_comp, re_exec—BSD regex functions

SYNOPSIS

```
#include <regex.h>
char *re_comp(char *regex);
int re_exec(char *string);
```

DESCRIPTION

re_comp is used to compile the null-terminated regular expression pointed to by *regex*. The compiled pattern occupies a static area, the pattern buffer, which is overwritten by subsequent use of *re_comp*. If *regex* is NULL, no operation is performed and the pattern buffer's contents are not altered.

re_exec is used to assess whether the null-terminated string pointed to by *string* matches the previously compiled *regex*.

RETURN VALUE

re_comp returns NULL on successful compilation of *regex*; otherwise, it returns a pointer to an appropriate error message.

re_exec returns 1 for a successful match, zero for failure.

CONFORMS TO

BSD 4.3

SEE ALSO

regex(7), GNU regex manual

Linux, 14 July 1995

regcomp, regex, regerror, regfree

regcomp, regex, regerror, regfree—POSIX regex functions

SYNOPSIS

```
#include <regex.h>
int regcomp(regex_t *preg, const char *regex, int cflags);
int regex(const regex_t *preg, const char *string, size_t nmatch, regmatch_t pmatch[], int eflags);
size_t regerror(int errcode, const regex_t *preg, char *errbuf, size_t errbuf_size);
void regfree(regex_t *preg);
```

POSIX REGEX COMPILING

regcomp is used to compile a regular expression into a form that is suitable for subsequent *regex* searches.

regcomp is supplied with *preg*, a pointer to a pattern buffer storage area; *regex*, a pointer to the null-terminated string; and *cflags*, flags used to determine the type of compilation. All regular expression searching must be done via a compiled pattern buffer; thus, *regex* must always be supplied with the address of a *regcomp* initialized pattern buffer.

`cflags` may be the bitwise or of one or more of the following:

<code>REG_EXTENDED</code>	Use POSIX extended regular expression syntax when interpreting <code>regex</code> . If not set, POSIX basic regular expression syntax is used.
<code>REG_ICASE</code>	Do not differentiate case. Subsequent <code>regex</code> searches using this pattern buffer will be case-insensitive.
<code>REG_NOSUB</code>	Support for substring addressing of matches is not required. The <code>nmatch</code> and <code>pmatch</code> parameters to <code>regex</code> are ignored if the pattern buffer supplied was compiled with this flag set.
<code>REG_NEWLINE</code>	Match-any-character operators don't match a newline. A nonmatching list (<code>[^...]</code>) not containing a newline matches a newline. Match-beginning-of-line operator (<code>^</code>) matches the empty string immediately after a newline, regardless of whether <code>eflags</code> , the execution flags of <code>regex</code> , contains <code>REG_NOTBOL</code> . Match-end-of-line operator (<code>\$</code>) matches the empty string immediately before a newline, regardless of whether <code>eflags</code> contains <code>REG_NOTEOL</code> .

POSIX REGEX MATCHING

`regex` is used to match a null-terminated string against the precompiled pattern buffer, `preg`. `nmatch` and `pmatch` are used to provide information regarding the location of any matches. `eflags` may be the bitwise or of one or both of `REG_NOTBOL` and `REG_NOTEOL`, which cause changes in matching behavior described in the following list.

<code>REG_NOTBOL</code>	The match-beginning-of-line operator always fails to match (but see the compilation flag <code>REG_NEWLINE</code> , in the preceding subsection). This flag may be used when different portions of a string are passed to <code>regex</code> and the beginning of the string should not be interpreted as the beginning of the line.
<code>REG_NOTEOL</code>	The match-end-of-line operator always fails to match (but see the compilation flag <code>REG_NEWLINE</code> , in the preceding subsection).

BYTE OFFSETS

Unless `REG_NOSUB` was set for the compilation of the pattern buffer, it is possible to obtain substring match addressing information. `pmatch` must be dimensioned to have at least `nmatch` elements. These are filled in by `regex` with substring match addresses. Any unused structure elements will contain the value `-1`.

The `regmatch_t` structure that is the type of `pmatch` is defined in `regex.h`:

```
typedef struct
{
    regoff_t rm_so;
    regoff_t rm_eo;
} regmatch_t;
```

Each `rm_so` element that is not `-1` indicates the start offset of the next largest substring match within the string. The relative `rm_eo` element indicates the end offset of the match.

POSIX ERROR REPORTING

`regerror` is used to turn the error codes that can be returned by both `regcomp` and `regex` into error message strings.

`regerror` is passed the error code, `errcode`; the pattern buffer, `preg`; a pointer to a character string buffer, `errbuf`; and the size of the string buffer, `errbuf_size`. It returns the size of the `errbuf` required to contain the null-terminated error message string. If both `errbuf` and `errbuf_size` are non-zero, `errbuf` is filled in with the first `errbuf_size - 1` characters of the error message and a terminating null.

POSIX PATTERN BUFFER FREEING

Supplying `regfree` with a precompiled pattern buffer, `preg` will free the memory allocated to the pattern buffer by the compiling process, `regcomp`.

RETURN VALUE

`regcomp` returns zero for a successful compilation or an error code for failure.

`regexexec` returns zero for a successful match or `REG_NOMATCH` for failure.

ERRORS

The following errors can be returned by `regcomp`:

<code>REG_BADRPT</code>	Invalid use of repetition operators, such as using <code>*</code> as the first character
<code>REG_BADBR</code>	Invalid use of back reference operator
<code>REG_EBRACE</code>	Unmatched brace interval operators
<code>REG_EBRACK</code>	Unmatched bracket list operators
<code>REG_ERANGE</code>	Invalid use of the range operator; for example, the ending point of the range occurs prior to the starting point
<code>REG_ETYPE</code>	Unknown character class name
<code>REG_EPAREN</code>	Unmatched parenthesis group operators
<code>REG_ESUBREG</code>	Invalid back reference to a subexpression
<code>REG_EEND</code>	Non-specific error
<code>REG_ESCAPE</code>	Invalid escape sequence
<code>REG_BADPAT</code>	Invalid use of pattern operators such as group or list
<code>REG_ESIZE</code>	Compiled regular expression requires a pattern buffer larger than 64Kb
<code>REG_ESPACE</code>	The regex routines ran out of memory

CONFORMS TO

POSIX

SEE ALSO

`regex(7)`, GNU regex manual

Linux, 13 July 1994

remove

`remove`—Deletes a name and possibly the file to which it refers

SYNOPSIS

```
#include <stdio.h>
int remove(const char *pathname);
```

DESCRIPTION

`remove` deletes a name from the filesystem. If that name was the last link to a file and no processes have the file open, the file is deleted and the space it was using is made available for reuse.

If the name was the last link to a file but any processes still have the file open, the file will remain in existence until the last file descriptor referring to it is closed.

If the name referred to a symbolic link, the link is removed.

If the name referred to a socket, fifo, or device, the name for it is removed, but processes that have the object open may continue to use it.

RETURN VALUE

On success, zero is returned. On error, `-1` is returned, and `errno` is set appropriately.

ERRORS

<code>EFAULT</code>	<code>pathname</code> points outside your accessible address space.
<code>EACCES</code>	Write access to the directory containing <code>pathname</code> is not allowed for the process's effective <code>uid</code> , or one of the directories in <code>pathname</code> did not allow search (execute) permission.
<code>EPERM</code>	The directory containing <code>pathname</code> has the sticky-bit (<code>S_ISVTX</code>) set and the process's effective <code>uid</code> is neither the <code>uid</code> of the file to be deleted nor that of the directory containing it.
<code>ENAMETOOLONG</code>	<code>pathname</code> was too long.
<code>ENOENT</code>	A directory component in <code>pathname</code> does not exist or is a dangling symbolic link.
<code>ENOTDIR</code>	A component used as a directory in <code>pathname</code> is not, in fact, a directory.
<code>EISDIR</code>	<code>pathname</code> refers to a directory.
<code>ENOMEM</code>	Insufficient kernel memory was available.
<code>EROFS</code>	<code>pathname</code> refers to a file on a read-only filesystem.

CONFORMS TO

SVID, AT&T, POSIX, X/OPEN, BSD 4.3

BUGS

Inadequacies in the protocol underlying NFS can cause the unexpected disappearance of files that are still being used.

SEE ALSO

`unlink(2)`, `rename(2)`, `open(2)`, `rmdir(2)`, `mknod(2)`, `mkfifo(3)`, `link(2)`, `rm(1)`, `unlink(8)`

Linux, 13 July 1994

res_query, res_search, res_mkquery, res_send, res_init, dn_comp, dn_expand

`res_query`, `res_search`, `res_mkquery`, `res_send`, `res_init`, `dn_comp`, `dn_expand`—Resolver routines

SYNOPSIS

```
#include <sys/types.h>
#include <netinet/in.h>
#include <arpa/nameser.h>
#include <resolv.h>

res_query(dname, class, type, answer, anslen)
const char *dname;
int class, type;
u_char *answer;
int anslen;
```

```

res_search(dname, class, type, answer, anslen)
const char *dname;
int class, type;
u_char *answer;
int anslen;

res_mkquery(op, dname, class, type, data, datalen, newrr, buf, buflen)
int op;
const char *dname;
int class, type;
const char *data;
int datalen;
struct rrec *newrr;
u_char *buf;
int buflen;

res_send(msg, msglen, answer, anslen)
const u_char *msg;
int msglen;
u_char *answer;
int anslen;

res_init()

dn_comp(exp_dn, comp_dn, length, dnptrs, lastdnptr)
const char *exp_dn;
u_char *comp_dn;
int length;
u_char **dnptrs, **lastdnptr;

dn_expand(msg, eomorig, comp_dn, exp_dn, length)
const u_char *msg, *eomorig, *comp_dn;
char *exp_dn;
int length;
hstrerror(int err);

```

DESCRIPTION

These routines are used for making, sending and interpreting query and reply messages with Internet domain name servers.

Global configuration and state information that is used by the resolver routines is kept in the structure `_res`. Most of the values have reasonable defaults and can be ignored. Options stored in `_res.options` are defined in `resolv.h` and are as follows. Options are stored as a simple bit mask containing the bitwise or of the options enabled.

<code>RES_INIT</code>	True if the initial name server address and default domain name are initialized (that is, <code>res_init</code> has been called).
<code>RES_DEBUG</code>	Print debugging messages.
<code>RES_AAONLY</code>	Accept authoritative answers only. With this option, <code>res_send</code> should continue until it finds an authoritative answer or finds an error. Currently, this is not implemented.
<code>RES_USEVC</code>	Use TCP connections for queries instead of UDP datagrams.
<code>RES_STAYOPEN</code>	Used with <code>RES_USEVC</code> to keep the TCP connection open between queries. This is useful only in programs that regularly do many queries. UDP should be the normal mode used.
<code>RES_IGNTC</code>	Unused currently (ignore truncation errors—don't retry with TCP).
<code>RES_RECURSE</code>	Set the recursion-desired bit in queries. This is the default. (<code>res_send</code> does not do iterative queries and expects the name server to handle recursion.)

<code>RES_DEFNAMES</code>	If set, <code>res_search</code> will append the default domain name to single-component names (those that do not contain a dot). This option is enabled by default.
<code>RES_DNSRCH</code>	If this option is set, <code>res_search</code> will search for hostnames in the current domain and in parent domains; see <code>hostname(7)</code> . This is used by the standard host lookup routine <code>gethostbyname(3)</code> . This option is enabled by default.
<code>RES_NOALIASES</code>	This option turns off the user level aliasing feature controlled by the <code>HOSTALIASES</code> environment variable. Network daemons should set this option.

The `res_init` routine reads the configuration file (if any; see `resolver(5)`) to get the default domain name, search list and the Internet address of the local name server(s). If no server is configured, the host running the resolver is tried. The current domain name is defined by the hostname if not specified in the configuration file; it can be overridden by the environment variable `LOCALDOMAIN`. This environment variable may contain several blank-separated tokens if you wish to override the search list on a per-process basis. This is similar to the `search` command in the configuration file. Another environment variable (`RES_OPTIONS`) can be set to override certain internal resolver options that are otherwise set by changing fields in the `_res` structure or are inherited from the configuration file's options command. The syntax of the `RES_OPTIONS` environment variable is explained in `resolver(5)`. Initialization normally occurs on the first call to one of the other resolver routines.

The `res_query` function provides an interface to the server query mechanism. It constructs a query, sends it to the local server, awaits a response, and makes preliminary checks on the reply. The query requests information of the specified type and class for the specified fully-qualified domain name `dnname`. The reply message is left in the `answer` buffer with length and `len` supplied by the caller.

The `res_search` routine makes a query and awaits a response like `res_query`, but in addition, it implements the default and search rules controlled by the `RES_DEFNAMES` and `RES_DNSRCH` options. It returns the first successful reply.

The remaining routines are lower-level routines used by `res_query`. The `res_mkquery` function constructs a standard query message and places it in `buf`. It returns the size of the query, or `-1` if the query is larger than `buflen`. The query type `op` is usually `QUERY`, but can be any of the query types defined in `<arpa/nameser.h>`. The domain name for the query is given by `dnname`. `Newrr` is currently unused but is intended for making update messages.

The `res_send` routine sends a preformatted query and returns an answer. It will call `res_init` if `RES_INIT` is not set, send the query to the local name server, and handle time-outs and retries. The length of the reply message is returned, or `-1` if there were errors.

The `dn_comp` function compresses the domain name `exp_dn` and stores it in `comp_dn`. The size of the compressed name is returned or `-1` if there were errors. The size of the array pointed to by `comp_dn` is given by `length`. The compression uses an array of pointers `dnptrs` to previously-compressed names in the current message. The first pointer points to the beginning of the message and the list ends with `NULL`. The limit to the array is specified by `lastdnptr`. A side effect of `dn_comp` is to update the list of pointers for labels inserted into the message as the name is compressed. If `dnptr` is `NULL`, names are not compressed. If `lastdnptr` is `NULL`, the list of labels is not updated.

The `dn_expand` entry expands the compressed domain name `comp_dn` to a full domain name. The compressed name is contained in a query or reply message; `msg` is a pointer to the beginning of the message. The uncompressed name is placed in the buffer indicated by `exp_dn`, which is of size `length`. The size of compressed name is returned or `-1` if there was an error.

FILES

`/etc/resolv.conf`

See `resolver(5)`

SEE ALSO

gethostbyname(3), named(8), resolver(5), hostname(7),
RFC1032, RFC1033, RFC1034, RFC1035, RFC974
SMM: 11 Name Server Operations Guide for BIND

11 December 1995

rewinddir

rewinddir—Resets directory stream

SYNOPSIS

```
#include <sys/types.h>
#include <dirent.h>
void rewinddir(DIR *dir);
```

DESCRIPTION

The `rewinddir()` function resets the position of the directory stream `dir` to the beginning of the directory.

RETURN VALUE

The `readdir()` function returns no value.

CONFORMS TO

SVID 3, POSIX, BSD 4.3

SEE ALSO

`opendir(3)`, `readdir(3)`, `closedir(3)`, `seekdir(3)`, `telldir(3)`, `scandir(3)`

11 June 1995

rint

rint—Rounds to closest integer

SYNOPSIS

```
#include <math.h>
double rint(double x);
```

DESCRIPTION

The `rint()` function rounds `x` to an integer value according to the prevalent rounding mode. The default rounding mode is to round to the nearest integer.

RETURN VALUE

The `rint()` function returns the integer value as a floating-point number.

CONFORMS TO

BSD 4.3

SEE ALSO

`abs(3)`, `ceil(3)`, `fabs(3)`, `floor(3)`, `labs(3)`

6 June 1993

rquota

`rquota`—Implements quotas on remote machines

SYNOPSIS

```
/usr/include/rpcsvc/rquota.x
```

DESCRIPTION

The `rquota( )` protocol inquires about quotas on remote machines. It is used in conjunction with NFS because NFS itself does not implement quotas.

PROGRAMMING

```
#include <rpcsvc/rquota.h>
```

The following XDR routines are available in `librpcsvc`: `xdr_getquota_arg`:

```
xdr_getquota_rslt
xdr_rquota
```

SEE ALSO

`quota(1)`, `quotactl(2)`

6 October 1987

scandir, alphasort

`scandir`, `alphasort`—Scan a directory for matching entries

SYNOPSIS

```
#include <dirent.h>
int scandir(const char *dir, struct dirent ***namelist,
int (*select)(const struct dirent *),
int (*compar)(const struct dirent **, const struct dirent **));
int alphasort(const struct dirent **a, const struct dirent **b);
```

DESCRIPTION

The `scandir( )` function scans the directory `dir`, calling `select( )` on each directory entry. Entries for which `select( )` returns non-zero are stored in strings allocated via `malloc( )`, sorted using `qsort( )` with the comparison function `compar( )`, and collected in array `namelist` that is allocated via `malloc( )`. If `select` is `NULL`, all entries are selected.

The `alphasort( )` function can be used as the comparison function for the `scandir( )` function to sort the directory entries into alphabetical order. Its parameters are the two directory entries, `a` and `b`, to compare.

RETURN VALUE

The `scandir( )` function returns the number of directory entries selected or `-1` if an error occurs.

The `alphasort( )` function returns an integer less than, equal to, or greater than zero if the first argument is considered to be respectively less than, equal to, or greater than the second.

ERRORS

ENOMEM

Insufficient memory to complete the operation

CONFORMS TO

BSD 4.3

EXAMPLE

```

/* print files in current directory in reverse order */
#include <dirent.h>
main(){
    struct dirent **namelist;
    int n;

    n = scandir(".", &namelist, 0, alphasort);
    if (n < 0)
        perror("scandir");
    else
        while(n--) printf("%s\n", namelist[n]->d_name);
}

```

SEE ALSO

opendir(3), readdir(3), closedir(3), rewinddir(3), telldir(3), seekdir(3)

GNU, 11 April 1996

scanf, fscanf, sscanf, vscanf, vsscanf, vfscanf

scanf, fscanf, sscanf, vscanf, vsscanf, vfscanf—Input format conversion

SYNOPSIS

```

#include <stdio.h>
int scanf( const char *format, ...);
int fscanf( FILE *stream, const char *format, ...);
int sscanf( const char *str, const char *format, ...);
#include <stdarg.h>
int vscanf( const char *format,va_list ap);
int vsscanf( const char *str, const char *format,va_list ap);
int vfscanf( FILE *stream, const char *format,va_list ap);

```

DESCRIPTION

The `scanf` family of functions scans input according to a format as described below. This format may contain conversion specifiers; the results from such conversions, if any, are stored through the pointer arguments. The `scanf` function reads input from the standard input stream `stdin`, `fscanf` reads input from the stream pointer `stream`, and `sscanf` reads its input from the character string pointed to by `str`.

The `vfscanf` function is analogous to `vfprintf(3)` and reads input from the stream pointer `stream` using a variable argument list of pointers (see `stdarg(3)`). The `vscanf` function scans a variable argument list from the standard input and the `vsscanf` function scans it from a string; these are analogous to the `vprintf` and `vsprintf` functions respectively.

Each successive pointer argument must correspond properly with each successive conversion specifier. All conversions are introduced by the `%` (percent sign) character. The format string may also contain other characters. Whitespace (such as blanks, tabs, or newlines) in the format string match any amount of whitespace, including none, in the input. Everything else matches only itself. Scanning stops when an input character does not match such a format character. Scanning also stops when an input conversion cannot be made.

CONVERSIONS

Following the % character introducing a conversion, there may be a number of flag characters, as follows:

- * Suppresses assignment. The conversion that follows occurs as usual, but no pointer is used; the result of the conversion is simply discarded.
- a Indicates that the conversion will be `s`, `malloc` will be applied to the needed memory space for the string, and the pointer to it will be assigned to the `char` pointer variable, which does not have to be initialized before. This flag does not exist in ANSI C.
- h Indicates that the conversion will be one of `dioux` or `n` and the next pointer is a pointer to a short `int` (rather than `int`).
- l Indicates either that the conversion will be one of `dioux` or `n` and the next pointer is a pointer to a long `int` (rather than `int`), or that the conversion will be one of `efg` and the next pointer is a pointer to `double` (rather than `float`). Specifying two `l` flags is equivalent to the `L` flag.
- L Indicates that the conversion will be either `efg` and the next pointer is a pointer to long `double` or the conversion will be `dioux` and the next pointer is a pointer to long `long`. (Note that long `long` is not an ANSI C type. Any program using this will not be portable to all architectures).
- q Equivalent to `L`. This flag does not exist in ANSI C.

In addition to these flags, there may be an optional maximum field width, expressed as a decimal integer, between the % and the conversion. If no width is given, a default of infinity is used (with one exception, below); otherwise, at most this many characters are scanned in processing the conversion. Before conversion begins, most conversions skip whitespace; this whitespace is not counted against the field width.

The following conversions are available:

- % Matches a literal %. That is, %% in the format string matches a single input % character. No conversion is done, and assignment does not occur.
- d Matches an optionally signed decimal integer; the next pointer must be a pointer to `int`.
- D Equivalent to `d`; this exists only for backwards compatibility.
- i Matches an optionally signed integer; the next pointer must be a pointer to `int`. The integer is read in base 16 if it begins with `0x` or `0X`, in base 8 if it begins with `0`, and in base 10 otherwise. Only characters that correspond to the base are used.
- o Matches an unsigned octal integer; the next pointer must be a pointer to unsigned `int`.
- u Matches an unsigned decimal integer; the next pointer must be a pointer to unsigned `int`.
- x Matches an unsigned hexadecimal integer; the next pointer must be a pointer to unsigned `int`.
- X Equivalent to `x`.
- f Matches an optionally signed floating-point number; the next pointer must be a pointer to `float`.
- e Equivalent to `f`.
- g Equivalent to `f`.
- E Equivalent to `f`.
- s Matches a sequence of nonwhitespace characters; the next pointer must be a pointer to `char`, and the array must be large enough to accept all the sequence and the terminating NUL character. The input string stops at whitespace or at the maximum field width, whichever occurs first.
- c Matches a sequence of width count characters (default 1); the next pointer must be a pointer to `char`, and there must be enough room for all the characters (no terminating NUL is added). The usual skip of leading whitespace is suppressed. To skip whitespace first, use an explicit space in the format.
- [Matches a nonempty sequence of characters from the specified set of accepted characters; the next pointer must be a pointer to `char`, and there must be enough room for all the characters in the string, plus a terminating NUL character. The usual skip of leading whitespace is suppressed. The string is to be made up of characters in (or not in) a particular set; the set is defined by the characters between the open bracket [character and a close bracket] character. The set excludes those characters if the first

character after the open bracket is a circumflex (^). To include a close bracket in the set, make it the first character after the open bracket or the circumflex; any other position will end the set. The hyphen character (-) is also special; when placed between two other characters, it adds all intervening characters to the set. To include a hyphen, make it the last character before the final close bracket. For instance, [^]0-9-] means the set “everything except close bracket, zero through nine, and hyphen.” The string ends with the appearance of a character not in (or, with a circumflex, in) the set or when the field width runs out.

- p Matches a pointer value (as printed by %p in printf(3); the next pointer must be a pointer to void.
- n Nothing is expected; instead, the number of characters consumed thus far from the input is stored through the next pointer, which must be a pointer to int. This is not a conversion, although it can be suppressed with the * flag.

RETURN VALUES

These functions return the number of input items assigned, which can be fewer than provided for, or even zero, in the event of a matching failure. Zero indicates that, while there was input available, no conversions were assigned; typically, this is due to an invalid input character, such as an alphabetic character for a %d conversion. The value EOF is returned if an input failure occurs before any conversion such as an end-of-file occurs. If an error or end-of-file occurs after conversion has begun, the number of conversions which were successfully completed is returned.

SEE ALSO

strtoul(3), strtoul(3), strtod(3),getc(3),printf(3)

STANDARDS

The functions fscanf, scanf, and sscanf conform to ANSI C3.159-1989 (ANSI C).

The q flag is the BSD 4.4 notation for long long, while ll or the usage of L in integer conversions is the GNU notation.

The Linux version of these functions is based on the GNU libio library. Take a look at the info documentation of GNU libc (glibc-1.08) for a more concise description.

BUGS

All functions are fully ANSI C3.159-1989-conformant, but provide the additional flags q and a as well as an additional behavior of the L and l flags. The latter may be considered to be a bug, as it changes the behavior of flags defined in ANSI C3.159-1989.

Some combinations of flags defined by ANSI C are not making sense in ANSI C (for example, %Ld). While they may have a well-defined behavior on Linux, this need not to be so on other architectures. Therefore, it usually is better to use flags that are not defined by ANSI C at all, that is, use q instead of L in combination with dioux conversions or ll.

The usage of q is not the same as on BSD 4.4, as it may be used in float conversions equivalently to L.

Linux man page, 1 November 1995

seekdir

seekdir—Sets the position of the next readdir() call in the directory stream.

SYNOPSIS

```
#include <dirent.h>
void seekdir(DIR *dir, off_t offset);
```

DESCRIPTION

The seekdir() function sets the location in the directory stream from which the next readdir() call will start. seekdir() should be used with an offset returned by telldir().

RETURN VALUE

The `seekdir()` function returns no value.

CONFORMS TO

BSD 4.3

SEE ALSO

`lseek(2)`, `opendir(3)`, `readdir(3)`, `closedir(3)`, `rewinddir(3)`, `telldir(3)`, `scandir(3)`

31 March 1993

setbuf, setbuffer, setlinebuf, setvbuf

setbuf, setbuffer, setlinebuf, setvbuf—Stream buffering operations

SYNOPSIS

```
#include <stdio.h>

int setbuf( FILE *stream, char *buf);
int setbuffer( FILE *stream, char *buf, size_tsize);
int setlinebuf( FILE *stream);
int setvbuf( FILE *stream, char *buf, intmode , size_t size);
```

DESCRIPTION

The three types of buffering available are unbuffered, block buffered, and line buffered. When an output stream is unbuffered, information appears on the destination file or terminal as soon as written; when it is block buffered, many characters are saved up and written as a block; when it is line buffered, characters are saved up until a newline is output or input is read from any stream attached to a terminal device (typically `stdin`). The function `fflush(3)` may be used to force the block out early. (See `fclose(3)`.) Normally all files are block buffered. When the first I/O operation occurs on a file, `malloc(3)` is called, and a buffer is obtained. If a stream refers to a terminal (as `stdout` normally does), it is line buffered. The standard error stream `stderr` is always unbuffered.

The `setvbuf` function may be used at any time on any open stream to change its buffer. The mode parameter must be one of the following three macros:

<code>_IONBF</code>	Unbuffered
<code>_IOLBF</code>	Line buffered
<code>_IOFBF</code>	Fully buffered

Except for unbuffered files, the `buf` argument should point to a buffer at least `size` bytes long; this buffer will be used instead of the current buffer. If the argument `buf` is `NULL`, only the mode is affected; a new buffer will be allocated on the next read or write operation. The `setvbuf` function may be used at any time, but can only change the mode of a stream when it is not “active”; that is, before any I/O, or immediately after a call to `fflush`.

The other three calls are, in effect, simply aliases for calls to `setvbuf`. The `setbuf` function is exactly equivalent to the call:

```
setvbuf(stream, buf, buf ? _IOFBF : _IONBF, BUFSIZ);
```

The `setbuffer` function is the same, except that the size of the buffer is up to the caller, rather than being determined by the default `BUFSIZ`. The `setlinebuf` function is exactly equivalent to the call:

```
setvbuf(stream, (char *)NULL, _IOLBF, 0);
```

SEE ALSO

fopen(3), fclose(3), fread(3), malloc(3), puts(3), printf(3)

STANDARDS

The setbuf and setvbuf functions conform to ANSI C3.159-1989 (ANSI C).

BUGS

The setbuffer and setlinebuf functions are not portable to versions of BSD before 4.2BSD, and may not be available under Linux. On 4.2BSD and 4.3BSD systems, setbuf always uses a suboptimal buffer size and should be avoided. You must make sure that both buf and the space it points to still exist by the time stream is closed, which also happens at program termination. For example, the following is illegal:

```
#include <stdio.h>
int main()
{
    char buf[BUFSIZ];
    setbuf(stdin, buf);
    printf("Hello, world!\n");
    return 0;
}
```

BSD man page, 29 November 1993

setenv

setenv—Changes or adds an environment variable

SYNOPSIS

```
#include <stdlib.h>
int setenv(const char *name, const char *value, int overwrite);
void unsetenv(const char *name);
```

DESCRIPTION

The setenv() function adds the variable name to the environment with the value value, if name does not already exist. If name does exist in the environment, then its value is changed to value if overwrite is non-zero; if overwrite is zero, then the value of name is not changed.

The unsetenv() function deletes the variable name from the environment.

RETURN VALUE

The setenv() function returns zero on success, or -1 if there was insufficient space in the environment.

CONFORMS TO

BSD 4.3

SEE ALSO

getenv(3), putenv(3)

BSD, 4 April 1993

setjmp

setjmp—Saves stack context for nonlocal goto

SYNOPSIS

```
#include <setjmp.h>
int setjmp(jmp_buf env );
```

DESCRIPTION

setjmp and longjmp(3) are useful for dealing with errors and interrupts encountered in a low-level subroutine of a program. setjmp() saves the stack context/environment in env for later use by longjmp(). The stack context will be invalidated if the function which called setjmp() returns.

RETURN VALUE

It returns the value 0 if returning directly and non-zero when returning from longjmp() using the saved context.

CONFORMS TO

POSIX

NOTES

POSIX does not specify if the signal context will be saved or not. If you want to save signal masks, use sigsetjmp(3). setjmp() makes programs hard to understand and maintain. If possible, an alternative should be used.

SEE ALSO

longjmp(3), sigsetjmp(2), siglongjmp(2)

25 November 1994

setlocale

setlocale—Sets the current locale

SYNOPSIS

```
#include <locale.h>
char *setlocale(int category, const char * locale);
```

DESCRIPTION

The setlocale() function is used to set or query the program's current locale. If locale is C or POSIX, the current locale is set to the portable locale.

If locale is "", the locale is set to the default locale that is selected from the environment variable LANG.

On startup of the main program, the portable locale is selected as default.

The argument category determines which functions are influenced by the new locale:

LC_ALL	For all of the locale.
LC_COLLATE	For the functions strcoll() and strxfrm().
LC_CTYPE	For the character classification and conversion routines.
LC_MONETARY	For localeconv().
LC_NUMERIC	For the decimal character.
LC_TIME	For strftime(). NULL if the request can not be honored. This string may be allocated in static storage.

A program may be made portable to all locales by calling `setlocale(LC_ALL, "")` after program initialization, by using the values returned from a `localeconv()` call for locale-dependent information and by using `strcoll()` or `strxfrm()` to compare strings.

CONFORMS TO

ANSI C, POSIX.1

Linux supports the portable locales C and POSIX and also the European Latin-1 and Russian locales.

The `printf()` family of functions may or may not honor the current locale.

SEE ALSO

`locale(1)`, `localedef(1)`, `strcoll(3)`, `isalpha(3)`, `localeconv(3)`, `strftime(3)`, `locale(7)`

GNU, 18 April 1993

siginterrupt

`siginterrupt`—Allows signals to interrupt system calls

SYNOPSIS

```
#include <signal.h>
int siginterrupt(int sig, int flag);
```

DESCRIPTION

The `siginterrupt()` function changes the restart behavior when a system call is interrupted by the signal `sig`. If the `flag` argument is false (0), then systems calls will be restarted if interrupted by the specified signal `sig`. This is the default behavior in Linux. However, when a new signal handler is specified with the `signal(2)` function, the system call is interrupted by default.

If the `flag` argument is true (1) and no data has been transferred, then a system call interrupted by the signal `sig` will return -1 and the global variable `errno` will be set to `EINTR`.

If the `flag` argument is true (1) and data transfer has started, then the system call will be interrupted and will return the actual amount of data transferred.

RETURN VALUE

The `siginterrupt()` function returns 0 on success, or -1 if the signal number `sig` is invalid.

ERRORS

`EINVAL` The specified signal number is invalid.

CONFORMS TO

BSD 4.3

SEE ALSO

`signal(2)`

13 April 1993

sigemptyset, sigfillset, sigaddset, sigdelset, sigismember

`sigemptyset`, `sigfillset`, `sigaddset`, `sigdelset`, `sigismember`—POSIX signal set operations

SYNOPSIS

```
#include <signal.h>
int sigemptyset(sigset_t *set);
int sigfillset(sigset_t *set);
int sigaddset(sigset_t *set, int signum);
int sigdelset(sigset_t *set, int signum);
int sigismember(const sigset_t *set, int signum);
```

DESCRIPTION

The `sigsetops(3)` functions allow the manipulation of POSIX signal sets.

`sigemptyset` initializes the signal set given by `set` to empty, with all signals excluded from the set.

`sigfillset` initializes `set` to full, including all signals.

`sigaddset` and `sigdelset` add and delete, respectively, signal `signum` from `set`.

`sigismember` tests whether `signum` is a member of `set`.

RETURN VALUES

`sigemptyset`, `sigfullset`, `sigaddset`, and `sigdelset` return 0 on success and -1 on error.

`sigismember` returns 1 if `signum` is a member of `set`, 0 if `signum` is not a member, and -1 on error.

ERRORS

`EINVAL` `sig` is not a valid signal.

CONFORMS TO

POSIX

SEE ALSO

`sigaction(2)`, `sigpending(2)`, `sigprocmask(2)`, `sigsuspend(2)`

Linux 1.0, 24 September 1994

sin

`sin`—Sine function

SYNOPSIS

```
#include <math.h>
double sin(double x);
```

DESCRIPTION

The `sin()` function returns the sine of `x`, where `x` is given in radians.

RETURN VALUE

The `sin()` function returns a value between -1 and 1.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`acos(3)`, `asin(3)`, `atan(3)`, `atan2(3)`, `cos(3)`, `tan(3)`

8 June 1993

sinh

`sinh`—Hyperbolic sine function

SYNOPSIS

```
#include <math.h>
double sinh(double x);
```

DESCRIPTION

The `sinh()` function returns the hyperbolic sine of `x`, which is defined mathematically as $[\exp(x) - \exp(-x)] / 2$.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`acosh(3)`, `asinh(3)`, `atanh(3)`, `cosh(3)`, `tanh(3)`

13 June 1993

sleep

`sleep`—Sleeps for the specified number of seconds

SYNOPSIS

```
#include <unistd.h>
unsigned int sleep(unsigned int seconds);
```

DESCRIPTION

`sleep()` makes the current process sleep until `seconds` seconds have elapsed or a signal arrives that is not ignored.

RETURN VALUE

The return value is zero if the requested time has elapsed, or the number of seconds left to sleep.

CONFORMS TO

POSIX.1

BUGS

`sleep()` may be implemented using `SIGALRM`; mixing calls to `alarm()` and `sleep()` is a bad idea.

Using `longjmp()` from a signal handler or modifying the handling of `SIGALRM` while sleeping will cause undefined results.

SEE ALSO

`signal(2)`, `alarm(2)`

GNU, 7 April 1993

snprintf, vsnprintf

snprintf, vsnprintf—Formatted output conversion

SYNOPSIS

```
#include <stdio.h>

int snprintf ( char *str, size_t n,
               const char *format, ... );

#include <stdarg.h>

int vsnprintf ( char *str, size_t n,
               const char *format, va_list ap );
```

DESCRIPTION

snprintf writes output to the string `str`, under control of the `format` string that specifies how subsequent arguments are converted for output. It is similar to `sprintf(3)`, except that `n` specifies the maximum number of characters to produce. The trailing null character is counted towards this limit, so you should allocate at least `n` characters for the string `str`.

vsnprintf is the equivalent of `snprintf` with the variable argument list specified directly as for `vprintf`.

RETURN VALUE

The return value is the number of characters stored, not including the terminating null. If this value equals `n`, then there was not enough space in `str` for all the output. You should try again with a bigger output string.

EXAMPLE

Here is a sample program that dynamically enlarges its output buffer:

```
/* Construct a message describing the value of a
   variable whose name is NAME and whose value is
   VALUE. */
char *
make_message (char *name, char *value)
{
    /* Guess we need no more than 100 chars of space. */
    int size = 100;
    char *buffer = (char *) xmalloc (size);
    while (1)
    {
        /* Try to print in the allocated space. */
        int nchars = snprintf (buffer, size,
                               "value of %s is %s", name, value);
        /* If that worked, return the string. */
        if (nchars < size)
            return buffer;
        /* Else try again with twice as much space. */
        size *= 2;
        buffer = (char *) xrealloc (size, buffer);
    }
}
```

CONFORMS TO

These are GNU extensions.

SEE ALSO

printf(3), sprintf(3), vsprintf(3), stdarg(3)

GNU, 16 September 1995

sqrt

sqrt—Square root function

SYNOPSIS

```
#include <math.h>
double sqrt(double x);
```

DESCRIPTION

The `sqrt()` function returns the non-negative square root of `x`. It fails and sets `errno` to `EDOM`, if `x` is negative.

ERRORS

`EDOM` `x` is negative.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

hypot(3)

21 June 1993

stdarg

stdarg—Variable argument lists

SYNOPSIS

```
#include <stdarg.h>
void va_start( va_list ap, last);
type va_arg( va_list ap, type);
void va_end( va_list ap);
```

DESCRIPTION

A function may be called with a varying number of arguments of varying types. The include file `stdarg.h` declares a type `va_list` and defines three macros for stepping through a list of arguments whose number and types are not known to the called function.

The called function must declare an object of type `va_list` that is used by the macros `va_start`, `va_arg`, and `va_end`.

The `va_start` macro initializes `ap` for subsequent use by `va_arg` and `va_end`, and must be called first.

The parameter `last` is the name of the last parameter before the variable argument list; that is, the last parameter of which the calling function knows the type.

Because the address of this parameter is used in the `va_start` macro, it should not be declared as a register variable, a function, or an array type.

The `va_start` macro returns no value.

The `va_arg` macro expands to an expression that has the type and value of the next argument in the call. The parameter `ap` is the `va_list` `ap` initialized by `va_start`. Each call to `va_arg` modifies `ap` so that the next call returns the next argument. The parameter type is a type name specified so that the type of a pointer to an object that has the specified type can be obtained simply by adding a `*` to type.

If there is no next argument, or if type is not compatible with the type of the actual next argument (as promoted according to the default argument promotions), random errors will occur.

The first use of the `va_arg` macro after that of the `va_start` macro returns the argument after last. Successive invocations return the values of the remaining arguments.

The `va_end` macro handles a normal return from the function whose variable argument list was initialized by `va_start`.

The `va_end` macro returns no value.

EXAMPLE

The function `foo` takes a string of format characters and prints out the argument associated with each format character based on the type.

```
void foo(char *fmt, ...)
{
    va_list ap;
    int d;
    char c, *p, *s;

    va_start(ap, fmt);
    while (*fmt)
        switch(*fmt++) {
            case 's':          /* string */
                s = va_arg(ap, char *);
                printf("string %s\n", s);
                break;
            case 'd':          /* int */
                d = va_arg(ap, int);
                printf("int %d\n", d);
                break;
            case 'c':          /* char */
                c = va_arg(ap, char);
                printf("char %c\n", c);
                break;
        }
    va_end(ap);
}
```

STANDARDS

The `va_start`, `va_arg`, and `va_end` macros conform to ANSI C3.159-1989 (ANSI C).

COMPATIBILITY

These macros are not compatible with the historic macros they replace. A backwards-compatible version can be found in the include file `varargs.h`.

BUGS

Unlike the `varargs` macros, the `stdarg` macros do not permit programmers to code a function with no fixed arguments. This problem generates work mainly when converting `varargs` code to `stdarg` code, but it also creates difficulties for variadic functions that wish to pass all of their arguments on to a function that takes a `va_list` argument, such as `vfprintf(3)`.

stdio

stdio—Standard input/output library functions

SYNOPSIS

```
#include <stdio.h>
FILE *stdin;
FILE *stdout;
FILE *stderr;
```

DESCRIPTION

The standard I/O library provides a simple and efficient buffered stream I/O interface. Input and output is mapped into logical data streams and the physical I/O characteristics are concealed. The functions and macros are listed in this section; more information is available from the individual man pages.

A stream is associated with an external file (which may be a physical device) by opening a file, which may involve creating a new file. Creating an existing file causes its former contents to be discarded. If a file can support positioning requests (such as a disk file, as opposed to a terminal), then a file position indicator associated with the stream is positioned at the start of the file (byte zero), unless the file is opened with append mode. If append mode is used, the position indicator will be placed the end-of-file. The position indicator is maintained by subsequent reads, writes, and positioning requests. All input occurs as if the characters were read by successive calls to the `fgetc(3)` function; all output takes place as if all characters were read by successive calls to the `fputc(3)` function.

A file is disassociated from a stream by closing the file. Output streams are flushed (any unwritten buffer contents are transferred to the host environment) before the stream is disassociated from the file. The value of a pointer to a `FILE` object is indeterminate after a file is closed (garbage).

A file may be subsequently reopened, by the same or another program execution, and its contents reclaimed or modified (if it can be repositioned at the start). If the main function returns to its original caller, or the `exit(3)` function is called, all open files are closed (hence all output streams are flushed) before program termination. Other methods of program termination, such as `abort(3)` do not bother about closing files properly.

At program startup, three text streams are predefined and need not be opened explicitly: standard input (for reading conventional input), standard output (for writing conventional input), and standard error (for writing diagnostic output). These streams are abbreviated `stdin`, `stdout`, and `stderr`. When opened, the standard error stream is not fully buffered; the standard input and output streams are fully buffered if and only if the streams do not refer to an interactive device.

Output streams that refer to terminal devices are always line buffered by default; pending output to such streams is written automatically whenever an input stream that refers to a terminal device is read. In cases where a large amount of computation is done after printing part of a line on an output terminal, it is necessary to `fflush(3)` the standard output before going off and computing so that the output will appear.

The `stdio` library is a part of the library `libc` and routines are automatically loaded as needed by the compilers `cc(1)` and `pc(1)`. The `SYNOPSIS` sections of the following manual pages indicate which include files are to be used, what the compiler declaration for the function looks like, and which external variables are of interest.

The following are defined as macros; these names may not be reused without first removing their current definitions with `#undef`: `BUFSIZ`, `EOF`, `FILENAME_MAX`, `FOPEN_MAX`, `L_cuserid`, `L_ctermid`, `L_tmpnam`, `NULL`, `SEEK_END`, `SEEK_SET`, `SEEK_CUR`, `TMP_MAX`, `clearerr`, `feof`, `ferror`, `fileno`, `fopen`, `fwopen`, `getc`, `getchar`, `putc`, `putchar`, `stderr`, `stdin`, `stdout`. Function versions of the macro functions `feof`, `ferror`, `clearerr`, `fileno`, `getc`, `getchar`, `putc`, and `putchar` exist and will be used if the macros definitions are explicitly removed.

SEE ALSO

`open(2)`, `close(2)`, `read(2)`, `write(2)`

BUGS

The standard buffered functions do not interact well with certain other library and system functions, especially `vfork` and `abort`. This may not be the case under Linux.

STANDARDS

The `stdio` library conforms to ANSI C3.159-1989 (ANSI C).

LIST OF FUNCTIONS

<i>Function</i>	<i>Description</i>
<code>clearerr</code>	Check and reset stream status
<code>fclose</code>	Close a stream
<code>fdopen</code>	Stream open functions
<code>feof</code>	Check and reset stream status
<code>ferror</code>	Check and reset stream status
<code>fflush</code>	Flush a stream
<code>fgetc</code>	Get next character or word from input stream
<code>fgetline</code>	Get a line from a stream
<code>fgetpos</code>	Reposition a stream
<code>fgets</code>	Get a line from a stream
<code>fileno</code>	Check and reset stream status
<code>fopen</code>	Stream open functions
<code>fprintf</code>	Formatted output conversion
<code>fpurge</code>	Flush a stream
<code>fputc</code>	Output a character or word to a stream
<code>fputs</code>	Output a line to a stream
<code>fread</code>	Binary stream input/output
<code>freopen</code>	Stream open functions
<code>fropen</code>	Open a stream
<code>fscanf</code>	Input format conversion
<code>fseek</code>	Reposition a stream
<code>fsetpos</code>	Reposition a stream
<code>ftell</code>	Reposition a stream
<code>fwrite</code>	Binary stream input/output
<code>getc</code>	Get next character or word from input stream
<code>getchar</code>	Get next character or word from input stream
<code>gets</code>	Get a line from a stream
<code>getw</code>	Get next character or word from input stream
<code>mktemp</code>	Make temporary filename (unique)
<code>perror</code>	System error messages
<code>printf</code>	Formatted output conversion
<code>putc</code>	Output a character or word to a stream
<code>putchar</code>	Output a character or word to a stream
<code>puts</code>	Output a line to a stream
<code>putw</code>	Output a character or word to a stream

<code>remove</code>	Remove directory entry
<code>rewind</code>	Reposition a stream
<code>scanf</code>	Input format conversion
<code>setbuf</code>	Stream buffering operations
<code>setbuffer</code>	Stream buffering operations
<code>setlinebuf</code>	Stream buffering operations
<code>setvbuf</code>	Stream buffering operations
<code>sprintf</code>	Formatted output conversion
<code>sscanf</code>	Input format conversion
<code>strerror</code>	System error messages
<code>sys_errlist</code>	System error messages
<code>sys_nerr</code>	System error messages
<code>tempnam</code>	Temporary file routines
<code>tmpfile</code>	Temporary file routines
<code>tmpnam</code>	Temporary file routines
<code>ungetc</code>	Un-get character from input stream
<code>vfprintf</code>	Formatted output conversion
<code>vfscanf</code>	Input format conversion
<code>vprintf</code>	Formatted output conversion
<code>vscanf</code>	Input format conversion
<code>vsprintf</code>	Formatted output conversion
<code>vsscanf</code>	Input format conversion

BSD man page, 29 November 1993

stpcpy

stpcpy—Copies a string returning a pointer to its end

SYNOPSIS

```
#include <string.h>
char *stpcpy(char *dest, const char *src);
```

DESCRIPTION

The `stpcpy()` function copies the string pointed to by `src` (including the terminating `\0` character) to the array pointed to by `dest`. The strings may not overlap, and the destination string `dest` must be large enough to receive the copy.

RETURN VALUE

`stpcpy()` returns a pointer to the end of the string `dest` (that is, the address of the terminating null character) rather than the beginning.

EXAMPLE

For example, this program uses `stpcpy` to concatenate `foo` and `bar` to produce `foobar`, which it then prints:

```
#include <string.h>

int
main (void)
{
```

```

char *to = buffer;
to = stpcpy (to, "foo");
to = stpcpy (to, "bar");
printf ("%s\n", buffer);
}

```

CONFORMS TO

This function is not part of the ANSI or POSIX standards, and is not customary on UNIX systems, but is not a GNU invention either. Perhaps it comes from MS-DOS.

SEE ALSO

`strcpy(3)`, `bcopy(3)`, `memcpy(3)`, `memmove(3)`

GNU, 3 September 1995

strcasemp, strncasemp

`strcasemp`, `strncasemp`—Compare two strings, ignoring case

SYNOPSIS

```

#include <string.h>
int strcasemp(const char *s1, const char *s2);
int strncasemp(const char *s1, const char *s2, size_t n);

```

DESCRIPTION

The `strcasemp()` function compares the two strings `s1` and `s2`, ignoring the case of the characters. It returns an integer less than, equal to, or greater than zero if `s1` is found, respectively, to be less than, to match, or be greater than `s2`.

The `strncasemp()` function is similar, except it only compares the first `n` characters of `s1`.

RETURN VALUE

The `strcasemp()` and `strncasemp()` functions return an integer less than, equal to, or greater than zero if `s1` (or the first `n` bytes thereof) is found, respectively, to be less than, to match, or be greater than `s2`.

CONFORMS TO

BSD 4.3

SEE ALSO

`bcmp(3)`, `memcmp(3)`, `strcmp(3)`, `strcoll(3)`, `strncmp(3)`

11 April 1993

strcat, strncat

`strcat`, `strncat`—Concatenate two strings

SYNOPSIS

```

#include <string.h>
char *strcat(char *dest, const char *src);
char *strncat(char *dest, const char *src, size_t n);

```


DESCRIPTION

The `strcat()` function appends the `src` string to the `dest` string, overwriting the `\0` character at the end of `dest`, and then adds a terminating `\0` character. The strings may not overlap, and the `dest` string must have enough space for the result.

The `strncat()` function is similar, except that only the first `n` characters of `src` are appended to `dest`.

RETURN VALUE

The `strcat()` and `strncat()` functions return a pointer to the resulting string `dest`.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`bcopy(3)`, `memccpy(3)`, `memcpy(3)`, `strcpy(3)`, `strncpy(3)`

GNU, 11 April 1993

strchr, strrchr

`strchr`, `strrchr`—Locate character in string

SYNOPSIS

```
#include <string.h>
char *strchr(const char *s, int c);
char *strrchr(const char *s, int c);
```

DESCRIPTION

The `strchr()` function returns a pointer to the first occurrence of the character `c` in the string `s`.

The `strrchr()` function returns a pointer to the last occurrence of the character `c` in the string `s`.

RETURN VALUE

The `strchr()` and `strrchr()` functions return a pointer to the matched character or `NULL` if the character is not found.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`index(3)`, `memchr(3)`, `rindex(3)`, `strpbrk(3)`, `strsep(3)`, `strspn(3)`, `strstr(3)`, `strtok(3)`

12 April 1993

strcmp, strncmp

`strcmp`, `strncmp`—Compare two strings

SYNOPSIS

```
#include <string.h>
int strcmp(const char *s1, const char *s2);
int strncmp(const char *s1, const char *s2, size_t n);
```

DESCRIPTION

The `strcmp()` function compares the two strings `s1` and `s2`. It returns an integer less than, equal to, or greater than zero if `s1` is found, respectively, to be less than, to match, or be greater than `s2`.

The `strncmp()` function is similar, except it only compares the first `n` characters of `s1`.

RETURN VALUE

The `strcmp()` and `strncmp()` functions return an integer less than, equal to, or greater than zero if `s1` (or the first `n` bytes thereof) is found, respectively, to be less than, to match, or be greater than `s2`.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`bcmp(3)`, `memcmp(3)`, `strcasemp(3)`, `strncasemp(3)`, `strcoll(3)`

11 April 1993

strcoll

`strcoll`—Compares two strings using the current locale

SYNOPSIS

```
#include <string.h>
int strcoll(const char *s1, const char *s2);
```

DESCRIPTION

The `strcoll()` function compares the two strings `s1` and `s2`. It returns an integer less than, equal to, or greater than zero if `s1` is found, respectively, to be less than, to match, or be greater than `s2`. The comparison is based on strings interpreted as appropriate for the program's current locale for category `LC_COLLATE`. (See `setlocale(3)`).

RETURN VALUE

The `strcoll()` function returns an integer less than, equal to, or greater than zero if `s1` is found, respectively, to be less than, to match, or be greater than `s2`, when both are interpreted as appropriate for the current locale.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

NOTES

The Linux C Library currently hasn't implemented the complete POSIX-collating.

In the POSIX or C locales, `strcoll()` is equivalent to `strcmp()`.

SEE ALSO

`bcmp(3)`, `memcmp(3)`, `strcasemp(3)`, `strcmp(3)`, `strxfrm(3)`, `setlocale(3)`

GNU, 12 April 1993

strcpy, strncpy

`strcpy`, `strncpy`—Copy a string

SYNOPSIS

```
#include <string.h>
char *strcpy(char *dest, const char *src);
char *strncpy(char *dest, const char *src, size_t n);
```

DESCRIPTION

The `strcpy()` function copies the string pointed to by `src` (including the terminating `\0` character) to the array pointed to by `dest`. The strings may not overlap, and the destination string `dest` must be large enough to receive the copy.

The `strncpy()` function is similar, except that not more than `n` bytes of `src` are copied. Thus, if there is no null byte among the first `n` bytes of `src`, the result will not be null-terminated.

In the case where the length of `src` is less than that of `n`, the remainder of `dest` will be padded with nulls.

RETURN VALUE

The `strcpy()` and `strncpy()` functions return a pointer to the destination string `dest`.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`bcopy(3)`, `memcpy(3)`, `memmove(3)`

GNU, 11 April 1993

strdup

`strdup`—Duplicates a string

SYNOPSIS

```
#include <string.h>
char *strdup(const char *s);
```

DESCRIPTION

The `strdup()` function returns a pointer to a new string that is a duplicate of the string `s`. Memory for the new string is obtained with `malloc(3)`, and can be freed with `free(3)`.

RETURN VALUE

The `strdup()` function returns a pointer to the duplicated string, or `NULL` if insufficient memory was available.

ERRORS

`ENOMEM`

Insufficient memory available to allocate duplicate string

CONFORMS TO

SVID 3, BSD 4.3

SEE ALSO

`calloc(3)`, `malloc(3)`, `realloc(3)`, `free(3)`

GNU, 12 April 1993

strerror

`strerror`—Returns string describing error code

SYNOPSIS

```
#include <string.h>

char *strerror(int errnum);
```

DESCRIPTION

The `strerror()` function returns a string describing the error code passed in the argument `errnum`. The string can only be used until the next call to `strerror()`.

RETURN VALUE

The `strerror()` function returns the appropriate description string, or an unknown error message if the error code is unknown.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`errno(3)`, `perror(3)`, `strsignal(3)`

GNU, 13 April 1993

strfry

`strfry`—Randomizes a string

SYNOPSIS

```
#include <string.h>

char *strfry(char *string);
```

DESCRIPTION

The `strfry()` function randomizes the contents of `string` by using `rand(3)` to randomly swap characters in the string. The result is an anagram of `string`.

RETURN VALUE

The `strfry()` function returns a pointer to the randomized string.

CONFORMS TO

The `strfry()` function is unique to the Linux C Library and GNU C Library.

SEE ALSO

`memfrob(3)`

GNU, 12 April 1993

strftime

`strftime`—Formats date and time

SYNOPSIS

```
#include <time.h>
size_t strftime(char *s, size_t max, const char *format,
const struct tm *tm);
```

DESCRIPTION

The `strftime()` function formats the broken-down time `tm` according to the format specification `format` and places the result in the character array `s` of size `max`.

Ordinary characters placed in the format string are copied to `s` without conversion. Conversion specifiers are introduced by a `%` character, and are replaced in `s` as follows:

<code>%a</code>	The abbreviated weekday name according to the current locale
<code>%A</code>	The full weekday name according to the current locale
<code>%b</code>	The abbreviated month name according to the current locale
<code>%B</code>	The full month name according to the current locale
<code>%c</code>	The preferred date and time representation for the current locale
<code>%d</code>	The day of the month as a decimal number (range 01 to 31)
<code>%H</code>	The hour as a decimal number using a 24-hour clock (range 00 to 23)
<code>%I</code>	The hour as a decimal number using a 12-hour clock (range 01 to 12)
<code>%j</code>	The day of the year as a decimal number (range 001 to 366)
<code>%m</code>	The month as a decimal number (range 01 to 12)
<code>%M</code>	The minute as a decimal number
<code>%p</code>	Either a.m. or p.m. according to the given time value, or the corresponding strings for the current locale
<code>%S</code>	The second as a decimal number
<code>%U</code>	The week number of the current year as a decimal number, starting with the first Sunday as the first day of the first week
<code>%W</code>	The week number of the current year as a decimal number, starting with the first Monday as the first day of the first week
<code>%w</code>	The day of the week as a decimal, Sunday being 0
<code>%x</code>	The preferred date representation for the current locale without the time
<code>%X</code>	The preferred time representation for the current locale without the date
<code>%y</code>	The year as a decimal number without a century (range 00 to 99)
<code>%Y</code>	The year as a decimal number including the century
<code>%Z</code>	The time zone or name or abbreviation
<code>%%</code>	A literal <code>%</code> character

The broken-down time structure `tm` is defined in `<time.h>` as follows:

```
struct tm
{
int tm_sec; /* seconds */
int tm_min; /* minutes */
int tm_hour; /* hours */
int tm_mday; /* day of the month */
int tm_mon; /* month */
int tm_year; /* year */
int tm_wday; /* day of the week */
int tm_yday; /* day in the year */
int tm_isdst; /* daylight saving time */
};
```

The members of the `tm` structure are

<code>tm_sec</code>	The number of seconds after the minute, normally in the range 0 to 59, but can be up to 61 to allow for leap seconds.
<code>tm_min</code>	The number of minutes after the hour, in the range 0 to 59.
<code>tm_hour</code>	The number of hours past midnight, in the range 0 to 23.
<code>tm_mday</code>	The day of the month, in the range 1 to 31.
<code>tm_mon</code>	The number of months since January, in the range 0 to 11.
<code>tm_year</code>	The number of years since 1900.
<code>tm_wday</code>	The number of days since Sunday, in the range 0 to 6.
<code>tm_yday</code>	The number of days since January 1, in the range 0 to 365.
<code>tm_isdst</code>	A flag that indicates whether daylight saving time is in effect at the time described. The value is positive if daylight saving time is in effect, zero if it is not, and negative if the information is not available.

RETURN VALUE

The `strptime()` function returns the number of characters placed in the array `s`, not including the terminating `NULL` character. If the value equals `max`, it means that the array was too small.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`date(1)`, `time(2)`, `ctime(3)`, `setlocale(3)`, `sprintf(3)`

NOTES

The function supports only those locales specified in `locale(7)`

GNU, 2 July 1993

`strcasemp`, `strcat`, `strchr`, `strcmp`, `strcoll`, `strcpy`, `strcspn`,
`strdup`, `strfry`, `strlen`, `strncat`, `strncmp`, `strncpy`, `strncasemp`,
`strpbrk`, `strrchr`, `strsep`, `strspn`, `strstr`, `strtok`, `strxfrm`,
`index`, `rindex`

`strcasemp`, `strcat`, `strchr`, `strcmp`, `strcoll`, `strcpy`, `strcspn`, `strdup`, `strfry`, `strlen`, `strncat`, `strncmp`, `strncpy`, `strncasemp`,
`strpbrk`, `strrchr`, `strsep`, `strspn`, `strstr`, `strtok`, `strxfrm`, `index`, `rindex`—String operations

SYNOPSIS

```
#include <string.h>
int strcasemp(const char *s1, const char *s2);
char *strcat(char *dest, const char *src);
char *strchr(const char *s, int c);
int strcmp(const char *s1, const char *s2);
int strcoll(const char *s1, const char *s2);
char *strcpy(char *dest, const char *src);
size_t strcspn(const char *s, const char *reject);
char *strdup(const char *s);
```

```

char *strfry(char *string);
size_t strlen(const char *s);
char *strncat(char *dest, const char *src, size_t n);
int strncmp(const char *s1, const char *s2, size_t n);
char *strncpy(char *dest, const char *src, size_t n);
int strncasecmp(const char *s1, const char *s2, size_t n);
char *strpbrk(const char *s, const char *accept);
char *strrchr(const char *s, int c);
char *strsep(char **stringp, const char *delim);
size_t strspn(const char *s, const char *accept);
char *strstr(const char *haystack, const char *needle);
char *strtok(char *s, const char *delim);
size_t strxfrm(char *dest, const char *src, size_t n);
char *index(const char *s, int c);
char *rindex(const char *s, int c);

```

DESCRIPTION

The string functions perform string operations on NULL-terminated strings. See the individual man pages for descriptions of each function.

SEE ALSO

index(3), rindex(3), strcasecmp(3), strcat(3), strchr(3), strcmp(3), strcoll(3), strcpy(3), strcspn(3), strdup(3), strfry(3), strlen(3), strncat(3), strncmp(3), strncpy(3), strncasecmp(3), strpbrk(3), strrchr(3), strsep(3), strspn(3), strstr(3), strtok(3), strxfrm(3)

9 April 1993

strlen

strlen—Calculates the length of a string

SYNOPSIS

```

#include <string.h>
size_t strlen(const char *s);

```

DESCRIPTION

The strlen() function calculates the length of the string s, not including the terminating \0 character.

RETURN VALUE

The strlen() function returns the number of characters in s.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

string(3)

12 April 1993

strpbrk

strpbrk—Searches a string for any of a set of characters

SYNOPSIS

```
#include <string.h>
char *strpbrk(const char *s, const char *accept);
```

DESCRIPTION

The `strpbrk()` function locates the first occurrence in the string `s` of any of the characters in the string `accept`.

RETURN VALUE

The `strpbrk()` function returns a pointer to the character in `s` that matches one of the characters in `accept`.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`index(3)`, `memchr(3)`, `rindex(3)`, `strchr(3)`, `strsep(3)`, `strspn(3)`, `strstr(3)`, `strtok(3)`

12 April 1993

strptime

`strptime`—Converts a string representation of time to a time `tm` structure

SYNOPSIS

```
#include <time.h>
char *strptime(char *buf, const char *format, const struct tm *tm);
```

DESCRIPTION

`strptime()` is the complementary function to `strftime()` and converts the character string pointed to by `buf` to a time value, which is stored in the `tm` structure pointed to by `tm`, using the format specified by `format`. `format` is a character string that consists of field descriptors and text characters, reminiscent of `scanf(3)`. Each field descriptor consists of a `%` character followed by another character that specifies the replacement for the field descriptor. All other characters are copied from `format` into the result. The following field descriptors are supported:

<code>%%</code>	Same as <code>%</code> .
<code>%a, %A</code>	Day of week, using locale's weekday names; either the abbreviated or full name may be specified.
<code>%b, %B, %h</code>	Month, using locale's month names; either the abbreviated or full name may be specified.
<code>%c</code>	Date and time as <code>%x, %X</code> .
<code>%C</code>	Date and time, in locale's long-format date and time representation.
<code>%d, %e</code>	Day of month (1–31; leading zeroes are permitted but not required).
<code>%D</code>	Date as <code>%m/%d/%y</code> .
<code>%H, %k</code>	Hour (0–23; leading zeroes are permitted but not required).
<code>%I, %l</code>	Hour (0–12; leading zeroes are permitted but not required).
<code>%j</code>	Day number of year (001–366).
<code>%m</code>	Month number (1–12; leading zeroes are permitted but not required).
<code>%M</code>	Minute (0–59; leading zeroes are permitted but not required).
<code>%p</code>	Locale's equivalent of a.m. or p.m.
<code>%r</code>	Time as <code>%I:%M:%S %p</code> .

%R	Time as %H:%M.
%S	Seconds (0–61; leading zeroes are permitted but not required; extra second allowed for leap years).
%T	Time as %H:%M:%S.
%w	Weekday number (0–6) with Sunday as the first day of the week.
%x	Date, using locale's date format.
%X	Time, using locale's time format.
%y	Year within century (0–99; leading zeroes are permitted but not required. Unfortunately, this makes the assumption that we are stuck in the 20th century, as 1900 is automatically added onto this number for the <code>tm</code> year field.)
%Y	Year, including century (for example, 1988).

Case is ignored when matching items such as month or weekday names.

The broken-down time structure `tm` is defined in `<time.h>` as follows:

```
struct tm
{
    int tm_sec; /* seconds */
    int tm_min; /* minutes */
    int tm_hour; /* hours */
    int tm_mday; /* day of the month */
    int tm_mon; /* month */
    int tm_year; /* year */
    int tm_wday; /* day of the week */
    int tm_yday; /* day in the year */
    int tm_isdst; /* daylight saving time */
};
```

RETURN VALUE

The `strptime()` function returns a pointer to the character following the last character in the string pointed to by `buf`.

SEE ALSO

`strftime(3)`, `time(2)`, `setlocale(3)`, `scanf(3)`

BUGS

The return values point to static data, whose contents are overwritten by each call.

NOTES

This function is only available in libraries newer than version 4.6.5.

The function supports only those locales specified in `locale(7)`.

GNU, 26 September 1994

strsep

`strsep`—Extracts token from string

SYNOPSIS

```
#include <string.h>
char *strsep(char **stringp, const char *delim);
```

DESCRIPTION

The `strsep()` function returns the next token from the string `stringp` which is delimited by `delim`. The token is terminated with a `\0` character and `stringp` is updated to point past the token.

RETURN VALUE

The `strsep()` function returns a pointer to the token, or `NULL` if `delim` is not found in `stringp`.

CONFORMS TO

BSD 4.3

SEE ALSO

`index(3)`, `memchr(3)`, `rindex(3)`, `strchr(3)`, `strpbrk(3)`, `strspn(3)`, `strstr(3)`, `strtok(3)`

GNU, 12 April 1993

strsignal

`strsignal`—Returns string describing signal

SYNOPSIS

```
#include <string.h>
char *strsignal(int sig);
extern const char * const sys_siglist[]
```

DESCRIPTION

The `strsignal()` function returns a string describing the signal number passed in the argument `sig`. The string can only be used until the next call to `strsignal()`.

The array `sys_siglist` holds the signal description strings indexed by signal number.

RETURN VALUE

The `strsignal()` function returns the appropriate description string, or an unknown signal message if the signal number is invalid.

SEE ALSO

`psignal(3)`, `strerror(3)`

GNU, 13 April 1993

strspn, strcspn

`strspn`, `strcspn`—Search a string for a set of characters

SYNOPSIS

```
#include <string.h>
size_t strspn(const char *s, const char *accept);
size_t strcspn(const char *s, const char *reject);
```

DESCRIPTION

The `strspn()` function calculates the length of the initial segment of `s`, which consists entirely of characters in `accept`.

The `strcspn()` function calculates the length of the initial segment of `s`, which consists entirely of characters not in `reject`.

RETURN VALUE

The `strspn()` function returns the number of characters in the initial segment of `s`, which consist only of characters from `accept`.

The `strcspn()` function returns the number of characters in the initial segment of `s`, which are not in the string `reject`.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`index(3)`, `memchr(3)`, `rindex(3)`, `strchr(3)`, `strpbrk(3)`, `strsep(3)`, `strstr(3)`, `strtok(3)`

12 April 1993

strstr

`strstr`—Locates a substring

SYNOPSIS

```
#include <string.h>
char *strstr(const char *haystack, const char *needle);
```

DESCRIPTION

The `strstr()` function finds the first occurrence of the substring `needle` in the string `haystack`. The terminating `\0` characters are not compared.

RETURN VALUE

The `strstr()` function returns a pointer to the beginning of the substring, or `NULL` if the substring is not found.

SEE ALSO

`index(3)`, `memchr(3)`, `rindex(3)`, `strchr(3)`, `strpbrk(3)`, `strsep(3)`, `strspn(3)`, `strtok(3)`

GNU, 12 April 1993

strtod

`strtod`—Converts ASCII string to double

SYNOPSIS

```
#include <stdlib.h>
double strtod(const char *nptr, char **endptr);
```

DESCRIPTION

The `strtod()` function converts the initial portion of the string pointed to by `nptr` to double representation.

The expected form of the string is optional leading whitespace as checked by `isspace(3)`, an optional plus (+) or minus sign (-) followed by a sequence of digits optionally containing a decimal point character, optionally followed by an exponent. An exponent consists of an `E` or `e`, followed by an optional plus or minus sign, followed by a nonempty sequence of digits. If the locale is not `C` or `POSIX`, different formats may be used.

RETURN VALUES

The `strtod` function returns the converted value, if any.

If `endptr` is not `NULL`, a pointer to the character after the last character used in the conversion is stored in the location referenced by `endptr`.

If no conversion is performed, zero is returned and the value of `nptr` is stored in the location referenced by `endptr`.

If the correct value would cause overflow, plus or minus `HUGE_VAL` is returned (according to the sign of the value), and `ERANGE` is stored in `errno`. If the correct value would cause underflow, zero is returned and `ERANGE` is stored in `errno`.

ERRORS

`ERANGE` Overflow or underflow occurred.

CONFORMS TO

ANSI C

SEE ALSO

`atof(3)`, `atoi(3)`, `atol(3)`, `strtol(3)`, `strtoul(3)`

BSD man page, 4 March 1996

strtok

`strtok`—Extracts token from string

SYNOPSIS

```
#include <string.h>
char *strtok(char *s, const char *delim);
```

DESCRIPTION

A token is a nonempty string of characters not occurring in the string `delim`, followed by `\0` or by a character occurring in `delim`.

The `strtok()` function can be used to parse the string `s` into tokens. The first call to `strtok()` should have `s` as its first argument. Subsequent calls should have the first argument set to `NULL`. Each call returns a pointer to the next token, or `NULL` when no more tokens are found.

If a token ends with a delimiter, this delimiting character is overwritten with a `\0` and a pointer to the next character is saved for the next call to `strtok`. The delimiter string `delim` may be different for each call.

BUGS

This function modifies its first argument. The identity of the delimiting character is lost.

RETURN VALUE

The `strtok()` function returns a pointer to the next token, or `NULL` if there are no more tokens.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`index(3)`, `memchr(3)`, `rindex(3)`, `strchr(3)`, `strpbrk(3)`, `strsep(3)`, `strspn(3)`, `strstr(3)`

GNU, 10 February 1996

strtol

strtol—Converts a string to a long integer

SYNOPSIS

```
#include <stdlib.h>
long int strtol(const char *nptr, char **endptr, int base);
```

DESCRIPTION

The `strtol()` function converts the string in `nptr` to a long integer value according to the given base, which must be between 2 and 36 inclusive, or be the special value 0.

The string must begin with an arbitrary amount of whitespace (as determined by `isspace(3)`) followed by a single optional `+` or `-` sign. If base is zero or 16, the string may then include a `0x` prefix, and the number will be read in base 16; otherwise, a zero base is taken as 10 (decimal) unless the next character is 0, in which case it is taken as 8 (octal).

The remainder of the string is converted to a long int value in the obvious manner, stopping at the first character that is not a valid digit in the given base. (In bases above 10, the letter A in either upper- or lowercase represents 10, b represents 11, and so forth, with z representing 35.)

If `endptr` is not NULL, `strtol()` stores the address of the first invalid character in `*endptr`. If there were no digits at all, `strtol()` stores the original value of `nptr` in `*endptr`. (Thus, if `*nptr` is not `\0` but `**endptr` is `\0` on return, the entire string is valid.)

RETURN VALUE

The `strtol()` function returns the result of the conversion, unless the value would underflow or overflow. If an underflow occurs, `strtol()` returns `LONG_MIN`. If an overflow occurs, `strtol()` returns `LONG_MAX`. In both cases, `errno` is set to `ERANGE`.

ERRORS

<code>ERANGE</code>	The given string was out of range; the value converted has been clamped.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

SEE ALSO

`atof(3)`, `atoi(3)`, `atol(3)`, `strtod(3)`, `strtoul(3)`

BUGS

Ignores the current locale.

GNU, 10 June 1995

strtoul

strtoul—Converts a string to an unsigned long integer.

SYNOPSIS

```
#include <stdlib.h>
unsigned long int strtoul(const char *nptr, char **endptr,
int base);
```

DESCRIPTION

The `strtoul()` function converts the string in `nptr` to an unsigned long integer value according to the given base, which must be between 2 and 36 inclusive, or be the special value 0.

The string must begin with an arbitrary amount of whitespace (as determined by `isspace(3)`) followed by a single optional `+` or `-` sign. If base is zero or 16, the string may then include a `0x` prefix, and the number will be read in base 16; otherwise, a zero base is taken as 10 (decimal) unless the next character is 0, in which case it is taken as 8 (octal).

The remainder of the string is converted to an unsigned long int value in the obvious manner, stopping at the first character that is not a valid digit in the given base. (In bases above 10, the letter A in either upper- or lowercase represents 10, B represents 11, and so forth, with Z representing 35.)

If `endptr` is not NULL, `strtoul()` stores the address of the first invalid character in `*endptr`. If there were no digits at all, `strtoul()` stores the original value of `nptr` in `*endptr`. (Thus, if `*nptr` is not `\0` but `**endptr` is `\0` on return, the entire string is invalid.)

RETURN VALUE

The `strtoul()` function returns either the result of the conversion or, if there was a leading minus sign, the negation of the result of the conversion, unless the original (non-negated) value would overflow; in the latter case, `strtoul()` returns `ULONG_MAX` and sets the global variable `errno` to `ERANGE`.

ERRORS

`ERANGE`

The given string was out of range; the value converted has been clamped.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

SEE ALSO

`atof(3)`, `atoi(3)`, `atol(3)`, `strtod(3)`, `strtol(3)`

BUGS

`strtoul` ignores the current locale.

GNU, 29 March 1993

strxfrm

`strxfrm`—String transformation

SYNOPSIS

```
#include <string.h>
```

```
size_t strxfrm(char *dest, const char *src, size_t n);
```

DESCRIPTION

The `strxfrm()` function transforms the `src` string into a form such that the result of `strcmp()` on two strings that have been transformed with `strxfrm()` is the same as the result of `strcoll()` on the two strings before their transformation. The first `n` characters of the transformed string are placed in `dest`. The transformation is based on the program's current locale for category `LC_COLLATE`. (See `setlocale(3)`).

RETURN VALUE

The `strxfrm()` function returns the number of bytes required to store the transformed string in `dest` excluding the terminating `\0` character. If the value returned is `n` or more, the contents of `dest` are indeterminate.

CONFORMS TO

SVID 3, BSD 4.3, ISO 9899

NOTES

The Linux C Library currently hasn't implemented the complete POSIX-collating.

In the POSIX or C locales `strxfrm()` is equivalent to copying the string with `strncpy()`.

SEE ALSO

`bcmp(3)`, `memcmp(3)`, `strcasecmp(3)`, `strcmp(3)`, `strcoll(3)`, `setlocale(3)`

GNU, 12 April 1993

swab

`swab`—Swaps adjacent bytes

SYNOPSIS

```
#include <string.h>
void swab(const void *from, void*to, size_t n);
```

DESCRIPTION

The `swab()` function copies `n` bytes from the array pointed to by `from` to the array pointed to by `to`, exchanging adjacent even and odd bytes. This function is used to exchange data between machines that have different low/high byte ordering.

RETURN VALUE

The `swab()` function returns no value.

CONFORMS TO

SVID 3, BSD 4.3

SEE ALSO

`bstring(3)`

GNU, 13 April 1993

sysconf

`sysconf`—Gets configuration information at runtime

SYNOPSIS

```
#include <unistd.h>
long sysconf(int name);
```

DESCRIPTION

`sysconf()` provides a way for the application to determine values for system limits or options at runtime.

The equivalent macros defined in `<unistd.h>` can only give conservative values; if an application wants to take advantage of values that may change, a call to `sysconf()` can be made, which may yield more liberal results.

For getting information about a particular file, see `fpathconf()` or `pathconf()`.

The following values are supported for `name`. First, the POSIX.1_compatible values:

<code>_SC_ARG_MAX</code>	The maximum length of the arguments to the <code>exec()</code> family of functions; the corresponding macro is <code>ARG_MAX</code> .
<code>_SC_CHILD_MAX</code>	The number of simultaneous processes per user ID; the corresponding macro is <code>_POSIX_CHILD_MAX</code> .
<code>_SC_CLK_TCK</code>	The number of clock ticks per second; the corresponding macro is <code>CLK_TCK</code> .
<code>_SC_STREAM_MAX</code>	The maximum number of streams that a process can have open at any time. The corresponding POSIX macro is <code>STREAM_MAX</code> ; the corresponding standard C macro is <code>FOPEN_MAX</code> .
<code>_SC_TZNAME_MAX</code>	The maximum number of bytes in a time zone name; the corresponding macro is <code>TZNAME_MAX</code> .
<code>_SC_OPEN_MAX</code>	The maximum number of files that a process can have open at any time; the corresponding macro is <code>_POSIX_OPEN_MAX</code> .
<code>_SC_JOB_CONTROL</code>	This indicates whether POSIX-style job control is supported, the corresponding macro is <code>_POSIX_JOB_CONTROL</code> .
<code>_SC_SAVED_IDS</code>	This indicates whether a process has a saved set-user-ID and a saved set-group-ID; the corresponding macro is <code>_POSIX_SAVED_IDS</code> .
<code>_SC_VERSION</code>	Indicates the year and month the POSIX.1 standard was approved in the format <code>YYMMML</code> ; the value <code>199009L</code> indicates the most recent revision, 1990.

Next, the POSIX.2 values:

<code>_SC_BC_BASE_MAX</code>	Indicates the maximum obase value accepted by the <code>bc(1)</code> utility; the corresponding macro is <code>BC_BASE_MAX</code> .
<code>_SC_BC_DIM_MAX</code>	Indicates the maximum value of elements permitted in an array by <code>bc(1)</code> ; the corresponding macro is <code>BC_DIM_MAX</code> .
<code>_SC_BC_SCALE_MAX</code>	Indicates the maximum scale value allowed by <code>bc(1)</code> ; the corresponding macro is <code>BC_SCALE_MAX</code> .
<code>_SC_BC_STRING_MAX</code>	Indicates the maximum length of a string accepted by <code>bc(1)</code> ; the corresponding macro is <code>BC_STRING_MAX</code> .
<code>_SC_COLL_WEIGHTS_MAX</code>	Indicates the maximum numbers of weights that can be assigned to an entry of the <code>LC_COLLATE</code> order keyword in the locale definition file; the corresponding macro is <code>COLL_WEIGHTS_MAX</code> .
<code>_SC_EXPR_NEST_MAX</code>	Is the maximum number of expressions that can be nested within parentheses by <code>expr(1)</code> . The corresponding macro is <code>EXPR_NEST_MAX</code> .
<code>_SC_LINE_MAX</code>	The maximum length of a utility's input line length, either from standard input or from a file. This includes length for a trailing newline. The corresponding macro is <code>LINE_MAX</code> .
<code>_SC_RE_DUP_MAX</code>	The maximum number of repeated occurrences of a regular expression when the interval notation <code>\{m,n\}</code> is used. The value of the corresponding macro is <code>RE_DUP_MAX</code> .
<code>_SC_2_VERSION</code>	Indicates the version of the POSIX.2 standard in the format of <code>YYMMML</code> . The corresponding macro is <code>POSIX2_VERSION</code> .
<code>_SC_2_DEV</code>	Indicates whether the POSIX.2 C language development facilities are supported. The corresponding macro is <code>POSIX2_C_DEV</code> .
<code>_SC_2_FORT_DEV</code>	Indicates whether the POSIX.2 FORTRAN development utilities are supported. The corresponding macro is <code>POSIX2_FORT_RUN</code> .
<code>_SC_2_FORT_RUN</code>	Indicates whether the POSIX.2 FORTRAN runtime utilities are supported. The corresponding macro is <code>POSIX2_FORT_RUN</code> .

`POSIX2_LOCALEDEF`

Indicates whether the POSIX.2 creation of locales via `locale(1)` is supported. The corresponding macro is `POSIX2_LOCALEDEF`.

`_SC_2_SW_DEV`

Indicates whether the POSIX.2 software development utilities option is supported. The corresponding macro is `POSIX2_SW_DEV`.

RETURN VALUE

The value returned is the value of the system resource, 1 if a queried option is available, 0 if it is not, or -1 on error. The variable `errno` is not set.

CONFORMS TO

POSIX.1, proposed POSIX.2

BUGS

It is difficult use `ARG_MAX` because it is not specified how much of the argument space for `exec()` is consumed by the user's environment variables.

Some returned values may be huge; they are not suitable for allocating memory.

POSIX.2 is not yet an approved standard; the information in this man page is subject to change.

SEE ALSO

`bc(1)`, `expr(1)`, `locale(1)`, `fpathconf(3)`, `pathconf(3)`

GNU, 18 April 1993

closelog, openlog, syslog

`closelog`, `openlog`, `syslog`—Send messages to the system logger

SYNOPSIS

```
#include <syslog.h>
void openlog( char *ident,int option,int facility);
void syslog( int priority, char *format, ...);
void closelog( void );
```

DESCRIPTION

`closelog()` closes the descriptor being used to write to the system logger. The use of `closelog()` is optional.

`openlog()` opens a connection to the system logger for a program. The string pointed to by `ident` is added to each message, and is typically set to the program name. Values for `option` and `facility` are given in the next subsection. The use of `openlog()` is optional; it will automatically be called by `syslog()` if necessary, in which case `ident` will default to `NULL`.

`syslog()` generates a log message, which will be distributed by `syslogd(8)`. `priority` is a combination of the `facility` and the `level`, values for which are given in the next subsection. The remaining arguments are a `format`, as in `printf(3)` and any arguments required by the `format`, except that the two characters `%m` will be replaced by the error message string (`strerror`) corresponding to the present value of `errno`.

PARAMETERS

This section lists the parameters used to set the values of `option`, `facility`, and `priority`.

OPTION

The option argument to `openlog()` is an OR of any of these:

<code>LOG_CONS</code>	Write directly to system console if there is an error while sending to system logger
<code>LOG_NDELAY</code>	Open the connection immediately (normally, the connection is opened when the first message is logged)
<code>LOG_PERROR</code>	Print to <code>stderr</code> as well
<code>LOG_PID</code>	Include <code>PID</code> with each message

FACILITY

The facility argument is used to specify what type of program is logging the message. This lets the configuration file specify that messages from different facilities will be handled differently.

<code>LOG_AUTH</code>	Security/authorization messages (DEPRECATED use <code>LOG_AUTHPRIV</code> instead)
<code>LOG_AUTHPRIV</code>	Security/authorization messages (private)
<code>LOG_CRON</code>	Clock daemon (<code>cron</code> and <code>at</code>)
<code>LOG_DAEMON</code>	Other system daemons
<code>LOG_KERN</code>	Kernel messages
<code>LOG_LOCAL0</code> through <code>LOG_LOCAL7</code>	Reserved for local use
<code>LOG_LPR</code>	Line printer subsystem
<code>LOG_MAIL</code>	Mail subsystem
<code>LOG_NEWS</code>	Usenet news subsystem
<code>LOG_SYSLOG</code>	Messages generated internally by <code>syslogd</code>
<code>LOG_USER</code> (default)	Generic user-level messages
<code>LOG_UUCP</code>	UUCP subsystem

LEVEL

This determines the importance of the message. The levels, in order of decreasing importance, are

<code>LOG_EMERG</code>	System is unusable
<code>LOG_ALERT</code>	Action must be taken immediately
<code>LOG_CRIT</code>	Critical conditions
<code>LOG_ERR</code>	Error conditions
<code>LOG_WARNING</code>	Warning conditions
<code>LOG_NOTICE</code>	Normal, but significant, condition
<code>LOG_INFO</code>	Informational message
<code>LOG_DEBUG</code>	Debug-level message

HISTORY

A `syslog` function call appeared in BSD 4.2.

SEE ALSO

`logger(1)`, `syslog.conf(5)`, `syslogd(8)`

system

system—Executes a shell command

SYNOPSIS

```
#include <stdlib.h>
int system (const char * string);
```

DESCRIPTION

system() executes a command specified in string by calling /bin/sh -c string, and returns after the command has been completed. During execution of the command, SIGCHLD will be blocked, and SIGINT and SIGQUIT will be ignored.

RETURN VALUE

The value returned is 127 if the execve() call for /bin/sh fails, -1 if there was another error, and the return code of the command otherwise.

If the value of string is NULL, system() returns non-zero if the shell is available, and zero if not.

system() does not affect the wait status of any other children.

CONFORMS TO

ANSI C, POSIX.1, proposed POSIX.2, BSD 4.3

BUGS

Do not use system() from a program with suid or sgid privileges, because strange values for some environment variables might be used to subvert system integrity. Use the exec(2) family of functions instead, but not exec1p(2) or execvp(2).

The check for the availability of /bin/sh is not actually performed; it is always assumed to be available.

It is possible for the shell command to return 127, so that code is not a sure indication that the execve() call failed; check errno to make sure.

SEE ALSO

sh(1), exec(2), signal(2)

GNU, 13 April 1993

tan

tan—Tangent function

SYNOPSIS

```
#include <math.h>
double tan(double x);
```

DESCRIPTION

The tan() function returns the tangent of x, where x is given in radians.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`acos(3)`, `asin(3)`, `atan(3)`, `atan2(3)`, `cos(3)`, `sin(3)`

8 June 1993

tanh

`tanh`—Hyperbolic tangent function

SYNOPSIS

```
#include <math.h>
double tanh(double x);
```

DESCRIPTION

The `tanh()` function returns the hyperbolic tangent of `x`, which is defined mathematically as $\sinh(x) / \cosh(x)$.

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`acosh(3)`, `asinh(3)`, `atanh(3)`, `cosh(3)`, `sinh(3)`

13 June 1993

telldir

`telldir`—Returns current location in directory stream

SYNOPSIS

```
#include <dirent.h>
off_t telldir(DIR *dir);
```

DESCRIPTION

The `telldir()` function returns the current location associated with the directory stream `dir`.

RETURN VALUE

The `telldir()` function returns the current location in the directory stream or `-1` if an error occurs.

ERRORS

`EBADF` Invalid directory stream descriptor `dir`

CONFORMS TO

BSD 4.3

SEE ALSO

`opendir(3)`, `readdir(3)`, `closedir(3)`, `rewinddir(3)`, `seekdir(3)`, `scandir(3)`

31 March 1993


```

int tcflow ( int fd,int action );
int cfmakeraw ( struct termios *termios_p );
speed_t cfgetospeed ( struct termios *termios_p );
int cfsetospeed ( struct termios *termios_p, speed_t speed );
speed_t cfgetispeed ( struct termios *termios_p );
int cfsetispeed ( struct termios *termios_p, speed_t speed );
pid_t tcgetpgrp ( int fd );
int tcsetpgrp ( int fd, pid_t pgrp );

```

DESCRIPTION

The `termios` functions describe a general terminal interface that is provided to control asynchronous communications ports.

Many of the functions described here have a `termios_p` argument that is a pointer to a `termios` structure. This structure contains the following members:

```

tcflag_t c_iflag; /* input modes */
tcflag_t c_oflag; /* output modes */
tcflag_t c_cflag; /* control modes */
tcflag_t c_lflag; /* local modes */
cc_t cc[NCCS]; /* control chars */

```

The `c_iflag` flag constants are

IGNBRK	Ignore BREAK condition on input.
BRKINT	If IGNBRK is not set, generate SIGINT on BREAK condition, else read BREAK as character <code>\0</code> .
IGNPAR	Ignore framing errors and parity errors.
PARMRK	If IGNPAR is not set, prefix a character with a parity error or framing error with <code>\377 \0</code> . If neither IGNPAR nor PARMRK is set, read a character with a parity error or framing error as <code>\0</code> .
INPCK	Enable input parity checking.
ISTRIP	Strip off eighth bit.
INLCR	Translate NL to CR on input.
IGNCR	Ignore carriage return on input.
ICRNL	Translate carriage return to newline on input (unless IGNCR is set).
IUCLC	Map uppercase characters to lowercase on input.
IXON	Enable XON/XOFF flow control on output.
IXANY	Enable any character to restart output.
IXOFF	Enable XON/XOFF flow control on input.
IMAXBEL	Ring bell when input queue is full.

The `c_oflag` flag constants are

OPOST	Enable implementation-defined output processing.
OLCUC	Map lowercase characters to uppercase on output.
ONLCR	Map NL to CR-NL on output.
OCRNL	Map CR to NL on output.
ONOCR	Don't output CR at column 0.
ONLRET	Don't output CR.
OFILL	Send fill characters for a delay, rather than using a timed delay.
OFDEL	Fill character is ASCII DEL. If unset, fill character is ASCII NUL.
NLDLY	Newline delay mask. Values are NL0 and NL1.
CRDLY	Carriage return delay mask. Values are CR0, CR1, CR2, or CR3.

`tcsetattr()` sets the parameters associated with the terminal (unless support is required from the underlying hardware that is not available) from the `termios` structure referred to by `termios_p`. `optional_actions` specifies when the changes take effect:

<code>TCSANOW</code>	The change occurs immediately.
<code>TCSADRAIN</code>	The change occurs after all output written to <code>fd</code> has been transmitted. This function should be used when changing parameters that affect output.
<code>TCSAFLUSH</code>	The change occurs after all output written to the object referred by <code>fd</code> has been transmitted, and all input that has been received but not read will be discarded before the change is made.

`tcsendbreak()` transmits a continuous stream of zero-valued bits for a specific duration, if the terminal is using asynchronous serial data transmission. If `duration` is zero, it transmits zero-valued bits for at least 0.25 seconds, and not more than 0.5 seconds. If `duration` is not zero, it sends zero-valued bits for `duration*N` seconds, where `N` is at least 0.25, and not more than 0.5.

If the terminal is not using asynchronous serial data transmission, `tcsendbreak()` returns without taking any action.

`tcdrain()` waits until all output written to the object referred to by `fd` has been transmitted.

`tcflush()` discards data written to the object referred to by `fd` but not transmitted, or data received but not read, depending on the value of `queue_selector`:

<code>TCIFLUSH</code>	Flushes data received but not read
<code>TCOFLUSH</code>	Flushes data written but not transmitted
<code>TCIOFLUSH</code>	Flushes both data received but not read, and data written but not transmitted

`tcflow()` suspends transmission or reception of data on the object referred to by `fd`, depending on the value of `action`:

<code>TCOOFF</code>	Suspends output
<code>TCOON</code>	Restarts suspended output
<code>TCIOFF</code>	Transmits a STOP character, which stops the terminal device from transmitting data to the system
<code>TCION</code>	Transmits a START character, which starts the terminal device transmitting data to the system

The default on open of a terminal file is that neither its input nor its output is suspended.

The baud rate functions are provided for getting and setting the values of the input and output baud rates in the `termios` structure. The new values do not take effect until `tcsetattr()` is successfully called.

Setting the speed to `B0` instructs the modem to hang up. The actual bit rate corresponding to `B38400` may be altered with `setserial(8)`.

The input and output baud rates are stored in the `termios` structure.

`cfmakeraw` sets the terminal attributes as follows:

```
termios_p->c_iflag &= ~(IGNBRK|BRKINT|PARMRK|ISTRIP
|INLCR|IGNCR|ICRNL|IXON);
termios_p->c_oflag &= ~OPOST;
termios_p->c_lflag &= ~(ECHO|ECHONL|ICANON|ISIG|IEXTEN);
termios_p->c_cflag &= ~(CSIZE|PARENB);
termios_p->c_cflag |= CS8;
```

`cfgetospeed()` returns the output baud rate stored in the `termios` structure pointed to by `termios_p`.

`cfsetospeed()` sets the output baud rate stored in the `termios` structure pointed to by `termios_p` to speed, which must be one of these constants:

```
B0
B50
B75
```



```

B110
B134
B150
B200
B300
B600
B1200
B1800
B2400
B4800
B9600
B19200
B38400
B57600
B115200
B230400

```

The zero baud rate, `B0`, is used to terminate the connection. If `B0` is specified, the modem control lines shall no longer be asserted. Normally, this will disconnect the line. `CBAUDEx` is a mask for the speeds beyond those defined in POSIX.1 (57600 and above). Thus, `B57600 & CBAUDEx` is non-zero.

`cfgetispeed()` returns the input baud rate stored in the `termios` structure.

`cfsetispeed()` sets the input baud rate stored in the `termios` structure to `speed`. If the input baud rate is set to zero, the input baud rate will be equal to the output baud rate.

`tcgetpgrp()` returns process group ID of foreground processing group, or `-1` on error.

`tcsetpgrp()` sets process group ID to `pgrp_id`. `pgrp_id` must be the ID of a process group in the same session.

RETURN VALUES

`cfgetispeed()` returns the input baud rate stored in the `termios` structure.

`cfgetospeed()` returns the output baud rate stored in the `termios` structure.

`tcgetpgrp()` returns process group ID of foreground processing group, or `-1` on error.

All other functions return

<code>0</code>	On success
<code>-1</code>	On failure and set <code>errno</code> to indicate the error

SEE ALSO

`setserial(8)`

Linux, 2 September 1995

tmpfile

tmpfile—Creates a temporary file

SYNOPSIS

```

#include <stdio.h>
FILE *tmpfile (void);

```

DESCRIPTION

The `tmpfile()` function generates a unique temporary filename using the path prefix `P_tmpdir` defined in `<stdio.h>`. The temporary file is then opened in binary read/write (`w+b`) mode. The file will be automatically deleted when it is closed or the program terminates.

RETURN VALUE

The `tmpfile()` function returns a stream descriptor, or `NULL` if a unique filename cannot be generated or the unique file cannot be opened.

ERRORS

<code>EACCES</code>	Search permission denied for directory in file's path prefix
<code>EEXIST</code>	Unable to generate a unique filename
<code>EMFILE</code>	Too many file descriptors in use by process
<code>ENFILE</code>	Too many files open in system
<code>EROFS</code>	Read-only filesystem

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`mktemp(3)`, `mkstemp(3)`, `tmpnam(3)`, `tempnam(3)`

GNU, 3 April 1993

tmpnam

`tmpnam`—Creates a name for a temporary file

SYNOPSIS

```
#include <stdio.h>
char *tmpnam(char *s);
```

DESCRIPTION

The `tmpnam()` function generates a unique temporary filename using the path prefix `P_tmpdir` defined in `<stdio.h>`. If the argument `s` is `NULL`, `tmpnam()` returns the address of an internal static area that holds the filename, which is overwritten by subsequent calls to `tmpnam()`. If `s` is not `NULL`, the filename is returned in `s`.

RETURN VALUE

The `tmpnam()` function returns a pointer to the unique temporary filename, or `NULL` if a unique name cannot be generated.

ERRORS

<code>EEXIST</code>	Unable to generate a unique filename

CONFORMS TO

SVID 3, POSIX, BSD 4.3, ISO 9899

SEE ALSO

`mktemp(3)`, `mkstemp(3)`, `tempnam(3)`, `tmpfile(3)`

GNU, 3 April 1993

toascii

toascii—Converts character to ASCII

SYNOPSIS

```
#include <ctype.h>
int toascii (int c);
```

DESCRIPTION

toascii() converts *c* to a 7-bit unsigned char value that fits into the ASCII character set, by clearing the high-order bits.

RETURN VALUE

The value returned is that of the converted character.

CONFORMS TO

SVID, BSD

BUGS

Many people will be unhappy if you use this function. This function will convert accented letters into random characters.

SEE ALSO

isascii(3), toupper(3), tolower(3)

GNU, 16 September 1995

toupper, tolower

toupper, tolower—Convert letter to uppercase or lowercase

SYNOPSIS

```
#include <ctype.h>
int toupper (int c);
int tolower (int c);
```

DESCRIPTION

toupper() converts the letter *c* to uppercase, if possible.

tolower() converts the letter *c* to lowercase, if possible.

RETURN VALUE

The value returned is that of the converted letter, or *c* if the conversion was not possible.

CONFORMS TO

ANSI C, BSD 4.3

BUGS

The details of what constitutes an uppercase or lowercase letter depend on the current locale. For example, the default locale does not know about umlauts, so no conversion is done for them.

In some non-English locales, there are lowercase letters with no corresponding uppercase equivalent; the German sharp *s* is one example.

SEE ALSO

`isalpha(3)`, `setlocale(3)`, `locale(7)`

GNU, 4 April 1993

tsearch, tfind, tdelete, twalk

`tsearch`, `tfind`, `tdelete`, `twalk`—Manage a binary tree

SYNOPSIS

```
#include <search.h>
void *tsearch (const void *key, void **rootp,
int (*compar)(const void *, const void *));
void *tfind (const void *key, const void **rootp,
int (*compar)(const void *, const void *));
void *tdelete (const void *key, void **rootp,
int (*compar)(const void *, const void *));
void twalk (const void *root, void (*action)(const void *nodep,
const VISIT which,
const int depth));
```

DESCRIPTION

`tsearch`, `tfind`, `twalk`, and `tdelete` manage a binary tree. They are generalized from Knuth (6.2.2) Algorithm T. The first field in each node of the tree is a pointer to the corresponding data item. (The calling program must store the actual data.) `compar` points to a comparison routine, which takes pointers to two items. It should return an integer that is negative, zero, or positive, depending on whether the first item is less than, equal to, or greater than the second.

`tsearch` searches the tree for an item. `key` points to the item to be searched for. `rootp` points to a variable that points to the root of the tree. If the tree is empty, then the variable that `rootp` points to should be set to `NULL`. If the item is found in the tree, then `tsearch` returns a pointer to it. If it is not found, then `tsearch` adds it, and returns a pointer to the newly added item.

`tfind` is like `tsearch`, except that if the item is not found, then `tfind` returns `NULL`.

`tdelete` deletes an item from the tree. Its arguments are the same as for `tsearch`.

`twalk` performs depth-first, left-to-right traversal of a binary tree. `root` points to the starting node for the traversal. If that node is not the root, then only part of the tree will be visited. `twalk` calls the user function `action` each time a node is visited (that is, three times for an internal node, and once for a leaf). `action`, in turn, takes three arguments. The first is a pointer to the node being visited. The second is an integer that takes on the values `preorder`, `postorder`, and `endorder` depending on whether this is the first, second, or third visit to the internal node, or leaf if it is the single visit to a leaf node. (These symbols are defined in `<search.h>`.) The third argument is the depth of the node, with zero being the root.

RETURN VALUE

`tsearch` returns a pointer to a matching item in the tree, or to the newly added item, or `NULL` if there was insufficient memory to add the item. `tfind` returns a pointer to the item, or `NULL` if no match is found. If there are multiple elements that match the key, the element returned is unspecified.

`tdelete` returns a pointer to the parent of the item deleted, or `NULL` if the item was not found.

`tsearch`, `tfind`, and `tdelete` also return `NULL` if `rootp` was `NULL` on entry.

WARNINGS

`twalk` takes a pointer to the root, while the other functions take a pointer to a variable that points to the root.

`twalk` uses `postorder` to mean “after the left subtree, but before the right subtree.” Some authorities would call this `inorder`, and reserve `postorder` to mean “after both subtrees.”

`tdelete` frees the memory required for the node in the tree. The user is responsible for freeing the memory for the corresponding data.

The example program depends on the fact that `twalk` makes no further reference to a node after calling the user function with argument `endorder` or `leaf`. This works with the GNU library implementation, but is not in the SysV documentation.

EXAMPLE

The following program inserts twelve random numbers into a binary tree, then prints the numbers in order. The numbers are removed from the tree and their storage freed during the traversal.

```
#include <search.h>
#include <stdlib.h>
#include <stdio.h>

void *root=NULL;

void *xmalloc(unsigned n)
{
    void *p;
    p = malloc(n);
    if(p) return p;
    fprintf(stderr, "insufficient memory\n");
    exit(1);
}

int compare(const void *pa, const void *pb)
{
    if(*(int *)pa < *(int *)pb) return -1;
    if(*(int *)pa > *(int *)pb) return 1;
    return 0;
}

void action(const void *nodep, const VISIT which, const int depth)
{
    int *datap;
    void *val;

    switch(which)
    {
        case preorder:
            break;
        case postorder:
            datap = *(int **)nodep;
            printf("%6d\n", *datap);
            break;
        case endorder:
            datap = *(int **)nodep;
            (void)tdelete(datap, &root, compare);
            free(datap);
            break;
        case leaf:
            datap = *(int **)nodep;
            printf("%6d\n", *datap);
            val = tdelete(datap, &root, compare);
            free(datap);
            break;
    }
    return;
}
```

```

    }

    int main()
    {
        int i, *ptr;
        void *val;

        for (i = 0; i < 12; i++)
        {
            ptr = (int *)xmalloc(sizeof(int));
            *ptr = rand() & 0xff;
            val = tsearch((void *)ptr, &root, compare);
            if (val == NULL) exit(1);
        }
        twalk(root, action);
        return 0;
    }

```

CONFORMS TO

SVID

SEE ALSO

qsort(3), bsearch(3), hsearch(3), lsearch(3)

GNU, 24 September 1995

ttyname

ttyname—Returns name of a terminal

SYNOPSIS

```

#include <unistd.h>
char *ttyname ( int desc );

```

DESCRIPTION

Returns a pointer to the pathname of the terminal device that is open on the file descriptor *desc*, or NULL on error (for example, if *desc* is not connected to a terminal).

CONFORMS TO

POSIX.1

SEE ALSO

isatty(3), fstat(3)

Linux, 20 April 1995

tzset

tzset—Initializes time conversion information

SYNOPSIS

```

#include <time.h>
void tzset (void);
extern char *tzname[2];

```

DESCRIPTION

The `tzset()` function initializes the `tzname` variable from the `TZ` environment variable. This function is automatically called by the other time conversion functions that depend on the time zone.

If the `TZ` variable does not appear in the environment, the `tzname` variable is initialized with the best approximation of local wall clock time, as specified by the `tzfile(5)`-format file `/usr/lib/zoneinfo/localtime`.

If the `TZ` variable does appear in the environment but its value is `NULL` or its value cannot be interpreted using any of the formats specified in the following paragraphs, Coordinated Universal Time (UTC) is used.

The value of `TZ` can be one of three formats. The first format is used when there is no daylight saving time in the local time zone:

`std offset`

The `std` string specifies the name of the time zone and must be three or more alphabetic characters. The `offset` string immediately follows `std` and specifies the time value to be added to the local time to get Coordinated Universal Time (UTC). The `offset` is positive if the local time zone is west of the Prime Meridian and negative if it is east. The hour must be between 0 and 24, and the minutes and seconds 0 and 59.

The second format is used when there is daylight saving time:

`std offset dst [offset],start[/time],end[/time]`

There are no spaces in the specification. The initial `std` and `offset` specify the standard time zone, as described. The `dst` string and `offset` specify the name and offset for the corresponding daylight savings time zone. If the `offset` is omitted, it defaults to one hour ahead of standard time.

The `start` field specifies when Daylight Savings Time goes into effect and the `end` field specifies when the change is made back to Standard Time. These fields may have the following formats:

- `Jn` This specifies the Julian day with *n* between 1 and 365. February 29 is never counted even in leap years.
- `n` This specifies the Julian day with *n* between 1 and 365. February 29 is counted in leap years.
- `Mm.w.d` This specifies day *d* ($0 \leq d \leq 6$) of week *w* ($1 \leq w \leq 5$) of month *m* ($1 \leq m \leq 12$). Week 1 is the first week in which day *d* occurs and week 5 is the last week in which day *d* occurs. Day 0 is a Sunday.

The time fields specify when, in the local time currently in effect, the change to the other time occurs. If omitted, the default is `02:00:00`.

The third format specifies that the time zone information should be read from a file:

`:[filespec]`

If the file specification `filespec` is omitted, the time zone information is read from `/usr/lib/zoneinfo/localtime`, which is in `tzfile(5)` format. If `filespec` is given, it specifies an-other `tzfile(5)`-format file to read the time zone information from. If `filespec` does not begin with a `/`, the file specification is relative to the system time conversion information directory `/usr/lib/zoneinfo`.

FILES

- `/usr/lib/zoneinfo` System time zone directory
- `/usr/lib/zoneinfo/localtime` Local time zone file
- `/usr/lib/zoneinfo/posixrules` Rules for POSIX-style `tz`s

CONFORMS TO

SVID 3, POSIX, BSD 4.3

SEE ALSO

date(1), gettimeofday(2), time(2), ctime(3), getenv(3), tzfile(5)

BSD, 2 July 1993

none

none—Undocumented library functions

SYNOPSIS

Undocumented library functions

DESCRIPTION

This man page mentions those library functions that are implemented in the standard libraries but not yet documented in man pages.

SOLICITATION

If you have information about these functions, please look in the source code, write a man page (using a style similar to that of the other Linux section 3 man pages), and send it to aeb@cw.i.n1 for inclusion in the next man page release.

THE LIST

des_setparity, dn_skipname, ecb_crypt, encrypt, endnetgrent, endrpcnt, endtutent, execlp, fcrypt, fp_nquery, fp_query, fp_resstat, get_myaddress, getnetgrent, getnetname, getopt_long_only, getpublickey, getrpcbyname, getrpcbynumber, getrpccent, getrpcport, getsecretkey, getutid, getutline, h_errlist, host2netname, hostalias, inet_nsap_addr, inet_nsap_ntoa_init_des, innnetgr, key_decryptsession, key_encryptsession, key_gendes, key_setsecret, lfind, libc_nls_init, lockf, lsearch, mcheck, memalign, mstats, mtrace, netname2host, netname2user, nlist, obstack_free, p_cdname, p_cdname, p_class, p_fqname, p_option, p_query, p_rr, p_time, p_type, passwd2des, pmap_getmaps, pmap_getport, pmap_rmtcall, pmap_set, pmap_unset, putlong, putshort, pututline, rcmd, re_compile_fastmap, re_compile_pattern, re_match, re_match_2, re_rx_search, re_search, re_search_2, re_set_registers, re_set_syntax, register_rpc, res_send_setqhook, res_send_setrhook, rexec, rresvport, rtime, ruserok, ruserpass, setfileno, sethostfile, setkey, setlogmask, setnetgrent, setrpcnt, settutent, siglongjmp, snprintf, stpcpy, svc_exit, svc_getreq, svc_getreqset, svc_register, svc_run, svc_sendreply, svc_unregister, svcerr_auth, svcerr_decode, svcerr_noproc, svcerr_noprog, svcerr_progvers, svcerr_systemerr, svcerr_weakauth, svcfd_create, svcraw_create, svctcp_create, svcudp_bufcreate, svcudp_create, svcudp_enablecachesyscall, tdelete, tell, tfind, timegm, tr_break, tsearch, twalk, tzsetwall, ufc_dofinalperm, ufc_doit, user2netname, utmpname, valloc, vsnprintf, vsyslog, xdecrypt, xdr_accepted_reply, xdr_array, xdr_authdes_cred, xdr_authdes_verf, xdr_authunix_parms, xdr_bool, xdr_bytes, xdr_callhdr, xdr_callmsg, xdr_char, xdr_cryptkeyarg, xdr_cryptkeyres, xdr_datum, xdr_des_block, xdr_domainname, xdr_double, xdr_enum, xdr_float, xdr_free, xdr_getcredres, xdr_int, xdr_keybuf, xdr_keystatus, xdr_long, xdr_mapname, xdr_netnamestr, xdr_netobj, xdr_opaque, xdr_opaque_auth, xdr_passwd, xdr_peername, xdr_pmap, xdr_pmaplist, xdr_pointer, xdr_reference, xdr_rejected_reply, xdr_replymsg, xdr_rmtcall_args, xdr_rmtcallres, xdr_short, xdr_string, xdr_u_char, xdr_u_int, xdr_u_long, xdr_u_short, xdr_union, xdr_unixcred, xdr_vector, xdr_void, xdr_wrapstring, xdr_yyp_buf, xdr_yyp_inaddr, xdr_yypbind_binding, xdr_yypbind_resp, xdr_yypbind_resptype, xdr_yypbind_setdom, xdr_yypdelete_args, xdr_yypmaplist, xdr_yypmaplist_str, xdr_yppasswd, xdr_yppreq_key, xdr_yppreq_nokey, xdr_ypresp_all, xdr_ypresp_all_seq, xdr_ypresp_key_val, xdr_ypresp_maplist, xdr_ypresp_master, xdr_ypresp_order, xdr_ypresp_val, xdr_yypstat, xdr_yypupdate_args, xdrmem_create, xdrrec_create, xdrrec_endofrecord, xdrrec_eof, xdrrec_skiprecord, xdrstdio_create, xencrypt, xprt_register, xprt_unregister, yp_all, yp_bind, yp_first, yp_get_default_domain, yp_maplist, yp_master, yp_match, yp_next, yp_order, yp_unbind, yp_update, yperr_string, ypprot_err

Linux 1.3.15, 25 August 1995

usleep

`usleep`—Suspends execution for interval of microseconds

SYNOPSIS

```
#include <unistd.h>
void usleep(unsigned long usec);
```

DESCRIPTION

The `usleep()` function suspends execution of the calling process for `usec` microseconds. The sleep may be lengthened slightly by any system activity or by the time spent processing the call.

CONFORMS TO

BSD 4.3

SEE ALSO

`setitimer(2)`, `getitimer(2)`, `sleep(3)`, `alarm(3)`, `select(3)`

4 July 1993

wcstombs

`wcstombs`—Converts a wide character string to a multibyte character string

SYNOPSIS

```
#include <stdlib.h>
size_t wcstombs(char *s, const wchar_t *pwcs, size_t n);
```

DESCRIPTION

The `wcstombs()` function converts a sequence of wide characters from the array `pwcs` into a sequence of multibyte characters and stores up to *n* bytes of multibyte characters in the array `s`.

RETURN VALUE

`wcstombs()` returns the number of bytes stored in `s` or `-1` if `s` contains an invalid wide character.

CONFORMS TO

SVID 3, ISO 9899

SEE ALSO

`mblen(3)`, `mbtowc(3)`, `mbstowcs(3)`, `wctomb(3)`

GNU, 29 March 1993

wctomb

`wctomb`—Converts a wide character to a multibyte character

SYNOPSIS

```
#include <stdlib.h>
int wctomb(char *s, wchar_t wchar);
```

DESCRIPTION

The `wctomb()` function converts a wide character `wchar` into a multibyte character and, if `s` is not `NULL`, stores the multibyte character representation in `s`.

RETURN VALUE

`wctomb()` returns the number of bytes in the multibyte character or `-1` if the wide character is not valid.

CONFORMS TO

SVID 3, ISO 9899

SEE ALSO

`mblen(3)`, `mbstowcs(3)`, `mbtowc(3)`, `wcstombs(3)`

GNU, 29 March 1993

Part IV:

Special Files

INTRODUCTION

This part describes special files.

FILES

`/dev/*` Device files

AUTHORS

Look at the header of the manual page for the author(s) and copyright conditions. Note that these can be different from page to page.

Linux, 24 July 1993

charsets

charsets—Programmer’s view of character sets and internationalization

DESCRIPTION

Linux is an international operating system. Several of its utilities and device drivers (including the console driver) support multilingual character sets including Latin-alphabet letters with diacritical marks, accents, ligatures, and entire non-Latin alphabets including Greek, Cyrillic, Arabic, and Hebrew.

This manual page presents a programmer’s-eye view of different character-set standards and how they fit together on Linux. Standards discussed include ASCII, ISO 8859, KOI8-R, Unicode, ISO 2022, and ISO 4873.

ASCII

ASCII (American Standard Code for Information) is the original 7-bit character set, originally designed for American English. It is currently described by the ECMA-6 standard.

An ASCII variant replacing the American crosshatch/octothorpe/hash pound symbol with the British pound-sterling symbol is used in Great Britain; when needed, the American and British variants may be distinguished as U.S. ASCII and U.K. ASCII.

As Linux was written for hardware designed in the United States, it natively supports U.S. ASCII.

ISO 8859

ISO 8859 is a series of 10 8-bit character sets, all of which have U.S. ASCII in their low (7-bit) half, invisible control characters in positions 128 to 159, and 96 fixed-width graphics in positions 160-255.

Of these, the most important is ISO 8859-1 (Latin-1). It is natively supported in the Linux console driver, fairly well supported in X11R6, and is the base character set of HTML.

Console support for the other 8859 character sets is available under Linux through user-mode utilities (such as `setfont(8)`) that modify keyboard bindings and the EGA graphics table and employ the “user mapping” font table in the console driver.

Here are brief descriptions of each set:

8859-1 (Latin-1)	Latin-1 covers most Western European languages such as Albanian, Catalan, Danish, Dutch, English, Faroese, Finnish, French, German, Galician, Irish, Icelandic, Italian, Norwegian, Portuguese, Spanish, and Swedish. The lack of the ligatures Dutch <i>ij</i> , French <i>oe</i> , and old-style German quotation marks is tolerable.
8859-2 (Latin-2)	Latin-2 supports most Latin-written Slavic and Central European languages: Czech, German, Hungarian, Polish, Rumanian, Croatian, Slovak, and Slovene.
8859-3 (Latin-3)	Latin-3 is popular with authors of Esperanto, Galician, Maltese, and Turkish.
8859-4 (Latin-4)	Latin-4 introduced letters for Estonian, Latvian, and Lithuanian. It is essentially obsolete; see 8859-10 (Latin-6).

8859-5	Cyrillic letters supporting Bulgarian, Byelorussian, Macedonian, Russian, Serbian, and Ukrainian. Ukrainians read the letter <i>ghe</i> with downstroke as <i>heh</i> and would need a <i>ghe</i> with upstroke to write a correct <i>ghe</i> . (See the discussion of KOI8-R in the next subsection.)
8859-6	Supports Arabic. The 8859-6 glyph table is a fixed font of separate letter forms, but a proper display engine should combine there pairwise into initial, medial, and final forms.
8859-7	Supports modern Greek.
8859-8	Supports Hebrew.
8859-9 (Latin-5)	This is a variant of Latin-1 that replaces rarely used Icelandic letters with Turkish ones.
8859-10 (Latin-6)	Latin-6 adds the last Inuit (Greenlandic) and Sami (Lappish) letters that were missing in Latin 4 to cover the entire Nordic area. RFC 1345 listed a preliminary and different Latin 6. Skolt Sami still needs a few more accents than these.

KOI8-R

KOI8-R is a non-ISO character set popular in Russia. The lower half is U.S. ASCII; the upper is a Cyrillic character set somewhat better designed than ISO 8859-5.

Console support for KOI8-R is available under Linux through user-mode utilities that modify keyboard bindings and the EGA graphics table, and that employ the “user mapping” font table in the console driver.

UNICODE

Unicode (ISO 10646) is a standard that aims to unambiguously represent every known glyph in every human language. Unicode's native encoding is 32-bit (older versions used 16 bits). Information on Unicode is available at <http://www.unicode.com>.

Linux represents Unicode using the 8-bit Unicode Transfer Format (UTF-8). UTF-8 is a variable length encoding of Unicode. It uses 1 byte to code 7 bits, 2 bytes for 11 bits, 3 bytes for 16 bits, 4 bytes for 21 bits, 5 bytes for 26 bits, and 6 bytes for 31 bits.

Let 0, 1, x stand for a zero, one, or arbitrary bit. A byte 0xxxxxxx stands for the Unicode 00000000 0xxxxxxx, which codes the same symbol as the ASCII 0xxxxxxx. Thus, ASCII goes unchanged into UTF-8, and people using only ASCII do not notice any change—not in code, and not in file size.

A byte 110xxxxx is the start of a 2-byte code, and 110xxxxx 10yyyyyy is assembled into 00000xxx xyyyyyyy. A byte 1110xxxx is the start of a 3-byte code, and 1110xxxx 10yyyyyy 10zzzzzz is assembled into xxxxyyyy yzzzzzz. (When UTF-8 is used to code the 31-bit ISO 10646, then this progression continues up to 6-byte codes.)

For ISO-8859-1 users this means that the characters with high bit set now are coded with two bytes. This tends to expand ordinary text files by one or two percent. There are no conversion problems, however, since the Unicode value of ISO-8859-1 symbols equals their ISO-8859-1 value (extended by eight leading zero bits). For Japanese users, this means that the 16-bit codes now in common use will take three bytes, and extensive mapping tables are required. Many Japanese therefore prefer ISO 2022.

Note that UTF-8 is self-synchronizing: 10xxxxxx is a tail, any other byte is the head of a code. Note that the only way ASCII bytes occur in a UTF-8 stream is as themselves. In particular, there are no embedded NULs or /s that form part of some larger code.

Because ASCII, and, in particular, NUL and /, are unchanged, the kernel does not notice that UTF-8 is being used. It does not care at all what the bytes it is handling stand for.

Rendering of Unicode data streams is typically handled through subfont tables that map a subset of Unicode to glyphs. Internally, the kernel uses Unicode to describe the subfont loaded in video RAM. This means that in UTF-8 mode one can use a character set with 512 different symbols. This is not enough for Japanese, Chinese, and Korean, but it is enough for most other purposes.

ISO 2022 AND ISO 4873

The ISO 2022 and 4873 standards describe a font-control model based on VT100 practice. This model is (partially) supported by the Linux kernel and by `xterm(1)`. It is popular in Japan and Korea.

There are four graphic character sets, called G0, G1, G2, and G3, and one of them is the current character set for codes with high bit zero (initially G0), and one of them is the current character set for codes with high bit one (initially G1). Each graphic character set has 94 or 96 characters, and is essentially a 7-bit character set. It uses codes either 040–0177 (041–0176) or 0240–0377 (0241–0376). G0 always has size 94 and uses codes 041–0176.

Switching between character sets is done using the shift functions `^N` (S0 or LS1), `^O` (S1 or LS0), `ESC n` (LS2), `ESC o` (LS3), `ESC N` (SS2),

`ESC 0` (SS3), `ESC ^` (LS1R), `ESC }` (LS2R), `ESC |` (LS3R). The function `LSn` makes character set *Gn* the current one for codes with high bit zero. The function `LSnR` makes character set *Gn* the current one for codes with high bit one. The function `SSn` makes character set *Gn* (*n*=2 or 3) the current one for the next character only (regardless of the value of its high order bit).

A 94-character set is designated as *Gn* character set by an escape sequence `ESC ( xx` (for G0), `ESC ) xx` (for G1), `ESC * xx` (for G2), `ESC + xx` (for G3), where *xx* is a symbol or a pair of symbols found in the ISO 2375 International Register of Coded Character Sets. For example, `ESC ( @` selects the ISO 646 character set as G0, `ESC ( A` selects the U.K. standard character set (with pound instead of number sign), `ESC ( B` selects ASCII (with dollar instead of currency sign), `ESC ( M` selects a character set for African languages, `ESC ( !` A selects the Cuban character set, and so on.

A 96-character set is designated as *Gn* character set by an escape sequence `ESC - xx` (for G1), `ESC . xx` (for G2) or `ESC / xx` (for G3). For example, `ESC - g` selects the Hebrew alphabet as G1.

A multibyte character set is designated as *Gn* character set by an escape sequence `ESC $ xx` or `ESC $ ( xx` (for G0), `ESC $ ) xx` (for G1), `ESC $ * xx` (for G2), `ESC $ + xx` (for G3). For example, `ESC $ ( c` selects the Korean character set for G0. The Japanese character set selected by `ESC $ B` has a more recent version selected by `ESC & @ESC $ B`.

ISO 4873 stipulates a narrower use of character sets, where G0 is fixed (always ASCII), so that G1, G2, and G3 can only be invoked for codes with the high order bit set. In particular, `^N` and `^O` are not used anymore, `ESC ( xx` can be used only with `xx=B`, and `ESC ) xx`, `ESC * xx`, `ESC + xx` are equivalent to `ESC - xx`, `ESC . xx`, and `ESC / xx`, respectively.

SEE ALSO

`console(4)`, `console_ioctl(4)`, `console_codes(4)`

Linux, 5 November 1996

console

`console`—Console terminal and virtual consoles

DESCRIPTION

A Linux system has up to 63 *virtual consoles* (character devices with major number 4 and minor number 1 to 63), usually called `/dev/ttyn` with `1 ≤ n ≤ 63`. The current console is also addressed by `/dev/console` or `/dev/tty0`, the character device with major number 4 and minor number 0. The device files `/dev/*` are usually created using the script `MAKEDEV`, or using `mknod(1)`, usually with mode `0622` and owner `root.tty`.

Before kernel version 1.1.54, the number of virtual consoles was compiled into the kernel (in `tty.h`: `#define NR_CONSOLES 8`) and could be changed by editing and recompiling because version 1.1.54 virtual consoles are created on-the-fly, as soon as they are needed.

Common ways to start a process on a console are the following:

- Tell `init(8)` (in `inittab(5)`) to start a `getty(8)` on the console
- Ask `open(1)` to start a process on the console
- Start `x`; it will find the first unused console and display its output there. (There is also the ancient `doshell(8)`.)

Common ways to switch consoles are the following:

- Use Alt+Fn or Ctrl+Alt+Fn to switch to console n; AltGr+Fn might bring you to console n+12 [here Alt and AltGr refer to the left and right Alt keys, respectively]
- Use Alt+RightArrow or Alt+LeftArrow to cycle through the presently allocated consoles
- Use the program chvt(1). (The key mapping can be set by the user; see loadkeys(1); the preceding key combinations are according to the default settings.)

The command disalloc(8) will free the memory taken by the screen buffers for consoles that no longer have any associated process.

PROPERTIES

Consoles carry a lot of state. I hope to document that some other time. The most important fact is that the consoles simulate vt100 terminals. In particular, a console is reset to the initial state by printing the two characters ESC c. All escape sequences can be found in console_codes(4).

FILES

```
/dev/console
/dev/tty*
```

SEE ALSO

charsets(4), console_codes(4), console_ioctl(4), mknod(1), tty(4), ttys(4), getty(8), init(8), chvt(1), open(1), disalloc(8), loadkeys(1), resizecons(8), setfont(8), mapscrn(8)

Linux, 31 October 1994

console_codes

console_codes—Linux console escape and control sequences

DESCRIPTION

The Linux console implements a large subset of the VT102 and ECMA-48/ISO 6429/ANSI X3.64 terminal controls, plus certain private-mode sequences for changing the color palette, character-set mapping, and so on. In the following tabular descriptions, the second column gives ECMA-48 or DEC mnemonics (the latter if prefixed with DEC) for the given function. Sequences without a mnemonic are neither ECMA-48 nor VT102.

After all the normal output processing has been done, and a stream of characters arrives at the console driver for actual printing, the first thing that happens is a translation from the code used for processing to the code used for printing.

If the console is in UTF-8 mode, then the incoming bytes are first assembled into 16-bit Unicode codes. Otherwise, each byte is transformed according to the current mapping table (which translates it to a Unicode value). (See the “Character Sets” subsection for discussion.)

In the normal case, the Unicode value is converted to a font index, and this is stored in video memory, so that the corresponding glyph (as found in video ROM) appears on the screen. Note that the use of Unicode (and the design of the PC hardware) allows the use of 512 different glyphs simultaneously.

If the current Unicode value is a control character, or you are currently processing an escape sequence, the value will be treated specially. Instead of being turned into a font index and rendered as a glyph, it may trigger cursor movement or other control functions. (See the “Linux Console Controls” subsection.)

It is generally not good practice to hardwire terminal controls into programs. Linux supports a terminfo(5) database of terminal capabilities. Rather than emitting console escape sequences by hand, you will almost always want to use a terminfo-aware screen library or utility such as ncurses(3), tput(1), or reset(1).

LINUX CONSOLE CONTROLS

This section describes all the control characters and escape sequences that invoke special functions (that is, anything other than writing a glyph at the current cursor location) on the Linux console.

CONTROL CHARACTERS

A character is a control character if (before transformation according to the mapping table) it has one of the 14 codes 00 (NUL), 07 (BEL), 08 (BS), 09 (HT), 0a (LF), 0b (VT), 0c (FF), 0d (CR), 0e (SO), 0f (SI), 18 (CAN), 1a (SUB), 1b (ESC), 7f (DEL). One can set a display control characters mode (see below), and allow 07, 09, 0b, 18, 1a, 7f to be displayed as glyphs. On the other hand, in UTF-8 mode all codes 00–1f are regarded as control characters, regardless of any display control characters mode.

If you have a control character, it is acted upon immediately and then discarded (even in the middle of an escape sequence) and the escape sequence continues with the next character. (However, ESC starts a new escape sequence, possibly aborting a previous unfinished one, and CAN and SUB abort any escape sequence.) The recognized control characters are BEL, BS, HT, LF, VT, FF, CR, SO, SI, CAN, SUB, ESC, DEL, CSI. They do what one would expect:

BEL (0x07, ^G) beeps.

BS (0x08, ^H) backspaces one column (but not past the beginning of the line).

HT (0x09, ^I) goes to the next tab stop or to the end of the line if there is no earlier tab stop.

LF (0x0A, ^J), VT (0x0B, ^K) and FF (0x0C, ^L) all give a linefeed.

CR (0x0D, ^M) gives a carriage return.

SO (0x0E, ^N) activates the G1 character set, and if LF/NL (new line mode) is set, also a carriage return.

SI (0x0F, ^O) activates the G0 character set.

CAN (0x18, ^X) and SUB (0x1A, ^Z) interrupt escape sequences.

ESC (0x1B, ^[]) starts an escape sequence.

DEL (0x7F) is ignored.

CSI (0x9B) is equivalent to ESC [.

ESC SEQUENCES, NOT CSI SEQUENCES

ESC c	RIS	Reset.
ESC D	IND	Linefeed.
ESC E	NEL	Newline.
ESC H	HTS	Set tab stop at current column.
ESC M	RI	Reverse linefeed.
ESC Z	DECID	DEC private identification. The kernel returns the string ESC [? 6 c, claiming that it is a VT102.
ESC 7	DECSG	Save current state (cursor coordinates, attributes, character sets).
ESC 8	DECRG	Restore most recently saved state.
ESC [	CSI	Control sequence introducer.
ESC %		Start sequence selecting character set.
ESC % @		Select default (ISO 646 / ISO 8859-1).
ESC % G		Select UTF-8.
ESC % 8		Select UTF-8 (obsolete).
ESC # 8	DECALN	DEC screen alignment test: fill screen with Es.
ESC (		Start sequence defining G0 character set.
ESC (B		Select default (ISO 8859-1 mapping).
ESC (0		Select vt100 graphics mapping.

ESC (U		Select null mapping—straight to character ROM.
ESC (K		Select user mapping, the map that is loaded by the utility mapscrn(8).
ESC)		Start sequence defining G1 (followed by one of B, Ø, u, K, as above).
ESC >	DECPNM	Set numeric keypad mode.
ESC =	DECPAM	Set application keypad mode.
ESC]	OSC	(Should be: Operating system command) ESC] P nrrggbb: set palette, with parameter given in 7 hexadecimal digits after the final P :-(. Here n is the color (0–16), and rrggbb indicates the red/green/blue values (0–255). ESC] R: reset palette.

ECMA-48 CSI SEQUENCES

CSI (or ESC [) is followed by a sequence of parameters, at most NPAR(16), that are decimal numbers separated by semicolons. An empty or absent parameter is taken to be Ø. The sequence of parameters may be preceded by a single question mark.

However, after CSI [(or ESC [) a single character is read and this entire sequence is ignored. (The idea is to ignore an echoed function key.)

The action of a CSI sequence is determined by its final character.

Character	Function	Description
@	ICH	Insert the indicated # of blank characters.
A	CUU	Move cursor up the indicated # of rows.
B	CUD	Move cursor down the indicated # of rows.
C	CUF	Move cursor right the indicated # of columns.
D	CUB	Move cursor left the indicated # of columns.
E	CNL	Move cursor down the indicated # of rows, to column 1.
F	CPL	Move cursor up the indicated # of rows, to column 1.
G	CHA	Move cursor to indicated column in current row.
H	CUP	Move cursor to the indicated row, column (origin at 1,1).
J	ED	Erase display (default: from cursor to end of display). ESC [1 J: erase from start to cursor. ESC [2 J: erase whole display.
K	EL	Erase line (default: from cursor to end of line). ESC [1 K: erase from start of line to cursor. ESC [2 K: erase whole line.
L	IL	Insert the indicated # of blank lines.
M	DL	Delete the indicated # of lines.
P	DCH	Delete the indicated # of characters on the current line.
X	ECH	Erase the indicated # of characters on the current line.
a	HPR	Move cursor right the indicated # of columns.
c	DA	Answer ESC [? 6 c: 'I am a VT102'.
d	VPA	Move cursor to the indicated row, current column.
e	VPR	Move cursor down the indicated # of rows.
f	HVP	Move cursor to the indicated row, column.

<i>Character</i>	<i>Function</i>	<i>Description</i>
g	TBC	Without parameter: clear tab stop at the current position. ESC [3 g: delete all tab stops.
h	SM	Set mode.
l	RM	Reset mode.
m	SGR	Set attributes.
n	DSR	Status report.
q	DECLL	Set keyboard LEDs. ESC [0 q: clear all LEDs ESC [1 q: set Scroll Lock LED ESC [2 q: set Num Lock LED ESC [3 q: set Caps Lock LED
r	DECSTBM	Set scrolling region; parameters are top and bottom row.
s	?	Save cursor location.
u	?	Restore cursor location.
'	HPA	Move cursor to indicated column in current row.

ECMA-48 SET GRAPHICS RENDITION

The ECMA-48 SGR sequence ESC [<parameters> m sets display attributes. Several attributes can be set in the same sequence.

<i>Parameter</i>	<i>Result</i>
0	Reset all attributes to their defaults.
1	Set bold.
2	Set half-bright (simulated with color on a color display).
4	Set underscore (simulated with color on a color display). (The colors used to simulate dim or underline are set using ESC] ...)
5	Set blink.
7	Set reverse video.
10	Reset selected mapping, display control flag, and toggle meta flag.
11	Select null mapping, set display control flag, reset toggle meta flag.
12	Select null mapping, set display control flag, set toggle meta flag. (The toggle meta flag causes the high bit of a byte to be toggled before the mapping table translation is done.)
21	Set normal intensity. (This is not compatible with ECMA-48.)
22	Set normal intensity.
24	Underline off.
25	Blink off.
27	Reverse video off.
30	Set black foreground.
31	Set red foreground.
32	Set green foreground.
33	Set brown foreground.
34	Set blue foreground.
35	Set magenta foreground.

<i>Parameter</i>	<i>Result</i>
36	Set cyan foreground.
37	Set white foreground.
38	Set underscore on, set default foreground color.
39	Set underscore off, set default foreground color.
40	Set black background.
41	Set red background.
42	Set green background.
43	Set brown background.
44	Set blue background.
45	Set magenta background.
46	Set cyan background.
47	Set white background.
49	Set default background color.

ECMA-48 MODE SWITCHES

ESC [3 h	DECCRM (default off): Display control chars.
ESC [4 h	DECIM (default off): Set insert mode.
ESC [20 h	LF/NL (default off): Automatically follow echo of LF, VT, or FF with CR.

ECMA-48 STATUS REPORT COMMANDS

ESC [5 n	Device status report (DSR): Answer is ESC [0 n (Terminal OK).
ESC [6 n	Cursor position report (CPR): Answer is ESC [y ; x R, where x, y is the cursor location.

DEC PRIVATE MODE(DECSET/DECRST) SEQUENCES

These are not described in ECMA-48. The Set Mode sequences are listed; the Reset Mode sequences are obtained by replacing the final h by 1.

ESC [? 1 h	DECCKM (default off): When set, the cursor keys send an ESC 0 prefix, rather than ESC [. .
ESC [? 3 h	DECCOLM (default off = 80 columns): 80/132 col mode switch. The driver sources note that this alone does not suffice; some user-mode utility such as <code>resizecons(8)</code> has to change the hardware registers on the console video card.
ESC [? 5 h	DECSNM (default off): Set reverse-video mode.
ESC [? 6 h	DECOM (default off): When set, cursor addressing is relative to the upper left corner of the scrolling region.
ESC [? 7 h	DECAWM (default on): Set autowrap on. In this mode, a graphics character emitted after column 80 (or column 132 of DECCOLM is on) forces a wrap to the beginning of the following line first.
ESC [? 8 h	DECARM (default on): Set keyboard autorepeat on.
ESC [? 9	h X10 Mouse Reporting (default off): Set reporting mode to 1 (or reset to 0). (See “Mouse Tracking.”)
ESC [? 25 h	DECCM (default on): Make cursor visible.
ESC [? 1000 h	X11 Mouse Reporting (default off): Set reporting mode to 2 (or reset to 0). (See “Mouse Tracking.”)

LINUX CONSOLE PRIVATE CSI SEQUENCES

The following sequences are neither ECMA-48 nor native VT102. They are native to the Linux console driver. Colors are in SGR parameters: 0 = black, 1 = red, 2 = green, 3 = brown, 4 = blue, 5 = magenta, 6 = cyan, 7 = white.

ESC [1 ; n]	Set color <i>n</i> as the underline color
ESC [2 ; n]	Set color <i>n</i> as the dim color
ESC [8]	Make the current color pair the default attributes
ESC [9 ; n]	Set screen blank time-out to <i>n</i> minutes
ESC [10 ; n]	Set bell frequency in Hz
ESC [11 ; n]	Set bell duration in msec
ESC [12 ; n]	Bring specified console to the front
ESC [13]	Unblank the screen
ESC [14]	Set the VESA powerdown interval

CHARACTER SETS

The kernel knows about four translations of bytes into console-screen symbols. The four tables are

- Latin1 to PC
- VT100 graphics to PC
- PC to PC
- User-defined

There are two character sets, called G0 and G1, and one of them is the current character set. (Initially G0.) Typing `^N` causes G1 to become current, `^O` causes G0 to become current.

These variables G0 and G1 point to a translation table, and can be changed by the user. Initially, they point at the first two tables, Latin1 to PC and VT100 graphics to PC, respectively. The sequences ESC (B and ESC (0 and ESC (U and ESC (K cause G0 to point at the first, second, third, and fourth translation tables in the preceding list, respectively. The sequences ESC) B and ESC) 0 and ESC) U and ESC) K cause G1 to point at the first, second, third, and fourth translation tables in the preceding list, respectively.

The sequence ESC c causes a terminal reset, which is what you want if the screen is all garbled. The oft-advised “echo `^V^O`” will only make G0 current, but there is no guarantee that G0 points at the first table. In some distributions there is a program `reset(1)` that just does `echo ^[c`. If your `terminfo` entry for the console is correct (and has an entry `rs1=c`), then `tput reset` will also work.

The user-defined mapping table can be set using `mapscrn(8)`. The result of the mapping is that if a symbol *c* is printed, the symbol *s* = `map[c]` is sent to the video memory. The bitmap that corresponds to *s* is found in the character ROM, and can be changed using `setfont(8)`.

MOUSE TRACKING

The mouse tracking facility is intended to return `xterm`-compatible mouse status reports. Because the console driver has no way to know the device or type of the mouse, these reports are returned in the console input stream only when the virtual terminal driver receives a mouse update ioctl. These ioctls must be generated by a mouse-aware user-mode application such as the `gpm(8)` daemon.

Parameters for all mouse tracking escape sequences generated by `xterm` encode numeric parameters in a single character as `value+040`. For example, 1 is 1. The screen coordinate system is 1-based.

The `x10` compatibility mode sends an escape sequence on button press encoding the location and the mouse button pressed. It is enabled by sending ESC [? 9 h and disabled with ESC [? 9 l. On button press, `xterm` sends ESC [M bxy (six characters). Here *b* is button 1, and *x* and *y* are the *x* and *y* coordinates of the mouse when the button was pressed. This is the same code the kernel also produces.

Normal tracking mode (not implemented in Linux 2.0.24) sends an escape sequence on both button press and release. Modifier information is also sent. It is enabled by sending ESC [? 1000 h and disabled with ESC [1000 l. On button press or release, xterm sends ESC [M bxy. The low two bits of b encode button information: 0=MB1 pressed, 1=MB2 pressed, 2=MB3 pressed, 3=release. The upper bits encode what modifiers were down when the button was pressed and are added together: 4=Shift, 8=Meta, 16=Control. Again, x and y are the x and y coordinates of the mouse event. The upper-left corner is (1,1).

COMPARISONS WITH OTHER TERMINALS

Many different terminal types are described, like the Linux console, as being VT100-compatible. Here we discuss differences between the Linux console and the two most important others, the DEC VT102 and xterm(1).

CONTROL-CHARACTER HANDLING

- The vt102 also recognized the following control characters:
- NUL (0x00) was ignored.
- ENQ (0x05) triggered an answerback message.
- DC1 (0x11, ^Q, XON) resumed transmission.
- DC3 (0x13, ^S, XOFF) caused vt100 to ignore (and stop transmitting) all codes except XOFF and XON.
- VT100-like DC1/DC3 processing may be enabled by the tty driver.
- The xterm program (in vt100 mode) recognizes the control characters BEL, BS, HT, LF, VT, FF, CR, SO, SI, ESC.

ESCAPE SEQUENCES

The following VT100 console sequences are not implemented on the Linux console:

<i>Escape Sequence</i>	<i>Function</i>	<i>Description</i>
ESC N	SS2	Single shift 2. (Select G2 character set for the next character only.)
ESC O	SS3	Single shift 3. (Select G3 character set for the next character only.)
ESC P	DCS	Device control string (ended by ESC \).
ESC X	SOS	Start of string.
ESC ^	PM	Privacy message (ended by ESC\).
ESC \	ST	String terminator.
ESC * ...		Designate G2 character set.
ESC + ...		Designate G3 character set.

The program xterm (in vt100 mode) recognizes ESC c, ESC # 8, ESC >, ESC =, ESC D, ESC E, ESC H, ESC M, ESC N, ESC O, ESC P ... ESC ESC Z (it answers ESC [? 1 ; 2 c, “I am a vt100 with advanced video option”) and ESC ^ ... ESC with the same meanings as indicated above. It accepts ESC (, ESC), ESC *, ESC + followed by 0, A, B for the DEC special character and line drawing set, UK, and USASCII, respectively. It accepts ESC] for the setting of certain resources:

- ESC] 0 ; txt BEL Set icon name and window title to txt.
- ESC] 1 ; txt BEL Set icon name to txt.
- ESC] 2 ; txt BEL Set window title to txt.
- ESC] 4 6 ; name BEL Change log file to name (normally disabled by a compile-time option).
- ESC] 5 0 ; fn BEL Set font to fn.

It recognizes the following with slightly modified meaning:

- ESC 7 DECSC Save cursor
- ESC 8 DECRC Restore cursor

It also recognizes

ESC F		Cursor to lower-left corner of screen (if enabled by the <code>hpLowerLeftBugCompat</code> resource).
ESC l		Memory lock (per HP terminals). Locks memory above the cursor.
ESC m		Memory unlock (per HP terminals).
ESC n	LS2	Invoke the G2 character set.
ESC o	LS3	Invoke the G3 character set.
ESC j	LS3R	Invoke the G3 character set as GR.
		Has no visible effect in <code>xterm</code> .
ESC g	LS2R	Invoke the G2 character set as GR.
		Has no visible effect in <code>xterm</code> .
ESC `	LS1R	Invoke the G1 character set as GR.
		Has no visible effect in <code>xterm</code> .

It does not recognize ESC % ...

CSI SEQUENCES

The `xterm` program (as of `xFree86 3.1.2G`) does not recognize the blink or invisible-mode SGRs. Stock X11R6 versions do not recognize the color-setting SGRs. All other ECMA-48 CSI sequences recognized by Linux are also recognized by `xterm`, and vice versa.

The `xterm` program will recognize all of the DEC Private Mode sequences listed earlier, but none of the Linux private-mode sequences. For discussion of `xterm`'s own private-mode sequences, refer to the *Xterm Control Sequences* document by Edward Moy and Stephen Gildea, available with the `x` distribution.

BUGS

In 2.0.23, CSI is broken, and NUL is not ignored inside escape sequences.

SEE ALSO

`console(4)`, `console_ioctl(4)`, `charsets(4)`

Linux, 31 October 1996

console ioctl

`console ioctl`—Ioctls for console terminal and virtual consoles

DESCRIPTION

The following Linux-peculiar `ioctl` requests are supported. Each requires a third argument, assumed here to be `argp`.

WARNING

If you use the following information, you are going to burn yourself. Ioctls are undocumented Linux internals, liable to be changed without warning. Use POSIX functions.

KDGETLED	Get state of LEDs. <i>argp</i> points to a long int. The lower three bits of <i>*argp</i> are set to the state of the LEDs, as follows:
LED_CAP	0x04 caps lock LED
LED_NUM	0x02 num lock LED
LED_SCR	0x01 scroll lock LED
KDSETLED	Set the LEDs. The LEDs are set to correspond to the lower three bits of <i>argp</i> . However, if a higher order bit is set, the LEDs revert to normal, displaying the state of the keyboard functions of caps lock, num lock, and scroll lock. Before 1.1.54, the LEDs just reflected the state of the corresponding keyboard flags, and <i>KDGETLED</i> / <i>KDSETLED</i> would also change the keyboard flags. Since 1.1.54 the LEDs can be made to display arbitrary information, but by default they display the keyboard flags. The following two ioctls are used to access the keyboard flags.
KDGKBLED	Get keyboard flags <i>CapsLock</i> , <i>NumLock</i> , <i>ScrollLock</i> (not lights). <i>argp</i> points to a char that is set to the flag state. The low order three bits (mask 0x7) get the current flag state, and the low order bits of the next nibble (mask 0x70) get the default flag state (since 1.1.54).
KDSKBLED	Set keyboard flags <i>CapsLock</i> , <i>NumLock</i> , <i>ScrollLock</i> (not lights). <i>argp</i> has the desired flag state. The low order three bits (mask 0x7) have the flag state, and the low order bits of the next nibble (mask 0x70) have the default flag state (since 1.1.54).
KDGKBTYPE	Get keyboard type. This returns the value <i>KB_101</i> , defined as 0x02.
KDADDIO	Add I/O port as valid. Equivalent to <i>ioperm</i> (<i>arg</i> , 1, 1).
KDDELIO	Delete I/O port as valid. Equivalent to <i>ioperm</i> (<i>arg</i> , 1, 0).
KDENABIO	Enable I/O to video board. Equivalent to <i>ioperm</i> (0x3b4, 0x3df-0x3b4+1, 1).
KDDISABIO	Disable I/O to video board. Equivalent to <i>ioperm</i> (0x3b4, 0x3df-0x3b4+1, 0).
KDSETMODE	Set text/graphics mode. <i>argp</i> is one of these: KD_TEXT 0x00 KD_GRAPHICS 0x01
KDGETMODE	Get text/graphics mode. <i>argp</i> points to a long which is set to one of the above values.
KDMKTONE	Generate tone of specified length. The lower 16 bits of <i>argp</i> specify the period in clock cycles, and the upper 16 bits give the duration in msec. If the duration is zero, the sound is turned off. Control returns immediately. For example, <i>argp</i> = (125<<16) + 0x637 would specify the beep normally associated with a <i>ctrl-G</i> .
KIOCSOUND	Start or stop sound generation. The lower 16 bits of <i>argp</i> specify the period in clock cycles (that is, <i>argp</i> = 1193180/frequency). <i>argp</i> = 0 turns sound off. In either case, control returns immediately.
GIO_CMAP	Get the current default color map from kernel. <i>argp</i> points to a 48-byte array. (Since 1.3.3.)
PIO_CMAP	Change the default text-mode color map. <i>argp</i> points to a 48-byte array that contains, in order, the red, green, and blue values for the 16 available screen colors: 0 is off, and 255 is full intensity. The default colors are, in order: black, dark red, dark green, brown, dark blue, dark purple, dark cyan, light grey, dark grey, bright red, bright green, yellow, bright blue, bright purple, bright cyan, and white. (Since 1.3.3.)
GIO_FONT	Gets 256-character screen font in expanded form. <i>argp</i> points to an 8192-byte array. Fails with error code <i>EINVAL</i> if the currently loaded font is a 512-character font, or if the console is not in text mode.

GIO_FONTX	Gets screen font and associated information. <i>argp</i> points to a struct <code>consolefontdesc</code> (see <code>PIO_FONTX</code>). On call, the <code>charcount</code> field should be set to the maximum number of characters that would fit in the buffer pointed to by <code>chardata</code> . On return, the <code>charcount</code> and <code>charheight</code> are filled with the respective data for the currently loaded font, and the <code>chardata</code> array contains the font data if the initial value of <code>charcount</code> indicated enough space was available; otherwise the buffer is untouched and <code>errno</code> is set to <code>ENOMEM</code> . (Since 1.3.1.)
PIO_FONT	Sets 256-character screen font. Load font into the EGA/VGA character generator. <i>argp</i> points to a 8192-byte map, with 32 bytes per character. Only first <i>N</i> of them are used for an 8x <i>N</i> font ($0 < N \leq 32$). This call also invalidates the Unicode mapping.
PIO_FONTX	Sets screen font and associated rendering information. <i>argp</i> points to a <pre> struct consolefontdesc { u_short charcount; /* characters in font (256 or 512) */ u_short charheight; /* scan lines per character (1-32) */ char *chardata; /* font data in expanded form */ }; </pre>
PIO_FONTRESET	If necessary, the screen will be appropriately resized, and <code>SIGWINCH</code> sent to the appropriate processes. This call also invalidates the Unicode mapping. (Since 1.3.1.) Resets the screen font, size, and Unicode mapping to the bootup defaults. <i>argp</i> is unused, but should be set to <code>NULL</code> to ensure compatibility with future versions of Linux. (Since 1.3.28.)
GIO_SCRNMAP	Get screen mapping from kernel. <i>argp</i> points to an area of size <code>E_TABSZ</code> , which is loaded with the font positions used to display each character. This call is likely to return useless information if the currently loaded font is more than 256 characters.
GIO_UNISCRNMAP	Get full Unicode screen mapping from kernel. <i>argp</i> points to an area of size <code>E_TABSZ*sizeof (unsigned short)</code> , which is loaded with the Unicodes each character represent. A special set of Unicodes, starting at <code>U+F000</code> , are used to represent “direct to font” mappings. (Since 1.3.1.)
PIO_SCRNMAP	Loads the user-definable (fourth) table in the kernel that maps bytes into console screen symbols. <i>argp</i> points to an area of size <code>E_TABSZ</code> .
PIO_UNISCRNMAP	Loads the user-definable (fourth) table in the kernel that maps bytes into Unicodes, which are then translated into screen symbols according to the currently loaded Unicode-to-font map. Special Unicodes starting at <code>U+F000</code> can be used to map directly to the font symbols. (Since 1.3.1.)
GIO_UNIMAP	Get Unicode-to-font mapping from kernel. <i>argp</i> points to a <pre> struct unimapdesc { u_short entry_ct; struct unipair *entries; }; </pre> where <i>entries</i> points to an array of <pre> struct unipair { u_short unicode; u_short fontpos; }; </pre> (Since 1.1.92.)
PIO_UNIMAP	Put Unicode-to-font mapping in kernel. <i>argp</i> points to a struct <code>unimapdesc</code> . (Since 1.1.92.)

PIO_UNIMAPCLR	Clear table, possibly advise hash algorithm. <i>argp</i> points to a <pre> struct unimapinit { u short advised hashsize; /* 0 if no opinion */ u short advised hashstep; /* 0 if no opinion */ u short advised hashlevel; /* 0 if no opinion */ }; </pre> (Since 1.1.92.)
KDGKBMODE	Gets current keyboard mode. <i>argp</i> points to a long, which is set to one of these: <pre> K_RAW 0x00 K_XLATE 0x01 K_MEDIUMRAW 0x02 K_UNICODE 0x03 </pre>
KDSKBMODE	Sets current keyboard mode. <i>argp</i> is a long equal to one of the above values.
KDGKBMETA	Gets meta key handling mode. <i>argp</i> points to a long which is set to one of these: <pre> K_METABIT 0x03 Set high order bit K_ESCPREFIX 0x04 Escape prefix </pre>
KDSKBMETA	Sets meta key handling mode. <i>argp</i> is a long equal to one of the preceding values.
KDGKBENT	Gets one entry in key translation table (keycode to action code). <i>argp</i> points to a <pre> struct kbentry { u_char kb_table; u_char kb_index; u_short kb_value; }; </pre> with the first two members filled in: <i>kb_table</i> selects the key table ($0 \leq \text{kb\_table} < \text{MAX\_NR\_KEYMAPS}$), and <i>kb_index</i> is the keycode ($0 \leq \text{kb\_index} < \text{NR\_KEYS}$). <i>kb_value</i> is set to the corresponding action code, or <i>K_HOLE</i> if there is no such key, or <i>K_NOSUCHMAP</i> if <i>kb_table</i> is invalid.
KDSKBENT	Sets one entry in translation table. <i>argp</i> points to a struct <i>kbentry</i> .
KDGKBSENT	Gets one function key string. <i>argp</i> points to a <pre> struct kbsentry { u_char kb_func; u_char kb_string[512]; }; </pre> <i>kb_string</i> is set to the (NULL-terminated) string corresponding to the <i>kb_func</i> function key action code.
KDSKBSENT	Sets one function key string entry. <i>argp</i> points to a struct <i>kbsentry</i> .
KDGKBDIACR	Read kernel accent table. <i>argp</i> points to a <pre> struct kbdiacrs { unsigned int kb_cnt; struct kbdiacr kbdiacr[256]; }; </pre> where <i>kb_cnt</i> is the number of entries in the array, each of which is a struct <i>kbdiacr</i> { <i>u_char</i> <i>diacr</i>, <i>base</i>, <i>result</i> };
KDGETKEYCODE	Read kernel keycode table entry (scan code to keycode). <i>argp</i> points to a <pre> struct kbkeycode { unsigned int scancode, keycode; }; </pre> <i>keycode</i> is set to correspond to the given <i>scancode</i>. ($89 \leq \text{scancode} \leq 255$ only. For $1 \leq \text{scancode} \leq 88$, <i>keycode</i>==<i>scancode</i>.) (Since 1.1.63.)
KDSETKEYCODE	Write kernel keycode table entry. <i>argp</i> points to struct <i>kbkeycode</i> . (Since 1.1.63.)

KDSIGACCEPT	The calling process indicates its willingness to accept the signal <code>argp</code> when it is generated by pressing an appropriate key combination. ($1 \leq \text{argp} \leq \text{NSIG}$). (See <code>spawn_console()</code> in <code>linux/drivers/char/keyboard.c</code>.)						
VT_OPENQRY	Returns the first available (nonopened) console. <code>argp</code> points to an <code>int</code> that is set to the number of the vt ($1 \leq *argp \leq \text{MAX\_NR\_CONSOLES}$).						
VT_GETMODE	Get mode of active vt. <code>argp</code> points to a <pre>struct vt_mode { char mode; /* vtmode */ char waitv; /* if set, hang on writes if not active */ short relsig; /* signal to raise on release req */ short acqsig; /* signal to raise on acquisition */ short frsig; /* unused (set to 0) */ };</pre> mode is set to one of these values: <table> <tr> <td>VT_AUTO</td><td>Auto vt switching</td></tr> <tr> <td>VT_PROCESS</td><td>Process controls switching</td></tr> <tr> <td>VT_ACKACQ</td><td>Acknowledge switch</td></tr> </table>	VT_AUTO	Auto vt switching	VT_PROCESS	Process controls switching	VT_ACKACQ	Acknowledge switch
VT_AUTO	Auto vt switching						
VT_PROCESS	Process controls switching						
VT_ACKACQ	Acknowledge switch						
VT_SETMODE	Set mode of active vt. <code>argp</code> points to a <code>struct vt_mode</code>.						
VT_GETSTATE	Get global vt state info. <code>argp</code> points to a <pre>struct vt_stat { ushort v_active; /* active vt */ ushort v_signal; /* signal to send */ ushort v_state; /* vt bitmask */ };</pre> For each vt in use, the corresponding bit in the <code>v</code> state member is set. (Kernels 1.0 through 1.1.92.)						
VT_RELDISP	Release a display.						
VT_ACTIVATE	Switch to vt <code>argp</code> ($1 \leq \text{argp} \leq \text{MAX\_NR\_CONSOLES}$).						
VT_WAITACTIVE	Wait until vt <code>argp</code> has been activated.						
VT_DISALLOCATE	Deallocate the memory associated with vt <code>argp</code>. (Since 1.1.54.)						
VT_RESIZE	Set the kernel's idea of screensize. <code>argp</code> points to a <pre>struct vt_sizes { ushort v_rows; /* #rows */ ushort v_cols; /* #columns */ ushort v_scrollsize; /* no longer used */ };</pre> Note that this does not change the video mode. See <code>resizecons(8)</code>. (Since 1.1.54.)						
VT_RESIZEX	Set the kernel's idea of various screen parameters. <code>argp</code> points to a <pre>struct vt_consize { ushort v_rows; /* number of rows */ ushort v_cols; /* number of columns */ ushort v_vlin; /* number of pixel rows on screen */ ushort v_clin; /* number of pixel rows per character */ ushort v_vcol; /* number of pixel columns on screen */ ushort v_ccol; /* number of pixel columns per character */ };</pre> Any parameter may be set to zero, indicating no change, but if multiple parameters are set, they must be self-consistent. Note that this does not change the video mode. See <code>resizecons(8)</code>. (Since 1.3.3.)						

The action of the following ioctls depends on the first byte in the struct pointed to by `argp`, referred to here as the subcode. These are legal only for the superuser or the owner of the current tty.

<code>TIOCLINUX, subcode=0</code>	Dump the screen. Disappeared in 1.1.92. (With kernel 1.1.92 or later, read from <code>/dev/vcsN</code> or <code>/dev/vcsaN</code> instead.)
<code>TIOCLINUX, subcode=1</code>	Get task information. Disappeared in 1.1.92.
<code>TIOCLINUX, subcode=2</code>	Set selection. <code>argp</code> points to a struct{fchar subcode; short xs, ys, xe, ye; short sel_mode; } xs and ys are the starting column and row. xe and ye are the ending column and row. (Upper-left corner is row=column=1.) sel_mode is 0 for character-by-character selection, 1 for word-by-word selection, or 2 for line-by-line selection. The indicated screen characters are highlighted and saved in the static array sel buffer in <code>devices/char/console.c</code> .
<code>TIOCLINUX, subcode=3</code>	Paste selection. The characters in the selection buffer are written to fd.
<code>TIOCLINUX, subcode=4</code>	Unblank the screen.
<code>TIOCLINUX, subcode=5</code>	Sets contents of a 256-bit look up table defining characters in a “word”, for word-by-word selection. (Since 1.1.32.)
<code>TIOCLINUX, subcode=6</code>	<code>argp</code> points to a char that is set to the value of the kernel variable shift state. (Since 1.1.32.)
<code>TIOCLINUX, subcode=7</code>	<code>argp</code> points to a char that is set to the value of the kernel variable report mouse. (Since 1.1.33.)
<code>TIOCLINUX, subcode=8</code>	Dump screen width and height, cursor position, and all the character-attribute pairs. (Kernels 1.1.67 through 1.1.91 only. With kernel 1.1.92 or later, read from <code>/dev/vcsa*</code> instead.)
<code>TIOCLINUX, subcode=9</code>	Restore screen width and height, cursor position, and all the character-attribute pairs. (Kernels 1.1.67 through 1.1.91 only. With kernel 1.1.92 or later, write to <code>/dev/vcsa*</code> instead.)
<code>TIOCLINUX, subcode=10</code>	Handles the power saving feature of the new generation of monitors. VESA screen blanking mode is set to <code>argp[1]</code> , which governs what screen blanking does: 0 Screen blanking is disabled. 1 The current video adapter register settings are saved, then the controller is programmed to turn off the vertical synchronization pulses. This puts the monitor into standby mode. If your monitor has an Off_Mode timer, then it will eventually power down by itself. 2 The current settings are saved, then both the vertical and horizontal synchronization pulses are turned off. This puts the monitor into off mode. If your monitor has no Off_Mode timer, or if you want your monitor to power down immediately when the blank timer times out, then you choose this option. (Caution: Powering down frequently will damage the monitor.) (Since 1.1.76.)

RETURN VALUES

-1 for error, and `errno` is set.

ERRORS

`errno` may take on these values:

<code>EBADF</code>	File descriptor is invalid.
<code>ENOTTY</code>	File descriptor is not associated with a character special device, or the specified request does not apply to it.

EINVAL

File descriptor or `argp` is invalid.

EPERM

Permission violation.

WARNING

Do not regard this man page as documentation of the Linux console `ioctl`s. This is provided for the curious only, as an alternative to reading the source. `Ioctls` are undocumented Linux internals, liable to be changed without warning. (And indeed, this page more or less describes the situation as of kernel version 1.1.94; there are many minor and not-so-minor differences with earlier versions.)

Very often, `ioctl`s are introduced for communication between the kernel and one particular well-known program (`fdisk`, `hdparm`, `setserial`, `tunelp`, `loadkeys`, `selection`, `setfont`, and so on), and their behavior will be changed when required by this particular program.

Programs using these `ioctl`s will not be portable to other versions of UNIX, will not work on older versions of Linux, and will not work on future versions of Linux.

Use POSIX functions.

SEE ALSO

`kbd_mode(1)`, `loadkeys(1)`, `dumpkeys(1)`, `mknod(1)`, `setleds(1)`, `setmetamode(1)`, `ioperm(2)`, `termios(2)`, `execve(2)`, `fcntl(2)`, `charsets(4)`, `console(4)`, `console_codes(4)`, `mt(4)`, `sd(4)`, `tty(4)`, `ttys(4)`, `vcs(4)`, `vcsa(4)`, `mapscrn(8)`, `setfont(8)`, `resizecons(8)`, `/usr/include/linux/kd.h`, `/usr/include/linux/vt.h`.

Linux, 18 September 1995

fd

`fd`—Floppy disk device

CONFIGURATION

Floppy drives are block devices with major number 2. Typically, they are owned by `root.floppy` (that is, user `root`, group `floppy`) and have either mode `0660` (access checking via group membership) or mode `0666` (everybody has access). The minor numbers encode the device type, drive number, and controller number. For each device type (that is, combination of density and track count), there is a base minor number. To this base number, add the drive's number on its controller and 128 if the drive is on the secondary controller. In the following device tables, `n` represents the drive number.

WARNING

If you use formats with more tracks than supported by your drive, you may cause it mechanical damage. Trying once if more tracks than the usual 40/80 are supported should not damage it, but no warranty is given for that. Don't create device entries for those formats to prevent their usage if you are not sure.

Drive-independent device files that automatically detect the media format and capacity are

<i>Name</i>	<i>Base minor #</i>
fdn	0

5.25-inch double density device files:

<i>Name</i>	<i>Capac.</i>	<i>Cyl.</i>	<i>Sect.</i>	<i>Heads</i>	<i>Base minor #</i>
fdnd360	360K	40	9	2	4

5.25-inch high density device files:

<i>Name</i>	<i>Capac.</i>	<i>Cyl.</i>	<i>Sect.</i>	<i>Heads</i>	<i>Base minor #</i>
fdnh360	360K	40	9	2	20
fdnh410	410K	41	10	2	48
fdnh420	420K	42	10	2	64
fdnh720	720K	80	9	2	24
fdnh880	880K	80	11	2	80
fdnh1200	1200K	80	15	2	8
fdnh1440	1440K	80	18	2	40
fdnh1476	1476K	82	18	2	56
fdnh1494	1494K	83	18	2	72
fdnh1600	1600K	80	20	2	92

3.5-inch double density device files:

<i>Name</i>	<i>Capac.</i>	<i>Cyl.</i>	<i>Sect.</i>	<i>Heads</i>	<i>Base minor #</i>
fdnD360	360K	80	9	1	12
fdnD720	720K	80	9	2	16
fdnD800	800K	80	10	2	120
fdnD1040	1040K	80	13	2	84
fdnD1120	1120K	80	14	2	88

3.5-inch high density device files:

<i>Name</i>	<i>Capac.</i>	<i>Cyl.</i>	<i>Sect.</i>	<i>Heads</i>	<i>Base minor #</i>
fdnH360	360K	40	9	2	12
fdnH720	720K	80	9	2	16
fdnH820	820K	82	10	2	52
fdnH830	830K	83	10	2	68
fdnH1440	1440K	80	18	2	28
fdnH1600	1600K	80	20	2	124
fdnH1680	1680K	80	21	2	44
fdnH1722	1722K	82	21	2	60
fdnH1743	1743K	83	21	2	76
fdnH1760	1760K	80	22	2	96
fdnH1840	1840K	80	23	2	116
fdnH1920	1920K	80	24	2	100

3.5-inch extra density device files:

<i>Name</i>	<i>Capac.</i>	<i>Cyl.</i>	<i>Sect.</i>	<i>Heads</i>	<i>Base minor #</i>
<code>fdnE2880</code>	2880K	80	36	2	32
<code>fdnCompaQ</code>	2880K	80	36	2	36
<code>fdnE3200</code>	3200K	80	40	2	104
<code>fdnE3520</code>	3520K	80	44	2	108
<code>fdnE3840</code>	3840K	80	48	2	112

DESCRIPTION

`fd` special files access the floppy disk drives in raw mode. The following `ioctl(2)` calls are supported by `fd` devices:

`FDCLRPRM` clears the media information of a drive (geometry of disk in drive).

`FDSETPRM` sets the media information of a drive. The media information will be lost when the media is changed.

`FDDEFPRM` sets the media information of a drive (geometry of disk in drive). The media information will not be lost when the media is changed. This will disable autodetection. In order to re-enable autodetection, you have to issue an `FDCLRPRM`.

`FDGETDRVTYPE` displays the type of a drive (name parameter). For formats that work in several drive types, `FDGETDRVTYPE` returns a name that is appropriate for the oldest drive type that supports this format.

`FDLUSH` invalidates the buffer cache for the given drive.

`FDLUSH` invalidates the buffer cache for the given drive.

`FDSETMAXERRS` sets the error thresholds for reporting errors, aborting the operation, recalibrating, resetting, and reading sector by sector.

`FDSETMAXERRS` gets the current error thresholds.

`FDGETDRVTYPE` gets the internal name of the drive.

`FDWERRORCLR` clears the write error statistics.

`FDWERRORGET` reads the write error statistics. These include the total number of write errors, the location and disk of the first write error, and the location and disk of the last write error. Disks are identified by a generation number that is incremented at (almost) each disk change.

`FDTWADDLE` switches the drive motor off for a few microseconds. This might be needed in order to access a disk whose sectors are too close together.

`FDSETDRVPRM` sets various drive parameters.

`FDGETDRVPRM` reads these parameters back.

`FDGETDRVSTAT` gets the cached drive state (disk changed, write protected et al.)

`FDPOLLDVSTAT` polls the drive and return its state.

`FDGETFDCSTAT` gets the floppy controller state.

`FDRESET` resets the floppy controller under certain conditions.

`FDRAWCMD` sends a raw command to the floppy controller.

For more precise information, consult also the `<linux/fd.h>` and `<linux/fdreg.h>` include files, as well as the manual page for floppy control.

NOTES

The various formats allow you to read and write many types of disks. However, if a floppy is formatted with a too small intersector gap, performance may drop, up to needing a few seconds to access an entire track. To prevent this, use interleaved formats. It is not possible to read floppies that are formatted using GCR (group code recording), which is used by Apple II and Macintosh computers (800K disks). Reading floppies that are hard sectored (one hole per sector, with the index hole being a little skewed) is not supported. This used to be common with older 8-inch floppies.

FILES

/dev/fd*

AUTHORS

Alain Knaff (Alain.Knaff@imag.fr), David Niemi (niemidc@clark.net), Bill Broadhurst (bbroad@netcom.com).

SEE ALSO

floppycontrol(1), mknod(1), chown(1), getfdprm(1), superformat(1), mount(8), setfd-prm(8)

Linux, 29 January 1995

hd

hd—MFM/IDE hard disk device

DESCRIPTION

hd* are block devices to access MFM/IDE hard disk drives in raw mode. The master drive on the primary IDE controller (major device number 3) is hda; the slave drive is hdb. The master drive of the second controller (major device number 22) is hdc and the slave hdd.

General IDE block device names have the form hd x , or hd x P, where x is a letter denoting the physical drive, and P is a number denoting the partition on that physical drive. The first form, hd x , is used to address the whole drive. Partition numbers are assigned in the order the partitions are discovered, and only nonempty, nonextended partitions get a number. However, partition numbers 1–4 are given to the four partitions described in the MBR (the primary partitions), regardless of whether they are unused or extended. Thus, the first logical partition will be hd x 5. Both DOS-type partitioning and BSD-disk label partitioning are supported. You can have at most 63 partitions on an IDE disk.

For example, /dev/hda refers to all of the first IDE drive in the system; and /dev/hdb3 refers to the third DOS primary partition on the second one.

They are typically created by the following:

```
mknod -m 660 /dev/hda b 3 0
mknod -m 660 /dev/hda1 b 3 1
mknod -m 660 /dev/hda2 b 3 2

...
mknod -m 660 /dev/hda8 b 3 8
mknod -m 660 /dev/hdb b 3 64
mknod -m 660 /dev/hdb1 b 3 65
mknod -m 660 /dev/hdb2 b 3 66

...
mknod -m 660 /dev/hdb8 b 3 72
chown root.disk /dev/hd*
```

FILES

/dev/hd*

SEE ALSO

mknod(1), chown(1), mount(8), sd(4)

Linux, 17 December 1992

ispell

ispell—Format of ispell dictionaries and affix files

DESCRIPTION

ispell(1) requires two files to define the language that it is spell checking. The first file is a dictionary containing words for the language, and the second is an affix file that defines the meaning of special flags in the dictionary. The two files are combined by `buildhash` (see `spell(1)`) and written to a hash file that is not described here.

A raw ispell dictionary (either the main dictionary or your own personal dictionary) contains a list of words, one per line. Each word may optionally be followed by a slash (/) and one or more flags, which modify the root word as explained later. Depending on the options with which ispell was built, case may or may not be significant in either the root word or the flags, independently. Specifically, if the compile-time option `CAPITALIZATION` is defined, case is significant in the root word; if not, case is ignored in the root word. If the compile-time option `MASKBITS` is set to a value of 32, case is ignored in the flags; otherwise, case is significant in the flags. Contact your system administrator or ispell maintainer for more information (or use the `-vv` flag to find out). The dictionary should be sorted with the `-f` flag of `sort(1)` before the hash file is built; this is done automatically by `unchlist(1)`, which is the normal way of building dictionaries.

If the dictionary contains words that have string characters (see the affix file documentation, following), they must be written in the format given by the `defstringtype` statement in the affix file. This will be the case for most non-English languages. Be careful to use this format, rather than that of your favorite formatter, when adding words to a dictionary. If you add words to your personal dictionary during an ispell session, they will automatically be converted to the correct format. This feature can be used to convert an entire dictionary if necessary:

```
echo qqqqq > dummy.dict
buildhash dummy.dict affix-file dummy.hash
awk 'fprint "***gENDfprint "#g' old-dict-file \
'| ispell -a -T old-dict-string-type \
-d ./dummy.hash -p ./new-dict-file \
> /dev/null
rm dummy.*'
```

The case of the root word controls the case of words accepted by ispell, as follows:

1. If the root word appears only in lowercase (for example, bob), it will be accepted in lowercase, capitalized, or all capitals.
2. If the root word appears capitalized (for example, Robert), it will not be accepted in all lowercase, but will be accepted capitalized or all in capitals.
3. If the root word appears all in capitals (for example, UNIX), it will only be accepted all in capitals.
4. If the root word appears with a “funny” capitalization (for example, ITCorp), a word will be accepted only if it follows that capitalization, or if it appears all in capitals.
5. More than one capitalization of a root word may appear in the dictionary. Flags from different capitalizations are combined using `OR`.

Redundant capitalizations (for example, bob and Bob) will be combined by `buildhash` and by `ispell` (for personal dictionaries), and can be removed from a raw dictionary by `munchlist`.

For example, the dictionary

```
bob
Robert
UNIX
ITCorp
ITCorp
```

will accept bob, Bob, BOB, Robert, ROBERT, UNIX, ITCorp, ITCorp, and ITCORP, and will reject all others. Some of the unacceptable forms are bOb, robert, Unix, and ItCorp.

As mentioned, root words in any dictionary may be extended by flags. Each flag is a single alphabetic character, which represents a prefix or suffix that may be added to the root to form a new word. For example, in an English dictionary the `o` flag can be added to `bathe` to make `bathed`. Because flags are represented as a single bit in the hashed dictionary, this results in significant space savings. The `munchlist` script will reduce an existing raw dictionary by adding flags when possible.

When a word is extended with an affix, the affix will be accepted only if it appears in the same case as the initial (prefix) or final (suffix) letter of the word. Thus, for example, the entry `UNIX/M` in the main dictionary (`M` means add an apostrophe and an `s` to make a possessive) would accept `UNIX'S` but would reject `UNIX's`. If `UNIX's` is legal, it must appear as a separate dictionary entry, and it will not be combined by `munchlist`. (In general, you don't need to worry about these things; `munchlist` guarantees that its output dictionary will accept the same set of words as its input, so all you have to do is add words to the dictionary and occasionally run `munchlist` to reduce its size.)

As mentioned, the affix definition file describes the affixes associated with particular flags. It also describes the character set used by the language.

Although the affix-definition grammar is designed for a line-oriented layout, it is actually a free-format grammar and can be laid out weirdly if you want. Comments are started by a pound (sharp) sign (`#`), and continue to the end of the line. Backslashes are supported in the usual fashion (`\nnn`, plus specials `\n`, `\r`, `\t`, `\v`, `\f`, `\b`, and the new hex format `\xnn`). Any character with special meaning to the parser can be changed to an uninterpreted token by backslashing it; for example, you can declare a flag named `asterisk` or `colon` with flag `n*:` or flag `n::`.

The grammar will be presented in a top-down fashion, with discussion of each element. An affix-definition file must contain exactly one table:

```
table :[headers][prefixes][suffixes]
```

At least one of prefixes and suffixes is required. They can appear in either order.

```
headers :[options ] char-sets
```

The headers describe options global to this dictionary and language. These include the character sets to be used and the formatter, and the defaults for certain *ispell* flags.

```
options : { fmtr-stmt | opt-stmt | flag-stmt | num-stmt }
```

The options statements define the defaults for certain *ispell* flags and for the character sets used by the formatters.

```
fmtr-stmt : { nroff-stmt | tex-stmt }
```

A `fmtr-stmt` statement describes characters that have special meaning to a formatter. Normally, this statement is not necessary, but some languages may have preempted the usual defaults for use as language-specific characters. In this case, these statements may be used to redefine the special characters expected by the formatter.

```
nroff-stmt : { nroffchars | troffchars } string
```

The `nroffchars` statement allows redefinition of certain `nroff` control characters. The string given must be exactly five characters long, and must list substitutions for the left and right parentheses, the period, the backslash, and the asterisk. (The right parenthesis is not currently used, but is included for completeness.) For example, the statement:

```
nroffchars { }.\\\*
```

would replace the left and right parentheses with left and right curly braces for purposes of parsing `nroff`/`troff` strings, with no effect on the others (admittedly a contrived example). Note that the backslash is escaped with a backslash.

```
tex-stmt : { TeXchars | texchars } string
```

The `TeXchars` statement allows redefinition of certain `TeX`/`LaTeX` control characters. The string given must be exactly thirteen characters long, and must list substitutions for the left and right parentheses, the left and right square brackets, the left and right curly braces, the left and right angle brackets, the backslash, the dollar sign, the asterisk, the period or dot, and the percent sign. For example, the statement:

```
texchars ( )\[\<\>\>\$*.%
```

would replace the functions of the left and right curly braces with the left and right angle brackets for purposes of parsing TeX/LaTeX constructs, while retaining their functions for the `tib` bibliographic preprocessor. Note that the backslash, the left square bracket, and the right angle bracket must be escaped with a backslash.

```
opt-stmt : { cmpnd-stmt | aff-stmt }
cmpnd-stmt : compoundwords compound-opt
  aff-stmt : allaffixes on-or-off
  on-or-off : { on | off }
compound-opt : { on-or-off | controlled character }
```

An `opt-stmt`, used in the preceding code, controls certain `ispell` defaults that are best made language-specific. The `allaffixes` statement controls the default for the `-P` and `-m` options to `ispell`. If `allaffixes` is turned off (the default), `ispell` will default to the behavior of the `-P` flag: root/affix suggestions will only be made if there are no “near misses.” If `allaffixes` is turned on, `ispell` will default to the behavior of the `-m` flag: root/affix suggestions will always be made.

The `compoundwords` statement controls the default for the `-B` and `-C` options to `ispell`. If `compoundwords` is turned off (the default), `ispell` will default to the behavior of the `-B` flag: run-together words will be reported as errors. If `compoundwords` is turned on, `ispell` will default to the behavior of the `-C` flag: run-together words will be considered as compounds if both are in the dictionary. This is useful for languages such as German and Norwegian, which form large numbers of compound words. Finally, if `compoundwords` is set to controlled, only words marked with the flag indicated by character (which should not be otherwise used) will be allowed to participate in compound formation. Because this option requires the flags to be specified in the dictionary, it is not available from the command line.

```
flag-stmt : flagmarker character
```

The `flagmarker` statement describes the character that is used to separate affix flags from the root word in a raw dictionary file. This must be a character that is not found in any word (including in string characters; see following). The default is `/` because this character is not normally used to represent special characters in any language.

```
num-stmt : compoundmin digit
```

The `compoundmin` statement controls the length of the two components of a compound word. This only has an effect if `compoundwords` is turned on or if the `-C` flag is given to `ispell`. In that case, only words at least as long as the given minimum will be accepted as components of a compound. The default is 3 characters.

```
char-sets : norm-sets [ alt-sets ]
```

The character-set section describes the characters that can be part of a word, and defines their collating order. There must always be a definition of “normal” character sets; in addition, there may be one or more partial definitions of “alternate” sets that are used with various text formatters.

```
norm-sets :[deftype ] charset-group
```

A “normal” character set may optionally begin with a definition of the file suffixes that make use of this set. Following this are one or more character-set declarations.

```
deftype : defstringtype name deformatter suffix*
```

The *defstringtype* declaration gives a list of file suffixes that should make use of the default string characters defined as part of the base character set; it is only necessary if string characters are being defined. The *name* parameter is a string giving the unique name associated with these suffixes; often it is a formatter name. If the formatter is a member of the `troff` family, `nroff` should be used for the name associated with the most popular macro package; members of the TeX family should use `tex`. Other names may be chosen freely, but they should be kept simple, as they are used in `ispell`’s `-T` switch to specify a formatter type. The *deformatter* parameter specifies the deformatting style to use when processing files with the given suffixes. Currently, this must be either `tex` or `nroff`. The suffix parameters are a whitespace-separated list of strings which, if present at the end of a filename, indicate that the associated set of string characters should be used by default for this file. For example, the suffix list for the `troff` family typically includes suffixes such as `.ms`, `.me`, `.mm`, and so on.

```
charset-group : { char-stmt | string-stmt | dup-stmt }*
```

A `char-stmt` describes single characters; a `string-stmt` describes characters that must appear together as a string, and which usually represent a single character in the target language. Either may also describe conversion between uppercase and lowercase. A `dup-stmt` is used to describe alternate forms of string characters, so that a single dictionary may be used with several formatting programs that use different conventions for representing non-ASCII characters.

```
char-stmt : wordchars character-range
          | wordchars lowercase-range uppercase-range
          | boundarychars character-range
          | boundarychars lowercase-range uppercase-range
string-stmt : stringchar string
           | stringchar lowercase-string uppercase-string
```

Characters described with the `boundarychars` statement are considered part of a word only if they appear singly, embedded between characters declared with the `wordchars` or `stringchar` statements. For example, if the hyphen is a boundary character (useful in French), the string `foo-bar` would be a single word, but `-foo` would be the same as `foo`, and `foo-bar` would be two words separated by nonword characters.

If two ranges or strings are given in a `char-stmt` or `string-stmt`, the first describes characters that are interpreted as lowercase and the second describes uppercase. In the case of a `stringchar` statement, the two strings must be of the same length. Also, in a `stringchar` statement, the actual strings may contain both uppercase and characters themselves without difficulty; for instance, the statement:

```
stringchar "\\*(sS" "\\*(Ss"
```

is legal and will not interfere with (or be interfered with by) other declarations of `"s"` and `"S"` as lowercase and uppercase, respectively.

A final note on string characters: some languages collate certain special characters as if they were strings. For example, the German “a-umlaut” is traditionally sorted as if it were *ae*. `ispell` is not capable of this; each character must be treated as an individual entity. So in certain cases, `ispell` will sort a list of words into a different order than the standard “dictionary” order for the target language.

```
alt-sets : alttype [ alt-stmt*]
```

Because different formatters use different notations to represent non-ASCII characters, `ispell` must be aware of the representations used by these formatters. These are declared as alternate sets of string characters.

```
alttype : altstringtype name suffix*
```

The `altstringtype` statement introduces each set by declaring the associated formatter name and filename suffix list. This name and list are interpreted exactly as in the `defstringtype` statement. Following this header are one or more `alt-stmts` that declare the alternate string characters used by this formatter.

```
alt-stmt : altstringchar alt-string std-string
```

The `altstringchar` statement describes alternate representations for string characters. For example, the `—mm` macro package of `troff` represents the German “a-umlaut” as `a\*`, while TeX uses the sequence `\a`. If the `troff` versions are declared as the standard versions using `stringchar`, the TeX versions may be declared as alternates by using the statement:

```
altstringchar "\\a a\*
```

When the `altstringchar` statement is used to specify alternate forms, all forms for a particular formatter must be declared together as a group. Also, each formatter or macro package must provide a complete set of characters, both uppercase and lowercase, and the character sequences used for each formatter must be completely distinct. Character sequences that describe uppercase and lowercase versions of the same printable character must also be the same length. It may be necessary to define some new macros for a given formatter to satisfy these restrictions. (The current version of `buildhash` does not enforce these restrictions, but failure to obey them may result in errors being introduced into files that are processed with `ispell`.)

An important minor point is that `ispell` assumes that all characters declared as `wordchars` or `boundarychars` will occupy exactly one position on the terminal screen.

A single character-set statement can declare either a single character or a contiguous range of characters. A range is given as in `egrep` and the shell: `[a-z]` means lowercase alphabets; `[^a-z]` means all but lowercase, and so on. All character-set statements are combined (unioned) to produce the final list of characters that may be part of a word. The collating order of the characters is defined by the order of their declaration; if a range is used, the characters are considered to have been declared in ASCII order. Characters that have case are collated next to each other, with the uppercase character first.

The character-declaration statements have a rather strange behavior caused by the need to match each lowercase character with its uppercase equivalent. In any given `wordchars` or `boundarychars` statement, the characters in each range are first sorted into ASCII collating sequence, then matched one-for-one with the other range. (The two ranges must have the same number of characters). Thus, for example, the two statements:

```
wordchars [aeiou] [AEIOU]
wordchars [aeiou] [UOIEA]
```

would produce exactly the same effect. To get the vowels to match up “wrong,” you would have to use separate statements:

```
wordchars a U
wordchars e O
wordchars i I
wordchars o E
wordchars u A
```

which would cause uppercase *e* to be *O*, and lowercase *O* to be *e*. This should normally be a problem only with languages that have been forced to use a strange ASCII collating sequence. If your uppercase and lowercase letters both collate in the same order, you shouldn’t have to worry about this “feature.”

The prefixes and suffixes sections have exactly the same syntax, except for the introductory keyword:

```
prefixes : prefixes flagdef*
suffixes : suffixes flagdef*
flagdef : flag [*jU] char : repl *
```

A prefix or suffix table consists of an introductory keyword and a list of flag definitions. Flags can be defined more than once, in which case the definitions are combined. Each flag controls one or more `repls` (replacements), which are conditionally applied to the beginnings or endings of various words.

Flags are named by a single character `char`. Depending on a configuration option, this character can be either any uppercase letter (the default configuration) or any 7-bit ASCII character. Most languages should be able to get along with just 26 flags.

A flag character may be prefixed with one or more option characters. (If you wish to use one of the option characters as a flag character, simply enclose it in double quotes.)

The asterisk (*) option means that this flag participates in cross-product formation. This only matters if the file contains both prefix and suffix tables. If so, all prefixes and suffixes marked with an asterisk will be applied in all cross-combinations to the root word. For example, consider the root *fix* with prefixes *pre* and *in*, and suffixes *es* and *ed*. If all flags controlling these prefixes and suffixes are marked with an asterisk, then the single root *fix* would also generate *prefix*, *prefixes*, *prefixed*, *infix*, *infixes*, *infixed*, *fix*, *fixes*, and *fixed*. Cross-product formation can produce a large number of words quickly, some of which may be illegal, so watch out. If cross-products produce illegal words, `munchlist` will not produce those flag combinations, and the flag will not be useful.

```
repl : condition* > [ - strip-string , ] append-string
```

The `~` option specifies that the associated flag is only active when a compound word is being formed. This is useful in a language like German, in which the form of a word sometimes changes inside a compound.

A `repl` is a conditional rule for modifying a root word. Up to eight conditions may be specified. If the conditions are satisfied, the rules on the rightside of the `repl` are applied, as follows:

1. If a `strip-string` is given, it is first stripped from the beginning or ending (as appropriate) of the root word.
2. The `append-string` is added at that point.

For example, the condition `.` means “any word”, and the condition `Y` means “any word ending in Y.” The following (suffix) replacements:

```
. > MENT
Y > -Y,IES
```

would change *induce* to *inducement* and *fly* to *flies*. (If they were controlled by the same flag, they would also change *fly* to *flyment*, which might not be what was wanted. `munchlist` can be used to protect against this sort of problem; see the command sequence given in the next paragraph.)

No matter how much you might want it, the strings on the right must be strings of specific characters, not ranges. The reasons are rooted deeply in the way `ispell` works, and it would be difficult or impossible to provide for more flexibility. For example, you might want to write:

```
[EY] > -[EY],IES
```

This will not work. Instead, you must use two separate rules:

```
E > -E,IES
Y > -Y,IES
```

The application of `repl`s can be restricted to certain words with conditions:

```
condition : { . | character | range }
```

A condition is a restriction on the characters that adjoin, and/or are replaced by, the right-hand side of the `repl`. Up to eight conditions may be given, which should be enough context for anyone. The right-hand side will be applied only if the conditions in the `repl` are satisfied. The conditions also implicitly define a length; roots shorter than the number of conditions will not pass the test. (As a special case, a condition of a single dot defines a length of zero, so that the rule applies to all words indiscriminately.) This length is independent of the separate test that insists that all flags produce an output word length of at least four.

Conditions that are single characters should be separated by whitespace. For example, to specify words ending in *ED*, write this:

```
E D> -ED,ING # As in covered > covering
```

If you write this:

```
ED > -ED,ING
```

the effect will be the same as

```
[ED] > -ED,ING
```

As a final, minor but important point, it is sometimes useful to rebuild a dictionary file using an incompatible suffix file. For example, suppose you expand the `R` flag to generate “er” and “ers” (thus making the `Z` flag somewhat obsolete). To build a new dictionary `newdict` that using new affixes will accept exactly the same list of words as the old list `olddict` did using old affixes, the `-c` switch of `munchlist` is useful, as in the following example:

```
$ munchlist -c oldaffixes -l newaffixes olddict > newdict
```

If you use this procedure, your new dictionary will always accept the same list the original did, even if you badly screwed up the affix file. This is because `munchlist` compares the words generated by a flag with the original word list and refuses to use any flags that generate illegal words. (Don’t forget that the `munchlist` step takes a long time and eats up temporary file space.)

EXAMPLES

As an example of conditional suffixes, here is the specification of the `S` flag from the English affix file:

```
flag *S:
[^AEIOU]Y > -Y,IES # As in imply > implies
[AEIOU]Y > S # As in convey > conveys
[SXZH] > ES # As in fix > fixes
[^SXZHY] > S #As in bat > bats
```

The first line applies to words ending in Y but not in vowel-Y. The second takes care of the vowel-Y words. The third then handles those words that end in a sibilant or near-sibilant, and the last picks up everything else.

Note that the conditions are written very carefully so that they apply to disjoint sets of words. In particular, note that the fourth line excludes words ending in Y as well as the obvious SXZH. Otherwise, it would convert “imply” into “implys.”

Although the English `affix` file does not do so, you can also have a flag generate more than one variation on a root word. For example, you could extend the English `R` flag as follows:

```
flag *R:
E > R #As in skate > skater
E > RS # As in skate > skaters
[^AEIOU]Y > -Y,IER # As in multiply > multiplier
[^AEIOU]Y > -Y,IERS # As in multiply > multipliers
[AEIOU]Y > ER # As in convey > conveyer
[AEIOU]Y > ERS # As in convey > conveyers
[^EY] > ER # As in build > builder
[^EY] > ERS # As in build > builders
```

This flag would generate both “skater” and “skaters” from “skate.” This capability can be very useful in languages that make use of noun, verb, and adjective endings. For instance, one could define a single flag that generated all the German “weak” verb endings.

SEE ALSO

`ispell(1)`

Local

lp

`lp`—Line printer devices.

SYNOPSIS

```
#include <linux/lp.h>
```

CONFIGURATION

`lp[02]` are character devices for the parallel line printers; they have major number 6 and minor number 02. The minor numbers correspond to the printer port base addresses 0x03bc, 0x0378, and 0x0278. Usually, they have mode 220 and are owned by root and group `lp`. You can use printer ports either with polling or with interrupts. Interrupts are recommended when high traffic is expected, such as for laser printers. For usual dot matrix printers, polling will usually be enough. The default is polling.

DESCRIPTION

The following `ioctl(2)` calls are supported:

```
int ioctl(int fd, LPTIME, int arg)
```

Sets the amount of time that the driver sleeps before rechecking the printer when the printer’s buffer appears to be filled to `arg`. If you have a fast printer, decrease this number; if you have a slow printer, then increase it. This is in hundredths of a second; the default 2 is 0.05 seconds. It only influences the polling driver.

```
int ioctl(int fd, LPCHAR, int arg)
```

Sets the maximum number of busy-wait iterations that the polling driver does while waiting for the printer to get ready for receiving a character to `arg`. If printing is too slow, increase this number; if the system gets too slow, decrease this number. The default is 1000. It only influences the polling driver.

```
int ioctl(int fd, LPABORT, int arg)
```

If `arg` is 0, the printer driver will retry on errors; otherwise, it will abort. The default is 0.

```
int ioctl(int fd, LPABORTOPEN, int arg)
```

If `arg` is 0, `open(2)` will be aborted on error; otherwise, the error will be ignored. The default is to ignore it.

```
int ioctl(int fd, LPCAREFUL, int arg)
```

If `arg` is 0, then the out-of-paper, offline, and error signals are required to be false on all writes; otherwise, they are ignored. The default is to ignore them.

```
int ioctl(int fd, LPWAIT, int arg)
```

Sets the number of busy-wait iterations to wait before strobing the printer to accept a just-written character and the number of iterations to wait before turning the strobe off again to `arg`. The specification says this time should be 0.5 microseconds, but experience has shown the delay caused by the code is already enough. For that reason, the default value is 0. This is used for both the polling and the interrupt driver.

```
int ioctl(int fd, LPSETIRQ, int arg)
```

This `ioctl()` requires superuser privileges. It takes an `int` containing the new IRQ as argument. As a side effect, the printer is reset. When `arg` is 0, the polling driver will be used, which is also default.

```
int ioctl(int fd, LPGETIRQ, int *arg)
```

Stores the currently used IRQ in `arg`.

```
int ioctl(int fd, LPGETSTATUS, int *arg)
```

Stores the value of the status port in `arg`. The bits have the following meaning:

```
LP_PBUSY
```

Inverted busy input, active high

```
LP_PACK
```

Unchanged acknowledge input, active low

```
LP_POUTPA
```

Unchanged out-of-paper input, active high

```
LP_PSELECD
```

Unchanged selected input, active high

```
LP_PERRORP
```

Unchanged error input, active low

Refer to your printer manual for the meaning of the signals. Note that undocumented bits can also be set, depending on your printer.

```
int ioctl(int fd, LPRESET)
```

Resets the printer. No argument is used.

FILES

```
/dev/lp*
```

AUTHORS

The printer driver was originally written by Jim Weigand and Linus Torvalds. It was further improved by Michael K. Johnson. The interrupt code was written by Nigel Gamble. Alan Cox modularized it. `LPCAREFUL`, `LPABORT`, `LPGETSTATUS` were added by Chris Metcalf.

SEE ALSO

```
mknod(1), chown(1), chmod(1), tune1p(8), 1pcntl(8)
```

15 January 1995

mem, kmem, port

mem, kmem, port—System memory, kernel memory, and system ports

DESCRIPTION

`mem` is a character device file that is an image of the main memory of the computer. It can be used, for example, to examine (and even patch) the system.

Byte addresses in `mem` are interpreted as physical memory addresses. References to non-existent locations cause errors to be returned.

Examining and patching is likely to lead to unexpected results when read-only or write-only bits are present.

It is typically created by

```
mknod -m 660 /dev/mem c 1 1
chown root.mem /dev/mem
```

The file `kmem` is the same as `mem`, except that the kernel virtual memory rather than physical memory is accessed.

It is typically created by

```
mknod -m 640 /dev/kmem c 1 2
chown root.mem /dev/kmem
```

`port` is similar to `mem`, but the IO ports are accessed.

It is typically created by

```
mknod -m 660 /dev/port c 1 4
chown root.mem /dev/port
```

FILES

```
/dev/mem
/dev/kmem
/dev/port
```

SEE ALSO

`mknod(1)`, `chown(1)`, `ioperm(2)`

Linux, 21 November 1992

mouse

`mouse`—Serial mouse interface.

CONFIG

Serial mice are connected to a serial RS232/V24 dialout line; see `cua(4)` for a description.

DESCRIPTION

The pinout of the usual 9 pin plug as used for serial mice is

<i>Pin</i>	<i>Name</i>	<i>Used for</i>
2	RX	Data
3	TX	-12 V, I _{max} = 10 mA
4	DTR	+12 V, I _{max} = 10 mA
7	RTS	+12 V, I _{max} = 10 mA
5	GND	Ground

This is the specification; in fact, 9 V suffices with most mice.

The mouse driver can recognize a mouse by dropping RTS to low. About 14ms later, the mouse will send 0x4D on the data line. After a further 63ms, Microsoft-compatible mice will send 0x33. Other mice send different values.

The relative mouse movement is sent as dx (positive means right) and dy (positive means down). Various mice can operate at different speeds. To select speeds, cycle through the speeds 9600, 4800, 2400, and 1200 bits/sec, each time writing the two characters from the table below and waiting 0.1 seconds. The following table shows available speeds and the strings that select them:

<i>Bits/sec</i>	<i>String</i>
9600	*q
4800	*p
2400	*o
1200	*n

The first byte of a data packet can be used to synchronization purposes.

MICROSOFT PROTOCOL

The Microsoft protocol uses 1 start bit, 7 data bits, no parity, and 1 stop bit at the speed of 1200 bits/sec. Data is sent to Rx/D in 3-byte packets. The dx and dy movements are sent as two's-complement, 1b (rb) is set when the left (right) button is pressed:

<i>Byte</i>	<i>d6</i>	<i>d5</i>	<i>d4</i>	<i>d3</i>	<i>d2</i>	<i>d1</i>	<i>d0</i>
1	1	lb	rb	dy7	dy6	dx7	dx7
2	0	dx5	dx4	dx3	dx2	dx1	dx0
3	0	dy5	dy4	dy3	dy2	dy1	dy0

Original Microsoft mice have only two buttons. However, there are some three-button mice that also use the Microsoft protocol. Pressing the third button is reported by sending a packet with zero movement and no buttons pressed.

MOUSESYSTEMS PROTOCOL

The MouseSystems protocol uses 1 start bit, 8 data bits, no parity, and 2 stop bits at the speed of 1200 bits/sec. Data is sent to Rx/D in 5-byte packets. dx is sent as the sum of the two two's-complement values, dy is sent as negated sum of the two two's-complement values. 1b (mb, rb) is cleared when the left (middle, right) button is pressed:

<i>Byte</i>	<i>d7</i>	<i>d6</i>	<i>d5</i>	<i>d4</i>	<i>d3</i>	<i>d2</i>	<i>d1</i>	<i>d0</i>
1	1	?	?	?	?	lb	mb	rb
2	0	dx6	dx5	dx4	dx3	dx2	dx1	dx0
3	0	dx6	dx5	dx4	dx3	dx2	dx1	dx0
4	0	dya6	dya5	dya4	dya3	dya2	dya1	dya0
5	0	dyb6	dyb5	dyb4	dyb3	dyb2	dyb1	dyb0

SUN PROTOCOL

The Sun protocol uses 1 start bit, 8 data bits, no parity, and 2 stop bits at the speed of 1200 bits/sec. Data is sent to Rx/D in 3-byte packets. dx is sent as single two's-complement value, dy as negated two's-complement value. 1b (mb, rb) is cleared when the left (middle, right) button is pressed:

<i>Byte</i>	<i>d7</i>	<i>d6</i>	<i>d5</i>	<i>d4</i>	<i>d3</i>	<i>d2</i>	<i>d1</i>	<i>d0</i>
1	1	?	?	?	?	lb	mb	rb
2	0	dx6	dx5	dx4	dx3	dx2	dx1	dx0
3	0	dy6	dy5	dy4	dy3	dy2	dy1	dy0

MM PROTOCOL

The MM protocol uses 1 start bit, 8 data bits, odd parity, and 1 stop bit at the speed of 1200 bits/sec. Data is sent to RxD in 3-byte packets. dx and dy are sent as single signed values, the sign bit indicating a negative value. 1b (mb, rb) is set when the left (middle, right) button is pressed:

Byte	d7	d6	d5	d4	d3	d2	d1	d0
1	1	?	?	dxs	dys	lb	mb	rb
2	0	dx6	dx5	dx4	dx3	dx2	dx1	dx0
3	0	dy6	dy5	dy4	dy3	dy2	dy1	dy0

FILES

`/dev/mouse` a commonly used symlink pointing to a mouse device

SEE ALSO

`cua(4)`, `bm(4)`

Linux, 10 February 1996

null, zero

`null`, `zero`—Data sink.

DESCRIPTION

Data written on a `null` or `zero` special file is discarded.
Reads from the `null` special file always return end of file, whereas reads from `zero` always return `\0` characters.
`null` and `zero` are typically created by

```
mknod -m 666 /dev/null c 1 3
mknod -m 666 /dev/zero c 1 5
chown root.mem /dev/null /dev/zero
```

NOTES

If these devices are not writable and readable for all users, many programs will act strangely.

FILES

`/dev/null`
`/dev/zero`

SEE ALSO

`mknod(1)`, `chown(1)`

Linux, 21 November 1992

ram

`ram`—Ram disk device.

DESCRIPTION

ram is a block device to access the ram disk in raw mode.

It is typically created by

```
mknod -m 660 /dev/ram b 1 1
chown root.disk /dev/ram
```

FILES

/dev/ram

SEE ALSO

mknod(1), chown(1), mount(8)

Linux, 21 November 1992

sd

sd—Driver for SCSI disk drives.

SYNOPSIS

```
#include <linux/hdreg.h>
```

CONFIG

The block device name has the following form: sd1p, where 1 is a letter denoting the physical drive, and p is a number denoting the partition on that physical drive. Often, the partition number, p, will be left off when the device corresponds to the whole drive.

SCSI disks have a major device number of 8 and a minor device number of the form (16 * drive_number) + partition_number, where drive_number is the number of the physical drive in order of detection and partition_number is as follows:

Partition 0	The whole drive
Partitions 1-4	The DOS “primary” partitions
Partitions 5-8	The DOS “extended” (or “logical”) partitions

For example, /dev/sda will have major 8 and minor 0 and will refer to all the first SCSI drives in the system; /dev/sdb3 will have major 8 and minor 19 and will refer to the third DOS “primary” partition on the second SCSI drive in the system.

At this time, only block devices are provided. Raw devices have not yet been implemented.

DESCRIPTION

The following ioctl's are provided:

HDIO_REQ

Returns the BIOS disk parameters in the following structure:

```
struct hd_geometry {
    unsigned char heads;
    unsigned char sectors;
    unsigned short cylinders;
    unsigned long start;
};
```

A pointer to this structure is passed as the ioctl(2) parameter.

The information returned in the parameter is the disk geometry of the drive as understood by DOS! This geometry is not the physical geometry of the drive. It is used when constructing the drive's partition table,

BLKGETSIZE

however, and is needed for convenient operation of `fdisk(1)`, `efdisk(1)`, and `lilo(1)`. If the geometry information is not available, zero is returned for all the parameters.

BLKRRPART

Returns the device size in sectors. The `ioctl(2)` parameter should be a pointer to a long.

Forces a re-read of the SCSI disk partition tables. No parameter is needed.

The `scsi(4)` `ioctl`s are also supported. If the `ioctl(2)` parameter is required and it is `NULL`, then `ioctl(2)` will return `-EINVAL`.

FILES

`/dev/sd[a-h]`: The whole device

`/dev/sd[a-h][0-8]`: Individual block partitions

SEE ALSO

`scsi(4)`

17 December 1992

st

`st`—SCSI tape device.

SYNOPSIS

```
#include <sys/mtio.h>
int ioctl(int fd, int request [, (void *)arg3])
int ioctl(int fd, MTIOCTOP, (struct mtop *)mt_cmd)
int ioctl(int fd, MTIOCGET, (struct mtget *)mt_status)
int ioctl(int fd, MTIOCPOS, (struct mtpos *)mt_pos)
```

DESCRIPTION

The `st` driver provides the interface to a variety of SCSI tape devices. Currently, the driver takes control of all detected devices of type sequential-access. The `st` driver uses major device number 9.

Each device uses two minor device numbers: a principal minor device number, `n`, assigned sequentially in order of detection, and a no-rewind device number, `(n + 128)`. Devices opened using the principal device number are sent a `REWIND` command when they are closed. Devices opened using the no-rewind device number are not. Options such as density or block size are not coded in the minor device number. These options must be set by explicit `ioctl()` calls and remain in effect when the device is closed and reopened.

Devices are typically created by

```
mknod -m 660 /dev/st0 c 9 0
mknod -m 660 /dev/st1 c 9 1
mknod -m 660 /dev/nst0 c 9 128
mknod -m 660 /dev/nst1 c 9 129
```

There is no corresponding block device. The character device provides buffering and read-ahead by default and supports reads and writes of arbitrary size (limited by the driver's internal buffer size, which defaults to 32768 bytes but can be changed either by using a kernel startup option or by changing a compile-time constant).

Device `/dev/tape` is usually created as a hard or soft link to the default tape device on the system.

ioctl1s

The driver supports three `ioctl1` requests. Requests not recognized by the `st` driver are passed to the `scsi` driver. The definitions below are from `/usr/include/linux/mtio.h`:

MTIOCTOP: PERFORM A TAPE OPERATION

This request takes an argument of type `(struct mtop *)`. Not all drives support all operations. The driver returns an EIO error if the drive rejects an operation.

```
/* Structure for MTIOCTOP - mag tape op command: */
struct mtop {
    short mt_op; /* operations defined below */
    int mt_count; /* how many of them */
};
```

Magnetic tape operations:

MTBSF	Backward space over <code>mt_count</code> filemarks.
MTBSFM	Backward space over <code>mt_count</code> filemarks. Reposition the tape to the EOT side of the last filemark.
MTBSR	Backward space over <code>mt_count</code> records (tape blocks).
MTBSS	Backward space over <code>mt_count</code> setmarks.
MTEOM	Go to the end of the recorded media (for appending files).
MTERASE	Erase tape.
MTFSF	Forward space over <code>mt_count</code> filemarks.
MTFSFM	Forward space over <code>mt_count</code> filemarks. Reposition the tape to the BOT side of the last filemark.
MTFSR	Forward space over <code>mt_count</code> records (tape blocks).
MTFSS	Forward space over <code>mt_count</code> setmarks.
MTNOP	No op; flushes the driver's buffer as a side effect. Should be used before reading status with <code>MTIOCGET</code> .
MTOFFL	Rewind and put the drive off line.
MTRESET	Reset drive.
MTRETEN	Retention tape.
MTREW	Rewind.
MTSEEK	Seek to the tape block number specified in <code>mt_count</code> . This operation requires either a SCSI-2 drive that supports the <code>LOCATE</code> command (device-specific address) or a Tandberg-compatible SCSI-1 drive (Tandberg, Archive Viper, Wangtek,...). The block number should be one that was previously returned by <code>MTIOCPOS</code> because the number is device-specific.
MTSETBLK	Set the drive's block length to the value specified in <code>mt_count</code> . A block length of zero sets the drive to variable block size mode.
MTSETDENSITY	Set the tape density to the code in <code>mt_count</code> . Some useful density codes are 18 0x00 Implicit 0x11 QIC-525 0x04 QIC-11 0x12 QIC-1350 0x05 QIC-24 0x13 DDS 0x0F QIC-120 0x14 Exabyte EXB-8200 0x10 QIC-150 0x15 Exabyte EXB-8500
MTWEOF	Write <code>mt_count</code> filemarks.
MTWSM	Write <code>mt_count</code> setmarks.

MTSETDRVBUFFER

Set various drive and driver options according to bits encoded in `mt_count`. These consist of the drive's buffering mode, six Boolean driver options, and the buffer write threshold. These parameters are initialized only when the device is first detected. The settings persist when the device is closed and reopened. A single operation can affect just the buffering mode, just the Boolean options, or just the write threshold.

A value having zeros in the high-order 4 bits will be used to set the drive's buffering mode. The buffering modes are:

- 0 The drive will not report `GOOD` status on write commands until the data blocks are actually written to the medium.
- 1 The drive may report `GOOD` status on write commands as soon as all the data has been transferred to the drive's internal buffer.
- 2 The drive may report `GOOD` status on write commands as soon as all the data has been transferred to the drive's internal buffer and all buffered data from different initiators has been successfully written to the medium.

To control the write threshold, the value in `mt_count` must include the constant `MT_ST_WRITE_THRESHOLD` logically ORed with a block count in the low 28 bits. The block count refers to 1024-byte blocks, not the physical block size on the tape. The threshold cannot exceed the driver's internal buffer size (see the description).

To set and clear the Boolean options, the value in `mt_count` must include the constant `MT_ST_BOOLEAN` logically ORed with whatever combination of the following options is desired. Any options not specified are set false. The Boolean options are

MT_ST_BUFFER_WRITES

(Default: true) Buffer all write operations. If this option is false and the drive uses a fixed block size, then all write operations must be for a multiple of the block size. This option must be set false to write reliable multi-volume archives.

MT_ST_ASYNC_WRITES

(Default: true) When this option is true, write operations return immediately without waiting for the data to be transferred to the drive if the data fits into the driver's buffer. The write threshold determines how full the buffer must be before a new SCSI write command is issued. Any errors reported by the drive will be held until the next operation. This option must be set false to write reliable multi-volume archives.

MT_ST_READ_AHEAD

(Default: true) This option causes the driver to provide read buffering and read-ahead. If this option is false and the drive uses a fixed block size, then all read operations must be for a multiple of the block size.

MT_ST_TWO_FM

(Default: false) This option modifies the driver behavior when a file is closed. The normal action is to write a single filemark. If the option is true, the driver will write two filemarks and backspace over the second one.

Note that this option should not be set true for QIC tape drives because they are unable to overwrite a filemark. These drives detect the end of recorded data by testing for blank tape rather than two consecutive filemarks.

MT_ST_DEBUGGING

(Default: false) This option turns on various debugging messages from the driver (effective only if the driver was compiled with `DEBUG` defined).

MT_ST_FAST_EOM

(Default: false) This option causes the `MTEOM` operation to be sent directly to the drive, potentially speeding up the operation but causing the driver

to lose track of the current file number normally returned by the MTIOCGET request. If MT_ST_FAST_EOM is false, the driver will respond to an MTEOM request by forward spacing over files.

Example:

```
struct mtop mt_cmd;
mt_cmd.mt_op = MTSETDRVBUFFER;
mt_cmd.mt_count = MT_ST_BOOLEANS |
                  MT_ST_BUFFER_WRITES |
                  MT_ST_ASYNC_WRITES;
ioctl(fd, MTIOCTOP, &mt_cmd);
```

MTIOCGET: GET STATUS

This request takes an argument of type (struct mtget *). The driver returns an EIO error if the drive rejects an operation.

```
/* structure for MTIOCGET - mag tape get status command */
struct mtget {
    long    mt_type;
    long    mt_resid;
    /* the following registers are device dependent */
    long    mt_dsreg;
    long    mt_gstat;
    long    mt_erreg;
    /* The next two fields are not always used */
    daddr_t  mt_fileno;
    daddr_t  mt_blkno;
};
```

The header file defines many values for mt_type, but the current driver reports only the generic types MT_ISSCSI1 (Generic SCSI-1 tape) and MT_ISSCSI2 (Generic SCSI-2 tape).

mt_resid is always zero. (Not implemented for SCSI tape drives.)

mt_dsreg reports the drive's current settings for block size (in the low 24 bits) and density (in the high 8 bits). These fields are defined by MT_ST_BLKSIZE_SHIFT, MT_ST_BLKSIZE_MASK, MT_ST_DENSITY_SHIFT, and MT_ST_DENSITY_MASK.

mt_gstat reports generic (device independent) status information. The header file defines macros for testing these status bits:

GMT_EOF(x)	The tape is positioned just after a filemark (always false after an MTSEEK operation).
GMT_BOT(x)	The tape is positioned at the beginning of the first file (always false after an MTSEEK operation).
GMT_EOT(x)	A tape operation has reached the physical End of Tape.
GMT_SM(x)	The tape is currently positioned at a setmark (always false after an MTSEEK operation).
GMT_EOD(x)	The tape is positioned at the end of recorded data.
GMT_WR_PROT(x)	The drive is write-protected. For some drives this can also mean that the drive does not support writing on the current medium type.
GMT_ONLINE(x)	The last open() found the drive with a tape in place and ready for operation.
GMT_D_6250(x), GMT_D_1600(x), GMT_D_800(x)	This generic status information reports the current density setting for 9-track tape drives only.
GMT_DR_OPEN(x)	The drive does not have a tape in place.
GMT_IM_REP_EN(x)	Immediate report mode (not supported).
	mt_erreg: The only field defined in mt_erreg is the recovered error count in the low 16 bits (as defined by MT_ST_SOFTERR_SHIFT and MT_ST_SOFTERR_MASK). Due to inconsistencies in the way drives report recovered errors, this count is often not maintained.

`mt_fileno` reports the current file number (zero-based). This value is set to -1 when the file number is unknown (such as after `MTBSS` or `MTSEEK`).

`mt_blkno` reports the block number (zero-based) within the current file. This value is set to -1 when the block number is unknown (such as after `MTBSF`, `MTBSS`, or `MTSEEK`).

MTIOCPOS: GET TAPE POSITION

This request takes an argument of type (`struct mtpos *`) and reports the drive's notion of the current tape block number, which is not the same as `mt_blkno` returned by `MTIOCGET`. This drive must be a SCSI-2 drive that supports the `READ POSITION` command (device-specific address) or a Tandberg-compatible SCSI-1 drive (Tandberg, Archive Viper, Wangtek,...).

```
/* structure for MTIOCPOS - mag tape get position command */
struct mtpos {
    long mt_blkno; /* current block number */
};
```

RETURN VALUE

<code>EIO</code>	The requested operation could not be completed.
<code>ENOSPC</code>	A write operation could not be completed because the tape reached end-of-medium.
<code>EACCES</code>	An attempt was made to write or erase a write-protected tape. (This error is not detected during <code>open()</code> .)
<code>ENXIO</code>	During opening, the tape device does not exist.
<code>EBUSY</code>	The device is already in use or the driver was unable to allocate a buffer.
<code>EOVERFLOW</code>	An attempt was made to read or write a variable-length block that is larger than the driver's internal buffer.
<code>EINVAL</code>	An <code>ioctl()</code> had an illegal argument, or a requested block size was illegal.
<code>ENOSYS</code>	Unknown <code>ioctl()</code> .

COPYRIGHT

Copyright 1995, Robert K. Nichols.

Permission is granted to make and distribute verbatim copies of this manual, provided the copyright notice and this permission notice are preserved on all copies. Additional permissions are contained in the header of the source file.

SEE ALSO

`mt(1)`

Linux 1.1.86, 31 January 1995

tty

`tty`—Controlling terminal.

DESCRIPTION

The file `/dev/tty` is a character file with major number 5 and minor number 0, usually of mode 0666 and owner.group `root.tty`. It is a synonym for the controlling terminal of a process, if any.

In addition to the `ioctl()` requests supported by the device that `tty` refers to, the following `ioctl()` request is supported:

TIOCNOTTY

Detach the current process from its controlling terminal and remove it from its current process group, without attaching it to a new process group (that is, set its process group ID to zero). This `ioctl()` call only works on file descriptors connected to `/dev/tty`; this is used by daemon processes when they are invoked by a user at a terminal. The process attempts to open `/dev/tty`; if the open succeeds, it detaches itself from the terminal by using `TIOCNOTTY`, but if the open fails, it is obviously not attached to a terminal and does not need to detach itself.

FILES

`/dev/tty`

SEE ALSO

`mknod(1)`, `chown(1)`, `getty(1)`, `termios(2)`, `console(4)`, `ttys(4)`

Linux, 21 January 1992

ttys

ttys—Serial terminal lines.

DESCRIPTION

`ttys[0-3]` are character devices for the serial terminal lines.

They are typically created by

```
mknod -m 660 /dev/ttyS0 c 4 64 # base address 0x03f8
mknod -m 660 /dev/ttyS1 c 4 65 # base address 0x02f8
mknod -m 660 /dev/ttyS2 c 4 66 # base address 0x03e8
mknod -m 660 /dev/ttyS3 c 4 67 # base address 0x02e8
chown root.tty /dev/ttyS[0-3]
```

FILES

`/dev/ttyS[0-3]`

SEE ALSO

`mknod(1)`, `chown(1)`, `getty(1)`, `tty(4)`

Linux, 19 December 1992

VCS, VCSA

vcs, vcsa—Virtual console memory.

DESCRIPTION

`/dev/vcs0` is a character device with major number 7 and minor number 0, usually of mode 0644 and owner `root.tty`. It refers to the memory of the currently displayed virtual console terminal.

`/dev/vcs[1-63]` are character devices for virtual console terminals; they have major number 7 and minor number 1 to 63, usually mode 0644 and owner `root.tty`. `/dev/vcsa[0-63]` are the same but include attributes and are prefixed with four bytes, giving the screen dimensions and cursor position: `lines`, `columns`, `x`, `y`. (`x = y = 0` at the top-left corner of the screen.)

These replace the screendump `ioctl`s of `console(4)`, so the system administrator can control access using filesystem permissions.

The devices for the first eight virtual consoles may be created by

```
for x in 0 1 2 3 4 5 6 7 8; do
mknod -m 644 /dev/vcs$x c 7 $x;
mknod -m 644 /dev/vcsa$x c 7 ${x+128};
done
chown root.tty /dev/vcs*
```

No `ioctl()` requests are supported.

EXAMPLES

You can do a screendump on vt3 by switching to vt1 and typing `cat /dev/vcs3 >foo`.

This program displays the character and screen attributes under the cursor of the second virtual console and then changes the background color there:

```
#include <unistd.h>
#include <stdio.h>
#include <fcntl.h>

void main()
{ int fd;
  struct {char lines, cols, x, y;} scrn;
  char ch, attrib;

  fd = open("/dev/vcsa2", O_RDWR);
  (void)read(fd, &scrn, 4);
  (void)lseek(fd, 4 + 2*(scrn.y*scrn.cols + scrn.x), 0);
  (void)read(fd, &ch, 1);
  (void)read(fd, &attrib, 1);
  printf("ch='%c' attrib=0x%02x\n", ch, attrib);
  attrib ^= 0x10;
  (void)lseek(fd, -1, 1);
  (void)write(fd, &attrib, 1);
}
```

FILES

```
/dev/vcs[0-63]
/dev/vcsa[0-63]
```

AUTHOR

Andries Brouwer (aeb@cwi.nl)

HISTORY

Introduced with version 1.1.92 of the Linux kernel.

SEE ALSO

`console(4)`, `tty(4)`, `ttys(4)`, `selection(1)`

Part V:

File Formats

intro

intro—Introduction to file formats.

DESCRIPTION

This chapter describes various file formats and protocols, and the used C structures, if any.

AUTHORS

Look at the header of the manual page for the authors and copyright conditions. Note that these can be different from page to page!

Linux, 24 July 1993

active, active.times

active, active.times—List of active Usenet newsgroups.

DESCRIPTION

The file `/news/lib/active` lists the newsgroups that the local site receives. Each newsgroup should be listed only once. Each line specifies one group; their order in the file does not matter. Within each newsgroup, articles are assigned unique names, which are monotonically increasing numbers.

If an article is posted to newsgroups not mentioned in this file, those newsgroups are ignored. If no valid newsgroups are specified, the article is filed into the newsgroup “junk” and only propagated to sites that receive the “junk” newsgroup.

Each line consists of four fields specified by a space:

```
name himark lomark flags
```

The first field is the name of the newsgroup. Newsgroups that start with the three characters `to.` are treated specially; see `innd(8)`. The second field is the highest article number that has been used in that newsgroup. The third field is the lowest article number in the group; this number is not guaranteed to be accurate and should only be taken as a hint. Note that because of article cancellations, there may be gaps in the numbering sequence. If the lowest article number is greater than the highest article number, there are no articles in the newsgroup. To make it possible to update an entry in-place without rewriting the entire file, the second and third fields are padded with leading zeros to make them a fixed width.

The fourth field can contain one of the following flags:

y	Local postings are allowed
n	No local postings are allowed, only remote ones
m	The group is moderated and all postings must be approved
j	Articles in this group are not kept but only passed on
x	Articles cannot be posted to this newsgroup
=foo.bar	Articles are locally filed into the foo.bar group

If a newsgroup has the `j` flag, then no articles will be filed into that newsgroup and local postings to that group should not be generated. If an article for such a newsgroup is received from a remote site, it will be filed into the “junk” newsgroup if it is not cross-posted. This is different from not having a newsgroup listed in the file because sites can subscribe to `j` newsgroups and the article will be propagated to them.

If the fourth field of a newsgroup starts with an equal sign, then the newsgroup is an alias. Articles can be posted to the group but will be treated as if they were posted to the group named after the equal sign. The second and third fields are ignored. Note that the newsgroup header is not modified (Alias groups are typically used during a transition and are typically created with `ctlinnd(8)`). An alias newsgroup should not point to another alias.

The file `/news/lib/active.times` provides a chronological record of when newsgroups are created. This file is normally updated by `inn(8)` whenever a `ctlinnd newgroup` command is done. Each line consist of three fields:

```
name time creator
```

The first field is the name of the newsgroup. The second field is the time it was created, expressed as the number of seconds since the epoch—a `time_t`; see `gettimeofday(2)`. The third field is the electronic mail address of the person who created the group.

HISTORY

Written by Rich Salz (`rsalz@uunet.uu.net`) for InterNetNews.

SEE ALSO

`ctlinnd(8)`, `inn(8)`

adduser.conf

`adduser.conf`—Configuration file for `adduser(8)` and `addgroup(8)`.

SYNOPSIS

`/etc/adduser.conf`

DESCRIPTION

The file `adduser.conf` contains defaults for the programs `adduser(8)` and `addgroup(8)`. Each option takes the form `option = value`.

The valid configuration options are

DSHELL	The login shell to be used for all new users. Defaults to <code>/bin/bash</code> .
DHOME	The directory in which new home directories should be created. Defaults to <code>/home</code> .
SKEL	The directory from which skeletal user configuration files should be copied. Defaults to <code>/etc/skel</code> .
FIRST_UID	Specifies the lowest valid UID for normal users on your system. IDs below <code>FIRST_UID</code> are reserved for administrative and system accounts. Defaults to <code>1000</code> .
USERGROUPS	The <code>USERGROUPS</code> variable can be either <code>yes</code> or <code>no</code> . If <code>yes</code> , each created user will be given their own group to use as a default, and their setup will arrange to have them create files group-writable by default, thus allowing them to effectively use group-writable filespace areas (such as <code>/usr/local</code>). If <code>no</code> , each created user will be placed in the group whose GID is <code>USERS_GID</code> , and they will create files not group-writable by default.
USERS_GID	If <code>USERGROUPS</code> is <code>no</code> , then <code>USERS_GID</code> is the GID given to all newly created users. The default value is <code>100</code> .

FILES

`/etc/adduser.conf`

SEE ALSO

`adduser(8)`

aliases

aliases—Aliases file for sendmail.

SYNOPSIS

aliases

DESCRIPTION

This file describes user ID aliases used by `.` The file resides in `/etc` and is formatted as a series of lines of the form:

```
name: name_1, name_2, name_3, ...
```

The `name` is the name to alias, and the `name_n` are the aliases for that name. Lines beginning with whitespace are continuation lines. Lines beginning with `#` are comments.

Aliasing occurs only on local names. Loops cannot occur because no message will be sent to any person more than once.

After aliasing has been done, local and valid recipients who have a `.forward` file in their home directory have messages forwarded to the list of users defined in that file.

This is only the raw data file; the actual aliasing information is placed into a binary format in the files `/etc/newaliases` and using the program `newaliases(1)`. A `newaliases` command should be executed each time the aliases file is changed for the change to take effect.

SEE ALSO

`newaliases(1)`, `dbm(3)`, `sendmail(8)`, “Sendmail Installation and Operation Guide,” “Sendmail: An Internet Network Mail Router.”

BUGS

Because of restrictions in `dbm(3)`, a single alias cannot contain more than about 1000 bytes of information. You can get longer aliases by “chaining”—that is, making the last name in the alias a dummy name that is a continuation alias.

HISTORY

The aliases file format appeared in BSD 4.0.

BSD 4, 10 May 1991

cfingerd

cfingerd—Configurable finger daemon.

SYNOPSIS

```
cfingerd [-c|-d|-e|-o|-v]
```

<code>-c</code>	Check configuration
<code>-d</code>	Run as daemon, not <code>inetd</code>
<code>-e</code>	Emulate local finger without <code>inetd</code>
<code>-o</code>	Turn off all finger queries
<code>-v</code>	Request version information

`-c` checks your installed configuration. This makes sure there are no existing errors in the current `cfingerd.conf` file.

`-d` runs `cfingerd` as a daemon. Don't run `cfingerd` this way if you're using `inetd`.

`-e` allows you to emulate a local finger on a user that exists on your system. This makes it so that you can test `cfingerd` on your system before installing it. Using the `-e` directive is the same as installing the software, typing `finger username@` and getting the output. Using `-e username` does the same.

- o turns off all finger queries. This makes it so that no one can finger your system—no matter what they try to do.
- v requests cfingerd version information.

DESCRIPTION

cfingerd is a totally new and totally configurable finger daemon—one of the first. It utilizes the finger port (port 79) to provide useful information on each user on your system. However, cfingerd provides a unique twist.

cfingerd was designed for the sole purpose of making output on finger queries configurable. If you want to change any text that is displayed during finger queries, you can configure the finger daemon to display just about anything you want.

cfingerd also takes into account any security breaches and attempts to close them. With .nofinger files, this is displayed instead of finger information, making it possible for users to keep themselves relatively anonymous from outside users.

WHY WAS IT DONE?

The answer is simple: security. Many sites turn off finger for the reason that they don't want outside users to see who's on their system or get information about a specific user on their system. This seemed unfair to the rest of the users out there, so this program was created. Those sites were waiting for this type of program. Many sites that originally had their finger turned off turned them back on because of cfingerd.

Many sites complained that they wanted the capability to create a fake user or a user that doesn't exist but calls a prewritten shell script. cfingerd takes this into account and provides the best method possible for creating such scripts. (See cfingerd.conf(5) for more information on the configuration file.)

FEATURES cfingerd PROVIDES AND DESCRIPTIONS OF EACH

cfingerd was totally rewritten. Why is this? The older version of cfingerd had quite a few bugs, and it didn't quite do all the things that cfingerd now does. This new version was totally revamped, and most of the bugs that were in the older version of cfingerd were removed in this one. The code is also more compact.

Header and footer displays were a big part of the original release of cfingerd and shall continue to remain in all versions. Headers and footers are only displays at the beginning and ending of all finger displays and are used as unique little advertisements.

The last time displayed is always a critical issue. It's covered in cfingerd. cfingerd simply shows how many times this user is connected, what their idle time is on each tty they're connected to, and whether they are accepting messages. If they're not accepting messages, a [MSG-N] display will be shown. This display also shows the last time mail was read and whether this user has mail.

Stand-alone and inetd support is compiled into the program, but only inetd support is given for the time being. The reason is that I have not yet added the option for stand-alone daemon mode.

.nofinger files are used when a user wants to remain anonymous. These files should be placed in their home directories and can display anything they want. There's just a few restrictions. These .nofinger display files cannot be character devices, directories, FIFOs, soft or hard links, or anything else of that caliber. They must only be normal files.

Fake users were supported for the simple fact that many sites want to create users who don't exist and make them execute a shell. If you want this done, install a fake user. Read cfingerd.conf(5) for more information on these useful options.

Service displays were used to show what fake users you have installed on your system. These can be formatted however you want and are explained in cfingerd.conf(5).

Searching for usernames is a powerful feature that cfingerd takes full advantage of. If you are looking for a specific username on the system or don't know what their name is, simply use the search.username directive with cfingerd, and you can search for a user on your system.

Searching for usernames is not case sensitive. If you are searching for a specific username or part of the user's name, chances are that it'll be displayed.

There's also an option to display your public PGP key if you have one. This is very useful if you want to keep your mail or other information secret to yourself and don't want "big brother" watching over your shoulder as you talk among yourselves. (Thanks to Andy Smith for this patch.) The standard plan file is `.plan`, project is `.project`, and PGP info is `.pgpkey`.

Remember, any or all of these options stated can be turned on or off at will. If you want a specific option turned off, turn it off.

ERROR MESSAGES

Any error messages that result are fairly easy to debug if you know what to look for.

Segmentation violations don't always occur, but if they ever do, you can pretty easily figure out what's going on. Unfortunately, `cfingerd` doesn't have any compatibility with older `cfingerd.conf` files, so if you get a segmentation violation, this means (usually) that your `cfingerd.conf` file needs to be replaced.

Time-outs usually mean that a script has timed out or a connection to another site timed out.

SYSLOGGING MESSAGES

There's no real way to describe SYSLOG messages because they can be changed as the system administrator chooses. Although, examples can be given based on the standard configuration that was distributed.

If any IP addresses cannot be matched to a hostname, SYSLOG will display `IP: Hostname not matched`.

If the `renice` fails (to make the program run at the highest priority), then SYSLOG will display `Fatal - Nice died: (reason)`.

If there is no buffer information is waiting in the `STDIN` buffer, SYSLOG will display `STDIN contains no data`.

If a trusted host fingers your site, a `<- Trusted` will appear.

If a rejected host fingers your site, a `<- Rejected` will appear.

If root is fingered on your site, it will display `Root`.

If a service listing was fingered on your site, SYSLOG will display `Service listing`.

If a user listing was requested, SYSLOG will display `User listing`.

If a fake user was requested, SYSLOG will display `Fake user`.

If whois data was requested, SYSLOG will display `Whois request`. (Note that whois was not implemented in this release because it wasn't RFC compliant.)

Any extra information pertaining to the incoming finger is displayed in the syslogging area. (It's also recommended that you reconfigure `syslog.conf(5)` to display to an unused VT.)

BUGS

When data is forwarded to other sites for fingering, it shows the output of the system that it forwarded the finger request to. This has got to change.

On ELF-specific systems, services lists usually show a bit of garbage at the beginning of the finger display. This doesn't appear to be a problem on `a.out` systems, so if you have ELF, you might want to compile `cfingerd` as `a.out` if this becomes a problem.

PLANS

Any other options or improvements will probably come from user suggestions.

Later plans will mean you can define your own display formats for the finger display. This means that you can redefine how you want your finger display to look.

CONTACTING

If you like the software and you want to learn more about it or want to see a feature added to it that isn't already here, write to khollis@bitgate.com.

I've received calls at work pertaining to the software, and although I appreciate the fact that people like the software I wrote, I'd appreciate it if you leave me e-mail and be considerate.

cfingerd is now being maintained by Michael Jarvis. Any additions after cfingerd 1.2.3 should be directed toward Michael. You can reach him at mjarvis@qns.com.

If you want to see other projects that Bitgate Software is currently developing, check out the Web page at <http://www.bitgate.com/>. This will contain all the update information on the software that is being developed and that is already released.

SEE ALSO

cfingerd.conf(5), finger(1), userlist(1), syslog.conf(5)

cfingerd 1.2.3, 24 May 1996

cfingerd.conf

cfingerd.conf—Configurable finger daemon configuration file.

SYNOPSIS

/etc/cfingerd.conf

DESCRIPTION

cfingerd.conf is the configuration file for cfingerd. This has been totally rewritten to support a more readable configuration file. This version of the new configuration file is not compatible with the older versions from 1.0.3 or earlier.

Each line in the configuration file is split into three sections: FILES, CONFIG, and HOSTS. Each one of those sections is split into subsections.

Subtext of each option is either Boolean options, string options, or switchable options, all changeable by the system administrator.

Each section is split into a series of sections that resembles C-type definition; it's not exact but close enough to be familiar. There's only one exception: These are not case sensitive. Any casing will do as long as the option is legal.

Thus, each option is formatted like this:

```
OPTION sub_option_name = {
(tab/space) string_option = "string format",
(tab/space) boolean_option = [BOOL, BOOL],
(tab/space) +/-internal_config_option
(tab/space) host.name.here
}
```

This shows that string options are strings put into quotes, Boolean options are given as TRUE and FALSE, switchable options are given with the + or - directive, and hostnames are used as substrings so that wildcards are not necessary.

You can add comments using the hash mark (#) at the beginning of the line. Please note that no comments are allowed inside of an OPTION.

DISPLAY FILES SECTION (FILES display files)

Each option here is a string option. These are formatted as the example shows.

PLAN is the plan file that is used when displaying a plan. The standard here is .plan.

PROJECT is the project file that is used when displaying a project description. The standard here is .project.

PGP_KEY is the Pretty-Good-Privacy file that is shown when displaying a public or private key. The standard here is .pgpkey.

(The preceding three files must be world readable but should not be world writable. This makes sure that `cfingerd` can read the file once it becomes the “nobody” UID/GID. This is generally a good idea for protection.)

`NO_FINGER` is the file that is shown when a user wants to remain anonymous. This is usually the case with root users (which should be standard anyway). The standard here is `.nofinger`. This file can only be a standard displayable file.

`LOGFILE` is the file that is used to keep logs of everything that happens to both your system and the finger program. These logs are kept as backups for your finger file and can be used to guard against attacks against your system if a finger attack occurs. Remember, the `cfingerd.conf` file is root owned, so this file should be kept in a safe, hidden place.

`HEADER_DISPLAY` is the file that is displayed at the top of each finger display. The standard here is `/etc/cfingerd/top_finger.txt`.

`FOOTER_DISPLAY` is the file that is displayed at the end of each finger display. The standard here is `/etc/cfingerd/bottom_finger.txt`.

`NO_USER_BANNER` is the file that is displayed if the user doesn’t exist. The standard here is `/etc/cfingerd/nouser_banner.txt`.

`NO_NAME_BANNER` is the file that is displayed if no name was specified in a finger display. This is used in conjunction with the `SYSTEM_LIST` option (explained later). The standard here is `/etc/cfingerd/noname_banner.txt`.

`REJECTED_BANNER` is the file that is displayed if a rejected host tries to finger your system for any reason. The standard here is `/etc/cfingerd/rejected_banner.txt`.

FINGER DISPLAY CONFIGURE SECTION (CONFIG finger display)

Each option in this section is Boolean. The way this works is as follows: The first Boolean option is the setting for a remote host or a host that fingers you from the outside. The second Boolean option is the setting for the local host or trusted host. This is what people from your own system will see.

Each option has a `-` or `+` option. This is for user-overridable options, which will be in the next release of `cfingerd`. These will allow users to manipulate if this information is displayed when that specific user is fingered.

`HEADER_FILE` displays the header file at the beginning of each finger query.

`FOOTER_FILE` displays the footer file at the end of each finger query.

`LOGIN_ID` displays the login ID of that particular user.

`REAL_NAME` displays the real name of that particular user.

`DIRECTORY` displays the user’s directory.

`SHELL` displays the user’s shell.

`ROOM_NUMBER` displays the user’s room number.

`WORK_NUMBER` displays the user’s work phone number.

`HOME_NUMBER` displays the user’s home phone number.

`OTHER` displays the user’s other information.

`LAST_TIME_ON` displays the last time the user logged into the fingered system.

`IF_ONLINE` displays whether the user is currently logged into the fingered system.

`TIME_MAIL_READ` displays the last time that the fingered user read mail.

`DAY_MAIL_READ` displays the last day that the fingered user read his or her mail.

`ORIGINATION` displays the site from which the user logged in (if applicable).

`PLAN` displays the user’s plan file.

`PROJECT` displays the user’s project file.

`PGP` displays the user’s Pretty–Good–Privacy key file.

NO_NAME_BANNER displays the banner if no username was given.

REJECTED_BANNER displays the rejected banner if the site fingering your system was in the banned-site listing.

SYSTEM_LIST displays the system list if one was requested.

NO_NAME displays the no-name display file if no user was selected.

INTERNAL CONFIG CONFIGURE SECTION (CONFIG internal config)

Each item in this section is a switchable option. This means that a + before the item is turned on and a - before the item is turned off.

ALLOW_MULTIPLE_FINGER_DISPLAY allows you to give a sorted output of all users on more than one specific system. This is useful when you have more than one ISP machine, located in different cities or even states.

ALLOW_SEARCHABLE_FINGER allows you to let others outside your system (or within it) to search for a specific username by using the search.username directive.

ALLOW_NO_IP_MATCH_FINGER allows you to let sites finger your system if a hostname could not be matched to their IP address successfully.

ALLOW_USER_OVERRIDE will allow your users to override specific options in the FINGER_DISPLAY section that you enable.

ALLOW_USERLIST_ONLY will allow other sites that are fingering your system for a specific compiled user list to finger your system and get a user listing of who's online. This could be a security risk, so you might want to turn this option off if you feel it's a security risk.

ALLOW_FINGER_FORWARDING will allow other sites to forward finger requests to a different machine if the user could not be located on the current machine. (In order to use this option, you must have the HOSTS finger forward option set and have other sites in there.)

ALLOW_STRICT_FORMATTING makes the finger display remove all returns between display options. This makes the finger display look horrible (as with GNU Finger or the other generic fingers) and makes your system look, well, "generic."

ALLOW_VERBOSE_TIMESTAMPING makes the timestamp that is displayed (at any place) very verbose. For instance, where it used to say

On since Sat Aug 12 03:43PM(PDT)

would now be shown as

On since Sat Aug 12, 1995 03:43PM(PDT)

(Basically, ALLOW_VERBOSE_TIMESTAMPING just takes up more room on the display field.)

ALLOW_NONIDENT_ACCESS lets you only allow connections from sites that run the ident daemon (or RFC 1413-compliant program.) This is for security sake and is a good measure against unknown users trying to finger your system. If this option is enabled, users who do not have identd running on their system (such as Windows users) will be able to finger your system. Systems not running identd will return unknown as the user ID and will not be permitted to finger a user on your system.

ALLOW_FINGER_LOGGING enables cfingerd to use the LOGFILE file to store any logs of activity that happen to your system via finger.

ALLOW_LINE_PARSING makes cfingerd parse each line of every display file (including the plan, project, and ppg files) for any cfingerd-specific \$ commands. If any are found, cfingerd will parse these commands and display correct information accordingly. Otherwise, if this is turned off, the display will appear without parsed commands.

ALLOW_EXECUTION will allow users to execute scripts in place of their .plan, .project, and .ppg files. This is used to display the standard output of another program directly to the screen of the user. Keep in mind that this is a huge security risk if you choose to use it. It's normally suggested that this option remain off, but you can turn it on if necessary. Nevertheless, these programs are called as nobody.nogroup.

`ALLOW_FAKEUSER_FINGER` turns on or off the fake user option in `cfingerd`. If you want fake users to be defined and available to be fingered, you will want to enable this option. This can be a security risk in some instances if you allow for searchable fingers and your script calls an execute routine on that variable. Chances are that'll never happen.

`ALLOW_USERLOG` will allow users to keep track of who has fingered them and at what time. A little file called `.fingerlog` will appear in their directory, which they can examine to see who has fingered them. If you don't care about this, you can disable it. Otherwise, it's not a bad idea. (It also logs root fingers as well.)

SYSTEM LIST SITES CONFIGURE SECTION (`CONFIG system list sites`)

This is just a series of hostnames that you want to finger when displaying your user-list display. If you have more than one system that you want to show, simply put their hostname in this list, separated on a line by itself.

For example, if I have a separate ISP system that I'm running on the side, say `chatlink.com`, I would change my configuration to say

```
CONFIG system_list_sites = { chatlink.com, localhost }
```

Remember, if you are listing only a couple of sites, list the sites you will want to have listed (in order) first. The ending entry must be `localhost` or the finger listing will not include your site. If you include `localhost` anywhere else in the list, it will stop once it has reached the `localhost` entry, so remember to list it last!

I want to get a user listing from my own machine and from `chatlink.com`'s system. This would be automatically formatted nicely (sorted and parsed) and would display on the screen in sorted order. This program is usually used in tandem with the supplied `userlist(1)` program.

If no system list sites are specified, multiple system sites will not be specified.

TRUSTED HOST SECTION (`HOSTS trusted`)

This is a listing of the sites that you allow to finger your system exclusively, giving them the same access that your local users would get. In other words, they are treated as `localhost` users.

Each site that you list in this section should be separated by using the `,` directive. You can include up to 80 sites in this listing.

Wildcards are supported in this section, and you can use them in the regex format as well. Any wildcards with `*`, `?`, or any other regex wildcard matching character will work. IP addresses will also work. Hostnames are compared case insensitive.

REJECTED HOST SECTION (`HOSTS rejected`)

This is a listing of the sites that you do not allow to finger your system. These sites don't get to finger anyone (or anything for that matter) on your system, regardless of what they try to do. In essence, finger is cut off to that particular system.

Each site that you list in this section should be separated by using the `,` directive. You can include up to 80 sites in this listing.

Wildcards are supported in this section, and you can use them in the regex format as well. Any wildcards with `*`, `?`, or any other regex wildcard matching character will work. IP addresses will also work. Hostnames are compared case insensitive.

FORWARDED HOST SECTION (`HOSTS finger forward`)

This is a listing of sites that are used to forward a finger query to when a finger request was processed but that particular user was not found on the associated system. It will step through this listing, and it will search for the user in question. If the user could not be found, then it will step through to the next host and the next, until it finds one.

Each site that you list in this section should be separated by using the `,` directive. You can include up to 80 sites in this listing.

Wildcards are supported in this section, and you can use them in the regex format as well. Any wildcards with `*`, `?`, or any other regex wildcard matching character will work. Hostnames are compared case insensitive.

If you do not specify any forwarding sites in this section, finger forwarding will be disabled for your system.

FINGER STRINGS CONFIGURE SECTION (CONFIG finger strings)

Each option in this section is a string that can be changed to fit your needs when displaying finger information. These strings are limited to about 20 characters on the display. (If you use more than 20, the finger display will end up looking strange.)

USER_NAME is the string that is displayed when the user's username is shown.

REAL_NAME is the string that is displayed when the user's real name is shown.

DIRECTORY is the string that is displayed when the user's directory is shown.

SHELL is the string that is displayed when the user's shell is shown.

ROOM_NUMBER is the string that is displayed when the user's room number is shown.

WORK_NUMBER is the string that is displayed when the user's work phone number is shown.

HOME_NUMBER is the string that is displayed when the user's home phone number is shown.

OTHER is the string that is displayed when the user's other display information is shown.

PLAN is the string that is displayed when the user's plan is shown.

PROJECT is the string that is displayed when the user's project is shown.

PGPKEY is the string that is displayed when the user's PGP key is shown.

NO_PLAN is the string that is displayed when the user doesn't have a plan file to show you.

NO_PROJECT is the string that is displayed when the user doesn't have a project file to show you.

NO_PGP is the string that is displayed when the user doesn't have a PGP key file to show you.

WAIT is the string that is shown when the system gathers information from other sites for a user listing.

INTERNAL STRINGS CONFIGURE SECTION (CONFIG internal strings)

These strings are changeable and can be any length you want (within reason). These strings are concatenated into the syslogging display when the appropriate finger has been issued. This section also includes error messages that may occur.

NO_IP_HOST is shown when there is no hostname that matches the incoming IP address. This usually indicates that either the site didn't register its IP address with the InterNIC or it is coming from a hacked site.

RENICE_FATAL is shown when the system failed to change the execution priority on the current process of cfingerd.

STDIN_EMPTY is shown when the input buffer on the cfingerd port is empty. (This should never really happen; it's here for sanity.)

TRUSTED_HOST is shown when a trusted host fingers your system. If you do not specify a trusted host, cfingerd will insert localhost into this field.

REJECTED_HOST is shown when a rejected host fingers your system. If you do not specify a rejected host, cfingerd will insert 0.0.0.0 into this field.

ROOT_FINGER is shown when a user fingers root.

SERVICE_FINGER is shown when a user requests fake user services from your system.

USER_LIST is shown when a user requests a user listing from your system.

FAKE_USER is shown when a user fingers a fake user from your system.

WHOIS_USER is shown when a user fingers a user with a WHOIS query. (This option is not yet available.)

FINGER_DENY is shown when a user tries to finger with a forward request such as user@host1@host2. This is not supported because it could result in finger loops and a lot of traffic.

SIGNAL STRINGS CONFIGURE SECTION (CONFIG signal strings)

This section is used in changing the output that is given when a system crashes, or a signal is caught, and reported to the finger output.

The supported caught signals are as follows:

SIGHUP, SIGINT, SIGQUIT, SIGILL, SIGTRAP, SIGABRT, SIGFPE, SIGUSR1, SIGSEGV, SIGUSR2, SIGPIPE, SIGALRM, SIGTERM, SIGCONT, SIGTSTP, SIGTTIN, SIGTTOU, SIGIO, SIGXCPU, SIGXFSZ, SIGVTALRM, SIGPROF, SIGWINCH

FINGER PROGRAMS FILES SECTION (FILES finger programs)

These are the programs that are called when a specific action is take on the finger display.

FINGER is the file that is used when a user listing is requested from your machine. This is used in the standard user list and in the sorted user list, so it is wise to use the standard here: `/usr/sbin/userlist`.

WHOIS is the program that is used when a WHOIS request is done on a specific user.

FINGER FAKE USERS FILES SECTION (FILES finger fakeusers)

These are the ever-popular fake users that you can create on your system. These users are ones that don't exist (and should not exist, for that matter). These are, instead, treated as normal scripts that can be called for your use.

The format is as follows for fake users:

```
fake_username Script_name SEARCHBOOL script
```

`fake_username` is the name of the fake user you want to request. Make sure that this is a user that does not exist on your system. Keep in mind that if you create a fake username and that user already exists, the fake username will be shown.

`Script_name` is the standard name of your script. This is used in the display of your services listing.

`SEARCHBOOL` specifies whether parameters can be sent to that specific fake user. If you decide to use the `SEARCHBOOL` option (TRUE in this case), the passed variables are

```
$1          First passed option
$2          Second passed option
$3          Third passed option
$4          Fourth passed option
```

(If more than four options were passed to this, the request will be ignored, and an error message will be returned to the user who requested the finger request.)

`script` is the location of your script. It should be `chmod 700` and readable only by root.

If you do not specify any fake users, a fake user called `None` will be created. This is a fake user that does nothing and calls `/dev/null` for the script.

SERVICES HEADER CONFIGURE SECTION (CONFIG services header)

This is the display that is given during a services finger. It should be formatted the same way that you want it to display on the screen.

When specifying the finger formatted options, you should specify them as C formatted strings as well, with the standard options. This should always be given last in the display.

An example of this is

```
Welcome to this system's services!
User: Service name: Searchable:
-----
%-8s %-20s %-s
```

Remember to keep the format string last or a `SIGSEGV` will result.

SERVICES POSITIONS CONFIGURE SECTION (CONFIG services positions)

This specifies where in the preceding display string that the information from a service listing is to appear. These numbers can be anywhere between 1 and 3.

USER specifies the position of the username listing.

SERVICE specifies the position of the service full-name listing.

SEARCH specifies the position of the Boolean search display.

CONTACTING

If you like this program and have questions or comments about the program's functionality or what-have-you, write to khollis@bitgate.com.

As always, I appreciate any suggestions or bug reports you might have, so bring them on!

SEE ALSO

`cfingerd(8)`, `cfingerd.text(5)`, `userlist(1)`, `finger(1)`, `regex(3)`, `regex(3)`

16 May 1996

cfingerd text rules

EXPLANATION

`cfingerd` offers different commands that can be placed in text files to display corresponding information. Each command used with `cfingerd` in text files begins with a dollar sign (\$). This usually indicates to `cfingerd` that when it's displaying a file, it parses the command directly after that character.

If you want to display a raw \$ sign, simply put two \$ signs together, or \$\$.

TEXT COMMANDS

The following is a list of text commands and what they do. Each of the text commands can be in any text case; it doesn't matter.

<code>\$CENTER</code>	Displays the entire contents of the line. This command must start at the beginning of the line. This is a very common command.
<code>\$DATE</code>	Displays the current system date in the format of MM/DD/YY.
<code>\$TIME</code>	Displays the current system time in the format HH:MM A/PM (time zone).
<code>\$IDENT</code>	Displays the identity of the current person fingering your system.
<code>\$COMPILE_DATETIME</code>	Displays the date and time of which the current issue of <code>cfingerd</code> was compiled on your system.
<code>\$VERSION</code>	Displays the current version of <code>cfingerd</code> .
<code>\$EXEC</code>	Executes a file with <code>x</code> parameters after it. The <code>\$EXEC</code> command must be on a line by itself in order to function properly. The command is executed as <code>nobody.nogroup</code> .

SEE ALSO

`cfingerd(8)`, `cfingerd.conf(5)`, `finger(1)`, `userlist(1)`, any of the included docs with the standard `cfingerd` distribution.

cfingerd 1.2.1, 6 Jan 1996

control.ctl

`control.ctl`—Specify handling of Usenet control messages.

DESCRIPTION

The file `/news/lib/control.ct1` is used to determine what action is taken when a control message is received. It is read by the `parsecontrol` script, which is called by all the control scripts. (For an explanation of how the control scripts are invoked, see `innd(8)`.)

The file consists of a series of lines; blank lines and lines beginning with a number sign (`#`) are ignored. All other lines consist of four fields separated by a colon:

```
message:from:newsgroups:action
```

The first field is the name of the message for which this line is valid. It should be either the name of the control message, or the word `all` to mean that it is valid for all messages.

The second field is a shell-style pattern that matches the e-mail address of the person posting the message. (The poster's address is first converted to lowercase.) The matching is done using the shell's case statement; see `sh(1)` for details.

If the control message is `newgroup` or `rmgroup`, then the third field specifies the shell-style pattern that must match the group being created or removed. If the control message is of a different type, then this field is ignored.

The fourth field specifies what action to take if this line is selected for the message. The following actions are understood:

<code>doit</code>	The action requested by the control message should be performed. In most cases, the control script will also send mail to Usenet.
<code>doifarg</code>	If the control message has an argument, this is treated as a <code>doit</code> action. If no argument was given, it is treated as a <code>mail</code> entry. This is used in a <code>sendsys</code> entries script so that a site can request its own <code>newsfeeds(5)</code> entry by posting a <code>sendsys</code> <code>mysite</code> article. On the other hand, <code>sendsys</code> <code>bombs</code> ask that the <code>newsfeeds</code> file be sent; if you use <code>doifarg</code> , such messages will not be processed automatically.
<code>doit=file</code>	The action is performed, but a log entry is written to the specified log file, <code>file</code> . If <code>file</code> is the word <code>mail</code> , then the record is mailed. A null string is equivalent to <code>/dev/null</code> . A pathname that starts with a slash is taken as the absolute filename to use as the log. All other pathnames are written to <code>/var/log/news/file.log</code> . The log is written by <code>writelog</code> (see <code>newslog(8)</code>).
<code>drop</code>	No action is taken; the message is ignored.
<code>log</code>	A one-line log notice is sent to standard error. <code>innd</code> normally directs this to the file <code>/var/log/news/errlog</code> .
<code>log=file</code>	A log entry is written to the specified log file, <code>file</code> , which is interpreted as described previously.
<code>mail</code>	A mail message is sent to the news administrator.

Lines are matched in order; the last match found in the file is the one that is used. For example, with the following three lines:

```
newgroup:*:~:drop
newgroup:tale@*.uu.net:comp.*|misc.*|news.*|rec.*|sci.*|soc.*|talk.*:doit
newgroup:kre@munnari.oz.au:aus.*:mail
```

A `newgroup` coming from `tale` at a UUNET machine will be honored if it is in the mainstream Usenet hierarchy. If `kre` posts a `newgroup` message creating `aus.foo`, then `mail` will be sent. All other `newgroup` messages are ignored.

HISTORY

Written by Rich Salz (`rsalz@uunet.uu.net`) for InterNetNews.

SEE ALSO

`innd(8)`, `newsfeeds(5)`, `scanlogs(8)`

CVS

cvs—Concurrent Versions System support files.

SYNOPSIS

```
$CVSROOT/CVSROOT/commitinfo,v
$CVSROOT/CVSROOT/cvsignore,v
$CVSROOT/CVSROOT/cvswrappers,v
$CVSROOT/CVSROOT/editinfo,v
$CVSROOT/CVSROOT/history
$CVSROOT/CVSROOT/logininfo,v
$CVSROOT/CVSROOT/modules,v
$CVSROOT/CVSROOT/rcsinfo,v
$CVSROOT/CVSROOT/taginfo,v
```

DESCRIPTION

cvs is a system for providing source control to hierarchical collections of source directories. Commands and procedures for using cvs are described in cvs(1). cvs manages source repositories, the directories containing master copies of the revision-controlled files, by copying particular revisions of the files to (and modifications back from) developers' private working directories. In terms of file structure, each individual source repository is an immediate subdirectory of \$CVSROOT. The files described here are supporting files; they do not have to exist for cvs to operate, but they allow you to make cvs operation more flexible.

You can use the `modules` file to define symbolic names for collections of source maintained with cvs. If there is no `modules` file, developers must specify complete pathnames (absolute or relative to \$CVSROOT) for the files they want to manage with cvs commands. You can use the `commitinfo` file to define programs to execute whenever `cvs commit` is about to execute. These programs are used for "precommit" checking to verify that the modified, added, and removed files are really ready to be committed. Some uses for this check might be to turn off a portion (or all) of the source repository from a particular person or group or perhaps to verify that the changed files conform to the site's standards for coding practice.

You can use the `cvswrappers` file to record cvs wrapper commands to be used when checking files into and out of the repository. Wrappers allow the file or directory to be processed on the way in and out of cvs. The intended uses are many; one possible use is to reformat a C file before the file is checked in so all the code in the repository looks the same. You can use the `logininfo` file to define programs to execute after any commit, which writes a log entry for changes in the repository. These logging programs might be used to append the log message to a file or send the log message through electronic mail to a group of developers. You can also post the log message to a particular newsgroup.

You can use the `taginfo` file to define programs to execute after any `tag` or `rtag` operation. These programs might be used to append a message to a file listing the new tag name and the programmer who created it, to send mail to a group of developers, or to post a message to a particular newsgroup. You can use the `rcsinfo` file to define forms for log messages. You can use the `editinfo` file to define a program to execute for editing or validating cvs `commit` log entries. This is most useful when used with a `rcsinfo` forms specification because it can verify that the proper fields of the form were filled in by the user committing the change. You can use the `cvsignore` file to specify the default list of files to ignore during update. You can use the `history` file to record the cvs commands that affect the repository. The creation of this file enables history logging.

FILES

`modules`

The `modules` file records your definitions of names for collections of source code. cvs will use these definitions if you use cvs to check in a file with the right format to \$CVSROOT/CVSROOT/modules,v. The `modules` file can contain blank lines and comments (lines beginning with #) as well as module definitions. Long lines can be continued on the next line by specifying a backslash (\) as the last character on the line. A module definition is a single line of the `modules` file in either of two formats. In both cases, `mname` represents the symbolic module name, and the remainder of the line is its definition.

```
mname -a aliases ...
```

This represents the simplest way of defining a module `mname`. The `-a` flags the definition as a simple alias: cvs will treat any use of `mname` (as a command argument) as if the list of names `aliases` had been specified instead. `aliases` may

contain either other module names or paths. When you use paths in `aliases`, `cvs checkout` creates all intermediate directories in the working directory, just as if the path had been specified explicitly in the `cvs` arguments.

```
mname [ options ] dir [ files ... ] [&module ...]
```

In the simplest case, this form of module definition reduces to `mname dir`. This defines all the files in directory `dir` as module `mname`. `dir` is a relative path (from `$CVSR00T`) to a directory of source in one of the source repositories. In this case, on checkout, a single directory called `mname` is created as a working directory; no intermediate directory levels are used by default, even if `dir` was a path involving several directory levels. By explicitly specifying files in the module definition after `dir`, you can select particular files from directory `dir`. The sample definition for modules is an example of a module defined with a single file from a particular directory. Here is another example:

```
m4test unsupported/gnu/m4 foreach.m4 forloop.m4
```

With this definition, executing `cvs checkout m4test` will create a single working directory `m4test` containing the two files listed, which both come from a common directory several levels deep in the `cvs` source repository. A module definition can refer to other modules by including `&module` in its definition. The `checkout` command creates a subdirectory for each such module in your working directory. New in `cvs` 1.3; avoid this feature if sharing module definitions with older versions of `cvs`.

Finally, you can use one or more of the following options in module definitions:

- `-d name` names the working directory something other than the module name. This option is new in `cvs` 1.3; avoid this feature if sharing module definitions with older versions of `cvs`.
- `-i prog` allows you to specify a program `prog` to run whenever files in a module are committed. `prog` runs with a single argument, the full pathname of the affected directory in a source repository. The `commitinfo`, `loginfo`, and `editinfo` files provide other ways to call a program on `commit`.
- `-o prog` allows you to specify a program `prog` to run whenever files in a module are checked out. `prog` runs with a single argument, the module name.
- `-e prog` allows you to specify a program `prog` to run whenever files in a module are exported. `prog` runs with a single argument, the module name.
- `-t prog` allows you to specify a program `prog` to run whenever files in a module are tagged. `prog` runs with two arguments: the module name and the symbolic tag specified to `rtag`.
- `-u prog` allows you to specify a program `prog` to run whenever `cvs update` is executed from the top-level directory of the checked-out module. `prog` runs with a single argument, the full path to the source repository for this module.

`commitinfo`, `loginfo`, `rcsinfo`, `editinfo`

These files all specify programs to call at different points in the `cvs` `commit` process. They have a common structure. Each line is a pair of fields: a regular expression, separated by whitespace from a filename or command-line template. Whenever one of the regular expression matches a directory name in the repository, the rest of the line is used. If the line begins with a `#` character, the entire line is considered a comment and is ignored. Whitespace between the fields is also ignored. For `loginfo`, the rest of the line is a command-line template to execute. The templates can include not only a program name, but also whatever list of arguments you want. If you write `%s` somewhere on the argument list, `cvs` supplies, at that point, the list of files affected by the `commit`. The first entry in the list is the relative path within the source repository where the change is being made. The remaining arguments list the files that are being modified, added, or removed by this `commit` invocation. For `taginfo`, the rest of the line is a command-line template to execute. The arguments passed to the command are,

in order, the tagname, operation (add for tag, mov for tag -F, and del for tag -d), and repository, and any remaining are pairs of filename revision. A nonzero exit of the filter program will cause the tag to be aborted. For `commitinfo`, the rest of the line is a command-line template to execute. The template can include not only a program name but also whatever list of arguments you want. The full path to the current source repository is appended to the template, followed by the filenames of any files involved in the commit (added, removed, and modified files). For `rcsinfo`, the rest of the line is the full path to a file that should be loaded into the log message template. For `editinfo`, the rest of the line is a command-line template to execute. The template can include not only a program name but also whatever list of arguments you want. The full path to the current log message template file is appended to the template. You can use one of two special strings instead of a regular expression: `ALL` specifies a command-line template that must always be executed, and `DEFAULT` specifies a command-line template to use if no regular expression is a match. The `commitinfo` file contains commands to execute before any other commit activity, to allow you to check any conditions that must be satisfied before commit can proceed. The rest of the commit will execute only if all selected commands from this file exit with exit status 0. The `rcsinfo` file allows you to specify log templates for the commit logging session; you can use this to provide a form to edit when filling out the commit log. The field after the regular expression, in this file, contains filenames (of files containing the logging forms) rather than command templates. The `editinfo` file allows you to execute a script before the commit starts but after the log information is recorded. These “edit” scripts can verify information recorded in the log file. If the edit script exits with a nonzero exit status, the commit is aborted. The `loginfo` file contains commands to execute at the end of a commit. The text specified as a commit log message is piped through the command; typical uses include sending mail, filing an article in a newsgroup, or appending to a central file.

`cvsignore`, `.cvsignore`

The default list of files (or `sh(1)` filename patterns) to ignore during `cvs update`. At startup time, `cvs` loads the compiled default list of filename patterns (see `cvs(1)`). Then the per-repository list included in `$CVSROOT/CVSROOT/cvsignore` is loaded, if it exists.

Then the per-user list is loaded from `$HOME/.cvsignore`. Finally, as `cvs` traverses through your directories, it will load any per-directory `.cvsignore` files whenever it finds one. These per-directory files are only valid for exactly the directory that contains them, not for any subdirectories.

`history`

Create this file in `$CVSROOT/CVSROOT` to enable history logging (see the description of `cvs history`).

SEE ALSO

`cvs(1)`

COPYING

Copyright © 1992, Cygnus Support, Brian Berliner, and Jeff Polk.

Permission is granted to make and distribute verbatim copies of this manual, provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the preceding conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

12 February 1992

DEVINFO

DEVINFO—Device entry database.

DESCRIPTION

DEVINFO is a text file that describes all the possible devices for a system. It is used by MAKEDEV(8) to create special file entries in `/dev`. It may be named either `/dev/DEVINFO` or `/etc/devinfo`. Information about custom local devices, if any, should be placed in `DEVINFO.local` or `/etc/devinfo.local`, which has the same syntax.

The file format is free-form. C, C++, and shell comments are understood. There are basically four statements:

<code>ignore { proc-device... }</code>	This causes the specified names to be ignored if found in <code>/proc/devices</code> .
<code>batch { device... }</code>	This creates a “batch”—a collection of devices that will all be created when the batch is invoked. For example, in the standard DEVINFO, “generic” is a batch.
<code>block device-spec</code>	This defines one or more block devices.
<code>char device-spec</code>	This defines one or more character devices.

Here is a sample device-spec:

```
(std, 1) {
mem (kmem) : 1
null (public) : 3
core -> "/proc/kcore"
}
```

This example defines a group of devices called `std`, with major number 1. Running will create all the devices in the group; running, for example, would make just the one device `null`.

It is possible to specify, instead of just `std`, something like `std=foo`. In this case, the stuff on the right-hand side of the equals sign specifies a name from `/proc/devices`, and the major number will be retrieved from there if present. If an entry from `/proc/devices` is specified, the explicit major number may be omitted. In this case, if the number is not found in `/proc/devices`, attempts to create the device will be rejected.

Inside the braces is a list of specific devices. The name in parenthesis is the “class”; this is something specified in `MAKEDEV.cfg` that determines the ownership and permissions of the special file created. In the preceding example, the device `mem` was set to have the class `kmem`, but `null` was set to be `public`. Ordinarily, you’d define `public` to be mode 666 but `kmem` to be mode 660 and owned by group `kmem`. The number after the colon is the minor number for this particular device; for instance, 3 for `null`.

You may also specify a symbolic link with `->`. For instance, `core` was made a link to `/proc/kcore`. Note that names may contain any characters, but names that contain things other than alphanumerics, dash, and underscore should be put in double quotes.

An entire range of devices can be created. You may specify a range of numbers in brackets:

```
tty[1-8] (tty) : 1
```

This creates `tty1–tty8` with minor device numbers starting with 1. If you specify the range in hex (prefixed by `0x`), the device names will be created numbered in hex, as is normal for `ptys`. The range may appear inside the name string, but there may only be one range.

There is a special syntax for creating the entire banks of devices for a hard drive:

```
hd[a-d] 8/64
```

What this means is as follows: Create `hda`, and eight partitions on `hda` (`hda1` through `hda8`), starting with minor number 0. Then create `hdb`, and eight partitions, starting with minor number 64. Then `hdc`, and so on, with minor number $64 \times 2 = 128$ —and so forth. These are automatically placed in the class `disk`. The necessary groups and batches are created so you can ask `MAKEDEV` to create `hd` or `hda` or `hda1` and expect it to do the correct thing.

Note that simple arithmetic is permitted for specifying the minor device number, as this often makes things much clearer and less likely to be accidentally broken.

SEE ALSO

`MAKEDEV(8)`, `MAKEDEV.cfg(5)`

Version 1.4, January 1995

environ

`environ`—User environment.

SYNOPSIS

```
extern char **environ;
```

DESCRIPTION

An array of strings called the `environment` is made available by `exec(2)` when a process begins. By convention, these strings have the form `name=value`. Common examples are

<code>USER</code>	The name of the logged-in user (used by some BSD-derived programs).
<code>LOGNAME</code>	The name of the logged-in user (used by some System-V derived programs).
<code>HOME</code>	A user's login directory, set by <code>login(1)</code> from the password file <code>passwd(5)</code> .
<code>LANG</code>	The name of a locale to use for locale categories when not overridden by <code>LC_ALL</code> or more specific environment variables.
<code>PATH</code>	The sequence of directory prefixes that <code>sh(1)</code> and many other programs apply in searching for a file known by an incomplete pathname. The prefixes are separated by <code>..</code>
<code>SHELL</code>	The filename of the user's login shell.
<code>TERM</code>	The terminal type for which output is to be prepared.

Further names maybe placed in the environment by the `export` command and `name=value` in `sh(1)` or by the `setenv` command if you use `csh(1)`. Arguments may also be placed in the environment at the point of an `exec(2)`.

It is risky practice to set `name=value` pairs that conflict with well-known shell variables. Setting these could cause surprising behavior in subshells or `system(3)` commands.

SEE ALSO

`login(1)`, `sh(1)`, `bash(1)`, `csh(1)`, `tcsh(1)`, `exec(2)`, `system(3)`

Linux, 21 October 1996

expire.ctl

`expire.ctl`—Control file for Usenet article expiration.

DESCRIPTION

The file `/news/lib/expire.ct1` is the default control file for the `expire(8)` program, which reads it at startup. Blank lines and lines beginning with a number sign (`#`) are ignored. All other lines should be in one of two formats.

The first format specifies how long to keep a record of fully expired articles. This is useful when a newsfeed intermittently offers older news that is not kept around very long. (The case of very old news is handled by the `-c` flag of `innd(8)`.) There should only be one line in this format, which looks like this:

```
/remember/:days
```

Where `days` is a floating-point number that specifies the upper limit to remember a Message-ID, even if the article has already expired. (It does not affect article expirations.)

Most of the lines in the file will consist of five colon-separated fields, as follows:

```
pattern:modflag:keep:default:purge
```

The `pattern` field is comma-separated set of single `wildmat(3)`-style patterns that specify the newsgroups to which the rest of the line applies. Because the file is interpreted in order, the most general patterns should be specified first, and the most specific patterns should be specified last.

The `modflag` field can be used to further limit newsgroups to which the line applies and should be chosen from the following set:

M	Only moderated groups
U	Only unmoderated groups
A	All groups

The next three fields are used to determine how long an article should be kept. Each field should be either a number of days (fractions such as 8.5 are allowed) or the word `never`. The most common use is to specify the default value for how long an article should be kept. The first and third fields—`keep` and `purge`—specify the boundaries within which an Expires header will be honored. They are ignored if an article has no Expires header. The fields are specified in the file as “lower-bound default upper-bound,” and they are explained in this order. Because most articles do not have explicit expiration dates, however, the second field tends to be the most important one.

The `keep` field specifies how many days an article should be kept before it will be removed. No article in the newsgroup will be removed if it has been filed for less than `keep` days, regardless of any expiration date. If this field is the word `never`, then an article cannot have been kept for enough days so it will never be expired.

The `default` field specifies how long to keep an article if no Expires header is present. If this field is the word `never`, then articles without explicit expiration dates will never be expired.

The `purge` field specifies the upper bound on how long an article can be kept. No article will be kept longer than the number of days specified by this field. All articles will be removed after they have been kept for `purge` days. If `purge` is the word `never`, then the article will never be deleted.

It is often useful to honor the expiration headers in articles, especially those in moderated groups. To do this, set `keep` to zero, `default` to whatever value you want, and `purge` to `never`. To ignore any Expires header, set all three fields to the same value.

There must be exactly one line with a `pattern` of `*` and a `modflags` of `A`; this matches all groups and is used to set the expiration default. It should be the first expiration line. For example:

```
## How long to keep expired history
/remember/:5
## Most things stay for two weeks
:A:14:14:14
## Believe expiration dates in moderated groups, up to six weeks
:M:1:30:42
## Keep local stuff for a long time
foo.*:A:30:30:30
```

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for InterNetNews.

SEE ALSO

`expire(8)`, `wildmat(3)`

exports

exports—NFS filesystems being exported.

SYNOPSIS

`/etc/exports`

DESCRIPTION

The file `/etc/exports` serves as the access control list for filesystems that can be exported to NFS clients. It is used by both the NFS mount daemon `mountd(8)` and the NFS file server daemon `nfsd(8)`.

The file format is similar to the SunOS `exports` file, except that several additional options are permitted. Each line contains a mount point and a list of machine or netgroup names allowed to mount the filesystem at that point. An optional parenthesized list of mount parameters may follow each machine name. Blank lines are ignored, and a `#` introduces a comment to the end of the line.

GENERAL OPTIONS

<code>secure</code>	This option requires that requests originate on an Internet port less than <code>IPPORT_RESERVED</code> (1024). This option is on by default. To turn it off, specify <code>insecure</code> .
<code>ro</code>	Allow only read-only requests on this NFS volume. The default is to allow write requests as well, which can also be made explicit by using the <code>rw</code> option.
<code>link_relative</code>	Convert absolute symbolic links (where the link contents start with a slash) into relative links by prepending the necessary number of <code>../s</code> to get from the directory containing the link to the root on the server. This has subtle, perhaps questionable, semantics when the file hierarchy is not mounted at its root.
<code>link_absolute</code>	Leave all symbolic links as they are. This is the default operation.

USER ID MAPPING

`nfsd` bases its access control to files on the server machine on the UID and GID provided in each NFS RPC request. The normal behavior a user would expect is that she can access her files on the server just as she would on a normal filesystem. This requires that the same UIDs and GIDs are used on the client and the server machine. This is not always true, nor is it always desirable.

Very often, it is not desirable that the root user on a client machine is also treated as root when accessing files on the NFS server. To this end, UID 0 is normally mapped to a different ID: the so-called anonymous or nobody UID. This mode of operation (called root squashing) is the default and can be turned off with `no_root_squash`.

By default, `nfsd` tries to obtain the anonymous UID and GID by looking up user nobody in the password file at startup time. If it isn't found, a UID and GID of -2 (65534) is used. These values can also be overridden by the `anonuid` and `anongid` options.

In addition to this, `nfsd` lets you specify arbitrary UIDs and GIDs that should be mapped to user nobody as well. Finally, you can map all user requests to the anonymous UID by specifying the `all_squash` option.

For the benefit of installations where UIDs differ between different machines, `nfsd` provides a way to dynamically map server UIDs to client UIDs and vice versa. This is enabled with the `map daemon` option and uses the `UGID` RPC protocol. For this to work, you have to run the `ugidd(8)` mapping daemon on the client host.

Here's the complete list of mapping options:

<code>root_squash</code>	Map requests from UID/GID 0 to the anonymous UID/GID. Note that this does not apply to any other UIDs that might be equally sensitive, such as user <code>bin</code> .
<code>no_root_squash</code>	Turn off root squashing. This option is mainly useful for diskless clients.
<code>squash_uids</code> and <code>squash_gids</code>	This option specifies a list of UIDs or GIDs that should be subject to anonymous mapping. A valid list of IDs looks like this: <code>squash_uids=0-15,20,25-50</code> Usually, your squash lists will look a lot simpler, such as <code>squash_uids=0-100</code>
<code>all_squash</code>	Map all UIDs and GIDs to the anonymous user. Useful for NFS-exported public FTP directories, newsspool directories, and so on. The opposite option is <code>no_all_squash</code> , which is the default setting.
<code>map_daemon</code>	This option turns on dynamic UID/GID mapping. Each UID in an NFS request will be translated to the equivalent server UID, and each UID in an NFS reply will be mapped the other way round. This option requires that <code>rpc.ugidd(8)</code> runs on the client host. The default setting is <code>map_identity</code> , which leaves all UIDs untouched. The normal squash options apply regardless of whether dynamic mapping is requested.
<code>anonuid</code> and <code>anongid</code>	These options explicitly set the UID and GID of the anonymous account. This option is primarily useful for PC/NFS clients, where you might want all requests appear to be from one user. As an example, consider the export entry for <code>/home/joe</code> in the section "Example," which maps all requests to UID 150 (which is supposedly that of user <code>joe</code>).

EXAMPLE

```
# sample /etc/exports file
/ master(rw) trusty(rw,no_root_squash)
/projects proj*.local.domain(rw)
/usr *.local.domain(ro) @trusted(rw)
/home/joe pc001(rw,all_squash,anonuid=150,anongid=100)
/pub (ro,insecure,all_squash)
```

The first line exports the entire filesystem to machines `master` and `trusty`. In addition to write access, all UID squashing is turned off for host `trusty`. The second and third entry show examples for wildcard hostnames and netgroups (this is the entry `@trusted`). The fourth line shows the entry for the PC/NFS client discussed previously. The last line exports the public FTP directory to every host in the world, executing all requests under the `nobody` account. The `insecure` option in this entry also allows clients with NFS implementations that don't use a reserved port for NFS.

CAVEATS

Unlike other NFS server implementations, this `nfsd` allows you to export both a directory and a subdirectory thereof to the same host, for instance `/usr` and `/usr/X11R6`. In this case, the mount options of the most specific entry apply. For instance, when a user on the client host accesses a file in `/usr/X11R6`, the mount options given in the `/usr/X11R6` entry apply. This is also true when the latter is a wildcard or netgroup entry.

FILES

<code>/etc/exports</code>	Configuration file for <code>nfsd(8)</code>
<code>/etc/passwd</code>	The password file

DIAGNOSTICS

An error parsing the file is reported using `syslogd(8)` as level `NOTICE` from a `DAEMON` whenever `nfsd(8)` or `mountd(8)` is started. Any unknown host is reported at that time, but often not all hosts are not yet known to `named(8)` at boot time, so as hosts are found, they are reported with the same `syslogd(8)` parameters.

SEE ALSO

mountd(8), nfsd(8), nfs(5), passwd(5)

21 October 1996

filesystems

filesystems—Linux filesystem types: minix, ext, ext2, xia, msdos, umsdos, vfat, proc, nfs, iso9660, hpfs, sysv, smb, ncdfs.

DESCRIPTION

In the file `/proc/filesystems`, you can find which filesystems your kernel currently supports. (If you need a currently unsupported one, insert the corresponding module or recompile the kernel.)

Following is a description of the various filesystems.

minix	The filesystem used in the Minix operating system, the first to run under Linux. It has a number of shortcomings: a 64MB partition size limit, short filenames, a single time stamp, and so on. It remains useful for floppies and RAM disks.
ext	An elaborate extension of the minix filesystem. It has been completely superseded by the second version of the extended filesystem (ext2) and will eventually be removed from the kernel.
ext2	The high performance disk filesystem used by Linux for fixed disks as well as removable media. The second extended filesystem was designed as an extension of the extended filesystem (ext). ext2 offers the best performance (in terms of speed and CPU usage) of the filesystems supported under Linux.
xiafs	Designed and implemented to be a stable, safe filesystem by extending the Minix filesystem code. It provides the basic, most requested features without undue complexity. The xia filesystem is no longer actively developed or maintained. It is used infrequently.
msdos	The filesystem used by DOS, Windows, and some OS/2 computers. msdos filenames can be no longer than an eight-character name followed by an optional period and three-character extension.
umsdos	An extended DOS filesystem used by Linux. It adds capability for long filenames, UID/GID, POSIX permissions, and special files (devices, named pipes, and so on) under the DOS filesystem, without sacrificing compatibility with DOS.
vfat	Extended DOS filesystem used by Microsoft Windows 95 and Windows NT. vfat adds capability for long filenames under the MS-DOS filesystem.
proc	A pseudo-filesystem that is used as an interface to kernel data structures rather than reading and interpreting <code>/dev/kmem</code> . In particular, its files do not take disk space. See <code>proc(5)</code> .
iso9660	A CD-ROM filesystem type conforming to the ISO 9660 standard.
High Sierra	Linux supports High Sierra, the precursor to the ISO 9660 standard for CD-ROM filesystems. It is automatically recognized within the iso9660 filesystem support under Linux.
Rock Ridge	Linux also supports the System Use Sharing Protocol records specified by the Rock Ridge Interchange Protocol. They are used to further describe the files in the iso9660 filesystem to a UNIX host and provides information such as long filenames, UID/GID, POSIX permissions, and devices. It is automatically recognized within the iso9660 filesystem support under Linux.
hpfs	The High Performance Filesystem, used in OS/2. This filesystem is read-only under Linux due to the lack of available documentation.
sysv	An implementation of the SystemV/Coherent filesystem for Linux. It implements all Xenix FS, SystemV/386 FS, and Coherent FS.
nfs	The network filesystem used to access disks located on remote computers.

smb	A network filesystem that supports the SMB protocol, used by Windows for Workgroups, Windows NT, and LAN Manager. To use smb, you need a special mount program, which can be found in the <code>ksmbfs</code> package at ftp://sunsite.unc.edu/pub/Linux/system/Filesystems/smbfs .
ncpfs	A network filesystem that supports the NCP protocol, used by Novell NetWare. To use ncpfs, you need special programs found at ftp://linux01.gwdg.de/pub/ncpfs .

SEE ALSO

`proc(5)`, `fsck(8)`, `mkfs(8)`, `mount(8)`

25 March 1996

fstab

`fstab`—Static information about the filesystems.

SYNOPSIS

```
#include <fstab.h>
```

DESCRIPTION

The file `fstab` contains descriptive information about the various filesystems. `fstab` is only read by programs and not written; it is the duty of the system administrator to properly create and maintain this file. Each filesystem is described on a separate line; fields on each line are separated by tabs or spaces. The order of records in `fstab` is important because `fsck(8)`, `mount(8)`, and `umount(8)` sequentially iterate through `fstab` doing their thing.

The first field (`fs_spec`) describes the block special device or remote filesystem to be mounted.

The second field (`fs_file`) describes the mount point for the filesystem. For swap partitions, this field should be specified as `none`.

The third field (`fs_vfstype`) describes the type of the filesystem. The system currently supports three types of filesystems:

<code>minix</code>	A local filesystem, supporting filenames of length 14 or 30 characters.
<code>ext</code>	A local filesystem with longer filenames and larger inodes. This filesystem has been replaced by the <code>ext2</code> filesystem and should no longer be used.
<code>ext2</code>	A local filesystem with longer filenames, larger inodes, and a lot of other features.
<code>xiafs</code>	A local filesystem with longer filenames, larger inodes, and a lot of other features.
<code>msdos</code>	A local filesystem for MS-DOS partitions.
<code>hpfs</code>	A local filesystem for HPFS partitions.
<code>iso9660</code>	A local filesystem used for CD-ROM drives.
<code>nfs</code>	A filesystem for mounting partitions from remote systems.
<code>swap</code>	A disk partition to be used for swapping.

If `vfs_fstype` is specified as `ignore`, the entry is ignored. This is useful to show disk partitions that are currently unused.

The fourth field (`fs_mntops`) describes the mount options associated with the filesystem.

It is formatted as a comma-separated list of options. It contains at least the type of mount plus any additional options appropriate to the filesystem type. For documentation on the available options for non-NFS file systems, see `mount(8)`. For documentation on all NFS-specific options, take a look at `nfs(5)`. Common for all types of filesystems are the options `noauto` (do not mount when `mount -a` is given, such as at boot time) and `user` (allow a user to mount). For more details, see `mount(8)`.

The fifth field (`fs_freq`) is used for these filesystems by the `dump(8)` command to determine which filesystems need to be dumped. If the fifth field is not present, a value of zero is returned and `dump` will assume that the filesystem does not need to be dumped.

The sixth field (`fs_passno`) is used by the `fsck(8)` program to determine the order in which filesystem checks are done at reboot time. The root filesystem should be specified with a `fs_passno` of 1, and other filesystems should have a `fs_passno` of 2. Filesystems within a drive will be checked sequentially, but filesystems on different drives will be checked at the same time to utilize parallelism available in the hardware. If the sixth field is not present or zero, a value of zero is returned and `fsck` will assume that the filesystem does not need to be checked.

The proper way to read records from `fstab` is to use the routine `getmntent(3)`.

FILES

`/etc/fstab`

BUGS

The documentation in `mount(8)` is often more up-to-date.

SEE ALSO

`getmntent(3)`, `mount(8)`, `swapon(8)`, `nfs(5)`

HISTORY

The `fstab` file format appeared in 4.0 BSD.

Linux 0.99, 27 November 1993

groff_font

`groff_font`—Format of `groff` device and font description files.

DESCRIPTION

The `groff_font` format is roughly a superset of the `ditroff` font format. Unlike the `ditroff` font format, there is no associated binary format. The font files for device name are stored in a directory `devname`. There are two types of file: a device description file called `DESC` and for each font `F`, a font file called `F`. These are text files; there is no associated binary format.

DESC FILE FORMAT

The `DESC` file can contain the following types of lines:

<code>res n</code>	There are <code>n</code> machine units per inch.
<code>hor n</code>	The horizontal resolution is <code>n</code> machine units.
<code>vert n</code>	The vertical resolution is <code>n</code> machine units.
<code>sizescale n</code>	The scale factor for point sizes. By default, this has a value of 1. One scaled point is equal to one point/ <code>n</code> . The arguments to the <code>unitwidth</code> and <code>sizes</code> commands are given in scaled points.
<code>unitwidth n</code>	Quantities in the font files are given in machine units for fonts whose point size is <code>n</code> scaled points.
<code>tcommand</code>	This means that the postprocessor can handle the <code>t</code> and <code>u</code> output commands.
<code>sizes s1 s2 ... sn</code>	This means that the device has fonts at <code>s1</code> , <code>s2</code> , ..., <code>sn</code> scaled points. The list of sizes must be terminated by a <code>0</code> . Each <code>si</code> can also be a range of sizes <code>m-n</code> . The list can extend over more than one line.
<code>styles S1 S2 ... Sm</code>	The first <code>m</code> font positions will be associated with styles <code>S1</code> ... <code>Sm</code> .
<code>fonts n F1 F2 F3 ... Fn</code>	Fonts <code>F1</code> ... <code>Fn</code> will be mounted in the font positions <code>m+1</code> , ..., <code>m+n</code> where <code>m</code> is the number of styles. This command may extend over more than one line. A font name of <code>0</code> will cause no font to be mounted on the corresponding font position.

<code>family fam</code>	The default font family is <code>fam</code> .
<code>charset</code>	This line and everything following in the file are ignored. It is allowed for the sake of backwards compatibility.

The `res`, `unitwidth`, `fonts`, and `sizes` lines are compulsory. Other commands are ignored by `troff` but may be used by postprocessors to store arbitrary information about the device in the `DESC` file.

FONT FILE FORMAT

A font file has two sections. The first section is a sequence of lines, each containing a sequence of blank delimited words; the first word in the line is a key, and subsequent words give a value for that key.

<code>name F</code>	The name of the font is <code>F</code> .
<code>spacewidth n</code>	The normal width of a space is <code>n</code> .
<code>slant n</code>	The characters of the font have a slant of <code>n</code> degrees. (Positive means forward.)
<code>ligatures lig1 lig2 ... lig_n [0]</code>	Characters <code>lig1</code> , <code>lig2</code> , ..., <code>lig_n</code> are ligatures; possible ligatures are <code>ff</code> , <code>fi</code> , <code>fl</code> , and <code>ffl</code> . For backwards compatibility, the list of ligatures may be terminated with a <code>0</code> . The list of ligatures may not extend over more than one line.
<code>special</code>	The font is <code>special</code> ; this means that when a character is requested that is not present in the current font, it will be searched for in any special fonts that are mounted.

Other commands are ignored by `troff` but may be used by postprocessors to store arbitrary information about the font in the font file.

The first section can contain comments, which start with the `#` character and extend to the end of a line.

The second section contains one or two subsections. It must contain a `charset` subsection and it may also contain a `kernpairs` subsection. These subsections can appear in any order. Each subsection starts with a word on a line by itself.

The word `charset` starts the `charset` subsection. The `charset` line is followed by a sequence of lines. Each line gives information for one character. A line comprises a number of fields separated by blanks or tabs. The format is

```
name metrics type code comment
```

`name` identifies the character: if `name` is a single character `c`, it corresponds to the `groff` input character `c`; if it is of the form `\c` where `c` is a single character, then it corresponds to the `groff` input character `nc`; otherwise, it corresponds to the `groff` input character `\[name]` (if it is exactly two characters `xx`, it can be entered as `\(xx)`). `groff` supports eight-bit characters; however, some utilities have difficulties with eight-bit characters. For this reason, there is a convention that the name `charn` is equivalent to the single character whose code is `n`. For example, `char163` is equivalent to the character with code 163, which is the pounds sterling sign in ISO Latin-1. The name `—` is special and indicates that the character is unnamed; such characters can only be used by means of the `\N` escape sequence in `troff`.

The `type` field gives the character type:

1	The character has an descender, such as <code>p</code> .
2	The character has an ascender, such as <code>b</code> .
3	The character has both an ascender and a descender, such as <code>(</code> .

The `code` field gives the code that the postprocessor uses to print the character. The character can also be input to `groff` using this code by means of the `\N` escape sequence. The code can be any integer. If it starts with a `0`, it will be interpreted as octal; if it starts with `0x` or `0X`, it will be interpreted as hexadecimal.

Anything on the line after the code field will be ignored.

The `metrics` field has the form:

```
width[,height[,depth[,italic_correction[,left_italic_correction
↳[,subscript_correction]]]]]
```

There must not be any spaces between these subfields. Missing subfields are assumed to be `0`. The subfields are all decimal integers. Because there is no associated binary format, these values are not required to fit into a variable of type `char` as they

are in `ditroff`. The `width` subfield gives the width of the character. The `height` subfield gives the height of the character (upwards is positive); if a character does not extend above the baseline, it should be given a zero height, rather than a negative height. The `depth` subfield gives the depth of the character, that is, the distance below the lowest point below the baseline to which the character extends (downwards is positive); if a character does not extend below above the baseline, it should be given a zero depth, rather than a negative depth. The `italic_correction` subfield gives the amount of space that should be added after the character when it is immediately to be followed by a character from a roman font. The `left_italic_correction` subfield gives the amount of space that should be added before the character when it is immediately to be preceded by a character from a roman font. The `subscript_correction` gives the amount of space that should be added after a character before adding a subscript. This should be less than the `italic_correction`.

A line in the `charset` section can also have the format

```
name "
```

This indicates that `name` is just another name for the character mentioned in the preceding line.

The word `kernpairs` starts the `kernpairs` section. This contains a sequence of lines of the form:

```
c1 c2 n
```

This means that when character `c1` appears next to character `c2`, the space between them should be increased by `n`. Most entries in `kernpairs` section will have a negative value for `n`.

FILES

<code>/usr/lib/groff/font/dev name/DESC</code>	Device description file for device name.
<code>/usr/lib/groff/font/devname/F</code>	Font file for font F of device name.

SEE ALSO

`groff_out(5)`, `gtroff(1)`

Groff Version 1.09, 14 February 1994

groff_out

`groff_out`—`groff` intermediate output format.

DESCRIPTION

This manual page describes the format output by GNU `troff`. The output format used by GNU `troff` is very similar to that used by UNIX device-independent `troff`. Only the differences are documented here.

The argument to the `s` command is in scaled points (units of points/`n`, where `n` is the argument to the `sizescale` command in the `DESC` file.) The argument to the `x Height` command is also in scaled points.

The first three output commands are guaranteed to be

```
x T device
x res n h v
x init
```

If the `tcommand` line is present in the `DESC` file, `troff` will use the following two commands:

<code>txxx</code>	<code>xxx</code> is any sequence of characters terminated by a space or a newline; the first character should be printed at the current position, the current horizontal position should be increased by the width of the first character, and so on for each character. The width of the character is that given in the font file, appropriately scaled for the current point size and rounded so that it is a multiple of the horizontal resolution. Special characters cannot be printed using this command.

`unxxx` This is same as the `t` command except that after printing each character, the current horizontal position is increased by the sum of the width of that character and `n`.

Note that single characters can have the eighth bit set, as can the names of fonts and special characters.

The names of characters and fonts can be of arbitrary length; drivers should not assume that they will be only two characters long.

When a character is to be printed, that character will always be in the current font. Unlike device-independent `troff`, it is not necessary for drivers to search special fonts to find a character.

The `d` drawing command has been extended. These extensions will not be used by GNU `pic` if the `-n` option is given.

<code>Df n\n</code>	Set the shade of gray to be used for filling solid objects to <code>n</code> ; <code>n</code> must be an integer between 0 and 1000, where 0 corresponds to solid white and 1000 to solid black and values in between correspond to intermediate shades of gray. This applies only to solid circles, solid ellipses, and solid polygons. By default, a level of 1000 will be used. Whatever color a solid object has, it should completely obscure everything beneath it. A value greater than 1000 or less than 0 can also be used: This means fill with the shade of gray that is currently being used for lines and text. Normally, this will be black, but some drivers may provide a way of changing this.
<code>DC d\n</code>	Draw a solid circle with a diameter of <code>d</code> with the leftmost point at the current position.
<code>DE dx dy\n</code>	Draw a solid ellipse with a horizontal diameter of <code>dx</code> and a vertical diameter of <code>dy</code> with the leftmost point at the current position.
<code>Dp dx1 dy1 dx2 dy2 ... dxn dyn\n</code>	Draw a polygon with, for $i = 1, \dots, n+1$, the i th vertex at the current position + $\sum_{j=1}^{i-1} (dx_j, dy_j)$. At the moment, GNU <code>pic</code> only uses this command to generate triangles and rectangles.
<code>DP dx1 dy1 dx2 dy2 ... dxn dyn\n</code>	Like <code>Dp</code> , but draw a solid rather than outlined polygon.
<code>Dt n\n</code>	Set the current line thickness to <code>n</code> machine units. Traditionally, UNIX <code>troff</code> drivers use a line thickness proportional to the current point size; drivers should continue to do this if no <code>Dt</code> command has been given or if a <code>Dt</code> command has been given with a negative value of <code>n</code> . A zero value of <code>n</code> selects the smallest available line thickness.

A difficulty arises in how the current position should be changed after the execution of these commands. This is not of great importance because the code generated by GNU `pic` does not depend on this. Given a drawing command of the form

`\Dc x1 y1 x2 y2 ... xn yn`

where `c` is not one of `c`, `e`, `l`, `a`, or `~`, UNIX `troff` will treat each of the x_i as a horizontal quantity and each of the y_i as a vertical quantity and will assume that the width of the drawn object is $\sum_{i=1}^n x_i$ and that the height is $\sum_{i=1}^n y_i$. (The assumption about the height can be seen by examining the `st` and `sb` registers after using such a `D` command in a `\w` escape sequence.) This rule also holds for all the original drawing commands with the exception of `De`. For the sake of compatibility, GNU `troff` also follows this rule, even though it produces an ugly result in the case of the `Df`, `Dt`, and, to a lesser extent, `DE` commands. Thus after executing a `D` command of the form

`Dc x1 y1 x2 y2 ... xn yn\n`

the current position should be increased by $(\sum_{i=1}^n x_i; \sum_{i=1}^n y_i)$.

A continuation convention permits the argument to the `x X` command to contain newlines: when outputting the argument to the `x X` command, GNU `troff` will follow each newline in the argument with a `+` character (as usual, it will terminate the entire argument with a newline); thus if the line after the line containing the `x X` command starts with `+`, then the newline ending the line containing the `x X` command should be treated as part of the argument to the `x X` command, the `+` should be ignored, and the part of the line following the `+` should be treated like the part of the line following the `x X` command.

SEE ALSO

groff_font(5)

groff version 1.09, 14 February 1994

group

group—User group file.

DESCRIPTION

/etc/group is an ASCII file that defines the groups to which users belong. There is one entry per line, and each line has the format

```
group_name:passwd:GID:user_list
```

The field descriptions are

group_name	The name of the group.
passwd	The (encrypted) group password. If this field is empty, no password is needed.
GID	The numerical group ID.
user_list	All the group member's usernames, separated by commas.

FILES

/etc/group

SEE ALSO

login(1), newgrp(1), passwd(5)

Linux, 29 December 1992

history

history—Record of current and recently expired Usenet articles.

DESCRIPTION

The file /news/lib/history keeps a record of all articles currently stored in the news system, as well as those that have been received but since expired.

The file consists of text lines. Each line corresponds to one article. The file is normally kept sorted in the order in which articles are received, although this is not a requirement. innd(8) appends a new line each time it files an article, and expire(8) builds a new version of the file by removing old articles and purging old entries.

Each line consists of two or three fields separated by a tab, shown below as \t:

```
<Message-ID>\t date
<Message-ID>\t date \t files
```

The Message-ID field is the value of the article's Message-ID header, including the angle brackets.

The date field consists of three subfields separated by a tilde. All subfields are the text representation of the number of seconds since the epoch—a time_t; see gettimeofday(2). The first subfield is the article's arrival date. If copies of the article are still present, then the second subfield is either the value of the article's Expires header or a hyphen if no expiration date was specified. If an article has been expired, the second subfield will be a hyphen. The third subfield is the value of the article's Date header, recording when the article was posted.

The `files` field is a set of entries separated by one or more spaces. Each entry consists of the name of the newsgroup, a slash, and the article number. This field is empty if the article has been expired.

For example, an article cross-posted to `comp.sources.unix` and `comp.sources.d` that was posted on February 10, 1991, (and received three minutes later) with an expiration date of May 5, 1991, could have a history line (broken into two lines for display) like the following:

```
<312@litchi.foo.com> \t 666162000`673329600`666162180
\t comp.sources.unix/1104 comp.sources.d/7056
```

In addition to the text file, there is a `dbz(3z)` database associated with the file that uses the Message-ID field as a key to determine the offset in the text file where the associated line begins. For historical reasons, the key includes the trailing `\0` byte (which is not stored in the text file).

HISTORY

Written by Rich Salz (`rsalz@uunet.uu.net`) for InterNetNews.

SEE ALSO

`dbz(3z)`, `expire(8)`, `innd(8)`, `news-recovery(8)`

hosts.nntp, hosts.nntp.nolimit

`hosts.nntp`, `hosts.nntp.nolimit`—List of hosts that feed NNTP news.

DESCRIPTION

The file `/news/lib/hosts.nntp` is read by `innd(8)` to get the list of hosts that feed the local site Usenet news using the NNTP protocol. The server reads this file at startup or when directed to by `ctlinnd(8)`. When a hosts connects to the NNTP port of the system on which `innd` is running, the server will do a check to see if their Internet address is the same as one of the hosts named in this file. If the host is not mentioned, then `innd` will spawn an `nnrpd(8)` to process the connection, with the accepted connection on standard input and standard output.

Comments begin with a number sign (`#`) and continue through the end of the line. Blank lines and comments are also ignored. All other lines should consist of two or three fields separated by a colon.

The first field should be either an Internet address in dotted-quad format or an address that can be parsed by `gethostbyname(3)`. If a host's entry has multiple addresses, all of them will be added to the access list. The second field, which may be blank, is the password the foreign host is required to use when first connecting. The third field, which may be omitted, is a list of newsgroups to which the host may post articles. This list is parsed as a `newsfeeds(5)` subscription list; groups not in the list are ignored.

Because `innd` is usually started at system boot time, the local nameserver may not be fully operational when `innd` parses this file. As a work-around, a `ctlinnd reload` command can be performed after a delay of an hour or so. It is also possible to provide both a host's name and its dotted-quad address in the file.

For example:

```
## FOO has a password, UUNET doesn't.
## UUNET cannot post to local groups.
## These are comment lines.
news.foo.com:magic
uunet.uu.net:!foo.*
```

If the file contains passwords, it should not be world-readable. The file `/news/lib/hosts.nntp.nolimit`, if it exists, is read whenever the `hosts.nntp` file is read. It has the same format, although only the first field is used. Any host mentioned in this file is not subject to the incoming connections limit specified by `innd's -c` flag. This can be used to allow local hosts or time-sensitive peers to connect regardless of the local conditions.

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for InterNetNews.

SEE ALSO

ctlinnd(8), innd(8), nnpd(8)

hosts_access

hosts_access—Format of host access control files.

DESCRIPTION

This manual page describes a simple access control language that is based on client (hostname/address, username) and server (process name) patterns. Examples are given at the end. The impatient reader can skip to the “Examples” section for a quick introduction.

In the following text, *daemon* is the process name of a network daemon process, and *client* is the name or address of a host requesting service. Network daemon process names are specified in the *inetd* configuration file.

ACCESS CONTROL FILES

The access control software consults two files. The search stops at the first match:

Access will be granted when a (*daemon*,*client*) pair matches an entry in the */etc/hosts.allow* file.

Otherwise, access will be denied when a (*daemon*,*client*) pair matches an entry in the */etc/hosts.deny* file.

Otherwise, access will be granted.

A non-existing access control file is treated as if it were an empty file. Thus, access control can be turned off by providing no access control files.

ACCESS CONTROL RULES

Each access control file consists of zero or more lines of text. These lines are processed in order of appearance. The search terminates when a match is found.

A newline character is ignored when it is preceded by a backslash character.

Blank lines or lines that begin with a *#* character are ignored.

All other lines should satisfy the following format, things between *[]* being optional:

```
daemon_list : client_list [ : shell_command ]
```

daemon_list is a list of one or more daemon process names (*argv[0]* values) or wildcards.

client_list is a list of one or more hostnames, host addresses, patterns, or wildcards that will be matched against the remote hostname or address.

List elements should be separated by blanks or commas.

With the exception of NIS (YP) netgroup lookups, all access control checks are case insensitive.

PATTERNS

The access control language implements the following patterns:

A string that begins with a *.* character: A client name or address is matched if its last components match the specified pattern. For example, the pattern *.tue.nl* matches the hostname *wzv.win.tue.nl*.

A string that ends with a *.* character: A client name or address is matched if its first fields match the given string. For example, the pattern *131.155.* matches the address of (almost) every host on the Eindhoven University network (*131.155.x.x*).

A string that begins with a @ character is treated as a netgroup name: Netgroups are usually supported on systems with NIS (formerly YP) databases. A client hostname is matched if it is a (host) member of the specified netgroup.

An expression of the form `n.n.n.n/m.m.m.m` is interpreted as a `net/mask` pair. A client address is matched if `net` is equal to the bitwise AND of the address and the mask. For example, the `net/mask` pattern `131.155.72.0/255.255.254.0` matches every address in the range `131.155.72.0` through `131.155.73.255`.

WILDCARDS

The access control language supports explicit wildcards:

ALL	If this token appears in a daemon list, it matches all network daemon process names. If the ALL token appears in a client list, it matches all client names and addresses.
LOCAL	Matches any string that does not contain a dot character. Typical use is in client lists.
UNKNOWN	Matches any host whose name or address are unknown. Should be used with care: Hostnames may be unavailable due to temporary nameserver problems. A network address will be unavailable when the software cannot figure out what type of network it is talking to.
KNOWN	Matches any host whose name and address are known. Should be used with care: Hostnames may be unavailable due to temporary nameserver problems. A network address will be unavailable when the software cannot figure out what type of network it is talking to.
FAIL	Like the ALL wildcard but causes the software to pretend that the scan of the current access control table fails. FAIL is being phased out; it will become an undocumented feature. The EXCEPT operator is a much cleaner alternative.

OPERATORS

EXCEPT	Intended use is of the form: <code>list_1 EXCEPT list_2</code> ; this construct matches anything that matches <code>list_1</code> unless it matches <code>list_2</code> . This construct can be used in daemon lists and in client lists. The EXCEPT operator can be nested: If the control language would permit the use of parentheses, a <code>EXCEPT b EXCEPT c</code> would parse as <code>(a EXCEPT (b EXCEPT c))</code> .

SHELL COMMANDS

If the first-matched access control rule contains a shell command, that command is subjected to the following substitutions:

%a	Expands to the remote host address.
%c	Expands to client information: <code>user@host</code> , <code>user@address</code> , a hostname, or just an address, depending on how much information is available.
%h	Expands to the remote hostname (or address, if the hostname is unavailable).
%d	Expands to the daemon process name (<code>argv[0]</code> value).
%p	Expands to the daemon process ID.
%u	Expands to the remote username (or unknown).
%%	Expands to a single % character.

Characters in % expansions that may confuse the shell are replaced by underscores. The result is executed by a `/bin/sh` child process with standard input, output, and error connected to `/dev/null`. Specify an & at the end of the command if you do not want to wait until it has completed.

Shell commands should not rely on the `PATH` setting of the `inetd`. Instead, they should use absolute pathnames, or they should begin with an explicit `PATH=whatever` statement.

REMOTE USERNAME LOOKUP

When the client host supports the RFC 931 protocol or one of its descendants (TAP, IDENT) the wrapper programs can retrieve additional information about the owner of a connection. When available, remote username information is logged together with the client hostname and can be used to match patterns like

```
daemon_list : ... user_pattern@host_pattern ...
```

The daemon wrappers can be configured at compile time to perform rule-driven username lookups (default) or to always interrogate the client host. In the case of rule-driven username lookups, the preceding rule would cause username lookup only when both the `daemon_list` and the `host_pattern` match.

A user pattern has the same syntax as a daemon process name, hostname, or host address pattern, so the same wildcards and so on apply (but netgroup membership of users is not supported). One should not get carried away with username lookups, however.

The remote username information cannot be trusted when it is needed most—that is, when the remote system has been compromised. In general, `ALL` and `(UN)KNOWN` are the only username patterns that make sense.

Username lookups are possible only with TCP-based services and only when the client host runs a suitable daemon; in all other cases the result is `unknown`.

A well-known UNIX kernel bug may cause loss of service when username lookups are blocked by a firewall. The wrapper `README` document describes a procedure to find out if your kernel has this bug.

Username lookups cause noticeable delays for PC users. The default time-out for username lookups is ten seconds: too short to cope with slow networks but long enough to irritate PC users.

Selective username lookups can alleviate the last problem. For example, a rule like

```
daemon_list : @pcnetgroup ALL@ALL
```

would match members of the `pcnetgroup` without doing username lookups but would perform username lookups with all other systems.

EXAMPLES

The language is flexible enough that different types of access control policy can be expressed with a minimum of fuss. Although the language uses two access control tables, the most common policies can be implemented with one of the tables being trivial or even empty.

When reading the following examples, it is important to realize that the `allow` table is scanned before the `deny` table, that the search terminates when a match is found, and that access is granted when no match is found at all.

The examples use host and domain names. They can be improved by including address or network/netmask information to reduce the impact of temporary nameserver lookup failures.

MOSTLY CLOSED

In this case, access is denied by default. Only explicitly authorized hosts are permitted access.

The default policy (no access) is implemented with a trivial deny file:

```
/etc/hosts.deny:
```

```
ALL: ALL
```

This denies all service to all hosts, unless they are permitted access by entries in the `allow` file.

The explicitly authorized hosts are listed in the `allow` file:

```
/etc/hosts.allow:
```

```
ALL: LOCAL @some_netgroup
```

```
ALL: .foobar.edu EXCEPT terminalserver.foobar.edu
```

The first rule permits access to all services from hosts in the local domain (no `.` in the hostname) and from members of the `some_netgroup` netgroup. The second rule permits access to all services from all hosts in the `.foobar.edu` domain, with the exception of `terminalserver.foobar.edu`.

MOSTLY OPEN

Here, access is granted by default; only explicitly specified hosts are refused service.

The default policy (access granted) makes the allow file redundant so that it can be omitted. The explicitly non-authorized hosts are listed in the deny file:

```
/etc/hosts.deny:

ALL: some.host.name, .some.domain
ALL EXCEPT in.fingerd: other.host.name, .other.domain
```

The first rule denies some hosts all services; the second rule still permits finger requests from other hosts.

BOOBY TRAPS

The next example permits tftp requests from hosts in the local domain. Requests from any other hosts are denied. Instead of the requested file, a finger probe is sent to the offending host. The result is mailed to the superuser.

```
/etc/hosts.allow:

in.tftpd: LOCAL, .my.domain
/etc/hosts.deny:

in.tftpd: ALL: (/some/where/safe_finger -l @%h | \
/usr/ucb/mail -s %d-%h root) &
```

The `safe_finger` command comes with the `tcpd` wrapper and should be installed in a suitable place. It limits possible damage from data sent by the remote finger server. It gives better protection than the standard finger command.

The expansion of the `%h` (remote host) and `%d` (service name) sequences is described in the section on shell commands.

Warning: Do not booby-trap your finger daemon, unless you are prepared for infinite finger loops.

On network firewall systems, this trick can be carried even further. The typical network firewall only provides a limited set of services to the outer world. All other services can be “bugged” just like the preceding tftp example. The result is an excellent early-warning system.

DIAGNOSTICS

An error is reported when a syntax error is found in a host access control rule, when the length of an access control rule exceeds the capacity of an internal buffer, when an access control rule is not terminated by a newline character, when the result of `%<character>` expansion would overflow an internal buffer, and when a system call fails that shouldn't. All problems are reported via the `syslog` daemon.

FILES

```
/etc/hosts.allow, (daemon,client) pairs that are granted access.
/etc/hosts.deny, (daemon,client) pairs that are denied access.
```

SEE ALSO

`tcpd(8)`, TCP/IP daemon wrapper program

BUGS

If a nameserver lookup times out, the hostname will not be available to the access control software, even though the host is registered.

Domain nameserver lookups are case insensitive; NIS (formerly YP) netgroup lookups are case sensitive.

AUTHOR

Wietse Venema (wietse@wzv.win.tue.nl), Department of Mathematics and Computing Science, Eindhoven University of Technology, Den Dolech 2, P.O. Box 513, 5600 MB Eindhoven, The Netherlands.

hosts_options

hosts_options—Host access control language extensions.

DESCRIPTION

This document describes optional extensions to the language described in the `hosts_access(5)` document. The extensions are enabled at program build time by editing the makefile.

The extensible language uses the following format:

```
daemon_list : client_list : option : option ...
```

The first two fields are described in the `hosts_access(5)` manual page. The remainder of the rules is a list of zero or more options. Any `:` characters within options should be protected with a backslash.

An option is of the form `keyword` or `keyword = value`. Options are processed in the specified order. With some options, the value is subjected to `%<character>` substitutions.

OPTIONS

```
severity = mail.info
```

Change the severity level at which the event will be logged. Facility names (such as `mail`) are optional and are not supported on systems with older `syslog` implementations. The severity option can be used to emphasize or to completely ignore specific events.

```
allow (deny)
```

Grant (deny) service, even when the matched rule was found in the `hosts.deny` (`hosts.allow`) file. These options must appear at the end of a rule.

With the `allow` and `deny` keywords, it is possible to keep all access control rules within a single file—for example, in the `hosts.allow` file:

```
ALL: .friendly.domain: allow
ALL: ALL: deny
```

This permits access from specific hosts only. On the other hand,

```
ALL: .trouble.makers: deny
ALL: ALL: allow
```

This permits access from all hosts except a few troublemakers.

```
twist = shell_command
```

Replace the current process by an instance of the specified shell command, after performing the `%<character>` expansions described in the `hosts_access(5)` manual page. `stdin`, `stdout`, and `stderr` are connected to the remote client process. This option must appear at the end of a rule. Examples:

```
in.ftpd : ... : twist = /bin/echo 421
```

Some bounce message sends a customized bounce message to the remote client instead of running the real FTP daemon.

```
in.telnetd : ... : twist = PATH=/some/other; exec in.telnetd
```

Runs `/some/other/in.telnetd` without polluting its command-line array or its process environment.

Warning: In case of UDP services, do not twist into commands that use the standard I/O or the `read(2)/write(2)` routines to communicate with the client process; UDP requires other I/O primitives.

```
spawn = shell_command
```

Execute the shell command in a child process, after performing the `%<character>` expansions described in the `hosts_access(5)` manual page. The command

```
spawn = (/some/where/safe_finger -l @%h | /usr/ucb/mail root) &
```

```
umask = 022
```

```
keepalive
```

```
linger = number_of_seconds
```

```
nice = niceval
```

```
nice (no argument)
```

```
user = nobody
```

```
group = tty
```

```
setenv = name value
```

is executed with `stdin`, `stdout`, and `stderr` connected to the null device so that it won't mess up the conversation with the remote host. Example:

Executes, in a background child process, the shell command `safe_finger -l @%h | mail root` after replacing `%h` by the name or address of the remote host.

The example uses the `safe_finger` command instead of the regular `finger` command to limit possible damage from data sent by the finger server. The `safe_finger` command is part of the `daemon wrapper` package; it is a wrapper around the regular `finger` command that filters the data sent by the remote host.

Like the `umask` command that is built into the shell. An `umask` of `022` prevents the creation of files with group and world write permission. The `umask` argument should be an octal number.

Causes the server to periodically send a message to the client. The connection is considered broken when the client does not respond. The `keepalive` option can be useful when users turn off their machine while it is still connected to a server. The `keepalive` option is not useful for datagram (UDP) services.

Specifies how long the kernel will try to deliver not-yet delivered data after the server process closes a connection.

Change the nice value of the process (default 10). Specify a positive value to spend more CPU resources on other processes.

Assume the privileges of the `nobody` account. This is useful with `inetd` implementations that run all services with root privilege. It is good practice to run services such as `finger` at a reduced privilege level.

Assume the privileges of the `tty` group. This is useful mostly in combination with the `user` option. In order to switch both user and group IDs, switch group ID before switching user ID.

Place a (name, value) pair into the process environment. The value is subjected to `%<character>` expansions and may contain whitespace (but leading and trailing blanks are stripped off).

Warning: Many network daemons reset their environment before spawning a login or shell process.

rfc931 = timeout_in_seconds
rfc931 (no argument)

Look up the remote user name with the RFC 931 (ident and so on) protocol. This option is silently ignored in case of services based on transports other than TCP. It requires that the client system runs an RFC 931 (ident and so on) compliant daemon and may cause noticeable delays with connections from non-UNIX hosts. The time-out period is optional. If no time-out is specified, a default value is taken.

DIAGNOSTICS

When a syntax error is found in an access control rule, the error is reported to the syslog daemon; further options will be ignored, and service is denied.

SEE ALSO

hosts_access(5), the default access control language

AUTHOR

Wietse Venema (wietse@wzv.win.tue.nl), Department of Mathematics and Computing Science, Eindhoven University of Technology, Den Dolech 2, P.O. Box 513, 5600 MB Eindhoven, The Netherlands.

inittab

inittab—Format of the inittab file used by the SysV-compatible init process.

DESCRIPTION

The inittab file describes which processes are started at bootup and during normal operation (such as /etc/rc, gettys). init distinguishes multiple run levels, of which each can have its own set of processes that are started. Valid runlevels are 0–6 and A, B, and C for ondemand entries. An entry in the inittab file has the following format:

id:runlevels:action:process

Lines beginning with # are ignored.

id	A unique two-character-sequence which identifies an entry in inittab. Note: For gettys or other login processes, the id field should be the tty suffix of the corresponding tty, such as 1 for tty1. Otherwise, the login accounting will not work correctly. This is a bug in login and will be fixed.
runlevels	Describes in which run levels the specified action should be taken.
action	Describes which action should be taken.
process	Specifies the process to be executed. If the process field starts with a + character, init will not do utmp and wtmp accounting for that process. This is needed for gettys that insist on doing their own utmp/wtmp housekeeping. This is also a historic bug.

Valid actions are

respawn	The process will be restarted whenever it terminates (such as getty).
wait	The process will be started once when the specified run level is entered and init will wait for its termination.
once	The process will be executed once when the specified run level is entered.
boot	The process will be executed during system boot. The run level field is ignored.

<code>bootwait</code>	The process will be executed during system boot while <code>init</code> waits for its termination (such as <code>/etc/rc</code>). The <code>runlevel</code> field is ignored.
<code>off</code>	This does nothing.
<code>ondemand</code>	A process marked with <code>ondemand</code> will be executed whenever the specified <code>ondemand</code> run level is called. However, no <code>runlevel</code> change will occur.
<code>initdefault</code>	An <code>initdefault</code> -entry specifies the run level that should be entered after system boot. If none exists, <code>init</code> will ask for a <code>runlevel</code> on the console.
<code>sysinit</code>	The process will be executed during system boot. It will be executed before any boot or <code>bootwait</code> entries.
<code>powerwait</code>	The process will be executed when <code>init</code> receives the <code>SIGPWR</code> signal, indicating that there is something wrong with the power. <code>init</code> will wait for the process to finish before continuing.
<code>powerfail</code>	As <code>powerwait</code> but <code>init</code> will not wait for the processes completion.
<code>powerokwait</code>	The process will be executed when <code>init</code> receives the <code>SIGPWR</code> signal, provided there is a file called <code>/etc/powerstatus</code> containing the word <code>OK</code> . This means that the power has come back again.
<code>ctrlaltdel</code>	The process will be executed when <code>init</code> receives the <code>SIGINT</code> signal. This means that someone on the system console pressed the <code>Ctrl+Alt+Del</code> key combination. Typically, one wants to execute some sort of shutdown either to get into single-user level or to reboot the machine.

The `runlevel` field may contain multiple characters for different run levels, such as `123` if the process should be started in run levels 1, 2 and 3. `ondemand` entries may contain an `A`, `B`, or `C`. The `runlevel` field of `sysinit`, `boot`, and `bootwait` entries are ignored.

When the run level is changed, any running processes that are not specified for the new run level are killed, first with `SIGTERM` and then with `SIGKILL`.

EXAMPLES

This is an example of an `inittab` that resembles the old Linux `inittab`:

```
# inittab for linux
id:1:initdefault:
rc::bootwait:/etc/rc
1:1:respawn:/etc/getty 9600 tty1
2:1:respawn:/etc/getty 9600 tty2
3:1:respawn:/etc/getty 9600 tty3
4:1:respawn:/etc/getty 9600 tty4
```

This `inittab` file executes `/etc/rc` during boot and starts `gettys` on `tty1`–`tty4`.

A more elaborate `inittab` with different run levels (see the comments inside) is

```
#Level to run in
id:4:initdefault:
ud::boot:/etc/update
rc::bootwait:/etc/rc
cr::boot:/etc/crond
#
# level 1: getty on tty1
# level 2: getty on tty1-4
# level 3: tty1-4, dialin via modem(ttys2)
# level 4: tty1-4, ttyb
#
mr:126:once:/usr/bin/nodialin
mi:345:once:/usr/bin/dialin
1:1234:respawn:/etc/getty 9600 tty1
2:234:respawn:/etc/getty 9600 tty2
3:234:respawn:/etc/getty 9600 tty3
```



```
4:234:respawn:/etc/getty 9600 tty4
s2:3:respawn:/etc/mgetty ttys2 19200
b:4:respawn:/etc/getty 19200L ttyb
ca::ctrlaltdel:/etc/shutdown -t3 -rf now
```

FILES

/etc/inittab

AUTHOR

init was written by Miquel van Smoorenburg (miquels@drinkel.nl.mugnet.org). The manual page was written by Sebastian Lederer (lederer@francium.informatik.uni-bonn.de) and modified by Michael Haardt (u31b3hs@pool.informatik.rwth-aachen.de).

SEE ALSO

init(8), telinit(8)

13 May 1993

inn.conf

inn.conf—Configuration data for InterNetNews programs.

DESCRIPTION

The file `/news/lib/inn.conf` is used to determine various parameters. Blank lines and lines starting with a number sign (#) are ignored. All other lines specify parameters that may be read and should be of the following form:

name : [optional whitespace] value

Everything after the whitespace and up to the end of the line is taken as the value; multi-word values should not be put in quotes. The case of names is significant; server is not the same as Server or SERVER.

Some parameters specified in the file may be overridden by environment variables, and some file parameters may be used to mask real data, such as when hiding a cluster of hosts behind a single electronic mail hostname. The current set of parameters is as follows:

fromhost	This is the name of the host to use when building the From header line. The default is the fully qualified domain name of the local host. The value of the FROMHOST environment variable, if it exists, overrides this.
moderatormailer	This names the default machine that contains forwarding aliases for all moderated groups. It is only used if the moderators(5) file doesn't exist or if the group is not matched by that file. The value is interpreted as a pattern match; see moderators(5).
organization	This specifies what to put in the Organization header if it is blank. The value of the ORGANIZATION environment variable, if it exists, overrides this.
pathhost	This specifies how to name the local site when building the Path header line. The default is the fully qualified domain name of the local host.
server	This specifies the name of the NNTP server to which an article should be posted. The value of the NNTPSERVER environment variable, if it exists, overrides this.
domain	This should be the domain name of the local host. It should not have a leading period, and it should not be a full host address. It is used only if the getFQDN routine in libinn(3) cannot get the fully qualified domain name by using either the gethostname(2) or gethostbyname(3) calls. The check is very simple; if either routine returns a name with a period in it, then it is assumed to have the full domain name.

Three parameters are used only by `nnrpd` when accepting postings from clients:

<code>mime-version</code>	If this parameter is present, then <code>nnrpd</code> will add the necessary MIME (Multipurpose Internet Mail Extensions) headers to all any articles that do not have a Mime-Version header. This parameter specifies the MIME version and should normally be 1.0.
<code>mime-contenttype</code>	If MIME headers are being added, this parameter specifies the value of the Content-Type header. The default value is <code>text/plain; charset=US-ASCII</code> .
<code>mime-encoding</code>	If MIME headers are being added, this parameter specifies the value of the Content-Transfer-Encoding header. The default value is 7bit.

Note that this file can be identical on all machines in an organization.

EXAMPLE

```
fromhost:          foo.com
moderatormailer:   %s@uunet.uu.net
organization:      Foo, Incorporated
#pathhost:         Use FQDN.
server:            news.foo.com
domain:            foo.com
```

This file is intended to be fairly static; any changes made to it are typically not reflected until a program restarts.

HISTORY

Written by Rich Salz (`rsalz@uunet.uu.net`) for InterNetNews.

SEE ALSO

`libinn(3)`, `moderators(5)`

innwatchctl

`innwatchctl`—Control Usenet supervision by `innwatch`.

DESCRIPTION

The file `/news/lib/innwatchctl` is used to determine what actions are taken during the periodic supervisions by `innwatch`.

The file consists of a series of lines; blank lines and lines beginning with a number sign (`#`) are ignored. All other lines consist of seven fields, each preceded by a delimiting character:

```
:label:state:condition:test:limit:command:reason
```

The delimiter can be any one of several non-alphanumeric characters that does not appear elsewhere in the line; there is no way to quote it to include it in any of the fields. Any of `!, , , : , @ , , ,` or `?` is a good choice. Each line can have a different delimiter; the first character on each line is the delimiter for that line. Whitespace surrounding delimiters, except before the first, is ignored and does not form part of the fields; whitespace within fields is permitted. All delimiters must be present.

The first field is a label for the control line. It is used as an internal state indicator and in `ctlinn` messages to control the server. If omitted, the line number is used.

The second field specifies when this control line should be used. It consists of a list of labels and special indicators separated by whitespace. If the current state matches against any of the labels in this field, this line will be used as described below. The values that may be used are

- This line matches if the current state is the same as the label on this line, or if the current state is run, the initial state. This is also the default state if this field is empty.

+	This line matches if the current state is run.
*	This line always matches.
label	This line matches if the current state is the specified label.
-label	This line matches if the current state is not the specified label.

The third field specifies a shell command that is invoked if this line matches. Do not use any shell filename expansion characters such as *, ?, or [(even quoted, they're not likely to work as intended). If the command succeeds, as indicated by its exit status, it is expected to have printed a single integer to standard output. This gives the value of this control line, to be used below. If the command fails, the line is ignored. The command is executed with its current directory set to the newsspool directory, /news/spool.

The fourth field specifies the operator to use to test the value returned above. It should be one of the two-letter numeric test operators defined in `test(1)` such as `eq`, `lt`, and the like. The leading dash (-) should not be included.

The fifth field specifies a constant with which to compare the value using the operator just defined. This is done by invoking the command

```
test value -operator constant
```

The line is said to “succeed” if it returns true.

The sixth field specifies what should be done if the line succeeds and in some cases if it fails. Any of the following words may be used:

throttle	Causes <code>innwatch</code> to throttle the server if this line succeeds. It also sets the state to the value of the line's label. If the line fails and the state was previously equal to the label on this line (that is, this line had previously succeeded), then a <code>go</code> command will be sent to the server, and <code>innwatch</code> will return to the run state. The <code>throttle</code> is only performed if the current state is run or a state other than the label of this line, regardless of whether the command succeeds.
pause	Is identical to <code>throttle</code> except that the server is paused.
shutdown	Sends a <code>shutdown</code> command to the server. It is for emergency use only.
flush	Sends a <code>flush</code> command to the server.
go	Causes <code>innwatch</code> to send a <code>go</code> command to the server and to set the state to run.
exit	Causes <code>innwatch</code> to exit.
skip	The result of the control file is skipped for the current pass.

The last field specifies the reason that is used in those `ctlinnnd` commands that require one. More strictly, it is part of the reason; `innwatch` appends some information to it. In order to enable other sites to recognize the state of the local `innnd` server, this field should usually be set to one of several standard values. Use `No space` if the server is rejecting articles because of a lack of filesystem resources. Use `loadav` if the server is rejecting articles because of a lack of CPU resources.

Once `innwatch` has taken some action as a consequence of its control line, it skips the rest of the control file for this pass. If the action was to restart the server (that is, issue a `go` command), then the next pass will commence almost immediately so that `innwatch` can discover any other condition that may mean that the server should be suspended again.

EXAMPLES

```
@@@df .|awk 'NR==2 {print $4}'@lt@10000@throttle@No space
@@@df -i .|awk 'NR==2 {print $4}'@lt@10000@throttle@No space (inodes)
```

The first line causes the server to be throttled if the free space drops below 10000 units (using whatever units `df` uses) and restarted again when free space increases above the threshold.

The second line does the same for `inodes`.

The next three lines act as a group and should appear in the following order. It is easier to explain them, however, if they are described from the last up.

```
!load!load hload!loadavg!lt!5!go!
:hload:+ load:loadavg:gt:8:throttle:loadav
/load/+/loadavg/ge/6/pause/loadav
```

The final line causes the server to be paused if `innwatch` is in the `run` state and the load average rises to, or above, six. The state is set to `load` when this happens. The previous line causes the server to be throttled when `innwatch` is in the `run` or `load` state, and the load average rises above eight. The state is set to `hload` when this happens. Note that `innwatch` can switch the server from paused to throttled if the load average rises from below six to between six and seven and then to above eight. The first line causes the server to be sent a `go` command if `innwatch` is in the `load` or `hload` state and the load average drops below five.

Note that all three lines assume a mythical command `loadavg` that is assumed to print the current load average as an integer. In more practical circumstances, a pipe of `uptime` into `awk` is more likely to be useful.

BUGS

This file must be tailored for each individual site; the sample supplied is truly no more than a sample. The file should be ordered so that the more common problems are tested first.

The `run` state is not actually identified by the label with that three letter name, and using it will not work as expected.

Using an “unusual” character for the delimiter such as `(`, `*`, `&`, `"`, and the like is likely to lead to obscure and hard-to-locate bugs.

HISTORY

Written by (kre@munnari.oz.au) for InterNetNews.

SEE ALSO

`innd(8)`, `ctlinnd(8)`, `news.daily(8)`

ipc

`ipc`—System V interprocess communication mechanisms.

SYNOPSIS

```
# include <sys/types.h>
# include <sys/ipc.h>
# include <sys/msg.h>
# include <sys/sem.h>
# include <sys/shm.h>
```

DESCRIPTION

The manual page refers to the Linux implementation of the System V interprocess communication mechanisms: message queues, semaphore sets, and shared memory segments. In the following, the word `resource` means an instantiation of one among such mechanisms.

RESOURCE ACCESS PERMISSIONS

For each resource, the system uses a common structure of type `struct ipc_perm` to store information needed in determining permissions to perform an `ipc` operation. The `ipc_perm` structure, defined by the `<sys/ipc.h>` system header file, includes the following members:

```
ushort cuid; /* creator user id */
ushort cgid; /* creator group id */
ushort uid; /* owner user id */
ushort gid; /* owner group id */
ushort mode; /* r/w permissions */
```

The mode member of the `ipc_perm` structure defines, with its lower nine bits, the access permissions to the resource for a process executing an `ipc` system call. The permissions are interpreted as follows:

0400	Read by user.
0200	Write by user.
0040	Read by group.
0020	Write by group.
0004	Read by others.
0002	Write by others.

Bits 0100, 0010, and 0001 (the execute bits) are unused by the system. Furthermore “write” effectively means “alter” for a semaphore set.

The same system header file defines also the following symbolic constants:

IPC_CREAT	Create entry if key doesn't exists.
IPC_EXCL	Fail if key exists.
IPC_NOWAIT	Error if request must wait.
IPC_PRIVATE	Private key.
IPC_RMID	Remove resource.
IPC_SET	Set resource options.
IPC_STAT	Get resource options.

Note that `IPC_PRIVATE` is a `key_t` type, whereas all the others symbolic constants are flag fields ORable into an `int` type variable.

MESSAGE QUEUES

A message queue is uniquely identified by a positive integer (its `msqid`) and has an associated data structure of type `struct msqid_ds`, defined in `<sys/msg.h>`, containing the following members:

```
struct ipc_perm msg_perm;
ushort msg_qnum; /* no of messages on queue */
ushort msg_qbytes; /* bytes max on a queue */
ushort msg_lspid; /* pid of last msgsnd call */
ushort msg_lrpid; /* pid of last msgrcv call */
time_t msg_stime; /* last msgsnd time */
time_t msg_rtime; /* last msgrcv time */
time_t msg_ctime; /* last change time */
```

<code>msg_perm</code>	<code>ipc_perm</code> structure that specifies the access permissions on the message queue.
<code>msg_qnum</code>	Number of messages currently on the message queue.
<code>msg_qbytes</code>	Maximum number of bytes of message text allowed on the message queue.
<code>msg_lspid</code>	ID of the process that performed the last <code>msgsnd</code> system call.
<code>msg_lrpid</code>	ID of the process that performed the last <code>msgrcv</code> system call.
<code>msg_stime</code>	Time of the last <code>msgsnd</code> system call.
<code>msg_rtime</code>	Time of the last <code>msgrcv</code> system call.
<code>msg_ctime</code>	Time of the last system call that changed a member of the <code>msqid_ds</code> structure.

SEMAPHORE SETS

A semaphore set is uniquely identified by a positive integer (its `semid`) and has an associated data structure of type `struct semid_ds`, defined in `<sys/sem.h>`, containing the following members:

```
struct ipc_perm sem_perm;
time_t sem_otime; /* last operation time */
```

```
time_t sem_ctime; /* last change time */
ushort sem_nsems; /* count of sems in set */
```

<code>sem_perm</code>	<code>ipc_perm</code> structure that specifies the access permissions on the semaphore set.
<code>sem_otime</code>	Time of last <code>semop</code> system call.
<code>sem_ctime</code>	Time of last <code>semctl</code> system call that changed a member of the above structure or of one semaphore belonging to the set.
<code>sem_nsems</code>	Number of semaphores in the set. Each semaphore of the set is referenced by a non-negative integer ranging from 0 to <code>sem_nsems-1</code> .

A semaphore is a data structure of type `struct sem` containing the following members:

```
ushort semval; /* semaphore value */
short sempid; /* pid for last operation */
ushort semncnt; /* no. of awaiting semval to increase */
ushort semzcnt; /* no. of awaiting semval = 0 */
```

<code>semval</code>	Semaphore value: a non-negative integer.
<code>sempid</code>	ID of the last process that performed a semaphore operation on this semaphore.
<code>semncnt</code>	Number of processes suspended awaiting for <code>semval</code> to increase.
<code>semzcnt</code>	Number of processes suspended awaiting for <code>semval</code> to become zero.

SHARED MEMORY SEGMENTS

A shared memory segment is uniquely identified by a positive integer (its `shmid`) and has an associated data structure of type `struct shmid_ds`, defined in `<sys/shm.h>`, containing the following members:

```
struct ipc_perm shm_perm;
int shm_segsz; /* size of segment */
ushort shm_cpid; /* pid of creator */
ushort shm_lpid; /* pid, last operation */
short shm_nattch; /* no. of current attaches */
time_t shm_atime; /* time of last attach */
time_t shm_dtime; /* time of last detach */
time_t shm_ctime; /* time of last change */
```

<code>shm_perm</code>	<code>ipc_perm</code> structure that specifies the access permissions on the shared memory segment.
<code>shm_segsz</code>	Size in bytes of the shared memory segment.
<code>shm_cpid</code>	ID of the process that created the shared memory segment.
<code>shm_lpid</code>	ID of the last process that executed a <code>shmat</code> or <code>shmdt</code> system call.
<code>shm_nattch</code>	Number of current alive attaches for this shared memory segment.
<code>shm_atime</code>	Time of the last <code>shmat</code> system call.
<code>shm_dtime</code>	Time of the last <code>shmdt</code> system call.
<code>shm_ctime</code>	Time of the last <code>shmctl</code> system call that changed <code>shmid_ds</code> .

SEE ALSO

`ftok(3)`, `msgctl(2)`, `msgget(2)`, `msgrcv(2)`, `msgsnd(2)`, `semctl(2)`, `semget(2)`, `semop(2)`, `shmat(2)`, `shmctl(2)`, `shmget(2)`, `shmdt(2)`

Linux 0.99.13, 1 November 1993

issue

`issue`—Issue identification file.

DESCRIPTION

The file `/etc/issue` is a text file that contains a message or system identification to be printed before the login prompt. It may contain various `@char` and `\char` sequences if supported by `getty(1)`.

FILES

`/etc/issue`

SEE ALSO

`getty(1)`, `motd(5)`

Linux, 24 July 1993

lilo.conf

`lilo.conf`—Configuration file for LILO.

DESCRIPTION

This file, by default `/etc/lilo.conf`, is read by the boot loader installer LILO (see `lilo(8)`).

It might look as follows:

```
boot = /dev/hda
delay = 40
compact
vga = normal
root = /dev/hda1
read-only
image = /zImage-1.5.99
        label = try
image = /zImage-1.0.9
        label = 1.0.9
image = /tamuvmlinux
        label = tamu
        root = /dev/hdb2
        vga = ask
other = /dev/hda3
        label = dos
        table = /dev/hda
```

This configuration file specifies that LILO uses the Master Boot Record on `/dev/hda`. (For a discussion of the various ways to use LILO and the interaction with other operating systems, see `user.tex` from the LILO documentation.)

When booting, the boot loader will wait 4 seconds (40 deciseconds) for you to press Shift. If you don't, then the first kernel image mentioned (`/zImage-1.5.99`, which you probably installed just 5 minutes ago) will be booted. If you do, the boot loader will ask you which image to boot. In case you forgot the possible choices, press Tab (or ? if you have a U.S. keyboard), and you will be presented with a menu. You now have the choice of booting this brand new kernel, an old trusted kernel, or a kernel on another root file system (just in case you did something stupid on your usual root) or booting a different operating system. There can be up to 16 images mentioned in `lilo.conf`.

As can be seen previously, a configuration file starts with a number of global options (the top six lines in the example), followed by descriptions of the options for the various images. An option in an image description will override a global option.

GLOBAL OPTIONS

There are many possible keywords. The description that follows is almost literally from `user.tex` (just slightly abbreviated):

<code>backup=backup-file</code>	Copy the original boot sector to <code>backup-file</code> (which may also be a device, such as <code>/dev/null</code>) instead of <code>/boot/boot.NNNN</code> .
<code>boot=boot-device</code>	Sets the name of the device (such as a hard disk partition) that contains the boot sector. If this keyword is omitted, the boot sector is read from (and possibly written to) the device that is currently mounted as root.
<code>compact</code>	Tries to merge read requests for adjacent sectors into a single read request. This drastically reduces load time and keeps the map smaller. Using <code>compact</code> is especially recommended when booting from a floppy disk.
<code>default=name</code>	Uses the specified image as the default boot image. If <code>default</code> is omitted, the image appearing first in the configuration file is used.
<code>delay=tsecs</code>	Specifies the number of tenths of a second the boot loader should wait before booting the first image. This is useful on systems that immediately boot from the hard disk after enabling the keyboard. The boot loader doesn't wait if <code>delay</code> is omitted or is set to zero.
<code>disk=device-name</code>	Defines non-standard parameters for the specified disk. See section "Disk Geometry" of <code>user.tex</code> for details.
<code>disktab=disktab-file</code>	Specifies the name of the disk parameter table. The map installer looks for <code>/etc/disktab</code> if <code>disktab</code> is omitted. The use of disktabs is discouraged.
<code>fix-table</code>	This allows LILO to adjust 3-D addresses in partition tables. Each partition entry contains a 3-D (sector/head/cylinder) and a linear address of the first and the last sector of the partition. If a partition is not track-aligned and if certain other operating systems (such as PC/MS-DOS or OS/2) are using the same disk, they may change the 3-D address. LILO can store its boot sector only on partitions where both address types correspond. LILO readjusts incorrect 3-D start addresses if <code>fix-table</code> is set. Warning: This does not guarantee that other operating systems may not attempt to reset the address later. It is also possible that this change has other, unexpected side effects. The correct fix is to repartition the drive with a program that does align partitions to tracks. Also, with some disks (such as some large EIDE disks with address translation enabled), under some circumstances, it may even be unavoidable to have conflicting partition table entries.
<code>force-backup=backup-file</code>	Like <code>backup</code> but overwrite an old backup copy if it exists.
<code>ignore-table</code>	Tells LILO to ignore corrupt partition tables.
<code>install=boot-sector</code>	Install the specified file as the new boot sector. If <code>install</code> is omitted, <code>/boot/boot.b</code> is used as the default.
<code>linear</code>	Generate linear sector addresses instead of sector/head/cylinder addresses. Linear addresses are translated at runtime and do not depend on disk geometry. Note that boot disks may not be portable if <code>linear</code> is used because the BIOS service to determine the disk geometry does not work reliably for floppy disks. When using <code>linear</code> with large disks, <code>/sbin/lilo</code> may generate references to inaccessible disk areas because 3-D sector addresses are not known before boot time.
<code>lock</code>	Enables automatic recording of boot command lines as the defaults for the following boots. This way, LILO "locks" on a choice until it is manually overridden.
<code>map=map-file</code>	Specifies the location of the map file. If <code>map</code> is omitted, the file <code>/boot/map</code> is used.
<code>message=message-file</code>	Specifies a file containing a message that is displayed before the boot prompt. No message is displayed while waiting for a shifting key after printing <code>LILO</code> . In the message, the <code>FF</code> character (Ctrl+L) clears the local screen. The size of the message file is limited to 65,535 bytes. The map file has to be rebuilt if the message file is changed or moved.
<code>nowarn</code>	Disables warnings about possible future dangers.

<code>optional</code>	The per-image option <code>optional</code> applies to all images.
<code>password=password</code>	The per-image option <code>password=...</code> applies to all images.
<code>prompt</code>	Forces entering the boot prompt without expecting any prior key presses. Unattended reboots are impossible if <code>prompt</code> is set and <code>timeout</code> isn't.
<code>restricted</code>	The per-image option <code>restricted</code> applies to all images.
<code>serial=parameters</code>	Enables control from a serial line. The specified serial port is initialized and the boot loader is accepting input from it and from the PC's keyboard. Sending a break on the serial line corresponds to pressing a Shift key on the console in order to get the boot loader's attention. All boot images should be password-protected if the serial access is less secure than access to the console, such as if the line is connected to a modem. The parameter string has the following syntax: <pre><port>[,<bps>[<parity>[<bits>]]]</pre> <code><port></code>: The number of the serial port, zero-based. 0 corresponds to COM1 alias <code>/dev/ttyS0</code>, and so on. All four ports can be used (if present). <code><bps></code>: The baud rate of the serial port. The following baud rates are supported: 110, 150, 300, 600, 1200, 2400, 4800, and 9600 bps. Default is 2400 bps. <code><parity></code>: The parity used on the serial line. The boot loader ignores input parity and strips the eighth bit. The following (uppercase or lowercase) characters are used to describe the parity: <code>n</code> for no parity, <code>e</code> for even parity, and <code>o</code> for odd parity. <code><bits></code>: The number of bits in a character. Only 7 and 8 bits are supported. Default is 8 if parity is none and 7 if parity is even or odd. If <code>serial</code> is set, the value of <code>delay</code> is automatically raised to 20. For example, <code>serial=0,2400n8</code> initializes COM1 with the default parameters.
<code>timeout=tsecs</code>	Sets a time-out (in tenths of a second) for keyboard input. If no key is pressed for the specified time, the first image is automatically booted. Similarly, password input is aborted if the user is idle for too long. The default time-out is infinite.
<code>verbose=level</code>	Turns on a lot of progress reporting. Higher numbers give more verbose output. If <code>-v</code> is additionally specified on the LILO command line, the level is increased accordingly. The maximum verbosity level is 5.

Additionally, the kernel configuration parameters `append`, `ramdisk`, `read-only`, `read-write`, `root`, and `vga` can be set in the global options section. They are used as defaults if they aren't specified in the configuration sections of the respective kernel images.

PER-IMAGE SECTION

A per-image section starts with either a line

```
image=pathname
```

to indicate a file or device containing the boot image of a Linux kernel or a line

```
other=pathname
```

to indicate an arbitrary system to boot.

In the former case, if an `image` line specifies booting from a device, then one has to indicate the range of sectors to be mapped using

```
range=start-end
```

In the latter case (booting another system), there are the three options:

```
loader=chain-loader
```

This specifies the chain loader that should be used. By default, `/boot/chain.b` is used. The chain loader must be specified if booting from a device other than the first hard or floppy disk.

<code>table=device</code>	This specifies the device that contains the partition table. The boot loader will not pass partition information to the booted operating system if this variable is omitted. (Some operating systems have other means to determine from which partition they have been booted. For example, MS-DOS usually stores the geometry of the boot disk or partition in its boot sector.) Note that <code>/sbin/lilo</code> must be rerun if a partition table mapped referenced with <code>table</code> is modified.
<code>unsafe</code>	Do not access the boot sector at map creation time. This disables some sanity checks, including a partition table check. If the boot sector is on a fixed-format floppy disk device, using <code>UNSAFE</code> avoids the need to put a readable disk into the drive when running the map installer. <code>unsafe</code> and <code>table</code> are mutually incompatible.

In both cases, the following options apply:

<code>label=name</code>	The boot loader uses the main file <code>name</code> (without its path) of each image specification to identify that image. A different name can be used by setting the variable <code>label</code> .
<code>alias=name</code>	A second name for the same entry can be used by specifying an alias.
<code>lock</code>	(See previous description.)
<code>optional</code>	Omit the image if it is not available at map creation time. This is useful to specify test kernels that are not always present.
<code>password=password</code>	Protect the image by a password.
<code>restricted</code>	A password is only required to boot the image if parameters are specified on the command line (such as <code>single</code>).

KERNEL OPTIONS

If the booted image is a Linux kernel, then one may pass command-line parameters to this kernel.

<code>append=string</code>	Appends the options specified to the parameter line passed to the kernel. This is typically used to specify parameters of hardware that can't be entirely autodetected or for which probing may be dangerous. Example: <code>append = "hd=64,32,202"</code> .
<code>literal=string</code>	Like <code>append</code> but removes all other options (such as setting of the root device). Because vital options can be removed unintentionally with <code>literal</code> , this option cannot be set in the global options section.
<code>ramdisk=size</code>	This specifies the size of the optional RAM disk. A value of zero indicates that no RAM disk should be created. If this variable is omitted, the RAM disk size configured into the boot image is used.
<code>read-only</code>	This specifies that the root filesystem should be mounted read-only. Typically, the system startup procedure remounts the root filesystem read-write later (such as after <code>fscking</code> it).
<code>read-write</code>	This specifies that the root filesystem should be mounted read-write.
<code>root=root-device</code>	This specifies the device that should be mounted as root. If the special name <code>current</code> is used, the root device is set to the device on which the root filesystem is currently mounted. If the root has been changed with <code>-r</code> , the respective device is used. If the variable <code>root</code> is omitted, the root device setting contained in the kernel image is used. (That is set at compile time using the <code>ROOT_DEV</code> variable in the kernel makefile and can later be changed with the <code>rdev(8)</code> program.)
<code>vga=mode</code>	This specifies the VGA text mode that should be selected when booting. The following values are recognized (case is ignored): <code>normal</code> : Select normal 80x25 text mode. <code>extended</code> (or <code>ext</code>): Select 80x50 text mode. <code>ask</code> : Stop and ask for user input (at boot time). <code><number></code> : Use the corresponding text mode. A list of available modes can be obtained by booting with <code>vga=ask</code> and pressing Enter.

If this variable is omitted, the VGA mode setting contained in the kernel image is used. (That is set at compile time using the `SVGA_MODE` variable in the kernel makefile and can later be changed with the `rdev(8)` program.)

SEE ALSO

`lilo(8)`, `rdev(8)`. The LILO distribution comes with very extensive documentation of which the preceding information is an extract.

28 July 1995

MAKEDEV.cfg

`MAKEDEV.cfg`—Configuration for `MAKEDEV(8)`.

DESCRIPTION

`MAKEDEV.cfg` is a text file that tells `MAKEDEV(8)` what to do (and equally importantly, what not to do). Unlike `DEVINFO(5)`, which is meant to be centrally maintained, it contains all local configuration for a particular site and all customization. There are basically two kinds of declaration in this file: a “class” declaration and an “omit” declaration.

A class declaration has the form

```
class name : owner group-owner permissions
```

This says that any devices placed in the specified class by `DEVINFO` should be created with this ownership and these permissions. A sample entry might be

```
class public: root system 0666
```

This says that devices marked `public` should be owned by `root.system` and have mode `666`.

An omit declaration has the form

```
omit { device... }
```

This causes the specified devices to never be created, even if explicitly specified. Use caution when setting this up. The intent is to be able to run `MAKEDEV` update and not have it create all sorts of useless devices you’d never use.

SEE ALSO

`MAKEDEV(8)`, `DEVINFO(5)`

Version 1.4, January 1995

moderators

`moderators`—Mail addresses for moderated Usenet newsgroups.

DESCRIPTION

The `GetModeratorAddress(3)` routine reads the file `/news/lib/moderators` to determine how to reach the moderator of a newsgroup. This is used by `inews(1)` when an unapproved local posting is made to a moderated newsgroup.

The file is read until a match is found. Blank lines and lines starting with a number sign (`#`) are ignored. All other lines should consist of two fields separated by a colon.

The first field is a `wildmat(3)`-style pattern. If it matches the name of the newsgroup, then the second field is taken to be a format string for `sprintf(3)`. This string should have at most one `%s` parameter, which will be given the name of the newsgroup with periods transliterated to dashes.

Here is a sample file:

```
foo.important:announce-request@foo.com
foo.*:%s@mailer.foo.com
gnu.*:%s@prep.ai.mit.edu
:%s@uunet.uu.net
```

Using this file, postings to the moderated newsgroup in the left column will be sent to the address shown in the right column:

```
foo.important announce-request@foo.com
foo.x.announce foo-x-announce@mailer.foo.com
gnu.emacs.sources gnu-emacs-sources@prep.ai.mit.edu
comp.sources.unix comp-sources-unix@uunet.uu.net
```

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for InterNetNews.

SEE ALSO

inews(1), inn.conf(5), libinn(3), wildmat(3)

/etc/modules

/etc/modules—Kernel modules to load at boot time.

DESCRIPTION

The */etc/modules* file contains the names of kernel modules that are to be loaded at boot time, one per line. Comments begin with a #, and everything on the line after them are ignored.

Debian GNU/Linux version 0.93

motd

motd—Message of the day.

DESCRIPTION

The contents of */etc/motd* are displayed by *login(1)* after a successful login but just before it executes the login shell.

The *motd* stands for “message of the day,” and this file has been traditionally been used for exactly that. (It requires much less disk space than mail to all users.)

FILES

/etc/motd

SEE ALSO

login(1) *issue(5)*

Linux, 29 December 1992

mtools

mtools—Table of DOS devices.

DESCRIPTION

`/etc/mtools.conf` and `~/mtoolsrc` are the configuration files for `mtools`. These configuration files describe the following items:

- Global configuration flags and variables
- Per-drive flags and variables
- Character translation tables

`/etc/mtools.conf` is the system-wide configuration file, and `~/mtoolsrc` is the user's private configuration file.

GENERAL SYNTAX

The configuration files is made up of sections. Each section starts with a keyword identifying the section followed by a colon. Then follow variable assignments and flags. Variable assignments take the following form:

```
name=value
```

Flags are lone keywords without an equal sign and `value` following them. A section either ends at the end of the file or where the next section begins.

Lines starting with a hash (`#`) are comments. Newline characters are equivalent to whitespace (except where ending a comment). The configuration file is case insensitive, except for items enclosed in quotes (such as filenames).

DEFAULT VALUES

For most platforms, `mtools` contains reasonable compiled-in defaults. You usually don't need to bother with the configuration file, if all you want to do with `mtools` is access your floppy drives. On the other hand, the configuration file is needed if you also want to use `mtools` to access your hard disk partitions and `dosemu` image files.

GLOBAL VARIABLES

Global variables may be set to 1 or to 0.

The following global flags are recognized:

<code>MTTOOLS_SKIP_CHECK</code>	If this is set to 1, <code>mtools</code> skips most of its sanity checks. This is needed to read some Atari disks that have been made with the earlier ROMs and that would not be recognized otherwise.
<code>MTTOOLS_FAT_COMPATIBILITY</code>	If this is set to 1, <code>mtools</code> skips the FAT size checks. Some disks have a bigger FAT than they really need. These are rejected if this option is not set.
<code>MTTOOLS_LOWER_CASE</code>	If this is set to 1, <code>mtools</code> displays all-uppercase short filenames as lowercase. This has been done to allow a behavior that is consistent with older versions of <code>mtools</code> , which didn't know about the case bits.

For example, inserting the following line into your configuration file instructs `mtools` to skip the sanity checks:

```
MTTOOLS_SKIP_CHECK=1.
```

Global variables may also be set via the environment: `export MTTOOLS_SKIP_CHECK=1.`

PER-DRIVE FLAGS AND VARIABLES

Per-drive flags and values may be described in a drive section. A drive section starts with `drive driveletter:`.

Then follow variable-value pairs and flags.

GENERAL PURPOSE DRIVE VARIABLES

The following variables are available:

<code>file</code>	The name of the file or device holding the disk image. This is mandatory. The filename should be enclosed in quotes.

<code>use_xdf</code>	If this is set to a nonzero value, <code>mtools</code> also tries to access this disk as an Xdf disk. Xdf is a high-capacity format used by OS/2. This is off by default.
<code>partition</code>	Tells <code>mtools</code> to treat the drive as a partitioned device and to use the given partition. Only primary partitions are accessible using this method, and they are numbered from 1 to 4. For logical partitions, use the more general <code>offset</code> variable. The <code>partition</code> variable is intended for Syquests, ZIP drives, and DOSEMU hdimages. It is not recommended for hard disks to which direct access to partitions is available.
<code>offset</code>	Describes where in the file the MS-DOS filesystem starts. This is useful for logical partitions in DOSEMU hdimages and for ATARI RAM disks. By default, this is zero, meaning that the filesystem starts right at the beginning of the device or file.
<code>fat_bits</code>	The number of FAT bits. This can be 12 or 16. This is very rarely needed because it can almost always be deduced from information in the boot sector. On the contrary, describing the number of fat bits can actually be harmful if you get it wrong. You should only use it if <code>mtools</code> gets the autodetected number of fat bits wrong or if you want to <code>mformat</code> a disk with a weird number of fat bits.

Only the `file` option is mandatory. The other parameters may be left out. In that case, a default value or an autodetected value is used.

DRIVE GEOMETRY CONFIGURATION

Geometry information describes the physical characteristics about the disk. Its has three purposes:

<code>mformat</code>	The geometry information is written into the boot sector of the newly made disk. However, you may also describe the geometry information on the command line. See <code>mformat(1)</code> for details.
<code>filtering</code>	On some Unices, device nodes only support one physical geometry. The geometry is compared to the actual geometry stored on the boot sector to make sure that this device node is able to correctly read the disk. If the geometry doesn't match, this drive entry fails, and the next drive entry bearing the same drive letter is tried. See the next section "Supplying Multiple Descriptions for a Drive" for more details on supplying several descriptions for a drive letter. If no geometry information is supplied in the configuration file, all disks are accepted. On Linux (and on Sparc), there exist device nodes with configurable geometry (<code>/dev/fd0</code>, <code>/dev/fd1</code> etc), so filtering is not needed (and ignored) for disk drives. (<code>mtools</code> still does do filtering on plain files (disk images) in Linux: This is mainly intended for test purposes because I don't have access to a UNIX that would actually need filtering.)
<code>initial geometry</code>	The geometry information (if available) is also used to set the initial geometry on configurable device nodes. This initial geometry is used to read the boot sector, which contains the real geometry. If no geometry information is supplied in the configuration file, no initial configuration is done. On Linux, this is not really needed either because the configurable devices are able to autodetect the disk type accurately enough (for most common formats) to read the boot sector.

Wrong geometry information may lead to very bizarre errors. That's why I strongly recommend that you don't use geometry configuration unless you really need it.

The following geometry related variables are available:

<code>cylinders</code>	The number of cylinders.
<code>heads</code>	The number of heads (sides).
<code>sectors</code>	The number of sectors per track.

For example, the following drive section describes a 1.44M drive:

```
drive a:
file="/dev/fd0H1440"
fat_bits=12
tracks=80 heads=2 sectors=18
```

The following shorthand geometry descriptions are available:

1.44M	High density, 3 1/2 disk. Equivalent to fat_bits=12 tracks=80 heads=2 sectors=18.
1.2M	High density, 5 1/4 disk. Equivalent to fat_bits=12 tracks=80 heads=2 sectors=15.
720K	Double density, 3 1/2 disk. Equivalent to fat_bits=12 tracks=80 heads=2 sectors=9.
360K	Double density, 5 1/4 disk. Equivalent to fat_bits=12 tracks=40 heads=2 sectors=9.

The shorthand format descriptions may be amended. For example, 360K sectors=8 describes a 320K disk and is equivalent to fat_bits=12 tracks=40 heads=2 sectors=8.

OPEN FLAGS

Moreover, the following flags are available:

sync	All I/O operations are done synchronously.
nodelay	The device or file is opened with the <code>O_NDELAY</code> flag. This is needed on some non-Linux architectures.
exclusive	The device or file is opened with the <code>O_EXCL</code> flag. On Linux, this ensures exclusive access to the floppy drive. On most other architectures and for plain files, it has no effect at all.

SUPPLYING MULTIPLE DESCRIPTIONS FOR A DRIVE

It is possible to supply multiple descriptions for a drive. In that case, the descriptions are tried in order until one is found that fits. Descriptions may fail for several reasons:

- The geometry is not appropriate
- There is no disk in the drive
- Other problems

Multiple definitions are useful when using physical devices that are only able to support one single disk geometry:

```
drive a: file="/dev/fd0H1440" 1.44m
drive a: file="/dev/fd0H720" 720k
```

This instructs mtools to use `/dev/fd0H1440` for 1.44M (high density) disks and `/dev/fd0H720` for 720K (double density) disks. On Linux, this feature is not really needed because the `/dev/fd0` device is able to handle any geometry.

You can also use multiple drive descriptions to access both of your physical drives through one drive letter:

```
drive z: file="/dev/fd0"
drive z: file="/dev/fd1"
```

With this description, `mdir z:` accesses your first physical drive if it contains a disk. If the first drive doesn't contain a disk, mtools checks the second drive.

When using multiple configuration files, drive descriptions in the files parsed last override descriptions for the same drive in earlier files. In order to avoid this, use the `drive+` or `+drive` keywords instead of `drive`. The first adds a description to the end of the list (will be tried last), and the second adds it to the start of the list.

CHARACTER TRANSLATION TABLES

If you live in the USA, in Western Europe, or in Australia, you can skip this section.

INTRODUCTION

DOS uses a different character code mapping from UNIX. Seven-bit characters still have the same meaning; only characters with the eight-bit set are affected. To make matters worse, there are several translation tables available depending on the country where you are. The appearance of the characters is defined using code pages. These code pages aren't the same for all countries. For instance, some code pages don't contain upper -case accented characters. On the other hand, some code pages contain characters that don't exist in UNIX, such as certain line-drawing characters or accented consonants used by some Eastern European countries. This affects two things relating to filenames:

Uppercase characters	In short names, only uppercase characters are allowed. This also holds for accented characters. For instance, in a code page that doesn't contain accented uppercase characters, the accented lowercase characters get transformed into their unaccented counterparts.
Long filenames	Microsoft has finally come to their senses and uses a more standard mapping for the long filenames. They use Unicode, which is basically a 32-bit version of ASCII. Its first 256 characters are identical to UNIX ASCII. Thus, the code page also affects the correspondence between the codes used in long names and those used in short names.

`mttools` considers the filenames entered on the command line as having the UNIX mapping and translates the characters to get short names. By default, code page 850 is used with the Swiss uppercase/lowercase mapping. I chose this code page because its set of existing characters most closely matches UNIX's. Moreover, this code page covers most characters in use in the USA, Australia, and Western Europe. However, it is still possible to chose a different mapping. There are two methods: the country variable and explicit tables.

CONFIGURATION USING COUNTRY

The `COUNTRY` variable is recommended for people that also have access to MS-DOS system files and documentation. If you don't have access to these, I'd suggest you use explicit tables instead.

Syntax: `COUNTRY=" country [, [ codepage ], country.sys ]"`

This tells `mttools` to use a UNIX-to-DOS translation table that matches `codepage` and an lowercase-to-uppercase table for `country` and to use the `country.sys` file to get the lowercase-to-uppercase table. The `country` code is most often the telephone prefix of the country. Refer to the DOS help page on `country` for more details. The `codepage` and the `country.sys` parameters are optional. Don't type in the square brackets; they are only there to indicate which parameters are optional. The `country.sys` file is supplied with MS-DOS. In most cases, you don't need it because the most common translation tables are compiled into `mttools`. Don't worry if you run a UNIX-only box that lacks this file.

If `codepage` is not given, a per-country default code page is used. If the `country.sys` parameter isn't given, compiled-in defaults are used for the lowercase-to-uppercase table. This is useful for other Unices than Linux, which may have no `country.sys` file available online.

The UNIX-to-DOS are not contained in the `country.sys` file, and thus `mttools` always uses compiled-in defaults for those. Thus, only a limited amount of code pages are supported. If your preferred code page is missing, or if you know the name of the Windows 95 file that contains this mapping, drop me a line at Alain.Knauff@inrialpes.fr.

The `COUNTRY` variable can also be set using the environment.

CONFIGURATION USING EXPLICIT TRANSLATION TABLES

Translation tables may be described in lines in the configuration file. Two tables are needed: first the DOS-to-UNIX table and then the lowercase-to-uppercase table. A DOS-to-UNIX table starts with the `tounix` keyword, followed by a colon and 128 hexadecimal numbers. A lower-to-upper table starts with the `fucase` keyword, followed by a colon and 128 hexadecimal numbers.

The tables only show the translations for characters whose codes is greater than 128 because translation for lower codes is trivial. Example:

tounix:

```
0xc7 0xfc 0xe9 0xe2 0xe4 0xe0 0xe5 0xe7
0xea 0xeb 0xe8 0xef 0xee 0xec 0xc4 0xc5
0xc9 0xe6 0xc6 0xf4 0xf6 0xf2 0xfb 0xf9
0xff 0xd6 0xdc 0xf8 0xa3 0xd8 0xd7 0x5f
0xe1 0xed 0xf3 0xfa 0xf1 0xd1 0xaa 0xba
0xbf 0xae 0xac 0xbd 0xbc 0xa1 0xab 0xbb
0x5f 0x5f 0x5f 0x5f 0x5f 0xc1 0xc2 0xc0
0xa9 0x5f 0x5f 0x5f 0x5f 0xa2 0xa5 0xac
0x5f 0x5f 0x5f 0x5f 0x5f 0x5f 0xe3 0xc3
0x5f 0x5f 0x5f 0x5f 0x5f 0x5f 0x5f 0xa4
0xf0 0xd0 0xc9 0xcb 0xc8 0x69 0xcd 0xce
0xcf 0x5f 0x5f 0x5f 0x5f 0x7c 0x49 0x5f
0xd3 0xdf 0xd4 0xd2 0xf5 0xd5 0xb5 0xfe
0xde 0xda 0xd9 0xfd 0xdd 0xde 0xaf 0xb4
0xad 0xb1 0x5f 0xbe 0xb6 0xa7 0xf7 0xb8
0xb0 0xa8 0xb7 0xb9 0xb3 0xb2 0x5f 0x5f
```

fucase:

```
0x80 0x9a 0x90 0xb6 0x8e 0xb7 0x8f 0x80
0xd2 0xd3 0xd4 0xd8 0xd7 0xde 0x8e 0x8f
0x90 0x92 0x92 0xe2 0x99 0xe3 0xea 0xeb
0x59 0x99 0x9a 0x9d 0x9c 0x9d 0x9e 0x9f
0xb5 0xd6 0xe0 0xe9 0xa5 0xa6 0xa7
0xa8 0xa9 0xaa 0xab 0xac 0xad 0xae 0xaf
0xb0 0xb1 0xb2 0xb3 0xb4 0xb5 0xb6 0xb7
0xb8 0xb9 0xba 0xbb 0xbc 0xbd 0xbe 0xbf
0xc0 0xc1 0xc2 0xc3 0xc4 0xc5 0xc7 0xc7
0xc8 0xc9 0xca 0xcb 0xcc 0xcd 0xce 0xcf
0xd1 0xd1 0xd2 0xd3 0xd4 0x49 0xd6 0xd7
0xd8 0xd9 0xda 0xdb 0xdc 0xdd 0xde 0xdf
0xe0 0xe1 0xe2 0xe3 0xe5 0xe5 0xe6 0xe8
0xe8 0xe9 0xea 0xeb 0xed 0xed 0xee 0xef
0xf0 0xf1 0xf2 0xf3 0xf4 0xf5 0xf6 0xf7
0xf8 0xf9 0xfa 0xfb 0xfc 0xfd 0xfe 0xff
```

The first table maps DOS character codes to UNIX character codes. For example, the DOS character number 129 is a u with two dots on top of it. To translate it into UNIX, we look at the character number 1 in the first table (1 = 129 - 128). This is 0xfc. (Beware; numbering starts at 0.) The second table maps lowercase DOS characters to uppercase DOS characters. The same lowercase u with dots maps to character 0x9a, which is an uppercase U with dots in DOS.

UNICODE CHARACTERS GREATER THAN 256

If an existing MS-DOS name contains Unicode character greater than 256, these are translated to underscores or to characters that are close in visual appearance. For example, accented consonants are translated into their unaccented counterparts. This translation is used for `mdir` and for the UNIX filenames generated by `mcopy`. Linux does support Unicode too, but unfortunately, too few applications support it yet to bother with it in `mtools`. Most importantly, `xterm` can't display Unicode yet. If there is sufficient demand, I might include support for Unicode in the UNIX filenames as well.

Caution: When deleting files with `mtools`, the underscore matches all characters that can't be represented in UNIX. Be careful before `mdel`!

LOCATION OF CONFIGURATION FILES AND PARSING ORDER

The configuration files are parsed in the following order:

Compiled-in defaults

```
/etc/mtools.conf
/etc/mtools. This is for backwards compatibility only and is only parsed if mtools.conf doesn't exist.
~/.mtoolsrc
```

Options described in the later files override those described in the earlier files. Drives defined in earlier files persist if they are not overridden in the later files. For instance, drives A and B may be defined in `/etc/mtools.conf` and drives C and D may be defined in `~/.mtoolsrc`. However, if `~/.mtoolsrc` also defines drive A, this new description would override the description of drive A in `/etc/mtools.conf` instead of adding to it. If you want to add a new description to a drive already described in an earlier file, you need to use either the `+drive` or `drive+` keywords.

BACKWARDS COMPATIBILITY

The syntax described herein is new for version `mtools 2.5.4`. The old line-oriented syntax is still supported. Each line beginning with a single letter is considered to be a drive description using the old syntax. Old style and new style drive sections may be mixed within the same configuration file to make upgrading easier. Support for the old syntax will be phased out eventually, and to discourage its use, I purposefully omit its description here.

FILES

```
/etc/mtools.conf
~/.mtoolsrc
```

SEE ALSO

`mtools(1)`

5 December 1995

newsfeeds

`newsfeeds`—Determine where Usenet articles get sent.

DESCRIPTION

The file `/news/lib/newsfeeds` specifies how incoming articles should be distributed to other sites. It is parsed by the InterNetNews server `innd(8)` when it starts up or when directed to by `ctlinnd(8)`.

The file is interpreted as a set of lines according to the following rules. If a line ends with a backslash, then the backslash, the newline, and any whitespace at the start of the next line is deleted. This is repeated until the entire “logical” line is collected. If the logical line is blank or starts with a number sign (`#`), it is ignored.

All other lines are interpreted as feed entries. An entry should consist of four colon-separated fields; two of the fields may have optional subfields, marked off by a slash. Fields or subfields that take multiple parameters should be separated by a comma. Extra whitespace can cause problems. Except for the site names, case is significant. The format of an entry is

```
sitename[/exclude,exclude,...]\
:pattern,pattern...[/distrib,distrib...]\
:flag,flag...\
:param
```

Each field is described below.

The `sitename` is the name of the site to which a news article can be sent. It is used for writing log entries and for determining if an article should be forwarded to a site. If `sitename` already appears in the article's Path header, then the article will not be sent to the site. The name is usually whatever the remote site uses to identify itself in the Path line but can be almost any word that makes sense; special local entries (such as archivers or gateways) should probably end with an exclamation point to make sure that they do not have the same name as any real site. For example, `gateway` is an obvious name for the local entry that forwards articles out to a mailing list. If a site with the name `gateway` posts an article, when the local site receives the

article, it will see the name in the Path and not send the article to its own gateway entry. If an entry has an exclusion subfield, then the article will not be sent to that site if any of the names specified as excludes appear in the Path header. The same sitename can be used more than once; the appropriate action will be taken for each site that should receive the article, regardless of the name, although this is recommended only for program feeds to avoid confusion. Case is not significant in site names.

The patterns specify which groups to send to the site and are interpreted to build a “subscription list” for the site. The default subscription is to get all groups. The patterns in the field are `wildmat(3)`-style patterns and are matched in order against the list of newsgroups that the local site receives. If the first character of a pattern is an exclamation mark, then any groups matching the pattern are removed from the subscription; otherwise, any matching groups are added. For example, to receive all `comp` groups but only `comp.sources.unix` within the `sources` newsgroups, the following set of patterns can be used:

```
comp.*,!comp.sources.*,comp.sources.unix
```

There are three things to note about this example. The first is that the trailing `.*` is required. The second is that, again, the result of the last match is the most important. The third is that `comp.sources.*` could be written as `comp.sources*`, but this would not have the same effect if there were a `comp.sources-only` group.

See `innd(8)` for details on the propagation of control messages.

A subscription can be further modified by specifying “distributions” that the site should or should not receive. The default is to send all articles to all sites that subscribe to any of the groups where it has been posted, but if an article has a Distribution header and any `distribs` are specified, then they are checked according to the following rules:

1. If the Distribution header matches any of the values in the subfield, then the article is sent.
2. If a `distrib` starts with an exclamation point and it matches the Distribution header, then the article is not sent.
3. If Distribution header does not match any `distrib` in the site’s entry and no negations were used, then the article is not sent.
4. If Distribution header does not match any `distrib` in the site’s entry and any `distrib` started with an exclamation point, then the article is sent.

If an article has more than one distribution specified, then each one is evaluated according to the preceding rules. If any of the specified distributions indicate that the article should be sent, it is. If none do, it is not sent: The rules are used as a “logical or.” It is almost definitely a mistake to have a single feed that specifies distributions that start with an exclamation point along with some that don’t.

Distributions are text words, not patterns; it is usually a mistake to have entries like `*` or `all` there.

The `flags` parameter specifies miscellaneous parameters. They may be specified in any order; flags that take values should have the value immediately after the flag letter with no whitespace. The valid flags are

<code>< size</code>	An article will only be sent to the site if it is less than <code>size</code> bytes long. The default is no limit.
<code>A checks</code>	An article will only be sent to the site if it meets the requirements specified in the checks, which should be chosen from the following set: <code>d</code> Distribution header required <code>p</code> Do not check Path header before propagating.
<code>B high/low</code>	If a site is being fed by a file, channel, or exploder, the server will usually start trying to write the information as soon as possible. Providing a buffer may give better system performance and help smooth out overall load if a large batch of news comes in. The value of the this flag should be two numbers separated by a slash. The first specifies the point at which the server can start draining the feed’s I/O buffer, and the second specifies when to stop writing and begin buffering again; the units are bytes. The default is to do no buffering, sending output as soon as it is possible to do so.
<code>F name</code>	This flag specifies the name of the file that should be used if it is necessary to begin spooling for the site. If <code>name</code> is not an absolute pathname, it is taken to be relative to <code>/news/spool/out.going</code> . Then, if the destination is a directory, the file to go in that directory will be used as filename.

G count	If this flag is specified, an article will only be sent to the site if it is posted to no more than <code>count</code> newsgroups.
H count	If this flag is specified, an article will only be sent to the site if it has <code>count</code> or fewer sites in its Path line. This flag should only be used as a rough guide because of the loose interpretation of the Path header; some sites put the poster's name in the header, and some sites that might logically be considered to be one hop become two because they put the posting workstation's name in the header. The default value for <code>count</code> is one.
I size	The flag specifies the size of the internal buffer for a file feed. If there are more file feeds than allowed by the system, they will be buffered internally in least recently used order. If the internal buffer grows bigger than <code>size</code> bytes, however, the data will be written out to the appropriate file.
N modifiers	The newsgroups that a site receives are modified according to the modifiers, which should be chosen from the following set: m Only moderated groups u Only unmoderated groups
S size	If the amount of data queued for the site gets to be larger than <code>size</code> bytes, then the server will switch to spooling, appending to a file specified by the F flag or <code>/news/spool/out.going/sitename</code> if the F flag is not specified. Spooling usually happens only for channel or exploder feeds.
T type	This flag specifies the type of feed for the site. <code>type</code> should be a letter chosen from the following set: c Channel f File l Log entry only m Funnel (multiple entries feed into one) p Program x Exploder. Each feed is described in the section on feed types. The default is <code>tf</code> .
W items	If a site is fed by file, channel, or exploder, this flag controls what information is written. If a site is fed by a program, only the asterisk (*) has any effect. The items should be chosen from the following set: b Size of the article in bytes. f Article's full pathname. g The newsgroup the article is in; if cross-posted, then the first of the groups this site gets. m Article's Message-ID. n Article's pathname relative to the spool directory. p The site that fed the article to the server; from the Path header. s The IP address of the site that sent the article. t Time article was received as seconds since epoch. * Names of the appropriate funnel entries; or all sites that get the article. D Value of the Distribution header; ? if none present. H All headers. N Value of the Newsgroups header. O Overview data. R Information needed for replication. More than one letter can be used; the entries will be separated by a space and written in the order in which they are specified. The default is <code>wn</code>.

The `H` and `O` items are intended for use by programs that create news overview databases. If `H` is present, then all the article's headers are written followed by a blank line. An `Xref` header (even if one does not appear in the filed article) and a `Bytes` header, specifying the article's size, will also be part of the headers. If used, this should be the only item in the list; if preceded by other items, however, a newline will be written before the headers. The `O` generates input to the `overchan(8)` program. It, too, should be the only item in the list.

The asterisk has special meaning. It expands to a space-separated list of all sites that received the current article. If the site is the target of a funnel, however (that is, it is named by other sites that have a `Tm` flag), then the asterisk expands to the names of the funnel feeds that received the article. If the site is fed by a program, then an asterisk in the `param` field will be expanded into the list of funnel feeds that received the article. A site fed by a program cannot get the site list unless it is the target of other `Tm` feeds.

The interpretation of the `param` field depends on the type of feed, and is explained in more detail in the section on feed types. It can be omitted.

The site named `ME` is special. There should only be one such entry, and it should be the first entry in the file. If the `ME` entry has a subscription list, then that list is automatically prepended to the subscription list of all other entries. For example, `*,!control,!junk,!foo.*` can be used to set up the initial subscription list for all feeds so that local postings are not propagated unless `foo.*` explicitly appears in the site's subscription list. Note that most subscriptions should have `!junk,!control` in their pattern list; see the discussion of control messages in `innd(8)`. (Unlike other news software, it does not affect what groups are received; that is done by the `active(5)` file.)

If the `ME` entry has a distribution subfield, then only articles that match the distribution list are accepted; all other articles are rejected. A commercial news server, for example, might have `!/local` to reject local postings from other, misconfigured, sites.

FEED TYPES

`innd` provides four basic types of feeds: `log`, `file`, `program`, and `channel`. An `exploder` is a special type of `channel`. In addition, several entries can feed into the same feed; these are funnel feeds, which refer to an entry that is one of the other types. Note that the term "feed" is technically a misnomer because the server does not transfer articles but reports that an article should be sent to the site.

The simplest feed is one that is fed by a `log` entry. Other than a mention in the news logfile, no data is ever written out. This is equivalent to a `Tf` entry writing to `/dev/null` except that no file is opened.

A site fed by a file is simplest type of feed. When the site should receive an article, one line is written to the file named by the `param` field. If `param` is not an absolute pathname, it is taken to be relative to `/news/spool/out.going`. If empty, the filename defaults to `/news/spool/out.going/sitename`. This name should be unique.

When a site fed by a file is flushed (see `ctlinnd`), the following steps are performed. The script doing the flush should have first renamed the file. The server tries to write out any buffered data and then closes the file. The renamed file is now available for use. The server will then reopen the original file, which will now get created.

A site fed by a program has a process spawned for every article that the site receives. The `param` field must be a `sprintf(3)` format string that may have a single `%s` parameter, which will be given a pathname for the article, relative to the news spool directory. The full pathname may be obtained by prefixing the `%s` in the `param` field by the news spool directory prefix. Standard input will be set to the article or `/dev/null` if the article cannot be opened for some reason. Standard output and error will be set to the error log. The process will run with the user and group ID of the `/news/lib/innd` directory. `innd` will try to avoid spawning a shell if the command has no shell meta-characters; this feature can be defeated by appending a semicolon to the end of the command. The full pathname of the program to be run must be specified; for security, `PATH` is not searched.

If the entry is the target of a funnel, and if the `w*` flag is used, then a single asterisk may be used in the `param` field where it will be replaced by the names of the sites that fed into the funnel. If the entry is not a funnel, or if the `w*` flag is not used, then the asterisk has no special meaning.

Flushing a site fed by a program does no action.

When a site is fed by a channel or exploder, the `param` field names the process to start. Again, the full pathname of the process must be given. When the site is to receive an article, the process receives a line on its standard input telling it about the article. Standard output and error and the user and group ID of the all subprocess are set as for a program feed. If the process exits, it will be restarted. If the process cannot be started, the server will spool input to a file named `/news/spool/out.going/sitename`. It will then try to start the process some time later.

When a site fed by a channel or exploder is flushed, the server closes down its end of the pipe. Any pending data that has not been written will be spooled; see the description of the `s` flag. No signal is sent; it is up to the program to notice EOF on its standard input and exit. The server then starts a new process.

Exploders are a superset of channel feeds. In addition to channel behavior, exploders can be sent command lines. These lines start with an exclamation point, and their interpretation is up to the exploder. The following messages are generated automatically by the server:

```
newgroup group
rmgroup group
flush
flush site
```

These messages are sent when the `ctlinn` command of the same name is received by the server. In addition, the `send` command can be used to send an arbitrary command line to the exploder child-process. The primary exploder is `buffchan(8)`.

Funnel feeds provide a way of merging several site entries into a single output stream. For a site feeding into a funnel, the `param` field names the actual entry that does the feeding.

For more details on setting up different types of news feeds, see the INN installation manual.

EXAMPLES

```
## Initial subscription list and our distributions.
ME:*,!junk,!foo.*/*world,usa,na,ne,foo,ddn,gnu,inet\
::
## Feed all moderated source postings to an archiver
source-archive!:*/*comp.sources.*\
:Tp,Nm:/usr/local/bin/archive %s
## Watch for big postings
watcher!:*\
:Tc,WbNm\
:exec awk '$1 > 1000000 { print "BIG", $2, $3 }' >/dev/console
## A UUCP feed, where we try to keep the "batching" between 4 and 1K.
ihnp4:/world,usa,na,ddn,gnu\
:Tf,Wfb,B4096/1024:
## Usenet as mail; note ! in funnel name to avoid Path conflicts.
## Can't use ! in "fred" since it would like look a UUCP address.
fred!:*/*comp.sources.unix,comp.sources.bugs\
:Tm:mailer!
barney@bar.com!:*/*news.software.nnntp,comp.sources.bugs\
:Tm:mailer!
mailer!:*\
:W*,Tp:/usr/ucb/Mail -s "News article" *
## NNTP feeds fed off-line via nntpsend or equivalent.
feed1::Tf,Wnm:feed1.domain.name
peer.foo.com:foo.*:Tf,Wnm:peer.foo.com
## Real-time transmission.
mit.edu:/world,usa,na,ne,ddn,gnu,inet\
:Tc,Wnm:/nntplink -i stdin mit.edu
## Two sites feeding into a hypothetical NNTP fan-out program:
nic.near.net:\
:Tm:nntpfunnel1
```

```

uunet.uu.net/uunet:line.*/world,usa,na,foo,ddn,gnu,inet\
:Tm:nntpfunnel1
nntpfunnel1:!*\\
:Tc,Wmn*/nntpfanout
## A UUCP site that wants comp.* and moderated soc groups
uucpsite!comp:!* ,comp.*/world,usa,na,gnu\
:Tm:uucpsite
uucpsite!soc:!* ,soc.*/world,usa,na,gnu\
:Tm,Nm:uucpsite
uucpsite:!*\\
:Tf,Wfb:/usr/spool/batch/uucpsite

```

The last two sets of entries show how funnel feeds can be used. For example, the nntpfanout program would receive lines like the following on its standard input:

```

<123@litchi.foo.com> comp/sources/unix/888 nic.near.net uunet.uu.net
<124@litchi.foo.com> ne/general/1003 nic.near.net

```

Because the UUCP funnel is only destined for one site, the asterisk is not needed and entries like the following will be written into the file:

```

<qwe#37x@snark.uu.net>comp/society/folklore/3
<123@litchi.foo.com> comp/sources/unix/888

```

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for InterNetNews.

SEE ALSO

active(5), buffchan(8), ctlinnd(8), innd(8), wildmat(3)

newslog

newslog—Description of Usenet log files.

DESCRIPTION

Most log files created by Usenet programs reside in the /var/log/news directory and have a .log extension. Several versions are usually kept with an additional extension such as .1, .2, and so on; the higher the number, the older the log. The older versions are compressed.

The scanlogs script and related utilities (see newslog(8)) are responsible for rotating and compressing these files.

Some log files always have data, others only have data if there is a problem, and others are only created if a particular program is used or configuration parameter is set. The innstat script (see newslog(8)) monitors the size of all log files.

The following files will only accumulate data under the direction of control.ct1(5):

control.log, miscctl.log, newgroup.log, rmgroup.log, unwanted.log

In order to create these files, the message and action fields of control.ct1 should be chosen from the following table:

<i>Message</i>	<i>Action</i>	<i>Meaning</i>
all	log=miscctl	Log all messages by default
default	log=miscctl	Log unknown messages
newgroup	doit=newgroup	Create group and log message
newgroup	log=newgroup	Log message

continues

<i>Message</i>	<i>Action</i>	<i>Meaning</i>
rmgroup	doit=rmgroup	Remove group and log message
rmgroup	log=rmgroup	Log message
“other”	doit=miscctl	Log and process the message
“other”	log=miscctl	Log message

Here, “other” refers to any other control message such as:

```
checkgroups ihave sendme sendsys senduname version
```

The following is a list of log files.

control.log	This file maintains a count of the number of newgroup and rmgroup control messages seen for each newsgroup. The count is of the number of control messages with identical arguments, regardless of whether they were actually processed. All control arguments, including invalid ones, are counted. This file is updated by tally.control, which is invoked by scanlogs if either the newgroup or rmgroup logs exist. This file is not rotated.
errlog	This file contains the standard output and standard error of any program spawned by innd(8). The most common programs are the control-message handlers found in /news/bin/control. This file should be empty. Scanlogs will print the entire contents of this log file if it is non-empty.
expire.log	By default, when news.daily is going to expire old news articles, it writes the date to this file, followed by any output from expire(8) and the ending date. All lines but the first are indented four spaces.
miscctl.log	When control.ct1 is configured as described above, all control messages except newgroup and rmgroup are appended to this file by writelog. There will be a summary line describing the message and the action taken, followed by the article indented by four spaces and a blank line.
newgroup.log	When control.ct1 is configured as described above, all newgroup messages are appended to this file using the same format as for miscctl.log.
news	This file logs articles received by innd. scanlogs summarizes the rejected articles reported in this file.
news.crit	All critical error messages issued by innd are appended to this file via syslog(3). This log file should be empty. scanlogs will print the entire contents of this log file if it is non-empty. You should have the following line in your syslog.conf(5) file: news.crit /var/log/news/news.crit
news.err	All major error messages issued by innd are appended to this file via syslog. This log file should be empty. scanlogs will print the entire contents of this log file if it is non-empty. You should have the following line in your syslog.conf file: news.err /var/log/news/news.err
news.notice	All standard error messages and status messages issued by innd are appended to this file via syslog. scanlogs uses the awk(1) script innlog.awk to summarize this file. You should have the following line in your syslog.conf file: news.notice /var/log/news/news.notice
nntpsend.log	The nntpsend(8) programs appends all status messages to this file.
rmgroup.log	When control.ct1 is configured as described previously, all rmgroup messages are appended to this file using the same format as for miscctl.log.
unwanted.log	This log maintains a count of the number of articles that were rejected because they were posted to newsgroups that do not exist at the local site. This file is updated by tally.unwanted and maintained in reverse numeric order (the most popular rejected group first). This file is not rotated.

HISTORY

Written by Landon Curt Noll (chongo@toad.com) and Rich \$alz (rsalz@uunet.uu.net) for InterNetNews.

SEE ALSO

control.ctl(5), ctlinnd(8), expire(8), innd(8), news.daily(8), nntpsend(8), newslog(8)

nfs

nfs—NFS fstab format and options.

SYNOPSIS

/etc/fstab

DESCRIPTION

The fstab file contains information about which filesystems to mount where and with what options. For NFS mounts, it contains the server name and exported server directory to mount from, the local directory that is the mount point, and the NFS-specific options that control the way the filesystem is mounted. Here is an example from an /etc/fstab file from an NFS mount.

```
server:/usr/local/pub /pub nfs rsize=8192,wsiz=8192,timeo=14,intr
```

OPTIONS

rsize=n	The number of bytes NFS uses when reading files from an NFS server. The default value is dependent on the kernel, currently 1024 bytes. (However, throughput is improved greatly by asking for rsize=8192.)
wsiz=n	The number of bytes NFS uses when writing files to an NFS server. The default value is dependent on the kernel, currently 1024 bytes. (However, throughput is improved greatly by asking for wsiz=8192.)
timeo=n	The value in tenths of a second before sending the first retransmission after an RPC time-out. The default value is 7 tenths of a second. After the first time-out, the time-out is doubled after each successive time-out until a maximum time-out of 60 seconds is reached or the enough retransmissions have occurred to cause a major time-out. Then, if the filesystem is hard mounted, each new time-out cascade restarts at twice the initial value of the previous cascade, again doubling at each retransmission. The maximum time-out is always 60 seconds. Better overall performance may be achieved by increasing the time-out when mounting on a busy network, to a slow server, or through several routers or gateways.
retrans=n	The number of minor time-outs and retransmissions that must occur before a major time-out occurs. The default is 3 time-outs. When a major time-out occurs, the file operation is either aborted or a “server not responding” message is printed on the console.
acregmin=n	The minimum time in seconds that attributes of a regular file should be cached before requesting fresh information from a server. The default is 3 seconds.
acregmax=n	The maximum time in seconds that attributes of a regular file can be cached before requesting fresh information from a server. The default is 60 seconds.
acdirmin=n	The minimum time in seconds that attributes of a directory should be cached before requesting fresh information from a server. The default is 30 seconds.
acdirmax=n	The maximum time in seconds that attributes of a directory can be cached before requesting fresh information from a server. The default is 60 seconds.
actimeo=n	Using actimeo sets all of acregmin, acregmax, acdirmin, and acdirmax to the same value. There is no default value.

<code>retry=n</code>	The number of times to retry a backgrounded NFS mount operation before giving up. The default value is 10000 times.
<code>namlen=n</code>	When an NFS server does not support version 2 of the RPC mount protocol, this option can be used to specify the maximum length of a filename that is supported on the remote filesystem. This is used to support the POSIX <code>pathconf</code> functions. The default is 255 characters.
<code>port=n</code>	The numeric value of the port to connect to the NFS server on. If the port number is 0 (the default) then query the remote host's port mapper for the port number to use. If the remote host's NFS daemon is not registered with its port mapper, the standard NFS port number 2049 is used instead.
<code>mountport=n</code>	The numeric value of the <code>mountd</code> port.
<code>mounthost=name</code>	The name of the host running <code>mountd</code> .
<code>mountprog=n</code>	Use an alternate RPC program number to contact the mount daemon on the remote host. This option is useful for hosts that can run multiple NFS servers. The default value is 100005, which is the standard RPC mount daemon program number.
<code>mountvers=n</code>	Use an alternate RPC version number to contact the mount daemon on the remote host. This option is useful for hosts that can run multiple NFS servers. The default value is version 1.
<code>nfsprog=n</code>	Use an alternate RPC program number to contact the NFS daemon on the remote host. This option is useful for hosts that can run multiple NFS servers. The default value is 100003, which is the standard RPC NFS daemon program number.
<code>nfsvers=n</code>	Use an alternate RPC version number to contact the NFS daemon on the remote host. This option is useful for hosts that can run multiple NFS servers. The default value is version 2.
<code>bg</code>	If the first NFS mount attempt times out, continue trying the mount in the background. The default is to not to background the mount on time-out but to fail.
<code>fg</code>	If the first NFS mount attempt times out, fail immediately. This is the default.
<code>soft</code>	If an NFS file operation has a major time-out, then report an I/O error to the calling program. The default is to continue retrying NFS file operations indefinitely.
<code>hard</code>	If an NFS file operation has a major time-out, then report "server not responding" on the console and continue retrying indefinitely. This is the default.
<code>intr</code>	If an NFS file operation has a major time-out and it is hard mounted, then allow signals to interrupt the file operation and cause it to return <code>EINTR</code> to the calling program. The default is to not allow file operations to be interrupted.
<code>posix</code>	Mount the NFS filesystem using POSIX semantics. This allows an NFS filesystem to properly support the POSIX <code>pathconf</code> command by querying the mount server for the maximum length of a filename. To do this, the remote host must support version 2 of the RPC mount protocol. Many NFS servers support only version 1.
<code>nocto</code>	Suppress the retrieval of new attributes when creating a file.
<code>noac</code>	Disable all forms of attribute caching entirely. This extracts a server performance penalty, but it allows two different NFS clients to get reasonably good results when both clients are actively writing to a common filesystem on the server.
<code>tcp</code>	Mount the NFS filesystem using the TCP protocol instead of the default UDP protocol. Many NFS servers only support UDP.
<code>udp</code>	Mount the NFS filesystem using the UDP protocol. This is the default. All the non-value options have corresponding <code>nooption</code> forms. For example, <code>nointr</code> means don't allow file operations to be interrupted.

FILES

`/etc/fstab`

SEE ALSO

fstab(5), mount(8), umount(8), exports(5)

AUTHOR

Rick Sladkey (jrs@world.std.com)

BUGS

The `bg`, `fg`, `retry`, `posix`, and `nocto` options are parsed by `mount` but currently are silently ignored. The `tcp` and `namlen` options are implemented but are not currently supported by the Linux kernel. The `umount` command should notify the server when an NFS filesystem is unmounted.

Linux 0.99, 20 November 1993

nnrp.access

`nnrp.access`—Access file for on-campus NNTP sites.

DESCRIPTION

The file `/news/lib/nnrp.access` specifies the access control for those NNTP sites that are not handled by the main InterNetNews daemon `inn(8)`. The `nnrpd(8)` server reads it when first spawned by `inn`.

Comments begin with a number sign (`#`) and continue through the end of the line. Blank lines and comments are ignored. All other lines should consist of five fields separated by colons:

```
hosts:perms:username:password:patterns
```

The first field is a `wildmat(3)`-style pattern specifying the names or Internet address of a set of hosts. Before a match is checked, the client's hostname (or its Internet address if `gethostbyaddr(3)` fails) is converted to lowercase. Each line is matched in turn, and the last successful match is taken as the correct one.

The second field is a set of letters specifying the permissions granted to the client. The `perms` should be chosen from the following set:

R	The client can retrieve articles
P	The client can post articles

The third and fourth fields specify the `username` and `password` that the client must use to authenticate themselves before the server will accept any articles. Note that no authentication (other than a matching entry in this file) is required for newsreading. If they are empty, then no password is required. Whitespace in these fields will result in the client being unable to properly authenticate themselves and may be used to disable access.

The fifth field is a set of patterns identifying the newsgroups that the client is allowed to access. The `patterns` are interpreted in the same manner as the `newsfeeds(5)` file. The default, however, denies access to all groups.

The access file is normally used to provide host-level access control for reading and posting articles. There are times, however, when this is not sufficient and user-level access control is needed. Whenever an NNTP `authinfo` command is used, the `nnrpd` server rereads this file and looks for a matching username and password. If the local newsreaders are modified to send the `authinfo` command, then all host entries can have no access and specific users can be granted the appropriate read and post access. For example:

```
## host:perm:user:pass:groups
## Default is no access.
:: -no- : -no- :!*
## F00 hosts have no password, can read anything.
.foo.com:Read Post:::*
## A related workstation can't access F00 newsgroups.
lenox.foo.net:RP:martha:hiatt:*,!foo.*
```

If the file contains passwords, it should not be world-readable.

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for InterNetNews.

SEE ALSO

[innd\(8\)](#), [newsfeeds\(5\)](#), [nnrpd\(8\)](#), [wildmat\(3\)](#)

nntpsend.ctl

[nntpsend.ctl](#)—List of sites to feed via [nntpsend](#).

DESCRIPTION

The file `/news/lib/nntpsend.ctl` specifies the default list of sites to be fed by [nntpsend\(8\)](#).

Comments begin with a number sign (`#`) and continue through the end of the line. Blank lines and comments are ignored. All other lines should consist of four fields separated by a colon.

The first field is the name of the site as specified in the [newsfeeds\(5\)](#) file.

The second field should be the hostname or IP address of the remote site.

The third field, if non-empty, specifies the default tail truncation size of site's batchfile. This is passed to `shrinkfile` as the `-s` flag. If this field is empty, no truncation is performed.

The fourth field specifies some default flags passed to [innxmit\(8\)](#). The flag `-a` is always given to [innxmit](#) and need not appear here. If no `-t` timeout flag is given in this field and on the [nntpsend](#) command line, `-t 180` will be given to [innxmit](#).

HISTORY

Written by Landon Curt Noll (chongo@toad.com) for InterNetNews.

SEE ALSO

[innxmit\(8\)](#), [newsfeeds\(5\)](#), [nntpsend\(8\)](#), [trunc\(1\)](#)

nologin

[nologin](#)—Prevent usual users from logging into the system.

DESCRIPTION

If the file `/etc/nologin` exists, [login\(1\)](#) will allow access only to root. Other users will be shown the contents of this file and their logins refused.

FILES

`/etc/nologin`

SEE ALSO

[login\(1\)](#), [shutdown\(8\)](#)

Linux, 29 December 1992

overview.fmt

[overview.fmt](#)—Format of news overview database.

DESCRIPTION

The file `/news/lib/overview.fmt` specifies the organization of the news overview database. Blank lines and lines beginning with a number sign (#) are ignored. The order of lines in this file is important; it determines the order in which the fields will appear in the database.

Most lines will consist of an article header name, optionally followed by a colon. A trailing set of lines can have the word `full` appear after the colon; this indicates that the header should appear as well as its value.

If this file is changed, it is usually necessary to rebuild the existing overview database using `expireover(8)` after removing all existing overview files.

The default file, show here, is compatible with Geoff Collyer's `nov` package:

```
Subject:
From:
Date:
Message-ID:
References:
Bytes:
Lines:
## Some newsreaders get better performance if Xref is present
#Xref:full
```

HISTORY

Written by Rich Salz (`rsalz@uunet.uu.net`) for InterNetNews. Intended to be compatible with the `nov` package written by Geoff Collyer (`geoff@world.std.com`).

passwd

passwd—Password file.

DESCRIPTION

`passwd` is an ASCII file that contains a list of the system's users and the passwords they must use for access. The password file should have general read permission (many utilities, such as `ls(1)`, use it to map user IDs to usernames) but write access only for the superuser.

In the good old days, there was no great problem with this general read permission. Everybody could read the encrypted passwords, but the hardware was too slow to crack a well-chosen password, and moreover, the basic assumption used to be that of a friendly user community. These days, many people run some version of the shadow password suite, where `/etc/passwd` has `*s` instead of passwords, and the encrypted passwords are in `/etc/shadow`, which is readable by root only.

When you create a new login, leave the password field empty and use `passwd(1)` to fill it. A star (*) in the password field means that this user cannot log in via `login(1)`.

There is one entry per line, and each line has the format:

```
login_name:passwd:UID:GID:user_name:directory:shell
```

The field descriptions are

<code>login_name</code>	The name of the user on the system.
<code>passwd</code>	The encrypted optional user password.
<code>UID</code>	The numerical user ID.
<code>GID</code>	The numerical group ID for this user.
<code>user_name</code>	The (optional) comment field (often a full username).
<code>directory</code>	The user's <code>\$HOME</code> directory.
<code>shell</code>	The program to run at login (if empty, use <code>/bin/sh</code>).

NOTE

If your root file system is on `/dev/ram`, you must save a changed password file to your root filesystem floppy before you shut down the system and check the access rights. If you want to create user groups, their GIDs must be equal and there must be an entry in `/etc/group`, or no group will exist.

FILES

`/etc/passwd`

SEE ALSO

`passwd(1)`, `login(1)`, `group(5)`, `shadow(5)`

Linux, 24 July 1993

passwd.nntp

`passwd.nntp`—Passwords for connecting to remote NNTP servers.

DESCRIPTION

The file `/news/lib/passwd.nntp` contains host-name-password triplets for use when authenticating client programs to NNTP servers. This file is normally interpreted by the `NNTPsend-password` routine in `libinn(3)`. Blank lines and lines beginning with a number sign (`#`) are ignored. All other lines should consist of three or fields separated by colons:

```
host:name:password
host:name:password:style
```

The first field is the name of a host and is matched in a case-insensitive manner. The second field is a username, and the third is a password. The optional fourth field specifies the type of authentication to use. The default is `authinfo`, which means that NNTP `authinfo` commands are used to authenticate to the remote host. If either the username or password are empty, then the related command will not be sent. (The `authinfo` command is a common extension to RFC 977.) For example:

```
## UUNET needs a password, MIT doesn't.
mit.edu:bbn::authinfo
uunet.uu.net:bbn:yoyoma:authinfo
```

This file should not be world-readable.

HISTORY

Written by Rich Salz (`rsalz@uunet.uu.net`) for InterNetNews.

SEE ALSO

`innd(8)`, `libinn(3)`

pbm

`pbm`—Portable bitmap file format.

DESCRIPTION

The portable bitmap format is a lowest common denominator monochrome file format. It was originally designed to make it reasonable to mail bitmaps between different types of machines using the typical stupid network mailers we have today. Now it serves as the common language of a large family of bitmap conversion filters. The definition is as follows:

A “magic number” for identifying the file type. A `pbm` file’s magic number is the two characters `P1`.

Whitespace (blanks, Tabs, CRs, LFs).

A width, formatted as ASCII characters in decimal.

Whitespace.

A height, again in ASCII decimal.

Whitespace.

Width * height bits, each either 1 or 0, starting at the top-left corner of the bitmap, proceeding in normal English reading order.

The character 1 means black; 0 means white.

Whitespace in the bits section is ignored.

Characters from a # to the next end-of-line are ignored (comments).

No line should be longer than 70 characters.

Here is an example of a small bitmap in this format:

```
P1
# feep.pbm
24 7
0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
0 1 1 1 1 0 0 1 1 1 1 0 0 1 1 1 1 0 0 1 1 1 1 0
0 1 0 0 0 0 0 1 0 0 0 0 0 1 0 0 0 0 0 1 0 0 1 0
0 1 1 1 0 0 0 1 1 1 0 0 0 1 1 1 0 0 0 1 1 1 1 0
0 1 0 0 0 0 0 1 0 0 0 0 0 1 0 0 0 0 0 1 0 0 0 0
0 1 0 0 0 0 0 1 1 1 1 0 0 1 1 1 1 0 0 1 0 0 0 0
0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
```

Programs that read this format should be as lenient as possible, accepting anything that looks remotely like a bitmap.

There is also a variant on the format, available by setting the `RAWBITS` option at compile time. This variant is different in the following ways:

The “magic number” is `P4` instead of `P1`.

The bits are stored eight per byte, high bit first and low bit last.

No whitespace is allowed in the bits section, and only a single character of whitespace (typically a newline) is allowed after the height.

The files are eight times smaller and many times faster to read and write.

SEE ALSO

`atktopbm(1)`, `brushtopbm(1)`, `cmuwmtopbm(1)`, `g3topbm(1)`, `gemitopbm(1)`, `icontopbm(1)`, `macptopbm(1)`, `mgrtopbm(1)`, `pi3topbm(1)`, `xbmtopbm(1)`, `ybmtopbm(1)`, `pbmto10x(1)`, `pnmtaascii(1)`, `pbmtoatk(1)`, `pbmtobnbg(1)`, `pbmtocmuwm(1)`, `pbmtoepson(1)`, `pbmtog3(1)`, `pbmtogem(1)`, `pbmtogo(1)`, `pbmtoicon(1)`, `pbmtolj(1)`, `pbmtomacp(1)`, `pbmtomgr(1)`, `pbmtopi3(1)`, `pbmtoplot(1)`, `pbmtoptx(1)`, `pbmtox10bm(1)`, `pbmtoxbm(1)`, `pbmtoybm(1)`, `pbmtozinc(1)`, `pbm1ife(1)`, `pbmmake(1)`, `pbmmask(1)`, `pbmreduce(1)`, `pbmtext(1)`, `pbmupc(1)`, `pnm(5)`, `pgm(5)`, `ppm(5)`

AUTHOR

Copyright 1989, 1991 by Jef Poskanzer.

27 September 1991

pgm

pgm—Portable graymap file format.

DESCRIPTION

The portable graymap format is a lowest common denominator grayscale file format. The definition is as follows:

A “magic number” for identifying the file type. A pgm file’s magic number is the two characters P2.

Whitespace (blanks, Tabs, CRs, LF’s).

A width, formatted as ASCII characters in decimal.

Whitespace.

A height, again in ASCII decimal.

Whitespace.

The maximum gray value, again in ASCII decimal.

Whitespace.

Width * height gray values, each in ASCII decimal, between 0 and the specified maximum value, separated by whitespace, starting at the top-left corner of the graymap, proceeding in normal English reading order. A value of 0 means black, and the maximum value means white.

Characters from a # to the next end-of-line are ignored (comments).

No line should be longer than 70 characters.

Here is an example of a small graymap in this format:

```
P2
# feep.pgm
24 7
15
0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
0 3 3 3 3 0 0 7 7 7 7 0 0 11 11 1111 0 0 15 1515 15 0
0 3 0 0 0 0 0 7 0 0 0 0 0 11 0 0 0 0 0 15 0 0 150
0 3 3 3 0 0 0 7 7 7 0 0 0 11 11 110 0 0 15 15 15 150
0 3 0 0 0 0 0 7 0 0 0 0 0 11 0 0 0 0 0 15 0 0 0 0
0 3 0 0 0 0 0 7 7 7 7 0 0 11 11 1111 0 0 15 0 0 0 0
0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
```

Programs that read this format should be as lenient as possible, accepting anything that looks remotely like a graymap.

There is also a variant on the format, available by setting the RAWBITS option at compile time. This variant is different in the following ways:

The “magic number” is P5 instead of P2.

The gray values are stored as plain bytes, instead of ASCII decimal.

No whitespace is allowed in the grays section, and only a single character of whitespace (typically a newline) is allowed after the maxval.

The files are smaller and many times faster to read and write.

Note that this raw format can only be used for maxvals less than or equal to 255. If you use the pgm library and try to write a file with a larger maxval, it will automatically fall back on the slower but more general plain format.

SEE ALSO

fitstopgm(1), fstopgm(1), hipstopgm(1), lispmtopgm(1), psidtopgm(1), rawtopgm(1), pgmbentley(1), pgmcrater(1), pgmedge(1), pgmenhance(1), pgmhists(1), pgmnorm(1), pgmoil(1), pgmramp(1), pgmtexture(1), pgmtofits(1), pgmtofs(1), pgmtolisp(1), pgmtopbm(1), pnm(5), pbm(5), ppm(5)

AUTHOR

Copyright 1989, 1991 by Jef Poskanzer.

12 November 1991

pnm

pnm—Portable anymap file format.

DESCRIPTION

The pnm programs operate on portable bitmaps, graymaps, and pixmaps produced by the pbm, pgm, and ppm segments. There is no file format associated with pnm itself.

SEE ALSO

anytopnm(1), rasttopnm(1), tifftopnm(1), xwdtopnm(1), pnmtops(1), pnmtoast(1), pnmtoiff(1), pnmtoxwd(1), pnmarith(1), pnmcat(1), pnmconvol(1), pnmcrop(1), pnmcut(1), pnmdepth(1), pnm enlarge(1), pnmfile(1), pnmflip(1), pnm gamma(1), pnmindex(1), pnminvert(1), pnm margin(1), pnmnoraw(1), pnpm paste(1), pnmrotate(1), pnm scale(1), pnm shear(1), pnm smooth(1), pnm tile(1), ppm(5), pgm(5), pbm(5)

AUTHOR

Copyright 1989, 1991 by Jef Poskanzer.

27 September 1991

ppm

ppm—Portable pixmap file format.

DESCRIPTION

The portable pixmap format is a lowest common denominator color image file format. The definition is as follows:

A “magic number” for identifying the file type. A ppm file’s magic number is the two characters P3.

Whitespace (blanks, Tabs, CRs, LFs).

A width, formatted as ASCII characters in decimal.

Whitespace.

A height, again in ASCII decimal.

Whitespace.

The maximum color-component value, again in ASCII decimal.

Whitespace.

Width * height pixels, each three ASCII decimal values between 0 and the specified maximum value, starting at the top-left corner of the pixmap, proceeding in normal English reading order. The three values for each pixel represent red, green, and blue; a value of 0 means that color is off, and the maximum value means that color is maxed out.

Characters from a # to the next end-of-line are ignored (comments).

No line should be longer than 70 characters.

Here is an example of a small pixmap in this format:

```
P3
# feep.ppm
4 4
15
0 0 0 0 0 0 0 0 15 0 15
0 0 0 0 15 7 0 0 0 0 0
0 0 0 0 0 0 0 0 15 7 0 0
15 0 15 0 0 0 0 0 0 0 0
```

Programs that read this format should be as lenient as possible, accepting anything that looks remotely like a pixmap.

There is also a variant on the format, available by setting the `RAWBITS` option at compile time. This variant is different in the following ways:

The “magic number” is `P6` instead of `P3`.

The pixel values are stored as plain bytes, instead of ASCII decimal.

Whitespace is not allowed in the pixels area, and only a single character of whitespace (typically a newline) is allowed after the `maxval`.

The files are smaller and many times faster to read and write.

Note that this raw format can only be used for `maxvals` less than or equal to 255. If you use the `ppm` library and try to write a file with a larger `maxval`, it will automatically fall back on the slower but more general plain format.

SEE ALSO

`giftoppm(1)`, `gouldtoppm(1)`, `ilbmtoppm(1)`, `imgtoppm(1)`, `mtvtoppm(1)`, `pcxtoppm(1)`, `pgmtoppm(1)`, `pi1ttoppm(1)`, `picttoppm(1)`, `pjttoppm(1)`, `qrttoppm(1)`, `rawtoppm(1)`, `rgb3toppm(1)`, `sldtoppm(1)`, `spctoppm(1)`, `sputoppm(1)`, `tgatoppm(1)`, `ximtoppm(1)`, `xpmtoppm(1)`, `yuvtoppm(1)`, `ppmtocad(1)`, `ppmtogif(1)`, `ppmtoicr(1)`, `ppmtoilbm(1)`, `ppmtopcx(1)`, `ppmtopgm(1)`, `ppmtopi1(1)`, `ppmtopict(1)`, `ppmtopj(1)`, `ppmtopuzz(1)`, `ppmtorgb3(1)`, `ppmtosixel(1)`, `ppmtotga(1)`, `ppmtouil(1)`, `ppmtoxpm(1)`, `ppmtoyuv(1)`, `ppmdither(1)`, `ppmforge(1)`, `ppmhist(1)`, `ppmmake(1)`, `ppmpat(1)`, `ppmquant(1)`, `ppmquantall(1)`, `ppmrelief(1)`, `pnm(5)`, `pgm(5)`, `pbm(5)`

AUTHOR

Copyright 1989, 1991 by Jef Poskanzer.

27 September 1991

/proc

`/proc`—Process information pseudo-filesystem.

DESCRIPTION

`/proc` is a pseudo-filesystem that is used as an interface to kernel data structures rather than reading and interpreting `/dev/kmem`. Most of it is read-only, but some files allow kernel variables to be changed.

The following outline gives a quick tour through the `/proc` hierarchy.

<code>[number]</code>	There is a numerical subdirectory for each running process; the subdirectory is named by the process ID. Each contains the following pseudo-files and directories.
<code>cmdline</code>	This holds the complete command line for the process, unless the whole process has been swapped out or unless the process is a zombie. In either of these later cases, there is nothing in this file: That is, a read on this file will return as having read 0 characters. This file is null-terminated but not newline-terminated.
<code>cwd</code>	This is a link current working directory of the process. To find out the <code>cwd</code> of process 20, for instance, you can do this: <code>cd /proc/20/cwd; /bin/pwd</code> . Note that the <code>pwd</code> command is often a shell built in and might not work properly in this context.
<code>environ</code>	This file contains the environment for the process. The entries are separated by null characters, and there may be a null character at the end. Thus, to print out the environment of process 1, you would do <pre>(cat /proc/1/environ; echo) tr "\000" "\n"</pre> For a reason why one should want to do this, see <code>lilo(8)</code> .
<code>exe</code>	A pointer to the binary that was executed and appears as a symbolic link. <code>readlink(2)</code> on the <code>exe</code> special file returns a string in the format: <pre>[device]:inode</pre> For example, <code>[0301]:1502</code> is inode 1502 on device major 03 (IDE, MFM, and so on drives), minor

01 (first partition on the first drive). Also, the symbolic link can be dereferenced normally; attempting to open `exe` will open the executable. You can even type `/proc/[number]/exe` to run another copy of the same process as `[number]`.

`find(1)` with the `-inum` option can be used to locate the file.

`fd`

This is a subdirectory containing one entry for each file that the process has open, named by its file descriptor, and that is a symbolic link to the actual file (as the `exe` entry does). Thus, 0 is standard input, 1 standard output, 2 standard error, and so on.

Programs that will take a filename but will not take the standard input and that write to a file but will not send their output to standard output can be effectively foiled this way, assuming that `-i` is the flag designating an input file and `-o` is the flag designating an output file:

```
foobar -i /proc/self/fd/0 -o /proc/self/fd/1 ...
```

and you have a working filter. Note that this will not work for programs that seek on their files because the files in the `fd` directory are not seekable.

`/proc/self/fd/N` is approximately the same as `/dev/fd/N` in some UNIX and UNIX-like systems. Most Linux MAKEDEV scripts symbolically link `/dev/fd` to `/proc/self/fd`, in fact.

`maps`

A file containing the currently mapped memory regions and their access permissions.

The format is

address	perms	offset	dev	inode
00000000-0002f000	r-x-	00000400	03:03	1401
0002f000-00032000	rw-x-p	0002f400	03:03	1401
00032000-0005b000	rw-x-p	00000000	00:00	0
60000000-60098000	rw-x-p	00000400	03:03	215
60098000-600c7000	rw-x-p	00000000	00:00	0
bfffa000-c0000000	rw-x-p	00000000	00:00	0

`address` is the address space in the process that it occupies. `perms` is a set of permissions: `r` = read, `w` = write, `x` = execute, `s` = shared, `p` = private (copy on write).

`offset` is the offset into the file/whatever, `dev` is the device (major: minor), and `inode` is the inode on that device. 0 indicates that no inode is associated with the memory region, as the case would be with `bss`.

`mem`

This is not the same as the `mem (1,1)` device, despite the fact that it has the same device numbers. The `/dev/mem` device is the physical memory before any address translation is done, but the `mem` file here is the memory of the process that accesses it. This cannot be `mmap(2)`ed currently, and will not be until a general `mmap(2)` is added to the kernel. (This might have happened by the time you read this.)

`mmap`

Directory of maps by `mmap(2)` that are symbolic links such as `exe`, `fd/*`, and so on. Note that maps includes a superset of this information, so `/proc/*/mmap` should be considered obsolete.

0 is usually `libc.so.4`.

`/proc/*/mmap` was removed in Linux kernel version 1.1.40. (It really was obsolete!)

`root`

UNIX and Linux support the idea of a per-process root of the filesystem, set by the `chroot(2)` system call. `root` points to the filesystem root and behaves as `exe`, `fd/*`, and so on do.

`stat`

Status information about the process. This is used by `ps(1)`. The fields, in order, with their proper `scanf(3)` format specifiers, are

`pid %d` The process ID.

`comm %s` The filename of the executable in parentheses. This is visible whether or not the executable is swapped out.

state %c	One character from the string RSDZT where R is running, S is sleeping in an interruptible wait, D is sleeping in an uninterruptible wait or swapping, Z is zombie, and T is traced or stopped (on a signal).
ppid %d	The PID of the parent.
pgrp %d	The process group ID of the process.
session %d	The session ID of the process.
tty %d	The tty the process uses.
tpgid %d	The process group ID of the process that currently owns the tty that the process is connected to.
flags %u	The flags of the process. Currently, every flag has the math bit set because crt0.s checks for math emulation, so this is not included in the output. This is probably a bug because not every process is a compiled C program. The math bit should be a decimal 4, and the traced bit is decimal 10.
minflt %u	The number of minor faults the process has made, those that have not required loading a memory page from disk.
cminflt %u	The number of minor faults that the process and its children have made.
majflt %u	The number of major faults the process has made, those that have required loading a memory page from disk.
cmajflt %u	The number of major faults that the process and its children have made.
utime %d	The number of jiffies that this process has been scheduled in user mode.
stime %d	The number of jiffies that this process has been scheduled in kernel mode.
cutime %d	The number of jiffies that this process and its children have been scheduled in user mode.
cstime %d	The number of jiffies that this process and its children have been scheduled in kernel mode.
counter %d	The current maximum size in jiffies of the process's next timeslice, or what is currently left of its current timeslice if it is the currently running process.
priority %d	The standard nice value, plus fifteen. The value is never negative in the kernel.
timeout %u	The time in jiffies of the process's next time-out.
itrealvalue %u	The time (in jiffies) before the next SIGALRM is sent to the process due to an interval timer.
starttime %d	Time the process started in jiffies after system boot.
vsize %u	Virtual memory size.
rss %u	Resident set size: Number of pages the process has in real memory, minus 3 for administrative purposes. This is just the pages that count toward text, data, or stack space. This does not include pages that have not been demand-loaded in or that are swapped out.
rlim %u	Current limit in bytes on the rss of the process (usually 2,147,483,647).
startcode %u	The address above which program text can run.
endcode %u	The address below which program text can run.
startstack %u	The address of the start of the stack.
kstkesp %u	The current value of esp (32-bit stack pointer), as found in the kernel stack page for the process.
kstkeip %u	The current EIP (32-bit instruction pointer).
signal %d	The bitmap of pending signals (usually 0).
blocked %d	The bitmap of blocked signals (usually 0, 2 for shells).

<code>sigignore %d</code>	The bitmap of ignored signals.
<code>sigcatch %d</code>	The bitmap of caught signals.
<code>wchan %u</code>	This is the “channel” in which the process is waiting. This is the address of a system call and can be looked up in a name list if you need a textual name. (If you have an up-to-date <code>/etc/psdatabase</code> , then try <code>ps -l</code> to see the <code>WCHAN</code> field in action.)
<code>cpuinfo</code>	This is a collection of CPU and system architecture dependent items; for each supported architecture is a different list. The only two common entries are <code>cpu</code> , which is the CPU currently in use, and <code>BogoMIPS</code> , a system constant that is calculated during kernel initialization.
<code>devices</code>	Text listing of major numbers and device groups. This can be used by <code>MAKEDEV</code> scripts for consistency with the kernel.
<code>dma</code>	This is a list of the registered ISA DMA (direct memory access) channels in use.
<code>filesystems</code>	A text listing of the filesystems that were compiled into the kernel. Incidentally, this is used by <code>mount(1)</code> to cycle through different filesystems when none is specified.
<code>interrupts</code>	This is used to record the number of interrupts per each IRQ on (at least) the i386 architecture. Very easy to read formatting done in ASCII.
<code>ioports</code>	This is a list of currently registered input-output port regions that are in use.
<code>kcore</code>	This file represents the physical memory of the system and is stored in the core file format. With this pseudo-file and an unstripped kernel (<code>/usr/src/linux/tools/zSystem</code>) binary, <code>GDB</code> can be used to examine the current state of any kernel data structures. The total length of the file is the size of physical memory (RAM) plus 4KB.
<code>kmsg</code>	This file can be used instead of the <code>syslog(2)</code> system call to log kernel messages. A process must have superuser privileges to read this file, and only one process should read this file. This file should not be read if a <code>syslog</code> process is running that uses the <code>syslog(2)</code> system call facility to log kernel messages. Information in this file is retrieved with the <code>dmesg(8)</code> program.
<code>ksyms</code>	This holds the kernel exported symbol definitions used by the <code>modules(X)</code> tools to dynamically link and bind loadable modules.
<code>loadavg</code>	The load average numbers give the number of jobs in the run queue averaged over 1, 5, and 15 minutes. They are the same as the load average numbers given by <code>uptime(1)</code> and other programs.
<code>malloc</code>	This file is only present if <code>CONFIGDEBUGMALLOC</code> was defined during compilation.
<code>meminfo</code>	This is used by <code>free(1)</code> to report the amount of free and used memory (both physical and swap) on the system as well as the shared memory and buffers used by the kernel. It is in the same format as <code>free(1)</code> except in bytes rather than KB.
<code>modules</code>	A text list of the modules that have been loaded by the system.
<code>net</code>	Various net pseudo-files, all of which give the status of some part of the networking layer. These files contain ASCII structures and are therefore readable with <code>cat</code> . However, the standard <code>netstat(8)</code> suite provides much cleaner access to these files.
<code>arp</code>	This holds an ASCII readable dump of the kernel ARP table used for address resolutions. It will show both dynamically learned and pre-programmed ARP entries. The format is

IP address	HW type	Flags	HW address
10.11.100.129	0x1	0x6	00:20:8A:00:0C:5A
10.11.100.5	0x1	0x2	00:C0:EA:00:00:4E
44.131.10.6	0x3	0x2	GW4PTS

IP address is the IPv4 address of the machine. The HW type is the hardware type of the address from RFC 826. The flags are the internal flags of the ARP structure (as defined in `/usr/include/linux/if_arp.h`) and the HW address is the physical layer mapping for that IP address if it is known.

dev	The dev pseudo-file contains network device status information. This gives the number of received and sent packets, the number of errors and collisions, and other basic statistics. These are used by the <code>ifconfig(8)</code> program to report device status. The format is <pre> Inter- Receive Transmit face packets errs drop fifo frame packets errs drop fifo colls carrier lo: 0 0 0 0 0 0 2353 0 0 0 0 0 eth0: 644324 1 0 0 1 0 563770 0 0 0 581 0 </pre>
ipx	No information.
ipx_route	No information.
rarp	This file uses the same format as the ARP file and contains the current reverse mapping database used to provide <code>rarp(8)</code> reverse address lookup services. If <code>rarp</code> is not configured into the kernel, this file will not be present.
raw	Holds a dump of the RAW socket table. Much of the information is not of use apart from debugging. The <code>s1</code> value is the kernel hash slot for the socket; the <code>local_address</code> is the local address and protocol number pair. <code>st</code> is the internal status of the socket. The <code>tx_queue</code> and <code>rx_queue</code> are the outgoing and incoming data queue in terms of kernel memory usage. The <code>tr</code> , <code>tm->when</code> , and <code>rexmits</code> fields are not used by RAW. The <code>uid</code> field holds the creator <code>euid</code> of the socket.
route	No information but looks similar to <code>route(8)</code> .
snmp	This file holds the ASCII data needed for the IP, ICMP, TCP, and UDP management information bases for an <code>snmp</code> agent. As of writing, the TCP <code>mib</code> is incomplete. It should be completed by 1.2.0.
tcp	Holds a dump of the TCP socket table. Much of the information is not of use apart from debugging. The <code>s1</code> value is the kernel hash slot for the socket; the <code>local_address</code> is the local address and port number pair. The <code>remote_address</code> is the remote address and port number pair (if connected). <code>st</code> is the internal status of the socket. The <code>tx_queue</code> and <code>rx_queue</code> are the outgoing and incoming data queue in terms of kernel memory usage. The <code>tr</code> , <code>tm->when</code> , and <code>rexmits</code> fields hold internal information of the kernel socket state and are only useful for debugging. The <code>uid</code> field holds the creator <code>euid</code> of the socket.
udp	Holds a dump of the UDP socket table. Much of the information is not of use apart from debugging. The <code>s1</code> value is the kernel hash slot for the socket; the <code>local_address</code> is the local address and port number pair. The <code>remote_address</code> is the remote address and port number pair (if connected). <code>st</code> is the internal status of the socket. The <code>tx_queue</code> and <code>rx_queue</code> are the outgoing and incoming data queue in terms of kernel memory usage. The <code>tr</code>, <code>tm->when</code>, and <code>rexmits</code> fields are not used by UDP. The <code>uid</code> field holds the creator <code>euid</code> of the socket. The format is <pre> s1 local_address rem_address st tx_queue rx_queue tr rexmits tm->when uid 1: 01642C89:0201 0C642C89:03FF 01 00000000:00000001 01:000071BA 00000000 0 1: 00000000:0801 00000000:0000 0A 00000000:00000000 00:00000000 6F000100 0 1: 00000000:0201 00000000:0000 0A 00000000:00000000 00:00000000 00000000 0 </pre>
unix	Lists the UNIX domain sockets present within the system and their status. The format is <pre> Num RefCount Protocol Flags Type St Path 0: 00000002 00000000 00000000 0001 03 1: 00000001 00000000 00010000 0001 01 /dev/printer </pre> <code>Num</code> is the kernel table slot number, <code>RefCount</code> is the number of users of the socket, <code>Protocol</code> is currently always 0, and <code>Flags</code> represents the internal kernel flags holding the status of the socket. <code>Type</code> is currently always 1 (UNIX domain datagram sockets are not yet supported in the kernel). <code>St</code> is the internal state of the socket and <code>Path</code> is the bound path (if any) of the socket.

pci	This is a listing of all PCI devices found during kernel initialization and their configuration.
scsi	A directory with the SCSI mid-level pseudo-file and various SCSI low-level driver directories, which contain a file for each SCSI host in this system, all of which give the status of some part of the SCSI IO subsystem. These files contain ASCII structures and are therefore readable with cat. You can also write to some of the files to reconfigure the subsystem or switch certain features on or off.
scsi/scsi	This is a listing of all SCSI devices known to the kernel. The listing is similar to the one seen during bootup. scsi currently supports only the single device command, which allows root to add a hot-plugged device to the list of known devices. An echo 'scsisingledevice1 0 5 0' > /proc/scsi/scsi will cause host scsi1 to scan on SCSI channel 0 for a device on ID 5 LUN 0. If there is already a device known on this address or the address is invalid, an error will be returned.
drivename	drivename can currently be NCR53c7xx, aha152x, aha1542, aha1740, aic7xxx, buslogic, eata_dma, eata_pio, fdomain, in2000, pas16, qllogic, scsi_debug, seagate, t128, u15-24f, ultrastor, or wd7000. These directories show up for all drivers that registered at least one SCSI HBA. Every directory contains one file per registered host. Every host-file is named after the number the host got assigned during initialization. Reading these files will usually show driver and host configuration, statistics, and so on. Writing to these files allows different things on different hosts. For example, with the latency and nolatency commands, root can switch on and off command latency measurement code in the eata_dma driver. With the lockup and unlock commands, root can control bus lockups simulated by the scsi_debug driver.
self	This directory refers to the process accessing the /proc filesystem and is identical to the /proc directory named by the process ID of the same process.
stat	kernel/system statistics.
cpu 3357 0 4313 1362393	The number of jiffies (1/100ths of a second) that the system spent in user mode, user mode with low priority (nice), system mode, and the idle task. The last value should be 100 times the second entry in the uptime pseudo-file.
disk 0 0 0 0	The four disk entries are not implemented at this time. I'm not even sure what this should be because kernel statistics on other machines usually track both transfer rate and I/Os per second and this only allows for one field per drive.
page 5741 1808	The number of pages the system paged in and the number that were paged out (from disk).
swap 1 0	The number of swap pages that have been brought in and out.
intr 1462898	The number of interrupts received from the system boot.
ctxt 115315	The number of context switches that the system underwent.
btime 769041601	Boot time in seconds since the epoch (January 1, 1970).
sys	This directory (present since 1.3.57) contains a number of files and subdirectories corresponding to kernel variables. These variables can be read and sometimes modified using the proc filesystem and using the sysctl(2) system call. Presently, there are subdirectories kernel, net, and vm that each contain more files and subdirectories.
kernel	This contains the files domainname, file-max, file-nr, hostname, inode-max, inode-nr, osrelease, ostype, panic, real-root-dev, securelevel, and version, with function fairly clear from the name. The (read-only) file file-nr gives the number of files presently opened. The file file-max gives the maximum number of open files the kernel is willing to handle. If 1024 is not enough for you, try echo 4096 > /proc/sys/kernel/file-max. Similarly, the files inode-nr and inode-max indicate the present and the maximum number of inodes.

	The files <code>ostype</code> , <code>osrelease</code> , and <code>version</code> give substrings of <code>/proc/version</code> .
	The file <code>panic</code> gives r/w access to the kernel variable <code>panic_timeout</code> . If this is zero, the kernel will loop on a panic; if nonzero, it indicates that the kernel should autoreboot after this number of minutes.
	The file <code>securelevel</code> seems rather meaningless at present; <code>root</code> is just too powerful.
uptime	This file contains two numbers: the uptime of the system (seconds) and the amount of time spent in idle process (seconds).
version	This string identifies the kernel version that is currently running. For instance: Linux version 1.0.9 (quinlan@phaze) #1 Sat May 14 01:51:54 EDT 1994

SEE ALSO

`cat(1)`, `find(1)`, `free(1)`, `mount(1)`, `ps(1)`, `tr(1)`, `uptime(1)`, `readlink(2)`, `mmap(2)`, `chroot(2)`, `syslog(2)`, `hier(7)`, `arp(8)`, `dmesg(8)`, `netstat(8)`, `route(8)`, `ifconfig(8)`, `procinfo(8)` and much more

CONFORMS TO

This roughly conforms to a Linux 1.3.11 kernel. Please update this as necessary! Last updated for Linux 1.3.11.

CAVEATS

Note that many strings (the environment and command line) are in the internal format, with subfields terminated by null bytes, so you might find that things are more readable if you use `od -c` or `tr "\000" "\n"` to read them.

This manual page is incomplete, possibly inaccurate, and is the kind of thing that needs to be updated very often.

BUGS

The `/proc` filesystem may introduce security holes into processes running with `chroot(2)`. For example, if `/proc` is mounted in the `chroot` hierarchy, a `chdir(2)` to `/proc/1/root` will return to the original root of the filesystem. This may be considered a feature instead of a bug because Linux does not yet support the `fchroot(2)` call.

22 July 1996

protocols

`protocols`—The protocols definition file.

DESCRIPTION

This file is a plain ASCII file, describing the various DARPA Internet protocols that are available from the TCP/IP subsystem. It should be consulted instead of using the numbers in the ARPA include files or, even worse, just guessing them. These numbers will occur in the protocol field of any IP header.

Keep this file untouched because changes would result in incorrect IP packages. Protocol numbers and names are specified by the DDN Network Information Center.

Each line is of the following format:

```
protocol number aliases ...
```

The fields are delimited by spaces or tabs. Empty lines and lines starting with a hash mark (`#`) are ignored. Remainder of lines are also ignored from the occurrence of a hash mark.

The field descriptions are

protocol	The native name for the protocol—for example, <code>ip</code> , <code>tcp</code> , or <code>udp</code> .
number	The official number for this protocol as it will appear within the IP header.
aliases	Optional aliases for the protocol.

This file might be distributed over a network using a network-wide naming service such as Yellow Pages/NIS or BIND/Hesiod.

FILES

/etc/protocols

The protocols definition file.

SEE ALSO

getprotoent(3), *Guide to Yellow Pages Service*, *Guide to BIND/Hesiod Service*

Linux, 18 October 1995

rcsfile

rcsfile—Format of RCS file.

DESCRIPTION

An RCS file's contents are described by the grammar below.

The text is free format: space, backspace, tab, newline, vertical tab, form feed, and carriage return (collectively, whitespace) have no significance except in strings. However, whitespace cannot appear within an ID, num, or sym, and an RCS file must end with a newline.

Strings are enclosed by @. If a string contains a @, it must be doubled; otherwise, strings can contain arbitrary binary data.

The meta syntax uses the following conventions: | (bar) separates alternatives; { and } enclose optional phrases. { and }* enclose phrases that can be repeated zero or more times. { and {+ enclose phrases that must appear at least once and can be repeated. Terminal symbols are in boldface; non-terminal symbols are in *italics*.

```
rcstext ::= admin {delta}* desc {deltatext}*
admin ::= head {num};
        { branch {num}; }
        access {id}*;
        symbols {sym : num}*;
        locks {id : num}*; {strict ;}

        { comment {string}; }
        { expand {string}; }
        { newphrase }*
delta ::= num
        date num;
        author id;
        state {id};
        branches {num}*;
        next {num};
        { new-phrase }*
desc ::= desc string
deltatext ::= num
            log string
            { newphrase }*
            text string
num ::= {digit | .}+
digit ::= 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9
id ::= {num} idchar {idchar | num}*
sym ::= {digit}* idchar {idchar | digit}*
idchar ::= any visible graphic character except special
special ::= $ | , | . | : | ; | ! | @
string ::= @{any character, with @doubled}*@
```

```
newphrase ::= id word* ;
word ::= id | num | string | :
```

Identifiers are case sensitive. Keywords are in lowercase only. The sets of keywords and identifiers can overlap. In most environments, RCS uses the ISO8859/1 encoding: visible graphic characters are codes 041–176 and 240–377, and whitespace characters are codes 010–015 and 040.


Dates, which appear after the `date` keyword, are of the form *Y.mm.dd.hh.mm.ss*, where *Y* is the year, *mm* the month (01–12), *dd* the day (01–31), *hh* the hour (00–23), *mm* the minute (00–59), and *ss* the second (00–60). *Y* contains just the last two digits of the year for years from 1900 through 1999, and all the digits of years thereafter. Dates use the Gregorian calendar; times use UTC.

The `newphrase` productions in the grammar are reserved for future extensions to the format of RCS files. No `newphrase` will begin with any keyword already in use.

The `delta` nodes form a tree. All nodes whose numbers consist of a single pair (such as 2.3, 2.1, 1.3, and so on) are on the trunk and are linked through the `next` field in order of decreasing numbers. The `head` field in the `admin` node points to the head of that sequence (contains the highest pair). The `branch` node in the `admin` node indicates the default branch (or revision) for most RCS operations. If empty, the default branch is the highest branch on the trunk.

All `delta` nodes whose numbers consist of $2n$ fields ($n \geq 2$) (such as 3.1.1.1, 2.1.2.2, and so on) are linked as follows. All nodes whose first $2n-1$ number fields are identical are linked through the `next` field in order of increasing numbers. For each such sequence, the `delta` node whose number is identical to the first $2n-2$ number fields of the deltas on that sequence is called the branchpoint. The `branches` field of a node contains a list of the numbers of the first nodes of all sequences for which it is a branchpoint. This list is ordered in increasing numbers.

The following diagram shows an example of an RCS file's organization.



IDENTIFICATION

Author: Walter F. Tichy, Purdue University, West Lafayette, IN, 47907. Manual Page Revision: 5.6; Release Date: 1995/06/05. Copyright 1982, 1988, 1989, Walter F. Tichy. Copyright 1990, 1991, 1992, 1993, 1994, 1995, Paul Eggert.

SEE ALSO

`rcsintro(1)`, `ci(1)`, `co(1)`, `ident(1)`, `rccs(1)`, `rccs-clean(1)`, `rccs-diff(1)`, `rccs-merge(1)`, `rlog(1)`, Walter F. Tichy, RCS, "A System for Version Control," *Software—Practice & Experience*, 15, 7 (July 1985), 637-654.

GNU, 5 June 1995

resolver

resolver—Resolver configuration file.

SYNOPSIS

`/etc/resolv.conf`

DESCRIPTION

The `resolver` is a set of routines in the C library (`resolv(3)`) that provides access to the Internet Domain Name System. The resolver configuration file contains information that is read by the resolver routines the first time they are invoked by a process. The file is designed to be human readable and contains a list of keywords with values that provide various types of resolver information.

On a normally configured system, this file should not be necessary. The only nameserver to be queried will be on the local machine, the domain name is determined from the host name, and the domain search path is constructed from the domain name.

The different configuration options are

<code>nameserver</code>	Internet address (in dot notation) of a nameserver that the <code>resolver</code> should query. Up to <code>MAXNS</code> (currently 3) nameservers may be listed, one per keyword. If there are multiple servers, the resolver library queries them in the order listed. If no <code>nameserver</code> entries are present, the default is to use the nameserver on the local machine. (The algorithm used is to try a nameserver, and if the query times out, try the next until you run out of nameservers, and then repeat trying all the nameservers until a maximum number of retries are made.)
<code>domain</code>	Local domain name. Most queries for names within this domain can use short names relative to the local domain. If no domain entry is present, the domain is determined from the local hostname returned by <code>gethostname(2)</code> ; the domain part is taken to be everything after the first <code>..</code> . Finally, if the hostname does not contain a domain part, the root domain is assumed.
<code>search</code>	Search list for hostname lookup. The search list is normally determined from the local domain name; by default, it contains only the local domain name. This may be changed by listing the desired domain search path following the search keyword with spaces or tabs separating the names. Most <code>resolver</code> queries will be attempted using each component of the search path in turn until a match is found. Note that this process may be slow and will generate a lot of network traffic if the servers for the listed domains are not local and that queries will time out if no server is available for one of the domains. The search list is currently limited to six domains with a total of 256 characters.
<code>sortlist</code>	<code>sortlist</code> allows addresses returned by <code>gethostbyname</code> to be sorted. A sort list is specified by IP address netmask pairs. The netmask is optional and defaults to the natural netmask of the net. The IP address and optional network pairs are separated by slashes. Up to 10 pairs may be specified.

`sortlist 130.155.160.0/255.255.240.0 130.155.0.0`

options

options allows certain internal resolver variables to be modified. The syntax is

options option ...

where option is one of the following:

debug sets RESDEBUG in res.options.

ndots:n sets a threshold for the number of dots that must appear in a name given to res_query (see resolver(3)) before an initial absolute query will be made. The default for n is 1, meaning that if there are any dots in a name, the name will be tried first as an absolute name before any search list elements are appended to it.

The domain and search keywords are mutually exclusive. If more than one instance of these keywords is present, the last instance wins.

The search keyword of a system's resolv.conf file can be overridden on a per-process basis by setting the environment variable LOCALDOMAIN to a space-separated list of search domains.

The options keyword of a system's resolv.conf file can be amended on a per-process basis by setting the environment variable RES_OPTIONS to a space-separated list of resolver options as explained previously.

The keyword and value must appear on a single line, and the keyword (such as nameserver) must start the line. The value follows the keyword, separated by whitespace.

FILES

/etc/resolv.conf

SEE ALSO

gethostbyname(3), resolver(3), hostname(7), named(8), Name Server Operations Guide for BIND

11 November 1993

securetty

securetty—File that lists ttys from which root can log in.

DESCRIPTION

/etc/securetty is used by login(1); the file contains the device names of tty lines (one per line, without leading /dev/) on which root is allowed to log in.

FILES

/etc/securetty

SEE ALSO

login(1)

Linux, 29 December 1992

services

services—Internet network services list.

DESCRIPTION

services is a plain ASCII file providing a mapping between friendly textual names for Internet services and their underlying assigned port numbers and protocol types. Every networking program should look into this file to get the port number (and

protocol) for its service. The C library routines `getservent(3)`, `getservbyname(3)`, `getservbyport(3)`, `setservent(3)`, and `endservent(3)` support querying this file from programs.

Port numbers are assigned by the IANA (Internet Assigned Numbers Authority), and their current policy is to assign both TCP and UDP protocols when assigning a port number. Therefore, most entries will have two entries, even for TCP-only services.

Port numbers below 1024 (so-called low-numbered ports) can only be bound to by root (see `bind(2)`, `tcp(7)`, and `udp(7)`.) This is so that clients connecting to low-numbered ports can trust that the service running on the port is the standard implementation and not a rogue service run by a user of the machine. Well-known port numbers specified by the IANA are normally located in this root-only space.

The presence of an entry for a service in the `services` file does not necessarily mean that the service is currently running on the machine. See `inetd.conf(5)` for the configuration of Internet services offered. Note that not all networking services are started by `inetd(8)` and so won't appear in `inetd.conf(5)`. In particular, news (NNTP) and mail (SMTP) servers are often initialized from the system boot scripts.

The location of the `services` file is defined by `PATH SERVICES` in `/usr/include/netdb.h`. This is usually set to `/etc/services`.

Each line describes one service and is of the form:

```
service-name port/protocol [aliases ...]
```

<code>service-name</code>	The friendly name the service is known by and looked up under. It is case sensitive. Often, the client program is named after the <code>service-name</code> .
<code>port</code>	The port number (in decimal) to use for this service.
<code>protocol</code>	The type of protocol to be used. This field should match an entry in the <code>protocols(5)</code> file. Typical values include <code>tcp</code> and <code>udp</code> .
<code>aliases</code>	An optional space- or tab-separated list of other names for this service (see the Bugs section below). Again, the names are case sensitive.

Either spaces or tabs may be used to separate the fields.

Comments are started by the hash sign (#) and continue until the end of the line. Blank lines are skipped.

The `service-name` should begin in the first column of the file because leading spaces are not stripped. `service-names` can be any printable characters excluding space and tab; however, a conservative choice of characters should be used to minimize inter-operability problems. For example, `a-z`, `0-9`, and hyphen (`-`) would seem a sensible choice.

Lines not matching this format should not be present in the file. (Currently, they are silently skipped by `getservent(3)`, `getservbyname(3)`, and `getservbyport(3)`. However, this behavior should not be relied on.)

As a backwards compatibility feature, the slash (/) between the port number and protocol name can in fact be either a slash or a comma (,). Use of the comma in modern installations is depreciated.

This file might be distributed over a network using a network-wide naming service such as Yellow Pages/NIS or BIND/Hesiod.

A sample `services` file might look like this:

```
netstat    15/tcp
qotd       17/tcp      quote
msp        18/tcp      # message send protocol
msp        18/udp      # message send protocol
chargen    19/tcp      ttytst source
chargen    19/udp      ttytst source
ftp        21/tcp
#          22 - unassigned
telnet     23/tcp
```

BUGS

There is a maximum of 35 aliases, due to the way the `getservent(3)` code is written.

Lines longer than `BUFSIZ` (currently 1024) characters will be ignored by `getservent(3)`, `getservbyname(3)`, and `getservbyport(3)`. However, this will also cause the next line to be misparsed.

FILES

<code>/etc/services</code>	The Internet network services list
<code>/usr/include/netdb.h</code>	Definition of <code>_PATH_SERVICES</code>

SEE ALSO

`getservent(3)`, `getservbyname(3)`, `getservbyport(3)`, `setservent(3)`, `endservent(3)`, `protocols(5)`, `listen(2)`, `inetd.conf(5)`, `inetd(8)`, Assigned Numbers RFC, most recently RFC 1700 (AKA STD0002), *Guide to Yellow Pages Service*, *Guide to BIND/Hesiod Service*.

Linux, 11 January 1996

shells

`shells`—Pathnames of valid login shells.

DESCRIPTION

`/etc/shells` is a text file that contains the full pathnames of valid login shells. This file is consulted by `chsh(1)` and is available to be queried by other programs.

EXAMPLES

`/etc/shells` may contain the following paths:

```
/bin/sh
/bin/csh
```

FILES

`/etc/shells`

SEE ALSO

`chsh(1)`

21 November 1993

syslog.conf

`syslog.conf`—`syslogd(8)` configuration file.

DESCRIPTION

The `syslog.conf` file is the configuration file for the `syslogd(8)` program. It consists of lines with two fields: the `selector` field, which specifies the types of messages and priorities to which the line applies, and an `action` field, which specifies the action to be taken if a message `syslogd` received matches the selection criteria. There cannot be any spaces in the `action` field. The `selector` field is separated from the `action` field by one or more tab or space characters. (This is a departure from the standard BSD way of doing things; both tabs and spaces can be used to separate the selector from the action.)

The `selector` functions are encoded as a facility, a period (`.`), and a level, with no intervening whitespace. Both the facility and the level are case insensitive.


```
# Root and Eric get alert and higher messages.
*.alert                                root,eric

# Save mail and news errors of level err and higher in a
# special file.
uucp,news.crit                        /var/log/spoolerr
```

FILES

`/etc/syslog.conf` The `syslogd(8)` configuration file.

BUGS

The effects of multiple selectors are sometimes not intuitive. For example `mail.crit,*err` will select mail facility messages at the level of `err` or higher, not at the level of `crit` or higher.

SEE ALSO

`syslog(3)`, `syslogd(8)`

10 May 1991

termcap

`termcap`—Terminal capability database.

DESCRIPTION

The `termcap` database is an obsolete facility for describing the capabilities of character-cell terminals and printers. It is retained only for capability with old programs; new ones should use the `terminfo(5)` database and associated libraries.

`/etc/termcap` is an ASCII file (the database master) that lists the capabilities of many different types of terminals. Programs can read `termcap` to find the particular escape codes needed to control the visual attributes of the terminal actually in use. (Other aspects of the terminal are handled by `stty`.) The `termcap` database is indexed on the `TERM` environment variable.

`termcap` entries must be defined on a single logical line, with `\` used to suppress the newline. Fields are separated by `:`. The first field of each entry starts at the left-hand margin and contains a list of names for the terminal, separated by `|`.

The first subfield may (in BSD `termcap` entries from versions 4.3 and prior) contain a short name consisting of two characters. This short name may consist of capital or small letters. In 4.4 BSD `termcap` entries, this field is omitted.

The second subfield (first in the newer 4.4 BSD format) contains the name used by the environment variable `TERM`. It should be spelled in lowercase letters. Selectable hardware capabilities should be marked by appending a hyphen and a suffix to this name. Usual suffixes are `w` (more than 80 characters wide), `am` (automatic margins), `nam` (no automatic margins) and `rv` (reverse video display). The third subfield contains a long and descriptive name for this `termcap` entry.

Subsequent fields contain the terminal capabilities; any continued capability lines must be indented one tab from the left margin.

Although there is no defined order, it is suggested to write first Boolean, then numeric, and at last string capabilities, each sorted alphabetically without looking at lower or upper spelling. Capabilities of similar functions can be written in one line.

Example:

```
Head line: vt|vt101|DEC VT 101 terminal in 80 character mode:\
Head line: Vt|vt101-w|DEC VT 101 terminal in (wide) 132 character mode:\
Boolean: :bs:\
Numeric: :co#80:\
String: :sr=nE[H:\
```


Boolean Capabilities

5i	Printer will not echo on screen
am	Automatic margins which means automatic line wrap
bs	Ctrl+H (8 dec.) performs a backspace
bw	Backspace on left margin wraps to previous line and right margin
da	Display retained above screen
db	Display retained below screen
eo	A space erases all characters at cursor position
es	Escape sequences and special characters work in status line
gn	Generic device
hc	This is a hardcopy terminal
HC	The cursor is hard to see when not on bottom line
hs	Has a status line
hz	Hazeltine bug; the terminal cannot print tilde characters
in	Terminal inserts nulls, not spaces, to fill whitespace
km	Terminal has a meta key
mi	Cursor movement works in insert mode
ms	Cursor movement works in standout/underline mode
NP	No pad character
NR	ti does not reverse te
nx	No padding; must use XON/XOFF
os	Terminal can overstrike
ul	Terminal underlines, although it cannot overstrike
xb	Beehive glitch; F1 sends Escape and F2 sends ^C
xn	Newline/wraparound glitch
xo	Terminal uses XON/XOFF protocol
xs	Text typed over standout text will be displayed in standout
xt	Telera y glitch; destructive tabs and odd standout mode

Numeric Capabilities

co	Number of columns
dB	Delay in milliseconds for backspace on hardcopy terminals
dC	Delay in milliseconds for carriage return on hardcopy terminals
dF	Delay in milliseconds for form feed on hardcopy terminals
dN	Delay in milliseconds for newline on hardcopy terminals
dT	Delay in milliseconds for tabulator stop on hardcopy terminals
dV	Delay in milliseconds for vertical tabulator stop on hardcopy terminals
it	Difference between tab positions
lh	Height of soft labels
lm	Lines of memory
lw	Width of soft labels

continues

Numeric Capabilities

li	Number of lines
Nl	Number of soft labels
pb	Lowest baud rate that needs padding
sg	Standout glitch
ug	Underline glitch
vt	Virtual terminal number
ws	Width of status line if different from screen width

String Capabilities

!1	Shifted save key
!2	Shifted suspend key
!3	Shifted undo key
#1	Shifted help key
#2	Shifted home key
#3	Shifted input key
#4	Shifted cursor left key
%0	Redo key
%1	Help key
%2	Mark key
%3	Message key
%4	Move key
%5	Next-object key
%6	Open key
%7	Options key
%8	Previous-object key
%9	Print key
%a	Shifted message key
%b	Shifted move key
%c	Shifted next key
%d	Shifted options key
%e	Shifted previous key
%f	Shifted print key
%g	Shifted redo key
%h	Shifted replace key
%i	Shifted cursor right key
%j	Shifted resume key
&0	Shifted cancel key
&1	Reference key
&2	Refresh key
&3	Replace key
&4	Restart key

String Capabilities

&5	Resume key
&6	Save key
&7	Suspend key
&8	Undo key
&9	Shifted begin key
*0	Shifted find key
*1	Shifted command key
*2	Shifted copy key
*3	Shifted create key
*4	Shifted delete character
*5	Shifted delete line
*6	Select key
*7	Shifted end key
*8	Shifted clear line key
*9	Shifted exit key
@0	Find key
@1	Begin key
@2	Cancel key
@3	Close key
@4	Command key
@5	Copy key
@6	Create key
@7	End key
@8	Enter/send key
@9	Exit key
a1	Insert one line
AL	Insert %1 lines
ac	Pairs of block graphic characters to map alternate character set
ae	End alternative character set
as	Start alternative character set for block graphic characters
bc	Backspace if not ^H
b1	Audio bell
bt	Move to previous tab stop
cb	Clear from beginning of line to cursor
cc	Dummy command character
cd	Clear to end of screen
ce	Clear to end of line
ch	Move cursor horizontally only to column %1
cl	Clear screen and cursor home
cm	Cursor move to row %1 and column %2 (on screen)
CM	Move cursor to row %1 and column %2 (in memory)

continues

String Capabilities

cr	Carriage return
cs	Scroll region from line %1 to %2
ct	Clear tabs
cv	Move cursor vertically only to line %1
dc	Delete one character
DC	Delete %1 characters
d1	Delete one line
DL	Delete %1 lines
dm	Begin delete mode
do	Cursor down one line
D0	Cursor down #1 lines
ds	Disable status line
eA	Enable alternate character set
ec	Erase %1 characters starting at cursor
ed	End delete mode
ei	End insert mode
ff	Formfeed character on hardcopy terminals
fs	Return character to its position before going to status line
F1	The string sent by function key f11
F2	The string sent by function key f12
F3	The string sent by function key f13
...	...
F9	The string sent by function key f19
FA	The string sent by function key f20
FB	The string sent by function key f21
...	...
FZ	The string sent by function key f45
Fa	The string sent by function key f46
Fb	The string sent by function key f47
...	...
Fr	The string sent by function key f63
hd	Move cursor a half line down
ho	Cursor home
hu	Move cursor a half line up
i1	Initialization string 1 at login
i3	Initialization string 3 at login
is	Initialization string 2 at login
ic	Insert one character
IC	Insert %1 characters
if	Initialization file
im	Begin insert mode

String Capabilities

ip	Insert pad time and needed special characters after insert
iP	Initialization program
K1	Upper-left key on keypad
K2	Center key on keypad
K3	Upper-right key on keypad
K4	Bottom-left key on keypad
K5	Bottom-right key on keypad
k0	Function key 0
k1	Function key 1
k2	Function key 2
k3	Function key 3
k4	Function key 4
k5	Function key 5
k6	Function key 6
k7	Function key 7
k8	Function key 8
k9	Function key 9
k;	Function key 10
ka	Clear all tabs key
kA	Insert line key
kb	Backspace key
kB	Back tab stop
kC	Clear screen key
kd	Cursor down key
kD	Key for delete character under cursor
ke	Turn keypad off
kE	Key for clear to end of line
kF	Key for scrolling forward/down
kh	Cursor home key
kH	Cursor down key
kI	Insert character/insert mode key
kI	Cursor left key
kL	Key for delete line
kM	Key for exit insert mode
kN	Key for next page
kP	Key for previous page
kr	Cursor right key
kR	Key for scrolling backward/up
ks	Turn keypad on
kS	Clear to end of screen key
kt	Clear this tab key

continues

String Capabilities

kT	Set tab here key
ku	Cursor up key
l0	Label of zeroth function key, if not f0
l1	Label of first function key, if not f1
l2	Label of first function key, if not f2
...	...
la	Label of tenth function key, if not f10
le	Cursor left one character
ll	Move cursor to lower-left corner
LE	Cursor left %1 characters
LF	Turn soft labels off
LO	Turn soft labels on
mb	Start blinking
MC	Clear soft margins
md	Start bold mode
me	End all modes such as so, us, mb, md, and mr
mh	Start half bright mode
mk	Dark mode (Characters invisible)
ML	Set left soft margin
mm	Put terminal in meta mode
mo	Put terminal out of meta mode
mp	Turn on protected attribute
mr	Start reverse mode
MR	Set right soft margin
nd	Cursor right one character
nw	Carriage return command
pc	Padding character
pf	Turn printer off
pk	Program key %1 to send string %2 as if typed by user
pl	Program key %1 to execute string %2 in local mode
pn	Program soft label %1 to show string %2
po	Turn the printer on
p0	Turn the printer on for %1 (<256) bytes
ps	Print screen contents on printer
px	Program key %1 to send string %2 to computer
r1	Reset string 1 to set terminal to sane modes
r2	Reset string 2 to set terminal to sane modes
r3	Reset string 3 to set terminal to sane modes
RA	Disable automatic margins
rc	Restore saved cursor position
rf	Reset string file name

String Capabilities

RF	Request for input from terminal
RI	Cursor right %1 characters
rp	Repeat character %1 for %2 times
rP	Padding after character sent in replace mode
rs	Reset string
RX	Turn off XON/XOFF flow control
sa	Set %1 %2 %3 %4 %5 %6%7 %8 %9 attributes
SA	Enable automatic margins
sc	Save cursor position
se	End standout mode
sf	Normal scroll one line
SF	Normal scroll %1 lines
so	Start standout mode
sr	Reverse scroll
SR	Scroll back %1 lines
st	Set tabulator stop in all rows at current column
SX	Turn on XON/XOFF flow control
ta	Move to next hardware tab
tc	Read in terminal description from another entry
te	End program that uses cursor motion
ti	Begin program that uses cursor motion
ts	Move cursor to column %1 of status line
uc	Underline character under cursor and move cursor right
ue	End underlining
up	Cursor up one line
UP	Cursor up %1 lines
us	Start underlining
vb	Visible bell
ve	Normal cursor visible
vi	Cursor invisible
vs	Standout cursor
wi	Set window from line %1 to %2 and column %3 to %4
XF	XOFF character if not ^S

There are several ways of defining the control codes for string capabilities:

Normal characters except ^, \, and % represent themselves.

A ^x means Ctrl+x. Ctrl+A equals 1 decimal. \x means a special code. x can be one of the following characters:

E	Escape (27).
n	Linefeed (10).
r	Carriage return (13).
t	Tabulation (9).

b	Backspace (8).
f	Form feed (12).
0	Null character. A \xxx specifies the octal character xxx.
i	Increments parameters by one.
r	Single parameter capability.
+	Add value of next character to this parameter and do binary output.
2	Do ASCII output of this parameter with a field width of 2.
d	Do ASCII output of this parameter with a field width of 3.
%	Print a %

If you use binary output, then you should avoid the null character because it terminates the string. You should reset tabulator expansion if a tabulator can be the binary output of a parameter.

Warning: The preceding metacharacters for parameters may be wrong; they document Minix `termcap`, which may not be compatible with Linux `termcap`.

The block graphic characters can be specified by three string capabilities:

as	Start the alternative charset.
ae	End it.
ac	Pairs of characters. The first character is the name of the block graphic symbol and the second character is its definition.

The following names are available:

+	Right arrow (>)
,	Left arrow (<)
.	Down arrow (v)
0	Full square (#)
I	Latern (#)
-	Upper arrow (^)
'	Rhombus (+)
a	Chess board (:)
f	Degree (')
g	Plus-minus (#)
h	Square (#)
j	Right bottom corner (+)
k	Right upper corner (+)
l	Left upper corner (+)
m	Left bottom corner (+)
n	Cross (+)
o	Upper horizontal line (-)
q	Middle horizontal line (·)
s	Bottom horizontal line (_)
t	Left tee (+)
u	Right tee (+)
v	Bottom tee (+)
w	Normal tee (+)
x	Vertical line (_)
-	Paragraph (???)

The values in parentheses are suggested defaults that are used by `curses` if the capabilities are missing.

SEE ALSO

`termcap(3)`, `curses(3)`, `terminfo(5)`

Linux

ttytype

`ttytype`—Terminal name and device list.

DESCRIPTION

The `/etc/ttytype` file associates `termcap`/`terminfo` terminal type names with `tty` lines. Each line consists of a terminal type, followed by whitespace, followed by a `tty` name (a device name without the `/dev/` prefix).

This association is used by the program `tset(1)` to set the environment variable `TERM` to the default terminal name for the user's current `tty`.

This facility was designed for a traditional time-sharing environment featuring character-cell terminals hardwired to a UNIX minicomputer. It is little used on modern workstation and personal UNIXes.

EXAMPLE

A typical `/etc/ttytype` is

```
con80x25 tty1
vt320 ttys0
```

FILES

`/etc/ttytype`

The `tty` definitions file

SEE ALSO

`getty(1)`, `terminfo(5)`, `termcap(5)`

Linux, 24 July 1993

tzfile

`tzfile`—Time zone information.

SYNOPSIS

```
#include <tzfile.h>
```

DESCRIPTION

The time zone information files used by `tzset(3)` begin with bytes reserved for future use, followed by six four-byte values of type `long`, written in a “standard” byte order (the high-order byte of the value is written first). These values are, in order

<code>tz_ttisgmtcnt</code>	The number of GMT/local indicators stored in the file.
<code>tz_ttisstdcnt</code>	The number of standard/wall indicators stored in the file.
<code>tz_leapcnt</code>	The number of leap seconds for which data is stored in the file.
<code>tz_timecnt</code>	The number of “transition times” for which data is stored in the file.
<code>tz_typecnt</code>	The number of “local time types” for which data is stored in the file (must not be zero).
<code>tz_charcnt</code>	The number of characters of “time zone abbreviation strings” stored in the file.

The preceding header is followed by `tzh_timecnt` four-byte values of type `long`, sorted in ascending order. These values are written in “standard” byte order. Each is used as a transition time (as returned by `time(2)`) at which the rules for computing local time change. Next come `tzh_timecnt` one-byte values of type `unsigned char`; each one tells which of the different types of “local time” types described in the file is associated with the same-indexed transition time. These values serve as indices into an array of `ttinfo` structures that appears next in the file; these structures are defined as follows:

```
struct ttinfo {
    long tt_gmtoff;
    int tt_isdst;
    unsigned int tt_abbrind;
};
```

Each structure is written as a four-byte value for `tt_gmtoff` of type `long`, in a standard byte order, followed by a one-byte value for `tt_isdst` and a one-byte value for `tt_abbrind`. In each structure, `tt_gmtoff` gives the number of seconds to be added to GMT, `tt_isdst` tells whether `tm_isdst` should be set by `localtime(3)` and `tt_abbrind` serves as an index into the array of time zone abbreviation characters that follow the `ttinfo` structures in the file.

Then there are `tzh_leapcnt` pairs of four-byte values, written in standard byte order; the first value of each pair gives the time (as returned by `time(2)`) at which a leap second occurs; the second gives the total number of leap seconds to be applied after the given time. The pairs of values are sorted in ascending order by time.

Then there are `tzh_ttsstdcnt` standard/wall indicators, each stored as a one-byte value; they tell whether the transition times associated with local time types were specified as standard time or wall clock time and are used when a time zone file is used in handling POSIX-style time zone environment variables.

Finally, there are `tzh_ttsgmtcnt` GMT/local indicators, each stored as a one-byte value; they tell whether the transition times associated with local time types were specified as GMT or local time and are used when a time zone file is used in handling POSIX-style time zone environment variables.

`Localtime` uses the first standard-time `ttinfo` structure in the file (or simply the first `ttinfo` structure in the absence of a standard-time structure) if either `tzh_timecnt` is zero or the time argument is less than the first transition time recorded in the file.

SEE ALSO

`newctime(3)`

utmp, wtmp

`utmp`, `wtmp`—Login records.

SYNOPSIS

```
#include <utmp.h>
```

DESCRIPTION

The `utmp` file allows you to discover information about who is currently using the system. There may be more users currently using the system because not all programs use `utmp` logging.

Warning: `utmp` must not be writable because many system programs depend on its integrity. You risk faked system log files and modifications of system files if you leave `utmp` writable to any user.

The file is a sequence of entries with the following structure declared in the include file:

```
#define UT_UNKNOWN 0
#define RUN_LVL 1
#define BOOT_TIME 2
#define NEW_TIME 3
#define OLD_TIME 4
```

```

#define INIT_PROCESS 5
#define LOGIN_PROCESS 6
#define USER_PROCESS 7
#define DEAD_PROCESS 8

#define UT_LINESIZE 12
#define UT_NAMESIZE 8
#define UT_HOSTSIZE 16

struct utmp {
    short ut_type;           /* type of login */
    pid_t ut_pid;           /* pid of process */
    char ut_line[UT_LINESIZE]; /* device name of tty - "/dev/" */
    char ut_id[2];          /* init id or abbrev. ttyname */
    time_t ut_time;         /* login time */
    char ut_user[UT_NAMESIZE]; /* user name */
    char ut_host[UT_HOSTSIZE]; /* host name for remote login */
    long ut_addr;           /* IP addr of remote host */
};

```

This structure gives the name of the special file associated with the user's terminal, the user's login name, and the time of login in the form of `time(2)`. String fields are terminated by `\0` if they are shorter than the size of the field.

The first entries ever created result from `init(8)` processing `inittab(5)`. Before an entry is processed, though, `init(8)` cleans up `utmp` by setting `ut_type` to `DEAD_PROCESS`, clearing `ut_user`, `ut_host` and `ut_time` with null bytes for each record that `ut_type` is not `DEAD_PROCESS` or `RUN_LVL` and where no process with PID `ut_pid` exists. If no empty record with the needed `ut_id` can be found, `init` creates a new one. It sets `ut_id` from the `inittab`, `ut_pid` and `ut_time` to the current values, and `ut_type` to `INIT_PROCESS`.

`getty(8)` locates the entry by the PID, changes `ut_type` to `LOGIN_PROCESS`, changes `ut_time`, sets `ut_line` and waits for connection to be established. `login(8)`, after a user has been authenticated, changes `ut_type` to `USER_PROCESS`, changes `ut_time`, and sets `ut_host` and `ut_addr`. Depending on `getty(8)` and `login(8)`, records may be located by `ut_line` instead of the preferable `ut_pid`.

When `init(8)` finds that a process has exited, it locates its `utmp` entry by `ut_pid`, sets `ut_type` to `DEAD_PROCESS`, and clears `ut_user`, `ut_host`, and `ut_time` with null bytes.

`xterm(1)` and other terminal emulators directly create a `USER_PROCESS` record and generate the `ut_id` by using the last two letters of `/dev/tty%c` or by using `p%d` for `/dev/pts/%d`.

If they find a `DEAD_PROCESS` for this ID, they recycle it; otherwise, they create a new entry. If they can, they will mark it as `DEAD_PROCESS` on exiting and it is advised that they null `ut_line`, `ut_time`, `ut_user`, and `ut_host` as well.

`xdm(8)` should not create an `utmp` record because there is no assigned terminal. Letting it create one will result in trouble such as `finger: cannot stat /dev/machine.dom`. It should create `wtmp` entries, though, just like `ftpd(8)` does.

`telnetd(8)` sets up a `LOGIN_PROCESS` entry and leaves the rest to `login(8)` as usual. After the Telnet session ends, `telnetd(8)` cleans up `utmp` in the described way.

The `wtmp` file records all logins and logouts. Its format is exactly like `utmp` except that a null username indicates a logout on the associated terminal. Furthermore, the terminal name `~` with username `shutdown` or `reboot` indicates a system shutdown or reboot and the pair of terminal names `"|"/"` logs the old/new system time when `date(1)` changes it. `wtmp` is maintained by `login(1)` and `init(1)` and some variation of `getty(1)`. Neither of these programs creates the file, so if it is removed, record-keeping is turned off.

FILES

```

/var/run/utmp
/var/log/wtmp

```

CONFORMING TO

Linux `utmp` entries conform neither to v7/BSD nor to SYSV: They are a mix of the two. v7/BSD has fewer fields; most importantly, it lacks `ut_type`, which causes native v7/BSD-like programs to display (for example) dead or login entries. Further there is no configuration file that allocates slots to sessions. BSD does so because it lacks `ut_id` fields. In Linux (as in SYSV), the `ut_id` field of a record will never change once it is set, which reserves that slot without needing a configuration file. Clearing `ut_id` may result in race conditions leading to corrupted `utmp` entries and potential security holes. Clearing the previously mentioned fields by filling them with null bytes is not required by SYSV semantics, but it allows you to run many programs that assume BSD semantics and that do not modify `utmp`. Linux uses the BSD conventions for line contents. SYSV only uses the type field to mark them and logs informative messages such as `new time` in the line field. SYSV has one more field to log the exit status of dead processes. `UT_UNKNOWN` seems to be a Linux invention. There is no type `ACCOUNTING` in Linux. SYSV has no `ut_host` or `ut_addr` fields. Unlike various other systems, where `utmp` logging can be disabled by removing the file, `utmp` must always exist on Linux. If you want to disable `who(1)`, then do not make `utmp` world readable.

RESTRICTIONS

The file format is machine dependent, so it is recommended that it be processed only on the machine architecture where it got created.

SEE ALSO

`ac(1)`, `date(1)`, `last(1)`, `login(1)`, `who(1)`, `getutent(3)`, `init(8)`

20 July 1996

uuencode

`uuencode`—Format of an encoded `uuencode` file.

DESCRIPTION

Files output by `uuencode(1)` consist of a header line, followed by a number of body lines, and a trailer line. The `uudecode(1)` command will ignore any lines preceding the header or following the trailer. Lines preceding a header must not, of course, look like a header.

The header line is distinguished by having the first six characters `begin`. The word `begin` is followed by a mode (in octal) and a string that names the remote file. A space separates the three items in the header line.

The body consists of a number of lines, each at most 62 characters long (including the trailing newline). These consist of a character count, followed by encoded characters, followed by a newline. The character count is a single printing character and represents an integer, the number of bytes the rest of the line represents. Such integers are always in the range from 0 to 63 and can be determined by subtracting the character space (octal 40) from the character.

Groups of three bytes are stored in four characters, six bits per character. All are offset by a space to make the characters print. The last line may be shorter than the normal 45 bytes. If the size is not a multiple of three, this fact can be determined by the value of the count on the last line. Extra garbage will be included to make the character count a multiple of four. The body is terminated by a line with a count of zero. This line consists of one ASCII space.

The trailer line consists of `end` on a line by itself.

SEE ALSO

`uuencode(1)`, `uudecode(1)`, `uuseid(1)`, `uucp(1)`, `mail(1)`

HISTORY

The `uuencode` file format appeared in BSD 4.0.

XF86Config

XF86Config—Configuration file for XFree86.

DESCRIPTION

XFree86 uses a configuration file called XF86Config for its initial setup. This configuration file is searched for in the following places:

```
/etc/XF86Config
<XRoot>/lib/X11/XF86Config.hostname
<XRoot>/lib/X11/XF86Config
```

<XRoot> refers to the root of the X11 install tree.

This file is composed of a number of sections. Each section has the form:

```
Section "SectionName"
SectionEntry ...
EndSection
```

The section names are

Files	File pathnames
ServerFlags	Server flags
Keyboard	Keyboard configuration
Pointer	Pointer configuration
Monitor	Monitor description
Device	Graphics device description
Screen	Screen configuration

The **Files** section is used to specify the default font path and the path to the RGB database. These paths can also be set from the command line (see `Xserver(1)`). The entries available for this section are

FontPath "path"	Sets the search path for fonts. This path is a comma-separated list of directories that the X server searches for font databases. Multiple FontPath entries may be specified, and they will be concatenated to build up the fontpath used by the server. X11R6 allows the X server to request fonts from a font server. A font server is specified by placing a "<trans>/<hostname>:<port_number>" entry into the fontpath. For example, the fontpath "/usr/X11R6/lib/X11/fonts/misc/,tcp/zok:7100" tells the X server to first try to locate the font in the local directory /usr/X11R6/lib/X11/fonts/misc. If that fails, then request the font from the font server running on machine zok listening for connections on TCP port number 7100.
RGBPath "path"	Sets the path name for the RGB color database.

The **ServerFlags** section is used to specify some miscellaneous X server options. The entries available for this section are

NoTrapSignals	This prevents the X server from trapping a range of unexpected fatal signals and exiting cleanly. Instead, the X server will die and drop core where the fault occurred. The default behavior is for the X server exit cleanly but still drop a core file. In general, you never want to use this option unless you are debugging an X server problem.
DontZap	This disallows the use of the Ctrl+Alt+Backspace sequence. This sequence allows you to terminate the X server. Setting DontZap allows this key sequence to be passed to clients.
DontZoom	This disallows the use of the Ctrl+Alt+Keypad-Plus and Ctrl+Alt+Keypad-Minus sequences. These sequences allow you to switch between video modes. Setting DontZoom allows these key sequences to be passed to clients.

The Keyboard section is used to specify the keyboard input device, parameters, and some default keyboard mapping options. The entries available for this section are

Protocol "kbd-protocol"	kbd-protocol may be either Standard or Xqueue. Xqueue is specified when using the event queue driver on SVR3 or SVR4.
AutoRepeat delay rate	Changes the behavior of the autorepeat of the keyboard. This does not work on all platforms.
ServerNumLock	Forces the X server to handle the numlock key internally. The X server sends a different set of keycodes for the numpad when the numlock key is active. This enables applications to make use of the numpad.

LeftAlt mapping RightAlt mapping AltGr mapping
ScrollLock mapping RightCtl mapping

Allows a default mapping to be set for the preceding keys (note that AltGr is a synonym for RightAlt). The values that may be specified for mapping are

Meta
Compose
ModeShift
ModeLock
ScrollLock
Control

The default mapping when none of these options are specified is

LeftAlt Meta
RightAlt Meta
ScrollLock Compose
RightCtl Control

XLeds led ...	Makes led available for clients instead of using the traditional function (Scroll Lock, Caps Lock, and Num Lock). led is a list of numbers in the range 1 to 3.
VTSysReq	Enables the SYSV-style VT switch sequence for non-SYSV systems that support VT switching. This sequence is Alt-SysRq followed by a function key (Fn). This prevents the X server trapping the keys used for the default VT switch sequence.
VTInit "command"	Runs command after the VT used by the server has been opened. The command string is passed to /bin/sh -c and is run with the real user's ID with stdin and stdout set to the VT. The purpose of this option is to allow system-dependent VT initialization commands to be run. One example is a command to disable the two-key VT switching sequence that is the default on some systems.

The Pointer section is used to specify the pointer device and parameters. The entries available for this section are

Protocol "protocol-type"	Specifies the pointer device protocol type. The protocol types available are
BusMouse	
Logitech	
Microsoft	
MMSeries	
Mouseman	
MouseSystems	
PS/2	

MMHitTab

Xqueue

OSMouse

One should specify `BusMouse` for the Logitech bus mouse. Also, many newer Logitech serial mice use either the Microsoft or MouseMan protocol. `Xqueue` should be specified here if it was used in the Keyboard section. `OSMouse` refers to the event-driver mouse interface available on SCO's SVR3. This may optionally be followed by a number specifying the number of buttons the mouse has.

Device "pointer-dev"	Specifies the device the server should open for pointer input (such as <code>/dev/tty00</code> or <code>/dev/mouse</code>). A device should not be specified when using the <code>Xqueue</code> or <code>OSMouse</code> protocols.
BaudRate rate	Sets the baud rate of the serial mouse to <code>rate</code> . For mice that allow dynamic speed adjustments (such as Logitech), the baud rate is changed in the mouse. Otherwise, the rate is simply set on the computer's side to allow mice with non-standard rates (the standard rate is 1200).
Emulate3Buttons	Enables the emulation of the third mouse button for mice that only have two physical buttons. The third button is emulated by pressing both buttons simultaneously.
Emulate3Timeout timeout	Sets the time (in milliseconds) that the server waits before deciding if two buttons were pressed "simultaneously" when three-button emulation is enabled. The default time-out is 50ms.
ChordMiddle	Handles mice that send left+right events when the middle button is used (such as some Logitech Mouseman mice).
SampleRate rate	Sets the number of motion/button-events the mouse sends per second. This is currently only supported for some Logitech mice.
ClearDTR	This option clears the DTR line on the serial port used by the mouse. This option is only valid for a mouse using the <code>MouseSystems</code> protocol. Some dual-protocol mice require DTR to be cleared to operate in <code>MouseSystems</code> mode. Note, in versions of <code>XFree86</code> prior to 2.1, this option also cleared the RTS line. A separate <code>ClearRTS</code> option has since been added for mice that require this.
ClearRTS	This option clears the RTS line on the serial port used by the mouse. This option is only valid for a mouse using the <code>MouseSystems</code> protocol. Some dual-protocol mice require both DTR and RTS to be cleared to operate in <code>MouseSystems</code> mode. Both the <code>ClearDTR</code> and <code>ClearRTS</code> options should be used for such mice.

The Monitor sections are used to define the specifications of a monitor and a list of video modes suitable for use with a monitor. More than one Monitor section may be present in an `XF86Config` file. The entries available for this section are

Identifier "ID string"	This specifies a string by which the monitor can be referred to in a later Screen section. Each Monitor section should have a unique ID string.
VendorName "vendor"	This optional entry specifies the monitor's manufacturer.
ModelName "model"	This optional entry specifies the monitor's model.
HorizSync horisync-range	Gives the ranges of horizontal sync frequencies supported by the monitor. <code>horisync-range</code> may be a comma-separated list of either discrete values or ranges of values. A range of values is two values separated by a dash. By default, the values are in units of kHz. They may be specified in MHz or Hz if MHz or Hz is added to the end of the line. The data given here is used by the X server to determine if video modes are within the specifications of the monitor. This information should be available in the monitor's handbook.

VertRefresh *vertrefresh-range*

Gives the ranges of vertical refresh frequencies supported by the monitor. *vertrefresh-range* may be a comma-separated list of either discrete values or ranges of values. A range of values is two values separated by a dash. By default, the values are in units of Hz. They may be specified in MHz or kHz if MHz or kHz is added to the end of the line. The data given here is used by the X server to determine if video modes are within the specifications of the monitor. This information should be available in the monitor's handbook.

Gamma *gamma-values*

This is an optional entry that can be used to specify the gamma correction for the monitor. It may be specified as either a single value or as three separate RGB values. Not all X servers are capable of using this information.

Mode *"name"*

Indicates the start of a multi-line video mode description. The mode description is terminated with an End-Mode line. The mode description consists of the following entries:

DotClock *clock*

The dot clock rate to be used for the mode.

HTimings *hdisp hsyncstart hsyncend htotal*

Specifies the horizontal timings for the mode.

VTimings *vdisp vsyncstart vsyncend vtotal*

Specifies the vertical timings for the mode.

Flags *"flag" ...*

Specifies an optional set of mode flags. *Interlace* indicates that the mode is interlaced. *DoubleScan* indicates a mode where each scanline is doubled. *+HSync* and *-HSync* can be used to select the polarity of the HSync signal. *+VSync* and *-VSync* can be used to select the polarity of the VSync signal. *Composite* can be used to specify composite sync on hardware where this is supported. Additionally, on some hardware, *+CSync* and *-CSync* may be used to select the composite sync polarity.

Modeline *"name" mode-description*

A single line format for specifying video modes. The *mode-description* is in four sections, the first three of which are mandatory. The first is the pixel clock. This is a single number specifying the pixel clock rate for the mode. The second section is a list of four numbers specifying the horizontal timings. These numbers are the *hdisp*, *hsyncstart*, *hsyncend*, *htotal*. The third section is a list of four numbers specifying the vertical timings. These numbers are *vdisp*, *vsyncstart*, *vsyncend*, *vtotal*. The final section is a list of flags specifying other characteristics of the mode. *Interlace* indicates that the mode is interlaced. *DoubleScan* indicates a mode where each scanline is doubled. *+HSync* and *-HSync* can be used to select the polarity of the HSync signal. *+VSync* and *-VSync* can be used to select the polarity of the VSync signal. *Composite* can be used to specify composite sync on hardware where this is supported. Additionally, on some hardware, *+CSync* and *-CSync* may be used to select the composite sync polarity.

The Device sections are used to define a graphics device (video board). More than one Device section may be present in an *XF86Config* file. The entries available for this section are

Identifier *"ID string"*

This specifies a string by which the graphics device can be referred to in a later Screen section. Each Device section should have a unique ID string.

VendorName *"vendor"*

This optional entry specifies the graphics device's manufacturer.

BoardName *"model"*

This optional entry specifies the name of the graphics device.

Chipset *"chipset-type"*

This optional entry specifies the chipset used on the graphics board. In most cases, this entry is not required because the X servers will probe the hardware to determine the chipset type.

Ramdac "ramdac-type"	This optional entry specifies the type of RAMDAC used on the graphics board. This is only used by a few of the X servers, and in most cases, it is not required because the X servers will probe the hardware to determine the RAMDAC type where possible.
DacSpeed speed	This optional entry specifies the RAMDAC speed rating (which is usually printed on the RAMDAC chip). The speed is in MHz. This is only used by a few of the X servers and only needs to be specified when the speed rating of the RAMDAC is different from the default built in to the X server.
Clocks clock ...	Specifies the dotclocks that are on your graphics board. The clocks are in MHz and may be specified as a floating-point number. The value is stored internally to the nearest kHz. The ordering of the clocks is important. It must match the order in which they are selected on the graphics board. Multiple <code>clocks</code> lines may be specified. For boards with programmable clock chips, the <code>clockchip</code> entry should be used instead of this. A <code>clocks</code> entry is not mandatory for boards with non-programmable clock chips but is highly recommended because it prevents the clock probing phase during server startup. This clock probing phase can cause problems for some monitors.
ClockChip "clockchip-type"	This optional entry is used to specify the clock chip type on graphics boards that have a programmable clock generator. Only a few X servers support programmable clock chips. For details, see the appropriate X server manual page.
ClockProg command [textclock]	This optional entry runs <code>command</code> to set the clock on the graphics board instead of using the internal code. The command string must consist of the full pathname (and no flags). When using this option, a <code>clocks</code> entry is required to specify which clock values are to be made available to the server (up to 128 clocks may be specified). The optional <code>textclock</code> value is to tell the server that <code>command</code> must be run to restore the text-mode clock at server exit (or when VT switching). <code>textclock</code> must match one of the values in the <code>clocks</code> entry. This parameter is required when the clock used for text mode is a programmable clock. The command is run with the real user's ID with <code>stdin</code> and <code>stdout</code> set to the graphics console device. Two arguments are passed to the command. The first is the clock frequency in MHz as a floating-point number and the second is the index of the clock in the <code>clocks</code> entry. The command should return an exit status of 0 when successful and something in the range 1–254 otherwise. The command is run when the initial graphics mode is set and when changing screen resolution with the hotkey sequences. If the program fails at initialization, the server exits. If it fails during a mode switch, the mode switch is aborted but the server keeps running. It is assumed that if the command fails, the clock has not been changed.
Option optionstring	This optional entry allows the user to select certain options provided by the drivers. Multiple <code>Option</code> entries may be given. The supported values for <code>optionstring</code> are given in the appropriate X server manual pages.
VideoRam mem	This optional entry specifies the amount of video RAM that is installed on the graphics board. This is measured in kilobytes. In most cases, this is not required because the X server probes the graphics board to determine this quantity.
BIOSBase baseaddress	This optional entry specifies the base address of the video BIOS for the VGA board. This address is usually 0xC0000, which is the default the X servers use. Some systems, particularly those with on-board VGA hardware, have the BIOS located at an alternate address, usually 0xE0000. If your video BIOS is at an address other than 0xC0000, you must specify the base address in the <code>XF86Config</code> file. Note that some X servers don't access the BIOS at all and those that do only use the BIOS when searching for information during the hardware probe phase.

MemBase baseaddress	This optional entry specifies the memory base address of a graphics board's linear frame buffer. This entry is only used by a few X servers, and the interpretation of this base address may be different for different X servers. Refer to the appropriate X server manual page for details.
IOBase baseaddress	This optional entry specifies the IO base address. This entry is only used for a few X servers. Refer to the appropriate X server manual page for details.
DACBase baseaddress	This optional entry specifies the DAC base address. This entry is only used for a few X servers. Refer to the appropriate X server manual page for details.
POSBase baseaddress	This optional entry specifies the POS base address. This entry is only used for a few X servers. Refer to the appropriate X server manual page for details.
COPBase baseaddress	This optional entry specifies the coprocessor base address. This entry is only used for a few X servers. Refer to the appropriate X server manual page for details.
VGABase baseaddress	This optional entry specifies the VGA memory base address. This entry is only used for a few X servers. Refer to the appropriate X server manual page for details.
Instance number	This optional entry specifies the instance (which indicates if the chip is integrated on the motherboard or on an expansion card). This entry is only used for a few X servers. Refer to the appropriate X server manual page for details.
Speedup selection	This optional entry specifies the selection of speedups to be enabled. This entry is only used for a few X servers. Refer to the appropriate X server manual page for details.
S3MNAdjust MN	This optional entry is specific to the S3 X server. For details, refer to the XF86_S3(1) manual page.
S3MC1k clock	This optional entry is specific to the S3 X server. For details, refer to the XF86_S3(1) manual page.
S3RefClock clock	This optional entry is specific to the S3 X server. For details, refer to the XF86_S3(1) manual page.

The Screen sections are used to specify which graphics boards and monitors are used with a particular X server and the configuration in which they are to be used. The entries available for this section are

Driver driver-name	Each Screen section must begin with a Driver entry, and the driver-name given in each Screen section must be unique. The driver-name determines which X server (or driver type within an X server when an X server supports more than one head) reads and uses a particular Screen section. The driver names available are Accel Mono SVGA VGA2 VGA16 Accel is used by all the accelerated X servers (see XF86_Accel(1)). Mono is used by the non-VGA mono drivers in the 2-bit and 4-bit X servers (see XF86_Mono(1) and XF86_VGA16(1)). VGA2 and VGA16 are used by the VGA drivers in the 2-bit and 4-bit X servers. SVGA is used by the XF86_SVGA X server.
Device device-id	Specifies which graphics device description is to be used.
Monitor monitor-id	Specifies which monitor description is to be used.
ScreenNo scrnum	This optional entry overrides the default screen numbering in a multi-headed configuration. The default numbering is determined by the ordering of the Screen sections in the XF86Config file. To override this, all relevant Screen sections must have this entry specified.

BlankTime time	Sets the inactivity time-out for the blanking phase of the screensaver. time is in minutes, and the default is 10. This is equivalent to the X server's -s flag, and the value can be changed at runtime with xset(1).
SuspendTime time	Sets the inactivity time-out for the "suspend" phase of the screensaver. time is in minutes, the default is 15, and it can be changed at runtime with xvidthune(1). This is only suitable for VESA DPMS compatible monitors and is only supported currently by some X servers. The "power_saver" option must be set for this to be enabled.
OffTime time	Sets the inactivity time-out for the "off" phase of the screensaver. time is in minutes, the default is 30, and it can be changed at runtime with xvidthune(1). This is only suitable for VESA DPMS compatible monitors and is only supported currently by some X servers. The "power_saver" option must be set for this to be enabled.
SubSection Display	This entry is a subsection that is used to specify some display specific parameters. This subsection is terminated by an EndSubSection entry. For some X servers and drivers (those requiring a list of video modes), this subsection is mandatory. For X servers that support multiple display depths, more than one Display subsection can be present. When multiple Display subsections are present, each must have a unique Depth entry. The entries available for the Display subsection are
Depth bpp	This entry is mandatory when more than one Display subsection is present in a Screen section. When only one Display subsection is present, it specifies the default depth where the X server will run. When more than one Display subsection is present, the depth determines which gets used by the X server. The subsection used is the one matching the depth at which the X server is run. Not all X servers (or drivers) support more than one depth. Permitted values for bpp are 8, 15, 16, 24, and 32. Not all X servers (or drivers) support all these values. bpp values of 24 and 32 are treated equivalently by those X servers that support them.
Weight RGB	This optional entry specifies the relative RGB weighting to be used for an X server running at 16bpp. This may also be specified from the command line (see XFree86(1)). Values supported by most 16bpp X servers are 555 and 565. For further details, refer to the appropriate X server manual page.
Virtual xdim ydim	This optional entry specifies the virtual screen resolution to be used. xdim must be a multiple of either 8 or 16 for most color X servers and a multiple of 32 for the monochrome X server. The given value is rounded down if this is not the case. For most X servers, video modes that are too large for the specified virtual size are rejected. If this entry is not present, the virtual screen resolution is set to accommodate all the valid video modes given in the Modes entry. Some X servers do not support this entry. Refer to the appropriate X server manual pages for details.
ViewPort x0 y0	This optional entry sets the upper-left corner of the initial display. This is only relevant when the virtual screen resolution is different from the resolution of the initial video mode. If this entry is not given, then the initial display is centered in the virtual display area.
Modes modename ...	This entry is mandatory for most X servers, and it specifies the list of video modes to use. The video mode names must correspond to those specified in the appropriate Monitor section. Most X servers delete modes from this list that don't satisfy various requirements. The first valid mode in this list is the default display mode for startup. The list of valid modes is converted internally into a circular list. It is possible to switch to the next mode with Ctrl+Alt+Keypad Plus and to the previous mode with Ctrl+Alt+Keypad Minus.
InvertVCLK modename 0 1	This optional entry is specific to the S3 server only. It can be used to change the default VCLK invert/non-invert state for individual modes. If "modename" is "", the setting applies to all modes unless overridden by later entries.

EarlySC modename 0 1	This optional entry is specific to the S3 server only. It can be used to change the default EarlySC setting for individual modes. This setting can affect screen wrapping. If "modename" is "", the setting applies to all modes unless overridden by later entries.
BlankDelay modename value1 value2	This optional entry is specific to the S3 server only. It can be used to change the default blank delay settings for individual modes. This can affect screen wrapping. value1 and value2 must be integers in the range 0–7. If "modename" is "", the setting applies to all modes unless overridden by later entries.
Visual visual-name	This optional entry sets the default root visual type. This can also be specified from the command line (see <code>xserver(1)</code>). The visual types available for 8bpp X servers are (default is <code>PseudoColor</code>): StaticGray GrayScale StaticColor PseudoColor TrueColor DirectColor The visual type available for the 16bpp and 32bpp X servers is <code>TrueColor</code> . The visual type available for the 1bpp X server is <code>StaticGray</code> . The visual types available for the 4bpp X server are (default is <code>PseudoColor</code>): StaticGray GrayScale StaticColor PseudoColor
Option optionstring	This optional entry allows the user to select certain options provided by the drivers. Multiple <code>Option</code> entries can be given. The supported values for <code>option-string</code> are given in the appropriate X server manual pages.
Black red green blue	This optional entry allows the “black” color to be specified. This is only supported with the VGA2 driver in the <code>XF86_Mono</code> server (for details, see <code>XF86_Mono(1)</code>).
White red green blue	This optional entry allows the “white” color to be specified. This is only supported with the VGA2 driver in the <code>XF86_Mono</code> server (for details, see <code>XF86_Mono(1)</code>).

For an example of an `XF86Config` file, see the file installed as `<XRoot>/lib/X11/XF86Config.eg`.

FILES

```
/etc/XF86Config
<XRoot>/lib/X11/XF86Config. hostname <XRoot>/lib/X11/XF86Config
```

Note that `<XRoot>` refers to the root of the X11 install tree.

SEE ALSO

`X(1)`, `Xserver(1)`, `XFree86(1)`, `XF86_SVGA(1)`, `XF86_VGA16(1)`, `XF86_Mono(1)`, `XF86_S3(1)`, `XF86_8514(1)`, `XF86_Mach8(1)`, `XF86_Mach32(1)`, `XF86_P9000(1)`, `XF86_AGX(1)`, `XF86_W32(1)`

AUTHORS

Refer to the `XFree86(1)` manual page.

Part VI:

Games

intro

intro—Introduction to games.

DESCRIPTION

This chapter describes all the games and funny little programs available on the system.

AUTHORS

Look at the header of the manual page for the authors and copyright conditions. Note that these can be different from page to page!

Linux, 24 July 1993

banner

banner—Print large banner on printer.

SYNOPSIS

```
/usr/games/banner [ -wn ] message ...
```

DESCRIPTION

banner prints a large, high-quality banner on the standard output. If the message is omitted, it prompts for and reads one line of its standard input. If `-w` is given, the output is scrunched down from a width of 132 to `n`, suitable for a narrow terminal. If `n` is omitted, it defaults to 80.

The output should be printed on a hard-copy device, up to 132 columns wide, with no breaks between the pages. The volume is great enough that you might want a printer or a fast hard-copy terminal, but if you are patient, a decwriter or other 300 baud terminal will do.

BUGS

Several ASCII characters are not defined, notably `<`, `>`, `[`, `]`, `\`, `^`, `_`, `{`, `}`, `|`, and ```. Also, the characters `"`, `'`, and `&` are funny-looking (but in a useful way).

The `-w` option is implemented by skipping some rows and columns. The smaller it gets, the grainier the output. Sometimes it runs letters together.

AUTHOR

Mark Horton

6 June 1993

ddate

ddate—Converts boring normal dates to fun Discordian dates.

SYNOPSIS

```
ddate
```

DESCRIPTION

`ddate` prints the date in Discordian date format.

AUTHOR

Druel the Chaotic, a.k.a. Jeremy Johnson (`mpython@gnu.ai.mit.edu`). Modifications for UNIX by Lee Harvey Oswald Smith, K.S.C. Five tons of flax.

55 Confusion 3160

Part VII:

Miscellaneous

intro

intro—Introduction to miscellany section.

DESCRIPTION

This chapter describes miscellaneous things such as `nroff` macro packages, tables, C header files, the file hierarchy, general concepts, and other things that don't fit anywhere else.

AUTHORS

Look at the header of the manual page for the authors and copyright conditions. Note that these can be different from page to page!

Linux, 23 April 1993

ascii

ascii—The ASCII character set encoded in octal, decimal, and hexadecimal

DESCRIPTION

The following table contains the 128 ASCII characters.

C program '\X' escapes are noted.

<i>Oct</i>	<i>Dec</i>	<i>Hex</i>	<i>Char</i>	<i>Oct</i>	<i>Dec</i>	<i>Hex</i>	<i>Char</i>
000	0	00	NUL '\0'	100	64	40	@
001	1	01	SOH	101	65	41	A
002	2	02	STX	102	66	42	B
003	3	03	ETX	103	67	43	C
004	4	04	EOT	104	68	44	D
005	5	05	ENQ	105	69	45	E
006	6	06	ACK	106	70	46	F
007	7	07	BEL '\a'	107	71	47	G
010	8	08	BS '\b'	110	72	48	H
011	9	09	HT '\t'	111	73	49	I
012	10	0A	LF '\n'	112	74	4A	J
013	11	0B	VT '\v'	113	75	4B	K
014	12	0C	FF '\f'	114	76	4C	L
015	13	0D	CR '\r'	115	77	4D	M
016	14	0E	SO	116	78	4E	N
017	15	0F	SI	117	79	4F	O
020	16	10	DLE	120	80	50	P
021	17	11	DC1	121	81	51	Q
022	18	12	DC2	122	82	52	R
023	19	13	DC3	123	83	53	S
024	20	14	DC4	124	84	54	T
025	21	15	NAK	125	85	55	U
026	22	16	SYN	126	86	56	V

<i>Oct</i>	<i>Dec</i>	<i>Hex</i>	<i>Char</i>	<i>Oct</i>	<i>Dec</i>	<i>Hex</i>	<i>Char</i>
027	23	17	ETB	127	87	57	W
030	24	18	CAN	130	88	58	X
031	25	19	EM	131	89	59	Y
032	26	1A	SUB	132	90	5A	Z
033	27	1B	ESC	133	91	5B	[
034	28	1C	FS	134	92	5C	\'\'
035	29	1D	GS	135	93	5D	]
036	30	1E	RS	136	94	5E	^
037	31	1F	US	137	95	5F	_
040	32	20	SPACE	140	96	60	'
041	33	21	!	141	97	61	a
042	34	22	"	142	98	62	b
043	35	23	#	143	99	63	c
044	36	24	\$	144	100	64	d
045	37	25	%	145	101	65	e
046	38	26	&	146	102	66	f
047	39	27	'	147	103	67	g
050	40	28	(	150	104	68	h
051	41	29	)	151	105	69	i
052	42	2A	*	152	106	6A	j
053	43	2B	+	153	107	6B	k
054	44	2C	,	154	108	6C	l
055	45	2D	-	155	109	6D	m
056	46	2E	.	156	110	6E	n
057	47	2F	/	157	111	6F	o
060	48	30	0	160	112	70	p
061	49	31	1	161	113	71	q
062	50	32	2	162	114	72	r
063	51	33	3	163	115	73	s
064	52	34	4	164	116	74	t
065	53	35	5	165	117	75	u
066	54	36	6	166	118	76	v
067	55	37	7	167	119	77	w
070	56	38	8	170	120	78	x
071	57	39	9	171	121	79	y
072	58	3A	:	172	122	7A	z
073	59	3B	;	173	123	7B	{
074	60	3C	<	174	124	7C	
075	61	3D	=	175	125	7D	}
076	62	3E	>	176	126	7E	~
077	63	3F	?	177	127	7F	DEL

HISTORY

An `ascii` manual page appeared in version 7 AT&T UNIX.

SEE ALSO

`iso_8859_1(7)`

Linux

bootparam

`bootparam`—Introduction to boot-time parameters of the Linux kernel.

DESCRIPTION

The Linux kernel accepts certain command-line options or boot-time parameters at the moment it is started. In general, this is used to supply the kernel with information about hardware parameters that the kernel would not be able to determine on its own, or to avoid or override the values that the kernel would otherwise detect.

When the kernel is booted directly by the BIOS (say, from a floppy to which you copied a kernel using `cp zImage /dev/fd0`), you have no opportunity to specify any parameters. To take advantage of this possibility, you have to use software that is able to pass parameters, such as LILO or loadlin. For a few parameters, one can also modify the kernel image itself, using `rdev`; see `rdev(8)` for further details.

The LILO program (LInux LOader) written by Werner Almesberger is the most commonly used. It has the ability to boot various kernels and stores the configuration information in a plain text file. (See `lilo(8)` and `lilo.conf(5)`.) LILO can boot DOS, OS/2, Linux, FreeBSD, and so on and is quite flexible.

The other commonly used Linux loader is loadlin, which is a DOS program that has the capability to launch a Linux kernel from the DOS prompt (with boot args) assuming that certain resources are available. This is good for people who want to launch Linux from DOS.

It is also very useful if you have certain hardware that relies on the supplied DOS driver to put the hardware into a known state. A common example is SoundBlaster-compatible sound cards that require the DOS driver to twiddle a few mystical registers to put the card into a SB-compatible mode. Booting DOS with the supplied driver and then loading Linux from the DOS prompt with loadlin avoids the reset of the card that happens if one reboots instead.

THE ARGUMENT LIST

Most of the boot args take the form of

```
name=[value_1][,value_2]...[,value_11]
```

`name` is a unique keyword that is used to identify what part of the kernel the associated values (if any) are to be given to. Multiple boot args are just a space-separated list of the preceding format. Note the limit of 11 is real because the present code handles only 11 comma-separated parameters per keyword. (However, you can reuse the same keyword with up to an additional 11 parameters in unusually complicated situations, assuming the setup function supports it.)

Most of the sorting occurs in `linux/init/main.c`. First, the kernel checks to see if the argument is any of the special arguments `root=`, `ro`, `rw`, or `debug`. The meaning of these special arguments is described later in the document.

Then, it walks a list of setup functions (contained in the `bootsetups` array) to see if the specified argument string (such as `foo`) is associated with a setup function (`foo_setup()`) for a particular device or part of the kernel. If you passed the kernel the line `foo=3,4,5,6`, then the kernel searches the `bootsetups` array to see if `foo` is registered. If it is, it calls the setup function associated with `foo` (`foo_setup()`) and hands it the arguments 3, 4, 5, and 6 as given on the kernel command line.

Anything of the form `foo=bar` that is not accepted as a setup function as described is then interpreted as an environment variable to be set. A (useless?) example is to use `TERM=vt100` as a boot argument.

Any remaining arguments that were not picked up by the kernel and were not interpreted as environment variables are then passed onto process one, which is usually the `init` program. The most common argument that is passed to the `init` process is the word `single`, which instructs `init` to boot the computer in single-user mode and not launch all the usual daemons. Check the manual page for the version of `init` installed on your system to see what arguments it accepts.

GENERAL NON-DEVICE-SPECIFIC BOOT ARGS

`no387`

Some i387 coprocessor chips have bugs that show up when used in 32-bit protected mode.

For example, some of the early ULSI-387 chips cause solid lockups while performing floating-point calculations. Using the '`no387`' boot arg causes Linux to ignore the maths coprocessor even if you have one. Of course, you must then have your kernel compiled with math emulation support!

`no-hlt`

Some of the early i486DX-100 chips have a problem with the `hlt` instruction in that they can't reliably return to operating mode after this instruction is used. Using the '`no-hlt`' instruction tells Linux to just run an infinite loop when there is nothing else to do and to not halt the CPU. This allows people with these broken chips to use Linux.

`root=...`

This argument tells the kernel what device is to be used as the root filesystem while booting. The default of this setting is determined at compile time and usually is the value of the root device of the system that the kernel was built on. To override this value and select the second floppy drive as the root device, one uses '`root=/dev/fd1`'. (The root device can also be set using `rdev(8)`.)

The root device can be specified symbolically or numerically. A symbolic specification has the form `/dev/XXYN`, where `XX` designates the device type (`hd` for ST-506-compatible hard disk with `Y` in `a-h`; `sd` for SCSI-compatible disk with `Y` in `a-e`; `xd` for XT-compatible disk with `Y` either `a` or `b`; `fd` for floppy disk with `Y` the floppy drive number—`fd0` is the DOS A: drive and `fd1` is B:), `Y` is the driver letter or number, and `N` is the number of the partition on this device (absent in the case of floppies).

Note that this has nothing to do with the designation of these devices on your filesystem. The `/dev/` part is purely conventional.

The more awkward and less portable numeric specification of the previous possible root devices in major/minor format is also accepted. (For example, `/dev/sda3` is major 8, minor 3, so you can use `root=0x803` as an alternative.)

`ro` and `rw`

The `ro` option tells the kernel to mount the root filesystem as `readonly` so that filesystem consistency check programs (`fsck`) can do their work on a quiescent file system. No processes can write to files on the filesystem in question until it is remounted as read/write capable, such as by `mount -w -n -o remount /`. (See also `mount(8)`.)

The `rw` option tells the kernel to mount the root filesystem read/write. This is the default.

The choice between read-only and read/write can also be set using `grdev(8)`.

`debug`

Kernel messages are handed off to the kernel log daemon `klogd` so that they can be logged to disk. Messages with a priority above `console_loglevel` are also printed on the console. (For these levels, see `<linux/kernel.h>`.) By default, this variable is set to log anything more important than debug messages. This boot argument causes the kernel to also print the messages of `DEBUG` priority. The console log level can also be set at runtime via an option to `klogd`. See `klogd(8)`.

`reserve=...`

This is used to protect I/O port regions from probes. The form of the command is

```
reserve=iobase,extent[, iobase,extent]...
```

In some machines, it might be necessary to prevent device drivers from checking for devices (auto-probing) in a specific region. This may be because of hardware that reacts badly to the probing, hardware that would be mistakenly identified, or hardware you don't want the kernel to initialize.

The `reserve` boot-time argument specifies an I/O port region that shouldn't be probed. A device driver does not probe a reserved region unless another boot argument explicitly specifies that it do so.

For example, the boot line

```
reserve=0x300,32 blah=0x300
```

keeps all device drivers except the driver for `blah` from probing 0x300-0x31f.

ramdisk=...

This option is obsolete since Linux 1.3.48 or so. It specifies the size in kilobytes of the optional RAM disk device. For example, if one wants to have a root filesystem on a 1.44MB floppy loaded into the RAM disk device, they use

```
ramdisk=1440
```

This option is set at compile time (default is no RAM disk), and can be modified using `rdev(8)`.

mem=...

The BIOS call defined in the PC specification that returns the amount of installed memory was only designed to be able to report up to 64MB. Linux uses this BIOS call at boot to determine how much memory is installed. If you have more than 64MB of RAM installed, you can use this boot arg to tell Linux how much memory you have. The value is in decimal or hexadecimal (prefix 0x), and the suffixes `K` (times 1024) or `M` (times 1048576) can be used. The following quote from Linus describes the use of the `mem=` parameter:

“The kernel will accept any `mem=xx` parameter you give it, and if it turns out that you lied to it, it will crash horribly sooner or later. The parameter indicates the highest addressable RAM address, so '`mem=0x1000000`' means you have 16MB of memory, for example. For a 96MB machine this would be `mem=0x6000000`.

NOTE: Some machines might use the top of memory for BIOS caching or whatever, so you might not actually have up to the full 96MB addressable. The reverse is also true: Some chipsets will map the physical memory that is covered by the BIOS area into the area just past the top of memory, so the top-of-mem might actually be 96MB + 384KB, for example. If you tell Linux that it has more memory than it actually does have, bad things will happen: maybe not at once, but surely eventually.”

reboot=warm

Since 2.0.22, a reboot is by default a cold reboot. This command-line option changes back to the old default, a warm reboot.

BOOT ARGUMENTS FOR SCSI DEVICES

General notation for this section:

iobase—the first I/O port that the SCSI host occupies. These are specified in hexadecimal notation and usually lie in the range from 0x200 to 0x3ff.

irq—the hardware interrupt that the card is configured to use. Valid values are dependent on the card in question but are usually 5, 7, 9, 10, 11, 12, and 15. The other values are usually used for common peripherals such as IDE hard disks, floppies, serial ports, and so on.

scsi.id—the ID that the host adapter uses to identify itself on the SCSI bus. Only some host adapters allow you to change this value because most have it permanently specified internally. The usual default value is 7, but the Seagate and Future Domain TMC-950 boards use 6.

parity—whether the SCSI host adapter expects the attached devices to supply a parity value with all information exchanges. Specifying a 1 indicates parity checking is enabled, and a 0 disables parity checking. Again, not all adapters support selection of parity behavior as a boot argument.

```
max_scsi_luns=...
```

A SCSI device can have a number of subdevices contained within itself. The most common example is one of the new SCSI CD-ROMs that handle more than one disk at a time. Each CD is addressed as a Logical Unit Number (LUN) of that particular device. Most devices, such as hard disks and tape drives, are only one device and are assigned to LUN 0.

Some poorly designed SCSI devices cannot handle being probed for LUNs not equal to 0. Therefore, if the compile-time flag `CONFIG SCSI MULTI LUN` is not set, newer kernels by default only probe LUN 0.

To specify the number of probed LUNs at boot, one enters `max_scsi_luns=n` as a boot arg, where `n` is a number between 1 and 8. To avoid problems as described, one uses `n=1` to avoid upsetting such broken devices.

SCSI TAPE CONFIGURATION

Some boot-time configuration of the SCSI tape driver can be achieved with the following:

```
st=buf_size[,write_threshold[,max_bufs]]
```

The first two numbers are specified in units of kilobytes. The default `buf_size` is 32KB, and the maximum size that can be specified is a ridiculous 16384KB. The `write_threshold` is the value at which the buffer is committed to tape with a default value of 30KB. The maximum number of buffers varies with the number of drives detected and has a default of two. A sample usage is

```
st=32,30,2
```

Full details can be found in the `README.st` file that is in the `scsi` directory of the kernel source tree.

ADAPTEC AHA151X, AHA152X, AIC6260, AIC6360, SB16-SCSI CONFIGURATION

The `aha` numbers refer to cards and the `aic` numbers refer to the actual SCSI chip on these types of cards, including the SoundBlaster-16 SCSI.

The probe code for these SCSI hosts looks for an installed BIOS, and if none is present, the probe will not find your card. Then you must use a boot arg of the form:

```
aha152x=iobase[,irq[,scsi-id[,reconnect[,parity]]]]
```

If the driver was compiled with debugging enabled, a sixth value can be specified to set the debug level.

All the parameters are as described at the top of this section, and the `reconnect` value allows device disconnect/reconnect if a nonzero value is used. A sample usage is as follows:

```
aha152x=0x340,11,7,1
```

Note that the parameters must be specified in order, meaning that if you want to specify a parity setting, then you must specify an `iobase`, `irq`, `scsi-id`, and `reconnect` value as well.

ADAPTEC AHA154X CONFIGURATION

The `aha1542` series cards have an `i82077` floppy controller on board, whereas the `aha1540` series cards do not. These are bus-mastering cards and have parameters to set the “fairness” that is used to share the bus with other devices. The boot arg looks like the following:

```
aha1542=iobase[,buson,busoff[,dmaspeed]]
```

Valid `iobase` values are usually one of `0x130`, `0x134`, `0x230`, `0x234`, `0x330`, or `0x334`. Clone cards may permit other values.

The `buson` and `busoff` values refer to the number of microseconds that the card dominates the ISA bus. The defaults are 11us on and 4us off so that other cards (such as an ISA LANCE Ethernet card) have a chance to get access to the ISA bus.

The `dmaspeed` value refers to the rate (in MB/s) at which the DMA (Direct Memory Access) transfers proceed. The default is 5MB/s. Newer revision cards allow you to select this value as part of the soft-configuration; older cards use jumpers. You can use values up to 10MB/s, assuming that your motherboard is capable of handling it. Experiment with caution if using values over 5MB/s.

ADAPTEC AHA274X, AHA284X, AIC7XXX CONFIGURATION

These boards can accept an argument of the form:

```
aic7xxx=extended,no_reset
```

The `extended` value, if nonzero, indicates that extended translation for large disks is enabled. The `no_reset` value, if nonzero, tells the driver not to reset the SCSI bus when setting up the host adapter at boot.

BUSLOGIC SCSI HOSTS CONFIGURATION (buslogic=)

At present, the buslogic driver accepts only one parameter, the I/O base. It expects that to be one of the following valid values: `0x130`, `0x134`, `0x230`, `0x234`, `0x330`, or `0x334`.

FUTURE DOMAIN TMC-8XX, TMC-950 CONFIGURATION

If your card is not detected at boot time, you must use a boot arg of the form

```
tmc8xx=mem_base,irq
```

The `mem_base` value is the value of the memory-mapped I/O region that the card uses. This is usually one of the following values: `0xc8000`, `0xca000`, `0xcc000`, `0xce000`, `0xdc000`, or `0xde000`.

PRO AUDIO SPECTRUM CONFIGURATION

The PAS16 uses an NC5380 SCSI chip, and newer models support jumperless configuration. The boot arg is of the form

```
pas16=iobase,irq
```

The only difference is that you can specify an IRQ value of 255, which tells the driver to work without using interrupts, albeit at a performance loss. The `iobase` is usually `0x388`.

SEAGATE ST-0X CONFIGURATION

If your card is not detected at boot time, you must use a boot arg of the form

```
st0x=mem_base,irq
```

The `mem_base` value is the value of the memory-mapped I/O region that the card uses. This is usually one of the following values: `0xc8000`, `0xca000`, `0xcc000`, `0xce000`, `0xdc000`, or `0xde000`.

TRANTOR T128 CONFIGURATION

These cards are also based on the NCR5380 chip and accept the following options:

```
t128=mem_base,irq
```

The valid values for `mem_base` are as follows: `0xcc000`, `0xc8000`, `0xdc000`, and `0xd8000`.

CARDS THAT DON'T ACCEPT BOOT ARGS

At present, the following SCSI cards do not make use of any boot-time parameters. In some cases, you can hard-wire values by directly editing the driver itself, if required.

Always IN2000, Adaptec aha1740, EATA-DMA, EATA-PIO, Future Domain 16xx, NCR5380 (generic), NCR53c7xx to NCR53c8xx, Qlogic, Ultrastor (including u?4f), and Western Digital wd7000.

HARD DISKS

IDE DISK/CD-ROM DRIVER PARAMETERS

The IDE driver accepts a number of parameters, which range from disk geometry specifications to support for broken controller chips. Drive specific options are specified by using `hdX=` with `X` in `a-h`.

Non-drive-specific options are specified with the prefix `hd=`. Note that using a drive-specific prefix for a non-drive-specific option will still work, and the option will just be applied as expected.

Also note that `hd=` can be used to refer to the next unspecified drive in the (a, ..., h) sequence. For the following discussions, the `hd=` option will be cited for brevity. See the file `README.ide` in `linux/drivers/block` for more details.

THE `hd=cyls,heads,sects[,wpcom[,irq]]` OPTIONS

These options are used to specify the physical geometry of the disk. Only the first three values are required. The cylinder, head, and sectors values are those used by `fdisk`. The write precompensation value is ignored for IDE disks. The IRQ value specified is the IRQ used for the interface that the drive resides on and is not really a drive-specific parameter.

THE `hd=serialize` OPTION

The dual IDE interface CMD-640 chip is broken as designed such that when drives on the secondary interface are used at the same time as drives on the primary interface, it will corrupt your data. Using this option tells the driver to make sure that both interfaces are never used at the same time.

THE `hd=dtc2278` OPTION

This option tells the driver that you have a DTC-2278D IDE interface. The driver then tries to do DTC-specific operations to enable the second interface and to enable faster transfer modes.

THE `hd=noprobe` OPTION

Do not probe for this drive. The following line

```
hdb=noprobe hdb=1166,7,17
```

disables the probe but still specifies the drive geometry so that it is registered as a valid block device and hence usable.

THE `hd=nowerr` OPTION

Some drives apparently have the `WRERR` STAT bit stuck on permanently. This enables a work-around for these broken devices.

THE `hd=cdrom` OPTION

This tells the IDE driver that there is an ATAPI compatible CD-ROM attached in place of a normal IDE hard disk. In most cases, the CD-ROM is identified automatically, but if it isn't, then this might help.

STANDARD ST-506 DISK DRIVER OPTIONS (`hd=`)

The standard disk driver can accept geometry arguments for the disks similar to the IDE driver. Note however that it only expects three values (C/H/S); any more or any less and it will silently ignore you. Also, it only accepts `hd=` as an argument; `hda=` and so on are not valid here. The format is as follows:

```
hd=cyls,heads,sects
```

If there are two disks installed, the preceding line is repeated with the geometry parameters of the second disk.

XT DISK DRIVER OPTIONS (`xd=`)

If you are unfortunate enough to be using one of these old 8-bit cards that move data at a whopping 125KB/s, then here is the scoop. If the card is not recognized, you must use a boot arg of the form

```
xd=type,irq,iobase,dma_chan
```

The `type` value specifies the particular manufacturer of the card, and you use one of the following: 0=generic, 1=DTC, 2, 3, 4=Western Digital, 5, 6, 7=Seagate, or 8=OMTI. The only difference between multiple types from the same manufacturer is the BIOS string used for detection, which is not used if the type is specified.

The `xd_setup()` function does no checking on the values and assumes that you entered all four values. Don't disappoint it. Here is a sample usage for a WD1002 controller with the BIOS disabled or removed, using the default XT controller parameters:

```
xd=2,5,0x320,3
```

CD-ROMS (NON-SCSI/ATAPI/IDE)

THE AZTECH INTERFACE

The syntax for this type of card is

```
aztcd=iobase[,magic_number]
```

If you set the `magic_number` to `0x79`, the driver will run anyway in the event of an unknown firmware version. All other values are ignored.

THE CDU-31A AND CDU-33A SONY INTERFACE

This CD-ROM interface is found on some of the Pro Audio Spectrum sound cards and other Sony supplied interface cards.

The syntax is as follows:

```
cd31a=iobase,[irq[,is_pas_card]]
```

Specifying an IRQ value of `0` tells the driver that hardware interrupts aren't supported (as on some PAS cards). If your card supports interrupts, you should use them because they cut down on the CPU usage of the driver.

The `is_pas_card` should be entered as `PAS` if using a Pro Audio Spectrum card; otherwise, it should not be specified at all.

THE CDU-535 SONY INTERFACE

The syntax for this CD-ROM interface is

```
sonycd535=iobase[,irq]
```

A `0` can be used for the I/O base as a placeholder if you want to specify an IRQ value.

THE GOLDSTAR INTERFACE

The syntax for this CD-ROM interface is

```
gscd=iobase
```

THE MITSUMI STANDARD INTERFACE

The syntax for this CD-ROM interface is

```
mcd=iobase,[irq[,wait_value]]
```

The `wait_value` is used as an internal time-out value for people who are having problems with their drive and may or may not be implemented depending on a compile-time `#define`. The Mitsumi FX400 is an IDE/ATAPI CD-ROM player and does not use the `mcd` driver.

THE MITSUMI XA/MULTISESSION INTERFACE (mcdx=)

At present, this experimental driver has a setup function, but no parameters are implemented (as of 1.3.15). This is for the same hardware as previously described, but the driver has extended features.

THE OPTICS STORAGE INTERFACE

The syntax for this type of card is

```
optcd=iobase
```

THE PHILLIPS CM206 INTERFACE

The syntax for this type of card is

```
cm206=[iobase][,irq]
```

The driver assumes numbers between 3 and 11 are IRQ values and numbers between `0x300` and `0x370` are I/O ports, so you can specify one, or both numbers, in any order. It also accepts `cm206=auto` to enable autoprobing.

THE SANYO INTERFACE

The syntax for this type of card is

```
sjcd=iobase[,irq[,dma_channel]]
```

THE SOUNDBLASTER PRO INTERFACE

The syntax for this type of card is

```
sbpcd=iobase,type
```

type is one of the following (case-sensitive) strings: SoundBlaster, LaserMate, or SPEA. The I/O base is that of the CD-ROM interface and not that of the sound portion of the card.

ETHERNET DEVICES

Different drivers use different parameters, but they all at least share having an IRQ, an I/O port base value, and a name. In its most generic form, it looks something like this:

```
ether=irq,iobase[,param_1[,param_2,...param_8]],name
```

The first non-numeric argument is taken as the name. The param_n values (if applicable) usually have different meanings for each different card or driver. Typical param_n values are used to specify things such as shared memory address, interface selection, DMA channel, and the like.

The most common use of this parameter is to force probing for a second ethercard because the default is to only probe for one. This can be accomplished with a simple

```
ether=0,0,eth1
```

Note that the values of 0 for the IRQ and I/O base in the example tell the drivers to autoprobe.

The Ethernet How To has extensive documentation on using multiple cards and on the card-specific or driver-specific implementation of the param_n values where used. Interested readers should refer to the section in that document on their particular card.

THE FLOPPY DISK DRIVER

There are many floppy driver options, and they are all listed in README.fd in linux/drivers/block. This information is taken directly from that file.

floppy=mask,allowed_drive_mask

Sets the bitmask of allowed drives to mask. By default, only units 0 and 1 of each floppy controller are allowed. This is done because certain non-standard hardware (ASUS PCI motherboards) mess up the keyboard when accessing units 2 or 3. This option is somewhat obsolete because of the cmos option.

floppy=all drives

Sets the bitmask of allowed drives to all drives. Use this if you have more than two drives connected to a floppy controller.

floppy=asus_pci

Sets the bitmask to allow only units 0 and 1 (the default).

floppy=daring

Tells the floppy driver that you have a well-behaved floppy controller. This allows more efficient and smoother operation but may fail on certain controllers. This can speed up certain operations.

floppy=0,daring

Tells the floppy driver that your floppy controller should be used with caution.

floppy=one_fdc

Tells the floppy driver that you have only one floppy controller (default).

floppy=two_fdc OR floppy=address,two_fdc

Tells the floppy driver that you have two floppy controllers. The second floppy controller is assumed to be at address. If address is not given, 0x370 is assumed.

floppy=thinkpad

Tells the floppy driver that you have a Thinkpad. Thinkpads use an inverted convention for the disk change line.

floppy=0,thinkpad

Tells the floppy driver that you don't have a Thinkpad.

floppy=drive,type,cmos

Sets the cmos type of drive to type. Additionally, this drive is allowed in the bitmask. This is useful if you have more than two floppy drives (only two can be described in the physical cmos), or if your BIOS uses non-standard cmos types. Setting the cmos to 0 for the first two drives (default) makes the floppy driver read the physical cmos for those drives.

floppy=unexpected_interrupts

Print a warning message when an unexpected interrupt is received (default behavior)

floppy=no_unexpected_interrupts OR floppy=L40SX

Don't print a message when an unexpected interrupt is received. This is needed on IBM L40SX laptops in certain video modes. (There seems to be an interaction between video and floppy. The unexpected interrupts only affect performance and can safely be ignored.)

THE SOUND DRIVER

The sound driver can also accept boot args to override the compiled in values. This is not recommended because it is rather complex. It is described in the `Readme.Linux` file in `linux/drivers/sound`. It accepts a boot arg of the form

```
sound=device1[,device2[,device3...[,device11]]]
```

Each deviceN value is of the format 0xTaaaId and the bytes are used as follows:

T—device type: 1=FM, 2=SB, 3=PAS, 4=GUS, 5=MPU401, 6=SB16, and 7=SB16-MPU401

aaa—I/O address in hex

I—interrupt line in hex (10=a, 11=b, ...)

d—DMA channel

As you can see, it gets pretty messy, and you are better off to compile in your own personal values as recommended. Using a boot arg of `sound=0` disables the sound driver entirely.

THE BUS MOUSE DRIVER (bmouse=)

The busmouse driver only accepts one parameter, the hardware IRQ value to be used.

AUTHORS

Linus Torvalds (and many others)

SEE ALSO

`klogd(8)`, `lilo.conf(5)`, `lilo(8)`, `mount(8)`, `rdev(8)`

This man page was derived from the Boot Parameter HOWTO (version 1.0.1) written by Paul Gortmaker. More information can be found in this (or a more recent) HOWTO.

groff_me

groff_me—troff macros for formatting papers.

SYNOPSIS

```
groff_me [ options ] file ...
troff_me [ options ] file ...
```

DESCRIPTION

This manual page describes the GNU version of the _me macros, which is part of the groff document formatting system. This version can be used with both GNU troff and UNIX troff. This package of troff macro definitions provides a canned formatting facility for technical papers in various formats.

The macro requests are defined as follows. Many troff requests are unsafe in conjunction with this package; however, these requests can be used with impunity after the first .pp:

.bp	Begin new page
.br	Break output line here
.sp n	Insert n spacing lines
.ls n	Line spacing; n=1 single, n=2 double space
.na	No alignment of right margin
.ce n	Center next n lines
.ul n	Underline next n lines

Output of the pic, eqn, refer, and tb1 preprocessors is acceptable as input.

FILES

/usr/lib/groff/tmac/tmac.e

SEE ALSO

groff(1), gtroff(1), _me Reference Manual, Eric P. Allman, Writing Papers with Groff Using _me

REQUESTS

This list is incomplete; see the _me Reference Manual for interesting details.

<i>Request</i>	<i>Initial Value</i>	<i>Cause Break</i>	<i>Explanation</i>
.(c	-	Yes	Begin centered block.
.(d	-	No	Begin delayed text.
.(f	-	No	Begin footnote.
.(l	-	Yes	Begin list.
.(q	-	Yes	Begin major quote.
.(x x	-	No	Begin indexed item in index x.
.(z	-	No	Begin floating keep.
.)c	-	Yes	End centered block.
.)d	-	Yes	End delayed text.
.)f	-	Yes	End footnote.
.)l	-	Yes	End list.
.)q	-	Yes	End major quote.

continues

<i>Request</i>	<i>Initial Value</i>	<i>Cause Break</i>	<i>Explanation</i>
.)x	-	Yes	End index item.
.)z	-	Yes	End floating keep.
.++ m H	-	No	Define paper section. m defines the part of the paper and can be C (chapter), A (appendix), P (preliminary, such as abstract, table of contents, and so on), B (bibliography), RC (chapters renumbered from page one each chapter), or RA (appendix renumbered from page one).
.+c T	-	Yes	Begin chapter (or appendix and so on as set by .++). T is the chapter title.
.1c	1	Yes	One column format on a new page.
.2c	1	Yes	Two column format. Equation number is y.
.EN	-	Yes	Space after equation produced by eqn or neqn.
.EQ x y	-	Yes	Precede equation; break out and add space. The optional argument x may be I to indent equation (default), L to left-adjust the equation, or C to center the equation.
.GE	-	Yes	End gremlin picture.
.GS	-	Yes	Begin gremlin picture.
.PE	-	Yes	End pic picture.
.PS	-	Yes	Begin pic picture.
.TE	-	Yes	End table.
.TH	-	Yes	End heading section of table.
.TS x	-	Yes	Begin table; if x is H, table has repeated heading.
.b x	No	No	Print x in boldface; if no argument switch to boldface.
.ba +n	0	Yes	Augments the base indent by n. This indent is used to set the indent on regular text (like paragraphs).
.bc	No	Yes	Begin new column.
.bi x	No	No	Print x in bold italics (no fill only).
.bu	-	Yes	Begin bulleted paragraph.
.bx x	No	No	Print x in a box (no fill only).
.ef 'x'y'z'	""	No	Set even footer to x y z.
.eh 'x'y'z'	""	No	Set even header to x y z.
.fo 'x'y'z'	""	No	Set footer to x y z.
.hx	-	No	Suppress headers and footers on next page.
.he 'x'y'z'	""	No	Set header to x y z.
.hl	-	Yes	Draw a horizontal line.
.i x	No	No	Italicize x; if x is missing, italic text follows.
.ip x y	No	Yes	Start indented paragraph with hanging tag x. Indentation is y ens (default is 5).

<i>Request</i>	<i>Initial Value</i>	<i>Cause Break</i>	<i>Explanation</i>
.lp	Yes	Yes	Start left-blocked paragraph.
.np	1	Yes	Start numbered paragraph.
.of 'x'y'z'	""	No	Set odd footer to x y z.
.oh 'x'y'z'	""	No	Set odd header to x y z.
.pd	-	Yes	Print delayed text.
.pp	No	Yes	Begin paragraph. First line indented.
.r	Yes	No	Roman text follows.
.re	-	No	Reset tabs to default values.
.sh n x	-	Yes	Section head follows; font is automatically bold. n is level of section. x is title of section.
.sk	No	No	Leave the next page blank. Only one page is remembered ahead.
.sm x	-	No	Set x in a smaller point size.
.sz +n	10p	No	Augment the point size by n points.
.tp	No	Yes	Begin title page.
.u x	-	No	Underline argument (even in troff) (nofill only).
.uh	-	Yes	Like .sh but unnumbered.
.xp x	-	No	Print index x.

Groff Version 1.09, 6 August 1992

groff_mm

groff_mm—groff mm macros.

SYNOPSIS

groff_mgm [options...] [files...]

DESCRIPTION

- The groff mm macros are intended to be compatible with the DWB mm macros with the following limitations:
- No letter macros are implemented (yet).
- No Bell Labs localisms are implemented.
- The macros OK and PM are not implemented.
- groff mm does not support cut marks.
- mgm is intended to be international. Therefore, it is possible to write short national macro-files that change all English text to the preferred language. Use mgmse as an example.
- groff mm has several extensions:
- 1C [1]

APP name text

Begin one column processing. A 1 as argument disables the page break.

Begin an appendix with the name name. Automatic naming occurs if name is "". The appendixes starts with A if auto is used. A new page is ejected, and a header is also produced if the number variable Aph is non-zero. This is the default. The appendix always appear in the list of contents with the correct page number. The name APPENDIX can be changed by setting the string App to the desired text.

APPSK name pages text	Same as .APP, but the page number is incremented with pages. This is used when diagrams or other non-formatted documents are included as appendices.
B1	Begin box (as the ms macro) Draws a box around the text.
B2	End box. Finish the box.
BVL	Start of broken variable-item list. Like vl but text begins always at the next line.
COVER [arg]	COVER begins a coversheet definition. It is important that .COVER appears before any normal text. .COVER uses arg to build the filename /usr/lib/groff/tmac/mm/arg.cov. Therefore, it is possible to create unlimited types of coversheets. ms.cov is supposed to look like the ms coversheet. .COVER requires a .COVEND at the end of the cover definition. Always use this order of the cover macros: .COVER .TL .AF .AU .AT .AS .AE .COVEND However, only .TL and .AU are required.
COVEND	This finishes the cover description and prints the cover page. It is defined in the cover file.
GETHN refname [varname]	Includes the header number where the corresponding SETR refname was placed. Will be x.x.x. in pass 1. See INITR. If varname is used, GETHN sets the string variable varname to the header number.
GETPN refname [varname]	Includes the page number where the corresponding SETR refname was placed. Will be 9999 in pass 1. See INITR. If varname is used, GETPN sets the string variable varname to the page number.
GETR refname	Combines GETHN and GETPN with the text 'chapter' and ', page'. The string Qrf contains the text for reference: .ds Qrf See chapter \ [Qrfh], page \ [Qrfp]. Qrf may be changed to support other languages. Strings Qrfh and Qrfp are set by GETR and contain the page and header number.
GETST refname [varname]	Includes the string saved with the second argument to .SETR. Will be dummy string in pass 1. If varname is used, GETST sets the string variable varname to the saved string. See INITR.
INITR filename	Initialize the reference macros. References will be written to filename. tmp and filename.qrf. Requires two passes with groff. The first looks for references and the second includes them. INITR can be used several times, but it is only the first occurrence of INITR that is active. See also SETR, GETPN, and GETHN.
MC column-size [column-separation]	Begin multiple columns. Return to normal with 1c.
MT [arg [addressee]]	Memorandum type. The arg is part of a filename in /usr/lib/groff/tmac/mm/*.MT. Memorandum type 0 through 5 are supported, including string. addressee just sets a variable, used in the AT&T macros.
MOVE y-pos [x-pos[line-length]]	Move to a position, page offset set to x-pos. If line-length is not given, the difference between the current and new page offset is used. Use PGFORM without arguments to return to normal.

MULB cw1 space1[cw2 space2 [cw3 ...]]

MULN

MULE

PGFORM [linelength[pagelength[pageoffset [1]]]
linelength, pagelength and/or pageoffset.

PGNH

SETR refname [string]

TAB

VERBON [flag [pointsize[font]]]

VERBOFF

New variables in mgm:

App

Aph

Begin a special multi-column mode. Every column's width must be specified. Also, the space between the columns must be specified. The last column does not need any space definition. MULB starts a diversion and MULE ends the diversion and prints the columns. The unit for width and space is n, but MULB accepts all normal unit specifications such as c and i. MULB operates in a separate environment.

Begin the next column. This is the only way to switch columns. End the multi-column mode and print the columns.

This macro can be used for special formatting, such as PGFORM letterheads. Sets can be used without arguments to reset everything after a MOVE. A line break is done unless the fourth argument is given. This can be used to avoid the page number on the first page while setting new width and length.

No header is printed on the next page. Used to get rid of the header in letters or other special texts. This macro must be used before any text to inhibit the page header on the first page.

Remember the current header and page number as refname. Saves string if string is defined. string is retrieved with .GETST. See INITR.

Reset tabs to every 5n. Usually used to reset any previous tab positions.

Begin verbatim output using Courier font. Usually for printing programs. All characters have equal width. The point size can be changed with the second argument. By specifying the font argument, it is possible to use another font instead of Courier. flag controls several special features. It contains the sum of all wanted features:

Value	Description
1	Disable the escape-character (n). This is usually turned on during verbose output.
2	Add an empty line before the verbose text.
4	Add an empty line after the verbose text.
8	Print the verbose text with numbered lines. This adds four digit-sized spaces in the beginning of each line. Finer control is available with the string-variable verbnm. It contains all arguments to the troff-command .nm, usually 1.
16	Indent the verbose text with five ns. This is controlled by the number-variable verbin (in units).

End verbatim output.

A string containing the word APPENDIX.

Print an appendix page for every new appendix if this number variable is nonzero. No output will occur if Aph is zero, but there

Hps	Number variable with the heading pre-space level. If the heading level is less than or equal to Hps, then two lines precede the section heading instead of one. Default is first level only. The real amount of lines is controlled by the variables Hps1 and Hps2.
Hps1	This is the number of lines preceding .H when the heading level is greater than Hps. Value is in units, usually 0.5v.
Hps2	This is the number of lines preceding .H when the heading level is less than or equal to Hps. Value is in units, usually 1v.
Lifg	String containing figure.
Litb	String containing table.
Liex	String containing exhibit.
Liec	String containing equation.
Licon	String containing contents.
Lsp	The size of an empty line. Usually 0.5v, but it is 1v if n is set (.nroff).
MO1 - MO12	Strings containing January to December.
Qrf	String containing "See chapter \[*[Qrfh], page \[n[Qrfp]".
Pgps	Controls whether header and footer point size should follow the current setting or just change when the header and footer is defined.

Value	Description
0	Point size will only change to the current setting when .PH, .PF, .OH, .EH, .OF, or .OE is executed.
1	Point size will change after every .S. This is the default.

Sectf	Flag controlling section figures. A nonzero value enables this. See also register N.
Sectp	Flag controlling section page numbers. A nonzero value enables this. See also register N.
.mgm	Always 1.

A file called `locale` or `lang_locale` is read after the initiation of the global variables. It is therefore possible to localize the macros with a company name and so on.

The following standard macros are implemented:

2C	Begin two column processing.
AE	Abstract end.
AF [name of firm]	Author's firm.
AL [type[text-indent [1]]]	Start autoincrement list.
AS [arg [indent]]	Abstract start. Indent is specified in ens, but scaling is allowed.
AST [title]	Abstract title. Default is 'ABSTRACT'.
AT title1 [title2 ...]	Author's title.
AU name [initials [loc [dept	[ext [room [arg [arg [arg]]]]]]] Author information.
B [bold-text[prev-font-text [...]]]	Begin boldface. No limit on the number of arguments.

BE	End bottom block.
BI[bold-text [<i>italic-text</i> [bold-text [...]]]]	Bold italic. No limit on the number of arguments.
BL [<i>text-indent</i> [1]]	Start bullet list.
BR [bold-text [<i>roman-text</i> [bold-text [...]]]]	Bold roman. No limit on the number of arguments.
BS	Bottom block start.
DE	Display end.
DF[format [fill [rindent]]]	Begin floating display (no nesting allowed).
DL [<i>text-indent</i> [1]]	Dash list start.
DS [format[fill [rindent]]]	Static display start. Can now have unlimited nesting. Also, right-adjusted text and block may be used (R or RB as format).
EC [title [override[flag [refname]]]]	Equation title. If refname is used, then the equation number is saved with .SETR and can be retrieved with .GETST refname.
EF [arg]	Even page footer.
EH [arg]	Even page header.
EN	Equation end.
EQ [label]	Equation start.
EX [title [override[flag [refname]]]]	Exhibit title. If refname is used, then the exhibit number is saved with .SETR and can be retrieved with .GETST refname.
FD [arg [1]]	Footnote default format.
FE	Footnote end.
FG [title [override[flag [refname]]]]	Figure title. If refname is used, then the figure number is saved with .SETR and can be retrieved with .GETST refname.
FS	Footnote start. Footnotes in displays is now possible.
H level [heading-text[heading-suffix]]	Numbered heading.
HC [hyphenation-character]	Set hyphenation character.
HM [arg1 [arg2[... [arg7]]]]	Heading mark style.
HU heading-text	Unnumbered header.
HX dlevel rlevel heading-text	User-defined heading exit. Called just before printing the header.
HY dlevel rlevel heading-text	User-defined heading exit. Called just before printing the header.
HZ dlevel rlevel heading-text	User-defined heading exit. Called just after printing the header.
I [<i>italic-text</i> .	
	[prev-font-text [<i>italic-text</i> [...]]] Italic.
IB [<i>italic-text</i>	
	[bold-text [<i>italic-text</i> [...]]] Italic bold.
IR [<i>italic-text</i>	
	[<i>roman-text</i> [<i>italic-text</i> [...]]] Italic roman.
LB text-indentmark-indent	
	pad type[mark [LI-space [LB-space]]] List begin macro.
LC [list level]	List status clear.
LE	List end.
LI [mark [1]]	List item.
ML mark [text-indent]	Marked list start.
MT [arg [addressee]]	Memorandum type. See above note about MT.

ND new-date
 OF [arg]
 OH [arg]
 OP
 P [type]
 PE
 PF [arg]
 PH [arg]
 PS
 PX
 R
 RB [roman-text [bold-text

 RD [prompt[diversion [string]]]
 RF
 RI [roman-text

 RL [text-indent [1]]
 RP [arg [arg]]
 RS [string-name]
 S [size [spacing]]

 SA [arg]
 SK [pages]
 SM string1[string2 [string3]]
 SP [lines]
 TB [title [override[flag [refname]]]]

 TC [slevel [spacing

 TE
 TH [N]
 TL
 TM [num1 [num2 [...]]]

 TP
 TS [H]
 TX
 TY

New date.
 Odd page footer.
 Odd page header.
 Skip to odd page.
 Begin new paragraph.
 Picture end.
 Page footer.
 Page header.
 Picture start (from pic).
 Page header user-defined exit.
 Roman.

[roman-text [...]] Roman-bold.
 Read to diversion and/or string.
 Reference end.

[italic-text
 [roman-text [...]] Roman italic.
 Reference list start.
 Produce reference page.
 Reference start.

Set point size and vertical spacing. If any argument equals P, then the previous value is used. A C means current value, and D means default value. If + or - is used before the value, an increment or decrement of the current value is done.

Set adjustment.

Skip pages.

Make a string smaller.

Space vertically. lines can have any scaling factor, such as 3i or 8v.

Table title. If refname is used, then the table number is saved with .SETR and can be retrieved with .GETST refname.

[tlevel [tab [h1 [h2
 [h3 [h4 [h5]]]]]]]]]]

Table of contents. All texts can be redefined. new string variables Lifg, Litb, Liex, Liec, and Licon contain "Figure", "TABLE", "Exhibit", "Equation", and "CONTENTS". These can be redefined to other languages.

Table end.

Table header.

Begin title of memorandum.

Technical memorandum numbers used in .MT. Unlimited number of arguments may be given.

Top of page user-defined macro. Note that header and footer is printed in a separate environment. Line length is preserved.

Table start.

User-defined table of contents exit.

User-defined table of contents exit (no "CONTENTS").

VL [text-indent [mark-indent [1]]]

VM [top [bottom]]

WC [format]

Strings used in mgm:

EM

HF

HP

Lf

Lt

Lx

Le

Rp

Tm

Number variables used in mgm:

C1=2

Cp=0

D=0

De=0

Df=5

Ds=1

Ej=0

Eq=0

Fs=1

H1 - H7

Hb=2

Hc=0

Hi=1

Hs=2

Ht=0

Hu=2

Hy=1

Lf=1, Lt=1, Lx=1, Le=0

Li=6

Ls=99

N=0

Variable-item list start.

Vertical margin.

Footnote and display width control.

Em dash string.

Font list for headings, usually "2 2 2 2 2 2". Nonnumeric font names may also be used.

Point size list for headings. Usually "0 0 0 0 0 0", which is the same as "10 10 10 10 10 10".

Contains "LIST OF FIGURES".

Contains "LIST OF TABLES".

Contains "LIST OF EXHIBITS".

Contains "LIST OF EQUATIONS".

Contains "REFERENCES".

Contains \ (tm, trademark).

Contents level [0:7]; contents saved if heading level <=c1.

Eject page between LIST OF xxxx if Cp == 0.

Debug flag, values greater than 0 produce varying degree of debug. A value of 1 gives information about the progress of formatting.

Eject after floating display is output [0:1].

Floating keep output [0:5].

Space before and after display if == 1 [0:1].

Eject page.

Equation label adjust 0=left, 1=right.

Footnote spacing.

Heading counters.

Heading break level [0:7].

Heading centering level [0:7].

Heading temporary indent [0:2]. 0 is no indent, left margin. 1 is indent to right, like .P 1. 2 is indent to line up with text part of preceding heading.

Heading space level [0:7]

Heading numbering type 0 is multiple (1.1.1 ...). 1 is single.

Unnumbered heading level.

Hyphenation in body. 0 is no hyphenation. 1 is hyphenation 14 on.

Enables (1) or disables (0) the printing of a list of figures, list of tables, list of exhibits, and list of equations.

List indent, used by .AL.

List space, if current list level is greater than Ls, then no spacing occurs around lists.

Numbering style [0:5]:

0 == (Default) Normal header for all pages.

1 == Header replaces footer on first page; header is empty.

2 == Page header is removed on the first page.

<code>Np=0</code>	3 == Section page numbering enabled. 4 == Page header is removed on the first page. 5 == Section page and section figure numbering enabled. See also the number register <code>Sectf</code> and <code>Sectp</code> . Numbered paragraphs. 0 is not numbered. 1 is numbered in first-level headings.
<code>Of=0</code>	Format of figure, table, exhibit, and equation titles. 0 is ". ". 1 is "-".
<code>P</code>	Current page number, usually the same as % unless section-page numbering is enabled.
<code>Pi=5</code>	Paragraph indent.
<code>Ps=1</code>	Paragraph spacing.
<code>Pt=0</code>	Paragraph type. 0 is left-justified. 1 is indented .P. 2 is indented .P except after .H, .DE, or .LE.
<code>Si=5</code>	Display indent.

AUTHOR

Jorgen Hagg, Lund Institute of Technology, Sweden (jh@efd.lth.se).

FILES

```
/usr/lib/groff/tmac/tmac.gm
/usr/lib/groff/tmac/mm/*.cov
/usr/lib/groff/tmac/mm/*.MT
/usr/lib/groff/tmac/mm/locale
```

SEE ALSO

`groff(1)`, `gtroff(1)`, `gtbl(1)`, `gpics(1)`, `geqn(1)`, `mm(7)`, `mgmse(7)`

Groff Version 1.09, 14 February 1994

groff_ms

groff_ms—groff ms macros.

SYNOPSIS

```
groff_mgs [ options... ] [ files... ]
```

DESCRIPTION

This manual page describes the GNU version of the `ms` macros, which is part of the `groff` document formatting system. The `groff ms` macros are intended to be compatible with the documented behavior of the 4.3 BSD UNIX `ms` macros, subject to the following limitations:

The internals of `groff ms` are not similar to the internals of UNIX `ms`, so documents that depend upon implementation details of UNIX `ms` might not work with `groff ms`.

There is no support for typewriter-like devices.

Berkeley localisms, in particular the `TM` and `CT` macros, are not implemented.

`groff ms` does not provide cut marks.

Multiple line spacing is not allowed. (Use a larger vertical spacing instead.)

`groff ms` does not work in compatibility mode (such as with the `-c` option).

The error-handling policy of `groff ms` is to detect and report errors, rather than silently ignore them.

The `groff ms` macros use many features of GNU `troff` and therefore cannot be used with any other `troff`.

Bell Labs localisms are not implemented in either the `BSD ms` macros or in the `groff ms` macros.

Some UNIX `ms` documentation says that the `CW` and `GW` number registers can be used to control the column width and gutter width. This is not the case. These number registers are not used in `groff ms`.

Macros that cause a reset set the indent. Macros that change the indent do not increment or decrement the indent, but rather set it absolutely. This can cause problems for documents that define additional macros of their own. The solution is to not use the `in request` but instead to use the `RS` and `RE` macros.

The number register `GS` is set to 1 by the `groff ms` macros but is not used by the UNIX `ms` macros. It is intended that documents that need to determine whether they are being formatted with UNIX `ms` or `groff ms` use this number register.

Footnotes are implemented so that they can safely be used within `keeps` and `displays`. Automatically numbered footnotes within floating `keeps` are not recommended. It is safe to have another `\**` between a `\**` and the corresponding `.FS`; it is required only that each `.FS` occur after the corresponding `\**` and that the occurrences of `.FS` are in the same order as the corresponding occurrences of `\**`.

The strings `\*{` and `\*}` can be used to begin and end a superscript.

Some UNIX `V10 ms` features are implemented. The `B`, `I`, and `BI` macros can have an optional third argument that is printed in the current font before the first argument. There is a macro `CW` like `B` that changes to a constant-width font.

The following strings can be redefined to adapt the `groff ms` macros to languages other than English:

String	Default Value
REFERENCES	References
ABSTRACT	ABSTRACT
TOC	Table of Contents
MONTH1	January
MONTH2	February
MONTH3	March
MONTH4	April
MONTH5	May
MONTH6	June
MONTH7	July
MONTH8	August
MONTH9	September
MONTH10	October
MONTH11	November
MONTH12	December

The font family is reset from the string `FAM`; at initialization if this string is undefined, it is set to the current font family. The point size, vertical spacing, and inter-paragraph spacing for footnotes are taken from the number registers `FPS`, `FVS`, and `FPD`; at initialization, these are set to `\n(PS-2`, `\n[FPS]+2`, and `\n(PD/2`; however, if any of these registers was defined before initialization, it is not set. The hyphenation flags (as set by the `.hy request`) are set from the `HV` register; if this was not defined at initialization, it is set to 14.

Right-aligned displays are available with `.DS R` and `.RD`.

The following conventions are used for names of macros, strings, and number registers. External names available to documents that use the `groff ms` macros contain only uppercase letters and digits. Internally, the macros are divided into

modules. Names used only within one module are of the form `module*name`. Names used outside the module in which they are defined are of the form `module@name`. Names associated with a particular environment are of the form `environment:name`; these are used only within the `par` module, and `name` does not have a module prefix. Constructed names used to implement arrays are of the form `array!index`. Thus, the `groff ms` macros reserve the following names:

Names containing `*`

Names containing `@`

Names containing `:`

Names containing only uppercase letters and digits

FILES

`/usr/lib/groff/tmac/tmac.gs`

SEE ALSO

`groff(1)`, `gtroff(1)`, `gtbl(1)`, `gpics(1)`, `geqn(1)`, `ms(7)`

Groff Version 1.09, 9 January 1994

hier

`hier`—Description of the filesystem hierarchy.

DESCRIPTION

A typical Linux system has, among others, the following directories:

<code>/</code>	This is the root directory. This is where the whole tree starts.
<code>/bin</code>	This directory contains executable programs that are needed in single-user mode and to bring the system up or repair it.
<code>/boot</code>	Contains static files for the boot loader. This directory only holds the files that are needed during the boot process. The map installer and configuration files should go to <code>/sbin</code> and <code>/etc</code> .
<code>/dev</code>	Special or device files that refer to physical devices. See <code>mknod(1)</code> .
<code>/dos</code>	If both MS-DOS and Linux are run on one computer, this is a typical place to mount a DOS filesystem.
<code>/etc</code>	Contains configuration files that are local to the machine. Some larger software packages, such as X11, can have their own subdirectories below <code>/etc</code> . Site-wide configuration files may be placed here or in <code>/usr/etc</code> . Nevertheless, programs should always look for these files in <code>/etc</code> and you may have links for these files to <code>/usr/etc</code> .
<code>/etc/skel</code>	When a new user account is created, files from this directory are usually copied into the user's home directory.
<code>/etc/X11</code>	Configuration files for the X11 window system.
<code>/home</code>	On machines with home directories for users, these are usually beneath this directory, directly or not. The structure of this directory depends on local administration decisions.
<code>/lib</code>	This directory should hold those shared libraries that are necessary to boot the system and to run the commands in the root filesystem.
<code>/mnt</code>	This is a mount point for temporarily mounted filesystems.
<code>/proc</code>	This is a mount point for the <code>proc</code> filesystem, which provides information about running processes and the kernel. This pseudo-filesystem is described in more detail in <code>proc(5)</code> .

<code>/sbin</code>	Like <code>/bin</code> , this directory holds commands needed to boot the system but usually not executed by normal users.
<code>/tmp</code>	This directory contains temporary files that may be deleted with no notice, such as by a regular job or at system startup.
<code>/usr</code>	This directory is usually mounted from a separate partition. It should hold only sharable, read-only data so that it can be mounted by various machines running Linux.
<code>/usr/X11R6</code>	The X window system, version 11, release 6.
<code>/usr/X11R6/bin</code>	Binaries that belong to the X window system; often, there is a symbolic link from the more traditional <code>/usr/bin/X11</code> to here.
<code>/usr/X11R6/lib</code>	Data files associated with the X window system.
<code>/usr/X11R6/lib/X11</code>	These contain miscellaneous files needed to run X; Often, there is a symbolic link from <code>/usr/lib/X11</code> to this directory.
<code>/usr/X11R6/include/X11</code>	Contains include files needed for compiling programs using the X11 window system. Often, there is a symbolic link from <code>/usr/include/X11</code> to this directory.
<code>/usr/bin</code>	This is the primary directory for executable programs. Most programs executed by normal users that are not needed for booting or for repairing the system and that are not installed locally should be placed in this directory.
<code>/usr/bin/X11</code>	This is the traditional place to look for X11 executables; on Linux, it usually is a symbolic link to <code>/usr/X11R6/bin</code> .
<code>/usr/dict</code>	This directory holds files containing word lists for spell-checkers.
<code>/usr/etc</code>	Site-wide configuration files to be shared between several machines may be stored in this directory. However, commands should always reference those files using the <code>/etc</code> directory. Links from files in <code>/etc</code> should point to the appropriate files in <code>/usr/etc</code> .
<code>/usr/include</code>	Include files for the C compiler.
<code>/usr/include/X11</code>	Include files for the C compiler and the X window system. This is usually a symbolic link to <code>/usr/X11R6/include/X11</code> .
<code>/usr/include/asm</code>	Include files that declare some assembler functions. This should be a symbolic link to <code>/usr/src/linux/include/asm</code> .
<code>/usr/include/linux</code>	This contains information that may change from system release to system release and should be a symbolic link to <code>/usr/src/linux/include/linux</code> to get at operating-system-specific information.
<code>/usr/include/g++</code>	Include files to use with the GNU C++ compiler.
<code>/usr/lib</code>	Object libraries, including dynamic libraries, plus some executables that usually are not invoked directly. More complicated programs may have whole subdirectories there.
<code>/usr/lib/X11</code>	The usual place for data files associated with X programs and configuration files for the X system itself. On Linux, it usually is a symbolic link to <code>/usr/X11R6/lib/X11</code> .
<code>/usr/lib/gcc-lib</code>	Contains executables and include files for the GNU C compiler, <code>gcc(1)</code> .
<code>/usr/lib/groff</code>	Files for the GNU <code>groff</code> document formatting system.
<code>/usr/lib/uucp</code>	Files for <code>uucp(1)</code> .
<code>/usr/lib/zoneinfo</code>	Files for time zone information.
<code>/usr/local</code>	This is where programs that are local to the site typically go.
<code>/usr/local/bin</code>	Binaries for programs local to the site go there.
<code>/usr/local/doc</code>	Local documentation.
<code>/usr/local/etc</code>	Configuration files associated with locally installed programs go there.
<code>/usr/local/lib</code>	Files associated with locally installed programs go there.
<code>/usr/local/info</code>	Info pages associated with locally installed programs go there.
<code>/usr/local/man</code>	Man pages associated with locally installed programs go there.
<code>/usr/local/sbin</code>	Locally installed programs for system administration.

<code>/usr/local/src</code>	Source code for locally installed software.
<code>/usr/man</code>	Man pages go in there into their subdirectories.
<code>/usr/man/cat[1-9]</code>	These directories contain preformatted manual pages according to their man page section.
<code>/usr/man/locale/man[1-9]</code>	These directories contain manual pages that are in source code form. Systems that use a unique language and code set for all manual pages may omit the <code>locale</code> substring.
<code>/usr/sbin</code>	This directory contains program binaries for system administration that are not essential for the boot process, for mounting <code>/usr</code> , or for system repair.
<code>/usr/src</code>	Source files for different parts of the system.
<code>/usr/src/linux</code>	This contains the sources for the kernel of the operating system itself.
<code>/usr/tmp</code>	An alternative place to store temporary files; This should be a link to <code>/var/tmp</code> .
<code>/var</code>	This directory contains files that may change in size, such as spool and log files.
<code>/var/adm</code>	This directory is superseded by <code>/var/log</code> and should be a symbolic link to <code>/var/log</code> .
<code>/var/lock</code>	Lock files are placed in this directory. The naming convention for device lock files is <code>LCK..device</code> where <code>device</code> is the device's name in the filesystem. The format used is that of HDU UUCP lock files—that is, lock files contain a PID as a 10-byte ASCII decimal number, followed by a newline character.
<code>/var/log</code>	Miscellaneous log files.
<code>/var/preserve</code>	This is where <code>vi(1)</code> saves edit sessions so they can be restored later.
<code>/var/run</code>	Runtime variable files, such as files holding process identifiers (PIDs) and logged user information (<code>utmp</code>). Files in this directory are usually cleared when the system boots.
<code>/var/spool</code>	Spooled (or queued) files for various programs.
<code>/var/spool/at</code>	Spooled jobs for <code>at(1)</code> .
<code>/var/spool/cron</code>	Spooled jobs for <code>cron(1)</code> .
<code>/var/spool/lpd</code>	Spooled files for printing.
<code>/var/spool/mail</code>	Users' mailboxes.
<code>/var/spool/smail</code>	Spooled files for the <code>smail(1)</code> mail delivery program.
<code>/var/spool/news</code>	Spool directory for the news subsystem.
<code>/var/spool/uucp</code>	Spooled files for <code>uucp(1)</code> .
<code>/var/tmp</code>	Like <code>/tmp</code> , this directory holds temporary files stored for an unspecified duration.

CONFORMS TO

The Linux filesystem standard, release 1.2.

BUGS

This list is not exhaustive; different systems may be configured differently.

SEE ALSO

`find(1)`, `ln(1)`, `mount(1)`, `proc(5)`, The Linux Filesystem Standard

Linux, 10 February 1996

hostname

`hostname`—Hostname resolution description.

DESCRIPTION

Hostnames are domains. A domain is a hierarchical, dot-separated list of subdomains. For example, the machine `monet` in the `Berkeley` subdomain of the `EDU` subdomain of the Internet Domain Name System is represented as `monet.Berkeley.EDU` (with no trailing dot).

Hostnames are often used with network client and server programs, which must generally translate the name to an address for use. (This task is usually performed by the library routine `gethostbyname(3)`.) The default method for resolving hostnames by the Internet name resolver is to follow RFC 1535's security recommendations. Actions can be taken by the administrator to override these recommendations and to have the resolver behave the same as earlier, non-RFC 1535 resolvers.

The default method (using RFC 1535 guidelines) follows.

If the name consists of a single component (that is, contains no dot) and if the environment variable `HOSTALIASES` is set to the name of a file, that file is searched for a string matching the input hostname. The file should consist of lines made up of two strings separated by whitespace, the first of which is the hostname alias and the second of which is the complete hostname to be substituted for that alias. If a case-insensitive match is found between the hostname to be resolved and the first field of a line in the file, the substituted name is looked up with no further processing.

If there is at least one dot in the name, then the name is first tried as is. The number of dots to cause this action is configurable by setting the threshold using the `ndots` option in `/etc/resolv.conf` (default is 1). If the name ends with a dot, the trailing dot is removed, and the remaining name is looked up (regardless of the setting of the `ndots` option) and no further processing is done.

If the input name does not end with a trailing dot, it is looked up by searching through a list of domains until a match is found. If neither the search option in the `/etc/resolv.conf` file or the `LOCALDOMAIN` environment variable is used, then the search list of domains contains only the full domain specified by the domain option (in `/etc/resolv.conf`) or the domain used in the local hostname (see `hostname(1)` and `resolver(5)`). For example, if the domain option is set to `CS.Berkeley.EDU`, then only `CS.Berkeley.EDU` is in the search list and is the only domain appended to the partial hostname. For example, a setting of `lithium` makes `lithium.CS.Berkeley.EDU` the only name to be tried using the search list.

If the search option is used in `/etc/resolv.conf` or the environment variable, `LOCALDOMAIN` is set by the user, then the search list includes what is set by these methods. For example, if the search option contained `CS.Berkeley.EDU CChem.Berkeley.EDU Berkeley.EDU`, then the partial hostname (such as `lithium`) is tried with each domain name appended (in the same order specified). The resulting hostnames that are tried include

```
lithium.CS.Berkeley.EDU
lithium.CChem.Berkeley.EDU
lithium.Berkeley.EDU
```

The environment variable `LOCALDOMAIN` overrides the search and domain options, and if both search and domain options are present in the resolver configuration file, then only the last one listed is used (see `resolver(5)`).

If the name was not previously tried "as is" (that is, it fell below the `ndots` threshold or did not contain a dot), then the name as originally provided is attempted.

SEE ALSO

`gethostbyname(3)`, `resolver(5)`, `mailaddr(7)`, `named(8)`

16 February 1994

iso_8859_1

`iso_8859_1`—The ISO 8859-1 character set encoded in octal, decimal, and hexadecimal.

DESCRIPTION

The ISO 8859 standard includes several 8-bit extensions to the ASCII character set (also known as ISO 646-IRV). Especially important is ISO 8859-1, the Latin Alphabet No. 1, which has become widely implemented and may already be seen as the

de facto standard ASCII replacement. ISO 8859-1 supports the following languages: Afrikaans, Basque, Catalan, Danish, Dutch, English, Faeroes, Finnish, French, Galician, German, Icelandic, Irish, Italian, Norwegian, Portuguese, Scottish, Spanish, and Swedish. Note that the ISO 8859-1 characters are also the first 256 characters of ISO 10646 (Unicode).

ISO 8859 ALPHABETS

The full set of ISO 8859 alphabets includes

ISO 8859-1	West European languages (Latin-1)
ISO 8859-2	East European languages (Latin-2)
ISO 8859-3	Southeast European and miscellaneous languages (Latin-3)
ISO 8859-4	Scandinavian/Baltic languages (Latin-4)
ISO 8859-5	Latin/Cyrillic
ISO 8859-6	Latin/Arabic
ISO 8859-7	Latin/Greek
ISO 8859-8	Latin/Hebrew
ISO 8859-9	Latin-1 modification for Turkish (Latin-5)
ISO 8859-10	Lappish/Nordic/Eskimo languages (Latin-6)

ISO 8859-1 CHARACTERS

The following table displays the characters in ISO 8859 Latin-1, which are printable and unlisted in the `ascii(7)` manual page.

<i>Oct</i>	<i>Dec</i>	<i>Hex</i>	<i>Char</i>	<i>Description</i>
240	160	A0		No-break space
241	161	A1	¡	Inverted exclamation mark
242	162	A2	¢	Cent sign
243	163	A3	£	Pound sign
244	164	A4	\$	Currency sign
245	165	A5	¥	Yen sign
246	166	A6	¦	Broken bar
247	167	A7	§	Section sign
250	168	A8	¨	Diaeresis
251	169	A9	©	Copyright sign
252	170	AA	ª	Feminine ordinal indicator
253	171	AB	<<	Left-pointing double angle quotation mark
254	172	AC	¬	Not sign
255	173	AD	-	Soft hyphen
256	174	AE	â	Registered sign
257	175	AF	ˉ	Macron
260	176	B0	°	Degree sign
261	177	B1	±	Plus-minus sign
262	178	B2	²	Superscript two
263	179	B3	³	Superscript three

<i>Oct</i>	<i>Dec</i>	<i>Hex</i>	<i>Char</i>	<i>Description</i>
264	180	B4	´	Acute accent
265	181	B5		Micro sign
266	182	B6	¶	Pilcrow sign
267	183	B7	.	Middle dot
270	184	B8	ç	Cedilla
271	185	B9	¹	Superscript one
272	186	BA	º	Masculine ordinal indicator
273	187	BB	>>	Right-pointing double angle quotation mark
274	188	BC	1/4	Vulgar fraction one quarter
275	189	BD	1/2	Vulgar fraction one half
276	190	BE	3/4	Vulgar fraction three quarters
277	191	BF	¿	Inverted question mark
300	192	C0	À	Latin capital letter A with grave
301	193	C1	Á	Latin capital letter A with acute
302	194	C2	Â	Latin capital letter A with circumflex
303	195	C3	Ã	Latin capital letter A with tilde
304	196	C4	Ä	Latin capital letter A with diaeresis
305	197	C5	Å	Latin capital letter A with ring above
306	198	C6	Æ	Latin capital ligature AE
307	199	C7	Ç	Latin capital letter C with cedilla
310	200	C8	È	Latin capital letter E with grave
311	201	C9	É	Latin capital letter E with acute
312	202	CA	Ê	Latin capital letter E with circumflex
313	203	CB	Ë	Latin capital letter E with diaeresis
314	204	CC	Ì	Latin capital letter I with grave
315	205	CD	Í	Latin capital letter I with acute
316	206	CE	Î	Latin capital letter I with circumflex
317	207	CF	Ï	Latin capital letter I with diaeresis
320	208	D0	Ð	Latin capital letter eth
321	209	D1	Ñ	Latin capital letter N with tilde
322	210	D2	Ó	Latin capital letter O with grave
323	211	D3	Ô	Latin capital letter O with acute
324	212	D4	Õ	Latin capital letter O with circumflex
325	213	D5	Ö	Latin capital letter O with tilde
326	214	D6	Ö	Latin capital letter O with diaeresis
327	215	D7	×	Multiplication sign
330	216	D8	Ø	Latin capital letter O with stroke
331	217	D9	Ù	Latin capital letter U with grave
332	218	DA	Ú	Latin capital letter U with acute
333	219	DB	Û	Latin capital letter U with circumflex

continues

<i>Oct</i>	<i>Dec</i>	<i>Hex</i>	<i>Char</i>	<i>Description</i>
334	220	DC	Ü	Latin capital letter U with diaeresis
335	221	DD	Ý	Latin capital letter Y with acute
336	222	DE	þ	Latin capital letter thorn
337	223	DF	ß	Latin small letter sharp s
340	224	E0	à	Latin small letter a with grave
341	225	E1	á	Latin small letter a with acute
342	226	E2	â	Latin small letter a with circumflex
343	227	E3	ã	Latin small letter a with tilde
344	228	E4	ä	Latin small letter a with diaeresis
345	229	E5	å	Latin small letter a with ring above
346	230	E6	æ	Latin small ligature ae
347	231	E7	ç	Latin small letter c with cedilla
350	232	E8	è	Latin small letter e with grave
351	233	E9	é	Latin small letter e with acute
352	234	EA	ê	Latin small letter e with circumflex
353	235	EB	ë	Latin small letter e with diaeresis
354	236	EC	ì	Latin small letter i with grave
355	237	ED	í	Latin small letter i with acute
356	238	EE	î	Latin small letter i with circumflex
357	239	EF	ï	Latin small letter i with diaeresis
360	240	F0	ð	Latin small letter eth
361	241	F1	ñ	Latin small letter n with tilde
362	242	F2	ò	Latin small letter o with grave
363	243	F3	ó	Latin small letter o with acute
364	244	F4	ô	Latin small letter o with circumflex
365	245	F5	õ	Latin small letter o with tilde
366	246	F6	ö	Latin small letter o with diaeresis
367	247	F7	÷	Division sign
370	248	F8	ø	Latin small letter o with stroke
371	249	F9	ù	Latin small letter u with grave
372	250	FA	ú	Latin small letter u with acute
373	251	FB	û	Latin small letter u with circumflex
374	252	FC	ü	Latin small letter u with diaeresis
375	253	FD	ý	Latin small letter y with acute
376	254	FE	þ	Latin small letter thorn
377	255	FF	ÿ	Latin small letter y with diaeresis

SEE ALSO

ascii(7)

11 July 1995

locale

Locale—Description of multi-language support.

SYNOPSIS

```
#include <locale.h>
```

DESCRIPTION

A locale is a set of language and cultural rules. These cover aspects such as language for messages, different character sets, lexicographic conventions, and so on. A program needs to be able to determine its locale and act accordingly to be portable to different cultures.

The header `<locale.h>` declares data types, functions and macros that are useful in this task.

The functions it declares are `setlocale()` to set the current locale and `localeconv()` to get information about number formatting.

There are different categories for local information a program might need; they are declared as macros. Using them as the first argument to the `setlocale()` function, it is possible to set one of these to the desired locale:

<code>LC_COLLATE</code>	This is used to change the behavior of the functions <code>strcoll()</code> and <code>strxfrm()</code> , which are used to compare strings in the local alphabet. For example, the German sharp <code>s</code> is sorted as “ <code>ss</code> .”
<code>LC_TYPE</code>	This changes the behavior of the character handling and classification functions, such as <code>isupper()</code> and <code>toupper()</code> and the multi-byte character functions such as <code>mblen()</code> or <code>wctomb()</code> .
<code>LC_MONETARY</code>	Changes the behavior of the information returned by <code>localeconv()</code> , which describes the way numbers are usually printed, with details such as decimal point versus decimal comma.
<code>LC_MESSAGES</code>	Changes the language messages are displayed in.
<code>LC_TIME</code>	Changes the behavior of the <code>strftime()</code> function to display the current time in a locally acceptable form; for example, most of Europe uses a 24-hour clock versus the U.S. 12-hour clock.
<code>LC_ALL</code>	All of the above.

If the second argument to `setlocale()` is empty string for the default locale, it is determined using the following steps:

1. If there is a non-null environment variable `LC_ALL`, the value of `LC_ALL` is used.
2. If an environment variable with the same name as one of the preceding categories exists and is non-null, its value is used for that category.
3. If there is a non-null environment variable `LANG`, the value of `LANG` is used.

Values about local numeric formatting are made available in a `struct lconv` returned by the `localeconv()` function, which has the following declaration:

```
struct lconv
{
    /* Numeric (non-monetary) information. */
    char *decimal_point; /* Decimal point character. */
    char *thousands_sep; /* Thousands separator. */
    /* Each element is the number of digits in each group;
    elements with higher indices are farther left.
    An element with value CHAR_MAX means that no further grouping is done.
    An element with value 0 means that the previous element is used for all
    groups farther left. */
    char *grouping;
    /* Monetary information. */
```

```

/* First three chars are a currency symbol from ISO 4217.
Fourth char is the separator. Fifth char is ' '. */
char *int_curr_symbol;
char *currency_symbol; /* Local currency symbol. */
char *mon_decimal_point; /* Decimal point character. */
char *mon_thousands_sep; /* Thousands separator. */
char *mon_grouping; /* Like 'grouping' element (above). */
char *positive_sign; /* Sign for positive values. */
char *negative_sign; /* Sign for negative values. */
char int_frac_digits; /* Int'l fractional digits. */
char frac_digits; /* Local fractional digits. */
/* 1 if currency_symbol precedes a positive value, 0 if succeeds. */
char p_cs_precedes;
/* 1 if a space separates currency_symbol from a positive value. */
char p_sep_by_space;
/* 1 if currency_symbol precedes a negative value, 0 if succeeds. */
char n_cs_precedes;
/* 1 if a space separates currency_symbol from a negative value. */
char n_sep_by_space;
/* Positive and negative sign positions:
0 Parentheses surround the quantity and currency_symbol.
1 The sign string precedes the quantity and currency_symbol.
2 The sign string succeeds the quantity and currency_symbol.
3 The sign string immediately precedes the currency_symbol.
4 The sign string immediately succeeds the currency_symbol. */
char p_sign_posn;
char n_sign_posn;
};

```

CONFORMS TO

POSIX.1

At the moment, the only locales supported by Linux are the portable C, POSIX (identical to the C locale), ISO-8859-1 (European Latin-1), and KOI-8 (Russian) locales.

SEE ALSO

setlocale(3), localeconf(3), locale(1), localedef(1)

Linux, 24 April 1993

mailaddr

mailaddr—Mail addressing description.

DESCRIPTION

Mail addresses are based on the ARPANET protocol listed at the end of this manual page. These addresses are in the general format

user@domain

A domain is a hierarchical dot separated list of subdomains. For example, the address

eric@monet.berkeley.edu

is usually interpreted from right to left. The message should go to the ARPA name tables (which do not correspond exactly to the physical ARPANET) and then to the Berkeley gateway, after which it should go to the local host monet. When the message reaches monet, it is delivered to the user eric.

Unlike some other forms of addressing, this does not imply any routing. Thus, although this address is specified as an ARPA address, it might travel by an alternate route if that were more convenient or efficient. For example, at Berkeley, the associated message would probably go directly to monet over the Ethernet rather than go via the Berkeley ARPANET gateway.

ABBREVIATION

Under certain circumstances, it might not be necessary to type the entire domain name. In general, anything following the first dot may be omitted if it is the same as the domain from which you are sending the message. For example, a user on calder.berkeley.edu could send to eric@monet without adding the berkeley.edu because it is the same on both sending and receiving hosts.

Certain other abbreviations may be permitted as special cases. For example, at Berkeley, ARPANET hosts may be referenced without adding the berkeley.edu as long as their names do not conflict with a local host name.

COMPATIBILITY

Certain old address formats are converted to the new format to provide compatibility with the previous mail system. In particular,

`user@host.ARPA`

is allowed and

`host:user`

is converted to

`user@host`

to be consistent with the `rcp(1)` command.

Also, the syntax

`host!user`

is converted to

`user@host.UUCP`

This is usually converted back to the `host!user` form before being sent on for compatibility with older UUCP hosts.

The current implementation is not able to route messages automatically through the UUCP network. Until that time, you must explicitly tell the mail system which hosts to send your message through to get to your final destination.

CASE DISTINCTIONS

Domain names (anything after the @ sign) may be given in any mixture of uppercase and lowercase with the exception of UUCP hostnames. Most hosts accept any combination of case in usernames, with the notable exception of MULTICS sites.

ROUTE-ADDRS

Under some circumstances, it might be necessary to route a message through several hosts to get it to the final destination. Usually, this routing is done automatically, but sometimes it is desirable to route the message manually. Addresses that show these relays are termed "route-addr's." These use the syntax

`<@hosta,@hostb:user@hostc>`

This specifies that the message should be sent to `hosta`, from there to `hostb`, and finally to `hostc`. This path is forced even if there is a more efficient path to `hostc`.

Route-addr's occur frequently on return addresses because these are generally augmented by the software at each host. It is generally possible to ignore all but the `user@domain` part of the address to determine the actual sender.

POSTMASTER

Every site is required to have a user or user alias designated “postmaster” to which problems with the mail system may be addressed.

OTHER NETWORKS

Some other networks can be reached by giving the name of the network as the last component of the domain. This is not a standard feature and might not be supported at all sites. For example, messages to CSNET or BITNET sites can often be sent to `user@host.CSNET` or `user@host.BITNET`.

BUGS

The RFC 822 group syntax (`group:user1,user2,user3;`) is not supported except in the special case of `group:;` because of a conflict with old berknet-style addresses.

Route-Address syntax is grotty.

UUCP- and ARPANET-style addresses do not coexist politely.

SEE ALSO

`mail(1)`, `sendmail(8)`; Crocker, D. H., Standard for the Format of Arpa Internet Text Messages, RFC822.

14 February 1989

man

`man`—Macros to format man pages.

SYNOPSIS

```
groff -Tascii -man file ...
groff -Tps -man file ...
man [section] title
```

DESCRIPTION

This manual page explains the `groff tmac.an` macro package. This macro package should be used by developers when writing or porting man pages for Linux. It is fairly compatible with other versions of this macro package, so porting man pages should not be a major problem (exceptions include the NET-2 BSD release, which uses a totally different macro package).

Note that NET-2 BSD man pages can be used with `groff` simply by specifying the `-mdoc` option instead of the `-man` option. Using the `-mandoc` option is, however, recommended because this automatically detects which macro package is in use.

PREAMBLE

The first command in a man page should be

```
.TH title section date source manual,
```

<code>title</code>	The title of the man page (such as <code>MAN</code>).
<code>section</code>	The section number the man page should be placed in (such as 7).
<code>date</code>	The date of the last revision; remember to change this every time a change is made to the man page because this is the most general way of doing version control.
<code>source</code>	The source of the command.
	For binaries, use something such as GNU, NET-2, SLS Distribution, MCC Distribution.
	For system calls, use the version of the kernel that you are currently looking at:

Linux 0.99.11.

For library calls, use the source of the function: GNU, BSD 4.3, Linux DLL 4.4.1.

manual

The title of the manual (such as *Linux Programmer's Manual*).

The manual sections are traditionally defined as follows:

1 Commands	Those commands that can be executed by the user from within a shell.
2 System calls	Those functions that must be performed by the kernel.
3 Library calls	Most of the <code>libc</code> functions, such as <code>sort(3)</code> .
4 Special files	Files found in <code>/dev</code> .
5 File formats and conventions	The format for <code>/etc/passwd</code> and other human-readable files.
6 Games	
7 Macro packages and conventions	A description of the standard file system layout, this man page, and other things.
8 System management commands	Commands such as <code>mount(8)</code> , which only root can execute.
9 Kernel routines	This is a non-standard manual section and is included because the source code to the Linux kernel is freely available under the GNU Public License and many people are working on changes to the kernel.

FORMATS

Although there are many arbitrary conventions for man pages in the UNIX world, the existence of several hundred Linux-specific man pages defines the standards:

For functions, the arguments are always specified using italics, even in the SYNOPSIS section, where the rest of the function is specified in bold:

```
int myfunction(int argc, char **argv);
```

Filenames are always in italics (such as `/usr/include/stdio.h`), except in the SYNOPSIS section, where included files are in bold (such as `#include <stdio.h>`).

Special macros, which are usually in uppercase, are in bold (such as `MAXINT`).

When enumerating a list of error codes, the codes are in bold (this list usually uses the `.TP` macro).

Any reference to another man page (or to the subject of the current man page) is in bold. If the manual section number is given, it is given in roman, without any spaces (such as `man(7)`).

The commands to select the typeface are given below:

<code>.B</code>	Bold
<code>.BI</code>	Bold alternating with italics
<code>.BR</code>	Bold alternating with Roman
<code>.I</code>	Italics
<code>.IB</code>	Italics alternating with bold
<code>.IR</code>	Italics alternating with Roman
<code>.RB</code>	Roman alternating with bold
<code>.RI</code>	Roman alternating with italics
<code>.SB</code>	Small alternating with bold
<code>.SM</code>	Small

Traditionally, each command can have up to six arguments, but the GNU version seems to remove this limitation. Arguments are delimited by spaces. Double quotes can be used to specify an argument that contains spaces. All the arguments will be printed next to each other without intervening spaces, so that the `.BR` command can be used to specify a word in bold followed by a mark of punctuation in Roman.

SECTIONS

Sections are started with `.SH` followed by the heading name. If the name contains spaces and appears on the same line as `.SH`, then place the heading in double quotes. Traditional headings include NAME, SYNOPSIS, DESCRIPTION, OPTIONS, FILES, SEE ALSO, DIAGNOSTICS, BUGS, and AUTHOR. The only required heading is NAME, which should be followed on the next line by a one line description of the program:

```
.SH NAME
chess \- the game of chess
```

It is extremely important that this format is followed and that there is a backslash before the single dash that follows the command name. This syntax is used by the `makewhatis(8)` program to create a database of short command descriptions for the `whatis(1)` and `apropos(1)` commands.

OTHER MACROS

Other macros include the following:

<code>.DT</code>	Default tabs.
<code>.HP</code>	Begin hanging indent.
<code>.IP</code>	Begin paragraph with hanging tag. This is the same as <code>.TP</code> , except the tag is given on the same line, not on the following line.
<code>.LP</code>	Same as <code>.PP</code> .
<code>.PD</code>	Set interparagraph distance to argument.
<code>.PP</code>	Begin a new paragraph.
<code>.RE</code>	End relative indent (indented paragraph).
<code>.RS</code>	Start relative indent (indented paragraph).
<code>.SS</code>	Subheading (like <code>.SH</code> but used for a subsection).
<code>.TP</code>	Begin paragraph with hanging tag. The tag is given on the next line. This command is similar to <code>.IP</code> .

FILES

```
/usr/local/lib/groff/tmac/tmac.an
/usr/man/whatis
```

SEE ALSO

`groff(1)`, `man(1)`, `whatis(1)`, `apropos(1)`, `makewhatis(8)`

Linux, 25 July 1993

signal

signal—List of available signals.

DESCRIPTION

Linux supports the signals listed in this section. Several signal numbers are architecture dependent. First are the signals described in POSIX.1:

`abort(3)` `alarm(1)` Next various other signals.

(Here, `–` denotes that a signal is absent; there, where three values are given, the first one is usually valid for alpha and sparc, the middle one for i386 and ppc, the last one for mips. Signal 29 is `SIGINFO/SIGPWR` on an alpha but `SIGLOST` on a sparc.)

The letters in the Action column have the following meanings:

A	Default action is to terminate the process.
B	Default action is to ignore the signal.
C	Default action is to dump core.
D	Default action is to stop the process.
E	Signal cannot be caught.
F	Signal cannot be ignored.
G	Not a POSIX.1 conformant signal.

CONFORMING TO

POSIX.1

BUGS

SIGIO and SIGLOST have the same value. The latter is commented out in the kernel source, but the build process of some software still thinks that Signal 29 is SIGLOST.

SEE ALSO

kill(1), kill(2), setitimer(2)

Linux 1.3.88, 14 April 1996

suffixes

suffixes—List of file suffixes.

DESCRIPTION

It is customary to indicate the contents of a file with the file suffix, which consists of a period followed by one or more letters. Many standard utilities, such as compilers, use this to recognize the type of file they are dealing with. The make(1) utility is driven by rules based on file suffixes.

Following is a list of suffixes that are likely to be found on a Linux system:

<i>Suffix</i>	<i>File Type</i>
.v	Files for RCS (Revision Control System)
-	Backup file
.C	C++ source code
.F	FORTRAN source with cpp(1) directives
.S	Assembler source with cpp(1) directives
.Z	File compressed using compress(1)
.[0-9]+pk	TeX font files
.[1-9]	Manual page for the corresponding section
.[1-9][a-z]	Manual page for section plus subsection
.a	Static object code library
.afm	PostScript font metrics
.arc	ARC archive
.arj	ARJ archive
.asc	PGP ASCII-armored data

continues

<i>Suffix</i>	<i>File Type</i>
.awk	AWK language program
.bak	Backup file
.bm	Bitmap source
.c	C source
.cat	Message catalog files
.cc	C++ source
.cf	Configuration file
.conf	Configuration file
.config	Configuration file
.cweb	Donald Knuth's WEB for C
.dat	Data file
.def	Modula-2 source for definition modules
.def	Other definition files
.diff	ASCII File differences
.doc	Documentation file
.dvi	TeX device independent output
.el	EMACS lisp source
.elc	Compiled EMACS lisp
.eps	Encapsulated PostScript
.f	FORTRAN source
.fas	Precompiled common lisp
.fi	FORTRAN include files
.gif	Graphics Interchange Format
.gsf	Ghostscript fonts
.gz	File compressed using gzip(1)
.h	C or C++ header files
.hlp	Help file
.htm	HTML file imported without renaming from a brain-damaged OS
.html	HTML document used with the World Wide Web
.i	C source after preprocessing
.idx	Reference or datum-index file for hypertext or database system
.icon	Bitmap source
.image	Bitmap source
.in	Configuration template, especially for GNU autoconf
.info	Files for the EMACS info browser
.java	A Java source file
.jpg	JPEG compressed picture format
.l	lex(1) or fllex(1) files
.lib	Common lisp library
.ln	Files for use with lint(1)
.lsp	Common lisp source
.m4	M4(1) source
.mac	Macro files for various programs

<i>Suffix</i>	<i>File Type</i>
.man	Manual page (usually source rather than formatted)
.me	nroff source using the me macro package
.mf	Metafont (font generator for TeX) source
.mm	Sources for groff(1) in mm format
.mod	Modula-2 source for implementation modules
.o	Object file
.old	Old or backup file
.orig	Backup (original) version of a file from patch(1)
.out	Output file, often an executable program (a.out)
.p	Pascal source
.patch	File differences from patch(1)
.pcf	X11 font files
.pfa	PostScript font definition files, ASCII format
.pfb	PostScript font definition files, binary format
.pgp	PGP binary data
.pid	File to store daemon PID (such as crond.pid)
.png	Portable Network Graphics file
.pl	Perl script
.pr	Bitmap source
.ps	PostScript file
.r	RATFOR source (obsolete)
.rej	Patches that patch(1) couldn't apply
.rules	Rules for something
.s	Assembler source
.sa	Stub libraries for a.out shared libraries
.sc	sc(1) spreadsheet commands
.sh	sh(1) scripts
.shar	Archive created by the shar(1) utility
.so	DLL dynamic library
.sql	SQL schema or query program
.sty	LaTeX style files
.sym	Modula-2 compiled definition modules
.tar	Archive created by the tar(1) utility
.tar.Z	tar archive compressed with compress(1)
.tar.gz	tar archive compressed with gzip(1)
.taz	tar archive compressed with compress(1)
.tex	TeX or LaTeX source
.texi	Equivalent to .texinfo
.texinfo	TeXinfo documentation source
.tfm	TeX font metrics
.tgz	tar archive compressed with gzip(1)
.tmpl	Template files

continues

<i>Suffix</i>	<i>File Type</i>
.txt	Text file
.uue	Binary file encoded with uuencode(1)
.web	Donald Knuth's WEB
.y	yacc(1) or bison(1) (parser generator) files
.z	File compressed using pack(1) (or an old gzip(1))
.zoo	ZOO archive
~	EMACS or patch backup file
rc	Startup (run control) file, such as .newsrsc

CONFORMS TO

General UNIX conventions.

BUGS

This list is not exhaustive.

SEE ALSO

file(1), make(1)

Linux, 4 April 1996

tr2tex

tr2tex—Convert a document from troff to LaTeX

SYNOPSIS

```
tr2tex [ -m ] filename
```

DESCRIPTION

tr2tex converts a document typeset in troff to a LaTeX format. It is intended to do the first pass of the conversion. The user should then finish up the rest of the conversion and customize the converted manuscript to his or her liking. It can also serve as a tutor for those who want to convert from troff to LaTeX.

Most of the converted document will be in LaTeX, but some of it may be in plain TeX. It will also use some macros in troffms.sty or troffman.sty, which are included in the package and must be available to the document when processed with LaTeX.

If there is more than one input file, they will all be converted into one LaTeX document.

tr2tex understands most of the -ms and -man macros and eqn preprocessor symbols. It also understands several plain troff commands. Few tbl preprocessor commands are understood to help convert very simple tables.

When converting manuals, use the -m flag.

If a troff command cannot be converted, the line that contain that command will be commented out.

Note that if you have eqn symbols, you must have the inline mathematics delimiter defined by delim in the file you are converting. If it is defined in another setup file, that setup file must be concatenated with the file to be converted; otherwise, tr2tex regards the inline math as ordinary text.

BUGS

Many of these bugs are harmless. Most of them cause local errors that can be fixed in the converted manuscript.

- Some macros and macro arguments are not recognized.
- Commands that are not separated from their argument by a space are not properly parsed (such as `.sp3i`).
- When some operators (notably `over`, `sub`, and `sup`) are renamed (via `define`) and then they are encountered in the text, `tr2tex` treats them as ordinary macros and does not apply their rules.
- `rpile`, `lpile`, and `cpile` are treated the same as `cpile`.
- `rcol` and `lcol` are treated the same as `ccol`.
- Math-mode `size`, `gsize`, `fat`, and `gfont` are ignored.
- `lineup` and `mark` are ignored. The rules are so different.
- Some `troff` commands are translated to commands that require delimiters that have to be explicitly put. Because they are sometimes not put in `troff`, they can create problems. Example: `.nf` is not closed by `.fi`.
- When local motions are converted to `nraise` or `nlower`, an `nhbox` is needed, which must be put manually after the conversion.
- `a sub i sub j` is converted to `a_i_j`, which TeX parses as `a_{i_j}` with a complaint that it is vague. `a sub {i sub j}` is parsed correctly and converted to `a_{i_j}`.
- Line spacing is not changed within a paragraph in TeX (which is a bad practice anyway). TeX uses the last line spacing in effect in that paragraph.

TO DO

Access registers via the `.nr` command.

SEE ALSO

`texmatch(9)`, `trmatch(9)`

AUTHOR

Kamal Al-Yahya, Stanford University

1 January 1987

Unicode

Unicode—The unified 16-bit super character set.

DESCRIPTION

The international standard ISO 10646 defines the Universal Character Set (UCS). UCS contains all the characters of all other character-set standards. It also guarantees round-trip compatibility; conversion tables can be built such that no information is lost when a string is converted from any other encoding to UCS and back.

UCS contains the characters required to represent almost all known languages. This includes apart from the many languages that use extensions of the Latin script also the following scripts and languages: Greek, Cyrillic, Hebrew, Arabic, Armenian, Gregorian, Japanese, Chinese, Hiragana, Katakana, Korean, Hangul, Devangari, Bengali, Gurmukhi, Gujarati, Oriya, Tamil, Telugu, Kannada, Malayam, Thai, Lao, Bopomofo, and a number of others. Work is going on to include further scripts such as Tibetan, Khmer, Runic, Ethiopian, Hieroglyphics, various Indo-European languages, and many others. For most of these latter scripts, it was not yet clear how they can be encoded best when the standard was published in 1993. In addition to the characters required by these scripts, also a large number of graphical, typographical, mathematical, and scientific symbols such as those provided by TeX, PostScript, MS-DOS, Macintosh, Videotext, OCR, and many word processing systems have been included, as well as special codes that guarantee round-trip compatibility to all other existing character-set standards.

The UCS standard (ISO 10646) describes a 31-bit character-set architecture; however, today only the first 65534 code positions (0x0000 to 0xffff), which are called the Basic Multilingual Plane (BMP), have been assigned characters, and it is expected that only very exotic characters (such as Hieroglyphics) for special scientific purposes will ever get a place outside this 16-bit BMP.

The UCS characters 0x0000 to 0x007f are identical to those of the classic US-ASCII character set and the characters in the range 0x0000 to 0x00ff are identical to those in the ISO 8859-1 Latin-1 character set.

COMBINING CHARACTERS

Some code points in UCS have been assigned to combining characters. These are similar to the non-spacing accent keys on a typewriter. A combining character just adds an accent to the previous character. The most important accented characters have codes of their own in UCS; however, the combining character mechanism allows you to add accents and other diacritical marks to any character. The combining characters always follow the character that they modify. For example, the German character Umlaut-A (“Latin capital letter A with diaeresis”) can either be represented by the precomposed UCS code 0x00c4 or alternately as the combination of a normal “Latin capital letter A” followed by a “combining diaeresis”: 0x0041 0x0308.

IMPLEMENTATION LEVELS

As not all systems are expected to support advanced mechanisms such as combining characters, ISO 10646 specifies the following three implementation levels of UCS:

Level 1	Combining characters and Hangul Jamo characters (a special, more complicated encoding of the Korean script, where Hangul syllables are coded as two or three subcharacters) are not supported.
Level 2	Like level 1, except in some scripts, some combining characters are now allowed (such as Hebrew, Arabic, Devangari, Bengali, Gurmukhi, Gujarati, Oriya, Tamil, Telugo, Kannada, Malayalam, Thai, and Lao).
Level 3	All UCS characters are supported.

The Unicode 1.1 standard published by the Unicode Consortium contains exactly the UCS Basic Multilingual Plane at implementation Level 3, as described in ISO 10646. Unicode 1.1 also adds some semantical definitions for some characters to the definitions of ISO 10646.

UNICODE UNDER LINUX

Under Linux, only the BMP at implementation Level 1 should be used at the moment to keep the implementation complexity of combining characters low. The higher implementation levels are more suitable for special word processing formats but not as a generic system character set. The C type `wchar_t` is on Linux an unsigned 16-bit integer type and its values are interpreted as UCS Level 1 BMP codes.

The locale setting specifies whether the system character encoding is UTF-8 or ISO 8859-1, for example. Library functions such as `wcrtomb`, `mbtowc`, or `wprintf` can be used to transform the internal `wchar_t` characters and strings into the system character encoding and back.

PRIVATE AREA

In the BMP, the range 0xe000 to 0xf8ff will never be assigned any characters by the standard and is reserved for private usage. For the Linux community, this private area is subdivided further into the range 0xe000 to 0xefff, which can be used individually by any end user and the Linux zone in the range 0xf000 to 0xf8ff where extensions are coordinated among all Linux users. The registry of the characters assigned to the Linux zone is currently maintained by H. Peter Anvin (Peter.Anvin@linux.org), Yggdrasil Computing, Inc. It contains some DEC VT100 graphics characters missing in Unicode, gives direct access to the characters in the console font buffer, and contains the characters used by a few advanced scripts such as Klingon.

LITERATURE

Information technology—Universal Multiple-Octet Coded Character Set (UCS). Part 1: Architecture and Basic Multilingual Plane. International Standard ISO 10646-1, International Organization for Standardization, Geneva, 1993.

This is the official specification of UCS. Pretty official, pretty thick, and pretty expensive. For ordering information, check www.iso.ch.

The Unicode Standard—Worldwide Character Encoding Version 1.0. The Unicode Consortium, Addison-Wesley, Reading, MA, 1991.

There is already Unicode 1.1.4 available. The changes to the 1.0 book are available from [ftp.unicode.org](ftp://ftp.unicode.org). Unicode 2.0 will be published again as a book in 1996.

S. Harbison, G. Steele. C, *A Reference Manual*. Fourth edition, Prentice Hall, Englewood Cliffs, 1995, ISBN 0-13-326224-3.

A good reference book about the C programming language. The fourth edition now covers also the 1994 Amendment 1 to the ISO C standard (ISO/IEC 9899:1990), which adds a large number of new C library functions for handling wide character sets.

BUGS

At the time when this man page was written, the Linux libc support for UCS was far from complete.

AUTHOR

Markus Kuhn (mskuhn@cip.informatik.uni-erlangen.de)

SEE ALSO

[utf-8\(7\)](#)

Linux, 27 December 1995

UTF - 8

UTF - 8—An ASCII-compatible multibyte Unicode encoding.

DESCRIPTION

The Unicode character set occupies a 16-bit code space. The most obvious Unicode encoding (known as UCS-2) consists of a sequence of 16-bit words. Such strings can contain as parts of many 16-bit characters bytes such as `\0` or `/`, which have a special meaning in filenames and other C library function parameters. In addition, the majority of UNIX tools expects ASCII files and can't read 16-bit words as characters without major modifications. For these reasons, UCS-2 is not a suitable external encoding of Unicode in filenames, text files, environment variables, and so on. The ISO 10646 Universal Character Set (UCS), a superset of Unicode, occupies even a 31-bit code space, and the obvious UCS-4 encoding for it (a sequence of 32-bit words) has the same problems.

The UTF-8 encoding of Unicode and UCS does not have these problems and is the way to go for using the Unicode character set under UNIX-style operating systems.

PROPERTIES

The UTF-8 encoding has the following nice properties:

UCS characters 0x00000000 to 0x0000007f (the classical U.S. ASCII characters) are encoded simply as bytes 0x00 to 0x7f (ASCII compatibility). This means that files and strings that contain only 7-bit ASCII characters have the same encoding under both ASCII and UTF-8.

All UCS characters greater than 0x7f are encoded as a multibyte sequence consisting only of bytes in the range 0x80 to 0xfd, so no ASCII byte can appear as part of another character and there are no problems with `\0` or `/`.

The lexicographic sorting order of UCS-4 strings is preserved.

All possible 2^{31} UCS codes can be encoded using UTF-8.

The bytes 0xfe and 0xff are never used in the UTF-8 encoding.

The first byte of a multibyte sequence that represents a single non-ASCII UCS character is always in the range 0xc0 to 0xfd and indicates how long this multibyte sequence is. All further bytes in a multibyte sequence are in the range 0x80 to 0xbf. This allows easy resynchronization and makes the encoding stateless and robust against missing bytes.

UTF-8-encoded UCS characters may be up to six bytes long; however, Unicode characters can only be up to three bytes long. Because Linux uses only the 16-bit Unicode subset of UCS, under Linux, UTF-8 multibyte sequences can only be one, two, or three bytes long.

ENCODING

The following byte sequences are used to represent a character. The sequence to be used depends on the UCS code number of the character:

```
0x00000000 - 0x0000007F: 0xxxxxxx
0x00000080 - 0x000007FF: 110xxxxx 10xxxxxx
0x00000800 - 0x0000FFFF: 1110xxxx 10xxxxxx 10xxxxxx
0x00010000 - 0x001FFFFF: 11110xxx 10xxxxxx 10xxxxxx 10xxxxxx
0x00200000 - 0x03FFFFFF: 111110xx 10xxxxxx 10xxxxxx 10xxxxxx 10xxxxxx
0x04000000 - 0x7FFFFFFF: 1111110x 10xxxxxx 10xxxxxx 10xxxxxx 10xxxxxx
10xxxxxx
```

The xxx-bit positions are filled with the bits of the character code number in binary representation. Only the shortest possible multibyte sequence that can represent the code number of the character can be used.

EXAMPLES

The Unicode character 0xa9 = 1010 1001 (the copyright sign) is encoded in UTF-8 as

```
11000010 10101001 = 0xc2 0xa9
```

and character 0x2260 = 0010 0010 0110 0000 (the “not equal” symbol) is encoded as

```
11100010 10001001 10100000 = 0xe2 0x89 0xa0
```

STANDARDS

ISO 10646, Unicode 1.1, XPG4, Plan 9.

AUTHOR

Markus Kuhn (mskuhn@cip.informatik.uni-erlangen.de)

SEE ALSO

unicode(7)

Part VIII:

Administration
and Privileged
Commands

intro

intro—Introduction to administration and privileged commands.

DESCRIPTION

This chapter describes commands that either can be or are only used by the superuser, such as daemons and machine or hardware-related commands.

AUTHORS

Look at the header of the manual page for the authors and copyright conditions. Note that these can be different from page to page.

Linux, 24 July 1993

adduser, addgroup

adduser, addgroup—Add a user or group to the system.

SYNOPSIS

```
adduser [--system [--home directory] [--group]] [--quiet]
  [--force-badname] [--help] [--version] [--debug] username
adduser [--quiet] [--force-badname] [--help] [--version]
  [--debug] username group
adduser [--group] [--quiet] [--force-badname] [--help]
  [--version] [--debug] group
```

DESCRIPTION

adduser and addgroup add users and groups to the system according to information provided in the configuration file `/etc/adduser.conf`. adduser and addgroup automatically determine the UID or GID and place the entity in the password or group file as appropriate.

If necessary, adduser creates a home directory for the new user, copies “skeletal” user files to it from `/etc/skel`, and allows the system administrator to set an initial password and finger information for the user.

Because it needs to be able to write to such files as `/etc/passwd`, adduser can only be run as root.

Generally, there are two types of users and groups on a system: those users that log into the system and those “non-user” accounts and groups that exist for various system tasks and projects. Henceforth, user will refer to the login type and system user or group will refer to the type used for system maintenance and projects.

By default, each user in Debian GNU/Linux is given a corresponding group with the same name and ID, allowing people easily to give access to their home directories to others. This option can be turned off in the configuration file, in which case each user is, by default, added to a group called users.

Under Debian GNU/Linux, IDs less than or equal to 100 are allocated by the base system maintainer for various purposes. IDs from 101 to the value specified in the configuration file (1000, by default) are used for system users and groups. IDs greater than 1000 are reserved for users and their corresponding groups.

When invoked with a single name, adduser creates a user with that name. When given two names, adduser assumes that the first name represents an existing user and that the second name represents an existing group. In this case, the user is added to the group.

OPTIONS

<code>--system</code>	Create a system user. This user will be assigned the shell <code>/bin/false</code> and have an asterisk in the password field. Unless otherwise specified, the user will be placed in the group <code>nogroup</code> . Skeletal configuration files will not be copied into the user's home directory.
<code>--home directory</code>	When used with <code>--system</code> , this uses <code>directory</code> as the user's home directory, rather than the default specified in the configuration file. If the directory does not exist, it is created.
<code>--group</code>	When combined with <code>--system</code> , a group with the same name and ID as the system user is created. If not combined with <code>--system</code> , a group with the given name is created. This is the default action if the program is invoked as <code>addgroup</code> .
<code>--quiet</code>	Suppress progress messages.
<code>--force-badname</code>	By default, user and group names are required to consist of a lowercase letter followed by one or more lowercase letters or numbers. This option forces <code>adduser</code> or <code>addgroup</code> to be more lenient.
<code>--help</code>	Display brief instructions.
<code>--version</code>	Display version and copyright information.
<code>--debug</code>	Display a large quantity of debugging information.

SEE ALSO

`adduser.conf(5)`

COPYRIGHT

Copyright(c) 1995, Ted Hajek, with a great deal borrowed from the original Debian `adduser`, copyright(c) 1994, Ian Murdock. `adduser` is free software; see the GNU General Public License version two or later for copying conditions. There is no warranty.

Debian GNU/Linux version 1.94

agetty

agetty—Alternative Linux getty.

SYNOPSIS

```
agetty [-i hL] [-l login_program] [-m] [-t timeout] port baud_rate,... [term]
agetty [-i hL] [-l login_program] [-m] [-t timeout] baud_rate,... port [term]
```

DESCRIPTION

agetty opens a tty port, prompts for a login name, and invokes the `/bin/login` command. It is usually invoked by `init(8)`.

agetty has several non-standard features that are useful for hard-wired and for dial-in lines:

- Adapts the tty settings to parity bits and to erase, kill, end-of-line, and uppercase characters when it reads a login name. The program can handle 7-bit characters with even, odd, none, or space parity and 8-bit characters with no parity. The following special characters are recognized: `@` and `Control+U` (kill); `#`, `Del` and `Backspace` (erase); carriage return and line feed (end of line).

- Optionally deduces the baud rate from the `CONNECT` messages produced by Hayes-compatible modems.

- Optionally does not hang up when it is given an already opened line (useful for call-back applications).

- Optionally does not display the contents of the `/etc/issue` file (System V only).

Optionally invokes a non-standard login program instead of `/bin/login`.

Optionally turns on hardware flow control.

Optionally forces the line to be local with no need for carrier detect.

This program does not use the `/etc/gettydefs` (System V) or `/etc/gettytab` (SunOS 4) files.

ARGUMENTS

<code>port</code>	A path name relative to the <code>/dev</code> directory. If <code>a -</code> is specified, <code>agetty</code> assumes that its standard input is already connected to a <code>tty</code> port and that a connection to a remote user has already been established. Under System V, a <code>- port</code> argument should be preceded by a <code>-</code> .
<code>baud rate,...</code>	A comma-separated list of one or more baud rates. Each time <code>agetty</code> receives a break character, it advances through the list, which is treated as if it were circular. Baud rates should be specified in descending order, so that the null character (<code>Ctrl+@</code>) can also be used for baud rate switching.
<code>term</code>	The value to be used for the <code>TERM</code> environment variable. This overrides whatever <code>init(8)</code> may have set and is inherited by <code>login</code> and the shell.

OPTIONS

<code>-h</code>	Enable hardware (RTS/CTS) flow control. It is left up to the application to disable software (XON/XOFF) flow protocol where appropriate.
<code>-i</code>	Do not display the contents of <code>/etc/issue</code> before writing the login prompt. Terminals or communications hardware might become confused when receiving lots of text at the wrong baud rate; dial-up scripts might fail if the login prompt is preceded by too much text.
<code>-l login_program</code>	Invoke the specified login program instead of <code>/bin/login</code> . This allows the use of a non-standard login program (for example, one that asks for a dial-up password or that uses a different password file).
<code>-m</code>	Try to extract the baud rate the connect status message produced by some Hayes-compatible modems. These status messages are of the form: " <code><junk><speed><junk></code> ". <code>agetty</code> assumes that the modem emits its status message at the same speed as specified with (the first) baud rate value on the command line. Because the <code>-m</code> feature might fail on heavily loaded systems, you still should enable break processing by enumerating all expected baud rates on the command line.
<code>-t timeout</code>	Terminate if no username could be read within <code>timeout</code> seconds. This option should probably not be used with hard-wired lines.
<code>-L</code>	Force the line to be a local line with no need for carrier detect. This can be useful when you have a locally attached terminal where the serial line does not set the carrier detect signal.

EXAMPLES

This section shows sample entries for the `/etc/inittab` file.

For a hard-wired line:

```
tty1:con80x60:/sbin/agetty 9600 tty1
```

For a dial-in line with a 9600/2400/1200 baud modem:

```
ttyS1:dumb:/sbin/agetty -mt60 ttyS1 9600,2400,1200
```


These examples assume you use the `simpleinit(8)` init program for Linux. If you use a SysV-like init (does `/etc/inittab` mention “respawn?”), refer to the appropriate manual page.

ISSUE ESCAPES

The `/etc/issue` file might contain certain escape codes to display the system name, date and time, and so on. All escape codes consist of a backslash (`\`) immediately followed by one of the following letters:

<code>b</code>	Insert the baudrate of the current line.
<code>d</code>	Insert the current date.
<code>s</code>	Insert the system name, the name of the operating system.
<code>l</code>	Insert the name of the current <code>tty</code> line.
<code>m</code>	Insert the architecture identifier of the machine, such as <code>i486</code> .
<code>n</code>	Insert the nodename of the machine, also known as the hostname.
<code>o</code>	Insert the domain name of the machine.
<code>r</code>	Insert the release number of the OS, such as <code>1.1.9</code> .
<code>t</code>	Insert the current time.
<code>u</code>	Insert the number of current users logged in.
<code>U</code>	Insert the string <code>1 user</code> or <code>n users</code> where <code>n</code> is the number of current users logged in.
<code>v</code>	Insert the version of the OS, such as the build date and so on.

For example, on my system, the following `/etc/issue` file

```
This is \n.\o (\s\m\r) \t
```

displays as

```
This is thingol.orcan.dk (Linux i386 1.1.9) 18:29:30
```

FILES

`/var/run/utmp`, the system status file
`/etc/issue`, printed before the login prompt (System V only)
`/dev/console`, problem reports (if `syslog(3)` is not used)
`/etc/inittab` (Linux `simpleinit(8)` configuration file)

BUGS

The baud-rate detection feature (the `-m` option) requires that `agetty` be scheduled soon enough after completion of a dial-in call (within 30ms with modems that talk at 2400 baud). For robustness, always use the `-m` option in combination with a multiple baud rate command-line argument so that break processing is enabled.

The text in the `/etc/issue` file and the login prompt are always output with 7-bit characters and space parity.

The baud-rate detection feature (the `-m` option) requires that the modem emits its status message after raising the DCD line.

DIAGNOSTICS

Depending on how the program was configured, all diagnostics are written to the console device or reported via the `syslog(3)` facility. Error messages are produced if the port argument does not specify a terminal device, if there is no `utmp` entry for the current process (System V only), and so on.

AUTHORS

W.Z. Venema (wietse@wzv.win.tue.nl) Eindhoven University of Technology, Department of Mathematics and Computer Science, Den Dolech 2, P.O. Box 513, 5600 MB Eindhoven, The Netherlands.

Peter Orbaek (poe@daimi.aau.dk), Linux port.

CREATION DATE

Sat Nov 25 22:51:05 MET 1989

LAST MODIFICATION

91/09/01 23:22:00

VERSION/RELEASE

1.29

archive

archive—Usenet article archiver.

SYNOPSIS

```
archive [ -a archive ][ -f ][ -i index ][ -m ][ -r ][ input ]
```

DESCRIPTION

archive makes copies of files specified on its standard input. It is usually run either as a channel feed under `innd(8)` or by a script before `expire(8)` is run.

archive reads the named input file or standard input if no file is given. The input is taken as a set of lines. Blank lines and lines starting with a number sign (#) are ignored. All other lines should specify the name of a file to archive. If a filename is not an absolute pathname, it is taken to be relative to `/news/spool`.

Files are copied to a directory within the archive directory, `/news/spool/news.archive`. The default is to create a hierarchy that mimics the input files; intermediate directories are created as needed. For example, the input file `comp/sources/unix/2211` (article 2211 in the newsgroup `comp.sources.unix`) is copied to `/news/spool/news.archive/comp/sources/unix/2211`. If the `-f` flag is used, then all directory names are flattened out, replacing the slashes with periods. In this case, the file is copied to `/news/spool/news.archive/comp.sources.unix/2211`.

If the `-i` flag is used, then archive appends one line to the specified index file for each article that it copies. This line contains the destination name and the Message-ID and Subject headers.

For example, a typical `newsfeeds(5)` entry to archive most source newsgroups is as follows:

```
source-archive\
:!*,*sources*,!*wanted*,!*.*d\
:Tc,Wn\
:/archive -f -i \
/usr/spool/news/news.archive/INDEX
```

Files are copied by making a link. If that fails, a new file is created. If the `-m` flag is used, then the file is copied to the destination, and the input file is replaced with a symbolic link pointing to the new file. The `-m` flag is ignored.

By default, archive sets its standard error to `/var/log/news/errlog`. To suppress this redirection, use the `-r` flag.

If the input is exhausted, archive exits with a zero status. If an I/O error occurs, it tries to spool its input, copying it to a file. If there was no input filename, the standard input is copied to `/news/spool/out.going/archive` and the program exits. If an input filename was given, a temporary file named `input.bch` (if input is an absolute pathname) or `/news/spool/out.going/input.bch` (if the filename does not begin with a slash) is created. Once the input is copied, archive tries to rename this temporary file to be the name of the input file and then exits.

HISTORY

Written by Rich Salz (`rsalz@uunet.uu.net`) for InterNetNews.

SEE ALSO

newsfeeds(5)

arp

arp—Manipulate the system ARP cache.

SYNOPSIS

```
arp [-v] [-t type] -a [hostname]
arp [-v] -d hostname ...
arp [-v] [-t type] -s hostname hw_addr
arp [-v] -f filename
```

DESCRIPTION

arp manipulates the kernel's ARP cache in various ways. The primary options are clearing an address mapping entry and manually setting up one. For debugging purposes, the arp program also allows a complete dump of the ARP cache.

OPTIONS

-v	Tell the user what is going on by being verbose.
-t type	When setting or reading the ARP cache, this optional parameter tells arp which class of entries it should check for. The default value of this parameter is ether (hardware code 0x01 for IEEE 802.3 10Mbps Ethernet). Other values might include network technologies such as ARCnet (arcnet), PRONet (pronet), and AX.25 (ax25).
-a [hostname]	Shows the entries of the specified hosts. If the hostname parameter is not used, all entries are displayed.
-d hostname	Remove the entries of the specified host. This can be used if the indicated host is brought down, for example.
-s hostname hw_addr	Manually create an ARP address mapping entry for host hostname with hardware address set to hw_addr. The format of the hardware address is dependent on the hardware class, but for most classes, you can assume that the usual presentation can be used. For the Ethernet class, this is six bytes in hexadecimal, separated by colons.
-f filename	Similar to the -s option, only this time the address info is taken from file filename. This can be used if ARP entries for a lot of hosts have to be set up. The name of the data file is often /etc/ethers, but this is not official. The format of the file is simple; it only contains ASCII text lines with a hostname and a hardware address separated by whitespace.

In all places where a hostname is expected, you can also enter an IP address in dotted-decimal notation.

FILES

```
/proc/net/arp
/etc/ethers
```

AUTHOR

Fred N. van Kempen (waltje@uwalnt.nl.mugnet.org)

09 June 1994

badblocks

badblocks—Search a device for bad blocks.

SYNOPSIS

```
badblocks [ -b block-size ] [ -o output_file ] [ -v ][-w ] device blocks-count
```

DESCRIPTION

badblocks is used to search for bad blocks on a device (usually a disk partition). *device* is the special file corresponding to the device (such as */dev/hdXX*). *blocks-count* is the number of blocks on the device.

OPTIONS

<code>-b block-size</code>	Specify the size of blocks in bytes.
<code>-o output_file</code>	Write the list of bad blocks to the specified file. Without this option, badblocks displays the list on its standard output.
<code>-v</code>	Verbose mode.
<code>-w</code>	Use write-mode test. With this option, badblocks scans for bad blocks by writing some patterns (0xaa, 0x55, 0xff, and 0x00) on every block of the device, reading every block and comparing the contents.

WARNING

Never use the `-w` option on a device containing an existing filesystem. This option erases data!

AUTHOR

badblocks was written by Remy Card (card@masi.ibp.fr), the developer and maintainer of the ext2 fs.

BUGS

I had no chance to make real tests of this program because I use IDE drives, which remap bad blocks. I only made some tests on floppies.

AVAILABILITY

badblocks is available for anonymous FTP from <ftp.ibp.fr> and <tsx-11.mit.edu> in */pub/linux/packages/ext2fs*.

SEE ALSO

[e2fsck\(8\)](#), [mke2fs\(8\)](#)

Version 0.5b, November 1994

buffchan

buffchan—Buffered file-writing back end for InterNetNews.

SYNOPSIS

```
buffchan [ -b ][-c lines ][-C seconds ][-d directory ]
[-f fields ][-m map ][-p pidfile ][-l lines ][-L seconds ]
[-r ][-s file_format ][-u ]
```

DESCRIPTION

buffchan reads lines from standard input and copies certain fields in each line into files named by other fields within the line. buffchan is intended to be called by [innd\(8\)](#) as an exploder feed.

`buffchan` input is interpreted as a set of lines. Each line contains a fixed number of initial fields, followed by a variable number of filename fields. All fields in a line are separated by whitespace. The default number of initial fields is one; the `-f` flag may be used to specify a different number of fields. See `filechan(8)` for an example.

After the initial fields, each remaining field names a file to write. The `-s` flag may be used to specify a format string that maps the field to a filename. This is a `sprintf(3)` format string, which should have a single `%s` parameter that is given the field. The default value is `/news/spool/out.going/%s`. See the description of this flag in `filechan(8)`. The `-d` flag may be used to specify a directory the program should change to before starting. If this flag is used, then the default for the `-s` flag is changed to be a simple `%s`.

Once `buffchan` opens a file, it keeps it open. The input must therefore never specify more files than the number of available descriptors can keep open. If the `-b` flag is used, the program will allocate a buffer and attach it to the file using `setbuf(3)`. If the `-u` flag is used, the program will request unbuffered output.

If the `-l` flag is used with a number `n`, then `buffchan` will call `fflush(3)` after every `n` lines are written to a file. If the `-c` flag is used with a number `n`, then `buffchan` will close, and reopen, a file after every `n` lines are written to a file.

If the `-L` flag is used with a number `n`, then all files will be flushed every `n` seconds. Similarly, the `-c` flag may be used to specify that all files should be closed and reopened every `n` seconds.

By default, the program sets its standard error to `/var/log/news/errlog`. To suppress this redirection, use the `-r` flag.

If the `-p` flag is used, the program will write a line containing its process ID (in text) to the specified file.

`buffchan` can be invoked as an exploder feed (see `newsfeeds(5)`). As such, if a line starts with an exclamation point, it is treated as a command. There are three commands:

<code>flush</code>	The <code>flush</code> command closes and reopens all open files; <code>flush xxx</code> flushes only the specified site. These are analogous to the <code>ctlinnd(8)</code> <code>flush</code> command and can be achieved by doing a <code>send flush xxx</code> command. Applications can tell that the flush has completed by renaming the file before issuing the command; <code>buffchan</code> has completed the command when the original filename reappears. <code>buffchan</code> also changes the access permissions of the file from read-only for everyone to read-write for owner and group as it flushes or closes each output file. It changes the modes back to read-only if it reopens the same file.
<code>drop</code>	The <code>drop</code> command is similar to the <code>flush</code> command except that any files are not reopened. If given an argument, then the specified site is dropped; otherwise, all sites are dropped. (Note that the site will be restarted if the input stream mentions the site.) When a <code>ctlinnd</code> “drop site” command is sent, <code>innd</code> will automatically forward the command to <code>buffchan</code> if the site is a funnel that feeds into this exploder. To drop all sites, use the <code>ctlinnd send buffchan-site drop</code> command.
<code>readmap</code>	The map file (specified with the <code>-m</code> flag) is reloaded.

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for InterNetNews.

SEE ALSO

`ctlinnd(8)`, `filechan(8)`, `innd(8)`, `newsfeeds(5)`.

cfdisk

`cfdisk`—Curses-based disk partition table manipulator for Linux.

SYNOPSIS

```
cfdisk [ -avz ] [ -c cylinders ] [ -h heads ] [ -s sectors-per-track ] [ -P opt ]
[ device ]
```

DESCRIPTION

`cfdisk` is a curses-based program for partitioning a hard disk drive. The device can be any one of the following:

```
/dev/hda [default]
/dev/hdb
/dev/sda
/dev/sdb
/dev/sdc
/dev/sdd
```

`cfdisk` first tries to read the geometry of the hard disk. If it fails, an error message is displayed and `cfdisk` exits. This should only happen when partitioning a SCSI drive on an adapter without a BIOS. To correct this problem, you can set the cylinders, heads, and sectors-per-track on the command line. Next, `cfdisk` tries to read the current partition table from the disk drive. If it is unable to figure out the partition table, an error is displayed and the program exits. This might also be caused by incorrect geometry information and can be overridden on the command line. Another way around this problem is with the `-z` option. This will ignore the partition table on the disk.

The main display is composed of four sections, from top to bottom: the header, the partitions, the command line, and a warning line. The header contains the program name and version number followed by the disk drive and its geometry. The partitions section always displays the current partition table. The command line is the place where commands and text are entered. The available commands are usually displayed in brackets. The warning line is usually empty except when there is important information to be displayed. The current partition is highlighted with reverse video (or an arrow if the `-a` option is given). All partition-specific commands apply to the current partition.

The format of the partition table in the partition's section is, from left to right: Name, Flags, Partition Type, Filesystem Type, and Size. The name is the partition device name. The flags can be `Boot`, which designates a bootable partition or `NC`, which stands for "Not Compatible with DOS or OS/2." DOS, OS/2, and possibly other operating systems require the first sector of the first partition on the disk and all logical partitions to begin on the second head. This wastes the second through the last sector of the first track of the first head (the first sector is taken by the partition table itself). `cfdisk` allows you to recover these "lost" sectors with the `maximize` command (`m`). Note that `fdisk(8)` and some early versions of DOS create all partitions with the number of sectors already maximized. For more information, see the `maximize` command later in this chapter. The partition type can be `Primary` or `Logical`. For unallocated space on the drive, the partition type can also be `Pri/Log` or empty (if the space is unusable). The filesystem type section displays the name of the filesystem used on the partition, if known. If it is unknown, then `Unknown` and the hex value of the filesystem type are displayed. A special case occurs when there are sections of the disk drive that cannot be used (because all the primary partitions are used). When this is detected, the filesystem type is displayed as `Unusable`. The size field displays the size of the partition in megabytes (by default). It can also display the size in sectors and cylinders (see the `change units` command later in this chapter). If an asterisk (*) appears after the size, this means that the partition is not aligned on cylinder boundaries.

DOS 6.X WARNING

The DOS 6.x `FORMAT` command looks for some information in the first sector of the data area of the partition and treats this information as more reliable than the information in the partition table. DOS `FORMAT` expects DOS `FDISK` to clear the first 512 bytes of the data area of a partition whenever a size change occurs. DOS `FORMAT` looks at this extra information even if the `/U` flag is given; we consider this a bug in DOS `FORMAT` and DOS `FDISK`.

The bottom line is that if you use `cfdisk` or `fdisk` to change the size of a DOS partition table entry and then you must also use `dd` to zero the first 512 bytes of that partition before using DOS `FORMAT` to format the partition. For example, if you were using `cfdisk` to make a DOS partition table entry for `/dev/hda1`, then (after exiting `fdisk` or `cfdisk` and rebooting Linux so that the partition table information is valid), you use the command `dd if=/dev/zero of=/dev/hda1 bs=512 count=1` to zero the first 512 bytes of the partition.

Be extremely careful if you use the `dd` command because a small typo can make all of the data on your disk useless.

For best results, you should always use an OS-specific partition table program. For example, you should make DOS partitions with the DOS `FDISK` program and Linux partitions with the Linux `fdisk` or Linux `cfdisk` program.

COMMANDS

`cfdisk` commands can be entered by pressing the desired key (pressing `Enter` after the command is not necessary). Here is a list of the available commands:

b	Toggle bootable flag of the current partition. This allows you to select which primary partition is bootable on the drive.
d	Delete the current partition. This will convert the current partition into free space and merge it with any free space immediately surrounding the current partition. A partition already marked as free space or marked as unusable cannot be deleted.
g	Change the disk geometry (cylinders, heads, or sectors-per-track). Warning: This option should only be used by people who know what they are doing. A command-line option is also available to change the disk geometry. While at the change disk geometry command line, you can choose to change cylinders (d), heads (h), and sectors per track (s). The default value will be printed at the prompt, which you can accept by simply pressing the <code>Enter</code> key or you can exit without changes by pressing the <code>Esc</code> key. If you want to change the default value, simply enter the desired value and press <code>Enter</code> . The altered disk parameter values do not take effect until you return to the main menu (by pressing <code>Enter</code> or <code>Esc</code> at the change disk geometry command line. If you change the geometry such that the disk appears larger, the extra sectors are added at the end of the disk as free space. If the disk appears smaller, the partitions that are beyond the new last sector are deleted and the last partition on the drive (or the free space at the end of the drive) is made to end at the new last sector.
h	Print the help screen.
m	Maximize disk usage of the current partition. This command will recover the the unused space between the partition table and the beginning of the partition, at the cost of making the partition incompatible with DOS, OS/2, and possibly other operating systems. This option will toggle between maximal disk usage and DOS, OS/2, and so on compatible disk usage. The default when creating a partition is to create DOS, OS/2, and so on compatible partitions.
n	Create new partitions from free space. If the partition type is <code>Primary</code> or <code>Logical</code> , a partition of that type will be created, but if the partition type is <code>Pri/Log</code> , you will be prompted for the type you want to create. Be aware that there are only four slots available for primary partitions and because there can be only one extended partition that contains all of the logical drives, all of the logical drives must be contiguous (with no intervening primary partition). <code>cfdisk</code> next prompts you for the size of the partition you want to create. The default size, equal to the entire free space of the current partition, is displayed in megabytes. You can either press the <code>Enter</code> key to accept the default size or enter a different size at the prompt. <code>cfdisk</code> accepts size entries in megabytes (M) (default), kilobytes (K), cylinders (d), and sectors (S) when you enter the number immediately followed by M, K, C, or S. If the partition fills the free space available, the partition is created and you are returned to the main command line. Otherwise, the partition can be created at the beginning or the end of the free space, and <code>cfdisk</code> will ask you to choose where to place the partition. After the partition is created, <code>cfdisk</code> automatically adjusts the other partition's partition types if all of the primary partitions are used.
p	Print the partition table to the screen or to a file. There are several different formats for the partition that you can choose from:
r	Raw data format (exactly what would be written to disk).
s	Partition table in sector order format.
t	Partition table in raw format. The raw data format will print the sectors that would be written to disk if a <code>write</code> command is selected. First, the primary partition table is printed, followed by the partition tables associated with each logical partition. The data is printed in hex byte-by-byte with 16 bytes per line. The partition table in sector order format will print the partition table ordered by sector number. The fields, from left to right, are the number of the partition, the partition type, the first sector, the last sector, the offset from the first sector of the partition to the start of the data, the

length of the partition, the filesystem type (with the hex value in parentheses), and the flags (with the hex value in parentheses). In addition to the primary and logical partitions, free and unusable space is printed and the extended partition is printed before the first logical partition.

If a partition does not start or end on a cylinder boundary or if the partition length is not divisible by the cylinder size, an asterisk (*) is printed after the non-aligned sector number/count. This usually indicates that a partition was created by an operating system that either does not align partitions to cylinder boundaries or that used different disk geometry information. If you know the disk geometry of the other operating system, you can enter the geometry information with the change geometry command (g).

For the first partition on the disk and for all logical partitions, if the offset from the beginning of the partition is not equal to the number of sectors per track (that is, the data does not start on the first head), a number sign (#) is printed after the offset. For the remaining partitions, if the offset is not zero, a number sign is printed after the offset. This corresponds to the `nc` flag in the partitions section of the main display.

The partition table in raw format will print the partition table ordered by partition number. It will leave out all free and unusable space. The fields, from left to right, are the number of the partition, the flags (in hex), the starting head, sector, and cylinder, the filesystem ID (in hex), the ending head, sector, and cylinder, the starting sector in the partition, and the number of sectors in the partition. The information in this table can be directly translated to the raw data format. The partition table entries only have 10 bits available to represent the starting and ending cylinders. Thus, when the absolute starting (ending) sector number is on a cylinder greater than 1023, the maximal values for starting (ending) head, sector, and cylinder are printed. This is the method used by OS/2, and it fixes the problems associated with OS/2's `fdisk` rewriting the partition table when it is not in this format. Because Linux and OS/2 use absolute sector counts, the values in the starting and ending head, sector, and cylinder are not used.

q	Quit program. This will exit the program without writing any data to disk.
t	Change the filesystem type. By default, new partitions are created as Linux partitions, but because <code>cfdisk</code> can create partitions for other operating systems, changing the partition type allows you to enter the hex value of the filesystem you desire. A list of the known filesystem types is displayed. You can type the filesystem type at the prompt or accept the default filesystem type (Linux).
u	Change units of the partition size display. It will rotate through megabytes, sectors, and cylinders.
w	Write partition table to disk (you must enter an uppercase w). Because this might destroy data on the disk, you must either confirm or deny the write by entering <code>yes</code> or <code>no</code> . If you enter <code>yes</code> , <code>cfdisk</code> will write the partition table to disk and tell the kernel to re-read the partition table from the disk. The re-reading of the partition table works in most cases, but I have seen it fail. Don't panic. It will be correct after you reboot the system. In all cases, I still recommend rebooting the system just to be safe.
Up arrow, Down arrow	Move cursor to the previous or next partition. If there are more partitions than can be displayed on a screen, you can display the next (previous) set of partitions by moving down (up) at the last (first) partition displayed on the screen.
Ctrl+L	Redraws the screen. In case something goes wrong and you cannot read anything, you can refresh the screen from the main command line.
?	Print the help screen.

All the commands can be entered with either uppercase or lowercase letters (except for writes). When in a submenu or at a prompt to enter a filename, you can hit the `Esc` key to return to the main command line.

OPTIONS

-a	Use an arrow cursor instead of reverse video for highlighting the current partition.
-v	Print the version number and copyright.

- z Start with zeroed partition table. This option is useful when you want to repartition your entire disk. Note that this option does not zero the partition table on the disk; rather, it simply starts the program without reading the existing partition table.
- c cylinders
- h heads
- s sectors-per-track Override the number of cylinders, heads, and sectors-per-track read from the BIOS. If your BIOS or adapter does not supply this information or if it supplies incorrect information, use these options to set the disk geometry values.
- P opt Prints the partition table in specified formats. opt can be one or more of r, s, or t. See the print command for more information on the print formats.

SEE ALSO

fdisk(8)

BUGS

The current version does not support multiple disks (future addition).

AUTHOR

Kevin E. Martin (martin@cs.unc.edu)

The BOGUS Linux Release, 3 June 1995

chat

chat—Automated conversational script with a modem.

SYNOPSIS

chat [options] script

DESCRIPTION

The chat program defines a conversational exchange between the computer and the modem. Its primary purpose is to establish the connection between the Point-to-Point protocol daemon (pppd) and the remote's pppd process.

OPTIONS

- f <chat file> Read the chat script from the chat file. The use of this option is mutually exclusive with the chat script parameters. The user must have read access to the file. Multiple lines are permitted in the file. Space or horizontal tab characters should be used to separate the strings.
- t <timeout> Set the time-out for the expected string to be received. If the string is not received within the time limit, then the reply string is not sent. An alternate reply may be sent or the script will fail if there is no alternate reply string. A failed script will cause the chat program to terminate with a nonzero error code.
- r <report file> Set the file for output of the report strings. If you use the keyword REPORT, the resulting strings are written to this file. If this option is not used and you still use REPORT keywords, the stderr file is used for the report strings.
- v Request that the chat script be executed in a verbose mode. The chat program will then log all text received from the modem and the output strings that it sends to the syslog.

-v	Request that the chat script be executed in a <code>stderr</code> verbose mode. The chat program will then log all text received from the modem and the output strings that it sends to the <code>stderr</code> device. This device is usually the local console at the station running the chat or <code>pppd</code> program. This option does not work properly if the <code>stderr</code> is redirected to the <code>/dev/null</code> location because in that case <code>pppd</code> should run in the detached mode. In that case, use the <code>-v</code> option to record the session on the <code>SYSLOG</code> device.
script	If the script is not specified in a file with the <code>-f</code> option, then the script is included as parameters to the chat program.

CHAT SCRIPT

The chat script defines the communications.

A script consists of one or more “expect-send” pairs of strings, separated by spaces, with an optional “subexpect-sendsend” string pair, separated by a dash as in the following example:

```
ogin:-BREAK-ogin: ppp ssword: hello2u2
```

This line indicates that the chat program should expect the string `ogin:.` If it fails to receive a login prompt within the time interval allotted, it is to send a break sequence to the remote and then expect the string `ogin:.` If the first `ogin:.` is received, then the break sequence is not generated.

Once it receives the login prompt, the chat program will send the string `ppp` and then expect the prompt `ssword:.` When it receives the prompt for the password, it will send the password `hello2u2`.

A carriage return is usually sent following the reply string. It is not expected in the “expect” string unless it is specifically requested by using the `nr` character sequence.

The expect sequence should contain only what is needed to identify the string. Because it is usually stored on a disk file, it should not contain variable information. It is generally not acceptable to look for time strings, network identification strings, or other variable pieces of data such as an expect string.

To help correct for characters that may be corrupted during the initial sequence, look for the string `ogin:.` rather than `login:.` It is possible that the leading `l` character might be received in error and you might never find the string even though it was sent by the system. For this reason, scripts look for `ogin:.` rather than `login:.` and `ssword:.` rather than `password:.`

A very simple script might look like this:

```
ogin: ppp ssword: hello2u2
```

In other words, expect `...ogin:.`, send `ppp`, expect `...ssword:.`, send `hello2u2`.

In actual practice, simple scripts are rare. At the very least, you should include subexpect sequences in case the original string is not received. For example, consider the following script:

```
ogin:-ogin: ppp ssword: hello2u2
```

This is a better script than the simple one used earlier. This looks for the same `login:.` prompt; however, if one was not received, a single return sequence is sent and then it will look for `login:.` again. Should line noise obscure the first login prompt then sending the empty line will usually generate a login prompt again.

ABORT STRINGS

Many modems will report the status of the call as a string. These strings may be `CONNECTED` or `NO CARRIER` or `BUSY`. It is often desirable to terminate the script if the modem fails to connect to the remote. The difficulty is that a script does not know exactly which modem string it might receive. On one attempt, it might receive `BUSY`, but the next time, it might receive `NO CARRIER`.

These “abort” strings can be specified in the script using the `ABORT` sequence. It is written in the script as in the following example:

```
ABORT BUSY ABORT 'NO CARRIER' " ATZ OK ATDT5551212 CONNECT
```

This sequence will expect nothing and then send the string ATZ. The expected response to this is the string OK. When it receives OK, the string ATDT5551212 dials the telephone. The expected string is CONNECT. If the string CONNECT is received, the remainder of the script is executed. However, if the modem finds a busy telephone, it sends the string BUSY. This causes the string to match the abort character sequence. The script then fails because it found a match to the abort string. If it received the string NO CARRIER, it aborts for the same reason. Either string may be received. Either string will terminate the chat script.

REPORT STRINGS

A report string is similar to the ABORT string. The difference is that the strings and all characters to the next control character such as a carriage return, are written to the report file.

The report strings may be used to isolate the transmission rate of the modem's connect string and return the value to the chat user. The analysis of the report string logic occurs in conjunction with the other string processing such as looking for the expect string. The use of the same string for a report and abort sequence is probably not very useful; however, it is possible.

The report strings do not change the completion code of the program.

These "report" strings may be specified in the script using the REPORT sequence. It is written in the script as in the following example:

```
REPORT CONNECT ABORT BUSY " ATDT5551212 CONNECT " ogin: account
```

This sequence expects nothing and then sends the string ATDT5551212 to dial the telephone. The expected string is CONNECT. If the string CONNECT is received, the remainder of the script is executed. In addition, the program writes to the expect-file the string CONNECT plus any characters that follow it such as the connection rate.

TIME-OUT

The initial time-out value is 45 seconds. This may be changed using the -t parameter.

To change the time-out value for the next expect string, the following example may be used:

```
ATZ OK ATDT5551212 CONNECT TIMEOUT 10 ogin:-ogin: TIMEOUT 5 password:: hello2u2
```

This changes the time-out to 10 seconds when it expects the login: prompt. The time-out is then changed to 5 seconds when it looks for the password prompt.

The time-out, once changed, remains in effect until it is changed again.

SENDING EOT

The special reply string of EOT indicates that the chat program should send an EOT character to the remote. This is usually the End-of-file character sequence. A return character is not sent following the EOT. The EOT sequence may be embedded into the send string using the sequence ^D.

GENERATING BREAK

The special reply string of BREAK causes a break condition to be sent. The break is a special signal on the transmitter. The normal processing on the receiver is to change the transmission rate. It may be used to cycle through the available transmission rates on the remote until you are able to receive a valid login prompt. The break sequence may be embedded into the send string using the \K sequence.

ESCAPE SEQUENCES

The expect and reply strings may contain escape sequences. All the sequences are legal in the reply string. Many are legal in the expect. Those that are not valid in the expect sequence are so indicated.

''	Expects or sends a null string. If you send a null string, it will still send the return character. This sequence may either be a pair of apostrophe or quote characters.
\\b	Represents a backspace character.

<code>\\c</code>	Suppresses the newline at the end of the reply string. This is the only method to send a string without a trailing return character. It must be at the end of the send string. For example, the sequence <code>hello\\c</code> will simply send the characters <code>h</code> , <code>e</code> , <code>l</code> , <code>l</code> , <code>o</code> . (Not valid in expect.)
<code>\\d</code>	Delay for one second. The program uses <code>sleep(1)</code> , which will delay to a maximum of one second. (Not valid in expect.)
<code>\\K</code>	Insert a <code>BREAK</code> . (Not valid in expect.)
<code>\\n</code>	Send a newline or linefeed character.
<code>\\N</code>	Send a null character. The same sequence may be represented by <code>\\0</code> . (Not valid in expect.)
<code>\\p</code>	Pause for a fraction of a second. The delay is one tenth of a second. (Not valid in expect.)
<code>\\q</code>	Suppress writing the string to the <code>SYSLOG</code> file. The string <code>?????</code> is written to the log in its place. (Not valid in expect.)
<code>\\r</code>	Send or expect a carriage return.
<code>\\s</code>	Represents a space character in the string. This may be used when it is not desirable to quote the strings that contains spaces. The sequence <code>HI TIM</code> and <code>HI\\sTIM</code> are the same.
<code>\\t</code>	Send or expect a tab character.
<code>\\\\\\</code>	Send or expect a backslash character.
<code>\\ddd</code>	Collapse the octal digits (<code>ddd</code>) into a single ASCII character and send that character. (Some characters are not valid in expect.)
<code>^c</code>	Substitute the sequence with the control character represented by <code>c</code> . For example, the character <code>DC1</code> (17) is shown as <code>^Q</code> . (Some characters are not valid in expect.)

TERMINATION CODES

The chat program will terminate with the following completion codes:

<code>0</code>	The normal termination of the program. This indicates that the script was executed without error to the normal conclusion.
<code>1</code>	One or more of the parameters are invalid or an expect string was too large for the internal buffers. This indicates that the program as not properly executed.
<code>2</code>	An error occurred during the execution of the program. This may be due to a read or write operation failing for some reason or chat receiving a signal such as <code>SIGINT</code> .
<code>3</code>	A time-out event occurred when there was an expect string without having a <code>-subsend</code> string. This may mean that you did not program the script correctly for the condition or that some unexpected event occurred and the expected string could not be found.
<code>4</code>	The first string marked as an <code>ABORT</code> condition occurred.
<code>5</code>	The second string marked as an <code>ABORT</code> condition occurred.
<code>6</code>	The third string marked as an <code>ABORT</code> condition occurred.
<code>7</code>	The fourth string marked as an <code>ABORT</code> condition occurred.
<code>...</code>	The other termination codes are also strings marked as an <code>ABORT</code> condition.

Using the termination code, it is possible to determine which event terminated the script. It is possible to decide if the string `BUSY` was received from the modem as opposed to `NO DIAL TONE`. Although the first event may be retried, the second will probably have little chance of succeeding during a retry.

SEE ALSO

Additional information about chat scripts may be found with UUCP documentation. The chat script was taken from the ideas proposed by the scripts used by the `uucico` program.

`uucico(1)`, `uucp(1)`

COPYRIGHT

The chat program is in public domain. This is not the GNU public license. If it breaks, then you get to keep both pieces.

Chat Version 1.9, 5 May 1995

chroot

chroot—Change root directory and execute a program there.

SYNOPSIS

```
chroot directory program [ arg ... ]
```

DESCRIPTION

chroot changes the root directory for a process to a new directory executes a program there.

SEE ALSO

chroot(2)

AUTHOR

Rick Sladkey (jrs@world.std.com)

Linux 0.99, 20 November 1993

clock

clock—Manipulate the CMOS clock.

SYNOPSIS

```
/sbin/clock [ -u ] -r
/sbin/clock [ -u ] -w
/sbin/clock [ -u ] -s
/sbin/clock [ -u ] -a
```

DESCRIPTION

clock manipulates the CMOS clock in various ways, allowing it to be read or written and allowing synchronization between the CMOS clock and the kernel's version of the system time.

OPTIONS

-u	Indicates that the CMOS clock is set to Universal Time.
-r	Read CMOS clock and print the result to <code>stdout</code> .
-w	Write the system time into the CMOS clock.
-s	Set the system time from the CMOS clock.
-a	Set the system time from the CMOS clock, adjusting the time to correct for systematic error and writing it back into the CMOS clock. This option uses the file <code>/etc/adjtime</code> to determine how the clock changes. It contains three numbers. The first number is the correction in seconds per day. (For example, if your clock runs 5 seconds fast each day, the first number should read <code>-5.0</code> .) The second number tells when clock was last used in seconds since 1/1/1970. The third number is the remaining part of a second that was leftover after the last adjustment.

The following instructions are from the source code:

1. Create a file `/etc/adjtime` containing as the first and only line `0.0 0 0.0`.
2. Run `clock -au` or `clock -a`, depending on whether your CMOS is in Universal or Local Time. This updates the second number.
3. Set your system time using the `date` command.
4. Update your CMOS time using `clock -wu` or `clock -w`.
5. Replace the first number in `/etc/adjtime` by your correction.
6. Put the command `clock -au` or `clock -a` in your `/etc/rc.local` or let `cron(8)` start it regularly.

FILES

`/etc/adjtime`

`/etc/rc.local`

AUTHORS

V1.0

Charles Hedrick (hedrick@cs.rutgers.edu) Apr 1992

V1.1

Modified for clock adjustments, Rob Hooft (hooft@chem.ruu.nl) Nov 1992

V1.2

Patches by Harald Koenig (koenig@nova.tat.physik.uni-tuebingen.de) applied by Rob Hooft (hooft@EMBL-Heidelberg.DE) Oct 1993

Linux 0.99, 24 December 1992

comsat

comsat—Biff server

SYNOPSIS

`comsat`

DESCRIPTION

`comsat` is the server process that receives reports of incoming mail and notifies users if they requested this service. `comsat` receives messages on a datagram port associated with the biff service specification (see `services(5)` and `inetd(8)`). The one-line messages are of the form

`user@mailbox-offset`

If the user specified is logged in to the system and the associated terminal has the owner execute bit turned on (by a biff y), the offset is used as a seek offset into the appropriate mailbox file and the first 7 lines or 560 characters of the message are printed on the user's terminal. Lines that appear to be part of the message header other than the From, To, Date, or Subject lines are not included in the displayed message.

FILES

`/var/run/utmp` to find out who's logged on and on what terminals

SEE ALSO

`biff(1)`, `inetd(8)`

BUGS

The message header filtering is prone to error. The density of the information presented is near the theoretical minimum.

Users should be notified of mail that arrives on other machines than the one to which they are currently logged in.

The notification should appear in a separate window so it does not mess up the screen.

HISTORY

The command appeared in BSD 4.2.

BSD 4.2, 16 March 1991

crond

crond—cron daemon (Dillon's Cron).

SYNOPSIS

```
crond [-l#] [-d[#]] [-f] [-b] [-c directory]
```

OPTIONS

crond is a background daemon that parses individual crontab files and executes commands on behalf of the users in question.

-l loglevel	Set logging level; default is 8.
-d [debuglevel]	Set debugging level; default is 0. If no level is specified with the -d option, the default is 1. This option also sets the logging level to 0 and causes crond to run in the foreground.
-f	Run crond in the foreground.
-b	Run crond in the background (the default unless -d is specified).
-c directory	Specify directory containing crontab files.

DESCRIPTION

crond is responsible for scanning the crontab files and running their commands at the appropriate time. The crontab program communicates with crond through the cron.update file, which resides in the crontabs directory, usually /var/spool/cron/crontabs. This is accomplished by appending the filename of the modified or deleted crontab file to cron.update, which crond then picks up to resynchronize or remove its internal representation of the file.

crond has a number of built-in limitations to reduce the chance of it being ill-used. Potentially infinite loops during parsing are dealt with via a failsafe counter, and user crontabs are generally limited to 256 crontab entries. crontab lines may not be longer than 1024 characters, including the newline.

Whenever crond must run a job, it first creates a daemon-owned temporary file O_EXCL and O_APPEND to store any output, and then it fork()s and changes its user and group permissions to match that of the user the job is being run for. Then, it executes /bin/sh -c to run the job. The temporary file remains under the ownership of the daemon to prevent the user from tampering with it. Upon job completion, crond verifies the secureness of the mail file and, if it has been appended to, mails to the file to user. The sendmail program is run under the user's UID to prevent mail-related security holes. Unlike crontab, the crond program does not leave an open descriptor to the file for the duration of the job's execution because this might cause crond to run out of descriptors. When the crontab program allows a user to edit his crontab, it copies the crontab to a user-owned file before running the user's preferred editor. The suid crontab program keeps an open descriptor to the file, which it later uses to copy the file back, thereby ensuring the user has not tampered with the file type.

crond always synchronizes to the top of the minute, checking the current time against the list of possible jobs. The list is stored such that the scan goes very quickly, and crond can deal with several thousand entries without taking any noticeable amount of CPU.

AUTHOR

Matthew Dillon (dillon@apollo.west.oic.com)

1 May 1994

ctlinnd

ctlinnd—Control the InterNetNews daemon.

SYNOPSIS

```
ctlinnd [ -h ][-s ][-t timeout ] command [ argument... ]
```

DESCRIPTION

ctlinnd sends a message to the control channel of innd(8), the InterNetNews server.

In the normal mode of behavior, the message is sent to the server, which then performs the requested action and sends back a reply with a text message and the exit code for ctlinnd. If the server successfully performed the command, ctlinnd will exit with a status of zero and print the reply on standard output. If the server could not perform the command (for example, it was told to remove a newsgroup that does not exist), it will direct ctlinnd to exit with a status of one. The shutdown, xabort, and xexec commands do not generate a reply; ctlinnd will always exit silently with a status of zero. If the -s flag is used, then no message will be printed if the command was successful.

The -t flag can be used to specify how long to wait for the reply from the server. The timeout value specifies the number of seconds to wait. A value of zero waits forever, and a value less than zero indicates that no reply is needed. When waiting for a reply, ctlinnd will try every two minutes to see if the server is still running, so it is unlikely that -t0 will hang. The default is -t0.

To see a command summary, use the -h flag. If a command is included when ctlinnd is invoked with the -h flag, then only the usage for that command will be given.

If a large number of groups are going to be created or deleted at once, it may be more efficient to pause or throttle the server and edit the active file directly.

The complete list of commands follows. Note that all commands have a fixed number of arguments. If a parameter can be an empty string, then it is necessary to specify it as two adjacent quotes ("").

addhistMessage-ID arr exp post paths	Add an entry to the history database. This directs the server to create a history line for Message-ID. The angle brackets are optional. arr, exp, and post specify when the article arrived, what its expiration date is, and when it was posted. All three values are a number indicating the number of seconds since the epoch. If the article does not have an Expires header, then exp should be zero. paths is the pathname within the newsspool directory where the article is filed. If the article is cross-posted, then the names should be separated by whitespace and the paths argument should be inside double quotes. If the server is paused or throttled, this command causes it to briefly open the history database.
allow reason	Remote connections are allowed. The reason must be the same text given with an earlier reject command or an empty string.
begin site	Begin feeding site. This will cause the server to rescan the newsfeeds(5) file to find the specified site and set up a newsfeed for it. If the site already exists, a “drop” is done first. This command is forwarded; see below.
cancel <Message-ID>	Remove the article with the specified Message-ID from the local system. This does not generate a cancel message. The angle brackets are optional. If the server is paused or throttled, this command causes it to briefly open the history database.
changegroup group rest	The newsgroup group is changed so that its fourth field in the active file becomes the value specified by the rest parameter. This may be used to make an existing group moderated or unmoderated, for example.
checkfile	Check the syntax of the newsfeeds file, and display a message if any errors are found. The details of the errors are reported to syslog(3).

<code>drop site</code>	Flush and drop <code>site</code> from the server's list of active feeds. This command is forwarded; see below.
<code>flush site</code>	Flush the buffer for the specified <code>site</code> . The actions taken depend on the type of feed the site receives; see <code>newsfeeds(5)</code> . This is useful when the site is fed by a file and batching is going to start. If <code>site</code> is an empty string, then all sites are flushed and the active file and history databases are also written out. This command is forwarded; see below.
<code>flushlogs</code>	Close the log and error log files and rename them to have a <code>.old</code> extension. The history database and active file are also written out.
<code>go reason</code>	Reopen the history database and start accepting articles after a pause or throttle command. The <code>reason</code> must either be an empty string or match the text that was given in the earlier pause or throttle command. If a reject command was done, this will also do an allow command if the reason matches the text that was given in the reject. If a reserve command was done, this will also clear the reservation if the reason matches the text that was given in the reserve. Note that if only the history database has changed while the server is paused or throttled, it is not necessary to send it a reload command before sending it a go command. If the server throttled itself because it accumulated too many I/O errors, this command will reset the error count. If the server was not started with the <code>-ny</code> flag, then this command also does a readers command with <code>yes</code> as the flag and <code>reason</code> as the text.
<code>hangup channel</code>	Close the socket on the specified incoming <code>channel</code> . This is useful when an incoming connection appears to be hung.
<code>help [command]</code>	Print a command summary for all commands, or just <code>command</code> if specified.
<code>mode</code>	Print the server's operating mode as a multiline summary of the parameters and operating state.
<code>name nnn</code>	Print the name of channel number <code>nnn</code> or of all channels if it is an empty string.
<code>newsgroup group rest creator</code>	Create the specified newsgroup. The <code>rest</code> parameter should be the fourth field as described in <code>active(5)</code> ; if it is not an equal sign, only the first letter is used. The <code>creator</code> should be the name of the person creating the group. If the newsgroup already exists, this is equivalent to the <code>changegroup</code> command. This is the only command that has defaults. The <code>creator</code> can be omitted and will default to the empty string, and the <code>rest</code> parameter can be omitted and will default to <code>y</code> . This command can be done while the server is paused or throttled; it will update its internal state when a go command is sent. This command updates the <code>active.times</code> (see <code>active(5)</code>) file.
<code>param letter value</code>	Change the command-line parameters of the server. The combination of defaults makes it possible to use the text of the Control header directly. <code>letter</code> is the <code>innnd</code> command-line option to set, and <code>value</code> is the new value. For example, <code>i 5</code> directs the server to allow only five incoming connections. To enable or disable the action of the <code>-n</code> flag, use the letter <code>y</code> or <code>n</code> for the value.
<code>pause reason</code>	Pause the server so that no incoming articles are accepted. No existing connections are closed, but the history database is closed. This command should be used for short-term locks, such as when replacing the history files. If the server was not started with the <code>-ny</code> flag, then this command also does a readers command with <code>no</code> as the flag and <code>reason</code> as the text.
<code>readers flag text</code>	Allow or disallow newsreaders. If <code>flag</code> starts with the letter <code>n</code> , then newsreading is disallowed by causing the server to pass the text as the value of the <code>nnrpd(8) -r</code> flag. If <code>flag</code> starts with the letter <code>y</code> and <code>text</code> is either an empty

<code>reject reason</code>	string, or the same string that was used when newsreading was disallowed, then newsreading will be allowed.
<code>reload what reason</code>	Remote connections (those that would not be handed off to <code>nnrpd</code>) are rejected, with <code>reason</code> given as the explanation. The server updates its in-memory copies of various configuration files. <code>what</code> identifies what should be reloaded. If it is an empty string or the word <code>all</code> , then everything is reloaded; if it is the word <code>history</code> , then the history database is closed and opened; if it is the word <code>hosts.nntp</code> , then the <code>hosts.nntp(5)</code> file is reloaded; if it is the word <code>active</code> or <code>newsfeeds</code> , then both the <code>active</code> and <code>newsfeeds</code> files are reloaded; if it is the word <code>overview.fmt</code> , then the <code>overview.fmt(5)</code> file is reloaded. The reason is reported to <code>syslog</code> . There is no way to reload the <code>data.inn.conf(5)</code> file; the server currently only uses the <code>pathhost</code> parameter, so this restriction should not be a problem.
<code>renumber group</code>	Scan the spool directory for the specified newsgroup and update the low-water mark in the active file. If <code>group</code> is an empty string, then all newsgroups are scanned.
<code>reserve reason</code>	The next pause or throttle command must use <code>reason</code> as its text. This reservation is cleared by giving an empty string for the reason. This command is used by programs such as <code>expire(8)</code> that want to avoid running into other instances of each other.
<code>rmgroup group</code>	Remove the specified newsgroup. This is done by editing the active file. The spool directory is not touched, and any articles in the group will be expired using the default expiration parameters. Unlike the <code>newgroup</code> command, this command does not update the <code>active.times</code> file.
<code>send feed text...</code>	The specified <code>text</code> is sent as a control line to the exploder feed.
<code>shutdown reason</code>	The server is shut down, with the specified <code>reason</code> recorded in the log and sent to all open connections. It is a good idea to send a throttle command first.
<code>signal sig site</code>	Signal <code>sig</code> is sent to the specified <code>site</code> , which must be a channel or exploder feed. <code>sig</code> can be a numeric signal number or the word <code>hup</code> , <code>int</code> , or <code>term</code> ; case is not significant.
<code>throttle reason</code>	Input is throttled so that all existing connections are closed and new connections are rejected. The history database is closed. This should be used for long-term locks, such as when <code>expire</code> is being run. If the server was not started with the <code>-ny</code> flag, then this command also does a <code>readers</code> command with <code>no</code> as the flag and <code>reason</code> as the text.
<code>trace item flag</code>	Tracing is turned on or off for the specified item. <code>flag</code> should start with the letter <code>y</code> or <code>n</code> to turn tracing on or off. If <code>item</code> starts as a number, then tracing is set for the specified <code>inn</code> channel, which must be for an incoming NNTP feed. If it starts with the letter <code>I</code> , then general <code>inn</code> tracing is turned on or off. If it starts with the letter <code>n</code> , then future <code>nnrpd</code> 's will or will not have the <code>-t</code> flag enabled, as appropriate.
<code>xabort reason</code>	The server logs the specified <code>reason</code> and then invokes the <code>abort(3)</code> routine.
<code>xexec path</code>	The server gets ready to shut itself down, but instead of exiting, it executes the specified <code>path</code> with all of its original arguments. If <code>path</code> is <code>inn</code> , then <code>/news/bin/inn</code> is invoked; if it is <code>innstart</code> , then <code>/news/bin/innstart</code> is invoked; if it is an empty string, it will invoke the appropriate program depending on whether it was started with the <code>-p</code> flag; any other value is an error.

In addition to being acted upon within the server, certain commands can be forwarded to the appropriate child process. If the site receiving the command is an exploder (such as `buffchan(8)`) or it is a funnel that feeds into an exploder, then the command can be forwarded. In this case, the server will send a command line to the exploder that consists of the `ctlinn` command name. If the site funnels into an exploder that has an asterisk (*) in its `w` flag (see `newsfeed(5)`), then the site name is appended to the command; otherwise, no argument is appended.

BUGS

`ctlinn` uses the `inncomm(3)` library and is therefore limited to server replies no larger than 4KB.

HISTORY

Written by Rich Salz (`rsalz@uunet.uu.net`) for InterNetNews.

SEE ALSO

`active(5)`, `expire(8)`, `inn(8)`, `inncomm(3)`, `inn.conf(5)`, `newsfeeds(5)`, `overview.fmt(5)`

ctrlaltdel

`ctrlaltdel`—Set the function of the Ctrl+Alt+Del combination.

SYNOPSIS

```
ctrlaltdel hard|soft
```

DESCRIPTION

Based on examination of the `linux/kernel/sys.c` code, it is clear that there are two supported functions that the Ctrl+Alt+Del sequence can perform: a hard reset, which immediately reboots the computer without calling `sync(2)` and without any other preparation, and a soft reset, which sends the `SIGINT` (interrupt) signal to the `init` process (this is always the process with PID 1). If this option is used, the `init(8)` program must support this feature. Because there are now several `init(8)` programs in the Linux community, consult the documentation for the version that you are currently using.

`ctrlaltdel` is usually used in the `/etc/rc.local` file.

FILES

`/etc/rc.local`

SEE ALSO

`simpleinit(8)`, `init(8)`

AUTHOR

Peter Orbaek (`poe@daimi.aau.dk`)

Linux 0.99, 25 October 1993

cvsgub

`cvsgub`—Send problem report (PR) about CVS to a central support site.

SYNOPSIS

```
cvsgub [ site ] [-f problem-report] [-t mail-address] [-P] [-L ]  
[ --request-id ] [-v ]
```

DESCRIPTION

`cvsgub` is a tool used to submit problem reports (PRs) to a central support site. In most cases, the correct site will be the default. This argument indicates the support site that is responsible for the category of problem involved. Some sites may use a local address as a default. Site values are defined by using the `aliases(5)`.

`cvsgub` invokes an editor on a problem report template (after trying to fill in some fields with reasonable default values). When you exit the editor, `cvsgub` sends the completed form to the Problem Report Management System (GNATS) at a central support site. At the support site, the PR is assigned a unique number and is stored in the GNATS database according to its category and submitter ID. GNATS automatically replies with an acknowledgment, citing the category and the PR number.

To ensure that a PR is handled promptly, it should contain your (unique) submitter ID and one of the available categories to identify the problem area. (Use `cvsgub -L` to see a list of categories.)

The `cvsgub` template at your site should already be customized with your submitter ID (running `install-sid submitter-id` to accomplish this is part of the installation procedures for `cvsgub`). If this hasn't been done, see your system administrator for your submitter ID, or request one from your support site by invoking `cvsgub -request-id`. If your site does not distinguish between different user sites, or if you are not affiliated with the support site, use `net` for this field.

The more precise your problem description and the more complete your information, the faster your support team can solve your problems.

OPTIONS

<code>-f problem-report</code>	Specify a file (<code>problem-report</code>) that already contains a complete problem report. <code>cvsgub</code> sends the contents of the file without invoking the editor. If the value for <code>problem-report</code> is <code>-</code> , then <code>cvsgub</code> reads from standard input.
<code>-t mail-address</code>	Change mail address at the support site for problem reports. The default <code>mail-address</code> is the address used for the default site. Use the <code>site</code> argument rather than this option in nearly all cases.
<code>-P</code>	Print the form specified by the environment variable <code>PR_FORM</code> on standard output. If <code>PR_FORM</code> is not set, print the standard blank PR template. No mail is sent.
<code>-L</code>	Print the list of available categories. No mail is sent.
<code>--request-id</code>	Sends mail to the default support site, or <code>site</code> if specified, with a request for your submitter ID. If you are not affiliated with <code>site</code> , use a submitter ID of <code>net</code> .
<code>-v</code>	Display the <code>cvsgub</code> version number.

Note: Use `cvsgub` to submit problem reports rather than mail them directly. Using both the template and `cvsgub` itself will help ensure all necessary information will reach the support site.

ENVIRONMENT

The environment variable `EDITOR` specifies the editor to invoke on the template. The default is `vi`.

If the environment variable `PR_FORM` is set, then its value is used as the filename of the template for your problem-report editing session. You can use this to start with a partially completed form (for example, a form with the identification fields already completed).

HOW TO FILL OUT A PROBLEM REPORT

Problem reports have to be in a particular form so that a program can easily manage them. Please remember the following guidelines:

- Describe only one problem with each problem report.

- For follow-up mail, use the same subject line as the one in the automatic acknowledgment. It consists of category, PR number, and the original synopsis line. This allows the support site to relate several mail messages to a particular PR and to record them automatically.

Please try to be as accurate as possible in the subject or synopsis line.

The subject and the synopsis line are not confidential. This is because open-bugs lists are compiled from them. Avoid putting confidential information there.

See the GNU Info file `cvsgub.info` or the document *Reporting Problems With cvsgub* for detailed information on reporting problems

HOW TO SUBMIT TEST CASES, CODE, AND SO ON

Submit small code samples with the PR. Contact the support site for instructions on submitting larger test cases and problematic source code.

FILES

`/tmp/p$$$` copy of PR used in editing session

`/tmp/pf$$$` copy of empty PR form, for testing purposes

`/tmp/pbad$$$` file for rejected PRs

EMACS USER INTERFACE

An EMACS user interface for `cvsgub` with completion of field values is part of the `cvsgub` distribution (invoked with `M-x cvsgub`). See the file `cvsgub.info` or the ASCII file `INSTALL` in the top-level directory of the distribution for configuration and installation information. The EMACS LISP template file is `cvsgub-e1.in` and is installed as `cvsgub.e1`.

INSTALLATION AND CONFIGURATION

See `cvsgub.info` or `INSTALL` for installation instructions.

SEE ALSO

Reporting Problems Using cvsgub (also installed as the GNU Info file `cvsgub.info`).

`gnats(1)`, `query-pr(1)`, `edit-pr(1)`, `gnats(8)`, `queue-pr(8)`, `at-pr(8)`, `mkcat(8)`, `mkdist(8)`

AUTHORS

Jeffrey Osier, Brendan Kehoe, Jason Merrill, Heinz G. Seidl (Cygnus Support).

COPYING

Copyright(c) 1992, 1993 Free Software Foundation, Inc. Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be included in translations approved by the Free Software Foundation instead of in the original English.

xVERSIONx, February 1993

cvtbatch

`cvtbatch`—Convert Usenet batch file to INN format.

SYNOPSIS

`cvtbatch [ -w items ]`

DESCRIPTION

`cvtbatch` reads standard input as a series of lines, converts each line, and writes it to standard output. It is used to convert simple batchfiles that contain just the article name to INN batchfiles that contain additional information about each article.

Each line is taken as the pathname to a Usenet article. If it is not an absolute pathname, it is taken relative to the spool directory, `/news/spool`. (Only the first word of each line is parsed; anything following whitespace is ignored.)

The `-w` flag specifies how each output line should be written. The items for this flag should be chosen from the `w` flag items as specified in `newsfeeds(5)`. They may be chosen from the following set:

<code>b</code>	Size of article in bytes
<code>f</code>	Full pathname of article
<code>m</code>	Article Message-ID
<code>n</code>	Relative pathname of article

If the input file consists of a series of Message-IDs, then use `grephistory(1)` with the `-s` flag piped into `cvtbatch`.

HISTORY

Written by Rich Salz (`rsalz@uunet.uu.net`) for InterNetNews.

SEE ALSO

`grephistory(1)` `newsfeeds(5)`

cytune

`cytune`—Tune Cyclades driver parameters.

SYNOPSIS

```
cytune [-q [-i interval]] ([-s value][[-S value]]
[-g|G] ([-t timeout][[-T timeout]]) tty [tty ...]
```

DESCRIPTION

`cytune` queries and modifies the interruption threshold for the Cyclades driver. Each serial line on a Cyclades card has a 12-byte FIFO for input (and another 12-byte FIFO for output). The “threshold” specifies how many input characters must be present in the FIFO before an interruption is raised. When a Cyclades `tty` is opened, this threshold is set to a default value based on baud rate:

<i>Baud</i>	<i>Threshold</i>
50-4800	10
9600	8
19200	4
38400	2
57600-150000	1

If the threshold is set too low, the large number of interruptions can load the machine and decrease overall system throughput. If the threshold is set too high, the FIFO buffer can overflow, and characters will be lost. Slower machines, however, may not be able to deal with the interrupt load and will require that the threshold be adjusted upwards.

If the Cyclades driver was compiled with `ENABLE_MONITORING` defined, the `cytune` command can be used with the `-q` option to report interrupts over the monitoring interval and characters transferred over the monitoring interval. It will also report

the state of the FIFO. The maximum number of characters in the FIFO when an interrupt occurred, the instantaneous count of characters in the FIFO, and how many characters are now in the FIFO are reported. This output might look like this:

```
/dev/cubC0: 830 ints, 9130 chars; fifo: 11 threshold, 11 max, 11 now
166.259866 interrupts/second, 1828.858521 characters/second
```

This output indicates that for this monitoring period, the interrupts were always being handled within one character time because max never rose above threshold. This is good, and you can probably run this way, provided that a large number of samples come out this way. You will lose characters if you overrun the FIFO because the Cyclades hardware does not seem to support the RTS RS-232 signal line for hardware flow control from the DCE to the DTE.

cytune will in query mode produce a summary report when ended with a SIGINT or when the threshold or time-out is changed.

There may be a responsiveness versus throughput tradeoff. The Cyclades card, at the higher speeds, is capable of putting a very high interrupt load on the system. This will reduce the amount of CPU time available for other tasks on your system. However, the time it takes to respond to a single character may be increased if you increase the threshold. This might be noticed by monitoring ping(8) times on a SLIP link controlled by a Cyclades card. If your SLIP link is generally used for interactive work such as telnet(1), you might want to leave the threshold low so that characters are responded to as quickly as possible. If your SLIP link is generally used for file transfer, WWW, and the like, setting the FIFO to a high value is likely to reduce the load on your system while not significantly affecting throughput. Alternatively, see the -t or -T options to adjust the time that the Cyclades waits before flushing its buffer. Units are 5ms.

If you are running a mouse on a Cyclades port, it is likely that you want to maintain the threshold and time-out at a low value.

OPTIONS

-s value	Set the current threshold to value characters. Note that if the tty is not being held open by another process, the threshold will be reset on the next open. Only values between 1 and 12, inclusive, are permitted.
-t value	Set the current flush time-out to value units. Note that if the tty is not being held open by another process, the threshold will be reset on the next open. Only values between 0 and 255, inclusive, are permitted. Setting value to 0 forces the default, currently 0x20 (160ms) but soon to be 0x02 (10ms). Units are 5ms.
-g	Get the current threshold and time-out.
-T value	Set the default flush time-out to value units. When the tty is next opened, this value is used instead of the default. If value is 0, then the value defaults to 0x20 (160ms), soon to be 0x02 (10ms).
-G	Get the default threshold and flush time-out values.
-q	Gather statistics about the tty. The results are only valid if the Cyclades driver has been compiled with ENABLE_MONITORING defined. This is probably not the default.
-i interval	Statistics will be gathered every interval seconds.

BUGS

If you run two copies of cytune at the same time to report statistics about the same port, the ints, chars, and max values will be reset and not reported correctly. cytune(8) should prevent this but does not.

AUTHOR

Nick Simicich (njs@scifi.emi.net), with modifications by Rik Faith (faith@cs.unc.edu)

FILES

```
/dev/ttyC[0-8]
```

```
/dev/cubC[0-8]
```

SEE ALSO

```
setserial(8)
```

4 March 1995

debugfs

debugfs—ext2 filesystem debugger.

SYNOPSIS

```
debugfs [[-w ]device]
```

DESCRIPTION

debugfs is a filesystem debugger. It can be used to examine and change the state of an ext2 filesystem. device is the special file corresponding to the device containing the ext2 filesystem (such as /dev/hdxx).

OPTIONS

-w Specify that the filesystem should be open in read-write mode. Without this option, the filesystem is open in read-only mode.

COMMANDS

debugfs is an interactive debugger. It understands a number of commands:

cd file	
chroot file	
close	Close the currently open filesystem.
clr! file	Clear the contents of the inode corresponding to file.
expand_dir, file	Expand a directory.
find_free_block [goal]	Find the first free block, starting from goal, and allocate it.
find_free_inode [dir [mode]]	Find a free inode and allocate it.
freeb block	Mark the block as not allocated.
freei file	Free the inode corresponding to file.
help	
iname inode	Print the filename corresponding to inode (currently not implemented).
initialize device blocksize	Create an ext2 file system on device.
kill_file file	Remove a file and deallocate its blocks.
ln source_file dest_file	Create a link.
ls [pathname]	Emulate the ls(1) command.
modify_inode file	Modify the contents of the inode corresponding to file.
mkdir file	Make a directory.
open [-w] device	Open a filesystem.
pwd	
quit	Quit debugfs.

<code>rm file</code>	Remove a file.
<code>rmdir file</code>	Remove a directory.
<code>setb block</code>	Mark the block as allocated.
<code>seti file</code>	Mark in use the inode corresponding to file
<code>show_super_stats</code>	List the contents of the super block.
<code>stat file</code>	Dump the contents of the inode corresponding to file.
<code>testb block</code>	Test if the block is marked as allocated.
<code>testi file</code>	Test if the inode corresponding to file is marked as allocated.
<code>unlink file</code>	Remove a link.

AUTHOR

debugfs was written by Theodore T'so (tytso@mit.edu).

SEE ALSO

`dumpe2fs(8)`, `e2fsck(8)`, `mke2fs(8)`

Version 0.5b, November 1994

dip

`dip`—Dialup IP connection handler.

SYNOPSIS

```
dip [-t]
dip [-ktv] [-m mtu] scriptfile
dip [-iv] [user_name]
```

DESCRIPTION

`dip` handles the connections needed for dialup IP links, such as SLIP or PPP. It can handle both incoming and outgoing connections, using password security for incoming connections. The outgoing connections use the system's `dial(3)` library if available.

COMMAND MODE

The first possible use of `dip` is as a stand-alone program to set up an outgoing IP connection. This can be done by invoking `dip` with the `-t` option, which means enter TEST mode and, more precisely, dump you in the `COMMAND-MODE` of the `dip` program. You are reminded of this by the `DIP>` prompt, or, if you also specified the `-v` debugging flag, the `DIP [NNNN]>` prompt. The latter prompt also displays the current value of the global `errlvl` variable, which is used mostly when `dip` runs in script mode. For the interactive mode, it can be used to determine if the result of the previous command was okay.

The following is a sample taken from a live session:

```
$dip-t
DIP: Dialup IP Protocol Driver version 3.3.7 (12/13/93)
Written by Fred N. van Kempen, MicroWalt Corporation.
```

```
DIP>_
```

The most helpful command in this mode is, of course, the `help` command, which should produce an output similar to this:

```
DIP> help
DIP knows about the following commands:
```

```

databits default dial echo flush
get goto help if init
mode modem parity print port
reset send sleep speed stopbits
term wait

```

```
DIP>_
```

All commands display how they should be used when invoking them with no or invalid arguments. Just experiment a little to get the feel of it, and have a look at the sample script files, which also use this command language.

DIALIN MODE

The second possible way of using `dip` is as a login shell for incoming IP connections, as in dialup SLIP and PPP connections. To make integration into the existing UNIX system as easy as possible, `dip` can be installed as simply as using it as a login shell in the system's password file. A sample entry looks like

```
suunet:ij/SMxiTlGVC0:1004:10:UUNET:/tmp:/usr/bin/dip -i
```

When user `suunet` logs in, the `login(1)` program sets the home directory to `/tmp` and execute the `dip` program with the `-i` option, which means that `dip` must run in input mode. `dip` then tries to locate the name of the logged-in user (the name corresponding to its current user ID, as returned by the `getuid(2)` system call) in its database file. An optional single argument to the `dip` program in this mode can be the username that must be used in this lookup, regardless of the current user ID.

`dip` now scans the `/etc/net/diphhosts` file for an entry for the given username. This file contains lines of text (much like the standard password file). The format looks like

```

#
# diphhosts This file describes a number of name to
# address mappings for the DIP program. It
# is used to determine which IP address to
# use for in incoming call of some user.
#
# Version: @(#)diphhosts 1.00 12/10/92 FvK
#
# Author: Fred N. van Kempen,
# <waltje@u.walt.nl.mugnet.org>
#
suunet::uunet.uu.net:UUNET SLIP:SLIP,296

# End of diphhosts.

```

The first field of a line identifies the username, which you must match. The second field can contain an encrypted password. If this field is non-null, the `dip` program asks for an external security password, which must match the password in this field. The third field contains the name (or raw IP address) of the host that is connecting to the system with this link. If a hostname is given, the usual address resolving process is started, using either a nameserver or a local hosts file.

The fourth field can contain any text; it is not (yet) used by the `dip` program. In future releases, this info may be used in the system log files. Finally, the fifth field of a line contains a mixture of comma-separated flags. Possible flags are

SLIP to indicate you must use the SLIP protocol.

PPP to indicate you must use the PPP protocol.

number, which gives the MTU parameter of this connection.

After finding the correct line, `dip` puts the terminal line into RAW mode and asks the system networking layer to allocate a channel of the desired protocol. Finally, if the channel is activated, it adds an entry to the system's routing table to make the connection work.

dip now goes into an endless loop of sleeping, which continues until the connection is physically aborted (the line is dropped). At that time, dip removes the entry it made in the system's routing table and releases the protocol channel for reuse. It then exits, making room for another session.

DIALOUT MODE

The last way of using dip is as a program that initiates outgoing connections. To make life easier for the people who have to manage links of this type, dip uses a chat script to set up a link to a remote system. This gives the user an enormous amount of flexibility when making the connection, which otherwise could require many command-line options. The pathname of the script to be run is then given as the single argument to dip; the program will automatically check if the file has a filename ending in a .dip part. This is not mandatory—just a tool to group scripts together in a single directory. A script should look something like this:

```
#
# sample.dip Dialup IP connection support program.
# This file (should show) shows how to use the DIP
# scripting commands to establish a link to a host.
# This host runs the 386bsd operating system, and
# thus can only be used for the "static" addresses.
#
# NOTE: We also need an example of a script used to
# connect to a "dynamic" SLIP server, like an Annex
# terminal server...
#
# Version: @(#)sample.dip 1.30 07/05/93
#
# Author: Fred N. van Kempen, <waltje@uWalt.NL.Mugnet.ORG>
#
main:
# First of all, set up our name for this connection.
# I am called "uwalt.hacktic.nl" (== 193.78.33.238)
get $local uwalt.hacktic.nl
# Next, set up the other side's name and address.
# My dialin machine is called 'xs4all.hacktic.nl' (== 193.78.33.42)
get $remote xs4all.hacktic.nl
# Set the desired serial port and speed.
port cua0
speed 38400
# Reset the modem and terminal line.
# This seems to cause trouble for some people!
reset
# Prepare for dialing.
send ATQ0V1E1X1
wait OK 2
if $errlvl != 0 goto error
dial 555-1234567
if $errlvl != 0 goto error
wait CONNECT 60
if $errlvl != 0 goto error
# We are connected. Login to the system.
login:
sleep 3
send \r\n\r\n
wait ogin: 10
if $errlvl != 0 goto error
send NO-WAY\n
wait ord: 5
if $errlvl != 0 goto error
send HA-HA\n
```

```

wait $ 30
if $errlvl != 0 goto error
loggedin:
# We are now logged in. Start the 'sliplogin' program,
# as this is not automatically done for me.
send sliplogin\n
wait SOME-STRING 15
# Set up the SLIP operating parameters.
get $mtu 1500
# Set Destination net/address as type 'default' (vice an address).
# This is used by the 'route' command to set the kernel routing table.
# Some machines seem to require this be done for SLIP to work properly.
default
# Say hello and fire up!
done:
print CONNECTED to $remote with address $rmtip
mode SLIP
goto exit
error:
print SLIP to $remote failed.
exit:

```

This script causes dip to dial up a host, log in, and get a SLIP interface channel going (in the same manner as with incoming connections). When all is set up, it simply goes into the background and waits for a hangup (or just a lethal signal), at which it hangs up and exits.

FILES

```

/etc/passwd
/etc/diphosts

```

AUTHORS

Fred N. van Kempen (waltje@u.walt.nl.mugnet.org), Paul Mossip (mossip@vizlab.rutgers.edu), Jeff Uphoff (juphoff@aoc.nrao.edu), Jim Seagrave (jes@grendel.demon.co.uk), Olaf Kirch (okir@monad.sub.de).

Version 3.3.7, 13 December 1993

dmesg

dmesg—Print or control the kernel ring buffer.

SYNOPSIS

```
dmesg [ -c ] [ -n level ]
```

DESCRIPTION

dmesg is used to examine or control the kernel ring buffer.

The program helps users to print their bootup messages. Instead of copying the messages by hand, the user need only

```
dmesg > boot.messages
```

and mail the `boot.messages` file to whoever can debug their problem.

OPTIONS

- c Clear the ring buffer contents after printing.
- n level Set the level at which logging of messages is done to the console. For example, -n 1 prevents all messages, except panic messages, from appearing on the console. All levels of messages are still written to `/proc/kmsg`, so `syslogd(8)` can still be used to control exactly where kernel messages appear. When the -n option is used, `dmesg` will not print or clear the kernel ring buffer.

When both options are used, only the last option on the command line will have an effect.

SEE ALSO

`syslogd(8)`

AUTHOR

Theodore Ts'o (tytso@athena.mit.edu)

Linux 0.99, 28 October 1993

dumpe2fs

`dumpe2fs`—Dump filesystem information.

SYNOPSIS

`dumpe2fs device`

DESCRIPTION

`dumpe2fs` prints the super block and blocks group information for the filesystem present on device.

`dumpe2fs` is similar to Berkeley's `dumpfs` program for the BSD Fast File System.

BUGS

You need to know the physical filesystem structure to understand the output.

AUTHOR

`dumpe2fs` was written by Remy Card (card@masi.ibp.fr), the developer and maintainer of the `ext2 fs`.

AVAILABILITY

`dumpe2fs` is available for anonymous FTP from <ftp.ibp.fr> and <tsx-11.mit.edu> in `/pub/linux/packages/ext2fs`.

SEE ALSO

`e2fsck(8)`, `mke2fs(8)`, `tune2fs(8)`

Version 0.5b, November 1994

e2fsck

`e2fsck`—Check a Linux second extended filesystem.

SYNOPSIS

```
e2fsck [ -panyrdfvtFV ][ -b superblock ][ -B blocksize ]
[ -l|-L bad_blocks_file ] device
```

DESCRIPTION

`e2fsck` is used to check a Linux second extended file system.

`device` The special file corresponding to the device (such as `/dev/hdXX`).

OPTIONS

- `-a` This option does the same thing as the `-p` option. It is provided for backwards compatibility only; it is suggested that people use `-p` option whenever possible.
- `-b superblock` Instead of using the normal superblock, use the alternative superblock specified by `superblock`.
- `-B blocksize` Usually, `e2fsck` will search for the superblock at various different block sizes in an attempt to find the appropriate block size. This search can be fooled in some cases. This option forces `e2fsck` to only try locating the superblock at a particular `blocksize`. If the superblock is not found, `e2fsck` will terminate with a fatal error.
- `-d` Print debugging output (useless unless you are debugging `e2fsck`).
- `-f` Force checking even if the filesystem seems clean.
- `-F` Flush the filesystem device's buffer caches before beginning. Only really useful for doing `e2fsck` time trials.
- `-l filename` Add the blocks listed in the file specified by `filename` to the list of bad blocks.
- `-L filename` Set the bad blocks list to be the list of blocks specified by `filename`. (This option is the same as the `-l` option except the bad blocks list is cleared before the blocks listed in the file are added to the bad blocks list.)
- `-n` Open the filesystem read-only, and assume an answer of “no” to all questions. Allows `e2fsck` to be used non-interactively. (Note: if the `-l` or `-L` options are specified in addition to the `-n` option, then the filesystem will be opened read-write to permit the bad-blocks list to be updated. However, no other changes will be made to the filesystem.)
- `-p` Automatically repair (“preen”) the filesystem without any questions.
- `-r` This option does nothing at all; it is provided only for backwards compatibility.
- `-t` Print timing statistics for `e2fsck`. If this option is used twice, additional timing statistics are printed on a pass-by-pass basis.
- `-v` Verbose mode.
- `-V` Print version information and exit.
- `-y` Assume an answer of “yes” to all questions; allows `e2fsck` to be used non-interactively.

EXIT CODE

The exit code returned by `e2fsck` is the sum of the following conditions:

- 0 No errors
- 1 Filesystem errors corrected
- 2 Filesystem errors corrected; system should be rebooted if filesystem was mounted
- 4 Filesystem errors left uncorrected
- 8 Operational error
- 16 Usage or syntax error
- 128 Shared library error

BUGS

Almost any piece of software will have bugs. If you manage to find a filesystem that causes `e2fsck` to crash, or that `e2fsck` is unable to repair, please report it to the author.

Please include as much information as possible in your bug report. Ideally, include a complete transcript of the `e2fsck` run, so I can see exactly what error messages are displayed. If you have a writeable filesystem where the transcript can be stored, the `script(1)` program is a handy way to save the output of `e2fsck` to a file.

It is also useful to send the output of `dumpe2fs(8)`. If a specific inode or inodes seems to be giving `e2fsck` trouble, try running the `debugfs(8)` command and send the output of the `stat` command run on the relevant inodes. If the inode is a directory, the `debugfs dump` command will allow you to extract the contents of the directory inode, which can sent to me after being first run through `uuencode(1)`.

Always include the full version string that `e2fsck` displays when it is run so I know which version you are running.

AUTHOR

This version of `e2fsck` is written by Theodore Ts'o (tytso@mit.edu).

SEE ALSO

`mke2fs(8)`, `tune2fs(8)`, `dumpe2fs(8)`, `debugfs(8)`

Version 0.5b, November 1994

edquota

edquota—Edit user quotas.

SYNOPSIS

```
/usr/etc/edquota [ -p proto-user ][ -ug ] name...
/usr/etc/edquota [ -ug ] -t
```

DESCRIPTION

`edquota` is a quota editor. One or more users or groups may be specified on the command line. For each user or group, a temporary file is created with an ASCII representation of the current disk quotas for that user or group and an editor is then invoked on the file. The quotas may then be modified, new quotas added, and so on. Upon leaving the editor, `edquota` reads the temporary file and modifies the binary quota files to reflect the changes made.

The editor invoked is `vi(1)` unless the environment variable specifies otherwise.

Only the superuser may edit quotas. (For quotas to be established on a filesystem, the root directory of the filesystem must contain a file, owned by root, called `quota.user` or `quota.group`. See `quotaon(8)` for details.)

OPTIONS

- u Edit the userquota. This is the default.
- g Edit the groupquota.
- p Duplicate the quotas of the prototypical user specified for each user specified. This is the normal mechanism used to initialize quotas for groups of users.
- t Edit the soft time limits for each filesystem. If the time limits are zero, the default time limits in `<linux/quota.h>` are used. Time units of sec(onds), min(utes), hour(s), day(s), week(s), and month(s) are understood. Time limits are printed in the greatest possible time unit such that the value is greater than or equal to one.

FILES

<code>quota.user</code> or <code>quota.group</code>	Quota file at the filesystem root
<code>/etc/mtab</code>	Mounted filesystems

SEE ALSO

`quota(1)`, `vi(1)`, `quotactl(2)`, `quotacheck(8)`, `quotaon(8)`, `repquota(8)`

BUGS

The format of the temporary file is inscrutable.

8 June 1993

expire

`expire`—Usenet article and history expiration program.

SYNOPSIS

```
expire [ -d dir ][-f file ][-g file ][-h file ]
        [-i ][-l ][-n ][-p ][-q ][-r reason ][-s ][-t ]
        [-v level ][-w number ][-x ][-z file ][expirectl]
```

DESCRIPTION

`expire` scans the `history(5)` text file `/news/lib/history` and uses the information recorded in it to purge old news articles. To specify an alternate history file, use the `-f` flag. To specify an alternate input text history file, use the `-h` flag. `expire` uses the old `dbz(3z)` database to determine the size of the new one. To ignore the old database, use the `-i` flag.

`expire` usually just unlinks each file if it should be expired. If the `-l` flag is used, then all articles after the first one are treated as if they could be symbolic links to the first one. In this case, the first article will not be removed as long as any other cross-posts of the article remain.

`expire` usually sends a pause command to the local `innd(8)` daemon when it needs exclusive access to the history file, using the string `Expiring` as the reason. To give a different reason, use the `-r` flag. The process ID will be appended to the reason. When `expire` is finished and the new history file is ready, it sends a go command. If `innd` is not running, use the `-n` flag and `expire` will not send the pause or go commands. (For more details on the commands, see `ctlinnd(8)`.) Note that `expire` only needs exclusive access for a very short time—long enough to see if any new articles arrived since it first hit the end of the file and to rename the new files to the working files.

If the `-s` flag is used, then `expire` will print a summary when it exits, showing the approximate number of kilobytes used by all deleted articles.

If the `-t` flag is used, then `expire` will generate a list of the files that should be removed on its standard output, and the new history file will be left in `history.n`, `history.n.dir`, and `history.n.pag`. This flag is useful for debugging when used with the `-n` and `-s` flags. Note that if the `-f` flag is used, then the name specified with that flag will be used instead of `history`.

If the `-x` flag is used, then `expire` will not create any new history files. This is most useful when combined with the `-n`, `-s`, and `-t` flags to see how different expiration policies would change the amount of disk space used.

If the `-z` flag is used, then articles are not removed, but their names are written to the specified file. See the description of `expirerm` in `news.daily(8)`.

`expire` makes its decisions on the time the article arrived, as found in the history file. This means articles are often kept a little longer than with other expiration programs that base their decisions on the article's posting date. To use the article's posting date, use the `-p` flag. Use the `-w` flag to “warp” time so that `expire` thinks it is running at some time other than the current time. The value should be a signed floating-point number of the number of days to use as the offset.

If the `-d` flag is used, then the new history file and database is created in the specified directory, `dir`. This is useful when the filesystem does not have sufficient space to hold both the old and new history files. When this flag is used, `expire` leaves the server paused and creates a zero-length file named after the new history file, with an extension of `.done` to indicate that it has successfully completed the expiration. The calling script should install the new history file and unpause the server. The `-r` flag should be used with this flag.

If a filename is specified, it is taken as the control file and parsed according to the rules in `expire.ct1(5)`. A single dash (`-`) may be used to read the file from standard input. If no file is specified, the file `/news/lib/expire.ct1` is read.

`expire` usually complains about articles that are posted to newsgroups not mentioned in the active file. To suppress this action, use the `-q` flag.

The `-v` flag is used to increase the verbosity of the program, generating messages to standard output. The level should be a number, where higher numbers result in more output. Level one will print totals of the various actions done (not valid if a new history file is not written), level two will print report on each individual file, and level five results in more than one line of output for every line processed. If the `-g` flag is given, then a one-line summary equivalent to the output of `-v1` and preceded by the current time will be appended to the specified file.

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for InterNetNews.

SEE ALSO

`ctlinnd(8)`, `dbz(3z)`, `expire.ct1(5)`, `history(5)`, `innd(8)`, `inndcomm(3)`

expireover

`expireover`—Expire entries from the news overview database.

SYNOPSIS

```
expireover [ -a ][-D overviewdir ][-f file ][-n ]
           [-O overview.fmt ][-s ][-v ][-z ][file... ]
```

DESCRIPTION

`expireover` expires entries from the news overview database. It reads a list of pathnames (relative to the spool directory, `/news/spool`) from the specified files or standard input if none are specified. (A filename of `-` may be used to specify the standard input.) It then removes any mention of those articles from the appropriate overview database. If the `-z` flag is used, then the input is assumed to be sorted such that all entries for a newsgroup appear together so that it can be purged at once. This flag can be useful when used with the sorted output of `expire(8)`'s `-z` flag.

If the `-s` flag is used, then `expireover` will read the spool directory for all groups mentioned in the `active(5)` file and remove the overview entries for any articles that do not appear. To specify an alternate file, use the `-f` flag; a name of `-` is taken to mean the standard input.

The `-a` flag reads the spool directory and adds any missing overview entries. It will create files if necessary. This can be used to initialize a database or to sync up a overview database that may be lacking articles due to a crash. `overchan` should be running, to ensure that any incoming articles get included. Using this flag implies the `-s` flag; the `-f` flag may be used to add only a subset of the newsgroups.

To see a list of the entries that would be added or deleted, use the `-v` flag. To perform no real updates, use the `-n` flag.

The `-D` flag can be used to specify where the databases are stored. The default directory is `/news/spool`.

The `-O` flag may be used to specify an alternate location for the `overview.fmt(5)` file; this is usually only useful for debugging.

HISTORY

Written by Rob Robertson (rob@violet.berkeley.edu) and Rich Salz (rsalz@uunet.uu.net) with help from Dave Laurence (tale@uunet.uu.net) for InterNetNews.

SEE ALSO

`expire(8)`, `overview.fmt(5)`

fastrm

fastrm—Quickly remove a set of files.

SYNOPSIS

```
fastrm [ -d ][-e ][-uN ][-sM ][-cI ] base_directory
```

DESCRIPTION

fastrm reads a list of files, one per line, from its standard input and removes them. If a file is not an absolute pathname, it is taken relative to the directory specified on the command line. The base directory parameter must be a simple absolute pathname—that is, it must not contain any `./` or `../` references.

fastrm is designed to be faster than the typical `| xargs rm` pipeline. For example, **fastrm** will usually `chdir(2)` into a directory before removing files from it. If the input is sorted, this means that most files to be removed will be simple names.

fastrm assumes that its input is valid and that it is safe to just do an `unlink(2)` call for each item to be removed. As a safety measure, if **fastrm** is run by root, it will first `stat(2)` the item to make sure that it is not a directory before unlinking it.

If the `-d` flag is used, then no files are removed. Instead, a list of the files to be removed, in debug form, is printed on the standard output. Each line contains either the current directory of **fastrm** at the time it would do the `unlink` and then the pathname it would pass to `unlink(2)` as two fields separated by white space and a `/` or the absolute pathname (a single field) of files it would unlink using the absolute pathname.

If the `-e` flag is used, **fastrm** will treat an empty input file (`stdin`) as an error. This is most useful when **fastrm** is last in a pipeline after a preceding `sort(1)` because if the sort fails, there will usually be no output to become input of **fastrm**.

If the `-u` flag is used, then **fastrm** makes further assumptions about its work environment—in particular, that there are no symbolic links in the target tree. This flag also suggests that it is probably faster to reference the path `.././../` rather than start from the root and come down (note that this probably isn't true on systems that have a `namei` cache, which usually holds everything except `..`). The optional `N` is an integer that specifies the maximum number of `..` segments to use—paths that would use more than this use the absolute pathname (from the root) instead. If the `-u` flag is given without a value, `-u1` is assumed.

If the `-s` flag is used, then **fastrm** will perform the unlinks from one directory—that is, when a group of files in one directory appear in the input consecutively—in the order that the files appear in the directory from which they are to be removed. The intent of this flag is that on systems that have a per-process directory cache, finding files in the directory should be faster. It can have smaller benefits on other systems. The optional `M` is an integer that specifies the number of files that must be going to be removed from one directory before the files will be ordered. If the `-s` flag is given without a value, `-s5` is assumed. When the directory reordering is in use, **fastrm** will avoid attempting to unlink files that it can't see in the directory, which can speed it appreciably when many of the filenames have already been removed.

The `-c` flag may be given to instruct **fastrm** when it should `chdir(2)`. If the number of files to be unlinked from a directory is at least `I`, then **fastrm** will `chdir` and unlink the files from in the directory. Otherwise, it will build a path relative to its current directory. If `-c` is given without the optional integer `I`, then `-c1` is assumed, which will cause **fastrm** to always use `chdir`. If `-c` is not used at all, then `-c3` is assumed. Use `-c0` to prevent **fastrm** from ever using `chdir(2)`.

There are also `-a` and `-r` options, which do nothing at all except allow you to say `fastrm -usa`, `fastrm -ussr`, or `fastrm -user`. These happen to often be convenient sets of options to use.

`fastrm` exits with a status of 0 if there were no problems or 1 if something went wrong. Attempting to remove a file that does not exist is not considered a problem. If the program exits with a nonzero status, it is probably a good idea to feed the list of files into an `xargs rm` pipeline.

fdformat

`fdformat`—Low-level formats a floppy disk.

SYNOPSIS

```
fdformat [ -n ] device
```

DESCRIPTION

`fdformat` does a low-level format on a floppy disk. `device` is usually one of the following (for floppy devices, the major is 2, and the minor is shown for informational purposes only):

```
/dev/fd0d360 (minor = 4)
/dev/fd0h1200 (minor = 8)
/dev/fd0D360 (minor = 12)
/dev/fd0H360 (minor = 12)
/dev/fd0D720 (minor = 16)
/dev/fd0H720 (minor = 16)
/dev/fd0h360 (minor = 20)
/dev/fd0h720 (minor = 24)
/dev/fd0H1440 (minor = 28)
/dev/fd1d360 (minor = 5)
/dev/fd1h1200 (minor = 9)
/dev/fd1D360 (minor = 13)
/dev/fd1H360 (minor = 13)
/dev/fd1D720 (minor = 17)
/dev/fd1H720 (minor = 17)
/dev/fd1h360 (minor = 21)
/dev/fd1h720 (minor = 25)
/dev/fd1H1440 (minor = 29)
```

The generic floppy devices, `/dev/fd0` and `/dev/fd1`, will fail to work with `fdformat` when a non-standard format is being used or if the format has not been autodetected earlier. In this case, use `setfdprm(8)` to load the disk parameters.

OPTIONS

`-n` No verify. This option will disable the verification that is performed after the format.

SEE ALSO

`fd(4)`, `setfdprm(8)`, `mkfs(8)`, `emkfs(8)`

AUTHOR

Werner Almesberger (almesber@nessie.cs.id.ethz.ch)

Linux 0.99, 1 February 1993

fdisk

`fdisk`—Partition table manipulator for Linux.

SYNOPSIS

```
fdisk [ -l ] [ -v ] [ -s partition ] [ device ]
```

DESCRIPTION

`fdisk` is a menu-driven program for manipulation of the hard disk partition table. The device is usually one of the following:

```
/dev/hda  
/dev/hdb  
/dev/sda  
/dev/sdb
```

The partition is a device name followed by a partition number. For example, `/dev/hda1` is the first partition on the first hard disk in the system.

If possible, `fdisk` will obtain the disk geometry automatically. This is not necessarily the physical disk geometry but is the disk geometry that MS-DOS uses for the partition table. If `fdisk` warns you that you need to set the disk geometry, please believe this statement and set the geometry. This should only be necessary with certain SCSI host adapters (the drivers for which are rapidly being modified to provide geometry information automatically).

Whenever a partition table is printed, a consistency check is performed on the partition table entries. This check verifies that the physical and logical start and end points are identical and that the partition starts and ends on a cylinder boundary (except for the first partition).

Old versions of `fdisk` (all versions prior to 1.1r including 0.93) incorrectly mapped the `cylinder/head/sector` specification onto absolute sectors. This might result in the first partition on a drive failing the consistency check. If you use LILO to boot, this situation can be ignored. However, there are reports that the OS/2 boot manager will not boot a partition with inconsistent data.

Some versions of MS-DOS create a first partition that does not begin on a cylinder boundary but on sector 2 of the first cylinder. Partitions beginning in cylinder 1 cannot begin on a cylinder boundary, but this is unlikely to cause difficulty unless you have OS/2 on your machine.

In version 1.1r, a `BLKRRPART ioctl()` is performed before exiting when the partition table is updated. This is primarily to ensure that removable SCSI disks have their partition table information updated. If the kernel does not update its partition table information, `fdisk` warns you to reboot. If you do not reboot your system after receiving such a warning, you might lose or corrupt the data on the disk. Sometimes `BLKRRPART` fails silently; when installing Linux, you should always reboot after editing the partition table.

DOS 6.X WARNING

The DOS 6.x `FORMAT` command looks for some information in the first sector of the data area of the partition and treats this information as more reliable than the information in the partition table. DOS `FORMAT` expects DOS `FDISK` to clear the first 512 bytes of the data area of a partition whenever a size change occurs. DOS `FORMAT` will look at this extra information even if the `/U` flag is given

We consider this a bug in `DOS FORMAT` and `DOS FDISK`.

The bottom line is that if you use `cfdisk` or `fdisk` to change the size of a DOS partition table entry, then you must also use `dd` to zero the first 512 bytes of that partition before using `DOS FORMAT` to format the partition. For example, if you were using `cfdisk` to make a DOS partition table entry for `/dev/hda1`, then (after exiting `fdisk` or `cfdisk` and rebooting Linux so that the partition table information is valid) you would use the command `dd if=/dev/zero of=/dev/hda1 bs=512 count=1` to zero the first 512 bytes of the partition.

Be extremely careful if you use the `dd` command because a small typo can make all of the data on your disk useless.

For best results, you should always use an OS-specific partition table program. For example, you should make DOS partitions with the `DOS FDISK` program and Linux partitions with the Linux `fdisk` or Linux `cfdisk` program.

OPTIONS

<code>-v</code>	Prints version number of <code>fdisk</code> program.
<code>-l</code>	Lists the partition tables for <code>/dev/hda</code> , <code>/dev/hdb</code> , <code>/dev/sda</code> , <code>/dev/sdb</code> , <code>/dev/sdc</code> , <code>/dev/sdd</code> , <code>/dev/sde</code> , <code>/dev/sdf</code> , <code>/dev/sdg</code> , and <code>/dev/sdh</code> and then exits.
<code>-s partition</code>	If the partition is not a DOS partition (the partition ID is greater than 10), then the size of that partition is printed on the standard output. This value is usually used as an argument to the <code>mkfs(8)</code> program to specify the size of the partition that will be formatted.

BUGS

Although this man page (written by `faith@cs.unc.edu`) is poor, there is excellent documentation in the `README.fdisk` file (written by `LeBlanc@mcc.ac.uk`) that should always be with the `fdisk` distribution. If you cannot find this file in the `util-linux-*` directory or with the `fdisk.c` source file, then you should write to the distributor of your version of `fdisk` and complain that you do not have all of the available documentation.

AUTHOR

A.V. LeBlanc (`LeBlanc@mcc.ac.uk`). v1.0r: SCSI and `extfs` support added by Rik Faith (`faith@cs.unc.edu`). v1.1r: Bug fixes and enhancements by Rik Faith (`faith@cs.unc.edu`), with special thanks to Michael Bischoff (`i1041905@ws.rz.tu-bs.de` or `mbi@mo.math.nat.tu-bs.de`). v1.3: Latest enhancements and bug fixes by A.V. LeBlanc, including the addition of the `-s` option. v2.0: Disks larger than 2GB are now fully supported, thanks to Remy Card's `llseek` support.

Linux 1.0, 3 June 1995

filechan

`filechan`—File-writing back end for InterNetNews.

SYNOPSIS

```
filechan [ -d directory ] [-f fields ] [-m mapfile ] [-p pidfile ]
```

DESCRIPTION

`filechan` reads lines from standard input and copies certain fields in each line into files named by other fields within the line. `filechan` is intended to be called by `innd(8)` as a channel feed. (It is not a full exploder and does not accept commands; see `newsfeeds(5)` for a description of the difference and `buffchan(8)` for an exploder program.)

`filechan` input is interpreted as a set of lines. Each line contains a fixed number of initial fields, followed by a variable number of filename fields. All fields in a line are separated by whitespace. The default number of initial fields is one; the `-f` flag may be used to specify a different number of fields.

For each line of input, `filechan` writes the initial fields, separated by whitespace and followed by a newline, to each of the files named in the `filename` fields. When writing to a file, `filechan` opens it in append mode and tries to lock it and change the ownership to the user and group who owns the directory where the file is being written.

By default, `filechan` writes its arguments into the directory `/news/spool/out.going`. The `-d` flag may be used to specify a directory the program should change to before starting.

If the `-p` flag is used, the program will write a line containing its process ID (in text) to the specified file.

If `filechan` is invoked with `-f 2` and given the following input:

```
news/software/b/132 <1643@munnnari.oz.au>foo uunet
news/software/b/133 <102060@litchi.foo.com> uunet munnnari
comp/sources/unix/2002 <999@news.foo.com>foo uunet munnnari
```

Then the file `foo` will have these lines:

```
news/software/b/132 <1643@munnnari.oz.au>
comp/sources/unix/2002 <999@news.foo.com>
```

The file `munnnari` will have these lines:

```
news/software/b/133 <102060@litchi.foo.com>
comp/sources/unix/2002 <999@news.foo.com>
```

The file `uunet` will have these lines:

```
news/software/b/132 <1643@munnnari.oz.au>
news/software/b/133 <102060@litchi.foo.com>
comp/sources/unix/2002 <999@news.foo.com>
```

Because the time window in which a file is open is very small, complicated flushing and locking protocols are not needed; a `mv(1)` followed by a `sleep(1)` for a couple of seconds is sufficient.

A map file may be specified by using the `-m` flag. Blank lines and lines starting with a number sign (`#`) are ignored. All other lines should have two hostnames separated by a colon. The first field is the name that may appear in the input stream; the second field names the file to be used when the name in the first field appears. For example, the following map file may be used to map the short names to the full domain names:

```
# This is a comment uunet:news.uu.net foo:foo.com munnnari:munnnari.oz.au
```

HISTORY

Written by Robert Elz (`kre@munnnari.oz.au`); flags added by Rich \$alz (`rsalz@uunet.uu.net`).

SEE ALSO

`buffchan(8)`, `innd(8)`, `newsfeeds(5)`

fsck

`fsck`—Check and repair a Linux filesystem.

SYNOPSIS

```
fsck [ -AVRTN ][-s ][-t fstype ][fs-options ] filesys [ ... ]
```

DESCRIPTION

`fscck` is used to check and optionally repair a Linux filesystem. `filesys` is either the device name (such as `/dev/hda1` or `/dev/sdb2`) or the mount point (such as `/`, `/usr`, or `/home`) for the filesystem. If this `fscck` has several filesystems on different physical disk drives to check, this `fscck` will try to run them in parallel. This reduces the total amount time it takes to check all of the filesystems because `fscck` takes advantage of the parallelism of multiple disk spindles.

The exit code returned by `fscck` is the sum of the following conditions:

0	No errors
1	Filesystem errors corrected
2	System should be rebooted
4	Filesystem errors left uncorrected
8	Operational error
16	Usage or syntax error
128	Shared library error

The exit code returned when all filesystems are checked using the `-A` option is the bitwise OR of the exit codes for each file system that is checked.

In actuality, `fscck` is simply a front end for the various filesystem checkers (`fscck.filesys`) available under Linux. The filesystem-specific checker is searched for in `/sbin` first, then in `/etc/fs` and `/etc`, and finally in the directories listed in the `PATH` environment variable. Please see the filesystem-specific checker manual pages for further details.

OPTIONS

-A	Walk through the <code>/etc/fstab</code> file and try to check all filesystems in one run. This option is typically used from the <code>/etc/rc</code> system initialization file, instead of multiple commands for checking a single file system.
-R	When checking all filesystems with the <code>-A</code> flag, skip the root file system (in case it's already mounted read-write).
-T	Don't show the title on startup.
-N	Don't execute; just show what would be done.
-s	Serialize <code>fscck</code> operations. This is a good idea if you checking multiple filesystems in and the checkers are in an interactive mode. (Note: <code>e2fscck</code> runs in an interactive mode by default. To make <code>e2fscck</code> run in a non-interactive mode, you must either specify the <code>-p</code> or <code>-a</code> option, if you want errors to be corrected automatically, or the <code>-n</code> option if you do not.)
-V	Produce verbose output, including all filesystem-specific commands that are executed.
-tfstype	Specifies the type of filesystem to be checked. When the <code>-A</code> flag is specified, only filesystems that match <code>fstype</code> are checked. If <code>fstype</code> is prefixed with <code>no</code> , only filesystems whose filesystem do not match <code>fstype</code> are checked. Usually, the filesystem type is deduced by searching for <code>filesys</code> in the <code>/etc/fstab</code> file and using the corresponding entry. If the type can not be deduced, <code>fscck</code> will use the type specified by the <code>-t</code> option if it specifies a unique filesystem type. If this type is not available, the the default filesystem type (currently <code>ext2</code>) is used.
fs-options	Any options that are not understood by <code>fscck</code> , or that follow the <code>-</code> option are treated as filesystem-specific options to be passed to the filesystem-specific checker.

Currently, standardized filesystem-specific options are somewhat in flux. Although not guaranteed, the following options are supported by most filesystem checkers:

- a Automatically repair the filesystem without any questions. (Use this option with caution.) Note that `e2fsck` supports `-a` for backwards compatibility only. This option is mapped to `e2fsck`'s `-p` option, which is safe to use, unlike the `-a` option that most filesystem checkers support.
- r Interactively repair the filesystem (ask for confirmations). Note: It is generally a bad idea to use this option if multiple `fsck`'s are run in parallel. Also note that this is `e2fsck` default behavior; it supports this option for backwards compatibility reasons only.

AUTHOR

Theodore Ts'o (tytso@mit.edu)

The manual page was shamelessly adapted from David Engel and Fred van Kempen's generic `fsck` front-end program, which in turn was shamelessly adapted from Remy Card's version for the `ext2` filesystem.

FILES

`/etc/fstab`

SEE ALSO

`fstab(5)`, `mkfs(8)`, `fsck.minix(8)`, `fsck.ext2(8)` or `e2fsck(8)`, `fsck.xiafs(8)`

Version 0.5b, November 1994

fsck.minix

`fsck.minix`—A filesystem consistency checker for Linux.

SYNOPSIS

```
fsck.minix [ -larvsmf ] device
```

DESCRIPTION

`fsck.minix` performs a consistency check for the Linux MINIX filesystem. The current version supports the 14 character and 30 character filename options.

The program assumes the filesystem is quiescent. `fsck.minix` should not be used on a mounted device unless you can be sure nobody is writing to it (and remember that the kernel can write to it when it searches for files).

The device will usually have the following form:

```
/dev/hda[1-8]
/dev/hdb[1-8]
/dev/sda[1-8]
/dev/sdb[1-8]
```

If the filesystem was changed (that is, repaired), then `fsck.minix` will print `File system has changed` and will `sync(2)` three times before exiting. Because Linux does not currently have raw devices, there is no need to reboot at this time (versus a system that does have raw devices).

WARNING

`fsck.minix` should not be used on a mounted filesystem. Using `fsck.minix` on a mounted filesystem is very dangerous due to the possibility that deleted files are still in use and can seriously damage a perfectly good filesystem! If you absolutely have to run `fsck.minix` on a mounted filesystem (that is, the root filesystem), make sure nothing is writing to the disk and that no files are “zombies” waiting for deletion.

OPTIONS

-l	Lists all filenames.
-r	Performs interactive repairs.
-a	Performs automatic repairs (this option implies -r) and serves to answer all of the questions asked with the default. Note that this can be extremely dangerous in the case of extensive filesystem damage.
-v	Verbose.
-s	Outputs super-block information.
-m	Activates MINIX-like “mode not cleared” warnings.
-f	Force filesystem check even if the filesystem was marked as valid. (This marking is done by the kernel when the filesystem is unmounted.)

SEE ALSO

`fsck(8)`, `fsck.ext(8)`, `fsck.ext2(8)`, `fsck.xiafs(8)`, `mkfs(8)`, `mkfs.minix(8)`, `mkfs.ext(8)`, `mkfs.ext2(8)`, `mkfs.xiafs(8)`, `reboot(8)`

DIAGNOSTICS

There are numerous diagnostic messages. The ones mentioned here are the most commonly seen in normal usage.

If the device does not exist, `fsck.minix` will print `Unable to read super block`. If the device exists but is not a MINIX filesystem, `fsck.minix` will print `Bad magic number in super-block`.

EXIT CODES

The exit code returned by `fsck.minix` is the sum of the following:

0	No errors.
3	Filesystem errors corrected; system should be rebooted if filesystem was mounted.
4	Filesystem errors left uncorrected.
8	Operational error.
16	Usage or syntax error.

In point of fact, only 0, 3, 4, 7, 8, and 16 can ever be returned.

AUTHOR

Linus Torvalds (torvalds@cs.helsinki.fi). Error code values by Rik Faith (faith@cs.unc.edu). Added support for filesystem valid flag: Dr. Wettstein (greg@wind.uucp@plains.nodak.edu). Check to prevent `fsck` of mounted filesystem added by Daniel Quinlan (quinlan@yggdrasil.com).

Linux 0.99, 10 January 1994

ftpd

ftpd—DARPA Internet File Transfer Protocol server.

SYNOPSIS

```
ftpd [-d] [-l] [-t timeout] [-T maxtimeout]
```

DESCRIPTION

ftpd is the DARPA Internet File Transfer Protocol server process. The server uses the TCP protocol and listens at the port specified in the FTP service specification; see `services(5)`.

Available options:

- d Debugging information is written to the syslog.
- l Each FTP 1 session is logged in the syslog.
- t The inactivity timeout period is set to timeout seconds. (The default is 15 minutes.)
- T A client can also request a different timeout period; the maximum period allowed can be set to timeout seconds with the -T option. The default limit is 2 hours.

The FTP server currently supports the following FTP requests; case is not distinguished.

<i>Request</i>	<i>Description</i>
ABOR	Abort previous command
ACCT	Specify account (ignored)
ALLO	Allocate storage (vacuously)
APPE	Append to a file
CDUP	Change to parent of current working directory
CWD	Change working directory
DELE	Delete a file
HELP	Give help information
LIST	Give list files in a directory (``ls -lgA ``)
MKD	Make a directory
MDTM	Show last modification time of file
MODE	Specify data transfer mode
NLST	Give name list of files in directory
NOOP	Do nothing
PASS	Specify password
PASV	Prepare for server-to-server transfer
PORT	Specify data connection port
PWD	Print the current working directory
QUIT	Terminate session
REST	Restart incomplete transfer
RETR	Retrieve a file
RMD	Remove a directory
RNFR	Specify rename-from filename
RNTO	Specify rename-to filename
SITE	Nonstandard commands (see next section)
SIZE	Return size of file
STAT	Return status of server
STOR	Store a file
STOU	Store a file with a unique name
STRU	Specify data transfer structure
SYST	show operating system type of server system
TYPE	specify data transfer type
USER	specify username
XCUP	change to parent of current working directory (deprecated)

<i>Request</i>	<i>Description</i>
XCWD	change working directory (deprecated)
XMKD	make a directory (deprecated)
XPWD	print the current working directory (deprecated)
XRMD	remove a directory (deprecated)

The following non-standard or UNIX-specific commands are supported by the SITE request:

<i>Request</i>	<i>Description</i>	<i>Example</i>
UMASK	Change umask	SITE UMASK 002
IDLE	Set idle timer	SITE IDLE 60
CHMOD	Change mode of a file	SITE CHMOD 755
HELP	Give help information	SITE HELP

The remaining FTP requests specified in Internet RFC 959 are recognized but not implemented. MDTM and SIZE are not specified in RFC 959 but will appear in the next updated FTP RFC.

The FTP server will abort an active file transfer only when the ABOR command is preceded by a Telnet “Interrupt Process” (IP) signal and a Telnet “Synch” signal in the command Telnet stream, as described in Internet RFC 959. If a STAT command is received during a data transfer, preceded by a Telnet IP and Synch, transfer status will be returned.

ftpd interprets filenames according to the globbing conventions used by csh(1). This allows users to utilize the metacharacters `Li &*[.]`.

ftpd authenticates users according to four rules:

- The username must be in the password database and not have a null password. In this case, a password must be provided by the client before any file operations may be performed.

- The username must not appear in the file (see ftpusers(5)).

- The user must have a standard shell returned by getusershell(3).

- If the username is anonymous or FTP, an anonymous FTP account must be present in the password file (user FTP). In this case, the user is allowed to log in by specifying any password. (By convention, this is given as the client host’s name.)

In the last case, ftpd takes special measures to restrict the client’s access privileges. The server performs a chroot(2) command to the home directory of the FTP user. So that system security is not breached, it is recommended that the FTP subtree be constructed with care; the following rules are recommended:

<code>~ftp</code>	Make the home directory owned by root and unwritable by anyone.
<code>~ftp/bin</code>	Make this directory owned by root and unwritable by anyone. The program <code>ls(1)</code> must be present to support the <code>list</code> command. This program should have mode <code>111</code> .
<code>~ftp/etc</code>	Make this directory owned by root and unwritable by anyone. The files <code>passwd(5)</code> and <code>group(5)</code> must be present for the <code>ls</code> command to be able to produce owner names rather than numbers. The password field in <code>passwd</code> is not used and should not contain real encrypted passwords. These files should be mode <code>444</code> and owned by root. Don’t use the system’s <code>/etc/passwd</code> file as the password file or the system’s <code>/etc/group</code> file as the group file in the <code>~ftp/etc</code> directory.
<code>Pa ~ftp/pub</code>	Make this directory mode <code>755</code> and owned by root. Create a subdirectory in <code>~ftp/pub</code> with the appropriate mode (<code>777</code> or <code>733</code>) if you want to allow normal users to upload files.

SEE ALSO

ftp(1), getusershell(3), ftpusers(5), syslogd(8)

BUGS

The anonymous account is inherently dangerous and should avoided when possible.

The server must run as the super-user to create sockets with privileged port numbers. It maintains an effective user ID of the logged-in user, reverting to the super-user only when binding addresses to sockets. The possible security holes have been extensively scrutinized but are possibly incomplete.

HISTORY

The command appeared in BSD 4.2.

BSD 4.2, 16 March 1991

ifconfig

`ifconfig`—Configure a network interface.

SYNOPSIS

```
ifconfig [interface]
ifconfig interface [atype] options | address ...
```

DESCRIPTION

`ifconfig` is used to set up (and maintain thereafter) the kernel-resident network interfaces. It is used at boot time to configure most of them to a running state. After that, it is usually only needed when debugging or when system tuning is needed.

If no arguments are given, `ifconfig` just displays the status of the currently defined interfaces. If the single interface argument is given, it displays the status of the given interface only. Otherwise, it assumes that things have to be set up.

ADDRESS FAMILIES

If the first argument after the interface name is recognized as the name of a supported address family, that address family is used for decoding and displaying all protocol addresses. Currently supported address families include `inet` (TCP/IP, default) and `ax25` (AMPR Packet Radio.)

OPTIONS

<code>interface</code>	The name of the NET interface. This usually is a name such as <code>wd0</code> , <code>s13</code> , or something like that: a device driver name followed by a unit number.
<code>up</code>	This flag causes the interface to be activated. It is implicitly specified if the interface is given a new address (see below).
<code>down</code>	This flag causes the driver for this interface to be shut down and is useful when things start going wrong.
<code>[-]arp</code>	Enable or disable the use of the ARP protocol on this interface. If the minus (–) sign is present, the flag is turned OFF.
<code>[-]trailers</code>	Enable or disable the use of trailers on Ethernet frames. This is not used in the current implementation of NET.
<code>[-]allmulti</code>	Enable or disable the promiscuous mode of the interface. This means that all incoming frames get sent to the network layer of the system kernel, allowing for networking monitoring.
<code>metric N</code>	This parameter sets the interface metric. It is not used at present, but we implement it for the future.
<code>mtu N</code>	This parameter sets the Maximum Transfer Unit (MTU) of an interface. For Ethernet, this is a number in the range of 1000-2000 (default is 1500). For SLIP, use something between 200 and 4096. Note that the current implementation does not handle IP fragmentation yet, so you'd better make the MTU large enough!
<code>dstaddr addr</code>	Set the “other end's” IP address in case of a point-to-point link, such as PPP. This keyword is obsoleted by the new <code>pointopoint</code> keyword.

<code>netmask addr</code>	Set the IP network mask for this interface. This value defaults to the usual class A, B, or C network mask (as deducted from the interface IP address), but it can be set to any value for the use of subnetting.
<code>[-]broadcast [addr]</code>	If the address argument is also given, set the protocol broadcast address for this interface. Otherwise, it only sets the <code>IFF_BROADCAST</code> flag of the interface. If the keyword was preceded by a minus (-) sign, then the flag is cleared instead.
<code>[-]pointopoint [addr]</code>	This keyword enables the point-to-point mode of an interface, meaning that it is a direct link between two machines with nobody else listening on it. (At least we hope that this is the case, grin :-).) If the address argument is also given, set the protocol address of the other side of the link, just like the obsolete <code>dstaddr</code> keyword does. Otherwise, it only sets the <code>IFF_POINTOPOINT</code> flag of the interface. If the keyword was preceded by a minus (-) sign, then the flag is cleared instead.
<code>hw</code>	Set the hardware address of this interface if the device driver supports this operation. The keyword must be followed by the name of the hardware class and the printable ASCII equivalent of the hardware address. Hardware classes currently supported include <code>ether</code> (Ethernet), <code>ax25</code> (AMPR AX.25), and <code>ppp</code> , although the latter is not really supported yet.
<code>address</code>	The hostname or IP address (a hostname will be resolved into an IP address) of that interface. This parameter is required, although the syntax doesn't currently require it.

FILES

`/dev/net/socket`

BUGS

None so far, although the syntax checking could be better.

AUTHOR

Fred N. van Kempen (waltje@uwal.nl, mugnet.org)

6 October 1993

inetd

inetd—Internet superserver.

SYNOPSIS

`inetd [-d] [configuration file]`

DESCRIPTION

`inetd` should be run at boot time by `/etc/rc.local` (see `rc(8)`). It then listens for connections on certain Internet sockets. When a connection is found on one of its sockets, it decides what service the socket corresponds to and invokes a program to service the request. After the program is finished, it continues to listen on the socket (except in some cases, which are described later). Essentially, `inetd` allows running one daemon to invoke several others, reducing load on the system.

The option available for `inetd`:

`-d` Turns on debugging.

Upon execution, `inetd` reads its configuration information from a configuration file, which, by default, is `/etc/inetd.conf`. There must be an entry for each field of the configuration file, with entries for each field separated by a tab or a space. Comments are denoted by a `#` at the beginning of a line. There must be an entry for each field. The fields of the configuration file are as follows:

```

service name
socket type
protocol
wait/nowait[.max]
user[.group]
server program
server program arguments

```

To specify an Sun-RPC based service, the entry would contain these fields:

```

service name/version
socket type
rpc/protocol
wait/nowait[.max]
user[.group]
server program
server program arguments

```

The service-name entry is the name of a valid service in the file `/etc/services`. For internal services, the service name must be the official name of the service (that is, the first entry in `/etc/services`). When used to specify a Sun-RPC based service, this field is a valid RPC service name in the file `/etc/rpc`. The part on the right of the `/` is the RPC version number. This can simply be a single numeric argument or a range of versions. A range is bounded by the low version to the high version - `rusers/1-3`.

The socket type should be one of `stream`, `dgram`, `raw`, `rdm`, or `seqpacket`, depending on whether the socket is a stream, datagram, raw, reliably delivered message, or sequenced packet socket.

The protocol must be a valid protocol as given in `/etc/protocols`. Examples might be `tcp` or `udp`. Rpc-based services are specified with the `rpc/tcp` or `rpc/udp` service type.

The wait/nowait entry is applicable to datagram sockets only. (Other sockets should have a nowait entry in this space.) If a datagram server connects to its peer, freeing the socket so `inetd` can receive further messages on the socket, it is said to be a multithreaded server and should use the nowait entry. For datagram servers that process all incoming datagrams on a socket and eventually time out, the server is said to be single-threaded and should use a wait entry. `Comsat(8)`, `biff(1)`, and `talkd(8)` are examples of the latter type of datagram server. `Tftpd(8)` is an exception; it is a datagram server that establishes pseudo-connections.

It must be listed as wait in order to avoid a race; the server reads the first packet, creates a new socket, and then forks and exits to allow `inetd` to check for new service requests to spawn new servers. The optional `max` suffix (separated from wait or nowait by a dot) specifies the maximum number of server instances that may be spawned from `inetd` within an interval of 60 seconds. When omitted, `max` defaults to 40.

The user entry should contain the username of the user as whom the server should run. This allows for servers to be given less permission than root. An optional group name can be specified by appending a dot to the username followed by the group name. This allows for servers to run with a different (primary) group ID than specified in the password file. If a group is specified and the user is not root, the supplementary groups associated with that user will still be set.

The server-program entry should contain the pathname of the program that is to be executed by `inetd` when a request is found on its socket. If `inetd` provides this service internally, this entry should be `internal`.

The server program arguments should appear just as arguments normally do, starting with `argv[0]`, which is the name of the program. If the service is provided internally, the word `internal` should take the place of this entry.

`inetd` provides several trivial services internally by use of routines within itself. These services are `echo`, `discard`, `chargen` (character generator), `daytime` (human readable time), and `time` (machine readable time in the form of the number of seconds since midnight, January 1, 1900). All of these services are TCP based. For details of these services, consult the appropriate RFC from the Network Information Center.

inetd rereads its configuration file when it receives a hangup signal, SIGHUP. Services may be added, deleted, or modified when the configuration file is reread. inetd creates a file `/etc/inetd.pid` that contains its process identifier.

SEE ALSO

comsat(8), fingerd(8), ftpd(8), rexecd(8), rlogind(8), rshd(8), telnetd(8), tftpd(8)

HISTORY

The command appeared in BSD 4.3. Support for Sun-RPC based services is modeled after that provided by Sun-OS 4.1.

BSD 4.3, 16 March 1991

init, telinit

init, telinit—Process control initialization.

SYNOPSIS

```
/sbin/init [ -t sec ][0123456SsQq ]
/sbin/telinit [ -t sec ][0123456sSQqabc ]
```

DESCRIPTION

init

init is the father of all processes. Its primary role is to create processes from a script stored in the file `/etc/inittab` (see `inittab(5)`). This file usually has entries that cause init to spawn gettys on each line that users can log in. It also controls autonomous processes required by any particular system.

A run level is a software configuration of the system that allows only a selected group of processes to exist. The processes spawned by init for each of these run levels are defined in the `/etc/inittab` file. init can be in one of eight run levels, 06 and S or s. The run level is changed by having a privileged user run `/sbin/telinit`, which sends appropriate signals to init, telling it which run level to change to.

After init is invoked as the last step of the kernel booting, it looks for the file `/etc/inittab` to see if there is an entry of the type `initdefault` (see `inittab(5)`). `initdefault` determines the initial run level of the system. If there is no such entry or no `/etc/inittab` at all, a run level must be entered at the system console.

Run level S or s brings the system to single-user mode and does not require an `/etc/inittab` file. In single-user mode,

`/bin/sh` is invoked on `/dev/console`.

`/dev/console` need not necessarily be the physical system console. When init is told to enter single-user mode or run level 1 (either directly, by `init S`, or by telling shutdown to enter maintenance mode), it will link the terminal line the command was executed from to `/dev/console`. The device `/dev/systty` is called the physical system console and the device `/dev/console` is called the logical system console. If the logical system console is not the physical system console, pressing the combination Ctrl+Alt+Del on the physical system console will force a relink of `/dev/console` to `/dev/systty`. A terminal line can only become the logical console if it's listed in the file `/etc/securetty`. All this is in preparation of the day that the Linux kernel will support serial consoles.

Beware: If you want to run X or anything else that is aware of Virtual Consoles, the logical system console (`/dev/console`) needs to be the same as the physical system console (`/dev/systty`).

When entering single-user mode, init reads the console's `ioctl(2)` states from `/etc/ioctl.save`. If this file does not exist, init initializes the line at 9600 baud and with `LOCAL` settings. When init leaves single-user mode, it stores the console's `ioctl` settings in this file so it can re-use them for the next single-user session. If the logical system console is changed to another terminal line, the settings of the line from which the init or telinit command was given are stored in `/etc/ioctl.save` too, so that the terminal line will be initialized correctly in single-user mode.

When entering a multi-user mode the first time, `init` performs the `boot` and `bootwait` entries to allow filesystems to be mounted before users can log in. Then all entries matching the run level are processed.

Each time a child terminates, `init` records the fact and the reason it died in `/etc/utmp` and `/var/adm/wtmp` if these files exist.

After it has spawned all the processes specified, `init` waits for one of its descendant processes to die, a powerfail signal, or a signal by `/sbin/telinit` to change the system's run level. When one of these three conditions occurs, it re-examines the `/etc/inittab` file. New entries can be added to this file at any time. However, `init` still waits for one of the three conditions to occur. To provide for an instantaneous response, the `Q` or `q` command can wake up `init` to re-examine the `/etc/inittab` file.

If `init` is not in single-user mode and receives a powerfail signal, special powerfail entries are invoked.

When `init` is requested to change the run level, it sends the warning signal `SIGTERM` to all processes that are undefined in the new run level. It then waits 20 seconds before forcibly terminating these processes via the kill signal `SIGKILL`.

Note that `init` assumes that all these processes (and their descendants) remain in the same process group that `init` originally created for them. If any process changes its process group affiliation, it will not receive these signals. Such processes need to be terminated separately.

telinit

`/sbin/telinit` is linked to `/sbin/init`. It takes a one-character argument and signals `init` to perform the appropriate action. The following arguments serve as directives to `/sbin/telinit`:

<code>0, 1, 2, 3, 4, 5, or 6</code>	Tell <code>/sbin/init</code> to switch to the specified run level.
<code>a, b, c</code>	Tell <code>/sbin/init</code> to process only those <code>/etc/inittab</code> file entries having run level <code>a, b, or c</code> .
<code>Q or q</code>	Tell <code>/sbin/init</code> to re-examine the <code>/etc/inittab</code> file.
<code>s or S</code>	Tell <code>/sbin/init</code> to switch to single-user mode.

`/sbin/telinit` can also tell `init` how much time it should wait between sending processes the `TERM` and the `KILL` signal; the default is 20 seconds, but it can be changed by the `-t sec` option.

`/sbin/telinit` can be invoked only by users with appropriate privileges.

RUN LEVELS

Run levels `0, 1, and 6` are reserved. Run level `0` is used to halt the system, run level `6` is used to reboot the system, and run level `1` is used to get the system down into single-user mode. Run level `s` is not really meant to be used directly but should be used by scripts that are executed when entering run level `1`. For more information on this, see the man pages for `shutdown(1)` and `inittab(5)`.

FILES

```
/etc/inittab
/dev/console
/dev/systty
/etc/ioctl.save
/etc/utmp
/var/adm/wtmp
```

CONFORMING TO

`init` is compatible with the System V `init`. The scripts that are used with it, however, are mostly modeled after the BSD startup scripts. There are startup scripts available that let Linux boot more like a System V system, but most people find them too complex.

WARNINGS

`init` assumes that processes and descendants of processes remain in the same process group that was originally created for them. If the processes change their group, `init` can't kill them and you might end up with two processes reading from one terminal line.

DIAGNOSTICS

If `/sbin/init` finds that it is continuously respawning an entry more than ten times in two minutes, it will assume that there is an error in the command string, generate an error message on the system console, and refuse to respawn this entry until either five minutes has elapsed or it receives a signal. This prevents it from eating up system resources when someone makes a typographical error in the `/etc/inittab` file or the program for the entry is removed.

AUTHOR

Miquel van Smoorenburg (miquels@drinkel.nl, mugnet.org); initial manual page by Michael Haardt (u31b3hs@pool.informatik.rwth-aachen.de).

SEE ALSO

`getty(1)`, `login(1)`, `sh(1)`, `who(1)`, `shutdown(1)`, `kill(2)`, `inittab(5)`, `utmp(5)`

19 January 1994

innd, inndstart

innd, inndstart—InterNetNews daemon.

SYNOPSIS

```
innd [ -a ][-c days ][-d ][-f ][-i count ][-o count ][-l size ]
[ -m mode ][-n flag ][ -p port ][-r ][-s ][-S host ][-t timeout ][-u ][-x ]
inndstart [ flags ]
```

DESCRIPTION

innd, the InterNetNews daemon, handles all incoming NNTP feeds. It reads the `active(5)`, `newsfeeds(5)`, and `hosts.nntp(5)` files into memory. It then opens the NNTP port to receive articles from remote sites, a UNIX-domain stream socket to receive articles from local processes such as `nnrpd(8)` and `rnews(1)`, and a UNIX-domain datagram socket for use by `ctlinnd(8)` to direct the server to perform certain actions. It also opens the `history(5)` database and two log files to replace its standard output and standard error. If the `-p` flag is used, then the NNTP port is assumed to be open on the specified descriptor. (If this flag is used, then innd assumes it is running with the proper permissions and it does not call `chown(2)` on any files or directories it creates.)

Once the files and sockets have been opened, innd waits for connections and data to be ready on its ports by using `select(2)` and non-blocking I/O. If no data is available, then it flushes its in-core data structures. The default number of seconds to time out before flushing is 300. This timeout may be changed by using the `-t` flag.

To limit the number of incoming NNTP connections, use the `-i` flag. A value of 0 suppresses this check.

To limit the number of files that are kept open for outgoing file feeds, use the `-o` flag. The default is the number of available descriptors minus some reserved for internal use.

To limit the size of an article, use the `-l` flag. If this flag is used, then any article bigger than `size` bytes is rejected. The default is no checking, which can also be obtained by using a value of 0.

innd rejects articles that are too old. Although this behavior can be controlled by the history database, occasionally a site dumps a batch of very old news back onto the network. Use the `-c` flag to specify a cutoff. For example, `-c21` rejects any articles that were posted more than 21 days ago. A value of 0 suppresses this check.

innd usually puts itself into the background, sets its standard output and error to log files, and disassociates itself from the terminal. Using the `-d` flag instructs the server to not do this, whereas using the `-f` flag just leaves the server running the foreground. The logs are usually buffered; use the `-u` flag to have them unbuffered.

To start the server in a paused or throttled state (see `ctlinnd(8)`) use the `-m` flag to set the initial running mode. The argument should start with a single letter `g`, `p`, or `t` to emulate the `go`, `pause`, or `throttle` commands.

If the `-r` flag is used, the server rennumbers the active file as if a `renumber` command were sent.

If the `-s` flag is used, then `innd` does not do any work but instead just checks the syntax of the `news-feeds` file. It exits with an error status if there are any errors; the actual errors are reported in `syslog(3)`.

If `innd` gets an `NOSPC` error (see `intro(2)`) while trying to write the active file, an article file, or the history database, it sends itself a `throttle` command. This also happens if it gets too many I/O errors while writing to any files.

Any subprocesses spawned by the server get a `nice(2)` value of 10.

The `-n` flag specifies whether pausing or throttling the server should also disable future news-reading processes. A value of `y` makes news readers act as the server, a value of `n` allows news reading even when the server is not running.

If the `-s` flag is used, then `innd` runs in `slave` mode. When running as a slave, the server only accepts articles from the specified host, which must use the `xreplc` protocol extension. Note that either the host must appear in the `hosts.nttp` file or the server must be started with the `-a` flag.

By default, if a host is not mentioned in the `hosts.nttp` file, then the connection is handed off to `nnrpd`. If the `-a` flag is used, then any host can connect and transfer articles.

If the `-x` flag is used, then a `Xref` header is added to all articles even if they are not cross-posted.

`inndstart` is a small front-end program that opens the NNTP port, sets its user ID and group ID to the news maintainer, and then executes `innd` with the `-p` flag and a minimal secure environment. This is a small, easily understood front-end program that can be used if a site does not want to run `innd` with root privileges.

CONTROL MESSAGES

Arriving articles that have a `Control` header or have a `Subject` header that starts with the five characters `cmsg` are called control messages. Except for the cancel message, these messages are implemented by external programs in the `/news/bin/control` directory. (Cancel messages update the history database, so they must be handled internally; the cost of synching, locking, and then unlocking is too high, given the number of cancel messages that are received.)

When a control message arrives, the first word of the text is converted to lowercase and used as the name of the program to execute; if the named program does not exist, then a program named `default` is executed.

All control programs are invoked with four parameters. The first is the address of the person who posted the message; this is taken from the `Sender` header. If that header is empty, then it is taken from the `From` header. The second parameter is the address to send replies to; this is taken from the `Reply-To` header. If that header is empty, then the poster's address is used. The third parameter is a name under which the article is filed, relative to the news spool directory. The fourth parameter is the host that sent the article, as specified on the `Path` line.

The distribution of control message is also different from those of standard articles.

Control messages are usually filed in the newsgroup named `control`. They can be filed in subgroups, however, based on the control message command. For example, a `newgroup` message is filed in `control.newgroup` if that group exists, otherwise it will be filed in `control`.

Sites may explicitly have the “control” newsgroup in their subscription list, although it is usually best to exclude it. If a control message is posted to a group whose name ends with the four characters `.ctl`, then the suffix is stripped off and what is left is used as the group name. For example, a cancel message posted to `news.admin.ctl` will be sent to all sites that subscribe to `control` or `news.admin.newgroup` and `rmgroup` messages receive additional special treatment. If the message is approved and posted to the name of the group being created or removed, then the message is sent to all sites whose subscription patterns would cause them to receive articles posted in that group.

If an article is posted to a newsgroup that starts with the three letters `to.`, it gets special treatment if the newsgroup does not exist in the active file. The article is filed into the newsgroup `to` and it is sent to the first site named after the prefix. For example, a posting to `to.uunet` is filed in `to` and sent to the site `uunet`.

PROTOCOL DIFFERENCES

`innd` implements the NNTP commands defined in RFC 977 with the following differences:

- The `list` may be followed by an optional `active`, `active.times`, or `newsgroups` argument. This common extension is not fully supported; see `nnrpd(8)`.
- The `authinfo user` and `authinfo pass` commands are implemented. These are based on the reference UNIX implementation; no other documentation is available.
- A new command, `mode reader`, is provided. This command causes the server to pass the connection on to `nnrpd`. The command `mode query` is intended for future use and is currently treated the same way.
- A new command, `xreplic news.group:art[,news.group:art]`, is provided. This is similar to the `ihave` command (the same reply codes are used) except for the data that follows the command word. The data consists of entries separated by a single comma. Each entry consists of a newsgroup name, a colon, and an article number. Once processed, the article is filed in the newsgroup and article numbers specified in the command.
- A new command, `xpath messageid`, is provided. The server responds with a 223 response and a space-separated list of filenames where the article was filed.
- The only other commands implemented are `head`, `help`, `ihave`, `quit`, and `stat`.

HEADER MODIFICATIONS

`innd` modifies as few article headers as possible, although it could be better in this area.

The following headers, if present, are removed:

- Date-Received
- Posted
- Posting-Version
- Received
- Relay-Version

Empty headers and headers that consist of nothing but whitespace are also dropped.

The local site's name and an exclamation point are prepended to the Path header.

The Xref header is removed. If the article is cross-posted, a new header is generated.

The Lines header is added if it is missing.

`innd` does not rewrite incorrect headers. For example, it does not replace an incorrect Lines header but rejects the article.

LOGGING

`innd` reports all incoming articles in its log file. This is a text file with a variable number of space-separated fields in one of the following formats:

```
mon dd hh:mm:ss.mmm + feed <Message-ID>site...
mon dd hh:mm:ss.mmm j feed <Message-ID> site...
mon dd hh:mm:ss.mmm c feed <Message-ID> site...
mon dd hh:mm:ss.mmm - feed <Message-ID> reason...
```

The first three fields are the date and time to millisecond resolution. The fifth field is the site that sent the article (based on the Path header), and the sixth field is the article's Message-ID; they will contain a question mark if the information is not available.

The fourth field indicates whether the article was accepted. If it is a plus sign, the article was accepted. If it is the letter `j`, the article was accepted, but all of newsgroups have a `j` in their active field, so the article was filed into the “junk” newsgroup. If the fourth field is the letter `c`, a cancel message was accepted before the original article arrived. In all three cases, the article has been accepted and the `site...` field contains the space-separated list of sites to which the article is sent.

If the fourth field is a minus sign, the article was rejected. The reasons for rejection include

- %s header too long
- %s wants to cancel <%s> by %s
- Article exceeds local limit of %s bytes
- Article posted in the future—%s

Bad %s header
 Can't write history
 Duplicate
 Duplicate %s header
 EOF in headers
 Linecount %s != %s +- %s
 Missing %s header
 No body
 No colon-space in %s header
 No space
 Space before colon in %s header
 Too old—%s
 Unapproved for %s
 Unwanted newsgroup %s
 Unwanted distribution %s
 Whitespace in “Newsgroups” header—%s

Where %s, above, is replaced by more specific information.

Note that if an article is accepted and none of the newsgroups are valid, it is logged with both two lines, a j line and a minus sign line.

innnd also makes extensive reports through syslog. The first word of the log message is the name of the site if the entry is site-specific (such as a connected message). The first word is ME if the message relates to the server itself, such as when a read error occurs.

If the second word is the four letters cant, an error is being reported. In this case, the next two words generally name the system call or library routine that failed and the object upon which the action was performed. The rest of the line might contain other information.

In other cases, the second word attempts to summarize what change has been made, and the rest of the line gives more specific information. The word internal generally indicates an internal logic error.

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for InterNetNews.

SEE ALSO

active(5), ctlinnd(8), dbz(3z), history(5), hosts.nttp(5), inn.conf(5), newsfeeds(5), nnrpd(8), rnews(1), syslog(8)

innxmit

innxmit—Send Usenet articles to a remote NNTP server.

SYNOPSIS

```
innxmit [ -A alt_spool ][-a ][-d ][-M ][-r ][-t timeout ]
        [-T timeout ][-p ][-S ] host file
```

DESCRIPTION

innxmit connects to the NNTP server at the specified host and sends it the articles specified in the batchfile named file. It is usually invoked by a script run out of cron(8) that uses shlock(1) to lock the hostname, followed by actlinnd(8) command to flush the batchfile.

`innxmit` usually blocks until the connection is made. To specify a timeout on how long to try to make the connection, use the `-t` flag. To specify the total amount of time that should be allowed for article transfers, use the `-T` flag. The default is to wait until an I/O error occurs or all the articles have been transferred. If the `-T` flag is used, the time is checked just before an article is started; it does not abort a transfer that is in progress. Both values are measured in seconds.

If the file is not an absolute pathname, it is taken relative to the `/news/spool/out.going` directory. It is usually written by specifying the `Wnn` flags in the `newsfeeds(5)` file. Each line in the batchfile should be in one of the following formats:

```
filename Message-ID
filename
```

The `filename` field names the article to be sent. If it is not an absolute pathname, it is taken relative to the news spool directory, `/news/spool`. If the `Message-ID` field is not specified, it is obtained by scanning the article. The `filename` and `Message-ID` fields are separated by a space.

If a communication error such as a `write(2)` failure occurs, `innxmit` stops sending and rewrites the batchfile to contain the current article and any other unsent articles.

If the remote server sends an unexpected reply code, `innxmit` requeues the article and proceeds. Use the `-r` flag if the article should not be requeued.

Upon exit, `innxmit` reports transfer and CPU usage statistics via `syslog(3)`. If the `-v` flag is used, they are also printed on the standard output. If all articles were sent successfully, `innxmit` removes the batchfile; otherwise, it rewrites it to contain the list of unsent articles. If no articles were sent or rejected, the file is left untouched. This can cause the batchfile to grow excessively large if many articles have been expired and there are communication problems. To always rewrite the batchfile, use the `-a` flag. If the `-p` flag is given, then no connection is made and the batchfile is purged of entries that refer to files that no longer exist. This implies the `-a` flag.

If the `-s` flag is given, then `innxmit` offers articles to the specified host using the `xreplic` protocol extension described in `innd(8)`. To use this flag, the input file must contain the history data (commas are transliterated to spaces by the server). For this flag to be used, the input must contain the necessary history entries. This is usually done by setting up a `Wnn` entry in the `newsfeeds` file.

Use the `-d` flag to print debugging information on standard error. This shows the protocol transactions between `innxmit` and the NNTP server on the remote host.

If the `-M` flag is used, `innxmit` scans an article's headers before sending it. If the article appears to be a MIME article that is not in seven-bit format, the article is sent in "quoted-printable" form.

The `-A` flag may be used to specify an alternate spool directory to use if the article is not found; this is usually an NFS-mounted spool directory of a master server with longer expiration times.

HISTORY

Written by Rich Salz (`rsalz@uunet.uu.net`) for InterNetNews.

SEE ALSO

`ctlinnd(8)`, `innd(8)`, `newsfeeds(5)`, `shlock(1)`

ipcrm

`ipcrm`—Remove ipc facilities.

SYNOPSIS

```
ipcrm [ shm | msg | sem ] id
```

DESCRIPTION

`ipcrm` removes the resource specified by `id`.

SEE ALSO

`ipcs(8)`

AUTHOR

Krishna Balasubramanian (balasub@cis.ohio-state.edu)

Linux 0.99, 9 October 1993

ipcs

`ipcs`—Provide information on ipc facilities.

SYNOPSIS

```
ipcs [ -asmq ] [ -tclup ]
ipcs [ -smq ] -i id
ipcs -h
```

DESCRIPTION

`ipcs` provides information on the ipc facilities for which the calling process has read access.The `-i` option allows a specific resource `id` to be specified. Only information on this `id` is printed.

Resources may be specified as follows:

<code>-m</code>	Shared memory segments
<code>-q</code>	Message queues
<code>-s</code>	Semaphore arrays
<code>-a</code>	All (this is the default)

The output format may be specified as follows:

<code>-t</code>	Time
<code>-p</code>	PID
<code>-c</code>	Creator
<code>-l</code>	Limits
<code>-u</code>	Summary

SEE ALSO

`ipcrm(8)`

AUTHOR

Krishna Balasubramanian (balasub@cis.ohio-state.edu)

Linux 0.99, 9 October 1993

kbdrate

`kbdrate`—Reset the keyboard repeat rate and delay time.

SYNOPSIS

```
kbdrate [ -s ] [ -r rate ] [ -d delay ]
```

DESCRIPTION

`kbdrate` is used to change the IBM keyboard repeat rate and delay time. The delay is the amount of time that a key must be pressed before it starts to repeat. Using `kbdrate` without any options resets the rate to 10.9 characters per second (cps) and the delay to 250 milliseconds (ms). These are the IBM defaults.

OPTIONS

- s Silent. No messages are printed.
- r *rate* Change the keyboard repeat rate to *rate* cps. The allowable range is from 2.0 to 30.0 cps. Only certain specific values are possible, and the program selects the nearest possible value to the one specified. The possible values are given, in characters per second, as follows: 2.0, 2.1, 2.3, 2.5, 2.7, 3.0, 3.3, 3.7, 4.0, 4.3, 4.6, 5.0, 5.5, 6.0, 6.7, 7.5, 8.0, 8.6, 9.2, 10.0, 10.9, 12.0, 13.3, 15.0, 16.0, 17.1, 18.5, 20.0, 21.8, 24.0, 26.7, 30.0.
- d *delay* Change the delay to *delay* milliseconds. The allowable range is from 250 to 1000 ms, but the only possible values (based on hardware restrictions) are 250 ms, 500 ms, 750 ms, and 1000 ms.

BUGS

Not all keyboards support all rates.

Not all keyboards have the rates mapped in the same way.

Setting the repeat rate on the Gateway AnyKey keyboard does not work. If someone with a Gateway figures out how to program the keyboard, please send mail to faith@cs.unc.edu.

FILES

/etc/rc.local
/dev/port

AUTHOR

Rik Faith (faith@cs.unc.edu)

Linux 1.1.19, 22 June 1994

klogd

`klogd`—Kernel log daemon.

SYNOPSIS

```
klogd -c [n] -d -f [fname] -os
```

DESCRIPTION

`klogd` is a system daemon that intercepts and logs Linux kernel messages.

OPTIONS

- c Sets the default log level of console messages to [n].
- d Enables debugging mode. This will generate a lot of output to `stderr`.
- f Logs messages to the specified filename rather than to the `syslog` facility.
- o Execute in one-shot mode. This causes `klogd` to read and log all the messages that are found in the kernel message buffers. After a single read and log cycle, the daemon exits.
- s Force `klogd` to use the system call interface to the kernel message buffers.

OVERVIEW

The functionality of `klogd` has been typically incorporated into other versions of `syslogd`, but this seems to be a poor place for it. In the modern Linux kernel, a number of kernel messaging issues such as sourcing and prioritization must be addressed. Incorporating kernel logging into a separate process appears to offer a cleaner separation of services.

In Linux, there are two potential sources of kernel log information: the `/proc` filesystem and the `syscall` (`sys_syslog`) interface, although ultimately they are one and the same. `klogd` is designed to choose whichever source of information is the most appropriate. It does this by first checking for the presence of a mounted `/proc` filesystem. If this is found, the `/proc/kmsg` file is used as the source of kernel log information. If the `proc` filesystem is not mounted, `klogd` uses a system call to obtain kernel messages. The command-line switch (`-s`) can be used to force `klogd` to use the system call interface as its messaging source.

If kernel messages are directed through the `syslogd` daemon, the `klogd` daemon, as of version 1.1, has the ability to properly prioritize kernel messages. Prioritization of the kernel messages was added at approximately the `p113` level of the kernel. The raw kernel messages are of the form:

```
<[0-7]>Something said by the kernel.
```

The priority of the kernel message is encoded as a single numeric digit enclosed inside the `<>` pair. The definitions of these values is given in the kernel include file `kernel.h`. When a message is received from the kernel, the `klogd` daemon reads this priority level and assigns the appropriate priority level to the `syslog` message. If file output (`-f`) is used, the prioritization sequence is left prepended to the kernel message.

The `klogd` daemon also allows the ability to alter the presentation of kernel messages to the system console. Consequent with the prioritization of kernel messages was the inclusion of default messaging levels for the kernel. In a stock kernel, the default console log level is set to 7. Any messages with a priority level numerically lower than 7 (higher priority) appear on the console.

Messages of priority level 7 are considered to be debug messages and do not appear on the console. Many administrators, particularly in a multi-user environment, prefer that all kernel messages be handled by `klogd` and either directed to a file or to the `syslogd` daemon. This prevents nuisance messages such as line printer out of paper or disk change detected from cluttering the console.

By default, the `klogd` daemon executes a system call to inhibit all kernel messages (except for panics) from being displayed on the console. The `-c` switch can be used to alter this behavior. The argument given to the `-c` switch specifies the priority level of messages that are directed to the console. Note that messages of a priority value lower than the indicated number are directed to the console.

For example, to have the kernel display all messages with a priority level of 3 (`KERN_ERR`) or more severe, the following command is executed:

```
klogd -c 4
```

The definitions of the numeric values for kernel messages are given in the file `kernel.h`, which can be found in the `/usr/include/linux` directory if the kernel sources are installed. These values parallel the `syslog` priority values, which are defined in the file `syslog.h`, found in the `/usr/include/sys` subdirectory.

The `klogd` daemon can also be used in a one-shot mode for reading the kernel message buffers. One-shot mode is selected by specifying the `-o` switch on the command line. Output is directed to either the `syslogd` daemon or to an alternate file specified by the `-f` switch.

For example, to read all the kernel messages after a system boot and record them in a file called `krrn1.msg`, the following command is given:

```
klogd -o -f ./krrn1.msg
```

SIGNAL HANDLING

The `klogd` daemon responds to six signals: `SIGHUP`, `SIGINT`, `SIGKILL`, `SIGTERM`, `SIGTSTP`, and `SIGCONT`. The `SIGINT`, `SIGKILL`, `SIGTERM`, and `SIGHUP` signals cause the daemon to close its kernel log sources and terminate gracefully.

The SIGTSTP and SIGCONT signals are used to start and stop kernel logging. Upon receipt of a SIGTSTP signal, the daemon closes its log sources and spins in an idle loop. Subsequent receipt of a SIGCONT signal causes the daemon to go through its initialization sequence and rechoose an input source. Using SIGTSTP and SIGCONT in combination, the kernel log input can be rechosen without stopping and restarting the daemon. For example, if the /proc filesystem is to be unmounted, the following command sequence should be used:

```
# kill -TSTP pid
# umount /proc
# kill -CONT pid
```

Notations will be made in the system logs with LOG INFO priority documenting the start/stop of logging.

FILES

/proc/kmsg

BUGS

Probably numerous. Well-formed context diffs appreciated.

AUTHOR

Dr. Greg Wettstein (greg%wind.uucp@plains.nodak.edu), Enjellic Systems Development, Oncology Research Division Computing Facility, Roger Maris Cancer Center, Fargo, ND 58122.

Version 1.1, 28 January 1994

lpc

lpc—Line printer control program.

SYNOPSIS

```
lpc [command [argument ...]]
```

DESCRIPTION

lpc is used by the system administrator to control the operation of the line printer system. For each line printer configured in /etc/printcap, lpc may be used to

- Disable or enable a printer
- Disable or enable a printer's spooling queue
- Rearrange the order of jobs in a spooling queue
- Find the status of printers and their associated spooling queues and printer daemons

Without any arguments, lpc prompts for commands from the standard input. If arguments are supplied, lpc interprets the first argument as a command and the remaining arguments as parameters to the command. The standard input may be redirected, causing lpc to read commands from file. Commands may be abbreviated; the following is the list of recognized commands:

```
? [ command ... ]help [ command ... ]
```

Print a short description of each command specified in the argument list or, if no arguments are given, a list of the recognized commands.

```
Ic abort No all - printer
```

Terminate an active spooling daemon on the local host immediately and then disable printing (preventing new daemons from being started by lpr) for the specified printers.

```
clean No all - printer
```

Remove any temporary files, data files, and control files that cannot be printed (that is, they do not form a complete printer job) from the specified printer queues on the local machine.

```
disable No all - printer
```

Turn the specified printer queues off. This prevents new printer jobs from being entered into the queue by lpr.

`lc down No all - printer message ...`

Turn the specified printer queue off, disable printing, and put message in the printer status file. The message doesn't need to be quoted; the remaining arguments are treated like `echo(1)`. This is usually used to take a printer down and let others know why `lpq(1)` indicates the printer is down and print the status message.

`enable No all -- printer`

Enable spooling on the local queue for the listed printers. This allows `lpr(1)` to put new jobs in the spool queue.

`exit, quit`

Exit from `lpc`.

`restart all - printer`

Attempt to start a new printer daemon. This is useful when some abnormal condition causes the daemon to die unexpectedly leaving jobs in the queue. `lpq` reports that there is no daemon present when this condition occurs. If the user is the super-user, try to abort the current daemon first (that is, kill and restart a stuck daemon).

`start all - printer`

Enable printing and start a spooling daemon for the listed printers.

`status No all - printer`

Display the status of daemons and queues on the local machine.

`stop all - printer`

Stop a spooling daemon after the current job completes and disable printing.

`topq printer [ jobnum ... ] [ user ... ]`

Place the jobs in the order listed at the top of the printer queue.

`up all - printer`

Enable everything and start a new printer daemon. Undoes the effects of `down`.

FILES

<code>/etc/printcap</code>	printer description file
<code>/var/spool/*</code>	spool directories
<code>/var/spool/*/lock</code>	lock file for queue control

SEE ALSO

`lpd(8)`, `lpr(1)`, `lpq(1)`, `lprm(1)`, `printcap(5)`

DIAGNOSTICS

?Ambiguous command	Abbreviation matches more than one command.
?Invalid command	No match was found.
?Privileged command	Command can be executed by root only.

HISTORY

The `lpc` command appeared in BSD 4.2.

BSD 4.2, 16 March 1991

lpd

`lpd`—Line printer spooler daemon.

SYNOPSIS

`lpd [-l] [port#]`

DESCRIPTION

`lpd` is the line printer daemon (spool area handler) and is usually invoked at boot time from the `rc(8)` file. It makes a single pass through the `printcap(5)` file to find out about the existing printers and prints any files left after a crash. It then uses the system calls `listen(2)` and `accept(2)` to receive requests to print files in the queue, transfer files to the spooling area, display

the queue, or remove jobs from the queue. In each case, it forks a child to handle the request so the parent can continue to listen for more requests.

Available options:

-l	The -l flag causes lpd to log valid requests received from the network. This can be useful for debugging purposes.
port#	The Internet port number used to rendezvous with other processes is usually obtained with <code>getservbyname(3)</code> but can be changed with the <code>port#</code> argument.

Access control is provided by two means. First, all requests must come from one of the machines listed in the file `/etc/hosts.equiv` or `/etc/hosts.lpd`. Second, if the `rs` capability is specified in the `printcap` entry for the printer being accessed, `lpr` requests are only honored for those users with accounts on the machine with the printer.

The file `minfree` in each spool directory contains the number of disk blocks to leave free so that the line printer queue won't completely fill the disk. The `minfree` file can be edited with your favorite text editor.

The daemon begins processing files after it has successfully set the lock for exclusive access (described later) and scans the spool directory for files beginning with `cf`. Lines in each `cf` file specify files to be printed or non-printing actions to be performed. Each such line begins with a key character to specify what to do with the remainder of the line:

J	Job name. String to be used for the job name on the burst page.
C	Classification. String to be used for the classification line on the burst page.
L	Literal. The line contains identification info from the password file and causes the banner page to be printed.
T	Title. String to be used as the title for <code>pr(1)</code> .
H	Host name. Name of the machine where <code>lpr</code> was invoked.
P	Person. Login name of the person who invoked <code>lpr</code> . This is used to verify ownership by <code>lprm</code> .
M	Send mail to the specified user when the current print job completes.
f	Formatted file. Name of a file to print which is already formatted.
l	Like <code>f</code> but passes control characters and does not make page breaks.
p	Name of a file to print using <code>pr(1)</code> as a filter.
t	Troff file. The file contains <code>troff(1)</code> output (cat phototypesetter commands).
n	Ditroff file. The file contains device independent <code>troff</code> output.
r	DVI file. The file contains Tex <code>l</code> output DVI format from Stanford.
g	Graph file. The file contains data produced by <code>p1ot(3)</code> .
c	Cifplot file. The file contains data produced by <code>cifp1ot</code> .
v	The file contains a raster image.
r	The file contains text data with FORTRAN carriage control characters.
1	Troff font R. Name of the font file to use instead of the default.
2	Troff font I. Name of the font file to use instead of the default.
3	Troff font B. Name of the font file to use instead of the default.
4	Troff font S. Name of the font file to use instead of the default.
W	Width. Changes the page width (in characters) used by <code>pr(1)</code> and the text filters.
I	Indent. The number of characters to indent the output by (in ASCII).
U	Unlink. Name of file to remove upon completion of printing.
N	Filename. The name of the file that is being printed or a blank for the standard input (when <code>lpr</code> is invoked in a pipeline).

If a file cannot be opened, a message is logged via `syslog(3)` using the `LOG_LPR` facility. `lpr` tries up to 20 times to reopen a file it expects to be there, after which it skips the file to be printed.

lpd uses flock(2) to provide exclusive access to the lock file and to prevent multiple daemons from becoming active simultaneously. If the daemon should be killed or die unexpectedly, the lock file need not be removed. The lock file is kept in a readable ASCII form and contains two lines. The first is the process ID of the daemon and the second is the control filename of the current job being printed. The second line is updated to reflect the current status of lpd for the programs lpq(1) and lprm(1).

FILES

/etc/printcap	Printer description file
/var/spool/*	Spool directories
/var/spool/*/minfree	Minimum free space to leave
/dev/lp*	Line printer devices
/dev/printer	Socket for local requests
/etc/hosts.equiv	Lists machine names allowed printer access
/etc/hosts.lpd	Lists machine names allowed printer access but not under same administrative control

SEE ALSO

lpc(8), pac(1), lpr(1), lpq(1), lprm(1), syslog(3), printcap(5)

4.2 BSD Line Printer Spooler Manual

HISTORY

An lpd daemon appeared in Version 6, AT&T UNIX.

BSD 4.2, 16 March 1991

MAKEDEV

MAKEDEV—Creates and maintains filesystem device entries.

SYNOPSIS

```
MAKEDEV [ -vcdnhV ] device or device-group names
```

DESCRIPTION

MAKEDEV is used to maintain the special filesystem entries found in /dev. It creates, or optionally removes, one or more device entries. The names and device numbers are defined in the devinfo file (q.v.); site-specific configuration is found in the file MAKEDEV.cfg. MAKEDEV itself has no knowledge of device information.

OPTIONS

-v	Verbose mode; print out exactly what's being done.
-c	Create; create the specified devices (default).
-d	Delete; remove the specified devices instead of creating them.
-n	Do nothing; only print what would be done. Implies -v as well.
-h	Print a usage message.
-V	Print the version string.

The following targets are special:

update	Run MAKEDEV in update mode. This reads the list of devices currently available from /proc/devices and updates all entries in /dev to match the device numbers found there.

`local` Run `MAKEDEV` to create local devices. This option is obsolete and just prints a warning message. Use `devinfo.local` and `madevdev.cfg` to achieve the same results.

FILES

<code>/etc/devinfo</code>	Device information
<code>/usr/local/etc/devinfo.local</code>	Local device information
<code>/etc/devinfo.local</code>	Alternate location for local device information
<code>/etc/madevdev.cfg</code>	Configuration file
<code>MAKEDEV.cache</code>	Cached data for update
<code>/proc/devices</code>	The kernel's list of current devices

AUTHOR

David A. Holland (dholland@husc.harvard.edu). Based on the older `MAKEDEV` shell script written by Nick Holloway. Additional ideas were contributed by Rik Faith.

NOTES

The LALR(1) parser generator used to build `madevdev.c` from `madevdev.syn` is a commercial product. You won't be able to do a complete rebuild unless you have it.

SEE ALSO

`devinfo(5)`, `madevdev.cfg(5)`

Version 1.5, March 1995

MAKEDEV

MAKEDEV—Creates devices.

SYNOPSIS

```
cd dev; ./MAKEDEV -V
cd dev; ./MAKEDEV [ -n ] [ -v ] update
cd dev; ./MAKEDEV [ -n ] [ -v ] [ -d ] device ...
```

DESCRIPTION

`MAKEDEV` is a script that creates the devices in `/dev` used to interface with drivers in the kernel.

Note that programs giving the error `ENOENT: No such file or directory` usually means that the device file is missing, whereas `ENODEV: No such device` usually means the kernel does not have the driver configured or loaded.

OPTIONS

<code>-v</code>	Print out version (actually RCS version information) and exit.
<code>-n</code>	Do not actually update the devices; just print the actions that would be performed.
<code>-d</code>	Delete the devices. The main use for this flag is by <code>MAKEDEV</code> itself.
<code>-v</code>	Be verbose. Print out the actions as they are performed. This is the same output as produced by <code>-n</code> .

CUSTOMIZATION

Because there is currently no standardization in what names are used for system users and groups, it is possible that you might need to modify `MAKEDEV` to reflect your site's settings. Near the top of the file is a mapping from device type to user, group, and permissions. (For example, all CD-ROM devices are set from the `$cdrom` variable.) If you want to change the defaults, this is the section to edit.

DEVICES

General Options

<code>update</code>	This only works on kernels that have <code>/proc/interrupts</code> (introduced during 1.1.x). This file is scanned to see what devices are currently configured into the kernel, and this is compared with the previous settings stored in the file called <code>DEVICES</code> . Devices that are new since then or have a different major number are created, and those that are no longer configured are deleted.
<code>generic</code>	Create a generic subset of devices. This is the standard devices, plus floppy drives, various hard drives, pseudo-terminals, console devices, basic serial devices, busmice, and printer ports.
<code>%std</code>	Standard devices. These are <code>mem</code> , access to physical memory; <code>kmem</code> , access to kernel virtual memory; <code>null</code> , null device (infinite sink); <code>port</code> , access to I/O ports; <code>zero</code> , null byte source (infinite source); <code>core</code> , symlink to <code>/proc/kcore</code> (for kernel debugging); <code>full</code> , always returns <code>ENOSPACE</code> on write; <code>ram</code> , <code>ramdisk</code> ; <code>tty</code> , to access the controlling <code>tty</code> of a process.
<code>local</code>	This simply runs <code>MAKEDEV.local</code> . This is a script that can create any local devices.

Virtual Terminals

<code>console</code>	This creates the devices associated with the console. This is the virtual terminals <code>ttyx</code> , where <code>x</code> can be from <code>0</code> though <code>63</code> . The device <code>tty0</code> is the currently active vt and is also known as console. For each vt, there are two devices, <code>vcsx</code> and <code>vcsax</code> , which are used to generate screen-dumps of the vt (the <code>vcsx</code> is just the text and <code>vcsax</code> includes the attributes).

Serial Devices

<code>ttyS{0..63}</code>	Serial ports and corresponding dial-out device. For device <code>ttySx</code> , there is also the device <code>cuax</code> , which is used to dial out with. This can avoid the need for cooperative locks in simple situations.
<code>cyclades</code>	Dial-in and dial-out devices for the cyclades intelligent I/O serial card. The dial in device is <code>ttyCx</code> and the corresponding dial-out device is <code>cubx</code> . By default, devices for 7 lines are created, but this can be changed to 15 by removing the comment.

Pseudo Terminals

<code>pty[p-s]</code>	Each possible argument will create a bank of 16 master and slave pairs. The current kernel (1.2) is limited to 64 such pairs. The master pseudo-terminals are <code>pty[p-s][0-9a-f]</code> and the slaves are <code>tty[p-s][0-9a-f]</code> .

Parallel Ports

<code>lp</code>	Standard parallel ports. The devices are created <code>lp0</code> , <code>lp1</code> , and <code>lp2</code> . These correspond to ports at <code>0x3bc</code> , <code>0x378</code> , and <code>0x278</code> . Hence, on some machines, the first printer port may actually be <code>lp1</code> .
<code>par</code>	Alternative to <code>lp</code> . Ports are named <code>parx</code> instead of <code>lpx</code> .

Bus Mice

<code>busmice</code>	The various bus mice devices. This creates the following devices: <code>logimouse</code> (Logitech bus mouse), <code>psmouse</code> (PS/2-style mouse), <code>msmouse</code> (Microsoft Inport bus mouse), <code>atimouse</code> (ATI XL bus mouse) and <code>jmouse</code> (J-mouse).

Joystick Devices

<code>js</code>	Joystick. Creates <code>js0</code> and <code>js1</code> .

Disk Devices

<code>fd[0-7]</code>	Floppy disk devices. The device <code>fdx</code> is the device that autodetects the format, and the additional devices are fixed format (whose size is indicated in the name). The other devices are named as

`fdxLn`. The single letter `L` identifies the type of floppy disk (`d` = 5.25" DD, `h` = 5.25" HD, `o` = 3.5" DD, `h` = 3.5" HD, `e` = 3.5" ED). The number `n` represents the capacity of that format in KB. Thus the standard formats are `fdxd360`, `fdxh1200`, `fdxD720`, `fdxH1440`, and `fdxE2880`.

For more information, see Alain Knaff's `fdutils` package.

Devices `fd0*` through `fd3*` are floppy disks on the first controller, and devices `fd4*` through `fd7*` are floppy disks on the second controller.

`hd[a-d]`

AT hard disks. The device `hdx` provides access to the whole disk, with the partitions being `hdx[0-20]`. The four primary partitions are `hdx1` through `hdx4`, with the logical partitions being numbered from `hdx5` through `hdx20`. (A primary partition can be made into an extended partition, which can hold four logical partitions). By default, only the devices for four logical partitions are made. The others can be made by uncommenting them.

Drives `hda` and `hdb` are the two on the first controller. If using the new IDE driver (rather than the old HD driver), then `hdc` and `hdd` are the two drives on the secondary controller. These devices can also be used to access IDE CD-ROMs if using the new IDE driver.

`xd[a-d]`

XT hard disks. Partitions are the same as IDE disks.

`sd[a-h]`

SCSI hard disks. The partitions are similar to the IDE disks, but there is a limit of 11 logical partitions (`sdx5` through `sdx15`). This is to allow 8 SCSI disks.

`loop`

Loopback disk devices. These allow you to use a regular file as a block device. This means that images of filesystems can be mounted and used as normal. This creates 8 devices `loop0` through `loop7`.

Tape Devices

`st[0-7]`

SCSI tapes. This creates the rewinding tape device `stx` and the non-rewinding tape device `nstx`.

`qic`

QIC-80 tapes. The devices created are `rmt8`, `rmt16`, `tape-d`, and `tape-reset`.

`ftape`

Floppy driver tapes (QIC-117). There are four methods of access depending on the floppy tape drive. For each of the access methods 0, 1, 2, and 3, the devices `rftx` (rewinding) and `nrftx` (non-rewinding) are created. For compatibility, devices `ftape` and `nftape` are symlinks to `rft0` and `nrft0`.

CD-ROM Devices

`scd[0-7]`

SCSI CD players.

`sonycd`

Sony CDU-31A CD player.

`mcd`

Mitsumi CD player.

`cdu535`

Sony CDU-535 CD player.

`lmscd`

LMS/Philips CD player.

`sbpcd{,1,2,3}`

SoundBlaster CD player. The kernel is capable of supporting 16 CD-ROMs, each of which is accessed as `sbpcd[0-9a-f]`. These are assigned in groups of four to each controller. `sbpcd` is a symlink to `sbpcd0`.

Scanner

`logiscan`

Logitech ScanMan32 and ScanMan 256.

`m105scan`

Mustek M105 Handscanner.

`ac4096`

A4Tek Color Handscanner.

Audio

`audio`

This creates the audio devices used by the sound driver. These include `mixer`, `sequencer`, `dsp`, and `audio`.

`pcaudio`

Devices for the PC Speaker sound driver. These are `pcmixer`, `pxsp`, and `pcaudio`.

Miscellaneous

<code>sg</code>	Generic SCSI devices. The devices created are <code>sg0</code> through <code>sg7</code> . These allow arbitrary commands to be sent to any SCSI device. This allows for querying information about the device or controlling SCSI devices that are not one of disk, tape, or CD-ROM (for example, a scanner or writable CD-ROM).
<code>fd</code>	To allow an arbitrary program to be fed input from file descriptor <code>x</code> , use <code>/dev/fd/x</code> as the filename. This also creates <code>BR/dev/stdin</code> , <code>BR/dev/stdout</code> , and <code>BR/dev/stderr</code> . (Note that these are just symlinks into <code>/proc/self/fd</code> .)
<code>ibcs2</code>	Devices (and symlinks) needed by the IBCS2 emulation.
<code>apm</code>	Devices for power management.
<code>dcf</code>	Driver for DCF-77 radio clock.
<code>helloworld</code>	Kernel modules demonstration device. See the modules source.
Network devices	Linux used to have devices in <code>/dev</code> for controlling network devices, but that is no longer the case. To see what network devices are known by the kernel, look at <code>/proc/net/dev</code> .

SEE ALSO

Linux Allocated Devices, maintained by H. Peter Anvin (Peter.Anvin@linux.org)

AUTHOR

Nick Holloway

Linux, 14 August 1994

mke2fs

`mke2fs`—Create a Linux second extended filesystem.

SYNOPSIS

```
mke2fs [ -c | -l filename ] [ -b block-size ] [ -f fragment-size ]
[ -i bytes-per-inode ] [ -m reserved-blocks-percentage ] [ -q ][-v ][-S ]
device [ blocks-count ]
```

DESCRIPTION

`mke2fs` is used to create a Linux second extended filesystem on a device (usually a disk partition). `device` is the special file corresponding to the device (such as `/dev/hdXX`). `blocks-count` is the number of blocks on the device. If omitted, `mke2fs` automatically figures the filesystem size.

OPTIONS

<code>-b block-size</code>	Specify the size of blocks in bytes.
<code>-c</code>	Check the device for bad blocks before creating the filesystem using a fast read-only test.
<code>-f fragment-size</code>	Specify the size of fragments in bytes.
<code>-i bytes-per-inode</code>	Specify the bytes/inode ratio. <code>mke2fs</code> creates an inode for every <code>bytes-per-inode</code> bytes of space on the disk. This value defaults to 4096 bytes. <code>bytes-per-inode</code> must be at least 1024.
<code>-l filename</code>	Read the bad blocks list from <code>filename</code> .
<code>-m reserved- blocks-percentage</code>	Specify the percentage of reserved blocks for the super-user. This value defaults to 5 percent.
<code>-q</code>	Quiet execution. Useful if <code>mke2fs</code> is run in a script.
<code>-v</code>	Verbose execution.

`-s` Write superblock and group descriptors only. This is useful if all the superblock and backup superblocks are corrupted and a last-ditch recovery method is desired. It causes `mke2fs` to reinitialize the superblock and group descriptors while not touching the inode table and the block and inode bitmaps. The `e2fsck` program should be run immediately after this option is used, and there is no guarantee that any data will be salvageable.

AUTHOR

This version of `mke2fs` has been written by Theodore T'so (tytso@mit.edu).

BUGS

`mke2fs` accepts the `-f` option but currently ignores it because the second extended filesystem does not support fragments yet. There may be some other bugs. Please report them to the author.

AVAILABILITY

`mke2fs` is available for anonymous FTP from `ftp.ibp.fr` and `tsx-11.mit.edu` in `/pub/linux/packages/ext2fs`.

SEE ALSO

`badblocks(8)`, `dumpe2fs(8)`, `e2fsck(8)`, `tune2fs(8)`

Version 0.5b, November 1994

mkfs

`mkfs`—Build a Linux filesystem.

SYNOPSIS

```
mkfs [ -V ][-t fstype ][fs-options ] filesystem [ blocks ]
```

DESCRIPTION

`mkfs` is used to build a Linux filesystem on a device, usually a hard disk partition. `filesystem` is either the device name (such as `/dev/hda1`, `/dev/sdb2`) or the mount point (such as `/`, `/usr`, `/home`) for the filesystem. `blocks` is the number of blocks to be used for the filesystem.

The exit code returned by `mkfs` is 0 on success and 1 on failure.

In actuality, `mkfs` is simply a front end for the various filesystem builders (`mkfs.fstype`) available under Linux. The filesystem-specific builder is searched for in `/etc/fs` first, then in `/etc`, and finally in the directories listed in the `PATH` environment variable. Please see the filesystem-specific builder manual pages for further details.

OPTIONS

<code>-V</code>	Produce verbose output, including all filesystem-specific commands that are executed. Specifying this option more than once inhibits execution of any filesystem-specific commands. This is really only useful for testing.
<code>-t fstype</code>	Specifies the type of filesystem to be built. If not specified, the type is deduced by searching for <code>filesystem</code> in <code>/etc/fstab</code> and using the corresponding entry. If the type cannot be deduced, the default filesystem type (currently <code>minix</code>) is used.
<code>fs-options</code>	Filesystem-specific options to be passed to the real filesystem builder. Although not guaranteed, the following options are supported by most filesystem builders.
<code>-c</code>	Check the device for bad blocks before building the filesystem.
<code>-l filename</code>	Read the bad blocks list from <code>filename</code> .
<code>-v</code>	Produce verbose output.

BUGS

All generic options must precede and not be combined with filesystem-specific options. Some filesystem-specific programs do not support the `-v` (verbose) option nor return meaningful exit codes. Also, some filesystem-specific programs do not automatically detect the device size and require the `blocks` parameter to be specified.

AUTHORS

David Engel (david@ods.com), Fred N. van Kempen (waltje@uualt.nl, mugnet.org), and Ron Sommeling (sommel@sci.kun.nl). The manual page was shamelessly adapted from Remy Card's version for the `ext2` filesystem.

SEE ALSO

`fsck(8)`, `mkfs.minix(8)`, `mkfs.ext(8)`, `mkfs.ext2(8)`, `mkfs.xiafs(8)`

Version 1.9, June 1995

mkfs

`mkfs`—Make a Linux MINIX filesystem.

SYNOPSIS

```
mkfs [ -c ] [ -n namelength ] [ -i inodecount ] device size-in-blocks
mkfs [ -l filename ] device size-in-blocks
```

DESCRIPTION

`mkfs` creates a Linux MINIX filesystem on a device (usually a disk partition).

The device is usually of the following form:

```
/dev/hda[1-8]
/dev/hdb[1-8]
/dev/sda[1-8]
/dev/sdb[1-8]
```

The `size-in-blocks` parameter is the desired size of the filesystem in blocks. This information can be determined from the `fdisk(8)` program. Only block counts strictly greater than 10 and strictly less than 65,536 are allowed.

OPTIONS

<code>-c</code>	Check the device for bad blocks before creating the filesystem. If any are found, the count is printed.
<code>-n namelength</code>	Specify the maximum length of filenames. No space is allowed between the <code>-n</code> and the <code>namelength</code> . Currently, the only allowable values are 14 and 30. 30 is the default.
<code>-i inodecount</code>	Specify the number of inodes for the filesystem.
<code>-l filename</code>	Read the bad blocks list from <code>filename</code> . The file has one bad block number per line. The count of bad blocks read is printed.

EXIT CODES

The exit code returned by `mkfs.minix` is one of the following:

0	No errors
8	Operational error
16	Usage or syntax error

SEE ALSO

`fsck(8)`, `mkefs(8)`, `efscck(8)`, `reboot(8)`

AUTHOR

Linus Torvalds (torvalds@cs.helsinki.fi). Error code values by Rik Faith (faith@cs.unc.edu). Inode request feature by Scott Heavner (sdh@po.cwru.edu). Support for the filesystem valid flag by Dr. Wettstein (greg%wind.uucp@plains.nodak.edu).

Check to prevent mkfs of mounted filesystem and boot sector clearing by Daniel Quinlan (quinlan@yggdrasil.com).

Linux 0.99, 10 January 1994

mklost+found

mklost+found—Create a lost+found directory on a mounted Linux second extended filesystem.

SYNOPSIS

mklost+found

DESCRIPTION

mklost+found is used to create a lost+found directory in the current working directory on a Linux second extended filesystem. mklost+found pre-allocates disk blocks to the directory to make it usable by e2fsck.

OPTIONS

There are none.

AUTHOR

mklost+found was written by Remy Card (card@masi.ibp.fr), the developer and maintainer of the ext2 fs.

BUGS

There are none. :-)

AVAILABILITY

mklost+found is available for anonymous FTP from ftp.ibp.fr and tsx-11.mit.edu in /pub/linux/packages/ext2fs.

SEE ALSO

e2fsck(8), mke2fs(8)

Version 0.5b, November 1994

mkswap

mkswap—Set up a Linux swap area.

SYNOPSIS

mkswap [-c] device [size-in-blocks]

DESCRIPTION

mkswap sets up a Linux swap area on a device or in a file.

The device is usually of the following form:

```
/dev/hda[1-8]
/dev/hdb[1-8]
/dev/sda[1-8]
/dev/sdb[1-8]
```

The `size-in-blocks` parameter is the desired size of the filesystem in blocks. This information is determined automatically by `mkswap` if it is omitted. Block counts are rounded down so that the total size is an integer multiple of the machine's page size. Only block counts in the range `MINCOUNT..MAXCOUNT` are allowed. If the block count exceeds the `MAXCOUNT`, it is truncated to that value and a warning message is issued.

The `MINCOUNT` and `MAXCOUNT` values for a swap area are

```
MINCOUNT = 10 * PAGE_SIZE / 1024
MAXCOUNT = (PAGE_SIZE-10)*8 *PAGE_SIZE / 1024
```

For example, on a machine with 4KB pages (such as x86), we get

```
MINCOUNT = 10 * 4096 / 1024 = 40
MAXCOUNT = (4096 - 10) * 8 * 4096 / 1024 = 130752
```

As each block is 1KB, the swap area in this example could have a size that is anywhere in the range from 40KB to 127.6875MB.

If you don't know the page size that your machine uses, you may be able to look it up with `cat /proc/cpuinfo`.

The reason for the limit on `MAXCOUNT` is that a single page is used to hold the swap bitmap at the start of the swap area, where each bit represents a single page. The reason for the `-10`, is that the signature is `SWAP-SPACE - 10` characters.

To set up a swap file, it is necessary to create that file before running `mkswap`. A sequence of commands similar to the following is reasonable for this purpose:

```
# dd if=/dev/zero of=swapfile bs=1024 count=8192
# mkswap swapfile 8192
# sync
# swapon swapfile
```

Note that a swap file must not contain any holes (so using `cp(1)` to create the file is not acceptable).

OPTIONS

`-c`

Check the device for bad blocks before creating the filesystem. If any are found, the count is printed. This option is meant to be used for swap partitions only and should not be used for regular files! To make sure that regular files do not contain bad blocks, the partition that contains the regular file should have been created with `mkfs -c`.

SEE ALSO

`fscck(8)`, `mkfs(8)`, `fdisk(8)`

AUTHOR

Linus Torvalds (torvalds@cs.helsinki.fi)

Linux 1.0, 8 February 1995

mount, umount

`mount`, `umount`—Mount and dismount filesystems.

SYNOPSIS

```
mount [-afrwuvn] [-t vfstype]
mount [-frwuvn] [-o remount [...]] special | node
mount [-frwun] [-t vfstype] [-o options] special | node
umount [-an] [-t vfstype]
umount special | node
```

DESCRIPTION

The `mount` command calls the `mount(2)` system call to prepare and graft a special device onto the filesystem tree at the point node. If either `special` or `node` are not provided, the appropriate information is taken from the `fstab(5)` file. The special keyword `none` can be used instead of a path or node specification. This is useful when mounting the `proc` filesystem.

The system maintains a list of currently mounted filesystems. If no arguments are given to `mount`, this list is printed.

Options available for the `mount` command:

<code>-f</code>	Causes everything to be done except for the actual system call; if it's not obvious, this "fakes" mounting the filesystem. This option is useful in conjunction with the <code>-v</code> flag to determine what the <code>mount</code> command is trying to do.
<code>-o</code>	Options are specified with a <code>-o</code> flag followed by a comma-separated string of options. Note that many of these options are only useful when they appear in the <code>/etc/fstab</code> file. The following options apply to any filesystem that is being mounted:
<code>async</code>	All I/O to the filesystem should be done asynchronously.
<code>auto</code>	Can be mounted with the <code>-a</code> option.
<code>defaults</code>	Use default options: <code>rw</code> , <code>suid</code> , <code>dev</code> , <code>exec</code> , <code>auto</code> , <code>nouser</code> , and <code>async</code> .
<code>dev</code>	Interpret character or block special devices on the filesystem.
<code>exec</code>	Permit execution of binaries.
<code>noauto</code>	Can only be mounted explicitly (that is, the <code>-a</code> option does not cause the filesystem to be mounted).
<code>nodev</code>	Do not interpret character or block special devices on the filesystem. This option is useful for a server that has filesystems containing special devices for architectures other than its own.
<code>noexec</code>	Do not allow execution of any binaries on the mounted filesystem. This option is useful for a server that has filesystems containing binaries for architectures other than its own.
<code>nosuid</code>	Do not allow set-user-identifier or set-group-identifier bits to take effect.
<code>nouser</code>	Forbid an ordinary (that is, non-root) user to mount the filesystem.
<code>remount</code>	Attempt to remount an already-mounted filesystem. This is commonly used to change the mount flags for a filesystem, especially to make a read-only filesystem writable.
<code>ro</code>	Mount the filesystem read-only.
<code>rw</code>	Mount the filesystem read-write.
<code>suid</code>	Allow set-user-identifier or set-group-identifier bits to take effect.
<code>sync</code>	All I/O to the filesystem should be done synchronously.
<code>user</code>	Allow an ordinary user to mount the filesystem. Ordinary users always have the following options activated: <code>noexec</code> , <code>nosuid</code> , and <code>nodev</code> (unless overridden by the super-user by using, for example, the following option line: <code>user,exec,dev,suid</code>).

The following options apply only to certain filesystems:

<code>case=value</code>	For the <code>hpf</code> s filesystem, specify <code>case</code> as <code>lower</code> or <code>asis</code> .
<code>check=value</code>	Tells the <code>ext2</code> filesystem kernel code to do some more checks while the filesystem is mounted. Currently (0.99.15), the following values can be specified with this option:
<code>none</code>	No extra check is performed by the kernel code.
<code>normal</code>	The inodes and blocks bitmaps are checked when the filesystem is mounted (this is the default).
<code>strict</code>	In addition to the normal checks, block deallocation checks that the block to free is in the data zone.
<code>check=value</code>	For the <code>msdos</code> filesystem, three different levels of specificity can be chosen:

relaxed	Uppercase and lowercase are accepted and equivalent, long name parts are truncated (for example, <code>ver1ongname.foo</code> becomes <code>verylong.foo</code>), leading and embedded spaces are accepted in each name part (name and extension).
normal	Like <code>relaxed</code> but many special characters (*, ?, <, spaces, and so on) are rejected. This is the default.
strict	Like <code>normal</code> , but names may not contain long parts and special characters that are sometimes used on Linux but are not accepted by MS-DOS are rejected (+, =, spaces, and so on).
conv=value	For the <code>msdos</code> , <code>hpfs</code> , and <code>iso9660</code> filesystems, specify file conversion as <code>binary</code> , <code>text</code> , or <code>auto</code> . The <code>iso9660</code> filesystem also allows value to be <code>mtext</code> . The <code>msdos</code> filesystem can perform <code>CRLF<->NL</code> (MS-DOS text format to UNIX text format) conversion in the kernel. The following conversion modes are available:
binary	No translation is performed. This is the default.
text	<code>CRLF<->NL</code> translation is performed on all files.
auto	<code>CRLF<->NL</code> translation is performed on all files that don't have a well-known binary extension. The list of known extensions can be found at the beginning of <code>fs/msdos/misc.c</code> (as of 09913r, the list is <code>exe</code> , <code>com</code> , <code>bin</code> , <code>app</code> , <code>sys</code> , <code>drv</code> , <code>ovl</code> , <code>ovr</code> , <code>obj</code> , <code>lib</code> , <code>dll</code> , <code>pif</code> , <code>arc</code> , <code>zip</code> , <code>lha</code> , <code>lzh</code> , <code>zoo</code> , <code>tar</code> , <code>z</code> , <code>arj</code> , <code>tz</code> , <code>taz</code> , <code>tzp</code> , <code>tpz</code> , <code>gif</code> , <code>bmp</code> , <code>tif</code> , <code>gl</code> , <code>jpg</code> , <code>pcx</code> , <code>tfm</code> , <code>vf</code> , <code>gf</code> , <code>pk</code> , <code>pxl</code> , and <code>dvi</code>).

Programs that do computed `lseek`s won't like in-kernel text conversion.

For filesystems mounted in binary mode, a conversion tool (`fromdos/todos`) is available.

block=value	For the <code>iso9660</code> filesystem, set the block size.
bsdgroups	See <code>grp</code> id.
cruft	For the <code>iso9660</code> filesystem, set the <code>cruft</code> flag to <code>y</code> . This option is available because there are buggy premastering programs out there that leave junk in the top byte of the file size. This option clears the top byte but restricts files to 16MB maximum in the process.
debug	For the <code>msdos</code> filesystem, turn on the debug flag. A version string and a list of filesystem parameters is printed. (These data are also printed if the parameters appear to be inconsistent.)
debug	For the <code>ext2fs</code> filesystem, cause the kernel code to display the filesystem parameters when the filesystem is mounted.
errors=value	For the <code>ext2fs</code> filesystem, specify the error behavior:
continue	No special action is taken on errors (except marking the filesystem as erroneous). This is the default.
remount, ro	The filesystem is remounted read only, and subsequent writes are refused.
panic	When an error is detected, the system panics.
fat=value	For the <code>msdos</code> filesystem, specify either a 12-bit fat or a 16-bit fat. This overrides the automatic FAT type detection routine. Use with caution!
gid=value	For the <code>msdos</code> and <code>hpfs</code> filesystems, give every file a <code>gid</code> equal to <code>value</code> .
B grp	id Causes the <code>ext2fs</code> to use the BSD behavior when creating files: Files are created with the group ID of their parent directory.
map=value	For the <code>iso9660</code> filesystem, specify mapping as <code>off</code> or <code>normal</code> . In general, non-Rock Ridge discs have all the filenames in uppercase, and all the filenames have a <code>;1</code> appended. The <code>map</code> option strips the <code>;1</code> and makes the name lowercase. (See also <code>norock</code> .)
nocheck	For the <code>ext2fs</code> , turns off checking (see <code>check=none</code>).
nogrp	id Causes the <code>ext2fs</code> to use the System V behavior when creating files. Files are created with the group ID of the creating process, unless the <code>setgid</code> bit is set on the parent directory. This is the default for all Linux filesystems.

norock	Normal iso9600 filenames appear in a 8.3 format (that is, DOS-like restrictions on filename length), and in addition, all characters are in uppercase. Also there is no field for file ownership, protection, number of links, provision for block/character devices, and so on. Rock Ridge is an extension to iso9600 that provides all of these UNIX-like features. Basically, there are extensions to each directory record that supply all of the additional information, and when Rock Ridge is in use, the filesystem is indistinguishable from a normal UNIX filesystem (except that it is read only, of course). The norock switch disables the use of Rock Ridge extensions, even if available. (See also map.)
quiet	For the msdos filesystem, turn on the quiet flag. Attempts to chown or chmod files do not yield errors, although they fail. Use with caution!
sb=value	For the ext2 filesystem, use an alternate superblock located at block value. value is numbered in 1024-byte blocks. An ext2 filesystem usually has backups of the superblock at blocks 1, 8193, 16385, and so on.
sysvgroups	See nogrpid.
uid=value	For the msdos and hpfs filesystems, give every file a uid equal to value.
umask=value	For the msdos and hpfs filesystems, give every file a umask of value. The radix defaults to octal.

The full set of options applied is determined by first extracting the options for the filesystem from the fstab table, then applying any options specified by the -o argument, and finally applying the -r or -w option.

If the msdos filesystem detects an inconsistency, it reports an error and sets the filesystem to read only. The filesystem can be made writable again by remounting it.

-r	The filesystem object is to be mounted read only.
-t vfstype	The argument following the -t is used to indicate the filesystem type. The filesystem types that are currently supported are listed in <code>linux/fs/filesystems.c</code>: minix, ext, ext2, xiafs, msdos, hpfs, proc, nfs, iso9600, sysv, xenix, coherent. Note that that last three are equivalent and that xenix and coherent will be removed at some point in the future; use sysv instead. The type minix is the default. If no -t option is given, or if the auto type is specified, the superblock is probed for the filesystem type (minix, ext, ext2, and xia are supported). If this probe fails and <code>/proc/filesystems</code> exists, then all the filesystems listed are tried, except for those labeled nodev (such as proc and nfs). Note that the auto type may be useful for user-mounted floppies. For example, the mount command mounts all filesystems except those of type msdos and ext: <pre>mount -a -t nomdos,ext</pre>
-v	Verbose mode.
-w	The filesystem object is to be read and write.
-n	Mount without writing in <code>/etc/mtab</code> .

umount removes the special device grafted at point node from the filesystem tree.

Options for the umount command:

-a	All of the filesystems described in <code>/etc/mtab</code> are unmounted.
-t vfstype	Is used to indicate the actions should only be taken on filesystems of the specified type. More than one type may be specified in a comma-separated list. The list of filesystem types can be prefixed with no to specify the filesystem types on which no action should be taken. (See example for the mount command.)

FILES

<code>/etc/fstab</code>	Filesystem table
<code>/etc/mtab</code>	Lock file
<code>/etc/mtab.tmp</code>	Temporary file

SEE ALSO

`mount(2)`, `umount(2)`, `fstab(5)`, `swapon(8)`

BUGS

It is possible for a corrupted filesystem to cause a crash.

Some Linux filesystems don't support `-o synchronous` (the `ext2fs` does support synchronous updates (a la BSD) when mounted with the `sync` option).

The `-o remount` may not be able to change mount parameters (all `ext2fs` parameters, except `sb`, are changeable with a `remount`, for example, but you can't change `gid` or `umask` for the `dosfs`).

HISTORY

A `mount` command appeared in Version 6, AT&T UNIX.

AUTHORS AND CONTRIBUTORS

The Linux `mount` command has a long and continuing history. The following major releases are noted with the name of the primary modifier:

- 0.97.3: Doug Quale (quale@saavik.cs.wisc.edu)
- 0.98.5: H.J. Lu (hlu@eecs.wsu.edu)
- 0.99.2: Rick Sladkey (jrs@world.std.com)
- 0.99.6: Rick Sladkey (jrs@world.std.com)
- 0.99.10: Stephen Tweedie (sct@dcs.ed.ac.uk)
- 0.99.14: Rick Sladkey (jrs@world.std.com)

(Filesystem-specific information added to man page on 27 November 1993 by Rik Faith with a lot of information and text from the following filesystem authors: Werner Almesberger, Eric Youngdale, and Remy Card.)

Linux 1.1, 8 February 1995

mountd

mountd—NFS mount daemon.

SYNOPSIS

```
/usr/etc/rpc.mountd [-f|-exports-file][|-dhnpv\]
[|-debug\][|-exports-file=file\] [|-help\]
[|-allow-non-root\][|-re-export\][|-version\]
```

DESCRIPTION

The `mountd` program is an NFS mount daemon.

OPTIONS

`-f` or `--exports-file` This option specifies the exports file, listing the clients that this server is prepared to serve and parameters to apply to each such mount (see `exports(5)`). By default, exports are read from `/etc/exports`.

-d OR --debug	Log each transaction verbosely to the syslog.
-h OR --help	Provide a short help summary.
-n OR --allow-non-root	Allow incoming mount requests to be honored even if they do not originate from reserved IP ports. Some older NFS client implementations require this. Some newer NFS client implementations don't believe in reserved port checking.
-p OR --promiscuous	Put the server into promiscuous mode where it will serve any host on the network.
-r OR --re-export	Allow imported NFS filesystems to be exported. This can be used to turn a machine into an NFS multiplier. Caution should be used when reexporting loopback NFS mounts because reentering the mount point results in deadlock between the NFS client and the NFS server.
-v OR --version	Report the current version number of the program.

SEE ALSO

exports(5), nfsd(8), ugid(8C)

BUGS

The current implementation (still) does not keep track of remote mounts.

13 October 1993

named-xfer

named-xfer—Ancillary agent for inbound zone transfers.

SYNOPSIS

```
named-xfer -z zone_to_transfer -f db_file -s serial_no [ -d debuglevel ]
[-l debug_log_file ][-t trace_file ][-p port# ][-S ] nameserver
```

DESCRIPTION

named-xfer is an ancillary program executed by named(8) to perform an inbound zone transfer. It is rarely executed directly and only by system administrators who are trying to debug a zone transfer problem. See RFCs 1033, 1034, and 1035 for more information on the Internet name-domain system.

Options are

-z	Specifies the name of the zone to be transferred.
-f	Specifies the name of the file into which the zone should be dumped when it is received from the primary server.
-s	Specifies the serial number of the current copy of this zone. If the SOA RR you get from the primary server does not have a serial number higher than this, the transfer is aborted.
-d	Print debugging information. A number after the d determines the level of messages printed.
-l	Specifies a log file for debugging messages. The default is system-dependent but is usually in /var/tmp or /usr/tmp. Note that this only applies if -d is also specified.
-t	Specifies a trace file that contains a protocol trace of the zone transfer. This is probably only of interest to people debugging the nameserver itself.
-p	Use a different port number. The default is the standard port number as returned by getservbyname(3) for service “domain”.
-S	Perform a restricted transfer of only the SOA, NS records, and glue A records for the zone. The SOA record is not loaded by named but is used to determine when to verify the NS records. See the stubs directive in named(8) for more information.

Additional arguments are taken as nameserver addresses in so-called “dotted-quad” syntax only; no hostnames are allowed here. At least one address must be specified. Any additional addresses are tried in order if the first one fails to transfer successfully.

SEE ALSO

`named(8)`, `resolver(3)`, `resolver(5)`, `hostname(7)`, RFC 882, RFC 883, RFC 973, RFC 974, RFC 1033, RFC 1034, RFC 1035, RFC 1123, *Name Server Operations Guide for BIND*

26 June 1993

named

`named`—Internet domain nameserver.

SYNOPSIS

```
named [ -d debuglevel ] [-p port#[/localport#]][{-b} bootfile ][-q ][-r ]
```

DESCRIPTION

`named` is the Internet domain nameserver. See RFCs 1033, 1034, and 1035 for more information on the Internet name-domain system. Without any arguments, `named` reads the default boot file `/etc/named.boot`, reads any initial data, and listens for queries.

Options are

- d Print debugging information. A number after the `d` determines the level of messages printed.
- p Use nonstandard port numbers. The default is the standard port number as returned by `getservbyname(3)` for service “domain”. The argument can specify two port numbers separated by a slash (`/`), in which case the first port is that used when contacting remote servers and the second one is the service port bound by the local instance of `named`. This is used mostly for debugging purposes.
- b Use an alternate boot file. This is optional and allows you to specify a file with a leading dash.
- q Trace all incoming queries if `named` has been compiled with `QUERYLOG` defined. Note that this option is deprecated in favor of the boot file directive options `query-log`.
- r Turns recursion off in the server. Answers can come only from local (primary or secondary) zones. This can be used on root servers. Note that this option is deprecated in favor of the boot file directive options `no-recursion`.

Any additional argument is taken as the name of the boot file. If multiple boot files are specified, only the last is used.

The boot file contains information about where the nameserver is to get its initial data. Lines in the boot file cannot be continued on subsequent lines. The following is a small example:

```
;
; boot file for name server
;
directory /usr/local/adm/named
; type domain source host/file backup file
cache . root.cache
primary Berkeley.EDU berkeley.edu.zone
primary 32.128.IN-ADDR.ARPA ucbhosts.rev
secondary CC.Berkeley.EDU 128.32.137.8 128.32.137.3 cc.zone.bak
secondary 6.32.128.IN-ADDR.ARPA 128.32.137.8 128.32.137.3 cc.rev.bak
primary 0.0.127.IN-ADDR.ARPA localhost.rev
```

```
forwarders 10.0.0.78 10.2.0.78
limit transfers-in 10
limit datasize 64M
options forward-only query-log fake-iquery
```

The `directory` line causes the server to change its working directory to the directory specified. This can be important for the correct processing of `$INCLUDE` files in primary zone files.

The `cache` line specifies that data in `root.cache` is to be placed in the backup cache.

Its main use is to specify data such as locations of root domain servers. This cache is not used during normal operation, but is used as “hints” to find the current root servers. The file `root.cache` is in the same format as `berkeley.edu.zone`. There can be more than one cache file specified. The `root.cache` file should be retrieved periodically from `FTP.RS.INTERNIC.NET` because it contains a list of root servers, and this list changes periodically.

The first sample primary line states that the file `berkeley.edu.zone` contains authoritative data for the `Berkeley.EDU` zone. The file `berkeley.edu.zone` contains data in the master file format described in RFC 883. All domain names are relative to the origin, in this case, `Berkeley.EDU` (see below for a more detailed description). The second primary line states that the file `ucbhosts.rev` contains authoritative data for the domain `32.128.IN-ADDR.ARPA`, which is used to translate addresses in network `128.32` to hostnames. Each master file should begin with an SOA record for the zone (see below).

The first sample secondary line specifies that all authoritative data under `CC.Berkeley.EDU` is to be transferred from the nameserver at `128.32.137.8`. If the transfer fails, it tries `128.32.137.3` and continues trying the addresses, up to ten, listed on this line. The secondary copy is also authoritative for the specified domain. The first non-dotted-quad address on this line is taken as a filename in which to back up the transferred zone. The nameserver loads the zone from this backup file if it exists when it boots, providing a complete copy even if the master servers are unreachable. Whenever a new copy of the domain is received by automatic zone transfer from one of the master servers, this file is updated. If no filename is given, a temporary file is used and deleted after each successful zone transfer. This is not recommended because it is a needless waste of bandwidth. The second sample secondary line states that the address-to-hostname mapping for the subnet `128.32.136` should be obtained from the same list of master servers as the previous zone.

The `forwarders` line specifies the addresses of sitewide servers that will accept recursive queries from other servers. If the boot file specifies one or more forwarders, then the server sends all queries for data not in the cache to the forwarders first. Each forwarder is asked in turn until an answer is returned or the list is exhausted. If no answer is forthcoming from a forwarder, the server continues as it would have without the `forwarders` line unless it is in `forward-only` mode. The forwarding facility is useful to cause a large sitewide cache to be generated on a master and to reduce traffic over links to outside servers. It can also be used to allow servers to run that do not have direct access to the Internet but want to look up exterior names anyway.

The `slave` line (deprecated) is allowed for backward compatibility. Its meaning is identical to `options forward-only`.

The `sortlist` line can be used to indicate networks that are to be preferred over other networks. Queries for host addresses from hosts on the same network as the server receive responses with local network addresses listed first, then addresses on the sort list, and then other addresses.

The `xfrnets` directive (not shown) can be used to implement primitive access control. If this directive is given, your nameserver only answers zone transfer requests from hosts that are on networks listed in your `xfrnets` directives. This directive may also be given as `tcplists` for compatibility with older, interim servers.

The `include` directive (not shown) can be used to process the contents of some other file as though they appeared in place of the `include` directive. This is useful if you have a lot of zones or if you have logical groupings of zones that are maintained by different people. The `include` directive takes one argument, the name of the file whose contents are to be included. No quotes are necessary around the filename.

The `bogusns` directive (not shown) tells BIND that no queries are to be sent to the specified nameserver addresses (which are specified as dotted quads, not as domain names). This is useful when you know that some popular server has bad data in a zone or cache, and you want to avoid contamination while the problem is being fixed.

The `limit` directive can be used to change BIND’s internal limits, some of which (`datasize`, for example) are implemented by the system and others (such as `transfers-in`) by BIND itself. The number following the limit name can be scaled by

postfixing a *k*, *m*, or *g* for kilobytes, megabytes, and gigabytes respectively. *datasize*'s argument sets the process data size enforced by the kernel. Note that not all systems provide a call to implement this; on such systems, the use of the *datasize* parameter of *limit* results in a warning message. *transfers-in*'s argument is the number of named-xfer subprocesses that BIND will spawn at any one time. *transfers-per-ns*'s argument is the maximum number of zone transfers to be simultaneously initiated to any given remote nameserver.

The *options* directive introduces a Boolean specifier that changes the behavior of BIND. More than one option can be specified in a single directive. The currently defined options are as follows: *no-recursion*, which causes BIND to answer with a referral rather than actual data whenever it receives a query for a name it is not authoritative for. Don't set this on a server that is listed in any host's *resolv.conf* file. *no-fetch-glue* keeps BIND from fetching missing glue when constructing the "additional data" section of a response; this can be used in conjunction with *no-recursion* to prevent BIND's cache from ever growing in size or becoming corrupted. *query-log* causes all queries to be logged via *syslog(3)*. This is a lot of data; don't turn it on lightly. *forward-only* causes the server to query only its forwarders. This option is usually used on a machine that wants to run a server but for physical or administrative reasons cannot be given access to the Internet. *fake-iquery* tells BIND to send back a useless and bogus reply to "inverse queries" rather than respond with an error. This is helpful if you have a lot of microcomputers or SunOS hosts or both.

The *max-fetch* directive (not shown) is allowed for backward compatibility; its meaning is identical to *limit transfers-in*.

The master file consists of control information and a list of resource records for objects in the zone of the forms:

```
$INCLUDE <filename><opt_domain>
$ORIGIN <domain>
<domain><opt_ttl> <opt_class><type><resource_record_data>
```

domain is *.* for root, *@* for the current origin, or a standard domain name. If *domain* is a standard domain name that does not end with *.*, the current origin is appended to the domain. Domain names ending with *.* are unmodified. The *opt_domain* field is used to define an origin for the data in an included file. It is equivalent to placing a *\$ORIGIN* statement before the first line of the included file. The field is optional. Neither the *opt_domain* field nor *\$ORIGIN* statements in the included file modify the current origin for this file. The *opt_ttl* field is an optional integer number for the time-to-live field. It defaults to 0, meaning the minimum value specified in the SOA record for the zone. The *opt_class* field is the object address type; currently only one type is supported, *IN*, for objects connected to the DARPA Internet. The type field contains one of the following tokens; the data expected in the *resource_record_data* field is in parentheses:

A	A host address (dotted quad).
NS	An authoritative nameserver (domain).
MX	A mail exchanger (domain), preceded by a preference value (0..32767) with lower numeric values representing higher logical preferences.
CNAME	The canonical name for an alias (domain).
SOA	Marks the start of a zone of authority (domain of originating host, domain address of maintainer, a serial number and the following parameters in seconds: refresh, retry, expire, and minimum TTL (see RFC 883)).
NULL	A null resource record (no format or data).
RP	A responsible person for some domain name (mailbox, TXT-referral).
PTR	A domain name pointer (domain).
HINFO	Host information (cpu_type, OS_type).

Resource records usually end at the end of a line but may be continued across lines between opening and closing parentheses. Comments are introduced by semicolons and continue to the end of the line.

Note that there are other resource record types, not shown here. You should consult the BIND Operations GUIDE (BOG) for the complete list. Some resource record types may have been standardized in newer RFCs but not yet implemented in this version of BIND.

Each master zone file should begin with an SOA record for the zone. A sample SOA record follows:

```
@ IN SOA ucbvax.Berkeley.EDU. rwh.ucbvax.Berkeley.EDU. (
1989020501 ; serial
10800 ; refresh
3600 ; retry
3600000 ; expire
86400 ) ; minimum
```

The SOA specifies a serial number, which should be changed each time the master file is changed. Note that the serial number can be given as a dotted number, but this is a very unwise thing to do because the translation to normal integers is via concatenation rather than multiplication and addition. You can spell out the year, month, day of month, and 0..99 version number and still fit inside the unsigned 32-bit size of this field. It's true that we will have to rethink this strategy in the year 4294, but we're not worried about it. Secondary servers check the serial number at intervals specified by the refresh time in seconds; if the serial number changes, a zone transfer is done to load the new data. If a master server cannot be contacted when a refresh is due, the retry time specifies the interval at which refreshes should be attempted. If a master server cannot be contacted within the interval given by the expire time, all data from the zone is discarded by secondary servers. The minimum value is the time-to-live (TTL) used by records in the file with no explicit time-to-live value.

NOTES

The boot file directives `domain` and `suffixes` have been obsoleted by a more useful resolver-based implementation of suffixing for partially qualified domain names. The prior mechanisms could fail under a number of situations, especially when then local nameserver did not have complete information.

The following signals have the specified effect when sent to the server process using the `kill(1)` command:

SIGHUP	Causes server to read <code>named.boot</code> and reload the database. If the server is built with the <code>FORCED RELOAD</code> compile-time option, then SIGHUP also causes the server to check the serial number on all secondary zones. Usually, the serial numbers are only checked at the SOA-specified intervals.
SIGINT	Dumps the current database and cache to <code>/var/tmp/named_dump.db</code> .
SIGIOT	Dumps statistics data into <code>/var/tmp/named.stats</code> if the server is compiled with <code>-DSTATS</code> . Statistics data is appended to the file. Some systems use <code>SIGABRT</code> rather than <code>SIGIOT</code> for this.
SIGSYS	Dumps the profiling data in <code>/var/tmp</code> if the server is compiled with profiling (the server forks, changes directories, and exits).
SIGTERM	Dumps the primary and secondary database files. Used to save modified data on shutdown if the server is compiled with dynamic updating enabled.
SIGUSR1	Turns on debugging; each <code>SIGUSR1</code> increments debug level (<code>SIGEMT</code> on older systems without <code>SIGUSR1</code>).
SIGUSR2	Turns off debugging completely (<code>SIGFPE</code> on older systems without <code>SIGUSR2</code>).
SIGWINCH	Toggles logging of all incoming queries via <code>syslog(3)</code> (requires server to have been built with the <code>QRYLOG</code> option).

FILES

<code>/etc/named.boot</code>	Nameserver configuration boot file
<code>/etc/named.pid</code>	The process ID (on older systems)
<code>/var/run/named.pid</code>	The process ID (on newer systems)
<code>/var/tmp/named_dump.db</code>	Dump of the nameserver database
<code>/var/tmp/named.run</code>	Debug output
<code>/var/tmp/named.stats</code>	Nameserver statistics data

SEE ALSO

`kill(1)`, `gethostbyname(3)`, `signal(2)`, `resolver(3)`, `resolver(5)`, `hostname(7)`, RFC 882, RFC 883, RFC 973, RFC 974, RFC 1033, RFC 1034, RFC 1035, RFC 1123, *Name Server Operations GUIDe for BIND*

20 June 1995

named.reload

`named.reload`—Cause the nameserver to synchronize its database.

DESCRIPTION

This command sends a `SIGHUP` to the running nameserver. This signal is documented in `named(8)`.

BUGS

It does not check to see if the nameserver is actually running and could use a stale pid cache file, which may result in the death of an unrelated process.

SEE ALSO

`named(8)`, `named.restart(8)`

26 June 1993

named.restart

`named.restart`—Stop and restart the nameserver.

DESCRIPTION

This command sends a `SIGKILL` to the running nameserver and then starts a new one.

BUGS

It does not check to see if the nameserver is actually running and could use a stale pid cache file, which may result in the death of an unrelated process.

It does not wait after killing the old server before starting a new one. Because the server could take some time to die and the new one experiences a fatal error if the old one isn't gone by the time it starts, you can be left in a situation where you have no nameserver at all.

SEE ALSO

`named(8)`, `named.reload(8)`

26 June 1993

ndc

`ndc`—Name daemon control interface.

SYNOPSIS

`ndc directive [ ... ]`

DESCRIPTION

This command allows the nameserver administrator to send various signals to the nameserver or to restart it. Zero or more directives may be given from the following list:

status	Displays the current status of named as shown by ps(1).
dumpdb	Causes named to dump its database and cache to /var/tmp/named_dump.db (uses the INT signal.)
reload	Causes named to check the serial numbers of all primary and secondary zones and to reload those that have changed (uses the HUP signal.)
stats	Causes named to dump its statistics to /var/tmp/named.stats (uses the IOT or ABRT signal.)
trace	Causes named to increment its “tracing level” by one. Whenever the tracing level is nonzero, trace information is written to /var/tmp/named.run. Higher tracing levels result in more detailed information (uses the USR1 signal).
notrace	Causes named to set its “tracing level” to zero, closing /var/tmp/named.run if it is open (uses the USR2 signal).
querylog	Causes named to toggle the “query logging” feature, which results in a syslog(3) of each incoming query (uses the WINCH signal). Note that query logging consumes quite a lot of log file space. This directive may also be given as qrylog.
start	Causes named to be started as long as it isn't already running.
stop	Causes named to be stopped if it is running.
restart	Causes named to be killed and restarted.

BUGS

Arguments to named are not preserved by restart or known by start. Some mechanism for controlling the parameters and environment should exist.

Implemented as a sh(1) script.

AUTHOR

Paul Vixie (Internet Software Consortium)

SEE ALSO

named(8), named.reload(8), named.restart(8)

27 November 1994

netstat

netstat—Display active network connections

SYNOPSIS

```
netstat [[-a | [-t | -u | -w]] [-n | -o] | -x] [-c]
netstat -r [-c] [-n]
netstat -v
```

DESCRIPTION

netstat displays the status of network connections on either TCP, UDP, or RAW sockets to the system. By default, netstat only displays status on those TCP sockets that are not in the LISTEN state (that is, connections to active processes). To obtain information about the kernel routing table, netstat may be invoked with the option -r. A listing of internal UNIX connections can be obtained by invoking netstat with the option -x.

netstat's display includes the following information for each socket:

Proto	The protocol (either TCP or UDP) used by the socket.
Recv-Q	The count of bytes not copied by the user program connected to this socket.
Send-Q	The count of bytes not acknowledged by the remote host.
Local Address	The local address (local hostname) and port number of the socket. Unless the <code>-n</code> switch is given, the socket address is resolved to its canonical hostname, and the port number is translated into the corresponding service name.
Foreign Address	The remote address (remote hostname) and port number of the socket. As with the local address:port, the <code>-n</code> switch turns off hostname and service name resolution.
(State)	The state of the socket. Because there are no states in RAW and usually no states used in UDP, this row may be left blank. Usually, this can be one of several values:
ESTABLISHED	The socket has an established connection.
SYN_SENT	The socket is actively attempting to establish a connection.
SYN_RECV	The connection is being initialized.
FIN_WAIT1	The socket is closed, and the connection is shutting down.
FIN_WAIT2	Connection is closed, and the socket is waiting for a shutdown from the remote end.
TIME_WAIT	The socket is waiting after close for remote shutdown re-transmission.
CLOSED	The socket is not being used.
CLOSE_WAIT	The remote end has shut down, waiting for the socket to close.
LAST_ACK	The remote end shut down, and the socket is closed. Waiting for acknowledgment.
LISTEN	The socket is listening for incoming connections.
UNKNOWN	The state of the socket is unknown.

If netstat is invoked with the option `-o`, additional information is displayed after the state info. This information is shown like this: keyword (time/backoff) and an optional asterisk. The keyword shows the state of the timer belonging to the socket, the time displayed (in seconds) is how long it will take the timer to expire, the backoff value indicates the current retry count for data transmission, and the asterisk indicates that this timer is in the expiration queue. The latter might be removed in future but is helpful for debugging the TCP-Code for now.

Invoked with the option `-x`, netstat displays a list of all active UNIX internal communication sockets.

netstat's display includes the following information for each socket:

Proto	The protocol (usually UNIX) used by the socket.
RefCnt	The reference count (attached processes via this socket).
Flags	The only known flag to me is <code>SO_ACCEPTON</code> (displayed as <code>ACC</code>); otherwise, left blank. <code>SO_ACCEPTON</code> is used on unconnected sockets if their corresponding processes are waiting for a connect request.
Type	There are several types of socket access:
SOCK_DGRAM	The socket is used in Datagram (connectionless) mode.
SOCK_STREAM	This is a stream (connection) socket.
SOCK_RAW	The socket is used as a raw socket.
SOCK_RDM	This one serves reliably delivered messages.
SOCK_SEQPACKET	This is a sequential packet socket.
SOCK_PACKET	This socket type is used as a Linux-specific way to get packets at the dev (kernel) level. It is assumed to be used to write things such as RARP (Reverse Address Resolution Protocol) and similar things on the user level.
UNKNOWN	Who ever knows, what future will bring; just fill in here. :-)
State	This field will contain one of the following keywords:
FREE	The socket is not allocated.

LISTENING	The socket is listening for a connection request.
UNCONNECTED	The socket is not connected to another one.
CONNECTING	The socket is about to establish a connection.
CONNECTED	The socket is connected.
DISCONNECTING	The socket is disconnecting.
UNKNOWN	This state should never happen.
Path	This displays the pathname that the corresponding processes attached to the socket.

The network routing table (invoked with `netstat -r`) shows up the following information:

Destination net/address	The destination address of a resolved host or hand-entered network is displayed. Unless the option <code>-n</code> is given, the hosts or nets are resolved. An entry named <code>default</code> shows up the default route for the kernel.														
Gateway address	If there is no asterisk (*) displayed, any data is routed to the dedicated gateway.														
Flags	Possible routing flags are <table> <tr> <td>U</td><td>This route is usable.</td></tr> <tr> <td>G</td><td>Destination is a gateway.</td></tr> <tr> <td>H</td><td>Destination is a host entry.</td></tr> <tr> <td>N</td><td>Destination is a Net entry.</td></tr> <tr> <td>R</td><td>Route will be reinstated after timeout.</td></tr> <tr> <td>D</td><td>This one is created dynamically (by redirection).</td></tr> <tr> <td>M</td><td>This one is modified dynamically (by redirection).</td></tr> </table>	U	This route is usable.	G	Destination is a gateway.	H	Destination is a host entry.	N	Destination is a Net entry.	R	Route will be reinstated after timeout.	D	This one is created dynamically (by redirection).	M	This one is modified dynamically (by redirection).
U	This route is usable.														
G	Destination is a gateway.														
H	Destination is a host entry.														
N	Destination is a Net entry.														
R	Route will be reinstated after timeout.														
D	This one is created dynamically (by redirection).														
M	This one is modified dynamically (by redirection).														
RefCnt	Reference count for this route.														
Use	How many times this route was used yet.														
Iface	This is the name of the interface where this route belongs.														

OPTIONS

-a	Display information about all Internet sockets, such as TCP, UDP, and RAW, including those sockets that are listening only.
-c	Generate a continuous listing of network status: network status is displayed every second until the program is interrupted.
-n	Causes <code>netstat</code> not to resolve hostnames and service names when displaying remote and local address and port information.
-o	Display timer states, expiration times, and backoff state.
-r	Display kernel routing table.
-t	Display information about TCP sockets only, including those that are listening.
-u	Display information about UDP sockets only.
-v	Print version information.
-w	Display information about raw sockets.
-x	Display information about UNIX domain sockets.

FILES

<code>/proc/net/tcp</code>	TCP socket information
<code>/proc/net/udp</code>	UDP socket information
<code>/proc/net/raw</code>	RAW socket information
<code>/proc/net/unix</code>	UNIX domain socket information

<code>/proc/net/route</code>	Kernel routing information
<code>/etc/services</code>	The services translation

BUGS

None reported yet (5/20/93).

AUTHORS

The netstat user interface was written by Fred Baumgarten (dc6iq@insu1.etec.uni-karlsruhe.de). The man page is basically by Matt Welsh (mdw@tc.cornell.edu).

Cohesive Systems, 20 May 1993

makeactive, makehistory, newsrequeue

makeactive, makehistory, newsrequeue—Tools to recover Usenet databases

SYNOPSIS

```
makeactive [ -m ][ -o ]
makehistory [ -b ][ -f filename ][ -i ][ -n ][ -o ][ -r ][ -s size ]
[-T tmpdir ][ -u ][ -v ]
newsrequeue [ -a active ][ -h history ][ -d days ][ -l ][ -n newsfeeds ][ input ]
```

DESCRIPTION

`makeactive` invokes `find(1)` to get a list of all directories in the news spool tree, `/news/spool`. It discards directories named `lost+found` as well as those that have a period in them. It scans all other directories for all-numeric filenames and determines the highest and lowest number. The program's output is a set of `active(5)` file lines. Because there is no way to know if a group is moderated or disabled, the fourth field of all entries is `y`. Also, mid-level directories that aren't newsgroups are also created as newsgroups with no entries. (For example, there is a `comp.sources.unix` group, but no `comp.sources`.)

If the `-o` flag is used, `makeactive` reads an existing active file for the list of group names and just renumber all groups. It preserves the fourth field of the active file if one is present. This is analogous to the `ctlinnd(8)` `renumber` command, except that `innd(8)` should be throttled or not running. Do not use this flag with output redirected to the standard active file!

If the `-m` flag is given, then `makeactive` attempts to adjust the highest and lowest article numbers wherever possible. If articles are found in a newsgroup, the numbers reflect what was found. If no articles are found in a newsgroup, the high number from the old file is kept, and the low number is set to one more than the high number. This flag may only be used if the `-o` flag is used.

`makeactive` exits with nonzero status if any problems occur. A typical way to use the program is with the following `/bin/sh` commands:

```
ctlinnd throttle "Rebuilding active file"
TEMP=${TMPDIR-/tmp}/act$$
if [ -f /var/lib/news/active ] ; then
    if makeactive -o >${TEMP} ; then
        mv ${TEMP} /var/lib/news/active
    fi
else
    if makeactive >${TEMP} ; then
        # Edit to restore moderated
        # and aliased groups.
        ...
        mv ${TEMP} /var/lib/news/active
    fi
fi
ctlinnd reload active "New active file"
```

makehistory rebuilds the history(5) text file and the associated dbz(3) database. The default name of the text file is /news/lib/history; to specify a different name, use the -f flag. makehistory scans the active(5) file to determine which newsgroup directories within the spool directory, /news/spool, should be scanned. (If a group is removed, but its spool directory still exists, makehistory ignores it.) The program reads each file found and writes a history line for it. If the -b flag is used, then makehistory removes any articles that do not have valid Message-ID headers in them.

After the text file is written, makehistory builds the dbz database. If the -f flag is used, then the database files are named file.dir and file.pag. If the -f flag is not used, then a temporary link to the name history.n is made and the database files are written as history.n.pag and history.n.dir. If the -o flag is used, then the link is not made and any existing history files are overwritten. If the old database exists, makehistory uses it to determine the size of the new database. To ignore the old database, use the -i flag. Using the -o flag implies the -i flag. The program also ignores any old database if the -s flag is used to specify the approximate number of entries in the new database. Accurately specifying the size is an optimization that creates a more efficient database. (The size should be the estimated eventual size of the file, typically the size of the old file.) For more information, see the discussion of dbzfresh and dbzsize in dbz(3).

If the -u flag is given, then makehistory assumes that innd is running. It pauses the server while scanning and then sends addhist commands (see ctlinnd(8)) to the server for any article that is not found in the dbz database. The command makehistory -bu is useful after a system crash to delete any mangled articles and bring the article database back into a more consistent state. If the -v flag is used with the -u flag, then makehistory puts a copy of all added lines on its standard output.

To scan the spool directory without rebuilding the dbz files, use the -n flag. If used with -u, the server is not paused while scanning. To just build the dbz files from an existing text file, use the -r flag. The -i or -s flags can be useful if there are no valid dbz files to use. A typical way to use this program is with the following /bin/sh commands:

```
ctlinnd throttle "Rebuilding history file"
cd /news/lib
if makehistory -n -f history.n ; then
:
else
echo Error creating history file!
exit 1
fi
# The following line can be used to retain expired history.
# It is not necessary for the history file to be sorted.
# awk 'NF==2 { print; }' <history >>history.n
# View history file for mistakes.
if makehistory -r -s 'wc -l <history' -f history.n; then
mv history.n history
mv history.n.dir history.dir
mv history.n.pag history.pag
fi
ctlinnd go "
```

makehistory needs to create a temporary file that contains one line for each article it finds, which can become very large. This file is created in the /tmp directory. The TMPDIR environment variable may be used to specify a different directory. Alternatively, the -T flag may be used to specify a temporary directory. In addition, the sort(1) that is invoked during the build writes large temporary files (often to /var/tmp, but see your system man pages). If the -T flag is used, then the flag and its value are passed to sort. On most systems, this changes the temporary directory that sort uses. If used, this flag and its value are passed on to the sort(1) command that is invoked during the build.

makehistory does not handle symbolic links. If the news spool area is split across multiple partitions, the following commands should probably be run before the database is regenerated:

```
cd /news/spool
find . -type l -name '[1-9]*' -print | xargs -t rm
```

Make sure to run the command on all the appropriate partitions!

`newsrqueue` can be used to rewrite batchfiles after a system crash. It operates in two modes. In the first mode, it first reads the `active` and `newsfeeds(5)` files to determine where the different newsgroups are to be distributed. To specify alternate locations for these files, use the `-a` or `-n` flags. It then opens the `history` database. To specify a different file, use the `-h` flag.

Once the files are opened, `newsrqueue` reads from the specified input file or standard input if no file is specified. Each line should have a single Message-ID, surrounded in angle brackets; any other text on the line is ignored. For example, the `history` file (or a trailing subset of it) is acceptable input to the program operating in this mode. If the `-d` flag is used, then only articles that were received within the specified number of days are processed.

`newsrqueue` uses the first two fields of the `newsfeed` entry—the `sitename` and the `excludes` field and the `patterns` and `distrib` field. It ignores all flags in the third field except for the `N` field and also ignores the fourth field altogether.

The second mode is used if the `-l` flag is used. In this mode, it reads from the specified input file or standard input if no file is specified. Each line should look like an `innd` log entry. It parses entries for accepted articles, looks up the Message-ID in the `history` database to get the filename, and then scans the list of sites.

In either mode, the output of `newsrqueue` consists of one line for each article that should be forwarded. Each such line contains the Message-ID, the filename, and the list of sites that should receive the article. The output is suitable for piping into `filechan(8)`.

HISTORY

Written by Rich Salz (`rsalz@uunet.uu.net`) for InterNetNews.

SEE ALSO

`active(5)`, `ctlinnd(8)`, `dbz(3)`, `filechan(8)`, `history(5)`, `innd(8)`, `newsfeeds(5)`

news.daily

`news.daily`—Do regular Usenet system administration

SYNOPSIS

```
news.daily [ keyword... ]
innwatch [ -t sleeptime ][-f controlfile ][-l logfile ]
expirerm file
inncheck [ -v ][-pedantic ][-perms [ -fix ]][-noperms ][file... ]
```

DESCRIPTION

`news.daily` performs a number of important Usenet administrative functions. This includes producing a status report, removing old news articles, processing log files, rotating the archived log files, renumbering the active file, removing any old socket files found in the firewall directory, and collecting the output. This program should be run under the news administrator's ID, not as root.

By default, `news.daily` performs all its functions and mails the output to the news administrator, `usenet`. By specifying keywords on the command line, it is possible to modify the functions performed, as well as change the arguments given to `expire(8)` and `expireover(8)`.

`news.daily` should be run once a day, typically out of `cron(8)`. It may be run more often, but such invocations should at least use the `norotate` keyword to prevent the log files from being processed and rotated too fast.

The `shlock(1)` program is used to prevent simultaneous executions.

The following keywords may be used:

<code>delayrm</code>	This uses the <code>-z</code> flag when invoking <code>expire</code> and <code>expireover</code> . The names of articles to be removed are written to a temporary file and then removed after expiration by calling <code>expirerm</code> .

nostat	This keyword disables the status report generated by innstat (see <code>newslog(8)</code>). Without this keyword, the status report is the first function performed, just prior to obtaining the <code>news.daily</code> lock.
noexpire	By default, <code>expire</code> is invoked to remove old news articles. Using this keyword disables this function.
noexplog	<code>expire</code> usually appends information to <code>/var/log/news/expire.log</code> (see <code>newslog(5)</code>). Using this keyword causes the <code>expire</code> output to be handled as part of <code>news.daily</code> 's output. It has no effect if the <code>noexpire</code> keyword is used.
flags='expire\args'	By default, <code>expire</code> is invoked with the an argument of <code>-v1</code> . Using this keyword changes the arguments to those specified. Be careful to use quotes if multiple arguments are needed. This keyword has no effect if the <code>noexpire</code> keyword is used.
nologs	After expiration, <code>scanlogs(8)</code> is invoked to process the log files. Using this keyword disables all log processing functions.
norotate	By default, log processing includes rotating and cleaning out log files. Using this keyword disables the rotating and cleaning aspect of the log processing. The log files are only scanned for information and no contents are altered. This keyword has no effect if the <code>nologs</code> keyword is used.
norenumber	This keyword disables the <code>ctlinnd(8)</code> renumber operation. Usually, the low watermark for all newsgroups (see <code>active(5)</code>) is reset.
norm	By default, any socket <code>ctlinnd</code> socket that has not been modified for two days is removed. Using this keyword disables this function.
nomail	<code>news.daily</code> usually sends a mail message containing the results to the administrator. Using this keyword causes this message to be sent to <code>stdout</code> and <code>stderr</code> instead. Usually, all utilities invoked by the script have their <code>stdout</code> and <code>stderr</code> redirected into a file. If the file is empty, no message is sent.
expireover	The <code>expireover</code> program is called after expiration to purge the overview databases.
expireoverflags='expireovernargs'	If the <code>expireover</code> keyword is used, this keyword may be used to specify the flags to be passed to <code>expireover</code> . If the <code>delayrm</code> keyword is used, then the default value is <code>-z</code> and the list of deleted files; otherwise, the default value is <code>-s</code> .
/full/path	The program specified by the given path is executed just before any expiration is done. A typical use is to specify an alternate expiration program and use the <code>noexpire</code> keyword. Multiple programs may be specified; they are invoked in order.

The `norotate` keyword is passed on to `scanlogs` if it is invoked. `expirerm` is a script that removes a list of files. The specified file lists the files. It is sorted and then fed into a pipeline responsible for doing the removal, usually `fastrm(8)`. If there seemed to be a problem removing the files, then mail is sent to the news administrator. If there were no problems, then file is renamed to `/var/log/news/expire.list` where it is kept (for safety) until the next day's expiration.

`innwatch` is a script that can be started at news boot time. It periodically—every `sleeptime` seconds—examines the load average and the number of free blocks and inodes on the spool partition, as described by its control file, `innwatch.ct1(5)`. If the load gets too high or the disk gets too full, it throttles the server. When the condition restores, it unblocks the server. In addition, on each pass through the loop, it checks the specified log file to see if it has been modified and sends mail to the news administrator if so. It is usually a good idea to set this to the `syslog(3)` file that receives critical news messages. Upon receipt of an interrupt signal, `innwatch` reports its status in the file `/news/lib/innwatch.status`.

`inncheck` is a `perl(1)` script that verifies the syntax and permissions of all InterNetNews configuration files. If no files are specified, it checks all files. A filename may be followed by an equal sign and a path to indicate the pathname to use for the file. For example, `newsfeeds=/tmp/nf` checks the syntax of a new `newsfeeds(5)` without requiring it to be installed. If the `-v` flag is used, it prints status information as it checks each file. If the `-pedantic` flag is used, it checks the files for omissions that are not strictly errors but might indicate a configuration error.

If any file is specified, only the permissions on those files are checked. The `-noperms` flag suppresses this check. If the `-perms` flag is used, the script verifies the ownership and permissions of all files. The `-fix` flag can also be used so that the output can be executed as a shell script.

HISTORY

`news.daily` and this manual page were written by Landon Curt Noll (`chongo@toad.com`) and Rich \$alz (`rsalz@uunet.uu.net`).

`inncheck` was written by Brendan Kehoe (`brendan@cs.widener.edu`) and Rich.

`innwatch` was written by Mike Cooper (`mcooper@usc.edu`) and (`kre@munnari.oz.au`).

SEE ALSO

`active(5)`, `ctlinnd(8)`, `expire(8)`, `fastrm(8)`, `newslog(5)`, `newslog(8)`, `innwatch.ctl(5)`, `shlock(1)`

newslog

`newslog`—Maintenance of Usenet log files

SYNOPSIS

```
scanlogs [ norotate ][nonn ]
writelog name text...
innstat
tally.unwanted
tally.control
innlog.awk
```

DESCRIPTION

`scanlogs` summarizes the information recorded in the `INN` log files (see `newslog(5)`). By default, it also rotates and cleans out the logs. It is usually invoked by the `news.daily(8)` script.

The following keywords are accepted:

<code>norotate</code>	Using this keyword disables the rotating and cleaning aspect of the log processing: The logs files are only scanned for information and no contents are altered.
<code>nonn</code>	Usually, the <code>nn</code> log file is scanned and rotated. Using this keyword disables this function.

If `scanlogs` is invoked more than once a day, the `norotate` keyword should be used to prevent premature log cleaning.

The `writelog` script is used to write a log entry or send it as mail. The `name` parameter specifies the name of the log file where the entry should be written. If it is the word `mail`, then the entry is mailed to the news administrator, Usenet. The data that is written or sent consists of the text given on the command line, followed by standard input indented by four spaces.

`shlock(1)` is used to avoid simultaneous updates to a single log file.

The `innstat` script prints a snapshot of the `INN` system. It displays the operating mode of the server, as well as disk usage and the status of all log and lock files.

The rest of the scripts described here are usually invoked by `scanlogs`. They parse log files that are described in `newslog(5)` and the server's article log file described in `innd(8)`.

`tally.unwanted` script parses the article log file to update the cumulative list of articles posted to unwanted newsgroups, `unwanted.log`.

`tally.control` reads its standard input, which should be the `newgroup.log` and `rmgroup.log` log files. It updates the cumulative list of newsgroup creations and deletions, `control.log`.

`innlog.awk` is an `awk(1)` script that summarizes the activity that `innd` and `nnrpd(8)` report to `syslog`.

HISTORY

Written by Landon Curt Noll (`chongo@toad.com`) and Rich \$alz (`rsalz@uunet.uu.net`) for InterNetNews.

SEE ALSO

innd(8) newslog(5), news.daily(8), nnrpd(8)

nfsd

nfsd—NFS service daemon.

SYNOPSIS

```
/usr/etc/rpc.nfsd [-f\exports-file\][\-dhnpv\]
[\--debug\][\--exports-file=file\] [\--help\]
[\--allow-non-root\][\--re-export\][\--version\]
```

DESCRIPTION

The `nfsd` program is an NFS service daemon that handles client filesystem requests. Unlike `nfsd` on some other systems, `nfsd` operates as a normal user-level process. The server also differs from other NFS server implementations in that it mounts an entire file hierarchy not limited by the boundaries of physical filesystems. The implementation allows the clients read-only or read-write access to the file hierarchy of the server machine.

The `mountd` program starts an ancillary user-level mount daemon.

OPTIONS

<code>-f</code> or <code>--exports-file</code>	This option specifies the exports file, listing the clients that this server is prepared to serve and parameters to apply to each such mount (see <code>exports(5)</code>). By default, exports are read from <code>/etc/exports</code> .
<code>-d</code> or <code>--debug</code>	Log each transaction verbosely to the <code>syslog</code> .
<code>-h</code> or <code>--help</code>	Provide a short help summary.
<code>-n</code> or <code>--allow-non-root</code>	Allow incoming NFS requests to be honored even if they do not originate from reserved IP ports. Some older NFS client implementations require this. Some newer NFS client implementations don't believe in reserved port checking.
<code>-p</code> or <code>--promiscuous</code>	Put the server into promiscuous mode where it serves any host on the network.
<code>-r</code> or <code>--re-export</code>	Allow imported NFS filesystems to be exported. This can be used to turn a machine into an NFS multiplier. Caution should be used when re-exporting loopback NFS mounts because re-entering the mount point results in deadlock between the NFS client and the NFS server.
<code>-v</code> or <code>--version</code>	Report the current version number of the program.

SEE ALSO

`exports(5)`, `mountd(8)`, `ugidd(8C)`

AUTHORS

Mark Shand wrote the original `unfsd`. Don Becker extended `unfsd` to support authentication and allow read-write access and called it `hnfs`. Rick Sladkey added host matching, `showmount -e` support, `mountd` authentication, `inetd` support, and all the portability and configuration code.

13 October 1993

nnrpd

nnrpd—NNTP server for on-campus hosts.

SYNOPSIS

```
nnrpd [ -r reason ][-s title padding ][-S host ][-t ]
```

DESCRIPTION

nnrpd is an NNTP server for newsreaders. It accepts commands on its standard input and responds on its standard output. It is usually invoked by innd(8) with those descriptors attached to a remote client connection.

If the `-r` flag is used, then nnrpd rejects the incoming connection giving reason as the text. This flag is used by innd when it is paused or throttled.

Unlike innd, nnrpd supports all NNTP commands for user-oriented reading and posting.

nnrpd uses the `nnrp.access(5)` file to control who is authorized to access the Usenet database. It also rejects connections if the load average is greater than 16.

As each command is received, nnrpd tries to change its `argv` array so that `ps(1)` prints the command being executed. To get a full display, the `-s` flag may be used with a long string as its argument, which is overwritten when the program changes its title.

On exit, nnrpd reports usage statistics through `syslog(3)`.

If the `-t` flag is used, all client commands and initial responses are traced by reporting them in `syslog`. This flag is set by innd under the control of the `ctlinnd(8)` trace command and is toggled upon receipt of a `SIGHUP`; see `signal(2)`.

If the `-s` flag is used, all postings are forwarded to the specified host, which should be the master NNTP server. This flag is set by innd if it is started with the `-s` flag.

nnrpd can accept multimedia postings that follow the MIME standard as long as such postings are also acceptable as SMTP messages. See the discussion of the MIME headers in `inn.conf(5)`.

PROTOCOL DIFFERENCES

nnrpd implements the NNTP commands defined in RFC 977 with the following differences:

- The `ihave` command is not implemented. Users should be using the `post` command to post articles.
- The `slave` command is not implemented. This command has never been fully defined.
- The `list` command may be followed by the optional word `active.times`, `distributions`, `distrib.pats`, `newsgroups`, or `overview.fmt` to get a list of when newsgroups were created, a list of valid distributions, a file specifying default distribution patterns, a one-per-line description of the current set of newsgroups, or a listing of the `overview.fmt(5)` file. The command `list active` is equivalent to the `list` command. This is a common extension.
- The `xhdr`, `authinfo user`, and `authinfo pass` commands are implemented. These are based on the reference UNIX implementation; no other documentation is available.
- A new command, `xpat header range MessageID pat [morepat...]`, is provided. The first argument is the case-insensitive name of the header to be searched. The second argument is either an article range or a single Message-ID as specified in RFC 977. The third argument is a `wildmat(3)`-style pattern; if there are additional arguments, they are joined together separated by a single space to form the complete pattern. This command is similar to the `xhdr` command. It returns a 221 response code, followed by the text response of all article numbers that match the pattern.
- The `listgroup group` command is provided. This is a comment extension. It is equivalent to the `group` command, except that the reply is a multi-line response containing the list of all article numbers in the group.
- The `xgtitle [group]` command is provided. This extension is used by ANU-News. It returns a 282 reply code, followed by a one-line description of all newsgroups that match the pattern. The default is the current group.
- The `xover [range]` command is provided. It returns a 224 reply code, followed by the overview data for the specified range; the default is to return the data for the current article.
- The `xpath MessageID` command is provided; see `innd(8)`.
- The `date` command is provided; this is based on the draft NNTP protocol revision. It returns a one-line response code of 111 followed by the GMT date and time on the server in the form `YYYYMMDDhhmmss`.

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for InterNetNews. Overview support added by Rob Robertston (rob@violet.berkeley.edu) and Rich in January 1993.

SEE ALSO

ctlinnd(8), innd(8), inn.conf(5), nnrp.access(5), signal(2), wildmat(3)

nntpsend

nntpsend—Send Usenet articles to remote site.

SYNOPSIS

```
nntpsend [ -d ][ -p ][ -r ][ -S ][ -s size ][ -t timeout ]
[ -T timelimit ][ sitename fqdn ] ...
```

DESCRIPTION

nntpsend is a front end that invokes innxmit(1) to send Usenet articles to a remote NNTP site.

The sites to be fed may be specified by giving sitename fqdn pairs on the command line. If no such pairs are given, nntpsend defaults to the information given in the nntpsend.ct1(5) config file.

The sitename should be the name of the site as specified in the newsfeeds(5) file. The fqdn should be the hostname or IP address of the remote site. An innxmit is launched for sites with queued news. All innxmit processes are spawned in the background and the script waits for them all to finish before returning. Output is sent to the file /var/log/news/nntpsend.log. To avoid overwhelming the local system, nntpsend waits five seconds before spawning each child. The flag -a is always given as a flag to innxmit.

nntpsend expects that the batchfile for a site is named /news/spool/out.going/sitename. To prevent batchfile corruption, shlock(1) is used to “lock” these files.

The -p, -r, -s, -t, and -T flags are passed on to the child innxmit program. Note that if the -p flag is used then no connection is made and no articles are fed to the remote site. It is useful to have cron(8) invoke nntpsend with this flag in case a site cannot be reached for an extended period of time.

If the -s flag is used, then shrinkfile(1) is invoked to perform a tail truncation on the batchfile and the flag is passed to it.

When sitename fqdn pairs are given on the command line, any flags given on the command completely describe how innxmit and shrinkfile operate. When no such pairs are given on the command line, then the information found in nntpsend.ct1 becomes the default flags for that site. Any flags given on the command line override the default flags for the site.

For example, with the following control file:

```
nsavax:erehwon.nsavax.gov:: -S -t60
group70:group70.org::
walldrug:walldrug.com:1m: -T1800 -t300
```

The command

```
nntpsend
```

will result in the following:

Sitename	Truncation	Innxmit flags
nsavax	(none)	-a -S -t60
group70	(none)	-a -t180
walldrug	1m	-a -T1800 -t300

The command

```
nntpsend -d -T1200
```

will result in the following:

Sitename	Truncation	Innxmlt flags
nsavax	(none)	-a -d -S -T1200 -t60
group70	(none)	-a -d -T1200 -t180
walldrug	1m	-a -d -T1200 -t300

The command

```
nntpsend -s 5m -T1200 nsavax erehwon.nsavax.gov group70 group70.org
```

will result in the following:

Sitename	Truncation	Innxmlt flags
nsavax	5m	-a -T1200 -t180
group70	5m	-a -T1200 -t180

Remember that `-a` is always given, and `-t` defaults to 180.

HISTORY

Written by Landon Curt Noll (chongo@toad.com) and Rich \$alz (rsalz@uunet.uu.net) for InterNetNews.

SEE ALSO

`innxmlt(1)`, `newsfeeds(5)`, `nntpsend.ctl(5)`, `shrinkfile(1)`

nslookup

nslookup—Query Internet nameservers interactively.

SYNOPSIS

```
nslookup [ -option ... ] [ host-to-find ] -[server ]
```

DESCRIPTION

nslookup is a program to query Internet domain nameservers. nslookup has two modes: interactive and non-interactive.

Interactive mode allows the user to query nameservers for information about various hosts and domains or to print a list of hosts in a domain. Non-interactive mode is used to print just the name and requested information for a host or domain.

ARGUMENTS

Interactive mode is entered in the following cases:

- When no arguments are given (the default nameserver is used)
- When the first argument is a hyphen (-) and the second argument is the hostname or Internet address of a nameserver

Non-interactive mode is used when the name or Internet address of the host to be looked up is given as the first argument. The optional second argument specifies the host name or address of a nameserver.

The options listed under the set command can be specified in the `.nslookuprc` file in the user's home directory if they are listed one per line. Options can also be specified on the command line if they precede the arguments and are prefixed with a hyphen. For example, to change the default query type to host information, and the initial timeout to 10 seconds, type:

```
nslookup -query=hinfo -timeout=10
```

INTERACTIVE COMMANDS

Commands may be interrupted at any time by typing Ctrl+C. To exit, type Ctrl+D (EOF) or type `exit`. The command-line length must be less than 256 characters. To treat a built-in command as a hostname, precede it with an escape character (`\`). Note that an unrecognized command is interpreted as a hostname.

<code>host [server]</code>	Look up information for host using the current default server or using <code>server</code> if specified. If <code>host</code> is an Internet address and the query type is <code>A</code> or <code>PTR</code> , the name of the host is returned. If <code>host</code> is a name and does not have a trailing period, the default domain name is appended to the name. (This behavior depends on the state of the <code>set options domain, srchlist, defname, and search</code>). To look up a host not in the current domain, append a period to the name.										
<code>server domain, lserver domain</code>	Change the default server to <code>domain</code> . <code>lserver</code> uses the initial server to look up information about <code>domain</code> , whereas <code>server</code> uses the current default server. If an authoritative answer can't be found, the names of servers that might have the answer are returned.										
<code>root</code>	Changes the default server to the server for the root of the domain name space. Currently, the host <code>ns.internic.net</code> is used. (This command is a synonym for <code>lserver ns.internic.net</code> .) The name of the root server can be changed with the <code>set root</code> command.										
<code>finger [name][> filename], finger [name][>> filename]</code>	Connects with the finger server on the current host. The current host is defined when a previous lookup for a host was successful and returned address information (see the <code>set query-type= A</code> command). <code>name</code> is optional. <code>></code> and <code>>></code> can be used to redirect output in the usual manner.										
<code>ls [option] domain [> filename], ls [option] domain [>> filename]</code>	List the information available for <code>domain</code> , optionally creating or appending to <code>filename</code> . The default output contains hostnames and their Internet addresses. <code>option</code> can be one of the following: <table> <tr> <td><code>-t querytype</code></td><td>Lists all records of the specified type (see <code>querytype</code>).</td></tr> <tr> <td><code>-a</code></td><td>Lists aliases of hosts in the domain. Synonym for <code>-t CNAME</code>.</td></tr> <tr> <td><code>-d</code></td><td>Lists all records for the domain. Synonym for <code>-t ANY</code>.</td></tr> <tr> <td><code>-h</code></td><td>Lists CPU and operating system information for the domain. Synonym for <code>-t HINFO</code>.</td></tr> <tr> <td><code>-s</code></td><td>Lists well-known services of hosts in the domain. Synonym for <code>-t WKS</code>. When output is directed to a file, hash marks are printed for every 50 records received from the server.</td></tr> </table>	<code>-t querytype</code>	Lists all records of the specified type (see <code>querytype</code>).	<code>-a</code>	Lists aliases of hosts in the domain. Synonym for <code>-t CNAME</code> .	<code>-d</code>	Lists all records for the domain. Synonym for <code>-t ANY</code> .	<code>-h</code>	Lists CPU and operating system information for the domain. Synonym for <code>-t HINFO</code> .	<code>-s</code>	Lists well-known services of hosts in the domain. Synonym for <code>-t WKS</code> . When output is directed to a file, hash marks are printed for every 50 records received from the server.
<code>-t querytype</code>	Lists all records of the specified type (see <code>querytype</code>).										
<code>-a</code>	Lists aliases of hosts in the domain. Synonym for <code>-t CNAME</code> .										
<code>-d</code>	Lists all records for the domain. Synonym for <code>-t ANY</code> .										
<code>-h</code>	Lists CPU and operating system information for the domain. Synonym for <code>-t HINFO</code> .										
<code>-s</code>	Lists well-known services of hosts in the domain. Synonym for <code>-t WKS</code> . When output is directed to a file, hash marks are printed for every 50 records received from the server.										
<code>view filename</code>	Sorts and lists the output of previous <code>ls</code> commands with <code>more(1)</code> .										
<code>help, ?</code>	Prints a brief summary of commands.										
<code>exit</code>	Exits the program.										
<code>set keyword[=value]</code>	This command is used to change state information that affects the lookups. Valid keywords are:										
<code>all</code>	Prints the current values of the frequently used options to <code>set</code> . Information about the current default server and host is also printed.										
<code>class=value</code>	Change the query class to one of the following: <table> <tr> <td><code>IN</code></td><td>The Internet class.</td></tr> <tr> <td><code>CHAOS</code></td><td>The Chaos class.</td></tr> </table>	<code>IN</code>	The Internet class.	<code>CHAOS</code>	The Chaos class.						
<code>IN</code>	The Internet class.										
<code>CHAOS</code>	The Chaos class.										

	HESIOD	The MIT Athena Hesiod class.
	ANY	Wildcard (any of the above).
	The class specifies the protocol group of the information. (Default = IN, abbreviation = cl.)	
[no]debug	Turn debugging mode on. A lot more information is printed about the packet sent to the server and the resulting answer. (Default = nodebug, abbreviation = [no]deb.)	
[no]d2	Turn exhaustive debugging mode on. Essentially, all fields of every packet are printed. (Default = nod2.)	
domain=name	Change the default domain name to name. The default domain name is appended to a lookup request depending on the state of the defname and search options. The domain search list contains the parents of the default domain if it has at least two components in its name. For example, if the default domain is CC.Berkeley.EDU, the search list is CC.Berkeley.EDU and Berkeley.EDU. Use the set srchlist command to specify a different list. Use the set all command to display the list. (Default = value from hostname, /etc/resolv.conf, or LOCALDO-MAIN, abbreviation = do.)	
srchlist=name1/name2/...	Change the default domain name to name1 and the domain search list to name1, name2, and so on. A maximum of six names separated by slashes (/) can be specified. For example, set srchlist=1cs.MIT.EDU/ai.MIT.EDU/MIT.EDU sets the domain to 1cs.MIT.EDU and the search list to the three names. This command overrides the default domain name and search list of the set domain command. Use the set all command to display the list. (Default = value based on hostname, /etc/resolv.conf, or LOCAL-DOMAIN, abbreviation = srchl.)	
[no]defname	If set, append the default domain name to a single-component lookup request (that is, one that does not contain a period). (Default = defname, abbreviation = [no]def.)	
[no]search	If the lookup request contains at least one period but doesn't end with a trailing period, append the domain names in the domain search list to the request until an answer is received. (Default = search, abbreviation = [no]sea.)	
port=value	Change the default TCP/UDP nameserver port to value. (Default = 53, abbreviation = po.)	
querytype=value, type=value	Change the type of information query to one of the following:	
	A	The host's Internet address.
	CNAME	The canonical name for an alias.
	HINFO	The host CPU and operating system type.
	MINFO	The mailbox or mail list information.
	MX	The mail exchanger.
	NS	The nameserver for the named zone.
	PTR	The host name if the query is an Internet address; otherwise, the pointer to other information.
	SOA	The domain's "start-of-authority" information.
	TXT	The text information.
	UINFO	The user information.
	WKS	The supported well-known services.
	Other types (ANY, AXFR, MB, MD, MF, NULL) are described in the RFC-1035 document. (Default = A, abbreviations = q, ty.)	
[no]recurse	Tell the nameserver to query other servers if it does not have the information. (Default = recurse, abbreviation = [no]rec.)	
retry=number	Set the number of retries to number. When a reply to a request is not received within a certain amount of time (changed with set timeout), the timeout period is doubled and the request is resent. The retry value controls how many times a request is resent before giving up. (Default = 4, abbreviation = ret.)	

<code>root=host</code>	Change the name of the root server to <code>host</code> . This affects the <code>root</code> command. (Default = <code>ns.internic.net</code> , abbreviation = <code>ro</code> .)
<code>timeout=number</code>	Change the initial timeout interval for waiting for a reply to <code>number</code> seconds. Each retry doubles the timeout period. (Default = 5 seconds, abbreviation = <code>ti</code> .)
<code>[no]vc</code>	Always use a virtual circuit when sending requests to the server. (Default = <code>novc</code> , abbreviation = <code>[no]v</code> .)
<code>[no]ignoretc</code>	Ignore packet truncation errors. (Default = <code>noignoretc</code> , abbreviation = <code>[no]ig</code> .)

DIAGNOSTICS

If the lookup request was not successful, an error message is printed. Possible errors are

Timed out	The server did not respond to a request after a certain amount of time (changed with <code>set timeout=value</code>) and a certain number of retries (changed with <code>set retry=value</code>).
No response from server	No nameserver is running on the server machine.
No records	The server does not have resource records of the current query type for the host, although the hostname is valid. The query type is specified with the <code>set querytype</code> command.
Non-existent domain	The host or domain name does not exist.
Connection refused, Network is unreachable	The connection to the name or finger server could not be made at the current time. This error commonly occurs with <code>ls</code> and <code>finger</code> requests.
Server failure	The nameserver found an internal inconsistency in its database and could not return a valid answer.
Refused	The nameserver refused to service the request.
Format error	The nameserver found that the request packet was not in the proper format. It may indicate an error in <code>nslookup</code> .

FILES

<code>/Etc/Resolv.conf</code>	Initial domain name and nameserver addresses.
<code>\$HOME/.nslookuprc</code>	User's initial options.
<code>/usr/share/misc/nslookup.help</code>	Summary of commands.

ENVIRONMENT

<code>HOSTALIASES</code>	File containing host aliases.
<code>LOCALDOMAIN</code>	Overrides default domain.

SEE ALSO

`resolver(3)`, `resolver(5)`, `named(8)`, RFC 1034 "Domain Names – Concepts and Facilities," RFC 1035 "Domain Names – Implementation and Specification"

AUTHOR

Andrew Cherenon

24 June 1990

overchan

overchan—Update the news overview database.

SYNOPSIS

```
overchan [ -D dir ] [-c ][file... ]
```

DESCRIPTION

overchan reads article data from files or standard input if none are specified. (A single dash in the file list means to read standard input.) It uses this information to update the news overview database. overchan is designed to be used by InterNetNews or the C News mkov packages to update the database as the articles come in. The database for each newsgroup is stored in a file named .overview in a newsgroup directory within the overview database tree.

overchan locks the database file (by locking an auxiliary file) before appending the new data. To purge data after articles have been expired, see expireover(8).

By default, overchan processes its input as an INN overview stream written as a WO entry in the newsfeeds(5) file:

```
overview:*:Tc,W0:/news/bin/overchan
```

This data consists of a line of text separated into two parts by a tab. The first part is a list of all relative pathnames where the article has been written with a single space between entries. The second part is the data to be written into the overview file, except that the initial article number is omitted.

To process the output of the mkov(8) program, use the -c flag. This format is described in the nov distribution.

The -D flag can be used to specify where the databases are stored. The default directory is /news/spool.

HISTORY

Written by Rob Robertson (rob@violet.berkeley.edu) and Rich Salz (rsalz@uunet.uu.net) for InterNetNews.

SEE ALSO

newsfeeds(5), newsoverview(5), newsoverview(8)

pac

pac—Printer/plotter accounting information.

SYNOPSIS

```
pac [-P printer] [-c] [-m] [-p price] [-s] [-r] [name ...]
```

DESCRIPTION

pac reads the printer/plotter accounting files, accumulating the number of pages (the usual case) or feet (for raster devices) of paper consumed by each user and printing how much each user consumed in pages or feet and dollars.

Options and operands available:

-P printer	Accounting is done for the named printer. Usually, accounting is done for the default printer (site dependent), or the value of the environment variable PRINTER is used.
-c	Flag causes the output to be sorted by cost; usually, the output is sorted alphabetically by name.
-m	Flag causes the hostname to be ignored in the accounting file. This allows for a user on multiple machines to have all his printing charges grouped together.
-p price	The value price is used for the cost in dollars instead of the default value of 0.02 or the price specified in /etc/printcap.
-r	Reverse the sorting order.
-s	Accounting information is summarized on the summary accounting file; this summarization is necessary because on a busy system, the accounting file can grow by several lines per day.

names

Statistics are only printed for users named; usually, statistics are printed for every user who has used any paper.

FILES

<code>/var/account/?acct</code>	Raw accounting files
<code>/var/account/?_sum</code>	Summary accounting files
<code>/etc/printcap</code>	Printer capability database

SEE ALSO

`printcap(5)`

BUGS

The relationship between the computed price and reality is as yet unknown.

HISTORY

The `pac` command appeared in BSD 4.0.

BSD 4.2, 16 March 1991

pcnfsd

pcnfsd—(PC)NFS authentication and print request server

SYNOPSIS

`/usr/etc/rpc.pcnfsd`

AVAILABILITY

This program is freely redistributable.

DESCRIPTION

pcnfsd is an RPC server that supports ONC clients on PC (DOS, OS/2, Macintosh, and other) systems. This page describes version 2 of the pcnfsd server.

`rpc.pcnfsd` may be started from `/etc/rc.local` or by the `inetd(8)` superdaemon. It reads the configuration file `/etc/pcnfsd.conf` if present and then services RPC requests directed to program number 150001. This release of the pcnfsd daemon supports both version 1 and version 2 of the pcnfsd protocol. Consult the `rpcgen` source file `pcnfsd.x` for details of the protocols.

The requests serviced by pcnfsd fall into three categories: authentication, printing, and other. Only the authentication and printing services have administrative significance.

AUTHENTICATION

When pcnfsd receives a PCNFSD AUTH or PCNFSD2 AUTH request, it “logs in” the user by validating the username and password and returning the corresponding UID, GIDs, home directory, and `umask`. If pcnfsd was built with the `WTMP` compile-time option, it also appends a record to the `wtmp(5)` database. If you do not want to record PC logins in this way, you should add a line of the form

```
wtmp off
```

to the `/etc/pcnfsd.conf` file.

By default, pcnfsd only allows authentication or print requests for users with UIDs in the range 101 to 60002. (This corresponds in `SVR4` to the range for non-system accounts.) To override this, you may add a line of the form

```
uidrange range[,range]...
```

to the `/etc/pcnfsd.conf` file. Here, each `range` is of the form `uid` or `uid-uid`, indicating an inclusive range.

PRINTING

`pcnfsd` supports a printing model based on the use of NFS to transfer the actual print data from the client to the server. The client system issues a `PCNFSD_PR_INIT` or `PCNFSD2_PR_INIT` request, and the server returns the path to a spool directory that the client may use and which is exported by NFS. `pcnfsd` creates a subdirectory for each of its clients: The parent directory is usually `/usr/spool/pcnfs` and the subdirectory is the hostname of the client system. If you want to use a different parent directory, you should add a line of the form

```
spooldir path
```

to the `/etc/pcnfsd.conf` file.

Once a client has mounted the spool directory using NFS and has transferred print data to a file in this directory, it issues a `PCNFSD_PR_START` or `PCNFSD2_PR_START` request. `pcnfsd` handles this, and most other print-related requests, by constructing a command based on the printing services of the server operating system and executing the command using the identity of the PC user. Because this involves set-user-ID privileges, `pcnfsd` must be run as root.

Every print request from the client includes the name of the printer that is to be used. In Linux, this name corresponds to a printer definition in the `/etc/printcap(5)` database. If you want to define a non-standard way of processing print data, you should define a new printer and arrange for the client to print to this printer. There are two ways of setting up a new printer. The first involves the addition of an entry to `/etc/printcap(5)` and the creation of filters to perform the required processing. This is outside the scope of this discussion. In addition, `pcnfsd` includes a mechanism by which you can define virtual printers known only to `pcnfsd` clients. Each printer is defined by a line in the `/etc/pcnfsd.conf` file of the following form:

```
printer name alias-for command
```

`name` is the name of the printer you want to define. `alias-for` is the name of a “real” printer that corresponds to this printer. For example, a request to display the queue for `name` is translated into the corresponding request for the printer `alias-for`. If you have defined a printer in such a way that there is no “real” printer to which it corresponds, use a single `.` for this field. (See the definition of the printer `test` for an example.) `command` is a command that will be executed whenever a file is printed on `name`. This command is executed by the shell at `/bin/sh` using the `-c` option. For complex operations, you should construct an executable shell program and invoke that in `command`.

Consider the following sample `/etc/pcnfsd.conf` file:

```
printer rotated lw /usr/local/bin/enscript -2r $FILE
printer test . /usr/bin/cp $FILE/usr/tmp/$HOST$USER
```

If a client system prints a job on the printer `rotated`, the utility `enscript` is invoked to pre-process the file `$FILE`. In this case, the `-2r` option causes the file to be printed in two-column rotated format on the default PostScript printer. If the client requests a list of the print queue for the printer `rotated`, the `pcnfsd` daemon translates this into a request for a listing for the printer `lw`.

The printer `test` is used only for testing. Any file sent to this printer is copied into `/usr/tmp`. Any request to list the queue, check the status, and so on of printer `test` is rejected because the `alias-for` is specified as `.`.

RECONFIGURATION

pcnfsd detects when printers are added or deleted and rebuilds its list of valid printers. To do this, it checks the modification time of `/etc/printcap`. However, it does not monitor the file `/etc/pcnfsd.conf` for updates; if you change this file, it is still necessary to kill and restart `pcnfsd` so the changes can take effect.

FILE

`/etc/pcnfsd.conf`

SEE ALSO

`lpr(1)`, `lprm(1)`, `lpc(8)`, `lpq(1)`

25 June 1995

plipconfig

plipconfig—Fine-tune PLIP device parameters.

SYNOPSIS

```
plipconfig interface
plipconfig interface [nibble NN] [trigger NN] [unit NN]
```

DESCRIPTION

`plipconfig` is used to improve PLIP performance by changing the default timing parameters used by the PLIP protocol. Results are dependent on the parallel port hardware, cable, and the CPU speed of each machine on each end of the PLIP link.

If the single `interface` argument is given, `plipconfig` displays the status of the given interface only. Otherwise, it tries to set the options.

OPTIONS

<code>nibble NN</code>	Sets the nibble wait value in microseconds. Default is 3000 .
<code>trigger NN</code>	Sets the trigger wait value in microseconds. Default is 500 .
<code>unit NN</code>	Sets the number of units of delay. Default is 1 .

In some cases, PLIP speed can be improved by lowering the default values. Values that are too low might cause excess use of CPU, poor interrupt response time resulting in serial ports dropping characters, or in dropping PLIP packets. Changing the `plip` MTU can also affect PLIP speed.

SEE ALSO

`ifconfig(8)`

BUGS

None so far.

AUTHOR

John Paul Morrison (jmorriso@bogomips.ee.ubc.ca, ve7jpm@ve7jpm.ampr.org)

1 July 1994

ping

ping—Send ICMP ECHO_REQUEST packets to network hosts.

SYNOPSIS

```
/etc/ping [ -r ][ -v ] host [ packetsize ][count ]
```

DESCRIPTION

The DARPA Internet is a large and complex aggregation of network hardware, connected together by gateways. Tracking a single-point hardware or software failure can often be difficult. Ping utilizes the ICMP protocol's mandatory ECHO_REQUEST datagram to elicit an ICMP ECHO_RESPONSE from a host or gateway. ECHO_REQUEST datagrams ("pings") have an IP and ICMP header, followed by a struct timeval and then an arbitrary number of "pad" bytes used to fill out the packet. Default datagram length is 64 bytes, but this may be changed using the command-line option. Other options are

- r Bypass the normal routing tables and send directly to a host on an attached network. If the host is not on a directly attached network, an error is returned. This option can be used to ping a local host through an interface that has no route through it (for example, after the interface was dropped by routed(8C)).
- v Verbose output. ICMP packets other than ECHO_RESPONSE that are received are listed.

When using ping for fault isolation, it should first be run on the local host to verify that the local network interface is up and running. Then, hosts and gateways further away should be pinged. Ping sends one datagram per second and prints one line of output for every ECHO_RESPONSE returned. No output is produced if there is no response. If an optional count is given, only that number of requests is sent. Round-trip times and packet-loss statistics are computed. When all responses have been received or the program times out (with a count specified), or if the program is terminated with a SIGINT, a brief summary is displayed.

This program is intended for use in network testing, measurement, and management. It should be used primarily for manual fault isolation. Because of the load it could impose on the network, it is unwise to use ping during normal operations or from automated scripts.

AUTHOR

Mike Muuss

SEE ALSO

netstat(1), ifconfig(8)

19 September 1988

portmap

portmap—DARPA port to RPC program number mapper.

SYNOPSIS

```
portmap [ -d ]
```

DESCRIPTION

portmap is a server that converts RPC program numbers into DARPA protocol port numbers. It must be running in order to make RPC calls.

When an RPC server is started, it tells portmap what port number it is listening to and what RPC program numbers it is prepared to serve. When a client wants to make an RPC call to a given program number, it first contacts portmap on the server machine to determine the port number where RPC packets should be sent.

portmap must be started before any RPC servers are invoked.

Usually, portmap forks and dissociates itself from the terminal like any other daemon. Portmap then logs errors using `syslog(3)`.

Option available:

`-d` (debug) prevents portmap from running as a daemon and causes errors and debugging information to be printed to the standard error output.

SEE ALSO

`inetd.conf(5)`, `rpcinfo(8)`, `inetd(8)`

BUGS

If portmap crashes, all servers must be restarted.

HISTORY

The portmap command appeared in BSD 4.3.

BSD 4.3, 16 March 1991

powerd

powerd—Monitor a serial line connected to a UPS.

SYNOPSIS

`/etc/powerd serial-device`

DESCRIPTION

powerd is a daemon process that sits in the background and monitors the state of the DCD line of the serial device. It is meant that this line is connected to a UPS (Uninterruptible Power Supply) so that it knows about the state of the UPS. As soon as powerd senses that the power is failing (it sees that DCD goes low) it notifies `init(8)` and `init` executes the `powerwait` and `powerfail` entries. If powerd senses that the power has been restored, it notifies `init` again and `init` executes the `powerokwait` entries.

ARGUMENTS

`serial-device`

Some serial port that is not being used by some other device and does not share an interrupt with any other serial port.

DIAGNOSTICS

powerd regularly checks the DSR line to see if it's high. DSR should be directly connected to DTR and powerd keeps that line high, so if DSR is low, something is wrong with the connection. powerd notifies you about this fact every two minutes. When it sees that the connection is restored, it will say so.

IMPLEMENTATION

It's pretty simple to connect your UPS to the Linux machine. The steps are easy:

1. Make sure you have an UPS with a simple relais output: it should close its connections (make) if the power is gone, and it should open its connections (break) if the power is good.
2. Buy a serial plug. Connect the DTR line to the DSR line directly. Connect the DTR line and the DCD line with a 10 kilo ohm resistor. Connect the relais-output of the UPS to GROUND and the DCD line. If you don't know what pins DSR, DTR, DCD and GROUND are, you can always ask at the store where you bought the plug.
3. You're all set.

BUGS

Well, it's not a real bug but `powerd` should be able to do a broadcast or something on the Ethernet in case more Linux-boxes are connected to the same UPS and only one of them is connected to the UPS status line.

SEE ALSO

`shutdown(8)`, `init(8)`, `inittab(5)`

AUTHOR

Miquel van Smoorenburg (miquels@drinkel.nl.mugnet.org)

14 February 1994

pppd

`pppd`—Point-to-Point Protocol daemon.

SYNOPSIS

```
pppd [ tty_name ][speed ][options ]
```

DESCRIPTION

The Point-to-Point Protocol (PPP) provides a method for transmitting datagrams over serial point-to-point links. PPP is composed of three parts: a method for encapsulating datagrams over serial links, an extensible Link Control Protocol (LCP), and a family of Network Control Protocols (NCP) for establishing and configuring different network-layer protocols.

The encapsulation scheme is provided by driver code in the kernel. `pppd` provides the basic LCP, authentication support, and an NCP for establishing and configuring the Internet Protocol (IP) (called the IP Control Protocol, IPCP).

FREQUENTLY USED OPTIONS

<code>tty_name</code>	Communicate over the named device. The string <code>/dev/</code> is prepended if necessary. If no device name is given, or if the name of the controlling terminal is given, <code>pppd</code> uses the controlling terminal and does not fork to put itself in the background.
<code>speed</code>	Set the baud rate to <code>speed</code> (a decimal number). On systems such as 4.4BSD and NetBSD, any speed can be specified. Other systems (such as SunOS) allow only a limited set of speeds.
<code>asyncmap map</code>	Set the async character map to <code>map</code> . This map describes which control characters cannot be successfully received over the serial line. <code>pppd</code> asks the peer to send these characters as a 2-byte escape sequence. The argument is a 32-bit hex number with each bit representing a character to escape. Bit 0 (<code>00000001</code>) represents the character <code>0x00</code> ; bit 31 (<code>80000000</code>) represents the character <code>0x1f</code> or <code>^</code> . If multiple <code>asyncmap</code> options are given, the values are <code>ored</code> together. If no <code>asyncmap</code> option is given, no async character map is negotiated for the receive direction; the peer should then escape all control characters.
<code>auth</code>	Require the peer to authenticate itself before allowing network packets to be sent or received.
<code>connect p</code>	Use the executable or shell command specified by <code>p</code> to set up the serial line. This script typically uses the <code>chat(8)</code> program to dial the modem and start the remote PPP session.
<code>crtcts</code>	Use hardware flow control (that is, RTS/CTS) to control the flow of data on the serial port. If neither the <code>crtcts</code> nor the <code>-crtcts</code> option is given, the hardware flow control setting for the serial port is left unchanged.
<code>defaultroute</code>	Add a default route to the system routing tables, using the peer as the gateway, when IPCP negotiation is successfully completed. This entry is removed when the PPP connection is broken.

<code>disconnect p</code>	Run the executable or shell command specified by <code>p</code> after <code>pppd</code> has terminated the link. This script could, for example, issue commands to the modem to cause it to hang up if hardware modem control signals were not available.
<code>escape xx,yy,...</code>	Specifies that certain characters should be escaped on transmission (regardless of whether the peer requests them to be escaped with its async control character map). The characters to be escaped are specified as a list of hex numbers separated by commas. Note that almost any character can be specified for the escape option, unlike the <code>asynctest</code> option, which only allows control characters to be specified. The characters that cannot be escaped are those with hex values <code>0x20</code> - <code>0x3f</code> or <code>0x5e</code> .
<code>file f</code>	Read options from file <code>f</code> (the format is described later).
<code>lock</code>	Specifies that <code>pppd</code> should create a UUCP-style lock file for the serial device to ensure exclusive access to the device.
<code>mrul n</code>	Set the MRU (Maximum Receive Unit) value to <code>n</code> for negotiation. <code>pppd</code> asks the peer to send packets of no more than <code>n</code> bytes. The minimum MRU value is 128. The default MRU value is 1500. A value of 296 is recommended for slow links (40 bytes for TCP/IP header plus 256 bytes of data).
<code>mtu n</code>	Set the MTU (Maximum Transmit Unit) value to <code>n</code> . Unless the peer requests a smaller value via MRU negotiation, <code>pppd</code> requests that the kernel networking code send data packets of no more than <code>n</code> bytes through the PPP network interface.
<code>netmask n</code>	Set the interface netmask to <code>n</code> , a 32-bit netmask in decimal dot notation (such as 255.255.255.0). If this option is given, the value specified is ORed with the default netmask. The default netmask is chosen based on the negotiated remote IP address; it is the appropriate network mask for the class of the remote IP address ORed with the netmasks for any non-point-to-point network interfaces in the system that are on the same network.
<code>passive</code>	Enables the passive option in the LCP. With this option, <code>pppd</code> attempts to initiate a connection; if no reply is received from the peer, <code>pppd</code> then waits passively for a valid LCP packet from the peer (instead of exiting as it does without this option).
<code>silent</code>	With this option, <code>pppd</code> does not transmit LCP packets to initiate a connection until a valid LCP packet is received from the peer (as for the passive option with ancient versions of <code>pppd</code>).

OPTIONS

<code>local IP address:remote IP address</code>	Set the local and/or remote interface IP addresses. Either one may be omitted. The IP addresses can be specified with a host name or in decimal dot notation (such as 150.234.56.78). The default local address is the (first) IP address of the system (unless the <code>noipdefault</code> option is given). The remote address is obtained from the peer if not specified in any option. Thus, in simple cases, this option is not required. If a local and/or remote IP address is specified with this option, <code>pppd</code> does not accept a different value from the peer in the IPCP negotiation, unless the <code>ipcp-accept-local</code> and/or <code>ipcp-accept-remote</code> options are given.
<code>-ac</code>	Disable Address/Control compression negotiation (use default, address/control field compression disabled).
<code>-all</code>	Don't request or allow negotiation of any options for LCP and IPCP (use default values).
<code>-am</code>	Disable <code>asynctest</code> negotiation (use the default <code>asynctest</code> ; that is, escape all control characters).
<code>-as n</code>	Same as <code>asynctest n</code> .

<code>bsdcomp nr,nt</code>	Request that the peer compress packets that it sends, using the BSD-Compress scheme, with a maximum code size of <code>nr</code> bits and agree to compress packets sent to the peer with a maximum code size of <code>nt</code> bits. If <code>nt</code> is not specified, it defaults to the value given for <code>nr</code> . Values in the range 9 to 15 may be used for <code>nr</code> and <code>nt</code> ; larger values give better compression but consume more kernel memory for compression dictionaries. Alternatively, a value of 0 for <code>nr</code> or <code>nt</code> disables compression in the corresponding direction.
<code>-bsdcomp</code>	Disables compression; <code>pppd</code> does not request or agree to compress packets using the BSD-Compress scheme.
<code>+chap</code>	Require the peer to authenticate itself using CHAP (Cryptographic Handshake Authentication Protocol) authentication.
<code>-chap</code>	Don't agree to authenticate using CHAP.
<code>chap-interval n</code>	If this option is given, <code>pppd</code> rechallenges the peer every <code>n</code> seconds.
<code>chap-max-challenge n</code>	Set the maximum number of CHAP challenge transmissions to <code>u</code> (default is 10).
<code>chap-restart n</code>	Set the CHAP restart interval (retransmission timeout for challenges) to <code>n</code> seconds (default is 3).
<code>-crtcts</code>	Disable hardware flow control (RTS/CTS) on the serial port. If neither the <code>crtcts</code> nor the <code>-crtcts</code> option is given, the hardware flow control setting for the serial port is left unchanged.
<code>-d</code>	Increase debugging level (same as the <code>debug</code> option).
<code>debug</code>	Increase debugging level (same as <code>-d</code>). If this option is given, <code>pppd</code> logs the contents of all control packets sent or received in a readable form. The packets are logged through <code>syslog</code> with facility daemon and level debug. This information can be directed to a file by setting up <code>/etc/syslog.conf</code> appropriately (see <code>syslog.conf(5)</code>).
<code>-defaultroute</code>	Disable the <code>defaultroute</code> option. The system administrator who wants to prevent users from creating default routes with <code>pppd</code> can do so by placing this option in the <code>/etc/ppp/options</code> file.
<code>-detach</code>	Don't fork to become a background process (otherwise, <code>pppd</code> will do so if a serial device other than its controlling terminal is specified).
<code>dns-addr n</code>	This option sets the IP address or addresses for the Domain Name Server. It is used by Microsoft Windows clients. The primary DNS address is specified by the first instance of the <code>dns-addr</code> option. The secondary is specified by the second instance.
<code>domain d</code>	Append the domain name <code>d</code> to the local hostname for authentication purposes. For example, if <code>gethost-name()</code> returns the name <code>porsche</code> , but the fully qualified domain name is <code>porsche.Quotron.COM</code> , you use the <code>domain</code> option to set the domain name to <code>Quotron.COM</code> .
<code>-ip</code>	Disable IP address negotiation. If this option is used, the remote IP address must be specified with an option on the command line or in an options file.
<code>+ip-protocol</code>	Enable the IPCP and IP protocols. This is the default condition. This option is only needed if the default setting is <code>-ip-protocol</code> .
<code>-ip-protocol</code>	Disable the IPCP and IP protocols. This should only be used if you know you are using a client that only understands IPX and you don't want to confuse the client with the IPCP protocol.
<code>+ipx-protocol</code>	Enable the IPXCP and IPX protocols. This is the default condition if your kernel supports IPX. This option is only needed if the default setting is <code>-ipx-protocol</code> . If your kernel does not support IPX, this option has no effect.

<code>-ipx-protocol</code>	Disable the IPXCP and IPX protocols. This should only be used if you know you are using a client that only understands IP and you don't want to confuse the client with the IPXCP protocol.
<code>ipcp-accept-local</code>	With this option, <code>pppd</code> accepts the peer's idea of a local IP address, even if the local IP address was specified in an option.
<code>ipcp-accept-remote</code>	With this option, <code>pppd</code> accepts the peer's idea of its (remote) IP address, even if the remote IP address was specified in an option.
<code>ipcp-max-configure n</code>	Set the maximum number of IPCP configure-request transmissions to <code>n</code> (default is 10).
<code>ipcp-max-failure n</code>	Set the maximum number of IPCP configure-NAKs returned before starting to send configure-Rejects instead to <code>n</code> (default is 10).
<code>ipcp-max-terminate n</code>	Set the maximum number of IPCP terminate-request transmissions to <code>n</code> (default is 3).
<code>ipcp-restart n</code>	Set the IPCP restart interval (retransmission timeout) to <code>n</code> seconds (default is 3).
<code>ipparam string</code>	Provides an extra parameter to the <code>ip-up</code> and <code>ip-down</code> scripts. If this option is given, the <code>string</code> supplied is given as the sixth parameter to those scripts.
<code>ipx-network n</code>	Set the IPX network number in the IPXCP configure request frame to <code>n</code> . There is no valid default. If this option is not specified, the network number is obtained from the peer. If the peer does not have the network number, the IPX protocol is not started. This is a hexadecimal number and is entered without any leading sequence such as <code>0x</code> . It is related to the <code>ipxcp-accept-network</code> option.
<code>ipx-node n:m</code>	Set the IPX node numbers. The two node numbers are separated from each other with a colon character. The first number <code>n</code> is the local node number. The second number <code>m</code> is the peer's node number. Each node number is a hexadecimal number to the maximum of ten significant digits. The node numbers on the <code>ipx-network</code> must be unique. There is no valid default. If this option is not specified, the node number is obtained from the peer. This option is related to the <code>ipxcp-accept-local</code> and <code>ipxcp-accept-remote</code> options.
<code>ipx-router-name string</code>	Set the name of the router. This is a string and is sent to the peer as information data.
<code>ipx-routing n</code>	Set the routing protocol to be received by this option. More than one instance of <code>ipx-routing</code> may be specified. The <code>none</code> option (0) may be specified as the only instance of <code>ipx-routing</code> . The values are 0 for none, 2 for RIP/SAP, and 4 for NLSP.
<code>ipxcp-accept-local</code>	Accept the peer's NAK for the node number specified in the <code>ipx-node</code> option. If a node number was specified and it is nonzero, the default is to insist that the value be used. If you include this option, you permit the peer to override the entry of the node number.
<code>ipxcp-accept-network</code>	Accept the peer's NAK for the network number specified in the <code>ipx-network</code> option. If a network number was specified and it is nonzero, the default is to insist that the value be used. If you include this option, you permit the peer to override the entry of the node number.
<code>ipxcp-accept-remote</code>	Use the peer's network number specified in the configure request frame. If a node number was specified for the peer and this option was not specified, the peer is forced to use the value that you specified.
<code>ipxcp-max-configure n</code>	Set the maximum number of IPXCP configure request frames that the system sends to <code>n</code> . The default is 10.

<code>ipxcp-max-failure n</code>	Set the maximum number of IPXCP NAK frames that the local system sends before it rejects the options. The default value is 3.
<code>ipxcp-max-terminate n</code>	Set the maximum number of IPXCP terminate request frames before the local system considers that the peer is not listening to them. The default value is 3.
<code>kdebug n</code>	Enable debugging code in the kernel-level PPP driver. The argument <i>n</i> is a number that is the sum of the following values: 1 to enable general debug messages, 2 to request that the contents of received packets be printed, and 4 to request that the contents of transmitted packets be printed.
<code>lcp-echo-failure n</code>	If this option is given, <code>pppd</code> presumes the peer is dead if <i>n</i> LCP echo-requests are sent without receiving a valid LCP echo-reply. If this happens, <code>pppd</code> terminates the connection. Use of this option requires a nonzero value for the <code>lcp-echo-interval</code> parameter. This option can be used to enable <code>pppd</code> to terminate after the physical connection has been broken (for example, the modem has hung up) in situations where no hardware modem control lines are available.
<code>lcp-echo-interval n</code>	If this option is given, <code>pppd</code> sends an LCP echo-request frame to the peer every <i>n</i> seconds. Under Linux, the echo-request is sent when no packets are received from the peer for <i>n</i> seconds. Usually, the peer should respond to the echo-request by sending an echo-reply. This option can be used with the <code>lcp-echo-failure</code> option to detect that the peer is no longer connected.
<code>lcp-max-configure n</code>	Set the maximum number of LCP configure-request transmissions to <i>n</i> (default is 10).
<code>lcp-max-failure n</code>	Set the maximum number of LCP configure-NAKs returned before starting to send configure-Rejects instead to <i>n</i> (default is 10).
<code>lcp-max-terminate n</code>	Set the maximum number of LCP terminate-request transmissions to <i>n</i> (default is 3).
<code>lcp-restart n</code>	Set the LCP restart interval (retransmission timeout) to <i>n</i> seconds (default is 3).
<code>local</code>	Don't use the modem control lines. With this option, <code>pppd</code> ignores the state of the CD (Carrier Detect) signal from the modem and does not change the state of the DTR (Data Terminal Ready) signal.
<code>login</code>	Use the system password database for authenticating the peer using PAP, and record the user in the system <code>wtmp</code> file.
<code>modem</code>	Use the modem control lines. This option is the default. With this option, <code>pppd</code> waits for the CD (Carrier Detect) signal from the modem to be asserted when opening the serial device (unless a connect script is specified), and it drops the DTR (Data Terminal Ready) signal briefly when the connection is terminated and before executing the connect script. On Ultrix, this option implies hardware flow control, as for the <code>crtsets</code> option.
<code>-mn</code>	Disable magic number negotiation. With this option, <code>pppd</code> cannot detect a looped-back line.
<code>-mru</code>	Disable MRU (MaximumReceive Unit) negotiation. With this option, <code>pppd</code> uses the default MRU value of 1500 bytes.
<code>name n</code>	Set the name of the local system for authentication purposes to <i>n</i> .
<code>noipdefault</code>	Disables the default behavior when no local IP address is specified, which is to determine (if possible) the local IP address from the hostname. With this option, the peer must supply the local IP address during IPCP

	negotiation (unless it specified explicitly on the command line or in an options file).
-p	Same as the passive option.
+pap	Require the peer to authenticate itself using PAP.
-pap	Don't agree to authenticate using PAP.
papcrypt	Indicates that all secrets in the <code>/etc/ppp/pap-secrets</code> file, which are used for checking the identity of the peer, are encrypted, and thus <code>pppd</code> should not accept a password (before encryption) that is identical to the secret from the <code>/etc/ppp/pap-secrets</code> file.
pap-max-authreq n	Set the maximum number of PAP authenticate-request transmissions to <code>n</code> (default is 10).
pap-restart n	Set the PAP restart interval (retransmission timeout) to <code>n</code> seconds (default is 3).
pap-timeout n	Set the maximum time that <code>pppd</code> waits for the peer to authenticate itself with PAP to <code>n</code> seconds (0 means no limit).
-pc	Disable protocol field compression negotiation (use default, protocol field compression disabled).
persist	Do not exit after a connection is terminated; instead, try to reopen the connection.
pred1comp	Attempt to request that the peer send the local system frames, which have been compressed by the Predictor-1 compression. The compression protocols must be loaded or this option is ignored.
-pred1comp	Do not accept Predictor-1 compression, even if the peer wants to send this type of compression and support has been defined in the kernel.
proxyarp	Add an entry to this system's ARP (Address Resolution Protocol) table with the IP address of the peer and the Ethernet address of this system.
-proxyarp	Disable the proxyarp option. The system administrator who wants to prevent users from creating proxy ARP entries with <code>pppd</code> can do so by placing this option in the <code>/etc/ppp/options</code> file.
remotename n	Set the assumed name of the remote system for authentication purposes to <code>n</code> .
+ua p	Agree to authenticate using PAP (Password Authentication Protocol) if requested by the peer and use the data in file <code>p</code> for the user and password to send to the peer. The file contains the remote username, followed by a newline, followed by the remote password, followed by a newline. This option is obsolescent.
usehostname	Enforce the use of the hostname as the name of the local system for authentication purposes (overrides the <code>name</code> option).
user u	Set the username to use for authenticating this machine with the peer using PAP to <code>u</code> .
-vj	Disable negotiation of Van Jacobson-style TCP/IP header compression (use default, no compression).
-vjccomp	Disable the connection-ID compression option in Van Jacobson style TCP/IP header compression. With this option, <code>pppd</code> does not omit the connection-ID byte from Van Jacobson compressed TCP/IP headers or ask the peer to do so.
vj-max-slots n	Sets the number of connection slots to be used by the Van Jacobson TCP/IP header compression and decompression code to <code>n</code> , which must be between 2 and 16 (inclusive).

xonxoff

Use software flow control (XON/XOFF) to control the flow of data on the serial port. This option is only implemented on Linux systems at present.

OPTIONS FILES

Options can be taken from files as well as the command line. `pppd` reads options from the files `/etc/ppp/options` and `~/.ppprc` before looking at the command line. An options file is parsed into a series of words, delimited by whitespace. Whitespace can be included in a word by enclosing the word in quotes (`"`). A backslash (`\`) quotes the following character. A hash (`#`) starts a comment, which continues until the end of the line.

AUTHENTICATION

`pppd` provides system administrators with sufficient access control so that PPP access to a server machine can be provided to legitimate users without fear of compromising the security of the server or the network it's on. In part, this is provided by the `/etc/ppp/options` file, where the administrator can place options to require authentication whenever `pppd` is run, and in part by the PAP and CHAP secrets files, where the administrator can restrict the set of IP addresses that individual users can use.

The default behavior of `pppd` is to agree to authenticate if requested and to not require authentication from the peer. However, `pppd` does not agree to authenticate itself with a particular protocol if it has no secrets that can be used to do so.

Authentication is based on secrets, which are selected from secrets files (`/etc/ppp/pap-secrets` for PAP, `/etc/ppp/chap-secrets` for CHAP). Both secrets files have the same format, and both can store secrets for several combinations of server (authenticating peer) and client (peer being authenticated). Note that `pppd` can be both a server and client and that different protocols can be used in the two directions if desired.

A secrets file is parsed into words as for an options file. A secret is specified by a line containing at least three words, in the order client name, server name, and secret. Any following words on the same line are taken to be a list of acceptable IP addresses for that client. If there are only three words on the line, it is assumed that any IP address is okay; to disallow all IP addresses, use `-`. If the secret starts with an `@`, what follows is assumed to be the name of a file from which to read the secret. A `*` as the client or server name matches any name. When selecting a secret, `pppd` takes the best match—that is, the match with the fewest wildcards.

A secrets file contains both secrets for use in authenticating other hosts and secrets that you use for authenticating yourself to others. Which secret to use is chosen based on the names of the host (the local name) and its peer (the remote name). The local name is set as follows:

If the <code>usehostname</code> option is given,	The local name is the hostname of this machine (with the domain appended, if given).
If the <code>name</code> option is given	Use the argument of the first <code>name</code> option seen.
If the local IP address is specified with a hostname	Use that name. Otherwise, use the hostname of this machine (with the domain appended, if given).

When authenticating yourself using PAP, there is also a username, which is the local name by default, but can be set with the `user` option or the `+ua` option.

The remote name is set as follows:

If the <code>remotename</code> option is given	Use the argument of the last <code>remote-name</code> option seen.
If the remote IP address is specified with a hostname	Use that host name. Otherwise, the remote name is the null string <code>""</code> .

Secrets are selected from the PAP secrets file as follows:

- For authenticating the peer, look for a secret with `client == username` specified in the PAP `authenticate-request` and `server == local name`.
- For authenticating yourself to the peer, look for a secret with `client == your username` and `server == remote name`.

When authenticating the peer with PAP, a secret of "" matches any password supplied by the peer. If the password doesn't match the secret, the password is encrypted using `crypt()` and checked against the secret again; thus secrets for authenticating the peer can be stored in encrypted form. If the `papcrypt` option is given, the first (unencrypted) comparison is omitted for better security.

If the `login` option was specified, the username and password are also checked against the system password database. Thus, the system administrator can set up the `pap-secrets` file to allow PPP access only to certain users and to restrict the set of IP addresses that each user can use. Typically, when using the `login` option, the secret in `/etc/ppp/pap-secrets` is "" to avoid the need to have the same secret in two places.

Secrets are selected from the CHAP secrets file as follows:

- For authenticating the peer, look for a secret with `client == name` specified in the CHAP-Response message and `server == local name`.
- For authenticating yourself to the peer, look for a secret with `client == local name` and `server == name` specified in the CHAP-Challenge message.

Authentication must be satisfactorily completed before IPCP (or any other Network Control Protocol) can be started. If authentication fails, `pppd` terminates the link (by closing LCP). If IPCP negotiates an unacceptable IP address for the remote host, IPCP is closed. IP packets can only be sent or received when IPCP is open.

In some cases, it is desirable to allow some hosts that can't authenticate themselves to connect and use one of a restricted set of IP addresses, even when the local host generally requires authentication. If the peer refuses to authenticate itself when requested, `pppd` takes that as equivalent to authenticating with PAP using the empty string for the username and password. Thus, by adding a line to the `pap-secrets` file, which specifies the empty string for the client and password, it is possible to allow restricted access to hosts that refuse to authenticate themselves.

ROUTING

When IPCP negotiation is completed successfully, `pppd` informs the kernel of the local and remote IP addresses for the PPP interface. This is sufficient to create a host route to the remote end of the link, which enables the peers to exchange IP packets. Communication with other machines generally requires further modification to routing tables and/or ARP (Address Resolution Protocol) tables. In some cases, this is done automatically through the actions of the routed or gated daemons, but in most cases, some further intervention is required.

Sometimes it is desirable to add a default route through the remote host, as in the case of a machine whose only connection to the Internet is through the PPP interface. The `defaultroute` option causes `pppd` to create such a default route when IPCP comes up and delete it when the link is terminated.

In some cases, it is desirable to use proxy ARP—for example, on a server machine connected to a LAN—to allow other hosts to communicate with the remote host. The `proxyarp` option causes `pppd` to look for a network interface on the same subnet as the remote host (an interface supporting broadcast and ARP, which is up and not a point-to-point or loopback interface). If found, `pppd` creates a permanent, published ARP entry with the IP address of the remote host and the hardware address of the network interface found.

EXAMPLES

In the simplest case, you can connect the serial ports of two machines and issue a command like

```
pppd /dev/ttya 9600 passive
```

to each machine, assuming there is no `getty` running on the serial ports. If one machine has a `getty` running, you can use `kermit` or `tip` on the other machine to log in to the first machine and issue a command like

```
pppd passive
```

Then exit from the communications program (making sure the connection isn't dropped) and issue a command like

```
pppd /dev/ttya 9600
```

The process of logging in to the other machine and starting `pppd` can be automated by using the `connect` option to run `chat`:

```
pppd /dev/ttya 38400 connect 'chat "" "" "login:" "username"
"Password:" "pass-word" "% " "exec pppd passive'
```

(Note, however, that running `chat` like this leaves the password visible in the parameter list of `pppd` and `chat`.)

If your serial connection is any more complicated than a piece of wire, you might need to arrange for some control characters to be escaped. In particular, it is often useful to escape XON (^Q) and XOFF (^S), using `asynmap a0000`. If the path includes a telnet, you probably should escape ^] as well (`asynmap 200a0000`). If the path includes an `rlogin`, you need to use the escape `ff` option on the end that is running the `rlogin` client because many `rlogin` implementations are not transparent; they remove the sequence (0xff, 0xff, 0x73, 0x73, followed by any 8 bytes) from the stream.

DIAGNOSTICS

Messages are sent to the `syslog` daemon using the facility `LOG_DAEMON`. (This can be overridden by recompiling `pppd` with the macro `LOG_PPP` defined as the desired facility.) To see the error and debug messages, you need to edit your `/etc/syslog.conf` file to direct the messages to the desired output device or file.

The `debug` option causes the contents of all control packets sent or received to be logged—that is, all LCP, PAP, CHAP, or IPCP packets. This can be useful if the PPP negotiation does not succeed. If debugging is enabled at compile time, the `debug` option also causes other debugging messages to be logged.

Debugging can also be enabled or disabled by sending a `SIGUSR1` to the `pppd` process. This signal acts as a toggle.

FILES

`/var/run/pppn.pid` (BSD or Linux)

`/etc/ppp/pppn.pid` (others)

`/etc/ppp/ip-up`

Process-ID for `pppd` process on PPP interface unit `n`.

A program or script that is executed when the link is available for sending and receiving IP packets (that is, IPCP has come up). It is executed with the parameters `interface-name tty-device speed local-IP-address remote-IP-address` and with its standard input, output and error streams redirected to `/dev/null`.

This program or script is executed with the same real and effective user-ID as `pppd`—that is, at least the effective user-ID and possibly the real user-ID will be root. This is so that it can be used to manipulate routes, run privileged daemons (such as `send-mail`), and so on. Be careful that the contents of the `/etc/ppp/ip-up` and `/etc/ppp/ip-down` scripts do not compromise your system's security.

`/etc/ppp/ip-down`

A program or script that is executed when the link is no longer available for sending and receiving IP packets. This script can be used for undoing the effects of the `/etc/ppp/ip-up` script. It is invoked with the same parameters as the `ip-up` script, and the same security considerations apply because it is executed with the same effective and real user-IDs as `pppd`.

`/etc/ppp/ipx-up`

A program or script that is executed when the link is available for sending and receiving IPX packets (that is, IPXCP has come up). It is executed with the parameters `interface-name tty-device speed network-number local-IPX-node-address remote-IPX-node-address local-IPX-routing-protocol remote-IPX-routing-protocol local-IPX-router-name remote-IPX-router-name ipparam pppd-pid` and with its standard input, output, and error streams redirected to `/dev/null`.

The `local-IPX-routing-protocol` and `remote-IPX-routing-protocol` field may be one of the following:

	NONE to indicate that there is no routing protocol. RIP to indicate that RIP/SAP should be used. NLSP to indicate that Novell NLSP should be used. RIP NLSP to indicate that both RIP/SAP and NLSP should be used.
	This program or script is executed with the same real and effective user-ID as <code>pppd</code> —that is, at least the effective user-ID and possibly the real user-ID will be root. This is so that it can be used to manipulate routes, run privileged daemons (such as <code>ripd</code>), and so on. Be careful that the contents of the <code>/etc/ppp/ix-up</code> and <code>/etc/ppp/ix-down</code> scripts do not compromise your system's security.
<code>/etc/ppp/ix-down</code>	A program or script that is executed when the link is no longer available for sending and receiving IPX packets. This script can be used for undoing the effects of the <code>/etc/ppp/ix-up</code> script. It is invoked with the same parameters as the <code>ix-up</code> script, and the same security considerations apply because it is executed with the same effective and real user-IDs as <code>pppd</code> .
<code>/etc/ppp/pap-secrets</code>	Username, password, and IP addresses for PAP authentication.
<code>/etc/ppp/chap-secrets</code>	Names, secrets, and IP addresses for CHAP authentication.
<code>/etc/ppp/options</code>	System default options for <code>pppd</code> , read before user default options or command-line options.
<code>~/.ppprc</code>	User default options, read before command-line options.
<code>/etc/ppp/options.ttyname</code>	System default options for the serial port being used, read after command-line options.

SEE ALSO

RFC 1144	Jacobson, V. Compressing TCP/IP headers for low-speed serial links. February 1990.
RFC 1321	Rivest, R. The MD5 Message-Digest Algorithm. April 1992.
RFC 1332	McGregor, G. PPP Internet Protocol Control Protocol (IPCP). May 1992.
RFC 1334	Lloyd, B.; Simpson, W.A. PPP authentication protocols. 1992 October.
RFC 1548	Simpson, W.A. The Point-to-Point Protocol (PPP). December 1993.
RFC 1549	Simpson, W.A. PPP in HDLC Framing. December 1993.

NOTES

The following signals have the specified effect when sent to the `pppd` process:

SIGINT, SIGTERM	These signals cause <code>pppd</code> to terminate the link (by closing LCP), restore the serial device settings, and exit.
SIGHUP	This signal causes <code>pppd</code> to terminate the link, restore the serial device settings, and close the serial device. If the <code>persist</code> option has been specified, <code>pppd</code> tries to reopen the serial device and start another connection. Otherwise, <code>pppd</code> exits.
SIGUSR2	This signal causes <code>pppd</code> to renegotiate compression. This can be useful to re-enable compression after it has been disabled as a result of a fatal decompression error. With the BSD Compress scheme, fatal decompression errors generally indicate a bug in one or another implementation.

AUTHORS

Drew Perkins, Brad Clements, Karl Fox, Greg Christy, Brad Parker, and Paul Mackerras (paulus@cs.anu.edu.au)

pppstats

pppstats—Print PPP statistics.

SYNOPSIS

```
pppstats [ -v ][-r ][-c ][-i secs][unit# ]
```

DESCRIPTION

pppstats prints PPP-related statistics.

The `-v` flag causes pppstats to display additional statistics, such as the number of packets tossed (that is, which the VJ TCP header decompression code rejected).

The `-r` flag causes pppstats to display the overall packet compression rate. The rate value is between 0 and 1, with 0 meaning that the data is incompressible.

The `-c` flag is used to specify an alternate display mode that shows packet compression statistics: the number of packets and bytes uncompressed (that is, before compression or after decompression), compressed, and incompressible (packets that did not shrink on compression and were transmitted uncompressed), and the recent compression rate. This rate reflects the recent performance of the compression code rather than the overall rate the code compression was enabled.

The `-i` flag is used to specify the interval between printouts. The default is 5 seconds.

`unit#` specifies which interface to use for gathering statistics.

2 May 1995

prunehistory

prunehistory—Remove filenames from Usenet history file.

SYNOPSIS

```
prunehistory [ -f filename ][-p ][input ]
```

DESCRIPTION

prunehistory modifies the `history(5)` text file to remove a set of filenames from it. The filenames are removed by overwriting them with spaces so that the size and position of any following entries do not change.

prunehistory reads the named input file or standard input if no file is given. The input is taken as a set of lines. Blank lines and lines starting with a number sign (#) are ignored. All other lines should consist of a Message-ID followed by zero or more filenames. prunehistory usually complains about lines that do not follow this format. If the `-p` flag is used, then the program silently prints any invalid lines on its standard output. (Blank lines and comment lines are also passed through.) This can be useful when prunehistory is used as a filter for other programs such as `reap`.

The Message-ID is used as the `dbz(3)` key to get an offset into the text file. If no filenames are mentioned on the input line, then all filenames in the text are removed. If any filenames are mentioned, they are converted into the history file notation. If they appear in the line for the specified Message-ID, they are removed.

The default name of the history file is `/news/lib/history`; to specify a different name, use the `-f` flag.

Because `innd(8)` only appends to the text file, prunehistory does not need to have any interaction with it.

It is a good idea to delete purged entries and rebuild the `dbz` database every so often by using a script such as the following:

```
ctlinnd throttle "Rebuilding history database"
cd /news/lib
awk 'NF > 2 {
printf "%s\t%s\t%s", $1, $2, $3;
for (i = 4; i <= NF; i++)
printf " %s", $i;
print "\n";
}' <history >history.n
if makehistory -r -f history.n ; then
```

```

mv history.n history
mv history.n.pag history.pag
mv history.n.dir history.dir
else
echo 'Problem rebuilding history; old file not replaced'
fi
ctlinnd go "Rebuilding history database"

```

Note that this keeps no record of expired articles.

HISTORY

Written by Rich Salz (rsalz@uunet.uu.net) for InterNetNews.

SEE ALSO

dbz(3), history(5), innd(8)

quotacheck

quotacheck—Scan a filesystem for disk usages.

SYNOPSIS

```

quotacheck [-g] [-u] [-v] -a
quotacheck [-g] [-u] [-v] filesystems ...

```

DESCRIPTION

quotacheck performs a filesystem scan for usage of files and directories, used by either user or group. The output is the quota file for the corresponding filesystem. By default, the names for these files are

A user scan	quota.user
A group scan	quota.group

The resulting file consists of a struct dqblk for each possible ID up to the highest existing UID or GID and contains the values for the disk file and block usage and possibly excess time for these values. (For definitions of struct dqblk, see linux/quota.h.)

quotacheck should be run each time the system boots and mounts non-valid filesystems. This is most likely to happen after a system crash.

The speed of the scan decreases with the amount of directories increasing. The time needed doubles when disk usage is doubled as well. A 100MB partition used for 94 percent is scanned in one minute; the same partition used for 50 percent is done in 25 seconds.

OPTIONS

-v	This way, the program will give some useful information about what it is doing, plus some fancy stuff.
-d	This means debug. It will result in a lot of information that can be used in debugging the program. The output is very verbose and the scan will not be fast.
-u	This flag tells the program to scan the disk and to count the files and directories used by a certain UID. This is the default action.
-g	This flag forces the program to count the files and directories used by a certain GID.

NOTE

checkquota should only be run as superuser. Non-privileged users are presumably not allowed to read all the directories on the given filesystem.

SEE ALSO

quota(1), quotactl(2), fstab(5), quotaon(8), quotaoff(8), edquota(8), repquota(8), fsck(8), efsck(8), e2fsck(8), xfsck(8)

FILES

quota.user
 quota.group
 /etc/fstab

AUTHOR

Edvard Tuinder (v892231@si.hhs.nl, etuinder@delirium.nl.mugnet.org), Marco van Wieringen (v892273@si.hhs.nl, mvw@mcsl.nl.mugnet.org).

21 August 1993

quotaon, quotaoff

quotaon, quotaoff—Turn filesystem quotas on and off.

SYNOPSIS

```
/usr/etc/quotaon [ -vug ] filesystem...
/usr/etc/quotaon [ -avug ]

/usr/etc/quotaoff [ -vug ] filesystem...
/usr/etc/quotaoff [ -avug ]
```

DESCRIPTION

quotaon announces to the system that disk quotas should be enabled on one or more filesystems. The filesystem quota files must be present in the root directory of the specified filesystem and be named quota.user for user quota or quota.group for group quota.

quotaoff announces to the system that filesystems specified should have any disk quotas turned off.

OPTIONS

quotaon

-a	All filesystems in <i>/etc/fstab</i> marked read-write with quotas will have their quotas turned on. This is usually used at boot time to enable quotas.
-v	Display a message for each filesystem where quotas are turned on.
-u	Manipulate user quotas. This is the default.
-g	Manipulate group quotas.

quotaoff

-a	Force all filesystems in <i>/etc/fstab</i> to have their quotas disabled.
-v	Display a message for each filesystem affected.
-u	Manipulate user quotas. This is the default.
-g	Manipulate group quotas.

FILES

quota.user	User quota file at the filesystem root
quota.group	Group quota file at the filesystem root
/etc/fstab	Default filesystems

SEE ALSO

quotactl(2), fstab(5)

8 June 1993

rarp

rarp—Manipulate the system RARP table.

SYNOPSIS

```
rarp [-v] [-t type] -a [hostname]
rarp [-v] -d hostname ...
rarp [-v] [-t type] -s hostname hw_addr
```

DESCRIPTION

rarp manipulates the kernel's RARP table in various ways. The primary options are clearing an address mapping entry and manually setting up one. For debugging purposes, the rarp program also allows a complete dump of the RARP table.

OPTIONS

-v	Tell the user what is going on by being verbose.
-t type	When setting or reading the RARP table, this optional parameter tells rarp which class of entries it should check for. The default value of this parameter is ether (hardware code 0x01 for IEEE 802.3 10Mbps Ethernet). Other values might include network technologies such as AX.25 (ax25).
-a [hostname]	Shows the entries of the specified hosts. If the hostname parameter is not used, all entries are displayed.
-d hostname	Remove the entries of the specified host. This can be used if the indicated host is brought down, for example.
-s hostname hw_addr	Create an RARP address mapping entry for host hostname with hardware address set to hw_addr class, but for most classes, you can assume that the usual presentation can be used. For the Ethernet class, this is 6 bytes in hexadecimal, separated by colons.

FILES

/proc/net/rarp

AUTHORS

Ross D. Martin (martin@trcsun3.eas.asu.edu), Fred N. van Kempen (waltje@uwalt.nl.mugnet.org).

11 June 1994

rdev

rdev—Query/set image root device, swap device, RAM disk size, or video mode.

SYNOPSIS

```
rdev [ -rsvh ] [ -o offset ][image [ value [ offset ]]]
rdev [ -o offset ][image [ root_device [ offset ]]]
swapdev [ -o offset ][image [ swap_device [ offset ]]]
ramsize [ -o offset ][image [ size [ offset ]]]
vidmode [ -o offset ][image [ mode [ offset ]]]
rootflags [ -o offset ][image [ flags [ offset ]]]
```

DESCRIPTION

With no arguments, `rdev` outputs an `/etc/mtab` line for the current root filesystem. With no arguments, `swapdev`, `ramsize`, `vidmode`, and `rootflags` print usage information.

In a bootable image for the Linux kernel, there are several pairs of bytes that specify the root device, the video mode, the size of the RAM disk, and the swap device. These pairs of bytes, by default, begin at offset 504 (decimal) in the kernel image:

- 498 Root flags
- (500 and 502 Reserved)
- 504 RAM Disk Size
- 506 VGA Mode
- 508 Root Device
- (510 Boot Signature)

`rdev` changes these values.

Typical values for the image parameter, which is a bootable Linux kernel image, are as follows:

```
/vmlinux
/vmlinux.test
/vmunix
/vmunix.test
/dev/fd0
/dev/fd1
```

When using the `rdev` or `swapdev` commands, the root device or swap device parameter are as follows:

```
/dev/hda[1-8]
/dev/hdb[1-8]
/dev/sda[1-8]
/dev/sdb[1-8]
```

For the `ramsize` command, the `size` parameter specifies the size of the RAM disk in kilobytes.

For the `rootflags` command, the `flags` parameter contains extra information used when mounting root. Currently, the only effect of these flags is to force the kernel to mount the root filesystem in read-only mode if `flags` is nonzero.

For the `vidmode` command, the `mode` parameter specifies the video mode:

-3	Prompt
-2	Extended VGA
-1	Normal VGA
0	As if 0 was pressed at the prompt
1	As if 1 was pressed at the prompt
2	As if 2 was pressed at the prompt
n	As if n was pressed at the prompt

If the value is not specified, the image is examined to determine the current settings.

OPTIONS

-s	Causes <code>rdev</code> to act like <code>swapdev</code> .
-r	Causes <code>rdev</code> to act like <code>ramsize</code> .
-R	Causes <code>rdev</code> to act like <code>rootflags</code> .
-v	Causes <code>rdev</code> to act like <code>vidmode</code> .
-h	Provides help.

BUGS

For historical reasons, there are two methods for specifying alternative values for the offset.

The user interface is cumbersome, non-intuitive, and should probably be rewritten from scratch, allowing multiple kernel image parameters to be changed or examined with a single command.

If LILO is used, `rdev` is no longer needed for setting the root device and the VGA mode because the parameters that `rdev` modifies can be set from the LILO prompt during a boot. However, `rdev` is still needed at this time for setting the RAM disk size. Users are encouraged to find the LILO documentation for more information and to use LILO when booting their systems.

AUTHORS

Originally by Werner Almesberger (almesber@nessie.cs.id.ethz.ch). Modified by Peter MacDonald (pmacdona@sanjuan.UVic.CA). `rootflags` support added by Stephen Tweedie (sct@dcs.ed.ac.uk).

Linux 0.99, 20 November 1993

renice

`renice`—Alter priority of running processes.

SYNOPSIS

```
renice priority [[-p] pid ...] [[-g] pgrp ...] [[-u] user ...]
```

DESCRIPTION

`renice` alters the scheduling priority of one or more running processes. The following “who” parameters are interpreted as process IDs, process group IDs, or user names. `renice`ing a process group causes all processes in the process group to have their scheduling priority altered. `renice`ing a user causes all processes owned by the user to have their scheduling priority altered. By default, the processes to be affected are specified by their process IDs.

Options supported by `renice`:

<code>-g</code>	Force who parameters to be interpreted as process group IDs.
<code>-u</code>	Force the who parameters to be interpreted as usernames.
<code>-p</code>	Reset the who interpretation to be (the default) process IDs.

The following example changes the priority of process IDs 987 and 32 and all processes owned by users `daemon` and `root`:

```
renice +1 987 -u daemon root -p 32
```

Users other than the superuser can only alter the priority of processes they own and can only monotonically increase their “nice value” within the range 0 to `PRIO_MAX` (20). (This prevents overriding administrative fiats.) The superuser can alter the priority of any process and set the priority to any value in the range `PRIO_MIN` (-20) to `PRIO_MAX`. Useful priorities are: 20 (the affected processes run only when nothing else in the system wants to), 0 (the “base” scheduling priority), and anything negative (to make things go very fast).

FILES

`/etc/passwd` to map usernames to user IDs

SEE ALSO

`getpriority(2)`, `setpriority(2)`

BUGS

Non-superusers cannot increase scheduling priorities of their own processes, even if they were the ones that decreased the priorities in the first place.

HISTORY

The `renice` command appeared in BSD 4.0.

BSD 4, 9 June 1993

repquota

`repquota`—Summarize quotas for a filesystem.

SYNOPSIS

```
/usr/etc/repquota [ -vug ] filesystem...
/usr/etc/repquota [ -avug ]
```

DESCRIPTION

`repquota` prints a summary of the disk usage and quotas for the specified filesystems. For each user, the current number of files and amount of space (in kilobytes) is printed, along with any quotas created with `edquota(8)`.

OPTIONS

<code>-a</code>	Report on all filesystems indicated in <code>/etc/fstab</code> to be read-write with quotas.
<code>-v</code>	Report all quotas even if there is no usage.
<code>-g</code>	Report quotas for groups.
<code>-u</code>	Report quotas for users. This is the default.

Only the superuser can view quotas that are not their own.

FILES

<code>quotas</code>	Quota file at the filesystem root
<code>/etc/fstab</code>	Default filesystems

SEE ALSO

`quota(1)`, `quotactl(2)`, `edquota(8)`, `quotacheck(8)`, `quotaon(8)`

8 June 1993

rexecd

`rexecd`—Remote execution server.

SYNOPSIS

```
rexecd
```

DESCRIPTION

`rexecd` is the server for the `rexec(3)` routine. The server provides remote execution facilities with authentication based on usernames and passwords.

`rexecd` listens for service requests at the port indicated in the `exec` service specification; see `services(5)`. When a service request is received, the following protocol is initiated:

1. The server reads characters from the socket up to a null `\0` byte. The resultant string is interpreted as an ASCII number, base 10.

2. If the number received in Step 1 is nonzero, it is interpreted as the port number of a secondary stream to be used for the `stderr`. A second connection is then created to the specified port on the client's machine.
3. A null-terminated username of at most 16 characters is retrieved on the initial socket.
4. A null-terminated, unencrypted password of at most 16 characters is retrieved on the initial socket.
5. A null-terminated command to be passed to a shell is retrieved on the initial socket. The length of the command is limited by the upper bound on the size of the system's argument list.
6. `rexecd` then validates the user as is done at login time and, if the authentication was successful, changes to the user's home directory and establishes the user and group protections of the user. If any of these steps fail, the connection is aborted with a diagnostic message returned.
7. A null byte is returned on the initial socket and the command line is passed to the normal login shell of the user. The shell inherits the network connections established by `rexecd`.

DIAGNOSTICS

Except for the last one listed, all diagnostic messages are returned on the initial socket, after which any network connections are closed. An error is indicated by a leading byte with a value of 1 (0 is returned in Step 7 upon successful completion of all the steps prior to the command execution).

username too long	The name is longer than 16 characters.
password too long	The password is longer than 16 characters.
command too long	The command line passed exceeds the size of the argument list (as configured into the system).
Login incorrect.	No password file entry for the username existed or the wrong password was supplied.
No remote directory.	The <code>chdir</code> command to the home directory failed.
Try again.	A fork by the server failed.
<shellname>: ...	The user's login shell could not be started. This message is returned on the connection associated with the <code>stderr</code> and is not preceded by a flag byte.

SEE ALSO

`rexec(3)`

BUGS

A facility to allow all data and password exchanges to be encrypted should be present.

HISTORY

The `rexecd` command appeared in BSD 4.2.

BSD 4.2, 16 March 1991

rlogind

`rlogind`—Remote login server.

SYNOPSIS

`rlogind [-aln]`

DESCRIPTION

`rlogind` is the server for the `rlogin(1)` program. The server provides a remote login facility with authentication based on privileged port numbers from trusted hosts.

Options supported by `rlogin`:

-a	Ask hostname for verification.
-1	Prevent any authentication based on the user's .rhosts file unless the user is logging in as the superuser.
-n	Disable keep-alive messages.

rlogind listens for service requests at the port indicated in the “login” service specification; see `services(5)`. When a service request is received, the following protocol is initiated:

1. The server checks the client's source port. If the port is not in the range 512-1023, the server aborts the connection.
2. The server checks the client's source address and requests the corresponding hostname (see `gethostbyaddr(3)`, `hosts(5)`, and `named(8)`). If the hostname cannot be determined, the dot-notation representation of the host address is used. If the hostname is in the same domain as the server (according to the last two components of the domain name), or if the `-a` option is given, the addresses for the hostname are requested, verifying that the name and address correspond. Normal authentication is bypassed if the address verification fails.

Once the source port and address have been checked, `rlogind` proceeds with the authentication process described in `rshd(8)`. It then allocates a pseudo terminal (see `pty(4)`) and manipulates file descriptors so that the slave half of the pseudo terminal becomes the `stdin`, `stdout`, and `stderr` for a login process. The login process is an instance of the `login(1)` program, invoked with the `-f` option if authentication has succeeded. If automatic authentication fails, the user is prompted to log in as if on a standard terminal line.

The parent of the login process manipulates the master side of the pseudo terminal, operating as an intermediary between the login process and the client instance of the `rlogin` program. In normal operation, the packet protocol described in `pty(4)` is invoked to provide $\hat{S}/\hat{Q}$ type facilities and propagate interrupt signals to the remote programs. The login process propagates the client terminal's baud rate and terminal type, as found in the environment variable, `TERM`; see `environ(7)`. The screen or window size of the terminal is requested from the client, and window size changes from the client are propagated to the pseudo terminal.

Transport-level keep-alive messages are enabled unless the `-n` option is present. The use of keep-alive messages allows sessions to be timed out if the client crashes or becomes unreachable.

DIAGNOSTICS

All initial diagnostic messages are indicated by a leading byte with a value of 1, after which any network connections are closed. If there are no errors before login is invoked, a null byte is returned as an indication of success.

Try again.

A fork by the server failed.

SEE ALSO

```
login(1), ruserok(3), rshd(8)
```

BUGS

The authentication procedure used here assumes the integrity of each client machine and the connecting medium. This is insecure but is useful in an “open” environment.

A facility to allow all data exchanges to be encrypted should be present.

A more extensible protocol should be used.

HISTORY

The `rlogind` command appeared in BSD 4.2.

route

route—Show/manipulate the IP routing table.

SYNOPSIS

```
route [ -vn ]
route [ -v ] add [ -net | -host ] XXXX [gw GGGG] [metric MMMM] [netmask NNNN]
[mss NNNN] [window NNNN] [dev DDDD]
route [ -v ] del XXXX
```

DESCRIPTION

route manipulates the kernel's IP routing table. Its primary use is to set up static routes to specific hosts or networks via an interface after it has been configured with the `ifconfig(8)` program. This version of `route` is intended solely for use with kernel versions 0.99p14n and newer kernels.

OPTIONS

(none)	Prints out the kernel routing table, listing destination address, gateway, netmask for route (“Genmask”), flags (u = Up, h = Host, g = Gateway, d = dynamic, m = Modified), Metric (currently not supported), Ref, Use, and Iface (which device the route maps to).
-n	Same as previous but shows numerical addresses instead of trying to determine symbolic host names.
-v	A flag for verbose (not actually used).
del XXXX	Deletes the route associated with the destination address XXXX.
add[-net -host] XXXX [gw GGGG] [metric MMMM] [netmask NNNN] [dev DDDD]	Adds a route to the IP address XXXX. The route is a network route if the <code>-net</code> modifier is used or XXXX is found in <code>/etc/networks</code> by the <code>getnetbyname()</code> library function and no <code>-host</code> modifier is used. The <code>gw GGGG</code> argument means that any IP packets sent to this address will be routed through the specified gateway. Note: The specified gateway must be reachable first. This usually means that you have to set up a static route to the gateway beforehand. The <code>metric MMMM</code> modifier is not yet implemented (and with the <code>-v</code> option will actually print a warning). The <code>netmask NNNN</code> modifier specifies the netmask of the route to be added. This only makes sense for a network route and when the address XXXX actually makes sense with the specified netmask. If no netmask is given, <code>route</code> guesses it instead, so for most normal setups, you won't need to specify a netmask. The <code>mss NNNN</code> modifier specifies the TCP <code>mss</code> for the route to be added. This is usually used only for fine optimization of routing setups. The <code>window NNNN</code> modifier specifies the TCP window for the route to be added. This is typically only used on AX.25 networks and with drivers unable to handle back-to-back frames—such as the 3c501 or DE600. The <code>dev DDDD</code> modifier forces the route to be associated with the specified device because the kernel will otherwise try to determine the device on its own (by checking already existing routes and device specifications and where the route is added to). In most normal networks, you won't need this. If <code>dev DDDD</code> is the last option on the command line, the word <code>dev</code> may be omitted because it's the default. Otherwise, the order of the route modifiers (<code>metric</code>, <code>netmask</code>, <code>gw</code>, and <code>dev</code>) doesn't matter.

EXAMPLES

```
route add -net 127.0.0.0
```

Adds the normal loopback entry, using netmask 255.0.0.0 (Class A net determined from the destination address) and associated with the `lo` device (assuming this device was previously set up correctly with `ifconfig(8)`).

```
route add -net 192.56.76.0
netmask 255.255.255.0 dev eth0
```

Adds a route to the network 192.56.76.x via `eth0`. The Class C netmask modifier is not really necessary here because 192.* is a Class C IP address. The word `dev` can be omitted here.

```
route add default gw mango-gw
```

Adds a default route (which will be used if no other route matches). All packets using this route will be gatewayed through `mango-gw`. The device that will actually be used for that route depends on how you can reach `mango-gw`; the static route to `mango-gw` will have to be set up before.

```
route add ipx4 sl0 route add -net
192.57.66.0 netmask 255.255.255.0
gw ipx4
```

This command sequence adds the route to the `ipx4` host via the SLIP interface (assuming that `ipx4` is the SLIP host) and then adds the net 192.57.66.0 to be gatewayed through that host.

FILES

```
/proc/net/route
/etc/networks
/etc/hosts
```

SEE ALSO

```
ifconfig(8)
```

HISTORY

`route` for Linux was originally written by Fred N. van Kempen (waltje@uualt.nl.mugnet.org) and then modified by Johannes Stille and Linus Torvalds for `pl15`. Alan Cox added the `mss` and `window` options for Linux 1.1.22.

14 June 1994

routed

`routed`—Network routing daemon.

SYNOPSIS

```
routed [-d] [-g] [-q] [-s] [-t] [logfile]
```

DESCRIPTION

`routed` is invoked at boot time to manage the network routing tables. The routing daemon uses a variant of the Xerox NS Routing Information Protocol in maintaining up-to-date kernel routing table entries. It used a generalized protocol capable of use with multiple address types but is currently used only for Internet routing within a cluster of networks.

In normal operation, `routed` listens on the `udp(4)` socket for the `route(8)` service (see `services(5)`) for routing information packets. If the host is an internetwork router, it periodically supplies copies of its routing tables to any directly connected hosts and networks.

When `routed` is started, it uses the `SIOCGIFCONF` `ioctl(2)` to find those directly connected interfaces configured into the system and marked “up” (the software loopback interface is ignored). If multiple interfaces are present, it is assumed that the host will forward packets between networks. `routed` then transmits a request packet on each interface (using a broadcast packet if the interface supports it) and enters a loop, listening for request and response packets from other hosts.

When a request packet is received, *routed* formulates a reply based on the information maintained in its internal tables. The response packet generated contains a list of known routes, each marked with a “hop count” metric (a count of 16, or greater, is considered “infinite”). The metric associated with each route returned provides a metric relative to the sender.

Response packets received by *routed* are used to update the routing tables if one of the following conditions is satisfied:

No routing table entry exists for the destination network or host, and the metric indicates the destination is “reachable” (the hop count is not infinite).

The source host of the packet is the same as the router in the existing routing table entry. That is, updated information is being received from the very internetwork router through which packets for the destination are being routed.

The existing entry in the routing table has not been updated for some time (defined to be 90 seconds) and the route is at least as cost effective as the current route.

The new route describes a shorter route to the destination than the one currently stored in the routing tables; the metric of the new route is compared against the one stored in the table to decide this.

When an update is applied, *routed* records the change in its internal tables and updates the kernel routing table. The change is reflected in the next response packet sent.

In addition to processing incoming packets, *routed* also periodically checks the routing table entries. If an entry has not been updated for three minutes, the entry’s metric is set to infinity and marked for deletion. Deletions are delayed an additional 60 seconds to ensure the invalidation is propagated throughout the local Internet.

Hosts acting as internetwork routers gratuitously supply their routing tables every 30 seconds to all directly connected hosts and networks. The response is sent to the broadcast address on nets capable of that function, to the destination address on point-to-point links, and to the router’s own address on other networks. The normal routing tables are bypassed when sending gratuitous responses. The reception of responses on each network is used to determine that the network and interface are functioning correctly. If no response is received on an interface, another route may be chosen to route around the interface, or the route may be dropped if no alternative is available.

Options supported by *routed*:

- d Enable additional debugging information to be logged, such as bad packets received.
- g This flag is used on internetwork routers to offer a route to the “default” destination. This is typically used on a gateway to the Internet or on a gateway that uses another routing protocol whose routes are not reported to other local routers.
- s Supplying this option forces *routed* to supply routing information whether it is acting as an internetwork router or not. This is the default if multiple network interfaces are present or if a point-to-point link is in use.
- q This is the opposite of the -s option.
- t If the -t option is specified, all packets sent or received are printed on the standard output. In addition, *routed* will not divorce itself from the controlling terminal so that interrupts from the keyboard will kill the process.

Any other argument supplied is interpreted as the name of file in which *routed*’s actions should be logged. This log contains information about any changes to the routing tables and, if not tracing all packets, a history of recent messages sent and received that are related to the changed route.

In addition to the facilities described previously, *routed* supports the notion of “distant” passive and active gateways. When *routed* is started, it reads the file to find gateways that might not be located using only information from the `SILOGIFCONFioct1` (2). Gateways specified in this manner should be marked passive if they are not expected to exchange routing information, whereas gateways marked active should be willing to exchange routing information (that is, they should have a *routed* process running on the machine). Routes through passive gateways are installed in the kernel’s routing tables once upon startup. Such routes are not included in any routing information transmitted. Active gateways are treated equally to network interfaces. Routing information is distributed to the gateway, and if no routing information is received for a period of the time, the associated route is deleted. Gateways marked external are also passive but are not placed in the kernel routing table

nor are they included in routing updates. The function of external entries is to inform `routed` that another routing process will install such a route and that alternate routes to that destination should not be installed. Such entries are only required when both routers might learn of routes to the same destination.

The `/etc/gateways` is comprised of a series of lines, each in the following format:

```
<net|host> name1 gateway name2 metric value <passive|active|external>
```

The `net` or `host` keyword indicates if the route is to a network or specific host.

`name1` is the name of the destination network or host. This can be a symbolic name located in or known to the name server if started after `named(8)` or an Internet address specified in “dot” notation; see `inet(3)`.

`name2` is the name or address of the gateway to which messages should be forwarded.

`value` is a metric indicating the hop count to the destination host or network.

One of the keywords `passive`, `active`, or `external` indicates if the gateway should be treated as passive or active (as described previously) or whether the gateway is external to the scope of the `routed` protocol.

Internetwork routers that are directly attached to the ARPAnet or Milnet should use the Exterior Gateway Protocol (EGP) to gather routing information rather than use a static routing table of passive gateways. EGP is required in order to provide routes for local networks to the rest of the Internet system. Sites needing assistance with such configurations should contact the Computer Systems Research Group at Berkeley.

FILES

`/etc/gateways` for distant gateways

SEE ALSO

`udp(4)`, `icmp(4)`, `XNSrouted(8)`, `htable(8)`

Internet Transport Protocols, XSI 028112, Xerox System Integration Standard

BUGS

The kernel's routing tables may not correspond to those of `routed` when redirects change or add routes. `routed` should note any redirects received by reading the ICMP packets received via a raw socket.

`routed` should incorporate other routing protocols, such as Xerox NS, `XNSrouted(8)`, and EGP. Using separate processes for each requires configuration options to avoid redundant or competing routes.

`routed` should listen to intelligent interfaces, such as an IMP, to gather more information. It does not always detect unidirectional failures in network interfaces (such as when the output side fails).

HISTORY

The `routed` command appeared in BSD 4.2.

BSD 4.2, 16 March 1991

rpc.rusersd

`rpc.rusersd`—Logged-in users server.

SYNOPSIS

```
/usr/libexec/rpc.rusersd
```

DESCRIPTION

`rpc.rusersd` is a server that returns information about users currently logged in to the system.

The currently logged-in users are queried using the `rusers(1)` command. The `rpc.rusersd` daemon is usually invoked by `inetd(8)`.

`rpc.rusersd` uses an RPC protocol defined in `/usr/include/rpcsvc`.

SEE ALSO

`rusers(1)`, `who(1)`, `w(1)`, `inetd(8)`

BSD 4.3, 7 June 1993

rpc.rwalld

`rpc.rwalld`—Write messages to users currently logged in to the server.

SYNOPSIS

`/usr/libexec/rpc.rwalld`

DESCRIPTION

`rpc.rwalld` is a server that will send a message to users currently logged in to the system. This server invokes the `wall(1)` command to actually write the messages to the system.

Messages are sent to this server by the `rwall(1)` command. The `rpc.rwalld` daemon is usually invoked by `inetd(8)`.

`rpc.rwalld` uses an RPC protocol defined in `/usr/include/rpcsvc/rwall.x`.

SEE ALSO

`rwall(1)`, `wall(1)`, `inetd(8)`

BSD 4.3, 7 June 1993

rpcinfo

`rpcinfo`—Report RPC information.

SYNOPSIS

```
rpcinfo -p [host]
rpcinfo [-n portnum] -u host program [version]
rpcinfo [-n portnum] -t host program [version]
rpcinfo -b program version
rpcinfo -d program version
```

DESCRIPTION

`rpcinfo` makes an RPC call to an RPC server and reports what it finds.

OPTIONS

- p Probe the port mapper on `host` and print a list of all registered RPC programs. If `host` is not specified, it defaults to the value returned by `hostname(1)`.
- u Make an RPC call to procedure 0 of `program` on the specified `host` using UDP and report whether a response was received.
- t Make an RPC call to procedure 0 of `program` on the specified `host` using TCP and report whether a response was received.
- n Use `portnum` as the port number for the `-t` and `-u` options instead of the port number given by the port mapper.

- b Make an RPC broadcast to procedure 0 of the specified program and version using UDP and report all hosts that respond.
- d Delete registration for the RPC service of the specified program and version. This option can be exercised only by the superuser.

The program argument can be either a name or a number. If a version is specified, `rpcinfo` attempts to call that version of the specified program. Otherwise, `rpcinfo` attempts to find all the registered version numbers for the specified program by calling version 0 (which is presumed not to exist; if it does exist, `rpcinfo` attempts to obtain this information by calling an extremely high version number instead) and attempts to call each registered version. Note that the version number is required for `-b` and `-d` options.

EXAMPLES

To show all the RPC services registered on the local machine, use

```
rpcinfo -p
```

To show all of the RPC services registered on the machine named klaxon, use

```
rpcinfo -p klaxon
```

To show all machines on the local net that are running the Yellow Pages service, use

```
rpcinfo -b ypserv 'version' -- uniq
```

'version' is the current Yellow Pages version obtained from the results of the `-p` switch above.

To delete the registration for version 1 of the `walld` service, use

```
rpcinfo -d walld 1
```

SEE ALSO

`rpc(5)`, `portmap(8)`, *RPC Programming Guide*

BUGS

In releases prior to SunOS 3.0, the Network File System (NFS) did not register itself with the port mapper; `rpcinfo` cannot be used to make RPC calls to the NFS server on hosts running such releases.

17 December 1987

rquotad, rpc.rquotad

`rquotad`, `rpc.rquotad`—Remote quota server.

SYNOPSIS

```
/usr/etc/rpc.rquotad
```

DESCRIPTION

`rquotad` is an `rpc(3N)` server that returns quotas for a user of a local filesystem that is mounted by a remote machine over the NFS. The results are used by `quota(1)` to display user quotas for remote filesystems. The `rquotad` daemon is usually started at boot time from the `rc.net` script.

FILES

`quotas` Quota file at the filesystem root

SEE ALSO

`quota(1)`, `rpc(3N)`, `nfs(4P)`, `services(5)` `inetd(8C)`

17 December 1987

rshd

rshd—Remote shell server.

SYNOPSIS

rshd [-aInL]

DESCRIPTION

The `rshd` server is the server for the `rcmd(3)` routine and, consequently, for the `rsh(1)` program. The server provides remote execution facilities with authentication based on privileged port numbers from trusted hosts.

The `rshd` server listens for service requests at the port indicated in the `cmd` service specification; see `services(5)`. When a service request is received, the following protocol is initiated:

1. The server checks the client's source port. If the port is not in the range 512-1023, the server aborts the connection.
2. The server reads characters from the socket up to a null (`\0`) byte. The resultant string is interpreted as an ASCII number, base 10.
3. If the number received in Step 2 is nonzero, it is interpreted as the port number of a secondary stream to be used for the `stderr`. A second connection is then created to the specified port on the client's machine. The source port of this second connection is also in the range 512-1023.
4. The server checks the client's source address and requests the corresponding hostname (see `gethostbyaddr(3)`, `hosts(5)`, and `named(8)`). If the hostname cannot be determined, the dot-notation representation of the host address is used. If the hostname is in the same domain as the server (according to the last two components of the domain name), or if the `-a` option is given, the addresses for the hostname are requested, verifying that the name and address correspond. If address verification fails, the connection is aborted with the message, `Host address mismatch`.
5. A null-terminated username of at most 16 characters is retrieved on the initial socket. This username is interpreted as the user identity on the client's machine.
6. A null-terminated username of at most 16 characters is retrieved on the initial socket. This username is interpreted as a user identity to use on the server's machine.
7. A null-terminated command to be passed to a shell is retrieved on the initial socket. The length of the command is limited by the upper bound on the size of the system's argument list.
8. `rshd` then validates the user using `ruserok(3)`, which uses the file and the file found in the user's home directory. The `-l` option prevents `ruserok(3)` from doing any validation based on the user's `.rhosts` file, unless the user is the superuser.
9. A null byte is returned on the initial socket and the command line is passed to the normal login shell of the user. The shell inherits the network connections established by `rshd`.

Transport-level keep-alive messages are enabled unless the `-n` option is present. The use of keep-alive messages allows sessions to be timed out if the client crashes or becomes unreachable.

The `-L` option causes all successful accesses to be logged to `syslogd(8)` as `auth.info` messages and all failed accesses to be logged as `auth.notice`.

DIAGNOSTICS

Except for the last one listed, all diagnostic messages are returned on the initial socket, after which any network connections are closed. An error is indicated by a leading byte with a value of 1 (0 is returned in Step 9 upon successful completion of all the steps prior to the execution of the login shell).

Locuser too long.	The name of the user on the client's machine is longer than 16 characters.
Ruser too long.	The name of the user on the remote machine is longer than 16 characters.
Command too long.	The command line passed exceeds the size of the argument list (as configured into the system).
Login incorrect.	No password file entry for the username existed.
Remote directory.	The <code>chdir</code> command to the home directory failed.

Permission denied.	The authentication procedure described previously failed.
Can't make pipe.	The pipe needed for the stderr wasn't created.
Can't fork; try again.	A fork by the server failed.
<shellname>: ...	The user's login shell could not be started. This message is returned on the connection associated with the stderr and is not preceded by a flag byte.

SEE ALSO

rsh(1), rcmd(3), ruserok(3)

BUGS

The authentication procedure used here assumes the integrity of each client machine and the connecting medium. This is insecure but is useful in an “open” environment.

A facility to allow all data exchanges to be encrypted should be present.

A more extensible protocol (such as Telnet) should be used.

BSD 4.2, 30 April 1991

rwhod

rwhod—System status server.

SYNOPSIS

rwhod

DESCRIPTION

rwhod is the server that maintains the database used by the *rwho*(1) and *ruptime*(1) programs. Its operation is predicated on the ability to broadcast messages on a network.

rwhod operates as both a producer and consumer of status information. As a producer of information, it periodically queries the state of the system and constructs status messages that are broadcast on a network. As a consumer of information, it listens for other *rwhod* servers' status messages, validating them and then recording them in a collection of files located in the directory.

The server transmits and receives messages at the port indicated in the *rwho* service specification; see *services*(5). The messages sent and received are of the form:

```
struct outmp {
char out_line[8]; /* tty name */
char out_name[8]; /* user id */
long out_time; /* time on */
};

struct whod {
char wd_vers;
char wd_type;
char wd_fill[2];
int wd_sendtime;
int wd_recvttime;
char wd_hostname[32];
int wd_loadav[3];
int wd_boottime;
struct whoent {
struct outmp we_utmp;
```

```

        int    we_idle;
    } wd_we[1024 / sizeof (struct whoent)];
};

```

All fields are converted to network byte order prior to transmission. The load averages are as calculated by the `w(1)` program and represent load averages over the 5-, 10-, and 15-minute intervals prior to a server's transmission; they are multiplied by 100 for representation in an integer. The hostname included is that returned by the `gethostname(2)` system call, with any trailing domain name omitted. The array at the end of the message contains information about the users logged in to the sending machine. This information includes the contents of the `utmp(5)` entry for each non-idle terminal line and a value indicating the time in seconds since a character was last received on the terminal line.

Messages received by the `rwho` server are discarded unless they originated at an `rwho` server's port. In addition, if the host's name, as specified in the message, contains any unprintable ASCII characters, the message is discarded. Valid messages received by `rwhod` are placed in files named in the directory. These files contain only the most recent message, in the format described previously.

Status messages are generated approximately once every three minutes. `rwhod` performs an `nlist(3)` every 30 minutes to guard against the possibility that this file is not the system image currently operating.

SEE ALSO

`rwho(1)`, `uptime(1)`

BUGS

There should be a way to relay status information between networks. Status information should be sent only upon request rather than continuously. People often interpret the server dying or network communication failures as a machine going down.

HISTORY

The `rwhod` command appeared in BSD 4.2.

BSD 4.2, 16 March 1991

sendmail

sendmail—Send mail over the Internet.

SYNOPSIS

```

sendmail [flags] [address ...]
newaliases
mailq [-v]
smtpd
bsmtp
runq

```

DESCRIPTION

`sendmail` sends a message to one or more recipients, routing the message over whatever networks are necessary. `sendmail` does internetwork forwarding as necessary to deliver the message to the correct place.

`sendmail` is not intended as a user interface routine. Other programs provide user-friendly front ends. `sendmail` is used only to deliver preformatted messages.

With no flags, `sendmail` reads its standard input up to an end-of-file or a line consisting only of a single dot and sends a copy of the message found there to all the addresses listed. It determines the networks to use based on the syntax and contents of the addresses.

Local addresses are looked up in a file and aliased appropriately. Aliasing can be prevented by preceding the address with a backslash. Usually, the sender is not included in any alias expansions; for example, if john sends to group and group includes john in the expansion, then the letter will not be delivered to john.

Flags are

-ba	Go into ARPANET mode. All input lines must end with a CR-LF, and all messages will be generated with a CR-LF at the end. Also, the From: and Sender: fields are examined for the name of the sender.
-bd	Run as a daemon. This requires Berkeley IPC. <code>sendmail</code> will fork and run in the background, listening on socket 25 for incoming SMTP connections. This is usually run from <code>/etc/rc</code> .
-bi	Initialize the alias database.
-bm	Deliver mail in the usual way (default).
-bp	Print a listing of the queue.
-bs	Use the SMTP protocol as described in RFC 821 on standard input and output. This flag implies all the operations of the -ba flag that are compatible with SMTP.
-bb	Read batched SMTP (BSMTP) commands from standard input.
-bt	Run in address test mode. This mode reads addresses and shows the steps in parsing; it is used for debugging configuration tables.
-bv	Verify names only; do not try to collect or deliver a message. Verify mode is usually used for validating users or mailing lists.
-bz	Create the configuration freeze file.
-C file	Use alternate configuration file. <code>sendmail</code> refuses to run as root if an alternate configuration file is specified. The frozen configuration file is bypassed.
-d X	Set debugging value to X.
-F fullname	Set the full name of the sender.
-f name	Sets the name of the “from” person (the sender of the mail). -f can only be used by trusted users (usually root, daemon, and network) or if the person you are trying to become is the same as the person you are.
-h N	Set the hop count to N. The hop count is incremented every time the mail is processed. When it reaches a limit, the mail is returned with an error message, the victim of an aliasing loop. If not specified, Received: lines in the message are counted.
-n	Don’t do aliasing.
-o x value	Set option x to the specified value. Options are described later in this section.
-q time	Processed saved messages in the queue at given intervals. If time is omitted, process the queue once. time is given as a tagged number, with s being seconds, m being minutes, h being hours, d being days, and w being weeks. For example, -q1h30m or -q90m both set the time-out to 1 hour, 30 minutes. If time is specified, <code>sendmail</code> runs in background. This option can be used safely with -bd.
-M ident	Process the queued message with the queue ID ident.
-R addr	Process the queued messages that have the string addr in one of the recipient addresses.
-S addr	Process the queued messages that have the string addr in the sender address.
-r name	An alternate and obsolete form of the -f flag.
-t	Read message for recipients. To:, Cc:, and Bcc: lines are scanned for recipient addresses. The Bcc: line is deleted before transmission. Any addresses in the argument list are suppressed; that is, they do not receive copies even if listed in the message header.
-v	Go into verbose mode. Alias expansions are announced and so on.

There are also a number of processing options that can be set. Usually, these will only be used by a system administrator. Options can be set either on the command line using the `-o` flag or in the configuration file. These are described in detail in the *Sendmail Installation and Operation Guide*. The options are

A file	Use alternate alias file.
c	On mailers that are considered “expensive” to connect to, don’t initiate immediate connection. This requires queuing.
d x	Set the delivery mode to x. Delivery modes are i for interactive (synchronous) delivery, b for background (asynchronous) delivery, and q for queue only (actual delivery is done the next time the queue is run).
D	Try to automatically rebuild the alias database if necessary.
e x	Set error processing to mode x. Valid modes are m to mail back the error message, w to “write” back the error message (or mail it back if the sender is not logged in), p to print the errors on the terminal (default), q to throw away error messages (only exit status is returned), and e to do special processing for the BerkNet. If the text of the message is not mailed back by modes m or w and if the sender is local to this machine, a copy of the message is appended to the file in the sender’s home directory.
F mode	The mode to use when creating temporary files.
f	Save UNIX–style From: lines at the front of messages.
g N	The default group ID to use when calling mailers.
H file	The SMTP help file.
i	Do not take dots on a line by themselves as a message terminator.
k N	Checkpoint the queue file after every N successful deliveries (default is 10). This avoids excessive duplicate deliveries when sending to long mailing lists interrupted by system crashes.
L n	The log level.
m	Send also to “me” (the sender) if I am in an alias expansion.
o	If set, this message may have old style headers. If not set, this message is guaranteed to have new style headers (commas instead of spaces between addresses). If set, an adaptive algorithm is used that will correctly determine the header format in most cases.
Q queuedir	Select the directory in which to queue messages.
r timeout	The time-out on reads; if none is set, sendmail will wait forever for a mailer. This option violates the word (if not the intent) of the SMTP specification, so the timeout should probably be fairly large.
S file	Save statistics in the named file.
s	Always instantiate the queue file, even under circumstances where it is not strictly necessary. This provides safety against system crashes during delivery.
T time	Set the time-out on undelivered messages in the queue to the specified time. After delivery has failed (for example, because of a host being down) for this amount of time, failed messages will be returned to the sender. The default is three days.
t stz, dtz	Set the name of the time zone.
U userdatabase	If set, a user database is consulted to get forwarding information. You can consider this an adjunct to the aliasing mechanism, except that the database is intended to be distributed; aliases are local to a particular host. This might not be available if your sendmail does not have the USERDB option compiled in.
u N	Set the default user ID for mailers.
w	If not set, name server lookups will use a query type of ANY to find types CNAME, A, and MX and will cause all existing records to be cached by the local server. If there is (or might be) a wildcard MX in the local domain or its parents that are searched, you must set this

option, which uses a query type of CNAME only; otherwise, it causes all fully qualified names to match as names in the local domain.

In aliases, the first character of a name can be a vertical bar to cause interpretation of the rest of the name as a command to pipe the mail to. It might be necessary to quote the name to keep `sendmail` from suppressing the blanks between arguments. For example, a common alias is

```
msgs: "|/usr/bin/msgs -s"
```

Aliases can also have the syntax to ask `sendmail` to read the named file for a list of recipients. For example, an alias such as

```
poets: ":include:/usr/local/lib/poets.list"
```

would read for the list of addresses making up the group.

`sendmail` returns an exit status describing what it did. The codes are defined in `sysexit.h`:

EX_OK	Successful completion on all addresses.
EX_NOUSER	Username not recognized.
EX_UNAVAILABLE	Catchall meaning necessary resources were not available.
EX_SYNTAX	Syntax error in address.
EX_SOFTWARE	Internal software error, including bad arguments.
EX_OSERR	Temporary operating system error, such as cannot fork.
EX_NOHOST	Hostname not recognized.
EX_TEMPFAIL	Message could not be sent immediately but was queued.

If invoked as `newaliases`, `sendmail` rebuilds the alias database. If invoked as `mailq`, `sendmail` prints the contents of the mail queue. If invoked as `smtpd`, `sendmail` forks and runs as a daemon. If invoked as `bsmtp`, `sendmail` processes batched SMTP on standard input. If invoked as `runq`, `sendmail` runs through the mail queue and makes what deliveries are possible.

FILES

Except for the file `/etc/sendmail.cf` itself, the following pathnames are all specified in `/etc/sendmail.cf`. Thus, these values are only approximations.

```
/etc/aliases raw data for alias names
/etc/aliases.pag
/etc/aliases.dir database of alias names
/etc/sendmail.cf configuration file
/etc/sendmail.fc frozen configuration
/etc/sendmail.hf help file
/var/log/sendmail.st collected statistics
/var/spool/mqueue/* temp files
```

SEE ALSO

`binmail(1)`, `mail(1)`, `rmail(1)`, `syslog(3)`, `aliases(5)`, `mailaddr(7)`, `rc(8)`; DARPA Internet Request for Comments RFC 819, RFC 821, RFC 822; "Sendmail: An Internetwork Mail Router," SMM and No.16, "Sendmail Installation and Operation Guide," SMM and No.7.

HISTORY

The `sendmail` command appeared in BSD 4.2.

setfdprm

setfdprm—Sets user-provided floppy disk parameters.

SYNOPSIS

```
setfdprm [ -p ] device name
setfdprm [ -p ] device size sectors heads tracks stretch gap rate spec1 fmt_gap
setfdprm [ -c ] device
setfdprm [ -y ] device
setfdprm [ -n ] device
```

DESCRIPTION

setfdprm is a utility that can be used to load disk parameters into the auto-detecting floppy devices, to clear old parameter sets, and to disable or enable diagnostic messages.

Without any options, setfdprm loads the device (usually `/dev/fd0` or `/dev/fd1`) with a new parameter set with the name entry found in `/etc/fdprm` (usually named `360/360` and so on). These parameters stay in effect until the media is changed.

OPTIONS

-p device name	Permanently loads a new parameter set for the specified auto-configuring floppy device for the configuration with name in <code>/etc/fdprm</code> . Alternatively, the parameters can be given directly from the command line.
-c device	Clears the parameter set of the specified auto-configuring floppy device.
-y device	Enables format detection messages for the specified auto-configuring floppy device.
-n device	Disables format detection messages for the specified auto-configuring floppy device.

BUGS

This documentation is grossly incomplete.

FILES

`/etc/fdprm`

AUTHOR

Werner Almesberger (almesber@nessie.cs.id.ethz.ch)

Linux 0.99, 20 November 1993

setserial

setserial—Get/set Linux serial port information.

SYNOPSIS

```
setserial [ -abqvVW ] device [ parameter1 [ arg ] ] ...
setserial -g [ -abv ] device1 ...
```

DESCRIPTION

setserial is a program designed to set or report the configuration information associated with a serial port. This information includes what I/O port and IRQ a particular serial port is using, whether the break key should be interpreted as the Secure Attention Key, and so on.

During the normal bootup process, only COM ports 1-4 are initialized, using the default I/O ports and IRQ values, as listed. To initialize any additional serial ports, or to change the COM 1-4 ports to a nonstandard configuration, the setserial program should be used. Typically, it is called from an `rc.serial` script, which is usually run out of `/etc/rc.local`.

The device argument or arguments specify the serial device that should be configured or interrogated. It will usually have the following form: `/dev/cua[0-3]`.

If no parameters are specified, `setserial` prints the port type (such as 8250, 16450, 16550, 16550A), the hardware I/O port, the hardware IRQ line, its “baud base,” and some of its operational flags.

If the `-g` option is given, the arguments to `setserial` are interpreted as a list of devices for which the characteristics of those devices should be printed.

Without the `-g` option, the first argument to `setserial` is interpreted as the device to be modified or characteristics to be printed, and any additional arguments are interpreted as parameters that should be assigned to that serial device.

For the most part, superuser privilege is required to set the configuration parameters of a serial port. A few serial port parameters can be set by normal users, however, and these are noted as exceptions in this manual page.

OPTIONS

`setserial` accepts the following options:

<code>-a</code>	When reporting the configuration of a serial device, print all available information.
<code>-b</code>	When reporting the configuration of a serial device, print a summary of the device's configuration, which might be suitable for printing during the bootup process during the <code>/etc/rc</code> script.
<code>-q</code>	Be quiet. <code>setserial</code> will print fewer lines of output.
<code>-v</code>	Be verbose. <code>setserial</code> will print additional status output.
<code>-V</code>	Display version and exit.
<code>-W</code>	Do wild interrupt initialization and exit.

PARAMETERS

The following parameters can be assigned to a serial port.

All argument values are assumed to be in decimal unless preceded by `0x`.

<code>port port_number</code>	The <code>port</code> option sets the I/O port as described previously.
<code>irq irq_number</code>	The <code>irq</code> option sets the hardware IRQ as described previously.
<code>uart uart_type</code>	This option is used to set the UART type. The permitted types are none, 8250, 16450, 16550, and 16550A. Because the 8250 and 16450 UARTs do not have FIFOs, and because the original 16550 have bugs that make the FIFOs unusable, the FIFO will only be used on chips identified as 16550A UARTs. Setting the UART type to 8250, 16450, or 16550 will enable the serial port without trying to use the FIFO. Using the UART type none will disable the port. Some internal modems are billed as having a “16550A UART with a 1KB buffer.” This is a lie. They do not really have a 16550A-compatible UART; instead, what they have is a 16450-compatible UART with a 1KB receive buffer to prevent receiver overruns. This is important because they do not have a transmit FIFO. Hence, they are not compatible with a 16550A UART, and the autoconfiguration process will correctly identify them as 16450s. If you attempt to override this using the <code>uart</code> parameter, you see dropped characters during file transmissions. These UARTs usually have other problems: The skip test parameter also often must be specified.
<code>autoconfig</code>	When this parameter is given, <code>setserial</code> asks the kernel to attempt to automatically configure the serial port. The I/O port must be correctly set; the kernel will attempt to determine the UART type, and if the <code>auto_irq</code> parameter is set, Linux will attempt to automatically determine the IRQ. The <code>autoconfig</code> parameter should be given after the <code>port</code> , <code>auto_irq</code> , and <code>skip_test</code> parameters have been specified.

auto_irq	During autoconfiguration, try to determine the IRQ. This feature is not guaranteed to always produce the correct result; some hardware configurations will fool the Linux kernel. It is generally safer not to use the auto_irq feature but rather to specify the IRQ to be used explicitly, using the irq parameter.
^auto_irq	During autoconfiguration, do not try to determine the IRQ.
skip_test	During autoconfiguration, skip the UART test. Some internal modems do not have National Semiconductor compatible UARTs but have cheap imitations instead. Some of these cheesy imitation UARTs do not fully support the loopback detection mode, which is used by the kernel to make sure there really is a UART at a particular address before attempting to configure it. For certain internal modems, you will need to specify this parameter so Linux can initialize the UART correctly.
^skip_test	During autoconfiguration, do not skip the UART test.
baud_base baud_base	This option sets the base baud rate, which is the clock frequency divided by 16. Usually, this value is 115200, which is also the fastest baud rate, which the UART can support.
spd_hi	Use 57.6KB when the application requests 38.4KB. This parameter can be specified by a non-privileged user.
spd_vhi	Use 115KB when the application requests 38.4KB. This parameter can be specified by a non-privileged user.
spd_cust	Use the custom divisor to set the speed when the application requests 38.4KB. In this case, the baud rate is the baud_base divided by the divisor. This parameter can be specified by a non-privileged user.
spd_normal	Use 38.4KB when the application requests 38.4KB. This parameter can be specified by a non-privileged user.
divisor divisor	This option sets the custom divisor. This divisor will be used when the spd_cust option is selected and the serial port is set to 38.4KB by the application. This parameter can be specified by a non-privileged user.
sak	Set the break key at the Secure Attention Key.
^sak	Disable the Secure Attention Key.
fourport	Configure the port as an AST Fourport card.
^fourport	Disable AST Fourport configuration.
close_delay delay	Specify the amount of time, in hundredths of a second, that DTR should remain low on a serial line after the callout device is closed before the blocked dial-in device raises DTR again. The default value of this option is 50, or a half-second delay.
Session_lockout	Lock out callout port (/dev/cuaXX) accesses across different sessions. That is, once a process has opened a port, do not allow a process with a different session ID to open that port until the first process has closed it.
^session_lockout	Do not lock out callout port accesses across different sessions.
pgrp_lockout	Lock out callout port (/dev/cuaXX) accesses across different process groups. That is, once a process has opened a port, do not allow a process in a different process group to open that port until the first process has closed it.
^pgrp_lockout	Do not lock out callout port accesses across different process groups.
hup_notify	Notify a process blocked on opening a dial-in line when a process has finished using a callout line (either by closing it or by the serial line being hung up) by returning EAGAIN to the open.
^hup_notify	The application of this parameter is for gettys that are blocked on a serial port's dial-in line. This allows the getty to reset the modem (which may have had its configuration modified by the application using the callout device) before blocking on the open again.
	Do not notify a process blocked on opening a dial-in line when the callout device is hung up.

<code>split_termios</code>	Treat the termios settings used by the callout device and the termios settings used by the dial-in devices as separate.
<code>^split_termios</code>	Use the same termios structure to store both the dial-in and callout ports. This is the default option.
<code>callout_nohup</code>	If this particular serial port is opened as a callout device, do not hang up the tty when carrier detect is dropped.
<code>^callout_nohup</code>	Do not skip hanging up the tty when a serial port is opened as a callout device. Of course, the HUPCL termios flag must be enabled if the hangup is to occur.

CONSIDERATIONS OF CONFIGURING SERIAL PORTS

It is important to note that `setserial` merely tells the Linux kernel where it should expect to find the I/O port and IRQ lines of a particular serial port. It does not configure the hardware, the actual serial board, to use a particular I/O port. To do that, you need to physically program the serial board, usually by setting some jumpers or by switching some DIP switches.

This section provides some pointers in helping you decide how you want to configure your serial ports.

The “standard MS-DOS” port associations are

<code>/dev/ttyS0 (COM1), port 0x3f8</code>	IRQ 4
<code>/dev/ttyS1 (COM2), port 0x2f8</code>	IRQ 3
<code>/dev/ttyS2 (COM3), port 0x3e8</code>	IRQ 4
<code>/dev/ttyS3 (COM4), port 0x2e8</code>	IRQ 3

Due to the limitations in the design of the AT/ISA bus architecture, an IRQ line usually cannot be shared between two or more serial ports. If you attempt to do this, one or both serial ports will become unreliable if you try to use both simultaneously. This limitation can be overcome by special multiport serial port boards, which are designed to share multiple serial ports over a single IRQ line. Multiport serial cards supported by Linux include the AST FourPort, the Accent Async board, the Usenet Serial II board, the Bocaboard BB-1004, BB-1008, and BB-2016 boards, and the HUB-6 serial board.

The selection of an alternative IRQ line is difficult because most of them are already used. The following table lists the “standard MS-DOS” assignments of available IRQ lines:

IRQ 3	COM2
IRQ 4	COM1
IRQ 5	LPT2
IRQ 7	LPT1

Most people find that IRQ 5 is a good choice, assuming that there is only one parallel port active in the computer. Another good choice is IRQ 2 (a.k.a. IRQ 9), although this IRQ is sometimes used by network cards, and very rarely will VGA cards be configured to use IRQ 2 as a vertical retrace interrupt. If your VGA card is configured this way, try to disable it so you can reclaim that IRQ line for some other card. It’s not necessary for Linux and most other operating systems.

The only other available IRQ lines are 3, 4, and 7, and these are probably used by the other serial and parallel ports. (If your serial card has a 16-bit card edge connector and supports higher interrupt numbers, then IRQ 10, 11, 12, and 15 are also available.)

On AT class machines, IRQ 2 is seen as IRQ 9, and Linux will interpret it in this manner.

IRQs other than 2 (9), 3, 4, 5, 7, 10, 11, 12, and 15 should not be used because they are assigned to other hardware and cannot, in general, be changed. Here are the “standard” assignments:

IRQ 0	Timer channel 0
IRQ 1	Keyboard
IRQ 2	Cascade for controller 2
IRQ 3	Serial port 2
IRQ 4	Serial port 1

IRQ 5	Parallel port 2 (Reserved in PS/2)
IRQ 6	Floppy diskette
IRQ 7	Parallel port 1
IRQ 8	Real-time clock
IRQ 9	Redirected to IRQ2
IRQ 10	Reserved
IRQ 11	Reserved
IRQ 12	Reserved (Auxiliary device in PS/2)
IRQ 13	Math coprocessor
IRQ 14	Hard disk controller
IRQ 15	Reserved

CAUTION

Using an invalid port can lock up your machine.

FILES

`/etc/rc.local`

`/etc/rc.serial`

SEE ALSO

`tty(4)`, `ttys(4)`, `kernel/chr_drv/serial.c`

AUTHOR

The original version of `setserial` was written by Rick Sladkey (jrs@world.std.com) and was modified by Michael K. Johnson (johnsonm@stolaf.edu).

This version has since been rewritten from scratch by Theodore Ts'o (tytso@mit.edu) on 1/1/93. Any bugs or problems are solely his responsibility.

setserial 2.10, 27 August 1994

setsid

`setsid`—Run a program in a new session.

SYNOPSIS

```
setsid program [ arg ... ]
```

DESCRIPTION

`setsid` runs a program in a new session.

SEE ALSO

`setsid(2)`

AUTHOR

Rick Sladkey (jrs@world.std.com)

Linux 0.99, 20 November 1993

showmount

showmount—Show mount information for an NFS server.

SYNOPSIS

```
/usr/etc/showmount [\-adehv][\--all][\--directories\]
[\--exports][\--help] [\--version][\host\]
```

DESCRIPTION

showmount queries the mount daemon on a remote host for information about the state of the NFS server on that machine. With no options, showmount lists the set of clients who are mounting from that host. The output from showmount is designed to appear as though it were processed through `sort -u`.

OPTIONS

<code>-a</code> or <code>--all</code>	List both the client hostname and mounted directory in <code>host:dir</code> format.
<code>-d</code> or <code>--directories</code>	List only the directories mounted by some client.
<code>-e</code> or <code>--exports</code>	Show the NFS server's export list.
<code>-h</code> or <code>--help</code>	Provide a short help summary.
<code>-v</code> or <code>--version</code>	Report the current version number of the program.
<code>--no-headers</code>	Suppress the descriptive headings from the output.

SEE ALSO

`rpc.mountd(8)`, `rpc.nfsd(8)`

BUGS

The completeness and accuracy of the information that showmount displays varies according to the NFS server's implementation. Because showmount sorts and uniques the output, it is impossible to determine from the output whether a client is mounting the same directory more than once.

AUTHOR

Rick Sladkey (jrs@world.std.com)

6 October 1993

shutdown

shutdown—Close down the system.

SYNOPSIS

```
shutdown [-h | -r] [-fqs] [now | hh:ss | +mins]
reboot [-h | -r] [-fqs] [now | hh:ss | +mins]
fastboot [-h | -r] [-fqs] [now | hh:ss | +mins]
halt [-h | -r] [-fqs] [now | hh:ss | +mins]
fasthalt [-h | -r] [-fqs] [now | hh:ss | +mins]
```

DESCRIPTION

In general, shutdown prepares the system for a power down or reboot. An absolute or delta time can be given, and periodic messages will be sent to all users warning of the shutdown.

halt is the same as `shutdown -h -q now`.

fasthalt is the same as `shutdown -h -q -f now`.

reboot is the same as shutdown -r -q now.

fastboot is the same as shutdown -r -q -f now.

The default delta time, if none is specified, is two minutes.

Five minutes before shutdown (or immediately, if shutdown is less than five minutes away), the `/etc/nologin` file is created with a message stating that the system is going down and that logins are no longer permitted. The `login(1)` program will not allow non-superusers to log in during this period. A message will be sent to all users at this time.

When the shutdown time arrives, shutdown notifies all users, tells `init(8)` not to spawn more `getty(8)s`, writes the shutdown time into the `/var/log/wtmp` file, kills all other processes on the system, `sync(2)s`, unmounts all the disks, `sync(2)s` again, waits for a second, and then either terminates or reboots the system.

OPTIONS

-h	Halt the system. Do not reboot. This option is used when powering down the system.
-r	Reboot the system.
-f	Fast. When the system is rebooted, the filesystems will not be checked. This is arranged by creating <code>/fastboot</code> , which <code>/etc/rc</code> must detect (and delete).
-q	Quiet. This uses a default broadcast message and does not prompt the user for one.
-s	Reboot in single-user mode. This is arranged by creating <code>/etc/singleboot</code> , which <code>simpleinit(8)</code> detects (and deletes).

FILES

`/etc/rc`
`/fastboot`
`/etc/singleboot`
`/etc/nologin`
`/var/log/wtmp`

SEE ALSO

`umount(8)`, `login(1)`, `reboot(2)`, `simpleinit(8)`, `init(8)`

BUGS

Unlike the BSD shutdown, users are notified of shutdown only once or twice, instead of many times, and at shorter and shorter intervals as “apocalypse approaches.”

AUTHOR

poe@daimi.aau.dk. Modified by jrs@world.std.com.

Linux 0.99, 20 November 1993

simpleinit

simpleinit—Process control initialization.

SYNOPSIS

`init [ single ]`

DESCRIPTION

`init` is invoked as the last step in the Linux boot sequence. If the `single` option is used, or if the file `/etc/singleboot` exists, then single-user mode will be entered, by starting `/bin/sh`. If the file `/etc/securesingle` exists, then the root password will be required to start single-user mode. If the root password does not exist, or if `/etc/passwd` does not exist, the checking of the password will be skipped.

If the file `/etc/TZ` exists, then the contents of that file will be read and used to set the `TZ` environment variable for each process started by `simpleinit`. This “feature” is only available if it’s configured at compile time. It’s not usually needed.

After single-user mode is terminated, the `/etc/rc` file is executed, and the information in `/etc/inittab` will be used to start processes.

While `init` is running, several signals are trapped with special action taken. Because `init` has PID 1, sending signals to the `init` process is easy with the `kill(1)` command.

If `init` catches a `SIGHUP` (hangup) signal, the `/etc/inittab` will be read again. If `init` catches a `SIGTSTP` (terminal stop) signal, no more processes will be spawned. This is a toggle, which is reset if `init` catches another `SIGTSTP` signal.

If `init` catches a `SIGINT` (interrupt) signal, `init` will sync a few times and try to start reboot. Failing this, `init` will execute the system `reboot(2)` call. Under Linux, it is possible to configure the `Ctrl+Alt+Del` sequence to send a signal to `init` instead of rebooting the system.

THE inittab FILE

Because of the number of `init` programs that are appearing in the Linux community, the documentation for the `/etc/inittab` file, which is usually found with the `inittab(5)` man page, is presented here:

The format is

```
ttyline:termcap-entry:getty-command
```

An example follows:

```
tty1:console:/sbin/getty 9600 tty1
tty2:console:/sbin/getty 9600 tty2
tty3:console:/sbin/getty 9600 tty3
tty4:console:/sbin/getty 9600 tty4
# tty5:console:/sbin/getty 9600 tty5
# ttyS1:dumb:/sbin/getty 9600 ttyS1
# ttyS2:dumb:/sbin/getty -m -t60 2400 ttyS2
```

Lines beginning with the `#` character are treated as comments. Please see documentation for the `getty(8)` command that you are using because there are several of these in the Linux community at this time.

FILES

```
/etc/inittab
/etc/singleboot
/etc/securesingle
/etc/TZ
/etc/passwd
/etc/rc
```

SEE ALSO

`inittab(5)`, `ctrlaltdel(8)`, `reboot(8)`, `termcap(5)`, `getty(8)`, `agetty(8)`, `shutdown(8)`

BUGS

This program is called `simpleinit` to distinguish it from the System V compatible versions of `init` that are starting to appear in the Linux community. `simpleinit` should be linked to, or made identical with, `init` for correct functionality.

AUTHOR

Peter Orbaek (poe@daimi.aau.dk), version 1.20, with patches for single-user mode by Werner Almesberger.

Linux 0.99, 20 November 1993

slattach

`slattach`—Attach a network interface to a serial line.

SYNOPSIS

```
slattach [-v] [-p proto] [-s speed] [tty]
```

DESCRIPTION

`slattach` is a little program that can be used to put a normal terminal (“serial”) line into one of several “network” modes, thus allowing you to use it for point-to-point links to other computers.

OPTIONS

<code>[-v]</code>	Enable debugging output. Useful when determining why a given setup doesn’t work.
<code>[-p proto]</code>	Set a specific kind of protocol to use on the line. The default is set to <code>cslip</code> , compressed SLIP. Other possible values are <code>slip</code> (normal SLIP), <code>ppp</code> (Point-to-Point Protocol), and <code>kiss</code> (AX.25 TNC protocol).
<code>[-s speed]</code>	Set a specific line speed other than the default. If no arguments are given, the current terminal line (usually the login device) is used. Otherwise, an attempt is made to claim the indicated terminal port, lock it, and open it.

FILES

`/dev/cua*`

BUGS

None so far.

AUTHOR

Fred N. van Kempen (waltje@uwalnt.nl.mugnet.org)

20 September 1993

sliplogin

`sliplogin`—Attach a serial line network interface.

SYNOPSIS

```
sliplogin [loginname]
```

DESCRIPTION

`sliplogin` is used to turn the terminal line on standard input into a serial line IP SLIP link to a remote host. To do this, the program searches the file for an entry matching `loginname` (which defaults to the current login name if omitted). If a

matching entry is found, the line is configured appropriately for slip (8-bit transparent I/O) and converted to slip line discipline. Then a shell script is invoked to initialize the slip interface with the appropriate local and remote IP address, netmask, and so on.

The usual initialization script is `/etc/slip/slip.lgin`, but if particular hosts need special initialization, the file `/etc/slip/slip.login.loginname` will be executed instead if it exists. The script is invoked with the parameters

<code>slipunit</code>	The unit number of the slip interface assigned to this line, such as 0 for <code>s10</code> .
<code>speed</code>	The speed of the line.
<code>args</code>	The arguments from the entry, in order starting with <code>loginname</code> .

Only the superuser can attach a network interface. The interface is automatically detached when the other end hangs up or the `sliplogin` process dies. If the kernel slip module has been configured for it, all routes through that interface will also disappear at the same time. If there is other processing a site wants done upon hangup, the file `/etc/slip/slip.logout` or `/etc/slip/slip.logout.loginname` is executed if it exists. It is given the same arguments as the login script.

FORMAT OF `/etc/slip.hosts`

Comments (lines starting with a #) and blank lines are ignored. Other lines must start with a `loginname`, but the remaining arguments can be whatever is appropriate for the file that will be executed for that name. Arguments are separated by whitespace and follow normal `sh(1)` quoting conventions (however, `loginname` cannot be quoted). Usually, lines have the form `loginname local-address remote-address netmask opt-args`. `local-address` and `remote-address` are the IP hostnames or addresses of the local and remote ends of the slip line, and `netmask` is the appropriate IP netmask. These arguments are passed directly to `ifconfig(8)`. `opt-args` are optional arguments used to configure the line.

EXAMPLE

The normal use of `sliplogin` is to create an entry for each legal, remote slip site with `sliplogin` as the shell for that entry, such as

```
Sfoo:ikhuy6:2010:1:slip line to foo:/tmp:/usr/sbin/sliplogin.
```

(Our convention is to name the account used by remote host `hostname` as `shostname`.) Then an entry is added that looks like

```
Sfoo 'hostname' foo netmask
```

'hostname' will be evaluated by `sh` to the local hostname and `netmask` is the local host IP netmask.

Note that `sliplogin` must be `setuid` to root, and although it's not a security hole, moral defectives can use it to place terminal lines in an unusable state or deny access to legitimate users of a remote slip line. To prevent this, a site can create a group, say `slip`, that only the slip login accounts are put in and then make sure that `/sbin/sliplogin` is in group `slip` and mode `4550` (`setuid` root, only group `slip` can execute binary).

DIAGNOSTICS

`sliplogin` logs various information to the system log daemon, `syslogd(8)`, with a facility code of `daemon`. The messages are listed here, grouped by severity level.

Error Severity

<code>ioctl (TCGETS): reason</code>	A <code>TCGETS ioctl</code> to get the line parameters failed.
<code>ioctl (TCSETS): reason</code>	A <code>TCSETS ioctl</code> to set the line parameters failed.
<code>/etc/slip.hosts: reason</code>	The file could not be opened.
<code>access denied for user</code>	No entry for user was found in <code>/etc/slip/slip.hosts</code>

Notice Severity

"attaching slip unit" unit for <code>loginname SLIP unit</code>	Unit was successfully attached.

SEE ALSO

slattach(8), syslogd(8)

HISTORY

The `sliplogin` command is currently in beta test.

5 August 1991

swapon, swapoff

swapon, swapoff—Enable/disable devices and files for paging and swapping.

SYNOPSIS

```
/sbin/swapon -a
/sbin/swapon specialfile ...
/sbin/swapoff -a
/sbin/swapoff specialfile ...
```

DESCRIPTION

`swapon` is used to specify devices on which paging and swapping are to take place. Calls to `swapon` usually occur in the system multiuser initialization file `/etc/rc` making all swap devices available, so that the paging and swapping activity is interleaved across several devices and files.

Usually, the first form is used:

`-a` All devices marked as `sw` swap devices in `/etc/fstab` are made available.

`swapoff` disables swapping on the specified devices and files or on all swap entries in `/etc/fstab` when the `-a` flag is given.

SEE ALSO

swapon(2), swapoff(2), fstab(5), init(8), mkswap(8), rc(8), mount(8)

FILES

<code>/dev/hd[ab]?</code>	Standard paging devices
<code>/dev/sd[ab]?</code>	Standard (SCSI) paging devices
<code>/etc/fstab</code>	ASCII filesystem description table

HISTORY

The `swapon` command appeared in 4.0 BSD.

AUTHORS

See the Linux `mount(8)` man page for a complete author list. Primary contributors include Doug Quale, H.J. Lu, Rick Sladkey, and Stephen Tweedie.

Linux 0.99, 27 November 1993

sync

sync—Flush Linux filesystem buffers.

SYNOPSIS

```
sync
```

DESCRIPTION

`sync` executes `sync(2)`, which flushes the filesystem buffers to disk. `sync` should be called before the processor is halted in an unusual manner (before causing a kernel panic when debugging new kernel code). In general, the processor should be halted using the `reboot(8)` or `halt(8)` commands, which attempt to put the system in a quiescent state before calling `sync(2)`.

From Linus: “Note that `sync` is only guaranteed to schedule the dirty blocks for writing: It can actually take a short time before all the blocks are finally written. If you are doing the `sync` with the expectation of killing the machine soon after, please take this into account and sleep for a few seconds. (The `reboot(8)` command takes these precautions.)”

SEE ALSO

`sync(2)`, `update(8)`, `reboot(8)`, `halt(8)`

AUTHOR

Linus Torvalds (torvalds@cs.helsinki.fi)

Linux 0.99, 20 November 1993

syslogd

`syslogd`—Linux system logging utilities.

DESCRIPTION

`syslogd` provides two system utilities, which provide support for system logging and kernel message trapping. Support of both `inetd` and UNIX domain sockets enables this utility package to support both local and remote logging.

System logging is provided by a version of `syslogd` derived from the stock BSD sources. Support for kernel logging is provided by the `klogd` utility, which allows kernel logging to be conducted in either a stand-alone fashion or as a client of `syslogd`.

Although the `syslogd` sources have been heavily modified, a couple of notes are in order. First of all, there has been a systematic attempt to ensure that `syslogd` follows standard BSD behavior as its default. The second important concept to note is that this version of `syslogd` interacts transparently with the version of `syslog` found in the standard libraries. If a binary linked to the standard shared libraries fails to function correctly, we want an example of the anomalous behavior.

CONFIGURATION FILE SYNTAX DIFFERENCES

`syslogd` uses a slightly different syntax for its configuration file from that of the original BSD sources. Originally, all messages of a specific priority and above were forwarded to the log file.

For example, the following line caused all output from the daemon facilities to go into `/usr/adm/daemons`:

```
# Sample syslog.conf
daemon.debug /usr/adm/daemons
```

Under the new scheme, this behavior remains the same. The difference is the addition of two new wildcard specifiers: the asterisk (*) and the equals sign (=). The * specifies that all messages for the indicated facility are to be directed to the destination. Note that this behavior is degenerate with specifying a priority level of debug. Users have indicated that the asterisk notation is more intuitive.

The = wildcard is used to restrict logging to the specified priority class. This allows, for example, routing only debug messages to a particular logging source.

For example, the following line in `syslog.conf` directs debug messages from all sources to the `/usr/adm/debug` file:

```
# Sample syslog.conf
daemon.=debug /usr/adm/debug
```

This may take some acclimatization for those individuals used to the pure BSD behavior, but testers have indicated that this syntax is somewhat more flexible than the BSD behavior. Note that these changes should not affect standard `syslog.conf` files. You must specifically modify the configuration files to obtain the enhanced behavior.

SUPPORT FOR REMOTE LOGGING

These modifications provide network support to the `syslogd` facility. Network support means that messages can be forwarded from one node running `syslogd` to another node running `syslogd` where they will be actually logged to a disk file.

The strategy is to have `syslogd` listen on a UNIX domain socket for locally generated log messages. This behavior will allow `syslogd` to interoperate with the `syslog` found in the standard C library. At the same time, `syslogd` listens on the standard `syslog` port for messages forwarded from other hosts. To have this work correctly, the services files (typically found in `/usr/etc/inet`) must have the following entry:

```
syslog 514/udp
```

To cause messages to be forwarded to another host, replace the normal file line in the `syslog.conf` file with the name of the host to which the messages is to be sent prepended with an `@`.

For example, to forward all messages to a remote host, use the following `syslog.conf` entry:

```
# Sample syslogd configuration file to
# messages to a remote host forward all.
.* @hostname
```

To forward all kernel messages to a remote host, the configuration file is

```
# Sample configuration file to forward all kernel
# messages to a remote host.
kern.* @hostname
```

OUTPUT TO NAMED PIPES (FIFOS)

This version of `syslogd` has support for logging output to named pipes (FIFOs). A FIFO or named pipe can be used as a destination for log messages by prepending a `|` to the name of the file. This is handy for debugging. Note that the FIFO must be created with the `mkfifo` command before `syslogd` is started.

The following configuration file routes debug messages from the kernel to a FIFO:

```
# Sample configuration to route kernel debugging
# messages ONLY to /usr/adm/debug which is a
# named pipe.
kern.=debug | /usr/adm/debug
```

INSTALLATION CONCERNS

There is probably one important consideration when installing this version of `syslogd`. This version of `syslogd` is dependent on proper formatting of messages by the `syslog` function. The functioning of the `syslog` function in the shared libraries changed somewhere in the region of `libc.so.4.[2-4].n`. The specific change was to null-terminate the message before transmitting it to the `/dev/log` socket. Proper functioning of this version of `syslogd` is dependent on null-termination of the message.

This problem will typically manifest itself if old statically linked binaries are being used on the system. Binaries using old versions of the `syslog` function will cause empty lines to be logged, followed by the message with the first character in the message removed. Relinking these binaries to newer versions of the shared libraries will correct this problem.

SECURITY THREATS

There is the potential for the `syslogd` daemon to be used as a conduit for a denial of service attack. Thanks go to John Morrison (jmorrison@rflab.ee.ubc.ca) for alerting me to this potential. A rogue programmer could very easily flood the `syslogd` daemon with `syslog` messages resulting in the log files consuming all the remaining space on the filesystem.

Activating logging over the `inet` domain sockets will of course expose a system to risks outside of programs or individuals on the local machine.

Version 1.2 of the utility set will address this problem. In the meantime, there are a number of methods for protecting a machine:

1. Logging can be directed to an isolated or non-root filesystem, which, if filled, will not impair the machine.
2. The `ext2` filesystem can be used, which can be configured to limit a certain percentage of a filesystem to usage by root only. Note that this will require `syslogd` to be run as a non-root process. Also note that this will prevent usage of remote logging because `syslogd` will be unable to bind to the 514/UDP socket.
3. Disabling `inet` domain sockets will limit risk to the local machine.
4. Use Step 3 and if the problem persists and is not secondary to a rogue program or daemon, get a 3.5 foot (approximately 1 meter) length of sucker rod and have a chat with the user in question. A sucker rod is 3/4-, 7/8-, or 1-inch hardened steel rod, male threaded on each end. Its primary use in the oil industry in Western North Dakota and other locations is to pump-suck oil from oil wells. Secondary uses are for the construction of cattle feed lots and for dealing with the occasional recalcitrant or belligerent individual.

FILES

`/etc/syslog.conf`

BUGS

Primarily, security concerns will be addressed in version 1.2.

SEE ALSO

`klogd(1)`

COLLABORATORS

Dr. Greg Wettstein (greg%wind.uucp@plains.nodak.edu)
 Enjellic Systems Development
 Oncology Research Division Computing Facility
 Roger Maris Cancer Center
 Fargo, ND
 Stephen Tweedie
 Department of Computer Science
 Edinburgh University, Scotland
 Juha Virtanen
 (jiivee@hut.fi)
 Shane Alderton
 (shane@scs.apana.org.au)

Version 1.1, 28 January 1994

syslogd

`syslogd`—Log systems messages.

SYNOPSIS

```
syslogd [-f config_file] [-m mark_interval] [-p log_socket]
```

DESCRIPTION

`syslogd` reads and logs messages to the system console, log files, and other machines or users as specified by its configuration file. The options are as follows:

- f Specify the pathname of an alternate configuration file; the default is `/etc/syslog.conf`.
- m Select the number of minutes between “mark” messages; the default is 20 minutes.
- p Specify the pathname of an alternate log socket; the default is `/dev/log`.

syslogd reads its configuration file when it starts up and whenever it receives a hangup signal. For information on the format of the configuration file, see `syslog.conf(5)`.

syslogd reads messages from the UNIX domain socket `/dev/log`, from an Internet domain socket specified in `/etc/services`, and from the special device `/dev/klog` (to read kernel messages).

syslogd creates the file `/var/run/syslog.pid` and stores its process ID there. This can be used to kill or reconfigure syslogd.

The message sent to syslogd should consist of a single line. The message can contain a priority code, which should be a preceding decimal number in angle braces, such as `<5>`. This priority code should map into the priorities defined in the include file `<sys/syslog.h>`.

FILES

<code>/etc/syslog.conf</code>	The configuration file
<code>/var/run/syslog.pid</code>	The process ID of current syslogd
<code>/dev/log</code>	Name of the UNIX domain datagram log socket
<code>/dev/klog</code>	The kernel log device

SEE ALSO

`logger(1)`, `syslog(3)`, `services(5)`, `syslog.conf(5)`

HISTORY

The `syslogd` command appeared in BSD 4.3.

BSD 4.2, 16 March 1991

talkd

talkd—Remote user communication server.

SYNOPSIS

talkd

DESCRIPTION

talkd is the server that notifies a user that someone else wants to initiate a conversation. It acts a repository of invitations, responding to requests by clients who want to rendezvous to hold a conversation. In normal operation, a client, the caller, initiates a rendezvous by sending a CTL MSG to the server of type LOOK UP (see `protocols/talkd.h`). This causes the server to search its invitation tables to check if an invitation currently exists for the caller (to speak to the callee specified in the message). If the lookup fails, the caller then sends an ANNOUNCE message, causing the server to broadcast an announcement on the callee's login ports requesting contact. When the callee responds, the local server uses the recorded invitation to respond with the appropriate rendezvous address and the caller and callee client programs establish a stream connection through which the conversation takes place.

SEE ALSO

`talk(1)`, `write(1)`

HISTORY

The `talkd` command appeared in BSD 4.3.

BSD 4.3, 16 March 1991

telnetd

`telnetd`—DARPA Telnet protocol server.

SYNOPSIS

```
/etc/telnetd [-debug [port]] [-l][-D options][-D report]
[-D exercise][-D netdata] [-D ptydata]
```

DESCRIPTION

`telnetd` is a server that supports the DARPA standard Telnet virtual terminal protocol. `telnetd` is invoked by the Internet server (see `inetd(8)`), usually for requests to connect to the Telnet port as indicated by the `/etc/services` file (see `services(5)`). If desired the `-debug` can be used, to start up `telnetd` manually, instead of through `inetd(8)`. If started up this way, `port` may be specified to run `telnetd` on an alternate TCP port number.

The `-d` option can be used for debugging purposes. This allows Telnet to print debugging information to the connection, allowing the user to see what `telnetd` is doing. There are several modifiers: `options` prints information about the negotiation of Telnet options, `report` prints the options information, plus some additional information about what processing is going on, `netdata` displays the data stream received by `telnetd`, `ptydata` displays data written to the `pty`, and `exercise` has not been implemented yet.

`telnetd` operates by allocating a pseudo-terminal device (see `pty(4)`) for a client) and then creating a login process that has the slave side of the pseudo-terminal as `stdin`, `stdout`, and `stderr`. `telnetd` manipulates the master side of the pseudo-terminal, implementing the Telnet protocol and passing characters between the remote client and the login process.

When a Telnet session is started, `telnetd` sends Telnet options to the client side, indicating a willingness to do a remote echo of characters, to suppress go ahead, to do remote flow control, and to receive terminal type information, terminal speed information, and window size information from the remote client. If the remote client is willing, the remote terminal type is propagated in the environment of the created login process. The pseudo-terminal allocated to the client is configured to operate in cooked mode and with `XTABS` and `CRMOD` enabled (see `tty(4)`).

`telnetd` is willing to do echo, binary, suppress go ahead, and timing mark. `telnetd` is willing to have the remote client do `linemode`, binary, terminal type, terminal speed, window size, toggle flow control, environment, X display location, and suppress go ahead.

If the file `/etc/issue.net` is present, `telnetd` will show its contents before the login prompt of a Telnet session (see `issue.net(5)`).

SEE ALSO

`telnet(1)`, `issue.net(5)`

BUGS

Some Telnet commands are only partially implemented.

Because of bugs in the original 4.2 BSD `telnet(1)`, `telnetd` performs some dubious protocol exchanges to try to discover if the remote client is, in fact, a 4.2 BSD `telnet(1)`.

Binary mode has no common interpretation except between similar operating systems (UNIX, in this case).

The terminal type name received from the remote client is converted to lowercase. `telnetd` never sends Telnet go ahead commands.

20 April 1991

tftpd

tftpd—DARPA Trivial File Transfer Protocol server.

SYNOPSIS

```
tftpd [directory ...]
```

DESCRIPTION

tftpd is a server that supports the DARPA Trivial File Transfer Protocol. The TFTP server operates at the port indicated in the tftp service description; see `services(5)`. The server is usually started by `inetd(8)`.

The use of `tftpd(1)` does not require an account or password on the remote system. Due to the lack of authentication information, `tftpd` will allow only publicly readable files to be accessed. Files may be written only if they already exist and are publicly writable. Note that this extends the concept of public to include all users on all hosts that can be reached through the network; this may not be appropriate on all systems, and its implications should be considered before enabling the tftp service. The server should have the user ID with the lowest possible privilege.

SEE ALSO

`tftp(1)`, `inetd(8)`

HISTORY

The `tftpd` command appeared in BSD 4.2.

BSD 4.2, 13 May 1991

timed

timed—Time server daemon.

SYNOPSIS

```
timed [-M] [-t] [-d] [-i network] [-n network] [-F host1 host2 ...]
```

DESCRIPTION

timed is a time server daemon and is usually invoked at boot time from the `rc(8)` file. It synchronizes the host's time with the time of other machines in a local area network running `timed(8)`. These time servers will slow down the clocks of some machines and speed up the clocks of others to bring them to the average network time. The average network time is computed from measurements of clock differences using the ICMP timestamp request message.

The service provided by `timed` is based on a master-slave scheme. When `timed(8)` is started on a machine, it asks the master for the network time and sets the host's clock to that time. After that, it accepts synchronization messages periodically sent by the master and calls `adjtime(2)` to perform the needed corrections on the host's clock.

It also communicates with `date(1)` to set the date globally and with `timedc(8)`, a timed control program. If the machine running the master crashes, then the slaves elect a new master from among slaves running with the `-M` flag. A `timed` running without the `-M` or `-F` flags remains a slave. The `-t` flag enables `timed` to trace the messages it receives in the file `/var/log/timed.log`. Tracing can be turned on or off by the program `timedc(8)`. The `-d` flag is for debugging the daemon. It causes the program to not put itself into the background. Usually, `timed` checks for a master time server on each network

to which it is connected, except as modified by the options. It requests synchronization service from the first master server located. If permitted by the `-M` flag, it provides synchronization service on any attached networks on which no current master server is detected. Such a server propagates the time computed by the top-level master. The `-n` flag, followed by the name of a network that the host is connected to (see `networks(5)`), overrides the default choice of the network addresses made by the program. Each time the `-n` flag appears, that network name is added to a list of valid networks. All other networks are ignored. The `-i` flag, followed by the name of a network to which the host is connected (see `networks(5)`), overrides the default choice of the network addresses made by the program. Each time the `-i` flag appears, that network name is added to a list of networks to ignore. All other networks are used by the time daemon. The `-n` and `-i` flags are meaningless if used together.

`timed` checks for a master time server on each network to which it is connected, except as modified by the `-n` and `-i` options. If it finds masters on more than one network, it chooses one network on which to be a “slave” and then periodically checks the other networks to see if the masters there have disappeared.

One way to synchronize a group of machines is to use an NTP daemon to synchronize the clock of one machine to a distant standard or a radio receiver and `-F hostname` to tell its `timed` daemon to trust only itself.

Messages printed by the kernel on the system console occur with interrupts disabled. This means that the clock stops while they are printing. A machine with many disk or network hardware problems and consequent messages cannot keep good time by itself. Each message typically causes the clock to lose a dozen milliseconds. A time daemon can correct the result.

Messages in the system log about machines that failed to respond usually indicate machines that crashed or were turned off. Complaints about machines that failed to respond to initial time settings are often associated with “multi-homed” machines that looked for time masters on more than one network and eventually chose to become a slave on the other network.

WARNING

If two or more time daemons, whether `timed`, NTP, try to adjust the same clock, temporal chaos will result. If both this and another time daemon are run on the same machine, ensure that the `-F` flag is used, so that `timed` never attempts to adjust the local clock.

The protocol is based on UDP/IP broadcasts. All machines within the range of a broadcast that are using the TSP protocol must cooperate. There cannot be more than a single administrative domain using the `-F` flag among all machines reached by a broadcast packet. Failure to follow this rule is usually indicated by complaints concerning “untrusted” machines in the system log.

FILES

`/var/log/timed.log` tracing file for `timed`

`/var/log/timed.masterlog` log file for master `timed`

SEE ALSO

`date(1)`, `adjtime(2)`, `gettimeofday(2)`, `icmp(4)`, `timedc(8)`, “TSP: The Time Synchronization Protocol for UNIX 4.3 BSD,” R. Gusella, S. Zatti.

HISTORY

The `timed` daemon appeared in BSD 4.3.

BSD 4.3, 11 May 1993

timedc

`timedc`—Timed control program.

SYNOPSIS

`timedc` [`command`] [`argument ...`]

DESCRIPTION

timedc is used to control the operation of the timed(8) program. It may be used to

- Measure the differences between machines' clocks
- Find the location where the master time server is running
- Enable or disable tracing of messages received by timed
- Perform various debugging actions

Without any arguments, timedc will prompt for commands from the standard input. If arguments are supplied, timedc interprets the first argument as a command and the remaining arguments as parameters to the command. The standard input may be redirected, causing timedc to read commands from a file. Commands may be abbreviated; recognized commands are

? [command ...]	
help [command ...]	Print a short description of each command specified in the argument list or, if no arguments are given, a list of the recognized commands.
clockdiff host ...	Compute the differences between the clock of the host machine and the clocks of the machines given as arguments.
mstime [host ...]	Show the master time server for specified hosts.
trace {on off}	Enable or disable the tracing of incoming messages to timed in the file.
election host	Asks the daemon on the target host to reset its "election" timers and to ensure that a time master has been elected.
quit	Exit from timedc

Other commands may be included for use in testing and debugging timed; the help command and the program source may be consulted for details.

FILES

- /var/log/timed.log tracing file for timed
- /var/log/timed.masterlog log file for master timed

SEE ALSO

date(1), adjtime(2), icmp(4), timed(8), "TSP: The Time Synchronization Protocol for UNIX 4.3 BSD," R. Gusella, S. Zatti.

DIAGNOSTICS

?Ambiguous command	Abbreviation matches more than one command
?Invalid command	No match found
?Privileged command	Command can be executed by root only

HISTORY

The timedc command appeared in BSD 4.3.

BSD 4.3, 11 May 1993

traceroute

traceroute—Print the route that packets take to the network host.

SYNOPSIS

```
traceroute [-m max_ttl] [-n] [-p port] [-q nqueries]
[-r] [-s src_addr] [-t tos] [-w waittime] host [packet_size]
```

DESCRIPTION

The Internet is a large and complex aggregation of network hardware, connected together by gateways. Tracking the route one's packets follow (or finding the miscreant gateway that's discarding your packets) can be difficult. `traceroute` utilizes the IP protocol time-to-live field and attempts to elicit an ICMP `TIME_EXCEEDED` response from each gateway along the path to some host.

The only mandatory parameter is the destination hostname or IP number. The default probe datagram length is 38 bytes, but this can be increased by specifying a packet size (in bytes) after the destination hostname.

Other options are

<code>-m maxttl</code>	Set the max time-to-live (max number of hops) used in outgoing probe packets. The default is 30 hops (the same default used for TCP connections).
<code>-n</code>	Print hop addresses numerically rather than symbolically and numerically (saves a nameserver address-to-name lookup for each gateway found on the path).
<code>-p port</code>	Set the base UDP port number used in probes (default is 33434). <code>traceroute</code> hopes that nothing is listening on UDP ports base to base + nhops -1 at the destination host (so an ICMP <code>PORT_UNREACHABLE</code> message will be returned to terminate the route tracing). If something is listening on a port in the default range, this option can be used to pick an unused port range.
<code>-q nqueries</code>	Set the number of probes per ttl to <code>nqueries</code> (default is three probes).
<code>-r</code>	Bypass the normal routing tables and send directly to a host on an attached network. If the host is not on a directly attached network, an error is returned. This option can be used to ping a local host through an interface that has no route through it (for example, after the interface was dropped by <code>routed(8)</code>).
<code>-s src_addr</code>	Use the following IP address (which must be given as an IP number, not a hostname) as the source address in outgoing probe packets. On hosts with more than one IP address, this option can be used to force the source address to be something other than the IP address of the interface the probe packet is sent on. If the IP address is not one of this machine's interface addresses, an error is returned and nothing is sent.
<code>-t tos</code>	Set the type-of-service in probe packets to the following value (default zero). The value must be a decimal integer in the range 0 to 255. This option can be used to see if different types of service result in different paths. (If you are not running a BSD 4.3 tahoe or later system, this may be academic because the normal network services such as Telnet and FTP don't let you control the TOS). Not all values of TOS are legal or meaningful; see the IP spec for definitions. Useful values are probably (<code>low delay</code>) and (<code>high throughput</code>).
<code>-v</code>	Verbose output. Received ICMP packets other than <code>TIME_EXCEEDED</code> and <code>UNREACHABLES</code> are listed.
<code>-w</code>	Set the time (in seconds) to wait for a response to a probe (default is 3 seconds).

This program attempts to trace the route an IP packet would follow to some Internet host by launching UDP probe packets with a small `ttl` (time to live) and then listening for an ICMP "time exceeded" reply from a gateway. We start our probes with a `ttl` of one and increase by one until we get an ICMP "port unreachable" (which means we got to "host") or hit a max (which defaults to 30 hops and can be changed with the `-m` flag). Three probes (changed with the `-q` flag) are sent at each `ttl` setting and a line is printed showing the `ttl`, address of the gateway, and round-trip time of each probe. If the probe answers come from different gateways, the address of each responding system will be printed. If there is no response within a three second time-out interval (changed with the `-w` flag), a * is printed for that probe.

We don't want the destination host to process the UDP probe packets, so the destination port is set to an unlikely value (if some clod on the destination is using that value, it can be changed with the `-p` flag).

A sample use and output might be

```
[yak 71]% traceroute nis.nsf.net.
traceroute to nis.nsf.net (35.1.1.48), 30 hops max,
 56 byte packet
 1 helios.ee.lbl.gov (128.3.112.1) 19 ms 19 ms 0 ms
 2 lilac-dmc.Berkeley.EDU (128.32.216.1) 39 ms 39 ms 19 ms
 3 lilac-dmc.Berkeley.EDU (128.32.216.1) 39 ms 39 ms 19 ms
 4 ccngw-ner-cc.Berkeley.EDU (128.32.136.23) 39 ms 40 ms 39 ms
 5 ccn-nerif22.Berkeley.EDU (128.32.168.22) 39 ms 39 ms 39 ms
 6 128.32.197.4 (128.32.197.4) 40 ms 59 ms 59 ms
 7 131.119.2.5 (131.119.2.5) 59 ms 59 ms 59 ms
 8 129.140.70.13 (129.140.70.13) 99 ms 99 ms 80 ms
 9 129.140.71.6 (129.140.71.6) 139 ms 239 ms 319 ms
10 129.140.81.7 (129.140.81.7) 220 ms 199 ms 199 ms
11 nic.merit.edu (35.1.1.48) 239 ms 239 ms 239 ms
```

Note that Lines 2 and 3 are the same. This is due to a buggy kernel on the second hop system—`lb1.csam.arpa`—that forwards packets with a zero `ttl` (a bug in the distributed version of 4.3 BSD). Note that you have to guess what path the packets are taking cross-country because the NSFNet (129.140) doesn't supply address-to-name translations for its NSSs.

A more interesting example is

```
[yak 72]% traceroute allspice.lcs.mit.edu.
traceroute to allspice.lcs.mit.edu (18.26.0.115), 30 hops max
 1 helios.ee.lbl.gov (128.3.112.1) 0 ms 0 ms 0 ms
 2 lilac-dmc.Berkeley.EDU (128.32.216.1) 19 ms 19 ms 19 ms
 3 lilac-dmc.Berkeley.EDU (128.32.216.1) 39 ms 19 ms 19 ms
 4 ccngw-ner-cc.Berkeley.EDU (128.32.136.23) 19 ms 39 ms 39 ms
 5 ccn-nerif22.Berkeley.EDU (128.32.168.22) 20 ms 39 ms 39 ms
 6 128.32.197.4 (128.32.197.4) 59 ms 119 ms 39 ms
 7 131.119.2.5 (131.119.2.5) 59 ms 59 ms 39 ms
 8 129.140.70.13 (129.140.70.13) 80 ms 79 ms 99 ms
 9 129.140.71.6 (129.140.71.6) 139 ms 139 ms 159 ms
10 129.140.81.7 (129.140.81.7) 199 ms 180 ms 300 ms
11 129.140.72.17 (129.140.72.17) 300 ms 239 ms 239 ms
12 * * *
13 128.121.54.72 (128.121.54.72) 259 ms 499 ms 279 ms
14 * * *
15 * * *
16 * * *
17 * * *
18 ALLSPICE.LCS.MIT.EDU (18.26.0.115) 339 ms 279 ms 279 ms
```

Note that the gateways 12, 14, 15, 16, and 17 hop away. Either don't send ICMP "time exceeded" messages or send them with a `ttl` too small to reach us. Lines 14–17 are running the MIT C Gateway code that doesn't send "time exceeded"s. God only knows what's going on with 12.

The silent gateway 12 may be the result of a bug in the 4.[23] BSD network code (and its derivatives): 4.x ($x \leq 3$) sends an unreachable message using whatever `ttl` remains in the original datagram. Because for gateways the remaining `ttl` is zero, the ICMP "time exceeded" is guaranteed to not make it back to us. The behavior of this bug is slightly more interesting when it appears on the destination system:

```
 1 helios.ee.lbl.gov (128.3.112.1) 0 ms 0 ms 0 ms
 2 lilac-dmc.Berkeley.EDU (128.32.216.1) 39 ms 19 ms 39 ms
 3 lilac-dmc.Berkeley.EDU (128.32.216.1) 19 ms 39 ms 19 ms
 4 ccngw-ner-cc.Berkeley.EDU (128.32.136.23) 39 ms 40 ms 19 ms
 5 ccn-nerif35.Berkeley.EDU (128.32.168.35) 39 ms 39 ms 39 ms
 6 csgw.Berkeley.EDU (128.32.133.254) 39 ms 59 ms 39 ms
 7 ***
 8 ***
```

```

9  ***
10 * * *
11 * * *
12 * * *
13 rip.Berkeley.EDU (128.32.131.22)  59 ms !  39 ms !  39 ms
!
```

Notice that there are 12 “gateways” (13 is the final destination) and exactly the last half of them are “missing.” What’s really happening is that rip (a Sun-3 running Sun OS3.5) is using the `ttl` from our arriving datagram as the `ttl` in its ICMP reply. The reply will time out on the return path (with no notice sent to anyone because ICMPs aren’t sent for ICMPs) until we probe with a `ttl` that’s at least twice the path length. That is, rip is really only seven hops away. A reply that returns with a `ttl` of 1 is a clue this problem exists. `traceroute` prints a `!` after the time if the `ttl` is less than or equal to 1. Because vendors ship a lot of obsolete (DEC Ultrix, Sun 3.x) or non-standard HP-UX software, expect to see this problem frequently or take care picking the target host of your probes. Other possible annotations after the time are `!H`, `!N`, `!P` (got a host, network, or protocol unreachable), `!S`, or `!F` (source route failed or fragmentation needed—neither of these should ever occur and the associated gateway is busted if you see one). If almost all the probes result in some kind of unreachable, `traceroute` will give up and exit.

This program is intended for use in network testing, measurement, and management. It should be used primarily for manual fault isolation. Because of the load it could impose on the network, it is unwise to use `traceroute` during normal operations or from automated scripts.

AUTHOR

Implemented by Van Jacobson from a suggestion by Steve Deering. Debugged by a cast of thousands with particularly cogent suggestions or fixes from C. Philip Wood, Tim Seaver, and Ken Adelman.

SEE ALSO

`netstat(1)`, `ping(8)`

BSD 4.3, 6 June 1993

tune2fs

`tune2fs`—Adjust tunable filesystem parameters on second extended filesystems.

SYNOPSIS

```

tune2fs [ -l ][-c max-mount-counts ][-e errors-behavior ]
[ -i interval-between-checks ][ -m reserved-blocks-percentage ]
[ -r reserved-blocks-count ][-u user ][-g group ]device
```

DESCRIPTION

`tune2fs` adjusts tunable filesystem parameters on a Linux second extended filesystem.

Never use `tune2fs` on a read/write mounted filesystem to change parameters!

OPTIONS

<code>-c max-mount-counts</code>	Adjust the maximal mounts count between two filesystem checks.
<code>-e errors-behavior</code>	Change the behavior of the kernel code when errors are detected. <code>errors-behavior</code> can be one of the following:
	<code>continue</code> Continue normal execution.
	<code>remount-ro</code> Remount the filesystem read-only.
	<code>panic</code> Causes a kernel panic.

<code>-g group</code>	Set the user group that can benefit from the reserved blocks. <code>group</code> can be a numerical GID or a group name.
<code>-i interval-between-checks[d m w]</code>	Adjust the maximal time between two filesystem checks. No postfix or <code>d</code> results in days, <code>m</code> in months, and <code>w</code> in weeks. A value of <code>0</code> will disable the time-dependent checking.
<code>-l</code>	List the contents of the filesystem superblock.
<code>-m reserved-blocks-percentage</code>	Adjust the reserved blocks percentage on the given device.
<code>-r reserved-blocks-count</code>	Adjust the reserved blocks count on the given device.
<code>-u user</code>	Set the user who can benefit from the reserved blocks. <code>user</code> can be a numerical UID or a username.

BUGS

We didn't find any bugs. Perhaps there are bugs, but it's unlikely.

WARNING

Use this utility at your own risk. You're modifying filesystems.

AUTHOR

`tune2fs` was written by Remy Card (`card@masi.ibp.fr`), the developer and maintainer of the `ext2` filesystem. `tune2fs` uses the `ext2fs` library written by Theodore T'so (`tytso@mit.edu`). This manual page was written by Christian Kuhtz (`chk@data-hh.Hanse.DE`). Time-dependent checking was added by Uwe Ohse (`uwe@tirka.gun.de`).

AVAILABILITY

`tune2fs` is available for anonymous FTP from `ftp.ibp.fr` and `tsx-11.mit.edu` in `/pub/linux/packages/ext2fs`.

SEE ALSO

`dumpe2fs(8)`, `e2fsck(8)`, `mke2fs(8)`

Version 0.5b, November 1994

tunelp

`tunelp`—Set various parameters for the `lp` device.

SYNOPSIS

```
tunelp device [-i IRQ] [-t TIME] [-c CHARS]
              [-w WAIT] [-a [on|off]] [-o [on|off]] [-C [on|off]]
              [-r] [-s] [-q [on|off]]
```

DESCRIPTION

`tunelp` sets several parameters for the `/dev/lp?` devices, for better performance (or for any performance at all, if your printer won't work without it...). Without parameters, `tunelp` tells whether the device is using interrupts, and if so, which one. With parameters, `tunelp` sets the device characteristics accordingly. The parameters are as follows:

<code>-i <IRQ></code>	The IRQ to use for the parallel port in question. If this is set to something nonzero, <code>-t</code> and <code>-c</code> have no effect. If your port does not use interrupts, this option will make printing stop. <code>tunelp -i 0</code> restores non-interrupt driven (polling) action, and your printer should work again. If your parallel port does support interrupts, interrupt-driven printing should be somewhat faster and efficient and will probably be desirable.
<code>-t <TIME></code>	The amount of time in jiffies that the driver waits if the printer doesn't take a character for the number of tries dictated by the <code>-c</code> parameter. <code>10</code> is the default value. If you want the fastest possible printing and don't care about system load, you can set this to <code>0</code> . If

	you don't care how fast your printer goes or are printing text on a slow printer with a buffer, then 500 (5 seconds) should be fine and will give you very low system load. This value generally should be lower for printing graphics than text, by a factor of approximately 10, for best performance.
-c <CHARS>	The number of times to try to output a character to the printer before sleeping for -t <TIME>. It is the number of times around a loop that tries to send a character to the printer. 120 appears to be a good value for most printers. 250 is the default because there are some printers that require a wait this long, but feel free to change this. If you have a very fast printer like an HP Laserjet 4, a value of 10 might make more sense. If you have a really old printer, you can increase this.
	Setting -t <TIME> to 0 is equivalent to setting -c <CHARS> to infinity.
-w <WAIT>	The busy loop counter for the strobe signal. Although most printers appear to be able to deal with an extremely short strobe, some printers demand a longer one. Increasing this from the default 0 might make it possible to print with those printers. This can also make it possible to use longer cables.
-a [on off]	This is whether to abort on printer error; the default is not to. If you are sitting at your computer, you probably want to be able to see an error and fix it and have the printer go on printing. On the other hand, if you aren't, you might rather that your printer spooler find out that the printer isn't ready, quit trying, and send you mail about it. The choice is yours.
-o [on off]	This option is much like -a. It makes any open() of this device check to see that the device is online and not reporting any out-of-paper or other errors. This is the correct setting for most versions of lpd.
-C [on off]	This option adds extra ("careful") error checking. When this option is on, the printer driver will ensure that the printer is online and not reporting any out-of-paper or other errors before sending data. This is particularly useful for printers that usually appear to accept data when turned off.
-s	This option returns the current printer status, both as a decimal number from 0 to 255 and as a list of active flags. When this option is specified, -q off, turning off the display of the current IRQ, is implied.
	-o, -C, and -s all require a Linux kernel version of 1.1.76 or later.
-r	This option resets the port. It requires a Linux kernel version of 1.1.80 or later.
-q [on off]	This option sets printing the display of the current IRQ setting.

Cohesive Systems, 26 August 1992

update_state

update_state—Update system state.

SYNOPSIS

```
update_state
```

DESCRIPTION

update_state updates a bunch of system states. It takes a long time to execute and would be suitable for execution in a cron job.

Currently, update_state performs the following functions: updates the locate database (in /usr/lib/locate), updates the whatis database (in /usr/man, /usr/local/man, /usr/X386/man, and /usr/interviews/man), and updates the TeX `ls-R` cache file (in /usr/lib/texmf).

BUGS

The script expects things to be where the FSSTND says they are. For example, if you have `makewhatis(8)` in `/usr/lib`, where it is traditionally, then you lose, because it should be in `/usr/bin`.

SEE ALSO

`cron(8)`, `find(1)`, `locate(1)`

AUTHOR

Rik Faith (faith@cs.unc.edu)

Linux 1.0 8, July 1994

uucico

uucico—UUCP file transfer daemon.

SYNOPSIS

`uucico [ options ]`

DESCRIPTION

The `uucico` daemon processes file transfer requests queued by `uucp(1)` and `uux(1)`. It is started when `uucp` or `uux` is run (unless they are given the `-r` option). It is also typically started periodically using entries in the `crontab` tables.

When invoked with `-r1`, `--master`, `-s`, `--system`, or `-S`, the daemon will place a call to a remote system, running in master mode. Otherwise, the daemon will start in slave mode, accepting a call from a remote system. Typically, a special login name will be set up for UUCP, which automatically invokes `uucico` when a call is made.

When `uucico` terminates, it invokes the `uuxqt(8)` daemon, unless the `-q` or `--nouuxqt` option is given; `uuxqt(8)` executes any work orders created by `uux(1)` on a remote system and any work orders created locally that have received remote files for which they were waiting.

If a call fails, `uucico` will usually refuse to retry the call until a certain (configurable) amount of time has passed. This may be overridden by the `-f`, `-force`, or `-S` option.

The `-l`, `--prompt`, `-e`, or `--loop` options may be used to force `uucico` to produce its own prompts of `login:` and `Password:`. When another daemon calls in, it will see these prompts and log in as usual. The login name and password are usually checked against a separate list kept specially for `uucico` rather than the `/etc/passwd` file; it is possible on some systems to direct `uucico` to use the `/etc/passwd` file. The `-l` or `--prompt` option will prompt once and then exit; in this mode, the UUCP administrator or the superuser may use the `-u` or `-login` option to force a login name, in which case `uucico` will not prompt for one. The `-e` or `-loop` option will prompt again after the first session is over; in this mode, `uucico` will permanently control a port.

If `uucico` receives a `SIGQUIT`, `SIGTERM`, or `SIGPIPE` signal, it will cleanly abort any current conversation with a remote system and exit. If it receives a `SIGHUP` signal, it will abort any current conversation, but will continue to place calls to (if invoked with `-r1` or `--master`) and accept calls from (if invoked with `-e` or `--loop`) other systems. If it receives a `SIGINT` signal, it will finish the current conversation but will not place or accept any more calls.

OPTIONS

The following options may be given to `uucico`:

<code>-r1</code> , <code>--master</code>	Start in master mode (call out to a system); implied by <code>-s</code> , <code>--system</code> , or <code>-S</code> . If no system is specified, call any system for which work is waiting to be done.
<code>-r0</code> , <code>--slave</code>	Start in slave mode. This is the default.
<code>-s system</code> , <code>--system system</code>	Call the named system.

<code>-S system</code>	Call the named system, ignoring any required wait. This is equivalent to <code>-s system -f</code> .
<code>-f, ---force</code>	Ignore any required wait for any systems to be called.
<code>-l, ---prompt</code>	Prompt for login name and password using <code>login:</code> and <code>Password:</code> . This allows <code>uucico</code> to be easily run from <code>inetd(8)</code> . The login name and password are checked against the UUCP password file, which probably has no connection to the file <code>/etc/passwd</code> . The <code>--login</code> option may be used to force a login name, in which case <code>uucico</code> will only prompt for a password.
<code>-p port, ---port port</code>	Specify a port to call out on or to listen to.
<code>-e, ---loop</code>	Enter endless loop of login/password prompts and slave mode daemon execution. The program will not stop by itself; you must use <code>kill(1)</code> to shut it down.
<code>-w, ---wait</code>	After calling out (to a particular system when <code>-s, --system</code> , or <code>-S</code> is specified or to all systems that have work when just <code>-r1</code> or <code>--master</code> is specified), begin an endless loop as with <code>--loop</code> .
<code>-q, ---nouuxqt</code>	Do not start the <code>uuxqt(8)</code> daemon when finished.
<code>-c, ---quiet</code>	If no calls are permitted at this time, then don't make the call, but also do not put an error message in the log file and do not update the system status (as reported by <code>uustat(1)</code>). This can be convenient for automated polling scripts, which may want to simply attempt to call every system rather than worry about which particular systems may be called at the moment. This option also suppresses the log message indicating that there is no work to be done.
<code>-C, ---ifwork</code>	Only call the system named by <code>-s, --system</code> , or <code>-S</code> if there is work for that system.
<code>-D, ---nodetach</code>	Do not detach from the controlling terminal. Normally, <code>uucico</code> detaches from the terminal before each call out to another system and before invoking <code>uuxqt</code> . This option prevents this.
<code>-u name, ---login name</code>	Set the login name to use instead of that of the invoking user. This option may only be used by the UUCP administrator or the superuser. If used with <code>--prompt</code> , this will cause <code>uucico</code> to prompt only for the password, not the login name.
<code>-z, ---try-next</code>	If a call fails after the remote system is reached, try the next alternate rather than simply exiting.
<code>-i type, ---stdin type</code>	Set the type of port to use when using standard input. The only support port type is TLI, and this is only available on machines that support the TLI networking interface. Specifying <code>-iTLI</code> causes <code>uucico</code> to use TLI calls to perform I/O.
<code>-x type, -X type, ---debug type</code>	Turn on particular debugging types. The following types are recognized: <code>abnormal</code> , <code>chat</code> , <code>handshake</code> , <code>uucp-proto</code> , <code>proto</code> , <code>port</code> , <code>config</code> , <code>spooldir</code> , <code>execute</code> , <code>incoming</code> , <code>outgoing</code> . Multiple types may be given, separated by commas, and the <code>--debug</code> option may appear multiple times. A number may also be given, which will turn on that many types from the foregoing list; for example, <code>--debug 2</code> is equivalent to <code>--debug abnormal,chat</code> . The debugging output is sent to the debugging file, usually one of <code>/usr/spool/uucp/Debug</code> , <code>/usr/spool/uucp/DEBUG</code> , or <code>/usr/spool/uucp/.Admin/audit.local</code> .
<code>-I file, ---config file</code>	Set configuration file to use. This option may not be available, depending on how <code>uucico</code> was compiled.
<code>-v, ---version</code>	Report version information and exit.
<code>--help</code>	Print a help message and exit.
<code>-u login</code>	This option is ignored. It is only included because some versions of <code>uucpd</code> invoke <code>uucico</code> with it.

FILES

The filenames may be changed at compilation time or by the configuration file, so these are only approximations:

<code>/usr/lib/uucp/config</code>	Configuration file.
<code>/usr/lib/uucp/passwd</code>	Default UUCP password file.

/usr/spool/uucp	UUCP spool directory.
/usr/spool/uucp/Log	UUCP log file.
/usr/spool/uucppublic	Default UUCP public directory.
/usr/spool/uucp/Debug	Debugging file.

SEE ALSO

kill(1), uucp(1), uux(1), uustat(1), uuxqt(8)

AUTHOR

Ian Lance Taylor (ian@airs.com)

Taylor UUCP 1.05

vmstat

vmstat—Report virtual memory statistics.

SYNOPSIS

vmstat [-n] [delay [count]]

DESCRIPTION

vmstat reports information about processes, memory, paging, block IO, traps, and CPU activity.

The first report produced gives averages since the last reboot. Additional reports give information on a sampling period of length delay. The process and memory reports are instantaneous in either case.

OPTIONS

The -n switch causes the header to be displayed only once rather than periodically.

delay is the delay between updates in seconds. If no delay is specified, only one report is printed with the average values since boot.

count is the number of updates. If no count is specified and delay is defined, count defaults to infinity.

FIELD DESCRIPTIONS

<i>Procs</i>	
r	The number of processes waiting for runtime.
b	The number of processes in uninterruptible sleep.
w	The number of processes swapped out but otherwise runnable. This field is calculated, but Linux never desperation swaps.
<i>Memory</i>	
swpd	The amount of virtual memory used (KB).
free	The amount of idle memory (KB).
buff	The amount of memory used as buffers (KB).
<i>Swap</i>	
si	Amount of memory swapped in from disk (KB/s).
so	Amount of memory swapped to disk (KB/s).

IO

bi	Blocks sent to a block device (blocks/s).
bo	Blocks received from a block device (blocks/s).

System

in	The number of interrupts per second, including the clock.
cs	The number of context switches per second.

CPU (These are percentages of total CPU time.)

us	User time.
sy	System time.
id	Idle time.

NOTES

vmstat does not require special permissions.

These reports are intended to help identify system bottlenecks. Linux vmstat does not count itself as a running process.

All Linux blocks are currently 1KB, except for CD-ROM blocks, which are 2KB.

FILES

/proc/meminfo
/proc/stat
/proc/*/stat

SEE ALSO

ps(1), top(1), free(1)

BUGS

vmstat does not tabulate the block IO per device or count the number of system calls.

AUTHOR

Written by Henry Ware (a1172@yfn.ysu.edu)

Throatwobbler Ginkgo Labs, 27 July 1994

vipw

vipw—Edit the password file.

SYNOPSIS

vipw

DESCRIPTION

vipw edits the password file after setting the appropriate locks and does any necessary processing after the password file is unlocked. If the password file is already locked for editing by another user, vipw will ask you to try again later. The default editor for vipw is vi(1).

ENVIRONMENT

If the following environment variable exists, it will be utilized by `vipw`:

EDITOR The editor specified by the string. `EDITOR` will be invoked instead of the default editor `vi(1)`.

SEE ALSO

`passwd(1)`, `vi(1)`, `passwd(5)`

HISTORY

The `vipw` command appeared in BSD 4.0.

BSD 4, 16 March 1991

zdump

`zdump`—Time zone dumper.

SYNOPSIS

```
zdump [ -v ] [ -c cutoffyear ] [ zonename ... ]
```

DESCRIPTION

`zdump` prints the current time in each `zonename` named on the command line.

These options are available:

<code>-v</code>	For each <code>zonename</code> on the command line, print the current time, the time at the lowest possible time value, the time one day after the lowest possible time value, the times both one second before and exactly at each detected time discontinuity, the time at one day less than the highest possible time value, and the time at the highest possible time value. Each line ends with <code>isdst=1</code> if the given time is Daylight Saving Time or <code>isdst=0</code> otherwise.
<code>-c cutoffyear</code>	Cut off the verbose output near the start of the given year.

SEE ALSO

`newctime(3)`, `tzfile(5)`, `zic(8)`

zic

`zic`—Time zone compiler.

SYNOPSIS

```
zic [ -v ] [ -d directory ] [ -l localtime ] [ -p posixrules ]
[ -L leapsecondfilename ] [ -s ] [ -y command ] [ filename ... ]
```

DESCRIPTION

`zic` reads text from the files named on the command line and creates the time conversion information files specified in this input. If a filename is `-`, the standard input is read.

These options are available:

<code>-d directory</code>	Create time conversion information files in the named directory rather than in the standard directory named below.

<code>-l timezone</code>	Use the given time zone as local time. <code>zic</code> will act as if the input contained a link line of the form. Link <code>timezone localtime</code> .
<code>-p timezone</code>	Use the given time zone's rules when handling POSIX-format time zone environment variables. <code>zic</code> will act as if the input contained a link line of the form. Link <code>timezone posixrules</code> .
<code>-L leapsecondfilename</code>	Read leap second information from the file with the given name. If this option is not used, no leap second information appears in output files.
<code>-v</code>	Complain if a year that appears in a data file is outside the range of years representable by <code>time(2)</code> values.
<code>-s</code>	Limit time values stored in output files to values that are the same whether they're taken to be signed or unsigned. You can use this option to generate SVVS-compatible files.
<code>-y command</code>	Use the given command rather than <code>yearistype</code> when checking year types.

Input lines are made up of fields. Fields are separated from one another by any number of whitespace characters. Leading and trailing whitespace on input lines is ignored. An unquoted sharp character (#) in the input introduces a comment that extends to the end of the line the sharp character appears on. Whitespace characters and sharp characters may be enclosed in double quotes (") if they're to be used as part of a field. Any line that is blank (after comment stripping) is ignored. Non-blank lines are expected to be of one of three types: rule lines, zone lines, and link lines.

A rule line has the form

```
Rule NAME FROM TO TYPE IN ON AT SAVE LETTER/S
```

For example:

```
Rule US 1967 1973 - Apr lastSun 2:00 1:00 D
```

The fields that make up a rule line are

NAME	Gives the (arbitrary) name of the set of rules this rule is part of.												
FROM	Gives the first year in which the rule applies. Any integer year can be supplied; the Gregorian calendar is assumed. The word <code>minimum</code> (or an abbreviation) means the minimum year representable as an integer. The word <code>maximum</code> (or an abbreviation) means the maximum year representable as an integer. Rules can describe times that are not representable as time values, with the unrepresentable times ignored; this allows rules to be portable among hosts with differing time value types.												
TO	Gives the final year in which the rule applies. In addition to minimum and maximum, the word <code>only</code> (or an abbreviation) may be used to repeat the value of the <code>FROM</code> field.												
TYPE	Gives the type of year in which the rule applies. If <code>TYPE</code> is <code>-</code> , the rule applies in all years between <code>FROM</code> and <code>TO</code> inclusive. If <code>TYPE</code> is something else, then <code>zic</code> executes the command <code>yearistype year type</code> to check the type of a year. An exit status of zero is taken to mean that the year is of the given type; an exit status of one is taken to mean that the year is not of the given type.												
IN	Names the month in which the rule takes effect. Month names may be abbreviated.												
ON	Gives the day on which the rule takes effect. Recognized forms include <table data-bbox="482 1407 1249 1621"> <tr> <td><code>5</code></td><td>The fifth of the month</td></tr> <tr> <td><code>lastSun</code></td><td>The last Sunday in the month</td></tr> <tr> <td><code>lastMon</code></td><td>The last Monday in the month</td></tr> <tr> <td><code>Sun>=8</code></td><td>First Sunday on or after the eighth</td></tr> <tr> <td><code>Sun<=25</code></td><td>Last Sunday on or before the 25th</td></tr> <tr> <td colspan="2">Names of days of the week may be abbreviated or spelled out in full. Note that there must be no spaces within the <code>ON</code> field.</td></tr> </table>	<code>5</code>	The fifth of the month	<code>lastSun</code>	The last Sunday in the month	<code>lastMon</code>	The last Monday in the month	<code>Sun>=8</code>	First Sunday on or after the eighth	<code>Sun<=25</code>	Last Sunday on or before the 25th	Names of days of the week may be abbreviated or spelled out in full. Note that there must be no spaces within the <code>ON</code> field.	
<code>5</code>	The fifth of the month												
<code>lastSun</code>	The last Sunday in the month												
<code>lastMon</code>	The last Monday in the month												
<code>Sun>=8</code>	First Sunday on or after the eighth												
<code>Sun<=25</code>	Last Sunday on or before the 25th												
Names of days of the week may be abbreviated or spelled out in full. Note that there must be no spaces within the <code>ON</code> field.													

AT	Gives the time of day at which the rule takes effect. Recognized forms include
2	Time in hours
2:00	Time in hours and minutes
15:00	24-hour format time (for times after noon)
1:28:14	Time in hours, minutes, and seconds
	Any of these forms may be followed by the letter <i>w</i> if the given time is local wall clock time, <i>s</i> if the given time is local standard time, or <i>u</i> (or <i>g</i> or <i>z</i>) if the given time is universal time; in the absence of an indicator, wall clock time is assumed.
SAVE	Gives the amount of time to be added to local standard time when the rule is in effect. This field has the same format as the AT field (although, of course, the <i>w</i> and <i>s</i> suffixes are not used).
LETTER/S	Gives the variable part (for example, the <i>s</i> or <i>d</i> in EST or EDT) of time-zone abbreviations to be used when this rule is in effect. If this field is <i>-</i> , the variable part is null.

A zone line has the form

Zone NAME GMTOFF RULES/SAVE FORMAT [UNTIL]

For example:

Zone Australia/Adelaide 9:30 Aus CST 1971 Oct 31 2:00

The fields that make up a zone line are

NAME	The name of the time zone. This is the name used in creating the time conversion information file for the zone.
GMTOFF	The amount of time to add to GMT to get standard time in this zone. This field has the same format as the AT and SAVE fields of rule lines; begin the field with a minus sign if time must be subtracted from GMT.
RULES/SAVE	The name of the rules that apply in the time zone or, alternately, an amount of time to add to local standard time. If this field is <i>-</i> , standard time always applies in the time zone.
FORMAT	The format for time zone abbreviations in this time zone. The pair of characters <i>%s</i> is used to show where the variable part of the time-zone abbreviation goes. Alternately, a slash (/) separates standard and daylight abbreviations.
UNTIL	The time at which the GMT offset or the rules change for a location. It is specified as a year, a month, a day, and a time of day. If this is specified, the time-zone information is generated from the given GMT offset and rule change until the time specified. The next line must be a continuation line; this has the same form as a zone line except that the string <i>Zone</i> and the name are omitted because the continuation line will place information starting at the time specified as the UNTIL field in the previous line in the file used by the previous line. Continuation lines may contain an UNTIL field, just as zone lines do, indicating that the next line is a further continuation.

A link line has the form

Link LINK-FROM LINK-TO

For example:

Link US/Eastern EST5EDT

The LINK-FROM field should appear as the NAME field in some zone line; the LINK-TO field is used as an alternate name for that zone.

Except for continuation lines, lines may appear in any order in the input.

Lines in the file that describe leap seconds have the following form:

Leap YEAR MONTH DAY HH:MM:SS CORR R/S

For example:

Leap 1974 Dec 31 23:59:60 + S

The YEAR, MONTH, DAY, and HH:MM:SS fields tell when the leap second happened. The CORR field should be + if a second was added or - if a second was skipped. The R/S field should be (an abbreviation of) *Stationary* if the leap second time given by the other fields should be interpreted as GMT or (an abbreviation of) *Rolling* if the leap second time given by the other fields should be interpreted as local wall clock time.

NOTE

For areas with more than two types of local time, you may need to use local standard time in the AT field of the earliest transition time's rule to ensure that the earliest transition time recorded in the compiled file is correct.

FILE

/usr/local/etc/zoneinfo standard directory used for created files.

SEE ALSO

`newctime(3)`, `tzfile(5)`, `zdump(8)`

Part IX:

Kernel Reference
Guide

add_timer, del_timer, init_timer

add_timer, del_timer, init_timer—Manage event timers.

SYNOPSIS

```
#include <asm/param.h>
#include <linux/timer.h>
extern void add_timer(struct timer_list * timer);
extern int del_timer(struct timer_list * timer);
extern inline void init_timer(struct timer_list * timer);
```

DESCRIPTION

add_timer schedules an event, adding it to a linked list of events maintained by the kernel. del_timer deletes a scheduled event. timer points to a

```
struct timer_list {
    struct timer_list *next;
    struct timer_list *prev;
    unsigned long expires;
    unsigned long data;
    void (*function)(unsigned long);
};
```

init_timer sets next and prev to NULL. This is required for the argument of add_timer. expires is the desired duration of the timer in jiffies, where there are HZ (typically 100) jiffies per second. When the timer expires, function is called with data as its argument. It is the responsibility of function to delete the event. If the same function is managing several timers, the argument can be used to distinguish which one expired.

RETURN VALUE

del_timer returns zero on error—if next or prev are not NULL, but the timer was not found. del_timer also sets expires to the time remaining before the timer expires and sets next and prev to NULL. Thus, calling del_timer followed immediately by add_timer is a no-op provided a kernel tick does not occur between the two calls.

AUTHOR

Linus Torvalds

Linux 1.2.8, 31 May 1995

adjust_clock

adjust_clock—Adjusts startup time counter to tick in GMT.

SYNOPSIS

```
linux/kernel/sys.c
void adjust_clock();
```

DESCRIPTION

This routine adjusts the startup time by adding the time zone information to it. The goal is to get the startup time ticking in GMT time.

NOTES

This routine is called from settimeofday(2) when the time-zone information is first set.

AUTHOR

Theodore T'so (tytso@mit.edu)

SEE ALSO

settimeofday(2)

Linux 0.99.10, 7 July 1993

ctrl_alt_del

ctrl_alt_del—Routes the keyboard interrupt Ctrl+Alt+Del key sequence.

SYNOPSIS

```
linux/kernel/sys.c
void ctrl_alt_del(void);
```

DESCRIPTION

This simple routine tests the variable `C_A_D` for a true/false condition. If it is true, a hard reset is done by the system. Otherwise, a signal `SIGINT` is sent to the process with the process ID 1, usually a program called `init`.

WARNINGS

This routine is in interrupt mode. It cannot `sync()` your system. Data loss may occur. It is recommended that you configure your system to send a signal to `init`, where you can control the shutdown.

NOTES

The default of this function is to do hard resets immediately.

AUTHOR

Linus Torvalds

SEE ALSO

reboot(2), reset_hard_now(9), sync(2)

Linux 0.99.10, 6 July 1993

file_table

file_table—Detailed description of the table and table entry.

SYNOPSIS

```
From #include <linux/fs.h>

struct file {
    mode_t f_mode;
    dev_t f_rdev; /* needed for /dev/tty */
    off_t f_pos;
    unsigned short f_flags;
    unsigned short f_count;
    unsigned short f_reada;
    struct file *f_next, *f_prev;
    struct inode *f_inode;
```

```
struct file_operations *f_op;
};
```

From `linux/fs/file_table.c`

```
struct file *first_file;
int nr_files = 0;
```

DESCRIPTION

The file table is fundamentally important to any UNIX system. It is where all open files (Linux includes closed files as well) are stored and managed by the kernel. For Linux, you can hardly do anything without referencing it in some way.

Linux stores its file table as a double circular linked list. The root pointer to the “head” of this list is `first_file`. Also, a count of how many entries are in the file table is maintained, called `nr_files`. Under this scheme, the file table for Linux could be as large as memory could hold. Unfortunately, this would be unmanageable in most cases. Your computer would be in the kernel most of the time when processes are more important. To keep this from happening, `nr_files` is tested against `NR_FILE` to limit the number of file table entries.

UNDERSTANDING THE STRUCTURE OF THE FILE TABLE

The file table is organized as a double circular linked list. Imagine a circle of people with everyone facing the same direction. Each person is facing so that one arm is in the circle and the other arm is outside the circle. Now, if each person put his or her right hand on the shoulder of the person in front of him or her and if each person touched the person behind him or her with his or her left hand. You have formed two circles of arms, one inside and the other outside. The right arms represent pointers to the next entry (or person). The left arms represent pointers to the previous entry (or person).

THE FILE STRUCTURE, A FILE TABLE ENTRY

At first glance, a table entry looks quite simple. An entry contains how a file was opened, what tty device, a reference count, pointers to other entries, pointer to v-node (the vfs i-node) filesystem-specific i-node information, and so on.

<code>f_mode</code>	After ANDing with 0 <code>ACCMODE</code> , this is what bits 0 and 1 mean:
00	No permissions needed
01	Read-permission
10	Write-permission
11	Read-write
<code>f_rdev</code>	It is used only with tty lines. It contains the major and minor numbers of the tty device.
<code>f_pos</code>	The current position in a file, if meaningful.
<code>f_flags</code>	Storage for the flags from <code>open()</code> and <code>fcntl()</code>
<code>f_count</code>	Reference counter
<code>f_reada</code>	This is a Boolean variable where <code>True</code> means that an actual read is needed.
<code>f_next, f_prev</code>	Pointers to other entries
<code>f_inode</code>	Pointer to v-node and filesystem-specific i-node information
<code>f_op</code>	Pointer to a file's operations

AUTHOR

Linus Torvalds

SEE ALSO

`insert_file_free(9)`, `remove_file_free(9)`, `put_last_free(9)` `grow_files(9)`, `file_table_init(9)`, `get_empty_filp(9)`

Linux 0.99.10, 11 July 1993

file_table_init

`file_table_init`—Initializes the file table in the kernel.

SYNOPSIS

```
linux/fs/file_table.c unsigned long file_table_init(
unsigned long start, unsigned long end);
```

DESCRIPTION

This routine is called from `kernel_start()` in `linux/init/main.c`. It sets `first_file`, a struct file pointer, to `NULL`. This is the head of the linked list of open files maintained in the kernel, the infamous file table in all UNIXs.

RETURN VALUE

Returns `start`.

NOTES

Because this is part of the kernel's startup routine, it has the option to allocate memory, in kernel space, for itself. It does not need to do this and returns the new start of memory for the next initializing section. In this case, `start` is returned unmodified.

AUTHOR

Linus Torvalds

Linux 0.99.10, 9 July 1993

filesystems

`filesystems`—Details the table of configured filesystems.

SYNOPSIS

```
linux/fs/filesystems.c
```

```
From #include <linux/fs.h>
```

```
struct file_system_type {
struct super_block *(*read_super) (struct super_block *, void *, int);
char *name;
int requires_dev;
};
```

DESCRIPTION

This source code makes a data structure call `file_systems[]`, which contains all the configured filesystems for the kernel. It is used primarily in `linux/fs/super.c` for many of the mounting of filesystems functions.

THE MEANINGS

This first member, in struct `file_system_type`, is a function pointer to a routine that will read in the `super_block`. A `super_block` generically means an i-node or special place on the device where information about the overall filesystem is stored.

The name is just the string representation of the name of a specific filesystem, such as `ext2` or `minix`.

The final member, `int_requires_dev`, is a Boolean value. If it is `True`, then the filesystem requires a block device. For `False`, it is unclear what happens, but an unnamed device is used, such as `proc` and `nfs`.

AUTHOR

Linus Torvalds

Linux 0.99.10, 12 July 1993

get_empty_filp

`get_empty_filp`—Fetches an unreferenced entry from the file table.

SYNOPSIS

```
linux/fs/file_table.c
struct file *get_empty_filp(void);
```

DESCRIPTION

This routine will seek out an entry that is not being referenced by any processes. If none are found, then it will add new entries to the file table, minimum of `NR_FILE` entries.

NOTES

Due to `grow_files()`, a whole page of entries is created at one time. This may make more than `NR_FILE` entries. Also when an unreferenced entry is found, it is moved to the “end” of the file table. This heuristic is used to speed up finding unreferenced entries.

RETURN VALUE

`NULL`—No entries were found and the file table is full.

Returns a pointer to the entry in the file table.

AUTHOR

Linus Torvalds

SEE ALSO

`grow_files(9)`

Linux 0.99.10, 12 July 1993

grow_files

`grow_files`—Adds entries to the file table.

SYNOPSIS

```
linux/fs/file_table.c
void grow_files(void);
```

DESCRIPTION

This function adds entries to the file table. First, it allocates a page of memory. It fills the entire page with entries, adding each to the file table.

AUTHOR

Linus Torvalds

SEE ALSO

insert_file_free(9), remove_file_free(9), put_last_free(9)

Linux 0.99.10, 12 July 1993

in_group_p

in_group_p—Searches group IDs for a match.

SYNOPSIS

```
linux/kernel/sys.c
int in_group_p(gid_t grp);
```

DESCRIPTION

Searches supplementary group IDs and the effective group ID for a match with `grp`.

RETURN VALUE

Returns `True` (1) if found; otherwise, `false` (0).

AUTHOR

Linus Torvalds

SEE ALSO

getgroups(2), getgid(2), getregid(2), setgid(2), setregid(2), setgroups(2)

Linux 0.99.10, 7 July 1993

insert_file_free

insert_file_free—Adds a file entry into the file table.

SYNOPSIS

```
linux/fs/file_table.c
static void insert_file_free(struct file *file);
```

DESCRIPTION

This nightmare of pointers adds `file` into the file table with the root pointer at `file`. This is a building block of the file table management.

AUTHOR

Linus Torvalds

SEE ALSO

file_table_init(9), remove_file_free(9), put_last_free(9)

See `file_table(9)` for details on the file table structure.

Linux 0.99.10

kernel_mktime

`kernel_mktime`—Convert startup `struct mktime` into the number of seconds since 00:00:00 January 1, 1970.

SYNOPSIS

```
linux/kernel/mktime.c
long kernel_mktime(struct mktime * time);
```

DESCRIPTION

This routine is called from `time_init(void)`, `linux/init/main.c`. `kernel_mktime()` converts `struct mktime` (initialized from CMOS) into an encoded long.

CONVERSION METHOD

First an array, `month[12]`, is created, holding how many seconds have passed to reach a peculiar month for a leap year. Next, it subtracts 70 from the current year, making 1970 the beginning year. It is math magic after this point; please look yourself. If you know why it does this, then send e-mail (see `nroff` source).

RETURN VALUE

Returns the encoded time in a long.

FILES

`linux/kernel/mktime.c` home of routine

NOTES

This routine is called only during startup of the kernel.

Historically, the value (encoded long) counts the number of seconds since the Epoch, which occurred at 00:00:00 January 1, 1970, and is called Coordinated Universal Time (UTC). In older manuals, this event is called Greenwich Mean Time (GMT).

WARNINGS

`kernel_mktime()` doesn't check to see if the year is greater than 1969. Be sure your CMOS is set correctly. It is customary to set on-board clocks to GMT and let processes who ask for the time to convert it to local time, if necessary.

RESTRICTIONS

For kernel use only.

AUTHOR

Linus Torvalds

Linux 0.99.10, 5 July 1993

proc_sel

`proc_sel`—Select a process by a criterion.

SYNOPSIS

```
linux/kernel/sys.c
#include <linux/resource.h>
static int proc_sel(struct task_struct *p, int which, int who);
```

DESCRIPTION

Compares a task *p* to supplied information or the current task in some aspect of priority. If *who* is zero, the comparison is task *p* and the current task. Otherwise, *who* and **p* are the supplied information for the comparison.

OPTIONS

Valid values of which:

PRIO_PROCESS	Compares process ID numbers. There is an exception here. If <i>who</i> is not zero and task <i>p</i> is the current task, then <code>True</code> is always returned.
PRIO_PGRP	Compares process group leader numbers.
PRIO_USER	Compares user ID numbers.

RETURN VALUE

Returns truth values (0, 1).

AUTHOR

Linus Torvalds

SEE ALSO

`sys_setpriority(2)`, `sys_getpriority(2)`

Linux 0.99.10, 7 July 1993

put_file_last

`put_file_last`—Moves a file to the “end” of the file table.

SYNOPSIS

```
linux/fs/file_table.c
static void put_last_free(struct file *file);
```

DESCRIPTION

This function will remove *file* from the file table and insert it again at the end. You can access by `first_file->prev`

AUTHOR

Linus Torvalds

SEE ALSO

`insert_file_free(9)`, `remove_file_free(9)`

Linux 0.99.10, 11 July 1993

remove_file_free

`remove_file_free`—Remove a file table entry from the linked list.

SYNOPSIS

```
linux/fs/file_table.c
static void remove_file_free(struct file *file);
```

DESCRIPTION

This routine removes the file from the table. This is used mostly for moving a file to the “end” of the list.

AUTHOR

Linus Torvalds

SEE ALSO

`insert_file_free(9)`, `put_file_last(9)`

Index

Symbols

* (asterisk), *bash special parameters*, 15
 @ (at sign), *bash special parameters*, 15
 \ (backslash), *bash escape character*, 14
 \$ (dollar sign)
 bash special parameters, 15
 expansion, 19
 ftp command, 148
 ! (exclamation point)
 bash special parameters, 15
 ftp command, 148
 ! command (telnet), 512
 > (greater than sign),
 redirection operator, 21
 - (hyphen), *bash special parameters*, 15
 < (less than sign), redirection operator, 21
 | (pipeline), *bash*, 12
 # (pound sign)
 bash comments, 14
 bash special parameters, 15
 ? (question mark)
 bash special parameters, 15
 ftp command, 152
 ? command
 telnet, 512
 xauth, 591
 _ (underscore), *bash special parameters*, 15
 / directory, 1236
 0, *bash special parameter*, 15
 8859-1 character set, 1064
 8859-2 character set, 1064
 8859-3 character set, 1064
 8859-4 character set, 1064
 8859-5 character set, 1065
 8859-6 character set, 1065
 8859-7 character set, 1065
 8859-8 character set, 1065
 8859-9 character set, 1065
 8859-10 character set, 1065

A

Abekas YUV bytes, converting to portable pixmaps, 731
 abort() function, 892
 abs() function, 892-893
 absolute values, 892-893
 floating-point numbers, 919
 long integers, 960-961
 accept, 740-741
 access, 741-742
 errors, 741
 restrictions, 741
 return value, 741
 access control
 files, changing permissions, 61-62
 hosts_access, 1133-1136
 diagnostics, 1136
 files, 1133, 1136
 operators, 1134
 patterns, 1133-1134
 remote username lookup, 1134-1135
 rules, 1133
 shell commands, 1134
 wildcards, 1134
 language extensions, 1137-1139
 memory, 804-805
 NNTP sites, 1167-1168
 account (ftp command), 148
 acct, 742
 acos() function, 893
 acosh() function, 893-894
 active, 1104-1105
 active.times, 1104-1105
 add (cvs command), 96
 ADD_ADDRESS environ-
 ment variable, 529
 add_timer, 1424
 addtinfo, 2
 addgroup, 1258-1259
 addmntent() function,
 935-936

addresses

Internet, manipulating,
 953-954
 mail addressing, 1244-1246
 abbreviations, 1245
 case sensitivity, 1245
 compatibility, 1245
 postmasters, 1246
 routing, 1245
 physical, accessing, 818
 sed, 476
 virtual memory, remapping,
 805-806
 adduser, 1258-1259
 adduser.conf, 1105
 adjtimex, 742-743
 adjust_clock, 1424-1425
 admin (cvs command), 96
 advisory locks, open files
 (applying/removing), 757
 afmtodit, 2-4
 files, 3
 options, 3
 running, 3
 agetty, 1259-1262
 arguments, 1260
 bugs, 1261
 diagnostics, 1261
 files, 1261
 issue escapes, 1261
 options, 1260
 alarm, 744
 alarm clock, setting, 744
 alias (shell command), 35
 aliases, 23-24, 1106
 bugs, 1106
 printing, 35
 removing names, 45
 alloca function, 894
 bugs, 894
 return values, 894
 allocating memory, 894, 976
 allow-null_glob_expansion
 variable (*bash*), 17
 allow-send-events() action
 (xterm), 714

- alphasort() function, 1012-1013
- American Standard Code for Information, *see* ASCII
- Andrew Toolkit raster objects, converting to portable bitmaps, 10
- ANSI C, converting to Kernighan & Ritchie, 4
- ansi2knr, 4
- antialiasing portable anymaps, 381-382
- anytopnm, 4
- append (ftp command), 148
- application resources, printing, 5
- applications (client), listing, 669-670
- appres, 5
- ar, 5-7
 - copying, 7
 - modifiers, 7
 - options, 6-7
- arc cosines, 893
- arc sines, 894-895
- arc tangents, 896
 - two variables, 896-897
- arch, 8
- archive, 1262-1263
- archives
 - creating, 5-7
 - extracting from, 5-7
 - indexes (generating), 437-438
 - modifying, 5-7
 - shell, creating, 484-487
- arguments
 - concatenating, 37
 - outputting, 36-37
 - reading from standard input, 586-587
- arithmetic
 - evaluation
 - bash*, 34
 - let command*, 39
 - expansion, *bash*, 20
- functions
 - awk*, 168-169
 - sin()*, 1020-1021
 - sinh()*, 1021
 - sqrt()*, 1023
 - tan()*, 1047-1048
 - tanh()*, 1048
- performing on portable anymaps, 382-383
- arp, 1263
- ARP cache, manipulating, 1263
- arrays
 - awk*, 164
 - linear searches, 975-976
 - searching sorted, 900-901
 - sorting, 1000
- articles (news), *see* tin
- as, 8-9
- ASCII (American Standard Code for Information), 1064
 - character set, 1214-1216
 - graphics, converting to portable graymap, 10
- ascii (ftp command), 148
- ascii manual page, 1214-1216
- asciitopgm, 10
- asctime, 984-986
- asctime() function, 910
- asin() function, 894-895
 - errors, 895
 - return value, 895
- asinh() function, 895
- assemblers, as, 8-9
- assert() function, 895-896
- asterisk (*), *bash* special parameters, 15
- at sign (@), *bash* special parameters, 15
- atan() function, 896
- atan2() function, 896-897
- atanh() function, 897
- Atari compressed Spectrum files, converting to portable pixmaps, 494
- Atari Degas PI1 files, converting to portable pixmaps, 378
- Atari Degas PI3 files, converting to portable bitmaps, 379
- Atari uncompressed Spectrum files, converting to portable pixmaps, 495-496
- atexit() function, 897-898
 - errors, 898
 - return value, 898
- atktopbm, 10
- atobm, 49-57
 - options, 50
- atof() function, 898
- atoi() function, 898-899
- atol() function, 899
- attributes, file, 59
- authentication
 - cidntd, 69-70
 - Kerberos authentication, 461
 - pcnfsd, 1355-1356
 - pppd, 1366-1367
- authority files (X), *xauth* utility, 587-592
- auto_resume variable (*bash*), 18
- AutoCAD slide files, converting to portable pixmaps, 490-491
- AUTOSUBSCRIBE environment variable, 529
- AUTOUNSUBSCRIBE environment variable, 530
- awk*
 - actions, 165-166
 - arithmetic functions, 168-169
 - control statements, 167
 - fields, 163
 - functions, 170
 - GNU extensions, 171
 - historical features supported by *gawk*, 172
 - I/O statements, 167
 - operators, 166-167
 - patterns, 165-166
 - printf statement, 167-168

- program execution, 162-163
- regular expressions, 166
- `sprintf()` function, 167-168
- string constants, 169-170
- string functions, 169
- time functions, 169
- variables, 163-165
 - arrays*, 164
 - built-in*, 163-164
 - typing and conversion*, 164-165

B

- backslashes (`\`), bash escape character, 14

- badblocks, 1264

- banner, 1210

- bash

- aliases, 23-24
- arguments, 11
- arithmetic evaluation, 34
- blanks, 12
- bugs, 46
- command execution, 25
- comments, 14
- compound commands, 13
 - case*, 13
 - list*, 13
 - while*, 13
- control operators, 12
- environments, 25-26
- escape character, 14
- exit status, 26
- expansion, 18-21
 - arithmetic*, 20
 - brace*, 19
 - command substitution*, 20
 - history*, 33-34
 - parameter*, 19-20
 - pathname*, 21
 - process substitution*, 20
 - quote removal*, 21
 - tilde*, 19
 - word splitting*, 21
- files, 46
- functions, 23

- history list, 32-33
- invocation, 45-46
- job control, 24-25
- lists, 12-13
- meta characters, 12
- names, 12
- options, 11
- parameters, 14-15
 - positional*, 14
 - special*, 14-15
- pipelines (`|`), 12
- prompting, 26
- quoting, 14
- readline, 27-32
 - commands*, 29-32
 - controlling key bindings*, 27
 - customizing*, 27
 - denoting keystrokes*, 27
 - macro definitions*, 28
 - parser directives*, 28-29
 - variables*, 28
- redirection, 21-23
 - duplicating file descriptors*, 23
 - here-documents*, 22-23
 - input*, 22
 - opening file descriptors*, 23
 - operators*, 21
 - output*, 22
 - standard error output*, 22
 - standard output*, 22
- reserved words, 12
- shell variables, 15-18
 - allow-null_glob_expansion*, 17
 - auto_resume*, 18
 - BASH*, 15
 - BASH_VERSION*, 15
 - cdable_vars*, 18
 - CDPATH*, 16
 - command_oriented_history*, 17
 - ENV*, 16
 - EUID*, 15
 - FCEDIT*, 17
 - FIGNORE*, 17

- glob_dot_filenames*, 17
- histchars*, 17-18
- HISTCMD*, 16
- HISTFILE*, 17
- HISTFILESIZE*, 17
- history control*, 17
- HISTSIZE*, 17
- HOME*, 16
- hostname_completion_file*, 18
- HOSTTYPE*, 16
- IFS*, 16
- IGNOREEOF*, 17
- INPUTRC*, 17
- LINENO*, 15
- MAIL*, 16
- MAIL_WARNING*, 16
- MAILCHECK*, 16
- MAILPATH*, 16
- no_exit_on_failed_exec*, 18
- noclobber*, 18
- nolinks*, 18
- notify*, 17
- OLDPWD*, 15
- OPTARG*, 16
- OPTERR*, 17
- OPTIND*, 16
- OSTYPE*, 16
- PATH*, 16
- PPID*, 15
- PROMPT_COMMAND*, 17
- PS1*, 16
- PS2*, 16
- PS3*, 17
- PS4*, 17
- PWD*, 15
- RANDOM*, 15
- REPLY*, 15
- SECONDS*, 15
- SHLVL*, 15
- TMOUT*, 17
- UID*, 15
- signals, 25
- simple commands, 12
- words, 12

- BASH variable (bash), 15
- BASH_VERSION variable (bash), 15
- bcmp() function, 899-901
- bcopy() function, 900-901
- BDF fonts, generating, 146-147
- bdflush, 744-745
 - errors, 745
 - return value, 745
- bdftopcf, 47
- beforelight, 47-48
- bell (ftp command), 148
- bell() action (xterm), 713
- bell-style variable (readline), 28
- Bennet Yee face files, *see* face files
- Bentleyizing portable graymaps, 369
- Bessel functions, 959-960
 - j0(), 959
 - j1(), 959
 - jn(), 959
 - y0(), 959
 - y1(), 959
 - yn(), 959
- bg (shell command), 35
- bibliographic databases, 219
 - fields, 219
 - inverted indexes, 209-210
 - searching, 210, 292-293
- biff, 48
- biff server, 1274-1275
- /bin directory, 1236
- binary (ftp command), 148
- binary dates/times, converting to ASCII, 909-911
- binary files, encoding/decoding, 565-566
- binary streams, input/output (getting), 926-927
- binary trees
 - deleting items, 1056
 - searching, 1056
 - traversing, 1056
- bind, 35, 745-746
 - errors, 745-746
 - return value, 745
- binding names to sockets, 745-746
- bioradtopgm, 48-49
 - bugs, 49
 - options, 49
- bit sets, finding first in words, 921
- Bitmap Distribution Format fonts, converting to Portable Compiled Format, 47
- bitmap widget, 56-57
- bitmaps, 49-57
 - CMU, converting to portable, 71
 - color, 56
 - conversion, 49
 - cutting and pasting, 54
 - display, 50
 - drawing commands, 51-53
 - Edit menu commands, 53-54
 - editing images, 50-51
 - File menu commands, 53
 - options, 49-50
 - Universal Product Code, creating, 368
 - widgets, 54-56
- blanks (bash), 12
- block buffered streams, 1016
- block special files, creating, 325
- BMP files, converting to portable pixmaps, 57
- bmptoppm, 57
- bmtoa, 49-57
- /boot directory, 1236
- boot-time parameters (kernel), *see* bootparam
- bootparam, 1216-1224
 - Adaptec configurations, 1219-1220
 - argument list, 1216-1217
 - BusLogic configuration, 1220
- busmouse driver parameters, 1224
- CD-ROM parameters, 1222-1223
- debug argument, 1217
- Ethernet device parameters, 1223
- floppy disk driver parameters, 1223-1224
- future domain configuration, 1220
- hard disk parameters, 1220-1221
- mem= argument, 1218
- no-hlt argument, 1217
- no387 argument, 1217
- Pro Audio configuration, 1220
- ramdisk= argument, 1218
- reboot=warm argument, 1218
- reserve= argument, 1217-1218
- ro argument, 1217
- root= argument, 1217
- rw argument, 1217
- SCSI device arguments, 1218-1219
- SCSI tape configuration, 1219
- Seagate ST-0x configuration, 1220
- sound driver parameters, 1224
- Trantor T128 configuration, 1220
- Bourne shell, *see* sh
- Bourne-again shell, *see* bash
- brace expansion, 19
- break (shell command), 35
- brk, 746
- browsers, lynx, 306-309
 - commands, 308-309
 - options, 306-308
- brushtopbm, 57
- bsearch() function, 900-901

buffchan, 1264-1265
 drop command, 1265
 flush command, 1265
 readmap command, 1265
 buffer-dirty-flush daemon,
 744-745
 buffering streams, 1016-1017
 buffers
 cache, committing to disk,
 869
 filesystem, flushing,
 1401-1402
 flushing from files to disk,
 756-757
 kernel log, 873
 kernel message ring, reading/
 clearing, 872-874
 multiple, reading/writing
 data, 1003-1004
 BUG_ADDRESS environ-
 ment variable, 529
 buildhash, 274, 279
 files, 281
 builtin (shell command), 35
 busmouse drivers, boot-time
 parameters, 1224
 bye (ftp command), 148
 byte strings
 comparing, 899-900
 copying, 900
 operations, 901
 writing zeros to, 902
 bytes
 counting (in files), 70
 swapping adjacent, 1043
 bzero() function, 901-902

C

C

converting ANSI to
 Kernighan & Ritchie, 4
 functions, displaying
 headers, 455-456
 preprocessors, 81-84
 imake, 264-267
 options, 82-84

 string table source files/
 headers, 314-315
 see also gcc
 C++ compiler, *see* g++
 cacheflush, 746-747
 bugs, 747
 errors, 747
 return value, 747
 caches (ARP), manipulating,
 1263
 CAClose routine, 964
 cal, 58
 calendar sheets, *see* gcal
 CAListopen routine, 964
 calling up systems, 88-90
 calloc() function, 976
 canonicalized absolute
 pathnames, 1004-1005
 CAopen routine, 964
 case
 bash command, 13
 ftp command, 148
 cat, 58-59
 catclose() function, 903-904
 catgets() function, 902-903
 catopen() function, 903-904
 cccp, 81-84
 copying, 84
 options, 82-84
 cd
 ftp command, 148
 shell command, 35-36
 CD-ROMs, boot-time
 parameters, 1222-1223
 cdable_vars variable (bash),
 18
 CDPATH variable (bash), 16
 cdtin, 516
 see also tin
 cdup (ftp command), 148
 ceil() function, 904
 cfdisk, 1265-1269
 bugs, 1269
 commands, 1267-1268
 options, 1268-1269
 cfgetispeed() function, 877,
 1053

cfgetospeed() function, 877,
 1052
 cfingerd, 1106-1109
 bugs, 1108
 error messages, 1108
 features, 1107-1108
 options, 1106-1107
 SYSLOG messages, 1108
 text commands, 1115
 cfingerd.conf, 1109-1115
 display files section,
 1109-1110
 finger display configure
 section, 1110-1111
 finger fake users files section,
 1114
 finger programs files section,
 1114
 finger strings configure
 section, 1113
 forwarded host section,
 1112
 internal config configure
 section, 1111-1112
 internal strings configure
 section, 1113
 rejected host section, 1112
 services header configure
 section, 1114
 services positions configure
 section, 1114-1115
 signal strings configure
 section, 1113-1114
 system list sites configure
 section, 1112
 trusted host section, 1112
 cfmakeraw() function, 1052
 cfsetispeed() function, 877,
 1053
 cfsetospeed() function, 877,
 1052-1053
 character sets, 1064-1066
 ASCII, 1064, 1214-1216
 ISO 2022, 1066
 ISO 4873, 1066
 ISO 8859, 1064-1065
 ISO 8859-1, 1239-1242
 alphabets, 1240
 characters, 1240-1242

- KOI8-R, 1065
- Unicode, 1065, 1253-1255
 - combining characters*, 1254
 - implementation levels*, 1254
- character special files, creating, 325
- characters
 - classifying, 957-958
 - converting
 - to ASCII*, 1055
 - wide to multibyte*, 1061-1062
 - locating in strings, 953, 1029
 - multibyte, converting to wide characters, 978
 - outputting, 997-999
 - returning number of bytes in, 977
 - searching strings for sets, 1035-1039
 - translating/deleting, 536-539
- chat, 727-730, 1269-1273
 - abort strings, 1270-1271
 - Boolean options, 729
 - daemons, 727
 - escape menu, 728
 - escape sequences, 1271-1272
 - options, 1269-1270
 - readdressing, 729
 - report strings, 1271
 - runtime options, 728-729
 - script, 1270
 - startup file, 729
 - termination codes, 1272
 - time-out value, 1271
 - username field, 727
 - X11 interface, 730
- chattr, 59-60
- chdir, 747-748
- checkout (cvs command), 96-97
- checksums, computing on files, 501
- chfn, 60
- chgrp, 61
- child processes, creating, 751, 758
- chkdupexe, 61
- chmod, 61-62, 148, 748-749
 - errors, 749
 - operators, 62
 - options, 62
 - return value, 748
 - specifying mode, 748
- chooser (xdm), 607
- chown, 62-63, 749-750
 - errors, 749-750
 - options, 63
- chroot, 750-751, 1273
 - errors, 750-751
 - return value, 750
- chsh, 63
- ci, 64-69
 - controlling file access, 67
 - diagnostics, 68
 - environment, 68
 - file modes, 67
 - options, 65-66
 - setuid privileges, 67-68
 - specifying files, 66-67
 - temporary files, 67
- cidentd, 69-70
- cksum, 70
- clear, 70-71
- clear-saved-lines() action (xterm), 715
- clearerr function, 919-920
- clearing terminal screen, 70-71
- clientlib, 904-905
- clients
 - listing running applications, 669-670
 - Remote Start, *see* rstart
 - X, killing, 666-667
- clipboards, X client, 595-597
 - buttons, 596
 - sending/retrieving contents, 596-597
- clock, 344, 1273-1274
 - colors, 344
 - options, 1273
 - xclock, 593-595
- clock() function, 905
- clocks
 - alarm, setting, 744
 - CMOS, 1273-1274
 - kernel, adjusting, 742-743
- clone, 751
- close, 752
 - ftp command, 148
 - telnet command, 508
- closedir() function, 905-906
- closelog() function, 1045-1046
- CloseOnExec routine, 965
- CMOS clock, 1273-1274
- CMU bitmaps, converting to portable, 71
- cmuwmktopbm, 71
- co, 71-75
 - diagnostics, 75
 - environment, 75
 - file modes, 75
 - keyword substitution, 74-75
 - limitations, 75
 - options, 72-74
- col, 76
- colcrt, 77
- color, bitmap application, 56
- colrm, 77-78
- column, 78
- columns
 - formatting lists into, 78
 - removing from files, 77-78
- comm, 78-79
 - options, 79
- command (shell command), 36
- command-line options, parsing, 937-940
- command_oriented_history variable (bash), 17
- commands
 - bitmap application
 - drawing*, 51-53
 - Edit menu*, 53-54
 - File menu*, 53

- building/executing from
 - standard input, 586-587
- cu, 88-89
- cvs, 91-104
- editres, 121-122
- execution, bash, 25
- exit status, 26
- ftp, 148-152
- gpic, 212-213
- history lists, displaying, 39
- info, 269-270
- ispell, 274-275
- locating source/binary and
 - manuals files, 575-576
- lpc, 1317-1318
- lynx, 308-309
- more, 328
- nslookup, 1351-1353
- options, parsing, 207-208
- RCS, 447-449
- readline library, 29-32
- redirection, 21-23
 - duplicating file descriptors*, 23
 - here-documents*, 22-23
 - input*, 22
 - opening file descriptors*, 23
 - operators*, 21
 - output*, 22
 - standard error output*, 22
 - standard output*, 22
- remote execution, 569-571
- sed, 478-479
 - grouping*, 478
 - syntax*, 476
- shell (built-in), 35-45
 - enabling/disabling*, 37
 - help information*, 38
- telnet, 508-512
- tftp, 514
- timedc, 1409
- tin
 - article viewer*, 522-524
 - editing*, 519
 - global options menu*, 524-525
 - group index*, 521-522
 - newsgroup selection*, 519-520
 - pool directory selection*, 520
 - thread listing*, 522
 - top*, 534-535
 - xauth*, 588, 591
 - zmore*, 733-734
- comment-begin variable (readline), 28
- comments
 - bash, 14
 - sed, 477
- commit (cvs command), 96-98
- comparing
 - files, 78-79
 - compressed*, 731-732
 - strings, 1029-1030
 - ignoring case*, 1028
 - using current locale*, 1030
- compilers
 - g++, 155-160, 174-201
 - bugs*, 160
 - copying*, 160, 201
 - filename suffixes*, 174-175
 - files*, 159-160, 200
 - options*, 155-159, 175-178
 - pragmas*, 159, 200
 - gcc, 174-201
 - assembling output*, 8-9
 - bugs*, 201
 - copying*, 201
 - filename suffixes*, 174-175
 - files*, 200
 - options*, 175-178
 - pragmas*, 200
 - rpcgen, 464-466
- compiling, make utility (recompiling programs), 310-312
- completion-query-items variable (readline), 28
- compound commands (bash), 13
- compressed files
 - comparing, 731-732
 - compressing/expanding, 248-252
 - executable files*, 252-253
 - searching for regular expressions, 733
 - viewing text, 733-734
- comsat, 1274-1275
- concatenating
 - files, 58-59
 - compressed*, 251
 - portable anymaps, 383
 - strings, 1028-1029
- Concurrent Versions System, *see* cvs
- conditional expressions, evaluating, 43
- configurable finger daemon, 1106-1109
- configuration file, 1109-1115
 - display files section*, 1109-1110
 - finger display configure section*, 1110-1111
 - finger fake users files section*, 1114
 - finger programs files section*, 1114
 - finger strings configure section*, 1113
 - forwarded host section*, 1112
 - internal config configure section*, 1111-1112
 - internal strings configure section*, 1113
 - rejected host section*, 1112
 - services header configure section*, 1114
 - services positions configure section*, 1114-1115
 - signal strings configure section*, 1113-1114
 - system list sites configure section*, 1112
 - trusted host section*, 1112

- error messages, 1108
- features, 1107-1108
- SYSLLOG messages, 1108
- configuration information,
 - getting at runtime, 1043-1045
- configuring
 - network interfaces, 1304-1305
 - rstartd, 469
 - keywords*, 470
 - serial ports, 1394-1395
 - SF86_SVGA servers, 627-628
 - SF86_VGA16 servers, 631
 - system logging file, 1402-1403
 - tinrc, 525-526
 - XF86_Accel servers, 615-616
 - XF86_Mono servers, 624
 - XFree86, 636
 - xfs, 642
 - xinetd, 656-660
- confstr() function, 906-907
- connect, 752-753
- connections
 - dialup IP, handler, 1285-1288
 - displaying active, 1339-1342
 - routing information*, 1341
 - socket information*, 1340-1341
 - displaying active routing information, 1341
 - full-duplex, shutting down, 855
 - socket
 - accepting*, 740-741
 - initiating*, 752-753
 - listening for*, 792-793
- console, 1066-1067
- console_codes, 1067-1074
 - character sets, 1072
 - control characters, 1068
 - CSI sequences, 1069-1070, 1074
 - display attributes, 1070-1071
 - ESC sequences, 1068-1069, 1073-1074
 - mode switches, 1071
 - mouse tracking, 1072-1073
 - private CSI sequences, 1072
 - Set/Reset Mode sequences, 1071
 - status report commands, 1071
- console_ioctls, 1074-1080
- consoles
 - control-character handling, 1073
 - properties, 1067
 - sequences, 1067-1074
 - character sets*, 1072
 - control characters*, 1068
 - CSI*, 1069-1070, 1074
 - display attributes*, 1070-1071
 - ESC*, 1068-1069, 1073-1074
 - mode switches*, 1071
 - mouse tracking*, 1072-1073
 - private CSI*, 1072
 - Set/Reset Mode*, 1071
 - status report commands*, 1071
 - starting processes on, 1066
 - switching, 1067
 - virtual, 1066
 - memory*, 1101-1102
- continue (shell command), 36
- control messages, 1310
- control operators (bash), 12
- control statements, awk, 167
- control.ctl, 1115-1116
- controlling terminal, getting name, 909
- convdate, 79
- conversational exchanges, 1269-1273
 - abort strings, 1270-1271
 - chat script, 1270
 - escape sequences, 1271-1272
 - report strings, 1271
 - termination codes, 1272
 - time-out value, 1271
- convert-meta variable (readline), 28
- converting
 - Abekas YUV bytes to portable pixmaps, 731
 - Andrew Toolkit raster objects to portable bitmaps, 10
 - ANSI C to Kernighan & Ritchie C, 4
 - ASCII graphics to portable graymap, 10
 - Atari files
 - compressed Spectrum files to portable pixmaps*, 494
 - Degas P11 files to portable pixmaps*, 378
 - Degas P13 files to portable bitmaps*, 379
 - uncompressed Spectrum files to portable pixmaps*, 495-496
 - AutoCAD slide files to portable pixmaps, 490-491
 - Bennet Yee face files to portable bitmaps, 726
 - Biorad confocal files to portable graymaps, 48-49
 - bitmap files, 49
 - CMU to portable*, 71
 - to portable pixmaps*, 57
 - characters
 - to ASCII*, 1055
 - wide to multibyte*, 1061-1062
 - dates/times, 79
 - to ASCII*, 984-986
 - to Discordian format*, 1210-1211
 - documents, troff to LaTeX, 1252-1253
 - doodle brush files to portable bitmaps, 57
 - FITS files to portable anymaps, 142-143

fonts

- Bitmap Distribution*
- Format to Portable*
- Compiled Format, 47*
- packed format to portable*
- bitmaps, 381*

- GEM IMG files to portable bitmaps, 201

- GIF files to portable anymaps, 208-209

- Gould scanner files to portable pixmaps, 211

- groff output to TeX dvi format, 227-228

- Group 3 fax files to portable bitmaps, 160-161

- HIPS files to portable graymaps, 256

- HP PaintJet files to portable pixmaps, 381

- ILBM files to portable pixmaps, 263-264

- image file to portable anymap, 4

- Img-whatnot files to portable pixmaps, 267

letters

- to lowercase, 1055-1056*
- to uppercase, 1055-1056*

- Lisp machine bitmap files to portable graymaps, 292

- Macintosh PICT files to portable pixmaps, 379-380

- MacPaint files to portable bitmaps, 309-310

- MGR bitmaps to portable bitmaps, 322-323

- multibyte characters to wide characters, 978

- multibyte strings to wide character, 977-978

- object code into NLM outfiles, 338-339

- PCX files to portable pixmaps, 368-369

- Photo-CD files to portable pixmaps, 260-261

portable anymaps

- to DDIF format, 396*
- to FITS format, 396-397*
- to PostScript, 397*
- to SGI image file, 398-399*
- to Solitaire format, 399*
- to Sun raster files, 398*
- to TIFF files, 399-400*
- into X11 window dumps, 400*

portable bitmaps

- to Andrew Toolkit raster objects, 358*
- to ASCII graphics, 357*
- to Atari Degas PI3 files, 364*
- to Bennet Yee "face" files, 367*
- to BitGraph graphics, 358*
- to CMU window manager bitmaps, 358-359*
- to compressed GraphOn graphics, 360-361*
- to DEC LN03+ Sixel output, 362*
- to encapsulated PostScript-style bitmaps, 359*
- to Epson printer graphics, 359*
- to GEM IMG files, 360*
- to Gemini 10x graphics, 356*
- to Group 3 fax files, 360*
- to HP LaserJet format, 361-362*
- to MacPaint files, 363*
- to MGR bitmap, 363*
- to packed format fonts, 364-365*
- to portable graymaps, 364*
- to PostScript, 362*
- to Printronix printer graphics, 366*
- to Sun icons, 361*
- to UNIX plot files, 365-366*

- to X10 bitmaps, 366*
- to X11 bitmaps, 367*
- to Zinc bitmaps, 367-368*

portable graymaps

- to Lisp machine format, 376-377*
- to portable bitmaps, 377*
- to portable pixmaps, 378*
- to Usenix FaceSaver format, 376*

portable pixmaps

- to Abekas YUV files, 428*
- to Atari Degas PI1 files, 422*
- to AutoCAD, 414-416*
- to BMP files, 416*
- to DEC sixel format, 425-426*
- to GIF files, 416-417*
- to HP PaintJet files, 423*
- to HP PaintJet XL PCL files, 424*
- to ILBM files, 418-419*
- to Macintosh PICT files, 422-423*
- to Mitsubishi S340-10 files, 420-421*
- to MotifUIL icon files, 427*
- to NCSA ICR format, 417-418*
- to PCX files, 421*
- to portable graymaps, 421-422*
- to red/blue 3D glasses, 400-401*
- to three portable graymaps, 425*
- to three raw YUV files, 428-429*
- to TrueVision Targa files, 426*
- to X11 pixmaps, 427-428*
- to X11 puzzle files, 424-425*

- PostScript files to portable anymaps, 434-435

- PostScript image data to portable graymap, 433-434
- QRT ray tracer output to portable pixmaps, 436-437
- raw grayscale bytes to portable graymaps, 439
- raw RGB bytes to portable pixmaps, 439-440
- ray tracer output to portable pixmaps, 333
- SGI image files to portable anymaps, 483-484
- Solitaire files to portable anymaps, 488-489
- spaces to tabs, 559
- SPOT satellite images to portable graymaps, 495
- strings
 - ASCII to double*, 1039-1040
 - to long integers*, 1041
 - to unsigned long integers*, 1041-1042
 - wide character to multibyte character*, 1061
- Sun icons to portable bitmaps, 262
- Sun raster files to portable anymaps, 438
- tabs to spaces, 137
- TIFF files to portable anymaps, 515-516
- times
 - initializing information*, 1058-1060
 - to ASCII*, 984-986
 - to tm structure*, 1036-1037
- TrueVision Targa files to portable pixmaps, 515
- Usenet batch files to INN format, 1281-1282
- Usenix FaceSaver files to portable graymaps, 147
- X11 or X10 bitmaps to portable, 592
- X11 pixmaps to portable, 677
- X11/X10 window dump files to portable anymaps, 722
- Xconfig file format to XF86Config, 454
- XIM files to portable pixmaps, 654
- XV thumbnail pictures to portable pixmaps, 720
- YUV files to portable pixmaps, 730-731
- convolution kernels, generating, 372-373
- cookies, generating, 317
- copying
 - ar utility, 7
 - as, 9
 - byte strings, 900
 - files, 80-81
 - converting while*, 108-109
 - install*, 272-273
 - MS-DOS to/from UNIX*, 317-318
 - UNIX-to-UNIX*, 563-565
 - MS-DOS files to UNIX, 329
 - number signs, 907
 - strings, 1030-1031
 - stpcpy()* function, 1027-1028
- copysign() function, 907
- cos() function, 907
- cosh() function, 908
- cosines, 907
- cp, 80-81
- cpp, 81-84
 - copying, 84
 - options, 82-84
- CPU, listing most intensive processes, 533-535
- cr (ftp command), 148
- creat, 815-816
- create_module, 800-802
- crond, 1275
- crontab, 84-85
- crypt function, 908-909
- csplit, 85-86
- ctags, 87-88, 135-137
 - bugs, 88
 - copying, 136-137
 - files, 87
 - options, 87, 136
- ctermid() function, 909
- ctime, 909-910, 984-986
- ctlinnd, 1276-1279
 - bugs, 1279
 - commands, 1276-1278
- Ctrl+Alt+Del combination, setting function, 1279
- ctrl_alt_del, 1425
- ctrlaltdel, 1279
- cu, 88-90
 - bugs, 90
 - commands, 88-89
 - options, 89-90
- cuserid() function, 934-935
 - bugs, 935
 - errors, 934
 - files, 935
- cut, 90-91
- cut buffers, copying selections into, 598-599
- cvs, 91-106, 1116-1120
 - commands, 91-104
 - add*, 96
 - admin*, 96
 - checkout*, 96-97
 - commit*, 96-98
 - diff*, 98
 - export*, 98
 - history*, 99
 - import*, 100
 - log*, 100
 - rdiff*, 101
 - release*, 101
 - remove*, 101-102
 - rtag*, 102
 - status*, 102
 - tag*, 102-103
 - update*, 103-104

- environment variables, 105-106
 - CVS_IGNORE_REMOTE_ROOT*, 105
 - CVS_RSH*, 106
 - CVS_SERVER*, 106
 - CVSEEDITOR*, 105
 - CVSREAD*, 105
 - CVSROOT*, 105
 - CVSWRAPPERS*, 106
 - RCSBIN*, 105
 - files, 104-105, 1117-1119
 - options, 92-104
 - checkout command*, 97
 - commit command*, 97
 - history command*, 99
 - import command*, 100
 - rdiff command*, 101
 - sending problem reports, 1279-1281
 - filling out reports*, 1280-1281
 - startup file, 93
 - support files, 1116-1120
 - CVS_IGNORE_REMOTE_ROOT* environment variable, 105
 - CVS_RSH* environment variable, 106
 - CVS_SERVER* environment variable, 106
 - cvsbug*, 1279-1281
 - EMACS interface, 1281
 - environment, 1280
 - files, 1281
 - filling out reports, 1280-1281
 - options, 1280
 - CVSEEDITOR* environment variable, 105
 - CVSREAD* environment variable, 105
 - CVSROOT* environment variable, 105
 - CVSWRAPPERS* environment variable, 106
 - cvtbatch*, 1281-1282
 - Cyclades drivers, tuning, 1282-1284
 - cytune*, 1282-1284
 - bugs, 1283
 - options, 1283
- ## D
-
- daemons
 - buffer-dirty-flush, 744-745
 - configurable finger daemon, 1106-1109
 - configuration file*, 1109-1115
 - error messages*, 1108
 - features*, 1107-1108
 - SYSLOG messages*, 1108
 - cron, 1275
 - InterNetNews, 1309-1312
 - control messages*, 1310
 - controlling*, 1276-1279
 - kernel log, 1315-1317
 - line printer spooler, 1318-1320
 - network routing, 1380-1382
 - NFS mount, 1332-1333
 - NFS service, 1347
 - powerd, 1359-1360
 - pppd, 1360-1369
 - time server, 1407-1408
 - UUCP file transfer, 1415-1417
 - DARPA
 - FTP server, 1301-1304
 - requests supported*, 1302-1303
 - port numbers, converting
 - PRC program numbers to, 1358-1359
 - Telnet server, 1406-1407
 - TFTP server, 1407
 - data buffers, flushing from
 - files to disk, 756-757
 - data cache, flushing contents, 746-747
 - data segments, changing, 746
 - databases
 - bibliographic, 219
 - fields*, 219
 - inverted indexes*, 209-210
 - searching*, 210, 292-293
 - filename, updating, 561-562
 - files, searching for patterns, 295
 - news overview
 - expiring entries*, 1293-1294
 - format*, 1168-1169
 - updating*, 1353-1354
 - ps, updating, 436
 - rebuilding for mail aliases
 - file, 336
 - RGB colorname, uncompiling, 488
 - terminal capability, 1188-1197
 - boolean capabilities*, 1189
 - numeric capabilities*, 1189-1190
 - string capabilities*, 1190-1197
 - Usenet, recovering, 1342-1344
 - date, 106-108
 - arguments, 106-107
 - files, 108
 - options, 108
 - dates/times
 - converting, 79
 - to ASCII*, 909-911, 984-986
 - to Discordian format*, 1210-1211
 - strings to numbers*, 989-990
 - formatting, *strftime()*
 - function, 1032-1034
 - returning current, 928-929
 - setting, 107-108
 - showing, 106-107
 - dd, 108-109
 - ddate, 1210-1211
 - DDcheck routine, 965

- DDend routine, 965
- DDstart routine, 965
- debug (ftp command), 149
- debugfs, 1284-1285
 - commands, 1284-1285
 - options, 1284
- declare (shell command), 36
- del_timer, 1424
- delete_module, 800-802
- delete (ftp command), 148
- deleting
 - binary tree items, 1056
 - directories, 829-830
 - MS-DOS directory trees, 319
 - MS-DOS files, 318-319
- depmod, 109-112
 - configuration, 110-111
 - files, 111
 - strategy, 111
- descriptor tables, size (getting), 760-761
- descriptors, testing, 958-959
- /dev directory, 1236
- devices
 - bad blocks (searching for), 1264
 - controlling, 774-788
 - ioctl calls (list of)*, 775-786
 - creating, 815-816, 1321-1324
 - describing all, 1120-1121
 - disk, ram, 1094-1095
 - DOS (table of), 1152-1158
 - Ethernet, boot-time parameters, 1223
 - floppy disk, 1080-1083
 - configuration*, 1080-1082
 - hard disk, 1083
 - line printer (*ioctl()* calls), 1090-1091
 - lp, parameters (setting), 1413-1414
 - opening, 815-816
 - PLIP, tuning parameters, 1357
 - SCSI tape, drivers, 1096-1100
 - setup, 849
 - swapping
 - enabling/disabling*, 1401
 - starting/stopping*, 866-867
 - terminal (list of), 1197
- DEVINFO, 1120-1121
- df, 112-113
- dialup IP connection handler, 1285-1288
 - dialin mode, 1286-1287
 - dialout mode, 1287-1288
- dictionaries, compressing/uncompressing, 496
- diff (cvs command), 98
- difftime, 911, 984-986
- dig, 113-117
 - bugs, 117
 - environment, 117
 - files, 117
 - options, 114-115
- dip, 1285-1288
 - command mode, 1285-1286
 - dialin mode, 1286-1287
 - dialout mode, 1287-1288
 - files, 1288
- dir, 303-304
 - bugs, 304
 - ftp command, 149
 - options, 303-304
- directories
 - /, 1236
 - adding to stack, 40
 - alphabetizing entries, 1012-1013
 - /bin, 1236
 - /boot, 1236
 - changing, 35-36, 747-748
 - closing, 905-906
 - creating, 323
 - mkdir*, 794-795
 - mknod*, 795-796
 - deleting, 829-830
 - /dev, 1236
 - displaying list of, 36
 - /dos, 1236
 - /etc, 1236
 - /etc/skel, 1236
 - /etc/X11, 1236
 - files (searching for), 137-142
 - getting current, 931
 - getting entries, 759
 - filesystem-independent format*, 931-932
 - hierarchies, creating, 323
 - /home, 1236
 - /lib, 1236
 - listing contents, 303-304
 - /mnt, 1236
 - MS-DOS
 - changing*, 316-317
 - displaying*, 319
 - opening, opendir, 989
 - printing pathnames, 40
 - /proc, 1236
 - promoting, 39-40
 - RCS, creating, 447-449
 - reading
 - entries*, 823
 - readdir() function*, 1002-1003
 - removing, 462
 - root, changing, 750-751, 1273
 - /sbin, 1237
 - scanning for matching entries, 1012-1013
 - stream, resetting, 1011
 - /tmp, 1237
 - trees, walking through, 930
 - /usr, 1237
 - /usr/X11R6, 1237
 - /usr/X11R6/bin, 1237
 - /usr/X11R6/lib, 1237
 - /usr/X11R6/lib/X11, 1237
 - /usrX11R6/include/X11, 1237
- directory stream, current location (returning), 1048
- directory trees
 - MS-DOS, deleting, 319
 - shadow directories (creating), 294

- dirs (shell command), 36
 - disconnect (ftp command), 149
 - Discordian dates (converting to), 1210-1211
 - disks
 - adding MS-DOS filesystems to, 321-322
 - devices, ram, 1094-1095
 - displaying usage/limits, 437
 - floppy
 - formatting*, 1295-1296
 - marking bad blocks*, 316
 - setting parameters*, 1391
 - MS-DOS, mounting, 326-327
 - quotas, manipulating, 821-822
 - SCSI, drivers, 1095-1096
 - summarizing free space, 112-113
 - summarizing usage, 120-121
 - Xdf, 332
 - display argument command (telnet), 508
 - DISTRIBUTION environment variable, 529
 - div() function, 911
 - dividing integers, 911
 - floating-point remainders, 913, 923
 - returning quotient and remainder, 961
 - dmesg, 1288-1289
 - dn_comp, 1008-1011
 - dn_expand, 1008-1011
 - dnsdomainname, 259-260
 - dnsquery, 117-119
 - bugs, 119
 - diagnostics, 118
 - files, 118
 - options, 117-118
 - documents
 - converting, troff to LaTeX, 1252-1253
 - formatting, gtroff, 237-248
 - dollar signs (\$)
 - bash special parameters, 15
 - expansion, 19
 - ftp command, 148
 - domain names
 - current host, 119
 - displaying, 259-260
 - getting/setting, 760
 - querying servers, 117-119
 - sending query packets to servers, 113-117
 - servers, resolver routines, 1008-1011
 - domain servers, looking up hostnames with, 257-258
 - domainname, 119
 - domains, nameserver, 1334-1338
 - querying, 1350-1353
 - doodle brush files, converting to portable bitmaps, 57
 - DOS devices, table of, 1152-1158
 - /dos directory, 1236
 - drand48() functions, 912
 - drawing bitmaps (commands), 51-53
 - drem() function, 913
 - drivers
 - busmouse, boot-time parameters, 1224
 - Cyclades, tuning, 1282-1284
 - floppy disk, boot-time parameters, 1223-1224
 - SCSI disks, 1095-1096
 - SCSI tape devices, 1096-1100
 - ioctl() calls*, 1097-1100
 - sound, boot-time parameters, 1224
 - dsplit, 119-120
 - du, 120-121
 - dumpe2fs, 1289
 - dumping files, 345-346
 - dup, 753-754
 - dup2, 753-754
 - duplicate executables, finding, 61
 - duplicating strings, 1031
- ## E
-
- e-mail
 - notification, 48
 - sending, 1387-1390
 - aliases*, 1390
 - e2fsck, 1289-1291
 - bugs, 1291
 - exit code, 1290
 - options, 1290
 - echo (shell command), 36-37
 - ECHO_REQUEST packets, sending, 1358
 - ecvt() function, 913-914
 - Edit menu commands, bitmap application, 53-54
 - editing bitmaps, 49-51
 - editing-mode variable (readline), 28
 - editors
 - emacs, 130-133
 - bugs*, 133
 - distributing*, 133
 - files*, 132-133
 - manuals*, 132
 - mouse button bindings*, 132
 - options*, 130
 - X Window System*, 131-132
 - stream-oriented, *see* sed
 - editres, 121-126
 - beginning sessions, 121
 - blocking requests, 124
 - commands, 121-122
 - environment, 126
 - files, 126
 - options, 121
 - resource box, 123-124
 - resources, 124-125
 - widgets, 125-126
 - window, 121

- edquota, 1291-1292
- egrep, 224-226
 - bugs, 226
 - diagnostics, 226
 - options, 224-225
 - regular expressions, 225-226
- \$else parser directive (readline), 29
- elvis, 126-128
 - bugs, 128
 - environment, 127-128
 - files, 127
 - options, 127
 - ref interaction, 455
 - tag files, 135-137
- elvprsv, 128-129
- elvrec, 129-130
- emacs, 130-133
 - bugs, 133
 - distributing, 133
 - files, 132-133
 - function key/mouse support, 134-135
 - manuals, 132
 - mouse button bindings, 132
 - options, 130
 - tag files, 135-137
 - using emacs tool with, 135
 - X Window System, 131-132
- EMACS user interface, cvsbug, 1281
- emacs tool, 134-135
 - bugs, 135
 - environment variables, 135
 - files, 135
 - options, 134
 - using with emacs, 135
- enable (shell command), 37
- encoded files, uuencode
 - format, 1200
- encryption
 - crypt function, 908-909
 - memory areas, 980-981
- endgrent() function, 932-933
- \$endif parser directive (readline), 29
- endmntent() function, 935-936
- endnetent subroutine, 936-937
- endprotoent() function, 941-942
- endpwent() function, 943
- endservent() function, 946
- endusershell() function, 946-947
- endutent() function, 947
- ENV variable (bash), 16
- environ, 1121
- environ command (telnet), 511
- environment variables
 - adding/changing, 996-997, 1017
 - bash, 25-26
 - ci, 68
 - co, 75
 - cvs, 105-106
 - CVS_IGNORE
 - _REMOTE_ROOT,
 - 105
 - CVS_RSH, 106
 - CVS_SERVER, 106
 - CVSEEDITOR, 105
 - CVSREAD, 105
 - CVSROOT, 105
 - CVSWRAPPERS, 106
 - RCSBIN, 105
 - cvsbug, 1280
 - dig, 117
 - editres, 126
 - elvis, 127-128
 - emacs tool, 135
 - fsinfo, 145
 - fsfonts, 146
 - fstobdf, 146
 - ftp, 154
 - gawk, 172
 - getopt() function, 939
 - getting, 932
 - groff, 229
 - gtroff, 248
 - gzip, 251
- imake, 267
- info, 270
- ld, 291
- lkbib, 293
- locate, 295
- lpq, 299
- lpr, 300
- lprm, 302
- more, 328
- nslookup, 1353
- rccs, 443
- rccsclean, 444
- rccsdiff, 445
- rccsmerge, 450
- ref, 455
- rlog, 459
- rlogin, 461
- script, 475
- startx, 497
- tcal, 506
- telnet, 512
- tin, 528-530
 - ADD_ADDRESS, 529
 - AUTOSUBSCRIBE, 529
 - AUTOUNSUBSCRIBE,
 - 530
 - BUG_ADDRESS, 529
 - DISTRIBUTION, 529
 - MAILER, 529
 - NNTPSERVER, 529
 - ORGANIZATION, 529
 - REPLYTO, 529
 - TI_ACTIVEFILE, 529
 - TI_NOVROOTDIR, 529
 - TIN_HOMEDIR, 528
 - TIN_INDEXDIR, 529
 - TIN_LIBDIR, 529
 - TIN_SPOOLDIR, 529
 - TINRC, 528
 - VISUAL, 529
- tset, 541
- twm, 557
- TZ, 987
- ul, 559
- xauth, 589, 592
- xclipboard, 597
- xclock, 595
- xcmsdb, 593

- xconsole, 598
- xdm, 608
- XFree86, 637
- xhost, 644
- xinit, 666
- xlogo, 668
- xlsatoms, 669
- xslclients, 669
- xlsfonts, 671
- xmodmap, 675
- xprop, 680
- xrdb, 684
- xrefresh, 685
- xstddmap, 700
- xterm, 717
- xwd, 722
- xwininfo, 724
- xwud, 726
- eqn, *see* geqn
- equation formatting, 202-206
- erand48() functions, 912
- erf() function, 914
- erfc() function, 914
- errno, 916-917
- error functions, 914
- errors
 - access, 741
 - adjtimex, 743
 - bdflush, 745
 - bind, 745-746
 - cacheflush, 747
 - chdir/fchdir, 747-748
 - chmod, 749
 - chown, 749-750
 - chroot, 750-751
 - clone, 751
 - close, 752
 - codes, describing (returning strings), 1032
 - creat, 816
 - dup/dup2, 753
 - execve, 754
 - fchmod, 749
 - fchown, 749-750
 - fcntl, 756
 - fdatasync, 757
 - fork/vfork, 758
 - fsync, 759
 - getdents, 759
 - getdomainname, 760
 - getgroups, 762
 - gethostname, 763
 - getitimer, 764
 - getpeername, 765
 - getpriority, 766-767
 - getrlimit, 768
 - getsid, 768
 - getsockname, 769
 - getsockopt, 771
 - gettimeofday, 773
 - idle, 774
 - ioctl, 774
 - iopl, 789
 - kill, 790
 - killpg, 791
 - link, 791-792
 - listen, 792
 - llseek, 793
 - lseek, 794
 - mkdir, 795
 - mknod, 796
 - mlockall, 798
 - mmap, 799
 - modify_ldt, 800
 - mount, 803
 - mprotect, 804
 - mremap, 806
 - msgctl, 807
 - msgget, 808
 - msgop, 810
 - munlock, 812
 - munmap, 799
 - mysnc, 811
 - nanosleep, 813
 - nice, 814
 - open, 816
 - pause, 817
 - personality, 818
 - return value, 797
 - returning number, 916-917
 - setdomainname, 760
 - setgroups, 762
 - sethostname, 763
 - setitimer, 764
 - setpriority, 766-767
 - setrlimit, 768
 - setsockopt, 771
 - settimeofday, 773
 - symbolic error names, 916-917
 - unmount, 803
- escape character, bash, 14
- etags, 135-137
 - copying, 136-137
 - options, 136
- /etc directory, 1236
- /etc/modules file, 1152
- /etc/skel directory, 1236
- /etc/X11 directory, 1236
- Ethernet devices, boot-time parameters, 1223
- Euclidean distance (finding), 953
- EUID variable (bash), 15
- eval (shell command), 37
- event timers, managing, 1424
- ex, *see* elvis
- exclamation points (!)
 - bash special parameters, 15
 - ftp command, 148
- exec (shell command), 37
- execl function, 914-916
- execle function, 914-916
- execlp function, 914-916
- execut function, 914-916
- executable files, compressing/
 - expanding, 252-253
- executables, duplicate
 - (finding), 61
- executing programs, 754-755
 - pausing, 813-814
 - suspending, 1061
- execv function, 914-916
- execve, 754-755
- execvp function, 914-916
- exit, 739-740, 917
 - shell command, 37
 - xauth, 591
- exit status (commands), 26
- exp() function, 918

expand, 137
 expand-tilde variable
 (readline), 28
 expanding files, *see* compress-
 ing/expanding files
 expansion, 18-21
 arithmetic, 20
 brace, 19
 command substitution, 20
 history, 33-34
 event designators, 33
 modifiers, 34
 word designators, 33
 parameter, 19-20
 pathname, 21
 process substitution, 20
 quote removal, 21
 tilde, 19
 word splitting, 21
 expire, 1292-1293
 expirectl, 1121-1123
 expireover, 1293-1294
 expm1() function, 918
 exponents, 918
 export
 cvs command, 98
 shell command, 37
 exported kernel symbols,
 displaying, 284-285
 exports, 1123-1125
 files, 1124
 options, 1123
 user ID mapping,
 1123-1124
 expressions
 conditional, evaluating, 43
 find, 138
 gawk, 166
 gpics, 213-214
 grep, 225-226
 label, *grefer*, 223-224
 numeric, *gtriff*, 239
 regular, *sed*, 476-477
 ext filesystem, 1125
 ext2 filesystem, 1125
 extracting from archives, 5-7

F

fabs() function, 919
 face files, converting to
 portable bitmaps, 726
 fastrm, 1294-1295
 fc (shell command), 37-38
 FCEDIT variable (bash), 17
 fchdir, 747-748
 fchmod, 748-749
 fchown, 749-750
 fclose function, 919
 fcntl, 755-756
 fcvt() function, 913-914
 fd, 1080-1083
 configuration, 1080-1082
 ioctl() calls supported, 1082
 FD_CLR macro, 836
 FD_ISSET macro, 836
 FD_SET macro, 836
 FD_ZERO macro, 836
 fdatsync, 756-757
 fdformat, 1295-1296
 fdisk, 1296-1297
 fdopen function, 924-925
 feof function, 919-920
 ferror function, 919-920
 fflush function, 920-921
 ffs() function, 921
 fg (shell command), 38
 fgetc() function, 945
 fgetgrent() function, 921-922
 fgetpos function, 927-928
 fgetpwent() function,
 922-923
 fgets() function, 945
 fgrep, 224-226
 bugs, 226
 diagnostics, 226
 options, 224-225
 regular expressions, 225-226
 fields, *awk*, 163
 FIFOs (named pipes), 1403
 creating, 323-325, 982-983
 system logging, 1403
 IGNORE variable (bash), 17

file descriptors
 duplicating, 23
 manipulating sets, 836
 opening, 23
 reading from, 822
 writing to, 889-890
 File menu commands, bitmap
 application, 53
 file table
 adding entries, 1428-1429
 description, 1425-1426
 initializing, 1427
 moving files to end, 1431
 removing files, 1431-1432
 structure, 1426
 table entries, 1426
 unreferenced entries,
 fetching, 1428
 file-creation mask, setting, 45
 file_table, 1425-1426
 table entries, 1426
 table structure, 1426
 file_table_init, 1427
 filechan, 1297-1298
 filename databases, updating,
 561-562
 filenames
 matching, 924
 temporary, creating,
 983-984
 fileno function, 919-920
 files
 aborting transfer, 152
 access permissions,
 changing, 61-62
 agetty, 1261
 Atari
 compressed Spectrum,
 converting to portable
 pixmap, 494
 Degas P11, converting to
 portable pixmap, 378
 Degas P13, converting to
 portable bitmaps, 379
 uncompressed Spectrum,
 converting to portable
 pixmap, 495-496

- attributes, 59
 - changing (second extended file system), 59-60*
- authority (X), xauth file utility, 587-592
- AutoCAD slide, converting to portable pixmaps, 490-491
- bash, 46
- binary
 - encoding/decoding, 565-566*
 - locating for commands, 575-576*
- Biorad confocal, converting to portable graymaps, 48-49
- bitmap, converting, 49
 - to portable pixmaps, 57*
- block special, creating, 325
- character special, creating, 325
- comparing, 78-79
- compressed
 - comparing, 731-732*
 - searching for regular expressions, 733*
 - viewing text, 733-734*
- compressing/expanding, 248-252
 - concatenation, 251*
 - executable files, 252-253*
- computing checksums, 501
- concatenating, 58-59
- configuration values, getting, 925-926
- copying, 80-81
 - between machines, 440-441*
 - converting while, 108-109*
 - install, 272-273*
- counting bytes/words/lines, 70, 574
- creating, 815-816
 - masks, 880*
- cuserid() function, 935
- cutting sections from, 90-91
- cvs, 104-105, 1117-1119
 - startup, 93*
- cvsbug, 1281
- database, searching for patterns, 295
- date, 108
- descriptors
 - closing, 752*
 - duplicating, 753-754*
 - manipulating, 755-756*
- domainname, 119
- doodle brush, converting to portable bitmaps, 57
- dumping, 345-346
- /etc/modules, 1152
- executing, 914-916
- exports, 1124
- face, converting to portable bitmaps, 726
- filesystem description, accessing, 935-936
- filters, hexdump, 254-256
- FITS, converting to portable anymaps, 142-143
- font, 1128
 - adding font-metric information, 2*
 - creating, 3*
 - groff (creating for), 513*
- formats, converting Xconfig to XF86Config, 454
- free, 144
- gcc/g++, 159-160, 200
- GEM IMG, converting to portable bitmaps, 201
- GIF, converting to portable anymaps, 208-209
- Gould scanner, converting to portable pixmaps, 211
- group, getting entries, 921-922, 932-934
- group ownership, changing, 61
- gtroff, 248
- gzip, forcing .gz extension, 732-733
- HIPS, converting to portable graymaps, 256
- HP PaintJet, converting to portable pixmaps, 381
- httpd, 261
- identifying processes, 154-155
- identifying RCS keyword strings in, 262-263
- ifconfig, 1305
- ILBM, converting to portable pixmaps, 263-264
- image, converting to portable anymap, 4
- imake, 266
- Img-whatnot, converting to portable pixmaps, 267
- joining fields, 282-283
- linking, 293-294, 791-792
- Lisp machine bitmap, converting to portable graymaps, 292
- listing attributes, 304-305
- location, changing, 828-829
- lock, creating for shell scripts, 487
- login, 297
- login record, 1198-1200
- Macintosh PICT, converting to portable pixmaps, 379-380
- MacPaint, converting to portable bitmaps, 309-310
- MAKEDEV, 1321
- makefiles, creating dependencies in, 312-314
- man, 1248
- manual page, locating for commands, 575-576
- mapping/unmapping, 799-800
- merging
 - lines, 347*
 - three-way, 320*
- mesg, 321
- modprobe, 111
- mount, 1332

- MS-DOS
 - changing attribute flags*, 315-316
 - copying to/from UNIX*, 317-318, 329
 - deleting*, 318-319
 - displaying contents*, 333-334
 - manipulating (mtools)*, 330-333
 - moving*, 327
 - renaming*, 329-330
- mtools, testing, 330
- named, 1337
- names
 - changing*, 828-829
 - displaying from Usenet history file*, 226-227
 - naming conventions*, 153
- .netrc, 153-154
- NLM outfiles, converting object code into, 338-339
- nontext, printing strings from, 498
- numbering lines, 337-338
- object
 - copying/translating*, 341-342
 - discarding symbols from*, 499
 - displaying information from*, 342-343
 - listing section and total sizes*, 489-490
 - listing symbols from*, 339-340
- offsets, repositioning, 793-794
- opening, 815-816
 - advisory locks (applying/removing)*, 757
- outputting
 - ends of*, 504
 - headers*, 253-254
- ownership, changing, 62-63, 749-750
- password, editing, 1418-1419
- PCX, converting to portable
 - pixmap*s, 368-369
- permissions
 - changing*, 748-749
 - checking*, 741-742
 - setting modes*, 272-273
- Photo-CD, converting to portable
 - pixmap*s, 260-261
- portable anymap
 - format*, 1173
 - reading*, 971
 - writing*, 971-972
- portable bitmap
 - format*, 1170-1171
 - reading*, 968
 - writing*, 968-969
- portable graymap
 - format*, 1171-1172
 - reading*, 970
 - writing*, 970
- portable pixmap
 - format*, 1173-1174
 - reading*, 974
 - writing*, 974
- PostScript, converting to portable
 - anymaps*, 434-435
- preserving after crashes, 128-129
- printer/plotter accounting, reading, 1354-1355
- printing, in reverse, 503-504
- protocol definition, 1180-1181
- RCS
 - changing attributes*, 441-443
 - cleaning*, 443-445
 - comparing revisions*, 445-446
 - controlling access*, 67
 - format*, 1181-1183
 - freezing configuration*, 446-447
 - modes*, 67
 - organization (diagram)*, 1182
 - printing log messages*, 458-460
 - retrieving revisions*, 71-75
 - specifying*, 66-67
 - storing revisions*, 64-69
 - temporary files*, 67
- recovering after crashes, 129-130
- refs, generating, 87-88
- remote distribution, 451-454
- removing, 461-462
 - columns*, 77-78
 - sets of*, 1294-1295
- renaming, 334-335
- resolver configuration, 1183-1184
- reversing lines, 457
- searching for (in directories), 137-142
- SF86Config, generating, 633
- SGI image, converting to portable
 - anymaps*, 483-484
- shar, unpacking, 560-561
- shrinking, 488
- Solitaire, converting to portable
 - anymaps*, 488-489
- sorted, removing duplicate lines, 560
- source, locating for
 - commands*, 575-576
- spell-checking utilities, 281
- splitting, 85-86, 119-120, 494-495
- status, getting, 863-864
- string table C source files/headers, 314-315
- substituting definitions into, 500-501
- suffixes, list of, 1249-1252
- Sun raster, converting to portable
 - anymaps*, 438

- swapping
 - enabling/disabling*, 1401
 - starting/stopping*, 866-867
 - symbolic links, 867-869
 - synchronizing
 - in-core data*, 756-757
 - in-core state*, 758-759
 - with memory maps*, 811
 - tag
 - emacs*, 135-137
 - vi*, 135-137
 - tags, generating, 87-88
 - temporary
 - creating*, 983, 1053-1054
 - naming*, 1049, 1054
 - text
 - converting for printing*, 429-430
 - creating gcal resource files from*, 558
 - sorting*, 492-493
 - TIFF, converting to portable
 - anymaps*, 515-516
 - time zone information, 1197-1198
 - timestamps (changing), 536
 - transfer parameters, 153
 - TrueVision Targa, converting to portable pixmaps, 515
 - truncating, 879-880
 - UNIX
 - copying between systems*, 563-565
 - copying to MS-DOS*, 335
 - restoring filenames*, 324-325
 - Usenix FaceSaver, converting to portable graymaps, 147
 - user group, 1131
 - UUCP transfer requests, processing, 1415-1417
 - uuencode, format, 1200
 - XFree86, 638-639, 1201-1208
 - Device sections*, 1204-1206
 - Files section*, 1201
 - Keyboard section*, 1202
 - Monitor sections*, 1203-1204
 - Pointer section*, 1202-1203
 - Screen sections*, 1206-1208
 - ServerFlags section*, 1201
 - XIM, converting to portable
 - pixmaps*, 654
 - YUV, converting to portable
 - pixmaps*, 730-731
 - Z, recompressing to GZ, 734-735
 - Zeiss confocal, converting to
 - portable anymaps*, 732
 - filesystem checks
 - group identity (setting)*, 843-844
 - user identity (setting)*, 844
 - filesystem description file, accessing, 935-936
 - filesystems, 1125-1126
 - buffers, flushing*, 1401-1402
 - building*, 1325-1326
 - checking*, 1298-1300
 - debugger*, 1284-1285
 - commands*, 1284-1285
 - options*, 1284
 - deleting names from*, 1008
 - device entries, maintaining*, 1320-1321
 - dumping information*, 1289
 - ext*, 1125
 - ext2*, 1125
 - hierarchy, description of*, 1236-1238
 - High Sierra*, 1125
 - hpfs*, 1125
 - iso9660*, 1125
 - MINIX*, 1125
 - consistency checker*, 1300-1301
 - creating*, 1326-1327
 - mounting/dismounting*, 802-804, 1328-1332
 - msdos*, 1125
 - names, deleting*, 882
 - ncpfs*, 1126
 - nfs*, 1125
 - export list*, 1123-1125
 - proc*, 1125
 - quotas*
 - summarizing*, 1376
 - turning on/off*, 1372-1373
 - repairing*, 1298-1299
 - Rock Ridge*, 1125
 - root, mounting*, 849
 - scanning*, 1371-1372
 - second extended*
 - checking*, 1289-1291
 - creating*, 1324-1325
 - lost+found directory*, 1327
 - tunable parameters (adjusting)*, 1412-1413
 - setup*, 849
 - smb*, 1126
 - static information*, 1126-1127
 - statistics, getting*, 883-884, 865-866
 - sysv*, 1125
 - table of*, 1427-1428
 - type information, getting*, 871
 - umsdos*, 1125
 - vfat*, 1125
 - xiafs*, 1125
- filesystems command, 1427-1428
- filters
- Laplacian relief, running on portable pixmaps*, 413
 - more*, 327-328
 - commands*, 328
 - environment*, 328
 - options*, 327-328
 - nonlinear (pnmnlfilt)*, 390-391
 - nroff output*, 77
 - reverse line feeds*, 76

- find, 137-142
 - actions, 140-142
 - expressions, 138
 - numeric arguments, 138-140
 - operators, 142
 - options, 138
- findaffix, 274, 280
 - bugs, 282
 - files, 281
 - see also* ispell
- finger daemons, configurable, 1106-1109
 - configuration file, 1109-1115
 - error messages, 1108
 - features, 1107-1108
 - SYSLOG messages, 1108
- finger information, changing, 60
- finite() function, 959
- first in - first out scheduling, 833-834
- FITS files, converting to portable anymaps, 142-143
- fitstopnm, 142-143
- floating-point numbers
 - absolute value, 919
 - converting
 - to fractional/integral components*, 927
 - to strings*, 913-914, 930-931
 - extracting integral and fractional values, 984
 - multiplying, by integral powers of 2, 961
- flock, 757
- floor() function, 923
- floppy disks
 - devices, 1080-1083
 - configuration*, 1080-1082
 - drivers, boot-time
 - parameters, 1223-1224
 - formatting, 1295-1296
 - marking bad blocks, 316
 - parameters, setting, 1391
- fmod() function, 923
- fmt, 143
- fnmatch() function, 924
- fold, 143-144
- font files
 - adding font-metric information, 2
 - creating, 3
- font formats
 - converting
 - Bitmap Distribution to Portable Compiled*, 47
 - packed format to portable bitmaps*, 381
 - PostScript PFB format to ASCII*, 369
 - groff_font, 1127-1129
 - DESC file*, 1127-1128
- font servers (X)
 - displaying information
 - about, 145
 - generating BDF fonts, 146-147
 - listing fonts, 145-146
- fonts
 - files, 1128
 - creating for groff*, 513
 - grops styles, 231-232
 - man pages, 1247
 - X
 - displaying all characters in*, 633-636
 - listing*, 670-671
 - X font server, 641-643, 689
 - configuration*, 642
 - naming*, 643
- fopen function, 924-925
 - errors, 925
 - mode argument sequences, 924-925
 - return values, 925
- fork, 758
- form (ftp command), 149
- formatting
 - dates, strftime() function, 1032-1034
 - documents, gtroff, 237-248
 - equations, 202-206
 - floppy disks, 1295-1296
 - input, 1013-1015
 - conversions*, 1014-1015
 - flags*, 1014
 - line lengths, 143
 - man pages, 1246-1248
 - fonts*, 1247
 - macros*, 1248
 - preamble*, 1246-1247
 - sections*, 1247-1248
 - output, 992-996, 1022-1023
 - conversion specifiers*, 994
 - examples*, 995
 - flags*, 993-994
 - technical papers
 - groff_me macros*, 1225-1227
 - groff_mm macros*, 1227-1234
 - groff_ms macros*, 1234-1236
 - times, strftime() function, 1032-1034
 - troff tables, 236-237
- fpathconf() function, 925-926
- fprintf function, 992-996
- fpurge function, 920-921
- fputc() function, 997-999
- fputs() function, 997-999
- fractal forgeries, 404-407
- fread function, 926-927
- free, 144
- free() function, 976
- freopen function, 924-925
- frexp() function, 927
- fscanf function, 1013-1015
- fsck, 1298-1300
- fsck.minix, 1300-1301
- fseek function, 927-928
- fsetpos function, 927-928
- fsinfo, 145
- fsfonts, 145-146
- fstab, 1126-1127
 - file format/options*, 1165-1167

fstat, 863-864
fstatfs, 865-866
fstobdf, 146-147
fstopgm, 147
fsync, 758-759
ftell function, 927-928
ftime function, 928-929
ftok function, 929-930
 FTP (File Transfer Protocol), DARPA server, 1301-1304
ftp, 147-154
 aborting transfer, 152
 bugs, 154
 commands, 148-152
 !, 148
 \$, 148
 ?, 152
 account, 148
 append, 148
 ascii, 148
 bell, 148
 binary, 148
 bye, 148
 case, 148
 cd, 148
 cdup, 148
 chmod, 148
 close, 148
 cr, 148
 debug, 149
 delete, 148
 dir, 149
 disconnect, 149
 form, 149
 get, 149
 glob, 149
 hash, 149
 help, 149
 idle, 149
 lcd, 149
 ls, 149
 macdef, 149
 mdelete, 149
 mdir, 150
 mget, 150
 mkdir, 150

mls, 150
mode, 150
modtime, 150
mput, 150
newer, 150
nlist, 150
nmap, 150
ntrans, 150-151
open, 151
prompt, 151
proxy ftp, 151
put, 151
pwd, 151
quit, 151
quote, 151
recv, 151
reget, 151
remotehelp, 151
remotestatus, 151
rename, 151
reset, 151
restart, 151
rmdir, 152
runique, 152
send, 152
sendport, 152
site, 152
size, 152
status, 152
struct, 152
system, 152
trace, 152
type, 152
umask, 152
user, 152
verbose, 152
 environment variables, 154
 file naming conventions, 153
 file transfer parameters, 153
 .netrc file, 153-154
 options, 147-148
 tenex, sendport, 152
ftpd, 1301-1304
 bugs, 1303
 FTP requests supported, 1302-1303
 options, 1302

ftruncate, 879-880
ftw() function, 930
 full-duplex connections, shutting down, 855
 function bindings, displaying, 35
 functions
 calling at termination, 897-898, 988
 headers, displaying, 455-456
 library, undocumented, 1060
 portable pixmap programs, 973-974
 color names, 974
 memory management, 973
 reading files, 974
 writing files, 974
fuser, 154-155
fwrite function, 926-927

G

g++, 155-160, 174-201
 bugs, 160
 copying, 160, 201
 filename suffixes, 174-175
 files, 159-160, 200
 options, 155-159, 175-178
 assembler, 181
 code generation, 198-199
 debugging, 186-187
 directory, 182-183
 language, 178-180
 linker, 181-182
 machine-dependent, 191-198
 optimization, 188-190
 preprocessor, 180-181
 target, 190-191
 warning, 183-186
 pragmas, 159, 200
g3topbm, 160-161
games, 1210
gawk, 161-173
 actions, 165-166
 arithmetic functions, 168-169

- bugs, 172
 - reporting, 172-173*
- control statements, 167
- environment variables, 172
- fields, 163
- functions, 170
- GNU extensions, 171
- historical awk features
 - supported, 172
- I/O statements, 167
- operators, 166-167
- options, 161-162
- patterns, 165-166
- POSIX compatibility, 171
- printf statement, 167-168
- program execution, 162-163
- regular expressions, 166
- special filenames, 168
- sprintf() function, 167-168
- string constants, 169-170
- string functions, 169
- time functions, 169
- variables, 163-165
 - arrays, 164*
 - built-in, 163-164*
 - typing and conversion, 164-165*
- version information, 172
- gcal, 173-174
 - running one day ahead, 506
 - resource files, creating from
 - text files, 558
- gcc, 174-201
 - assembling output, 8-9
 - bugs, 201
 - copying, 201
 - filename suffixes, 174-175
 - files, 200
 - options, 175-178
 - assembler, 181*
 - code generation, 198-199*
 - debugging, 186-187*
 - directory, 182-183*
 - language, 178-180*
 - linker, 181-182*
 - machine-dependent, 191-198*
 - optimization, 188-190*
 - preprocessor, 180-181*
 - target, 190-191*
 - warning, 183-186*
 - pragmas, 200
- gcvt() function, 930-931
- GEM IMG files, converting to
 - portable bitmaps, 201
- gemtopbm, 201
- GenerateMessageID routine, 964
- geqn, 202-206
 - automatic spacing, 203
 - bugs, 206
 - customization, 204-205
 - equation components, 202-203
 - files, 206
 - fonts, 206
 - macros, 206
 - new primitives, 203-204
 - options, 202
- get (ftp command), 149
- get_current_dir_name()
 - function, 931
- get_empty_filp, 1428
- get_kernel_syms, 800-802
- getc() function, 945
- getchar() function, 945
- GetConfigValue routine, 965
- getcwd() function, 931
- getdents, 759
- getdirenties function, 931-932
- getdomainname, 760
- getdtablesize, 760-761
- getegid, 761
- getenv() function, 932
- geteuid, 773
- GetFileConfigValue routine, 965
- GetFQDN routine, 965
- getgid, 761
- getgrent() function, 932-933
- getgrgid() function, 933-934
- getgrnam() function, 933-934
- getgroups, 761-762
- gethostid, 762-763
- gethostname, 763
- getitimer, 763-764
- getlist, 206-207
- getlogin() function, 934-935
- getmntent() function, 935-936
- GetModeratorAddress
 - routine, 965
- getnetbyaddr subroutine, 936-937
- getnetbyname subroutine, 936-937
- getnetent subroutine, 936-937
- getopt, 207-208
- getopt() function, 937-940
 - environment variables, 939
 - getopt_long() example, 939-940
 - return value, 939
- getopt_long() function, 938-940
- getopt_long_only() function, 938
- getopts (shell command), 38
- getpagesize, 765
- getpass function, 940-941
- getpeername, 765
- getpgid, 845-846
- getpgrp, 845-846
- getpid, 766
- getppid, 766
- getpriority, 766-767
- getprotobyname() function, 941-942
- getprotobynumber()
 - function, 941-942
- getprotoent() function, 941-942
- getpw() function, 942-943
- getpwent() function, 943
- getpwnam() function, 944
- getpwuid() function, 944
- GetResourceUsage routine, 965
- getrlimit, 767-768
- getrusage, 767-768

- gets() function, 945
- getservbyname() function, 946
- getservbyport() function, 946
- getservent() function, 946
- getsid, 768
- getsockname, 769
- getsockopt, 769-772
 - bugs, 772
 - errors, 771
 - options recognized, 770-771
 - SO_BROADCAST, 771
 - SO_DEBUG, 770
 - SO_DONTROUTE, 770
 - SO_ERROR, 771
 - SO_KEEPAIVE, 770
 - SO_LINGER, 770
 - SO_RCVBUF, 771
 - SO_RCVLOWAT, 771
 - SO_RCVTIMEO, 771
 - SO_REUSEADDR, 770
 - SO_SNDBUF, 771
 - SO_SNDLOWAT, 771
 - SO_SNDTIMEO, 771
 - SO_TYPE, 771
 - return value, 771
- GetTimeInfo routine, 965
- gettimeofday, 772-773
- getuid, 773
- getusershell() function, 946-947
- getutent() function, 947
- getutid() function, 947
- getutline() function, 948
- getw function, 948
- getwd() function, 931
- GIF files, converting to
 - portable anymaps, 208-209
- giftopnm, 208-209
- giles, gpics, 215
- gindxbib, 209-210
- glob (ftp command), 149
- glob() function, 949-950
- glob_dot_filenames variable (bash), 17
- globfree() function, 949-950
- glookbib, 210
- gmtime, 984-986
- gmtime() function, 909-910
- gnroff, 210-211
- GNU linker, 287-291
 - copying, 291
 - environment, 291
 - options, 288-291
- GNU ar, *see* ar
- GNU as, *see* as
- GNU Bourne-again shell, *see* bash
- Gould scanner files, converting to portable pixmaps, 211
- gouldtoppm, 211
- gpics, 211-215
 - bugs, 215
 - commands, 212-213
 - expressions, 213-214
 - file, 215
 - mode, 212
 - options, 211-212
 - versus pic, 212-215
- gprof, 216-217
- graph profile data, displaying, 216-217
- graphics (ASCII), converting to portable graymap, 10
- graphs
 - system load average, 533
 - topological sorts, 542
- grayscale ramps, generating, 374-375
- greater than signs (>), redirection operator, 21
- grefer, 217-224
 - bibliographic databases, 219
 - bugs, 224
 - citations, 219-220
 - commands, 220-222
 - files, 224
 - label expressions, 223-224
 - macro interface, 224
 - options, 218-219
- grep, 224-226
 - bugs, 226
 - diagnostics, 226
 - options, 224-225
 - regular expressions, 225-226
- groddvi, 227-228
- groff, 228-230
 - availability, 230
 - bugs, 230
 - creating font files for, 513
 - environment, 229
 - files, 229
 - guessing options, 230
 - interpreting .so requests, 236
 - options, 229
 - output, converting to TeX
 - dvi format, 227-228
 - PostScript driver, 230-235
 - preprocessing references, 217-224
 - typewriter device driver, 235
- groff_font format, 1127-1129
 - DESC file, 1127-1128
- groff_me, 1225-1227
- groff_mm, 1227-1234
 - extensions, 1227-1229
 - number variables, 1233-1234
 - strings, 1233
 - variables, 1229-1230
- groff_ms, 1234-1236
- groff_out, 1129-1131
- grog, 230
- grogs, 230-235
 - files, 234
 - font styles, 231-232
 - options, 231
 - X commands, 232-233
- grotty, 235-236
- group, 1131
- Group 3 fax files, converting to portable bitmaps, 160-161
- group access lists
 - getting/setting, 761-762
 - initializing, 955

group file entries, getting, 921-922, 932-934

group identity, setting, 845

group IDs

- getting/setting, 761, 845-846
- real and effective, setting, 846-847

group ownership (files), changing, 61

groups

- adding to system, 1258-1259
- logging into, 336-337
- process, sending signals to, 960

group_files, 1428-1429

grttoppm, 436-437

gsoelim, 236

gtbl, 236-237

gtroff, 237-248

- environment, 248
- escape sequences, 239-240
- files, 248
- fractional point sizes, 238-239
- incompatibilities, 247-248
- long names, 238
- numeric expressions, 239
- options, 238
- requests, 241-244
 - extended*, 244
 - number registers*, 245-246
- warnings, 246-247

gunzip, 248-249

- see also* gzip

gzexe, 252-253

gzip, 248-252

- bugs, 252
- diagnostics, 251-252
- environment, 251
- options, 249-250

gzip files, forcing .gz extension, 732-733

H

handling signals, 857-858

hard disks

- boot-time parameters, 1220-1221
- devices, 1083
- partition tables, manipulating, 1296-1297

hard drives, partitioning, 1265-1269

hard-reset() action (xterm), 715

hardware, video (identifying), 501-503

hash

- ftp command, 149
- shell command, 38

hash tables

- creating, 951
- freeing memory, 951
- searching, 951

hasmntopt() function, 935-936

hcreate() function, 951-952

hd, 1083

hdestroy() function, 951

head, 253-254

HeaderCleanFrom routine, 964

HeaderFind routine, 964

headers function, displaying, 455-456

help

- ftp command, 149
- shell command, 38
- xauth command, 591

here-documents, 22-23

hexdump, 254-256

hier, 1236-1238

- directories, 1236-1238
 - /, 1236
 - /bin, 1236
 - /boot, 1236
 - /dev, 1236
 - /dos, 1236
 - /etc, 1236
 - /etc/skel, 1236
 - /etc/X11, 1236
 - /home, 1236
 - /lib, 1236
 - /mnt, 1236
 - /proc, 1236
 - /sbin, 1237
 - /tmp, 1237
 - /usr, 1237
 - /usr/X11R6, 1237
 - /usr/X11R6/bin, 1237
 - /usr/X11R6/lib, 1237
 - /usr/X11R6/lib/X11, 1237
 - /usr/X11R6/include/X11, 1237

hierarchies

- directory (creating), 323
- filesystem, description of, 1236-1238

High Sierra filesystem, 1125

HIPS files, converting to portable graymaps, 256

hipstopgm, 256

histchars variable (bash), 17-18

HISTCMD variable (bash), 16

HISTFILE variable (bash), 17

HISTFILESIZE variable (bash), 17

histograms

- drawing for PGM or PPM files, 388
- portable pixmaps, printing, 408

history, 1131-1132

- control variable (bash), 17
- cvs command, 99
- shell command, 39

history expansion (bash), 33-34

- event designators, 33
- modifiers, 34
- word designators, 33

history lists (bash), 32-33

- displaying, 39

HISTSIZE variable (bash), 17

- HOME variable (bash), 16
 - /home directory, 1236
 - horizontal-scroll-mode variable (readline), 28
 - host, 257-258
 - bugs, 258
 - customizing, 258
 - options, 257-258
 - host byte order, converting
 - between network byte order, 901-902
 - host IDs, printing, 258-259
 - hostid, 258-259
 - hostname, 259-260, 1238-1239
 - hostname_completion_file variable (bash), 18
 - hostnames
 - displaying, 259-260
 - looking up, 257-258
 - resolving, 1238-1239
 - hosts
 - identifiers, getting/setting, 762-763
 - names, getting/setting, 763
 - sending messages to users on, 473
 - hosts.nntp, 1132-1133
 - hosts.nntp.nolimit, 1132-1133
 - hosts_access, 1133-1136
 - access control files, 1133
 - access control rules, 1133
 - bugs, 1136
 - diagnostics, 1136
 - files, 1136
 - operators, 1134
 - patterns, 1133-1134
 - remote username lookup, 1134-1135
 - shell commands, 1134
 - wildcards, 1134
 - hosts_access() function, 950-951
 - hosts_ctl() function, 950-951
 - hosts_options, 1137-1139
 - diagnostics, 1139
 - options, 1137
 - HOSTTYPE variable (bash), 16
 - HP PaintJet files, converting to portable pixmaps, 381
 - hpcdtoppm, 260-261
 - hpfs filesystem, 1125
 - hsearch() function, 951-952
 - htonl() function, 901-902
 - htons() function, 901-902
 - httpd, 261
 - hyperbolic cosines, 908
 - hyphens (-), bash special parameters, 15
 - hypot() function, 953
-
- I
 - I/O
 - awk statement, 167
 - port permissions, setting, 788
 - ports, functions, 816
 - privilege level, changing, 788-789
 - standard I/O library, 1025-1027
 - ICccancel routine, 956
 - ICCclose routine, 956
 - ICCcommand routine, 956
 - ICCopen routine, 956
 - ICCpause routine, 956
 - ICCreserve routine, 956
 - ICCsettimeout routine, 956
 - icombo, 274, 281
 - files, 281
 - see also* ispell
 - icontopbm, 262
 - ident, 262-263
 - idle, 774
 - errors, 774
 - ftp command, 149
 - return value, 774
 - IDs (group), searching for matches, 1429
 - \$if parser directive (readline), 28-29
 - ifconfig, 1304-1305
 - IFS variable (bash), 16
 - ignore() action (xterm), 713
 - IGNOREEOF variable (bash), 17
 - ijoin, 274, 281
 - files, 281
 - see also* ispell
 - ILBM files, converting to portable pixmaps, 263-264
 - ilbmtoppm, 263-264
 - image files, converting to portable anymap, 4
 - image parameter, values, 1374
 - imake, 264-267
 - environment variables, 267
 - files, 266
 - input*, 266
 - options, 265
 - X Window System, 266
 - Imakefiles, creating Makefiles from, 672
 - Img-whatnot file, converting to portable pixmaps, 267
 - imgtoppm, 267
 - import (cvs command), 100
 - in_group_p, 1429
 - inb, 816
 - inb_p, 816
 - inbound zone transfers, 1333-1334
 - index() function, 953
 - indexes, archives (generating for), 437-438
 - inet_addr() function, 954
 - inet_aton() function, 954
 - inet_lnaof() function, 954
 - inet_makeaddr() function, 954
 - inet_netof() function, 954
 - inet_network() function, 954
 - inet_ntoa() function, 954
 - inetd, 1305-1307
 - inews, 267-269
 - infinite results
 - returning value for, 954-955
 - testing for, 959
 - infnan() function, 954-955

- info, 269-270
 - commands, 269-270
 - environment, 270
 - options, 269
- info command (xauth), 591
- init, 1307-1309
 - diagnostics, 1309
 - files, 1308
 - run levels, 1308
- init_module, 800-802
- init_timer, 1424
- initgroups() function, 955
- initializing
 - terminals, 539-542
 - X sessions, 496-497
- initstate() function, 1001-1002
- inittab, 1139-1141
- inittab file, 1398
- inl, 816
- inl_p, 816
- inn.conf, 1141-1142
- innconfval, 270-271
- innnd, 1309-1312
 - control messages, 1310
 - header modifications, 1311
 - logging, 1311-1312
 - protocol differences, 1310-1311
- innndcomm routines, 956
- innndstart, 1309-1312
- INNVersion routine, 966
- innwatch.ctl, 1142-1144
- innxmit, 1312-1313
- input
 - formatting, 1013-1015
 - conversions, 1014-1015
 - flags, 1014
 - reading, 27-32
 - controlling key bindings, 27
 - denoting keystrokes, 27
 - macro definitions, 28
 - readline commands, 29-32
 - redirecting, 22
- input lines, wrapping, 143-144
- input, *see* elvis
- INPUTRC variable (bash), 17
- insb, 816
- insert() action (xterm), 713
- insert-eight-bit() action (xterm), 713
- insert-selection() action (xterm), 713
- insert-seven-bit() action (xterm), 713
- insert_file_free, 1429
- insl, 816
- insmod, 271-272
- insque() function, 957
- install, 272-273
- installing
 - loadable modules, 271-272
 - rstartd, 469
 - spottopgm, 495
 - sysklogd, 1403
- installit, 273-274
- insw, 816
- integers
 - absolute values, 892-893
 - converting, between host and network byte order, 901-902
 - dividing, 911
 - floating-point remainders, 913, 923
 - returning quotient and remainder, 961
 - long, labs, 960-961
 - rounding, 904
 - downward, 923
 - to, 1011-1012
- interactive shells, 45
- interfaces
 - name daemon control, 1338-1339
 - network
 - attaching to serial line, 1399
 - configuring, 1304-1305
- serial mouse, 1092-1094
 - Microsoft protocol, 1093
 - MM protocol, 1094
 - MouseSystems protocol, 1093
 - Sun protocol, 1093
- interned atoms, listing, 668-669
- Internet
 - addresses, manipulating, 953-954
 - extended Internet services daemon, 655-664
 - inetd superserver, 1305-1307
 - services, listing, 1184-1186
- InterNetNews
 - buffered file-writing, 1264-1265
 - configuration data, 1141-1142
 - daemon, 1309-1312
 - control messages, 1310
 - controlling, 1276-1279
 - file-writing, 1297-1298
- InterNetNews library
 - clientlib, 904-905
 - INND communication routines, 956
 - libinn routines, 962-966
 - CAClose, 964
 - CAlistopen, 964
 - CAopen, 964
 - CloseOnExec, 965
 - DDcheck, 965
 - DDend, 965
 - DDstart, 965
 - GetConfigValue, 965
 - GetFileConfigValue, 965
 - GetFQDN, 965
 - GetModeratorAddress, 965
 - GetResourceUsage, 965
 - GetTimeInfo, 965
 - HeaderFind, 964
 - INNVersion, 966

- LockFile*, 965
 - NNTPcheckarticle*, 965
 - NNTPconnect*, 965
 - NNTPlocalopen*, 965
 - NNTPremoteopen*, 965
 - NNTPsendarticle*, 966
 - NNTPsendpassword*, 966
 - Radix32*, 966
 - ReadInDescriptor*, 966
 - ReadInFile*, 966
 - SetNonBlocking*, 965
 - Quick I/O, 998
 - interrupt key sequence, routing, 1425
 - interval timers
 - getting/setting value, 763-764
 - ITIMER_PROF, 764
 - ITIMER_REAL, 764
 - ITIMER_VIRTUAL, 764
 - value definitions, 764
 - inverse hyperbolic cosines, 893-894
 - inverse hyperbolic sines, 895
 - inverse hyperbolic tangents, 897
 - inverted indexes, bibliographic databases, 209-210
 - invocation, bash, 45-46
 - inw, 816
 - inw_p, 816
 - ioctl, 774-788
 - arguments, 787-788
 - calls
 - consoles*, 1074-1080
 - fd device support*, 1082
 - list of*, 775-786
 - lp*, 1090-1091
 - sd*, 1095-1096
 - st*, 1097-1100
 - duplicates, 788
 - errors, 774
 - return value, 774
 - ioperm, 788
 - iopl, 788-789
 - errors, 789
 - return value, 789
 - IP
 - dialup connections, handler, 1285-1288
 - routing table (manipulating), 1379-1380
 - ipc, 789, 1144-1146
 - message queues, 1145
 - resource access permissions, 1144-1145
 - semaphore sets, 1145-1146
 - shared memory segments, 1146
 - ipc facilities
 - getting information on, 1314
 - removing, 1313-1314
 - IPC system calls, 789
 - ipcrm, 1313-1314
 - ipcrs, 1314
 - isalnum() function, 958
 - isalpha() function, 958
 - isascii() function, 958
 - isatty function, 958-959
 - isblank() function, 958
 - iscntrl() function, 958
 - isdigit() function, 958
 - isgraph() function, 958
 - isinf() function, 959
 - islower() function, 958
 - isnan() function, 959
 - ISO character sets
 - 2022, 1066
 - 4873, 1066
 - 8859, 1064-1065
 - 8859-1, 1239-1242
 - alphabets*, 1240
 - characters*, 1240-1242
 - iso9660 filesystem, 1125
 - ispell, 274-279, 1084-1090
 - affix file, 1084-1085
 - alternate string characters, 1087
 - bugs, 282
 - capitalization rules, 279
 - character-set section, 1086
 - commands, 274-275
 - flags, 1088
 - headers, 1085
 - options, 275-279
 - options statements, 1085-1086
 - prefix/suffix tables, 1088
 - root words
 - case*, 1084
 - extending*, 1085
 - modifying*, 1088-1089
 - isprint() function, 958
 - ispunct() function, 958
 - isspace() function, 958
 - issue, 1146-1147
 - isupper() function, 958
 - isxdigit() function, 958
 - ITIMER_PROF interval timer, 764
 - ITIMER_REAL interval timer, 764
 - ITIMER_VIRTUAL interval timer, 764
-
- ## J
-
- j0() function, 959
 - j1() function, 959
 - jn() function, 959
 - job control, 24-25
 - jobs, displaying, 39
 - jobs (shell command), 39
 - join, 282-283
 - rand48() functions, 912
-
- ## K
-
- kbdrate, 1314-1315
 - Kerberos authentication, 461
 - kernel
 - boot-time parameters, 1216-1224
 - Adaptec configurations*, 1219-1220
 - argument list*, 1216-1217
 - BusLogic configuration*, 1220
 - busmouse drivers*, 1224
 - cards not accepting*, 1220

- CD-ROMs, 1222-1223
 - debug* argument, 1217
 - Ethernet devices, 1223
 - floppy disk drivers, 1223-1224
 - future domain configuration*, 1220
 - hard disks, 1220-1221
 - mem=* argument, 1218
 - no-hlt* argument, 1217
 - no387* argument, 1217
 - Pro Audio* configuration, 1220
 - ramdisk=* argument, 1218
 - reboot=warm* argument, 1218
 - reserve=* argument, 1217-1218
 - ro* argument, 1217
 - root=* argument, 1217
 - rw* argument, 1217
 - SCSI device arguments, 1218-1219
 - SCSI tape configuration, 1219
 - Seagate ST-0x configuration, 1220
 - sound drivers, 1224
 - Trantor T128 configuration, 1220
 - exported symbols, displaying, 284-285
 - log buffer, 873
 - message ring buffer, reading/clearing, 872-874
 - modules, loading at boot time, 1152
 - name, getting, 880-881
 - ring buffer, controlling, 1288-1289
 - kernel clock, adjusting, 742-743
 - kernel log daemon, 1315-1317
 - kernel logging, 1402
 - kernel_mktime, 1430
 - key bindings, displaying, 35
 - key combinations, Ctrl+Alt+Del (setting function), 1279
 - key sequences (interrupt), routing, 1425
 - keyboard repeat rate, resetting, 1314-1315
 - keymap variable (readline), 28
 - keymap() action (xterm), 713
 - keymaps (X), modifying, 672-676
 - keywords, RCS, identifying in files, 262-263
 - kill, 283-284, 790
 - bugs, 790
 - errors, 790
 - options, 283
 - return value, 790
 - shell command, 39
 - killall, 284
 - killing client connections (X servers), 666-667
 - killpg, 790-791, 960
 - klogd, 1315-1317
 - files, 1317
 - options, 1315
 - signal handling, 1316-1317
 - kmem, 1091-1092
 - KOI8-R character set, 1065
 - ksyms, 284-285
- ## L
-
- labs() function, 960-961
 - Laplacian relief filters, running on portable pixmaps, 413
 - last, 285-286
 - Latin-1 character set, 1064
 - Latin-2 character set, 1064
 - Latin-3 character set, 1064
 - Latin-4 character set, 1064
 - Latin-5 character set, 1065
 - Latin-6 character set, 1065
 - lbxproxy, 286-287
 - network connections, 286
 - options, 286
 - lcd (ftp command), 149
 - lcong48() functions, 912
 - ld, 287-291
 - copying, 291
 - environment, 291
 - options, 288-291
 - ldexp() function, 961
 - ldiv() function, 961
 - less than signs (<), redirection operator, 21
 - let (shell command), 39
 - letters, converting
 - to lowercase, 1055-1056
 - to uppercase, 1055-1056
 - lfind() function, 975-976
 - lgamma() function, 962
 - /lib directory, 1236
 - libinn routines, 962-966
 - CAClose, 964
 - CAListopen, 964
 - CAopen, 964
 - CloseOnExec, 965
 - DDcheck, 965
 - DDend, 965
 - DDstart, 965
 - GetConfigValue, 965
 - GetFileConfigValue, 965
 - GetFQDN, 965
 - GetModeratorAddress, 965
 - GetResourceUsage, 965
 - GetTimeInfo, 965
 - HeaderFind, 964
 - INNVersion, 966
 - LockFile, 965
 - NNTPPcheckarticle, 965
 - NNTPPconnect, 965
 - NNTPPlocalopen, 965
 - NNTPPremoteopen, 965
 - NNTPPsendarticle, 966
 - NNTPPsendpassword, 966
 - Radix32, 966
 - ReadInDescriptor, 966
 - ReadInFile, 966
 - SetNonBlocking, 965
 - libpbm routines, 966-969
 - constants, 968
 - endian i/o, 967
 - errors, 967

- file management, 967
- initialization, 968
- keyword matching, 967
- memory management, 968
- messages, 967
- reading files, 968
- types, 968
- writing files, 968-969
- libpgm routines, 969-970
 - constants, 969
 - initialization, 969
 - memory management, 969
 - reading files, 970
 - types, 969
 - writing files, 970
- libpnm routines, 970-972
 - constants, 970
 - format promotion, 972
 - initialization, 971
 - memory management, 971
 - reading files, 971
 - types, 970
 - writing files, 971-972
 - XEL manipulation, 972
 - XEL manipulations, 971
- libppm, 973-974
 - color names, 974
 - memory management, 973
 - reading files, 974
 - writing files, 974
- libraries
 - shared, selecting, 883
 - standard I/O, 1025-1027
- library functions, undocumented, 1060
- LILO, 1216
 - configuration file, 1147-1151
 - global options, 1148-1149*
 - kernel options, 1150-1151*
 - per-image section, 1149-1150*
- line buffered streams, 1016
- line printer
 - control program, 1317-1318
 - devices, 1090-1091
 - ioctl() calls, 1090-1091*
 - spooler daemon, 1318-1320
- linear searches, arrays, 975-976
- LINENO variable (bash), 15
- link, 791-792
- linkers, ld (GNU linker), 287-291
 - copying, 291
 - environment, 291
 - options, 288-291
- linking files, 293-294, 791-792
- Lisp Machine bitmap files, converting to portable graymaps, 292
- lispmtopgm, 292
- list
 - bash command, 13
 - xauth command, 591
- listen, 792-793
- lists
 - bash, 12-13
 - columnating, 78
 - variable argument (declaring), 1023-1024
- lkbib, 292-293
- llseek, 793
- ln, 293-294
- ln_dir, 294
- loadable modules
 - installing, 271-272
 - support, 800-802
 - unloading, 462-463
 - viewing, 305
- loadlin program, 1216
- local (shell command), 39
- local descriptor table, reading/writing, 800
- local variables, creating, 39
- locale, 1243-1244
 - setting, 1018-1019
- localeconv, 974-975
- localtime, 909-910, 984-986
- locate, 295
- lock files, creating for shell scripts, 487
- LockFile routine, 965
- locking memory
 - mlock, 796-797
 - mlockall, 797-798
- locks (advisory), applying/removing open files, 757
- log (cvs command), 100
- log() function, 918
- log10() function, 918
- log1p() function, 918
- logarithms, 918
 - 1 plus argument, 918
 - base-10, 918
- logger, 295-296
- logging
 - innd, 1311-1312
 - kernel, 1402
 - system, 1402-1404
 - configuration file, 1402-1403*
 - FIFOs, 1403*
 - messages, 1404-1405*
 - remote, 1403*
 - Usenet, log file maintenance, 1346-1347
- login, 296-297
- login shells, 45
 - changing, 63
 - exiting, 39
- logins
 - changing groups, 336-337
 - displaying last, 285-286
 - login command, 296-297
 - login record files, 1198-1200
 - preventing, 1168
 - remote, 460-461
 - Kerberos authentication, 461*
 - root, tty lines (listing), 1184
 - shells, pathnames, 1186
- logout (shell command), 39
- logs
 - system
 - making entries, 295-296*
 - sending messages to, 1045-1046*
 - xinetd, 661-663

- long integers, absolute values, 960-961
- longjmp() function, 975
- look, 297-298
- loops
 - exiting, 35
 - resuming, 36
- lowercase, converting letters to, 1055-1056
- lp, 1090-1091
- lp devices, setting parameters, 1413-1414
- lpc, 1317-1318
 - commands, 1317-1318
 - diagnostics, 1318
- lpd, 1318-1320
 - key characters, 1319
 - options, 1319
- lpq, 298-299
 - bugs, 299
 - diagnostics, 299
 - environment, 299
 - options, 298-299
- lpr, 299-301
 - bugs, 301
 - diagnostics, 301
 - environment, 300
 - options, 299-300
- lprm, 301-302
 - bugs, 302
 - diagnostics, 302
 - environment, 302
 - options, 301
- lpptest, 302
- lrand48() functions, 912
- ls, 303-304
- ls (ftp command), 149
- lsattr, 304-305
- lsearch() function, 975-976
- lseek, 793-794
- lsmmod, 305
- lstat, 863-864
- lynx, 306-309
 - commands, 308-309
 - options, 306-308

M

- macdef (ftp command), 149
- Macintosh PICT files, converting to portable pixmaps, 379-380
- MacPaint files, converting to portable bitmaps, 309-310
- macptopbm, 309-310
- magic cookies, generating, 317
- mail addressing, 1244-1246
 - abbreviations, 1245
 - case sensitivity, 1245
 - compatibility, 1245
 - postmasters, 1246
 - routing, 1245
- mail, *see* e-mail
- MAIL variable (bash), 16
- MAIL_WARNING variable (bash), 16
- mailaddr, 1244-1246
 - abbreviations, 1245
 - bugs, 1246
 - case sensitivity, 1245
 - compatibility, 1245
 - postmasters, 1246
 - routing, 1245
- MAILCHECK variable (bash), 16
- MAILER environment variable, 529
- MAILPATH variable (bash), 16
- make, 310-312
 - imake preprocessor, 264-267
 - options, 311
- makeactive, 1342-1344
- makedepend, 312-314
 - algorithm, 313
 - bugs, 314
 - options, 312-313
- MAKEDEV, 1320-1324
 - files, 1321
 - options, 1321-1324
- MAKEDEV.cfg, 1151
- makefiles
 - creating dependencies in, 312-314
 - creating from Imakefiles, 672
- makehistory, 1342-1344
- makestrs, 314-315
 - bugs, 315
 - directives, 315
 - options, 314
 - syntax, 314-315
- malloc() function, 976
- man, 1246-1248
- man pages, formatting, 1246-1248
 - fonts, 1247
 - macros, 1248
 - preamble, 1246-1247
 - sections, 1247-1248
- mapping files to memory, 799-800
- mark-modified-lines variable (readline), 28
- mask bitmaps, creating from regular, 353-354
- masks, file-creation, 880
 - setting, 45
- mattrib, 315-316, 330
- mbadblocks, 316, 330
- mblen, 977
- mbstowcs() function, 977-978
- mbtowc() function, 978
- mcd, 316-317, 330
- mcookie, 317
- mcoppy, 317-318, 330
- MD5 message digests, generating/checking, 318
- md5sum, 318
- mdel, 318-319, 330
- mdelete (ftp command), 149
- mdeltree, 319
- mdir, 150, 319, 330
- mem, 1091-1092
- memccpy() function, 901, 978-979
- memchr() function, 901, 979

■ *memcmp() function*

- memcmp() function*, 901, 979-980
- memcpy() function*, 901, 980
- memfrob() function*, 901, 980-981
- memmem() function*, 901, 981
- memmove() function*, 901, 981
- memory*
 - access, controlling, 804-805
 - allocating, 894, 976
 - displaying amount, 144
 - freeing, 976
 - kernel, 1091-1092
 - locking
 - mlock*, 796-797
 - mlockall*, 797-798
 - mapping/unmapping files to, 799-800
 - reallocating, 976
 - scanning for characters, 979
 - shared
 - allocating, 851-853
 - controlling, 849-851
 - operations, 853-854
 - system, 1091-1092
 - unlocking
 - munlock*, 811-812
 - munlockall*, 812-813
 - virtual
 - remapping addresses, 805-806
 - reports, 1417-1418
 - virtual console, 1101-1102
- memory areas*
 - comparing, 979-980
 - copying, 978-981
 - encrypting, 980-981
 - filling with constant bytes, 982
 - locating substrings in, 981
- memset() function*, 901, 982
- merge*, 320
- merge command (xauth)*, 591
- merging files, three-way*, 320
- mesg*, 321
- message catalogs*
 - getting messages from, 902-903
 - opening/closing, 903-904
- message queue identifier*, retrieving, 807-808
- messages*
 - control, 1310
 - control operations, 806-807
 - displaying, 321
 - log (RCS files), printing, 458-460
 - message of the day file, 1152
 - receiving, from sockets, 826-828
 - sending/receiving, 808-811
 - sending
 - from sockets, 842-843
 - to system logger, 1045-1046
 - to users, 473, 576-577
 - signal, printing, 996
 - system console, monitoring with X, 597-598
 - system error, printing, 990-991
 - systems, logging, 1404-1405
 - Usenet control, handling, 1115-1116
 - writing to users, 574, 1383
- meta characters (bash)*, 12
- meta-flag variable (readline)*, 28
- mformat*, 321-322, 330
 - bugs, 322
 - options, 321-322
- mget (ftp command)*, 150
- MGR bitmaps, converting to portable bitmaps*, 322-323
- mgrtopbm*, 322-323
- MINIX filesystems*, 1125
 - consistency checker, 1300-1301
 - creating, 1326-1327
- mkdir*, 150, 323, 794-795
 - bugs, 795
 - errors, 795
 - options, 323
 - return value, 795
- mkdirhier*, 323
- mke2fs*, 1324-1325
- mkfifo*, 323-324, 982-983
 - errors, 982-983
 - options, 324
- mkfs*, 1325-1327
- mklost+found*, 1327
- mkmanifest*, 324-325
- mknod*, 325, 795-796
 - bugs, 796
 - errors, 796
 - options, 325
 - return value, 796
- mkstemp() function*, 983
- mkswap*, 1327-1328
- mktemp() function*, 983-984
- mktime*, 910, 984-986
- mlabel*, 325-326, 330
- mlock*, 796-797
- mlockall*, 797-798
- mls (ftp command)*, 150
- mmap*, 799-800
- mmd*, 326, 330
- mmount*, 326-327, 330
- mmove*, 327, 330
- /mnt directory*, 1236
- mode (ftp command)*, 150
- mode command (telnet)*, 508
- mode parameter, values*, 1374
- modems, conversational exchanges*, 1269-1273
 - abort strings, 1270-1271
 - chat script, 1270
 - escape sequences, 1271-1272
 - report strings, 1271
 - termination codes, 1272
 - time-out value, 1271
- moderators*, 1151-1152
- modf() function*, 984
- modify_ldt*, 800
- modprobe*, 109-112
 - configuration, 110-111
 - files, 111
 - strategy, 111

- modtime (ftp command), 150
- modules
 - kernel, loading at boot time, 1152
 - loadable
 - support*, 800-802
 - unloading*, 462-463
 - viewing*, 305
- more, 327-328
- motd, 1152
- mount, 802-804, 1328-1332
 - bugs, 1332
 - errors, 803
 - files, 1332
 - options, 1329-1331
 - return value, 803
- mountd, 1332-1333
- mounting MS-DOS disks, 326-327
- mouse, 1092-1094
 - Microsoft protocol, 1093
 - MM protocol, 1094
 - MouseSystems protocol, 1093
 - Sun protocol, 1093
- mprotect, 804-805
- mput (ftp command), 150
- mrnd48() functions, 912
- mrdr, 329-330
- mread, 329
- mremap, 805-806
- mren, 329-330
- MS-DOS
 - directories
 - changing*, 316-317
 - displaying*, 319
 - trees, deleting*, 319
 - disks, mounting, 326-327
 - files
 - changing attribute flags*, 315-316
 - copying to/from UNIX*, 317-318, 329
 - deleting*, 318-319
 - displaying contents*, 333-334
 - manipulating (mtools)*, 330-333
 - moving*, 327
 - renaming*, 329-330
 - filesystems, adding to disks, 321-322
 - floppies, marking bad blocks, 316
 - subdirectories
 - creating*, 326
 - moving*, 327
 - removing*, 329
 - renaming*, 329-330
 - volume labels, creating, 325-326
- msdos filesystem, 1125
- msgctl, 806-807
- msgget, 807-808
- msgop, 808-811
- msync, 811
- mtest, 330
- mttools, 330-333, 1152-1158
 - bugs, 333
 - case sensitivity of VFAT, 332
 - character translation tables, 1155-1157
 - configuration files, testing, 330
 - default values, 1153
 - drive geometry
 - configuration, 1154-1155
 - exit codes, 333
 - general purpose drive variables, 1153-1154
 - global variables, 1153
 - long filenames, 331
 - mattrib, 330
 - mbadblocks, 330
 - mcd, 330
 - mcop, 330
 - mdel, 330
 - mdir, 330
 - mformat, 330
 - mlabel, 330
 - mmd, 330
 - mmount, 330
 - mmove, 330
 - mrdr, 330
- mren, 330
- mtest, 330
- mtype, 330
- multiple descriptions, 1155
- name clashes, 332
- open flags, 1155
- parsing order of files, 1157-1158
- per-drive flags/variables, 1153
- working directory, 331
- Xdf disks, 332
- MTV ray tracers, converting output to portable pixmaps, 333
- mtvtppm, 333
- mtype, 330, 333-334
- multilanguage support (description), 1243-1244
- multibyte characters, converting to wide characters, 978
- multibyte strings, converting to wide character, 977-978
- multiple buffers, reading/writing data, 1003-1004
- multiuser chat program, 727-730
 - Boolean options, 729
 - daemons, 727
 - escape menu, 728
 - readdressing, 729
 - runtime options, 728-729
 - startup file, 729
 - username field, 727
 - X11 interface, 730
- munchlist, 274, 279
 - bugs, 282
 - files, 281
 - options, 279-280
 - see also* ispell
- munlock, 811-812
- munlockall, 812-813
- munmap, 799-800
- mv, 334-335
- mwrite, 335
- mysnc, 811

N

- named, 1334-1338
 - boot file, 1334-1336
 - files, 1337
 - master file, 1336
 - options, 1334
 - signals, 1337
 - SOA record, 1336-1337
- named pipes, *see* FIFOs
- named-xfer, 1333-1334
- named.reload, 1338
- named.restart, 1338
- namei, 335-336
 - options, 336
 - output, 335
- names
 - bash, 12
 - peer, getting, 765
 - socket, getting, 769
- nameserver (Internet domains), 1334-1338
 - boot file, 1334-1336
 - control interface, 1338-1339
 - master file, 1336
 - querying, 1350-1353
 - signals, 1337
 - SOA record, 1336-1337
 - stopping/restarting, 1338
 - synchronizing database, 1338
- naming
 - font servers, 643
 - temporary files, 1049, 1054
 - xhost, 644
- NaN (not-a-number) results
 - returning value for, 954-955
 - testing for, 959
- nanosleep, 813-814
- ncpfs filesystem, 1126
- ndc, 1338-1339
- Netnews reader, *see* tin
- .netrc file, 153-154
- netstat, 1339-1342
 - files, 1341
 - routing information, 1341
 - socket information, 1340-1341
- network byte order, converting between host byte order, 901-902
- network entries, getting, 936-937
- networking
 - displaying active connections, 1339-1342
 - routing information, 1341
 - socket information, 1340-1341
 - interfaces
 - attaching to serial line, 1399
 - configuring, 1304-1305
 - routing daemon, 1380-1382
- newaliases, 336
- newer (ftp command), 150
- newgrp, 336-337
- news
 - Netnews, *see* tin
 - news software information
 - newsgroups, 530
 - overview database
 - expiring entries, 1293-1294
 - format, 1168-1169
 - updating, 1353-1354
 - receiving from UUCP connections, 463-464
- news.daily, 1344-1346
 - keywords, 1344-1345
- newsfeeds, 1158-1163
 - Distribution headers, 1159
 - entries, 1158-1159
 - examples, 1162-1163
 - feed types, 1161-1162
 - flags, 1159-1161
 - ME entry, 1161
- newsgroups
 - news software information, 530
 - Usenet, listing active, 1104-1105
- newslog, 1163-1165, 1346-1347
 - files, 1164
 - keywords, 1346
 - message/action fields, 1163-1164
- newsqueue, 1342-1344
- NFS
 - mount daemon, 1332-1333
 - servers, authentication/print request, 1355-1357
 - service daemon, 1347
- nfs, 1165-1167
- nfs filesystem, 1125
 - export list, 1123-1125
- NFS servers, mount information, 1396
- nfsd, 1347
- nice, 814
- nl, 337-338
- nlist (ftp command), 150
- NLM outfiles, converting object code into, 338-339
- nlmconv, 338-339
- nm, 339-340
- nmap (ftp command), 150
- nnrp.access, 1167-1168
- nnrpd, 1347-1349
- NNTP
 - news, host list, 1132-1133
 - servers, 1347-1349
 - getting lists from, 206-207
 - passwords, 1170
 - retrieving Usenet articles from, 340-341
 - sites, access control, 1167-1168
- NNTPcheckarticle routine, 965
- NNTPconnect routine, 965
- nttpget, 340-341
- NNTPlocalopen routine, 965
- NNTPremoteopen routine, 965
- nttpsend, 1349-1350
- nttpsendctl, 1168
- NNTPsendarticle routine, 966
- NNTPsendpassword routine, 966
- NNTPSERVER environment variable, 529

no_exit_on_failed_exec
variable (bash), 18

noclobber variable (bash), 18

nolinks variable (bash), 18

nologin, 1168

none, 881

none (undocumented library
functions), 1060

not-a-number (NaN) results
returning value for, 954-955
testing for, 959

notify variable (bash), 17

nrnd48() functions, 912

nrff
emulating, 210-211
output, filtering, 77

nslookup, 1350-1353
arguments, 1350
commands, 1351-1353
diagnostics, 1353
environment, 1353
files, 1353

ntohl() function, 901-902

ntohs() function, 901-902

ntrans (ftp command),
150-151

null, 1094

numbers
floating-point
absolute value, 919
converting to fractional/
integral components,
927
converting to strings,
913-914, 930-931

pseudo-random, generating,
912-913

random, generating,
1001-1002

rounding, 1011-1012

signs, copying, 907

square roots, 1023

numeric expressions, gtroff,
239

O

objcopy, 341-342

objdump, 342-343

object files
copying/translating,
341-342
discarding symbols from,
499
displaying information from,
342-343
listing section and total sizes,
489-490
listing symbols from,
339-340

oclock, 344

od, 345-346

offline printing, 299-301

oldfstat, 814

oldlstat, 814

oldolduname, 814

OLDPWD variable (bash), 15

oldstat, 814

olduname, 814

on_exit() function, 988

open, 815-816
bugs, 816
errors, 816
flags, 815
ftp command, 151
modes, 815
return value, 816

open host command (telnet),
508

opendir, 989

openlog() function,
1045-1046
facility argument, 1046
option argument, 1046

operators
awk, 166-167
find, 142
redirection, 21

OPTARG variable (bash), 16

OPTERR variable (bash), 17

OPTIND variable (bash), 16

ORGANIZATION environ-
ment variable, 529

OSTYPE variable (bash), 16

outb, 816

outb_p, 816

outl, 816

outl_p, 816

output
formatting, 992-996,
1022-1023
conversion specifiers, 994
examples, 995
flags, 993-994
redirecting, 22

output-meta variable
(readline), 28

outsb, 816

outsl, 816

outsw, 816

outw, 816

outw_p, 816

overchan, 1353-1354

overview.fmt, 1168-1169

ownership (file), changing,
62-63, 749-750

P

pac, 1354-1355

packed format fonts, convert-
ing to portable bitmaps, 381

packets
ECHO_REQUEST,
sending, 1358
route, printing, 1409-1412

page size, system (getting),
765

paging
disabling, 796-797
calling process, 797-798
reenabling, 811-813

papers, formatting
groff_me macros,
1225-1227
groff_mm macros,
1227-1234
groff_ms macros,
1234-1236

- paragraphs, formatting line length, 143
- parameter command substitution (bash), 20
- parameter expansion (bash), 19-20
- parameters
 - bash, 14-15
 - positional*, 14
 - special*, 14-15
 - boot-time (kernel), 1216-1224
 - Adaptec configurations*, 1219-1220
 - argument list*, 1216-1217
 - BusLogic configuration*, 1220
 - busmouse drivers*, 1224
 - cards not accepting*, 1220
 - CD-ROMs*, 1222-1223
 - debug argument*, 1217
 - Ethernet devices*, 1223
 - floppy disk drives*, 1223-1224
 - future domain configuration*, 1220
 - hard disks*, 1220-1221
 - mem= argument*, 1218
 - no-hlt argument*, 1217
 - no387 argument*, 1217
 - Pro Audio configuration*, 1220
 - ramdisk= argument*, 1218
 - reboot=warm argument*, 1218
 - reserve= argument*, 1217-1218
 - ro argument*, 1217
 - root= argument*, 1217
 - rw argument*, 1217
 - SCSI device arguments*, 1218-1219
 - SCSI tape configuration*, 1219
 - Seagate ST-0x configuration*, 1220
 - sound drivers*, 1224
 - Trantor T128 configuration*, 1220
 - floppy disk, setting, 1391
 - positional
 - parsing*, 38
 - renaming*, 42
 - serial ports, 1392-1394
- parsedate, 989-990
- parser directives, readline, 28-29
 - \$else, 29
 - \$endif, 29
 - \$if, 28-29
- parsing
 - command options, 207-208
 - command-line options, 937-940
 - positional parameters, 38
- partition tables, manipulating, 1296-1297
 - DOS 6.x, 1296-1297
- partitioning disk drives, 1265-1269
- passwd, 346-347, 1169-1170
 - bugs, 347
 - files, 347
- passwd.nntp, 1170
- password files, editing, 1418-1419
- passwords
 - changing, 346-347
 - encryption, 908-909
 - file entries, writing, 997
 - getting, 940-941
 - getting file entry, 943-944
 - password file, 1169-1170
 - reconstructing line entry, 942-943
- paste, 347
- PATH variable (bash), 16
- pathconf() function, 925-926
 - options returned, 926
 - return value, 926
- pathname expansion (bash), 21
- pathnames
 - canonicalized absolute, 1004-1005
 - following to terminal point, 335-336
 - matching, 924, 949-950
- patterns
 - printing lines matching, 224-226
 - searching database files for, 295
- pause, 817
- pausing execution, 813-814
- pbm, 1170-1171
- PBM images, displaying on 4425 terminals, 357
- pbmclean, 348
- pbmfilters, 348-352
- pbmlife, 352-353
- pbmmake, 353
- pbm mask, 353-354
- PBMPlus package, programs, 348-352
- pbmpscale, 354
- pbmreduce, 355
- pbmtext, 355-356
- pbmto10x, 356
- pbmto4425, 357
- pbmtoascii, 357
- pbmtoatk, 358
- pbmtobg, 358
- pbmtocmuwm, 358-359
- pbmtoepsi, 359
- pbmtoepson, 359
- pbmtog3, 360
- pbmtogem, 360
- pbmtogo, 360-361
- pbmtoicon, 361
- pbmtolj, 361-362
- pbmtoln03, 362
- pbmtolps, 362
- pbtomacp, 363
- pbtomgr, 363
- pbtompgm, 364
- pbmtopi3, 364
- pbmtopk, 364-365

- pbmtoplot, 365-366
- pbmtoptx, 366
- pbmtox10bm, 366
- pbmtoxbm, 367
- pbmtoybm, 367
- pbmtozinc, 367-368
- pbmupc, 368
- pclose(), 991-992
- pcnfsd, 1355-1357
 - authentication, 1355-1356
 - file, 1357
 - printing, 1356
 - reconfiguration, 1357
- PCX files, converting to
 - portable pixmaps, 368-369
- pcxtoppm, 368-369
- peers, getting names, 765
- permissions
 - file
 - changing*, 748-749
 - setting*, 272-273
 - port input/output, setting, 788
- perrow, 990-991
- personality, 817-818
- pfbtops, 369
- pgm, 1171-1172
- pgmbentley, 369
- pgmcrater, 370-371
- pgmedge, 371
- pgmenhance, 371-372
- pgmhist, 372
- pgmkernel, 372-373
- pgmnoise, 373
- pgmnorm, 373-374
- pgmoil, 374
- pgmramp, 374-375
- pgmtexture, 375-376
- pgmtofs, 376
- pgmtolisp, 376-377
- pgmtoptbm, 377
- pgmtoppm, 378
- Photo-CD files, converting to
 - portable pixmaps, 260-261
- phys, 818
- physical addresses, accessing, 818
- pi3topbm, 379
- pic, versus gpic, 212-215
 - commands, 212-213
 - expressions, 213-214
 - mode, 212
- picttoppm, 379-380
 - bugs, 379
 - fontdir file format, 380
- ping, 1358
- pipe, 818-819
- pipelines (|), bash, 12
- pipes, creating, 818-819
- pjtoppm, 381
- pktopbm, 381
- PLIP devices, tuning
 - parameters, 1357
- plipconfig, 1357
- pnm, 1173
- pnmalias, 381-382
- pnmarith, 382-383
- pnmcats, 383
- pnmcomp, 383-384
- pnmconvol, 384
- pnmcrop, 385
- pnmcut, 385
- pnmdepth, 385-386
- pnmenlarge, 386
- pnmfile, 386-387
- pnmflip, 387
- pnmgamma, 387
- pnmhistmap, 388
- pnminindex, 388-389
- pnminvert, 389
- pnmmargin, 389-390
- pnmnlfilt, 390-391
 - alpha-trimmed mean filter, 390
 - bugs, 391
 - combining modes, 391
 - edge enhancement, 391
 - optimal estimation smoothing, 390
- pnmnoraw, 391-392
- pnmpad, 392
- pnmpaste, 392-393
- pnmrotate, 393
- pnmscale, 393-394
- pnmshear, 394-395
- pnmsmooth, 395
- pnmtile, 395
- pnmtodiff, 396
- pnmtofits, 396-397
- pnmtioff, 399-400
- pnmtops, 397
- pnmtorast, 398
- pnmtosgi, 398-399
- pnmtosir, 399
- pnmtowd, 400
- popd (shell command), 39-40
- popen() function, 991-992
- popup-menu() action (xterm), 713
- port, 1091-1092
- portable anymaps
 - antialiasing, 381-382
 - bordering, 389-392
 - changing maxval, 385-386
 - compositing, 383-384
 - concatenating, 383
 - converting
 - to DDIF format*, 396
 - to FITS format*, 396-397
 - to PostScript*, 397
 - to red/blue 3D glasses*, 400-401
 - to SGI image file*, 398-399
 - to Solitaire format*, 399
 - to Sun raster files*, 398
 - to TIFF files*, 399, 400
 - to X11 window dumps*, 400
 - convolving, 384
 - creating index of, 388, 389
 - cropping, 385
 - cutting rectangles from, 385
 - describing, 386, 387
 - drawing histograms from, 388
 - enlarging, 386
 - file format, 1173
 - flipping, 387
 - gamma correction, 387

- inverting, 389
- pasting rectangles into, 392, 393
- performing arithmetic on, 382, 383
- plain format, 391, 392
- programs
 - constants*, 970
 - format promotion*, 972
 - functions supporting*, 970, 971, 972
 - initialization*, 971
 - memory management*, 971
 - reading files*, 971
 - types*, 970
 - writing files*, 971, 972
 - XEL manipulations*, 971-972
- replicating into specified size, 395
- rotating, 393
- scaling, 393, 394
- shearing, 394, 395
- smoothing, 395
- portable bitmaps
 - applying Rules of Life to, 352, 353
 - converting
 - to Andrew Toolkit raster objects*, 358
 - to ASCII graphics*, 357
 - to Atari Degas PI3 files*, 364
 - to Bennet Yee "face" files*, 367
 - to BitGraph graphics*, 358
 - to CMU window manager bitmaps*, 358-359
 - to compressed GraphOn graphics*, 360-361
 - to DEC LN03+ Sixel output*, 362
 - to encapsulated PostScript-style bitmaps*, 359
 - to Epson printer graphics*, 359
 - to GEM IMG files*, 360
 - to Gemini 10x graphics*, 356
 - to Group 3 fax files*, 360
 - to HP LaserJet format*, 361-362
 - to MacPaint files*, 363
 - to MGR bitmap*, 363
 - to packed format fonts*, 364-365
 - to portable graymaps*, 364
 - to PostScript*, 362
 - to Printronix printer graphics*, 366
 - to Sun icons*, 361
 - to UNIX plot files*, 365-366
 - to X10 bitmaps*, 366
 - to X11 bitmaps*, 367
 - to Zinc bitmaps*, 367-368
 - creating with specified size, 353
 - enlarging, 354
 - file format, 1170-1171
 - flipping pixels in, 348
 - programs
 - constants*, 968
 - endian i/o*, 967
 - errors*, 967
 - file management*, 967
 - functions supporting*, 966-969
 - initialization*, 968
 - keyword matching*, 967
 - memory management*, 968
 - messages*, 967
 - reading files*, 968
 - types*, 968
 - writing files*, 968-969
 - reducing, 355
- portable graymaps
 - Bentleyizing, 369
 - calculating textural features on, 375-376
 - combining three into a portable pixmap, 457-458
 - converting
 - to Lisp machine format*, 376-377
 - to portable bitmaps*, 377
 - to portable pixmaps*, 378
 - to Usenix FaceSaver format*, 376
 - creating from white noise, 373
 - enhancing edges, 371-372
 - file format, 1171-1172
 - mimicking cratered terrain, 370-371
 - normalizing contrast, 373-374
 - outlining edges, 371
 - performing oil transfers on, 374
 - printing histogram of values, 372
 - programs
 - constants*, 969
 - functions supporting*, 969-970
 - initialization*, 969
 - memory management*, 969
 - reading files*, 970
 - types*, 969
 - writing files*, 970
- portable pixmaps
 - blending together, 408-409
 - brightening, 404
 - changing pixel color, 401-402
 - changing saturation and value, 401
 - converting
 - to Abekas YUV files*, 428
 - to Atari Degas PI1 files*, 422
 - to AutoCAD*, 414-416
 - to BMP files*, 416
 - to DEC sixel format*, 425-426
 - to GIF files*, 416-417
 - to HP PaintJet files*, 423

- to HP PaintJet XL PCL files, 424
- to ILBM files, 418-419
- to Macintosh PICT files, 422-423
- to Mitsubishi S340-10 files, 420-421
- to MotifUIL icon files, 427
- to NCSA ICR format, 417-418
- to PCX files, 421
- to portable graymaps, 421-422
- to three portable graymaps, 425
- to three raw YUV files, 428-429
- to TrueVision Targa files, 426
- to X11 pixmaps, 427-428
- to X11 puzzle files, 424-425
- creating, 408
 - patterns, 410-411
 - specifying color, 408
- creating from three portable graymaps, 457-458
- dimming
 - to black, 402
 - every other row, 409-410
- displacing pixels, 414
- dithering, 403
- extracting color from, 419-420
- file format, 1173-1174
- files
 - reading, 974
 - writing, 974
- fractal forgeries, 404-407
- grayscale assignments (performing), 402-403
- histograms (printing), 408
- Laplacian relief filters (running on), 413
- normalizing contrast, 409
- programs, functions
 - supporting, 973-974
- quantizing colors, 411
 - 8-plane quantization, 412-413
 - multiple files, 412
 - shifting lines, 413-414
- portmap, 1358-1359
- ports
 - input/output functions, 816
 - input/output permissions, setting, 788
 - serial
 - configuring, 1394-1395
 - parameters, 1392-1394
 - setting/getting information, 1391-1395
 - system, 1091-1092
- positional parameters
 - bash, 14
 - parsing, 38
 - renaming, 42
- POSIX
 - gawk compatibility, 171
 - regex functions, 1005-1007
 - compiling, 1005-1006
 - error reporting, 1006
 - matching, 1006
 - pattern buffer freeing, 1007
 - signal set operations, 1019-1020
- PostScript
 - bounding box, extracting, 433
 - files, converting to portable
 - anymaps, 434-435
 - fonts
 - translating from PFB format to ASCII, 369
 - translating from PFB format to ASCII, 369
 - image data, converting into
 - portable graymap, 433-434
- pound sign (#)
 - bash comments, 14
 - bash special parameters, 15
- pow() function, 918
- powerd, 1359-1360
- powers (raising numbers to), 918
- PPID variable (bash), 15
- ppm, 1173-1174
- ppm3d, 400-401
- ppmbrighten, 401
- ppmchange, 401-402
- ppmdim, 402
- ppmdist, 402-403
- ppmdither, 403
- ppmflash, 404
- ppmforge, 404-407
 - bugs, 407
 - options, 405-407
- ppmhist, 408
- ppmmake, 408
- ppmmix, 408-409
- ppmnorm, 409
- ppmntsc, 409-410
- ppmpat, 410-411
- ppmquant, 411-412
- ppmquantall, 412
- ppmqvga, 412-413
- ppmrelief, 413
- ppmshift, 413-414
- ppmspread, 414
- ppmtoacad, 414-416
- ppmtobmp, 416
- ppmtogif, 416-417
- ppmtoicr, 417-418
- ppmtoilbm, 418-419
- ppmtomap, 419-420
- ppmtomitsu, 420-421
- ppmtopcx, 421
- ppmtopgm, 421-422
- ppmtopi1, 422
- ppmtopict, 422-423
- ppmtopj, 423
- ppmtopjxl, 424
- ppmtopuzz, 424-425
- ppmtorgb3, 425
- ppmtosixel, 425-426
- ppmtotga, 426
- ppmtouil, 427
- ppmtoxpm, 427-428

- ppmtoyuv, 428
- ppmtoyvsplit, 428-429
- PPP
 - daemon, 1360-1369
 - statistics, printing, 1369-1370
- pppd, 1360-1369
 - authentication, 1366-1367
 - diagnostics, 1368
 - examples, 1367-1368
 - files, 1366-1369
 - options, 1360-1366
 - routing, 1367
 - signals, 1369
- pppstats, 1369-1370
- pr, 429-430
- preprocessor, 81-84
- preprocessors, imake, 264-267
- printf function, 992-996
 - bugs, 995-996
- printf statement, awk, 167-168
- printing
 - aliases, 35
 - application resources, 5
 - banners, 1210
 - converting text files for, 429-430
 - files, in reverse, 503-504
 - histograms of portable pixmaps, 408
 - host IDs, 258-259
 - lines matching a pattern, 224-226
 - log messages (RCS files), 458-460
 - machine architecture, 8
 - offline, 299-301
 - packet route, 1409-1412
 - pcnfsd, 1356
 - PPP statistics, 1369-1370
 - printer/plotter accounting files (reading), 1354-1355
 - removing jobs from queue, 301-302
 - ripple test pattern, 302
 - signal messages, 996
 - spool queue examination, 298-299
 - system activity summary, 573
 - system error messages, 990-991
 - time zones, 1419
 - user/system times, 43
 - see also* line printer
- priority values, getting range, 830-831
- privileges
 - I/O, changing level, 788-789
 - setuid (RCS files), 67-68
- /proc, 1174-1180, 1236
 - bugs, 1180
 - hierarchy outline, 1174-1180
- proc filesystem, 1125
- proc_sel, 1430-1431
- process control, initialization, 1307-1309, 1397-1399
- process groups, sending signals to, 790-791, 960
- process substitution (bash), 20
- processes
 - 0, making idle, 774
 - accounting, switching on/off, 742
 - child, creating, 751, 758
 - closing, pclose() function, 991-992
 - displaying tree of, 435-436
 - execution, suspending, 1061
 - execution domain, setting, 817-818
 - group identity, setting, 845
 - group IDs
 - getting/setting, 845-846
 - real and effective (setting)*, 846-847
 - groups
 - access lists (*getting/setting*), 761-762
 - IDs (*getting*), 761
 - identifying, 154-155
 - IDs, getting, 766
 - listing most CPU-intensive, 533-535
 - opening, popen() function, 991-992
 - parents, IDs (*getting*), 766
 - priorities, altering, 1375-1376
 - priority, changing, 814
 - reporting status, 430-433
 - SCHED_RR interval, getting, 831
 - scheduling priorities, getting/setting, 766-767
 - selecting, by criteria, 1430-1431
 - sending signals to, 790
 - raise function*, 1000
 - starting, on consoles, 1066
 - terminating, 283-284, 739-740
 - by name*, 284
 - times, getting, 878-879
 - tracing, 820
 - user IDs
 - getting, 773
 - real and effective (setting)*, 847-848
 - setting, 848-849
 - waiting for termination, 886-889
 - yielding processor, 835
- processor, time used (determining), 905
- profil, 819
- profiling, 819
- programs
 - executing, 754-755
 - portable anymap
 - constants, 970
 - format promotion, 972
 - functions supporting, 970-972
 - initialization, 971
 - memory management, 971
 - reading files, 971

- types*, 970
- writing files*, 971-972
- XEL manipulations*, 971-972
- portable bitmap, functions supporting, 966-969
- portable graymap
 - constants*, 969
 - functions supporting*, 969-970
 - initialization*, 969
 - memory management*, 969
 - reading files*, 970
 - types*, 969
 - writing files*, 970
- recompiling, make utility, 310-312
- running, in new session, 1395
- terminating
 - abort() function*, 892
 - assert() function*, 895-896
 - exit() function*, 917
- promoting directories, 39-40
- prompt (ftp command), 151
- PROMPT_COMMAND variable (bash), 17
- prompting (bash), 26
- properties, consoles, 1067
- protocols
 - protocols definition file, 1180-1181
 - RPC, rpcgen compiler, 464-466
 - Telnet, interface, 507-512
 - XIE, testing, 645-654
- proxy ftp (ftp command), 151
- proxy servers, LBX, 286-287
- PRT ray tracers, converting output to portable pixmaps, 333
- prunehistory, 1370-1371
- ps, 430-433
 - bugs, 433
 - field descriptions, 432
 - options, 430-431

- sort keys, 431-432
- updating, 432, 436
- PS1 variable (bash), 16
- PS2 variable (bash), 16
- PS3 variable (bash), 17
- PS4 variable (bash), 17
- psbb, 433
- pseudo-file systems, /proc, 1174-1180
 - bugs, 1180
 - hierarchy outline, 1174-1180
- pseudo-random numbers, generating, 912-913
- psidtopgm, 433-434
- pstopnm, 434-435
- pstree, 435-436
- psupdate, 436
- ptrace, 820
- pushd (shell command), 40
- put (ftp command), 151
- put_file_last, 1431
- putc() function, 997-999
- putchar() function, 997-999
- putenv, 996-997
 - errors, 996
- putpwent() function, 997
 - errors, 997
- puts() function, 997-999
- pututline() function, 948
- putw function, 948
- pwd (ftp command), 151
- pwd (shell command), 40
- PWD variable (bash), 15

Q

- qio, 998
- QRT ray tracer, converting output to portable pixmaps, 436-437
- qsort, 1000
- quantizing colors (pixmap), 411
 - 8-plane quantization, 412-413
 - multiple files, 412

- question marks (?)
 - bash special parameters, 15
 - ftp command, 152
- queues, inserting/removing items, 957
- quit command
 - ftp command, 151
 - telnet, 508
 - xauth, 591
- quit() action (xterm), 714
- quota, 437
- quotacheck, 1371-1372
- quotactl, 821-822
- quotaoff, 1372-1373
- quotaon, 1372-1373
- quotas
 - disk, manipulating, 821-822
 - remote machines, 1012
- quote (ftp command), 151
- quoting (bash), 14

R

- Radix32 routine, 966
- raise function, 1000
- ram, 1094-1095
- rand() function, 1001
- random numbers, generating, 1001-1002
- RANDOM variable (bash), 15
- random() function, 1001-1002
- randomizing strings, 1032
- ranlib, 437-438
- rarp, 1373
- RARP table, manipulating, 1373
- rasttopnm, 438
- raw grayscale bytes, converting to portable graymaps, 439
- raw RGB bytes, converting to portable pixmaps, 439-440
- rawtopgm, 439
- rawtoppm, 439-440

- ray tracers
 - converting output to portable pixmaps, 333
 - QRT, converting output to portable pixmaps, 436-437
- rcp, 440-441
- RCS (Revision Control System), 447-449
 - automatic identification, 449
 - commands, 447-449
 - directories, creating, 447-449
 - files
 - changing attributes*, 441-443
 - cleaning*, 443-445
 - comparing revisions*, 445-446
 - freezing configuration*, 446-447
 - functions, 447
 - revisions, merging, 449-451
- rcs, 441-443
 - bugs, 443
 - compatibility, 443
 - diagnostics, 443
 - environment, 443
 - files, 443
 - options, 441-443
- RCS files
 - controlling access, 67
 - format, 1181-1183
 - modes, 67
 - organization (diagram), 1182
 - printing log messages, 458-460
 - retrieving revisions, 71-75
 - specifying, 66-67
 - storing revisions, 64-69
 - setuid privileges*, 67-68
 - temporary files, 67
- RCS keyword strings, identifying, 262-263
- RCSBIN environment variable, 105
- rcsclean, 443-445
- rcsdiff, 445-446
- rcsfile, 1181-1183
 - organization (diagram), 1182
- rcsfreeze, 446-447
- rcsintro, 447-449
 - automatic identification, 449
 - RCS functions, 447
- rcsmmerge, 449-451
- rdev, 1373-1375
- rdiff (cvs command), 101
- rdist, 451-454
 - bugs, 454
 - diagnostics, 454
 - files, 453
 - options, 451-452
- re_comp function, 1005
- re_exec function, 1005
- read (shell command), 40
- read(), file descriptors, 822
- readdir, 823
- readdir() calls, setting position, 1015-1016
- readdir() function, 1002-1003
- ReadInDescriptor routine, 966
- ReadInFile routine, 966
- readline library, 27-32
 - commands, 29-32
 - controlling key bindings, 27
 - customizing, 27
 - denoting keystrokes, 27
 - macro definitions, 28
 - parser directives, 28-29
 - \$else*, 29
 - \$endif*, 29
 - \$if*, 28-29
 - variables, 28
 - bell-style*, 28
 - comment-begin*, 28
 - completion-query-items*, 28
 - convert-meta*, 28
 - editing-mode*, 28
 - expand-tilde*, 28
 - horizontal-scroll-mode*, 28
 - keymap*, 28
 - mark-modified-lines*, 28
 - meta-flag*, 28
 - output-meta*, 28
 - show-all-if-ambiguous*, 28
- readlink, 823-824
- readonly (shell command), 40
- readv, 824-825
- readv() function, 1003-1004
- realloc() function, 976-977
- realpath, 1004-1005
- reboot, 825-826
- recompiling programs, make utility, 310-312
- recompressing Z files, 734-735
- reconfig, 454
- recv, 151, 826-828
- recvfrom, 826-828
- recvmsg, 826-828
- redirection, 21-23
 - duplicating file descriptors, 23
 - here-documents, 22-23
 - input, 22
 - opening file descriptors, 23
 - operators, 21
 - output, 22
- redraw() action (xterm), 714
- ref, 455-456
 - elvis interaction, 455
 - environment, 455
 - files, 455
 - options, 455
 - search method, 455
- refreshing screen (X), 684-685
- refs files, generating, 87-88
- regcomp function, 1005-1007
- regerror function, 1005-1007
- reget (ftp command), 151
- regex functions, 1005
 - POSIX, 1005-1007
 - compiling*, 1005-1006
 - error reporting*, 1006
 - matching*, 1006
 - pattern buffer freeing*, 1007

- regexec function, 1005-1007
- regfree function, 1005-1007
- regular expressions
 - grep, 225-226
 - sed, 476-477
- release (cvs command), 101
- remote execution server, 1376-1377
- remote file copying, 440-441
- remote logging, 1403
- remote login server, 1377-1378
- remote logins, 460-461
 - Kerberos authentication, 461
- remote machines, starting X programs on, 676
- remote quota server, 1384
- remote shell, 466-467
- remote shell server, 1385-1386
- Remote Start client, *see* **rstart**
- Remote Start rsh helper, *see* **rstartd**
- remote status, displaying, 472
- remote systems, command execution, 569-571
- remote user communication server, 1405-1406
- remotehelp (ftp command), 151
- remotestatus (ftp command), 151
- remove, 1008
 - cvs command, 101-102
 - xauth command, 591
- remove_file_free, 1431-1432
- remque() function, 957
- rename, 828-829
- rename (ftp command), 151
- renice, 1375-1376
- REPLY variable (bash), 15
- REPLYTO environment variable, 529
- repquota, 1376
- res_init, 1008-1011
- res_mkquery, 1008-1011
- res_query, 1008-1011
- res_search, 1008-1011
- res_send, 1008-1011
- reserved words (bash), 12
- reset, 456, 539-542
 - compatibility, 542
 - options, 540
 - setting environment, 540
 - terminal type mapping, 540-541
- reset (ftp command), 151
- resize, 456-457
- resolver, 1183-1184
- resolver routines, 1008-1011
- resolving hostnames, 1238-1239
- resource editor, *see* **editres**
- resources
 - limits, getting/setting, 767-768
 - usage, getting, 767-768
- restart (ftp command), 151
- return (shell command), 40
- return value, errors, 797
- rev, 457
- reverse line feeds, filtering, 76
- Revision Control System, *see* **RCS**
- rewind function, 927-928
- rewinddir() function, 1011
- rexecd, 1376-1377
 - bugs, 1377
 - diagnostics, 1377
 - protocol, 1376-1377
- RGB colorname databases, uncompiling, 488
- rgb3toppm, 457-458
- rindex() function, 953
- rint() function, 1011-1012
- ripple test pattern (printing), 302
- rlog, 458-460
- rlogin, 460-461
- rlogind, 1377-1378
- rm, 461-462
- rmdir, 462, 829-830
 - bugs, 830
 - errors, 829
 - options, 462
- rmdir (ftp command), 152
- rmmod, 462-463
- rnews, 463-464
- Rock Ridge filesystem, 1125
- root logins, tty lines (listing), 1184
- root directories
 - changing, 750-751, 1273
- root filesystem, mounting, 849
- root window (X), setting parameters, 693-694
- round-robin scheduling, 834
- rounding integers, 904
- rounding numbers, 1011-1012
- route, 1379-1380
- routed, 1380-1382
 - bugs, 1382
 - files, 1382
 - gateways, 1381-1382
 - options, 1381
 - request packets, 1381
 - response packets, 1381
 - starting, 1380
- routines
 - ICCCancel, 956
 - ICCclose, 956
 - ICCcommand, 956
 - ICCGo, 956
 - ICCCopen, 956
 - ICCpause, 956
 - ICCreserve, 956
 - ICCsettimeout, 956
 - libinn library, 962-966
 - CAClose, 964
 - CAListopen, 964
 - CAopen, 964
 - CloseOnExec, 965
 - DDcheck, 965
 - DDend, 965
 - DDstart, 965
 - GetConfigValue, 965

- GetFileConfigValue*, 965
 - GetFQDN*, 965
 - GetModeratorAddress*, 965
 - GetResourceUsage*, 965
 - GetTimeInfo*, 965
 - HeaderFind*, 964
 - INNVersion*, 966
 - LockFile*, 965
 - NNTPcheckarticle*, 965
 - NNTPconnect*, 965
 - NNTPlocalopen*, 965
 - NNTPremoteopen*, 965
 - NNTPsendarticle*, 966
 - NNTPsendpassword*, 966
 - Radix32*, 966
 - ReadInDescriptor*, 966
 - ReadInFile*, 966
 - SetNonBlocking*, 965
 - libpbm*, 966-969
 - constants*, 968
 - endian i/o*, 967
 - errors*, 967
 - file management*, 967
 - initialization*, 968
 - keyword matching*, 967
 - memory management*, 968
 - messages*, 967
 - reading files*, 968
 - types*, 968
 - writing files*, 968-969
 - libpgm*, 969-970
 - constants*, 969
 - initialization*, 969
 - memory management*, 969
 - reading files*, 970
 - types*, 969
 - writing files*, 970
 - libpnm*, 970-972
 - constants*, 970
 - format promotion*, 972
 - initialization*, 971
 - memory management*, 971
 - reading files*, 971
 - types*, 970
 - writing files*, 971-972
 - XEL manipulation*, 972
 - XEL manipulations*, 971
 - routing, pppd, 1367
 - RPC
 - program numbers, converting to DARPA port numbers, 1358-1359
 - protocol compiler, *see* rpcgen
 - services, reporting information, 1383-1384
 - rpc.rquotad, 1384
 - rpc.rusersd, 1382-1383
 - rpc.rwalld, 1383
 - rpcgen, 464-466
 - options, 465-466
 - preprocessor symbols, 465
 - rpcinfo, 1383-1384
 - rquota() protocol, 1012
 - rquotad, 1384
 - rsh, 466-467
 - rshd, 1385-1386
 - rstart, 467-468
 - rstartd, 468-471
 - configuring, 469
 - keywords*, 470
 - installing, 469
 - options, 469
 - rtag (cvs command), 102
 - runique (ftp command), 152
 - rup, 472
 - rusers, 472-473
 - rwall, 473
 - rwho, 474
 - rwhod, 1386-1387
- ## S
-
- saving stack context, 1018
 - /sbin directory, 1237
 - sbrk, 746
 - scandir() function, 1012-1013
 - scanf functions, 1013-1015
 - bugs, 1015
 - conversions, 1014-1015
 - flags, 1014
 - return values, 1015
 - sched_get_priority_max, 830-831
 - sched_get_priority_min, 830-831
 - sched_getparam, 832
 - sched_getscheduler, 833-835
 - errors, 834
 - policies, 833
 - SCHED_FIFO*, 833-834
 - SCHED_OTHER*, 834
 - SCHED_RR*, 834
 - response time, 834
 - sched_rr_get_interval, 831
 - sched_setparam, 832
 - sched_setscheduler, 833-835
 - errors, 834
 - policies, 833
 - SCHED_FIFO*, 833-834
 - SCHED_OTHER*, 834
 - SCHED_RR*, 834
 - response time, 834
 - sched_yield, 835
 - scheduling
 - algorithm, getting/setting, 833-835
 - parameters, getting/setting, 832
 - policies, 833
 - first in - first out*, 833-834
 - round-robin*, 834
 - time-sharing*, 834
 - priorities
 - getting/setting*, 766-767
 - value ranges*, 830-831
 - yielding processor, 835
 - screen, clearing, 70-71
 - screen savers, beforelight, 47-48
 - script, 474-475
 - scripts, chat, 1270
 - scroll-back() action (xterm), 714
 - scroll-forw() action (xterm), 714
 - SCSI drivers
 - disk drives, 1095-1096
 - tape devices, 1096-1100
 - sd, 1095-1096

- searching
 - binary trees, 1056
 - strings, for character sets, 1035-1039
- second extended filesystems
 - creating, 1324-1325
 - lost+found directory, 1327
 - tunable parameters
 - (adjusting), 1412-1413
- SECONDS variable (bash), 15
- secure() action (xterm), 713
- securetty, 1184
- security
 - syslogd, 1403-1404
 - X server, 688-689
 - xterm, 712
- sed, 475-480
 - addresses, 476
 - bugs, 480
 - commands, 478-479
 - grouping*, 478
 - syntax*, 476
 - comments, 477
 - diagnostics, 479-480
 - options, 475
 - regular expressions, 476-477
 - replacement pattern
 - symbols, 477
 - search pattern symbols, 476-477
- seed48() functions, 912
- seekdir() function, 1015-1016
- select, 835-837
- select-cursor-end action (xterm), 714
- select-cursor-start() action (xterm), 714
- select-end() action (xterm), 714
- select-extend() action (xterm), 714
- select-start() action (xterm), 714
- selections, copying into cut buffers, 598-599
- semaphore sets
 - control operations, 837-839
 - GETALL*, 838
 - GETNCNT*, 838
 - GETPID*, 838
 - GETVAL*, 838
 - GETZCNT*, 838
 - IPC_RMID*, 838
 - IPC_SET*, 838
 - IPC_STAT*, 837
 - SETALL*, 838
 - SETVAL*, 838
 - identifiers (getting), 839-840
 - operations, 840-842
- semctl, 837-839
 - errors, 838-839
 - operations, 837-838
 - GETALL*, 838
 - GETNCNT*, 838
 - GETPID*, 838
 - GETVAL*, 838
 - GETZCNT*, 838
 - IPC_RMID*, 838
 - IPC_SET*, 838
 - IPC_STAT*, 837
 - SETALL*, 838
 - SETVAL*, 838
- semget, 839-840
- semop, 840-842
- send, 842-843
 - ftp command, 152
- send arguments command (telnet), 508-509
- send-signal() action (xterm), 714
- sendmail, 1387-1390
 - aliases, 1390
 - exit status codes, 1390
 - files, 1390
 - flags, 1388
 - options, 1389-1390
- sendmsg, 842-843
- sendport (ftp command), 152
- sendto, 842-843
- serial lines
 - monitoring, 1359-1360
 - network interfaces, attaching, 1399-1401
- serial mouse interface, 1092-1094
 - Microsoft protocol, 1093
 - MM protocol, 1094
 - MouseSystems protocol, 1093
 - Sun protocol, 1093
- serial ports
 - configuring, 1394-1395
 - parameters, 1392-1394
 - setting/getting information, 1391-1395
- serial terminal lines, 1101
- servers
 - biff, 1274-1275
 - controlling with xdm, 612-613
 - DARPA FTP, 1301-1304
 - requests supported*, 1302-1303
 - DARPA Telnet protocol, 1406-1407
 - DARPA TFTP, 1407
 - domain
 - looking up hostnames with*, 257-258
 - resolver routines*, 1008-1011
 - font (X)
 - displaying information about*, 145
 - generating BDF fonts*, 146-147
 - listing fonts*, 145-146
 - interned atoms, listing, 668-669
 - Internet, xinetd (starting with), 655-664
 - Internet domain nameserver, 1334-1338
 - boot file*, 1334-1336
 - control interface*, 1338-1339
 - master file*, 1336
 - querying*, 1350-1353
 - signals*, 1337

- SOA record, 1336-1337
- stopping/restarting, 1338
- synchronizing database, 1338
- Internet superserver, 1305-1307
- LBX proxy server, 286-287
- logged-in users, 1382-1383
- news, sending Usenet articles to, 267-269
- NFS
 - authentication/print request, 1355-1357
 - mount information, 1396
- NNTP, 1347-1349
 - getting lists from, 206-207
 - passwords, 1170
 - retrieving Usenet articles from, 340-341
- portmap, 1358-1359
- remote execution, 1376-1377
- remote login, 1377-1378
- remote quota, 1384
- remote shell, 1385-1386
- remote user communication, 1405-1406
- specifying, xdm, 607-608
- system status, 1386-1387
 - message format, 1386-1387
- X Window System
 - access control program, 643-645
 - display server, 685-690
 - file utility, 587-592
 - font server, 641-643
 - information utility, 614
 - killing clients, 666-667
 - starting, 664-666
 - virtual framebuffer, 717-718
- X11
 - performance comparison program, 585-586
 - performance test program, 577-585
- XF86_8514, 615
- XF86_Accel, 614-623
 - configuration, 615-616
 - files, 622
 - options, 616
 - setup, 616-622
- XF86_AGX, 615
- XF86_Mach32, 615
- XF86_Mach64, 615
- XF86_Mach8, 615
- XF86_Mono, 624-627
 - configuration, 624
 - files, 626
 - setup, 624-626
- XF86_P9000, 615
- XF86_S3, 615
- XF86_SVGA, 627-631
 - configuration, 627-628
 - files, 630-631
 - options, 628
 - setup, 628-630
- XF86_VGA16, 631-633
 - configuration, 631
 - files, 633
 - options, 632
 - setup, 632
- XF86_W32, 615
- XFree86, 636-641
 - configuration, 636
 - environment variables, 637
 - files, 638-639
 - key combinations, 638
 - network connections, 636-637
 - options, 637-638
 - setup, 638
- services, 1184-1186
 - bugs, 1186
 - files, 1186
 - Internet, listing, 1184-1186
 - NFS, daemon, 1347
 - RPC, reporting information, 1383-1384
- Session Manager Proxy, *see* smproxy
- sessions
 - creating, setid, 848
 - IDs, getting, 768
 - typescripts, creating, 474-475
- X Session Manager, 694-698
 - default startup applications, 695
 - options, 695-698
 - proxy, 698
 - remote applications, 698
 - Session menu, 695-696
 - SM_SAVE_DIR
 - environment variable, 695
 - starting, 695
 - tester, 698-699
 - .xsession file, 695
- xdm, 600
- sessreg, 480-481
- set
 - shell command, 40-42
 - telnet command, 509-510
- set-allow132() action (xterm), 715
- set-altscreen() action (xterm), 715
- set-appcursor() action (xterm), 715
- set-appkeypad() action (xterm), 715
- set-autolinefeed() action (xterm), 715
- set-autowrap() action (xterm), 715
- set-cursesemul() action (xterm), 715
- set-jumpscroll() action (xterm), 715
- set-marginbell() action (xterm), 715
- set-reverse-video() action (xterm), 715
- set-reversewrap() action (xterm), 715
- set-scroll-on-key() action (xterm), 715

- set-scroll-on-tty-output()
 - action (xterm), 715
- set-scrollbar() action (xterm), 715
- set-tek-text() action (xterm), 715
- set-terminal-type() action (xterm), 715
- set-visibility() action (xterm), 715
- set-visual-bell() action (xterm), 715
- set-vt-font() action (xterm), 714
- setbuf function, 1016-1017
- setbuffer function, 1016-1017
- setdomainname, 760
- setegid, 846-847
- setenv() function, 1017
- seteuid, 847-848
- setfdprm, 1391
- setfsgid, 843-844
- setfsuid, 844
- setgid, 845
- setgrent() function, 932-933
- setgroups, 761-762
- sethostid, 762-763
- sethostname, 763
- setitimer, 763-764
 - bugs, 764
 - defining values, 764
 - errors, 764
 - return value, 764
 - timer types, 764
- setjmp() function, 1018
- setlinebuf function, 1016-1017
- setlocale() function, 1018-1019
- setmntent() function, 935-936
- SetNonBlocking routine, 965
- setpgid, 845-846
- setpgrp, 845-846
- setpriority, 766-767
- setprotoent() function, 941-942
- setpwent() function, 943
- setregid, 846-847
- setreuid, 847-848
- setrlimit, 767-768
- setserial, 1391-1395
 - configuration considerations, 1394-1395
 - files, 1395
 - options, 1392
 - parameters, 1392-1394
- setservent() function, 946
- setsid, 848, 1395
 - errors, 848
- setsockopt, 769-772
 - bugs, 772
 - errors, 771
 - options recognized, 770-771
 - SO_BROADCAST, 771
 - SO_DEBUG, 770
 - SO_DONTROUTE, 770
 - SO_ERROR, 771
 - SO_KEEPAIVE, 770
 - SO_LINGER, 770
 - SO_RCVBUF, 771
 - SO_RCVLOWAT, 771
 - SO_RCVTIMEO, 771
 - SO_REUSEADDR, 770
 - SO_SNDBUF, 771
 - SO_SNDLOWAT, 771
 - SO_SNDTIMEO, 771
 - SO_TYPE, 771
 - return value, 771
- setstate() function, 1001-1002
- setterm, 482-483
- settimeofday, 772-773
- setuid, 848-849
- setup, 849
- setusershell() function, 946-947
- setutent() function, 947
- setvbuf function, 1016-1017
- SGI image files, converting to portable anymaps, 483-484
- sgitopnm, 483-484
- sh, expansion, 19
- shadow directories (creating), 294
- shar, 484-487
 - files, unpacking, 560-561
 - options, 484-486
- shared libraries, selecting, 883
- shared memory
 - allocating, 851-853
 - controlling, 849-851
 - commands, 850
 - system calls, 851
 - operations, 853-854
- shell variables (bash), 15-18
 - allow-null_glob_expansion, 17
 - auto_resume, 18
 - BASH, 15
 - BASH_VERSION, 15
 - cdable_vars, 18
 - CDPATH, 16
 - command_oriented_history, 17
 - ENV, 16
 - EUID, 15
 - FCEDIT, 17
 - FIGIGNORE, 17
 - glob_dot_filenames, 17
 - histchars, 17-18
 - HISTCMD, 16
 - HISTFILE, 17
 - HISTFILESIZE, 17
 - history control, 17
 - HISTSIZE, 17
 - HOME, 16
 - hostname_completion_file, 18
 - HOSTTYPE, 16
 - IFS, 16
 - IGNOREEOF, 17
 - INPUTRC, 17
 - LINENO, 15
 - MAIL, 16
 - MAIL_WARNING, 16
 - MAILCHECK, 16
 - MAILPATH, 16
 - no_exit_on_failed_exec, 18
 - noclobber, 18

- nolinks, 18
- notify, 17
- OLDPWD, 15
- OPTARG, 16
- OPTERR, 17
- OPTIND, 16
- OSTYPE, 16
- PATH, 16
- PPID, 15
- PROMPT_COMMAND, 17
- PS1, 16
- PS2, 16
- PS3, 17
- PS4, 17
- PWD, 15
- RANDOM, 15
- REPLY, 15
- SECONDS, 15
- SHLVL, 15
- TMOUT, 17
- UID, 15
- shells
 - archives, creating, 484-487
 - Bourne-again, 11-46
 - aliases, 23-24
 - arguments, 11
 - arithmetic evaluation, 34
 - blanks, 12
 - bugs, 46
 - command execution, 25
 - comments, 14
 - compound commands, 13
 - control operators, 12
 - environments, 25-26
 - escape character, 14
 - exit status, 26
 - expansion, 18-21
 - files, 46
 - functions, 23
 - history list, 32-33
 - invocation, 45-46
 - job control, 24-25
 - lists, 12-13
 - meta characters, 12
 - names, 12
 - options, 11
 - parameters, 14-15
 - pipelines (`()`), 12
 - prompting, 26
 - quoting, 14
 - readline, 27-32
 - redirection, 21-23
 - reserved words, 12
 - shell variables, 15-18
 - signals, 25
 - simple commands, 12
 - words, 12
 - built-in commands, 35-45
 - alias, 35
 - bg, 35
 - bind, 35
 - break, 35
 - builtin, 35
 - cd, 35-36
 - command, 36
 - continue, 36
 - declare, 36
 - dirs, 36
 - echo, 36-37
 - enabling/disabling, 37
 - eval, 37
 - exec, 37
 - exit, 37
 - export, 37
 - fc, 37-38
 - fg, 38
 - getopts, 38
 - hash, 38
 - help, 38
 - history, 39
 - jobs, 39
 - kill, 39
 - let, 39
 - local, 39
 - logout, 39
 - popd, 39-40
 - pushd, 40
 - pwd, 40
 - read, 40
 - readonly, 40
 - return, 40
 - set, 40-42
 - shift, 42
 - suspend, 42-43
 - test expr, 43
 - times, 43
 - trap, 43-44
 - type, 44
 - ulimit, 44-45
 - umask, 45
 - unalias, 45
 - unset, 45
 - wait, 45
 - commands, executing, 1047
 - exiting, 37
 - interactive, 45
 - login, 45
 - changing, 63
 - exiting, 39
 - pathnames, 1186
 - remote, 466-467
 - server, 1385-1386
 - suspending execution, 42-43
 - user, getting, 946-947
- shells file, 1186
- shift (shell command), 42
- shlock, 487
- SHLVL variable (bash), 15
- shmctl, 849-851
 - commands, 850
 - errors, 851
 - system calls, 851
- shmget, 851-853
 - bugs, 853
 - errors, 852
 - system calls, 852
- shmop, 853-854
- show-all-if-ambiguous
 - variable (readline), 28
- showmount, 1396
- showrgb, 488
- shrinkfile, 488
- shutdown, 855, 1396-1397
 - bugs, 1397
 - errors, 855
 - files, 1397
 - options, 1397
- sigaction, 855-857
- sigaddset, 1019-1020
- sigblock, 858

- sigdelset, 1019-1020
- sigemptyset, 1019-1020
- sigfillset, 1019-1020
- siggetmask, 858
- siginterrupt() function, 1019
- sigismember, 1019-1020
- sigmask, 858
- signal, 857-858, 1248-1249
 - bugs, 1249
 - signal messages, printing, 996
- signals
 - available (list of), 1248-1249
 - bash, 25
 - blocked
 - changing list of*, 856
 - releasing*, 858-859
 - changing process action, 855-856
 - describing with strings, 1038
 - handling, 857-858
 - interrupting system calls, 1019
 - masks
 - manipulating*, 858
 - replacing*, 856
 - pending, examining, 856
 - POSIX signal set operations, 1019-1020
 - sending to processes, raise function, 1000
 - waiting for, 817
- signatures, tin, 528
- sigpause, 858-859
- sigpending, 855-857
- sigprocmask, 855-857
- sigreturn, 859
- sigsetmask, 858
- sigsuspend, 855-857
- sigvec, 860
- simple commands (bash), 12
- simpleinit, 1397-1399
 - bugs, 1399
 - files, 1398
- sin() function, 1020-1021
- sinh() function, 1021
- sirtopnm, 488-489
- site (ftp command), 152
- size, 489-490
 - copying, 489-490
 - ftp command, 152
 - options, 489
- slattach, 1399
- slc command (telnet), 510
- sldtoppm, 490-491
- sleep() function, 1021
- sliplogin, 1399-1401
 - diagnostics, 1400
 - /etc/slip.hosts format, 1400
 - example, 1400
 - parameters, 1400
- smb filesystem, 1126
- smproxy, 491-492
- snprintf function, 992-996
- SOCK_DGRAM sockets, 860-861
- SOCK_RAW sockets, 861
- SOCK_RDM sockets, 861
- SOCK_SEQPACKET sockets, 860-861
- SOCK_STREAM sockets, 860-861
- socket, 860-861
 - errors, 861
 - socket types, 860
 - SOCK_DGRAM, 860-861
 - SOCK_RAW, 861
 - SOCK_RDM, 861
 - SOCK_SEQPACKET, 860-861
 - SOCK_STREAM, 860-861
- socketcall, 862
- socketpair, 862-863
- sockets
 - connections
 - accepting*, 740-741
 - initiating*, 752-753
 - listening for*, 792-793
 - creating, 860-861
 - names
 - binding*, 745-746
 - getting*, 769
 - options, 770-771
 - getting/setting*, 769-772
 - SO_BROADCAST, 771
 - SO_DEBUG, 770
 - SO_DONTROUTE, 770
 - SO_ERROR, 771
 - SO_KEEPAIVE, 770
 - SO_LINGER, 770
 - SO_RCVBUF, 771
 - SO_RCVLOWAT, 771
 - SO_RCVTIMEO, 771
 - SO_REUSEADDR, 770
 - SO_SNDBUF, 771
 - SO_SNDLOWAT, 771
 - SO_SNDTIMEO, 771
 - SO_TYPE, 771
 - pairs, creating, 862-863
 - peers, getting names, 765
 - receiving messages from, 826-828
 - sending messages from, 842-843
 - system calls, 862
 - types, 860
 - SOCK_DGRAM, 860-861
 - SOCK_RAW, 861
 - SOCK_RDM, 861
 - SOCK_SEQPACKET, 860-861
 - SOCK_STREAM, 860-861
- soft-reset() action (xterm), 715
- Solitaire files, converting to portable anymaps, 488-489
- sort, 492-493
- sorted arrays, searching, 900-901
- sorted files, removing duplicate lines, 560
- sorted word lists, compressing/uncompressing, 496
- sorting arrays, 1000
- sound drivers, boot-time parameters, 1224
- source command (xauth), 591

- spaces, converting to tabs, 559
- spectopm, 494
- special parameters, bash, 14-15
 - ! (exclamation points), 15
 - # (pound signs), 15
 - \$ (dollar signs), 15
 - * (asterisks), 15
 - (hyphens), 15
 - ? (question marks), 15
 - @ (at signs), 15
 - _ (underscores), 15
 - 0, 15
- spell-checking, 274, 280
 - buildhash, 279
 - findaffix, 280
 - icombine, 281
 - ijoin, 281
 - ispell, 274-279
 - ispell dictionaries, 1084-1090
 - affix file, 1084-1085*
 - alternate string characters, 1087*
 - character-set section, 1086*
 - flags, 1088*
 - headers, 1085*
 - options statements, 1085-1086*
 - prefix/suffix tables, 1088*
 - root words, 1084-1085*
 - munchlist, 279-280
 - tryaffix, 281
- split, 494-495
- splitting files, 85-86, 119-120
- spool queue
 - examining, 298-299
 - removing jobs from, 301-302
- SPOT satellite images,
 - converting to portable graymaps, 495
- spottopgm, 495
- sprintf function, 992-996
- sprintf() function, awk, 167-168
- spuotppm, 495-496
- sq, 496
- sqrt() function, 1023
- square roots (returning), 1023
- rand() function, 1001
- rand48() functions, 912
- random() function, 1001-1002
- scanf function, 1013-1015
- st, 1096-1100
 - ioctl() calls, 1097-1100
 - return values, 1100
- stack, saving context, 1018
- standard colormap utility (X), 699-700
- standard error output,
 - redirecting, 22
- standard output, redirecting, 22
- start-cursor-extend() action (xterm), 714
- start-extend() action (xterm), 714
- startup time
 - adjusting to GMT, 1424-1425
 - converting, 1430
- startx, 496-497
- stat, 863-864
- statements, awk, 167-168
- states (system), updating, 1414-1415
- statfs, 865-866
- status
 - cvs, 102
 - ftp, 152
 - telnet command, 512
- stdarg, 1023-1024
- stdio library, 1025-1027
 - bugs, 1026
 - functions, 1026-1027
- stime, 866
- stpcpy() function, 1027-1028
- strcasemp(), 1028
- strcat() function, 1028-1029
- strchr() function, 1029
- strcmp() function, 1029-1030
- strcoll() function, 1030
- strcpy() function, 1030-1031
- strcspn() function, 1038-1039
- strdup() function, 1031
- stream-oriented editor, *see* sed
- streams
 - binary, input/output (getting), 926-927
 - block buffered, 1016
 - buffering operations, 1016-1017
 - checking/resetting status, 919-920
 - closing, 919
 - directory
 - current location (returning), 1048*
 - resetting, 1011*
 - flushing, 920-921
 - line buffered, 1016
 - opening, 924-925
 - repositioning, 927-928
 - unbuffered, 1016
- strerror() function, 1032
- strfry(), 1032
- strftime() function, 1032-1034
 - conversion specifiers, 1033
 - tm structure members, 1034
- string constants, awk, 169-170
- string functions, awk, 169
- string variables, configuration-dependent, 906-907
- string() action (xterm), 714
- strings, 498
 - byte
 - copying, 900*
 - operations, 901*
 - writing zeros to, 902*
 - comparing, 1029-1030
 - byte, 899-900*
 - ignoring case, 1028*
 - using current locale, 1030*
- concatenating, 1028-1029
- converting
 - to doubles, 898, 1039-1040*
 - to integers, 898-899*

- to long integers*, 899, 1041
- to multibyte character (from wide character)*, 1061
- to tm structure*, 1036-1037
- to unsigned long integers*, 1041-1042
- to wide character (from multibyte)*, 977-978
- copying, 498, 1030-1031
 - strcpy() function*, 1027-1028
- describing signals with, 1038
- duplicating, 1031
- extracting tokens from, 1037-1040
- length (calculating), 1035
- locating characters in, 953, 1029
- options, 498
- outputting, 997-999
- randomizing, 1032
- searching, for character sets, 1035-1039
- string operation functions, 1034-1035
- transformation, 1042-1043
 - see also* substrings
- strip, 499
- strlen() function, 1035
- strncasecmp(), 1028
- strncat() function, 1028-1029
- strncmp() function, 1029-1030
- strncpy() function, 1030-1031
- strpbrk() function, 1035-1036
- strptime() function, 1036-1037
 - bugs, 1037
 - field descriptors, 1036-1037
- strrchr() function, 1029
- strsep() function, 1037-1038
- strsignal() function, 1038
- strspn() function, 1038-1039
- strstr() function, 1039
- strtod() function, 1039-1040
- strtok() function, 1040
- strtol() function, 1041
- strtoul() function, 1041-1042
- struct (ftp command), 152
- strxfrm() function, 1042-1043
- subdirectories, MS-DOS
 - creating, 326
 - moving, 327
 - removing, 329
 - renaming, 329-330
- subroutines
 - endnetent, 936-937
 - getnetbyaddr, 936-937
 - getnetbyname, 936-937
 - getnetent, 936-937
- subst, 500-501
- substrings
 - locating, 1039
 - locating in memory areas, 981
 - see also* strings
- suffixes, 1249-1252
- sum, 501
- Sun icons, converting to portable bitmaps, 262
- Sun raster files, converting to portable anymaps, 438
- SuperProbe, 501-503
 - bugs, 503
 - options, 502
 - running, 502-503
- suspend (shell command), 42-43
- suspending execution, 1061
- swab() function, 1043
- swap area, setting up, 1327-1328
- swap device parameter, values, 1374
- swapoff, 866-867, 1401
 - errors, 867
 - files, 1401
 - priority, 867
- swapon, 866-867, 1401
 - errors, 867
 - files, 1401
 - priority, 867
- swapping
 - enabling/disabling, 1401
 - starting/stopping, 866-867
 - priority, 867
- swapping bytes, 1043
- symbolic links, 867-869
 - reading values, 823-824
- symlink, 867-869
- sync, 869, 1401-1402
- synchronizing files with memory maps, 811
- synchronous I/O,
 - multiplexing, 835-837
- syscall macros, 738
- syscall() macros, 738
- sysconf() function, 1043-1045
- sysctl, 869-871
- sysfs, 871
- sysinfo, 871-872
- sysklogd, 1402-1404
 - configuration file, 1402-1403
 - FIFOs, 1403
 - files, 1404
 - installing, 1403
 - remote logging, 1403
 - security, 1403-1404
- syslog, 872-874
- syslog() function, 1045-1046
- syslog.conf, 1186-1188
 - action field, 1186-1187
 - examples, 1187-1188
 - facility keyword, 1187
 - level keyword, 1187
 - selector field, 1186-1187
- syslogd, 1404-1405
 - configuration file, 1186-1188
 - action field*, 1186-1187
 - examples*, 1187-1188
 - facility keyword*, 1187
 - level keyword*, 1187
 - selector field*, 1186-1187

- files, 1405
- options, 1405
- system
 - configuration, getting
 - information at runtime, 1043-1045
 - displaying information
 - about, 562
 - load average, graphing, 533
 - page size, getting, 765
 - parameters, reading/writing, 869-871
 - printing activity summary, 573
 - shutting down, 1396-1397
 - state, updating, 1414-1415
 - status server, 1386-1387
 - message format*, 1386-1387
- system (ftp command), 152
- system calls, 738-739
 - calling directly, 738
 - interrupting with signals, 1019
- IPC, 789
- obsolete, 814
- prototypes, 738
- socket, 862
- syscall macros, 738
- undocumented, 881
- unimplemented, 881-882
- system logging, 1402-1404
 - configuration file, 1402-1403
- FIFOs, 1403
- making log entries, 295-296
- messages, 1404-1405
- remote, 1403
- sending messages to, 1045-1046
- System V interprocess
 - communication, 1144-1146
 - message queues, 1145
 - resource access permissions, 1144-1145
 - semaphore sets, 1145-1146
 - shared memory segments, 1146

- System V IPC keys, converting pathnames/project identifiers to, 929-930
- system() function, 1047
- sysv filesystem, 1125

T

- Tab Window Manager, *see* twm

tables

- descriptor, size (getting), 760-761
- file
 - adding entries*, 1428-1429
 - description*, 1425-1426
 - initializing*, 1427
 - moving files to end*, 1431
 - removing files*, 1431-1432
 - structure*, 1426
 - table entries*, 1426
 - unreferenced entries (fetching)*, 1428

hash

- creating*, 951
- freeing memory*, 951
- searching*, 951

- IP routing (manipulating), 1379-1380

- local descriptor, reading/writing, 800

- RARP, manipulating, 1373
- troff, formatting, 236-237

- tabs, converting to spaces, 137

- tac, 503-504

- tag (cvs command), 102-103

tag files

- emacs, 135-137
- generating, 87-88
- vi, 135-137

- tail, 504

- talk, 505

- talkd, 1405-1406

- tan() function, 1047-1048

- tanh() function, 1048

- tcal, 506

- tcdrain(), 876, 1052
- tcflow(), 876, 1052
- tcflush(), 876, 1052
- tcgetattr(), 876, 1051
- tcgetpgrp(), 877, 1053
- tcsendbreak(), 876, 1052
- tcsetattr(), 876, 1052
- tcsetpgrp(), 877, 1053
- tdelete, 1056-1058
- tek-copy() action (xterm), 716
- tek-page() action (xterm), 715
- tek-reset() action (xterm), 716
- telinit, 1307-1309
 - diagnostics, 1309
 - files, 1308
 - run levels, 1308
- tellmdir() function, 1048
- telnet, 507-512
 - commands, 508-512
 - !, 512
 - ?, 512
 - close, 508
 - display argument, 508
 - environ, 511
 - mode, 508
 - open host, 508
 - quit, 508
 - send arguments, 508-509
 - set, 509-510
 - slc, 510
 - status, 512
 - toggle, 511-512
 - unset, 509-510
 - z, 512
 - environment, 512
 - files, 512
 - options, 507
- Telnet protocol
 - DARPA server, 1406-1407
 - interface, *see* telnet
- telnetd, 1406-1407
- tempnam() function, 1049
- temporary filenames, creating, 983-984

- temporary files
 - creating, 983, 1053-1054
 - naming, 1049, 1054
- tenex (ftp command), 152
- termcap, 1188-1197
 - Boolean capabilities, 1189
 - numeric capabilities, 1189-1190
 - string capabilities, 1190-1197
 - control codes, 1195-1196*
- terminals
 - attributes, 1049-1053
 - getting, 876*
 - setting, 482-483, 876*
 - baud rate, 1049-1053
 - capability database, 1188-1197
 - Boolean capabilities, 1189*
 - numeric capabilities, 1189-1190*
 - string capabilities, 1190-1197*
 - controlling terminal, 1100-1101
 - creating typescript of sessions, 474-475
 - displaying last login, 285-286
 - foreground processes, group ID, 1049-1053
 - initializing, 539-542
 - line control, 1049-1053
 - name and device list, 1197
 - names (returning), 1058
 - resetting, 456
 - serial lines, 1101
 - termios functions, 874-878
 - type mapping, 540-541
 - type, setting in shell environment, 540
 - virtual hangups, 885
 - window size, setting, 456-457
- terminating processes, 283-284
- terminating programs
 - abort() function, 892
 - assert() function, 895-896
- termios functions, 874
 - flag constants, 874-876
- termios structure
 - c_cflag flag constants, 1051
 - c_iflag flag constants, 1050
 - c_lflag flag constants, 1051
 - c_oflag flag constants, 1050-1051
- test expr (shell command), 43
- text
 - compressed, viewing, 733-734
 - filters, more, 327-328
 - formatting line lengths, 143
 - rendering to bitmaps, 355-356
 - sorting, 492-493
 - editors, elvis, 126-128
 - files
 - converting for printing, 429-430*
 - creating gcal resource files from, 558*
- tfind, 1056-1058
- tfmtodit, 513
- TFTP (Trivial File Transfer Protocol), 1407
 - DARPA server, 1407
- tftp, 514-515
- TFTP (Trivial File Transfer Protocol), 514
- tftpd, 1407
- tgatoppm, 515
- TI_ACTIVEFILE environ-
ment variable, 529
- TI_NOVROOTDIR environ-
ment variable, 529
- TIFF files, converting to
portable anymaps, 515-516
- tifftopnm, 515-516
- tilde expansion (bash), 19
- time
 - calculating differences, 911
 - getting/setting, 772-773
 - in seconds, 878*
 - returning current, 928-929
 - setting, 866
 - startup
 - adjusting to GMT, 1424-1425*
 - converting, 1430*
- time functions, 878
 - awk, 169
- time server daemon, 1407-1408
- time zones
 - compiling, 1419-1422
 - printing, 1419
- time-sharing scheduling, 834
- timed, 1407-1409
 - control program, 1408-1409
 - files, 1408
- timedc, 1408-1409
- timers (event), managing, 1424
- times
 - binary, converting to ASCII, 909-911
 - converting
 - to ASCII, 984-986*
 - initializing conversion information, 986-988, 1058-1060*
 - strings to numbers, 989-990*
 - to tm structure, 1036-1037*
 - formatting, strftime()
function, 1032-1034
 - process, getting, 878-879
 - time zone information files, 1197-1198
 - user/system, printing, 43
- times (shell command), 43
- times function, 878-879
- timestamps, changing, 536
- tin, 516-533
 - articles
 - automatic mailing, 528*
 - autoselect/autokill, 526-527*
 - crossposting, 527*

- customizing quote string*, 527
 - mailing*, 527
 - pipng*, 527
 - posting*, 527
 - printing*, 527
 - saving*, 527-528
 - tagging/untagging*, 528
- bugs, 531
- commands
 - article viewer*, 522-524
 - editing*, 519
 - global options menu*, 524-525
 - group index*, 521-522
 - newsgroup selection*, 519-520
 - spool directory selection*, 520
 - thread listing*, 522
- environment variables, 528-530
 - ADD_ADDRESS*, 529
 - AUTOSUBSCRIBE*, 529
 - AUTOUNSUBSCRIBE*, 530
 - BUG_ADDRESS*, 529
 - DISTRIBUTION*, 529
 - MAILER*, 529
 - NNTPSERVER*, 529
 - ORGANIZATION*, 529
 - REPLYTO*, 529
 - TI_ACTIVEFILE*, 529
 - TI_NOVROOTDIR*, 529
 - TIN_HOMEDIR*, 528
 - TIN_INDEXTDIR*, 529
 - TIN_LIBDIR*, 529
 - TIN_SPOOLDIR*, 529
 - TINRC*, 528
 - VISUAL*, 529
- files, 531
- group attributes, 526
- index files, 517-518
- moving between levels, 519
- news administration, 518
- options, 516-517
- screen format, 518-519
- signatures, 528
- starting, 518
- tinrc configurable variables, 525-526
 - xterm buttons, 530-531
- TIN_HOMEDIR
 - environment variable, 528
- TIN_INDEXTDIR
 - environment variable, 529
- TIN_LIBDIR
 - environment variable, 529
- TIN_SPOOLDIR
 - environment variable, 529
- tinrc configurable variables, 525-526
 - see also* tin
- TINRC
 - environment variable, 528
- tload, 533
- TMOU variable (bash), 17
- /tmp directory, 1237
- tmpfile() function, 1053-1054
- tmpnam() function, 1054
- toascii() function, 1055
- toggle command (telnet), 511-512
- tokens, extracting from strings, 1037-1040
- tolower() function, 1055-1056
- top, 533-535
 - bugs, 535
 - commands, 534-535
 - field descriptions, 534
 - options, 534
- topological sorting (graphs), 542
- touch, 536
- toupper() function, 1055-1056
- tr, 536-539
 - character classes, 537-538
 - escape characters, 537
 - ranges, 537
 - repeated characters, 537
 - specifying character sets, 537
 - squeezing/deleting, 538-539
 - translating, 538
 - warning messages, 539
- tr2tex, 1252-1253
- trace (ftp command), 152
- traceroute, 1409-1412
 - examples, 1411
 - options, 1410
- transforming strings, 1042-1043
- translating/deleting characters, 536-539
- trap (shell command), 43-44
- Trivial File Transfer Protocol, *see* TFTP
- troff
 - compiling pictures for, 211-215
 - converting to LaTeX, 1252-1253
 - formatting tables, 236-237
 - output format, 1129-1131
- TrueVision Targa files, converting to portable pixmaps, 515
- truncate, 879-880
- tryaffix, 274, 281
 - files, 281
 - see also* ispell
- tsearch, 1056-1058
- tset, 539-542
 - compatibility, 542
 - environment, 541
 - files, 541
 - options, 540
 - setting environment, 540
 - terminal type mapping, 540-541
- tsort, 542
- tty, 1100-1101
- ttyname, 1058
- ttys, 1101
- ttytype, 1197
- tune2fs, 1412-1413
- tunelp, 1413-1414
- twalk, 1056-1058

twm, 542-557

- bindings, 552-553
- bugs, 557
- customizing, 543-544
- environment, 557
- files, 557
- functions, 554-556
 - !, 554
 - f.auroraise*, 554
 - f.backiconmgr*, 554
 - f.beep*, 554
 - f.bottomzoom*, 554
 - f.circledown*, 554
 - f.circleup*, 554
 - f.colormap*, 554
 - f.deiconify*, 554
 - f.delete*, 554
 - f.deltastop*, 554
 - f.destroy*, 554
 - f.downiconmgr*, 554
 - f.exec*, 554
 - f.focus*, 554
 - f.forcmove*, 555
 - f.forwiconmgr*, 555
 - f.fullzoom*, 555
 - f.function*, 555
 - f.hbzoom*, 555
 - f.hideiconmgr*, 555
 - f.horizoom*, 555
 - f.htzoom*, 555
 - f.hzoom*, 555
 - f.iconify*, 555
 - f.identify*, 555
 - f.lefticonmgr*, 555
 - f.leftzoom*, 555
 - f.lower*, 555
 - f.menu*, 555
 - f.move*, 555
 - f.nexticonmgr*, 555
 - f.nop*, 555
 - f.previconmgr*, 555
 - f.priority*, 555
 - f.quit*, 555
 - f.raise*, 555
 - f.raiselower*, 555
 - f.refresh*, 555
 - f.resize*, 555

- f.restart*, 555
- f.righticonmgr*, 555
- f.rightzoom*, 556
- f.saveyourself*, 556
- f.showiconmgr*, 556
- f.sorticonmgr*, 556
- f.title*, 556
- f.topzoom*, 556
- f.unfocus*, 556
- f.upiconmgr*, 556
- f.vlzoom*, 556
- f.vrzoom*, 556
- f.warping*, 556
- f.warpto*, 556
- f.warptoiconmgr*, 556
- f.warptoscreen*, 556
- f.winrefresh*, 556
- f.zoom*, 556

icons, 557

menus, 556-557

options, 543

starting, 543

startup files, 543-544

variables, 544-552

- AutoRaise*, 544
- AutoRelativeResize*, 544-545
- BorderColor*, 545
- BorderTileBackground*, 545
- BorderTileForeground*, 545
- BorderWidth*, 545
- ButtonIndent*, 545
- ClientBorderWidth*, 545
- Color*, 545-546
- ConstrainedMoveTime*, 546
- Cursors*, 546
- DecorateTransients*, 546
- DefaultBackground*, 546
- DefaultForeground*, 547
- DefaultFunction*, 552
- DontIconifyByUnmapping*, 547
- DontMoveOff*, 547
- DontSqueezeTitle*, 547

- ForceIcons*, 547
- FramePadding*, 547
- Grayscale*, 547
- IconBackground*, 547
- IconBorderColor*, 547
- IconBorderWidth*, 547
- IconDirectory*, 547
- IconFont*, 547
- IconForeground*, 547
- IconifyByUnmapping*, 547
- IconManagerBackground*, 547
- IconManagerDontShow*, 547
- IconManagerFont*, 548
- IconManagerForeground*, 548
- IconManagerGeometry*, 548
- IconManagerHighlight*, 548
- IconManagers*, 548
- IconManagerShow*, 548
- IconRegion*, 548
- Icons*, 548-549
- InterpolateMenuColors*, 549
- MakeTitle*, 549
- MaxWindowSize*, 549
- MenuBackground*, 549
- MenuFont*, 549
- MenuForeground*, 549
- MenuShadowColor*, 549
- MenuTitleBackground*, 549
- MenuTitleForeground*, 549
- Monochrome*, 549
- MoveDelta*, 549
- NoBackingStore*, 549
- NoCaseSensitive*, 549
- NoDefaults*, 549
- NoGrabServer*, 549
- NoHighlight*, 550
- NoIconManagers*, 550
- NoMenuShadows*, 550

- NoRaiseOnDeiconify*, 550
- NoRaiseOnMove*, 550
- NoRaiseOnResize*, 550
- NoRaiseOnWarp*, 550
- NoSaveUnders*, 550
- NoStackMode*, 550
- NoTitle*, 550
- NoTitleFocus*, 550
- NoTitleHighlight*, 550
- OpaqueMove*, 550
- Pixmap*s, 550
- Priority*, 550
- RandomPlacement*, 550
- ResizeFont*, 551
- RestartPreviousState*, 551
- SaveColor*, 551
- ShowIconManager*, 551
- SortIconManager*, 551
- SqueezeTitle*, 551
- StartIconified*, 551
- TitleBackground*, 551
- TitleButtonBorderWidth*, 551
- TitleFont*, 552
- TitleForeground*, 552
- TitlePadding*, 552
- UnknownIcon*, 552
- UsePPosition*, 552
- WarpCursor*, 552
- WarpUnmapped*, 552
- WindowFunction*, 552
- WindowRing*, 552
- XorValue*, 552
- Zoom*, 552
- windows, 543
 - creating, 543
 - resizing, 543
- txt2gcal, 558
- type
 - ftp command, 152
 - shell command, 44
- TZ environment variable, 987
- tzfile, 1197-1198
- tzset, 986-988
 - files, 988
 - TZ environment variable, 987
- tzset() function, 1058-1060

U

- UID variable (bash), 15
- ul, 558-559
- ulimit (shell command), 44-45
- umask, 880
 - ftp command, 152
 - shell command, 45
- umsdos filesystem, 1125
- unalias (shell command), 45
- uname, 880-881
- unbuffered streams, 1016
- underlining, 558-559
- underscores (_), bash special parameters, 15
- undocumented system calls, 881
- unexpand, 559
- ungetc() function, 945
- Unicode, 1065, 1253-1255
 - ASCII-compatible encoding, 1255-1256
 - combining characters, 1254
 - implementation levels, 1254
 - Web site, 1065
- unimplemented system calls, 881-882
- uniq, 560
- Universal Product Code
 - bitmaps, creating, 368
- UNIX
 - copying MS-DOS files to/
 - from, 317-318
 - filenames, restoring, 324-325
 - files, copying
 - between systems, 563-565
 - to MS-DOS, 335
- unlink, 882
- unlocking memory
 - munlock, 811-812
 - munlockall, 812-813
- unmapping files to memory, 799-800
- unmount, 802-804, 1328-1332
 - bugs, 1332
 - errors, 803
 - files, 1332
 - options, 1331
 - return value, 803
- unset
 - shell command, 45
 - telnet command, 509-510
- unshar, 560-561
- unsq, 496
- update (cvs command), 103-104
- update_state, 1414-1415
- updatedb, 561-562
- uppercase, converting letters to, 1055-1056
- uptime, 562
- uselib, 883
- Usenet
 - administration, 1344-1346
 - archiver, 1262-1263
 - articles
 - expiring, 1121-1123
 - libinn routines, 962-966
 - purging, 1292-1293
 - record of, 1131-1132
 - retrieving from NNTP server, 340-341
 - sending to remote NNTP server, 1312-1313
 - sending to remote site, 1349-1350
 - specifying distribution, 1158-1163
 - batch files, converting to INN, 1281-1282
 - control messages, handling, 1115-1116
 - databases, recovering, 1342-1344
 - history file
 - displaying filenames from, 226-227
 - removing filenames, 1370-1371

- innwatch supervision, 1142-1144
 - log files, 1163-1165
 - list of*, 1164
 - maintenance*, 1346-1347
 - message/action fields*, 1163-1164
 - moderated newsgroups, mail addresses, 1151-1152
 - newsgroups, listing active, 1104-1105
 - sending articles to servers, 267-269
 - Unix FaceSaver files, converting to portable graymaps, 147
 - user (ftp command), 152
 - user group file, 1131
 - user IDs (processes), setting, 848-849
 - real and effective, 847-848
 - userlist, 563
 - usernames
 - getting, 934-935
 - remote lookup, 1134-1135
 - users
 - adding to system, 1258-1259
 - displaying last login, 285-286
 - file permissions, checking, 741-742
 - IDs, getting, 773
 - listing, 563
 - logins, preventing, 1168
 - outputting logged in
 - on local machines*, 474
 - on networks*, 472-473
 - preference utility (X), 690-693
 - printing activity summary (w), 573
 - quotas, editing, 1291-1292
 - sending messages to, 473, 576-577
 - shells, getting, 946-947
 - switching between, 296
 - talking to online, 505
 - writing messages to, 574, 1383
 - usleep() function, 1061
 - /usr directory, 1237
 - /usr/X11R6 directory, 1237
 - /usr/X11R6/bin directory, 1237
 - /usr/X11R6/lib directory, 1237
 - /usr/X11R6/lib/X11 directory, 1237
 - /usr/X11R6/include/X11 directory, 1237
 - ustat, 883-884
 - UTF-8, 1255-1256
 - examples, 1256
 - properties, 1255-1256
 - utime, 884-885
 - utimes, 884-885
 - utmp, 1198-1200
 - utmp file entries, accessing, 947-948
 - utmp/wtmp entries, managing, 480-481
 - utmpname() function, 947
 - uucico, 1415-1417
 - files, 1416-1417
 - options, 1415-1416
 - uucp, 563-565
 - bugs, 565
 - execution daemon, 572
 - files, 564-565
 - options, 564
 - remote command execution, 569-571
 - status inquiry, 566-569
 - UUCP
 - connections, receiving news, 463-464
 - file transfer requests, processing, 1415-1417
 - uudecode, 565-566
 - uuencode, 565-566, 1200
 - uustat, 566-569
 - examples, 568-569
 - files, 569
 - options, 567-568
 - uux, 569-571
 - bugs, 571
 - examples, 571
 - files, 571
 - options, 570-571
 - restrictions, 571
 - uuxqt, 572
- ## V
-
- variable argument lists (declaring), 1023-1024
 - variables
 - awk, 163-165
 - arrays*, 164
 - built-in*, 163-164
 - typing and conversion*, 164-165
 - bash, 15-18
 - allow-null_glob_expansion*, 17
 - auto_resume*, 18
 - BASH*, 15
 - BASH_VERSION*, 15
 - cdable_vars*, 18
 - CDPATH*, 16
 - command_oriented_history*, 17
 - ENV*, 16
 - EUID*, 15
 - FCEDIT*, 17
 - FIGNORE*, 17
 - glob_dot_filenames*, 17
 - histchars*, 17-18
 - HISTCMD*, 16
 - HISTFILE*, 17
 - HISTFILESIZE*, 17
 - HISTSIZ*, 17
 - HOME*, 16
 - hostname_completion_file*, 18
 - HOSTTYPE*, 16
 - IFS*, 16
 - IGNOREEOF*, 17
 - INPUTRC*, 17
 - LINENO*, 15
 - MAIL*, 16

MAIL_WARNING, 16
MAILCHECK, 16
MAILPATH, 16
no_exit_on_failed_exec, 18
noclobber, 18
nolinks, 18
notify, 17
OLDPWD, 15
OPTARG, 16
OPTERR, 17
OPTIND, 16
OSTYPE, 16
PATH, 16
PPID, 15-17
PROMPT_COMMAND, 17
PS1, 16
PS2, 16
PS3, 17
PS4, 17
PWD, 15
RANDOM, 15
REPLY, 15
SECONDS, 15
SHLV, 15
TMOU, 17
UID, 15
 declaring, 36
 local, creating, 39
 readline, 28
 bell-style, 28
 comment-begin, 28
 completion-query-items, 28
 convert-meta, 28
 editing-mode, 28
 expand-tilde, 28
 horizontal-scroll-mode, 28
 keymap, 28
 mark-modified-lines, 28
 meta-flag, 28
 output-meta, 28
 show-all-if-ambiguous, 28
 string, configuration-dependent, 906-907

vcs, 1101-1102
vcsa, 1101-1102
 vectors, reading/writing, 824-825
 verbose (ftp command), 152
 vfat filesystem, 1125
 case sensitivity (mtools and), 332
 vfork, 758
 vfprintf function, 992-996
 vfscanf function, 1013-1015
 vhangup, 885
 vi, *see* elvis
 video hardware, identifying, 501-503
 video mode tuner (XFree86), 719-720
 buttons, 719
 moving display, 719
 options, 720
 vidr, 303-304
 view, *see* elvis
 vipw, 1418-1419
 virtual 8086 mode, entering, 885-886
 virtual consoles, 1066
 memory, 1101-1102
 virtual framebuffer X server, 717-718
 virtual memory
 addresses, remapping, 805-806
 reports, 1417-1418
 VISUAL environment
 variable, 529
 visual-bell() action (xterm), 716
 vm86, 885-886
 vmstat, 1417-1418
 volume labels (MS-DOS), creating, 325-326
 vprintf function, 992-996
 vsnprintf function, 992-996
 vsprintf function, 992-996
 vscanf function, 1013-1015

W

w, 573
 wait, 886-888
 errors, 887
 shell command, 45
 status macros, 887
 wait3, 888-889
 wait4, 888-889
 waitpid, 886-888
 wall, 574
 wc, 574
 wcstomb() function, 1061-1062
 wcstombs() function, 1061
 Web sites, Unicode, 1065
 whereis, 575-576
 while (bash command), 13
 wide character strings,
 converting to multibyte
 character strings, 1061
 wide characters, converting to
 multibyte characters,
 1061-1062
 widgets
 bitmap application, 54-57
 editres, 125-126
 xclipboard, 596
 xclock, 595
 xconsole, 598
 xcutsel, 599
 xdm authentication widget,
 609-610
 actions supported, 610
 resources, 609-610
 xfd, 634-635
 xlogo, 668
 xmag, 671
 windows, X
 dumping utility, 721-722
 information utility, 722-724
 word splitting (bash), 21
 words
 bash, 12
 finding first bit set, 921
 input/output, 948

wrapping input lines, 143-144
 write, 576-577, 889-890
 errors, 889-890
 writew, 824-825, 1003-1004
 bugs, 1004
 errors, 825, 1004
 wttmp, 1198-1200

X

X Color Management System,
 Device Color Characteriza-
 tion utility, 592-593

X commands, grops, 232-233

X font servers

 displaying information
 about, 145
 generating BDF fonts,
 146-147
 listing fonts, 145-146

X sessions, initializing,
 496-497

X Window System

 clients
 clipboard client, 595-597
 listing applications,
 669-670
 clock, 593-595
 Display Manager, 599-614
 authentication widget,
 609-610
 chooser, 607
 configuration file, 606
 controlling, 613
 environment variables,
 608
 files, 613
 limitations, 613
 local server specification,
 607-608
 options, 600-601
 reset program, 612
 resources, 601-606
 resources file, 608
 server control, 612-613
 session program, 611-612
 sessions, 600

 setup program, 608-609
 startup program, 610-611
 XDMCP service access
 control, 606-607
 emacs, 131-132
 fonts
 displaying all characters
 in, 633-636
 listing, 670-671
 image displayer, 725-726
 environment, 726
 options, 725-726
 imake, 266
 initializer, 664-666
 keymaps, modifying,
 672-676
 LBX proxy server, 286-287
 logo, 667-668
 magnifying screen, 671-672
 monitoring system console
 messages, 597-598
 property displayer, 677-681
 constructing formats, 679
 examples, 680
 format characters, 679
 selecting windows, 678
 remote program starts, 676
 resource database utility,
 681-684
 file symbols, 681-682
 options, 682-684
 root window parameters
 (setting), 693-694
 screen, refreshing, 684-685
 server information utility,
 614
 servers
 access control program,
 643-645
 display server, 685-690
 font server, 641-643
 killing clients, 666-667
 virtual framebuffer,
 717-718
 XFree86, 636-641
 Session Manager, 694-698
 default startup applica-

 tions, 695
 options, 695-698
 proxy, 698
 remote applications, 698
 Session menu, 695-696
 SM_SAVE_DIR
 environment variable,
 695
 starting sessions, 695
 tester, 698-699
 .xsession file, 695
 standard colormap utility,
 699-700
 Tab Window Manager,
 542-557
 bindings, 552-553
 bugs, 557
 customizing, 543-544
 functions, 554-556
 icons, 557
 menus, 556-557
 options, 543
 starting, 543
 startup files, 543-544
 variables, 544-552
 windows, 543
 terminal emulator, 700-717
 actions, 713-716
 character classes, 712-713
 emulations, 700
 environment, 717
 features, 700-701
 menus, 711-712
 options, 701-705
 pointer usage, 710-711
 resources, 705-710
 security, 712
 user preference utility,
 690-693
 window dumping utility,
 721-722
 window information utility,
 722-724
 X10 bitmaps, converting to
 portable, 592
 X11 bitmaps, converting to
 portable, 592

- X11 pixmaps, converting to portable, 677
- X11 server
 - performance comparison program, 585-586
 - performance test program, 577-585
- X11/X10 window dump files, converting to portable
 - anymaps, 722
- x11perf, 577-585
 - options, 578-585
- x11perfcomp, 585-586
- xargs, 586-587
- xauth, 587-592
 - bugs, 592
 - commands, 588, 591
 - ?, 591
 - exit, 591
 - help, 591
 - info, 591
 - list, 591
 - merge, 591
 - quit, 591
 - remove, 591
 - source, 591
 - display names, 591
 - environment, 589
 - environment variables, 592
 - example, 591
 - files, 589, 592
 - generating magic cookies for, 317
 - options, 587-588
- xbmtopbm, 592
- xclipboard, 595-597
 - buttons, 596
 - environment, 597
 - files, 597
 - options, 596
 - sending/retrieving contents, 596-597
 - widgets, 596
- xclock, 593-595
 - bugs, 595
 - defaults, 594-595
 - environment, 595
 - files, 595
 - options, 594
 - widgets, 595
- xcmsdb, 592-593
- xconsole, 597-598
- xcutsel, 598-599
- Xdf disks, 332
- xdm, 599-614
 - authentication widget, 609-610
 - actions supported, 610
 - resources, 609-610
 - chooser, 607
 - configuration file, 606
 - controlling, 613
 - environment variables, 608
 - files, 613
 - limitations, 613
 - local server specification, 607-608
 - options, 600-601
 - reset program, 612
 - resources, 601-606
 - DisplayManager.*, 604
 - DisplayManager.accessFile*, 603
 - DisplayManager.authDir*, 602
 - DisplayManager.autoRescan*, 602
 - DisplayManager.choiceTimeout*, 603
 - DisplayManager.daemonMode*, 602
 - DisplayManager.debugLevel*, 602
 - DisplayManager.DISPLAY.authComplain*, 605
 - DisplayManager.DISPLAY.authFile*, 605
 - DisplayManager.DISPLAY.authName*, 605
 - DisplayManager.DISPLAY.authorize*, 605
 - DisplayManager.DISPLAY.chooser*, 603
 - DisplayManager.DISPLAY.cpp*, 603
 - DisplayManager.DISPLAY.failSafeClient*, 605
 - DisplayManager.DISPLAY.grabServer*, 605
 - DisplayManager.DISPLAY.grabTimeout*, 605
 - DisplayManager.DISPLAY.openDelay*, 604
 - DisplayManager.DISPLAY.openRepeat*, 604
 - DisplayManager.DISPLAY.openTimeout*, 604
 - DisplayManager.DISPLAY.pingInterval*, 604
 - DisplayManager.DISPLAY.pingTimeout*, 604
 - DisplayManager.DISPLAY.reset*, 604
 - DisplayManager.DISPLAY.resetForAuth*, 606
 - DisplayManager.DISPLAY.resetSignal*, 605
 - DisplayManager.DISPLAY.resources*, 603
 - DisplayManager.DISPLAY.session*, 603
 - DisplayManager.DISPLAY.setup*, 603
 - DisplayManager.DISPLAY.startup*, 603
 - DisplayManager.DISPLAY.systemPath*, 604-605
 - DisplayManager.DISPLAY.systemShell*, 605
 - DisplayManager.DISPLAY.terminateServer*, 604
 - DisplayManager.DISPLAY.termSignal*, 605
 - DisplayManager.DISPLAY.userAuthDir*, 606
 - DisplayManager.DISPLAY.userPath*, 604
 - DisplayManager.DISPLAY.xrdb*, 603

- DisplayManager.errorLogFile*, 602
- DisplayManager.exportList*, 603
- DisplayManager.greeterLib*, 603
- DisplayManager.keyFile*, 602
- DisplayManager.lockPidFile*, 602
- DisplayManager.pidFile*, 602
- DisplayManager.randomFile*, 603
- DisplayManager.removeDomainname*, 602
- DisplayManager.requestPort*, 601
- DisplayManager.servers*, 601
- resources file, 608
- server control, 612-613
- session program, 611-612
- sessions, 600
- setup program, 608-609
- startup program, 610-611
- XDMCP service access control, 606-607
- XDMCP service, access control, 606-607
- xdpyinfo, 614
- XF86_8514 server, 615
- XF86_Accel, 614-623
 - bugs, 623
 - configuration, 615-616
 - files, 622
 - options, 616
 - setup, 616-622
- XF86_AGX server, 615
- XF86_Mach32 server, 615
- XF86_Mach64 server, 615
- XF86_Mach8 server, 615
- XF86_Mono, 624-627
 - configuration, 624
 - files, 626
 - options, 624
 - setup, 624-626
- XF86_P9000 server, 615
- XF86_S3 server, 615
- XF86_SVGA, 627-631
 - configuration, 627-628
 - files, 630-631
 - options, 628
 - setup, 628-630
- XF86_VGA16, 631-633
 - configuration, 631
 - files, 633
 - options, 632
 - setup, 632
- XF86_W32 server, 615
- XF86Config, 1201-1208
 - Device sections, 1204-1206
 - Files section, 1201
 - Keyboard section, 1202
 - Monitor sections, 1203-1204
 - Pointer section, 1202-1203
 - Screen sections, 1206-1208
 - ServerFlags section, 1201
- xf86config, 633
- xfd, 633-636
 - application-specific resources, 635
 - bugs, 636
 - fontgrid resources, 635
 - options, 634
 - widgets, 634-635
- XFree86, 636-641
 - configuration, 636
 - configuration file, 1201-1208
 - Device sections*, 1204-1206
 - Files section*, 1201
 - Keyboard section*, 1202
 - Monitor sections*, 1203-1204
 - Pointer section*, 1202-1203
 - Screen sections*, 1206-1208
 - ServerFlags section*, 1201
 - environment variables, 637
 - key combinations, 638
 - network connections, 636-637
 - options, 637-638
 - setup, 638
 - video mode tuner, 719-720
 - buttons*, 719
 - moving display*, 719
 - options*, 720
- xfs, 641-643
 - bugs, 643
 - configuration, 642
 - naming, 643
 - options, 641
 - signals, 641
- xhost, 643-645
 - bugs, 644
 - diagnostics, 644
 - environment, 644
 - files, 644
 - names, 644
 - options, 643-644
- xiafs filesystem, 1125
- XIE protocol, testing, 645-654
- xieperf, 645-654
 - bugs, 654
 - options, 646-654
- XIM files, converting to portable pixmaps, 654
- ximtoppm, 654
- xinetd, 655-664
 - bugs, 664
 - configuration file, 656-660
 - editing signal responses, 660-661
 - files, 663
 - internal services, 660
 - log format, 661-663
 - options, 655-656
- xinit, 664-666
 - environment variables, 666
 - examples, 665-666
 - files, 666
- xkill, 666-667
- xlogo, 667-668
 - environment variables, 668
 - resources, 668
 - widgets, 668

- xlsatoms*, 668-669
- xlsclients*, 669-670
- xlsfonts*, 670-671
- xmag*, 671-672
- xmkmf*, 672
- xmodmap*, 672-676
 - bugs, 675
 - environment, 675
 - examples, 674-675
 - expression grammar, 673-674
 - options, 673
- xon*, 676
- xpmtoppm*, 677
- xprop*, 677-681
 - constructing formats, 679
 - environment, 680
 - examples, 680
 - format characters, 679
 - options, 677-678
 - selecting windows, 678
- xrdb*, 681-684
 - bugs, 684
 - environment, 684
 - file symbols, 681-682
 - options, 682-684
- xrefresh*, 684-685
 - arguments, 684-685
 - bugs, 685
 - defaults, 685
 - environment, 685
- Xresources* file, 608
- Xserver*, 685-690
 - file utility, 587-592
 - files, 690
 - fonts, 689
 - options, 686-687
 - network connections*, 688
 - server-dependent*, 687-688
 - XDMCP*, 688
 - XKEYBOARD*, 688
 - security, 688-689
 - signals, 689
 - starting, 685
- xset*, 690-693
- xsetroot*, 693-694
- xsm*, 694-698
 - default startup applications, 695
 - options, 695-698
 - proxy, 698
 - remote applications, 698
 - Session menu, 695-696
 - SM_SAVE_DIR* environment variable, 695
 - starting sessions, 695
 - tester, 698-699
 - .xsession* file, 695
- xsmclient*, 698-699
- xstdcmap*, 699-700
- xterm*, 700-717
 - actions, 713-716
 - allow-send-events()*, 714
 - bell()*, 713
 - clear-saved-lines()*, 715
 - hard-reset()*, 715
 - ignore()*, 713
 - insert()*, 713
 - insert-eight-bit()*, 713
 - insert-selection()*, 713
 - insert-seven-bit()*, 713
 - keymap()*, 713
 - popup-menu()*, 713
 - quit()*, 714
 - redraw()*, 714
 - scroll-back()*, 714
 - scroll-forw()*, 714
 - secure()*, 713
 - select-cursor-end*, 714
 - select-cursor-start()*, 714
 - select-end()*, 714
 - select-extend()*, 714
 - select-start()*, 714
 - send-signal()*, 714
 - set-allow132()*, 715
 - set-altscreen()*, 715
 - set-appcursor()*, 715
 - set-appkeypad()*, 715
 - set-autolinefeed()*, 715
 - set-autowrap()*, 715
 - set-cursesemul()*, 715
 - set-jumpscroll()*, 715
 - set-marginbell()*, 715
 - set-reverse-video()*, 715
 - set-reversewrap()*, 715
 - set-scroll-on-key()*, 715
 - set-scroll-on-tty-output()*, 715
 - set-scrollbar()*, 715
 - set-tek-text()*, 715
 - set-terminal-type()*, 715
 - set-visibility()*, 715
 - set-visual-bell()*, 715
 - set-vt-font()*, 714
 - soft-reset()*, 715
 - start-cursor-extend()*, 714
 - start-extend()*, 714
 - string()*, 714
 - tek-copy()*, 716
 - tek-page()*, 715
 - tek-reset()*, 716
 - visual-bell()*, 716
- bugs, 717
- character classes, 712-713
- emulations, 700
- environment, 717
- features, 700-701
- menus, 711-712
- options, 701-705
- pointer usage, 710-711
- resources, 705-710
 - fontMenu* entries, 710
 - mainMenu* entries, 709
 - tekMenu* entries, 710
 - vtMenu* entries, 709-710
- security, 712
- XV thumbnail pictures, converting to portable pixmaps, 720
- Xvfb*, 717-718
- xvidtune*, 719-720
- xvminitoppm*, 720

xwd, 721-722
 xwdtopnm, 722
 xwininfo, 722-724
 xwud, 725-726

Y

y0() function, 959
 y1() function, 959
 ybmtopbm, 726
 yn() function, 959
 ytalk, 727-730

- Boolean options, 729
- daemons, 727
- escape menu, 728
- files, 730
- readdressing, 729
- runtime options, 728-729
- startup file, 729
- username field, 727
- X11 interface, 730

 YUV bytes, converting to

- portable pixmaps, 731

 YUV files, converting to

- portable pixmaps, 730-731

 yuvplittoppm, 730-731
 yuvtoppm, 731

Z

z command (telnet), 512
 Z files, recompressing to GZ,

- 734-735

 zcat, 248-249

- see also* gzip

 zcatgzip, 248-249

- see also* gzip

 zcmp, 731-732
 zdiff, 731-732
 zdump, 1419
 Zeiss confocal files, converting

- to portable anymaps, 732

 zeisstopnm, 732
 zero, 1094
 zforce, 732-733
 zgrep, 733

zic, 1419-1422

- files, 1422
- link lines, 1421-1422
- options, 1419-1420
- rule lines, 1420-1421
- zone lines, 1421

 zmore, 733-734
 znew, 734-735